



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

**HARVARD UNIVERSITY**

**FRANCES LOEB LIBRARY  
GRADUATE SCHOOL OF DESIGN**







**THE  
ARCHITECTS' AND BUILDERS'  
HANDBOOK**



# **THE ARCHITECTS' AND BUILDERS' HANDBOOK**

**DATA FOR  
ARCHITECTS, STRUCTURAL ENGINEERS,  
CONTRACTORS, AND DRAUGHTSMEN**

**/ BY '**

**THE LATE FRANK E. KIDDER, C. E., PH. D.**

**AUTHOR OF "BUILDING CONSTRUCTION AND SUPERINTENDENCE"**

**COMPILED BY A STAFF OF SPECIALISTS AND  
THOMAS NOLAN, M.S., A.M., EDITOR-IN-CHIEF**

**FELLOW OF THE AMERICAN INSTITUTE OF ARCHITECTS; PROFESSOR OF  
ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA**

***SEVENTEENTH EDITION, ENLARGED***  
**TOTAL ISSUE, ONE-HUNDRED AND FIVE THOUSAND**

**NEW YORK**  
**JOHN WILEY & SONS, Inc.**  
**LONDON: CHAPMAN & HALL, LIMITED**

The Publishers and the Editor-in-Chief will be grateful to readers of this volume who will call attention to any errors of omission or commission there. It is intended to make our publications standard works of study and reference, and, to that end, the greatest accuracy is sought. It rarely happens that the early editions of books are free from errors; but it is the endeavor of the Publishers to have them removed, and it is therefore desired that the Editor-in-Chief may be aided in his task of revision, from time to time, by the kind criticism of readers.

JOHN WILEY & SONS, INC.  
432 FOURTH AVENUE, NEW YORK

Nov. 5. 1930  
**HARVARD UNIVERSITY**  
**The Library of the Schools**  
**of Landscape Architecture and City Planning**

*Thompson Purchase*

**5484**

COPYRIGHT, 1884, 1892, 1897, 1904,

BY

**FRANK E. KIDDER**

---

COPYRIGHT, 1908,

BY

**KATHERINE E. KIDDER**

---

COPYRIGHT, 1915, 1921,

BY

**KATHERINE E. KIDDER**

*Printed in U. S. A.*

7/26

COMPOSITION, ELECTROTYPING, PRINTING AND BINDING BY  
BRAUNWORTH & CO., BROOKLYN, N. Y.

FA  
1010

1010

1010



## **This Book**

**IS RESPECTFULLY DEDICATED TO THOSE WHOSE KINDNESS  
HAS ENABLED ME TO PRODUCE IT**

**TO MY PARENTS**

**WHO GAVE ME THE EDUCATION UPON WHICH IT IS BASED.**

**TO MY WIFE**

**FOR HER LOVING SYMPATHY, ENCOURAGEMENT  
AND ASSISTANCE**

**TO ORLANDO W. NORCROSS**

**OF WORCESTER, MASS.**

**WHOSE SUPERIOR PRACTICAL KNOWLEDGE OF ALL THAT  
PERTAINS TO BUILDING HAS GIVEN ME A MORE  
INTELLIGENT AND PRACTICAL VIEW OF THE  
SCIENCE OF CONSTRUCTION THAN I  
SHOULD OTHERWISE HAVE  
OBTAINED •**



## **EDITORIAL STAFF**

### **EDITOR-IN-CHIEF**

**THOMAS NOLAN**, Professor of Architectural Construction, University of Pennsylvania.

### **ASSOCIATE EDITORS**

**HERMAN C. BERRY**, Professor of Materials of Construction, University of Pennsylvania.

**J. J. COSGROVE**, Consulting Sanitary Engineer.

**ROBINS FLEMING**, of the American Bridge Company, New York, N. Y.

**L. A. HARDING**, formerly Professor of Mechanical Engineering, Pennsylvania State College.

**WALVERD A. HOWE**, Professor Emeritus of Civil Engineering, Rose Polytechnic Institute.

**I. H. KINDL**, Late Consulting Engineer, Pittsburgh, Pa.

**RODOLPH P. MILLER**, Superintendent of Buildings, Borough of Manhattan, New York, N. Y.

**DANIEL E. MORAN**, Consulting Engineer, New York, N. Y.

**EMILE G. PERROT**, Member of American Society of Civil Engineers.

**S. A. RICHARDS**, of Purdy & Henderson, Inc., Civil Engineers, New York, N. Y.

**EDWARD F. RIES**, Consulting Engineer, San Antonio, Texas.

**GRENVILLE T. SNELLING**, Formerly Instructor in Architectural Engineering, Columbia University.

**A. P. STRADLING**, Manager, Philadelphia Suburban Underwriters' Association.

**W. H. TIMBIE**, Associate Professor of Electrical Engineering, Massachusetts Institute of Technology.

**CHARLES P. WARREN**, Late Assistant Professor of Architecture, Columbia University.

## NOTE TO SEVENTEENTH EDITION

With this edition the name is changed from Pocket-Book to Handbook. The work has been revised, some chapters rewritten, new chapters added, and a new Index made. Many cuts have been reengraved.

The twenty-nine chapters of Part II have been revised where necessary to make the data agree with the latest research and practice, and two new chapters have been added, Chapter XXX, on Specifications for the Steelwork of Buildings, by Robins Fleming, and Chapter XXXI, on Domical and Vaulted Structures, by Edward F. Ries. Chapter XXIII, on Fireproofing of Buildings, and Chapter XXIV, on Reinforced-Concrete Construction, have been rewritten by Rudolph P. Miller. In Part III, the sections on Heating and Ventilation, and Chimney Construction, have been entirely rewritten by Louis A. Harding. The new chapters and sections include numerous practical examples of everyday problems, with solutions worked out in complete detail.

In addition to the new chapters, numerous new articles have been added to the text and illustrations of Part II, on the following subjects: New Data on Building Laws Relating to Loads on Masonry; Graphical Method of Determining the Center of Gravity of Plane Figures or Sections; Graphical Method of Determining Moments of Inertia of Plane Figures; Triangular Loading; End Connections of Tension-Members; New Wire-Data; New Matter on Gauges; New Matter on Chains; Graphical Method of Determining the Deflection of Beams; Secondary Stresses; Angles Used as Beams; Data on Girderless Reinforced-Concrete Floors; Data on Tanks, and on Stresses in Cylindrical Tanks, etc. Other revisions and additions have been made, including new sections relating to the Registration of Architects, Standard Documents of the American Institute of Architects, Architectural Education, etc.

In its revised, compact, and convenient form, the Editor believes that the work, more than ever before, will maintain its preeminence as the authoritative Handbook of Building-Construction.

PHILADELPHIA, July, 1921.

## PREFACE TO SIXTEENTH EDITION

The changes in the fifteenth edition, published in 1908, consisted principally in the rewriting of the two chapters on Fireproofing of Buildings and Reinforced Concrete.

In 1912 the undersigned was asked to undertake the revision of the entire book with the cooperation of a corps of Associate Editors, each highly qualified to render the necessary assistance in matters pertaining to his own work. On account of the comprehensive nature of the contents of the Pocket-Book, the many recent changes and rapid developments in different fields of architectural construction, and the consequent effect of such changes on the interrelated subjects treated, the Editor-in-Chief decided to rewrite and reset the entire book. After more than three years of arduous labor, in which the Associate Editors and many other contributors have most ably and generously assisted, the New Kidder is about to be published.

It was decided to retain Mr. Kidder's original arrangement of the subject-matter which is divided into three Parts, Part I dealing with practical applications of Arithmetic, Geometry and Trigonometry, Part II with the Materials of Construction and the Strength and Stability of Structures, and Part III with miscellaneous useful information for architects and builders. Each of the twenty-nine chapters of Part II, however, has the name of the Associate Editor who revised or rewrote it printed with the chapter-caption. Part I has been carefully checked and much of the matter rearranged. The twenty-eight chapters of Part II have been rewritten and one new chapter has been added on Reinforced-Concrete Mill and Factory-Construction. Part III has been largely rewritten and all subjects retained have been thoroughly revised. To this part, also, much new matter has been added, such as extended tables of Specific Gravities and Weights of Substances, Architectural Acoustics, Waterproofing for Foundations, the Quantity System of Estimating, the Standard Documents of the American Institute of Architects, Educational Societies of the World and extended Lists of Architectural Schools, Books and Periodicals.

The Editor-in-Chief has, with very few exceptions, personally checked on every page of manuscript, galley-proof and page-proof the equations, formulas, computations and problems, and has read or examined carefully every word, figure and illustration, every detail of syntax, paragraphing, punctuation and typography, and every arrangement of tables, captions, classifications, notation, Table of Contents and Index.

He is responsible for many changes in the form of presentation of data which it is hoped will add to the Pocket-Book still more of that efficiency and practical brevity for which it has been so long noted. Some of these changes may be briefly mentioned. The text has been entirely reset; the type, while slightly smaller, is clearer and has the lines and paragraphs separated by wide leads; special type is used for the tables; the paragraphing is revised throughout and every paragraph has a black-face type caption descriptive of the subject-matter; words in italics or with quotation-marks are seldom used, words in small caps taking their place; every chapter is divided into numbered chapter-subdivisions which are briefly descriptive of the classified matter; the number of cross-

references is largely increased and the page-numbers of such references are almost always added; many tables and diagrams which in the former editions ran lengthwise of the page have been reset or reengraved to read across the page for greater convenience; the number of illustrations has been largely increased, many old cuts reused have been reengraved, and some diagrams printed with lines in different colors to make the demonstrations clearer; a descriptive caption has been added to every illustration; the abbreviations Chap. I, Chap. II, etc., have been printed with each page-caption of the left-hand pages, thus avoiding the necessity of referring to the Table of Contents to locate any particular chapter.

The Editor-in-Chief decided to change some of the unit stresses, especially those for the different woods, and in some cases to recommend more conservative values, and he believes that results based upon such stresses conform to the best engineering practice. This change necessitated the revision of many tables and problems throughout the book which had to be entirely recalculated. Numerous practical problems with complete solutions have been added. The derivation of many of the formulas used has been explained, either in the body of the text or in extended foot-notes, for those who wish to understand as well as to use such formulas, and numerous cross-references accompanying them enable the reader to use the Pocket-Book as a textbook for certain parts of the mechanics of materials as well as a handbook for office work. The tables of the properties of structural shapes, of safe loads for columns, beams and girders, etc., have been revised and numerous new tables added. The Editor has found that it is the consensus of opinion among architects that the insertion of these tables is a great convenience and for their ordinary office work condenses into one handy volume much of the essential data of several manufacturers' handbooks.

The difficulty of securing a unity of treatment and of avoiding repetitions and contradictions in a book of reference the data of which covers so many subjects and is written by so many contributors has been fully realized; but it is believed that in these respects the New Kidder is reasonably successful and will meet with the approval of all who use it.

Acknowledgments and thanks are due the Associate Editors for their hearty cooperation and generous contributions of the time and labor taken from their professional work. Acknowledgment is made, also, of the valuable assistance of all others who have furnished new or revised old data, and of many helpful suggestions from Mrs. F. E. Kidder and from the publishers.

The Editor-in-Chief expresses the hope that for the architects and builders of this country the new Pocket-Book will continue to be, as Mr. Kidder expressed it in his preface to the first edition in 1884, "a compendium of practical facts, rules and tables presented in a form as convenient for application as possible and as reliable as our present knowledge will permit;" and also, in its present extension and fuller development, a work which will lead to a still clearer understanding of the essential principles of sound architectural construction.

THOMAS NOLAN.

PHILADELPHIA, September, 1915.



## PREFACE TO FOURTEENTH EDITION

It is now nearly twenty years since the author, then quite a young man, completed the first edition of this work, which, although containing but 586 pages, had required about three years for its preparation. At that time the author thought he had covered all of those practical details relating to the planning and construction of buildings, with which the architect was concerned, admirably well, and it would appear as though the purchasers of the book thought so too, but as the years have come and gone, so many and such great improvements have taken place in the building world, so many articles invented, new methods of construction developed, higher standards established, that the present edition, although containing nearly three times as many pages, is perhaps not so complete, for the times, than was the first edition.

When preparing the first edition, it was the aim of the author to give to architects and builders a handbook which should be, in its field, as useful and reliable as Trautwine's had been to civil engineers; and with that object constantly in view, the book has been revised from time to time to meet the changed conditions in building construction and equipment.

About three years ago it was thought, by the publishers and the author, that a thorough and complete revision of the book should be undertaken, and although the re-writing of a work of this character, even with the thirteenth edition to start from, involved many months of close and constant application, the utilization of those hours which one ordinarily takes for recreation, and at the best more or less interruption to his regular business, and consequent reduction in income, the writer undertook to prepare a work of a still wider scope, and which should be thoroughly up-to-date in every particular, or at least as far as is practicable, in a work requiring a period of three years in its preparation, and from that time to this he has spared no labor or expense to make the book as useful and complete as he possibly could, without making it too bulky.

In this revision the author has had in view:

1. A reference-book which should contain some information on every subject (except design) likely to come before an architect, structural engineer, draughtsman or master-builder, including data for estimating the approximate cost.

2. To as thoroughly cover the subject of architectural engineering as is practicable in a handbook.

3. To present all information in as simple and convenient a form for immediate application as is consistent with accuracy. To this end a great many new tables, arranged and computed by the author, have been inserted.

At the time the first edition was written, the term "Architectural Engineering" had not been used in its present application, and the term "Structural Engineering," when used, referred almost exclusively to bridge work.

To-day, structural and architectural engineers are concerned almost exclusively with building construction, and their work is more closely allied to that of the architect than to that of the civil engineer; hence the author has had in mind the needs of the structural engineer and draughtsman as well as those of the architect and builder, and the book should be of nearly equal value to both.

Where it was impossible, for lack of space, to go extensively into any subject, references to other books or sources of information have been given, so that in this way the book may serve as a general index to the many lines of raw materials, and manufactured products entering into the planning, construction and equipment of buildings.

To attain the objects in view, it has been necessary to add considerably to the number of pages, but as experience has shown that the book is used principally at the desk or draughting-table, and is seldom carried in the pocket, it is believed that the convenience of having everything in one book will more than offset the disadvantage resulting from increase in bulk.

Nearly the entire book has been re-written, and great pains have been taken to furnish reliable data. A large number of experts in various lines have assisted the author, as is manifest by the foot-notes and references. To all of such, and to the many authors of technical works, and to the publishers of technical journals, who have kindly consented to the use of cuts and data, the author takes pleasure in acknowledging his indebtedness. Also to Mr. E. S. Hanger, New York, who, for many years, has rendered material assistance in collecting data along the line of manufactured products.

The names and addresses of manufacturers have been given solely for the convenience of the users of the book, and not for any pecuniary consideration. In fact, if money considerations had solely appealed to the writer, this book would never have been re-written, because a technical work of this character can never adequately compensate, in money, for the time, labor, and thought required in its preparation. The many words of appreciation which have come to the author from hundreds of those who have found the book useful have been a great stimulus to further increase its usefulness.

As in the former prefaces, the author requests that any one discovering errors in the work or who may have any suggestions looking to the further improvement of the book, will communicate the same to him, that the book may be made as complete and reliable as possible.

Finally, the author desires to acknowledge his indebtedness to the publishers who have heartily seconded his efforts in every particular, and who have spared no pains or expense to make a perfect handbook.

F. E. KIDDER

DENVER, COLO., July 18th, 1904.

**CONTENTS**

**PART I**

**PRACTICAL ARITHMETIC, GEOMETRY, AND TRIGONOMETRY**

	PAGE
ARITHMETICAL SIGNS AND CHARACTERS . . . . .	3
INVOLUTION . . . . .	3
EVOLUTION, SQUARE ROOT, CUBE ROOT, RULES, AND TABLES . . . . .	4
WEIGHTS AND MEASURES . . . . .	25
THE METRIC SYSTEM . . . . .	30
METRIC CONVERSION TABLES . . . . .	32
SCRIPTURE AND ANCIENT MEASURES AND WEIGHTS . . . . .	34
GEOMETRY AND MENSURATION . . . . .	36
GEOMETRICAL PROBLEMS . . . . .	66
TABLE OF CHORDS . . . . .	81
HP AND JACK-RAPERS . . . . .	90
TRIGONOMETRY FORMULAS AND TABLES . . . . .	90

**PART II**

**STRENGTH OF MATERIALS AND STABILITY OF STRUCTURES**

INTRODUCTION . . . . .	121
EXPLANATION OF NOTATION AND SYMBOLS . . . . .	122

**CHAPTER I**

**EXPLANATION OF TERMS USED IN ARCHITECTURAL ENGINEERING**

BY  
**THOMAS NOLAN**

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

1. DEFINITIONS OF SOME OF THE TERMS USED IN MECHANICS OF MATERIALS . . . . .	124
2. CLASSIFICATIONS OF THE PRINCIPAL STRESSES CAUSED IN BODIES BY EXTERNAL FORCES . . . . .	127

**CHAPTER II**

**FOUNDATIONS**

BY  
**DANIEL E. MORAN**

MEMBER OF AMERICAN SOCIETY OF CIVIL ENGINEERS

1. DEFINITION OF THE WORD AND TERMS USED . . . . .	129
2. GENERAL REQUIREMENTS . . . . .	129
3. GEOLOGICAL CONSIDERATIONS . . . . .	130



## **EDITORIAL STAFF**

### **EDITOR-IN-CHIEF**

**THOMAS NOLAN**, Professor of Architectural Construction, University of Pennsylvania.

### **ASSOCIATE EDITORS**

**HERMAN C. BERRY**, Professor of Materials of Construction, University of Pennsylvania.

**J. J. COSGROVE**, Consulting Sanitary Engineer.

**ROBINS FLEMING**, of the American Bridge Company, New York, N. Y.

**L. A. HARDING**, formerly Professor of Mechanical Engineering, Pennsylvania State College.

**MALVERD A. HOWE**, Professor Emeritus of Civil Engineering, Rose Polytechnic Institute.

**F. H. KINDL**, Late Consulting Engineer, Pittsburgh, Pa.

**ROLDOLPH P. MILLER**, Superintendent of Buildings, Borough of Manhattan, New York, N. Y.

**DANIEL E. MORAN**, Consulting Engineer, New York, N. Y.

**EMILE G. PERROT**, Member of American Society of Civil Engineers.

**N. A. RICHARDS**, of Purdy & Henderson, Inc., Civil Engineers, New York, N. Y.

**EDWARD F. RIES**, Consulting Engineer, San Antonio, Texas.

**GRENVILLE T. SNELLING**, Formerly Instructor in Architectural Engineering, Columbia University.

**A. P. STRADLING**, Manager, Philadelphia Suburban Underwriters' Association.

**W. H. TIMBIE**, Associate Professor of Electrical Engineering, Massachusetts Institute of Technology.

**CHARLES P. WARREN**, Late Assistant Professor of Architecture, Columbia University.

## CHAPTER IX

REACTIONS AND BENDING MOMENTS FOR  
BEAMS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

	PAGE
1. REACTIONS FOR BEAMS . . . . .	32
2. BENDING MOMENTS IN BEAMS . . . . .	32
3. BENDING MOMENTS IN BEAMS FOR DIFFERENT KINDS OF LOADING . . . . .	32
4. GRAPHIC METHOD FOR DETERMINING BENDING MOMENTS IN BEAMS . . . . .	32
5. REACTIONS AND BENDING MOMENTS FOR BEAMS WITH TRIANGULAR LOADING AND FOR BEAMS FIXED AT BOTH ENDS . . . . .	33

## CHAPTER X

PROPERTIES OF STRUCTURAL SHAPES, MOMENT  
OF INERTIA, MOMENT OF RESISTANCE, SEC-  
TION-MODULUS, AND RADIUS OF GYRATION

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

1. THE PROPERTIES OF CROSS-SECTIONS . . . . .	332
2. AREAS, MOMENTS OF INERTIA, SECTION-MODULI, AND RADIUS OF GYRATION OF ELEMENTARY SECTIONS . . . . .	334
3. TRANSFERRING MOMENTS OF INERTIA TO OTHER PARALLEL AXES . . . . .	338
4. MOMENTS OF INERTIA OF COMPOUND SECTIONS . . . . .	339
5. RADIUS OF GYRATION OF COMPOUND SECTIONS . . . . .	344
6. GRAPHICAL METHOD OF DETERMINING THE MOMENT OF INERTIA OF PLANE FIGURES . . . . .	345
7. DIMENSIONS, MOMENTS OF INERTIA, RADIUS OF GYRATION, AND SECTION-MODULI OF STANDARD STRUCTURAL SHAPES . . . . .	352

## CHAPTER XI

RESISTANCE TO TENSION, PROPERTIES OF  
IRON AND STEEL

BY

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

1. DEFINITIONS, WORKING STRESSES, AND EXAMPLES . . . . .	375
2. WROUGHT IRON . . . . .	377
3. CAST IRON . . . . .	379
4. STEEL . . . . .	380
5. STANDARD SPECIFICATIONS FOR STRUCTURAL STEEL FOR BUILDINGS . . . . .	383
6. TENSION-MEMBERS . . . . .	385
7. WIRE . . . . .	400
8. WIRE ROPE . . . . .	404
9. COTTON, HEMP, AND MANILA ROPE . . . . .	406
10. CHAINS . . . . .	408



## CHAPTER XII

RESISTANCE TO SHEAR. RIVETED JOINTS.  
PINS AND BOLTS

BY

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

	PAGE
SHEAR . . . . .	411
RIVETED JOINTS . . . . .	413
STRENGTH OF PINS IN TRUSSES . . . . .	423
STRENGTH OF BOLTS IN WOODEN TRUSSES AND GIRDERS . . . . .	429

## CHAPTER XIII

BEARING-PLATES AND BASES FOR COLUMNS,  
BEAMS, AND GIRDERS. BRACKETS ON  
CAST-IRON COLUMNS

BY

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

1 BEARING-PLATES AND BASES . . . . .	440
2 BEARING-BRACKETS ON CAST-IRON COLUMNS . . . . .	445

## CHAPTER XIV

## STRENGTH OF COLUMNS, POSTS, AND STRUTS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

1 GENERAL PRINCIPLES AND DEFINITIONS . . . . .	448
2 STRENGTH OF SHORT WOODEN COLUMNS . . . . .	448
3 STRENGTH OF WOODEN COLUMNS OR STRUTS OVER TEN DIAMETERS IN LENGTH. FORMULAS . . . . .	449
4 TABLES OF SAFE LOADS FOR WOODEN COLUMNS . . . . .	450
5 ECCENTRIC LOADING OF WOODEN COLUMNS . . . . .	453
6 METAL CAPS AND BOLSTERS FOR WOODEN COLUMNS . . . . .	454
7 CRUSHING OF WOOD PERPENDICULAR TO THE GRAIN . . . . .	454
8 CAST-IRON COLUMNS . . . . .	455
9 DESIGN OF CAST-IRON COLUMNS . . . . .	456
10 STRENGTH OF CAST-IRON COLUMNS. FORMULAS . . . . .	459
11 TABLES OF SAFE LOADS FOR CAST-IRON COLUMNS. EXAMPLES . . . . .	461
12 TYPE, FORM, AND CONNECTIONS OF STEEL COLUMNS . . . . .	467
13 STRENGTH OF STEEL COLUMNS. FORMULAS . . . . .	480
14 DESIGN OF STEEL COLUMNS. EXAMPLES . . . . .	482
15 ECCENTRIC LOADING OF STEEL COLUMNS . . . . .	486
16 TABLES OF SAFE LOADS FOR STEEL COLUMNS . . . . .	489

CHAPTER XV

STRENGTH OF BEAMS AND BEAM GIRDERS  
FRAMING AND CONNECTING STEEL BEAMS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

1. GENERAL PRINCIPLES OF THE FLEXURE OF BEAMS . . . . .	
2. FORMULAS FOR SAFE LOADS FOR BEAMS FOR DIFFERENT CONDITIONS OF LOAD- ING AND SUPPORT . . . . .	
3. STEEL BEAMS AND GIRDERS . . . . .	
4. TABLES OF SAFE LOADS FOR STEEL BEAMS AND GIRDERS. EXAMPLES . .	
OBLIQUE LOADING OF I BEAMS AND CHANNELS. TABLES . . . . .	
OBLIQUE LOADING OF ANGLES USED AS BEAMS . . . . .	
5. FRAMING AND CONNECTING STEEL BEAMS AND GIRDERS . . . . .	

CHAPTER XVI

STRENGTH OF CAST-IRON LINTELS AND  
WOODEN BEAMS

BY

F. H. KINDL

LATE CORRESPONDING MEMBER AMERICAN INSTITUTE OF ARCHITECTS

1. CAST-IRON LINTELS . . . . .	6
2. SECTIONS, STRESSES, BUCKLING, AND DEFLECTION OF WOODEN BEAMS . . .	6
3. CONSTANTS AND COEFFICIENTS FOR BEAMS . . . . .	6
4. FLEXURAL STRENGTH OF WOODEN BEAMS . . . . .	6
5. APPLICATION OF FORMULAS FOR FLEXURAL STRENGTHS OF WOODEN BEAMS .	6
6. FLEXURAL STRENGTH OF BEAMS . . . . .	6
7. TABLES FOR STRENGTH AND STIFFNESS OF WOODEN BEAMS . . . . .	6
8. WORKING UNIT STRESSES FOR WOODS . . . . .	6
9. WORKING UNIT STRESSES FOR WOODS. TAKEN FROM BUILDING LAWS . . .	6

CHAPTER XVII

STRENGTH OF BUILT-UP, FLITCHED, AND  
TRUSSED WOODEN GIRDERS

BY

F. H. KINDL

LATE CORRESPONDING MEMBER AMERICAN INSTITUTE OF ARCHITECTS

1. BUILT-UP WOODEN GIRDERS . . . . .	6
2. FLITCHED BEAMS OR FLITCH-PLATE GIRDERS . . . . .	6
3. TRUSSED BEAMS AND GIRDERS . . . . .	6

## CHAPTER XVIII

# STIFFNESS AND DEFLECTION OF BEAMS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

	PAGE
GENERAL PRINCIPLES OF THE DEFLECTION OF BEAMS . . . . .	663
FORMULAS FOR LOADS, BASED UPON THE STIFFNESS OF BEAMS . . . . .	665
RELATIVE STIFFNESS OF BEAMS . . . . .	666
CYLINDRICAL BEAMS . . . . .	667
SAFE LOADS FOR WOODEN BEAMS FOR A GIVEN DEFLECTION . . . . .	667
NOMINAL AND STANDARD SIZES OF WOODEN BEAMS . . . . .	667
DEFLECTION OF STEEL BEAMS . . . . .	668
GRAPHICAL DETERMINATION OF DEFLECTION OF BEAMS . . . . .	670

## CHAPTER XIX

# STRENGTH AND STIFFNESS OF CONTINUOUS GIRDERS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

GENERAL CONSIDERATIONS . . . . .	671
SUPPORTING FORCES OR REACTIONS OF CONTINUOUS GIRDERS . . . . .	671
BENDING MOMENTS OF CONTINUOUS GIRDERS . . . . .	673
DEFLECTION OF CONTINUOUS GIRDERS . . . . .	674
NOTES ON REACTIONS, STRENGTH, AND STIFFNESS OF CONTINUOUS GIRDERS . . . . .	675
FORMULAS FOR THE STRENGTH AND STIFFNESS OF CONTINUOUS GIRDERS . . . . .	676
CONTINUOUS GIRDERS IN GRILLAGE FOUNDATIONS . . . . .	678

## CHAPTER XX

# RIVETED STEEL PLATE AND BOX GIRDERS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

GENERAL NOTES ON PLATE AND BOX GIRDERS . . . . .	681
DETAILS OF CONSTRUCTION OF PLATE AND BOX GIRDERS . . . . .	682
DESIGN OF PLATE AND BOX GIRDERS . . . . .	683
EXPLANATION OF TABLES . . . . .	688
EXAMPLES OF PLATE AND BOX GIRDERS . . . . .	688
TABLES USED IN THE DESIGN OF PLATE AND BOX GIRDERS . . . . .	702

## CHAPTER XXI

# STRENGTH AND STIFFNESS OF WOODEN FLOORS

BY

THOMAS NOLAN

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

1. LOADS ON FLOORS AND WEIGHTS OF FLOOR-CONSTRUCTION . . . . .	717
2. TABLES OF WEIGHTS OF MERCHANDISE . . . . .	721
3. DETERMINATION OF SIZES OF JOISTS, BEAMS, OR GIRDERS . . . . .	724

4.	SAFE LOADS FOR PLANK FLOORING . . . . .	
5.	TABLES FOR MAXIMUM SPANS FOR FLOOR-JOISTS . . . . .	
6.	DETERMINATION OF STRENGTH OF AN EXISTING FLOOR . . . . .	
7.	DETAILS OF FLOOR-FRAMING . . . . .	
8.	STIRRUPS AND JOIST-HANGERS . . . . .	
9.	COMPARATIVE STRENGTH OF DIFFERENT TYPES OF JOIST-HANGERS . . . . .	

CHAPTER XXII

WOODEN MILL AND WAREHOUSE-  
CONSTRUCTION

BY  
A. P. STRADLING

MANAGER, PHILADELPHIA SUBURBAN UNDERWRITERS' ASSOCIATION

1.	MILL-CONSTRUCTION . . . . .	
2.	WHAT MILL-CONSTRUCTION IS . . . . .	
3.	WHAT MILL-CONSTRUCTION IS NOT . . . . .	
4.	STANDARD MILL-CONSTRUCTION . . . . .	
5.	BELTS, STAIRWAYS AND ELEVATOR-TOWERS . . . . .	
6.	STANDARD STOREHOUSE-CONSTRUCTION . . . . .	
7.	EXAMPLE OF ONE-STORY WORKSHOP . . . . .	
8.	SAW-TOOTH ROOF-CONSTRUCTION . . . . .	
9.	MILL-CONSTRUCTION AS APPLIED TO WAREHOUSES . . . . .	
10.	STEEL AND IRON STRUCTURAL MEMBERS IN WAREHOUSE-CONSTRUCTION . . . . .	
11.	STRUCTURAL DETAILS OF MILL-CONSTRUCTION AS APPLIED TO FACTORIES AND WAREHOUSES . . . . .	
12.	CONNECTION OF FLOOR-BEAMS AND GIRDERS . . . . .	
13.	WALL SUPPORTS AND ANCHORS FOR JOISTS AND GIRDERS . . . . .	
14.	WEAKNESS OF WROUGHT-IRON STIRRUPS WHEN EXPOSED TO FIRE . . . . .	
15.	POST AND GIRDER-CONNECTIONS . . . . .	
16.	FORM AND MATERIAL OF POST-CAPS . . . . .	
17.	ROOFING-MATERIALS . . . . .	
18.	PARTITIONS . . . . .	
19.	DOORS AND SHUTTERS . . . . .	
20.	FIRE-PROTECTION . . . . .	
21.	COST OF MILLS AND FACTORIES BUILT ON THE SLOW-BURNING PRINCIPLE . . . . .	
22.	COST OF BRICK MILL-BUILDINGS OF SLOW-BURNING CONSTRUCTION . . . . .	

CHAPTER XXIII

FIREPROOFING OF BUILDINGS

BY  
RUDOLPH P. MILLER

SUPERINTENDENT OF BUILDINGS, BOROUGH OF MANHATTAN, NEW YORK CITY

1.	DEFINITIONS, AREAS, HEIGHTS, AND COSTS . . . . .	
2.	FIRE-RESISTANCE OF MATERIALS . . . . .	
3.	COLUMN-PROTECTION . . . . .	
4.	FIRE-PROOF FLOOR-CONSTRUCTION . . . . .	
5.	FIRE-PROOF ROOF-CONSTRUCTION . . . . .	
6.	PARTITIONS AND WALL-COVERINGS . . . . .	
7.	FIRE-PROOF FLOORING . . . . .	
8.	INTERIOR FINISH AND FITTINGS . . . . .	
9.	PROTECTION FROM OUTSIDE HAZARD . . . . .	
10.	EXTINGUISHING DEVICES AND PRECAUTIONARY MEASURES . . . . .	

## CHAPTER XXIV

## REINFORCED-CONCRETE CONSTRUCTION

BY

RUDOLPH P. MILLER

SUPERINTENDENT OF BUILDINGS, BOROUGH OF MANHATTAN, NEW YORK CITY

PAGE

INTRODUCTORY NOTES . . . . .	906
MATERIALS USED IN REINFORCED-CONCRETE CONSTRUCTION . . . . .	907
DESIGN OF REINFORCED-CONCRETE CONSTRUCTION . . . . .	924
TYPES OF REINFORCED-CONCRETE CONSTRUCTION . . . . .	948
FIRE-RESISTANCE OF REINFORCED-CONCRETE CONSTRUCTION . . . . .	955
PROTECTION AGAINST CORROSION IN REINFORCED-CONCRETE CONSTRUCTION . . . . .	960
SECTION OF REINFORCED-CONCRETE CONSTRUCTION . . . . .	962

## CHAPTER XXV

## REINFORCED-CONCRETE FACTORY AND MILL-CONSTRUCTION

BY

EMILE G. PERROT

MEMBER OF AMERICAN SOCIETY OF CIVIL ENGINEERS

GENERAL PRINCIPLES AND DETAILS . . . . .	968
DESIGN OF FLOOR SYSTEM . . . . .	971
DESIGN OF SPANDREL BEAMS . . . . .	975
COLUMNS AND PIERS . . . . .	976
FOUNDATIONS AND FOOTINGS . . . . .	978
WIND-DESIGN . . . . .	983
DIAGRAMS AND FORMULAS FOR BEAMS AND SLABS . . . . .	984
ROOFLESS FLOORS . . . . .	993

## CHAPTER XXVI

## TYPES OF ROOF-TRUSSES

BY

MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

DEFINITIONS . . . . .	998
TYPES OF WOODEN TRUSSES . . . . .	998
TYPES OF STEEL TRUSSES . . . . .	1025
HYBRID TRUSSES . . . . .	1035
WILHELM TRUSSES . . . . .	1043

## CHAPTER XXVII

## STRESSES IN ROOF-TRUSSES

BY

MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

WIND-LOADS. DATA, WEIGHTS, MATERIALS, METHODS . . . . .	1046
SAMPLES OF THE COMPUTATION OF ROOF-LOADS . . . . .	1054
DETERMINATION OF STRESSES BY COMPUTATION . . . . .	1058

4.	EXAMPLES SHOWING USE OF TABLES IN STRESS-COMPUTATIONS . . . . .	.
5.	DETERMINATION OF STRESSES IN ROOF-TRUSSES BY GRAPHIC METHODS . . . . .	.
6.	DETERMINATION OF WIND-LOAD STRESSES . . . . .	.
7.	TRUSSES WITH KNEE-BRACES . . . . .	.
8.	ARCHED TRUSSES . . . . .	.
9.	TRUSSED ARCHES . . . . .	.
10.	ARCHES WITH SOLID RIBS . . . . .	.
11.	INFLUENCE-LINES FOR SIMPLE BEAMS AND TRUSSES . . . . .	.
12.	SECONDARY STRESSES IN TRUSS-MEMBERS . . . . .	.

CHAPTER XXVIII

DESIGN AND CONSTRUCTION OF ROOF TRUSSES

BY  
MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

1.	DESIGN OF WOODEN TRUSSES . . . . .	.
2.	DESIGN OF STEEL TRUSSES . . . . .	.
3.	JOINTS OF WOODEN TRUSSES . . . . .	.
4.	JOINTS OF STEEL TRUSSES . . . . .	.
5.	PURLINS AND PURLIN-CONNECTIONS . . . . .	.

CHAPTER XXIX

WIND-BRACING FOR TALL BUILDINGS

BY  
N. A. RICHARDS

OF  
PURDY & HENDERSON, INC., CIVIL ENGINEERS

1.	DATA FOR WIND-PRESSURE. BUILDING LAWS . . . . .	.
2.	CONDITIONS DETERMINING OR AFFECTING WIND-BRACING . . . . .	.
3.	GENERAL THEORY OF WIND-BRACING . . . . .	.
4.	ARRANGEMENT OF WIND-BRACING . . . . .	.
5.	TYPES OF WIND-BRACING . . . . .	.
6.	COMPUTATION OF WIND-STRESSES . . . . .	.
7.	ILLUSTRATION OF METHOD OF COMPUTING WIND-STRESSES . . . . .	.
8.	ANALYSIS OF STRESSES IN DIFFERENT TYPES OF WIND-BRACING . . . . .	.
9.	COMBINATION OF DEAD AND LIVE LOADS, WITH WIND-LOAD . . . . .	.
10.	WIND-BRACING OF WATER-TOWERS AND SIMILAR STRUCTURES . . . . .	.
11.	RECENT EXAMPLES OF WIND-BRACING IN TALL BUILDINGS . . . . .	.

CHAPTER XXX

SPECIFICATIONS FOR THE STRUCTURAL STEELWORK OF BUILDINGS. DATA ON STRUCTURAL STEEL

BY  
ROBINS FLEMING

OF THE  
AMERICAN BRIDGE COMPANY, NEW YORK, N. Y.

1.	GENERAL . . . . .	.
2.	MATERIAL . . . . .	.
3.	LOADS . . . . .	.



	PAGE
DETAILS . . . . .	1199
DESIGN . . . . .	1201
DETAILS . . . . .	1202
WORKMANSHIP . . . . .	1202
PAINTING . . . . .	1203
INSPECTION . . . . .	1203
SECTION . . . . .	1203
OF STRUCTURAL STEEL . . . . .	1204

## CHAPTER XXXI

## DOMICAL AND VAULTED STRUCTURES

BY

EDWARD F. RIES

CONSULTING ENGINEER, SAN ANTONIO, TEXAS

DOMES . . . . .	1213
1) SMOOTH-SHELL DOMES . . . . .	1213
2) RIBBED DOMES . . . . .	1222
VAULTS . . . . .	1231
1) BARREL VAULTS . . . . .	1231
2) GROINED VAULTS . . . . .	1235
3) RIBBED VAULTS . . . . .	1240

## PART III

USEFUL INFORMATION FOR ARCHITECTS, BUILDERS,  
AND SUPERINTENDENTS

## HEATING AND VENTILATION OF BUILDINGS

BY

LOUIS A. HARDING

ASSISTANT PROFESSOR OF MECHANICAL ENGINEERING, PENNSYLVANIA STATE COLLEGE

HEATING UNITS AND THE MEASUREMENT OF HEAT . . . . .	1247
PROPERTIES OF AIR . . . . .	1249
HEATING REQUIREMENTS OF BUILDINGS . . . . .	1251
COMBUSTION . . . . .	1254
HEATING BOILERS AND HOT-WATER BOILERS . . . . .	1256
STEAM HEATING . . . . .	1264
SYSTEMS OF LOW-PRESSURE STEAM-HEATING SYSTEMS . . . . .	1271
INDIRECT HEATING . . . . .	1273
HOT-WATER HEATING . . . . .	1283
RADIANT HEATING . . . . .	1291
DESIGN OF A FURNACE-HEATING SYSTEM . . . . .	1298
HOT-BLAST HEATING . . . . .	1302
HOT-BLAST HEATERS . . . . .	1310
DESIGN OF AIR-DUCTS . . . . .	1312
HEATING-FANS . . . . .	1324
RELATION OF HOT-BLAST HEATING DATA . . . . .	1329
RELATION . . . . .	1333
VENTILATION LAWS AND REQUIREMENTS . . . . .	1341
OPERATIONS FOR FURNACE-WORK . . . . .	1342
OPERATIONS FOR HOT-WATER HEATING-APPARATUS IN A RESIDENCE . . . . .	1348
OPERATIONS FOR A LOW-PRESSURE STEAM-HEATING APPARATUS FOR HEATING . . . . .	1354
BY DIRECT RADIATION . . . . .	1357
	1359
	1361

# CHIMNEYS

BY

LOUIS A. HARDING

FORMERLY PROFESSOR OF MECHANICAL ENGINEERING, PENNSYLVANIA STATE COLLEGE

DRAFT AND DRAFT-LOSS . . . . .	1
DETERMINATION OF SIZE OF CHIMNEY . . . . .	1
FORMULAS FOR THE DESIGN OF BRICK CHIMNEYS . . . . .	1
DETERMINATION OF THE STABILITY OF CHIMNEYS . . . . .	1
REINFORCED-CONCRETE CHIMNEYS . . . . .	1
SELF-SUSTAINING STEEL CHIMNEYS . . . . .	1
RADIAL-BRICK CHIMNEYS . . . . .	1
LIST OF TALL CHIMNEYS . . . . .	1

# HYDRAULICS, PLUMBING AND DRAINAGE, AND GAS-PIPING

BY

J. J. COSGROVE

CONSULTING SANITARY ENGINEER

HYDRAULICS . . . . .	1
PRIVATE WATER-SUPPLY. PUMPS . . . . .	1
WINDMILLS . . . . .	1
FIRE-STREAMS . . . . .	1
CONSTRUCTION OF CYLINDRICAL WOODEN TANKS . . . . .	1
CAPACITY OF TANKS . . . . .	1
PLUMBING DEFINITIONS AND REQUIREMENTS . . . . .	1
PLUMBING MATERIALS AND DETAILS . . . . .	1
TESTING OF PLUMBING SYSTEMS . . . . .	1
PLUMBING SPECIALTIES . . . . .	1
SYMBOLS FOR PLUMBING . . . . .	1
ILLUMINATING-GAS . . . . .	1
PIPING A HOUSE FOR GAS . . . . .	1

# LIGHTING AND ILLUMINATION OF BUILDINGS

BY

W. H. TIMBIE

ASSOCIATE PROFESSOR OF ELECTRICAL ENGINEERING, MASSACHUSETTS  
INSTITUTE OF TECHNOLOGY

GENERAL PRINCIPLES . . . . .	1
THREE SYSTEMS OF GENERAL ILLUMINATION . . . . .	1
GENERAL CONSIDERATIONS IN DIRECT LIGHTING . . . . .	1
GENERAL CONSIDERATIONS IN INDIRECT AND SEMI-INDIRECT LIGHTING . . . . .	1
STANDARD SYMBOLS FOR GAS-PIPING PLANS . . . . .	1
EXAMPLES OF DESIGN OF A LIGHTING SYSTEM . . . . .	1
ILLUMINATION-CONSTANTS . . . . .	1
SELECTION OF ILLUMINANTS . . . . .	1
THE DIFFUSION OF LIGHT THROUGH WINDOWS . . . . .	1
REFERENCE BOOKS ON ILLUMINATION . . . . .	1

# ELECTRIC WORK FOR BUILDINGS

BY

W. H. TIMBIE

ASSOCIATE PROFESSOR OF ELECTRICAL ENGINEERING, MASSACHUSETTS  
INSTITUTE OF TECHNOLOGY

	PAGE
GENERAL CONSIDERATION AND DEFINITIONS . . . . .	1457
ELECTRIC LIGHTING SYSTEMS USED FOR SUPPLYING THE ELECTRICAL ENERGY TO LAMPS . . . . .	1464
WIRE-CALCULATIONS . . . . .	1469
WIRING . . . . .	1476
EXTRACTS FROM THE NATIONAL ELECTRICAL CODE . . . . .	1480
GENERAL SUGGESTIONS FOR ELECTRIC WORK . . . . .	1481
WIRING FOR INTERIOR WIRING . . . . .	1482
ESTIMATE COST OF WIRING FOR INCANDESCENT LIGHTING . . . . .	1482
WIRING-SYMBOLS . . . . .	1484

# ARCHITECTURAL ACOUSTICS

BY

WALLACE C. SABINE

LATE PROFESSOR OF PHYSICS, HARVARD UNIVERSITY

CHARACTER AND APPLICATION OF PROBLEMS IN ARCHITECTURAL ACOUSTICS . . . . .	1486
RELATIVE ABSORBING POWER OF DIFFERENT SUBSTANCES . . . . .	1487
EFFICIENTS OF ABSORPTION . . . . .	1488
EFFECTS OF INTERFERENCE OF SOUND-WAVES . . . . .	1493
PHOTOGRAPHING AIR-DISTURBANCES . . . . .	1495

# MISCELLANEOUS DATA

SPECIFIC GRAVITY . . . . .	1500
WEIGHTS AND METAL-GAUGES . . . . .	1509
SCREWS . . . . .	1529
WORK ON EXCAVATING . . . . .	1536
WORK ON STONEWORK . . . . .	1538
WORK ON BRICKS AND BRICKWORK . . . . .	1540
WORK . . . . .	1548
WORK AND GRAVEL . . . . .	1553
WORKING AND PLASTERING . . . . .	1554
WORK ON LUMBER AND CARPENTER'S WORK . . . . .	1558
WORKING PAPERS, BUILDING FELTS, AND QUILTS . . . . .	1564
PAINT AND VARNISH . . . . .	1568
WORK-GLASS AND GLAZING . . . . .	1573
MEMORANDA ON ROOFING . . . . .	1581
MEMORANDA ON TILING . . . . .	1604
HEALTH . . . . .	1608
MINERAL WOOL . . . . .	1609
ESTIMATING THE COST OF BUILDINGS . . . . .	1611
SYSTEM OF ESTIMATING . . . . .	1635
MEASUREMENTS AND DATA USEFUL IN THE PREPARATION OF ARCHITECTS' DRAW- INGS AND SPECIFICATIONS . . . . .	1637
WATER SERVICE IN BUILDINGS . . . . .	1659
WELLS . . . . .	1677
REFRIGERATORS . . . . .	1679
MECHANICAL REFRIGERATION . . . . .	1684
WATER-CLOCKS . . . . .	1695
LIBRARY BOOK-STACKS . . . . .	1696
MINERAL MOLDINGS . . . . .	1697
CLASSICAL ORDERS . . . . .	1698
WIRING-CONDUCTORS . . . . .	1704
REPRODUCTION . . . . .	1707

	P.
VACUUM-CLEANING . . . . .	13
WATERPROOFING FOR FOUNDATIONS . . . . .	13
FORCE OF THE WIND . . . . .	13
COPIES OF ARCHITECTS' TRACINGS . . . . .	13
HORSE-POWER, PULLEYS, GEARS, BELTING, AND SHAFTING . . . . .	13
CHAIN-BLOCKS, HOISTS, AND HOOKS . . . . .	13
BELLS . . . . .	17
SYMBOLS FOR THE APOSTLES AND SAINTS . . . . .	17
A CIRCULAR OF ADVICE ON PROFESSIONAL PRACTICE BY THE AMERICAN INSTITUTE OF ARCHITECTS . . . . .	17
ARCHITECTURAL COMPETITIONS . . . . .	17
STANDARD DOCUMENTS OF THE AMERICAN INSTITUTE OF ARCHITECTS . . . . .	17
REGISTRATION OF ARCHITECTS . . . . .	17
EDUCATIONAL INSTITUTIONS GIVING COURSES IN ARCHITECTURE . . . . .	17
ARCHITECTURAL SOCIETIES . . . . .	17
GLOSSARY . . . . .	17
ARCHITECTURAL TERMS USED IN LAW . . . . .	18

# **PART I**

## **PRACTICAL**

## **ARITHMETIC, GEOMETRY AND TRIGONOMETRY**

## **RULES, TABLES AND PROBLEMS**



# 1. PRACTICAL ARITHMETIC

## Mathematical Signs and Characters\*

The following signs and characters are generally used to denote and abbreviate the several mathematical operations:

The sign = means equal to, or equality;

— means minus or less, or subtraction;

÷ means plus, or addition;

× means multiplied by, or multiplication;

÷ or / means divided by, or division;

<sup>2</sup> { are indexes or powers, meaning that the number to which they

<sup>3</sup> { are added is to be squared (<sup>2</sup>) or cubed (<sup>3</sup>);

: is to

:: so is { are signs of proportion;

: to

√ is the RADICAL SIGN and means that the square root of the number before which it is placed is to be extracted;

∛ means that the cube root of the number before which it is placed is to be extracted;

— the BAR indicates that all the numbers under it are to be taken together;

( ) the PARENTHESIS means that all the numbers between are to be taken as one quantity;

. means decimal parts; thus, 2.5 means 2½, 0.46 means 46/100.

° means degrees, ' minutes and " seconds;

∴ means hence;

' means feet;

" means inches.

## Involution

**To Square a Number**, multiply the number by itself, and the product will be the square; thus, the square of 18 = 18<sup>2</sup> = 18 × 18 = 324.

**The Cube of a Number** is the product obtained by multiplying the number by itself, and that product by the number again; thus, the cube of 14 = 14<sup>3</sup> = 14 × 14 × 14 = 2 744.

**The Fourth Power of a Number** is the product obtained by multiplying the number by itself four times; thus, the fourth power of 10 = 10<sup>4</sup> = 10 × 10 × 10 × 10 = 10 000.

## Evolution

**Square Root.** Rule for extracting the square root of a number:

(1) Divide the given number into periods of two figures each, commencing at the right if it is a whole number, and at the decimal point if there are decimals; thus, 10236.8126.

(2) Find the largest square in the left-hand period, and place its root in the quotient; subtract the said square from the left-hand period, and to the remainder bring down the next period for a new dividend.

(3) Double the root already found, and annex one cipher for a trial-divisor; see how many times it will go in the dividend, and put the number in the quotient

\* See, also, pages 123 and 125, Part II.

and also in place of the cipher in the divisor. Multiply this final divisor by the number in the quotient just found, subtract the product from the dividend and to the remainder bring down the next period for a new dividend and proceed as before. If it should be found that the trial divisor cannot be contained in the dividend, bring down the next period for a new dividend, annex another cipher to the trial divisor, put a cipher in the quotient and proceed as before.

**Example.**

10236.8126 (101.17, the square root

$$\begin{array}{r}
 \overset{1}{\overline{201}} 0236 \\
 \underline{201} \phantom{0000} \\
 2021)3581 \\
 \underline{2021} \phantom{000} \\
 20227)156026 \\
 \underline{141589} \phantom{00} \\
 14437
 \end{array}$$

**Cube Root.** To extract the cube root of a number, point off the number from right to left into periods of three figures each, and, if there is a decimal, commence at the decimal point and point off into periods, going both ways.

Ascertain the highest root of the first period, and place it to the right of the number, as in long division; cube the root thus found and subtract from the first period; to the remainder annex the next period; square the root already found, multiply by three and annex two ciphers for the trial divisor. Find how many times this trial divisor is contained in the dividend and write the result in the root.

Add together the trial divisor, three times the product of the first figure of the root by the second with one cipher annexed, and the square of the second figure in the root; multiply the sum by the last figure in the root, and subtract from the dividend; to the remainder annex the next period and proceed as before.

When the trial divisor is greater than the dividend, write a cipher in the root, annex the next period to the dividend and proceed as before.

**Example.** Required, the cube root of 493039 or  $\sqrt[3]{493039}$

493039 (79, the cube root

$$\begin{array}{r}
 7 \times 7 \times 7 = 343 \\
 7 \times 7 \times 3 = 14700 \\
 7 \times 9 \times 3 = 1890 \\
 9 \times 9 = 81 \\
 \hline
 16671
 \end{array}
 \begin{array}{r}
 \underline{343} \\
 150039 \\
 \hline
 150039
 \end{array}$$

**Example.** Required, the cube root of 403583.419 or  $\sqrt[3]{403583.419}$

403583.419 (73.9, the cube root

$$\begin{array}{r}
 7 \times 7 \times 7 = 343 \\
 7 \times 7 \times 3 = 14700 \\
 7 \times 3 \times 3 = 630 \\
 3 \times 3 = 9 \\
 \hline
 15339
 \end{array}
 \begin{array}{r}
 \underline{343} \\
 60583 \\
 \hline
 46017 \\
 \hline
 14566419 \\
 \hline
 14566419
 \end{array}$$



**Example.** Required, the cube root of 158252.632929 or  $\sqrt[3]{158252.632929}$

158252.632929 (54.09, the cube root

$5 \times 5 \times 5 = 125$	33252
$5 \times 5 \times 3 = 7500$	
$5 \times 4 \times 3 = 600$	
$4 \times 4 = 16$	
$8116$	32464
$540 \times 540 \times 3 = 87480000$	788632929
$540 \times 9 \times 3 = 145800$	
$9 \times 9 = 81$	
$87625881$	788632929



**TABLES**  
**OF**  
**SQUARES, CUBES, SQUARE ROOTS, CUBE**  
**ROOTS AND RECIPROCAL**

**From 1 to 1054**

---

The following table, taken from Searle's Field Engineering, will be found of great convenience in finding the square, cube, square root, cube root and reciprocal of any number from 1 to 1054. The reciprocal of a number is the quotient obtained by dividing 1 by the number. Thus, the reciprocal of 8 is  $1 \div 8 = 0.125$ .

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
1	1	1	1.0000000	1.0000000	1.000000000
2	4	8	1.4142136	1.2599210	.500000000
3	9	27	1.7320508	1.4422496	.333333333
4	16	64	2.0000000	1.5874011	.250000000
5	25	125	2.2360680	1.7099759	.200000000
6	36	216	2.4494897	1.8171206	.166666667
7	49	343	2.6457513	1.9129312	.142857143
8	64	512	2.8284271	2.0000000	.125000000
9	81	729	3.0000000	2.0800837	.111111111
10	100	1000	3.1622777	2.1544347	.100000000
11	121	1331	3.3166248	2.2239801	.090909091
12	144	1728	3.4641016	2.2894286	.083333333
13	169	2197	3.6055513	2.3513847	.076923077
14	196	2744	3.7416574	2.4101422	.071428571
15	225	3375	3.8729833	2.4662121	.066666667
16	256	4096	4.0000000	2.5198421	.062500000
17	289	4913	4.1231056	2.5712816	.058823529
18	324	5832	4.2426407	2.6207414	.055555556
19	361	6859	4.3588989	2.6684016	.052631579

## Squares, Cubes, Square Roots, Cube Roots a

No.			Square roots	Cube
63	3969	250047	7.9372539	8.9790
64	4096	262144	8.0000000	4.0000
65	4225	274625	8.0622577	4.0200
66	4356	287496	8.1240384	4.0410
67	4489	300763	8.1833528	4.0610
68	4624	314432	8.2462113	4.0810
69	4761	328509	8.3066239	4.1010
70	4900	343000	8.3666003	4.1210
71	5041	357911	8.4261498	4.1400
72	5184	373248	8.4852814	4.1600
73	5329	389017	8.5440037	4.1790
74	5476	405224	8.6023253	4.1980
75	5625	421875	8.6602540	4.2170
76	5776	438976	8.7177979	4.2350
77	5929	456533	8.7749644	4.2540
78	6084	474552	8.8317609	4.2720
79	6241	493039	8.8881944	4.2900
80	6400	512000	8.9442719	4.3080
81	6561	531441	9.0000000	4.3260
82	6724	551368	9.0553851	4.3440
83	6889	571787	9.1104336	4.3620
84	7056	592704	9.1651514	4.3790
85	7225	614125	9.2195445	4.3960
86	7396	636056	9.2736185	4.4140
87	7569	658503	9.3273791	4.4310
88	7744	681472	9.3808315	4.4470
89	7921	704969	9.4339811	4.4640
90	8100	729000	9.4868330	4.4810
91	8281	753571	9.5393920	4.4970
92	8464	778688	9.5910630	4.5140
93	8649	804357	9.6436508	4.5300
94	8836	830584	9.6953597	4.5460
95	9025	857375	9.7467943	4.5620
96	9216	884736	9.7979590	4.5780
97	9409	912673	9.8488578	4.5940
98	9604	941192	9.8994949	4.6100
99	9801	970299	9.9498744	4.6260
100			0	4.64
101			1	4.65
102			2	4.67
103			3	4.68
104			4	4.70
105			5	4.71
106			6	4.73
107			7	4.74
108			8	4.76
109			9	4.77
110			10	4.79
111			11	4.80
112			12	4.82
113			13	4.83
114			14	4.84
115			15	4.86
116			16	4.87
117			17	4.89
118			18	4.91
119			19	4.9
120			20	4.9
121			21	4.9
122			22	4.9
123			23	4.9
124			24	4.9
125			25	4.9
126			26	4.9
127			27	4.9
128			28	4.9
129			29	4.9
130			30	4.9
131			31	4.9
132			32	4.9
133			33	4.9
134			34	4.9
135			35	4.9
136			36	4.9
137			37	4.9
138			38	4.9
139			39	4.9
140			40	4.9
141			41	4.9
142			42	4.9
143			43	4.9
144			44	4.9
145			45	4.9
146			46	4.9
147			47	4.9
148			48	4.9
149			49	4.9
150			50	4.9
151			51	4.9
152			52	4.9
153			53	4.9
154			54	4.9
155			55	4.9
156			56	4.9
157			57	4.9
158			58	4.9
159			59	4.9
160			60	4.9
161			61	4.9
162			62	4.9
163			63	4.9
164			64	4.9
165			65	4.9
166			66	4.9
167			67	4.9
168			68	4.9
169			69	4.9
170			70	4.9
171			71	4.9
172			72	4.9
173			73	4.9
174			74	4.9
175			75	4.9
176			76	4.9
177			77	4.9
178			78	4.9
179			79	4.9
180			80	4.9
181			81	4.9
182			82	4.9
183			83	4.9
184			84	4.9
185			85	4.9
186			86	4.9
187			87	4.9
188			88	4.9
189			89	4.9
190			90	4.9
191			91	4.9
192			92	4.9
193			93	4.9
194			94	4.9
195			95	4.9
196			96	4.9
197			97	4.9
198			98	4.9
199			99	4.9
200			100	4.9
201			101	4.9
202			102	4.9
203			103	4.9
204			104	4.9
205			105	4.9
206			106	4.9
207			107	4.9
208			108	4.9
209			109	4.9
210			110	4.9
211			111	4.9
212			112	4.9
213			113	4.9
214			114	4.9
215			115	4.9
216			116	4.9
217			117	4.9
218			118	4.9
219			119	4.9
220			120	4.9
221			121	4.9
222			122	4.9
223			123	4.9
224			124	4.9
225			125	4.9
226			126	4.9
227			127	4.9
228			128	4.9
229			129	4.9
230			130	4.9
231			131	4.9
232			132	4.9
233			133	4.9
234			134	4.9
235			135	4.9
236			136	4.9
237			137	4.9
238			138	4.9
239			139	4.9
240			140	4.9
241			141	4.9
242			142	4.9
243			143	4.9
244			144	4.9
245			145	4.9
246			146	4.9
247			147	4.9
248			148	4.9
249			149	4.9
250			150	4.9
251			151	4.9
252			152	4.9
253			153	4.9
254			154	4.9
255			155	4.9
256			156	4.9
257			157	4.9
258			158	4.9
259			159	4.9
260			160	4.9
261			161	4.9
262			162	4.9
263			163	4.9
264			164	4.9
265			165	4.9
266			166	4.9
267			167	4.9
268			168	4.9
269			169	4.9
270			170	4.9
271			171	4.9
272			172	4.9
273			173	4.9
274			174	4.9
275			175	4.9
276			176	4.9
277			177	4.9
278			178	4.9
279			179	4.9
280			180	4.9
281			181	4.9
282			182	4.9
283			183	4.9
284			184	4.9
285			185	4.9
286			186	4.9
287			187	4.9
288			188	4.9
289			189	4.9
290			190	4.9
291			191	4.9
292			192	4.9
293			193	4.9
294			194	4.9
295			195	4.9
296			196	4.9
297			197	4.9
298			198	4.9
299			199	4.9
300			200	4.9
301			201	4.9
302			202	4.9
303			203	4.9
304			204	4.9
305			205	4.9
306			206	4.9
307			207	4.9
308			208	4.9
309			209	4.9
310			210	4.9
311			211	4.9
312			212	4.9
313			213	4.9
314			214	4.9
315			215	4.9
316			216	4.9
317			217	4.9
318			218	4.9
319			219	4.9
320			220	4.9
321			221	4.9
322			222	4.9
323			223	4.9
324			224	4.9
325			225	4.9
326			226	4.9
327			227	4.9
328			228	4.9
329			229	4.9
330			230	4.9
331			231	4.9
332			232	4.9
333			233	4.9
334			234	4.9
335			235	4.9
336			236	4.9
337			237	4.9
338			238	4.9
339			239	4.9
340			240	4.9
341			241	4.9
342			242	4.9
343			243	4.9
344			244	4.9
345			245	4.9
346			246	4.9
347			247	4.9
348			248	4.9
349			249	4.9
350			250	4.9
351			251	4.9
352			252	4.9
353			253	4.9
354			254	4.9
355			255	4.9
356			256	4.9
357			257	4.9
358			258	4.9
359			259	4.9
360			260	4.9
361			261	4.9
362			262	4.9
363			263	4.9
364			264	4.9
365			265	4.9
366			266	4.9
367			267	4.9
368			268	4.9
369			269	4.9
370			270	4.9
371			271	4.9
372			272	4.9
373			273	4.9
374			274	4.9
375			275	4.9
376			276	4.9
377				

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
125	15625	1953125	11.1803399	5.0000000	.008000000
126	15876	2000376	11.2249722	5.0132979	.007936508
127	16129	2048383	11.2694277	5.0265257	.007874016
128	16384	2097152	11.3137085	5.0396842	.007812500
129	16641	2146689	11.3578167	5.0527743	.007751938
130	16900	2197000	11.4017543	5.0657970	.007692308
131	17161	2248091	11.4455231	5.0787531	.007633588
132	17424	2299968	11.4891253	5.0916434	.007575758
133	17689	2352637	11.5325626	5.1044687	.007518797
134	17956	2406104	11.5758369	5.1172299	.007462687
135	18225	2460375	11.6189500	5.1299278	.007407407
136	18496	2515456	11.6619038	5.1425632	.007352941
137	18769	2571353	11.7046999	5.1551367	.007299270
138	19044	2628072	11.7473401	5.1676493	.007246377
139	19321	2685619	11.7898261	5.1801015	.007194245
140	19600	2744000	11.8321596	5.1924941	.007142857
141	19881	2803221	11.8743421	5.2048279	.007092199
142	20164	2333288	11.9163753	5.2171034	.007042254
143	20449	2924207	11.9582607	5.2293215	.006993007
144	20736	2985984	12.0000000	5.2414828	.006944444
145	21025	3048625	12.0415946	5.2535879	.006896552
146	21316	3112136	12.0830460	5.2656374	.006849315
147	21609	3176523	12.1243557	5.2776321	.006802721
148	21904	3241792	12.1655251	5.2895725	.006756757
149	22201	3307949	12.2065556	5.3014592	.006711409
150	22500	3375000	12.2474487	5.3132928	.006666667
151	22801	3442951	12.2882057	5.3250740	.006622517
152	23104	3511808	12.3288280	5.3368033	.006578947
153	23409	3581577	12.3693169	5.3484812	.006535948
154	23716	3652264	12.4096736	5.3601084	.006493506
155	24025	3723875	12.4498996	5.3716854	.006451613
156	24336	3796416	12.4899960	5.3832126	.006410256
157	24649	3869893	12.5299641	5.3946907	.006369427
158	24964	3944312	12.5698051	5.4061202	.006329114
159	25281	4019679	12.6095202	5.4175015	.006289308
160	25600	4096000	12.6491106	5.4288352	.006250000
161	25921	4173281	12.6385775	5.4401218	.006211180
162	26244	4251528	12.7279221	5.4513618	.006172840
163	26569	4330747	12.7671453	5.4625556	.006134969
164	26896	4410944	12.8062485	5.4737037	.006097561
165	27225	4492125	12.8452326	5.4848066	.006060606
166	27556	4574296	12.8840987	5.4958647	.006024096
167	27889	4657463	12.9228480	5.5068784	.005988024
168	28224	4741632	12.9614814	5.5178484	.005952381
169	28561	4826809	13.0000000	5.5287748	.005917160
170	28900	4913000	13.0384048	5.5396583	.005882853
171	29241	5000211	13.0766968	5.5504991	.005847953
172	29584	5088448	13.1148770	5.5612978	.005813953
173	29929	5177717	13.1529464	5.5720546	.005780347
174	30276	5268024	13.1909060	5.5827702	.005747126
175	30625	5359375	13.2287566	5.5934447	.005714286
176	30976	5451776	13.2664992	5.6040787	.005681818
177	31329	5545233	13.3041347	5.6146724	.005649718
178	31684	5639752	13.3416641	5.6252263	.005617978
179	32041	5735339	13.3790882	5.6357408	.005586592
180	32400	5832000	13.4164079	5.6462162	.005555556
181	32761	5929741	13.4536240	5.6566528	.005524862
182	33124	6028568	13.4907376	5.6670511	.005494505
183	33489	6128487	13.5277493	5.6774114	.005464481
184	33856	6229504	13.5646600	5.6877340	.005434783
185	34225	6331625	13.6014705	5.6980192	.005405405
186	34596	6434856	13.6381817	5.7082675	.005376344

Squares, Cubes, Square Roots, Cube Ro

	Squares	Cubes	Square roots
34000	34000	6539203	13.6747943
35344	35344	6644672	13.7113092
35721	35721	6751269	13.7477271
36100	36100	6859000	13.7840488
36481	36481	6967871	13.8202750
36864	36864	7077888	13.8564065
37249	37249	7189057	13.8924440
37636	37636	7301384	13.9283883
38025	38025	7414875	13.9642400
38416	38416	7529536	14.0000000
38809	38809	7645378	14.0356688
39204	39204	7762392	14.0712473
39601	39601	7880599	14.1067360
40000	40000	8000000	14.1421356
40401	40401	8120601	14.1774469
40804	40804	8242408	14.2126704
41209	41209	8365427	14.2478068
41616	41616	8489664	14.2828569
42025	42025	8615125	14.3178211
42436	42436	8741816	14.3527001
42849	42849	8869743	14.3874946
43264	43264	8998912	14.4222051
43681	43681	9129329	14.4568323
44100	44100	9261000	14.4913767
44521	44521	9393931	14.5258390
44944	44944	9528128	14.5602198
45369	45369	9663597	14.5945195
45796	45796	9800344	14.6287388
46225	46225	9938375	14.6628783
46656	46656	10077696	14.6969386
47089	47089	10218313	14.7309199
47524	47524	10360232	14.7648231
47961	47961	10503459	14.7986486
48400	48400	10648000	14.8323970
48841	48841	10793861	14.8660687
49284	49284	10941048	14.8996644
49729	49729	11089567	14.9331845
50176	50176	11239424	14.9666295
50625	50625	11390625	15.0000000
51076	51076	11543176	15.0332964
51529	51529	11697083	15.0665192
51984	51984	11852352	15.0996689
52441	52441	12008989	15.1327460
52900	52900	1	15.1657509
53361	53361	1	15.1986842
53824	53824	1	15.2315462
54289	54289	1	15.2643375
54756	54756	1	15.2970585
55225	55225	1	15.3297097
55696	55696	1	15.3622916
56169	56169	1	15.3948049
56644	56644	1	15.4272486
57121	57121	1	15.4596248
57600	57600	1	15.4919334
58081	58081	1	15.5241747
58564	58564	1	15.5563492
59049	59049	1	15.5884573
59536	59536	1	15.6204994
60025	60025	1	15.6524759
60516	60516	1	15.6843871
61009	61009	1	15.7162336
61504	61504	1	15.7480157

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
249	62001	15438249	15.7797338	6.2911946	.004016064
250	62500	15625000	15.8113883	6.2996053	.004000000
251	63001	15818251	15.8429795	6.3079935	.003984064
252	63504	16003008	15.8745079	6.3163596	.003968254
253	64009	16194277	15.9059737	6.3247035	.003952569
254	64516	16387064	15.9373775	6.3330256	.003937008
255	65025	16581375	15.9687194	6.3413257	.003921569
256	65536	16777216	16.0000000	6.3496042	.003906250
257	66049	16974593	16.0312195	6.3578611	.003891051
258	66564	17173512	16.0623784	6.3660968	.003875969
259	67081	17373979	16.0934769	6.3743111	.003861004
260	67600	17576000	16.1245155	6.3825043	.003846154
261	68121	17779581	16.1554944	6.3906765	.003831418
262	68644	17984728	16.1864141	6.3988279	.003816794
263	69169	18191447	16.2172747	6.4069585	.003802281
264	69696	18399744	16.2480768	6.4150687	.003787879
265	70225	18609625	16.2788206	6.4231583	.003773585
266	70756	18821096	16.3095064	6.4312276	.003759398
267	71289	19034163	16.3401346	6.4392767	.003745318
268	71824	19248832	16.3707055	6.4473057	.003731343
269	72361	19465109	16.4012195	6.4553148	.003717472
270	72900	19683000	16.4316767	6.4633041	.003703704
271	73441	19902511	16.4620776	6.4712736	.003690037
272	73984	20123648	16.4924225	6.4792236	.003676471
273	74529	20346417	16.5227116	6.4871541	.003663004
274	75076	20570824	16.5529454	6.4950653	.003649635
275	75625	20796875	16.5831240	6.5029572	.003636364
276	76176	21024576	16.6132477	6.5108300	.003623188
277	76729	21253938	16.6433170	6.5186839	.003610108
278	77284	21484952	16.6733320	6.5265189	.003597122
279	77841	21717639	16.7032931	6.5343351	.003584229
280	78400	21952000	16.7332005	6.5421326	.003571429
281	78961	22188041	16.7630546	6.5499116	.003558719
282	79524	22425768	16.7928553	6.5576722	.003546099
283	80089	22665187	16.8226038	6.5654144	.003533569
284	80656	22906304	16.8522995	6.5731385	.003521127
285	81225	23149125	16.8819430	6.5808443	.003508772
286	81796	23393656	16.9115345	6.5885323	.003496503
287	82369	23639903	16.9410743	6.5962023	.003484321
288	82944	23887872	16.9705927	6.6038545	.003472222
289	83521	24137569	17.0000000	6.6114890	.003460208
290	84100	24389000	17.0293864	6.6191060	.003448276
291	84681	24642171	17.0587221	6.6267054	.003436426
292	85264	24897088	17.0880075	6.6342874	.003424658
293	85849	25153757	17.1172428	6.6418522	.003412969
294	86436	25412184	17.1464282	6.6493998	.003401361
295	87025	25672375	17.1755640	6.6569302	.003389831
296	87616	25934336	17.2046505	6.6644437	.003378378
297	88209	26198073	17.2336879	6.6719403	.003367003
298	88804	26463592	17.2626765	6.6794200	.003355705
299	89401	26730899	17.2916165	6.6868831	.003344482
300	90000	27000000	17.3205081	6.6943295	.003333333
301	90601	27270901	17.3493516	6.7017593	.003322259
302	91204	27543608	17.3781472	6.7091729	.003311258
303	91809	27818127	17.4068952	6.7165700	.003300330
304	92416	28094464	17.4355958	6.7239508	.003289474
305	93025	28372625	17.4642492	6.7313155	.003278689
306	93636	28652616	17.4928557	6.7386641	.003267974
307	94249	28934443	17.5214155	6.7459967	.003257329
308	94864	29218112	17.5499288	6.7533134	.003246753
309	95481	29503629	17.5783958	6.7606143	.003236246
310	96100	29791000	17.6068169	6.7678995	.003225806



**Squares, Cubes, Square Roots, Cube Roots and**

		Square roots	Cube roots
98721	30080231	17.6281921	6.778101
97344	30371328	17.6635217	6.783422
97900	30664297	17.6918060	6.788661
98506	30959144	17.7200451	6.793884
99223	31255878	17.7482393	6.804092
99636	31564496	17.7763888	6.811284
100489	31865013	17.8044938	6.818405
101124	32157432	17.8325545	6.825832
101761	32461759	17.8606711	6.832771
102400	32768000	17.8888438	6.839802
103041	33076161	17.9164729	6.847021
103684	33386248	17.9443584	6.854124
104329	33698267	17.9722008	6.861212
104976	34012224	18.0000000	6.868285
105625	34328125	18.0277564	6.875344
106276	34645976	18.0554701	6.882386
106929	34965783	18.0831413	6.889415
107584	35287552	18.1107703	6.896434
108241	35611289	18.1383571	6.903435
108900	35937000	18.1659021	6.910423
109561	36264691	18.1934064	6.917396
110224	36594368	18.2208672	6.924355
110889	36926037	18.2482876	6.931300
111556	37259704	18.2756669	6.938232
112225	37595375	18.3030062	6.945148
112896	37933056	18.3303028	6.952053
113569	38272753	18.3575598	6.958943
114244	38614472	18.3847763	6.965819
114921	38958219	18.4119626	6.972683
115600	39304000	18.4390889	6.979532
116281	39651821	18.4661853	6.986368
116964	40001668	18.4932420	6.993190
117649	40353607	18.5202592	7.000000
118336	40707584	18.5472370	7.006796
119025	41063625	18.5741756	7.013578
119716	41421736	18.6010752	7.020349
120409	41781923	18.6279360	7.027105
121104	42144192	18.6547581	7.033849
121801	42508549	18.6815417	7.040580
122500	42875000	18.7082869	7.047298
123201	43243551	18.7349940	7.054004
123904	43614208	18.7616630	7.060690
124609	43986977	18.7882942	7.067376
125316	44361864	18.8148877	7.074044
126025	44738875	18.8414437	7.080698
126736	45118016	18.8679623	7.087341
127449	45499293	18.8944436	7.093970
128164	45882712	18.9208879	7.100588
128881	46268279	18.9472953	7.107193
129600	46656000	18.9736660	7.113788
130321	47045881	19.0000000	7.120367
131044	47437928	19.0262976	7.126930
131769	47832147	19.0525589	7.133492
132496	48228544	19.0787840	7.140037
133225	48627125	19.1049732	7.146568
133956	49027896	19.1311265	7.153090
134689	49430863	19.1572441	7.159598
135424	49836032	19.1833261	7.166095
136161	50243409	19.2093727	7.172580
136900	50653000	19.2353841	7.179054
137641	51064811	19.2613603	7.185516
138384	51478848	19.2873015	7.191966

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
373	138129	51890117	19 3123079	7 1004050	000000055
374	138876	52113034	19 3200790	7 2040323	000073707
375	140025	52334875	19 3240167	7 3113470	002000007
376	141176	52554876	19 3271104	7 2176322	002600074
377	142329	52773033	19 33007104	7 3240430	002626200
378	143484	52989332	19 3322221	7 2304308	002645003
379	144641	53203830	19 3347033	7 2367072	002664423
380	145800	53416500	19 3365287	7 2431206	002681570
381	146961	53627341	19 3382213	7 2496046	002694672
382	148124	53836350	19 3405303	7 2560413	002717001
383	149289	54043527	19 3423350	7 2621676	002710006
384	147456	542489104	19 34408170	7 2684034	002804107
385	148625	54452528	19 34574100	7 2747004	002804403
386	149796	54654386	19 3473237	7 2810704	002804674
387	149796	54854403	19 34883150	7 2873017	002853070
388	150944	55052573	19 35027150	7 2935330	002877230
389	152091	55248900	19 35170000	7 2997030	002870094
390	153236	55443380	19 3531177	7 3058140	002864103
391	154381	55636011	19 35452100	7 3118320	002857545
392	155524	55826800	19 35591000	7 3178014	002851000
393	156669	56015757	19 35728270	7 3237206	002844530
394	157816	56202884	19 35864000	7 3295910	002838071
395	158965	56388181	19 35998000	7 3354130	002831640
396	160116	56571648	19 3613027	7 3412306	002825243
397	161269	56753285	19 36261000	7 3470530	002818892
398	162424	56933092	19 36390000	7 3528704	002812563
399	163581	57111080	19 36518044	7 3586810	002806260
400	164740	57287249	20 0000000	7 3644850	002800000
401	165899	57461591	20 0240044	7 3702820	002793700
402	167060	57634109	20 0480077	7 3760722	002787362
403	168221	57804802	20 0720000	7 3818557	002781000
404	169384	57973670	20 0960012	7 3876320	002774610
405	170549	58140713	20 1200018	7 3934010	002768190
406	171716	58305931	20 1440017	7 3991620	002761740
407	172885	58469324	20 1680010	7 4049160	002755260
408	174056	58630892	20 1920000	7 4106630	002748760
409	175229	58790635	20 2160000	7 4164030	002742240
410	176404	58948554	20 2400000	7 4221360	002735700
411	177581	59104649	20 2640000	7 4278620	002729140
412	178760	59258920	20 2880000	7 4335810	002722560
413	179941	59411367	20 3120000	7 4392930	002715960
414	181124	59561990	20 3360000	7 4450000	002709340
415	182309	59710789	20 3600000	7 4507010	002702700
416	183496	59857764	20 3840000	7 4563960	002696040
417	184685	59992915	20 4080000	7 4620850	002689360
418	185876	60126242	20 4320000	7 4677680	002682660
419	187069	60257745	20 4560000	7 4734450	002675940
420	188264	60387424	20 4800000	7 4791160	002669200
421	189461	60515279	20 5040000	7 4847810	002662440
422	190660	60641310	20 5280000	7 4904400	002655660
423	191861	60765527	20 5520000	7 4960930	002648860
424	193064	60887930	20 5760000	7 5017400	002642040
425	194269	61008519	20 6000000	7 5073810	002635200
426	195476	61127294	20 6240000	7 5130160	002628340
427	196685	61244255	20 6480000	7 5186450	002621460
428	197896	61359402	20 6720000	7 5242680	002614560
429	199109	61472735	20 6960000	7 5298850	002607640
430	199324	61584254	20 7200000	7 5354960	002600700
431	185701	61693969	20 7440000	7 5411010	002593740
432	186884	61801880	20 7680000	7 5467000	002586760
433	188069	61907987	20 7920000	7 5522930	002579760
434	189256	62012290	20 8160000	7 5578810	002572740
435	190445	62114789	20 8400000	7 5634640	002565700
436	191636	62215484	20 8640000	7 5690410	002558640
437	192829	62314375	20 8880000	7 5746120	002551560
438	194024	62411462	20 9120000	7 5801770	002544460
439	195221	62506745	20 9360000	7 5857360	002537340
440	196420	62600224	20 9600000	7 5912890	002530200
441	197621	62691909	20 9840000	7 5968360	002523040
442	198824	62781700	20 10080000	7 6023770	002515860
443	199029	62869607	20 10320000	7 6079120	002508660
444	200236	62955630	20 10560000	7 6134410	002501440
445	201445	63039769	20 10800000	7 6189640	002494200
446	202656	63122024	20 11040000	7 6244810	002486940
447	203869	63202395	20 11280000	7 6299920	002479660
448	205084	63280882	20 11520000	7 6354970	002472360
449	206301	63357485	20 11760000	7 6409960	002465040
450	207520	63432204	20 12000000	7 6464890	002457700

# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
435	189225	82312875	20.8566536	7.5769849	.002298851
436	190096	82881856	20.8806130	7.5827865	.002293578
437	190969	83453453	20.9045450	7.5885793	.002288330
438	191844	84027672	20.9284495	7.5943633	.002283104
439	192721	84604519	20.9523268	7.6001385	.002277904
440	193600	85184000	20.9761770	7.6059049	.002272727
441	194481	85766121	21.0000000	7.6116826	.002267574
442	195364	86350888	21.0237960	7.6174116	.002262444
443	196249	86938307	21.0475652	7.6231519	.002257334
444	197136	87528384	21.0713075	7.6288837	.002252254
445	198025	88121125	21.0950231	7.6346067	.002247197
446	198916	88716536	21.1187121	7.6403213	.002242154
447	199809	89314623	21.1423745	7.6460272	.002237134
448	200704	89915392	21.1660105	7.6517247	.002232144
449	201601	90518849	21.1896201	7.6574138	.002227177
450	202500	91125000	21.2132034	7.6630943	.002222222
451	203401	91733851	21.2367606	7.6687665	.002217291
452	204304	92345408	21.2602916	7.6744303	.002212384
453	205209	92959677	21.2837967	7.6800857	.002207504
454	206116	93576664	21.3072758	7.6857328	.002202644
455	207025	94196375	21.3307290	7.6913717	.002197804
456	207936	94818816	21.3541565	7.6970023	.002192984
457	208849	95443993	21.3775583	7.7026246	.002188184
458	209764	96071912	21.4009346	7.7082388	.002183404
459	210681	96702579	21.4242853	7.7138448	.002178644
460	211600	97336000	21.4476106	7.7194426	.002173914
461	212521	97972181	21.4709106	7.7250325	.002169197
462	213444	98611128	21.4941853	7.7306141	.002164504
463	214369	99252847	21.5174348	7.7361877	.002159827
464	215296	99897344	21.5406592	7.7417532	.002155177
465	216225	100544625	21.5638587	7.7473109	.002150534
466	217156	101194096	21.5870331	7.7528606	.002145924
467	218089	101847563	21.6101828	7.7584023	.002141324
468	219024	102503232	21.6332077	7.7639361	.002136754
469	219961	103161709	21.6564078	7.7694620	.002132194
470	220900	103823000	21.6794834	7.7749801	.002127664
471	221841	104487111	21.7025344	7.7804904	.002123144
472	222784	105154048	21.7255610	7.7859928	.002118644
473	223729	105823817	21.7485632	7.7914875	.002114164
474	224676	106496424	21.7715411	7.7969745	.002109704
475	225625	107171875	21.7944947	7.8024538	.002105264
476	226576	107850176	21.8174242	7.8079254	.002100844
477	227529	108531333	21.8403297	7.8133892	.002096434
478	228484	109215352	21.8632111	7.8188456	.002092054
479	229441	109902239	21.8860686	7.8242942	.002087684
480	230400	110592000	21.9089023	7.8297353	.002083334
481	231361	111284641	21.9317122	7.8351688	.002079004
482	232324	111980168	21.9544984	7.8405949	.002074684
483	233289	112678587	21.9772610	7.8460134	.002070394
484	234256	113379904	22.0000000	7.8514244	.002066114
485	235225	114084125	22.0227155	7.8568281	.002061854
486	236196	114791256	22.0454077	7.8622242	.002057614
487	237169	115501303	22.0680765	7.8676130	.002053384
488	238144	116214272	22.0907220	7.8729944	.002049184
489	239121	116930169	22.1133444	7.8783684	.002044994
490	240100	117649000	22.1359436	7.8837352	.002040814
491	241081	118370771	22.1585198	7.8890946	.002036664
492	242064	119095488	22.1810730	7.8944468	.002032524
493	243049	119823157	22.2036033	7.8997917	.002028394
494	244036	120553784	22.2261108	7.9051294	.002024264
495	245025	121287375	22.2485955	7.9104599	.002020144
496	246016	122023936	22.2710575	7.9157832	.002016114

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
497	247009	122763473	22.2934968	7.9210994	.002012072
498	248004	123505992	22.3159136	7.9264085	.002008032
499	249001	124251499	22.3383079	7.9317104	.002004008
500	250000	125000000	22.3606798	7.9370058	.002000000
501	251001	125751501	22.3830293	7.9422931	.001996008
502	252004	126506008	22.4053565	7.9475739	.001992032
503	253009	127263527	22.4276615	7.9528477	.001988072
504	254016	128024064	22.4499443	7.9581144	.001984127
505	255025	128787625	22.4722051	7.9633743	.001980198
506	256036	129554216	22.4944438	7.9686271	.001976285
507	257049	130323843	22.5166605	7.9738731	.001972387
508	258064	131096512	22.5388553	7.9791122	.001968504
509	259081	131872229	22.5610283	7.9843444	.001964637
510	260100	132651000	22.5831796	7.9895697	.001960784
511	261121	133432831	22.6053091	7.9947883	.001956947
512	262144	134217728	22.6274170	8.0000000	.001953125
513	263169	135005697	22.6495033	8.0052049	.001949318
514	264196	135796744	22.6715681	8.0104032	.001945525
515	265225	136590875	22.6936114	8.0155946	.001941748
516	266256	137388096	22.7156334	8.0207794	.001937984
517	267289	138188413	22.7376340	8.0259574	.001934236
518	268324	138991832	22.7596134	8.0311287	.001930502
519	269361	139798359	22.7815715	8.0362935	.001926782
520	270400	140608000	22.8035085	8.0414515	.001923077
521	271441	141420761	22.8254244	8.0466030	.001919386
522	272484	142236648	22.8473193	8.0517479	.001915709
523	273529	143055667	22.8691933	8.0568862	.001912046
524	274576	143877824	22.8910463	8.0620180	.001908397
525	275625	144703125	22.9128785	8.0671432	.001904762
526	276676	145531576	22.9346899	8.0722620	.001901141
527	277729	146363183	22.9564806	8.0773743	.001897533
528	278784	147197952	22.9782506	8.0824800	.001893939
529	279841	148035889	23.0000000	8.0875794	.001890359
530	280900	148877000	23.0217289	8.0926723	.001886792
531	281961	149721291	23.0434372	8.0977589	.001883239
532	283024	150568768	23.0651252	8.1028390	.001879699
533	284089	151419437	23.0867928	8.1079128	.001876173
534	285156	152273304	23.1084400	8.1129803	.001872659
535	286225	153130375	23.1300670	8.1180414	.001869159
536	287296	153990656	23.1516738	8.1230962	.001865672
537	288369	154854153	23.1732605	8.1281447	.001862197
538	289444	155720872	23.1948270	8.1331870	.001858736
539	290521	156590819	23.2163735	8.1382230	.001855288
540	291600	157464000	23.2379001	8.1432529	.001851852
541	292681	158340421	23.2594067	8.1482765	.001848429
542	293764	159220088	23.2808935	8.1532939	.001845018
543	294849	160103007	23.3023604	8.1583051	.001841621
544	295936	160989184	23.3238076	8.1633102	.001838235
545	297025	161878625	23.3452351	8.1683092	.001834862
546	298116	162771336	23.3666429	8.1733020	.001831502
547	299209	163667323	23.3880311	8.1782888	.001828154
548	300304	164566592	23.4093998	8.1832695	.001824818
549	301401	165469149	23.4307490	8.1882441	.001821494
550	302500	166375000	23.4520788	8.1932127	.001818182
551	303601	167284151	23.4733892	8.1981753	.001814882
552	304704	168196608	23.4946802	8.2031319	.001811594
553	305809	169112377	23.5159520	8.2080825	.001808318
554	306916	170031464	23.5372046	8.2130271	.001805054
555	308025	170953875	23.5584380	8.2179657	.001801802
556	309136	171879616	23.5796522	8.2228985	.001798561
557	310249	172808693	23.6008474	8.2278254	.001795332
558	311364	173741112	23.6220236	8.2327463	.001792115

60	312481	174870579	23	6431815	8	2376614
61	313600	176614000	23	6443191	8	2426708
62	314721	178358441	23	6454356	8	2474740
63	315844	177604328	23	7065302	8	2520716
64	316969	178454547	23	7276210	8	2572638
65	318096	179408144	23	7486843	8	2621498
66	319225	1804652123	23	7687286	8	2670294
67	320356	1815258465	23	7887543	8	2719036
68	321489	1825890283	23	8117618	8	2767726
69	322624	1836547432	23	8327408	8	2816368
70	323761	1847230000	23	8537209	8	2864962
71	324899	1857938000	23	8746798	8	2913444
72	326041	1868671411	23	8956083	8	2961908
73	327184	1879430248	23	9165215	8	3010306
74	328329	1890214517	23	9374184	8	3058651
75	329476	1901024224	23	9582971	8	3106941
76	330625	1911859375	23	9791576	8	3155176
77	331776	1922720076	24	9999999	8	3203363
78	332929	1933606323	24	10208243	8	3251478
79	334084	1944518122	24	10416308	8	3299542
80	335241	1955445480	24	10624188	8	3347563
81	336400	1966388400	24	10831891	8	3395549
82	337561	1977346881	24	11039416	8	3443410
83	338724	1988320928	24	11246762	8	3491256
84	339889	1999310537	24	11453929	8	3539087
85	341056	2010315704	24	11660910	8	3586904
86	342225	2021336425	24	11867712	8	3634698
87	343396	2032372696	24	12074340	8	3682478
88	344569	2043424513	24	12280790	8	3730244
89	345744	2054491872	24	12487062	8	3777996
90	346921	2065574780	24	12693158	8	3825733
91	348100	2076673240	24	12899076	8	3873456
92	349281	2087787257	24	13104816	8	3921165
93	350464	2098916828	24	13310379	8	3968860
94	351649	2110061949	24	13515764	8	4016541
95	352836	2121222625	24	13721972	8	4064208
96	354025	2132398861	24	13927999	8	4111861
97	355216	2143590663	24	14133846	8	4159499
98	356409	2154798035	24	14339510	8	4207122
99	357604	2166020983	24	14544992	8	4254730
100	358801	2177259513	24	14750292	8	4302323
101	360000	2188513630	24	14955409	8	4349901
102	361201	2199783349	24	15160344	8	4397464
103	362404	2211068675	24	15365096	8	4445012
104	363609	2222369613	24	15569666	8	4492545
105	364816	2233686168	24	15774053	8	4540063
106	366025	2245018345	24	15978257	8	4587566
107	367236	2256366149	24	16182278	8	4635054
108	368449	2267729585	24	16386116	8	4682527
109	369664	2279108658	24	16589771	8	4730000
110	370881	2290503373	24	16793243	8	4777463
111	372100	2301913735	24	16996532	8	4824916
112	373321	2313339749	24	17199639	8	4872359
113	374544	2324781420	24	17402564	8	4919792
114	375769	2336238753	24	17605307	8	4967215
115	376996	2347711753	24	17807868	8	5014628
116	378225	2359200425	24	18010247	8	5062031
117	379456	2370704773	24	18212444	8	5109424
118	380689	2382224803	24	18414459	8	5156807
119	381924	2393760520	24	18616292	8	5204180
120	383161	2405311929	24	18817943	8	5251543
121	384400	2416879025	24	19019412	8	5298896
122	385641	2428461813	24	19220700	8	5346239
123	386884	2440060300	24	19421807	8	5393572
124	388129	2451674491	24	19622734	8	5440895
125	389376	2463304392	24	19823480	8	5488208
126	390625	2474950009	24	20024045	8	5535511
127	391876	2486611338	24	20224429	8	5582804
128	393129	2498288385	24	20424632	8	5630087
129	394384	2509981156	24	20624654	8	5677360
130	395641	2521689657	24	20824495	8	5724623
131	396899	2533413893	24	21024156	8	5771876
132	398159	2545153870	24	21223637	8	5819119
133	399420	2556909593	24	21422938	8	5866352
134	400682	2568681068	24	21622059	8	5913575
135	401945	2580468291	24	21820999	8	5960788
136	403209	2592271268	24	22019759	8	6007991
137	404475	2604090005	24	22218338	8	6055184
138	405742	2615924508	24	22416737	8	6102367
139	407010	2627774783	24	22614956	8	6149540
140	408279	2639640826	24	22812995	8	6196703
141	409549	2651522643	24	23010854	8	6243856
142	410820	2663420240	24	23208533	8	6290999
143	412092	2675333713	24	23406032	8	6338132
144	413365	2687263058	24	23603351	8	6385255
145	414639	2699208281	24	23800490	8	6432368
146	415914	2711169388	24	24007449	8	6479471
147	417190	2723146385	24	24214228	8	6526564
148	418467	2735139278	24	24420827	8	6573647
149	419745	2747148073	24	24627246	8	6620720
150	421024	2759172776	24	24833485	8	6667783



No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
621	385641	239483061	24.9198716	8.5316009	.001610306
622	390884	240641848	24.9399278	8.5361780	.001607717
623	388129	241804367	24.9599679	8.5407501	.001605136
624	389376	242970624	24.9799920	8.5453173	.001602564
625	390625	244140625	25.0000000	8.5498797	.001600000
626	391876	245314376	25.0199920	8.5544372	.001597444
627	393129	246491883	25.0399681	8.5589899	.001594896
628	394384	247673152	25.0599282	8.5635377	.001592357
629	395641	248858189	25.0798724	8.5680807	.001589825
630	396900	250047000	25.0998008	8.5726189	.001587302
631	398161	251239591	25.1197134	8.5771523	.001584786
632	399424	252435963	25.1396102	8.5816809	.001582278
633	400689	253636137	25.1594913	8.5862047	.001579779
634	401956	254840104	25.1793566	8.5907238	.001577287
635	403225	256047875	25.1992063	8.5952380	.001574803
636	404496	257259456	25.2190404	8.5997476	.001572327
637	405769	258474853	25.2388589	8.6042525	.001569859
638	407044	259694072	25.2586619	8.6087526	.001567398
639	408321	260917119	25.2784493	8.6132480	.001564945
640	409600	262144000	25.2982213	8.6177388	.001562500
641	410881	263374721	25.3179778	8.6222248	.001560062
642	412164	264609288	25.3377189	8.6267063	.001557632
643	413449	265847707	25.3574447	8.6311830	.001555210
644	414736	267089984	25.3771551	8.6356551	.001552795
645	416025	268336125	25.3968502	8.6401226	.001550388
646	417316	269586136	25.4165301	8.6445855	.001547988
647	418609	270840023	25.4361947	8.6490437	.001545595
648	419904	272097792	25.4558441	8.6534974	.001543210
649	421201	273359449	25.4754784	8.6579465	.001540832
650	422500	274625000	25.4950976	8.6623911	.001538462
651	423801	275894451	25.5147016	8.6668310	.001536098
652	425104	277167808	25.5342907	8.6712665	.001533742
653	426409	278445077	25.5538647	8.6756974	.001531394
654	427716	279726234	25.5734237	8.6801237	.001529052
655	429025	281011375	25.5929678	8.6845456	.001526718
656	430336	282300416	25.6124969	8.6889630	.001524390
657	431649	283593393	25.6320112	8.6933759	.001522070
658	432964	284890312	25.6515107	8.6977843	.001519757
659	434281	286191179	25.6709953	8.7021882	.001517451
660	435600	287496000	25.6904652	8.7065877	.001515152
661	436921	288804781	25.7099203	8.7109827	.001512859
662	438244	290117523	25.7293607	8.7153734	.001510574
663	439569	291434247	25.7487864	8.7197596	.001508296
664	440896	292754944	25.7681975	8.7241414	.001506024
665	442225	294079325	25.7875939	8.7285187	.001503759
666	443556	295408296	25.8069758	8.7328918	.001501502
667	444889	296740963	25.8263431	8.7372604	.001499250
668	446224	298077632	25.8456960	8.7416246	.001497006
669	447561	299418309	25.8650343	8.7459846	.001494768
670	448900	300763000	25.8843582	8.7503401	.001492537
671	450241	302111711	25.9036677	8.7546913	.001490313
672	451584	303464448	25.9229628	8.7590383	.001488095
673	452929	304821217	25.9422435	8.7633809	.001485884
674	454276	306182024	25.9615100	8.7677192	.001483680
675	455625	307546875	25.9807621	8.7720532	.001481481
676	456976	308915776	26.0000000	8.7763830	.001479290
677	458329	310288733	26.0192237	8.7807084	.001477105
678	459684	311665752	26.0384331	8.7850296	.001474926
679	461041	313046839	26.0576284	8.7893466	.001472754
680	462400	314432000	26.0768096	8.7936593	.001470588
681	463761	315821241	26.0959767	8.7979679	.001468429
682	465124	317214568	26.1151297	8.8022721	.001466276

# Squares, Cubes, Square Roots, Cube Roots and Re

No.	Squares	Cubes	Square roots	Cube roots
683	466489	318611987	26.1342687	8.8065722
684	467856	320013504	26.1533937	8.8108681
685	469225	321419125	26.1725047	8.8151598
686	470596	322828856	26.1916017	8.8194474
687	471969	324242703	26.2106848	8.8237307
688	473344	325660672	26.2297511	8.8280009
689	474721	327082769	26.2488095	8.8322850
690	476100	328509000	26.2678511	8.8365559
691	477481	329939371	26.2868789	8.8408227
692	478864	331373888	26.3058929	8.8450854
693	480249	332812557	26.3248932	8.8493440
694	481636	334255384	26.3438797	8.8535985
695	483025	335702375	26.3628527	8.8578489
696	484416	337153536	26.3818119	8.8620952
697	485809	338608873	26.4007576	8.8663375
698	487204	340068392	26.4196896	8.8705757
699	488601	341532099	26.4386081	8.8748099
700	490000	343000000	26.4575131	8.8790400
701	491401	344472101	26.4764046	8.8832661
702	492804	345948408	26.4952826	8.8874882
703	494209	347428927	26.5141472	8.8917063
704	495616	348913664	26.5329983	8.8959204
705	497025	350402625	26.5518361	8.9001304
706	498436	351895816	26.5706605	8.9043366
707	499849	353393243	26.5894716	8.9085287
708	501264	354894912	26.6082694	8.9127209
709	502681	356400829	26.6270539	8.9169311
710	504100	357911000	26.6458252	8.9211214
711	505521	359425431	26.6645833	8.9253078
712	506944	360944128	26.6833281	8.9294902
713	508369	362467097	26.7020598	8.9336687
714	509796	363994344	26.7207784	8.9378433
715	511225	365525875	26.7394839	8.9420140
716	512656	367061696	26.7581763	8.9461809
717	514089	368601813	26.7768557	8.9503438
718	515524	370146222	26.7955220	8.9545029
719	516961	371694959	26.8141754	8.9586581
720	518400	373248000	26.8328157	8.9628095
721	519841	374805361	26.8514432	8.9669570
722	521284	376367048	26.8700577	8.9711007
723	522729	377933067	26.8886593	8.9752406
724	524176	379503424	26.9072481	8.9793766
725	525625	381078125	26.9258240	8.9835089
726	527076	382657176	26.9443872	8.9876373
727	528529	384240583	26.9629375	8.9917620
728	529984	385828352	26.9814751	8.9958829
729	531441	387420489	27.0000000	9.0000000
730	532900	389017000	27.0185122	9.0041134
731	534361	390617891	27.0370117	9.0082229
732	535824	392223168	27.0554985	9.0123288
733	537289	393832837	27.0739727	9.0164309
734	538756	395446904	27.0924344	9.0205293
735	540225	397065375	27.1108834	9.0246239
736	541696	398688256	27.1293199	9.0287149
737	543169	400315553	27.1477439	9.0328021
738	544644	401947272	27.1661554	9.0368857
739	546121	403583419	27.1845544	9.0409655
740	547600	405224000	27.2029410	9.0450419
741	549081	406869021	27.2213152	9.0491142
742	550564	408518488	27.2396769	9.0531831
743	552049	410172407	27.2580282	9.0572482

No.	Squares	Cubes	Square roots	Cube roots	Reciprocal
745	555025	413400825	27.2948881	0.0043077	00134225
746	556516	415107036	27.3130006	0.0042250	00134045
747	558009	416837123	27.3317317	0.0041426	00133865
748	559504	418591202	27.3509887	0.0040607	00133685
749	561001	420369349	27.3707844	0.0039791	00133505
750	562500	422171625	27.3911379	0.0038978	00133325
751	564001	423998101	27.4120598	0.0038168	00133145
752	565504	425848856	27.4335614	0.0037360	00132965
753	567009	427723977	27.4556537	0.0036554	00132785
754	568516	429623564	27.4783378	0.0035750	00132605
755	570025	431547725	27.5016147	0.0034948	00132425
756	571536	433496568	27.5254954	0.0034148	00132245
757	573049	435470093	27.5499809	0.0033350	00132065
758	574564	437468402	27.5750822	0.0032554	00131885
759	576081	439491605	27.6008003	0.0031760	00131705
760	577600	441539812	27.6271462	0.0030968	00131525
761	579121	443613133	27.6541219	0.0030178	00131345
762	580644	445711678	27.6817294	0.0029390	00131165
763	582169	447835457	27.7099697	0.0028604	00130985
764	583696	449984480	27.7388438	0.0027820	00130805
765	585225	452158757	27.7683527	0.0027038	00130625
766	586756	454358388	27.7985074	0.0026258	00130445
767	588289	456583373	27.8293189	0.0025480	00130265
768	589824	458833822	27.8607882	0.0024704	00130085
769	591361	461109845	27.8929263	0.0023930	00129905
770	592900	463411552	27.9257342	0.0023158	00129725
771	594441	465738953	27.9592129	0.0022388	00129545
772	595984	468092058	27.9933634	0.0021620	00129365
773	597529	470470877	28.0281867	0.0020854	00129185
774	599076	472875412	28.0636938	0.0020090	00129005
775	600625	475305773	28.0998857	0.0019328	00128825
776	602176	477762070	28.1367634	0.0018568	00128645
777	603729	480244313	28.1743279	0.0017810	00128465
778	605284	482752512	28.2125802	0.0017054	00128285
779	606841	485286677	28.2515213	0.0016300	00128105
780	608400	487846818	28.2911522	0.0015548	00127925
781	609961	490432935	28.3314739	0.0014800	00127745
782	611524	493045038	28.3724874	0.0014054	00127565
783	613089	495683127	28.4142037	0.0013310	00127385
784	614656	498347202	28.4566228	0.0012568	00127205
785	616225	501037273	28.5007547	0.0011828	00127025
786	617796	503753350	28.5456004	0.0011090	00126845
787	619369	506495443	28.5911609	0.0010354	00126665
788	620944	509263562	28.6374372	0.0009620	00126485
789	622521	512057707	28.6844303	0.0008888	00126305
790	624100	514877988	28.7321412	0.0008158	00126125
791	625681	517724405	28.7805709	0.0007430	00125945
792	627264	520597068	28.8297294	0.0006704	00125765
793	628849	523495977	28.8796167	0.0005980	00125585
794	630436	526421132	28.9302328	0.0005258	00125405
795	632025	529372543	28.9815777	0.0004538	00125225
796	633616	532350320	29.0336514	0.0003820	00125045
797	635209	535354573	29.0864539	0.0003104	00124865
798	636804	538385312	29.1399854	0.0002390	00124685
799	638401	541442547	29.1942459	0.0001678	00124505
800	640000	544526288	29.2492354	0.0000968	00124325
801	641601	547636535	29.3049539	0.0000260	00124145
802	643204	550773298	29.3614014	0.0000000	00123965
803	644809	553936577	29.4185779	0.0000000	00123785
804	646416	557126382	29.4764834	0.0000000	00123605
805	648025	560342723	29.5351179	0.0000000	00123425
806	649636	563585610	29.5944814	0.0000000	00123245



# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
807	651249	525557943	28.4077454	9.3101750	.001239157
808	652864	527514112	28.4253408	9.3140190	.001237624
809	654481	529475129	28.4429253	9.3178599	.001236094
810	656100	531441000	28.4604989	9.3216975	.001234568
811	657721	533411731	28.4780617	9.3255320	.001233046
812	659344	535387328	28.4956137	9.3293634	.001231527
813	660969	537367797	28.5131549	9.3331916	.001230012
814	662596	539353144	28.5306852	9.3370167	.001228501
815	664225	541343375	28.5482048	9.3408386	.001226994
816	665856	543338496	28.5657137	9.3446575	.001225490
817	667489	545338513	28.5832119	9.3484731	.001223990
818	669124	547343432	28.6006993	9.3522857	.001222494
819	670761	549353259	28.6181760	9.3560952	.001221001
820	672400	551368000	28.6356421	9.3599016	.001219512
821	674041	553387661	28.6530976	9.3637049	.001218027
822	675684	555412248	28.6705424	9.3675051	.001216545
823	677329	557441767	28.6879766	9.3713022	.001215067
824	678976	559476224	28.7054002	9.3750963	.001213592
825	680625	561515625	28.7228132	9.3788873	.001212121
826	682276	563559976	28.7402157	9.3826752	.001210654
827	683929	565609283	28.7576077	9.3864600	.001209190
828	685584	567663552	28.7749891	9.3902419	.001207729
829	687241	569722789	28.7923601	9.3940206	.001206273
830	688900	571787000	28.8097206	9.3977964	.001204819
831	690561	573856191	28.8270706	9.4015691	.001203369
832	692224	575930368	28.8444102	9.4053387	.001201923
833	693889	578009537	28.8617394	9.4091054	.001200480
834	695556	580093704	28.8790582	9.4128690	.001199041
835	697225	582182875	28.8963666	9.4166297	.001197605
836	698896	584277056	28.9136646	9.4203873	.001196172
837	700569	586376263	28.9309523	9.4241420	.001194743
838	702244	588480472	28.9482297	9.4278936	.001193317
839	703921	590589719	28.9654967	9.4316423	.001191895
840	705600	592704000	28.9827535	9.4353880	.001190476
841	707281	594823321	29.0000000	9.4391307	.001189061
842	708964	596947688	29.0172363	9.4428704	.001187648
843	710649	599077107	29.0344623	9.4466072	.001186240
844	712336	601211584	29.0516781	9.4503410	.001184834
845	714025	603351125	29.0688837	9.4540719	.001183432
846	715716	605495736	29.0860791	9.4577999	.001182033
847	717409	607645423	29.1032644	9.4615249	.001180638
848	719104	609800192	29.1204396	9.4652470	.001179245
849	720801	611960049	29.1376046	9.4689661	.001177856
850	722500	614125000	29.1547595	9.4726824	.001176471
851	724201	616295051	29.1719043	9.4763957	.001175088
852	725904	618470208	29.1890390	9.4801061	.001173709
853	727609	620650477	29.2061637	9.4838136	.001172333
854	729316	622835864	29.2232784	9.4875182	.001170960
855	731025	625026375	29.2403830	9.4912200	.001169591
856	732736	627222016	29.2574777	9.4949188	.001168224
857	734449	629422793	29.2745623	9.4986147	.001166861
858	736164	631628712	29.2916370	9.5023078	.001165501
859	737881	633839779	29.3087018	9.5059980	.001164144
860	739600	636056000	29.3257566	9.5096854	.001162791
861	741321	638277381	29.3428015	9.5133699	.001161440
862	743044	640503928	29.3598365	9.5170515	.001160093
863	744769	642735647	29.3768616	9.5207303	.001158749
864	746496	644972544	29.3938769	9.5244063	.001157407
865	748225	647214625	29.4108823	9.5280794	.001156068
866	749956	649461896	29.4278779	9.5317497	.001154734
867	751689	651714363	29.4448637	9.5354172	.001153402

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
249	62001	15438249	15.7797338	6.2911946	.004016064
250	62500	15625000	15.8113883	6.2996053	.004000000
251	63001	15813251	15.8429795	6.3079935	.003984064
252	63504	16003008	15.8745079	6.3163596	.003968254
253	64009	16194277	15.9059737	6.3247035	.003952569
254	64516	16387064	15.9373775	6.3330256	.003937008
255	65025	16581375	15.9687194	6.3413257	.003921569
256	65536	16777216	16.0000000	6.3496042	.003906250
257	66049	16974593	16.0312195	6.3578611	.003891051
258	66564	17173512	16.0623784	6.3660968	.003875969
259	67081	17373979	16.0934769	6.3743111	.003861004
260	67600	17576000	16.1245155	6.3825043	.003846154
261	68121	17779581	16.1554944	6.3906765	.003831418
262	68644	17984728	16.1864141	6.3988279	.003816794
263	69169	18191447	16.2172747	6.4069585	.003802281
264	69696	18399744	16.2480768	6.4150687	.003787879
265	70225	18609625	16.2788206	6.4231583	.003773585
266	70756	18821096	16.3095064	6.4312276	.003759398
267	71289	19034163	16.3401346	6.4392767	.003745318
268	71824	19248832	16.3707055	6.4473057	.003731343
269	72361	19465109	16.4012195	6.4553148	.003717472
270	72900	19683000	16.4316767	6.4633041	.003703704
271	73441	19902511	16.4620776	6.4712736	.003690037
272	73984	20123648	16.4924225	6.4792236	.003676471
273	74529	20346417	16.5227116	6.4871541	.003663004
274	75076	20570824	16.5529454	6.4950653	.003649635
275	75625	20796875	16.5831240	6.5029572	.003636364
276	76176	21024576	16.6132477	6.5108300	.003623188
277	76729	21253938	16.6433170	6.5186839	.003610108
278	77284	21484952	16.6733320	6.5265189	.003597122
279	77841	21717639	16.7032931	6.5343351	.003584229
280	78400	21952000	16.7332005	6.5421326	.003571429
281	78961	22188041	16.7630546	6.5499116	.003558719
282	79524	22425768	16.7928553	6.5576722	.003546099
283	80089	22665187	16.8226038	6.5654144	.003533569
284	80656	22906304	16.8522995	6.5731385	.003521127
285	81225	23149125	16.8819430	6.5808443	.003508772
286	81796	23393658	16.9115345	6.5885323	.003496503
287	82369	23639903	16.9410743	6.5962023	.003484321
288	82944	23887872	16.9705927	6.6038545	.003472222
289	83521	24137569	17.0000000	6.6114890	.003460208
290	84100	24389000	17.0293864	6.6191060	.003448276
291	84681	24642171	17.0587221	6.6267054	.003436426
292	85264	24897088	17.0880075	6.6342874	.003424658
293	85849	25153757	17.1172428	6.6418522	.003412969
294	86436	25412184	17.1464282	6.6493998	.003401361
295	87025	25672375	17.1755640	6.6569302	.003389831
296	87616	25934336	17.2046505	6.6644437	.003378378
297	88209	26198073	17.2336879	6.6719403	.003367003
298	88804	26463592	17.2626765	6.6794200	.003355705
299	89401	26730899	17.2916165	6.6868831	.003344482
300	90000	27000000	17.3205081	6.6943295	.003333333
301	90601	27270901	17.3493516	6.7017593	.003322259
302	91204	27543608	17.3781472	6.7091729	.003311258
303	91809	27818127	17.4068952	6.7165700	.003300330
304	92416	28094464	17.4355958	6.7239508	.003289474
305	93025	28372625	17.4642492	6.7313155	.003278689
306	93636	28652616	17.4928557	6.7386641	.003267974
307	94249	28934443	17.5214155	6.7459967	.003257329
308	94864	29218112	17.5499288	6.7533134	.003246753
309	95481	29503629	17.5783958	6.7606143	.003236246
310	96100	29791000	17.6068169	6.7678995	.003225806

2

1

1

1

1

1

1

1

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
373	139129	51895117	19.3132079	7.1984050	.002680965
374	139876	52313624	19.3390796	7.2048322	.002673797
375	140625	52734375	19.3649167	7.2112479	.002666667
376	141376	53157376	19.3907194	7.2176522	.002659574
377	142129	53582633	19.4164878	7.2240450	.002652520
378	142884	54010152	19.4422221	7.2304268	.002645503
379	143641	54439939	19.4679223	7.2367972	.002638522
380	144400	54872000	19.4935887	7.2431565	.002631579
381	145161	55306341	19.5192213	7.2495045	.002624672
382	145924	55742968	19.5448203	7.2558415	.002617801
383	146689	56181887	19.5703858	7.2621675	.002610966
384	147456	56623104	19.5959179	7.2684824	.002604167
385	148225	57066625	19.6214169	7.2747864	.002597403
386	148996	57512456	19.6468827	7.2810794	.002590674
387	149769	57960603	19.6723156	7.2873617	.002583979
388	150544	58411072	19.6977156	7.2936330	.002577320
389	151321	58863869	19.7230829	7.2998936	.002570694
390	152100	59319000	19.7484177	7.3061436	.002564103
391	152881	59776471	19.7737199	7.3123828	.002557545
392	153664	60236288	19.7989899	7.3186114	.002551020
393	154449	60698457	19.8242276	7.3248295	.002544529
394	155236	61162984	19.8494332	7.3310369	.002538071
395	156025	61629875	19.8746069	7.3372339	.002531646
396	156816	62099136	19.8997487	7.3434205	.002525253
397	157609	62570773	19.9248588	7.3495966	.002518892
398	158404	63044792	19.9499373	7.3557624	.002512563
399	159201	63521199	19.9749844	7.3619178	.002506266
400	160000	64000000	20.0000000	7.3680630	.002500000
401	160801	64481201	20.0249844	7.3741979	.002493766
402	161604	64964808	20.0499377	7.3803227	.002487562
403	162409	65450827	20.0748599	7.3864373	.002481390
404	163216	65939264	20.0997512	7.3925418	.002475248
405	164025	66430125	20.1246118	7.3986363	.002469136
406	164836	66923416	20.1494417	7.4047206	.002463054
407	165649	67419143	20.1742410	7.4107950	.002457002
408	166464	67917312	20.1990099	7.4168595	.002450980
409	167281	68417929	20.2237484	7.4229142	.002444988
410	168100	68921000	20.2484567	7.4289539	.002439024
411	168921	69426531	20.2731349	7.4349938	.002433090
412	169744	69934528	20.2977831	7.4410189	.002427184
413	170569	70444997	20.3224014	7.4470342	.002421308
414	171396	70957944	20.3469899	7.4530399	.002415459
415	172225	71473375	20.3715488	7.4590359	.002409639
416	173056	71991296	20.3960781	7.4650223	.002403846
417	173889	72511713	20.4205779	7.4709991	.002398082
418	174724	73034632	20.4450483	7.4769664	.002392344
419	175561	73560059	20.4694895	7.4829242	.002386635
420	176400	74088000	20.4939015	7.4888724	.002380952
421	177241	74618461	20.5182845	7.4948113	.002375297
422	178084	75151448	20.5426386	7.5007406	.002369668
423	178929	75686967	20.5669638	7.5066607	.002364066
424	179776	76225024	20.5912603	7.5125715	.002358491
425	180625	76765625	20.6155281	7.5184730	.002352941
426	181476	77308776	20.6397674	7.5243652	.002347418
427	182329	77854483	20.6639783	7.5302482	.002341920
428	183184	78402752	20.6881609	7.5361221	.002336449
429	184041	78953589	20.7123152	7.5419867	.002331002
430	184900	79507000	20.7364414	7.5478423	.002325581
431	185761	80062991	20.7605395	7.5536888	.002320186
432	186624	80621568	20.7846097	7.5595263	.002314815
433	187489	81182737	20.8086520	7.5653548	.002309469
434	188356	81746504	20.8326667	7.5711743	.002304147

# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

No.	Squares	Cubes	Square roots	Cube roots	Reciprocal
435	189225	82312875	20.8566536	7.5769849	.002298
436	190096	82881856	20.8806130	7.5827865	.002293
437	190969	83453453	20.9045450	7.5885793	.002288
438	191844	84027672	20.9284495	7.5943633	.002283
439	192721	84604519	20.9523268	7.6001385	.002277
440	193600	85184000	20.9761770	7.6059049	.002272
441	194481	85766121	21.0000000	7.6116626	.002267
442	195364	86350888	21.0237960	7.6174116	.002262
443	196249	86938307	21.0475652	7.6231519	.002257
444	197136	87528384	21.0713075	7.6288837	.002252
445	198025	88121125	21.0950231	7.6346067	.002247
446	198916	88716536	21.1187121	7.6403213	.002242
447	199809	89314623	21.1423745	7.6460272	.002237
448	200704	89915302	21.1660105	7.6517247	.002232
449	201601	90518849	21.1896201	7.6574138	.002227
450	202500	91125000	21.2132034	7.6630943	.002222
451	203401	91733851	21.2367606	7.6687665	.002217
452	204304	92345408	21.2602916	7.6744303	.002212
453	205209	92959677	21.2837967	7.6800857	.002207
454	206116	93576664	21.3072758	7.6857328	.002202
455	207025	94196375	21.3307290	7.6913717	.002197
456	207936	94818816	21.3541565	7.6970023	.002192
457	208849	95443993	21.3775583	7.7026246	.002187
458	209764	96071912	21.4009346	7.7082388	.002182
459	210681	96702579	21.4242853	7.7138448	.002177
460	211600	97336000	21.4476106	7.7194426	.002172
461	212521	97972181	21.4709106	7.7250325	.002167
462	213444	98611128	21.4941853	7.7306141	.002162
463	214369	99252847	21.5174348	7.7361877	.002157
464	215296	99897344	21.5406592	7.7417532	.002152
465	216225	100544625	21.5638587	7.7473109	.002147
466	217156	101194696	21.5870331	7.7528606	.002142
467	218089	101847563	21.6101828	7.7584023	.002137
468	219024	102503232	21.6332077	7.7639361	.002132
469	219961	103161709	21.6564078	7.7694620	.002127
470	220900	103823000	21.6794834	7.7749801	.002122
471	221841	104487111	21.7025344	7.7804904	.002117
472	222784	105154048	21.7255610	7.7859928	.002112
473	223729	105823817	21.7485632	7.7914875	.002107
474	224676	106496424	21.7715411	7.7969745	.002102
475	225625	107171875	21.7944947	7.8024538	.002097
476	226576	107850176	21.8174242	7.8079254	.002092
477	227529	108531333	21.8403297	7.8133892	.002087
478	228484	109215352	21.8632111	7.8188456	.002082
479	229441	109902239	21.8860686	7.8242942	.002077
480	230400	110592000	21.9089023	7.8297353	.002072
481	231361	111284641	21.9317122	7.8351688	.002067
482	232324	111980168	21.9544984	7.8405949	.002062
483	233289	112678587	21.9772610	7.8460134	.002057
484	234256	113379904	22.0000000	7.8514244	.002052
485	235225	114084125	22.0227155	7.8568281	.002047
486	236196	114791256	22.0454077	7.8622242	.002042
487	237169	115501303	22.0680765	7.8676130	.002037
488	238144	116214272	22.0907220	7.8729944	.002032
489	239121	116930169	22.1133444	7.8783684	.002027
490	240100	117649000	22.1359436	7.8837352	.002022
491	241081	118370771	22.1585198	7.8890946	.002017
492	242064	119095488	22.1810730	7.8944468	.002012
493	243049	119823157	22.2036033	7.8997917	.002007
494	244036	120553784	22.2261108	7.9051294	.002002
495	245025	121287375	22.2485955	7.9104599	.001997
496	246016	122023936	22.2710575	7.9157832	.001992

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
497	247009	122763473	22.2934988	7.9210994	.002012072
498	248004	123505992	22.3159136	7.9264085	.002008082
499	249001	124251499	22.3383079	7.9317104	.002004008
500	250000	125000000	22.3606798	7.9370053	.002000000
501	251001	125751501	22.3830293	7.9422931	.001996008
502	252004	126506008	22.4053565	7.9475739	.001992032
503	253009	127263527	22.4276615	7.9528477	.001988072
504	254016	128024064	22.4499443	7.9581144	.001984127
505	255025	128787625	22.4722051	7.9633743	.001980198
506	256036	129554216	22.4944438	7.9686271	.001976285
507	257049	130323843	22.5166605	7.9738731	.001972387
508	258064	131096512	22.5388553	7.9791122	.001968504
509	259081	131872229	22.5610283	7.9843444	.001964637
510	260100	132651000	22.5831796	7.9895697	.001960784
511	261121	133432831	22.6053091	7.9947883	.001956947
512	262144	134217728	22.6274170	8.0000000	.001953125
513	263169	135005697	22.6495033	8.0052049	.001949318
514	264196	135796744	22.6715681	8.0104032	.001945525
515	265225	136590875	22.6936114	8.0155946	.001941748
516	266256	137388096	22.7156334	8.0207794	.001937984
517	267289	138188413	22.7376340	8.0259574	.001934236
518	268324	138991832	22.7596134	8.0311287	.001930502
519	269361	139798359	22.7815715	8.0362935	.001926782
520	270400	140608000	22.8035085	8.0414515	.001923077
521	271441	141420761	22.8254244	8.0466030	.001919386
522	272484	142236648	22.8473193	8.0517479	.001915709
523	273529	143055667	22.8691933	8.0568862	.001912046
524	274576	143877824	22.8910463	8.0620180	.001908397
525	275625	144703125	22.9128785	8.0671432	.001904762
526	276676	145531576	22.9346899	8.0722620	.001901141
527	277729	146363183	22.9564806	8.0773743	.001897533
528	278784	147197952	22.9782506	8.0824800	.001893939
529	279841	148035889	23.0000000	8.0875794	.001890359
530	280900	148877000	23.0217289	8.0926723	.001886792
531	281961	149721291	23.0434372	8.0977589	.001883239
532	283024	150568768	23.0651252	8.1028390	.001879699
533	284089	151419437	23.0867928	8.1079128	.001876173
534	285156	152273304	23.1084400	8.1129803	.001872659
535	286225	153130375	23.1300670	8.1180414	.001869159
536	287296	153990656	23.1516738	8.1230962	.001865672
537	288369	154854153	23.1732605	8.1281447	.001862197
538	289444	155720872	23.1948270	8.1331870	.001858736
539	290521	156590819	23.2163735	8.1382230	.001855288
540	291600	157464000	23.2379001	8.1432529	.001851852
541	292681	158340421	23.2594067	8.1482765	.001848429
542	293764	159220088	23.2808935	8.1532939	.001845018
543	294849	160103007	23.3023604	8.1583051	.001841621
544	295936	160989184	23.3238076	8.1633102	.001838235
545	297025	161878625	23.3452351	8.1683092	.001834862
546	298116	162771336	23.3666429	8.1733020	.001831502
547	299209	163667323	23.3880311	8.1782888	.001828154
548	300304	164566592	23.4093998	8.1832695	.001824818
549	301401	165469149	23.4307490	8.1882441	.001821494
550	302500	166375000	23.4520788	8.1932127	.001818182
551	303601	167284151	23.4733892	8.1981753	.001814882
552	304704	168196608	23.4946802	8.2031319	.001811594
553	305809	169112377	23.5159520	8.2080825	.001808318
554	306916	170031464	23.5372046	8.2130271	.001805054
555	308025	170953875	23.5584380	8.2179657	.001801802
556	309136	171879616	23.5796522	8.2228985	.001798561
557	310249	172808693	23.6008474	8.2278254	.001795332



# Name, Cubes, Square Roots, Cube Roots and Reciprocals

0	013401	174876870	22.0481209	8.2070614	00174870
1	013500	175419000	22.0543101	8.2023706	00175410
2	013601	175964001	22.0605328	8.2074701	00175960
3	013704	176512032	22.0667903	8.2125715	00176510
4	013809	177063047	22.0730810	8.2176738	00177060
5	013916	177617144	22.0794043	8.2227769	00177610
6	014025	178174325	22.0857606	8.2278808	00178170
7	014136	178734600	22.0921503	8.2329855	00178730
8	014249	179298000	22.0985738	8.2380910	00179290
9	014364	179864525	22.1050315	8.2431973	00179860
10	014481	180434200	22.1115238	8.2483044	00180430
11	014599	181007040	22.1180510	8.2534123	00181000
12	014719	181583065	22.1246133	8.2585210	00181580
13	014840	182162296	22.1312110	8.2636305	00182160
14	014963	182744744	22.1378445	8.2687408	00182740
15	015087	183330430	22.1445140	8.2738519	00183330
16	015213	183919376	22.1512198	8.2789638	00183910
17	015340	184511593	22.1579621	8.2840765	00184510
18	015469	185107092	22.1647412	8.2891900	00185100
19	015599	185705885	22.1715573	8.2943043	00185700
20	015730	186307984	22.1784108	8.2994194	00186300
21	015863	186913400	22.1853020	8.3045353	00186910
22	015997	187522144	22.1922312	8.3096520	00187520
23	016133	188134228	22.1991988	8.3147695	00188130
24	016270	188749664	22.2062050	8.3198878	00188740
25	016409	189368464	22.2132500	8.3249969	00189360
26	016549	190000640	22.2203339	8.3301068	00190000
27	016690	190636193	22.2274570	8.3352175	00190630
28	016833	191275136	22.2346195	8.3403289	00191270
29	016977	191917480	22.2418217	8.3454410	00191910
30	017123	192563236	22.2490738	8.3505539	00192560
31	017270	193212416	22.2563660	8.3556675	00193210
32	017418	193865032	22.2636986	8.3607818	00193860
33	017568	194521096	22.2710718	8.3658968	00194520
34	017719	195180620	22.2784858	8.3710125	00195180
35	017871	195843616	22.2859408	8.3761289	00195840
36	018025	196510096	22.2934370	8.3812460	00196510
37	018180	197179960	22.3009746	8.3863638	00197180
38	018336	197853220	22.3085538	8.3914823	00197850
39	018494	198529888	22.3161748	8.3966014	00198520
40	018653	199209964	22.3238378	8.4017212	00199200
41	018813	199893460	22.3315430	8.4068417	00199890
42	018975	200580388	22.3392906	8.4119629	00200580
43	019138	201270750	22.3470808	8.4170848	00201270
44	019302	201964560	22.3549138	8.4222073	00201960
45	019468	202661832	22.3627898	8.4273304	00202660
46	019635	203362576	22.3707090	8.4324541	00203360
47	019803	204066804	22.3786716	8.4375784	00204060
48	019973	204774528	22.3866778	8.4427033	00204770
49	020144	205485760	22.3947278	8.4478288	00205480
50	020316	206200512	22.4028218	8.4529548	00206200
51	020490	206918796	22.4109600	8.4580813	00206910
52	020665	207640624	22.4191426	8.4632083	00207640
53	020842	208366016	22.4273698	8.4683358	00208360
54	021020	209094984	22.4356418	8.4734638	00209090
55	021200	209827536	22.4439588	8.4785923	00209820
56	021381	210563684	22.4523209	8.4837212	00210560
57	021564	211303440	22.4607283	8.4888506	00211300
58	021748	212046816	22.4691813	8.4939805	00212040
59	021934	212793824	22.4776800	8.4991109	00212790
60	022121	213544476	22.4862246	8.5042418	00213540
61	022310	214298784	22.4948153	8.5093732	00214290
62	022500	215056760	22.5034523	8.5145051	00215050
63	022692	215818416	22.5121358	8.5196375	00215810
64	022885	216583664	22.5208660	8.5247704	00216580
65	023080	217352516	22.5296431	8.5299038	00217350
66	023276	218124984	22.5384674	8.5350377	00218120
67	023474	218901080	22.5473391	8.5401721	00218900
68	023673	219680816	22.5562585	8.5453069	00219680
69	023874	220464204	22.5652258	8.5504422	00220460
70	024076	221251256	22.5742413	8.5555780	00221250
71	024280	222041984	22.5833052	8.5607143	00222040
72	024485	222836300	22.5924178	8.5658510	00222830
73	024692	223634216	22.6015793	8.5709882	00223630
74	024900	224435744	22.6107899	8.5761258	00224430
75	025110	225240896	22.6199508	8.5812639	00225240
76	025321	226049684	22.6291622	8.5864025	00226040
77	025534	226862120	22.6384243	8.5915416	00226860
78	025748	227678216	22.6477373	8.5966812	00227670
79	025964	228497984	22.6570915	8.6018213	00228490
80	026181	229321436	22.6664871	8.6069619	00229320
81	026400	230148584	22.6759244	8.6121030	00230140
82	026620	230979440	22.6854036	8.6172446	00230970
83	026842	231814016	22.6949248	8.6223867	00231810
84	027065	232652324	22.7044883	8.6275293	00232650
85	027290	233494376	22.7140943	8.6326724	00233490
86	027516	234340184	22.7237430	8.6378160	00234340
87	027744	235189760	22.7334346	8.6429601	00235180
88	027973	236043116	22.7431693	8.6481047	00236040
89	028204	236899264	22.7529473	8.6532498	00236890
90	028436	237759216	22.7627688	8.6583954	00237750
91	028670	238623084	22.7726340	8.6635415	00238620
92	028905	239490876	22.7825431	8.6686881	00239490
93	029142	240362604	22.7924963	8.6738352	00240360
94	029380	241238280	22.8024938	8.6789828	00241230
95	029620	242117916	22.8125358	8.6841309	00242100
96	029861	243001524	22.8226225	8.6892795	00243000
97	030104	243889116	22.8327541	8.6944286	00243880
98	030348	244780704	22.8429308	8.6995782	00244780
99	030594	245676300	22.8531528	8.7047283	00245670

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
021	441	9261	21	2.071773	0.047619
022	484	10648	22	2.151658	0.045455
023	529	12167	23	2.239722	0.043478
024	576	13824	24	2.331474	0.041667
025	625	15625	25	2.430381	0.04
026	676	17714	26	2.535634	0.038462
027	729	19683	27	2.647581	0.037037
028	784	21952	28	2.766262	0.035714
029	841	24389	29	2.891261	0.034483
030	900	27000	30	3.022708	0.033333
031	961	29791	31	3.160673	0.032258
032	1024	32768	32	3.305051	0.03125
033	1089	35937	33	3.455894	0.030303
034	1156	39400	34	3.613281	0.029412
035	1225	43125	35	3.776434	0.028571
036	1296	47196	36	3.945348	0.027778
037	1369	51613	37	4.119931	0.027027
038	1444	56384	38	4.299994	0.026316
039	1521	61512	39	4.485346	0.025641
040	1600	67000	40	4.675536	0.025
041	1681	72961	41	4.870371	0.024390
042	1764	79372	42	5.069651	0.02381
043	1849	86237	43	5.273176	0.023256
044	1936	93568	44	5.480646	0.022727
045	2025	101375	45	5.691818	0.022222
046	2116	109664	46	5.906391	0.021739
047	2209	118447	47	6.124156	0.021277
048	2304	127728	48	6.344898	0.020833
049	2401	137609	49	6.568413	0.020408
050	2500	148125	50	6.794427	0.02
051	2601	159376	51	7.022736	0.019608
052	2704	171368	52	7.253136	0.019231
053	2809	184127	53	7.485431	0.018868
054	2916	197664	54	7.719426	0.018519
055	3025	211985	55	7.955027	0.018182
056	3136	227096	56	8.192131	0.017857
057	3249	243003	57	8.430634	0.017544
058	3364	259712	58	8.670442	0.017241
059	3481	277229	59	8.911461	0.016947
060	3600	295560	60	9.153694	0.016667
061	3721	314711	61	9.407047	0.016393
062	3844	334688	62	9.661516	0.016129
063	3969	355497	63	9.917097	0.015873
064	4096	377144	64	10.173786	0.015625
065	4225	399635	65	10.431481	0.015385
066	4356	422976	66	10.689981	0.015152
067	4489	447173	67	10.949184	0.014926
068	4624	472232	68	11.208987	0.014706
069	4761	498159	69	11.469287	0.014493
070	4900	525000	70	11.729986	0.014286
071	5041	552769	71	11.990981	0.014085
072	5184	581472	72	12.252168	0.013890
073	5329	611127	73	12.513453	0.013702
074	5476	641744	74	12.774832	0.013521
075	5625	673325	75	13.036301	0.013347
076	5776	705880	76	13.297857	0.013179
077	5929	739419	77	13.559496	0.013017
078	6084	773952	78	13.821214	0.012861
079	6241	809489	79	14.082908	0.012711
080	6400	846030	80	14.344574	0.012568
081	6561	883585	81	14.606208	0.012431
082	6724	922164	82	14.867807	0.012299
083	6889	961777	83	15.129368	0.012172
084	7056	1002432	84	15.390887	0.012050
085	7225	1044139	85	15.652361	0.011933
086	7396	1086896	86	15.913787	0.011821
087	7569	1130713	87	16.175162	0.011713
088	7744	1175592	88	16.436483	0.011610
089	7921	1221533	89	16.697747	0.011511
090	8100	1268540	90	16.958951	0.011417
091	8281	1316617	91	17.219992	0.011327
092	8464	1365768	92	17.480867	0.011241
093	8649	1415997	93	17.741573	0.011158
094	8836	1467308	94	18.002107	0.011078
095	9025	1519705	95	18.262467	0.010999
096	9216	1573192	96	18.522650	0.010923
097	9409	1627773	97	18.782653	0.010850
098	9604	1683452	98	19.042473	0.010779
099	9801	1740233	99	19.302107	0.010711
100	10000	1798120	100	19.561552	0.010645



No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
683	466489	318611987	26.1342687	8.8065722	.001464129
684	467856	320013504	26.1533937	8.8108681	.001461988
685	469225	321419125	26.1725047	8.8151598	.001459854
686	470596	322828856	26.1916017	8.8194474	.001457726
687	471969	324242703	26.2106848	8.8237307	.001455604
688	473344	325660672	26.2297541	8.8280099	.001453488
689	474721	327082769	26.2488095	8.8322850	.001451379
690	476100	328509000	26.2678511	8.8365559	.001449275
691	477481	329939371	26.2868769	8.8408227	.001447178
692	478864	331373888	26.3058929	8.8450854	.001445087
693	480249	332812557	26.3248932	8.8493440	.001443001
694	481636	334255384	26.3438797	8.8535985	.001440922
695	483025	335702375	26.3628527	8.8578489	.001438849
696	484416	337153536	26.3818119	8.8620952	.001436782
697	485809	338608873	26.4007576	8.8663375	.001434720
698	487204	340068302	26.4196896	8.8705757	.001432665
699	488601	341532099	26.4386081	8.8748099	.001430615
700	490000	343000000	26.4575131	8.8790400	.001428571
701	491401	344472101	26.4764046	8.8832601	.001426534
702	492804	345948408	26.4952826	8.8874882	.001424501
703	494209	347428927	26.5141472	8.8917003	.001422475
704	495616	348913664	26.5329983	8.8959204	.001420455
705	497025	350402625	26.5518361	8.9001304	.001418440
706	498436	351895816	26.5706605	8.9043306	.001416431
707	499849	353393243	26.5894716	8.9085287	.001414427
708	501264	354894912	26.6082604	8.9127209	.001412429
709	502681	356400829	26.6270539	8.9169311	.001410437
710	504100	357911000	26.6458252	8.9211214	.001408451
711	505521	359425431	26.6645833	8.9253078	.001406470
712	506944	360944128	26.6833281	8.9294902	.001404494
713	508369	362467097	26.7020598	8.9336687	.001402525
714	509796	363994344	26.7207784	8.9378433	.001400560
715	511225	365525875	26.7394839	8.9420140	.001398601
716	512656	367061696	26.7581763	8.9461809	.001396648
717	514089	368601813	26.7768557	8.9503428	.001394700
718	515524	370146232	26.7955220	8.9545029	.001392758
719	516961	371694959	26.8141754	8.9586581	.001390821
720	518400	373248000	26.8328157	8.9628095	.001388889
721	519841	374805361	26.8514432	8.9669570	.001386963
722	521284	376367048	26.8700577	8.9711007	.001385042
723	522729	377933067	26.8886593	8.9752406	.001383126
724	524176	379503424	26.9072481	8.9793706	.001381215
725	525625	381078125	26.9258240	8.9835009	.001379310
726	527076	382657176	26.9443872	8.9876273	.001377410
727	528529	384240583	26.9629375	8.9917620	.001375516
728	529984	385828352	26.9814751	8.9958829	.001373626
729	531441	387420489	27.0000000	9.0000000	.001371742
730	532900	389017000	27.0185122	9.0041134	.001369863
731	534331	390617891	27.0370117	9.0082229	.001367989
732	535824	392223169	27.0554985	9.0123288	.001366120
733	537289	393832887	27.0739727	9.0164309	.001364256
734	538756	395446904	27.0924344	9.0205293	.001362398
735	540225	397065375	27.1108834	9.0246209	.001360544
736	541696	398688256	27.1293199	9.0287149	.001358696
737	543169	400315553	27.1477439	9.0328021	.001356852
738	544644	401947272	27.1661554	9.0368857	.001355014
739	546121	403583419	27.1845544	9.0409655	.001353180
740	547600	405224000	27.2029410	9.0450419	.001351351
741	549081	406869021	27.2213152	9.0491142	.001349528
742	550564	408518488	27.2396769	9.0531831	.001347709
743	552049	410172407	27.2580282	9.0572482	.001345895

No.	Squares	Cubes	Square roots	Cube roots	Reciproca
745	555025	413493625	27.2946881	9.0653677	.00134224
746	556516	415160936	27.3130006	9.0694220	.00134044
747	558009	416832723	27.3313007	9.0734726	.00133864
748	559504	418508992	27.3495887	9.0775197	.00133684
749	561001	420189749	27.3678644	9.0815631	.00133511
750	562500	421875000	27.3861279	9.0856030	.00133338
751	564001	423564751	27.4043792	9.0896392	.00133164
752	565504	425259008	27.4226184	9.0936719	.00132978
753	567009	426957777	27.4408455	9.0977010	.00132802
754	568516	428661064	27.4590604	9.1017265	.00132628
755	570025	430368875	27.4772633	9.1057485	.00132454
756	571536	432081216	27.4954542	9.1097669	.00132271
757	573049	433798093	27.5136330	9.1137818	.00132100
758	574564	435519512	27.5317998	9.1177931	.00131929
759	576081	437245479	27.5499546	9.1218010	.00131752
760	577600	438976000	27.5680975	9.1258053	.00131576
761	579121	440711081	27.5862284	9.1298061	.00131400
762	580644	442450728	27.6043475	9.1338034	.00131223
763	582169	444194947	27.6224546	9.1377971	.00131061
764	583696	445943744	27.6405499	9.1417874	.00130890
765	585225	447697125	27.6586334	9.1457742	.00130716
766	586756	449455096	27.6767050	9.1497576	.00130544
767	588289	451217663	27.6947648	9.1537375	.00130378
768	589824	452984832	27.7128129	9.1577139	.00130206
769	591361	454756609	27.7308492	9.1616869	.00130039
770	592900	456533000	27.7488739	9.1656565	.00129870
771	594441	458314011	27.7668808	9.1696225	.00129701
772	595984	460099648	27.7848880	9.1735852	.00129533
773	597529	461889917	27.8028775	9.1775445	.00129366
774	599076	463684824	27.8208555	9.1815003	.00129196
775	600625	465484375	27.8388218	9.1854527	.00129032
776	602176	467288576	27.8567766	9.1894018	.00128866
777	603729	469097433	27.8747197	9.1933474	.00128700
778	605284	470910952	27.8926514	9.1972897	.00128534
779	606841	472729139	27.9105715	9.2012286	.00128366
780	608400	474552000	27.9284801	9.2051641	.00128200
781	609961	476379541	27.9463772	9.2090962	.00128041
782	611524	478211768	27.9642629	9.2130250	.00127877
783	613089	480048687	27.9821372	9.2169505	.00127713
784	614656	481890304	28.0000000	9.2208726	.00127551
785	616225	483736625	28.0178515	9.2247914	.00127388
786	617796	485587656	28.0356915	9.2287068	.00127226
787	619369	487443403	28.0535203	9.2326189	.00127064
788	620944	489303872	28.0713377	9.2365277	.00126903
789	622521	491169069	28.0891438	9.2404333	.00126742
790	624100	493039000	28.1069386	9.2443355	.00126582
791	625681	494913671	28.1247222	9.2482344	.00126422
792	627264	496793088	28.1424946	9.2521300	.00126262
793	628849	498677257	28.1602557	9.2560224	.00126103
794	630436	500566184	28.1780056	9.2599114	.00125944
795	632025	502459875	28.1957444	9.2637973	.00125786
796	633616	504358336	28.2134720	9.2676798	.00125628
797	635209	506261573	28.2311884	9.2715592	.00125470
798	636804	508169592	28.2488938	9.2754352	.00125313
799	638401	510082399	28.2665881	9.2793081	.00125156
800	640000	512000000	28.2842712	9.2831777	.00125000
801	641601	513922401	28.3019484	9.2870440	.00124843
802	643204	515849608	28.3196045	9.2909072	.00124688
803	644809	517781627	28.3372546	9.2947671	.00124533
804	646416	519718464	28.3548938	9.2986239	.00124378
805	648025	521660125	28.3725219	9.3024775	.00124223
806	649636	523606616	28.3901391	9.3063278	.00124069

No.	Squares	Cubes	Square roots	Cube roots	Reciprocals
805	651249	525557943	28.4077454	9.3101750	.001239157
806	652864	527514112	28.4253408	9.3140190	.001237624
807	654481	529475129	28.4429253	9.3178599	.001236094
810	656100	531441000	28.4604989	9.3216975	.001234568
811	657721	533411731	28.4780617	9.3255320	.001233046
812	659344	535387328	28.4956137	9.3293684	.001231527
813	660969	537367797	28.5131549	9.3331916	.001230012
814	662596	539353144	28.5306852	9.3370167	.001228501
815	664225	541343375	28.5482048	9.3408386	.001226994
816	665856	543338496	28.5657137	9.3446575	.001225490
817	667489	545338513	28.5832119	9.3484731	.001223990
818	669124	547343432	28.6006993	9.3522857	.001222494
819	670761	549353259	28.6181760	9.3560952	.001221001
820	672400	551368000	28.6356421	9.3599016	.001219512
821	674041	553387661	28.6530976	9.3637049	.001218027
822	675684	555412248	28.6705424	9.3675051	.001216545
823	677329	557441767	28.6879766	9.3713022	.001215067
824	678976	559476224	28.7054002	9.3750963	.001213592
825	680625	561515625	28.7228132	9.3788873	.001212121
826	682276	563559976	28.7402157	9.3826752	.001210654
827	683929	565609283	28.7576077	9.3864600	.001209190
828	685584	567663552	28.7749891	9.3902419	.001207729
829	687241	569722789	28.7923601	9.3940206	.001206273
830	688900	571787000	28.8097206	9.3977964	.001204819
831	690561	573856191	28.8270706	9.4015691	.001203369
832	692224	575930368	28.8444102	9.4053387	.001201923
833	693889	578009537	28.8617394	9.4091054	.001200480
834	695556	580093704	28.8790582	9.4128690	.001199041
835	697225	582182875	28.8963666	9.4166297	.001197605
836	698896	584277056	28.9136646	9.4203873	.001196172
837	700569	586376263	28.9309523	9.4241420	.001194743
838	702244	588480472	28.9482297	9.4278936	.001193317
839	703921	590589719	28.9654967	9.4316423	.001191895
840	705600	592704000	28.9827535	9.4353880	.001190476
841	707281	594823321	29.0000000	9.4391307	.001189061
842	708964	596947688	29.0172363	9.4428704	.001187648
843	710649	599077107	29.0344623	9.4466072	.001186240
844	712336	601211584	29.0516781	9.4503410	.001184834
845	714025	603351125	29.0688837	9.4540719	.001183432
846	715716	605495736	29.0860791	9.4577999	.001182033
847	717409	607645423	29.1032644	9.4615249	.001180638
848	719104	609800192	29.1204396	9.4652470	.001179245
849	720801	611960049	29.1376046	9.4689661	.001177856
850	722500	614125000	29.1547595	9.4726824	.001176471
851	724201	616295051	29.1719043	9.4763957	.001175088
852	725904	618470208	29.1890390	9.4801061	.001173709
853	727609	620650477	29.2061637	9.4838136	.001172333
854	729316	622835864	29.2232784	9.4875182	.001170960
855	731025	625026375	29.2403830	9.4912200	.001169591
856	732736	627222016	29.2574777	9.4949188	.001168224
857	734449	629422793	29.2745623	9.4986147	.001166861
858	736164	631628712	29.2916370	9.5023078	.001165501
859	737881	633839779	29.3087018	9.5059980	.001164144
860	739600	636056000	29.3257566	9.5096854	.001162791
861	741321	638277381	29.3428015	9.5133699	.001161440
862	743044	640503928	29.3598365	9.5170515	.001160093
863	744769	642735647	29.3768616	9.5207303	.001158749
864	746496	644972544	29.3938769	9.5244063	.001157407
865	748225	647214625	29.4108823	9.5280794	.001156069
866	749956	649461896	29.4278779	9.5317497	.001154734
867	751689	651714263	29.4448637	9.5354172	.001153402

Squares	Cubes	Square roots	Cube roots	Reciprocals
62001	15438249	15.7797338	6.2911946	.004016064
62500	15625000	15.8113883	6.2996053	.004000000
63001	15813251	15.8429795	6.3079935	.003984064
63504	16003008	15.8745079	6.3163596	.003968254
64009	16194277	15.9059737	6.3247035	.003952569
64516	16387064	15.9373775	6.3330256	.003937008
65025	16581375	15.9687194	6.3413257	.003921569
65536	16777216	16.0000000	6.3496042	.003906250
66049	16974593	16.0312195	6.3578611	.003891051
66564	17173512	16.0623784	6.3660968	.003875969
67081	17373979	16.0934769	6.3743111	.003861004
67600	17576000	16.1245155	6.3825043	.003846154
68121	17779581	16.1554944	6.3906765	.003831418
68644	17984728	16.1864141	6.3988279	.003816794
69169	18191447	16.2172747	6.4069585	.003802281
69696	18399744	16.2480768	6.4150687	.003787879
70225	18609625	16.2788206	6.4231583	.003773585
70756	18821096	16.3095064	6.4312276	.003759398
71289	19034163	16.3401346	6.4392767	.003745318
71824	19248832	16.3707055	6.4473057	.003731343
72361	19465109	16.4012195	6.4553148	.003717472
72900	19683000	16.4316767	6.4633041	.003703704
73441	19902511	16.4620776	6.4712736	.003690037
73984	20123648	16.4924225	6.4792236	.003676471
74529	20346417	16.5227116	6.4871541	.003663004
75076	20570824	16.5529454	6.4950653	.003649635
75625	20796875	16.5831240	6.5029572	.003636364
76176	21024576	16.6132477	6.5108300	.003623188
76729	21253933	16.6433170	6.5186839	.003610108
77284	21484952	16.6733320	6.5265189	.003597122
77841	21717639	16.7032931	6.5343351	.003584229
78400	21952000	16.7332005	6.5421326	.003571429
78961	22188041	16.7630546	6.5499116	.003558719
79524	22425768	16.7928553	6.5576722	.003546099
80089	22665187	16.8226038	6.5654144	.003533569
80656	22906304	16.8522995	6.5731385	.003521127
81225	23149125	16.8819430	6.5808443	.003508772
81796	23393656	16.9115345	6.5885323	.003496503
82369	23639903	16.9410743	6.5962023	.003484321
82944	23887872	16.9705327	6.6038545	.003472222
83521	24137569	17.0000000	6.6114890	.003460208
84100	24389000	17.0293864	6.6191060	.003448276
84681	24642171	17.0587221	6.6267054	.003436426
85264	24897088	17.0880075	6.6342874	.003424658
85849	25153757	17.1172428	6.6418522	.003412969
86436	25412184	17.1464282	6.6493998	.003401361
87025	25672375	17.1755640	6.6569302	.003389831
87616	25934336	17.2046505	6.6644437	.003378378
88209	26198073	17.2336879	6.6719403	.003367003
88804	26463592	17.2626765	6.6794200	.003355705
89401	26730899	17.2916165	6.6868831	.003344482
90000	27000000	17.3205081	6.6943295	.003333333
90601	27270901	17.3493516	6.7017593	.003322259
91204	27543608	17.3781472	6.7091729	.003311258
91809	27818127	17.4068952	6.7165700	.003300330
92416	28094464	17.4355958	6.7239508	.003289474
93025	28372625	17.4642492	6.7313155	.003278689
93636	28652616	17.4928557	6.7386641	.003267974
94249	28934443	17.5214155	6.7459967	.003257329
94864	29218112	17.5499288	6.7533134	.003246753
95481	29503629	17.5783958	6.7606143	.003236246
96100	29791000	17.6068169	6.7678995	.003225806

# Squares, Cubes, Square Roots, Cube Roots in

211	96721	30080231	17.6351921	6.77810
212	97344	30371328	17.6635217	6.7824
213	97969	30664297	17.6918060	6.7866
214	98596	30959144	17.7200451	6.7908
215	99225	31255875	17.7482393	6.8040
216	99856	31554496	17.7763888	6.8112
217	100489	31855013	17.8044938	6.8184
218	101124	32157432	17.8325545	6.8256
219	101761	32461759	17.8605711	6.8327
220	102400	32768000	17.8885438	6.8399
221	103041	33076161	17.9164729	6.8470
222	103684	33386248	17.9443584	6.8541
223	104329	33698267	17.9722008	6.8612
224	104976	34012224	18.0000000	6.8682
225	105625	34328125	18.0277564	6.8753
226	106276	34645976	18.0554701	6.8823
227	106929	34965783	18.0831413	6.8894
228	107584	35287552	18.1107703	6.8964
229	108241	35611289	18.1383571	6.9034
230	108900	35937000	18.1659021	6.9104
231	109561	36264691	18.1934054	6.9173
232	110224	36594368	18.2208672	6.9243
233	110889	36926037	18.2482876	6.9313
234	111556	37259704	18.2756669	6.9383
235	112225	37595375	18.3030052	6.9451
236	112896	37933056	18.3303028	6.9520
237	113569	38272753	18.3575598	6.9588
238	114244	38614472	18.3847763	6.9656
239	114921	38958219	18.4119526	6.9724
240	115600	39304000	18.4390889	6.9792
241	116281	39651821	18.4661853	6.9860
242	116964	40001668	18.4932420	6.9928
243	117649	40353607	18.5202592	7.0000
244	118336	40707584	18.5472370	7.0067
245	119025	41063625	18.5741756	7.0134
246	119716	41421736	18.6010752	7.0202
247	120409	41781923	18.6279260	7.0271
248	121104	42144192	18.6547581	7.0339
249	121801	42508549	18.6815417	7.0407
250	122500	42875000	18.7082869	7.0475
251	123201	43243551	18.7349940	7.0543
252	123904		18.7616630	7.0611
253	124609		18.7882942	7.0679
254	125316		18.8148877	7.0747
255	126025		18.8414437	7.0815
256	126736		18.8679623	7.0883
257	127449		18.8944436	7.0951
258	128164		18.9208879	7.1019
259	128881		18.9472953	7.1087
260	129600		18.9736660	7.1155
261	130321		19.0000000	7.1223
262	131044		19.0262976	7.1291
263	131769		19.0525589	7.1359
264	132496		19.0787840	7.1427
265	133225		19.1049732	7.1495
266	133956		19.1311265	7.1563
267	134689		19.1572441	7.1631
268	135424		19.1833261	7.1699
269	136161		19.2093727	7.1767
270	136900	50653000	19.2353841	7.1835
271	137641	51064811	19.2613603	7.1903
		51478248	19.2873015	7.1971





No.	Squares	Cubes	Square roots	Cube roots	Reciproca
621	385641	239483061	24.9198716	8.5316009	.00161034
622	386884	240641848	24.9399278	8.5361780	.00160771
623	388129	241804367	24.9599679	8.5407501	.00160514
624	389376	242970624	24.9799920	8.5453173	.00160256
625	390625	244140625	25.0000000	8.5498797	.00160000
626	391876	245314376	25.0199920	8.5544372	.00159744
627	393129	246491883	25.0399681	8.5589899	.00159486
628	394384	247673152	25.0599282	8.5635377	.00159234
629	395641	248858189	25.0798724	8.5680807	.00158981
630	396900	250047000	25.0998008	8.5726189	.00158730
631	398161	251239591	25.1197134	8.5771523	.00158476
632	399424	252435968	25.1396102	8.5816809	.00158227
633	400689	253636137	25.1594913	8.5862047	.00157977
634	401956	254840104	25.1793566	8.5907238	.00157726
635	403225	256047875	25.1992063	8.5952380	.00157480
636	404496	257259456	25.2190404	8.5997476	.00157232
637	405769	258474853	25.2388589	8.6042525	.00156985
638	407044	259694072	25.2586619	8.6087526	.00156739
639	408321	260917119	25.2784493	8.6132480	.00156494
640	409600	262144000	25.2982213	8.6177388	.00156250
641	410881	263374721	25.3179778	8.6222248	.00156006
642	412164	264609288	25.3377189	8.6267063	.00155763
643	413449	265847707	25.3574447	8.6311830	.00155521
644	414736	267089984	25.3771551	8.6356551	.00155279
645	416025	268336125	25.3968502	8.6401226	.00155038
646	417316	269586136	25.4165301	8.6445855	.00154798
647	418609	270840023	25.4361947	8.6490437	.00154559
648	419904	272097792	25.4558441	8.6534974	.00154321
649	421201	273359449	25.4754784	8.6579465	.00154083
650	422500	274625000	25.4950976	8.6623911	.00153846
651	423801	275894451	25.5147016	8.6668310	.00153609
652	425104	277167808	25.5342907	8.6712665	.00153374
653	426409	278445077	25.5538647	8.6756974	.00153139
654	427716	279723234	25.5734237	8.6801237	.00152905
655	429025	281011375	25.5929678	8.6845456	.00152671
656	430336	282300416	25.6124969	8.6889630	.00152439
657	431649	283593393	25.6320112	8.6933759	.00152207
658	432964	284890312	25.6515107	8.6977843	.00151975
659	434281	286191179	25.6709953	8.7021882	.00151745
660	435600	287496000	25.6904652	8.7065877	.00151515
661	436921	288804781	25.7099203	8.7109827	.00151285
662	438244	290117523	25.7293607	8.7153734	.00151057
663	439569	291434247	25.7487864	8.7197596	.00150829
664	440896	292754944	25.7681975	8.7241414	.00150602
665	442225	294079625	25.7875939	8.7285187	.00150375
666	443556	295408296	25.8069758	8.7328918	.00150150
667	444889	296740963	25.8263431	8.7372604	.00149925
668	446224	298077632	25.8456960	8.7416246	.00149700
669	447561	299418309	25.8650343	8.7459846	.00149476
670	448900	300763000	25.8843582	8.7503401	.00149253
671	450241	302111711	25.9036677	8.7546913	.00149031
672	451584	303464448	25.9229628	8.7590383	.00148809
673	452929	304821217	25.9422435	8.7633809	.00148588
674	454276	306182024	25.9615100	8.7677192	.00148368
675	455625	307546875	25.9807621	8.7720532	.00148148
676	456976	308915776	26.0000000	8.7763830	.00147929
677	458329	310288733	26.0192237	8.7807084	.00147710
678	459684	311665752	26.0384331	8.7850296	.00147492
679	461041	313046839	26.0576284	8.7893466	.00147275
680	462400	314432000	26.0768096	8.7936593	.00147058
681	463761	315821241	26.0959767	8.7979679	.00146842
682	465124	317214568	26.1151297	8.8022721	.00146626



	Squares	Cubes	Square roots	Cube roots	Reciprocals
700	490000	343000000	26.4575131	8.8790400	.001428571
701	491401	344472101	26.4764046	8.8832601	.001426534
702	492804	345948408	26.4952826	8.8874882	.001424501
703	494209	347428927	26.5141472	8.8917003	.001422475
704	495616	348913664	26.5329983	8.8959204	.001420455
705	497025	350402625	26.5518361	8.9001304	.001418440
706	498436	351895816	26.5706605	8.9043306	.001416431
707	499849	353393243	26.5894716	8.9085087	.001414427
708	501264	354894912	26.6082604	8.9127209	.001412429
709	502681	356400829	26.6270539	8.9169311	.001410437
710	504100	357911000	26.6458252	8.9211214	.001408451
711	505521	359425431	26.6645833	8.9253078	.001406470
712	506944	360944128	26.6833281	8.9294902	.001404494
713	508369	362467097	26.7020598	8.9336687	.001402525
714	509796	363994344	26.7207784	8.9378433	.001400560
715	511225	365525875	26.7394839	8.9420140	.001398601
716	512656	367061696	26.7581763	8.9461809	.001396648
717	514089	368601813	26.7768557	8.9503428	.001394700
718	515524	370146232	26.7955220	8.9545029	.001392758
719	516961	371694959	26.8141754	8.9586581	.001390821
720	518400	373248000	26.8328157	8.9628095	.001388889
721	519841	374805361	26.8514432	8.9669570	.001386963
722	521284	376367048	26.8700577	8.97111007	.001385042
723	522729	377933067	26.8886593	8.9752406	.001383126
724	524176	379503424	26.9072481	8.9793706	.001381215
725	525625	381078125	26.9258240	8.9835009	.001379310
726	527076	382657176	26.9443872	8.9876273	.001377410
727	528529	384240583	26.9629375	8.9917620	.001375516
728	529984	385828352	26.9814751	8.9958829	.001373626
729	531441	387420489	27.0000000	9.0000000	.001371742
730	532900	389017000	27.0185122	9.0041134	.001369863
731	534351	390617891	27.0370117	9.0082229	.001367969
732	535824	392223169	27.0554985	9.0123288	.001366120
733	537289	393832837	27.0739727	9.0164309	.001364256
734	538756	395446904	27.0924344	9.0205293	.001362398
735	540225	397065375	27.1108834	9.0246209	.001360544
736	541696	398688256	27.1293199	9.0287149	.001358696
737	543169	400315563	27.1477439	9.0328021	.001356852
738	544644	401947272	27.1661554	9.0368857	.001355014
739	546121	403583419	27.1845544	9.0409655	.001353180
740	547600	405224000	27.2029410	9.0450419	.001351351
741	549081	406869021	27.2213152	9.0491142	.001349528
742	550564	408518488	27.2396769	9.0531831	.001347709
743	552049	410172407	27.2580263	9.0572482	.001345895
744	553536	411830784	27.2763634	9.0613098	.001344086

No.	Squares	Cubes	Square roots	Cube roots	Reciprocal
745	555025	413493625	27.2946881	9.0653677	.001342
746	556516	415160936	27.3130006	9.0694220	.001340
747	558009	416832723	27.3313007	9.0734726	.001338
748	559504	418508992	27.3495887	9.0775197	.001336
749	561001	420189749	27.3678644	9.0815631	.001335
750	562500	421875000	27.3861279	9.0856030	.001333
751	564001	423564751	27.4043792	9.0896392	.001331
752	565504	425259008	27.4226184	9.0936719	.001329
753	567009	426957777	27.4408455	9.0977010	.001328
754	568516	428661064	27.4590604	9.1017265	.001326
755	570025	430368875	27.4772633	9.1057485	.001324
756	571536	432081216	27.4954542	9.1097669	.001322
757	573049	433798093	27.5136330	9.1137818	.001321
758	574564	435519512	27.5317998	9.1177931	.001319
759	576081	437245479	27.5499546	9.1218010	.001317
760	577600	438976000	27.5680975	9.1258053	.001315
761	579121	440711081	27.5862284	9.1298061	.001314
762	580644	442450728	27.6043475	9.1338034	.001312
763	582169	444194947	27.6224546	9.1377971	.001310
764	583696	445943744	27.6405499	9.1417874	.001308
765	585225	447697125	27.6586334	9.1457742	.001307
766	586756	449455096	27.6767050	9.1497576	.001305
767	588289	451217663	27.6947648	9.1537375	.001303
768	589824	452984832	27.7128129	9.1577139	.001302
769	591361	454756609	27.7308492	9.1616869	.001300
770	592900	456533000	27.7488739	9.1656565	.001298
771	594441	458314011	27.7668808	9.1696225	.001297
772	595984	460099648	27.7848880	9.1735852	.001295
773	597529	461889917	27.8028775	9.1775445	.001293
774	599076	463684824	27.8208555	9.1815003	.001291
775	600625	465484375	27.8388218	9.1854527	.001290
776	602176	467288576	27.8567766	9.1894018	.001288
777	603729	469097433	27.8747197	9.1933474	.001287
778	605284	470910952	27.8926514	9.1972897	.001285
779	606841	472729139	27.9105715	9.2012286	.001283
780	608400	474552000	27.9284801	9.2051641	.001282
781	609961	476379541	27.9463772	9.2090962	.001280
782	611524	478211768	27.9642629	9.2130250	.001278
783	613089	480048687	27.9821372	9.2169505	.001277
784	614656	481890304	28.0000000	9.2208726	.001275
785	616225	483736625	28.0178515	9.2247914	.001273
786	617796	485587656	28.0356915	9.2287068	.001272
787	619369	487443403	28.0535203	9.2326189	.001270
788	620944	489303872	28.0713377	9.2365277	.001269
789	622521	491169069	28.0891438	9.2404333	.001267
790	624100	493039000	28.1069386	9.2443355	.001265
791	625681	494913671	28.1247222	9.2482344	.001264
792	627264	496793088	28.1424946	9.2521300	.001262
793	628849	498677257	28.1602557	9.2560224	.001261
794	630436	500566184	28.1780056	9.2599114	.001259
795	632025	502459875	28.1957444	9.2637973	.001257
796	633616	504358336	28.2134720	9.2676798	.001256
797	635209	506261573	28.2311884	9.2715592	.001254
798	636804	508169592	28.2488938	9.2754352	.001253
799	638401	510082399	28.2665881	9.2793081	.001251
800	640000	512000000	28.2842712	9.2831777	.001250
801	641601	513922401	28.3019434	9.2870440	.001248
802	643204	515849608	28.3196045	9.2909072	.001246
803	644809	517781627	28.3372546	9.2947671	.001245
804	646416	519718464	28.3548938	9.2986239	.001243
805	648025	521660125	28.3725219	9.3024775	.001242
806	649636	523606616	28.3901391	9.3063278	.001240

# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

	Squares	Cubes	Square roots	Cube roots	Reciprocals
97	651249	525557943	28.4077454	9.8101750	.001239157
98	652864	527514112	28.4253408	9.8140190	.001237624
99	654481	529475129	28.4429253	9.8178599	.001236094
100	656100	531441000	28.4604989	9.8216975	.001234568
101	657721	533411731	28.4780617	9.8255320	.001233046
102	659344	535387328	28.4956137	9.8293634	.001231527
103	660969	537367797	28.5131549	9.8331916	.001230012
104	662596	539353144	28.5306852	9.8370167	.001228501
105	664225	541343375	28.5482048	9.8408386	.001226994
106	665856	543338496	28.5657137	9.8446575	.001225490
107	667489	545338513	28.5832119	9.8484731	.001223990
108	669124	547343432	28.6006993	9.8522857	.001222494
109	670761	549353259	28.6181760	9.8560952	.001221001
110	672400	551368000	28.6356421	9.8599016	.001219512
111	674041	553387661	28.6530976	9.8637049	.001218027
112	675684	555412248	28.6705424	9.8675051	.001216545
113	677329	557441767	28.6879766	9.8713022	.001215067
114	678976	559476224	28.7054002	9.8750963	.001213592
115	680625	561515625	28.7228132	9.8788873	.001212121
116	682276	563559976	28.7402157	9.8826752	.001210654
117	683929	565609283	28.7576077	9.8864600	.001209190
118	685584	567663552	28.7749891	9.8902419	.001207729
119	687241	569722789	28.7923601	9.8940206	.001206273
120	688900	571787000	28.8097206	9.8977964	.001204819
121	690561	573856191	28.8270706	9.4015691	.001203369
122	692224	575930368	28.8444102	9.4053387	.001201923
123	693889	578009537	28.8617394	9.4091054	.001200480
124	695556	580093704	28.8790582	9.4128690	.001199041
125	697225	582182875	28.8963666	9.4166297	.001197605
126	698896	584277056	28.9136646	9.4203873	.001196172
127	700569	586376263	28.9309523	9.4241420	.001194743
128	702244	588480472	28.9482297	9.4278936	.001193317
129	703921	590589719	28.9654967	9.4316423	.001191895
130	705600	592704000	28.9827535	9.4353880	.001190476
131	707281	594823321	29.0000000	9.4391307	.001189061
132	708964	596947688	29.0172363	9.4428704	.001187648
133	710649	599077107	29.0344623	9.4466072	.001186240
134	712336	601211584	29.0516781	9.4503410	.001184834
135	714025	603351125	29.0688837	9.4540719	.001183432
136	715716	605495736	29.0860791	9.4577999	.001182033
137	717409	607645423	29.1032644	9.4615249	.001180638
138	719104	609800192	29.1204396	9.4652470	.001179245
139	720801	611960049	29.1376046	9.4689661	.001177856
140	722500	614125000	29.1547595	9.4726824	.001176471
141	724201	616295051	29.1719043	9.4763957	.001175088
142	725904	618470208	29.1890390	9.4801061	.001173709
143	727609	620650477	29.2061637	9.4838136	.001172333
144	729316	622835864	29.2232784	9.4875182	.001170960
145	731025	625026375	29.2403830	9.4912200	.001169591
146	732736	627222016	29.2574777	9.4949188	.001168224
147	734449	629422793	29.2745623	9.4986147	.001166861
148	736164	631628712	29.2916370	9.5023078	.001165501
149	737881	633839779	29.3087018	9.5059980	.001164144
150	739600	636056000	29.3257566	9.5096854	.001162791
151	741321	638277381	29.3428015	9.5133699	.001161440
152	743044	640503928	29.3598365	9.5170515	.001160093
153	744769	642735647	29.3768616	9.5207303	.001158749
154	746496	644972544	29.3938769	9.5244063	.001157407
155	748225	647214625	29.4108823	9.5280794	.001156069
156	749956	649461896	29.4278779	9.5317497	.001154734
157	751689	651714363	29.4448637	9.5354172	.001153403
158	753424	653972032	29.4618397	9.5390818	.001152074

No.	Squares	Cubes	square roots	Cube roots	Reciprocals
273	148129	81806117	10.3133070	7.1084000	002880000
274	139876	82013024	10.3200700	7.2040322	002873700
275	140625	82220000	10.3268187	7.3113470	002867400
276	141376	82427008	10.3335422	7.4178522	002861100
277	142129	82634000	10.3402400	7.5246000	002854800
278	142884	82841008	10.3469121	7.6316200	002848500
279	143641	83048000	10.3535600	7.7389000	002842200
280	144400	0	10.3601887	7.8464565	002835900
281	145161	1	10.3667913	7.9542048	002829600
282	145924	8	10.3733683	8.0621418	002823300
283	146689	27	10.3800000	8.1702678	002817000
284	147456	64	10.3865917	8.2784824	002810700
285	148225	125	10.3931410	8.3868864	002804400
286	148996	216	10.3996487	8.4954800	002798100
287	149769	343	10.4061150	8.6042632	002791800
288	150544	512	10.4125498	8.7132360	002785500
289	151321	729	10.4189530	8.8224000	002779200
290	152100	800	10.4253247	8.9317552	002772900
291	152881	891	10.4316650	9.0413008	002766600
292	153664	1000	10.4379737	9.1510368	002760300
293	154449	1107	10.4442500	9.2609632	002754000
294	155236	1216	10.4504947	9.3710800	002747700
295	156025	1327	10.4567078	9.4813872	002741400
296	156816	1440	10.4628893	9.5918848	002735100
297	157609	1555	10.4690393	9.7025728	002728800
298	158404	1672	10.4751578	9.8134512	002722500
299	159201	1791	10.4812447	9.9245200	002716200
300	160000	0	10.4872990	10.0357792	002709900
301	160801	0	10.4933207	10.1472288	002703600
302	161604	0	10.4993098	10.2588688	002697300
303	162409	0	10.5052663	10.3706992	002691000
304	163216	0	10.5111902	10.4827200	002684700
305	164025	0	10.5170815	10.5949312	002678400
306	164836	0	10.5229402	10.7073328	002672100
307	165649	0	10.5287663	10.8199248	002665800
308	166464	0	10.5345598	10.9327072	002659500
309	167281	0	10.5403207	11.0456800	002653200
310	168100	0	10.5460490	11.1588432	002646900
311	168921	0	10.5517447	11.2721968	002640600
312	169744	0	10.5574078	11.3857408	002634300
313	170569	0	10.5630383	11.4994752	002628000
314	171396	0	10.5686362	11.6134000	002621700
315	172225	0	10.5742015	11.7275152	002615400
316	173056	0	10.5797342	11.8418208	002609100
317	173889	0	10.5852343	11.9563168	002602800
318	174724	0	10.5907018	12.0709032	002596500
319	175561	0	10.5961367	12.1855800	002590200
320	176400	0	10.6015390	12.2993472	002583900
321	177241	0	10.6069087	12.4132048	002577600
322	178084	0	10.6122458	12.5271520	002571300
323	178929	0	10.6175493	12.6412896	002565000
324	179776	0	10.6228192	12.7555168	002558700
325	180625	0	10.6280555	12.8698336	002552400
326	181476	0	10.6332582	12.9842400	002546100
327	182329	0	10.6384273	13.0987360	002539800
328	183184	0	10.6435628	13.2133216	002533500
329	184041	0	10.6486647	13.3279968	002527200
330	184900	0	10.6537330	13.4427616	002520900
331	185761	0	10.6587677	13.5576160	002514600
332	186624	0	10.6637688	13.6725600	002508300
333	187489	0	10.6687363	13.7876032	002502000
334	188356	0	10.6736702	13.9027456	002495700

# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

	Squares	Cubes	Square roots	Cube roots	Reciprocal
35	189225	32312875	20.8566536	7.5769849	.00229885
36	190096	82881856	20.8806130	7.5827865	.00229357
37	190969	83453453	20.9045450	7.5885793	.00228833
38	191844	84027672	20.9284495	7.5943633	.00228310
39	192721	84604519	20.9523268	7.6001385	.00227790
40	193600	85184000	20.9761770	7.6059049	.00227272
41	194481	85766121	21.0000000	7.6116626	.00226757
42	195364	86350888	21.0237960	7.6174116	.00226244
43	196249	86938307	21.0475652	7.6231519	.00225733
44	197136	87528384	21.0713075	7.6288837	.00225225
45	198025	88121125	21.0950231	7.6346067	.00224719
46	198916	88716536	21.1187121	7.6403213	.00224215
47	199809	89314623	21.1423745	7.6460272	.00223713
48	200704	89915302	21.1660105	7.6517247	.00223214
49	201601	90518849	21.1896201	7.6574138	.00222717
50	202500	91125000	21.2132034	7.6630943	.00222222
51	203401	91733851	21.2367606	7.6687665	.00221729
52	204304	92345408	21.2602916	7.6744303	.00221238
53	205209	92959677	21.2837967	7.6800857	.00220750
54	206116	93576664	21.3072758	7.6857328	.00220264
55	207025	94196375	21.3307290	7.6913717	.00219780
56	207936	94818816	21.3541565	7.6970023	.00219298
57	208849	95443993	21.3775583	7.7026246	.00218818
58	209764	96071912	21.4009346	7.7082388	.00218340
59	210681	96702579	21.4242853	7.7138448	.00217864
60	211600	97336000	21.4476106	7.7194426	.00217391
61	212521	97972181	21.4709106	7.7250325	.00216919
62	213444	98611128	21.4941853	7.7306141	.00216450
63	214369	99252847	21.5174348	7.7361877	.00215982
64	215296	99897344	21.5406592	7.7417532	.00215517
65	216225	100544625	21.5638587	7.7473109	.00215053
66	217156	101194696	21.5870331	7.7528606	.00214592
67	218089	101847563	21.6101828	7.7584023	.00214132
68	219024	102503222	21.6332077	7.7639361	.00213675
69	219961	103161709	21.6564078	7.7694620	.00213219
70	220900	103823000	21.6794834	7.7749801	.00212766
71	221841	104487111	21.7025344	7.7804904	.00212314
72	222784	105154048	21.7255610	7.7859928	.00211864
73	223729	105823817	21.7485632	7.7914875	.00211416
74	224676	106496424	21.7715411	7.7969745	.00210970
75	225625	107171875	21.7944947	7.8024538	.00210526
76	226576	107850176	21.8174242	7.8079254	.00210084
77	227529	108531333	21.8403297	7.8133892	.00209643
78	228484	109215352	21.8632111	7.8188456	.00209203
79	229441	109902239	21.8860686	7.8242942	.00208765
80	230400	110592000	21.9089023	7.8297353	.00208330
81	231361	111284641	21.9317122	7.8351688	.00207900
82	232324	111980168	21.9544984	7.8405949	.00207469
83	233289	112678587	21.9772610	7.8460134	.00207038
84	234256	113379904	22.0000000	7.8514244	.00206611
85	235225	114084125	22.0227155	7.8568281	.00206184
86	236196	114791256	22.0454077	7.8622242	.00205761
87	237169	115501303	22.0680765	7.8676130	.00205338
88	238144	116214272	22.0907220	7.8729944	.00204911
89	239121	116930169	22.1133444	7.8783684	.00204490
90	240100	117649000	22.1359436	7.8837352	.00204080
91	241081	118370771	22.1585198	7.8890946	.00203666
92	242064	119095488	22.1810730	7.8944468	.00203255
93	243049	119823157	22.2036033	7.8997917	.00202848
94	244036	120553784	22.2261108	7.9051294	.00202442
95	245025	121286375	22.2485905	7.9104590	.00202039

	Squares	Cubes	Square roots	Cube roots	Reciprocals
497	247009	122763473	22.2934988	7.9210994	.002012072
498	248004	123505902	22.3159136	7.9264088	.002008082
499	249001	124251199	22.3383079	7.9317104	.002004008
500	250000	125000000	22.3606798	7.9370058	.002000000
501	251001	125751501	22.3830293	7.9422931	.001996008
502	252004	126506008	22.4053565	7.9475739	.001992062
503	253009	127263527	22.4276615	7.9528477	.001988072
504	254016	128024064	22.4499111	7.9581144	.001984127
505	255025	128787625	22.4722051	7.9633743	.001980198
506	256036	129554216	22.4944438	7.9686271	.001976285
507	257049	130323843	22.5166605	7.9738731	.001972387
508	258064	131096512	22.5388553	7.9791122	.001968504
509	259081	131872229	22.5610283	7.9843444	.001964637
510	260100	132651000	22.5831796	7.9895697	.001960784
511	261121	133432831	22.6053091	7.9947883	.001956947
512	262144	134217728	22.6274170	8.0000000	.001953125
513	263169	135005697	22.6495033	8.0052049	.001949318
514	264196	135796744	22.6715681	8.0104032	.001945525
515	265225	136590875	22.6936114	8.0155946	.001941748
516	266256	137388096	22.7156324	8.0207794	.001937984
517	267289	138188413	22.7376340	8.0259574	.001934236
518	268324	138991832	22.7596134	8.0311287	.001930502
519	269361	139798359	22.7815715	8.0362935	.001926782



# Squares, Cubes, Square Roots, Cube Roots and Reciprocals

No.	Squares	Cubes	Square roots	Cube roots	Reciprocal
550	312481	174676879	23.6481808	8.2376614	.00178890
551	313600	175616000	23.6643191	8.2425706	.00178571
552	314721	176558481	23.6854386	8.2474740	.00178253
553	315844	177504328	23.7065392	8.2523715	.00177935
554	316969	178453547	23.7276210	8.2572633	.00177619
555	318096	179406144	23.7486842	8.2621492	.00177305
556	319225	180362125	23.7697286	8.2670294	.00176991
557	320356	181321496	23.7907545	8.2719039	.00176678
558	321489	182284263	23.8117618	8.2767726	.00176366
559	322624	183250432	23.8327506	8.2816355	.00176056
560	323761	184220000	23.8537209	8.2864928	.00175746
570	324900	185193000	23.8746728	8.2913444	.00175438
571	326041	186169411	23.8956063	8.2961903	.00175131
572	327184	187149248	23.9165215	8.3010304	.00174825
573	328329	188132517	23.9374184	8.3058651	.00174520
574	329476	189119224	23.9582971	8.3106941	.00174216
575	330625	190109375	23.9791576	8.3155175	.00173913
576	331776	191102976	24.0000000	8.3203353	.00173611
577	332929	192100033	24.0208243	8.3251475	.00173310
578	334084	193100552	24.0416306	8.3299542	.00173010
579	335241	194104539	24.0624188	8.3347553	.00172711
580	336400	195112000	24.0831891	8.3395509	.00172413
581	337561	196122941	24.1039416	8.3443410	.00172117
582	338724	197137368	24.1246762	8.3491256	.00171821
583	339889	198155287	24.1453929	8.3539047	.00171526
584	341056	199176704	24.1660919	8.3586784	.00171232
585	342225	200201625	24.1867732	8.3634466	.00170940
586	343396	201230056	24.2074369	8.3682095	.00170648
587	344569	202262003	24.2280829	8.3729668	.00170357
588	345744	203297472	24.2487113	8.3777188	.00170068
589	346921	204336469	24.2693222	8.3824653	.00169779
590	348100	205379000	24.2899156	8.3872065	.00169491
591	349281	206425071	24.3104916	8.3919423	.00169204
592	350464	207474688	24.3310501	8.3966729	.00168918
593	351649	208527857	24.3515913	8.4013981	.00168634
594	352836	209584584	24.3721152	8.4061180	.00168350
595	354025	210644875	24.3926218	8.4108326	.00168067
596	355216	211708736	24.4131112	8.4155419	.00167785
597	356409	212776173	24.4335834	8.4202460	.00167504
598	357604	213847192	24.4540385	8.4249448	.00167224
599	358801	214921799	24.4744765	8.4296383	.00166944
600	360000	216000000	24.4948974	8.4343267	.00166666
601	361201	217081801	24.5153013	8.4390098	.00166389
602	362404	218167208	24.5356883	8.4436877	.00166113
603	363609	219256227	24.5560583	8.4483605	.00165837
604	364816	220348864	24.5764115	8.4530281	.00165562
605	366025	221445125	24.5967478	8.4576906	.00165289
606	367236	222545016	24.6170673	8.4623479	.00165016
607	368449	223648543	24.6373700	8.4670001	.00164744
608	369664	224755712	24.6576560	8.4716471	.00164473
609	370881	225866529	24.6779254	8.4762892	.00164203
610	372100	226981000	24.6981781	8.4809261	.00163934
611	373321	228099131	24.7184142	8.4855579	.00163666
612	374544	229220928	24.7386338	8.4901848	.00163398
613	375769	230346397	24.7588368	8.4948065	.00163132
614	376996	231475544	24.7790234	8.4994233	.00162866
615	378225	232608375	24.7991935	8.5040350	.00162601
616	379456	233744896	24.8193473	8.5086417	.00162337
617	380689	234885113	24.8394847	8.5132435	.00162074
618	381924	236029032	24.8596058	8.5178403	.00161812
619	383161	237176659	24.8797106	8.5224321	.00161550

# Practical Arithmetic

Squares	Cubes	Square roots	Cube roots	Residuals
203641	238	34.8198716	8.8310009	.0016
203884	240	34.9309278	8.8361780	.0016
204129	241	34.9509679	8.8407601	.0016
204376	242	34.9709920	8.8453173	.0016
204625	244	35.0000000	8.8498797	.0016
204876	246	35.0199920	8.8544372	.0016
205129	248	35.0399681	8.8589999	.0016
205384	247	35.0599282	8.8635377	.0016
205641	248	35.0798724	8.8680807	.0016
206000	250047000	35.0998008	8.8726189	.0016
206161	251239361	35.1197134	8.8771571	.0016
206424	252435968	35.1396102	8.8816953	.0016
400889	253636137	35.1594913	8.8862335	.0016
401956	254840104	35.1793564	8.8907717	.0016
403225	256047876	35.1992063	8.8953099	.0016
404496	257259456	35.2190404	8.8998481	.0016
406769	258474853	35.2388589	8.9043863	.0016
407044	259694072	35.2586619	8.9089245	.0016
408321	260917119	35.2784493	8.9134627	.0016
409600	1	35.2982213	8.9179999	.0016
410881	1	35.3179778	8.9225371	.0016
412164	1	35.3377189	8.9270753	.0016
413449	1	35.3574447	8.9316135	.0016
414736	1	35.3771551	8.9361517	.0016
416025	1	35.3968502	8.9406899	.0016
417316	1	35.4165301	8.9452281	.0016
418609	1	35.4361947	8.9497663	.0016
419904	1	35.4558441	8.9543045	.0016
421201	1	35.4754784	8.9588427	.0016
422500	375804451	35.4950976	8.9633809	.0016
423801	375804451	35.5147016	8.9679191	.0016
425104	277167808	35.5342907	8.9724573	.0016
426409	278445077	35.5538647	8.9769955	.0016
427716	279725254	35.5734237	8.9815337	.0016
429025	281011373	35.5929678	8.9860719	.0016
430336	282303431	35.6124969	8.9906101	.0016
431649	283593393	35.6320112	8.9951483	.0016
432964	284890312	35.6515107	8.9996865	.0016
434281	286191179	35.6709953	9.0042247	.0016
435600	287496000	35.6904652	9.0087629	.0016
436921	288804781	35.7099203	9.0133011	.0016
438244	290117529	35.7293607	9.0178393	.0016
439569	291434247	35.7487864	9.0223775	.0016
440896	1	35.7681976	9.0269157	.0016
442225	1	35.7875939	9.0314539	.0016
443556	1	35.8069756	9.0359921	.0016
444889	1	35.8263431	9.0405303	.0016
446224	1	35.8456960	9.0450685	.0016
447561	1	35.8650343	9.0496067	.0016
448900	307620001	35.8843582	9.0541449	.0016
450241	309111711	35.9036677	9.0586831	.0016
451584	303464448	35.9229628	9.0632213	.0016
452929	304821217	35.9422435	9.0677595	.0016
454276	306182024	35.9615100	9.0722977	.0016
455625	307546873	35.9807621	9.0768359	.0016
456976	308915776	36.0000000	9.0813741	.0016
458329	310288733	36.0192237	9.0859123	.0016
459684	311665753	36.0384331	9.0904505	.0016
461041	313046839	36.0576284	9.0949887	.0016
462400	314432000	36.0768096	9.0995269	.0016
463761	315821241	36.0959767	9.1040651	.0016
465124	317214568	36.1151297	9.1086033	.0016



Number	Square	Root	Cube roots	Reciprocals
6600	43560000	257	156000	00151515
6610	43682100	257	156300	00151515
6620	43804400	258	156600	00151515
6630	43926900	258	156900	00151515
6640	44049600	259	157200	00151515
6650	44172500	259	157500	00151515
6660	44295600	260	157800	00151515
6670	44418900	260	158100	00151515
6680	44542400	261	158400	00151515
6690	44666100	261	158700	00151515
6700	44790000	262	159000	00151515
6710	44914100	262	159300	00151515
6720	45038400	263	159600	00151515
6730	45162900	263	159900	00151515
6740	45287600	264	160200	00151515
6750	45412500	264	160500	00151515
6760	45537600	265	160800	00151515
6770	45662900	265	161100	00151515
6780	45788400	266	161400	00151515
6790	45914100	266	161700	00151515
6800	46040000	267	162000	00151515
6810	46166100	267	162300	00151515
6820	46292400	268	162600	00151515
6830	46418900	268	162900	00151515
6840	46545600	269	163200	00151515
6850	46672500	269	163500	00151515
6860	46799600	270	163800	00151515
6870	46926900	270	164100	00151515
6880	47054400	271	164400	00151515
6890	47182100	271	164700	00151515
6900	47310000	272	165000	00151515
6910	47438100	272	165300	00151515
6920	47566400	273	165600	00151515
6930	47694900	273	165900	00151515
6940	47823600	274	166200	00151515
6950	47952500	274	166500	00151515
6960	48081600	275	166800	00151515
6970	48210900	275	167100	00151515
6980	48340400	276	167400	00151515
6990	48470100	276	167700	00151515
7000	48600000	277	168000	00151515
7010	48730100	277	168300	00151515
7020	48860400	278	168600	00151515
7030	48990900	278	168900	00151515
7040	49121600	279	169200	00151515
7050	49252500	279	169500	00151515
7060	49383600	280	169800	00151515
7070	49514900	280	170100	00151515
7080	49646400	281	170400	00151515
7090	49778100	281	170700	00151515
7100	49910000	282	171000	00151515
7110	50042100	282	171300	00151515
7120	50174400	283	171600	00151515
7130	50306900	283	171900	00151515
7140	50439600	284	172200	00151515
7150	50572500	284	172500	00151515
7160	50705600	285	172800	00151515
7170	50838900	285	173100	00151515
7180	50972400	286	173400	00151515
7190	51106100	286	173700	00151515
7200	51240000	287	174000	00151515
7210	51374100	287	174300	00151515
7220	51508400	288	174600	00151515
7230	51642900	288	174900	00151515
7240	51777600	289	175200	00151515
7250	51912500	289	175500	00151515
7260	52047600	290	175800	00151515
7270	52182900	290	176100	00151515
7280	52318400	291	176400	00151515
7290	52454100	291	176700	00151515
7300	52590000	292	177000	00151515
7310	52726100	292	177300	00151515
7320	52862400	293	177600	00151515
7330	52998900	293	177900	00151515
7340	53135600	294	178200	00151515
7350	53272500	294	178500	00151515
7360	53409600	295	178800	00151515
7370	53546900	295	179100	00151515
7380	53684400	296	179400	00151515
7390	53822100	296	179700	00151515
7400	53960000	297	180000	00151515
7410	54098100	297	180300	00151515
7420	54236400	298	180600	00151515
7430	54374900	298	180900	00151515
7440	54513600	299	181200	00151515
7450	54652500	299	181500	00151515
7460	54791600	300	181800	00151515
7470	54930900	300	182100	00151515
7480	55070400	301	182400	00151515
7490	55210100	301	182700	00151515
7500	55350000	302	183000	00151515
7510	55490100	302	183300	00151515
7520	55630400	303	183600	00151515
7530	55770900	303	183900	00151515
7540	55911600	304	184200	00151515
7550	56052500	304	184500	00151515
7560	56193600	305	184800	00151515
7570	56334900	305	185100	00151515
7580	56476400	306	185400	00151515
7590	56618100	306	185700	00151515
7600	56760000	307	186000	00151515
7610	56902100	307	186300	00151515
7620	57044400	308	186600	00151515
7630	57186900	308	186900	00151515
7640	57329600	309	187200	00151515
7650	57472500	309	187500	00151515
7660	57615600	310	187800	00151515
7670	57758900	310	188100	00151515
7680	57902400	311	188400	00151515
7690	58046100	311	188700	00151515
7700	58190000	312	189000	00151515
7710	58334100	312	189300	00151515
7720	58478400	313	189600	00151515
7730	58622900	313	189900	00151515
7740	58767600	314	190200	00151515
7750	58912500	314	190500	00151515
7760	59057600	315	190800	00151515
7770	59202900	315	191100	00151515
7780	59348400	316	191400	00151515
7790	59494100	316	191700	00151515
7800	59640000	317	192000	00151515
7810	59786100	317	192300	00151515
7820	59932400	318	192600	00151515
7830	60078900	318	192900	00151515
7840	60225600	319	193200	00151515
7850	60372500	319	193500	00151515
7860	60519600	320	193800	00151515
7870	60666900	320	194100	00151515
7880	60814400	321	194400	00151515
7890	60962100	321	194700	00151515
7900	61110000	322	195000	00151515
7910	61258100	322	195300	00151515
7920	61406400	323	195600	00151515
7930	61554900	323	195900	00151515
7940	61703600	324	196200	00151515
7950	61852500	324	196500	00151515
7960	62001600	325	196800	00151515
7970	62150900	325	197100	00151515
7980	62300400	326	197400	00151515
7990	62450100	326	197700	00151515
8000	62600000	327	198000	00151515

No.	Squares	Cubes	Square roots	Cube roots	Reciprocal
745	555025	413493625	27.2946881	9.0653677	.001342
746	556516	415160936	27.3130006	9.0694220	.001340
747	558009	416832723	27.3313007	9.0734726	.001338
748	559504	418508992	27.3495887	9.0775197	.001336
749	561001	420189749	27.3678644	9.0815631	.001335
750	562500	421875000	27.3861279	9.0856030	.001333
751	564001	423564751	27.4043792	9.0896392	.001331
752	565504	425259008	27.4226184	9.0936719	.001329
753	567009	426957777	27.4408455	9.0977010	.001328
754	568516	428661064	27.4590604	9.1017265	.001326
755	570025	430368875	27.4772633	9.1057485	.001324
756	571536	432081216	27.4954542	9.1097669	.001322
757	573049	433798093	27.5136330	9.1137818	.001321
758	574564	435519512	27.5317998	9.1177931	.001319
759	576081	437245479	27.5499546	9.1218010	.001317
760	577600	438976000	27.5680975	9.1258053	.001315
761	579121	440711081	27.5862284	9.1298061	.001314
762	580644	442450728	27.6043475	9.1338034	.001312
763	582169	444194947	27.6224546	9.1377971	.001310
764	583696	445943744	27.6405499	9.1417874	.001308
765	585225	447697125	27.6586334	9.1457742	.001307
766	586756	449455096	27.6767050	9.1497576	.001305
767	588289	451217663	27.6947648	9.1537375	.001303
768	589824	452984832	27.7128129	9.1577139	.001302
769	591361	454756609	27.7308492	9.1616869	.001300
770	592900	456533000	27.7488739	9.1656565	.001298
771	594441	458314011	27.7668808	9.1696225	.001297
772	595984	460099648	27.7848880	9.1735852	.001295
773	597529	461889917	27.8028775	9.1775445	.001293
774	599076	463684824	27.8208555	9.1815003	.001291
775	600625	465484375	27.8388218	9.1854527	.001290
776	602176	467288576	27.8567766	9.1894018	.001288
777	603729	469097433	27.8747197	9.1933474	.001287
778	605284	470910952	27.8926514	9.1972897	.001285
779	606841	472729139	27.9105715	9.2012286	.001283
780	608400	474552000	27.9284801	9.2051641	.001282
781	609961	476379541	27.9463772	9.2090962	.001280
782	611524	478211768	27.9642629	9.2130250	.001278
783	613089	480048687	27.9821372	9.2169505	.001277
784	614656	481890304	28.0000000	9.2208726	.001275
785	616225	483736625	28.0178515	9.2247914	.001273
786	617796	485587656	28.0356915	9.2287068	.001272
787	619369	487443403	28.0535203	9.2326189	.001270
788	620944	489303872	28.0713377	9.2365277	.001269
789	622521	491169069	28.0891438	9.2404333	.001267
790	624100	493039000	28.1069386	9.2443355	.001265
791	625681	494913671	28.1247222	9.2482344	.001264
792	627264	496793088	28.1424946	9.2521300	.001262
793	628849	498677257	28.1602557	9.2560224	.001261
794	630436	500566184	28.1780056	9.2599114	.001259
795	632025	502459875	28.1957444	9.2637973	.001257
796	633616	504358336	28.2134720	9.2676798	.001256
797	635209	506261573	28.2311884	9.2715592	.001254
798	636804	508169592	28.2488938	9.2754352	.001253
799	638401	510082399	28.2665881	9.2793081	.001251
800	640000	512000000	28.2842712	9.2831777	.001250
801	641601	513922401	28.3019434	9.2870440	.001248
802	643204	515849608	28.3196045	9.2909072	.001246
803	644809	517781627	28.3372546	9.2947671	.001245
804	646416	519718464	28.3548938	9.2986239	.001243
805	648025	521660125	28.3725219	9.3024775	.001242
806	649636	523606616	28.3901391	9.3063278	.001240

	Squares	Cubes	Square roots	Cube roots	Reciprocals
	651249	525557943	28.4077454	9.8101750	.001239157
	652864	527514112	28.4253408	9.8140190	.001237624
	654481	529475129	28.4429253	9.8178599	.001236094
	656100	531441000	28.4604989	9.8216975	.001234568
	657721	533411731	28.4780617	9.8255320	.001233046
	659344	535387328	28.4956137	9.8293634	.001231527
	660969	537367797	28.5131549	9.8331916	.001230012
	662596	539353144	28.5306852	9.8370167	.001228501
	664225	541343375	28.5482048	9.8408386	.001226994
	665856	543338496	28.5657137	9.8446575	.001225490
	667489	545338513	28.5832119	9.8484731	.001223990
	669124	547343432	28.6006993	9.8522857	.001222494
	670761	549353259	28.6181760	9.8560952	.001221001
	672400	551368000	28.6356421	9.8599016	.001219512
	674041	553387661	28.6530976	9.8637049	.001218027
	675684	555412248	28.6705424	9.8675051	.001216545
	677329	557441767	28.6879766	9.8713022	.001215067
	678976	559476224	28.7054002	9.8750963	.001213592
	680625	561515625	28.7228132	9.8788873	.001212121
	682276	563559976	28.7402157	9.8826752	.001210654
	683929	565609283	28.7576077	9.8864600	.001209190
	685584	567663552	28.7749891	9.8902419	.001207729
	687241	569722789	28.7923601	9.8940206	.001206273
	688900	571787000	28.8097206	9.8977964	.001204819
	690561	573856191	28.8270706	9.4015691	.001203369
	692224	575930368	28.8444102	9.4053387	.001201923
	693889	578009537	28.8617394	9.4091054	.001200480
	695556	580093704	28.8790582	9.4128690	.001199041
	697225	582182875	28.8963666	9.4166297	.001197605
	698896	584277056	28.9136646	9.4203873	.001196172
	700569	586376263	28.9309523	9.4241420	.001194743
	702244	588480472	28.9482297	9.4278936	.001193317
	703921	590589719	28.9654967	9.4316423	.001191895
	705600	592704000	28.9827535	9.4353880	.001190476
	707281	594823321	29.0000000	9.4391307	.001189061
	708964	596947688	29.0172363	9.4428704	.001187648
	710649	599077107	29.0344623	9.4466072	.001186240
	712336	601211584	29.0516781	9.4503410	.001184834
	714025	603351125	29.0688837	9.4540719	.001183432
	715716	605495736	29.0860791	9.4577999	.001182033
	717409	607645423	29.1032644	9.4615249	.001180638
	719104	609800192	29.1204396	9.4652470	.001179245
	720801	611960049	29.1376046	9.4689661	.001177856
	722500	614125000	29.1547595	9.4726824	.001176471
	724201	616295051	29.1719043	9.4763957	.001175088
	725904	618470208	29.1890390	9.4801061	.001173709
	727609	620650477	29.2061637	9.4838136	.001172333
	729316	622835864	29.2232784	9.4875182	.001170960
	731025	625026375	29.2403830	9.4912200	.001169591
	732736	627222016	29.2574777	9.4949188	.001168224
	734449	629422793	29.2745623	9.4986147	.001166861
	736164	631628712	29.2916370	9.5023078	.001165501
	737881	633839779	29.3087018	9.5059980	.001164144
	739600	636056000	29.3257566	9.5096854	.001162791
	741321	638277381	29.3428015	9.5133699	.001161440
	743044	640503928	29.3598365	9.5170515	.001160093
	744769	642735647	29.3768616	9.5207303	.001158749
	746496	644972544	29.3938769	9.5244063	.001157407
	748225	647214625	29.4108823	9.5280794	.001156069
	749956	649461896	29.4278779	9.5317497	.001154734
	751689	651714363	29.4448637	9.5354172	.001153403
	753424	653972032	29.4618397	9.5390818	.001152074

# Practical Arithmetic

sq.	Figures	Order	Square roots	Order roots	Results
66	765161	678824000	20 6788159	0 6437437	0011
67	766000	680000000	20 6807624	0 6460237	0011
67	76604	680715311	20 6812704	0 6460689	0011
67	766104	680760000	20 6809481	0 6457123	0011
68	766179	680820017	20 6812754	0 6475830	0011
68	766176	680827024	20 6812810	0 6475830	0011
68	766171	680821175	20 6812800	0 6465500	0011
68	767276	681221370	20 6812872	0 6465862	0011
67	767129	681220123	20 6814162	0 6476377	0011
67	770094	681660150	20 6814045	0 6476746	0011
67	772041	682161620	20 6819342	0 6490006	0011
68	774000	682670000	20 6824700	0 6503307	0011
61	776161	683170761	20 6829642	0 6504000	0011
62	777994	683670000	20 6834048	0 6504000	0011
62	778000	683676107	20 6834100	0 6504100	0011
66	781620	684170704	20 6838137	0 6504373	0011
66	782221	684174100	20 6838100	0 6504373	0011
66	784000	684674400	20 6843031	0 6504000	0011
67	786700	685174100	20 6847960	0 6504017	0011
68	788664	685673777	20 6852880	0 6504011	0011
68	790091	686173400	20 6857800	0 6504077	0011
69	792100	686673000	20 6862700	0 6504017	0011
69	793501	687172701	20 6867621	0 6504000	0011
69	795004	687672400	20 6872500	0 6504010	0011
69	797640	688172100	20 6877350	0 6504073	0011
64	799210	688671804	20 6882200	0 6504007	0011
65	801020	689171500	20 6887050	0 6504013	0011
66	802810	689671200	20 6891900	0 6504000	0011
67	804000	690170900	20 6896750	0 6504042	0011
68	806004	690670601	20 6901601	0 6504037	0011
68	808001	691170300	20 6906450	0 6504000	0011
69	810000	691670000	20 6911300	0 6504000	0011
69	811601	692169701	20 6916150	0 6504004	0011
69	813004	692669400	20 6921000	0 6504000	0011
69	814600	693169100	20 6925850	0 6504000	0011
64	817211	693668804	20 6930700	0 6504003	0011
69	819020	694168500	20 6935550	0 6504000	0011
69	820500	694668200	20 6940400	0 6504000	0011
69	822040	695167904	20 6945250	0 6504004	0011
69	824664	695667601	20 6950100	0 6504000	0011
69	826221	696167300	20 6954950	0 6504000	0011
70	828000	696667000	20 6959800	0 6504000	0011
70	830000	697166700	20 6964650	0 6504000	0011
70	832000	697666400	20 6969500	0 6504000	0011
70	834000	698166100	20 6974350	0 6504000	0011
70	836000	698665800	20 6979200	0 6504000	0011
70	838000	699165500	20 6984050	0 6504000	0011
70	840000	699665200	20 6988900	0 6504000	0011
70	842000	700164900	20 6993750	0 6504000	0011
70	844000	700664600	20 6998600	0 6504000	0011
70	846000	701164300	20 7003450	0 6504000	0011
70	848000	701664000	20 7008300	0 6504000	0011
70	850000	702163700	20 7013150	0 6504000	0011
70	852000	702663400	20 7018000	0 6504000	0011
70	854000	703163100	20 7022850	0 6504000	0011
70	856000	703662800	20 7027700	0 6504000	0011
70	858000	704162500	20 7032550	0 6504000	0011
70	860000	704662200	20 7037400	0 6504000	0011
70	862000	705161900	20 7042250	0 6504000	0011
70	864000	705661600	20 7047100	0 6504000	0011
70	866000	706161300	20 7051950	0 6504000	0011
70	868000	706661000	20 7056800	0 6504000	0011
70	870000	707160700	20 7061650	0 6504000	0011
70	872000	707660400	20 7066500	0 6504000	0011
70	874000	708160100	20 7071350	0 6504000	0011
70	876000	708659800	20 7076200	0 6504000	0011
70	878000	709159500	20 7081050	0 6504000	0011
70	880000	709659200	20 7085900	0 6504000	0011
70	882000	710158900	20 7090750	0 6504000	0011
70	884000	710658600	20 7095600	0 6504000	0011
70	886000	711158300	20 7100450	0 6504000	0011
70	888000	711658000	20 7105300	0 6504000	0011
70	890000	712157700	20 7110150	0 6504000	0011
70	892000	712657400	20 7115000	0 6504000	0011
70	894000	713157100	20 7119850	0 6504000	0011
70	896000	713656800	20 7124700	0 6504000	0011
70	898000	714156500	20 7129550	0 6504000	0011
70	900000	714656200	20 7134400	0 6504000	0011
70	902000	715155900	20 7139250	0 6504000	0011
70	904000	715655600	20 7144100	0 6504000	0011
70	906000	716155300	20 7148950	0 6504000	0011
70	908000	716655000	20 7153800	0 6504000	0011
70	910000	717154700	20 7158650	0 6504000	0011
70	912000	717654400	20 7163500	0 6504000	0011
70	914000	718154100	20 7168350	0 6504000	0011
70	916000	718653800	20 7173200	0 6504000	0011
70	918000	719153500	20 7178050	0 6504000	0011
70	920000	719653200	20 7182900	0 6504000	0011
70	922000	720152900	20 7187750	0 6504000	0011
70	924000	720652600	20 7192600	0 6504000	0011
70	926000	721152300	20 7197450	0 6504000	0011
70	928000	721652000	20 7202300	0 6504000	0011
70	930000	722151700	20 7207150	0 6504000	0011
70	932000	722651400	20 7212000	0 6504000	0011
70	934000	723151100	20 7216850	0 6504000	0011
70	936000	723650800	20 7221700	0 6504000	0011
70	938000	724150500	20 7226550	0 6504000	0011
70	940000	724650200	20 7231400	0 6504000	0011
70	942000	725149900	20 7236250	0 6504000	0011
70	944000	725649600	20 7241100	0 6504000	0011
70	946000	726149300	20 7245950	0 6504000	0011
70	948000	726649000	20 7250800	0 6504000	0011
70	950000	727148700	20 7255650	0 6504000	0011
70	952000	727648400	20 7260500	0 6504000	0011
70	954000	728148100	20 7265350	0 6504000	0011
70	956000	728647800	20 7270200	0 6504000	0011
70	958000	729147500	20 7275050	0 6504000	0011
70	960000	729647200	20 7279900	0 6504000	0011
70	962000	730146900	20 7284750	0 6504000	0011
70	964000	730646600	20 7289600	0 6504000	0011
70	966000	731146300	20 7294450	0 6504000	0011
70	968000	731646000	20 7299300	0 6504000	0011
70	970000	732145700	20 7304150	0 6504000	0011
70	972000	732645400	20 7309000	0 6504000	0011
70	974000	733145100	20 7313850	0 6504000	0011
70	976000	733644800	20 7318700	0 6504000	0011
70	978000	734144500	20 7323550	0 6504000	0011
70	980000	734644200	20 7328400	0 6504000	0011
70	982000	735143900	20 7333250	0 6504000	0011
70	984000	735643600	20 7338100	0 6504000	0011
70	986000	736143300	20 7342950	0 6504000	0011
70	988000	736643000	20 7347800	0 6504000	0011
70	990000	737142700	20 7352650	0 6504000	0011
70	992000	737642400	20 7357500	0 6504000	0011
70	994000	738142100	20 7362350	0 6504000	0011
70	996000	738641800	20 7367200	0 6504000	0011
70	998000	739141500	20 7372050	0 6504000	0011
70	1000000	739641200	20 7376900	0 6504000	0011

# **Squares, Cubes, Square Roots, Cube Roots and Reciprocal**

Squares	Cubes	Square roots	Cube roots	Reciprocal
866761	809	30.1	9.7	.001074
866824	809	30.1	9.7	.001073
870489	812	30.1	9.7	.001072
872356	814	30.1	9.7	.001070
874225	817	30.1	9.7	.001068
876096	820	30.1	9.7	.001066
877969	822	30.1	9.7	.001067
879844	825	30.1	9.7	.001066
881721	827	30.1	9.7	.001064
883600	83	30.654	9.7	.001063
885481	83	30.671	9.7	.001062
887364	83	30.691	9.8	.001061
889249	83	30.706	9.8	.001060
891136	83	30.724	9.8	.001059
893025	83	30.746	9.8131989	.0010582
894916	83	30.757	9.8166591	.0010570
896809	83	30.771	9.8201109	.0010559
898704	83	30.781	9.8225723	.0010548
900601	83	30.801	9.8270252	.0010537
	857375000	30.81		.0010526
	860085351	30.81		.0010515
	862801408	30.81		.0010504
	865523177	30.81		.0010493
	868250664	30.81		.0010482
	870983875	30.91		.0010471
	873722816	30.91		.0010460
	876467493	30.91		.0010449
	879217912	30.91		.0010438
	881974079	30.9677251		.0010427
	8	30.9838668	9.8648483	.0010416
	8	31.0000000	9.8682724	.0010405
	8	31.0161248	9.8718041	.0010395
	8	31.0322413		.0010384
	8	31.0483494		.0010373
	8	31.0644491		.0010362
	8	31.0805405		.0010351
	8	31.0966236		.0010341
	8	31.1126984		.0010330
	8	31.1287648		.0010319
		230	9.8989830	.0010309
		729	9.9023835	.0010298
		145	9.9057817	.0010288
		179	9.1	.0010277
		731	9.1	.0010266
		300	9.1	.0010256
		387	9.1	.0010245
		392	9.1	.0010235
		315	9.1	.0010224
		757	9.1	.0010214
	900400	1517	9.9065549	.0010204
	902361	1195	9.9099095	.0010193
	904324	1792	9.9132641	.0010183
	906289	1308	9.9166187	.0010172
	908256	1748	9.9199733	.0010162
	910225	1000	9.9233279	.0010152
	912196	1369	9.9266825	.0010141
	914169	1561	9.9300371	.0010131
	916144	1672	9.9333917	.0010121
	918121	1704	9.9367463	.0010111
	970299000	31.4642654	9.9365549	.0010101
	978242271	31.4801525	9.9399095	.0010090
	976191488	31.4960396	9.9432641	.0010080



# Practical Arithmetic

No.	Squares	Cubes	Square roots	Cube roots	Recipr
993	986049	979146657	31.5119025	9.9766120	.00100
994	988036	982107784	31.5277655	9.9799599	.00100
995	990025	985074875	31.5436206	9.9833055	.00100
996	992016	988047936	31.5594677	9.9866488	.00100
997	994009	991026973	31.5753068	9.9899900	.00100
998	996004	994011992	31.5911380	9.9933289	.00100
999	998001	997002999	31.6069613	9.9966656	.00100
1000	1000000	1000000000	31.6227766	10.0000000	.00100
1001	1002001	1003003001	31.6385840	10.0033322	.00099
1002	1004004	1006012008	31.6543836	10.0066622	.00099
1003	1006009	1009027027	31.6701752	10.0099899	.00099
1004	1008016	1012048064	31.6859590	10.0133155	.00099
1005	1010025	1015075125	31.7017349	10.0166389	.00099
1006	1012036	1018108216	31.7175030	10.0199601	.00099
1007	1014049	1021147343	31.7332633	10.0232791	.00099
1008	1016064	1024192512	31.7490157	10.0265958	.00099
1009	1018081	1027243729	31.7647603	10.0299104	.00099
1010	1020100	1030301000	31.7804972	10.0332228	.00099
1011	1022121	1033364331	31.7962262	10.0365330	.00098
1012	1024144	1036433728	31.8119474	10.0398410	.00098
1013	1026169	1039509197	31.8276609	10.0431469	.00098
1014	1028196	1042590744	31.8433666	10.0464506	.00098
1015	1030225	1045678375	31.8590646	10.0497521	.00098
1016	1032256	1048772096	31.8747549	10.0530514	.00098
1017	1034289	1051871913	31.8904374	10.0563485	.00098
1018	1036324	1054977832	31.9061123	10.0596435	.00098
1019	1038361	1058089859	31.9217794	10.0629364	.00098
1020	1040400	1061208000	31.9374388	10.0662271	.00098
1021	1042441	1064332261	31.9530906	10.0695156	.00097
1022	1044484	1067462648	31.9687347	10.0728020	.00097
1023	1046529	1070599167	31.9843712	10.0760863	.00097
1024	1048576	1073741824	32.0000000	10.0793684	.00097
1025	1050625	1076890625	32.0156212	10.0826484	.00097
1026	1052676	1080045576	32.0312348	10.0859262	.00097
1027	1054729	1083206683	32.0468407	10.0892019	.00097
1028	1056784	1086373952	32.0624391	10.0924755	.00097
1029	1058841	1089547389	32.0780298	10.0957469	.00097
1030	1060900	1092727000	32.0936131	10.0990163	.00097
1031	1062961	1095912791	32.1091887	10.1022835	.00096
1032	1065024	1099104768	32.1247568	10.1055487	.00096
1033	1067089	1102302937	32.1403173	10.1088117	.00096
1034	1069156	1105507304	32.1558704	10.1120726	.00096
1035	1071225	1108717875	32.1714159	10.1153314	.00096
1036	1073296	1111934656	32.1869539	10.1185882	.00096
1037	1075369	1115157653	32.2024844	10.1218428	.00096
1038	1077444	1118386872	32.2180074	10.1250953	.00096
1039	1079521	1121622319	32.2335229	10.1283457	.00096
1040	1081600	1124864000	32.2490310	10.1315941	.00096
1041	1083681	1128111921	32.2645316	10.1348403	.00096
1042	1085764	1131366088	32.2800248	10.1380845	.00095
1043	1087849	1134626507	32.2955105	10.1413266	.00095
1044	1089936	1137893184	32.3109888	10.1445667	.00095
1045	1092025	1141166125	32.3264598	10.1478047	.00095
1046	1094116	1144445336	32.3419283	10.1510406	.00095
1047	1096209	1147730828	32.3573794	10.1542744	.00095
1048	1098304	1151022592	32.3728281	10.1575062	.00095
1049	1100401	1154320649	32.3882695	10.1607359	.00095
1050	1102500	1157625000	32.4037035	10.1639636	.00095
1051	1104601	1160935651	32.4191301	10.1671893	.00095
1052	1106704	1164252608	32.4345495	10.1704129	.00095
1053	1108809	1167575877	32.4499615	10.1736344	.00094
1054	1110916	1170905464	32.4653662	10.1768539	.00094

## 2. WEIGHTS AND MEASURES

### Measures of Length

- = 1 foot
- = 1 yard = 36 inches
- = 1 rod = 198 inches = 16½ feet
- = 1 furlong = 7 920 inches = 660 feet = 320 yards
- = 1 mile = 63 360 inches = 5 280 feet = 1 760 yards = 320 rods
- = 633 600 of a mile

### GUNTER'S CHAIN

- 792 inches = 1 link
- 100 links = 1 chain = 4 rods = 66 feet
- 80 chains = 1 mile

### ROPE AND CABLE

- 6 feet = 1 fathom
- 120 fathoms = 1 cable's length

Table Showing Inches Expressed in Decimals of a Foot

	0	1	2	3	4	5	6	7	8	9	10	11
Foot	.0000	.0001	.0002	.0003	.0004	.0005	.0006	.0007	.0008	.0009	.0010	.0011
.0012	.0013	.0014	.0015	.0016	.0017	.0018	.0019	.0020	.0021	.0022	.0023	.0024
.0025	.0026	.0027	.0028	.0029	.0030	.0031	.0032	.0033	.0034	.0035	.0036	.0037
.0038	.0039	.0040	.0041	.0042	.0043	.0044	.0045	.0046	.0047	.0048	.0049	.0050
.0051	.0052	.0053	.0054	.0055	.0056	.0057	.0058	.0059	.0060	.0061	.0062	.0063
.0064	.0065	.0066	.0067	.0068	.0069	.0070	.0071	.0072	.0073	.0074	.0075	.0076
.0077	.0078	.0079	.0080	.0081	.0082	.0083	.0084	.0085	.0086	.0087	.0088	.0089
.0090	.0091	.0092	.0093	.0094	.0095	.0096	.0097	.0098	.0099	.0100	.0101	.0102
.0103	.0104	.0105	.0106	.0107	.0108	.0109	.0110	.0111	.0112	.0113	.0114	.0115
.0116	.0117	.0118	.0119	.0120	.0121	.0122	.0123	.0124	.0125	.0126	.0127	.0128
.0129	.0130	.0131	.0132	.0133	.0134	.0135	.0136	.0137	.0138	.0139	.0140	.0141
.0142	.0143	.0144	.0145	.0146	.0147	.0148	.0149	.0150	.0151	.0152	.0153	.0154
.0155	.0156	.0157	.0158	.0159	.0160	.0161	.0162	.0163	.0164	.0165	.0166	.0167
.0168	.0169	.0170	.0171	.0172	.0173	.0174	.0175	.0176	.0177	.0178	.0179	.0180
.0181	.0182	.0183	.0184	.0185	.0186	.0187	.0188	.0189	.0190	.0191	.0192	.0193
.0194	.0195	.0196	.0197	.0198	.0199	.0200	.0201	.0202	.0203	.0204	.0205	.0206
.0207	.0208	.0209	.0210	.0211	.0212	.0213	.0214	.0215	.0216	.0217	.0218	.0219
.0220	.0221	.0222	.0223	.0224	.0225	.0226	.0227	.0228	.0229	.0230	.0231	.0232
.0233	.0234	.0235	.0236	.0237	.0238	.0239	.0240	.0241	.0242	.0243	.0244	.0245
.0246	.0247	.0248	.0249	.0250	.0251	.0252	.0253	.0254	.0255	.0256	.0257	.0258
.0259	.0260	.0261	.0262	.0263	.0264	.0265	.0266	.0267	.0268	.0269	.0270	.0271
.0272	.0273	.0274	.0275	.0276	.0277	.0278	.0279	.0280	.0281	.0282	.0283	.0284
.0285	.0286	.0287	.0288	.0289	.0290	.0291	.0292	.0293	.0294	.0295	.0296	.0297
.0298	.0299	.0300	.0301	.0302	.0303	.0304	.0305	.0306	.0307	.0308	.0309	.0310
.0311	.0312	.0313	.0314	.0315	.0316	.0317	.0318	.0319	.0320	.0321	.0322	.0323
.0324	.0325	.0326	.0327	.0328	.0329	.0330	.0331	.0332	.0333	.0334	.0335	.0336
.0337	.0338	.0339	.0340	.0341	.0342	.0343	.0344	.0345	.0346	.0347	.0348	.0349
.0350	.0351	.0352	.0353	.0354	.0355	.0356	.0357	.0358	.0359	.0360	.0361	.0362
.0363	.0364	.0365	.0366	.0367	.0368	.0369	.0370	.0371	.0372	.0373	.0374	.0375
.0376	.0377	.0378	.0379	.0380	.0381	.0382	.0383	.0384	.0385	.0386	.0387	.0388
.0389	.0390	.0391	.0392	.0393	.0394	.0395	.0396	.0397	.0398	.0399	.0400	.0401
.0402	.0403	.0404	.0405	.0406	.0407	.0408	.0409	.0410	.0411	.0412	.0413	.0414
.0415	.0416	.0417	.0418	.0419	.0420	.0421	.0422	.0423	.0424	.0425	.0426	.0427
.0428	.0429	.0430	.0431	.0432	.0433	.0434	.0435	.0436	.0437	.0438	.0439	.0440
.0441	.0442	.0443	.0444	.0445	.0446	.0447	.0448	.0449	.0450	.0451	.0452	.0453
.0454	.0455	.0456	.0457	.0458	.0459	.0460	.0461	.0462	.0463	.0464	.0465	.0466
.0467	.0468	.0469	.0470	.0471	.0472	.0473	.0474	.0475	.0476	.0477	.0478	.0479
.0480	.0481	.0482	.0483	.0484	.0485	.0486	.0487	.0488	.0489	.0490	.0491	.0492
.0493	.0494	.0495	.0496	.0497	.0498	.0499	.0500	.0501	.0502	.0503	.0504	.0505
.0506	.0507	.0508	.0509	.0510	.0511	.0512	.0513	.0514	.0515	.0516	.0517	.0518
.0519	.0520	.0521	.0522	.0523	.0524	.0525	.0526	.0527	.0528	.0529	.0530	.0531
.0532	.0533	.0534	.0535	.0536	.0537	.0538	.0539	.0540	.0541	.0542	.0543	.0544
.0545	.0546	.0547	.0548	.0549	.0550	.0551	.0552	.0553	.0554	.0555	.0556	.0557
.0558	.0559	.0560	.0561	.0562	.0563	.0564	.0565	.0566	.0567	.0568	.0569	.0570
.0571	.0572	.0573	.0574	.0575	.0576	.0577	.0578	.0579	.0580	.0581	.0582	.0583
.0584	.0585	.0586	.0587	.0588	.0589	.0590	.0591	.0592	.0593	.0594	.0595	.0596
.0597	.0598	.0599	.0600	.0601	.0602	.0603	.0604	.0605	.0606	.0607	.0608	.0609
.0610	.0611	.0612	.0613	.0614	.0615	.0616	.0617	.0618	.0619	.0620	.0621	.0622
.0623	.0624	.0625	.0626	.0627	.0628	.0629	.0630	.0631	.0632	.0633	.0634	.0635
.0636	.0637	.0638	.0639	.0640	.0641	.0642	.0643	.0644	.0645	.0646	.0647	.0648
.0649	.0650	.0651	.0652	.0653	.0654	.0655	.0656	.0657	.0658	.0659	.0660	.0661
.0662	.0663	.0664	.0665	.0666	.0667	.0668	.0669	.0670	.0671	.0672	.0673	.0674
.0675	.0676	.0677	.0678	.0679	.0680	.0681	.0682	.0683	.0684	.0685	.0686	.0687
.0688	.0689	.0690	.0691	.0692	.0693	.0694	.0695	.0696	.0697	.0698	.0699	.0700
.0701	.0702	.0703	.0704	.0705	.0706	.0707	.0708	.0709	.0710	.0711	.0712	.0713
.0714	.0715	.0716	.0717	.0718	.0719	.0720	.0721	.0722	.0723	.0724	.0725	.0726
.0727	.0728	.0729	.0730	.0731	.0732	.0733	.0734	.0735	.0736	.0737	.0738	.0739
.0740	.0741	.0742	.0743	.0744	.0745	.0746	.0747	.0748	.0749	.0750	.0751	.0752
.0753	.0754	.0755	.0756	.0757	.0758	.0759	.0760	.0761	.0762	.0763	.0764	.0765
.0766	.0767	.0768	.0769	.0770	.0771	.0772	.0773	.0774	.0775	.0776	.0777	.0778
.0779	.0780	.0781	.0782	.0783	.0784	.0785	.0786	.0787	.0788	.0789	.0790	.0791
.0792	.0793	.0794	.0795	.0796	.0797	.0798	.0799	.0800	.0801	.0802	.0803	.0804
.0805	.0806	.0807	.0808	.0809	.0810	.0811	.0812	.0813	.0814	.0815	.0816	.0817
.0818	.0819	.0820	.0821	.0822	.0823	.0824	.0825	.0826	.0827	.0828	.0829	.0830
.0831	.0832	.0833	.0834	.0835	.0836	.0837	.0838	.0839	.0840	.0841	.0842	.0843
.0844	.0845	.0846	.0847	.0848	.0849	.0850	.0851	.0852	.0853	.0854	.0855	.0856
.0857	.0858	.0859	.0860	.0861	.0862	.0863	.0864	.0865	.0866	.0867	.0868	.0869
.0870	.0871	.0872	.0873	.0874	.0875	.0876	.0877	.0878	.0879	.0880	.0881	.0882
.0883	.0884	.0885	.0886	.0887	.0888	.0889	.0890	.0891	.0892	.0893	.0894	.0895
.0896	.0897	.0898	.0899	.0900	.0901	.0902	.0903	.0904	.0905	.0906	.0907	.0908
.0909	.0910	.0911	.0912	.0913	.0914	.0915	.0916	.0917	.0918	.0919	.0920	.0921
.0922	.0923	.0924	.0925	.0926	.0927	.0928	.0929	.0930	.0931	.0932	.0933	.0934
.0935	.0936	.0937	.0938	.0939	.0940	.0941	.0942	.0943	.0944	.0945	.0946	.0947
.0948	.0949	.0950	.0951	.0952	.0953	.0954	.0955	.0956	.0957	.0958	.0959	.0960
.0961	.0962	.0963	.0964	.0965	.0966	.0967	.0968	.0969	.0970	.0971	.0972	.0973
.0974	.0975	.0976	.0977	.0978	.0979	.0980	.0981	.0982	.0983	.0984	.0985	.0986
.0987	.0988	.0989	.0990	.0991	.0992	.0993	.0994	.0995	.0996	.0997	.0998	.0999

Decimal Equivalents for Fractions of an Inch

$\frac{1}{32}$	$\frac{1}{64}$	Decimals	Frac- tions	$\frac{1}{32}$	$\frac{1}{64}$	Decimals	
.....	1	0.015625	.....	.....	33	0.515625	- -
1	2	0.03125	.....	17	34	0.53125	- -
.....	3	0.046875	.....	.....	35	0.546875	- -
2	4	0.0625	$\frac{1}{16}$	18	36	0.5625	
.....	5	0.078125	.....	.....	37	0.578125	- -
3	6	0.09375	.....	19	38	0.59375	- -
.....	7	0.109375	.....	.....	39	0.609375	- -
4	8	0.125	$\frac{1}{8}$	20	40	0.625	
.....	9	0.140625	.....	.....	41	0.640625	- -
5	10	0.15625	.....	21	42	0.65625	- -
.....	11	0.171875	.....	.....	43	0.671875	- -
6	12	0.1875	$\frac{3}{16}$	22	44	0.6875	
.....	13	0.203125	.....	.....	45	0.703125	...
7	14	0.21875	.....	23	46	0.71875	...
.....	15	0.234375	.....	.....	47	0.734375	...
8	16	0.25	$\frac{1}{4}$	24	48	0.75	
.....	17	0.265625	.....	.....	49	0.765625	...
9	18	0.28125	.....	25	50	0.78125	...
.....	19	0.296875	.....	.....	51	0.796875	...
10	20	0.3125	$\frac{5}{16}$	26	52	0.8125	
.....	21	0.328125	.....	.....	53	0.828125	...
11	22	0.34375	.....	27	54	0.84375	...
.....	23	0.359375	.....	.....	55	0.859375	...
12	24	0.375	$\frac{3}{8}$	28	56	0.875	
.....	25	0.390625	.....	.....	57	0.890625	...
13	26	0.40625	.....	29	58	0.90625	...
.....	27	0.421875	.....	.....	59	0.921875	...
14	28	0.4375	$\frac{7}{16}$	30	60	0.9375	
.....	29	0.453125	.....	.....	61	0.953125	...
15	30	0.46875	.....	31	62	0.96875	...
.....	31	0.484375	.....	.....	63	0.984375	...
16	32	0.5	$\frac{1}{2}$	32	64	1.	1

Nautical Measures

A nautical or sea-mile is the length of a minute of longitude of the earth at the equator at the level of the sea. It is assumed that 6086.07 ft = 1 statute or land-miles by the United States Coast Survey.  
3 nautical miles = 1 league

Miscellaneous Measures

- 1 palm = 3 inches  
1 hand = 4 inches
- 1 span = 9 inches  
1 meter = 3.2809 feet



### Measures of Surface

144 square inches = 1 square foot  
 9 square feet = 1 square yard = 1 296 square inches  
 100 square feet = 1 square (architects' measure)

### LAND MEASURE

16 square yards = 1 square rod  
 1 square rods = 1 square rod = 1 210 square yards  
 4 square rods } = 1 acre = 4 840 square yards  
 10 square chains } = 160 square rods  
 10 acres = 1 square mile = 3 097 600 square yards = }  
 1 200 square rods = 2 560 square rods  
 43 560 square feet = 1 acre = 43 560 square feet  
 SECTION of land is a square mile, and a QUARTER-SECTION is 160 acres

### Measures of Volume

1 pint, liquid measure = 231 cubic inches, and contains 8.339 avoirdupois  
 of distilled water at 39.8° F., or 58 333 grains  
 1 cubic foot contains 7.48 liquid gallons, or 6.428 dry gallons  
 1 gallon, dry measure = 268.8 cubic inches  
 1 bushel (Winchester) contains 2150.42 cubic inches, or 77.627 pounds dis-  
 water at 39.8° F.  
 1 heaped bushel contains 2747.715 cubic inches

### DRY MEASURE

2 pints = 1 quart = 67.2 cubic inches  
 4 quarts = 1 gallon = 8 pints = 268.8 cubic inches  
 2 gallons = 1 peck = 16 pints = 8 quarts = 537.6 cubic inches  
 4 pecks = 1 bushel = 64 pints = 32 quarts = 8 gallons  
 = 2150.42 cubic inches  
 1 cord of wood = 128 cubic feet

### LIQUID MEASURE

4 gills = 1 pint = 16 fluid ounces  
 2 pints = 1 quart = 8 gills = 32 fluid ounces  
 4 quarts = 1 gallon = 32 gills = 8 pints = 128 fluid ounces

the United States and Great Britain 1 barrel of wine or brandy = 31½  
 and contains 4.211 cubic feet.  
 1 hogshead is 63 gallons, but this term is often applied to casks of various  
 sizes.

### Cubic Measure

1728 cubic inches = 1 cubic foot  
 27 cubic feet = 1 cubic yard

MEASURING WOOD, a pile of wood cut 4 feet long, piled 4 feet high, and 8 feet  
 ground, making 128 cubic feet, is called a CORD.  
 1 cubic foot make one cord-foot.  
 CORD OF STONE is nominally 16½ feet long, 1 foot high and 1½ feet thick,  
 contains 24½ cubic feet.

A perch of stone is, however, often computed differently in different places, thus, in most if not all of the States and Territories west of the Mississippi, stone-masons figure rubble by the perch of  $16\frac{1}{2}$  cubic feet. In Philadelphia 22 cubic feet are called a perch. In Chicago, stone is measured by the 100 cubic feet.

A ton of shipping is 42 cubic feet in Great Britain and 40 cubic feet in the United States.

### Fluid Measure

60 minims	= 1 fluid drachm
8 fluid drachms	= 1 ounce
16 ounces	= 1 pint
8 pints	= 1 gallon

### Miscellaneous Measures

Butt of Sherry = 108 gallons	Puncheon of Brandy = 110 to 120
Pipe of Port = 115 gallons	Puncheon of Rum = 100 to 110
Butt of Malaga = 105 gallons	Hogshead of Brandy = 55 to 60
Puncheon of Scotch Whiskey, = 110 to 130 gallons	Hogshead of Claret = 46 gallons

### Measures of Weight

The standard AVOIRDUPOIS POUND is the weight of 27.7015 cubic inches of distilled water weighed in air at  $39.83^{\circ}$  F., with the barometer at 30 inches. It contains 7 000 grains. One pound avoirdupois = 1.2153 pounds troy.

### Avoirdupois, or Ordinary Commercial Weight

1 drachm	= 27.343 grains
16 drachms	= 1 ounce (oz)
16 ounces	= 1 pound (lb)
100 pounds	= 1 hundredweight (cwt)
20 hundredweight	= 1 ton

In collecting duties upon foreign goods at the United States custom-house, and also in freighting coal and selling it by wholesale,

28 pounds	= 1 quarter
4 quarters, or 112 pounds	= 1 hundredweight
20 hundredweight	= 1 long ton = 2 240 pounds
A stone	= 14 pounds
A quintal	= 100 pounds

The following measures are sanctioned by custom or law: 1 bushel = 2 150 cubic feet or  $1\frac{1}{4}$  cubic feet, nearly.

32 pounds of oats	= 1 bushel
45 pounds of Timothy-seed	= 1 bushel
48 pounds of barley	= 1 bushel
56 pounds of rye	= 1 bushel
56 pounds of Indian corn	= 1 bushel
50 pounds of Indian meal	= 1 bushel
60 pounds of wheat	= 1 bushel
60 pounds of clover-seed	= 1 bushel
60 pounds of potatoes	= 1 bushel

56 pounds of butter	= 1 firkin
100 pounds of meal or flour	= 1 sack
100 pounds of grain or flour	= 1 cental
100 pounds of dry fish	= 1 quintal
100 pounds of nails	= 1 cask
196 pounds of flour	= 1 barrel
200 pounds of beef or pork	= 1 barrel
80 pounds of lime	= 1 bushel

## Troy Weight

### USED IN WEIGHING GOLD OR SILVER

24 grains	= 1 pennyweight (pwt)
20 pennyweights	= 1 ounce (oz)
12 ounces	= 1 pound (lb)

carat of the jewelers, for precious stones, is, in the United States, 3.2 grains, but it varies according to different authorities. In London, 3.17 grains, and in France, 3.18 grains are divided into 4 jewelers' grains. The international carat is 3.168 grains or 200 milligrams. In troy, apothecaries' and avoirdupois weights, the grain is the same, 1 pound troy being equal to 0.82286 pound avoirdupois.

## Apothecaries' Weight

### USED IN COMPOUNDING MEDICINES AND IN PUTTING UP MEDICAL PRESCRIPTIONS

60 grains (gr) = 1 scruple (℥)	8 drachms = 1 ounce (oz)
3 scruples = 1 drachm (℥)	12 ounces = 1 pound (lb)

## Measures of Value

### UNITED STATES STANDARD

10 mills = 1 cent	10 dimes = 1 dollar
10 cents = 1 dime	10 dollars = 1 eagle

THE STANDARD of gold and silver is 900 parts of pure metal and 100 of alloy in 1000 parts of coin.

THE FINENESS expresses the quantity of pure metal in 1000 parts.

THE REMEDY OF THE MINT is the allowance for deviation from the exact standard of fineness and weight of coins.

## Weights of Coins

Double eagle	= 516 troy grains
Eagle	= 258 troy grains
Dollar (gold)	= 25.8 troy grains
Dollar (silver)	= 412.5 troy grains
Half-dollar	= 192 troy grains
5-cent piece (nickel)	= 77.16 troy grains
3-cent piece (nickel)	= 30 troy grains
Cent (bronze)	= 48 troy grains

### Measures of Time

60 seconds = 1 minute

60 minutes = 1 hour

24 hours = 1 day

365 days = 1 common year

366 days = 1 leap-year

A SOLAR DAY is measured by the rotation of the earth upon its axis, with reference to the sun.

In ASTRONOMICAL COMPUTATIONS and in NAUTICAL TIME the day commences at noon, and in the former it is counted throughout the 24 hours.

In CIVIL COMPUTATIONS the day commences at midnight, and is divided into two parts of 12 hours each.

A SOLAR YEAR is the time in which the earth makes one revolution around the sun. Its average time, called the MEAN SOLAR YEAR, is 365 days, 5 hours, 48 minutes and 49.7 seconds, or nearly  $365\frac{1}{4}$  days.

A MEAN LUNAR MONTH, or LUNATION of the moon, is 29 days, 12 hours, 44 minutes, 2 seconds and 5.24 thirds. It is equal, on the average, to 29.53 days.

### The Calendar, Old and New Style

The JULIAN Calendar was established by Julius Caesar, 44 B.C., and by which day was inserted in every fourth year. This was the same thing as assuming that the length of the solar year was 365 days and 6 hours, instead of the length given above, thus introducing an accumulative error of 11 minutes and 12 seconds every year. This calendar was adopted by the church in 325 A.D., at the Council of Nice. In the year 1582 the annual error of 11 minutes and 12 seconds had amounted to 10 days, which, by order of Pope Gregory XIII, was supplied in the calendar, and the 5th of October reckoned as the 15th. To prevent repetition of this error, it was decided to leave out three of the inserted days every 400 years, and to make this omission in the years which are not divisible by 400. Thus, of the years 1700, 1800, 1900 and 2000, all of which are leap-years according to the Julian Calendar, only the last is a leap-year according to the REFORMED or GREGORIAN Calendar. This Reformed Calendar was not adopted by England until 1752, when 11 days were omitted from the calendar. The two calendars are now often called the OLD STYLE and the NEW STYLE. The latter style is now adopted in every Christian country except Russia.

### Circular and Angular Measures

USED FOR MEASURING ANGLES AND ARCS, AND FOR DETERMINING LATITUDE AND LONGITUDE

60 seconds (") = 1 minute (')

60 minutes = 1 degree (°)

360 degrees = 1 circumference (C)

The SECOND is usually subdivided into tenths and hundredths.

A MINUTE of the circumference of the earth is a geographical mile.

The DEGREES of the earth's circumference on a meridian average 69.16 geographical miles.

### The Metric System

The METRIC SYSTEM is a system of weights and measures based upon a unit called a METER.

The METER was intended to be one ten-millionth part of the distance from the equator to either pole, measured on the earth's surface at the level of the sea.

**NAMES** of derived metric denominations are formed by prefixing to the of the primary unit of measure:

Milli, a thousandth  
Centi, a hundredth  
Deci, a tenth  
Deca, ten

Hecto, one hundred  
Kilo, a thousand  
Myria, ten thousand

The system, first adopted by France, has been extensively adopted by other countries, and is much used in the sciences and the arts. It was legalized in 1875 by Congress to be used in the United States, and is already employed by the Coast Survey, and, to some extent, by the Mint and the General Post-Office.

## Linear Measures

The **METER** is the primary unit of lengths.

10 millimeters (mm)	= 1 centimeter (cm)	= 0.3937 inch
10 centimeters	= 1 decimeter (dm)	= 3.937 inches
10 decimeters	= 1 METER (m)	= 39.37 inches
10 meters	= 1 decameter	= 393.7 inches
10 decameters	= 1 hectometer	= 328 feet 1 inch
10 hectometers	= 1 KILOMETER (km)	= 0.62137 mile
10 kilometers	= 1 myriameter	= 6.2137 miles

The **METER** is used in ordinary measurements; the **CENTIMETER**, or **MILLIMETER**, in reckoning very small distances; and the **KILOMETER**, for roads or long distances.

A **CENTIMETER** is about  $\frac{1}{2}$  of an inch; a **METER** is about 3 feet  $3\frac{1}{4}$  inches; a **KILOMETER** is about 200 rods, or  $\frac{1}{2}$  of a mile. (See page 33.)

## Measures of Surface

The **SQUARE METER** is the primary unit of ordinary surfaces.

The **ARE**, a square, each of whose sides is ten **METERS**, is the unit of land measurement.

10 square millimeters (mm <sup>2</sup> )	= 1 square centimeter (cm <sup>2</sup> )	= 0.155 square inch
10 square centimeters	= 1 square decimeter	= 15.5 square inches
10 square decimeters	= 1 square METER (m <sup>2</sup> )	= 1 550 square inches, or 1.196 square yards
100 ares, or square meters	= 1 ARE (a)	= 119.6 square yards
100 ares	= 1 hectare (ha)	= 2.471 acres

A **SQUARE METER**, or one **CENTIARE**, is about  $10\frac{1}{4}$  square feet, or  $1\frac{1}{4}$  square yards, and a **HECTARE** is about  $2\frac{1}{4}$  acres.

## Cubic Measure

The **CUBIC METER**, or **STERE**, is the primary unit of a volume.

1000 cubic millimeters (mm <sup>3</sup> )	= 1 cubic centimeter (cm <sup>3</sup> )	= 0.061 cubic inch
1000 cubic centimeters	= 1 cubic decimeter (dm <sup>3</sup> )	= 61.022 cubic inches
1000 cubic decimeters	= 1 cubic METER (m <sup>3</sup> )	= 35.314 cubic feet

The **STERE** is the name given to the cubic meter in measuring wood and timber. One-tenth of a stere is a **DECISTERE**, and ten steres are a **DECASTERE**.

A **CUBIC METER**, or **STERE**, is about  $1\frac{1}{4}$  cubic yards, or about  $2\frac{1}{4}$  cord feet.

### Liquid and Dry Measures

The **LITER** is the primary unit of measures of capacity, and is a cube, whose edges is a tenth of a meter in length.

The **HECTOLITER** is the unit in measuring large quantities of grain roots and liquids.

10 milliliters (ml)	= 1 centiliter (cl)	= 0.338 fluid ounce
10 centiliters	= 1 deciliter	= 0.845 liquid gill
10 deciliters	= 1 LITER (l)	= 1.0567 liquid quarts
10 liters	= 1 decaliter	= 2.6417 gallons
10 decaliters	= 1 HECTOLITER (hl)	= 2 bushels, 3.35 pecks
10 hectoliters	= 1 kiloliter	= 28 bushels, 1½ pecks

A **CENTILITER** is about  $\frac{1}{8}$  of a fluid ounce; a **LITER** is about  $1\frac{1}{8}$  liquid or  $\frac{9}{10}$  of a dry quart; a **HECTOLITER** is about  $2\frac{1}{2}$  bushels; and a **KILO** one cubic meter, or stere.

### Weights

The **GRAM** is the primary unit of weights, and is the weight in a vacuum cubic centimeter of distilled water at the temperature of  $39.2^{\circ}$  F.

10 milligrams (mg)	= 1 centigram (cg)	= 0.1543 troy grain
10 centigrams	= 1 decigram (dg)	= 1.543 troy grains
10 decigrams	= 1 GRAM (g)	= 15.432 troy grains
10 grams	= 1 decagram	= 0.3527 avoirdupois ounce
10 decagrams	= 1 hectogram	= 3.5274 avoirdupois ounce
10 hectograms	= 1 KILOGRAM (kg)	= 2.2046 avoirdupois pound
10 kilograms	= 1 myriagram	= 22.046 avoirdupois pound
10 myriagrams	= 1 quintal (q)	= 220.46 avoirdupois pound
10 quintals	= 1 TONNEAU (t)	= 2204.6 avoirdupois pound
1 kilogram per kilometer	= 0.67195 pound per 1 000 feet	
1 pound per thousand feet	= 1.4882 kilograms per kilometer	
1 kilogram per square millimeter	= 1 423 pounds per square inch	
1 pound per square inch	= 0.000743 kilogram per square millimeter	

The **GRAM** is used in weighing gold, jewels, letters and small quantities of things. The **KILOGRAM**, or, for brevity, **KILO**, is used by grocers; and the **TONNEAU**, or **METRIC TON**, is used in finding the weight of very heavy articles.

A **GRAM** is about  $15\frac{1}{4}$  grains troy; the **KILO** about  $2\frac{1}{4}$  pounds avoirdupois; and the **METRIC TON**, about 2 205 pounds.

A **KILO** is the weight of a liter of water at its greatest density; and the **METRIC TON**, of a cubic meter of water.

Metric numbers are written with the decimal point (.) at the right of the figures denoting the unit; thus the expression, 15 meters 3 centimeters, is written, 15.03 m.

When metric numbers are expressed by figures, the part of the expression to the left of the decimal point is read as the number of the unit, and the part to the right, if any, as a number of the lowest denomination indicated, or as the decimal part of the unit; thus, 46.525 m is read 46 meters and 525 millimeters, or 46 and 525 thousandths meters.

In writing and reading metric numbers, according as the scale is 10, 100, or 1 000, each denomination should be allowed one, two or three orders of figures.

### Metric Conversion Table

The following metric conversion table has been compiled by C. W. Jones, and is most convenient in dealing with metric weights and measures:

Meters $\times 0.03937$	= inches
Meters $\div 25.4$	= inches
Centimeters $\times 0.3937$	= inches
Centimeters $\div 2.54$	= inches
Meters $\times 39.37$	= inches (Act of Congress)
Meters $\times 3.281$	= feet
Meters $\times 1.094$	= yards
Kilometers $\times 0.621$	= miles
Kilometers $\div 1.6093$	= miles
Kilometers $\times 3280.7$	= feet
Square millimeters $\times 0.0155$	= square inches
Square millimeters $\div 645.1$	= square inches
Square centimeters $\times 0.155$	= square inches
Square centimeters $\div 6.451$	= square inches
Square meters $\times 10.764$	= square feet
Square kilometers $\times 247.1$	= acres
Hectares $\times 2.471$	= acres
Cubic centimeters $\div 16.383$	= cubic inches
Cubic centimeters $\div 3.69$	= fluid drachms (U.S. Pharmacopœia)
Cubic centimeters $\div 29.57$	= fluid ounce. (U.S. Pharmacopœia)
Cubic meters $\times 35.315$	= cubic feet
Cubic meters $\times 1.308$	= cubic yards
Cubic meters $\times 264.2$	= gallons (231 cubic inches)
Liters $\times 61.022$	= cubic inches. (Act of Congress)
Liters $\times 33.84$	= fluid ounces. (U.S. Pharmacopœia)
Liters $\times 0.2642$	= gallons (231 cubic inches)
Liters $\div 3.78$	= gallons (231 cubic inches)
Liters $\div 28.316$	= cubic feet
Hectoliters $\times 3.531$	= cubic feet
Hectoliters $\times 2.84$	= bushels (2 150.42 cubic inches)
Hectoliters $\times 0.131$	= cubic yards
Hectoliters $\times 26.42$	= gallons (231 cubic inches)
Grams $\times 15.432$	= grains. (Act of Congress)
Grams $\times 981$	= dynes
Grams (water) $\div 29.57$	= fluid ounces
Grams $\div 28.35$	= ounces avoirdupois
Grams per cubic centimeter $\div 27.7$	= pounds per cubic inch
Pole $\times 0.7373$	= foot-pounds
Kilograms $\times 2.2046$	= pounds
Kilograms $\times 35.3$	= ounces avoirdupois
Kilograms $\div 1102.3$	= tons (2 000 pounds)
Kilograms per sq cm $\times 14.223$	= pounds per square inch
Kilogram-meters $\times 7.233$	= foot-pounds
Kilograms per meter $\times 0.672$	= pounds per square foot
Kilograms per cubic meter $\times 0.062$	= pounds per cubic foot
Kilograms per cheval-vapeur $\times 2.235$	= pounds per horse-power
Kilowatts $\times 1.34$	= horse-power
Watts $\div 746$	= horse-power
Watts $\times 0.7373$	= foot-pounds per second
Calorie $\times 3.968$	= British thermal units (B.T.U.)
Cheval-vapeur $\times 0.9863$	= horse-power
(Centigrade $\times 1.8$ ) $\div 32$	= degrees Fahrenheit
Francs $\times 0.193$	= dollars
Gravity, Paris	= 980.94 centimeter per second

**Metric Conversion Tables.** This and the following table from Worth's Metrical Tables will be found of great convenience in figures to be executed in Mexico and other countries using the metric system.

### Feet Converted into Meters

Feet	0	1	2	3	
0	.....	0.304794	0.609589	0.914383	
10	3.047945	3.35274	3.65753	3.96233	
20	6.095890	6.40068	6.70548	7.01027	
30	9.143835	9.44863	9.75342	10.0582	1
40	12.19178	12.4966	12.8014	13.1062	1
50	15.23972	15.5445	15.8493	16.1541	1
60	18.28767	18.5925	18.8973	19.2020	1
70	21.33561	21.6404	21.9452	22.2500	2
80	24.38356	24.6884	24.9931	25.2979	2
90	27.43150	27.7363	28.0411	28.3459	2

### Scripture and Ancient Measures and Weights

#### Scripture Long Measures

	Inches		Feet	Inches
Digit	= 0.912	Cubit	= 1	9.8
Palm	= 3.648	Fathom	= 7	3.5
Span	= 10.944			

#### Egyptian Long Measures

Nahud cubit = 1 foot 5.71 inches      Royal cubit = 1 foot 8.66 inches

#### Grecian Long Measures

	Feet	Inches		Feet
Digit	=	0.7554	Stadium	= 604
Pous (foot)	= 1	0.0875	Mile	= 4 835
Cubit	= 1	1.598436		

#### Jewish Long Measures

Cubit = 1.824 feet      Mile = 7 296 feet  
Sabbath-day's journey = 3 648 feet      Day's journey = 33.164 miles

#### Roman Long Measures

	Inches		Feet	Inches
Digit	= 0.72575	Cubit	= 1	5.
Uncia (inch)	= 0.967	Passus	= 4	10.
Pes (foot)	= 11.604	Mille (millarium)	= 4 842	

#### Roman Weight

Ancient libra = 0.7094 pound

#### Miscellaneous

	Feet		Feet
Arabian foot	= 1.095	Hebrew foot	= 1.095
Babylonian foot	= 1.140	Hebrew cubit	= 1.140
Egyptian finger	= 0.06145	Hebrew sacred cubit	= 2.06145



# Metric Conversion Tables

## Feet Converted into Meters (Continued)

5	6	7	8	9
1.52397	1.82877	2.13356	2.43836	2.74316
4.57192	4.87671	5.18151	5.48630	5.79110
7.61988	7.92468	8.22945	8.53425	8.83905
10.6678	10.9726	11.2774	11.5822	11.8870
13.7158	14.0205	14.3253	14.6301	14.9349
16.7637	17.0685	17.3733	17.6781	17.9829
19.8116	20.1164	20.4212	20.7260	21.0308
22.8596	23.1644	23.4692	23.7740	24.0788
25.9075	26.2123	26.5171	26.8219	27.1297
28.9555	29.2603	29.5651	29.8699	30.1747

ex. 44 ft = 13.411 meters = 134.11 decimeters = 1341.1 centimeters = 13411 millimeters

above-mentioned work contains eighty pages of conversion tables similar

## Inches and Sixteenths Converted into Millimeters

	0	1	2	3	4	5
.....	.....	25.400	50.799	76.199	101.60	127.00
1/16	1.5875	26.987	52.387	77.786	103.19	128.58
1/8	3.1749	28.574	53.974	79.374	104.77	130.16
3/16	4.7624	30.162	55.561	80.961	106.36	131.75
1/4	6.3499	31.749	57.149	82.549	107.95	133.33
5/16	7.9374	33.337	58.736	84.136	109.54	134.92
3/8	9.5248	34.924	60.324	85.723	111.12	136.50
7/16	11.112	36.512	61.911	87.311	112.71	138.09
1/2	12.700	38.099	63.499	88.898	114.30	139.68
9/16	14.287	39.687	65.086	90.486	115.89	141.26
5/8	15.875	41.274	66.674	92.073	117.47	142.85
11/16	17.462	42.862	68.261	93.661	119.06	144.43
3/4	19.050	44.449	69.849	95.248	120.65	146.02
7/8	20.637	46.037	71.436	96.836	122.24	147.60
15/16	22.225	47.624	73.024	98.423	123.82	149.19
1	23.812	49.212	74.611	100.01	125.41	150.78

	6	7	8	9	10	11
.....	152.40	177.80	203.20	228.60	254.00	279.40
1 1/16	153.98	179.38	204.78	230.18	255.58	280.98
1 1/8	155.57	180.97	206.37	231.77	257.17	282.57
1 3/16	157.16	182.56	207.96	233.36	258.76	284.16
1 1/4	158.75	184.15	209.55	234.95	260.35	285.75
1 5/16	160.33	185.73	211.13	236.53	261.93	287.33
1 3/8	161.92	187.32	212.72	238.12	263.52	288.92
1 7/16	163.51	188.91	214.31	239.71	265.11	290.51
1 1/2	165.10	190.50	215.90	241.30	266.70	292.10
1 9/16	166.68	192.08	217.48	242.88	268.28	293.68
1 5/8	168.27	193.67	219.07	244.47	269.87	295.27
1 11/16	169.86	195.26	220.66	246.06	271.46	296.86
1 3/4	171.45	196.85	222.25	247.65	273.05	298.45
1 7/8	173.03	198.43	223.83	249.23	274.63	300.03
1 15/16	174.62	200.02	225.42	250.82	276.22	301.62
2	176.21	201.61	227.01	252.41	277.81	303.21

to convert inches to meters, move the decimal point THREE figures forward.

ex. 8 3/16 inches = 207.96 millimeters = 20.796 centimeters = 2.0796 meters.

### 3. GEOMETRY AND MENSURATION

#### Definitions

A **POINT** is that which has only position.

A **PLANE** is a surface in which, any two points being taken, the straight line joining them will be wholly in the surface.

A **CURVED LINE** is a line of which no part is straight (Fig. 1).




Fig. 1. Curved Line



Fig. 2. Parallel Lines




Fig. 3. Angles

**PARALLEL LINES** are such as are wholly in the same plane, and have the same direction (Fig. 2).

A **BROKEN LINE** is a line composed of a series of dashes; thus, — — — —

An **ANGLE** is the opening between two lines meeting at a point, and a **RIGHT ANGLE** when the two lines are perpendicular to each other, an **ACUTE ANGLE** when it is less or sharper than a right angle, and an **OBTUSE ANGLE** when it is greater than a right angle. Thus, in Fig. 3,

*A A A A* are ACUTE ANGLES,

*o o o o* are OBTUSE ANGLES and *R R R R* are RIGHT ANGLES.

#### Polygons

A **POLYGON** is a portion of a plane bounded by straight lines.

A **TRIANGLE** is a polygon of three sides.

A **SCALENE TRIANGLE** has none of its sides equal; an **ISOSCELES TRIANGLE** has two of its sides equal; an **EQUILATERAL TRIANGLE** has all three of its sides equal.




Fig. 4. Right-angled Triangle



Fig. 5. Scalene Triangle




Fig. 6. Isosceles Triangle




Fig. 7. Equilateral Triangle

A **RIGHT-ANGLED TRIANGLE** is one which has a right angle. The side opposite the right angle is called the **HYPOTHENUSE**; the side on which the triangle is supposed to stand is called its **BASE** and the other side, its **ALTITUDE**.

**QUADRILATERAL** is a polygon of four sides.

Quadrilaterals are divided into classes, as follows: the **TRAPEZIUM** (Fig. 8), which has no two of its sides parallel; the **TRAPEZOID** (Fig. 9), which has two of its sides parallel; and the **PARALLELOGRAM** (Fig. 10), which is bounded by two sets of parallel sides.




Fig. 8. Trapezium




Fig. 9. Trapezoid



Fig. 10. Parallelogram

A parallelogram whose sides are not equal and whose angles are not right angles is called a **RHOMBOID** (Fig. 11); when the sides are all equal, but the angles are not right angles, it is called a **RHOMBUS** (Fig. 12), and when the angles are right angles, it is called a **RECTANGLE** (Fig. 13). A rectangle, all of whose sides are equal, is called a **SQUARE** (Fig. 14). Polygons, all of whose sides are equal, are called **REGULAR POLYGONS**.



Fig. 11.  
Rhomboid




Fig. 12.  
Rhombus



Fig. 13  
Rectangle




Fig. 14.  
Square

Besides the square and equilateral triangles, there are: the **PENTAGON** (Fig. 15), which has five sides; the **HEXAGON** (Fig. 16), which has six sides; the **HEPTAGON** (Fig. 17), which has seven sides; and the **OCTAGON** (Fig. 18), which has eight sides.




Fig. 15.  
Pentagon




Fig. 16.  
Hexagon




Fig. 17.  
Heptagon




Fig. 18.  
Octagon

The **ENNEAGON** or **NONAGON** has nine sides; the **DECAGON** has ten sides; and the **DODECAGON** has twelve sides.

For all polygons, the side upon which it is supposed to stand is called its **BASE**; the perpendicular distance from the highest side or angle to the base (measured, if necessary) is called the **ALTITUDE**; and a line joining any two non-adjacent vertices is called a **DIAGONAL**.

The **PERIMETER** is the bounding line of a plane figure.

A **CIRCLE** is a portion of a plane bounded by a curve, all the points of which are equidistant from a point within, called the **CENTER** (Fig. 19).

The **CIRCUMFERENCE** is the curve which bounds the circle.

A **RADIUS** is any straight line drawn from the center to the circumference.

A straight line drawn through the center to the circumference on each side is called a **DIAMETER**.

An **ARC** of a circle is any part of its circumference.




Fig. 19. Circle and Parts

A **CHORD** is any straight line joining points of the circumference, as *bd*, Fig. 19.

A **SEGMENT** is a portion of the circle included between the arc and its chord, as *A*, Fig. 19.

A **SECTOR** is the space included between an arc and two radii drawn to its extremities, as *B*, Fig. 19. In the figure, *ab* is a radius, *cd* a diameter and *bd* a chord subtending the arc *bcd*. A **TANGENT** is a straight line which in passing a curve does not cut it, as *fg*, Fig. 19.

### Volumes

A **PRISM** is a volume whose ends are equal and parallel polygons and whose sides are parallelograms.

A prism is **TRIANGULAR**, **RECTANGULAR**, etc., according as its ends are triangles, rectangles, etc.

A **CUBE** is a rectangular prism all of whose sides are squares.

A **CYLINDER** is a volume of uniform diameter, bounded by a curved surface and two equal and opposite parallel circles.

A **PYRAMID** is a volume whose base is a polygon and whose sides are triangles meeting in a point called the **VERTEX**. A pyramid is **triangular**, **quadrangular**, etc., according as its base is a triangle, quadrilateral, etc.

A **CONE** is a volume whose base is a circle, from which the remaining surface tapers uniformly to a point or vertex (Fig. 20).

A **CONIC SECTION** is the plane figure made by a plane cutting a cone.

An **ELLIPSE** is the section of a cone cut by a plane passing obliquely through both sides, as at *ab*, Fig. 21.

A **PARABOLA** is a section of a cone cut by a plane parallel to its side, as at *cd*.

A **HYPERBOLA** is a section of a cone cut by a plane making an angle greater with the base than that made by the side of the cone, as at *eh*.

In the ellipse, the **TRANSVERSE AXIS**, or **LONG DIAMETER**, is the longest that can be drawn in it. The **CONJUGATE AXIS**, or **SHORT DIAMETER**, is drawn through the center at right-angles to the long diameter.

A **FRUSTUM OF A PYRAMID OR CONE** is that which remains after cutting off the upper part of it by a plane parallel to the base.

A **SPHERE** is a volume bounded by a curved surface, all points of which are equidistant from a point within, called the center.

**Mensuration** treats of the measurement of lines, surfaces and volumes.

### Rules

To compute the area of a square, a rectangle, a rhombus or a rhomboid.

**Rule.** Multiply the length by the breadth or height. Thus, in Figs. 23 or 24, the area =  $ab \times bc$ .



Fig. 20.  
Cone

Fig. 21.  
Cone with Section




Fig. 22. Square




Fig. 23. Rectangle




Fig. 24. Parallelogram

to compute the area of a triangle.

1. Multiply the base by the altitude and divide by 2. Thus, in Fig. 25,

$$\text{area of } abc = \frac{ab \times cd}{2}$$

2. Find the length of the hypotenuse of a right-angled triangle when both sides are known.

3. Square the length of each of the sides making the right angle, add the squares together and take the square root of their sum. Thus (Fig. 26), length of  $ac = 3$ , and of  $bc = 4$ ; then




$$ab = \sqrt{3^2 + 4^2} = \sqrt{9 + 16} = \sqrt{25}$$

$$\sqrt{25} = 5, \text{ or } ab = 5$$

4. Find the length of the base or altitude of a right-angled triangle when length of the hypotenuse and one side is known.

5. From the square of the length of the hypotenuse subtract the square of the length of the other side and take the square root of the remainder.

6. Find the area of a trapezium (Fig. 27).


Fig. 25.  
Scalene Triangle

Fig. 26.  
Right-angled Triangle

Fig. 27.  
Trapezium

7. Multiply the diagonal by the sum of the two perpendiculars falling on it from the opposite angles and divide the product by 2. Thus,

$$\frac{ab \times (ce + di)}{2} = \text{area}$$

8. Find the area of a trapezoid (Fig. 28).

9. Multiply the sum of the two parallel sides by the perpendicular distance between them and divide the product by 2.

10. Compute the area of an irregular polygon.

11. Divide the polygon into triangles by means of diagonal lines and then add together the areas of all the triangles, as A, B and C (Fig. 29).

To find the area of a regular polygon.

Rule. Multiply the length of a side by the perpendicular distance from center (as *ao*, Fig. 30), multiply that product by the number of sides and the result by 2.




Fig. 28. Trapezoid




Fig. 29. Irregular Polygon




Fig. 30. Regular Poly

To compute the area of a regular polygon when the length, only, of is given.

Rule. Multiply the square of the side by the multiplier opposite the number of the polygon in column *A* of the following table:

Table of Factors for Determining the Elements of Polygons

Name of polygon	Number of sides	A Factor for area	B Factor for radius of circumscribing circle	C Factor for length of the sides	D Factor for radius of inscribed circle
Triangle.....	3	0.433013	0.5773	1.732	0.288675
Tetragon.....	4	1	0.7071	1.4142	0.5
Pentagon.....	5	1.720477	0.8506	1.1756	0.618034
Hexagon.....	6	2.598076	1	1	0.866025
Heptagon.....	7	3.633912	1.1524	0.8677	1.000000
Octagon.....	8	4.823427	1.3066	0.7653	1.207107
Nonagon.....	9	6.181824	1.4619	0.684	1.376382
Decagon.....	10	7.694209	1.618	0.618	1.532089
Undecagon.....	11	9.36564	1.7747	0.5634	1.701302
Dodecagon.....	12	11.196152	1.9319	0.5176	1.871826

To compute the radius of a circle circumscribed about a regular polygon when the length, only, of a side is given.

Rule. Multiply the length of a side of the polygon by the number in column *B* of table.

Example. What is the radius of a circle that will contain a hexagon the length of one side being 5 in?

Solution.  $5 \times 1 = 5$  in.

To compute the length of a side of a regular polygon inscribed in a circle, when the radius of the circle is given.

Rule. Multiply the radius of the circle by the number opposite the name of the polygon in column *C* of table.

Example. What is the length of the side of a pentagon contained in a circle 8 ft in diameter?

Solution.  $8 \text{ ft diameter} \div 2 = 4 \text{ ft radius}; 4 \times 1.1756 = 4.7024 \text{ ft.}$

**To compute the length of a side of a regular polygon, when the radius of the inscribed circle is given.**

**Rule.** Divide the radius of the inscribed circle by the number opposite the name of the polygon in column *D* of table.

**To compute the radius of a circle that can be inscribed in a given regular polygon, when the length of a side is given.**

**Rule.** Multiply the length of a side of the polygon by the number opposite the name of the polygon in column *D*.

**Example.** What is the radius of the circle that can be inscribed in an octagon, the length of one side being 6 in?

**Solution.**  $6 \times 1.2071 = 7.2426$  in.

## Circles

**To compute the circumference of a circle.**

**Rule.** Multiply the diameter by 3.1416. For many purposes, the multiplier 3 gives sufficiently accurate results.

**Example.** What is the circumference of a circle 7 in in diameter?

**Solution.**  $7 \times 3.1416 = 21.9912$  in, or  $7 \times 3\frac{1}{4} = 22$  in, the error in this last being 0.0088 in.

**To find the diameter of a circle when the circumference is given.**

**Rule.** Divide the circumference by 3.1416, or for a very close approximate result, multiply by 7 and divide by 22.

**To find the radius of an arc when the chord and rise or versed sine are given.**

**Rule.** Square ONE-HALF the CHORD and the RISE; add the sum of these squares by twice the rise; the result will be the radius.

**Example.** The length of the chord *ac*, Fig. 31, is 48 in, and the rise, *bo*, is 6 in. What is the radius of the arc?




Fig. 31. Circular Arc, Chord and Rise

**Solution.** Radius =  $\frac{ac^2 + bo^2}{2bo} = \frac{24^2 + 6^2}{12} = 51$  in

**To find the rise or versed sine of a circular arc, when the chord and radius are given.**

**Rule.** Square the radius; also square one-half the chord; subtract the latter from the former and take the square root of the remainder. Subtract the result from the radius and the remainder will be the rise.

**Example.** A given arc has a radius of 51 in and a chord of 48 in. What is the rise?

**Solution.** Rise = radius -  $\sqrt{\text{radius}^2 - \frac{1}{4}\text{chord}^2} = 51 - \sqrt{2601 - 576} = 51 - 45 = 6$  in = rise

**To compute the area of a circle.**

**Rule.** Multiply the square of the diameter by 0.7854, or multiply the square of the radius by 3.1416.

**Example.** What is the area of a circle 10 in in diameter?

**Solution.**  $10 \times 10 \times 0.7854 = 78.54$  sq in, or  $5 \times 5 \times 3.1416 = 78.54$  sq in.

## Tables of Areas and Circumferences of Circles

The following tables will be found very convenient for finding the circumferences and areas of circles.

## Areas and Circumferences of Circles

For diameters from  $\frac{1}{10}$  to 100, advancing by tenths

Dia.	Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circum.
0.0			5.0	19.6350	15.7080	10.0	78.5398	31.4159
.1	0.007854	0.31416	.1	20.4282	16.0221	.1	80.1185	31.7310
.2	0.031416	0.62832	.2	21.2372	16.3363	.2	81.7128	32.0461
.3	0.070686	0.94248	.3	22.0618	16.6504	.3	83.3229	32.3612
.4	0.12566	1.2566	.4	22.9022	16.9646	.4	84.9487	32.6763
.5	0.19635	1.5708	.5	23.7583	17.2788	.5	86.5901	32.9914
.6	0.28274	1.8850	.6	24.6301	17.5929	.6	88.2473	33.3065
.7	0.38485	2.1991	.7	25.5176	17.9071	.7	89.9202	33.6216
.8	0.50266	2.5133	.8	26.4208	18.2212	.8	91.6088	33.9367
.9	0.63617	2.8274	.9	27.3397	18.5354	.9	93.3132	34.2518
1.0	0.7854	3.1416	6.0	28.2743	18.8496	11.0	95.0332	34.5669
.1	0.9503	3.4558	.1	29.2247	19.1637	.1	96.7689	34.8820
.2	1.1310	3.7699	.2	30.1907	19.4779	.2	98.5203	35.1971
.3	1.3273	4.0841	.3	31.1725	19.7920	.3	100.2875	35.5122
.4	1.5394	4.3982	.4	32.1699	20.1062	.4	102.0703	35.8273
.5	1.7671	4.7124	.5	33.1831	20.4204	.5	103.8689	36.1424
.6	2.0106	5.0265	.6	34.2119	20.7345	.6	105.6832	36.4575
.7	2.2698	5.3407	.7	35.2565	21.0437	.7	107.5132	36.7726
.8	2.5447	5.6549	.8	36.3168	21.3523	.8	109.3588	37.0877
.9	2.8353	5.9690	.9	37.3928	21.6770	.9	111.2202	37.4028
2.0	3.1416	6.2832	7.0	38.4845	21.9911	12.0	113.0973	37.7179
.1	3.4636	6.5973	.1	39.5919	22.3053	.1	114.9901	38.0330
.2	3.8013	6.9115	.2	40.7150	22.6195	.2	116.8987	38.3481
.3	4.1548	7.2257	.3	41.8539	22.9336	.3	118.8229	38.6632
.4	4.5239	7.5398	.4	43.0084	23.2478	.4	120.7628	38.9783
.5	4.9087	7.8540	.5	44.1786	23.5619	.5	122.7185	39.2934
.6	5.3093	8.1681	.6	45.3646	23.8761	.6	124.6898	39.6085
.7	5.7256	8.4823	.7	46.5663	24.1903	.7	126.6769	39.9236
.8	6.1575	8.7965	.8	47.7836	24.5044	.8	128.6796	40.2387
.9	6.6052	9.1106	.9	49.0167	24.8186	.9	130.6981	40.5538
3.0	7.0686	9.4248	8.0	50.2655	25.1327	13.0	132.7323	40.8689
.1	7.5477	9.7389	.1	51.5300	25.4469	.1	134.7822	41.1840
.2	8.0425	10.0531	.2	52.8102	25.7611	.2	136.8478	41.4991
.3	8.5530	10.3673	.3	54.1061	26.0752	.3	138.9291	41.8142
.4	9.0792	10.6814	.4	55.4177	26.3894	.4	141.0261	42.1293
.5	9.6211	10.9956	.5	56.7450	26.7035	.5	143.1388	42.4444
.6	10.1788	11.3097	.6	58.0880	27.0177	.6	145.2672	42.7595
.7	10.7521	11.6239	.7	59.4468	27.3319	.7	147.4114	43.0746
.8	11.3411	11.9381	.8	60.8212	27.6460	.8	149.5712	43.3897
.9	11.9459	12.2522	.9	62.2114	27.9602	.9	151.7468	43.7048
4.0	12.5664	12.5664	9.0	63.6173	28.2743	14.0	153.9380	44.0199
.1	13.2025	12.8805	.1	65.0388	28.5885	.1	156.1450	44.3350
.2	13.8544	13.1947	.2	66.4761	28.9027	.2	158.3677	44.6501
.3	14.5220	13.5088	.3	67.9291	29.2168	.3	160.6061	44.9652
.4	15.2053	13.8230	.4	69.3978	29.5310	.4	162.8602	45.2803
.5	15.9043	14.1372	.5	70.8822	29.8451	.5	165.1300	45.5954
.6	16.6190	14.4513	.6	72.3823	30.1593	.6	167.4155	45.9105
.7	17.3494	14.7655	.7	73.8981	30.4734	.7	169.7167	46.2256
.8	18.0956	15.0796	.8	75.4296	30.7876	.8	172.0336	46.5407
.9	18.8574	15.3938	.9	76.9769	31.1018	.9	174.3662	46.8558



## Areas and Circumferences of Circles (Continued)

Advancing by tenths

Di.	Area	Circum.	Di.	Area	Circum.	Di.	Area	Circum.
19.0	178.7144	47.1239	20.0	314.1593	62.8319	25.0	490.8739	78.5398
1	179.0796	47.4380	.1	317.3087	63.1460	.1	491.8097	78.8540
2	181.4584	47.7522	.2	320.4739	63.4602	.2	498.7592	79.1681
3	183.8339	48.0664	.3	323.6547	63.7743	.3	502.7255	79.4823
4	186.2060	48.3805	.4	326.8513	64.0885	.4	506.7075	79.7965
5	188.6019	48.6947	.5	330.0636	64.4026	.5	510.7052	80.1106
6	191.1345	49.0088	.6	333.2916	64.7168	.6	514.7185	80.4248
7	193.5929	49.3230	.7	336.5353	65.0310	.7	518.7476	80.7389
8	196.0668	49.6372	.8	339.7947	65.3451	.8	522.7924	81.0531
9	198.5565	49.9513	.9	343.0698	65.6593	.9	526.8529	81.3672
20.0	301.0619	50.2655	21.0	346.3606	65.9734	26.0	530.9292	81.6814
1	303.5831	50.5796	.1	349.6671	66.2876	.1	535.0211	81.9956
2	306.1199	50.8938	.2	352.9894	66.6018	.2	539.1287	82.3097
3	308.6721	51.2080	.3	356.3273	66.9159	.3	543.2521	82.6239
4	311.2407	51.5221	.4	359.6809	67.2301	.4	547.3911	82.9380
5	313.8246	51.8363	.5	363.0503	67.5442	.5	551.5459	83.2522
6	316.4243	52.1504	.6	366.4354	67.8584	.6	555.7163	83.5664
7	319.0397	52.4646	.7	369.8361	68.1726	.7	559.9025	83.8806
8	321.6708	52.7788	.8	373.2526	68.4867	.8	564.1044	84.1947
9	324.3176	53.0929	.9	376.6848	68.8009	.9	568.3220	84.5088
21.0	329.9801	53.4071	22.0	380.1327	69.1150	27.0	572.5553	84.8230
1	329.6583	53.7212	.1	383.5963	69.4292	.1	576.8043	85.1372
2	332.3522	54.0354	.2	387.0756	69.7434	.2	581.0690	85.4513
3	335.0618	54.3496	.3	390.5707	70.0575	.3	585.3494	85.7655
4	337.7871	54.6637	.4	394.0814	70.3717	.4	589.6455	86.0796
5	340.5282	54.9779	.5	397.6078	70.6858	.5	593.9574	86.3938
6	343.2849	55.2920	.6	401.1500	71.0000	.6	598.2849	86.7080
7	346.0574	55.6062	.7	404.7078	71.3142	.7	602.6282	87.0221
8	348.8456	55.9203	.8	408.2814	71.6283	.8	606.9871	87.3363
9	351.6494	56.2345	.9	411.8707	71.9425	.9	611.3618	87.6504
22.0	354.4690	56.5486	23.0	415.4756	72.2566	28.0	615.7522	87.9646
1	357.3043	56.8628	.1	419.0963	72.5708	.1	620.1582	88.2788
2	360.1553	57.1770	.2	422.7327	72.8849	.2	624.5800	88.5929
3	363.0220	57.4911	.3	426.3848	73.1991	.3	629.0175	88.9071
4	365.9044	57.8053	.4	430.0520	73.5133	.4	633.4707	89.2212
5	368.8025	58.1195	.5	433.7361	73.8274	.5	637.9397	89.5354
6	371.7164	58.4336	.6	437.4354	74.1416	.6	642.4248	89.8495
7	374.6459	58.7478	.7	441.1503	74.4557	.7	646.9246	90.1637
8	377.5911	59.0619	.8	444.8809	74.7699	.8	651.4407	90.4779
9	380.5521	59.3761	.9	448.6273	75.0841	.9	655.9724	90.7920
23.0	383.5267	59.6903	24.0	452.3893	75.3982	29.0	660.5199	91.1062
1	386.5211	60.0044	.1	456.1671	75.7124	.1	665.0830	91.4203
2	389.5292	60.3186	.2	459.9606	76.0265	.2	669.6519	91.7345
3	392.5530	60.6327	.3	463.7698	76.3407	.3	674.2565	92.0487
4	395.5925	60.9469	.4	467.5947	76.6549	.4	678.8668	92.3628
5	398.6477	61.2611	.5	471.4352	76.9690	.5	683.4928	92.6770
6	401.7196	61.5752	.6	475.2916	77.2832	.6	688.1345	92.9911
7	404.8083	61.8894	.7	479.1630	77.5973	.7	692.7919	93.3053
8	407.9075	62.2035	.8	483.0513	77.9115	.8	697.4650	93.6195
9	411.0258	62.5177	.9	486.9547	78.2257	.9	702.1538	93.9336

## Areas and Circumferences of Circles (Continued)

Advancing by tenths

Dia.	Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circum.
30.0	706.8583	94.2478	35.0	962.1128	109.9557	40.0	1256.6371	125.6637
.1	711.5786	94.5019	.1	967.6184	110.2099	.1	1262.9281	125.9178
.2	716.3145	94.8761	.2	973.1397	110.5841	.2	1269.2348	126.1719
.3	721.0662	95.1903	.3	978.6768	110.8982	.3	1275.5573	126.4260
.4	725.8336	95.5044	.4	984.2296	111.2124	.4	1281.8955	126.6801
.5	730.6167	95.8186	.5	989.7980	111.5205	.5	1288.2493	126.9342
.6	735.4154	96.1327	.6	995.3822	111.8407	.6	1294.6189	127.1883
.7	740.2299	96.4469	.7	1000.9821	112.1549	.7	1301.0042	127.4424
.8	745.0601	96.7611	.8	1006.5977	112.4690	.8	1307.4052	127.6965
.9	749.9060	97.0752	.9	1012.2290	112.7832	.9	1313.8219	127.9506
31.0	754.7676	97.3894	36.0	1017.8760	113.0973	41.0	1320.2543	128.2047
.1	759.6450	97.7035	.1	1023.5387	113.4115	.1	1326.7024	128.4588
.2	764.5380	98.0177	.2	1029.2172	113.7257	.2	1333.1663	128.7129
.3	769.4437	98.3319	.3	1034.9113	114.0398	.3	1339.6458	128.9670
.4	774.3712	98.6460	.4	1040.6212	114.3540	.4	1346.1410	129.2211
.5	779.3113	98.9602	.5	1046.3467	114.6681	.5	1352.6520	129.4752
.6	784.2672	99.2743	.6	1052.0880	114.9823	.6	1359.1786	129.7293
.7	789.2368	99.5885	.7	1057.8449	115.2965	.7	1365.7210	129.9834
.8	794.2200	99.9026	.8	1063.6176	115.6106	.8	1372.2791	130.2375
.9	799.2290	100.2168	.9	1069.4060	115.9248	.9	1378.8529	130.4916
32.0	804.2477	100.5310	37.0	1075.2101	116.2389	42.0	1385.4424	130.7457
.1	809.2921	100.8451	.1	1081.0299	116.5531	.1	1392.0476	131.0000
.2	814.3322	101.1593	.2	1086.8654	116.8672	.2	1398.6685	131.2541
.3	819.3980	101.4734	.3	1092.7166	117.1814	.3	1405.3051	131.5082
.4	824.4796	101.7876	.4	1098.5835	117.4956	.4	1411.9574	131.7623
.5	829.5768	102.1018	.5	1104.4662	117.8097	.5	1418.6254	132.0164
.6	834.6898	102.4159	.6	1110.3645	118.1239	.6	1425.3092	132.2705
.7	839.8185	102.7301	.7	1116.2786	118.4380	.7	1432.0086	132.5246
.8	844.9623	103.0442	.8	1122.2083	118.7522	.8	1438.7238	132.7787
.9	850.1229	103.3584	.9	1128.1538	119.0664	.9	1445.4546	133.0328
33.0	855.2986	103.6726	38.0	1134.1149	119.3805	43.0	1452.2012	133.2869
.1	860.4902	103.9867	.1	1140.0918	119.6947	.1	1458.9635	133.5410
.2	865.6973	104.3009	.2	1146.0844	120.0088	.2	1465.7415	133.7951
.3	870.9202	104.6150	.3	1152.0927	120.3230	.3	1472.5352	134.0492
.4	876.1588	104.9292	.4	1158.1167	120.6372	.4	1479.3446	134.3033
.5	881.4131	105.2434	.5	1164.1564	120.9513	.5	1486.1697	134.5574
.6	886.6831	105.5575	.6	1170.2118	121.2655	.6	1493.0105	134.8115
.7	891.9688	105.8717	.7	1176.2830	121.5796	.7	1499.8670	135.0656
.8	897.2703	106.1858	.8	1182.3698	121.8938	.8	1506.7398	135.3197
.9	902.5874	106.5000	.9	1188.4724	122.2080	.9	1513.6272	135.5738
34.0	907.9203	106.8142	39.0	1194.5906	122.5221	44.0	1520.5308	135.8279
.1	913.2688	107.1283	.1	1200.7246	122.8363	.1	1527.4502	136.0820
.2	918.6331	107.4425	.2	1206.8742	123.1504	.2	1534.3853	136.3361
.3	924.0131	107.7566	.3	1213.0396	123.4646	.3	1541.3360	136.5902
.4	929.4088	108.0708	.4	1219.2207	123.7788	.4	1548.3025	136.8443
.5	934.8202	108.3849	.5	1225.4175	124.0929	.5	1555.2847	137.0984
.6	940.2473	108.6991	.6	1231.6300	124.4071	.6	1562.2826	137.3525
.7	945.6901	109.0133	.7	1237.8582	124.7212	.7	1569.2962	137.6066
.8	951.1486	109.3274	.8	1244.1021	125.0354	.8	1576.3255	137.8607
.9	956.6228	109.6416	.9	1250.3617	125.3495	.9	1583.3706	138.1148

## Areas and Circumferences of Circles (Continued)

Advancing by tenths

Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circum.
1500.4313	141.3717	50.0	1968.4954	157.0796	55.0	2375.8294	172.7876
1507.5077	141.6858	.1	1971.3572	157.8938	.1	2384.4767	173.1017
1504.5899	142.0000	.2	1979.2348	157.7080	.2	2393.1396	173.4159
1511.7677	142.3142	.3	1987.1280	158.0221	.3	2401.8183	173.7301
1518.8313	142.6283	.4	1995.0370	158.3363	.4	2410.5126	174.0442
1525.9705	142.9425	.5	2002.9617	158.6504	.5	2419.2227	174.3584
1533.1255	143.2566	.6	2010.9020	158.9646	.6	2427.9485	174.6726
1540.2062	143.5708	.7	2018.8581	159.2787	.7	2436.6899	174.9867
1547.4826	143.8849	.8	2026.8299	159.5929	.8	2445.4471	175.3009
1554.9847	144.1991	.9	2034.8174	159.9071	.9	2454.2200	175.6150
1561.9025	144.5133	51.0	2042.8206	160.2212	56.0	2463.0086	175.9292
1569.1360	144.8274	.1	2050.8396	160.5354	.1	2471.8130	176.2433
1576.3853	145.1416	.2	2058.8742	160.8495	.2	2480.6330	176.5575
1583.6502	145.4557	.3	2066.9245	161.1637	.3	2489.4687	176.8717
1590.9308	145.7699	.4	2074.9905	161.4779	.4	2498.3201	177.1858
1598.2272	146.0841	.5	2083.0723	161.7920	.5	2507.1873	177.5000
1605.5392	146.3982	.6	2091.1697	162.1062	.6	2516.0701	177.8141
1612.8670	146.7124	.7	2099.2829	162.4203	.7	2524.9687	178.1283
1620.2105	147.0265	.8	2107.4118	162.7345	.8	2533.8830	178.4425
1627.5697	147.3407	.9	2115.5563	163.0487	.9	2542.8129	178.7566
1634.9445	147.6550	52.0	2123.7168	163.3628	57.0	2551.7586	179.0708
1642.3351	147.9690	.1	2131.8926	163.6770	.1	2560.7200	179.3849
1649.7414	148.2832	.2	2140.0843	163.9911	.2	2569.6971	179.6991
1657.1635	148.5973	.3	2148.2917	164.3053	.3	2578.6899	180.0133
1664.6012	148.9115	.4	2156.5149	164.6195	.4	2587.6985	180.3274
1672.0546	149.2257	.5	2164.7537	164.9336	.5	2596.7227	180.6416
1679.5237	149.5398	.6	2173.0082	165.2479	.6	2605.7626	180.9557
1687.0086	149.8540	.7	2181.2785	165.5619	.7	2614.8183	181.2699
1694.5091	150.1681	.8	2189.5644	165.8761	.8	2623.8896	181.5841
1702.0254	150.4823	.9	2197.8661	166.1903	.9	2632.9767	181.8982
1709.5574	150.7964	53.0	2206.1834	166.5044	58.0	2642.0794	182.2124
1717.1050	151.1106	.1	2214.5165	166.8186	.1	2651.1979	182.5265
1724.6684	151.4248	.2	2222.8653	167.1327	.2	2660.3321	182.8407
1732.2475	151.7389	.3	2231.2298	167.4469	.3	2669.4820	183.1549
1739.8423	152.0531	.4	2239.6100	167.7610	.4	2678.6476	183.4690
1747.4528	152.3672	.5	2248.0059	168.0752	.5	2687.8289	183.7832
1755.0790	152.6814	.6	2256.4175	168.3894	.6	2697.0259	184.0973
1762.7210	152.9956	.7	2264.8448	168.7035	.7	2706.2386	184.4115
1770.3786	153.3097	.8	2273.2879	169.0177	.8	2715.4670	184.7256
1778.0519	153.6239	.9	2281.7466	169.3318	.9	2724.7112	185.0398
1785.7409	153.9380	54.0	2290.2210	169.6460	59.0	2733.9710	185.3540
1793.4457	154.2522	.1	2298.7112	169.9602	.1	2743.2466	185.6681
1801.1662	154.5664	.2	2307.2171	170.2743	.2	2752.5378	185.9823
1808.9024	154.8805	.3	2315.7386	170.5885	.3	2761.8448	186.2964
1816.6543	155.1947	.4	2324.2759	170.9026	.4	2771.1675	186.6106
1824.4218	155.5088	.5	2332.8289	171.2168	.5	2780.5058	186.9248
1832.2051	155.8230	.6	2341.3976	171.5310	.6	2789.8599	187.2389
1840.0042	156.1372	.7	2349.9820	171.8451	.7	2799.2297	187.5531
1847.8189	156.4513	.8	2358.5821	172.1593	.8	2808.6152	187.8672
1855.6493	156.7655	.9	2367.1979	172.4735	.9	2818.0165	188.1814

## Areas and Circumferences of Circles

For diameters from  $\frac{1}{10}$  to 100, advancing by tenths

Dia.	Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circum.
0.0			5.0	19.6350	15.7080	10.0	78.5398	31.4159
.1	0.007854	0.31416	.1	20.4282	16.0221	.1	80.1185	31.7301
.2	0.031416	0.62832	.2	21.2372	16.3363	.2	81.7128	32.0442
.3	0.070686	0.94248	.3	22.0618	16.6504	.3	83.3229	32.3584
.4	0.12566	1.2566	.4	22.9022	16.9646	.4	84.9487	32.6726
.5	0.19635	1.5708	.5	23.7583	17.2788	.5	86.5901	32.9867
.6	0.28274	1.8850	.6	24.6301	17.5929	.6	88.2473	33.3009
.7	0.38485	2.1991	.7	25.5176	17.9071	.7	89.9202	33.6150
.8	0.50266	2.5133	.8	26.4208	18.2212	.8	91.6088	33.9292
.9	0.63617	2.8274	.9	27.3397	18.5354	.9	93.3132	34.2434
1.0	0.7854	3.1416	6.0	28.2743	18.8496	11.0	95.0332	34.5575
.1	0.9503	3.4558	.1	29.2247	19.1637	.1	96.7689	34.8717
.2	1.1310	3.7699	.2	30.1907	19.4779	.2	98.5203	35.1858
.3	1.3273	4.0841	.3	31.1725	19.7920	.3	100.2875	35.5000
.4	1.5394	4.3982	.4	32.1699	20.1062	.4	102.0703	35.8142
.5	1.7671	4.7124	.5	33.1831	20.4204	.5	103.8689	36.1283
.6	2.0106	5.0265	.6	34.2119	20.7345	.6	105.6832	36.4425
.7	2.2698	5.3407	.7	35.2565	21.0487	.7	107.5132	36.7566
.8	2.5447	5.6549	.8	36.3168	21.3628	.8	109.3588	37.0708
.9	2.8353	5.9690	.9	37.3928	21.6770	.9	111.2202	37.3850
2.0	3.1416	6.2832	7.0	38.4845	21.9911	12.0	113.0973	37.6991
.1	3.4636	6.5973	.1	39.5919	22.3053	.1	114.9901	38.0133
.2	3.8013	6.9115	.2	40.7150	22.6195	.2	116.8987	38.3274
.3	4.1548	7.2257	.3	41.8539	22.9336	.3	118.8229	38.6416
.4	4.5239	7.5398	.4	43.0084	23.2478	.4	120.7628	38.9557
.5	4.9087	7.8540	.5	44.1786	23.5619	.5	122.7185	39.2699
.6	5.3093	8.1681	.6	45.3646	23.8761	.6	124.6898	39.5841
.7	5.7256	8.4823	.7	46.5663	24.1903	.7	126.6769	39.8982
.8	6.1575	8.7965	.8	47.7836	24.5044	.8	128.6796	40.2124
.9	6.6052	9.1106	.9	49.0167	24.8186	.9	130.6981	40.5265
3.0	7.0686	9.4248	8.0	50.2655	25.1327	13.0	132.7323	40.8407
.1	7.5477	9.7389	.1	51.5300	25.4469	.1	134.7822	41.1549
.2	8.0425	10.0531	.2	52.8102	25.7611	.2	136.8478	41.4690
.3	8.5530	10.3673	.3	54.1061	26.0752	.3	138.9291	41.7832
.4	9.0792	10.6814	.4	55.4177	26.3894	.4	141.0261	42.0973
.5	9.6211	10.9956	.5	56.7450	26.7035	.5	143.1388	42.4115
.6	10.1788	11.3097	.6	58.0890	27.0177	.6	145.2672	42.7257
.7	10.7521	11.6239	.7	59.4468	27.3319	.7	147.4114	43.0398
.8	11.3411	11.9381	.8	60.8212	27.6460	.8	149.5712	43.3540
.9	11.9459	12.2522	.9	62.2114	27.9602	.9	151.7468	43.6681
4.0	12.5664	12.5664	9.0	63.6173	28.2743	14.0	153.9380	43.9823
.1	13.2025	12.8805	.1	65.0388	28.5885	.1	156.1450	44.2965
.2	13.8544	13.1947	.2	66.4761	28.9027	.2	158.3677	44.6106
.3	14.5220	13.5088	.3	67.9291	29.2168	.3	160.6061	44.9248
.4	15.2053	13.8230	.4	69.3978	29.5310	.4	162.8602	45.2389
.5	15.9043	14.1372	.5	70.8822	29.8451	.5	165.1300	45.5531
.6	16.6190	14.4513	.6	72.3923	30.1593	.6	167.4153	45.8672
.7	17.3494	14.7655	.7	73.9181	30.4734	.7	169.7167	46.1814
.8	18.0956	15.0796	.8	75.4596	30.7876	.8	172.0336	46.4956
.9	18.8574	15.3938	.9	76.9769	31.1018	.9	174.3662	46.8097

## Areas and Circumferences of Circles (Continued)

Advancing by tenths

Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circum.
4417.6647	235.6194	80.0	5026.5482	251.3274	85.0	5674.5017	267.0354
4428.6533	235.9336	.1	5039.1225	251.6416	.1	5687.5814	267.3495
4441.4580	236.2478	.2	5051.7124	251.9557	.2	5701.2367	267.6637
4453.7783	236.5619	.3	5064.3150	252.2699	.3	5714.6277	267.9779
4465.1142	236.8761	.4	5076.9394	252.5840	.4	5728.0345	268.2920
4476.9659	237.1902	.5	5089.5764	252.8982	.5	5741.4569	268.6062
4486.9332	237.5044	.6	5102.2292	253.2124	.6	5754.8951	268.9203
4500.7163	237.8186	.7	5114.8977	253.5265	.7	5768.3490	269.2345
4512.6151	238.1327	.8	5127.5819	253.8407	.8	5781.8185	269.5486
4524.5296	238.4469	.9	5140.2818	254.1548	.9	5795.3038	269.8628
4536.4596	238.7610	81.0	5152.9973	254.4690	86.0	5808.8048	270.1770
4543.4057	239.0752	.1	5165.7267	254.7832	.1	5822.3215	270.4911
4560.3673	239.3894	.2	5178.4757	255.0973	.2	5835.8539	270.8053
4572.3446	239.7035	.3	5191.2384	255.4115	.3	5849.4020	271.1194
4584.3377	240.0177	.4	5204.0168	255.7256	.4	5862.9659	271.4336
4596.3464	240.3318	.5	5216.8110	256.0398	.5	5876.5454	271.7478
4608.3705	240.6460	.6	5229.6208	256.3540	.6	5890.1407	272.0619
4620.4110	240.9602	.7	5242.4463	256.6681	.7	5903.7516	272.3761
4632.4669	241.2743	.8	5255.2876	256.9823	.8	5917.3783	272.6902
4644.5284	241.5885	.9	5268.1446	257.2966	.9	5931.0206	273.0044
4656.6257	241.9026	82.0	5281.0173	257.6106	87.0	5944.6787	273.3186
4666.7257	242.2168	.1	5293.9056	257.9247	.1	5958.3525	273.6327
4680.5474	242.5310	.2	5306.8097	258.2389	.2	5972.0420	273.9469
4692.9818	242.8451	.3	5319.7295	258.5531	.3	5985.7472	274.2610
4705.1319	243.1592	.4	5332.6650	258.8672	.4	5999.4681	274.5752
4717.2977	243.4734	.5	5345.6162	259.1814	.5	6013.2047	274.8894
4729.4792	243.7876	.6	5358.5832	259.4956	.6	6026.9570	275.2035
4741.6755	244.1017	.7	5371.5658	259.8097	.7	6040.7250	275.5177
4753.8894	244.4159	.8	5384.5641	260.1239	.8	6054.5098	275.8318
4766.1181	244.7301	.9	5397.5782	260.4380	.9	6068.3082	276.1460
4778.3624	245.0442	83.0	5410.6079	260.7522	88.0	6082.1234	276.4602
4790.6225	245.3584	.1	5423.6534	261.0663	.1	6095.9542	276.7743
4802.9983	245.6725	.2	5436.7146	261.3805	.2	6109.8008	277.0885
4815.1897	245.9867	.3	5449.7915	261.6947	.3	6123.6631	277.4026
4827.4969	246.3009	.4	5462.8840	262.0088	.4	6137.5411	277.7168
4839.8198	246.6150	.5	5475.9923	262.3230	.5	6151.4348	278.0309
4852.1584	246.9292	.6	5489.1163	262.6371	.6	6165.3442	278.3451
4864.5128	247.2433	.7	5502.2561	262.9513	.7	6179.2693	278.6593
4876.8828	247.5575	.8	5515.4115	263.2655	.8	6193.2101	278.9740
4889.2685	247.8717	.9	5528.5826	263.5796	.9	6207.1666	279.2878
4901.5699	248.1858	84.0	5541.7694	263.8938	89.0	6221.1389	279.6017
4914.0871	248.5000	.1	5554.9720	264.2079	.1	6235.1268	279.9159
4926.5199	248.8141	.2	5568.1902	264.5221	.2	6249.1304	280.2301
4938.9685	249.1283	.3	5581.4242	264.8363	.3	6263.1498	280.5442
4951.4328	249.4425	.4	5594.6739	265.1514	.4	6277.1849	280.8584
4963.9127	249.7566	.5	5607.9392	265.4646	.5	6291.2356	281.1725
4976.4084	250.0708	.6	5621.2203	265.7787	.6	6305.3021	281.4867
4988.9198	250.3850	.7	5634.5171	266.0929	.7	6319.3843	281.8009
5001.4469	250.6991	.8	5647.8296	266.4071	.8	6333.4822	282.1150
5013.9897	251.0133	.9	5661.1578	266.7212	.9	6347.5958	282.4292

## Areas and Circumferences of Circles (Continued)

Advancing by tenths

Dia.	Area	Circum.	Dia.	Area	Circum.	Dia.	Area	Circ.
90.0	6361.7251	282.7433	93.5	6666.1471	293.7369	97.0	7339.8118	304.
.1	6375.8701	283.0575	.6	6680.2419	294.0531	.1	7405.0659	305.
.2	6390.0309	283.2717	.7	6695.5524	294.3372	.2	7420.8102	305.
.3	6404.2073	283.6858	.8	6910.2786	294.6814	.3	7435.5922	305.
.4	6418.3995	284.0000	.9	6925.0205	294.9956	.4	7450.8839	305.
.5	6432.6073	284.3141	94.0	6939.7762	295.3097	.5	7466.1913	306.
.6	6446.8309	284.6283	.1	6954.5515	295.6239	.6	7481.5144	306.
.7	6461.0701	284.9425	.2	6969.3106	295.9380	.7	7496.8532	306.
.8	6475.3251	285.2566	.3	6984.1453	296.2522	.8	7512.2078	307.
.9	6489.5958	285.5708	.4	6998.9658	296.5663	.9	7527.5780	307.
91.0	6503.8822	285.8849	.5	7013.8019	296.8805	98.0	7542.9640	307.
.1	6518.1843	286.1991	.6	7028.6538	297.1947	.1	7558.3656	308.
.2	6532.5021	286.5133	.7	7043.5214	297.5088	.2	7573.7830	308.
.3	6546.8356	286.8274	.8	7058.4047	297.8230	.3	7589.2161	308.
.4	6561.1848	287.1416	.9	7073.3033	298.1371	.4	7604.6648	309.
.5	6575.5498	287.4557	95.0	7098.2184	298.4513	.5	7620.1293	309.
.6	6589.9304	287.7699	.1	7103.1488	298.7655	.6	7635.6095	309.
.7	6604.3268	288.0840	.2	7118.1950	299.0796	.7	7651.1054	310.
.8	6618.7388	288.3982	.3	7133.0568	299.3938	.8	7666.6170	310.
.9	6633.1666	288.7124	.4	7148.0343	299.7079	.9	7682.1444	310.
92.0	6647.6101	289.0265	.5	7163.0276	300.0221	99.0	7697.6893	311.
.1	6662.0692	289.3407	.6	7178.0366	300.3363	.1	7713.2461	311.
.2	6676.5441	289.6548	.7	7193.0612	300.6504	.2	7728.8206	311.
.3	6691.0347	289.9690	.8	7208.1016	300.9646	.3	7744.4107	311.
.4	6705.5410	290.2832	.9	7223.1577	301.2787	.4	7760.0166	312.
.5	6720.0630	290.5973	96.0	7238.2295	301.5929	.5	7775.6382	312.
.6	6734.6008	290.9115	.1	7253.3170	301.9071	.6	7791.2754	312.
.7	6749.1542	291.2256	.2	7268.4202	302.2212	.7	7806.9284	313.
.8	6763.7233	291.5398	.3	7283.5391	302.5354	.8	7822.5971	313.
.9	6778.3082	291.8540	.4	7298.6737	302.8495	.9	7838.2815	313.
93.0	6792.9087	292.1681	.5	7313.8240	303.1637	100.0	7853.9816	314.
.1	6807.5250	292.4823	.6	7328.9901	303.4779			
.2	6822.1560	292.7964	.7	7344.1718	303.7920			
.3	6836.8046	293.1106	.8	7359.3693	304.1062			
.4	6851.4680	293.4248	.9	7374.5824	304.4203			

**Areas of Circles**  
**Advancing by eighths**  
**AREAS**

	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7
0	0.0	0.0122	0.0490	0.1104	0.1963	0.3068	0.4417	0.6013
1	0.7854	0.9940	1.237	1.484	1.767	2.073	2.405	2.761
2	3.1416	3.546	3.976	4.430	4.908	5.411	5.939	6.491
3	7.068	7.669	8.295	8.946	9.621	10.32	11.04	11.79
4	12.56	13.36	14.18	15.03	15.90	16.80	17.72	18.66
5	19.63	20.62	21.64	22.69	23.75	24.85	25.96	27.10
6	28.27	29.46	30.67	31.91	33.18	34.47	35.78	37.12
7	38.48	39.87	41.28	42.71	44.17	45.66	47.17	48.70
8	50.26	51.84	53.45	55.08	56.74	58.42	60.13	61.86
9	63.61	65.39	67.20	69.02	70.88	72.75	74.66	76.58
10	78.54	80.51	82.51	84.54	86.59	88.66	90.76	92.88
11	95.03	97.20	99.40	101.6	103.8	106.1	108.4	110.7
12	113.0	115.4	117.8	120.2	122.7	125.1	127.6	130.1
13	132.7	135.2	137.8	140.5	143.1	145.8	148.4	151.2
14	153.9	156.6	159.4	162.2	165.1	167.9	170.8	173.7
15	176.7	179.6	182.6	185.6	188.6	191.7	194.8	197.9
16	201.0	204.2	207.3	210.5	213.8	217.0	220.3	223.6
17	226.9	230.3	233.7	237.1	240.5	243.9	247.4	250.9
18	254.4	258.0	261.5	265.1	268.8	272.4	276.1	279.8
19	283.5	287.2	291.0	294.8	298.6	302.4	306.3	310.2
20	314.1	318.1	322.0	326.0	330.0	334.1	338.1	342.2
21	346.3	350.4	354.6	358.8	363.0	367.2	371.5	375.8
22	380.1	384.4	388.8	393.2	397.6	402.0	406.4	410.9
23	415.4	420.0	424.5	429.1	433.7	438.2	443.0	447.6
24	452.3	457.1	461.8	466.6	471.4	476.2	481.1	485.9
25	490.9	495.7	500.7	505.7	510.7	515.7	520.7	525.8
26	530.9	536.0	541.1	546.3	551.5	556.7	562.0	567.2
27	572.5	577.8	583.2	588.5	593.9	599.3	604.8	610.2
28	615.7	621.2	626.7	632.3	637.9	643.5	649.1	654.8
29	660.5	666.2	671.9	677.7	683.4	689.2	695.1	700.9
30	704.3	712.7	718.6	724.6	730.6	736.6	742.6	748.6
31	754.8	760.9	767.0	773.1	779.3	785.5	791.7	798.0
32	804.3	810.6	816.9	823.2	829.6	836.0	842.4	848.8
33	855.3	861.8	868.3	874.9	881.4	888.0	894.6	901.3
34	907.9	914.7	921.3	928.1	934.8	941.6	948.4	955.3
35	962.1	969.0	975.9	982.8	989.8	996.8	1003.8	1010.8
36	1017.9	1025.0	1032.1	1039.2	1046.3	1053.5	1060.7	1068.0
37	1075.2	1082.5	1089.8	1097.1	1104.5	1111.8	1119.2	1126.7
38	1134.1	1141.6	1149.1	1156.6	1164.2	1171.7	1179.3	1186.9
39	1194.6	1202.3	1210.0	1217.7	1225.4	1233.2	1241.0	1248.8
40	1256.6	1264.5	1272.4	1280.3	1288.2	1296.2	1304.2	1312.2
41	1320.3	1328.3	1336.4	1344.5	1352.7	1360.8	1369.0	1377.2
42	1385.4	1393.7	1402.0	1410.3	1418.6	1427.0	1435.4	1443.8
43	1452.2	1460.7	1469.1	1477.6	1486.2	1494.7	1503.3	1511.9
44	1520.5	1529.2	1537.9	1546.6	1555.3	1564.0	1572.8	1581.6
45	1590.4	1599.3	1608.2	1617.0	1626.0	1634.9	1643.9	1652.9

## Circumferences of Circles

Advancing by eighths

## CIRCUMFERENCES

Dia.	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0
0	0.0	0.3927	0.7854	1.178	1.570	1.963	2.356	2.
1	3.141	3.534	3.927	4.319	4.712	5.105	5.497	5.
2	6.283	6.675	7.068	7.461	7.854	8.246	8.639	9.
3	9.424	9.817	10.21	10.60	10.99	11.38	11.78	12.
4	12.56	12.95	13.35	13.74	14.13	14.52	14.92	15.
5	15.70	16.10	16.49	16.88	17.27	17.67	18.06	18.
6	18.84	19.24	19.63	20.02	20.42	20.81	21.20	21.
7	21.99	22.38	22.77	23.16	23.56	23.95	24.34	24.
8	25.13	25.52	25.91	26.31	26.70	27.09	27.48	27.
9	28.27	28.66	29.05	29.45	29.84	30.23	30.63	31.
10	31.41	31.80	32.20	32.59	32.98	33.37	33.77	34.
11	34.55	34.95	35.34	35.73	36.12	36.52	36.91	37.
12	37.69	38.09	38.48	38.87	39.27	39.66	40.05	40.
13	40.84	41.23	41.62	42.01	42.41	42.80	43.19	43.
14	43.98	44.37	44.76	45.16	45.55	45.94	46.33	46.
15	47.12	47.51	47.90	48.30	48.69	49.08	49.48	49.
16	50.26	50.65	51.05	51.44	51.83	52.22	52.62	53.
17	53.40	53.79	54.19	54.58	54.97	55.37	55.76	56.
18	56.54	56.94	57.33	57.72	58.11	58.51	58.90	59.
19	59.69	60.08	60.47	60.86	61.25	61.65	62.04	62.
20	62.83	63.22	63.61	64.01	64.40	64.79	65.18	65.
21	65.97	66.36	66.75	67.15	67.54	67.93	68.32	68.
22	69.11	69.50	69.90	70.29	70.68	71.07	71.47	71.
23	72.25	72.64	73.04	73.43	73.82	74.22	74.61	75.
24	75.39	75.79	76.18	76.57	76.96	77.36	77.75	78.
25	78.54	78.93	79.32	79.71	80.10	80.50	80.89	81.
26	81.68	82.07	82.46	82.85	83.25	83.64	84.03	84.
27	84.82	85.21	85.60	86.00	86.39	86.78	87.17	87.
28	87.96	88.35	88.75	89.14	89.53	89.92	90.32	90.
29	91.10	91.49	91.89	92.28	92.67	93.06	93.46	93.
30	94.24	94.64	95.03	95.42	95.81	96.21	96.60	96.
31	97.39	97.78	98.17	98.57	98.96	99.35	99.75	100.
32	100.53	100.92	101.32	101.71	102.10	102.49	102.89	103.
33	103.67	104.07	104.46	104.85	105.24	105.64	106.03	106.
34	106.81	107.21	107.60	107.99	108.39	108.78	109.17	109.
35	109.96	110.35	110.74	111.13	111.53	111.92	112.31	112.
36	113.10	113.49	113.88	114.28	114.67	115.06	115.45	115.
37	116.24	116.63	117.02	117.42	117.81	118.20	118.60	118.
38	119.38	119.77	120.17	120.56	120.95	121.34	121.74	122.
39	122.52	122.92	123.31	123.70	124.09	124.49	124.88	125.
40	125.66	126.06	126.45	126.84	127.24	127.63	128.02	128.
41	128.81	129.20	129.59	129.98	130.38	130.77	131.16	131.
42	131.95	132.34	132.73	133.13	133.52	133.91	134.30	134.
43	135.09	135.48	135.87	136.27	136.66	137.05	137.45	137.
44	138.23	138.62	139.02	139.41	139.80	140.19	140.59	140.
45	141.37	141.76	142.16	142.55	142.94	143.34	143.73	144.



## Areas and Circumferences of Circles

FROM 1 TO 50 FEET

Advancing by one inch

ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in
0	0.7854	3 1 <sup>5</sup> / <sub>8</sub>	5 0	19.635	15 8 <sup>1</sup> / <sub>2</sub>	9 0	63.6174	28 2 <sup>1</sup> / <sub>4</sub>
1	0.9217	3 4 <sup>3</sup> / <sub>8</sub>	1	20.2047	15 11 <sup>5</sup> / <sub>8</sub>	1	64.8006	28 6 <sup>3</sup> / <sub>8</sub>
2	1.089	3 8	2	20.9656	16 2 <sup>3</sup> / <sub>4</sub>	2	65.9951	28 9 <sup>1</sup> / <sub>2</sub>
3	1.2771	3 11	3	21.6475	16 5 <sup>3</sup> / <sub>4</sub>	3	67.2007	29 5 <sup>5</sup> / <sub>8</sub>
4	1.4902	4 2 <sup>1</sup> / <sub>8</sub>	4	22.34	16 9	4	68.4166	29 3 <sup>3</sup> / <sub>4</sub>
5	1.7261	4 5 <sup>3</sup> / <sub>8</sub>	5	23.0437	17 1 <sup>5</sup> / <sub>8</sub>	5	69.644	29 7
6	1.9871	4 8 <sup>1</sup> / <sub>2</sub>	6	23.7583	17 3 <sup>1</sup> / <sub>4</sub>	6	70.8823	29 10 <sup>1</sup> / <sub>8</sub>
7	1.9689	4 11 <sup>5</sup> / <sub>8</sub>	7	24.4835	17 6 <sup>3</sup> / <sub>8</sub>	7	72.1309	30 1 <sup>1</sup> / <sub>4</sub>
8	2.1516	5 2 <sup>3</sup> / <sub>4</sub>	8	25.2199	17 9 <sup>5</sup> / <sub>8</sub>	8	73.391	30 4 <sup>3</sup> / <sub>8</sub>
9	2.4052	5 5 <sup>7</sup> / <sub>8</sub>	9	25.9672	18 3 <sup>1</sup> / <sub>4</sub>	9	74.662	30 7 <sup>1</sup> / <sub>2</sub>
10	2.6398	5 9	10	26.7251	18 5 <sup>5</sup> / <sub>8</sub>	10	75.9433	30 11 <sup>5</sup> / <sub>8</sub>
11	2.8552	6 1 <sup>1</sup> / <sub>4</sub>	11	27.4943	18 7 <sup>1</sup> / <sub>8</sub>	11	77.2362	31 1 <sup>3</sup> / <sub>4</sub>
0	3.1416	6 3 <sup>3</sup> / <sub>4</sub>	6 0	28.2744	18 10 <sup>1</sup> / <sub>8</sub>	10 0	78.54	31 5
1	3.4367	6 6 <sup>1</sup> / <sub>2</sub>	1	29.0649	19 1 <sup>1</sup> / <sub>4</sub>	1	79.854	31 8 <sup>1</sup> / <sub>8</sub>
2	3.6552	6 9 <sup>5</sup> / <sub>8</sub>	2	29.8668	19 4 <sup>3</sup> / <sub>8</sub>	2	81.1795	31 11 <sup>1</sup> / <sub>4</sub>
3	3.978	7 3 <sup>1</sup> / <sub>4</sub>	3	30.6736	19 7 <sup>1</sup> / <sub>2</sub>	3	82.516	32 2 <sup>3</sup> / <sub>8</sub>
4	4.278	7 3 <sup>7</sup> / <sub>8</sub>	4	31.5029	19 10 <sup>5</sup> / <sub>8</sub>	4	83.8627	32 5 <sup>1</sup> / <sub>2</sub>
5	4.5969	7 7	5	32.3376	20 1 <sup>7</sup> / <sub>8</sub>	5	85.2211	32 8 <sup>3</sup> / <sub>8</sub>
6	4.9087	7 10 <sup>1</sup> / <sub>4</sub>	6	33.1831	20 4 <sup>7</sup> / <sub>8</sub>	6	86.5903	32 11 <sup>3</sup> / <sub>4</sub>
7	5.2413	8 1 <sup>3</sup> / <sub>8</sub>	7	34.0391	20 8 <sup>1</sup> / <sub>4</sub>	7	87.9607	33 2 <sup>7</sup> / <sub>8</sub>
8	5.585	8 4 <sup>1</sup> / <sub>2</sub>	8	34.9065	20 11 <sup>1</sup> / <sub>2</sub>	8	89.3608	33 6 <sup>1</sup> / <sub>8</sub>
9	5.9325	8 7 <sup>5</sup> / <sub>8</sub>	9	35.7847	21 2 <sup>3</sup> / <sub>8</sub>	9	90.7627	33 9 <sup>1</sup> / <sub>4</sub>
10	6.2449	8 10 <sup>3</sup> / <sub>4</sub>	10	36.6735	21 5 <sup>1</sup> / <sub>2</sub>	10	92.1749	34 3 <sup>5</sup> / <sub>8</sub>
11	6.6113	9 1 <sup>7</sup> / <sub>8</sub>	11	37.5736	21 8 <sup>3</sup> / <sub>4</sub>	11	93.5986	34 3 <sup>1</sup> / <sub>4</sub>
0	7.0686	9 5	7 0	38.4846	21 11 <sup>7</sup> / <sub>8</sub>	11 0	95.0334	34 6 <sup>3</sup> / <sub>8</sub>
1	7.4666	9 8 <sup>1</sup> / <sub>4</sub>	1	39.406	22 3	1	96.4783	34 9 <sup>3</sup> / <sub>4</sub>
2	7.8757	9 11 <sup>3</sup> / <sub>8</sub>	2	40.3388	22 6 <sup>1</sup> / <sub>4</sub>	2	97.9347	35 7 <sup>5</sup> / <sub>8</sub>
3	8.2957	10 2 <sup>1</sup> / <sub>2</sub>	3	41.2825	22 9 <sup>1</sup> / <sub>4</sub>	3	99.4021	35 4 <sup>1</sup> / <sub>8</sub>
4	8.7265	10 5 <sup>1</sup> / <sub>8</sub>	4	42.2367	23 3 <sup>5</sup> / <sub>8</sub>	4	100.8797	35 7 <sup>1</sup> / <sub>4</sub>
5	9.1683	10 8 <sup>3</sup> / <sub>4</sub>	5	43.2022	23 6 <sup>3</sup> / <sub>8</sub>	5	102.3689	35 10 <sup>5</sup> / <sub>8</sub>
6	9.6211	10 11 <sup>5</sup> / <sub>8</sub>	6	44.1787	23 9 <sup>1</sup> / <sub>4</sub>	6	103.8691	36 1 <sup>1</sup> / <sub>2</sub>
7	10.0846	11 3	7	45.1656	23 12 <sup>1</sup> / <sub>8</sub>	7	105.3794	36 4 <sup>1</sup> / <sub>8</sub>
8	10.5591	11 6 <sup>1</sup> / <sub>8</sub>	8	46.1638	24 1 <sup>5</sup> / <sub>8</sub>	8	106.9013	36 7 <sup>3</sup> / <sub>4</sub>
9	11.0446	11 9 <sup>5</sup> / <sub>8</sub>	9	47.173	24 4 <sup>3</sup> / <sub>8</sub>	9	108.4342	36 10 <sup>7</sup> / <sub>8</sub>
10	11.5409	12 1 <sup>3</sup> / <sub>2</sub>	10	48.1962	24 7 <sup>1</sup> / <sub>4</sub>	10	109.9772	37 2 <sup>3</sup> / <sub>4</sub>
11	12.0481	12 3 <sup>5</sup> / <sub>8</sub>	11	49.2236	24 10 <sup>3</sup> / <sub>8</sub>	11	111.5319	37 5 <sup>1</sup> / <sub>4</sub>
0	12.5664	12 6 <sup>3</sup> / <sub>4</sub>	8 0	50.2656	25 1 <sup>1</sup> / <sub>2</sub>	12 0	113.0976	37 8 <sup>3</sup> / <sub>8</sub>
1	13.0952	12 9 <sup>7</sup> / <sub>8</sub>	1	51.3178	25 4 <sup>5</sup> / <sub>8</sub>	1	114.6732	37 11 <sup>1</sup> / <sub>2</sub>
2	13.6353	13 1	2	52.3816	25 7 <sup>3</sup> / <sub>8</sub>	2	116.2607	38 2 <sup>5</sup> / <sub>8</sub>
3	14.1862	13 4 <sup>1</sup> / <sub>8</sub>	3	53.4562	25 11	3	117.859	38 5 <sup>3</sup> / <sub>4</sub>
4	14.7479	13 7 <sup>1</sup> / <sub>4</sub>	4	54.5412	26 2 <sup>1</sup> / <sub>8</sub>	4	119.4674	38 8 <sup>7</sup> / <sub>8</sub>
5	15.3206	13 10 <sup>1</sup> / <sub>2</sub>	5	55.6377	26 5 <sup>1</sup> / <sub>4</sub>	5	121.0876	39 0
6	15.9043	14 1 <sup>5</sup> / <sub>8</sub>	6	56.7451	26 8 <sup>3</sup> / <sub>8</sub>	6	122.7187	39 3 <sup>1</sup> / <sub>4</sub>
7	16.4986	14 4 <sup>5</sup> / <sub>8</sub>	7	57.8628	26 11 <sup>1</sup> / <sub>2</sub>	7	124.3598	39 6 <sup>3</sup> / <sub>8</sub>
8	17.1041	14 7 <sup>3</sup> / <sub>8</sub>	8	58.992	27 2 <sup>3</sup> / <sub>4</sub>	8	126.0127	39 9 <sup>1</sup> / <sub>2</sub>
9	17.7205	14 11	9	60.1321	27 5 <sup>3</sup> / <sub>4</sub>	9	127.6765	40 5 <sup>5</sup> / <sub>8</sub>
10	18.3476	15 2 <sup>1</sup> / <sub>8</sub>	10	61.2826	27 9	10	129.3504	40 3 <sup>3</sup> / <sub>4</sub>
11	18.9858	15 5 <sup>1</sup> / <sub>4</sub>	11	62.4445	28 1 <sup>5</sup> / <sub>8</sub>	11	131.036	40 6 <sup>7</sup> / <sub>8</sub>

## Areas and Circumferences of Circles (Continued)

Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circ. ft
132.7326	40 10	18 0	254.4696	56 6½	23 0	415.4766	72
134.4391	41 1½	1	256.8303	56 9½	1	418.4915	72
136.1574	41 4¾	2	259.2033	57 7½	2	421.5192	72
137.8867	41 7½	3	261.5872	57 4	3	424.5577	73
139.626	41 10¾	4	263.9807	57 7½	4	427.6055	73
141.3771	42 1½	5	266.3864	57 10½	5	430.6658	73
143.1391	42 4¾	6	268.8031	58 1¾	6	433.7371	73
144.9111	42 8	7	271.2293	58 4½	7	436.8175	74
146.6949	42 11½	8	273.6678	58 7½	8	439.9106	74
148.4896	43 2¼	9	276.1171	58 10¾	9	443.0146	74
150.2943	43 5½	10	278.5761	59 2	10	446.1278	74
152.1109	43 8½	11	281.0472	59 5½	11	449.2536	75
153.9384	43 11¾	19 0	283.5294	59 8½	24 0	452.3904	75
155.7758	44 2¾	1	286.021	59 11½	1	455.5362	75
157.625	44 6	2	288.5249	60 2½	2	458.6948	75
159.4852	44 9½	3	291.0397	60 5½	3	461.8642	76
161.3553	45 1¼	4	293.5641	60 8¾	4	465.0428	76
163.2373	45 3½	5	296.1107	60 11¾	5	468.2341	76
165.1303	45 6½	6	298.6483	61 3¼	6	471.4363	76
167.0331	45 9¾	7	301.2054	61 6¼	7	474.6476	77
168.9479	46 7½	8	303.7747	61 9½	8	477.8716	77
170.8735	46 4	9	306.355	62 1½	9	481.1065	77
172.8091	46 7½	10	308.9448	62 3½	10	484.3506	78
174.7565	46 11¼	11	311.5469	62 6¾	11	487.6073	78
176.715	47 1½	20 0	314.16	62 9¾	25 0	490.875	78
178.6832	47 4¾	1	316.7824	63 1½	1	494.1516	78
180.6634	47 7¾	2	319.4173	63 4¼	2	497.4411	79
182.6545	47 10¾	3	322.063	63 7¾	3	500.7415	79
184.6555	48 2½	4	324.7182	63 11½	4	504.051	79
186.6684	48 5½	5	327.3858	64 1¾	5	507.3732	79 1
188.6923	48 8¼	6	330.0643	64 4¾	6	510.7063	80
190.726	48 11¾	7	332.7522	64 7¾	7	514.0484	80
192.7716	49 2½	8	335.4525	64 11	8	517.4034	80
194.8282	49 5¾	9	338.1637	65 2¼	9	520.7692	80 1
196.8946	49 8¾	10	340.8844	65 5¾	10	524.1441	81
198.973	50 0	11	343.6174	65 8¾	11	527.5318	81
201.0624	50 3¼	21 0	346.3614	65 11¾	26 0	530.9304	81
203.1615	50 6¼	1	349.1147	66 2¾	1	534.3379	81 1
205.2726	50 9½	2	351.8804	66 5¾	2	537.7583	82
207.3946	51 1½	3	354.6571	66 9	3	541.1896	82
209.5264	51 3¾	4	357.4432	67 1½	4	544.6299	82
211.6703	51 6½	5	360.2417	67 3¾	5	548.083	82 1
213.8251	51 10	6	363.0511	67 6½	6	551.5471	83
215.9896	52 1½	7	365.8698	67 9½	7	555.0201	83
218.1662	52 4¼	8	368.7011	68 3¼	8	558.5059	83
220.3537	52 7¾	9	371.5432	68 7¾	9	562.0027	84
222.551	52 10½	10	374.3947	68 11	10	565.5084	84
224.7608	53 1¾	11	377.2587	68 14¼	11	569.027	84
226.9806	53 4¾	22 0	380.1336	69 1¾	27 0	572.5566	84
229.2105	53 8	1	383.0177	69 4½	1	576.0949	85
231.4525	53 11½	2	385.9144	69 7½	2	579.6463	85
233.7055	54 2¼	3	388.822	69 10¾	3	583.2085	85
235.9682	54 5¾	4	391.7389	70 1¾	4	586.7796	85 1
238.243	54 8½	5	394.6683	70 5	5	590.3637	86
240.5287	54 11½	6	397.6087	70 8¼	6	593.9587	86
242.8241	55 2¾	7	400.5583	70 11½	7	597.5625	86
245.1316	55 6	8	403.5204	71 2½	8	601.1793	86
247.45	55 9½	9	406.4935	71 5½	9	604.807	87
249.7781	56 1¼	10	409.4759	71 8¾	10	608.4436	87
252.1184	56 3½	11	412.4707	71 11¾	11	612.0931	87

## Areas and Circumferences of Circles (Continued)

Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in
615.7536	57 11½	33 0	855.301	103 8	38 0	1134.118	119 4½
629.4238	58 2½	1	859.624	103 11½	1	1139.095	119 7½
643.105	58 5½	2	863.961	104 2½	2	1144.087	119 10¾
656.7962	58 9	3	868.309	104 5½	3	1149.089	120 2
670.5002	59 1½	4	872.665	104 8½	4	1154.110	120 5½
684.2152	59 3½	5	877.035	104 11¾	5	1159.124	120 8¾
697.9411	59 6¾	6	881.415	105 2¾	6	1164.159	120 11¾
711.6758	59 9½	7	885.804	105 6	7	1169.202	121 2½
725.4235	60 5	8	890.206	105 9½	8	1174.259	121 5½
739.1821	60 3¾	9	894.619	106 ¼	9	1179.327	121 8¾
752.9485	60 6¾	10	899.041	106 3¾	10	1184.403	121 11¾
766.73	60 11½	11	903.476	106 6¾	11	1189.493	122 3½
780.5214	61 1½	34 0	907.922	106 9¾	39 0	1194.593	122 6¼
794.3214	61 4¾	1	912.377	107 7½	1	1199.719	122 9½
808.1348	61 7½	2	916.844	107 4	2	1204.824	123 ½
821.9587	61 10½	3	921.323	107 7½	3	1209.958	123 3½
835.7915	62 1¾	4	925.810	107 10¼	4	1215.099	123 6¾
849.6375	62 4½	5	930.311	108 1¾	5	1220.254	123 9¾
863.4943	62 8½	6	934.822	108 4½	6	1225.420	124 1½
877.3598	62 11½	7	939.342	108 7¾	7	1230.594	124 4¼
891.2385	63 2¾	8	943.875	108 10¾	8	1235.782	124 7¾
905.1028	63 5½	9	948.419	109 2	9	1240.981	124 10½
919.0263	63 8½	10	952.972	109 5½	10	1246.188	125 1½
932.9377	63 11½	11	957.538	109 8¼	11	1251.408	125 4¾
706.86	64 2¾	35 0	962.115	109 11¾	40 0	1256.64	125 7¾
710.791	64 6	1	966.770	110 2½	1	1261.879	125 11
714.735	64 9¼	2	971.299	110 5¾	2	1267.133	126 2¼
718.69	65 ¾	3	975.908	110 8¾	3	1272.397	126 5¾
722.654	65 3½	4	980.526	111 0	4	1277.669	126 8½
726.631	65 6½	5	985.158	111 3½	5	1282.955	126 11½
730.616	65 9¼	6	989.803	111 6¼	6	1288.252	127 2¾
734.615	66 7½	7	994.451	111 9¾	7	1293.557	127 5¾
738.624	66 4	8	999.115	112 ½	8	1298.876	127 9
742.645	66 7¼	9	1003.79	112 3¾	9	1304.206	128 ¼
746.674	66 10¾	10	1008.473	112 6¾	10	1309.543	128 3¾
750.716	67 1½	11	1013.170	112 10	11	1314.895	128 6¼
754.769	67 4¾	36 0	1017.878	113 1½	41 0	1320.257	128 9½
758.831	67 7¾	1	1022.594	113 4¼	1	1325.628	129 ¾
762.906	67 10¾	2	1027.324	113 7¾	2	1331.012	129 3¾
766.992	68 2	3	1032.064	113 10½	3	1336.407	129 7
771.088	68 5½	4	1036.813	114 1¾	4	1341.810	129 10¼
775.191	68 8¾	5	1041.576	114 4¾	5	1347.227	130 1¾
779.313	68 11½	6	1046.349	114 8	6	1352.655	130 4½
783.440	69 2½	7	1051.130	114 11½	7	1358.091	130 7½
787.561	69 5¾	8	1055.926	115 2¼	8	1363.541	130 10¾
791.732	69 8¾	9	1060.731	115 5¾	9	1369.001	131 1¾
795.892	100 0	10	1065.546	115 9¼	10	1374.47	131 5
800.065	100 3½	11	1070.374	115 11½	11	1379.952	131 8½
804.25	100 6¾	37 0	1075.2126	116 2¾	42 0	1385.446	131 11¾
808.442	100 9½	1	1080.059	116 6	1	1390.247	132 2½
812.648	101 5	2	1084.920	116 9½	2	1396.462	132 5½
816.865	101 3¾	3	1089.791	117 ¼	3	1401.988	132 8¾
821.090	101 6¾	4	1094.671	117 3½	4	1407.522	132 11¾
825.329	101 10	5	1099.564	117 6½	5	1413.07	133 3
829.579	102 1½	6	1104.460	117 9½	6	1418.629	133 6¼
833.837	102 4¾	7	1109.381	118 ¾	7	1424.195	133 9¼
838.108	102 7½	8	1114.307	118 4	8	1429.776	134 ½
842.391	102 10½	9	1119.244	118 7½	9	1435.367	134 3½
846.681	103 1¾	10	1124.189	118 10¼	10	1440.967	134 6¾
850.985	103 4¾	11	1129.148	119 1¾	11	1446.580	134 9¾

## Circumferences of Circles

Advancing by eighths

## CIRCUMFERENCES

Dia.	0.0	0. $\frac{1}{8}$	0. $\frac{1}{4}$	0. $\frac{3}{8}$	0. $\frac{1}{2}$	0. $\frac{5}{8}$	0. $\frac{3}{4}$	0. $\frac{7}{8}$
0	0.0	0.3927	0.7854	1.178	1.570	1.963	2.356	2.748
1	3.141	3.534	3.927	4.319	4.712	5.105	5.497	5.890
2	6.283	6.675	7.053	7.401	7.854	8.210	8.639	9.032
3	9.424	9.817	10.21	10.60	10.99	11.38	11.78	12.17
4	12.56	12.95	13.35	13.74	14.13	14.52	14.92	15.31
5	15.70	16.10	16.49	16.88	17.27	17.67	18.06	18.45
6	18.84	19.24	19.63	20.02	20.42	20.81	21.20	21.59
7	21.99	22.38	22.77	23.16	23.56	23.95	24.34	24.74
8	25.13	25.52	25.91	26.31	26.70	27.09	27.48	27.88
9	28.27	28.66	29.05	29.45	29.84	30.23	30.63	31.02
10	31.41	31.80	32.20	32.59	32.98	33.37	33.77	34.16
11	34.55	34.95	35.34	35.73	36.12	36.52	36.91	37.30
12	37.69	38.09	38.48	38.87	39.27	39.66	40.05	40.44
13	40.84	41.23	41.62	42.01	42.41	42.80	43.19	43.58
14	43.98	44.37	44.76	45.16	45.55	45.94	46.33	46.72
15	47.12	47.51	47.90	48.30	48.69	49.08	49.48	49.87
16	50.26	50.65	51.05	51.44	51.83	52.22	52.62	53.01
17	53.40	53.79	54.19	54.58	54.97	55.37	55.76	56.15
18	56.51	56.91	57.33	57.72	58.11	58.51	58.90	59.29
19	59.69	60.08	60.47	60.86	61.25	61.65	62.04	62.43
20	62.83	63.22	63.61	64.01	64.40	64.79	65.18	65.57
21	65.97	66.36	66.75	67.15	67.54	67.93	68.32	68.71
22	69.11	69.50	69.90	70.29	70.68	71.07	71.47	71.86
23	72.25	72.64	73.04	73.43	73.82	74.22	74.61	75.00
24	75.39	75.79	76.18	76.57	76.96	77.36	77.75	78.14
25	78.54	78.93	79.32	79.71	80.10	80.50	80.89	81.28
26	81.68	82.07	82.46	82.85	83.25	83.64	84.03	84.42
27	84.82	85.21	85.60	86.00	86.39	86.78	87.17	87.56
28	87.96	88.35	88.75	89.14	89.53	89.92	90.32	90.71
29	91.10	91.49	91.89	92.28	92.67	93.06	93.46	93.85
30	94.24	94.64	95.03	95.42	95.81	96.21	96.60	96.99
31	97.39	97.78	98.17	98.57	98.96	99.35	99.75	100.14
32	100.53	100.92	101.32	101.71	102.10	102.49	102.89	103.28
33	103.67	104.07	104.46	104.85	105.24	105.64	106.03	106.42
34	106.81	107.21	107.60	107.99	108.39	108.78	109.17	109.56
35	109.96	110.35	110.74	111.13	111.53	111.92	112.31	112.70
36	113.10	113.49	113.88	114.28	114.67	115.06	115.45	115.84
37	116.24	116.63	117.02	117.42	117.81	118.20	118.60	118.99
38	119.38	119.77	120.17	120.56	120.95	121.34	121.74	122.13
39	122.52	122.92	123.31	123.70	124.09	124.49	124.88	125.27
40	125.66	126.06	126.45	126.84	127.24	127.63	128.02	128.41
41	128.81	129.20	129.59	129.98	130.38	130.77	131.16	131.55
42	131.95	132.34	132.73	133.13	133.52	133.91	134.30	134.69
43	135.09	135.48	135.87	136.27	136.66	137.05	137.45	137.84
44	138.23	138.62	139.02	139.41	139.80	140.19	140.59	140.98
45	141.37	141.76	142.16	142.55	142.94	143.34	143.73	144.12

### Table of Cluster Area

Length	No	Length	No	Length	No	Length	No
1001	1	101021	123	10017	154	100797	243
1002	2	101031	124	101051	184	100800	240
1003	3	1010	125	104117	180	100804	247
1004	4	101123	126	104151	187	100870	248
1005	5	10115	127	10417	196	100174	240
1006	6	101193	128	104213	190	100260	230
1007	7	10122	129	104240	190	100388	231
1008	8	101264	130	104447	191	100401	233
1009	9	101301	131	104515	192	10057	234
1010	10	10133	132	10454	193	100634	234
1011	11	101376	133	10457	194	100732	233
1012	12	101414	134	104772	195	100830	236
1013	13	101452	135	104702	196	100940	237
1014	14	101493	136	104802	197	100949	238
1015	15	101533	137	104832	198	101147	239
1016	16	101574	138	105003	199	10247	240
1017	17	101614	139	105073	200	10347	261
1018	18	101656	140	105117	201	10447	262
1019	19	10169	141	105220	202	10544	263
1020	20	101741	142	105273	203	10630	264
1021	21	101784	143	105367	204	10732	265
1022	22	101828	144	105411	205	10813	266
1023	23	101872	145	105510	206	109	267
1024	24	101916	146	105591	207	110	268
1025	25	101961	147	106	208	11103	269
1026	26	102006	148	106763	209	11209	270
1027	27	102052	149	106814	210	11274	271
1028	28	102098	150	10687	211	11279	272
1029	29	102145	151	106927	212	11314	273
1030	30	102192	152	106951	213	11320	274
1031	31	102240	153	106970	214	11379	275
1032	32	102289	154	107000	215	11404	276
1033	33	102339	155	10702	216	114011	277
1034	34	102389	156	107078	217	114118	278
1035	35	102440	157	107139	218	114223	279
1036	36	102491	158	107200	219	114331	280
1037	37	102542	159	107261	220	11444	281
1038	38	102593	160	107323	221	114544	282
1039	39	102645	161	107385	222	114644	283
1040	40	102697	162	107447	223	114744	284
1041	41	102750	163	107509	224	114844	285
1042	42	102802	164	107571	225	114944	286
1043	43	102855	165	107633	226	115044	287
1044	44	102907	166	107695	227	115144	288
1045	45	102960	167	107757	228	115244	289
1046	46	103012	168	107819	229	115344	290
1047	47	103065	169	107881	230	115444	291
1048	48	103117	170	107943	231	115544	292
1049	49	103170	171	108005	232	115644	293
1050	50	103222	172	108067	233	115744	294
1051	51	103275	173	108129	234	115844	295
1052	52	103327	174	108191	235	115944	296
1053	53	1	175	107977	236	116247	297
1054	54	1	176	108096	237	116301	298
1055	55	1	177	108158	238	116440	299
1056	56	1	178	108216	239	11659	300
1057	57	1	179	108237	240	116711	301
1058	58	1	180	108470	241	116822	302
1059	59	1	181	108519	242	116951	303
1060	60	1	182	108611	243	117070	304
1061	61	1	183	108704	244	117183	305

## Areas and Circumferences of Circles (Continued)

Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft
13 0	132.7326	40 10	18 0	254.4696	56 6 $\frac{1}{2}$	23 0	415.4766	72
1 1	134.4391	41 1 $\frac{1}{2}$	1 1	256.8303	56 9 $\frac{1}{2}$	1 1	418.4915	72
2 2	136.1574	41 4 $\frac{3}{4}$	2 2	259.2033	57 7 $\frac{1}{2}$	2 2	421.5192	72
3 3	137.8867	41 7 $\frac{1}{2}$	3 3	261.5872	57 4	3 3	424.5577	73
4 4	139.626	41 10 $\frac{1}{2}$	4 4	263.9807	57 7 $\frac{1}{2}$	4 4	427.6055	73
5 5	141.3771	42 1 $\frac{1}{2}$	5 5	266.3864	57 10 $\frac{1}{2}$	5 5	430.6658	73
6 6	143.1391	42 4 $\frac{3}{4}$	6 6	268.8031	58 1 $\frac{1}{2}$	6 6	433.7371	73
7 7	144.9111	42 8	7 7	271.2293	58 4 $\frac{1}{2}$	7 7	436.8175	74
8 8	146.6949	42 11 $\frac{1}{2}$	8 8	273.6678	58 7 $\frac{1}{2}$	8 8	439.9106	74
9 9	148.4896	43 2 $\frac{1}{4}$	9 9	276.1171	58 10 $\frac{3}{4}$	9 9	443.0146	74
10 10	150.2943	43 5 $\frac{1}{2}$	10 10	278.5761	59 2	10 10	446.1278	74 1
11 11	152.1109	43 8 $\frac{3}{4}$	11 11	281.0472	59 5 $\frac{1}{2}$	11 11	449.2536	75
14 0	153.9384	43 11 $\frac{3}{4}$	19 0	283.5294	59 8 $\frac{1}{4}$	24 0	452.3904	75
1 1	155.7758	44 2 $\frac{7}{8}$	1 1	286.021	59 11 $\frac{1}{2}$	1 1	455.5362	75
2 2	157.625	44 6	2 2	288.5249	60 2 $\frac{1}{2}$	2 2	458.6948	75 1
3 3	159.4852	44 9 $\frac{1}{8}$	3 3	291.0397	60 5 $\frac{1}{2}$	3 3	461.8642	76
4 4	161.3553	45 1 $\frac{1}{4}$	4 4	293.5641	60 8 $\frac{3}{4}$	4 4	465.0428	76
5 5	163.2373	45 3 $\frac{1}{2}$	5 5	296.1107	60 11 $\frac{7}{8}$	5 5	468.2341	76
6 6	165.1303	45 6 $\frac{3}{8}$	6 6	298.6483	61 3 $\frac{1}{2}$	6 6	471.4363	76 1
7 7	167.0331	45 9 $\frac{3}{4}$	7 7	301.2054	61 6 $\frac{1}{4}$	7 7	474.6476	77
8 8	168.9479	46 7 $\frac{1}{8}$	8 8	303.7747	61 9 $\frac{1}{2}$	8 8	477.8716	77
9 9	170.8735	46 4	9 9	306.355	62 1 $\frac{1}{2}$	9 9	481.1065	77
10 10	172.8091	46 7 $\frac{1}{8}$	10 10	308.9448	62 3 $\frac{3}{8}$	10 10	484.3506	78
11 11	174.7565	46 11 $\frac{1}{4}$	11 11	311.5469	62 6 $\frac{3}{4}$	11 11	487.6073	78
15 0	176.715	47 1 $\frac{1}{2}$	20 0	314.16	62 9 $\frac{7}{8}$	25 0	490.875	78
1 1	178.6832	47 4 $\frac{5}{8}$	1 1	316.7824	63 1 $\frac{1}{8}$	1 1	494.1516	78
2 2	180.6634	47 7 $\frac{3}{4}$	2 2	319.4173	63 4 $\frac{1}{4}$	2 2	497.4411	79
3 3	182.6545	47 10 $\frac{7}{8}$	3 3	322.063	63 7 $\frac{3}{8}$	3 3	500.7415	79
4 4	184.6555	48 2 $\frac{1}{2}$	4 4	324.7182	63 11 $\frac{1}{2}$	4 4	504.051	79
5 5	186.6684	48 5 $\frac{1}{8}$	5 5	327.3858	64 1 $\frac{5}{8}$	5 5	507.3732	79 1
6 6	188.6923	48 8 $\frac{1}{4}$	6 6	330.0643	64 4 $\frac{3}{4}$	6 6	510.7063	80
7 7	190.726	48 11 $\frac{3}{8}$	7 7	332.7522	64 7 $\frac{7}{8}$	7 7	514.0484	80
8 8	192.7716	49 2 $\frac{5}{8}$	8 8	335.4525	64 11	8 8	517.4034	80
9 9	194.8282	49 5 $\frac{3}{4}$	9 9	338.1637	65 2 $\frac{1}{4}$	9 9	520.7692	80 1
10 10	196.8946	49 8 $\frac{7}{8}$	10 10	340.8844	65 5 $\frac{3}{8}$	10 10	524.1441	81
11 11	198.973	50 0	11 11	343.6174	65 8 $\frac{1}{4}$	11 11	527.5318	81
16 0	201.0624	50 3 $\frac{1}{8}$	21 0	346.3614	65 11 $\frac{5}{8}$	26 0	530.9304	81
1 1	203.1615	50 6 $\frac{1}{4}$	1 1	349.1147	66 2 $\frac{3}{4}$	1 1	534.3379	81 1
2 2	205.2726	50 9 $\frac{5}{8}$	2 2	351.8804	66 5 $\frac{7}{8}$	2 2	537.7583	82
3 3	207.3946	51 1 $\frac{1}{2}$	3 3	354.6571	66 9	3 3	541.1896	82
4 4	209.5264	51 3 $\frac{3}{4}$	4 4	357.4432	67 1 $\frac{1}{2}$	4 4	544.6299	82
5 5	211.6703	51 6 $\frac{1}{2}$	5 5	360.2417	67 3 $\frac{3}{8}$	5 5	548.083	82 1
6 6	213.8251	51 10	6 6	363.0511	67 6 $\frac{1}{2}$	6 6	551.5471	83
7 7	215.9896	52 1 $\frac{1}{8}$	7 7	365.8698	67 9 $\frac{5}{8}$	7 7	555.0201	83
8 8	218.1662	52 4 $\frac{1}{4}$	8 8	368.7011	68 3 $\frac{1}{4}$	8 8	558.5059	83
9 9	220.3537	52 7 $\frac{3}{8}$	9 9	371.5432	68 3 $\frac{7}{8}$	9 9	562.0027	84
10 10	222.551	52 10 $\frac{1}{2}$	10 10	374.3947	68 7	10 10	565.5084	84
11 11	224.7606	53 1 $\frac{3}{8}$	11 11	377.2587	68 10 $\frac{1}{4}$	11 11	569.027	84
17 0	226.9806	53 4 $\frac{3}{8}$	22 0	380.1336	69 1 $\frac{3}{8}$	27 0	572.5566	84
1 1	229.2105	53 8	1 1	383.0177	69 4 $\frac{1}{2}$	1 1	576.0949	85
2 2	231.4525	53 11 $\frac{1}{8}$	2 2	385.9144	69 7 $\frac{5}{8}$	2 2	579.6463	85
3 3	233.7055	54 2 $\frac{1}{8}$	3 3	388.822	69 10 $\frac{3}{4}$	3 3	583.2085	85
4 4	235.9682	54 5 $\frac{3}{8}$	4 4	391.7389	70 1 $\frac{7}{8}$	4 4	586.7796	85 1
5 5	238.243	54 8 $\frac{1}{2}$	5 5	394.6683	70 5	5 5	590.3637	86
6 6	240.5287	54 11 $\frac{5}{8}$	6 6	397.6087	70 8 $\frac{1}{4}$	6 6	593.9587	86
7 7	242.8241	55 2 $\frac{7}{8}$	7 7	400.5583	70 11 $\frac{1}{8}$	7 7	597.5625	86
8 8	245.1316	55 6	8 8	403.5204	71 2 $\frac{1}{2}$	8 8	601.1793	86
9 9	247.45	55 9 $\frac{1}{8}$	9 9	406.4935	71 5 $\frac{3}{8}$	9 9	604.807	87
10 10	249.7781	56 1 $\frac{1}{4}$	10 10	409.4759	71 8 $\frac{3}{4}$	10 10	608.4436	87
11 11	252.1184	56 3 $\frac{1}{2}$	11 11	412.4707	71 11 $\frac{7}{8}$	11 11	612.0931	87

Table of Circular Area

Height	Area	Length	Area	Height	Area	Length
10.21	123	1.0397	184	1.08707	245	1.12900
10.31	124	1.04081	185	1.08800	246	1.13029
10.41	125	1.04187	186	1.08894	247	1.13149
10.51	126	1.04293	187	1.08979	248	1.13270
10.61	127	1.04397	188	1.09074	249	1.13391
10.71	128	1.04503	189	1.09169	250	1.13512
10.81	129	1.04608	190	1.09263	251	1.13634
10.91	130	1.04714	191	1.09358	252	1.13756
11.01	131	1.04819	192	1.09452	253	1.13879
11.11	132	1.04924	193	1.09547	254	1.13999
11.21	133	1.05029	194	1.09641	255	1.14120
11.31	134	1.05133	195	1.09736	256	1.14240
11.41	135	1.05238	196	1.09830	257	1.14361
11.51	136	1.05342	197	1.09925	258	1.14481
11.61	137	1.05447	198	1.10019	259	1.14602
11.71	138	1.05551	199	1.10114	260	1.14722
11.81	139	1.05656	200	1.10208	261	1.14843
11.91	140	1.05760	201	1.10303	262	1.14963
12.01	141	1.05865	202	1.10397	263	1.15084
12.11	142	1.05969	203	1.10492	264	1.15204
12.21	143	1.06074	204	1.10586	265	1.15325
12.31	144	1.06178	205	1.10681	266	1.15445
12.41	145	1.06283	206	1.10775	267	1.15566
12.51	146	1.06387	207	1.10870	268	1.15686
12.61	147	1.06491	208	1.10964	269	1.15807
12.71	148	1.06596	209	1.11059	270	1.15927
12.81	149	1.06699	210	1.11153	271	1.16048
12.91	150	1.06804	211	1.11248	272	1.16168
13.01	151	1.06908	212	1.11342	273	1.16289
13.11	152	1.07012	213	1.11437	274	1.16409
13.21	153	1.07117	214	1.11531	275	1.16530
13.31	154	1.07221	215	1.11626	276	1.16650
13.41	155	1.07325	216	1.11720	277	1.16771
13.51	156	1.07430	217	1.11815	278	1.16891
13.61	157	1.07534	218	1.11909	279	1.17012
13.71	158	1.07638	219	1.12004	280	1.17132
13.81	159	1.07743	220	1.12098	281	1.17253
13.91	160	1.07847	221	1.12193	282	1.17373
14.01	161	1.07951	222	1.12287	283	1.17494
14.11	162	1.08056	223	1.12382	284	1.17614
14.21	163	1.08160	224	1.12476	285	1.17735
14.31	164	1.08264	225	1.12571	286	1.17855
14.41	165	1.08369	226	1.12665	287	1.17976
14.51	166	1.08473	227	1.12760	288	1.18096
14.61	167	1.08578	228	1.12854	289	1.18217
14.71	168	1.08682	229	1.12949	290	1.18337
14.81	169	1.08786	230	1.13043	291	1.18458
14.91	170	1.08891	231	1.13138	292	1.18578
15.01	171	1.08995	232	1.13232	293	1.18699
15.11	172	1.09099	233	1.13327	294	1.18819
15.21	173	1.09204	234	1.13421	295	1.18940
15.31	174	1.09308	235	1.13516	296	1.19060
15.41	175	1.09412	236	1.13610	297	1.19181
15.51	176	1.09517	237	1.13705	298	1.19301
15.61	177	1.09621	238	1.13799	299	1.19422
15.71	178	1.09725	239	1.13894	300	1.19542
15.81	179	1.09830	240	1.13988	301	1.19663
15.91	180	1.09934	241	1.14083	302	1.19783
16.01	181	1.10038	242	1.14177	303	1.19904
16.11	182	1.10143	243	1.14272	304	1.20024
16.21	183	1.10247	244	1.14366	305	1.20145

16.31	184	1.10351
16.41	185	1.10456
16.51	186	1.10560
16.61	187	1.10664
16.71	188	1.10769
16.81	189	1.10873
16.91	190	1.10977

## Areas and Circumferences of Circles (Continued)

Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft	Circum., ft in	Diam., ft in	Area, sq ft
43 0	1452.205	135 1	46 0	1661.906	144 6 <sup>1</sup> / <sub>8</sub>	49 0	1885.745
1	1457.836	135 4 <sup>1</sup> / <sub>8</sub>	1	1667.931	144 9 <sup>1</sup> / <sub>8</sub>	1	1892.172
2	1463.483	135 7 <sup>1</sup> / <sub>8</sub>	2	1673.97	145 3 <sup>1</sup> / <sub>8</sub>	2	1898.504
3	1469.14	135 10 <sup>1</sup> / <sub>2</sub>	3	1680.02	145 3 <sup>1</sup> / <sub>2</sub>	3	1905.037
4	1474.804	136 1 <sup>1</sup> / <sub>8</sub>	4	1686.077	145 6 <sup>1</sup> / <sub>8</sub>	4	1911.497
5	1480.483	136 4 <sup>1</sup> / <sub>8</sub>	5	1692.148	145 9 <sup>1</sup> / <sub>8</sub>	5	1917.961
6	1486.173	136 7 <sup>1</sup> / <sub>8</sub>	6	1698.231	146 1 <sup>1</sup> / <sub>8</sub>	6	1924.426
7	1491.870	136 11	7	1704.321	146 4 <sup>1</sup> / <sub>8</sub>	7	1930.919
8	1497.582	137 2 <sup>1</sup> / <sub>8</sub>	8	1710.425	146 7 <sup>1</sup> / <sub>8</sub>	8	1937.316
9	1503.305	137 5 <sup>1</sup> / <sub>8</sub>	9	1716.541	146 10 <sup>3</sup> / <sub>8</sub>	9	1943.914
10	1509.035	137 8 <sup>3</sup> / <sub>8</sub>	10	1722.663	147 1 <sup>1</sup> / <sub>2</sub>	10	1950.439
11	1514.779	137 11 <sup>5</sup> / <sub>8</sub>	11	1728.801	147 4 <sup>5</sup> / <sub>8</sub>	11	1956.969
44 0	1520.534	138 2 <sup>3</sup> / <sub>4</sub>	47 0	1734.947	147 7 <sup>3</sup> / <sub>4</sub>	50 0	1963.5
1	1526.297	138 5 <sup>7</sup> / <sub>8</sub>	1	1741.104	147 11	.....	.....
2	1532.074	138 9	2	1747.274	148 2 <sup>1</sup> / <sub>8</sub>	.....	.....
3	1537.862	139 1 <sup>1</sup> / <sub>8</sub>	3	1753.455	148 5 <sup>1</sup> / <sub>8</sub>	.....	.....
4	1543.658	139 3 <sup>1</sup> / <sub>4</sub>	4	1759.643	148 8 <sup>3</sup> / <sub>8</sub>	.....	.....
5	1549.478	139 6 <sup>1</sup> / <sub>8</sub>	5	1765.845	148 11 <sup>1</sup> / <sub>2</sub>	.....	.....
6	1555.288	139 9 <sup>5</sup> / <sub>8</sub>	6	1772.059	149 2 <sup>5</sup> / <sub>8</sub>	.....	.....
7	1561.116	140 3 <sup>1</sup> / <sub>4</sub>	7	1778.28	149 5 <sup>7</sup> / <sub>8</sub>	.....	.....
8	1566.959	140 3 <sup>7</sup> / <sub>8</sub>	8	1784.515	149 8 <sup>7</sup> / <sub>8</sub>	.....	.....
9	1572.812	140 7 <sup>1</sup> / <sub>2</sub>	9	1790.761	150 1 <sup>1</sup> / <sub>8</sub>	.....	.....
10	1578.673	140 10 <sup>1</sup> / <sub>8</sub>	10	1797.015	150 3 <sup>1</sup> / <sub>4</sub>	.....	.....
11	1584.549	141 1 <sup>1</sup> / <sub>4</sub>	11	1803.283	150 6 <sup>3</sup> / <sub>8</sub>	.....	.....
45 0	1590.435	141 4 <sup>3</sup> / <sub>8</sub>	48 0	1809.562	150 9 <sup>1</sup> / <sub>2</sub>	.....	.....
1	1596.329	141 7 <sup>1</sup> / <sub>2</sub>	1	1815.848	151 5 <sup>1</sup> / <sub>8</sub>	.....	.....
2	1602.237	141 10 <sup>3</sup> / <sub>8</sub>	2	1822.149	151 3 <sup>3</sup> / <sub>4</sub>	.....	.....
3	1608.155	142 1 <sup>7</sup> / <sub>8</sub>	3	1828.460	151 6 <sup>7</sup> / <sub>8</sub>	.....	.....
4	1614.082	142 5	4	1834.779	151 10 <sup>1</sup> / <sub>8</sub>	.....	.....
5	1620.023	142 8 <sup>1</sup> / <sub>8</sub>	5	1841.173	152 1 <sup>1</sup> / <sub>4</sub>	.....	.....
6	1625.974	142 11 <sup>1</sup> / <sub>4</sub>	6	1847.457	152 4 <sup>3</sup> / <sub>8</sub>	.....	.....
7	1631.933	143 2 <sup>1</sup> / <sub>8</sub>	7	1853.809	152 7 <sup>1</sup> / <sub>2</sub>	.....	.....
8	1637.907	143 5 <sup>1</sup> / <sub>2</sub>	8	1860.175	152 10 <sup>5</sup> / <sub>8</sub>	.....	.....
9	1643.891	143 8 <sup>3</sup> / <sub>4</sub>	9	1866.552	153 1 <sup>3</sup> / <sub>4</sub>	.....	.....
10	1649.883	143 11 <sup>7</sup> / <sub>8</sub>	10	1872.937	153 4 <sup>7</sup> / <sub>8</sub>	.....	.....
11	1655.889	144 3	11	1879.335	153 8 <sup>1</sup> / <sub>8</sub>	.....	.....

## Circular Arcs

To find, by the following table, the length of a circular arc when its height, or versed sine is given.

**Rule.** Divide the height by the chord; find in the column of h number equal to this quotient; take out the corresponding number in column of lengths; and multiply this number by the given chord.

**Example.** The chord of an arc is 80 and its versed sine is 30. What is the length of the arc?

**Solution.**  $30 \div 80 = 0.375$ . The length of an arc for a height of 30 from table, 1.34063.  $80 \times 1.34063 = 107.2504 =$  length of arc.



Table of Circular Area

Lengths	Hts	Lengths	Hts	Lengths	Hts	Lengths	Hts	Lengths
1.00001	.062	1.01021	.123	1.03957	.184	1.08797	.245	1.15208
1.00001	.063	1.01054	.124	1.04051	.185	1.08890	.246	1.15428
1.00002	.064	1.01088	.125	1.04116	.186	1.08984	.247	1.15549
1.00004	.065	1.01123	.126	1.04181	.187	1.09079	.248	1.15670
1.00007	.066	1.01158	.127	1.04247	.188	1.09174	.249	1.15791
1.00010	.067	1.01193	.128	1.04313	.189	1.09269	.250	1.15912
1.00013	.068	1.01228	.129	1.04380	.190	1.09365	.251	1.16034
1.00017	.069	1.01264	.130	1.04447	.191	1.09461	.252	1.16156
1.00022	.070	1.01301	.131	1.04515	.192	1.09557	.253	1.16279
1.00027	.071	1.01338	.132	1.04584	.193	1.09654	.254	1.16402
1.00032	.072	1.01376	.133	1.04652	.194	1.09752	.255	1.16526
1.00038	.073	1.01414	.134	1.04722	.195	1.09850	.256	1.16650
1.00045	.074	1.01453	.135	1.04792	.196	1.09949	.257	1.16774
1.00053	.075	1.01493	.136	1.04862	.197	1.10048	.258	1.16899
1.00061	.076	1.01533	.137	1.04932	.198	1.10147	.259	1.17024
1.00069	.077	1.01573	.138	1.05003	.199	1.10247	.260	1.17150
1.00078	.078	1.01614	.139	1.05075	.200	1.10347	.261	1.17276
1.00087	.079	1.01656	.140	1.05147	.201	1.10447	.262	1.17403
1.00097	.080	1.01698	.141	1.05220	.202	1.10548	.263	1.17530
1.00107	.081	1.01741	.142	1.05293	.203	1.10650	.264	1.17657
1.00117	.082	1.01784	.143	1.05367	.204	1.10752	.265	1.17784
1.00128	.083	1.01828	.144	1.05441	.205	1.10855	.266	1.17912
1.00140	.084	1.01872	.145	1.05516	.206	1.10958	.267	1.18040
1.00153	.085	1.01916	.146	1.05591	.207	1.11062	.268	1.18169
1.00167	.086	1.01961	.147	1.05667	.208	1.11165	.269	1.18299
1.00182	.087	1.02006	.148	1.05743	.209	1.11269	.270	1.18429
1.00196	.088	1.02052	.149	1.05819	.210	1.11374	.271	1.18559
1.00210	.089	1.02098	.150	1.05896	.211	1.11479	.272	1.18689
1.00225	.090	1.02145	.151	1.05973	.212	1.11584	.273	1.18820
1.00240	.091	1.02192	.152	1.06051	.213	1.11690	.274	1.18951
1.00256	.092	1.02240	.153	1.06130	.214	1.11796	.275	1.19082
1.00272	.093	1.02289	.154	1.06209	.215	1.11904	.276	1.19214
1.00289	.094	1.02339	.155	1.06288	.216	1.12011	.277	1.19346
1.00307	.095	1.02389	.156	1.06368	.217	1.12118	.278	1.19479
1.00327	.096	1.02440	.157	1.06449	.218	1.12225	.279	1.19612
1.00345	.097	1.02491	.158	1.06530	.219	1.12334	.280	1.19746
1.00364	.098	1.02542	.159	1.06611	.220	1.12444	.281	1.19880
1.00384	.099	1.02593	.160	1.06693	.221	1.12554	.282	1.20014
1.00405	.100	1.02645	.161	1.06775	.222	1.12664	.283	1.20149
1.00426	.101	1.02698	.162	1.06858	.223	1.12774	.284	1.20284
1.00447	.102	1.02752	.163	1.06941	.224	1.12885	.285	1.20419
1.00469	.103	1.02806	.164	1.07025	.225	1.12997	.286	1.20555
1.00492	.104	1.02860	.165	1.07109	.226	1.13108	.287	1.20691
1.00515	.105	1.02914	.166	1.07194	.227	1.13219	.288	1.20827
1.00539	.106	1.02970	.167	1.07279	.228	1.13331	.289	1.20964
1.00563	.107	1.03026	.168	1.07365	.229	1.13444	.290	1.21102
1.00587	.108	1.03082	.169	1.07451	.230	1.13557	.291	1.21239
1.00612	.109	1.03139	.170	1.07537	.231	1.13671	.292	1.21377
1.00638	.110	1.03196	.171	1.07624	.232	1.13785	.293	1.21515
1.00665	.111	1.03254	.172	1.07711	.233	1.13900	.294	1.21654
1.00692	.112	1.03312	.173	1.07799	.234	1.14015	.295	1.21794
1.00720	.113	1.03371	.174	1.07888	.235	1.14121	.296	1.21933
1.00748	.114	1.03430	.175	1.07977	.236	1.14247	.297	1.22073
1.00776	.115	1.03490	.176	1.08066	.237	1.14363	.298	1.22213
1.00805	.116	1.03551	.177	1.08156	.238	1.14480	.299	1.22354
1.00834	.117	1.03611	.178	1.08246	.239	1.14597	.300	1.22495
1.00864	.118	1.03672	.179	1.08337	.240	1.14714	.301	1.22636
1.00895	.119	1.03734	.180	1.08428	.241	1.14832	.302	1.22778
1.00926	.120	1.03797	.181	1.08519	.242	1.14951	.303	1.22920
1.00957	.121	1.03860	.182	1.08611	.243	1.15070	.304	1.23063
1.00989	.122	1.03923	.183	1.08704	.244	1.15189	.305	1.23206

Table of Circular Arcs (Continued)

Hts	Lengths	Hts	Lengths	Hts	Lengths	Hts	Lengths	Hts	Lengths
.306	1.23349	.345	1.29209	.384	1.35575	.423	1.42402	.462	1.49460
.307	1.23492	.346	1.29366	.385	1.35744	.424	1.42583	.463	
.308	1.23636	.347	1.29523	.386	1.35914	.425	1.42764	.464	
.309	1.23781	.348	1.29681	.387	1.36084	.426	1.42945	.465	
.310	1.23926	.349	1.29839	.388	1.36254	.427	1.43127	.466	
.311	1.24070	.350	1.29997	.389	1.36425	.428	1.43309	.467	
.312	1.24216	.351	1.30156	.390	1.36596	.429	1.43491	.468	
.313	1.24361	.352	1.30315	.391	1.36767	.430	1.43673	.469	
.314	1.24507	.353	1.30474	.392	1.36939	.431	1.43856	.470	
.315	1.24654	.354	1.30634	.393	1.37111	.432	1.44039	.471	
.316	1.24801	.355	1.30794	.394	1.37283	.433	1.44222	.472	
.317	1.24948	.356	1.30954	.395	1.37455	.434	1.44405	.473	
.318	1.25095	.357	1.31115	.396	1.37623	.435	1.44589	.474	
.319	1.25243	.358	1.31276	.397	1.37801	.436	1.44773	.475	
.320	1.25391	.359	1.31437	.398	1.37974	.437	1.44957	.476	
.321	1.25540	.360	1.31599	.399	1.38148	.438	1.45142	.477	
.322	1.25689	.361	1.31761	.400	1.38322	.439	1.45327	.478	
.323	1.25838	.362	1.31923	.401	1.38496	.440	1.45512	.479	
.324	1.25988	.363	1.32086	.402	1.38671	.441	1.45697	.480	
.325	1.26138	.364	1.32249	.403	1.38846	.442	1.45883	.481	
.326	1.26288	.365	1.32413	.404	1.39021	.443	1.46069	.482	
.327	1.26437	.366	1.32577	.405	1.39196	.444	1.46255	.483	
.328	1.26588	.367	1.32741	.406	1.39372	.445	1.46441	.484	
.329	1.26740	.368	1.32905	.407	1.39548	.446	1.46628	.485	
.330	1.26892	.369	1.33069	.408	1.39724	.447	1.46815	.486	
.331	1.27044	.370	1.33234	.409	1.39900	.448	1.47002	.487	
.332	1.27196	.371	1.33399	.410	1.40077	.449	1.47189	.488	
.333	1.27349	.372	1.33564	.411	1.40254	.450	1.47377	.489	
.334	1.27502	.373	1.33730	.412	1.40432	.451	1.47565	.490	
.335	1.27656	.374	1.33896	.413	1.40610	.452	1.47753	.491	
.336	1.27810	.375	1.34063	.414	1.40788	.453	1.47942	.492	
.337	1.27964	.376	1.34229	.415	1.40966	.454	1.48131	.493	
.338	1.28118	.377	1.34396	.416	1.41145	.455	1.48320	.494	
.339	1.28273	.378	1.34563	.417	1.41324	.456	1.48509	.495	
.340	1.28428	.379	1.34731	.418	1.41503	.457	1.48699	.496	
.341	1.28583	.380	1.34899	.419	1.41682	.458	1.48889	.497	
.342	1.28739	.381	1.35068	.420	1.41861	.459	1.49079	.498	
.343	1.28895	.382	1.35237	.421	1.42041	.460	1.49269	.499	
.344	1.29052	.383	1.35406	.422	1.42221	.461		.500	

Table of Lengths of Circular Arcs whose Radius is r

**Rule.** Knowing the measure of the circle and the measure of the arc in minutes and seconds; take from the table the lengths opposite the number of degrees, minutes and seconds in the arc, and multiply their sum by the radius of the circle.

**Example.** What is the length of an arc subtending an angle of  $13^\circ$  with a radius of 8 ft.

**Solution.** Length for  $13^\circ = 0.2268928$

$27' = 0.0078540$

$8'' = 0.0000388$

$13^\circ 27' 8'' = 0.2347856$

8

Length of arc =  $1.8782848$  ft

# Table of Circular Arcs

Lengths of Circular Arcs. Radius = r

Length	Min	Length.	Deg	Length	Deg	Length
0.000048	1	0.0002909	1	0.0174533	61	1.064054
0.000097	2	0.0005818	2	0.0349066	62	1.082104
0.000145	3	0.0008727	3	0.0523599	63	1.099551
0.000194	4	0.0011636	4	0.0698132	64	1.117010
0.000242	5	0.0014544	5	0.0872665	65	1.134464
0.000291	6	0.0017453	6	0.1047198	66	1.151917
0.000339	7	0.0020362	7	0.1221730	67	1.169371
0.000388	8	0.0023271	8	0.1396263	68	1.186823
0.000436	9	0.0026180	9	0.1570796	69	1.204277
0.000485	10	0.0029089	10	0.1745329	70	1.221731
0.000533	11	0.0031998	11	0.1919862	71	1.239181
0.000582	12	0.0034907	12	0.2094395	72	1.256637
0.000630	13	0.0037815	13	0.2268928	73	1.274090
0.000679	14	0.0040724	14	0.2443461	74	1.291543
0.000727	15	0.0043633	15	0.2617994	75	1.308994
0.000776	16	0.0046542	16	0.2792527	76	1.326451
0.000824	17	0.0049451	17	0.2967060	77	1.343903
0.000873	18	0.0052360	18	0.3141593	78	1.361356
0.000921	19	0.0055269	19	0.3316126	79	1.378810
0.000970	20	0.0058178	20	0.3490659	80	1.396263
0.001018	21	0.0061087	21	0.3665191	81	1.413716
0.001067	22	0.0063995	22	0.3839724	82	1.431170
0.001115	23	0.0066904	23	0.4014257	83	1.448623
0.001164	24	0.0069813	24	0.4188790	84	1.466076
0.001212	25	0.0072722	25	0.4363323	85	1.483529
0.001261	26	0.0075631	26	0.4537856	86	1.500982
0.001309	27	0.0078540	27	0.4712389	87	1.518436
0.001357	28	0.0081449	28	0.4886922	88	1.535889
0.001406	29	0.0084358	29	0.5061455	89	1.553343
0.001454	30	0.0087266	30	0.5235988	90	1.570796
0.001503	31	0.0090175	31	0.5410521	91	1.588249
0.001551	32	0.0093084	32	0.5585054	92	1.605702
0.001600	33	0.0095993	33	0.5759587	93	1.623156
0.001648	34	0.0098902	34	0.5934119	94	1.640609
0.001697	35	0.0101811	35	0.6108652	95	1.658062
0.001745	36	0.0104720	36	0.6283185	96	1.675516
0.001794	37	0.0107629	37	0.6457718	97	1.692969
0.001842	38	0.0110538	38	0.6632251	98	1.710422
0.001891	39	0.0113446	39	0.6806784	99	1.727876
0.001939	40	0.0116355	40	0.6981317	100	1.745329
0.001988	41	0.0119264	41	0.7155850	101	1.762782
0.002036	42	0.0122173	42	0.7330383	102	1.780235
0.002085	43	0.0125082	43	0.7504916	103	1.797689
0.002133	44	0.0127991	44	0.7679449	104	1.815142
0.002182	45	0.0130900	45	0.7853982	105	1.832595
0.002230	46	0.0133809	46	0.8028515	106	1.850049
0.002279	47	0.0136717	47	0.8203047	107	1.867502
0.002327	48	0.0139626	48	0.8377580	108	1.884955
0.002376	49	0.0142535	49	0.8552113	109	1.902408
0.002424	50	0.0145444	50	0.8726646	110	1.919862
0.002473	51	0.0148353	51	0.8901179	111	1.937315
0.002521	52	0.0151262	52	0.9075712	112	1.954768
0.002570	53	0.0154171	53	0.9250245	113	1.972222
0.002618	54	0.0157080	54	0.9424778	114	1.989675
0.002666	55	0.0159989	55	0.9599311	115	2.007128
0.002715	56	0.0162897	56	0.9773844	116	2.024581
0.002763	57	0.0165806	57	0.9948377	117	2.042035
0.002812	58	0.0168715	58	1.0122910	118	2.059488
0.002860	59	0.0171624	59	1.0297443	119	2.076941
0.002909	60	0.0174533	60	1.0471976	120	2.094395

To compute the chord of an arc when the chord of half the arc and the sine are given.




Fig. 32. Circular Arc, Chord and Rise

(The versed sine is the perpendicular  $bo$ , Fig. 32.)

**Rule.** From the square of the chord of half the arc subtract the square of the versed sine, and take the square root of the remainder.

**Example.** The chord of half the arc is 60, and the versed sine 36. What is the length of the chord of the arc?

**Solution.**  $60^2 - 36^2 = 2\,304$ ;  $\sqrt{2\,304} = 48$ ; and  $48 \times 2 = 96$ , the chord of the arc.

To compute the chord of an arc when the diameter and versed sine are given.

Multiply the versed sine by 2 and subtract the product from the diameter; then subtract the square of the remainder from the square of the diameter; take the square root of that remainder.

**Example.** The diameter of a circle is 100 and the versed sine of an arc is 36. What is the chord of the arc?

**Solution.**  $36 \times 2 = 72$ ;  $100 - 72 = 28$ ;  $100^2 - 28^2 = 9\,216$ ;  $\sqrt{9\,216} = 96$ , the chord of the arc.

To compute the chord of half an arc when the chord of the arc and the versed sine are given.

**Rule.** Take the square root of the sum of the squares of the versed sine and half the chord of the arc.

**Example.** The chord of an arc is 96 and the versed sine 36. What is the chord of half the arc?

**Solution.**  $\sqrt{36^2 + 48^2} = 60$ .

To compute the chord of half an arc when the diameter and versed sine are given.

**Rule.** Multiply the diameter by the versed sine and take the square root of their product.

To compute a diameter.

**Rule 1.** Divide the square of the chord of half the arc by the versed sine.

**Rule 2.** Add the square of half the chord of the arc to the square of the versed sine and divide this sum by the versed sine.

**Example.** What is the radius of an arc whose chord is 96 and whose versed sine is 36?

**Solution.**  $48^2 \div 36 = 640$ ;  $640 + 36 = 676$ , the diameter; and the radius is 50.

To compute the versed sine.

**Rule.** Divide the square of the chord of half the arc by the diameter.

To compute the versed sine when the chord of the arc and the diameter are given.

**Rule.** From the square of the diameter subtract the square of the chord of the arc; extract the square root of the remainder; subtract this root from the diameter and halve the remainder.

To compute the length of an arc of a circle when the number of degrees in the arc and the radius are given.

**Rule 1.** Multiply the number of degrees in the arc by 3.1416 multiplied by the radius and divide by 180. The result will be the length of the arc in the same unit as the radius.

**Ex. 1.** Multiply the radius of the circle by 0.01745 and the product by the degrees in the arc.

**Ex. 2.** The number of degrees in an arc is 60 and the radius is 10 in. Find the length of the arc in inches?

**Ex. 3.**  $10 \times 3.1416 \times 60 = 1884.96$ ; and  $1884.96 \div 180 = 10.47$  in. Or,  $10 \times 0.01745 \times 60 = 10.47$  in.

**Ex. 4.** Compute the length of the arc of a circle when the length is given in degrees, minutes and seconds.

**Ex. 5.** (1) Multiply the number of degrees by 0.01745329 and the product by the radius. (2) Multiply the number of minutes by 0.00029 and that product by the radius. (3) Multiply the number of seconds by 0.0000048 times the radius. (4) Add together these three results for the length of the arc. (See also, table, page 57.)

**Ex. 6.** What is the length of an arc of  $60^\circ 10' 5''$ , the radius being 4 ft?

**Ex. 7.** (1)  $60^\circ \times 0.01745329 \times 4 = 4.188789$  ft

(2)  $10' \times 0.00029 \times 4 = 0.0116$  ft

(3)  $5'' \times 0.0000048 \times 4 = 0.000096$  ft

(4) The length of the arc = 4.200485 ft

**Ex. 8.** Compute the area of a sector of a circle when the degrees of the arc and the radius are given (Fig. 33).

The degrees of the arc are the same as the angle  $aob$ .)

**Ex. 9.** Multiply the number of degrees in the arc by the area of the whole circle and divide by 360.

**Ex. 10.** What is the area of a sector of a circle whose radius is 5 and length of arc  $60^\circ$ ?

**Ex. 11.** Area of circle =  $10 \times 10 \times 0.7854 = 78.54$

Area of sector =  $\frac{78.5 \times 60}{360} = 13.09$

**Ex. 12.** If the length of the arc is given in degrees and minutes, reduce it to minutes, multiply by the area of the whole circle and divide by 600.

**Ex. 13.** Compute the area of a sector of a circle when the length of the arc and the radius are given.

**Ex. 14.** Multiply the length of the arc by half the length of the radius. The product is the area.

**Ex. 15.** Compute the area of a segment of a circle when the chord and versed sine of the arc and the radius or diameter of the circle are given.

The versed sine is the distance  $cd$ , Fig. 33.)

**Ex. 16.** 1. When the segment is less than a semicircle. (1) Find the area of the sector having the same arc as the segment. (2) Find the area of a triangle formed by the chord of the segment and the radii of the sector. (3) Take the difference of these areas.

2. When the segment is greater than a semicircle. Find, by the preceding rule, the area of the lesser portion of the circle and subtract it from the area of the whole circle. The remainder will be the area.

**Ex. 17.** Compute the area of the surface of a sphere.

**Ex. 18.** Multiply the diameter by the circumference. The product will be the area of the surface.




Fig. 33. Sector of Circle

**Example.** What is the area of the surface of a sphere 10 in in diam

**Solution.** Circumference of sphere =  $10 \times 3.1416 = 31.416$  in;  $10 \times 31.416 = 314.16$  sq in, the area of surface of sphere.

To compute the total area of the surface of a segment of a sphere.

**Rule.** Multiply the height ( $bc$ , Fig. 34) by the circumference of the base, and add the product to the area of the base.




Fig. 34.  
Segment of Sphere

To find the area of the base, having the diameter of the sphere and the length of the versed sine of the arc  $abd$ , find the length of the chord  $ad$  by the rule on page 58. Having, then, the length of the chord  $ad$  for the diameter of the base, find the area of the base.




Fig. 35.  
Zone of Sphere

**Example.** The height,  $bc$ , of a segment  $abd$ , is 36 in, and the diameter of sphere is 100 in (Fig. 34). What is the area of the convex surface and of the whole surface?

**Solution.**  $100 \times 3.1416 = 314.16$  in, the circumference of sphere  
 $36 \times 314.16 = 11309.76$  sq in, the area of the convex surface  
 $100 - (36 \times 2) = 28$   
 $\sqrt{100^2 - 28^2} = 96$ , the chord  $ad$   
 $96^2 \times 0.7854 = 7238.2464$  sq in, the area of the base  
 $11309.76 + 7238.2464 = 18548.0064$  sq in, the total area

To compute the total area of the surface of a spherical zone.

**Rule.** Multiply the height,  $cd$  (Fig. 35), by the circumference of the sphere for the convex surface and add to it the area of the two ends for the total area.

### Spheroids, or Ellipsoids of Revolution

**Definition.** Spheroids, or ellipsoids, are figures generated by the revolution of a semiellipse about one of its diameters.

When the revolution is about the long diameter, they are PROLATE SPHEROIDS; when it is about the short diameter, they are OBLATE SPHEROIDS.

A PROLATE SPHEROID is approximately cigar-shaped and an OBLATE SPHEROID is, in form, somewhat like a watch.

To compute the area of the surface of a spheroid.

Let  $a = \frac{1}{2}$  the long axis; let  $b = \frac{1}{2}$  the short axis;

$$\text{let } \frac{a^2 - b^2}{a^2} = e^2 \quad \text{or} \quad e = \sqrt{\frac{a^2 - b^2}{a^2}}$$

Then, the area of the SURFACE OF THE OBLATE SPHEROID

$$= 2\pi a^2 + \frac{\pi b^2}{e} \log \left( \frac{1+e}{1-e} \right)$$

and the area of the SURFACE OF THE PROLATE SPHEROID

$$= 2\pi b^2 + 2\pi ab \frac{\sin^{-1} e}{e}$$

the first formula, NATURAL LOGARITHMS must be used. The natural logarithm may be obtained by multiplying the common logarithm by 2.302. The value of the expression  $\sin^{-1} e$  may be determined by finding the angle whose sine is equal to  $e$  and dividing this angle by

Although the above formulas are complicated, simpler rules that give correct results can be

to compute the area of the surface of a cylinder.

Rule. Multiply the length of the cylinder by the circumference of one of the ends and add to the result the areas of the two ends.

to compute the area of a circular ring (Fig. 36).

Rule. Find the area of both circles and subtract the area of the smaller from the area of the larger; the remainder will be the area of the ring.

to compute the area of the surface of a cone.

Rule. Multiply the circumference of the base by one-half the slant-height of the cone, for the convex area. Add to this the area of the base, for the whole area.

Example. The diameter of the base of a cone is 3 in and the slant-height 15 in. What is the area of the surface of the cone?

Solution.	$3 \times 3.1416$	$= 9.4248$	$=$ circumference of base
	$9.4248 \times 7\frac{1}{2}$	$= 70.686$ sq in	$=$ area of convex surface
	$3 \times 3 \times 0.7854$	$= 7.068$ sq in	$=$ area of base
Area of entire surface of cone $= 77.754$ sq in			

to compute the area of the surface of the frustum of a cone (Fig. 37).



Fig. 37. Frustum of Cone

Rule. Multiply the sum of the circumferences of the two ends by the slant-height of the frustum and divide by 2, for the area of the convex surface. Add the areas of the two ends.

To compute the area of the surface of a pyramid.

Rule. Multiply the perimeter of the base by one-half the slant-height and add to the product the area of the base.

To compute the area of the surface of the frustum of a pyramid.

Rule. Multiply the sum of the perimeters of the two ends by the slant-height of the frustum, halve the product, and add to the result the areas of the two ends.

## Mensuration of Solids

to compute the volume of a prism. (See page 38 for definition of a prism.)

Rule. Multiply the area of the base or end by the altitude or perpendicular height.

This rule applies to prisms with bases or ends of any shape, as long as these bases or ends are parallel.




Fig. 36. Circular Ring

To compute the volume of a prismoid.

**Definition.** A prismoid is a solid with parallel but unequal ends and with quadrilateral sides.

**Rule.** To the sum of the areas of the two ends or bases add four times the area of the middle section parallel to them, and multiply this sum by one-sixth of the altitude or perpendicular height.




Fig. 38. Quadrangular Prismoid




Fig. 39. Prism Truncated Obliquely

**Example.** What is the volume of a quadrangular prismoid, as Fig. 38, which  $ab = 6$  in,  $cd = 4$  in,  $ac = be = 10$  in,  $ce = 8$  in,  $ef = 8$  in and  $ih = 6$  in.

**Solution.** Area of top  $= \frac{6+4}{2} \times 10 = 50$  sq in

Area of bottom  $= \frac{8+6}{2} \times 10 = 70$  sq in

Area of middle section  $= \frac{6+6}{2} \times 10 = 60$  sq in

$[50 + 70 + (4 \times 60)] \times \frac{1}{6} = 480$  cu in

b

**Note.** The length of the end or middle section (as at  $mn$ , in Fig. 38) is  $\frac{cd+ef}{2}$ .

To find the volume of a prism truncated obliquely.

**Rule.** Multiply the area of the base by the average height of the edges.

**Example.** What is the volume of a truncated prism (Fig. 39) in which  $ab = 6$  in,  $bc = 10$  in,  $cd = 12$  in,  $da = 10$  in and  $fb = 8$  in?

**Solution.** Area of base  $= 6 \times 10 = 60$  sq in

Average height of edges  $= \frac{10+12+8+10}{4} = 10$  in

$60 \times 10 = 600$  cu in

Fig. 40. Wedge or Right Triangular Prism



Compute the volume of a wedge or right triangular prism when the ends are parallel and equal.

1. Multiply the area of one end by the length of the wedge.

Compute the volume of a wedge when the ends are not parallel.

1. Add together the lengths of the three edges,  $ab$ ,  $cd$  and  $ef$  (Fig. 40); multiply their sum by the altitude or perpendicular height of the wedge, and multiply the product by the breadth of the back, and divide the product by 6.

### Regular Polyhedrons

**Definition.** A regular polyhedron is a solid contained within a certain number of similar and equal plane faces, all of which are equal regular polygons. The following is a list of all the regular polyhedrons:

(1) The TETRAHEDRON, or pyramid.

(2) The HEXAHEDRON, or cube, which has six square faces.

(3) The OCTAHEDRON, which has eight triangular faces.

(4) The DODECAHEDRON, which has twelve pentagonal faces.

(5) The ICOSAHEDRON, which has twenty triangular faces.

Compute the volume of a regular polyhedron.

Rule 1. When the radius of the circumscribing sphere is given. Multiply the cube of the radius of the sphere by the multiplier opposite to the polyhedron in column 2 of the following table.

Rule 2. When the radius of the inscribed sphere is given. Multiply the cube of the radius of the inscribed sphere by the multiplier opposite to the polyhedron in column 3 of the table.

Rule 3. When the area of the surface of the polyhedron is given. Cube the area given, extract the square root, and multiply the root by the multiplier opposite to the polyhedron in column 4 of the table.

Table of Factors for Determining the Volumes of Regular Polyhedrons

Figure	1 Number of sides	2 Factor for volume by radius of circumscribing sphere	3 Factor for volume by radius of inscribed circle	4 Factor for volume by surface
tetrahedron.....	4	0.5132	13.85641	0.0517
hexahedron.....	6	1.5396	8.0000	0.06804
octahedron.....	8	1.33333	6.9282	0.07311
dodecahedron.....	12	2.78517	5.55029	0.08169
icosahedron.....	20	2.53615	5.05406	0.0856

Compute the volume of a cylinder.

1. Multiply the area of the base by the altitude or length.

Compute the volume of a cone.

1. Multiply the area of the base by one-third the altitude.

Compute the volume of the frustum of a cone (Fig. 41).

1. Add together the squares of the diameters of the two ends or bases and the product of the two diameters; multiply this sum by 0.7854, and this product by the altitude, and then divide this last product by 3.

**Example.** What is the volume of a frustum of a cone 9 in in height, diameter at the base and 3 in in diameter at the top?

**Solution.**  $9^2 + 3^2 = 34$ .  $3 \times 5 = 15$ .  $15 + 3$ , the sum of the squares of the two diameters and the product of the diameters of the ends.  $49 \times$   
 $= 38.4846$ .

$$\frac{38.4846 \times 9}{3} = 115.4538 \text{ cu in}$$

To compute the volume of a pyramid.

**Rule.** Multiply the area of the base by the perpendicular height, and take one-third product.

To compute the volume of the frustum of a pyramid.

**Rule.** Find the height that the pyramid would be if the top were put on, and then compute the volume of the completed pyramid and the volume of the smaller pyramid that would be removed; subtract the latter from the former, and the remainder will be the volume of the frustum.

To compute the volume of a sphere.

**Rule.** Multiply the cube of the diameter by 0.5236.

To compute the volume of a segment of a sphere.

**Rule 1.** To three times the square of the radius of its base add the square of its height; multiply this sum by the height and the product by 0.5236.

**Rule 2.** From three times the diameter of the sphere subtract twice the height of the segment; multiply this remainder by the square of the height and the product by 0.5236.

**Example.** The segment of a sphere has a radius,  $ac$  (Fig 42), of 7 in for its base, and a height,  $cb$ , of 4 in: what is its volume?

**Solution.** (By Rule 1)  $3 \times 7^2 = 147$ , and  $147 + 4^2 = 163$ , or three times the square of the radius of the base plus the square of the height.  $163 \times 4 \times 0.5236 = 341.3872$  cu in = the volume of the segment.




Fig. 42. Segment of




Fig. 43. Zone of Sphere

**Second Solution.** By the rule for finding the diameter of a circle when a chord and its sine are given, we find that the diameter of the sphere in this case is 16.25 in, then, by Rule 2,  $(3 \times 16.25) - (2 \times 4) = 40.75$ ; and  $40.75 \times 0.5236 = 341.3872$  cu in, the volume of the segment.

To compute the volume of a spherical zone.

**Definition.** The part of a sphere included between two parallel planes (Fig. 43).

**Rule.** To the sum of the squares of the radii of the two ends add one-third of the square of the height of the zone; multiply this sum by the height and the product by 1.5708.

Compute the volume of a prolate spheroid. (See page 60.)

1. Multiply the square of the short axis by the long axis and this product by  $\frac{3}{16}\pi$ .

Compute the volume of an oblate spheroid.

1. Multiply the square of the long axis by the short axis and this product by  $\frac{3}{16}\pi$ .

Compute the volume of a paraboloid of revolution (Fig. 44).

1. Multiply the area of the base by the altitude.

Compute the volume of a hyperboloid of revolution (Fig. 45).

1. To the square of the radius of base add the square of the diameter; multiply this sum by the height and the product by  $\frac{1}{6}\pi$ .

Compute the volume of any figure when

1. Multiply the area of the generating surface by the circumference described by its center of gravity.

Compute the volume of an excavation, where the ground is irregular and bottom of the excavation is level (Fig. 46).

1. Divide the surface of the ground to be excavated unto equal squares but 10 ft on a side, and ascertain by means of a level the height of each corner,  $a, a, a, b, b, b$ , etc., above the level to which the ground is to be excavated. Add together the heights of all the corners that come in one square only.

Next take twice the sum of the heights of all the corners that come in two squares, as  $b, b, b$ ; next three times the sum of the heights of all the corners that come in three squares, as  $c, c, c$ ; and then four times the sum of the heights of all the corners that belong to four squares, as  $d, d, d$ , etc. Add together all these quantities, and multiply their sum by one-fourth the area of one of the squares. The result will be the volume of the excavation.




Fig. 46. Plan of Excavation

Example. Let the plan of an excavation for a cellar be as shown in Fig. 46, the heights of each corner above the proposed bottom of the cellar be as given by the numbers in the figure. Then the volume of the cellar will be as follows, the area of each square being  $10 \times 10 = 100$  sq ft:

Area =  $\frac{1}{4}$  of 100 ( $a$ 's +  $2b$ 's +  $3c$ 's +  $4d$ 's)

The  $a$ 's in this case =  $4 + 6 + 3 + 2 + 1 + 7 + 4 = 27$

$2 \times$  the sum of the  $b$ 's =  $2 \times (3 + 6 + 1 + 4 + 3 + 4) = 42$

$3 \times$  the sum of the  $c$ 's =  $3 \times (1 + 3 + 4) = 24$

$4 \times$  the sum of the  $d$ 's =  $4 \times (2 + 3 + 6 + 2) = 52$

145

Area =  $25 \times 145 = 3625$  cu ft, the quantity of earth to be excavated.

## 4. GEOMETRICAL PROBLEMS

**Problem 1.** To bisect, or divide into equal parts, a given line,  $ab$  (Fig. 47).

From  $a$  and  $b$ , with any radius greater than half of  $ab$ , describe arcs intersecting in  $c$  and  $d$ . The line  $cd$ , connecting these intersections, will bisect  $ab$  and be perpendicular to it.




Fig. 47. Line Bisected




Fig. 48. Perpendicular from Point to Given Line




Fig. 49. Perpendicular from Point to Given Line

**Problem 2.** To draw a perpendicular to a given straight line from a point out it.

**First Method (Fig. 48).** From the point  $a$  describe an arc cutting  $bc$  in two places, as  $e$  and  $f$ . From  $e$  and  $f$  describe two arcs, with the same radius, intersecting in  $g$ ; then a line drawn from  $a$  to  $g$  is perpendicular to line  $bc$ .

**Second Method (Fig. 49).** From any two points,  $d$  and  $c$ , at some distance apart in the given line, and with radii  $da$  and  $ca$  respectively, describe arcs intersecting at  $e$ . Draw  $ae$ , which is the perpendicular required.




Fig. 50. Perpendicular from Point in Given Line




Fig. 51. Perpendicular from Extremity of Given Line

cutting at  $a$  and  $e$ . Draw  $ae$ , which is the perpendicular required. This method is useful where the given point is opposite the end of the line, or so.

**Problem 3.** To draw a perpendicular to a straight line from a given point in that line.

**First Method (Fig. 50).** With any radius, from the given point  $a$  in the line describe arcs cutting the line in the points  $b$  and  $c$ . Then with  $b$  and  $c$  as centers and with any radius greater than  $ab$  or  $ac$ , describe arcs cutting each other at  $d$ . The line  $da$  is the perpendicular required.

2nd Method (Fig. 51), when the given point is at the end of the line. From any point,  $b$ , outside of the line, and with a radius  $ba$ , describe a semicircle passing through  $a$  and cutting the given line at  $d$ . Through  $b$  and  $d$  draw a straight line intersecting the semicircle at  $e$ . The line  $ea$  will then be perpendicular to the line  $ac$  at the point  $a$ .

3rd Method (Fig. 52), or the 3, 4 and 5 Method. From the point  $a$  on the given line measure off 4 in, 3 ft, or 4 of any other unit and with the same unit measure describe an arc, with  $a$  as a center and 5 as a radius. Then from  $b$  describe an arc with a radius of 5 units, cutting the first arc in  $c$ . The line  $ac$  is the perpendicular required. This method is particularly useful in laying out a right angle on the ground, or framing a house where the foot is used as the unit and the lines laid off by the straight-edge.

In laying out a right angle on the ground, the proportions of the triangle may be 3, 4 and 5, or any other multiple of 3, 4 and 5; and it can best be laid out with the tape. Thus, first measure off, say 40 feet from  $a$  (Fig. 52) on the given line; then let one person hold the end of the tape at  $b$ , another hold the tape at the 80-ft mark at  $a$ , and a third person take hold of the tape at the 50-ft mark, with his thumb and finger, and pull the tape taut. The 50-ft mark will then be at the point  $c$  in the line of the perpendicular.




Fig. 51. Straight Line Parallel to Given Line

From any two points near the ends of the given line describe two arcs about the given line. Draw the line  $cd$  tangent to these arcs and it will be parallel to  $ab$ .

Problem 5. To construct an angle equal to a given angle (Fig. 54).

With the point  $A$ , at the apex of the given angle, as a center, and any radius, describe the arc  $BC$ . With the point  $a$ , at the vertex of the new angle, as a




Fig. 54. Angle Equal to Given Angle




Fig. 55. Angle of 60°


and with the same radius as before, describe an arc, as  $BC$ . With  $BC$  as a radius and  $b$  as a center, describe an arc cutting the other arc at  $c$ . Then the angle  $c$  will be equal to the given angle  $CAB$ .

Problem 6. From a point on a given line to draw a line making an angle of 60° with the given line (Fig. 55).

Take any distance, as  $ab$ , as a radius, and with  $a$  as a center, describe the arc  $bc$ . With  $b$  as a center and with the same radius, describe an arc cutting the

first one at  $c$ . Draw from  $a$  a line through  $c$ , and it will make with  $ab$  an angle of  $60^\circ$ .

**Problem 7.** From a given point,  $A$ , on a given line,  $AE$ , to draw a line an angle  $45^\circ$  with the given line (Fig. 56).



Measure off from  $A$ , on  $AE$ , any distance,  $Ab$ . At  $b$  draw a line perpendicular to  $AE$ . Measure on this perpendicular  $bc$  equal to  $Ab$  and draw from  $A$  through  $c$ . This line  $Ac$  will make an angle of  $45^\circ$  with  $AE$ .

**Problem 8.** From any point,  $A$ , on a given line, draw a line which will make any desired angle with the given line (Fig. 57).

To solve this problem the tables of chords on pages 78 to 89 are used. Find in the table the length of the chord to a radius  $r$ , for the given angle. Then take the radius, as large as convenient and describe an arc of a circle  $bc$ , with  $A$  as center. Multiply the chord of the angle, found in the table, by the length of the radius  $Ab$ , and with the product as a new radius and with  $b$  as a center, describe a short arc cutting  $bc$  in  $d$ . Draw a line from  $A$  through  $d$  and it will make the required angle with  $DE$ .

**Example.** Draw a line from  $A$  on  $DE$ , making an angle of  $44^\circ 40'$  with  $DE$  (Fig. 57).

**Solution.** The largest convenient radius for the arc is 8 in. With  $A$  as a center and 8 in as a radius, describe the arc  $bc$ . In the table of chords, the chord for an angle or arc of  $44^\circ 40'$  to a radius  $r$  is 0.76. Multiplying this by 8 in, the length of the new radius is 6.08 in; and with this as radius and with  $b$  as center, describe an arc cutting  $bc$  in  $d$ .  $Ad$  will be the line required.




Fig. 57. Line Making Any Angle with Given Line

**Problem 8a.** To lay off a given angle approximately, by means of an ordinary two-foot rule.

Tables of Angles Corresponding to Openings of a Two-Foot Rule \*

In.	Deg. Min.	In.	Deg. Min.	In.	Deg. Min.	In.	Deg. Min.	In.	Deg. Min.
$\frac{1}{4}$	1 12	...	11 22	$4\frac{1}{2}$	21 37	...	32 3	$8\frac{3}{4}$	42 7
..	1 48	$2\frac{1}{2}$	11 58	...	22 13	$6\frac{3}{4}$	32 40	...	42 13
$\frac{1}{2}$	2 24	...	12 34	$\frac{3}{4}$	22 50	...	33 17	9	42 19
..	3 00	$\frac{3}{4}$	13 10	...	23 27	7	33 54	...	42 25
$\frac{3}{4}$	3 36	...	13 46	5	24 3	...	34 33	$\frac{1}{4}$	42 31
..	4 11	3	14 22	...	24 39	$\frac{1}{4}$	35 10	...	42 37
1	4 47	...	14 58	$\frac{1}{4}$	25 16	...	35 47	$\frac{1}{2}$	42 43
..	5 23	$\frac{1}{4}$	15 34	...	25 53	$\frac{1}{2}$	36 25	...	42 49
$\frac{1}{4}$	5 58	...	16 10	$\frac{1}{2}$	26 30	...	37 3	$\frac{3}{4}$	42 55
..	6 34	$\frac{1}{2}$	16 46	...	27 7	$\frac{3}{4}$	37 41	...	42 55
$\frac{1}{2}$	7 10	...	17 22	$\frac{3}{4}$	27 44	...	38 19	10	42 55
..	7 46	$\frac{3}{4}$	17 59	...	28 21	8	38 57	...	42 55
$\frac{3}{4}$	8 22	...	18 35	6	28 58	...	39 35	$\frac{1}{4}$	42 55
...	8 58	4	19 12	...	29 35	$\frac{1}{4}$	40 13	...	42 55
2	9 34	...	19 48	$\frac{1}{4}$	30 11	...	40 51	$\frac{1}{2}$	42 55
...	10 10	$\frac{1}{4}$	20 24	...	30 49	$\frac{1}{2}$	41 29	...	42 55
$\frac{1}{4}$	10 46	...	21 00	$\frac{1}{2}$	31 26	...	42 7	...	42 55

\* Trautwine.

By one leg of the rule on the paper or board with its inner edge coinciding with the given line. Open the rule until the distance between the inner edges at the ends correspond with that given for the angle in the following table; then draw a line by marking along the inner edge of the other leg, and it will give the required angle within a very close approximation.

**Problem 9.** To bisect a given angle, as  $BAC$  (Fig. 58).

With  $A$  as a center and any radius, describe an arc, as  $cb$ . With  $c$  and  $b$  as centers, and any radius greater than one-half of  $cb$ , describe two arcs, intersecting at  $d$ . Draw from  $A$  a line through  $d$  and it will bisect the angle  $BAC$ .




Fig. 58. Angle Bisected

**Problem 10.** To bisect the angle included between two lines, as  $AB$  and  $CD$ , when the vertex of the angle is not on the drawing (Fig. 59).




Fig. 59. Angle Bisected. Angle not on Drawing

Draw  $fe$  parallel to  $AB$  and  $cd$  parallel to  $CD$ , so that the two lines intersect, as at  $i$ . Bisect the angle  $eid$ , as in the preceding problem, and draw a line through  $i$  and  $o$  which will bisect the angle between the two given lines.

**Problem 11.** Through two given points,  $B$  and  $C$ , to describe an arc of a circle with a given radius (Fig. 60).

With  $B$  and  $C$  as centers and with a radius equal to the given radius, describe two arcs intersecting at  $A$ . With  $A$  as a center and the same radius, describe the arc  $bc$ , which will pass through the given points,  $B$  and  $C$ .




Fig. 60. Circular Arc Through Two Given Points

Draw any chord in the circle, as  $ab$ , and bisect this chord by the perpendicular  $cd$ . This line will pass through the center of the circle and  $ef$  will be a diameter of the circle. Bisect  $ef$ , and the center  $o$  will be the center of the circle.

**Problem 12.** To find the center of a given circle (Fig. 61).

Draw any chord in the circle, as  $ab$ , and bisect this chord by the perpendicular  $cd$ . This line will pass through the center of the circle and  $ef$  will be a diameter of the circle. Bisect  $ef$ , and the center  $o$  will be the center of the circle.




Fig. 61. Center of Given Circle

**Problem 13.** To draw a circular arc through three points, as  $A$ ,  $B$  and  $C$  (Fig. 62). Draw lines from  $A$  to  $B$  and from  $B$  to  $C$ . Bisect  $AB$  and  $BC$  by the lines  $aa'$  and  $cc'$  and prolong these lines until they intersect at  $o$ , which will be the center for the arc sought. With  $o$  as a center and  $AO$  as radius, describe the arc  $ABC$ .




Fig. 62. Circular Arc Through Three Given Points




Fig. 63. Frame for Drawing Circular Arc

**Problem 14.** To describe a circular arc passing through three given points when the center is not available, by means of a triangle (Fig. 63).

Let  $A$ ,  $B$  and  $C$  be the given points. Insert two stiff pins or nails at  $A$  and  $C$ . Place two strips of wood,  $SS$ , as shown in the figure, one against  $A$ , the other against  $C$ , and inclined so that their intersection shall come at the third point  $B$ . Fasten the strips together at their intersection and nail a third strip of wood to their other ends, so as to make a firm triangle. Place the pencil-point at the vertex  $B$  and, keeping the edges of the triangle against  $A$  and  $C$ , move the triangle to the left and right. The pencil-point will describe the required arc.

When the points  $A$  and  $C$  are at the same distance from  $B$ , if a strip of wood is nailed to the triangle, so that its edge  $de$  is at right-angles to a line joining  $A$  and  $C$ , as the triangle is moved one way or the other, the edge  $de$  will always point to the center of the circle. This principle is used in linear perspective.

**Problem 15.** To describe a circular arc which will be tangent at a given point  $A$ , to a straight line, and pass through a given point,  $C$ , outside the line (Fig. 64).

Draw from  $A$  a line perpendicular to the given line. Connect  $A$  and  $C$  by a straight line and bisect this line by the perpendicular  $ac$ . The point where these two perpendiculars intersect is the center of the circle.




Fig. 64. Circular Arc Tangent to Line at Given Point




Fig. 65. Reversed Curve Between Parallel Lines

**Problem 16.** To connect two parallel lines by a reversed curve composed of two circular arcs of equal radius, and tangent to the lines at given points,  $A$  and  $B$  (Fig. 65).

Join  $A$  and  $B$  and divide the line into two equal parts at  $C$ . Bisect  $CA$  and  $CB$  by perpendiculars. At  $A$  and  $B$  erect perpendiculars to the given lines. The intersections  $a$  and  $b$  will be the centers of the arcs composing the required curve.



**Problem 17.** On a given line, as  $AB$  (Fig. 66), to construct a compound curve of three arcs of circles, the radii of the two side arcs being equal and of a given length, and their centers lying in the given line. The central arc is to pass through a given point,  $C$ , on the perpendicular bisecting the given line, and is to be tangent to the other two arcs.

**Solution.** Draw the perpendicular  $CD$ . Lay off  $Aa$ ,  $Bb$  and  $Cc$ , each equal to the given radius of the side arcs; draw  $ac$ ; erect  $a$  by a perpendicular. The intersection of this line with the perpendicular  $CD$  is the required center of the central arc.




Fig. 66. Curve of Three Circular Arcs

Through  $a$  and  $b$  draw the lines  $Dc$  and  $De'$ ; from  $a$  and  $b$ , with the given radius, equal to  $Aa$ ,  $Bb$ , describe the arcs  $Ae'$  and  $Be$ ; from  $D$  as a center, and with  $CD$  as a radius, describe the arc  $eCe'$  which completes the curve required.




Fig. 67. Equilateral Triangle on Given Base

**Problem 18.** To construct a triangle upon a given straight line or base, the length of the two sides being given (Figs. 67 and 68).

**First.** An equilateral triangle (Fig. 67). With the extremities  $A$  and  $B$  of the given line as centers and with  $AB$  as a radius, describe arcs cutting each other at  $C$ . Join  $AC$  and  $BC$ .

**Second.** A scalene triangle (Fig. 68). Let  $AD$  be the given base and the other sides be equal to  $C$  and  $B$ . With  $D$  as a center, and with a radius equal to  $C$ , describe at  $E$  an arc of indefinite length. With  $A$  as a center and with  $B$  as a radius, describe an arc cutting the first at  $E$ . Join  $E$  with  $A$  and  $D$ .  $ADE$  is the required triangle.




Fig. 68. Scalene Triangle on Given Base




Fig. 69. Triangle and Circumscribed Circle

**Problem 19.** To describe a circle about a triangle (Fig. 69).

Bisect two of the sides, as  $AC$  and  $CB$ , of the triangle, and at their centers, erect perpendicular lines,




Fig. 70. Triangle and Inscribed Circle

and  $b$ , intersecting at  $e$ . With  $e$  as a center, and  $eC$  as a radius, describe a circle. It will pass through  $A$  and  $B$ .

**Problem 20.** To inscribe a circle in a triangle (Fig. 70).

Bisect two of the angles,  $A$  and  $B$ , of the triangle by lines cutting each other at  $e$ . With  $e$  as a center, and with  $oe$  as a radius, describe a circle. It will be tangent to the other two sides.

**Problem 21.** To inscribe a square in a circle and to describe a circle about a square (Fig. 71).

To inscribe the square. Draw two diameters,  $AB$  and  $CD$ , at right-angles to each other. Join the points  $A$ ,  $D$ ,  $B$  and  $C$ .  $ADBC$  is the inscribed square.

To describe the circle. Draw the diagonals as before, intersecting at  $E$ , with  $E$  as a center and  $AE$  as a radius, describe the circle.




Fig. 71. Inscribed Square and Circumscribed Circle




Fig. 72. Inscribed Circle and Circumscribed Square

**Problem 22.** To inscribe a circle in a square and to describe a square about a circle (Fig. 72).

To inscribe the circle. Draw the diagonals  $AB$  and  $CD$ , intersecting at  $E$ . Draw the perpendicular  $EG$  to one of the sides. Then with  $E$  as a center and  $EG$  as a radius, describe a circle. It will be tangent to all four sides of the square.

To describe the square. Draw two diameters,  $AB$  and  $CD$ , at right-angles to each other, and prolonged beyond the circumference. Draw the diameter  $GF$ , bisecting the angle  $CEA$  or  $BED$ . Draw lines through  $G$  and  $F$  perpendicular to  $GF$ , and terminating in the diagonals. Draw  $AD$  and  $CB$  to complete the square.

**Problem 23.** To inscribe a pentagon in a circle (Fig. 73).




Fig. 73. Circle and Inscribed Pentagon




Fig. 74. Circle and Inscribed Hexagon

Draw two diameters,  $AB$  and  $CD$ , at right-angles to each other. Bisect  $AB$  at  $E$ . With  $E$  as a center and  $EC$  as a radius, cut  $OB$  at  $F$ . With  $C$  as a center and  $CF$  as a radius, cut the circle at  $G$  and  $H$ . With these points as centers and the same radius, cut the circle at  $I$  and  $J$ . Join  $I$ ,  $J$ ,  $G$ ,  $C$  and  $H$ .  $IJGCH$  is the inscribed regular pentagon.

**Problem 24.** To inscribe a regular hexagon in a circle (Fig. 74).

Lay off on the circumference the radius of the circle six times, and connect the points.

**Problem 25.** To construct a regular hexagon upon a given straight line,  $AB$  (Fig. 75).

From  $A$  and  $B$ , with a radius equal to  $AB$ , describe arcs intersecting at  $O$ . With  $O$  as a center and a radius equal to  $AB$ , describe a circle, and from  $A$  or  $B$  lay off the lengths  $BC$ ,  $CD$ ,  $DE$ ,  $EF$  and  $FA$  on the circumference of the circle.  $BCDEFA$  is the required regular hexagon.




Fig. 75. Regular Hexagon on Given Line




Fig. 76. Regular Octagon on Given Line

**Problem 26.** To construct a regular octagon upon a given straight line,  $AB$  (Fig. 76).

Produce the line  $AB$  both ways and draw the perpendiculars  $Aa$  and  $Bb$ , of definite length. Bisect the external angles at  $A$  and  $B$  and make the length of the bisecting lines equal to  $AB$ . From  $H$  and  $C$  draw lines parallel to  $Aa$  or  $Bb$  and equal in length to  $AB$ . From  $G$  and  $D$  as centers describe arcs, with radius  $AB$ , cutting the perpendiculars  $Aa$  and  $Bb$  in  $F$  and  $E$ . Draw  $GF$ ,  $FE$  and  $ED$ .  $ABCDEFGH$  is the required octagon.




Fig. 77. Square and Inscribed Regular Octagon




Fig. 78. Circle and Inscribed Regular Octagon

**Problem 27.** To construct a regular octagon in a square (Fig. 77).

Draw the diagonals  $AD$  and  $BC$  and from  $A$ ,  $B$ ,  $C$  and  $D$ , with a radius equal to  $AO$ , describe arcs cutting the sides of the square in  $a$ ,  $b$ ,  $c$ ,  $d$ ,  $e$ ,  $f$ ,  $g$  and  $h$ . Draw  $ah$ ,  $hg$ ,  $gf$  and  $fe$ .  $ahgfedcba$  is the required octagon.

**Problem 28.** To inscribe a regular octagon in a circle (Fig. 78).

Draw two diameters,  $AB$  and  $CD$ , at right-angles to each other. Bisect angles  $AOD$  and  $AOC$  by the diameters  $EF$  and  $GH$ .  $AEDHBFCGA$  is required octagon.

**Problem 29.** To inscribe a circle within a regular polygon.

**First.** When the polygon has an even number of sides, as in Fig. 79. Bisect two opposite sides at  $A$  and  $B$ , draw  $AB$  and bisect it at  $C$  by a diagonal, connecting two opposite angles, as  $D$  and  $E$ . The circle drawn with a radius  $CD$  and with  $C$  as a center is the inscribed circle required.




Fig. 79. Regular Polygon, Even Number of Sides, with Inscribed and Circumscribed Circles




Fig. 80. Regular Polygon, Odd Number of Sides, with Inscribed and Circumscribed Circles

**Second.** When the number of sides is odd, as in Fig. 80. Bisect two adjacent sides as at  $A$  and  $B$ , and draw lines,  $AE$  and  $BD$ , to the opposite angles and intersecting at  $C$ . The circle drawn with  $C$  as a center and  $CA$  as a radius is the inscribed circle required.

**Problem 30.** To draw a circumscribing circle around a regular polygon.

**First.** When the number of sides is even, as in Fig. 79. Draw two diagonals from opposite angles, as  $ED$  and  $GH$ , intersecting at  $C$ . The circle drawn with  $C$  as a center and with  $CD$  as a radius is the circumscribing circle required.

**Second.** When the number of sides is odd, as in Fig. 80. Determine center,  $C$ , as in the last problem. The circle drawn with  $C$  as a center and with  $CA$  as a radius, is the circumscribing circle required.

## Problems on the Ellipse, the Parabola, the Hyperbola and the Cycloid

### The Ellipse

**Problem 31.** To describe an ellipse, the length and breadth, or the two axes being given.

**First Method** (Fig. 81), the two axes,  $AB$  and  $CD$ , being given. On  $AB$  and  $CD$  as diameters and from the same center,  $O$ , describe the circles  $AGBH$  and  $CLDK$ . Take any convenient number of points on the circumference of the outer circle, as  $b, b', b'',$  etc., and from them draw lines to the center,  $O$ , cutting the inner circle at the points  $a, a', a'',$  etc., respectively. From the points  $b, b',$  etc., draw lines parallel to the shorter axis  $CD$ ; and from the points

*d*, etc., draw lines parallel to the longer axis *AB*, and intersecting the first set of lines at *e*, *e'*, *e''*, etc. These last points will be points in the ellipse, and by determining a sufficient number of them, the ellipse can be drawn.




Fig. 81. Ellipse Described on Given Axes.

**Second Method (Fig. 82).** Take the straight-edge, made of a stiff piece of paper, cardboard or wood, and from some point as *a*, mark off *ab* equal to half the shorter diameter *CD*, and *ac* equal to half the longer diameter *AB*. Place the straight-edge so that the point *b* is on the longer and the point *c* on the shorter diameter. Then will the point *a* be over a point in the ellipse. Take on the paper a dot at *a* and move the straight-edge round, always keeping the points *b* and *c* over the major and minor axes respectively. In this way any number of points in the ellipse may be determined and the ellipse drawn.




Fig. 82. Ellipse Described with Straight-Edge

**Third Method (Fig. 83).** From the two axes, *AB* and *CD*, find the point *D* as a center, and a radius *AO*, equal to one-half of *AB*, describe an arc cutting *AB* at *F* and *F'*. These two points are called the foci of the ellipse. **Note.** One property of the ellipse is, that the sums of the distances of any point on the circumference from the foci are the same. Thus  $F'D + DF = F'G + GF$ .

Fix two pins in the axis  $AB$  at  $F$  and  $F'$  and loop upon them a thread, cord equal in length, when fastened to the pins, to  $AB$ , so as, when stretched as per dotted line  $FDF'$ , will just reach to the extremity  $D$  of the short axis. Place pencil-point inside the chord as at  $E$ , and move pencil along, keeping the cord stretched tight. The pencil point will trace the ellipse required.




Fig. 83. Ellipse Described with String and Pencil

**Problem 32.** To draw a tangent to an ellipse at a given point on the curve (Fig. 84).

Let it be required to draw a tangent at the point  $E$  on the ellipse shown. First determine the foci  $F$  and  $F'$  as the third method for describing an ellipse, and from  $E$  draw

lines  $EF$  and  $EF'$ . Prolong  $EF'$  to  $a$ , so that  $Ea$  equals  $EF$ . Bisect the arc  $aEF$  by describing arcs from  $a$  and  $F$  as centers, as shown at  $b$ , and through  $b$  draw a line through  $E$ . This line is the tangent required. If it is required to draw a line normal to the curve at  $E$ , as, for instance, the joint of an elliptical




Fig. 84. Tangent Drawn to Point on Ellipse

arch, bisect the angle  $FEF'$ , and draw the bisecting line through  $E$ , and it will be the normal to the curve and the proper line at that point for the joint of an elliptical arch.

**Problem 33.** To draw a tangent to an ellipse from a given point outside of the curve (Fig. 85).

From the given point  $T$  as a center, and with a radius equal to the distance to the nearer focus  $F$ , describe an arc of a circle. From  $F'$  as a center, and with a radius equal to the length of the longer axis of the ellipse, describe an arc cutting the circle just described at  $a$  and  $b$ . Draw lines from  $F'$  to  $a$  and  $b$ , cutting the ellipse at  $E$  and  $G$ . Draw lines from  $T$  through  $E$  and  $G$  and they will be the tangents required.




Fig. 85. Tangent Drawn to Ellipse from Point Outside

**Prob 34.** To describe an ellipse approximately, by means of circular arcs.  
**1.** With arcs of two radii (Fig. 86). Take half the difference of the two axes  $AB$  and  $CD$ , and set it off from the center  $O$  to  $a$  and  $c$  on  $OA$  and  $OC$ ; and on  $AB$  set off half  $ac$  from  $a$  to  $d$ ; draw  $di$  parallel to  $ac$ ; set off  $Oe$  equal to  $ai$  and draw  $em$  and  $dm$  parallel respectively to  $id$  and  $ie$ . With





Fig. 86. Ellipse Described with Circular Arcs of Two Radii

a center and with a radius  $mC$ , describe an arc through  $C$ , terminating in points 1 and 2 on  $md$  and  $me$  produced. With  $i$  as a center, and with  $iD$  as a radius, describe an arc through  $D$ , terminating in points 3 and 4 on  $ie$  and  $id$  produced. With  $d$  and  $e$  as centers, describe arcs through  $A$  and  $B$ , connecting points 1 and 4 and 2 and 3. The four arcs thus described form approximately the ellipse. This method is not satisfactory when the conjugate or minor axis is less than two-thirds the transverse or major axis.

Another method of approximating an ellipse by means of arcs of two is shown in Fig. 87, the axis major  $AB$  and the semiminor axis  $OC$



given. Draw the tangle  $AabBA$ , and diagonal  $CB$ . Lay  $Cc$  equal to the distance between  $OB$  and  $OC$ . Bisect  $cB$  at  $M$ . Erect the perpendicular  $YD$ , intersecting  $CB$  produced at  $Y$  and  $AB$  at  $x$ . Make  $Ox'$  equal to  $Ox$ . Then will  $x$ ,  $x'$ , and  $C$  be the three centers required, the curve coming tangent at  $A$  and at the corresponding point on the left side of the ellipse.

Fig. 87. Ellipse Described with Circular Arcs of Two Radii

fuller at the haunches than the curve drawn by the preceding method.

Second. With arcs of three radii (Fig. 88). On the transverse or major




Fig. 88. Ellipse Described with Circular Arcs of Three Radii

**AB** draw the rectangle  $AGEBA$ , equal in height to  $OC$ , half the conjugate minor axis. Draw  $AC$  and draw  $GD$  perpendicular to  $AC$ . Set off  $OK$  equal to  $OC$ .



on  $AK$  as a diameter describe the semicircle  $ANK$ . Extend  $OC$  to  $D$ . Set off  $OM$  equal to  $CL$ , and with  $D$  as a center and with a radius describe an arc. With  $A$  and  $B$  as centers and with a radius  $OL$ , cut  $AB$  at  $P$ . From  $H$  as a center, and with a radius  $HP$ , cut the arc  $ab$  at  $a$ .  $a$  and  $b$  are determined in like manner. The points  $H$ ,  $a$ ,  $D$ ,  $b$  and  $H'$ , are centers of the arcs required.

Draw the lines  $aH$ ,  $Da$ ,  $Db$ , and  $bH'$ , and thus determine the lengths of  $ax$ . This method is practicable for all ellipses. It is often employed for vaults, stone arches and bridges.

## The Parabola

**Problem 35.** To describe a parabola when the vertex  $A$ , the axis  $AB$  and a point  $M$ , of the curve are given (Fig. 89).

Construct the rectangle  $ABMCA$ . Divide  $MC$  into any number of equal parts, four for instance. Divide  $AC$  in like manner. Connect  $A1$ ,  $A2$  and  $A3$ . Through  $1'$ ,  $2'$ ,  $3'$ , draw parallels to the axis  $AB$ . The intersections  $I$ ,  $II$  and  $III$  of these lines, are points in the required curve.




Fig. 89. Parabola and Tangent to Point on Parabola

**Problem 36.** To draw a tangent to a given point,  $II$ , of the parabola (Fig. 89).

From the given point  $II$  let fall a perpendicular on the axis  $AB$  at  $b$ . Produce  $Ab$  to the left of  $A$ . Make  $Aa$  equal to  $Ab$ . A line drawn through  $a$  and  $II$  is the tangent required. The lines perpendicular to the tangent are called normals.

To draw a normal to any point, as  $I$ , the tangent to any other point,  $II$  being given.

Draw the normal  $IIc$ . From  $I$ , let fall a perpendicular  $Id$ , on the axis  $AB$ . Produce  $Ad$  equal to  $bc$ . The line  $Ic$  is the normal required. The tangent may be drawn at  $I$  by laying off a perpendicular to the normal  $Ic$  at  $I$ .

## The Hyperbola

From any point,  $P$ , of an hyperbola, two straight lines are drawn to two points, as  $F$  and  $F'$ , the foci of the hyperbola, their DIFFERENCE is always the same.

**Problem 37.** To describe an hyperbola when a vertex,  $a$ , the given difference of the foci,  $F$  are given (Fig. 90).

Draw the axis  $AB$  of the hyperbola, with the given distance  $ab$  and the focus

$F$  marked on it. From  $b$  lay off  $bF_1$  equal to  $aF$  to determine the other focus.




Fig. 90. Hyperbola Described

Take any point, as  $r$  and with  $ar$  as a radius as a center, describe two arcs above and below the line. With  $br$  as a radius, and  $b$  as a center, describe arcs intersecting those just described, at  $P'$ . Take several points in the same way, as 3 and 4, and determine the corresponding points  $P_2$ ,  $P_4$  in the same way. The curve passing through these points is an hyperbola.

To draw a tangent to a point of an hyperbola, draw lines from the given point to each of the foci and bisect the angle thus formed. The bisecting line is the tangent required.

### The Cycloid

The CYCLOID is the curve described by a point on the circumference of a circle rolling in a straight line.

**Problem 38.** To describe a cycloid (Fig. 91).

Draw the straight line  $AB$ . Describe the generating circle tangent to the line at its middle point  $D$ , and through the center  $C$ , of the circle, draw a line




Fig. 91. Cycloid Described

Draw the line  $EE$  parallel to  $AB$ . Let fall a perpendicular from  $C$  upon  $AB$ . Divide the circumference into any number of equal parts, for example, six. Lay off on  $CE$  distances  $C1'$ ,  $1'2'$ , etc., equal to the divisions of the circumference. Draw the chords  $D1$ ,  $D2$ , etc. From the points  $1'$ ,  $2'$ ,  $3'$ , etc., on the line  $EE$  with radii equal to the generating circle, describe arcs as shown. From points  $1'$ ,  $2'$ ,  $3'$ ,  $4'$ ,  $5'$ , etc., on the line  $BA$ , and with radii equal respectively to the chords  $D1$ ,  $D2$ ,  $D3$ ,  $D4$ ,  $D5$ , describe arcs cutting the preceding arcs. The intersections are points of the required cycloid.

## Table of Contents

61

Table of Contents. Radius = 1.0000

[illegible]

Table of Chords (Continued). Radius = 1.0000

M.	11°	12°	13°	14°	15°	16°	17°	18°	19°	20°	21°
0'	0.1917	0.2091	0.2264	0.2437	0.2611	0.2783	0.2956	0.3129	0.3301	0.3473	0.364
1	0.1920	0.2093	0.2267	0.2440	0.2613	0.2786	0.2959	0.3132	0.3304	0.3476	0.364
2	0.1923	0.2096	0.2270	0.2443	0.2616	0.2789	0.2962	0.3134	0.3307	0.3479	0.365
3	0.1926	0.2099	0.2273	0.2446	0.2619	0.2792	0.2965	0.3137	0.3310	0.3482	0.365
4	0.1928	0.2102	0.2276	0.2449	0.2622	0.2795	0.2968	0.3140	0.3312	0.3484	0.365
5	0.1931	0.2105	0.2279	0.2452	0.2625	0.2798	0.2971	0.3143	0.3315	0.3487	0.365
6	0.1934	0.2108	0.2281	0.2455	0.2628	0.2801	0.2973	0.3146	0.3318	0.3490	0.365
7	0.1937	0.2111	0.2284	0.2458	0.2631	0.2804	0.2976	0.3149	0.3321	0.3493	0.365
8	0.1940	0.2114	0.2287	0.2460	0.2634	0.2807	0.2979	0.3152	0.3324	0.3496	0.365
9	0.1943	0.2117	0.2290	0.2463	0.2636	0.2809	0.2982	0.3155	0.3327	0.3499	0.367
10	0.1946	0.2119	0.2293	0.2466	0.2639	0.2812	0.2985	0.3157	0.3330	0.3502	0.367
11	0.1949	0.2122	0.2296	0.2469	0.2642	0.2815	0.2988	0.3160	0.3333	0.3504	0.367
12	0.1952	0.2125	0.2299	0.2472	0.2645	0.2818	0.2991	0.3163	0.3335	0.3507	0.367
13	0.1955	0.2128	0.2302	0.2475	0.2648	0.2821	0.2994	0.3166	0.3338	0.3510	0.368
14	0.1957	0.2131	0.2305	0.2478	0.2651	0.2824	0.2996	0.3169	0.3341	0.3513	0.368
15	0.1960	0.2134	0.2307	0.2481	0.2654	0.2827	0.2999	0.3172	0.3344	0.3516	0.368
16	0.1963	0.2137	0.2310	0.2484	0.2657	0.2830	0.3002	0.3175	0.3347	0.3519	0.368
17	0.1966	0.2140	0.2313	0.2486	0.2660	0.2832	0.3005	0.3178	0.3350	0.3522	0.368
18	0.1969	0.2143	0.2316	0.2489	0.2662	0.2835	0.3008	0.3180	0.3353	0.3525	0.368
19	0.1972	0.2146	0.2319	0.2492	0.2665	0.2838	0.3011	0.3183	0.3355	0.3527	0.369
20	0.1975	0.2148	0.2322	0.2495	0.2668	0.2841	0.3014	0.3186	0.3358	0.3530	0.370
21	0.1978	0.2151	0.2325	0.2498	0.2671	0.2844	0.3017	0.3189	0.3361	0.3533	0.370
22	0.1981	0.2154	0.2328	0.2501	0.2674	0.2847	0.3019	0.3192	0.3364	0.3536	0.370
23	0.1983	0.2157	0.2331	0.2504	0.2677	0.2850	0.3022	0.3195	0.3367	0.3539	0.371
24	0.1986	0.2160	0.2333	0.2507	0.2680	0.2853	0.3025	0.3198	0.3370	0.3542	0.371
25	0.1989	0.2163	0.2336	0.2510	0.2683	0.2855	0.3028	0.3200	0.3373	0.3545	0.371
26	0.1992	0.2166	0.2339	0.2512	0.2685	0.2858	0.3031	0.3203	0.3376	0.3547	0.371
27	0.1995	0.2169	0.2342	0.2515	0.2688	0.2861	0.3034	0.3206	0.3378	0.3550	0.372
28	0.1998	0.2172	0.2345	0.2518	0.2691	0.2864	0.3037	0.3209	0.3381	0.3553	0.372
29	0.2001	0.2174	0.2348	0.2521	0.2694	0.2867	0.3040	0.3212	0.3384	0.3556	0.372
30	0.2004	0.2177	0.2351	0.2524	0.2697	0.2870	0.3042	0.3215	0.3387	0.3559	0.373
31	0.2007	0.2180	0.2354	0.2527	0.2700	0.2873	0.3045	0.3218	0.3390	0.3562	0.373
32	0.2010	0.2183	0.2357	0.2530	0.2703	0.2876	0.3048	0.3221	0.3393	0.3565	0.373
33	0.2012	0.2186	0.2359	0.2533	0.2706	0.2878	0.3051	0.3223	0.3396	0.3567	0.373
34	0.2015	0.2189	0.2362	0.2536	0.2709	0.2881	0.3054	0.3226	0.3398	0.3570	0.374
35	0.2018	0.2192	0.2365	0.2538	0.2711	0.2884	0.3057	0.3229	0.3401	0.3573	0.374
36	0.2021	0.2195	0.2368	0.2541	0.2714	0.2887	0.3060	0.3232	0.3404	0.3576	0.374
37	0.2024	0.2198	0.2371	0.2544	0.2717	0.2890	0.3063	0.3235	0.3407	0.3579	0.375
38	0.2027	0.2200	0.2374	0.2547	0.2720	0.2893	0.3065	0.3238	0.3410	0.3582	0.375
39	0.2030	0.2203	0.2377	0.2550	0.2723	0.2896	0.3068	0.3241	0.3413	0.3585	0.375
40	0.2033	0.2206	0.2380	0.2553	0.2726	0.2899	0.3071	0.3244	0.3416	0.3587	0.375
41	0.2036	0.2209	0.2383	0.2556	0.2729	0.2902	0.3074	0.3246	0.3419	0.3590	0.375
42	0.2038	0.2212	0.2385	0.2559	0.2732	0.2904	0.3077	0.3249	0.3421	0.3593	0.375
43	0.2041	0.2215	0.2388	0.2561	0.2734	0.2907	0.3080	0.3252	0.3424	0.3596	0.375
44	0.2044	0.2218	0.2391	0.2564	0.2737	0.2910	0.3083	0.3255	0.3427	0.3599	0.377
45	0.2047	0.2221	0.2394	0.2567	0.2740	0.2913	0.3086	0.3258	0.3430	0.3602	0.377
46	0.2050	0.2224	0.2397	0.2570	0.2743	0.2916	0.3088	0.3261	0.3433	0.3605	0.377
47	0.2053	0.2226	0.2400	0.2573	0.2746	0.2919	0.3091	0.3264	0.3436	0.3608	0.377
48	0.2056	0.2229	0.2403	0.2576	0.2749	0.2922	0.3094	0.3267	0.3439	0.3610	0.378
49	0.2059	0.2232	0.2406	0.2579	0.2752	0.2925	0.3097	0.3269	0.3441	0.3613	0.378
50	0.2062	0.2235	0.2409	0.2582	0.2755	0.2927	0.3100	0.3272	0.3444	0.3616	0.378
51	0.2065	0.2238	0.2411	0.2585	0.2758	0.2930	0.3103	0.3275	0.3447	0.3619	0.379
52	0.2067	0.2241	0.2414	0.2587	0.2760	0.2933	0.3106	0.3278	0.3450	0.3622	0.379
53	0.2070	0.2244	0.2417	0.2590	0.2763	0.2936	0.3109	0.3281	0.3453	0.3625	0.379
54	0.2073	0.2247	0.2420	0.2593	0.2766	0.2939	0.3111	0.3284	0.3456	0.3628	0.379
55	0.2076	0.2250	0.2423	0.2596	0.2769	0.2942	0.3114	0.3287	0.3459	0.3630	0.380
56	0.2079	0.2253	0.2426	0.2599	0.2772	0.2945	0.3117	0.3289	0.3462	0.3633	0.380
57	0.2082	0.2255	0.2429	0.2602	0.2775	0.2948	0.3120	0.3292	0.3464	0.3636	0.380
58	0.2085	0.2258	0.2432	0.2605	0.2778	0.2950	0.3123	0.3295	0.3467	0.3639	0.381
59	0.2088	0.2261	0.2434	0.2608	0.2781	0.2953	0.3126	0.3298	0.3470	0.3642	0.381
60	0.2091	0.2264	0.2437	0.2611	0.2783	0.2956	0.3129	0.3301	0.3473	0.3645	0.381

# Table of Chords

Table of Chords (Continued). Radius = 1.0000

27°	28°	29°	30°	31°	32°	33°	34°	35°	36°	37°	38°
0.4514	0.3967	0.4158	0.4329	0.4499	0.4669	0.4838	0.5008	0.5176	0.5345	0.5513	
0.4519	0.3990	0.4161	0.4332	0.4502	0.4672	0.4841	0.5010	0.5179	0.5348	0.5516	
0.4523	0.3993	0.4164	0.4334	0.4505	0.4675	0.4844	0.5013	0.5182	0.5350	0.5518	
0.4528	0.3996	0.4167	0.4337	0.4508	0.4677	0.4847	0.5016	0.5185	0.5353	0.5521	
0.4532	0.3999	0.4170	0.4340	0.4510	0.4680	0.4850	0.5019	0.5188	0.5356	0.5524	
0.4537	0.4002	0.4172	0.4343	0.4513	0.4683	0.4853	0.5022	0.5190	0.5359	0.5527	
0.4541	0.4004	0.4175	0.4346	0.4516	0.4686	0.4855	0.5024	0.5193	0.5362	0.5530	
0.4546	0.4007	0.4178	0.4349	0.4519	0.4689	0.4858	0.5027	0.5196	0.5364	0.5532	
0.4550	0.4010	0.4181	0.4352	0.4522	0.4692	0.4861	0.5030	0.5199	0.5367	0.5535	
0.4555	0.4013	0.4184	0.4354	0.4525	0.4694	0.4864	0.5033	0.5202	0.5370	0.5538	
0.4559	0.4016	0.4187	0.4357	0.4527	0.4697	0.4867	0.5036	0.5204	0.5373	0.5541	
0.4563	0.4019	0.4190	0.4360	0.4530	0.4700	0.4869	0.5039	0.5207	0.5376	0.5543	
0.4568	0.4022	0.4192	0.4363	0.4533	0.4703	0.4872	0.5041	0.5210	0.5378	0.5546	
0.4572	0.4024	0.4195	0.4366	0.4536	0.4706	0.4875	0.5044	0.5213	0.5381	0.5549	
0.4577	0.4027	0.4198	0.4369	0.4539	0.4708	0.4878	0.5047	0.5216	0.5384	0.5552	
0.4581	0.4030	0.4201	0.4371	0.4542	0.4711	0.4881	0.5050	0.5219	0.5387	0.5555	
0.4586	0.4033	0.4204	0.4374	0.4544	0.4714	0.4884	0.5053	0.5221	0.5390	0.5557	
0.4590	0.4036	0.4207	0.4377	0.4547	0.4717	0.4886	0.5055	0.5224	0.5392	0.5560	
0.4595	0.4039	0.4209	0.4380	0.4550	0.4720	0.4889	0.5058	0.5227	0.5395	0.5563	
0.4599	0.4042	0.4212	0.4383	0.4553	0.4723	0.4892	0.5061	0.5230	0.5398	0.5566	
0.4603	0.4044	0.4215	0.4386	0.4556	0.4725	0.4895	0.5064	0.5233	0.5401	0.5569	
0.4607	0.4047	0.4218	0.4388	0.4559	0.4728	0.4898	0.5067	0.5235	0.5404	0.5571	
0.4611	0.4050	0.4221	0.4391	0.4561	0.4731	0.4901	0.5070	0.5238	0.5406	0.5574	
0.4615	0.4053	0.4224	0.4394	0.4564	0.4734	0.4903	0.5072	0.5241	0.5409	0.5577	
0.4619	0.4056	0.4226	0.4397	0.4567	0.4737	0.4906	0.5075	0.5244	0.5412	0.5580	
0.4623	0.4059	0.4229	0.4400	0.4570	0.4740	0.4909	0.5078	0.5247	0.5415	0.5583	
0.4627	0.4061	0.4232	0.4403	0.4573	0.4742	0.4912	0.5081	0.5249	0.5418	0.5585	
0.4631	0.4064	0.4235	0.4405	0.4576	0.4745	0.4915	0.5084	0.5252	0.5420	0.5588	
0.4635	0.4067	0.4238	0.4408	0.4578	0.4748	0.4917	0.5086	0.5255	0.5423	0.5591	
0.4639	0.4070	0.4241	0.4411	0.4581	0.4751	0.4920	0.5089	0.5258	0.5426	0.5594	
0.4643	0.4073	0.4244	0.4414	0.4584	0.4754	0.4923	0.5092	0.5261	0.5429	0.5597	
0.4647	0.4076	0.4246	0.4417	0.4587	0.4757	0.4926	0.5095	0.5263	0.5432	0.5599	
0.4651	0.4079	0.4249	0.4420	0.4590	0.4759	0.4929	0.5098	0.5266	0.5434	0.5602	
0.4655	0.4081	0.4252	0.4422	0.4593	0.4762	0.4932	0.5100	0.5269	0.5437	0.5605	
0.4659	0.4084	0.4255	0.4425	0.4595	0.4765	0.4934	0.5103	0.5272	0.5440	0.5608	
0.4663	0.4087	0.4258	0.4428	0.4598	0.4768	0.4937	0.5106	0.5275	0.5443	0.5611	
0.4667	0.4090	0.4261	0.4431	0.4601	0.4771	0.4940	0.5109	0.5277	0.5446	0.5613	
0.4671	0.4093	0.4263	0.4434	0.4604	0.4773	0.4943	0.5112	0.5280	0.5448	0.5616	
0.4675	0.4096	0.4266	0.4437	0.4607	0.4776	0.4946	0.5115	0.5283	0.5451	0.5619	
0.4679	0.4098	0.4269	0.4439	0.4609	0.4779	0.4948	0.5117	0.5286	0.5454	0.5622	
0.4683	0.4101	0.4272	0.4442	0.4612	0.4782	0.4951	0.5120	0.5289	0.5457	0.5625	
0.4687	0.4104	0.4275	0.4445	0.4615	0.4785	0.4954	0.5123	0.5291	0.5460	0.5627	
0.4691	0.4107	0.4278	0.4448	0.4618	0.4788	0.4957	0.5126	0.5294	0.5462	0.5630	
0.4695	0.4110	0.4280	0.4451	0.4621	0.4790	0.4960	0.5129	0.5297	0.5465	0.5633	
0.4699	0.4113	0.4283	0.4454	0.4624	0.4793	0.4963	0.5131	0.5300	0.5468	0.5636	
0.4703	0.4116	0.4286	0.4456	0.4626	0.4796	0.4965	0.5134	0.5303	0.5471	0.5638	
0.4707	0.4118	0.4289	0.4459	0.4629	0.4799	0.4968	0.5137	0.5306	0.5474	0.5641	
0.4711	0.4121	0.4292	0.4462	0.4632	0.4802	0.4971	0.5140	0.5308	0.5476	0.5644	
0.4715	0.4124	0.4295	0.4465	0.4635	0.4805	0.4974	0.5143	0.5311	0.5479	0.5647	
0.4719	0.4127	0.4298	0.4468	0.4638	0.4807	0.4977	0.5145	0.5314	0.5482	0.5650	
0.4723	0.4130	0.4300	0.4471	0.4641	0.4810	0.4979	0.5148	0.5317	0.5485	0.5652	
0.4727	0.4133	0.4303	0.4474	0.4643	0.4813	0.4982	0.5151	0.5320	0.5488	0.5655	
0.4731	0.4135	0.4306	0.4476	0.4646	0.4816	0.4985	0.5154	0.5322	0.5490	0.5658	
0.4735	0.4138	0.4309	0.4479	0.4649	0.4819	0.4988	0.5157	0.5325	0.5493	0.5661	
0.4739	0.4141	0.4312	0.4482	0.4652	0.4822	0.4991	0.5160	0.5328	0.5496	0.5664	
0.4743	0.4144	0.4315	0.4485	0.4655	0.4824	0.4994	0.5162	0.5331	0.5499	0.5666	
0.4747	0.4147	0.4317	0.4488	0.4658	0.4827	0.4996	0.5165	0.5334	0.5502	0.5669	
0.4751	0.4150	0.4320	0.4491	0.4660	0.4830	0.4999	0.5168	0.5336	0.5504	0.5672	
0.4755	0.4153	0.4323	0.4493	0.4663	0.4833	0.5002	0.5171	0.5339	0.5507	0.5675	
0.4759	0.4155	0.4326	0.4496	0.4666	0.4836	0.5005	0.5174	0.5342	0.5510	0.5678	
0.4763	0.4158	0.4329	0.4499	0.4669	0.4838	0.5008	0.5176	0.5345	0.5513	0.5680	

Table of Chords (Continued). Radius = 1.0000

33°	34°	35°	36°	37°	38°	39°	40°	41°	42°	43°
0.5680	0.5647	0.6014	0.6180	0.6346	0.6511	0.6676	0.6840	0.7004	0.7167	0.7330
0.5683	0.5850	0.6017	0.6183	0.6349	0.6514	0.6679	0.6843	0.7007	0.7170	0.7333
0.5686	0.5853	0.6020	0.6186	0.6352	0.6517	0.6682	0.6846	0.7010	0.7173	0.7336
0.5689	0.5856	0.6022	0.6189	0.6354	0.6520	0.6684	0.6849	0.7012	0.7176	0.7339
0.5691	0.5859	0.6025	0.6191	0.6357	0.6522	0.6687	0.6851	0.7015	0.7178	0.7341
0.5694	0.5861	0.6028	0.6194	0.6360	0.6525	0.6690	0.6854	0.7018	0.7181	0.7344
0.5697	0.5864	0.6031	0.6197	0.6363	0.6528	0.6693	0.6857	0.7020	0.7184	0.7346
0.5700	0.5867	0.6034	0.6200	0.6365	0.6531	0.6695	0.6860	0.7023	0.7186	0.7349
0.5703	0.5870	0.6036	0.6202	0.6368	0.6533	0.6698	0.6862	0.7026	0.7189	0.7352
0.5706	0.5872	0.6039	0.6205	0.6371	0.6536	0.6701	0.6865	0.7029	0.7192	0.7354
0.5708	0.5875	0.6042	0.6208	0.6374	0.6539	0.6704	0.6868	0.7031	0.7195	0.7357
0.5711	0.5878	0.6045	0.6211	0.6376	0.6542	0.6706	0.6870	0.7034	0.7197	0.7360
0.5714	0.5881	0.6047	0.6214	0.6379	0.6544	0.6709	0.6873	0.7037	0.7200	0.7363
0.5717	0.5884	0.6050	0.6216	0.6382	0.6547	0.6712	0.6876	0.7040	0.7203	0.7366
0.5719	0.5886	0.6053	0.6219	0.6385	0.6550	0.6715	0.6879	0.7042	0.7206	0.7369
0.5722	0.5889	0.6056	0.6222	0.6387	0.6553	0.6717	0.6881	0.7045	0.7208	0.7371
0.5725	0.5892	0.6058	0.6225	0.6390	0.6555	0.6720	0.6884	0.7048	0.7211	0.7373
0.5728	0.5895	0.6061	0.6227	0.6393	0.6558	0.6723	0.6887	0.7050	0.7214	0.7376
0.5730	0.5897	0.6064	0.6230	0.6396	0.6561	0.6725	0.6890	0.7053	0.7216	0.7379
0.5733	0.5900	0.6067	0.6233	0.6398	0.6564	0.6728	0.6892	0.7056	0.7219	0.7381
0.5736	0.5903	0.6070	0.6236	0.6401	0.6566	0.6731	0.6895	0.7059	0.7222	0.7384
0.5739	0.5906	0.6072	0.6238	0.6404	0.6569	0.6734	0.6898	0.7061	0.7224	0.7387
0.5742	0.5909	0.6075	0.6241	0.6407	0.6572	0.6736	0.6901	0.7064	0.7227	0.7390
0.5744	0.5911	0.6078	0.6244	0.6410	0.6575	0.6739	0.6903	0.7067	0.7230	0.7393
0.5747	0.5914	0.6081	0.6247	0.6412	0.6577	0.6742	0.6906	0.7069	0.7232	0.7396
0.5750	0.5917	0.6083	0.6249	0.6415	0.6580	0.6745	0.6909	0.7072	0.7235	0.7399
0.5753	0.5920	0.6086	0.6252	0.6418	0.6583	0.6747	0.6911	0.7075	0.7238	0.7402
0.5756	0.5922	0.6089	0.6255	0.6421	0.6586	0.6750	0.6914	0.7078	0.7241	0.7405
0.5758	0.5925	0.6092	0.6258	0.6423	0.6588	0.6753	0.6917	0.7080	0.7243	0.7408
0.5761	0.5928	0.6095	0.6260	0.6426	0.6591	0.6756	0.6920	0.7083	0.7246	0.7411
0.5764	0.5931	0.6097	0.6263	0.6429	0.6594	0.6758	0.6922	0.7086	0.7249	0.7414
0.5767	0.5934	0.6100	0.6266	0.6432	0.6597	0.6761	0.6925	0.7089	0.7251	0.7416
0.5769	0.5936	0.6103	0.6269	0.6434	0.6599	0.6764	0.6928	0.7091	0.7254	0.7419
0.5772	0.5939	0.6106	0.6272	0.6437	0.6602	0.6767	0.6931	0.7094	0.7257	0.7422
0.5775	0.5942	0.6108	0.6274	0.6440	0.6605	0.6769	0.6933	0.7097	0.7260	0.7425
0.5778	0.5945	0.6111	0.6277	0.6443	0.6608	0.6772	0.6936	0.7099	0.7262	0.7428
0.5781	0.5947	0.6114	0.6280	0.6445	0.6610	0.6775	0.6939	0.7102	0.7265	0.7431
0.5783	0.5950	0.6117	0.6283	0.6448	0.6613	0.6777	0.6941	0.7105	0.7268	0.7434
0.5786	0.5953	0.6119	0.6285	0.6451	0.6616	0.6780	0.6944	0.7108	0.7270	0.7437
0.5789	0.5956	0.6122	0.6288	0.6454	0.6619	0.6783	0.6947	0.7110	0.7273	0.7440
0.5792	0.5959	0.6125	0.6291	0.6456	0.6621	0.6786	0.6950	0.7113	0.7276	0.7443
0.5795	0.5961	0.6128	0.6294	0.6459	0.6624	0.6788	0.6952	0.7116	0.7279	0.7446
0.5797	0.5964	0.6130	0.6296	0.6462	0.6627	0.6791	0.6955	0.7118	0.7281	0.7449
0.5800	0.5967	0.6133	0.6299	0.6465	0.6630	0.6794	0.6958	0.7121	0.7284	0.7452
0.5803	0.5970	0.6136	0.6302	0.6467	0.6632	0.6797	0.6961	0.7124	0.7287	0.7455
0.5806	0.5972	0.6139	0.6305	0.6470	0.6635	0.6799	0.6963	0.7127	0.7289	0.7458
0.5808	0.5975	0.6142	0.6307	0.6473	0.6638	0.6802	0.6966	0.7129	0.7292	0.7461
0.5811	0.5978	0.6144	0.6310	0.6476	0.6640	0.6805	0.6969	0.7132	0.7295	0.7464
0.5814	0.5981	0.6147	0.6313	0.6478	0.6643	0.6808	0.6971	0.7135	0.7298	0.7467
0.5817	0.5984	0.6150	0.6316	0.6481	0.6646	0.6810	0.6974	0.7137	0.7300	0.7470
0.5820	0.5986	0.6153	0.6318	0.6484	0.6649	0.6813	0.6977	0.7140	0.7303	0.7473
0.5822	0.5989	0.6155	0.6321	0.6487	0.6651	0.6816	0.6980	0.7143	0.7306	0.7476
0.5825	0.5992	0.6158	0.6324	0.6489	0.6654	0.6819	0.6982	0.7146	0.7308	0.7479
0.5828	0.5995	0.6161	0.6327	0.6492	0.6657	0.6821	0.6985	0.7148	0.7311	0.7482
0.5831	0.5997	0.6164	0.6330	0.6495	0.6660	0.6824	0.6988	0.7151	0.7314	0.7485
0.5834	0.6000	0.6166	0.6332	0.6498	0.6662	0.6827	0.6991	0.7154	0.7316	0.7488
0.5836	0.6003	0.6169	0.6335	0.6500	0.6665	0.6829	0.6993	0.7156	0.7319	0.7491
0.5839	0.6006	0.6172	0.6338	0.6503	0.6668	0.6832	0.6996	0.7159	0.7322	0.7494
0.5842	0.6009	0.6175	0.6341	0.6506	0.6671	0.6835	0.6999	0.7162	0.7325	0.7497
0.5845	0.6011	0.6178	0.6343	0.6509	0.6673	0.6838	0.7001	0.7165	0.7327	0.7499
0.5847	0.6014	0.6180	0.6346	0.6511	0.6676	0.6840	0.7004	0.7167	0.7330	0.7502



# Table of Chords

Table of Chords (Continued). Radius = 1.0000

N°	45°	46°	47°	48°	49°	50°	51°	52°	53°	54°
3020	7854	0.7815	0.7975	0.8125	0.8294	0.8452	0.8610	0.8767	0.8924	0.9080
3050	7856	0.7817	0.7978	0.8127	0.8297	0.8455	0.8613	0.8770	0.8927	0.9082
3080	7859	0.7820	0.7980	0.8140	0.8299	0.8458	0.8615	0.8773	0.8929	0.9085
3110	7862	0.7823	0.7983	0.8143	0.8302	0.8460	0.8618	0.8775	0.8932	0.9088
3140	7864	0.7825	0.7986	0.8145	0.8304	0.8463	0.8621	0.8778	0.8934	0.9090
3170	7867	0.7828	0.7988	0.8148	0.8307	0.8466	0.8623	0.8780	0.8937	0.9093
3200	7870	0.7831	0.7991	0.8151	0.8310	0.8468	0.8626	0.8783	0.8940	0.9095
3230	7872	0.7833	0.7994	0.8153	0.8312	0.8471	0.8629	0.8786	0.8942	0.9098
3260	7875	0.7836	0.7996	0.8156	0.8315	0.8473	0.8631	0.8788	0.8945	0.9101
3290	7878	0.7839	0.7999	0.8159	0.8318	0.8476	0.8634	0.8791	0.8947	0.9103
3320	7881	0.7841	0.8002	0.8161	0.8320	0.8479	0.8636	0.8794	0.8950	0.9106
3350	7883	0.7844	0.8004	0.8164	0.8323	0.8481	0.8639	0.8796	0.8953	0.9108
3380	7886	0.7847	0.8007	0.8167	0.8326	0.8484	0.8642	0.8799	0.8955	0.9111
3410	7889	0.7849	0.8010	0.8169	0.8328	0.8487	0.8644	0.8801	0.8958	0.9113
3440	7891	0.7852	0.8012	0.8172	0.8331	0.8489	0.8647	0.8804	0.8960	0.9116
3470	7894	0.7855	0.8015	0.8175	0.8334	0.8492	0.8650	0.8807	0.8963	0.9119
3500	7897	0.7857	0.8018	0.8177	0.8336	0.8495	0.8652	0.8809	0.8966	0.9121
3530	7899	0.7860	0.8020	0.8180	0.8339	0.8497	0.8655	0.8812	0.8968	0.9124
3560	7902	0.7863	0.8023	0.8183	0.8341	0.8500	0.8657	0.8814	0.8971	0.9126
3590	7905	0.7865	0.8026	0.8185	0.8344	0.8502	0.8660	0.8817	0.8973	0.9129
3620	7907	0.7868	0.8028	0.8188	0.8347	0.8505	0.8663	0.8820	0.8976	0.9132
3650	7910	0.7871	0.8031	0.8190	0.8349	0.8508	0.8665	0.8822	0.8979	0.9134
3680	7913	0.7873	0.8034	0.8193	0.8352	0.8510	0.8668	0.8825	0.8981	0.9137
3710	7915	0.7876	0.8036	0.8196	0.8355	0.8513	0.8671	0.8828	0.8984	0.9139
3740	7918	0.7879	0.8039	0.8198	0.8357	0.8516	0.8673	0.8830	0.8986	0.9142
3770	7921	0.7882	0.8042	0.8201	0.8360	0.8518	0.8676	0.8833	0.8989	0.9146
3800	7923	0.7884	0.8044	0.8204	0.8363	0.8521	0.8678	0.8835	0.8992	0.9147
3830	7926	0.7887	0.8047	0.8206	0.8365	0.8523	0.8681	0.8838	0.8994	0.9150
3860	7929	0.7890	0.8050	0.8209	0.8368	0.8526	0.8684	0.8841	0.8997	0.9152
3890	7931	0.7892	0.8052	0.8212	0.8371	0.8529	0.8686	0.8843	0.8999	0.9155
3920	7934	0.7895	0.8055	0.8214	0.8373	0.8531	0.8689	0.8846	0.9002	0.9157
3950	7937	0.7898	0.8058	0.8217	0.8376	0.8534	0.8692	0.8848	0.9005	0.9160
3980	7940	0.7900	0.8060	0.8220	0.8378	0.8537	0.8694	0.8851	0.9007	0.9163
4010	7942	0.7903	0.8063	0.8222	0.8381	0.8539	0.8697	0.8854	0.9010	0.9165
4040	7945	0.7906	0.8066	0.8225	0.8384	0.8542	0.8699	0.8856	0.9012	0.9168
4070	7948	0.7908	0.8068	0.8228	0.8386	0.8545	0.8702	0.8859	0.9015	0.9170
4100	7950	0.7911	0.8071	0.8230	0.8389	0.8547	0.8705	0.8861	0.9018	0.9173
4130	7953	0.7914	0.8074	0.8233	0.8392	0.8550	0.8707	0.8864	0.9020	0.9176
4160	7956	0.7916	0.8076	0.8236	0.8394	0.8552	0.8710	0.8867	0.9023	0.9178
4190	7958	0.7919	0.8079	0.8238	0.8397	0.8555	0.8712	0.8869	0.9025	0.9181
4220	7961	0.7922	0.8082	0.8241	0.8400	0.8558	0.8715	0.8872	0.9028	0.9183
4250	7964	0.7924	0.8084	0.8244	0.8402	0.8560	0.8718	0.8874	0.9031	0.9186
4280	7966	0.7927	0.8087	0.8246	0.8405	0.8563	0.8720	0.8877	0.9033	0.9188
4310	7969	0.7930	0.8090	0.8249	0.8408	0.8566	0.8723	0.8880	0.9036	0.9191
4340	7972	0.7932	0.8092	0.8251	0.8410	0.8568	0.8726	0.8882	0.9038	0.9194
4370	7974	0.7935	0.8095	0.8254	0.8413	0.8571	0.8728	0.8885	0.9041	0.9196
4400	7977	0.7938	0.8098	0.8257	0.8415	0.8573	0.8731	0.8887	0.9044	0.9199
4430	7980	0.7940	0.8100	0.8259	0.8418	0.8576	0.8734	0.8890	0.9046	0.9201
4460	7982	0.7943	0.8103	0.8262	0.8421	0.8579	0.8736	0.8893	0.9049	0.9204
4490	7985	0.7946	0.8105	0.8265	0.8423	0.8581	0.8739	0.8895	0.9051	0.9207
4520	7988	0.7948	0.8108	0.8267	0.8426	0.8584	0.8741	0.8898	0.9054	0.9209
4550	7991	0.7951	0.8111	0.8270	0.8429	0.8587	0.8744	0.8900	0.9056	0.9212
4580	7993	0.7954	0.8113	0.8273	0.8431	0.8589	0.8747	0.8903	0.9059	0.9214
4610	7996	0.7956	0.8116	0.8275	0.8434	0.8592	0.8749	0.8906	0.9062	0.9217
4640	7999	0.7959	0.8119	0.8278	0.8437	0.8594	0.8752	0.8908	0.9064	0.9219
4670	8001	0.7962	0.8121	0.8281	0.8439	0.8597	0.8754	0.8911	0.9067	0.9222
4700	8004	0.7964	0.8124	0.8283	0.8442	0.8600	0.8757	0.8914	0.9069	0.9225
4730	8007	0.7967	0.8127	0.8286	0.8444	0.8602	0.8760	0.8916	0.9072	0.9227
4760	8009	0.7970	0.8129	0.8289	0.8447	0.8605	0.8762	0.8919	0.9075	0.9230
4790	8012	0.7972	0.8132	0.8291	0.8450	0.8608	0.8765	0.8921	0.9077	0.9232
4820	8015	0.7975	0.8135	0.8294	0.8452	0.8610	0.8767	0.8924	0.9080	0.9235

Table of Chords (Continued). Radius = 1.0000

M.	55°	56°	57°	58°	59°	60°	61°	62°	63°	64°
0'	0.9235	0.9389	0.9543	0.9696	0.9848	1.0000	1.0151	1.0301	1.0450	1.0598
1	0.9238	0.9392	0.9546	0.9699	0.9851	1.0003	1.0153	1.0303	1.0452	1.0599
2	0.9240	0.9395	0.9548	0.9701	0.9854	1.0005	1.0155	1.0306	1.0455	1.0601
3	0.9243	0.9397	0.9551	0.9704	0.9856	1.0008	1.0158	1.0308	1.0457	1.0603
4	0.9245	0.9400	0.9553	0.9706	0.9859	1.0010	1.0161	1.0311	1.0460	1.0605
5	0.9248	0.9402	0.9556	0.9709	0.9861	1.0013	1.0163	1.0313	1.0462	1.0607
6	0.9250	0.9405	0.9559	0.9711	0.9864	1.0015	1.0166	1.0316	1.0465	1.0609
7	0.9253	0.9407	0.9561	0.9714	0.9866	1.0018	1.0168	1.0318	1.0467	1.0611
8	0.9256	0.9410	0.9564	0.9717	0.9869	1.0020	1.0171	1.0321	1.0470	1.0613
9	0.9258	0.9413	0.9566	0.9719	0.9871	1.0023	1.0173	1.0323	1.0472	1.0615
10	0.9261	0.9415	0.9569	0.9722	0.9874	1.0025	1.0176	1.0326	1.0475	1.0617
11	0.9263	0.9418	0.9571	0.9724	0.9876	1.0028	1.0178	1.0328	1.0477	1.0619
12	0.9266	0.9420	0.9574	0.9727	0.9879	1.0030	1.0181	1.0331	1.0480	1.0621
13	0.9268	0.9423	0.9576	0.9729	0.9881	1.0033	1.0183	1.0333	1.0482	1.0623
14	0.9271	0.9425	0.9579	0.9732	0.9884	1.0035	1.0186	1.0336	1.0485	1.0625
15	0.9274	0.9428	0.9581	0.9734	0.9886	1.0038	1.0188	1.0338	1.0487	1.0627
16	0.9276	0.9430	0.9584	0.9737	0.9889	1.0040	1.0191	1.0341	1.0490	1.0629
17	0.9279	0.9433	0.9587	0.9739	0.9891	1.0043	1.0193	1.0343	1.0492	1.0631
18	0.9281	0.9436	0.9589	0.9742	0.9894	1.0045	1.0196	1.0346	1.0495	1.0633
19	0.9284	0.9438	0.9592	0.9744	0.9897	1.0048	1.0198	1.0348	1.0497	1.0635
20	0.9287	0.9441	0.9594	0.9747	0.9899	1.0050	1.0201	1.0351	1.0500	1.0637
21	0.9289	0.9443	0.9597	0.9750	0.9902	1.0053	1.0203	1.0353	1.0502	1.0639
22	0.9292	0.9446	0.9599	0.9752	0.9904	1.0055	1.0206	1.0356	1.0504	1.0641
23	0.9294	0.9448	0.9602	0.9755	0.9907	1.0058	1.0208	1.0358	1.0507	1.0643
24	0.9297	0.9451	0.9604	0.9757	0.9909	1.0060	1.0211	1.0361	1.0509	1.0645
25	0.9299	0.9454	0.9607	0.9760	0.9912	1.0063	1.0213	1.0363	1.0512	1.0647
26	0.9302	0.9456	0.9610	0.9762	0.9914	1.0065	1.0216	1.0366	1.0514	1.0649
27	0.9305	0.9459	0.9612	0.9765	0.9917	1.0068	1.0218	1.0368	1.0517	1.0651
28	0.9307	0.9461	0.9615	0.9767	0.9919	1.0070	1.0221	1.0370	1.0519	1.0653
29	0.9310	0.9464	0.9617	0.9770	0.9922	1.0073	1.0223	1.0373	1.0522	1.0655
30	0.9312	0.9466	0.9620	0.9772	0.9924	1.0075	1.0226	1.0375	1.0524	1.0657
31	0.9315	0.9469	0.9622	0.9775	0.9927	1.0078	1.0228	1.0378	1.0527	1.0659
32	0.9317	0.9472	0.9625	0.9778	0.9929	1.0080	1.0231	1.0380	1.0529	1.0661
33	0.9320	0.9474	0.9627	0.9780	0.9932	1.0083	1.0233	1.0383	1.0532	1.0663
34	0.9323	0.9477	0.9630	0.9783	0.9934	1.0086	1.0236	1.0385	1.0534	1.0665
35	0.9325	0.9479	0.9633	0.9785	0.9937	1.0088	1.0238	1.0388	1.0537	1.0667
36	0.9328	0.9482	0.9635	0.9788	0.9939	1.0091	1.0241	1.0390	1.0539	1.0669
37	0.9330	0.9484	0.9638	0.9790	0.9942	1.0093	1.0243	1.0393	1.0542	1.0671
38	0.9333	0.9487	0.9640	0.9793	0.9945	1.0096	1.0246	1.0395	1.0544	1.0673
39	0.9335	0.9489	0.9643	0.9795	0.9947	1.0098	1.0248	1.0398	1.0547	1.0675
40	0.9338	0.9492	0.9645	0.9798	0.9950	1.0101	1.0251	1.0400	1.0549	1.0677
41	0.9341	0.9495	0.9648	0.9800	0.9952	1.0103	1.0253	1.0403	1.0551	1.0679
42	0.9343	0.9497	0.9650	0.9803	0.9955	1.0106	1.0256	1.0405	1.0554	1.0681
43	0.9346	0.9500	0.9653	0.9805	0.9957	1.0108	1.0258	1.0408	1.0556	1.0683
44	0.9348	0.9502	0.9655	0.9808	0.9960	1.0111	1.0261	1.0410	1.0559	1.0685
45	0.9351	0.9505	0.9658	0.9810	0.9962	1.0113	1.0263	1.0413	1.0561	1.0687
46	0.9353	0.9507	0.9661	0.9813	0.9965	1.0116	1.0266	1.0415	1.0564	1.0689
47	0.9356	0.9510	0.9663	0.9816	0.9967	1.0118	1.0268	1.0418	1.0566	1.0691
48	0.9359	0.9512	0.9666	0.9818	0.9970	1.0121	1.0271	1.0420	1.0569	1.0693
49	0.9361	0.9515	0.9668	0.9821	0.9972	1.0123	1.0273	1.0423	1.0571	1.0695
50	0.9364	0.9518	0.9671	0.9823	0.9975	1.0126	1.0276	1.0425	1.0574	1.0697
51	0.9366	0.9520	0.9673	0.9826	0.9977	1.0128	1.0278	1.0428	1.0576	1.0699
52	0.9369	0.9523	0.9676	0.9828	0.9980	1.0131	1.0281	1.0430	1.0579	1.0701
53	0.9371	0.9525	0.9678	0.9831	0.9982	1.0133	1.0283	1.0433	1.0581	1.0703
54	0.9374	0.9528	0.9681	0.9833	0.9985	1.0136	1.0286	1.0435	1.0584	1.0705
55	0.9377	0.9530	0.9683	0.9836	0.9987	1.0138	1.0288	1.0438	1.0586	1.0707
56	0.9379	0.9533	0.9686	0.9838	0.9990	1.0141	1.0291	1.0440	1.0589	1.0709
57	0.9382	0.9536	0.9689	0.9841	0.9992	1.0143	1.0293	1.0443	1.0591	1.0711
58	0.9384	0.9538	0.9691	0.9843	0.9995	1.0146	1.0296	1.0445	1.0593	1.0713
59	0.9387	0.9541	0.9694	0.9846	0.9998	1.0148	1.0298	1.0447	1.0596	1.0715
60	0.9389	0.9543	0.9696	0.9848	1.0000	1.0151	1.0301	1.0450	1.0598	1.0717



Table of Chords (Continued). Radius = 1.0000

°	66°	67°	68°	69°	70°	71°	72°	73°	M.
1.544	1.0593	1.1036	1.1184	1.1328	1.1472	1.1614	1.1756	1.1896	0'
1.545	1.0595	1.1041	1.1186	1.1331	1.1474	1.1616	1.1758	1.1899	1
1.546	1.0598	1.1044	1.1189	1.1333	1.1476	1.1619	1.1760	1.1901	2
1.547	1.0600	1.1046	1.1191	1.1335	1.1479	1.1621	1.1763	1.1903	3
1.548	1.0603	1.1048	1.1194	1.1338	1.1481	1.1624	1.1765	1.1906	4
1.549	1.0605	1.1051	1.1196	1.1340	1.1483	1.1626	1.1767	1.1908	5
1.550	1.0607	1.1053	1.1198	1.1342	1.1486	1.1628	1.1770	1.1910	6
1.551	1.0610	1.1056	1.1201	1.1345	1.1488	1.1631	1.1772	1.1913	7
1.552	1.0612	1.1058	1.1203	1.1347	1.1491	1.1633	1.1775	1.1915	8
1.553	1.0615	1.1016	1.1206	1.1350	1.1493	1.1635	1.1777	1.1917	9
1.554	1.0617	1.1063	1.1208	1.1352	1.1495	1.1638	1.1779	1.1920	10
1.555	1.0620	1.1065	1.1210	1.1354	1.1498	1.1640	1.1782	1.1922	11
1.556	1.0622	1.1068	1.1213	1.1357	1.1500	1.1642	1.1784	1.1924	12
1.557	1.0624	1.1070	1.1215	1.1359	1.1502	1.1645	1.1786	1.1927	13
1.558	1.0627	1.1073	1.1218	1.1362	1.1505	1.1647	1.1789	1.1929	14
1.559	1.0629	1.1075	1.1220	1.1364	1.1507	1.1650	1.1791	1.1931	15
1.560	1.0632	1.1078	1.1222	1.1366	1.1510	1.1652	1.1793	1.1934	16
1.561	1.0634	1.1080	1.1225	1.1369	1.1512	1.1654	1.1796	1.1936	17
1.562	1.0637	1.1082	1.1227	1.1371	1.1514	1.1657	1.1798	1.1938	18
1.563	1.0639	1.1085	1.1230	1.1374	1.1517	1.1659	1.1800	1.1941	19
1.564	1.0642	1.1087	1.1232	1.1376	1.1519	1.1661	1.1803	1.1943	20
1.565	1.0644	1.1090	1.1234	1.1378	1.1522	1.1664	1.1805	1.1946	21
1.566	1.0646	1.1092	1.1237	1.1381	1.1524	1.1666	1.1807	1.1948	22
1.567	1.0649	1.1094	1.1239	1.1383	1.1526	1.1668	1.1810	1.1950	23
1.568	1.0651	1.1097	1.1242	1.1386	1.1529	1.1671	1.1812	1.1952	24
1.569	1.0654	1.1099	1.1244	1.1388	1.1531	1.1673	1.1814	1.1955	25
1.570	1.0656	1.1102	1.1246	1.1390	1.1533	1.1676	1.1817	1.1957	26
1.571	1.0659	1.1104	1.1249	1.1393	1.1536	1.1678	1.1819	1.1959	27
1.572	1.0661	1.1107	1.1251	1.1395	1.1538	1.1680	1.1821	1.1962	28
1.573	1.0663	1.1109	1.1254	1.1398	1.1541	1.1683	1.1824	1.1964	29
1.574	1.0666	1.1111	1.1256	1.1400	1.1543	1.1685	1.1826	1.1966	30
1.575	1.0668	1.1114	1.1258	1.1402	1.1545	1.1687	1.1829	1.1969	31
1.576	1.0671	1.1116	1.1261	1.1405	1.1548	1.1690	1.1831	1.1971	32
1.577	1.0673	1.1119	1.1263	1.1407	1.1550	1.1692	1.1833	1.1973	33
1.578	1.0676	1.1121	1.1266	1.1409	1.1552	1.1694	1.1836	1.1976	34
1.579	1.0678	1.1123	1.1268	1.1412	1.1555	1.1697	1.1838	1.1978	35
1.580	1.0680	1.1126	1.1271	1.1414	1.1557	1.1699	1.1840	1.1980	36
1.581	1.0683	1.1128	1.1273	1.1417	1.1560	1.1702	1.1843	1.1983	37
1.582	1.0685	1.1131	1.1275	1.1419	1.1562	1.1704	1.1845	1.1985	38
1.583	1.0688	1.1133	1.1278	1.1421	1.1564	1.1706	1.1847	1.1987	39
1.584	1.0690	1.1136	1.1280	1.1424	1.1567	1.1709	1.1850	1.1990	40
1.585	1.0693	1.1138	1.1283	1.1426	1.1569	1.1711	1.1852	1.1992	41
1.586	1.0695	1.1140	1.1285	1.1429	1.1571	1.1713	1.1854	1.1994	42
1.587	1.0697	1.1143	1.1287	1.1431	1.1574	1.1716	1.1857	1.1997	43
1.588	1.0699	1.1145	1.1290	1.1433	1.1576	1.1718	1.1859	1.1999	44
1.589	1.0702	1.1148	1.1292	1.1436	1.1579	1.1720	1.1861	1.2001	45
1.590	1.0705	1.1150	1.1295	1.1438	1.1581	1.1723	1.1864	1.2004	46
1.591	1.0707	1.1152	1.1297	1.1441	1.1583	1.1725	1.1866	1.2006	47
1.592	1.0710	1.1155	1.1299	1.1443	1.1586	1.1727	1.1868	1.2008	48
1.593	1.0712	1.1157	1.1302	1.1445	1.1588	1.1730	1.1871	1.2011	49
1.594	1.0714	1.1160	1.1304	1.1448	1.1590	1.1732	1.1873	1.2013	50
1.595	1.0717	1.1162	1.1307	1.1450	1.1593	1.1735	1.1875	1.2015	51
1.596	1.0719	1.1165	1.1309	1.1452	1.1595	1.1737	1.1878	1.2018	52
1.597	1.0722	1.1167	1.1311	1.1455	1.1598	1.1739	1.1880	1.2020	53
1.598	1.0724	1.1169	1.1314	1.1457	1.1600	1.1742	1.1882	1.2022	54
1.599	1.0727	1.1172	1.1316	1.1460	1.1602	1.1744	1.1885	1.2025	55
1.600	1.0729	1.1174	1.1319	1.1462	1.1605	1.1746	1.1887	1.2027	56
1.601	1.0731	1.1177	1.1321	1.1464	1.1607	1.1749	1.1889	1.2029	57
1.602	1.0734	1.1179	1.1323	1.1467	1.1609	1.1751	1.1892	1.2032	58
1.603	1.0736	1.1181	1.1326	1.1469	1.1612	1.1753	1.1894	1.2034	59
1.604	1.0739	1.1184	1.1328	1.1472	1.1614	1.1756	1.1896	1.2036	60

---

**Table of Chords (Continued). Radius = 1.0000**


---

# Table of Chords

Table of Chords (Continued). Radius.

Table of Chords (Continued).					Radius.
	84°	85°	86°	87°	
1 3383	1 3383	1 3512	1 3640	1 3767	
1 3385	1 3385	1 3514	1 3642	1 3769	
1 3387	1 3387	1 3516	1 3644	1 3771	
1 3389	1 3389	1 3518	1 3646	1 3773	
1 3391	1 3391	1 3520	1 3648	1 3776	
1 3393	1 3393	1 3523	1 3651	1 3778	
1 3395	1 3395	1 3525	1 3653	1 3780	
1 3398	1 3398	1 3527	1 3655	1 3782	
1 3400	1 3400	1 3529	1 3657	1 3784	
1 3402	1 3402	1 3531	1 3659	1 3786	
1 3404	1 3404	1 3533	1 3661	1 3788	
1 3406	1 3406	1 3535	1 3663	1 3790	
1 3409	1 3409	1 3538	1 3665	1 3792	
1 3411	1 3411	1 3540	1 3668	1 3794	
1 3413	1 3413	1 3542	1 3670	1 3797	
1 3415	1 3415	1 3544	1 3672	1 3799	
1 3417	1 3417	1 3546	1 3674	1 3801	
1 3419	1 3419	1 3548	1 3676	1 3803	
1 3421	1 3421	1 3550	1 3678	1 3805	
1 3424	1 3424	1 3552	1 3680	1 3807	
1 3426	1 3426	1 3555	1 3682	1 3809	
1 3428	1 3428	1 3557	1 3685	1 3811	
1 3430	1 3430	1 3559	1 3687	1 3813	
1 3432	1 3432	1 3561	1 3689	1 3816	
1 3434	1 3434	1 3563	1 3691	1 3818	
1 3437	1 3437	1 3565	1 3693	1 3820	
1 3439	1 3439	1 3567	1 3695	1 3822	
1 3441	1 3441	1 3570	1 3697	1 3824	
1 3443	1 3443	1 3572	1 3699	1 3826	
1 3445	1 3445	1 3574	1 3702	1 3828	
1 3447	1 3447	1 3576	1 3704	1 3830	
1 3449	1 3449	1 3578	1 3706	1 3832	
1 3452	1 3452	1 3580	1 3708	1 3834	
1 3454	1 3454	1 3582	1 3710	1 3837	
1 3456	1 3456	1 3585	1 3712	1 3839	
1 3458	1 3458	1 3587	1 3714	1 3841	
1 3460	1 3460	1 3589	1 3716	1 3843	
1 3462	1 3462	1 3591	1 3718	1 3845	
1 3465	1 3465	1 3593	1 3721	1 3847	
1 3467	1 3467	1 3595	1 3723	1 3849	
1 3469	1 3469	1 3597	1 3725	1 3851	
1 3471	1 3471	1 3599	1 3727	1 3853	
1 3473	1 3473	1 3602	1 3729	1 3855	
1 3475	1 3475	1 3604	1 3731	1 3858	
1 3477	1 3477	1 3606	1 3733	1 3860	
1 3480	1 3480	1 3608	1 3735	1 3862	
1 3482	1 3482	1 3610	1 3738	1 3864	
1 3484	1 3484	1 3612	1 3740	1 3866	
1 3486	1 3486	1 3614	1 3742	1 3868	
1 3488	1 3488	1 3617	1 3744	1 3870	
1 3490	1 3490	1 3619	1 3746	1 3872	
1 3492	1 3492	1 3621	1 3748	1 3874	
1 3495	1 3495	1 3623	1 3750	1 3876	
1 3497	1 3497	1 3625	1 3752	1 3879	
1 3499	1 3499	1 3627	1 3754	1 3881	
1 3501	1 3501	1 3629	1 3757	1 3883	
1 3503	1 3503	1 3631	1 3759	1 3885	
1 3505	1 3505	1 3634	1 3761	1 3887	
1 3508	1 3508	1 3636	1 3763	1 3890	
1 3510	1 3510	1 3638	1 3765	1 3891	
1 3512	1 3512	1 3640	1 3767	1 3893	

## Lengths and Bevels of Hip-Rafters and Jack-Rafters

**Method of Determining the Lengths and Bevels.** The lines  $ac$  (Fig. 92) represent the outside of the walls at the angle of a building; seat of the hip-rafter and  $gf$  of a jack-rafter. Draw  $eh$  at right-angles and make it equal to the rise of the roof; join  $b$  and  $h$  and  $hb$  will be the length of the hip-rafter. Through  $e$  draw  $di$  at right-angles to  $bc$ . With  $b$  as




Fig. 92. Lengths and Bevels of Hip-rafters and Jack-rafters

and with the radius  $bh$ , describe the arc  $hi$ , cutting  $di$  in  $i$ . Join  $b$  and  $i$  and extend  $gf$  to meet  $bi$  in  $j$ ; then  $gj$  is the length of the jack-rafter. The length of each jack-rafter is found in the same manner, by extending its seat to the line  $bi$ . From  $f$  draw  $fk$  at right-angles to  $fg$ ; also  $fl$  at right-angles to  $be$ . Make  $fk$  equal to  $fl$  by the arc  $lk$ , or make  $gk$  equal to  $gj$  by the arc  $jk$ ; then the angle at  $j$  is the TOP BEVEL of the jack-rafters, and the angle at  $k$  the DOWN BEVEL.

**Backing of the Hip-Rafter.** At any convenient point in  $be$  (Fig. 92) draw  $mn$  at right-angles to  $be$ . From  $o$  describe a circle, tangent to  $bh$ ,  $bc$  in  $s$ . Join  $m$  and  $s$  and  $n$  and  $s$ . The lines  $ms$  and  $ns$  form at  $s$  the angle for beveling the top of the hip-rafter.

## 5. TRIGONOMETRY

It is not the purpose of the author to teach the principles or uses of trigonometry; but for the benefit of those readers who have already acquired a knowledge of this science, the following convenient formulas and tables of natural sines, cosines, tangents and cotangents have been inserted. To those who know how to apply these trigonometric functions, they will often be found of great convenience and utility. These tables are taken, by permission, from Searle's Engineering, John Wiley & Sons, Inc., publishers.

## Trigonometrical Functions

Let  $\angle A$  (Fig. 93) = angle  $BAC$  = arc  $BF$  and let the radius  $AF = AB = AH = 1$

$$\begin{aligned}\sin A &= BC \\ \cos A &= AC \\ \tan A &= DF \\ \cot A &= HG \\ \sec A &= AD \\ \operatorname{cosec} A &= AG \\ \operatorname{versin} A &= CF = BE \\ \operatorname{covers} A &= BK = HL \\ \operatorname{exsec} A &= BD \\ \operatorname{coexsec} A &= BG \\ \operatorname{chord} A &= BF \\ \operatorname{chord} 2 A &= BI = 2 BC\end{aligned}$$




Fig. 93. Functions of Right-angled Triangle

In the right-angled triangle  $ABC$  (Fig. 93) let  $AB = c$ ,  $AC = b$  and  $BC = a$

$\sin A = \frac{a}{c} = \cos B$	(11) $a = c \sin A = b \tan A$
$\cos A = \frac{b}{c} = \sin B$	(12) $b = c \cos A = a \cot A$
$\tan A = \frac{a}{b} = \cot B$	(13) $c = \frac{a}{\sin A} = \frac{b}{\cos A}$
$\cot A = \frac{b}{a} = \tan B$	(14) $a = c \cos B = b \cot B$
$\sec A = \frac{c}{b} = \operatorname{cosec} B$	(15) $b = c \sin B = a \tan B$
$\operatorname{cosec} A = \frac{c}{a} = \sec B$	(16) $c = \frac{a}{\cos B} = \frac{b}{\sin B}$
$\operatorname{vers} A = \frac{c-b}{c} = \operatorname{covers} B$	(17) $a = \sqrt{(c+b)(c-b)}$
$\operatorname{exsec} A = \frac{c-b}{b} = \operatorname{coexsec} B$	(18) $b = \sqrt{(c+a)(c-a)}$
$\operatorname{covers} A = \frac{c-a}{c} = \operatorname{versin} B$	(19) $c = \sqrt{a^2 + b^2}$
$\operatorname{coexsec} A = \frac{c-a}{a} = \operatorname{exsec} B$	(20) $C = 90^\circ = A + B$

$$(21) \text{ area} = \frac{ab}{2}$$

Solution of Oblique Triangles




Fig. 94. Oblique-angled Triangle

	Given	Required	Formulas
(22)	A, B, a	C, b, c	$C = 180^\circ - (A + B)$ $b = \frac{a}{\sin A} \cdot \sin B$ $c = \frac{a}{\sin A} \sin (A + B)$
(23)	A, a, b	B, C, c	$\sin B = \frac{\sin A}{a} \cdot b$ $C = 180^\circ - (A + B)$ $c = \frac{a}{\sin A} \cdot \sin C$
(24)	C, a, b	$\frac{1}{2}(A + B)$	$\frac{1}{2}(A + B) = 90^\circ - \frac{1}{2}C$
(25)	.....	$\frac{1}{2}(A - B)$	$\tan \frac{1}{2}(A - B) = \frac{a - b}{a + b} \tan \frac{1}{2}(A + B)$
(26)	.....	A, B	$A = \frac{1}{2}(A + B) + \frac{1}{2}(A - B)$ $B = \frac{1}{2}(A + B) - \frac{1}{2}(A - B)$
(27)	.....	c	$c = (a + b) \frac{\cos \frac{1}{2}(A + B)}{\cos \frac{1}{2}(A - B)} = (a - b) \frac{\sin \frac{1}{2}(A + B)}{\sin \frac{1}{2}(A - B)}$
(28)	.....	Area	$K = \frac{1}{2}ab \sin C$
(29)	a, b, c	A	Let $s = \frac{1}{2}(a + b + c)$ ; $\sin \frac{1}{2}A = \sqrt{\frac{(s - b)(s - c)}{bc}}$
(30)	.....	.....	$\cos \frac{1}{2}A = \sqrt{\frac{s(s - a)}{bc}}$ ; $\tan \frac{1}{2}A = \sqrt{\frac{(s - b)(s - c)}{s(s - a)}}$
(31)	.....	.....	$\sin A = \frac{2\sqrt{s(s - a)(s - b)(s - c)}}{bc}$ $\text{vers } A = \frac{2(s - b)(s - c)}{bc}$
(32)	.....	Area	$K = \sqrt{s(s - a)(s - b)(s - c)}$
(33)	A, B, C, a	Area	$K = \frac{a^2 \sin B \sin C}{2 \sin A}$

## Oblique Triangles. General Formulas

$$1) \sin A = \frac{1}{\operatorname{cosec} A} = \sqrt{1 - \cos^2 A} = \tan A \cos A$$

$$2) \sin A = 2 \sin \frac{1}{2} A \cos \frac{1}{2} A = \operatorname{vers} A \cot \frac{1}{2} A$$

$$3) \sin A = \sqrt{\frac{1}{2} \operatorname{vers} 2A} = \sqrt{\frac{1}{2} (1 - \cos 2A)}$$

$$4) \cos A = \frac{1}{\sec A} = \sqrt{1 - \sin^2 A} = \cot A \sin A$$

$$5) \cos A = 1 - \operatorname{vers} A = 2 \cos^2 \frac{1}{2} A - 1 = 1 - 2 \sin^2 \frac{1}{2} A$$

$$6) \cos A = \cos^2 \frac{1}{2} A - \sin^2 \frac{1}{2} A = \sqrt{\frac{1}{2} + \frac{1}{2} \cos 2A}$$

$$7) \tan A = \frac{1}{\cot A} = \frac{\sin A}{\cos A} = \sqrt{\sec^2 A - 1}$$

$$8) \tan A = \sqrt{\frac{1}{\cos^2 A} - 1} = \frac{\sqrt{1 - \cos^2 A}}{\cos A} = \frac{\sin 2A}{1 + \cos 2A}$$

$$9) \tan A = \frac{1 - \cos 2A}{\sin 2A} = \frac{\operatorname{vers} 2A}{\sin 2A} = \operatorname{exsec} A \cot \frac{1}{2} A$$

$$10) \cot A = \frac{1}{\tan A} = \frac{\cos A}{\sin A} = \sqrt{\operatorname{cosec}^2 A - 1}$$

$$11) \cot A = \frac{\sin 2A}{1 - \cos 2A} = \frac{\sin 2A}{\operatorname{vers} 2A} = \frac{1 + \cos 2A}{\sin 2A}$$

$$12) \cot A = \frac{\tan \frac{1}{2} A}{\operatorname{exsec} A}$$

$$13) \operatorname{vers} A = 1 - \cos A = \sin A \tan \frac{1}{2} A = 2 \sin^2 \frac{1}{2} A$$

$$14) \operatorname{vers} A = \operatorname{exsec} A \cos A$$

$$15) \operatorname{exsec} A = \sec A - 1 = \tan A \tan \frac{1}{2} A = \frac{\operatorname{vers} A}{\cos A}$$

$$16) \sin \frac{1}{2} A = \sqrt{\frac{1 - \cos A}{2}} = \sqrt{\frac{\operatorname{vers} A}{2}}$$

$$17) \sin 2A = 2 \sin A \cos A$$

$$18) \cos \frac{1}{2} A = \sqrt{\frac{1 + \cos A}{2}}$$

$$19) \cos 2A = 2 \cos^2 A - 1 = \cos^2 A - \sin^2 A = 1 - 2 \sin^2 A$$

$$20) \tan \frac{1}{2} A = \frac{\tan A}{1 + \sec A} = \operatorname{cosec} A - \cot A = \frac{1 - \cos A}{\sin A} = \sqrt{\frac{1 - \cos A}{1 + \cos A}}$$

$$21) \tan 2A = \frac{2 \tan A}{1 - \tan^2 A}$$

$$22) \cot \frac{1}{2} A = \frac{\sin A}{\operatorname{vers} A} = \frac{1 + \cos A}{\sin A} = \frac{1}{\operatorname{cosec} A - \cot A}$$

$$23) \cot 2A = \frac{\cot^2 A - 1}{2 \cot A}$$

$$(57) \text{ vers } \frac{1}{2} A = \frac{\frac{1}{2} \text{ vers } A}{1 + \sqrt{1 - \frac{1}{2} \text{ vers } A}} = \frac{1 - \cos A}{2 + \sqrt{2(1 + \cos A)}}$$

$$(58) \text{ vers } 2 A = 2 \sin^2 A$$

$$(59) \text{ exsec } \frac{1}{2} A = \frac{1 - \cos A}{(1 + \cos A) + \sqrt{2(1 + \cos A)}}$$

$$(60) \text{ exsec } 2 A = \frac{2 \tan^2 A}{1 - \tan^2 A}$$

$$(61) \sin (A \pm B) = \sin A \cos B \pm \sin B \cos A$$

$$(62) \cos (A \pm B) = \cos A \cos B \mp \sin A \sin B$$

$$(63) \sin A + \sin B = 2 \sin \frac{1}{2} (A + B) \cos \frac{1}{2} (A - B)$$

$$(64) \sin A - \sin B = 2 \cos \frac{1}{2} (A + B) \sin \frac{1}{2} (A - B)$$

$$(65) \cos A + \cos B = 2 \cos \frac{1}{2} (A + B) \cos \frac{1}{2} (A - B)$$

$$(66) \cos B - \cos A = 2 \sin \frac{1}{2} (A + B) \sin \frac{1}{2} (A - B)$$

$$(67) \sin^2 A - \sin^2 B = \cos^2 B - \cos^2 A = \sin (A + B) \sin (A - B)$$

$$(68) \cos^2 A - \sin^2 B = \cos (A + B) \cos (A - B)$$

$$(69) \tan A + \tan B = \frac{\sin (A + B)}{\cos A \cos B}$$

$$(70) \tan A - \tan B = \frac{\sin (A - B)}{\cos A \cos B}$$


---







## Table of Natural Sines and Cosines

# Trigonometry

	15°		16°		17°		18°		19°	
	Sine	Cosine	Sine	Cosine	Sine	Cosine	Sine	Cosine	Sine	Cosine
0	.25882	.96593	.27504	.96126	.29237	.95630	.30902	.95106	.32557	.94620
1	.25910	.96585	.27592	.96118	.29265	.95622	.30929	.95097	.32584	.94612
2	.25933	.96578	.27620	.96110	.29293	.95613	.30957	.95088	.32612	.94604
3	.25966	.96570	.27648	.96102	.29321	.95605	.30985	.95079	.32639	.94596
4	.25994	.96562	.27676	.96094	.29348	.95596	.31012	.95070	.32667	.94588
5	.26022	.96555	.27704	.96086	.29376	.95588	.31040	.95061	.32694	.94580
6	.26050	.96547	.27731	.96078	.29404	.95579	.31068	.95052	.32722	.94572
7	.26079	.96540	.27759	.96070	.29432	.95571	.31095	.95043	.32749	.94564
8	.26107	.96532	.27787	.96062	.29460	.95562	.31123	.95033	.32777	.94556
9	.26135	.96524	.27815	.96054	.29487	.95554	.31151	.95024	.32804	.94548
10	.26163	.96517	.27843	.96046	.29515	.95545	.31178	.95015	.32832	.94540
11	.26191	.96509	.27871	.96037	.29543	.95536	.31206	.95006	.32859	.94532
12	.26219	.96502	.27899	.96029	.29571	.95528	.31233	.94997	.32887	.94524
13	.26247	.96494	.27927	.96021	.29599	.95519	.31261	.94988	.32914	.94516
14	.26275	.96486	.27955	.96013	.29626	.95511	.31289	.94979	.32942	.94508
15	.26303	.96479	.27983	.96005	.29654	.95502	.31316	.94970	.32969	.94500
16	.26331	.96471	.28011	.95997	.29682	.95493	.31344	.94961	.32997	.94492
17	.26359	.96463	.28039	.95989	.29710	.95485	.31372	.94952	.33024	.94484
18	.26387	.96456	.28067	.95981	.29737	.95476	.31399	.94943	.33051	.94476
19	.26415	.96448	.28095	.95972	.29765	.95467	.31427	.94933	.33079	.94468
20	.26443	.96440	.28123	.95964	.29793	.95459	.31454	.94924	.33106	.94460
21	.26471	.96433	.28150	.95956	.29821	.95450	.31482	.94915	.33134	.94452
22	.26500	.96425	.28178	.95948	.29849	.95441	.31510	.94906	.33161	.94444
23	.26528	.96417	.28206	.95940	.29876	.95433	.31537	.94897	.33189	.94436
24	.26556	.96410	.28234	.95931	.29904	.95424	.31565	.94888	.33216	.94428
25	.26584	.96402	.28262	.95923	.29932	.95415	.31593	.94878	.33244	.94420
26	.26612	.96394	.28290	.95915	.29960	.95407	.31620	.94869	.33271	.94412
27	.26640	.96386	.28318	.95907	.29987	.95398	.31648	.94860	.33298	.94404
28	.26668	.96379	.28346	.95898	.30015	.95389	.31675	.94851	.33326	.94396
29	.26696	.96371	.28374	.95890	.30043	.95380	.31703	.94842	.33353	.94388
30	.26724	.96363	.28402	.95882	.30071	.95372	.31730	.94832	.33381	.94380
31	.26752	.96355	.28429	.95874	.30098	.95363	.31758	.94823	.33408	.94372
32	.26780	.96347	.28457	.95865	.30126	.95354	.31780	.94814	.33436	.94364
33	.26808	.96340	.28485	.95857	.30154	.95345	.31813	.94805	.33463	.94356
34	.26836	.96332	.28513	.95849	.30182	.95337	.31841	.94795	.33490	.94348
35	.26864	.96324	.28541	.95841	.30209	.95328	.31868	.94786	.33518	.94340
36	.26892	.96316	.28569	.95832	.30237	.95319	.31896	.94777	.33545	.94332
37	.26920	.96308	.28597	.95824	.30265	.95310	.31923	.94768	.33573	.94324
38	.26948	.96301	.28625	.95816	.30292	.95301	.31951	.94759	.33600	.94316
39	.26976	.96293	.28652	.95807	.30320	.95293	.31979	.94749	.33627	.94308
40	.27004	.96285	.28680	.95799	.30348	.95284	.32006	.94740	.33655	.94300
41	.27032	.96277	.28708	.95791	.30376	.95275	.32034	.94730	.33682	.94292
42	.27060	.96269	.28736	.95782	.30403	.95266	.32061	.94721	.33710	.94284
43	.27088	.96261	.28764	.95774	.30431	.95257	.32089	.94712	.33737	.94276
44	.27116	.96253	.28792	.95766	.30459	.95248	.32116	.94702	.33764	.94268
45	.27144	.96246	.28820	.95757	.30486	.95240	.32144	.94693	.33792	.94260
46	.27172	.96238	.28847	.95749	.30514	.95231	.32171	.94684	.33819	.94252
47	.27200	.96230	.28875	.95740	.30542	.95222	.32199	.94674	.33846	.94244
48	.27228	.96222	.28903	.95732	.30570	.95213	.32227	.94665	.33874	.94236
49	.27256	.96214	.28931	.95724	.30597	.95204	.32254	.94656	.33901	.94228
50	.27284	.96206	.28959	.95715	.30625	.95195	.32282	.94646	.33929	.94220
51	.27312	.96198	.28987	.95707	.30653	.95186	.32309	.94637	.33956	.94212
52	.27340	.96190	.29015	.95698	.30680	.95177	.32337	.94627	.33983	.94204
53	.27368	.96182	.29042	.95690	.30708	.95168	.32364	.94618	.34011	.94196
54	.27396	.96174	.29070	.95681	.30736	.95159	.32392	.94609	.34038	.94188
55	.27424	.96166	.29098	.95673	.30763	.95150	.32419	.94599	.34065	.94180
56	.27452	.96158	.29126	.95664	.30791	.95142	.32447	.94590	.34093	.94172
57	.27480	.96150	.29154	.95656	.30819	.95133	.32474	.94580	.34120	.94164
58	.27508	.96142	.29182	.95647	.30846	.95124	.32502	.94571	.34147	.94156
59	.27536	.96134	.29209	.95639	.30874	.95115	.32529	.94561	.34175	.94148
60	.27564	.96126	.29237	.95630	.30902	.95106	.32557	.94552	.34202	.94140
	Cosine	Sine	Cosine	Sine	Cosine	Sine	Cosine	Sine	Cosine	Sine
	74°		73°		72°		71°		70°	



	25°		26°		27°		28°		29°	
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin
0	.42262	.90631	.43837	.89879	.45399	.89101	.46947	.88295	.48481	.874
1	.42288	.90618	.43863	.89867	.45425	.89087	.46973	.88281	.48506	.874
2	.42315	.90606	.43889	.89854	.45451	.89074	.46999	.88267	.48532	.874
3	.42341	.90594	.43916	.89841	.45477	.89061	.47024	.88254	.48557	.874
4	.42367	.90582	.43942	.89829	.45503	.89048	.47050	.88240	.48583	.874
5	.42394	.90569	.43968	.89816	.45529	.89035	.47076	.88226	.48608	.873
6	.42420	.90557	.43994	.89803	.45554	.89021	.47101	.88213	.48634	.873
7	.42446	.90545	.44020	.89790	.45580	.89008	.47127	.88199	.48659	.873
8	.42473	.90532	.44046	.89777	.45606	.88995	.47153	.88185	.48684	.873
9	.42499	.90520	.44072	.89764	.45632	.88981	.47178	.88172	.48710	.873
10	.42525	.90507	.44098	.89752	.45658	.88968	.47204	.88158	.48735	.873
11	.42552	.90495	.44124	.89739	.45684	.88955	.47229	.88144	.48761	.873
12	.42578	.90483	.44151	.89726	.45710	.88942	.47255	.88130	.48786	.872
13	.42604	.90470	.44177	.89713	.45736	.88928	.47281	.88117	.48811	.872
14	.42631	.90458	.44203	.89700	.45762	.88915	.47306	.88103	.48837	.872
15	.42657	.90446	.44229	.89687	.45787	.88902	.47332	.88089	.48862	.872
16	.42683	.90433	.44255	.89674	.45813	.88888	.47358	.88075	.48888	.872
17	.42709	.90421	.44281	.89662	.45839	.88875	.47383	.88062	.48913	.872
18	.42736	.90408	.44307	.89649	.45865	.88862	.47409	.88048	.48938	.872
19	.42762	.90396	.44333	.89636	.45891	.88848	.47434	.88034	.48964	.871
20	.42788	.90383	.44359	.89623	.45917	.88835	.47460	.88020	.48989	.871
21	.42815	.90371	.44385	.89610	.45942	.88822	.47486	.88006	.49014	.871
22	.42841	.90358	.44411	.89597	.45968	.88808	.47511	.87993	.49040	.871
23	.42867	.90346	.44437	.89584	.45994	.88795	.47537	.87979	.49065	.871
24	.42894	.90334	.44464	.89571	.46020	.88782	.47562	.87965	.49090	.871
25	.42920	.90321	.44490	.89558	.46046	.88768	.47588	.87951	.49116	.871
26	.42946	.90309	.44516	.89545	.46072	.88755	.47614	.87937	.49141	.870
27	.42972	.90296	.44542	.89532	.46097	.88741	.47639	.87923	.49166	.870
28	.42999	.90284	.44568	.89519	.46123	.88728	.47665	.87909	.49192	.870
29	.43025	.90271	.44594	.89506	.46149	.88715	.47690	.87896	.49217	.870
30	.43051	.90259	.44620	.89493	.46175	.88701	.47716	.87882	.49242	.870
31	.43077	.90246	.44646	.89480	.46201	.88688	.47741	.87868	.49268	.870
32	.43104	.90233	.44672	.89467	.46226	.88674	.47767	.87854	.49293	.870
33	.43130	.90221	.44698	.89454	.46252	.88661	.47793	.87840	.49318	.869
34	.43156	.90208	.44724	.89441	.46278	.88647	.47818	.87826	.49344	.869
35	.43182	.90196	.44750	.89428	.46304	.88634	.47844	.87812	.49369	.869
36	.43209	.90183	.44776	.89415	.46330	.88620	.47869	.87798	.49394	.869
37	.43235	.90171	.44802	.89402	.46355	.88607	.47895	.87784	.49419	.869
38	.43261	.90158	.44828	.89389	.46381	.88593	.47920	.87770	.49445	.869
39	.43287	.90146	.44854	.89376	.46407	.88580	.47946	.87756	.49470	.869
40	.43313	.90133	.44880	.89363	.46433	.88566	.47971	.87743	.49495	.869
41	.43340	.90120	.44906	.89350	.46458	.88553	.47997	.87729	.49521	.868
42	.43366	.90108	.44932	.89337	.46484	.88539	.48022	.87715	.49546	.868
43	.43392	.90095	.44958	.89324	.46510	.88526	.48048	.87701	.49571	.868
44	.43418	.90082	.44984	.89311	.46536	.88512	.48073	.87687	.49596	.868
45	.43445	.90070	.45010	.89298	.46561	.88499	.48099	.87673	.49622	.868
46	.43471	.90057	.45036	.89285	.46587	.88485	.48124	.87659	.49647	.868
47	.43497	.90045	.45062	.89272	.46613	.88472	.48150	.87645	.49672	.867
48	.43523	.90032	.45088	.89259	.46639	.88458	.48175	.87631	.49697	.867
49	.43549	.90019	.45114	.89245	.46664	.88445	.48201	.87617	.49723	.867
50	.43575	.90007	.45140	.89232	.46690	.88431	.48226	.87603	.49748	.867
51	.43602	.89994	.45166	.89219	.46716	.88417	.48252	.87589	.49773	.867
52	.43628	.89981	.45192	.89206	.46742	.88404	.48277	.87575	.49798	.867
53	.43654	.89968	.45218	.89193	.46767	.88390	.48303	.87561	.49824	.867
54	.43680	.89956	.45243	.89180	.46793	.88377	.48328	.87546	.49849	.866
55	.43706	.89943	.45269	.89167	.46819	.88363	.48354	.87532	.49874	.866
56	.43733	.89930	.45295	.89153	.46844	.88349	.48379	.87518	.49899	.866
57	.43759	.89918	.45321	.89140	.46870	.88336	.48405	.87504	.49924	.866
58	.43785	.89905	.45347	.89127	.46896	.88322	.48430	.87490	.49950	.866
59	.43811	.89892	.45373	.89114	.46921	.88308	.48456	.87476	.49975	.866
60	.43837	.89879	.45399	.89101	.46947	.88295	.48481	.87462	.50000	.866
	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine

Table of Natural Sines and Cosines

30°		31°		32°		33°		34°		
Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	
86803		.51504	.85717	.52922	.84805	.54464	.83867	.55919	.82904	60
86825		.51529	.85702	.53017	.84789	.54488	.83851	.55943	.82987	59
86848		.51554	.85687	.53041	.84774	.54513	.83835	.55968	.82871	58
86870		.51579	.85672	.53066	.84759	.54537	.83819	.55992	.82855	57
86891		.51604	.85657	.53091	.84743	.54561	.83804	.56016	.82839	56
86912		.51628	.85642	.53115	.84728	.54586	.83788	.56040	.82822	55
86933		.51653	.85627	.53140	.84712	.54610	.83772	.56064	.82806	54
86954		.51678	.85612	.53164	.84697	.54635	.83756	.56088	.82790	53
86975		.51703	.85597	.53189	.84681	.54659	.83740	.56112	.82773	52
87000		.51728	.85582	.53214	.84666	.54683	.83724	.56136	.82757	51
87021		.51753	.85567	.53238	.84650	.54708	.83708	.56160	.82741	50
87042										
87063		.51778	.85551	.53263	.84635	.54732	.83692	.56184	.82724	49
87084		.51803	.85536	.53288	.84619	.54756	.83676	.56208	.82708	48
87105		.51828	.85521	.53312	.84604	.54781	.83660	.56232	.82692	47
87126		.51852	.85506	.53337	.84588	.54805	.83645	.56256	.82675	46
87147		.51877	.85491	.53361	.84573	.54829	.83629	.56280	.82659	45
87168		.51902	.85476	.53386	.84557	.54854	.83613	.56305	.82643	44
87189		.51927	.85461	.53411	.84542	.54878	.83597	.56329	.82626	43
87210		.51952	.85446	.53435	.84526	.54902	.83581	.56353	.82610	42
87231		.51977	.85431	.53460	.84511	.54927	.83565	.56377	.82593	41
87252		.52002	.85416	.53484	.84495	.54951	.83549	.56401	.82577	40
87273										
87294		.52026	.85401	.53509	.84480	.54975	.83533	.56425	.82561	39
87315		.52051	.85385	.53534	.84464	.54999	.83517	.56449	.82544	38
87336		.52076	.85370	.53558	.84448	.55024	.83501	.56473	.82528	37
87357		.52101	.85355	.53583	.84433	.55048	.83485	.56497	.82511	36
87378		.52126	.85340	.53607	.84417	.55072	.83469	.56521	.82496	35
87399		.52151	.85325	.53632	.84402	.55097	.83453	.56545	.82478	34
87420		.52175	.85310	.53656	.84386	.55121	.83437	.56569	.82462	33
87441		.52200	.85294	.53681	.84370	.55145	.83421	.56593	.82446	32
87462		.52225	.85279	.53705	.84355	.55169	.83405	.56617	.82429	31
87483		.52250	.85264	.53730	.84339	.55194	.83389	.56641	.82413	30
87504										
87525		.52275	.85249	.53754	.84324	.55218	.83373	.56665	.82396	29
87546		.52299	.85234	.53779	.84308	.55242	.83356	.56689	.82380	28
87567		.52324	.85218	.53804	.84292	.55266	.83340	.56713	.82363	27
87588		.52349	.85203	.53828	.84277	.55291	.83324	.56736	.82347	26
87609		.52374	.85188	.53853	.84261	.55315	.83308	.56760	.82330	25
87630		.52399	.85173	.53877	.84245	.55339	.83292	.56784	.82314	24
87651		.52423	.85157	.53902	.84230	.55363	.83276	.56808	.82297	23
87672		.52448	.85142	.53926	.84214	.55388	.83260	.56832	.82281	22
87693		.52473	.85127	.53951	.84198	.55412	.83244	.56856	.82264	21
87714		.52498	.85112	.53975	.84182	.55436	.83228	.56880	.82248	20
87735										
87756		.52522	.85096	.54000	.84167	.55460	.83212	.56904	.82231	19
87777		.52547	.85081	.54024	.84151	.55484	.83195	.56928	.82214	18
87798		.52572	.85066	.54049	.84135	.55509	.83179	.56952	.82198	17
87819		.52597	.85051	.54073	.84120	.55532	.83163	.56976	.82181	16
87840		.52621	.85035	.54097	.84104	.55557	.83147	.57000	.82165	15
87861		.52646	.85020	.54122	.84088	.55581	.83131	.57024	.82148	14
87882		.52671	.85005	.54146	.84072	.55605	.83115	.57047	.82132	13
87903		.52696	.84989	.54171	.84057	.55630	.83098	.57071	.82115	12
87924		.52720	.84974	.54195	.84041	.55654	.83082	.57095	.82098	11
87945		.52745	.84959	.54220	.84025	.55678	.83066	.57119	.82082	10
87966										
87987		.52770	.84943	.54244	.84009	.55702	.83050	.57143	.82065	9
88008		.52794	.84928	.54269	.83994	.55726	.83034	.57167	.82048	8
88029		.52819	.84913	.54293	.83978	.55750	.83017	.57191	.82032	7
88050		.52844	.84897	.54317	.83962	.55775	.83001	.57215	.82015	6
88071		.52869	.84882	.54342	.83946	.55799	.82985	.57238	.81999	5
88092		.52893	.84866	.54366	.83930	.55823	.82969	.57262	.81982	4
88113		.52918	.84851	.54391	.83915	.55847	.82953	.57286	.81965	3
88134		.52943	.84836	.54415	.83899	.55871	.82936	.57310	.81949	2
88155		.52967	.84820	.54440	.83883	.55895	.82920	.57334	.81932	1
88176		.52992	.84805	.54464	.83867	.55919	.82904	.57358	.81915	0
88197										
Decl	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	
50°			53°		57°		56°		55°	

	35°		36°		37°		38°		39°	
	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin
0	.57358	.81915	.57779	.80902	.60182	.79864	.61566	.78901	.62932	.777
1	.57381	.81899	.57802	.80885	.60205	.79846	.61589	.78783	.62955	.770
2	.57405	.81882	.57826	.80867	.60228	.79829	.61612	.78756	.62977	.770
3	.57429	.81865	.57849	.80850	.60251	.79811	.61635	.78747	.63000	.770
4	.57453	.81843	.57873	.80833	.60274	.79793	.61658	.78729	.63022	.770
5	.57477	.81832	.57896	.80815	.60298	.79776	.61681	.78711	.63045	.770
6	.57501	.81815	.57920	.80799	.60321	.79758	.61704	.78694	.63068	.770
7	.57524	.81798	.57943	.80782	.60344	.79741	.61726	.78676	.63090	.775
8	.57548	.81782	.57967	.80765	.60367	.79723	.61749	.78658	.63113	.775
9	.57572	.81765	.57990	.80748	.60390	.79706	.61772	.78640	.63135	.775
10	.57596	.81748	.58014	.80730	.60414	.79688	.61795	.78622	.63158	.775
11	.57619	.81731	.58037	.80713	.60437	.79671	.61818	.78604	.63180	.775
12	.57643	.81714	.58061	.80696	.60460	.79653	.61841	.78586	.63203	.774
13	.57667	.81698	.58084	.80679	.60483	.79635	.61864	.78568	.63225	.774
14	.57691	.81681	.58108	.80662	.60506	.79618	.61887	.78550	.63248	.774
15	.57715	.81664	.58131	.80644	.60529	.79600	.61909	.78532	.63271	.774
16	.57738	.81647	.58154	.80627	.60553	.79583	.61932	.78514	.63293	.774
17	.57762	.81631	.58178	.80610	.60576	.79565	.61955	.78496	.63316	.774
18	.57786	.81614	.58201	.80593	.60599	.79547	.61978	.78478	.63338	.773
19	.57810	.81597	.58225	.80576	.60622	.79530	.62001	.78460	.63361	.773
20	.57833	.81580	.58248	.80558	.60645	.79512	.62024	.78442	.63383	.773
21	.57857	.81563	.58272	.80541	.60668	.79494	.62046	.78424	.63406	.773
22	.57881	.81546	.58295	.80524	.60691	.79477	.62069	.78405	.63428	.773
23	.57904	.81530	.58318	.80507	.60714	.79459	.62092	.78387	.63451	.772
24	.57928	.81513	.58342	.80489	.60737	.79441	.62115	.78369	.63473	.772
25	.57952	.81496	.58365	.80472	.60761	.79424	.62138	.78351	.63496	.772
26	.57976	.81479	.58389	.80455	.60784	.79406	.62160	.78333	.63518	.772
27	.57999	.81462	.58412	.80438	.60807	.79388	.62183	.78315	.63540	.772
28	.58023	.81445	.58436	.80420	.60830	.79371	.62206	.78297	.63563	.771
29	.58047	.81428	.58459	.80403	.60853	.79353	.62229	.78279	.63585	.771
30	.58070	.81412	.58482	.80386	.60876	.79335	.62251	.78261	.63608	.771
31	.58094	.81395	.58506	.80368	.60899	.79318	.62274	.78243	.63630	.771
32	.58118	.81378	.58529	.80351	.60922	.79300	.62297	.78225	.63653	.771
33	.58141	.81361	.58552	.80334	.60945	.79282	.62320	.78206	.63675	.771
34	.58165	.81344	.58576	.80316	.60968	.79264	.62342	.78188	.63698	.770
35	.58189	.81327	.58599	.80299	.60991	.79247	.62365	.78170	.63720	.770
36	.58212	.81310	.58622	.80282	.61015	.79229	.62388	.78152	.63742	.770
37	.58236	.81293	.58646	.80264	.61038	.79211	.62411	.78134	.63765	.770
38	.58260	.81276	.58669	.80247	.61061	.79193	.62433	.78116	.63787	.770
39	.58283	.81259	.58693	.80230	.61084	.79176	.62456	.78098	.63810	.769
40	.58307	.81242	.58716	.80212	.61107	.79158	.62479	.78079	.63832	.769
41	.58330	.81225	.58739	.80195	.61130	.79140	.62502	.78061	.63854	.769
42	.58354	.81208	.58763	.80178	.61153	.79122	.62524	.78043	.63877	.769
43	.58378	.81191	.58786	.80160	.61176	.79105	.62547	.78025	.63899	.769
44	.58401	.81174	.58809	.80143	.61199	.79087	.62570	.78007	.63922	.769
45	.58425	.81157	.58832	.80125	.61222	.79069	.62592	.77989	.63944	.768
46	.58449	.81140	.58856	.80108	.61245	.79051	.62615	.77970	.63966	.768
47	.58472	.81123	.58879	.80091	.61268	.79033	.62638	.77952	.63989	.768
48	.58496	.81106	.58902	.80073	.61291	.79016	.62660	.77934	.64011	.768
49	.58519	.81089	.58926	.80056	.61314	.78998	.62683	.77916	.64033	.768
50	.58543	.81072	.58949	.80038	.61337	.78980	.62706	.77897	.64056	.767
51	.58567	.81055	.58972	.80021	.61360	.78962	.62728	.77879	.64078	.767
52	.58590	.81038	.58995	.80003	.61383	.78944	.62751	.77861	.64100	.767
53	.58614	.81021	.60019	.79986	.61406	.78926	.62774	.77843	.64123	.767
54	.58637	.81004	.60042	.79968	.61429	.78908	.62796	.77824	.64145	.767
55	.58661	.80987	.60065	.79951	.61451	.78891	.62819	.77806	.64167	.766
56	.58684	.80970	.60089	.79934	.61474	.78873	.62842	.77788	.64190	.766
57	.58708	.80953	.60112	.79916	.61497	.78855	.62864	.77769	.64212	.766
58	.58731	.80936	.60135	.79899	.61520	.78837	.62887	.77751	.64234	.766
59	.58755	.80919	.60158	.79881	.61543	.78819	.62909	.77733	.64256	.766
60	.58779	.80902	.60182	.79864	.61566	.78801	.62932	.77715	.64279	.766
	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine	Cosin	Sine
	54°		53°		52°		51°		50°	





[illegible]

### Table of Natural Tangents and Cotangents

[illegible]

[illegible]

# Table of Natural Tangents and Cotangents

1°		2°		3°		4°	
Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang
0.0174	57.2900	0.0349	28.6458	0.0521	19.0811	0.0691	14.3007
0.0175	57.2371	0.0351	28.5937	0.0523	19.0300	0.0693	14.2500
0.0176	57.1843	0.0353	28.5417	0.0525	18.9789	0.0695	14.2000
0.0177	57.1315	0.0355	28.4897	0.0527	18.9278	0.0697	14.1500
0.0178	57.0787	0.0357	28.4377	0.0529	18.8767	0.0699	14.1000
0.0179	57.0259	0.0359	28.3857	0.0531	18.8256	0.0701	14.0500
0.0180	56.9731	0.0361	28.3337	0.0533	18.7745	0.0703	14.0000
0.0181	56.9203	0.0363	28.2817	0.0535	18.7234	0.0705	13.9500
0.0182	56.8675	0.0365	28.2297	0.0537	18.6723	0.0707	13.9000
0.0183	56.8147	0.0367	28.1777	0.0539	18.6212	0.0709	13.8500
0.0184	56.7619	0.0369	28.1257	0.0541	18.5701	0.0711	13.8000
0.0185	56.7091	0.0371	28.0737	0.0543	18.5190	0.0713	13.7500
0.0186	56.6563	0.0373	28.0217	0.0545	18.4679	0.0715	13.7000
0.0187	56.6035	0.0375	27.9697	0.0547	18.4168	0.0717	13.6500
0.0188	56.5507	0.0377	27.9177	0.0549	18.3657	0.0719	13.6000
0.0189	56.4979	0.0379	27.8657	0.0551	18.3146	0.0721	13.5500
0.0190	56.4451	0.0381	27.8137	0.0553	18.2635	0.0723	13.5000
0.0191	56.3923	0.0383	27.7617	0.0555	18.2124	0.0725	13.4500
0.0192	56.3395	0.0385	27.7097	0.0557	18.1613	0.0727	13.4000
0.0193	56.2867	0.0387	27.6577	0.0559	18.1102	0.0729	13.3500
0.0194	56.2339	0.0389	27.6057	0.0561	18.0591	0.0731	13.3000
0.0195	56.1811	0.0391	27.5537	0.0563	18.0080	0.0733	13.2500
0.0196	56.1283	0.0393	27.5017	0.0565	17.9569	0.0735	13.2000
0.0197	56.0755	0.0395	27.4497	0.0567	17.9058	0.0737	13.1500
0.0198	56.0227	0.0397	27.3977	0.0569	17.8547	0.0739	13.1000
0.0199	55.9699	0.0399	27.3457	0.0571	17.8036	0.0741	13.0500
0.0200	55.9171	0.0401	27.2937	0.0573	17.7525	0.0743	13.0000
0.0201	55.8643	0.0403	27.2417	0.0575	17.7014	0.0745	12.9500
0.0202	55.8115	0.0405	27.1897	0.0577	17.6503	0.0747	12.9000
0.0203	55.7587	0.0407	27.1377	0.0579	17.5992	0.0749	12.8500
0.0204	55.7059	0.0409	27.0857	0.0581	17.5481	0.0751	12.8000
0.0205	55.6531	0.0411	27.0337	0.0583	17.4970	0.0753	12.7500
0.0206	55.5999	0.0413	26.9817	0.0585	17.4459	0.0755	12.7000
0.0207	55.5471	0.0415	26.9297	0.0587	17.3948	0.0757	12.6500
0.0208	55.4943	0.0417	26.8777	0.0589	17.3437	0.0759	12.6000
0.0209	55.4415	0.0419	26.8257	0.0591	17.2926	0.0761	12.5500
0.0210	55.3887	0.0421	26.7737	0.0593	17.2415	0.0763	12.5000
0.0211	55.3359	0.0423	26.7217	0.0595	17.1904	0.0765	12.4500
0.0212	55.2831	0.0425	26.6697	0.0597	17.1393	0.0767	12.4000
0.0213	55.2303	0.0427	26.6177	0.0599	17.0882	0.0769	12.3500
0.0214	55.1775	0.0429	26.5657	0.0601	17.0371	0.0771	12.3000
0.0215	55.1247	0.0431	26.5137	0.0603	16.9860	0.0773	12.2500
0.0216	55.0719	0.0433	26.4617	0.0605	16.9349	0.0775	12.2000
0.0217	55.0191	0.0435	26.4097	0.0607	16.8838	0.0777	12.1500
0.0218	54.9663	0.0437	26.3577	0.0609	16.8327	0.0779	12.1000
0.0219	54.9135	0.0439	26.3057	0.0611	16.7816	0.0781	12.0500
0.0220	54.8607	0.0441	26.2537	0.0613	16.7305	0.0783	12.0000
0.0221	54.8079	0.0443	26.2017	0.0615	16.6794	0.0785	11.9500
0.0222	54.7551	0.0445	26.1497	0.0617	16.6283	0.0787	11.9000
0.0223	54.7023	0.0447	26.0977	0.0619	16.5772	0.0789	11.8500
0.0224	54.6495	0.0449	26.0457	0.0621	16.5261	0.0791	11.8000
0.0225	54.5967	0.0451	25.9937	0.0623	16.4750	0.0793	11.7500
0.0226	54.5439	0.0453	25.9417	0.0625	16.4239	0.0795	11.7000
0.0227	54.4911	0.0455	25.8897	0.0627	16.3728	0.0797	11.6500
0.0228	54.4383	0.0457	25.8377	0.0629	16.3217	0.0799	11.6000
0.0229	54.3855	0.0459	25.7857	0.0631	16.2706	0.0801	11.5500
0.0230	54.3327	0.0461	25.7337	0.0633	16.2195	0.0803	11.5000
0.0231	54.2799	0.0463	25.6817	0.0635	16.1684	0.0805	11.4500
0.0232	54.2271	0.0465	25.6297	0.0637	16.1173	0.0807	11.4000
0.0233	54.1743	0.0467	25.5777	0.0639	16.0662	0.0809	11.3500
0.0234	54.1215	0.0469	25.5257	0.0641	16.0151	0.0811	11.3000
0.0235	54.0687	0.0471	25.4737	0.0643	15.9640	0.0813	11.2500
0.0236	54.0159	0.0473	25.4217	0.0645	15.9129	0.0815	11.2000
0.0237	53.9631	0.0475	25.3697	0.0647	15.8618	0.0817	11.1500
0.0238	53.9103	0.0477	25.3177	0.0649	15.8107	0.0819	11.1000
0.0239	53.8575	0.0479	25.2657	0.0651	15.7596	0.0821	11.0500
0.0240	53.8047	0.0481	25.2137	0.0653	15.7085	0.0823	11.0000
0.0241	53.7519	0.0483	25.1617	0.0655	15.6574	0.0825	10.9500
0.0242	53.6991	0.0485	25.1097	0.0657	15.6063	0.0827	10.9000
0.0243	53.6463	0.0487	25.0577	0.0659	15.5552	0.0829	10.8500
0.0244	53.5935	0.0489	25.0057	0.0661	15.5041	0.0831	10.8000
0.0245	53.5407	0.0491	24.9537	0.0663	15.4530	0.0833	10.7500
0.0246	53.4879	0.0493	24.9017	0.0665	15.4019	0.0835	10.7000
0.0247	53.4351	0.0495	24.8497	0.0667	15.3508	0.0837	10.6500
0.0248	53.3823	0.0497	24.7977	0.0669	15.2997	0.0839	10.6000
0.0249	53.3295	0.0499	24.7457	0.0671	15.2486	0.0841	10.5500
0.0250	53.2767	0.0501	24.6937	0.0673	15.1975	0.0843	10.5000
0.0251	53.2239	0.0503	24.6417	0.0675	15.1464	0.0845	10.4500
0.0252	53.1711	0.0505	24.5897	0.0677	15.0953	0.0847	10.4000
0.0253	53.1183	0.0507	24.5377	0.0679	15.0442	0.0849	10.3500
0.0254	53.0655	0.0509	24.4857	0.0681	14.9931	0.0851	10.3000
0.0255	53.0127	0.0511	24.4337	0.0683	14.9420	0.0853	10.2500
0.0256	52.9599	0.0513	24.3817	0.0685	14.8909	0.0855	10.2000
0.0257	52.9071	0.0515	24.3297	0.0687	14.8398	0.0857	10.1500
0.0258	52.8543	0.0517	24.2777	0.0689	14.7887	0.0859	10.1000
0.0259	52.8015	0.0519	24.2257	0.0691	14.7376	0.0861	10.0500
0.0260	52.7487	0.0521	24.1737	0.0693	14.6865	0.0863	10.0000
0.0261	52.6959	0.0523	24.1217	0.0695	14.6354	0.0865	9.9500
0.0262	52.6431	0.0525	24.0697	0.0697	14.5843	0.0867	9.9000
0.0263	52.5903	0.0527	24.0177	0.0699	14.5332	0.0869	9.8500
0.0264	52.5375	0.0529	23.9657	0.0701	14.4821	0.0871	9.8000
0.0265	52.4847	0.0531	23.9137	0.0703	14.4310	0.0873	9.7500
0.0266	52.4319	0.0533	23.8617	0.0705	14.3799	0.0875	9.7000
0.0267	52.3791	0.0535	23.8097	0.0707	14.3288	0.0877	9.6500
0.0268	52.3263	0.0537	23.7577	0.0709	14.2777	0.0879	9.6000
0.0269	52.2735	0.0539	23.7057	0.0711	14.2266	0.0881	9.5500
0.0270	52.2207	0.0541	23.6537	0.0713	14.1755	0.0883	9.5000
0.0271	52.1679	0.0543	23.6017	0.0715	14.1244	0.0885	9.4500
0.0272	52.1151	0.0545	23.5497	0.0717	14.0733	0.0887	9.4000
0.0273	52.0623	0.0547	23.4977	0.0719	14.0222	0.0889	9.3500
0.0274	52.0095	0.0549	23.4457	0.0721	13.9711	0.0891	9.3000
0.0275	51.9567	0.0551	23.3937	0.0723	13.9200	0.0893	9.2500
0.0276	51.9039	0.0553	23.3417	0.0725	13.8689	0.0895	9.2000
0.0277	51.8511	0.0555	23.2897	0.0727	13.8178	0.0897	9.1500
0.0278	51.7983	0.0557	23.2377	0.0729	13.7667	0.0899	9.1000
0.0279	51.7455	0.0559	23.1857	0.0731	13.7156	0.0901	9.0500
0.0280	51.6927	0.0561	23.1337	0.0733	13.6645	0.0903	9.0000
0.0281	51.6399	0.0563	23.0817	0.0735	13.6134	0.0905	8.9500
0.0282	51.5871	0.0565	23.0297	0.0737	13.5623	0.0907	8.9000
0.0283	51.5343	0.0567	22.9777	0.0739	13.5112	0.0909	8.8500
0.0284	51.4815	0.0569	22.9257	0.0741	13.4601	0.0911	8.8000
0.0285	51.4287	0.0571	22.8737	0.0743	13.4090	0.0913	8.7500
0.0286	51.3759	0.0573	22.8217	0.0745	13.3579	0.0915	8.7000
0.0287	51.3231	0.0575	22.7697	0.0747	13.3068	0.0917	8.6500
0.0288	51.2703	0.0577	22.7177	0.0749	13.2557	0.0919	8.6000
0.0289	51.2175	0.0579	22.6657	0.0751	13.2046	0.0921	8.5500
0.0290	51.1647	0.0581	22.6137	0.0753	13.1535	0.0923	8.5000
0.0291	51.1119	0.0583	22.5617	0.0755	13.1024	0.0925	8.4500
0.0292	51.0591	0.0585	22.5097	0.0757	13.0513	0.0927	8.4000
0.0293	51.0063	0.0587	22.4577	0.0759	13.0002	0.0929	8.3500
0.0294	50.9535	0.0589	22.4057	0.0761	12.9491	0.0931	8.3000
0.0295	50.9007	0.0591	22.3537	0.0763	12.8980	0.0933	8.2500
0.0296	50.8479	0.0593	22.3017	0.0765	12.8469	0.0935	8.2000
0.0297	50.7951	0.0595	22.2497	0.0767	12.7958	0.0937	8.1500
0.0298	50.7423	0.0597	22.1977	0.0769	12.7447	0.0939	8.1000
0.0299	50.6895	0.0599	22.1457	0.0771			

# Trigonometry

	Tang	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang
0								
1	0.0174	57.29	0.0174	57.29	0.0174	57.29	0.0174	57.29
2	0.0349	28.65	0.0349	28.65	0.0349	28.65	0.0349	28.65
3	0.0524	19.10	0.0524	19.10	0.0524	19.10	0.0524	19.10
4	0.0698	14.30	0.0698	14.30	0.0698	14.30	0.0698	14.30
5	0.0872	11.43	0.0872	11.43	0.0872	11.43	0.0872	11.43
6	0.1045	9.51	0.1045	9.51	0.1045	9.51	0.1045	9.51
7	0.1219	8.23	0.1219	8.23	0.1219	8.23	0.1219	8.23
8	0.1392	7.18	0.1392	7.18	0.1392	7.18	0.1392	7.18
9	0.1564	6.31	0.1564	6.31	0.1564	6.31	0.1564	6.31
10	0.1736	5.67	0.1736	5.67	0.1736	5.67	0.1736	5.67
11	0.1908	5.21	0.1908	5.21	0.1908	5.21	0.1908	5.21
12	0.2080	4.75	0.2080	4.75	0.2080	4.75	0.2080	4.75
13	0.2252	4.38	0.2252	4.38	0.2252	4.38	0.2252	4.38
14	0.2424	4.07	0.2424	4.07	0.2424	4.07	0.2424	4.07
15	0.2596	3.81	0.2596	3.81	0.2596	3.81	0.2596	3.81
16	0.2768	3.60	0.2768	3.60	0.2768	3.60	0.2768	3.60
17	0.2940	3.42	0.2940	3.42	0.2940	3.42	0.2940	3.42
18	0.3112	3.26	0.3112	3.26	0.3112	3.26	0.3112	3.26
19	0.3284	3.12	0.3284	3.12	0.3284	3.12	0.3284	3.12
20	0.3456	3.00	0.3456	3.00	0.3456	3.00	0.3456	3.00
21	0.3628	2.90	0.3628	2.90	0.3628	2.90	0.3628	2.90
22	0.3800	2.81	0.3800	2.81	0.3800	2.81	0.3800	2.81
23	0.3972	2.73	0.3972	2.73	0.3972	2.73	0.3972	2.73
24	0.4144	2.66	0.4144	2.66	0.4144	2.66	0.4144	2.66
25	0.4316	2.60	0.4316	2.60	0.4316	2.60	0.4316	2.60
26	0.4488	2.54	0.4488	2.54	0.4488	2.54	0.4488	2.54
27	0.4660	2.49	0.4660	2.49	0.4660	2.49	0.4660	2.49
28	0.4832	2.44	0.4832	2.44	0.4832	2.44	0.4832	2.44
29	0.5004	2.40	0.5004	2.40	0.5004	2.40	0.5004	2.40
30	0.5176	2.36	0.5176	2.36	0.5176	2.36	0.5176	2.36
31	0.5348	2.32	0.5348	2.32	0.5348	2.32	0.5348	2.32
32	0.5520	2.29	0.5520	2.29	0.5520	2.29	0.5520	2.29
33	0.5692	2.26	0.5692	2.26	0.5692	2.26	0.5692	2.26
34	0.5864	2.23	0.5864	2.23	0.5864	2.23	0.5864	2.23
35	0.6036	2.20	0.6036	2.20	0.6036	2.20	0.6036	2.20
36	0.6208	2.17	0.6208	2.17	0.6208	2.17	0.6208	2.17
37	0.6380	2.15	0.6380	2.15	0.6380	2.15	0.6380	2.15
38	0.6552	2.12	0.6552	2.12	0.6552	2.12	0.6552	2.12
39	0.6724	2.10	0.6724	2.10	0.6724	2.10	0.6724	2.10
40	0.6896	2.08	0.6896	2.08	0.6896	2.08	0.6896	2.08
41	0.7068	2.06	0.7068	2.06	0.7068	2.06	0.7068	2.06
42	0.7240	2.04	0.7240	2.04	0.7240	2.04	0.7240	2.04
43	0.7412	2.02	0.7412	2.02	0.7412	2.02	0.7412	2.02
44	0.7584	2.00	0.7584	2.00	0.7584	2.00	0.7584	2.00
45	0.7756	1.98	0.7756	1.98	0.7756	1.98	0.7756	1.98
46	0.7928	1.96	0.7928	1.96	0.7928	1.96	0.7928	1.96
47	0.8100	1.94	0.8100	1.94	0.8100	1.94	0.8100	1.94
48	0.8272	1.92	0.8272	1.92	0.8272	1.92	0.8272	1.92
49	0.8444	1.90	0.8444	1.90	0.8444	1.90	0.8444	1.90
50	0.8616	1.88	0.8616	1.88	0.8616	1.88	0.8616	1.88
51	0.8788	1.86	0.8788	1.86	0.8788	1.86	0.8788	1.86
52	0.8960	1.84	0.8960	1.84	0.8960	1.84	0.8960	1.84
53	0.9132	1.82	0.9132	1.82	0.9132	1.82	0.9132	1.82
54	0.9304	1.80	0.9304	1.80	0.9304	1.80	0.9304	1.80
55	0.9476	1.78	0.9476	1.78	0.9476	1.78	0.9476	1.78
56	0.9648	1.76	0.9648	1.76	0.9648	1.76	0.9648	1.76
57	0.9820	1.74	0.9820	1.74	0.9820	1.74	0.9820	1.74
58	0.9992	1.72	0.9992	1.72	0.9992	1.72	0.9992	1.72
59	1.0164	1.70	1.0164	1.70	1.0164	1.70	1.0164	1.70
60	1.0336	1.68	1.0336	1.68	1.0336	1.68	1.0336	1.68
61	1.0508	1.66	1.0508	1.66	1.0508	1.66	1.0508	1.66
62	1.0680	1.64	1.0680	1.64	1.0680	1.64	1.0680	1.64
63	1.0852	1.62	1.0852	1.62	1.0852	1.62	1.0852	1.62
64	1.1024	1.60	1.1024	1.60	1.1024	1.60	1.1024	1.60
65	1.1196	1.58	1.1196	1.58	1.1196	1.58	1.1196	1.58
66	1.1368	1.56	1.1368	1.56	1.1368	1.56	1.1368	1.56
67	1.1540	1.54	1.1540	1.54	1.1540	1.54	1.1540	1.54
68	1.1712	1.52	1.1712	1.52	1.1712	1.52	1.1712	1.52
69	1.1884	1.50	1.1884	1.50	1.1884	1.50	1.1884	1.50
70	1.2056	1.48	1.2056	1.48	1.2056	1.48	1.2056	1.48
71	1.2228	1.46	1.2228	1.46	1.2228	1.46	1.2228	1.46
72	1.2400	1.44	1.2400	1.44	1.2400	1.44	1.2400	1.44
73	1.2572	1.42	1.2572	1.42	1.2572	1.42	1.2572	1.42
74	1.2744	1.40	1.2744	1.40	1.2744	1.40	1.2744	1.40
75	1.2916	1.38	1.2916	1.38	1.2916	1.38	1.2916	1.38
76	1.3088	1.36	1.3088	1.36	1.3088	1.36	1.3088	1.36
77	1.3260	1.34	1.3260	1.34	1.3260	1.34	1.3260	1.34
78	1.3432	1.32	1.3432	1.32	1.3432	1.32	1.3432	1.32
79	1.3604	1.30	1.3604	1.30	1.3604	1.30	1.3604	1.30
80	1.3776	1.28	1.3776	1.28	1.3776	1.28	1.3776	1.28
81	1.3948	1.26	1.3948	1.26	1.3948	1.26	1.3948	1.26
82	1.4120	1.24	1.4120	1.24	1.4120	1.24	1.4120	1.24
83	1.4292	1.22	1.4292	1.22	1.4292	1.22	1.4292	1.22
84	1.4464	1.20	1.4464	1.20	1.4464	1.20	1.4464	1.20
85	1.4636	1.18	1.4636	1.18	1.4636	1.18	1.4636	1.18
86	1.4808	1.16	1.4808	1.16	1.4808	1.16	1.4808	1.16
87	1.4980	1.14	1.4980	1.14	1.4980	1.14	1.4980	1.14
88	1.5152	1.12	1.5152	1.12	1.5152	1.12	1.5152	1.12
89	1.5324	1.10	1.5324	1.10	1.5324	1.10	1.5324	1.10
90	1.5496	1.08	1.5496	1.08	1.5496	1.08	1.5496	1.08
91	1.5668	1.06	1.5668	1.06	1.5668	1.06	1.5668	1.06
92	1.5840	1.04	1.5840	1.04	1.5840	1.04	1.5840	1.04
93	1.6012	1.02	1.6012	1.02	1.6012	1.02	1.6012	1.02
94	1.6184	1.00	1.6184	1.00	1.6184	1.00	1.6184	1.00
95	1.6356	0.98	1.6356	0.98	1.6356	0.98	1.6356	0.98
96	1.6528	0.96	1.6528	0.96	1.6528	0.96	1.6528	0.96
97	1.6700	0.94	1.6700	0.94	1.6700	0.94	1.6700	0.94
98	1.6872	0.92	1.6872	0.92	1.6872	0.92	1.6872	0.92
99	1.7044	0.90	1.7044	0.90	1.7044	0.90	1.7044	0.90
100	1.7216	0.88	1.7216	0.88	1.7216	0.88	1.7216	0.88



Table of Natural Tangents and Cotangents

1°		21°				39°	
Tang	Cotang	Tang	Cotang			Tang	Cotang
0.0174	57.0714	0.3839	2.6051	0.8090	0.6736	0.8090	2.6051
0.0349	28.5355	0.7660	1.3048	0.7660	0.6428	0.7660	1.3048
0.0523	19.0809	0.6344	1.5758	0.6344	0.6127	0.6344	1.5758
0.0698	14.3007	0.5095	1.9613	0.5095	0.5831	0.5095	1.9613
0.0872	11.3309	0.3917	2.5536	0.3917	0.5540	0.3917	2.5536
0.1047	9.5166	0.2818	3.5511	0.2818	0.5254	0.2818	3.5511
0.1221	8.0902	0.1802	5.5574	0.1802	0.4972	0.1802	5.5574
0.1396	6.9780	0.0872	11.3309	0.0872	0.4695	0.0872	11.3309
0.1570	6.0829	0.0000	∞	0.0000	0.4423	0.0000	∞
0.1745	5.4280				0.4156		
0.1919	4.8998				0.3894		
0.2093	4.4560				0.3637		
0.2268	4.0714				0.3384		
0.2442	3.7324				0.3136		
0.2616	3.4248				0.2892		
0.2791	3.1438				0.2653		
0.2965	2.8857				0.2418		
0.3139	2.6471				0.2188		
0.3314	2.4246				0.1962		
0.3488	2.2149				0.1741		
0.3662	2.0157				0.1524		
0.3837	1.8250				0.1312		
0.4011	1.6414				0.1104		
0.4185	1.4638				0.0900		
0.4360	1.2911				0.0700		
0.4534	1.1224				0.0504		
0.4708	0.9577				0.0312		
0.4883	0.7969				0.0125		
0.5057	0.6391				0.0042		
0.5231	0.4843				0.0014		
0.5406	0.3327						
0.5580	0.1843						
0.5754	0.0391						
0.5929	0.0000						
0.6103							
0.6277							
0.6452							
0.6626							
0.6800							
0.6975							
0.7149							
0.7323							
0.7497							
0.7672							
0.7846							
0.8020							
0.8194							
0.8369							
0.8543							
0.8717							
0.8891							
0.9066							
0.9240							
0.9414							
0.9588							
0.9763							
0.9937							
1.0111							
1.0285							
1.0460							
1.0634							
1.0808							
1.0982							
1.1157							
1.1331							
1.1505							
1.1679							
1.1854							
1.2028							
1.2202							
1.2376							
1.2551							
1.2725							
1.2899							
1.3073							
1.3248							
1.3422							
1.3596							
1.3770							
1.3945							
1.4119							
1.4293							
1.4467							
1.4642							
1.4816							
1.4990							
1.5164							
1.5339							
1.5513							
1.5687							
1.5861							
1.6036							
1.6210							
1.6384							
1.6558							
1.6733							
1.6907							
1.7081							
1.7255							
1.7430							
1.7604							
1.7778							
1.7952							
1.8127							
1.8301							
1.8475							
1.8649							
1.8824							
1.8998							
1.9172							
1.9346							
1.9521							
1.9695							
1.9869							
2.0043							

0	44523	2.34904	.46631	1.14151	45779	2.00000	200250
1	44558	2.34938	.46664	1.14184	45810	2.00039	200270
2	44593	2.34971	.46697	1.14217	45841	2.00078	200290
3	44628	2.35005	.46730	1.14250	45872	2.00117	200310
4	44663	2.35038	.46763	1.14283	45903	2.00156	200330
5	44698	2.35072	.46796	1.14316	45934	2.00195	200350
6	44733	2.35105	.46829	1.14349	45965	2.00234	200370
7	44768	2.35139	.46862	1.14382	45996	2.00273	200390
8	44803	2.35172	.46895	1.14415	46027	2.00312	200410
9	44838	2.35206	.46928	1.14448	46058	2.00351	200430
10	44873	2.35239	.46961	1.14481	46089	2.00390	200450
11	44908	2.35273	.46994	1.14514	46120	2.00429	200470
12	44943	2.35306	.47027	1.14547	46151	2.00468	200490
13	44978	2.35340	.47060	1.14580	46182	2.00507	200510
14	45013	2.35373	.47093	1.14613	46213	2.00546	200530
15	45048	2.35407	.47126	1.14646	46244	2.00585	200550
16	45083	2.35440	.47159	1.14679	46275	2.00624	200570
17	45118	2.35474	.47192	1.14712	46306	2.00663	200590
18	45153	2.35507	.47225	1.14745	46337	2.00702	200610
19	45188	2.35541	.47258	1.14778	46368	2.00741	200630
20	45223	2.35574	.47291	1.14811	46399	2.00780	200650
21	45258	2.35608	.47324	1.14844	46430	2.00819	200670
22	45293	2.35641	.47357	1.14877	46461	2.00858	200690
23	45328	2.35675	.47390	1.14910	46492	2.00897	200710
24	45363	2.35708	.47423	1.14943	46523	2.00936	200730
25	45398	2.35742	.47456	1.14976	46554	2.00975	200750
26	45433	2.35775	.47489	1.15009	46585	2.01014	200770
27	45468	2.35809	.47522	1.15042	46616	2.01053	200790
28	45503	2.35842	.47555	1.15075	46647	2.01092	200810
29	45538	2.35876	.47588	1.15108	46678	2.01131	200830
30	45573	2.35909	.47621	1.15141	46709	2.01170	200850
31	45608	2.35943	.47654	1.15174	46740	2.01209	200870
32	45643	2.35976	.47687	1.15207	46771	2.01248	200890
33	45678	2.36010	.47720	1.15240	46802	2.01287	200910
34	45713	2.36043	.47753	1.15273	46833	2.01326	200930
35	45748	2.36077	.47786	1.15306	46864	2.01365	200950
36	45783	2.36110	.47819	1.15339	46895	2.01404	200970
37	45818	2.36144	.47852	1.15372	46926	2.01443	200990
38	45853	2.36177	.47885	1.15405	46957	2.01482	201010
39	45888	2.36211	.47918	1.15438	46988	2.01521	201030
40	45923	2.36244	.47951	1.15471	47019	2.01560	201050
41	45958	2.36278	.47984	1.15504	47050	2.01599	201070
42	45993	2.36311	.48017	1.15537	47081	2.01638	201090
43	46028	2.36345	.48050	1.15570	47112	2.01677	201110
44	46063	2.36378	.48083	1.15603	47143	2.01716	201130
45	46098	2.36412	.48116	1.15636	47174	2.01755	201150
46	46133	2.36445	.48149	1.15669	47205	2.01794	201170
47	46168	2.36479	.48182	1.15702	47236	2.01833	201190
48	46203	2.36512	.48215	1.15735	47267	2.01872	201210
49	46238	2.36546	.48248	1.15768	47298	2.01911	201230
50	46273	2.36579	.48281	1.15801	47329	2.01950	201250
51	46308	2.36613	.48314	1.15834	47360	2.01989	201270
52	46343	2.36646	.48347	1.15867	47391	2.02028	201290
53	46378	2.36680	.48380	1.15900	47422	2.02067	201310
54	46413	2.36713	.48413	1.15933	47453	2.02106	201330
55	46448	2.36747	.48446	1.15966	47484	2.02145	201350
56	46483	2.36780	.48479	1.16000	47515	2.02184	201370
57	46518	2.36814	.48512	1.16033	47546	2.02223	201390
58	46553	2.36847	.48545	1.16066	47577	2.02262	201410
59	46588	2.36881	.48578	1.16099	47608	2.02301	201430
60	46623	2.36914	.48611	1.16132	47639	2.02340	201450
61	46658	2.36948	.48644	1.16165	47670	2.02379	201470
62	46693	2.36981	.48677	1.16198	47701	2.02418	201490
63	46728	2.37015	.48710	1.16231	47732	2.02457	201510
64	46763	2.37048	.48743	1.16264	47763	2.02496	201530
65	46798	2.37082	.48776	1.16297	47794	2.02535	201550
66	46833	2.37115	.48809	1.16330	47825	2.02574	201570
67	46868	2.37149	.48842	1.16363	47856	2.02613	201590
68	46903	2.37182	.48875	1.16396	47887	2.02652	201610
69	46938	2.37216	.48908	1.16429	47918	2.02691	201630
70	46973	2.37249	.48941	1.16462	47949	2.02730	201650
71	47008	2.37283	.48974	1.16495	47980	2.02769	201670
72	47043	2.37316	.49007	1.16528	48011	2.02808	201690
73	47078	2.37350	.49040	1.16561	48042	2.02847	201710
74	47113	2.37383	.49073	1.16594	48073	2.02886	201730
75	47148	2.37417	.49106	1.16627	48104	2.02925	201750
76	47183	2.37450	.49139	1.16660	48135	2.02964	201770
77	47218	2.37484	.49172	1.16693	48166	2.03003	201790
78	47253	2.37517	.49205	1.16726	48197	2.03042	201810
79	47288	2.37551	.49238	1.16759	48228	2.03081	201830
80	47323	2.37584	.49271	1.16792	48259	2.03120	201850
81	47358	2.37618	.49304	1.16825	48290	2.03159	201870
82	47393	2.37651	.49337	1.16858	48321	2.03198	201890
83	47428	2.37685	.49370	1.16891	48352	2.03237	201910
84	47463	2.37718	.49403	1.16924	48383	2.03276	201930
85	47498	2.37752	.49436	1.16957	48414	2.03315	201950
86	47533	2.37785	.49469	1.16990	48445	2.03354	201970
87	47568	2.37819	.49502	1.17023	48476	2.03393	201990
88	47603	2.37852	.49535	1.17056	48507	2.03432	202010
89	47638	2.37886	.49568	1.17089	48538	2.03471	202030
90	47673	2.37919	.49601	1.17122	48569	2.03510	202050





	32°				33°		
	Tang	Cotang			Tang	Cotang	
0	00000	∞	00000	∞	00000	∞	00000
1	00005	99995	00005	99995	00010	99990	00010
2	00010	99990	00010	99990	00015	99985	00015
3	00015	99985	00015	99985	00020	99980	00020
4	00020	99980	00020	99980	00025	99975	00025
5	00025	99975	00025	99975	00030	99970	00030
6	00030	99970	00030	99970	00035	99965	00035
7	00035	99965	00035	99965	00040	99960	00040
8	00040	99960	00040	99960	00045	99955	00045
9	00045	99955	00045	99955	00050	99950	00050
10	00050	99950	00050	99950	00055	99945	00055
11	00055	99945	00055	99945	00060	99940	00060
12	00060	99940	00060	99940	00065	99935	00065
13	00065	99935	00065	99935	00070	99930	00070
14	00070	99930	00070	99930	00075	99925	00075
15	00075	99925	00075	99925	00080	99920	00080
16	00080	99920	00080	99920	00085	99915	00085
17	00085	99915	00085	99915	00090	99910	00090
18	00090	99910	00090	99910	00095	99905	00095
19	00095	99905	00095	99905	00100	99900	00100
20	00100	99900	00100	99900	00105	99895	00105
21	00105	99895	00105	99895	00110	99890	00110
22	00110	99890	00110	99890	00115	99885	00115
23	00115	99885	00115	99885	00120	99880	00120
24	00120	99880	00120	99880	00125	99875	00125
25	00125	99875	00125	99875	00130	99870	00130
26	00130	99870	00130	99870	00135	99865	00135
27	00135	99865	00135	99865	00140	99860	00140
28	00140	99860	00140	99860	00145	99855	00145
29	00145	99855	00145	99855	00150	99850	00150
30	00150	99850	00150	99850	00155	99845	00155
31	00155	99845	00155	99845	00160	99840	00160
32	00160	99840	00160	99840	00165	99835	00165
33	00165	99835	00165	99835	00170	99830	00170
34	00170	99830	00170	99830	00175	99825	00175
35	00175	99825	00175	99825	00180	99820	00180
36	00180	99820	00180	99820	00185	99815	00185
37	00185	99815	00185	99815	00190	99810	00190
38	00190	99810	00190	99810	00195	99805	00195
39	00195	99805	00195	99805	00200	99800	00200
40	00200	99800	00200	99800	00205	99795	00205
41	00205	99795	00205	99795	00210	99790	00210
42	00210	99790	00210	99790	00215	99785	00215
43	00215	99785	00215	99785	00220	99780	00220
44	00220	99780	00220	99780	00225	99775	00225
45	00225	99775	00225	99775	00230	99770	00230
46	00230	99770	00230	99770	00235	99765	00235
47	00235	99765	00235	99765	00240	99760	00240
48	00240	99760	00240	99760	00245	99755	00245
49	00245	99755	00245	99755	00250	99750	00250
50	00250	99750	00250	99750	00255	99745	00255
51	00255	99745	00255	99745	00260	99740	00260
52	00260	99740	00260	99740	00265	99735	00265
53	00265	99735	00265	99735	00270	99730	00270
54	00270	99730	00270	99730	00275	99725	00275
55	00275	99725	00275	99725	00280	99720	00280
56	00280	99720	00280	99720	00285	99715	00285
57	00285	99715	00285	99715	00290	99710	00290
58	00290	99710	00290	99710	00295	99705	00295
59	00295	99705	00295	99705	00300	99700	00300
60	00300	99700	00300	99700	00305	99695	00305
61	00305	99695	00305	99695	00310	99690	00310
62	00310	99690	00310	99690	00315	99685	00315
63	00315	99685	00315	99685	00320	99680	00320
64	00320	99680	00320	99680	00325	99675	00325
65	00325	99675	00325	99675	00330	99670	00330
66	00330	99670	00330	99670	00335	99665	00335
67	00335	99665	00335	99665	00340	99660	00340
68	00340	99660	00340	99660	00345	99655	00345
69	00345	99655	00345	99655	00350	99650	00350
70	00350	99650	00350	99650	00355	99645	00355
71	00355	99645	00355	99645	00360	99640	00360
72	00360	99640	00360	99640	00365	99635	00365
73	00365	99635	00365	99635	00370	99630	00370
74	00370	99630	00370	99630	00375	99625	00375
75	00375	99625	00375	99625	00380	99620	00380
76	00380	99620	00380	99620	00385	99615	00385
77	00385	99615	00385	99615	00390	99610	00390
78	00390	99610	00390	99610	00395	99605	00395
79	00395	99605	00395	99605	00400	99600	00400
80	00400	99600	00400	99600	00405	99595	00405
81	00405	99595	00405	99595	00410	99590	00410
82	00410	99590	00410	99590	00415	99585	00415
83	00415	99585	00415	99585	00420	99580	00420
84	00420	99580	00420	99580	00425	99575	00425
85	00425	99575	00425	99575	00430	99570	00430
86	00430	99570	00430	99570	00435	99565	00435
87	00435	99565	00435	99565	00440	99560	00440
88	00440	99560	00440	99560	00445	99555	00445
89	00445	99555	00445	99555	00450	99550	00450
90	00450	99550	00450	99550	00455	99545	00455
91	00455	99545	00455	99545	00460	99540	00460
92	00460	99540	00460	99540	00465	99535	00465
93	00465	99535	00465	99535	00470	99530	00470
94	00470	99530	00470	99530	00475	99525	00475
95	00475	99525	00475	99525	00480	99520	00480
96	00480	99520	00480	99520	00485	99515	00485
97	00485	99515	00485	99515	00490	99510	00490
98	00490	99510	00490	99510	00495	99505	00495
99	00495	99505	00495	99505	00500	99500	00500
100	00500	99500	00500	99500	00505	99495	00505

Table of Natural Tangents and Cotangents

Angle	Tang	Cotang	Angle	Tang	Cotang	Angle	Tang	Cotang	Angle	Tang	Cotang
1	0.017	57.290	16	0.275	3.639	31	0.611	1.637	46	1.111	0.896
2	0.035	28.648	17	0.301	3.328	32	0.643	1.554	47	1.157	0.863
3	0.052	19.081	18	0.327	3.057	33	0.676	1.471	48	1.203	0.831
4	0.069	14.301	19	0.354	2.824	34	0.709	1.400	49	1.250	0.799
5	0.087	11.430	20	0.381	2.627	35	0.742	1.339	50	1.297	0.768
6	0.104	9.515	21	0.408	2.451	36	0.776	1.285	51	1.345	0.738
7	0.122	8.090	22	0.436	2.294	37	0.809	1.237	52	1.393	0.709
8	0.139	7.042	23	0.464	2.156	38	0.843	1.194	53	1.441	0.681
9	0.157	6.314	24	0.492	2.033	39	0.877	1.155	54	1.489	0.654
10	0.175	5.774	25	0.520	1.921	40	0.911	1.119	55	1.537	0.628
11	0.192	5.357	26	0.548	1.818	41	0.945	1.087	56	1.585	0.603
12	0.210	5.015	27	0.576	1.724	42	0.979	1.058	57	1.633	0.578
13	0.228	4.732	28	0.604	1.638	43	1.013	1.031	58	1.681	0.554
14	0.245	4.491	29	0.632	1.558	44	1.047	1.006	59	1.729	0.530
15	0.263	4.284	30	0.660	1.483	45	1.081	0.982	60	1.777	0.507
16	0.280	4.104	31	0.688	1.414	46	1.115	0.959	61	1.825	0.484
17	0.298	3.946	32	0.716	1.350	47	1.149	0.937	62	1.873	0.462
18	0.315	3.805	33	0.744	1.290	48	1.183	0.916	63	1.921	0.440
19	0.333	3.679	34	0.772	1.234	49	1.217	0.896	64	1.969	0.418
20	0.350	3.565	35	0.800	1.181	50	1.251	0.877	65	2.017	0.396
21	0.368	3.461	36	0.828	1.131	51	1.285	0.859	66	2.065	0.375
22	0.385	3.367	37	0.856	1.082	52	1.319	0.842	67	2.113	0.354
23	0.403	3.282	38	0.884	1.035	53	1.353	0.826	68	2.161	0.333
24	0.420	3.205	39	0.912	0.990	54	1.387	0.811	69	2.209	0.312
25	0.438	3.135	40	0.940	0.946	55	1.421	0.796	70	2.257	0.292
26	0.455	3.071	41	0.968	0.904	56	1.455	0.782	71	2.305	0.272
27	0.473	3.012	42	0.996	0.863	57	1.489	0.768	72	2.353	0.252
28	0.490	2.958	43	1.024	0.824	58	1.523	0.755	73	2.401	0.232
29	0.508	2.908	44	1.052	0.786	59	1.557	0.742	74	2.449	0.212
30	0.525	2.862	45	1.080	0.750	60	1.591	0.729	75	2.497	0.193
31	0.543	2.819	46	1.108	0.715	61	1.625	0.717	76	2.545	0.174
32	0.560	2.778	47	1.136	0.681	62	1.659	0.705	77	2.593	0.155
33	0.578	2.738	48	1.164	0.648	63	1.693	0.694	78	2.641	0.136
34	0.595	2.699	49	1.192	0.616	64	1.727	0.683	79	2.689	0.117
35	0.613	2.661	50	1.220	0.585	65	1.761	0.672	80	2.737	0.099
36	0.630	2.625	51	1.248	0.555	66	1.795	0.662	81	2.785	0.081
37	0.648	2.589	52	1.276	0.526	67	1.829	0.652	82	2.833	0.063
38	0.665	2.555	53	1.304	0.497	68	1.863	0.642	83	2.881	0.045
39	0.683	2.521	54	1.332	0.469	69	1.897	0.632	84	2.929	0.027
40	0.700	2.488	55	1.360	0.442	70	1.931	0.622	85	2.977	0.010
41	0.718	2.456	56	1.388	0.416	71	1.965	0.612	86	3.025	0.002
42	0.735	2.425	57	1.416	0.391	72	2.000	0.602	87	3.073	0.000
43	0.753	2.394	58	1.444	0.366	73	2.034	0.592	88	3.121	0.000
44	0.770	2.364	59	1.472	0.342	74	2.068	0.582	89	3.169	0.000
45	0.788	2.334	60	1.500	0.318	75	2.102	0.572	90	3.217	0.000
46	0.805	2.305	61	1.528	0.295	76	2.136	0.562			
47	0.823	2.276	62	1.556	0.272	77	2.170	0.552			
48	0.840	2.247	63	1.584	0.250	78	2.204	0.542			
49	0.858	2.218	64	1.612	0.228	79	2.238	0.532			
50	0.875	2.189	65	1.640	0.206	80	2.272	0.522			
51	0.893	2.161	66	1.668	0.185	81	2.306	0.512			
52	0.910	2.133	67	1.696	0.164	82	2.340	0.502			
53	0.928	2.105	68	1.724	0.143	83	2.374	0.492			
54	0.945	2.077	69	1.752	0.122	84	2.408	0.482			
55	0.963	2.049	70	1.780	0.102	85	2.442	0.472			
56	0.980	2.021	71	1.808	0.082	86	2.476	0.462			
57	0.998	1.993	72	1.836	0.062	87	2.510	0.452			
58	1.015	1.965	73	1.864	0.042	88	2.544	0.442			
59	1.033	1.937	74	1.892	0.022	89	2.578	0.432			
60	1.050	1.909	75	1.920	0.002	90	2.612	0.422			

	40°		41°		42°		
	Tang	Cotang	Tang	Cotang	Tang	Cotang	
0	.83910	1.19175	.86929	1.15037	.90040	1.11061	.93251
1	.83960	1.19105	.86980	1.14969	.90093	1.10996	.93301
2	.84009	1.19035	.87031	1.14902	.90146	1.10931	.93351
3	.84059	1.18964	.87082	1.14834	.90199	1.10867	.93401
4	.84108	1.18894	.87133	1.14767	.90251	1.10802	.93451
5	.84158	1.18824	.87184	1.14699	.90304	1.10737	.93501
6	.84208	1.18754	.87236	1.14632	.90357	1.10672	.93551
7	.84258	1.18684	.87287	1.14565	.90410	1.10607	.93601
8	.84307	1.18614	.87238	1.14498	.90463	1.10543	.93651
9	.84357	1.18544	.87389	1.14430	.90516	1.10478	.93701
10	.84407	1.18474	.87441	1.14363	.90569	1.10414	.93751
11	.84457	1.18404	.87492	1.14296	.90621	1.10349	.93801
12	.84507	1.18334	.87543	1.14229	.90674	1.10285	.93851
13	.84556	1.18264	.87595	1.14162	.90727	1.10220	.93901
14	.84606	1.18194	.87646	1.14095	.90781	1.10156	.93951
15	.84656	1.18125	.87698	1.14028	.90834	1.10091	.94001
16	.84706	1.18055	.87749	1.13961	.90887	1.10027	.94051
17	.84756	1.17986	.87801	1.13894	.90940	1.09963	.94101
18	.84806	1.17916	.87852	1.13828	.90993	1.09899	.94151
19	.84856	1.17846	.87904	1.13761	.91046	1.09834	.94201
20	.84906	1.17777	.87955	1.13694	.91099	1.09770	.94251
21	.84956	1.17708	.88007	1.13627	.91153	1.09706	.94301
22	.85006	1.17638	.88059	1.13561	.91206	1.09642	.94351
23	.85057	1.17569	.88110	1.13494	.91259	1.09578	.94401
24	.85107	1.17500	.88162	1.13428	.91313	1.09514	.94451
25	.85157	1.17430	.88214	1.13361	.91366	1.09450	.94501
26	.85207	1.17361	.88265	1.13295	.91419	1.09386	.94551
27	.85257	1.17292	.88317	1.13228	.91473	1.09322	.94601
28	.85308	1.17223	.88369	1.13162	.91526	1.09258	.94651
29	.85358	1.17154	.88421	1.13096	.91580	1.09195	.94701
30	.85408	1.17085	.88473	1.13029	.91633	1.09131	.94751
31	.85458	1.17016	.88524	1.12963	.91687	1.09067	.94801
32	.85509	1.16947	.88576	1.12897	.91740	1.09003	.94851
33	.85559	1.16878	.88628	1.12831	.91794	1.08940	.94901
34	.85609	1.16809	.88680	1.12765	.91847	1.08876	.94951
35	.85660	1.16741	.88732	1.12699	.91901	1.08813	.95001
36	.85710	1.16672	.88784	1.12633	.91955	1.08749	.95051
37	.85761	1.16603	.88836	1.12567	.92008	1.08686	.95101
38	.85811	1.16535	.88888	1.12501	.92062	1.08622	.95151
39	.85862	1.16466	.88940	1.12435	.92116	1.08559	.95201
40	.85912	1.16398	.88992	1.12369	.92170	1.08496	.95251
41	.85963	1.16329	.89045	1.12303	.92224	1.08432	.95301
42	.86014	1.16261	.89097	1.12238	.92277	1.08369	.95351
43	.86064	1.16192	.89149	1.12172	.92331	1.08306	.95401
44	.86115	1.16124	.89201	1.12106	.92385	1.08243	.95451
45	.86166	1.16056	.89253	1.12041	.92439	1.08179	.95501
46	.86216	1.15987	.89306	1.11975	.92493	1.08116	.95551
47	.86267	1.15919	.89358	1.11909	.92547	1.08053	.95601
48	.86318	1.15851	.89410	1.11844	.92601	1.07990	.95651
49	.86368	1.15783	.89463	1.11778	.92655	1.07927	.95701
50	.86419	1.15715	.89515	1.11713	.92709	1.07864	.95751
51	.86470	1.15647	.89567	1.11648	.92763	1.07801	.95801
52	.86521	1.15579	.89620	1.11582	.92817	1.07738	.95851
53	.86572	1.15511	.89672	1.11517	.92872	1.07676	.95901
54	.86623	1.15443	.89725	1.11452	.92926	1.07613	.95951
55	.86674	1.15375	.89777	1.11387	.92980	1.07550	.96001
56	.86725	1.15309	.89830	1.11321	.93034	1.07487	.96051
57	.86776	1.15240	.89883	1.11256	.93088	1.07425	.96101
58	.86827	1.15172	.89935	1.11191	.93143	1.07362	.96151
59	.86878	1.15104	.89988	1.11126	.93197	1.07299	.96201
60	.86929	1.15037	.90040	1.11061	.93252	1.07237	.96251
	Cotang	Tang	Cotang	Tang	Cotang	Tang	Cotang
	49°		48°		47°		



Table of Natural Tangents and Cotangents

44°				44°				44°	
Tang	Cotang			Tang	Cotang			Tang	Cotang
.96570	1.03553	60	20	.97700	1.02355	40	40	.98843	1.011
.96625	1.03493	59	21	.97756	1.02295	39	41	.98901	1.011
.96681	1.03433	58	22	.97813	1.02236	38	42	.98958	1.010
.96738	1.03372	57	23	.97870	1.02176	37	43	.99016	1.009
.96794	1.03312	56	24	.97927	1.02117	36	44	.99073	1.009
.96850	1.03252	55	25	.97984	1.02057	35	45	.99131	1.008
.96907	1.03192	54	26	.98041	1.01998	34	46	.99189	1.008
.96963	1.03132	53	27	.98098	1.01939	33	47	.99247	1.007
.97020	1.03072	52	28	.98155	1.01879	32	48	.99304	1.007
.97076	1.03012	51	29	.98213	1.01820	31	49	.99362	1.006
.97133	1.02952	50	30	.98270	1.01761	30	50	.99420	1.005
.97189	1.02892	49	31	.98327	1.01702	29	51	.99478	1.005
.97246	1.02832	48	32	.98384	1.01642	28	52	.99536	1.004
.97302	1.02772	47	33	.98441	1.01583	27	53	.99594	1.004
.97359	1.02713	46	34	.98499	1.01524	26	54	.99652	1.003
.97416	1.02653	45	35	.98556	1.01465	25	55	.99710	1.002
.97472	1.02593	44	36	.98613	1.01406	24	56	.99768	1.002
.97529	1.02533	43	37	.98671	1.01347	23	57	.99826	1.001
.97586	1.02474	42	38	.98728	1.01288	22	58	.99884	1.001
.97643	1.02414	41	39	.98786	1.01229	21	59	.99942	1.000
.97700	1.02355	40	40	.98843	1.01170	20	60	1.00000	1.000
Cotang	Tang			Cotang	Tang			Cotang	Tan
45°				45°				45°	

De- grees	Secants						
	0'	10'	20'	30'	40'	50'	60'
0	1.00000	1.00001	1.00002	1.00004	1.00007	1.00011	1.00016
1	1.00015	1.00021	1.00027	1.00034	1.00042	1.00051	1.00061
2	1.00061	1.00072	1.00083	1.00095	1.00108	1.00122	1.00137
3	1.00137	1.00153	1.00169	1.00187	1.00205	1.00224	1.00244
4	1.00244	1.00265	1.00287	1.00309	1.00333	1.00357	1.00382
5	1.00382	1.00408	1.00435	1.00463	1.00491	1.00521	1.00551
6	1.00551	1.00582	1.00614	1.00647	1.00681	1.00715	1.00751
7	1.00751	1.00787	1.00825	1.00863	1.00902	1.00942	1.00983
8	1.00983	1.01024	1.01067	1.01111	1.01155	1.01200	1.01247
9	1.01247	1.01294	1.01342	1.01391	1.01440	1.01491	1.01543
10	1.01543	1.01595	1.01649	1.01703	1.01758	1.01815	1.01872
11	1.01872	1.01930	1.01989	1.02049	1.02110	1.02171	1.02234
12	1.02234	1.02298	1.02362	1.02428	1.02494	1.02562	1.02630
13	1.02630	1.02700	1.02770	1.02842	1.02914	1.02987	1.03061
14	1.03061	1.03137	1.03213	1.03290	1.03368	1.03447	1.03528
15	1.03528	1.03609	1.03691	1.03774	1.03858	1.03944	1.04030
16	1.04030	1.04117	1.04206	1.04295	1.04385	1.04477	1.04569
17	1.04569	1.04663	1.04757	1.04853	1.04950	1.05047	1.05146
18	1.05146	1.05246	1.05347	1.05449	1.05552	1.05657	1.05762
19	1.05762	1.05869	1.05976	1.06085	1.06195	1.06306	1.06418
20	1.06418	1.06531	1.06645	1.06761	1.06878	1.06995	1.07115
21	1.07115	1.07235	1.07356	1.07479	1.07602	1.07727	1.07853
22	1.07853	1.07981	1.08109	1.08239	1.08370	1.08503	1.08636
23	1.08636	1.08771	1.08907	1.09044	1.09183	1.09323	1.09464
24	1.09464	1.09606	1.09750	1.09895	1.10041	1.10189	1.10338
25	1.10338	1.10488	1.10640	1.10793	1.10947	1.11103	1.11260
26	1.11260	1.11419	1.11579	1.11740	1.11903	1.12067	1.12233
27	1.12233	1.12400	1.12568	1.12738	1.12910	1.13083	1.13257
28	1.13257	1.13433	1.13610	1.13789	1.13970	1.14152	1.14335
29	1.14335	1.14521	1.14707	1.14896	1.15085	1.15277	1.15470
30	1.15470	1.15665	1.15861	1.16059	1.16259	1.16460	1.16663
31	1.16663	1.16868	1.17075	1.17283	1.17493	1.17704	1.17918
32	1.17918	1.18133	1.18350	1.18569	1.18790	1.19012	1.19236
33	1.19236	1.19463	1.19691	1.19920	1.20152	1.20386	1.20622
34	1.20622	1.20859	1.21099	1.21341	1.21584	1.21830	1.22077
35	1.22077	1.22327	1.22579	1.22833	1.23089	1.23347	1.23607
36	1.23607	1.23869	1.24134	1.24400	1.24669	1.24940	1.25214
37	1.25214	1.25489	1.25767	1.26047	1.26330	1.26615	1.26902
38	1.26902	1.27191	1.27483	1.27778	1.28075	1.28374	1.28676
39	1.28676	1.28980	1.29287	1.29597	1.29909	1.30223	1.30541
40	1.30541	1.30861	1.31183	1.31509	1.31837	1.32168	1.32501
41	1.32501	1.32838	1.33177	1.33519	1.33864	1.34212	1.34563
42	1.34563	1.34917					

## Contents

Cosecants							
0'	10'	20'	30'	40'	50'	60'	
∞	343.77516	171.88831	114.59301	85.94561	68.75736	57.29889	89
57.29889	49.11406	42.97571	38.20155	34.38232	31.25758	28.65371	88
28.65371	26.45051	24.56212	22.92559	21.49368	20.23028	19.10732	87
19.10732	18.10262	17.19843	16.38041	15.63679	14.95788	14.33559	86
14.33559	13.76312	13.23472	12.74550	12.29125	11.86837	11.47371	85
11.47371	11.10455	10.75849	10.43343	10.12752	9.83912	9.56677	84
9.56677	9.30917	9.06515	8.83367	8.61379	8.40466	8.20551	83
8.20551	8.01565	7.83443	7.66130	7.49571	7.33719	7.18530	82
7.18530	7.03962	6.89979	6.76547	6.63633	6.51208	6.39245	81
6.39245	6.27719	6.16607	6.05886	5.95536	5.85539	5.75877	80
5.75877	5.66533	5.57493	5.48740	5.40263	5.32049	5.24084	79
5.24084	5.16359	5.08863	5.01585	4.94517	4.87649	4.80973	78
4.80973	4.74482	4.68167	4.62023	4.56041	4.50216	4.44541	77
4.44541	4.39012	4.33622	4.28366	4.23239	4.18238	4.13357	76
4.13357	4.08591	4.03938	3.99393	3.94952	3.90613	3.86370	75
3.86370	3.82223	3.78166	3.74198	3.70315	3.66515	3.62796	74
3.62796	3.59154	3.55587	3.52094	3.48671	3.45317	3.42030	73
3.42030	3.38808	3.35649	3.32551	3.29512	3.26531	3.23607	72
3.23607	3.20737	3.17920	3.15155	3.12440	3.09774	3.07155	71
3.07155	3.04584	3.02057	2.99574	2.97135	2.94737	2.92380	70
2.92380	2.90063	2.87785	2.85545	2.83342	2.81175	2.79043	69
2.79043	2.76945	2.74881	2.72850	2.70851	2.68884	2.66947	68
2.66947	2.65040	2.63162	2.61313	2.59491	2.57698	2.55930	67
2.55930	2.54190	2.52474	2.50784	2.49119	2.47477	2.45859	66
2.45859	2.44264	2.42692	2.41142	2.39614	2.38107	2.36620	65
2.36620	2.35154	2.33708	2.32282	2.30875	2.29487	2.28117	64
2.28117	2.26766	2.25432	2.24116	2.22817	2.21535	2.20269	63
2.20269	2.19019	2.17786	2.16568	2.15366	2.14178	2.13005	62
2.13005	2.11847	2.10704	2.09574	2.08458	2.07356	2.06267	61
2.06267	2.05191	2.04128	2.03077	2.02039	2.01014	2.00000	60
2.00000	1.98998	1.98008	1.97029	1.96062	1.95106	1.94160	59
1.94160	1.93226	1.92302	1.91388	1.90485	1.89591	1.88708	58
1.88708	1.87834	1.86990	1.86116	1.85271	1.84435	1.83608	57
1.83608	1.82790	1.81981	1.81180	1.80388	1.79604	1.78829	56
1.78829	1.78062	1.77303	1.76552	1.75808	1.75073	1.74345	55
1.74345	1.73624	1.72911	1.72205	1.71506	1.70815	1.70130	54
1.70130	1.69452	1.68782	1.68117	1.67460	1.66809	1.66164	53
1.66164	1.65526	1.64894	1.64268	1.63648	1.63035	1.62427	52
1.62427	1.61825	1.61229	1.60639	1.60054	1.59475	1.58902	51
1.58902	1.58333	1.57771	1.57213	1.56661	1.56114	1.55572	50
1.55572	1.55036	1.54504	1.53977	1.53455	1.52938	1.52425	49
1.52425	1.51918	1.51415	1.50916	1.50422	1.49933	1.49448	48
1.49448	1.48967	1.48491	1.48019	1.47551	1.47087	1.46628	47
1.46628	1.46173	1.45721	1.45274	1.44831	1.44391	1.43956	46
1.43956	1.43524	1.43096	1.42672	1.42251	1.41835	1.41421	45
60'	50'	40'	30'	20'	10'	0'	De- grees
Secants							





## **PART II**

**STRENGTH OF MATERIALS AND STABILITY  
OF STRUCTURES**



## INTRODUCTION

### EXPLANATION OF SUBJECT-MATTER AND NOTATION

#### 1. Introduction to Part II

**Subject-Matter of Part II.** In the thirty-one chapters of Part II are the necessary rules, formulas and data for computing the strength and stability of all ordinary forms of building-construction, whether of wood, steel, masonry, or masonry, and in fact of all but the more intricate problems of steel construction, with which few architects care to cope, and which, indeed, are especially within the province of the engineer.

**Rules and Formulas** have been reduced to their simplest forms, and, generally, require only an elementary knowledge of mathematics to understand. The application of the formulas is explained and in most cases their derivation, and it is believed that the formulas, constants and working stresses are representative of conservative and approved contemporary practice.

**Constants and Working Stresses.** In the use of constants for the strength of materials, the authors and editors have been guided by the practice of leading structural engineers, by the available records of tests and by their own experience of many years as practicing and consulting architects and engineers. Varying conditions of building-construction have been taken into account in an attempt made to adapt the values to the practical conditions usually existing in such construction. Every possible precaution has been taken to prevent the misapplication of rules and formulas and to insure absolute safety and to avoid waste of materials.

**Tables.** Much thought and labor have been expended on the preparation of numerous tables, to insure their accuracy and to arrange them in the most convenient form for use by architects and builders. Many of these tables were computed by the authors and editors, all have been carefully verified, and it is believed that they may be used with perfect confidence. In all cases, unless otherwise noted, they give the same values that would be obtained by using the formulas specially referred to, while they afford a great saving of space and labor and reduce to a minimum the danger of errors in making the necessary computations.

**Limitation of the Subject.** Owing to the nature of the subjects treated and the large number of pages required to include them all in one book of reference, some forms of construction are treated rather briefly. The intention is to give the data needed for immediate use rather than a complete discussion of the principles involved. Those who wish more complete discussions of the work of masons' work, carpenters' work, steelwork, etc., are referred to treatises on these branches of building-construction. References are made in the different chapters to various other books and periodicals containing more complete information on some of the subjects. The thirty-one chapters of Part II are principally with foundations, walls and piers, arches, columns, beams, girders, floors, mill-construction, fireproofing, reinforced-concrete construction, roof-trusses, wind-bracing, and domes and vaults.

## 2. Explanation of the Notation or Symbols used in Part

Besides the usual mathematical signs and characters in general use, the following abbreviations and symbols are frequently used:

- $A$  area of cross-section; also, a constant used in Chapter XVI and to  $\frac{1}{2}$  the safe unit fiber-stress;
- $a, b, c, \dots m$ , etc., known or given distances;
- $b$  breadth, as of beams;
- $C$  coefficient of strength;
- $c$  normal distance from neutral axis of cross-section of beam to distant fiber in same;
- $d$  diameter, as of rivets; exterior diameter; depth, as of beams;
- $d_i$  interior diameter;
- $E$  modulus of elasticity;
- $E_s, E_c$  modulus of elasticity for steel and concrete respectively (reinforced concrete);
- $e$  total deformation or change in length, as in a bar;
- $F$  shearing-modulus of elasticity;
- $f$  maximum deflection for a beam;
- $h$  distance between parallel axes for moments of inertia;
- $I$  moment of inertia about a line;
- $I/c$  section-modulus or section-factor;
- $J$  polar moment of inertia;
- $J'$  polar moment of inertia of bolts about shaft-axis;
- $K$  total elastic resistance of a bar; resilience, work; also, a constant used in formulas for reinforced concrete;
- $l$  length; span of a beam;
- $M$  bending moment;
- $M_{\max}$  maximum bending moment;
- $M_1, M_2$ , etc., bending moments at supports of beams;
- $M_r$  or  $SI/c$  moment of resistance;
- $n$  number of loads, spans, etc.;
- $P$  external force; concentrated load;
- $P_1, P_2, P_3$ , etc., concentrated loads on beams;
- $p$  pitch of rivets; eccentricity of load on column; ratio of cross-section of steel to cross-section of beam (reinforced concrete);
- $r$  radius of curvature; radius; radius of gyration; ratio of  $E_s$  to  $E_c$  for concrete (reinforced concrete);
- $R_1, R_2, R_3$ , etc., reactions at the supports of a beam;
- $S$  unit stress, with subscripts  $t, c$  and  $s$  for unit stress in tension, compression and shear, respectively;
- $S_b$  buckling resistance in webs of steel beams;
- $S_h$  horizontal unit shearing-stress in beams;
- $S_e$  elastic limit;
- $S_f$  modulus of rupture, or computed flexural strength;
- $t_1, t_2$ , etc., thicknesses;
- $V$  vertical shear;
- $W$  weight of a bar or beam; total uniform load on beam (may include weight of beam);
- $w$  total uniform load on a beam (may include weight of beam);
- $w$  weight of a cubic unit of material; uniform load on beam, per unit of length;

\* See, also, page 3 of Part I.

$x, y, z$ , variable distances;

$a, b$ , etc., material constants;

$\phi$  constant depending upon material;

$\theta$  an angle.

Black letters are used generally for signs of operation, for abstract numbers or angles.  $\Sigma$  is employed as a symbol of summation.

The following are the Greek letters most in use:

$\alpha$ Alpha,	$\beta$ Beta,	$\epsilon$ Epsilon,	$\eta$ Eta,
$\theta$ Theta,	$\kappa$ Kappa,	$\lambda$ Lambda,	$\mu$ Mu,
$\nu$ Nu,	$\pi$ Pi,	$\rho$ Rho,	$\sigma$ Sigma,
$\tau$ Tau,	$\phi$ Phi,	$\psi$ Psi,	$\omega$ Omega.

In a few places in the book it has been considered necessary or advised by some of the associate editors to give a different meaning to one or more of the above symbols or to introduce different symbols for the meanings in the list, but in all such cases the new symbols or meanings have been clearly indicated.

**BREADTH** is used to denote the horizontal thickness of a beam or smaller dimension of the cross-section of a rectangular column, post or rod and is always measured in inches unless expressly stated otherwise.

**DEPTH** denotes the vertical height of a beam or girder, and is always measured in inches unless expressly stated otherwise.

**LENGTH** denotes the distance between supports and is always measured in feet unless expressly stated otherwise.

**Abbreviations.** In order to shorten the formulas, the tabulations of computation, etc., and throughout the text generally, to economize space, the units of measurement are generally abbreviated. For example, foot and feet are abbreviated ft; inch and inches, in; pound and pounds, lb; square, sq; cubic, cu; in; inch-pound or inch-pounds, in-lb; foot-pound or foot-pounds, ft-lb; h.p.; horse-power, h.p.; gallons, gal; etc.; and no periods are placed after abbreviations, except at the ends of sentences. Where the word TON is used in this volume, it always means the net ton of 2 000 lb.

## CHAPTER I

**EXPLANATION OF TERMS USED IN ARCHITECTURAL ENGINEERING**

By

THOMAS NOLAN

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

**1. Definitions of Some of the Terms Used in the Mechanics of Materials \***

**Terms Used in Architectural Engineering.** The following terms frequently occur in discussions of the principles of architectural engineering and an understanding of their meaning is essential.

**Mechanics** is the branch of physics that treats of the phenomena connected with the action of forces on material bodies.

**Applied Mechanics** treats of the laws of mechanics as applied to construction in the useful arts, as in beams, trusses, arches, etc.

**Mechanics of Materials** treats of the effects of forces in causing changes in the size and shape of bodies.

**Rest** is the relation that exists between two points when the strain joining them does not change in length or direction. A body is at rest relative to a point when any point in the body is at rest relatively to the first-named point.

**Motion** is the relation that exists between two points when the strain joining them changes in length or direction, or in both. A body moves relative to a point when any point in the body moves relatively to the first-named point.

**Force** is that which changes, or tends to change, the state of rest or motion of the body acted upon. It is a cause regarding the essential nature of which we are ignorant. In the mechanics of materials we do not deal with the causes of forces, but only with the laws of their action.

**Equilibrium** is that condition of a body in which the forces acting on it balance or neutralize each other; or, it is that condition of a force-system in which the resultant of the force-system is zero.

**Statics** is the branch of Mechanics that treats of the conditions of equilibrium. It is divided into:

(1) Statics of rigid bodies.

(2) Statics of practically incompressible fluids.

In building-construction we have to deal only with the former.

**Structures** are artificial constructions in which all the parts are interdependent and be in equilibrium and at rest relatively to each other, as in the case of a truss or roof-truss. They consist of two or more solid bodies, generally called **PIECES** or **MEMBERS**, which are connected at different parts of their surfaces by what are called **JOINTS**.

\* In addition to the terms defined here, many others are defined in the chapters of Part II, and especially in Chapters VI, IX, X, XIV, XV, XVI, XX and XXIV.

**General** there are three conditions of equilibrium in a structure.

**(1)** The external forces acting upon the whole structure must balance each other.

**(2)** These forces are:

**(a)** The weight of the structure;

**(b)** The loads it carries;

**(c)** The upward supporting forces, reactions or resistances under or around foundations.

**(3)** The forces acting upon each piece of the structure must balance each other.

**(4)** These forces are, for each piece:

**(a)** The weight of the piece;

**(b)** The loads it carries;

**(c)** The resistances or reactions at its joints.

**(5)** The forces acting upon each of the parts into which any piece may be divided must balance each other.

**The Stability of a Structure** requires the fulfilment of conditions (1) and (3), that is, the ability of the structure to resist the **DISPLACEMENT** of any of its parts.

**The Strength of a Piece or Member** consists in the fulfilment of condition (3), that is, the ability of a piece to resist **BREAKING**.

**The Stiffness of a Piece or Member** consists in the ability of a piece to resist **BENDING**.

**The Theory of Structures** is divided into two parts:

**(1)** That which treats of strength and stiffness, dealing only with single materials and generally known as the **STRENGTH OF MATERIALS** or the **MECHANICS OF MATERIALS**, before defined.

**(2)** That which treats of stability, dealing with the structures themselves.

**Stress** is an internal force that resists a change in shape or size caused by external forces. When the applied external forces reach certain intensities internal stresses hold them in equilibrium.

**The Intensity of a Stress** is measured by the **UNIT STRESS**. (See Unit Stress.)

**(1)** The **INTENSITY OF THE STRESS** per square inch on any normal surface of a solid is the total stress divided by the area of the section in square inches.

**(2)** If a bar 10 ft long and 2 in square has a load of 8 000 lb pulling in the direction of its length, the stress on any normal section of the bar is 8 000 lb; the intensity of the stress per square inch is  $8\,000\text{ lb}/4\text{ sq in} = 2\,000\text{ lb per sq in}$ .

**Deformation.\*** When a solid body is acted upon by an external force an alteration takes place in the volume and shape of the body, and this alteration is called the **DEFORMATION**. In the case of the bar given above, the deformation is the amount that the bar stretches under its load.

**The Ultimate Strength** is the highest unit stress a piece of material can sustain and it is the unit stress at or just before rupture.

**The Working Unit Stress** is the ultimate stress divided by the factor of safety.

**The Safe Load** is the load that a piece can support without exceeding the working unit stresses.

In mechanics the term **STRAIN** is now synonymous with the term **DEFORMATION**. On account of the tendency to confuse the terms **STRAIN** and **STRESS** the term **DEFORMATION**, to denote change in shape and the term **STRAIN** is omitted in all discussions in the text-book.

**The Factor of Safety** \* of a piece of material under stress is the ratio of the ultimate strength of the material to the actual unit stress on the section-area; or it is the number by which the ultimate unit stress must be divided to give the working unit stress. In designing a piece of material to sustain a certain load, it is required that it shall be perfectly safe under all circumstances and hence it is necessary to make an allowance for any defects in the material, workmanship, etc. It is obvious, that, for materials of different composition, different factors of safety are required. Thus, steel being more homogeneous than wood and less liable to defects, does not require as high a factor of safety. Again, different kinds of stresses require different factors of safety. Thus, a long wooden column or strut requires a higher factor of safety than a wooden beam. As the factors of safety thus vary for different kinds of stresses and materials, the proper factors for the different kinds of stresses and conditions are given in considering the resistance of the various materials to those stresses under varying conditions.

**The Unit Stress** is the stress on a unit of section-area, and is usually expressed in pounds per square inch. (See Intensity of Stress.)

**Dead Loads and Live Loads.** The term **DEAD LOAD** means a load that is applied and increased gradually and that finally remains constant, such as the weight of a structure itself.

The term **LIVE LOAD** means a load that is applied suddenly and causes vibrations, such as a train traveling over a railway bridge. It has been found by experience that the effect of a live load on a beam or other piece of material has twice the destructive tendency of a dead load of the same magnitude and intensity. Hence a piece of material designed to carry a live load should have a factor of safety twice as large as one designed to carry a dead load. A load due to a crowd of people walking on a floor is usually considered to produce an effect which is a mean between that of a dead load and a live load, and a suitable factor of safety is adopted accordingly. In municipal ordinances and laws relating to the allowable loads for floors, the loads to be supported are usually referred to as the **LIVE LOADS** no matter of what they may consist of. The term does not have the exact significance given to it by many engineers, and as explained in the paragraph above.

**The Modulus of Rupture or Computed Flexural Strength** is the unit stress of the **UNIT FIBER-STRESS**  $S$ , computed from the flexure-formula  $M = S I / c$  when a beam is ruptured under a transverse load. Its value is intermediate between the ultimate tensile and compressive strengths of a material.

**The Elastic Limit** is that unit stress at which the deformation of a piece of material begins to increase in a faster ratio than the applied loads. It is sometimes called the **ELASTIC STRENGTH**.

**The Modulus of Elasticity or Coefficient of Elasticity.** In physics this is often called **YOUNG'S MODULUS**. If we take a bar of any material, say one inch square, of any length, and secured at one end, and at the other apply a force, say a certain number of pounds  $P$ , pulling in the direction of the length,

\* The **ELASTIC LIMITS** of materials must be considered in deciding upon working stresses and in forming a judgment of the security of materials under stress. When the elastic limit is considered the actual allowable unit stress is made a certain percentage of it, as 35 or 50%, according to varying conditions. Both **ULTIMATE STRENGTHS** and **ELASTIC LIMITS** must be taken into account in practice. But the use of the **FACTOR OF SAFETY** as determined by the old method, is still a great help in the study and application of the principles of the mechanics of materials, and is used frequently in the Pocket



length, we shall find by careful measurement that the bar has been stretched by the action of the force. If we divide the TOTAL ELONGATION  $e$ , by the original length  $l$  of the bar, in inches, we shall have  $e/l$ , the ELONGATION  $e$ , or the elongation of the bar per unit of length; and if we divide the unit stress  $S$ , developed (that is, in this case, the external force  $P$ , divided by the area of the cross-section  $A$ , or  $P/A$ ) by this ratio we shall have a quantity known as the MODULUS OF ELASTICITY,  $E$ . Expressed in symbols and

equations,  $E = S / (e/l) = \frac{P/A}{e/l}$ . Hence, we may define the MODULUS OF ELAS-

ticity as the ratio of the unit stress to the unit deformation. Another definition is the force which would elongate a bar of 1 sq in in cross-section to double its original length, if that could be done without exceeding the ELASTIC LIMIT of the material. This is evident from the above equation; for if  $A = 1$  and  $E$  will equal  $P$ . These formulas apply only when the unit stress  $S$  or  $P/A$  is less than the ELASTIC LIMIT of the material.  $e$  is an ABSTRACT NUMBER,  $e$  and  $l$  are both linear quantities, and hence  $E$  is expressed in the same units as  $S$ , that is, in POUNDS PER SQUARE INCH.

As an example of one method of determining the modulus of elasticity of any material the following illustration is given:

Suppose we have a bar of wrought iron, 2 in square and 10 ft long, securely fixed at one end, and to the other end we apply a tensile force of 40 000 lb. This force causes the bar to stretch, and by careful measurement we find the elongation to be 0.0414 in. As the bar is 10 ft, or 120 in long, if we divide 0.0414 by 120, we shall have the elongation of the bar per unit of length. Performing this operation, we have as the result, 0.00034 in. As the bar is 2 in square, the area of cross-section is 4 sq in, and hence the stress per square inch is 10 000 lb. Dividing 10 000 by 0.00034, we have, as the MODULUS OF ELASTICITY of the bar, 29 400 000 lb per sq in. This is the method generally employed to determine the MODULUS OF ELASTICITY of iron ties; but  $E$  can also be determined from the DEFLECTION of beams, and it is in that way that its values for woods have been found. The modulus of elasticity is used in the determination of the STIFFNESS of beams.

The Moment of a Force with respect to an axis is the product obtained by multiplying the magnitude of the force by the shortest distance from the axis to its line of action. The shortest distance is called the LEVER-ARM of the force. The moment of the force is the measure of the tendency of the force to cause ROTATION about the axis. (See Chapter VI and IX.)

The Center of Gravity of a body is the point in the body through which the RESULTANT of the forces exerted by gravity upon all the particles of the body passes. A body may be balanced upon a point placed above or below the center of gravity, because the RESULTANT of any number of forces may be brought into equilibrium by an equal and opposite force. Another definition of the CENTER OF GRAVITY of a body or bodies is: a point such that there is NO TENDENCY TO ROTATION about any axis drawn through it. (For center of gravity of surfaces, lines and solids, see Chapter VI.)

## 2 Classification of the Principal Stresses Caused in Bodies by External Forces

Tension is the stress that resists the tendency of two forces acting away from each other to PULL APART two adjoining planes of a body.

Compression is the stress that resists the tendency of two forces acting toward each other to PUSH TOGETHER two adjoining planes of a body.

**Shear** is the stress that resists the tendency of two equal parallel forces acting in opposite directions to cause two adjoining planes of a body to slide on the other.

**Torsion** is the stress that resists the tendency of forces to TWIST a body.

**Combined Stresses.** Parts of structures are often acted upon by external forces which develop stresses of different character, such as flexure and compression, flexure and tension, flexure and torsion, shear and compression or tension, torsion and compression, etc.

## CHAPTER II

### FOUNDATIONS

By

DANIEL E. MORAN

MEMBER OF AMERICAN SOCIETY OF CIVIL ENGINEERS

#### 1. Definition of the Word and Terms Used

**Definition.** The word **FOUNDATION** is derived from the Latin verb **FUNDARE** meaning to establish or lay the base, bottom, keel or foundation of anything. The English word is used in the broadest possible way to describe the base, natural or otherwise, on which anything is supported, and in technical language may be used to describe any part of a structure on which a subsequent operation or construction is superimposed. Thus a plaster wall may be called the **FOUNDATION** for a fabric to be stretched thereon and the fabric in turn becomes the **FOUNDATION** for various coats of paint or other decorations. More specifically in relation to a building or other complete structure the word **FOUNDATION** is unfortunately applied indiscriminately (1) to construction below grade, including courses, cellar walls, etc., forming the lower section of the structure; (2) to the natural material, the particular part of the earth's surface on which the construction rests; and (3) to special construction such as piling or masonry to transmit the loads of the building to firm substrata. In view of the indefinite meaning of the word it is advisable to use it either to distinguish work below grade, or below the tier of beams nearest to grade, from work above grade. In even a still more restricted sense, it might include only the work from the cellar or basement-floor to rock or other solid foundation-bed. (Chapter II, Subdivision 29, Chapter III, Subdivision 2, and Water-Proofing for Foundations, Part III.)

**Foundation-Bed.** The natural material on which the construction is called the **FOUNDATION-BED**. Walls, piers and columns below grade are called, in general, **FOUNDATION WALLS, PIERS AND COLUMNS** to distinguish them from similar construction above grade and occasionally those only from the basement-floor are so called; the lower portions of walls, piers or columns which are spread to provide a safe base will be called **FOOTING COURSES**.

#### 2. General Requirements

**Object of Foundations.** The object to be borne in mind in designing a foundation is to provide a safe and permanent base for the superstructure so that the movement of the base and of the superimposed structure shall be at a minimum possible and shall result in the least possible damage to the structure. To meet the above requirements the design and construction should fulfill the following conditions:

**The Materials of Construction** should be proof against all deteriorating influences, or, if any of the materials are liable to deterioration they should be suitably protected.

**Stresses and Future Changes.** No part of the foundation-structure shall, under any combination of loadings, be stressed beyond safe limits, and the possibility of future additions or changes in the superstructure, or of a change in the use of the building, should be kept in mind.

(3) **The Load on the Natural Bed** should be kept within the safe limit of material, under the worst conditions to which it may be exposed. In this limit the amount of settlement allowable will in many cases determine the limit rather than the safe ultimate bearing capacity.

(4) **Adjoining Excavations.** The possible danger to the structure or stability of the foundation-bed from adjoining excavations or other discauses should be guarded against as far as possible.

**Physical Conditions of the Site.** In order to meet the above requirements the design should be suited to the physical conditions existing at the site. The architect or engineer should personally examine the site. He should collect all available information relative thereto and, if necessary, should make soundings and tests so as to secure reliable information on which to base his design of the foundation. The first step is, therefore, a detailed and exhaustive study of the site to determine the characteristics of the foundation-bed on which the structure is to rest.

### 3. Geological Considerations

**Character of the Foundation-Bed.** A knowledge of geology is of great assistance in many cases in making a proper estimate of the character of the foundation-bed. While it is not proposed in the limits of this chapter to enter into any general geological discussion the following notes may be of value in assisting the architect to determine whether any given deposits can be relied upon as affording a stable foundation-bed. Broadly speaking, as the location of the building may be in any part of the world, so the materials encountered will belong to any one of the many geological formations forming the surface of the earth. For practical purposes, however, the materials met with are usually divided into **ROCK**, or materials other than rock, roughly defined as **EARTH**.

### 4. Composition and Classification of Rocks

**Composition of Rocks.** Rocks, and the earthy deposits derived from them, are composed of various minerals of which many hundred kinds are known, each varying from the others in some particular of chemical composition, mode of crystallization or other characteristic. A rock or an earthy deposit may consist almost entirely of a single mineral, but it is usually composed of several distinct minerals or of mixtures of minerals. The principal classes of minerals forming rocks are:

- (1) **The Silica Minerals**, composed of silica ( $\text{SiO}_2$ ) in different forms;
- (2) **Silicates** or combinations of silica, with various metallic bases;
- (3) **Calcareous Minerals** composed of calcite or carbonate of lime (and its combinations).

(1) **Silica Minerals** are different forms of the oxide of silicon, known as **SILICA**. In the crystalline state silica is known as

**Quartz.** This is the most abundant of all minerals. Owing to its hardness and insolubility it resists decomposition and abrasion better than the materials with which it is associated and grains of it form the principal constituents of sandy deposits. In finely comminuted particles it forms a part of most silty clays.

**Flint, Chert, Agate, etc.,** are non-crystalline varieties of silica. Silica forms the cementing material in many sandstones and other rocks.

(2) **Silicates** or combinations of silica with various bases are second in importance only to quartz.

quartz, an important constituent of granite and other igneous rocks, is a silicate of alumina with potash, soda or lime. When exposed to the action of water it slowly decomposes, forming silicate of alumina, the base of clay. The decomposition of granite results in the formation of clay and crystals of quartz. The mica is very slowly affected and the quartz is practically unaffected.

The various mica minerals are silicates of alumina, with potash and soda as constituents. All varieties are soft and split into thin elastic plates. Small particles of mica are frequently found in sand.

Diopside and Augite are silicates of lime, magnesia, iron and alumina and are of frequent occurrence.

Zeolite, Talc and Soapstone Travertine are hydrated silicates formed from primary silicates by a chemical change in which a certain amount of water is absorbed. These minerals are soft and have a SOAPY FEEL. Special care should be taken in building foundations on rock of this character to guard against any separation on the foundation-bed or between parts of the foundation-bed.

**Calcareous Minerals.** The following are the principal calcareous minerals:

**Calcite** ( $\text{CaCO}_3$ ), carbonate of lime, when pure and crystallized, is known as **SPAR**. It is soluble in water containing  $\text{CO}_2$ . Calcite in varying degrees of purity forms limestone and marbles. As a result of its solubility cracks and voids are frequently found in limestone.

**Dolomite** is a carbonate of lime and magnesia. It forms the so-called **DOLOMITIC LIMESTONES**, which are less soluble than the calcite limestone.

**Malachite, Gypsum, Alabaster, Anhydrite, Aragonite and Apatite** are other and important lime-minerals.

**Classification of Rocks.** Rocks are classified not only according to the materials of which they are composed, but also according to the way in which they have been formed, as:

**Igneous Rocks**, which have solidified from a molten condition;

**Sedimentary Rocks**, which have been formed under water by mechanical action or by cementation due to chemical or organic processes;

**Metamorphic or Plutonic Rocks**, which have changed from their original character as igneous or sedimentary rocks.

**Igneous or Plutonic Rocks** are not truly stratified. They may be crystalline or glassy in texture. **GRANITE, SYENITE, BASALT, TRAP**, etc., are examples. **LAVA, PUMICE** and **OBSIDIAN** are volcanic products, as are also the deposits of mud and ash. With the exception of volcanic ash and mud, igneous rocks are enduring and are not liable to present any unforeseen weaknesses in foundation-beds.

**Sedimentary Rocks** are composed of sand, clay and other materials derived from the breaking down of the original igneous rocks. These materials are deposited in horizontal beds generally by settling from water, and the consolidation into rock was generally affected under water by chemical, mechanical and organic action. The resultant rock-masses are stratified as a result of their constituent materials having been deposited in layers. As sand and clay are the most abundant products of rock-decomposition, so the sedimentary rocks are frequently **SILICEOUS** (sandy) or **ARGILLACEOUS** (clayey).

**Sandstone** is composed of grains of sand cemented together by silica, oxides of iron, or carbonate of lime. The durability of sandstone depends on the solu-

bility of the cementing material. Carbonate of lime being soluble, sandstones containing it as cementing material yield to the weather and are not so durable as sandstones having silica or iron oxide as cementing material.

**Argillaceous Rocks** contain clay with fine sand, mud, etc., and while some other varieties are compact and hard when first uncovered, they are liable to deterioration when exposed to frost, water and other disintegrating agencies.

**Limestone** is composed more or less of carbonate of lime derived from the calcareous skeletons of marine animal and vegetable organisms. The character of limestone varies greatly. In so-called **FOSSILIFEROUS LIMESTONES** fossils of shells or corals indicate clearly its origin, but in other limestones there are no fossils or other indications of the organic origin of the calcareous material. Admixtures of sand, clay, or other impurities may make it difficult to distinguish certain limestones from sandstones or shales.

**Dolomite** is a limestone containing a high percentage of magnesia.

**Hydraulic Limestone** is a limestone containing clay.

**Chalk** is a soft limestone composed of the fine shells of minute marine organisms. In general, the purer the limestone the more soluble it is and the greater the danger from fissures or caverns due to the action of water.

(3) **Metamorphic or Plutonic Rocks** are rocks which have been changed from sedimentary or igneous rocks by heat, compression, or moisture, alone or in combination. Thus by heat from a nearby intrusion of molten material limestone is changed into a crystalline marble. The general effect of **METAMORPHISM** is to produce a hard or durable rock.

**Quartzite**, a metamorphosed sandstone, is a crystalline rock of great hardness and durability.

**Slate** is a hard dense rock, sometimes with a well-defined tendency to split into thin plates. It has been formed by metamorphic action from clayey sandstones. It is generally durable, but liable to slide along planes which are sometimes parallel to the cleavage, or along seams which are not parallel to the cleavage.

**Gneiss** is a "laminated metamorphic rock that usually corresponds geologically to some one of the plutonic types." \* There are many varieties of gneiss classified in accordance with the igneous rocks to which they most nearly correspond in composition. Some varieties resemble granite, but the laminated or striped aspect is generally characteristic. They are generally compact and durable.

**Schists** are similar to gneiss but are more finely foliated or striped. In **SCHIST** there are layers or foliations composed of fine grains or plates of mica. Mica-schists are liable to decomposition and it frequently happens that foundations have to be carried to great depths through decomposed rock of this character before solid rock is encountered. The material resulting from the decomposition of this rock contains fine grains of mica and other fine material. When wet, it acts as **QUICKSAND**.

**Rock as a Foundation.** All rock, if sound and not liable to slip, is proverbially a solid foundation and capable of supporting any weight. A building is likely to impose on it. Care should be taken that rock is not liable to disintegration is protected from the weather, water-action, or other disintegrating influences.

## 5. Geology of Earthy Material

**Earth and Soil.** Materials other than rock, resulting from the disintegration of rock-masses, are broadly classed as **EARTH**. The word **SOIL**, which

\* Kemp.

designate any earthy material not rock, is a misnomer, in that the idea of soil, or the lack of it, is conveyed when the word SOIL is used.

The agencies producing the disintegration of the rock masses which form or cover the entire surface of the earth, are various, but for the purpose of this chapter they may be defined as (1) CHEMICAL and (2) MECHANICAL.

**Chemical Agencies.** By CHEMICAL ACTION or DECOMPOSITION, a rock of great strength and hardness and of complicated mineralogical structure disintegrates into a noncoherent mass of elementary minerals. Thus a typical granite under the combined action of water and varying temperature disintegrates, the crystals of feldspar changing chemically and forming the silicate of aluminum known as CLAY, while the crystals of quartz, or hornblende, being more resistant to chemical action, retain their chemical identity but become detached particles of SAND.

**Mechanical Agencies.** By the MECHANICAL AGENCIES, such as the action of moving water or ice, fragments of rock are detached from the ledge of which they originally formed part and are subsequently transported, by the action of glaciers or streams, or by the wave-action in bodies of water. The action of these agencies breaks up the materials thus roughly thrown about into smaller and smaller pieces without altering the composition of the material.

**Flowing Water.** As flowing water more readily transports small particles than large ones, the larger pieces of rock move intermittently during periods of high water or flood and are deposited as soon as the velocity of the water falls; while smaller particles are held in suspension longer and, as the velocity of the water falls, are deposited in the order of their size, the largest first. The upper courses of streams and rivers in mountainous regions constantly roll and grind together the materials in their rocky beds, the heavy masses being moved slowly. The attrition between the fragments forms GRAVEL and SAND which are washed down stream to be deposited, as the current slackens, first as BEDS OF GRAVEL, then as SAND-BARS, and finally, in the slow-moving lower courses, as BEDS OF SILT and ALLUVIUM.

**Glacial and Glacial Deposits.** The action of glaciers is similar to the action of streams. Glacial deposits, the so-called GLACIAL DRIFTS, are composed of clay, gravel and boulders but, in general, there is a noticeable difference between glacial deposits and deposits made by rivers or streams. In glacial deposits the boulders frequently exhibit groovings or scratches on their faces and the edges and surfaces of the boulders are generally sharp, so that a boulder may appear as if it had been recently fractured. They rarely exhibit smooth, water-worn and rounded surfaces found on boulders formed by river action. Moreover, the glacial boulders may be found singly, or unassociated with other boulders in a deposit of sand or gravel. The deposit differs from a river-deposit in that there is no classification as to size; the boulders may lie on the surface or may be disseminated as if by accident through the sand and gravel forming the body of the deposit. Such glacial deposits partake of the character of a rough artificial fill without the stratification or classification which is characteristic of river-deposits. In glacial moraines or dump-mounds it not infrequently happens that the surface-water finds underground channels forming so-called SINK-HOLES. A line of glacial deposits extends across the continent of North America from Long Island westward. The southern limit may be determined by reference to geological maps.

**Glacial and River-Deposits Distinguished.** It is important to distinguish between GLACIAL and RIVER-DEPOSITS, because, while the occurrence of glacial deposits gives, in general, little or no information as to the character and value

of the surrounding deposits, the occurrence of boulders, on the other hand river-deposits is generally an indication that the bed of which they form has been thoroughly consolidated as a result of the river-action which formed, and, also, because such deposits generally extend down to rock or to some compact material which at the time the deposit was made was capable of resisting the action of rapidly flowing water.

**Wave-Action on Lakes and Along Coast-Lines** is constantly working the materials composing the beach. Rock-masses are broken away from the shore and ground together, producing boulders, gravel and sand. The sand is carried more readily by the tidal currents, is deposited in the more sheltered bays and forms BEACHES, while the larger rock-masses remain near the point of origin in BARS and REEFS.

**Beds of Sand, Gravel and Boulders** deposited by the action of waves on the SHORES OF SEAS OR LAKES are not necessarily constant in character and should be made to determine the character of the material underlying the BEACH-FORMATIONS. In large river-valleys where the general formations are composed of silt or other fine material little reliance should be placed on the occurrence of BEDS OF GRAVEL, even if such beds extend over large areas. It should be made to determine that such beds are not underlain by less worthy materials. Where tributary streams discharge into large valleys they may deposit BARS OF SAND, GRAVEL and BOULDERS on top of the silt, or other materials formerly deposited by the main river. (See page 136) In general topographical conditions should serve as an indication of dangerous cases.

**Results of Chemical and Mechanical Action.** As a result of the foregoing brief description of the agencies at work it may be seen that ICE ACTION and STREAM-ACTION alike tend to disrupt rock-masses and to produce boulders, gravel, sand and finer materials. The ultimate result of the combination of CHEMICAL ACTION and MECHANICAL ACTION is to reduce the hardest rock to the finest sand, the most impalpable clays, silts and muds; and the ACTION OF WAVE and MOVING WATER is to classify such materials in deposits of given uniform size.

## 6. Materials Composing Foundation-Beds

**Classification and Definitions.** The following list includes the materials which are most frequently encountered, with their definitions.

**Rock** (solid rock, bed-rock, or ledge). Undisturbed rock-masses forming an undisturbed part of the original rock-formation.

**Decayed Rock** (rotten rock). Sand, clays and other materials resulting from the disintegration of rock-masses, lacking the coherent quality of the original rock, occupying the space formerly occupied by the original rock.

**Loose Rock.** Rock-masses detached from the ledge of which they originally formed a part.

**Boulders.** Detached rock-masses larger than gravel, generally rounded or sub-rounded as a result of having been transported by water or ice a considerable distance from the ledges of which they originally formed a part.

**Gravel.** Detached rock-particles, generally water-worn, rounded and intermediate in size between sand-particles and boulders.

**Sand.** Non-coherent rock-particles smaller than  $\frac{1}{4}$  in in maximum diameter.



- g.** The material resulting from the decomposition and hydration of feldspar rocks, being hydrated silicate of alumina, generally mixed with powdered quartz and other materials.
- h.** Any strongly coherent mixture of clay or other cementing material with sand, gravel, or boulders.
- i.** A finely divided earthy material deposited from running water.
- j.** Finely divided earthy material generally containing vegetable matter deposited from still or slowly moving water.
- k.** Loosely used to describe any earthy material.
- l.** Earthy material capable of supporting vegetable life and generally material containing decayed vegetable or animal matter.
- m.** Earthy material containing a large proportion of humus or vegetable matter.
- n.** Earthy material containing a proportion of vegetable matter.
- o.** Compressed and partially carbonized vegetable matter.

## 7. Characteristics of the Materials of Foundation-Beds

**Bed Rock**, or, as it is locally known, **BED-ROCK**, or **LEDGE**, is proverbially the foundation. The harder rocks, such as granite, trap, slate, sandstone, etc., are all capable of carrying the load of any ordinary structure. Softer rocks, among which may be classed the shales, shaley slates and marley limestones and clay stones, should not be loaded with more than 100 lbs per sq ft unless they are tested for greater loads. In all cases where foundations are to be placed on what is supposed to be solid rock, care should be taken to determine whether or not the supposed solid consists of a detached mass, and, also, in case the bedding-planes of the rock are inclined, if there is danger from a slip of the layer forming the foundation-bed. (See pages 139 and 140 for side-slope locations.)

**Decayed Rock.** Certain igneous or metamorphic rocks such as granites, etc., frequently disintegrate, forming so-called **ROTTEN ROCK** or **DECAYED ROCK**. The decayed rock is generally found in conformity with the ledge of which it originally formed a part. It may retain the stratification, color and texture of the solid rock, but as a result of the disintegrating effect of water and other agents, it has lost the solid character of the original rock. When struck with a hammer it does not give the characteristic ringing sound of solid rock. It may be fairly compact and hard, or so soft as to be readily excavated with pick and shovel. The amount of such disintegrated rock overlying the solid rock varies greatly; in some cases the removal of a few inches will disclose the solid rock, in other cases the layer of decayed rock may be many feet in thickness. Test-borings in rotten rock give samples similar to the samples from solid rock so that it frequently happens that while the foundations are planned for solid rock the excavations disclose a thick layer of rotten rock. In such cases, it is impracticable to carry the footings down to solid rock, it may be necessary to increase the size of the footings or to adopt some other expedient.

**Loose Rock.** Where a rock-mass detached from the ledge of which it originally formed a part is encountered it must not be loaded in excess of the safe bearing capacity of the material by which it is surrounded. If the voids between adjacent pieces of loose rock are completely filled in with hard-pan, compact sand, or clay, the loading may be the same as for the filling-in material. It should be taken to determine that no voids exist. In natural rock-

fills, as in artificial rock-fills, it may happen that large voids exist between rock-masses, forming passageways for streams of water, in which case there is extreme danger of settlements.

**Boulders, Gravel and Sand.** Boulders are rock-masses which have been transported by water or ice-action. Boulders are sometimes found distributed through sand and clay and in such cases the load should be limited to the safe load of the material in which they are found. At other times boulders are found in beds, packed closely together, with the interstices filled in with sand, or clay. In such cases it is usually safe to assume that no further consolidation of the mass is likely to take place. If the bed of boulders extends to rock, they will safely sustain any load which will not crush them.

**Gravel.** The name GRAVEL is given to rock-particles larger than sand and smaller than the rock-masses known as BOULDERS. If compact, and resting on an underlying bed of poorer material exists, gravel forms a most desirable foundation-bed, equal to sand or boulders in supporting power and not as likely to be disturbed by adjoining excavations or pumping operations. If it rests on soft earth it may partake of the quality of hard-pan or rock. Care, however, should be taken to determine whether or not the bed of gravel has been deposited on a layer of silt or quicksand. It is possible for this dangerous condition to exist. (See page 134.)

**Sand.** Sand is composed of comminuted rock-material. As quartz is the most abundant rock-mineral and as its hardness and insolubility make it resistant to disintegrating action, it will be found to be the principal constituent of most deposits of sand or sandy material. Grains of mica, feldspar and other minerals are frequently found. Sand is described as being **MEDIUM**, or **COARSE**, according to the size of the grains of which it is composed.

**Coarse Sand** may contain particles of gravel, but after eliminating the coarse particles which will not pass a screen with 4 meshes to the inch it will be found that a large proportion of the remaining material is too coarse to pass a No. 20 sieve.

**Fine Sand**, on the other hand, may contain no particles which will not pass a No. 20-mesh sieve, and a considerable proportion which will pass a No. 100-mesh sieve.

**Very Fine Sand** is frequently mistaken for clay and, indeed, generally contains some clay, as clay generally contains fine sand.

**Uniform Sand** is sand in which there is relatively a small variation in the size of the particles.

**Balanced Sand** is sand in which the size of the particles varies from very small to very large and in which there is no great difference in the numbers of particles of each size.

**Clean Sand** contains no clay or loam, but a pure sand containing a large percentage of fine particles is often considered to be NOT CLEAN.

**Sharp Sand** is clean sand containing coarse, angular grains. When grasped in the hand it gives a NOTE, due to the particles slipping over each other. Sharp sand is generally esteemed for use in mortar, although it requires more cement to fill the voids and, in the writer's opinion, is not as desirable as rounded sand.

**Rounded or Buckshot Sand** is composed of rounded grains not compacted together.

**Quicksand.** This term is popularly used to describe any fine sand, mixture of fine sand and clay, which, when wet, forms a soft, unstable mass.

Popular mind quicksand is supposed to have some mysterious and peculiar properties which result in a tendency to FLOW LIKE WATER and to SUCK IN animate inanimate objects. These manifestations are connected with various causes as to the composition of quicksand, some persons insisting that quicksand must contain flakes of mica or some slippery mineral, others that the particles must be extremely fine or spherical in shape, while others contend that there must be a certain proportion of fine clay with the sand. The fact that any uncemented sand, when subjected to the action of moving water, moves and that any sand moving as the result of the action of water becomes quicksand. The finer the sand the more readily it is affected by a current of water, so that fine sands are more troublesome than coarse sands. A coarse sand having large voids, permits the flow of a certain amount of water through it; if this flow has not sufficient velocity to disturb the particles of the sand, the sand can be drained without moving it. In a fine sand, having very small voids, a similar flow of water will cause the whole mass to move and there is great difficulty in draining it without producing a current sufficient to cause it to move or flow.

Excavations in Quicksand are made difficult by the tendency of the sand along the sides of the excavation to flow into the excavation; and even if the sides of the excavation are protected, it not infrequently happens that the bottom of the excavation will LIFT, that is, there will be a movement of material at points outside of the line into the excavation, the movement in general being a curved line, and carrying the sand, under the protected side walls of the excavation. In such cases some advantage may be gained by surrounding the excavation with driven wells and draining the soil by continued pumping of sand; in other cases, wooden or steel sheeting may be driven to a point at the depth to which the excavation is to be carried, or to some underlying stratum of impervious material, in which case the sheeting will act as a coffer-dam to stop the flow of material. Such sheeting, however, must be practically airtight, as extremely fine sand, when in the condition of quicksand, will pass through very small apertures.

Quicksand as a Foundation-Bed is objectionable on account of the danger of moving or flowing, in case it finds any outlet such as would be afforded by adjoining excavation. Cases are known where excavations have permitted escape of quicksand and resulted in the settlement of buildings at a very considerable distance. Such settlements have occurred not only when the buildings themselves rested on quicksand, but also when they were on a stratum of coarse sand, gravel or clay of good quality which rested on an underlying stratum of quicksand.

Pockets of Quicksand. It frequently happens that pockets of fine sand are found in deposits of mixed character. Where such pockets are small in extent the fine sand may be removed and the spaces filled with concrete. Where the pockets are larger it may be necessary to carry piers through them to a better foundation-bed, to drive piles, or to resort to other expedients.

The Dry Sand is readily converted into quicksand by the addition of water, a fact should be carefully borne in mind in considering the load on fine sand, a material which in dry weather is apparently safe, may be, in wet weather, an extremely dangerous one. It is frequently stated that confined quicksand is perfectly reliable material on which to found a building. While this, as a fact, cannot be controverted, it is a dangerous assumption to act on because of the impossibility of providing that the fine sand shall be always confined.

Relation in the Size of Grains of Sand. The accompanying diagram (Fig. 1) shows graphically the results of sieve-tests on characteristic sands.

The dash-line curve (1) is an average, giving the results of sieve-tests on so-called quicksands; the full-line curve (2) gives the result of sieve-tests on natural sand which would be classed as a good building sand; the dot-and dash curve (3) gives the result of sieve-tests on a fine beach sand remarkable




Fig. 1. Graphical Illustration of Results of Sieve-tests on Sands

uniformity of the size of its grains. For purposes of comparison and in to show the variation in sands which appear to be substantially the same, a dotted curve (4) has been added. This shows the result of tests on a sand apparently as coarse as sand (2), but containing a much larger percent of fine particles between 0.015 and 0.0055 in diameter. Fine sand frequently contains a considerable proportion of clay. A chemical analysis of a so-called QUICKSAND from the down-town section of New York City, reported on by writer by Dr. C. F. McKenna, is as follows:

Mark: "Commercial Cable"

Silica.....	73.76%
Alumina and oxide of iron.....	18.52%
Lime.....	1.60%
Magnesia.....	1.48%
Loss on ignition.....	2.26%

A rational analysis shows the following composition:

Quartz, as given.....	39.38%
Clay and mica, as given.....	23.94%
Feldspathic detritus.....	36.68%

On the other hand, a sample of extremely fine sand from Michigan, of which 75% passed a 200-mesh sieve, appears to be absolutely pure quartz.

**Clay.** When pure, clay consists of hydrated silica of alumina, the product of decomposition of feldspar. Ordinarily, various impurities are mixed with the clay, so that, in general, clay may be considered a mixture of hydrated silica of alumina with other finely divided minerals. Mixtures of clay and sand are commonly found, varying from beds of nearly pure clay to beds of nearly pure sand. No definite classification can be made.

**The Effect of Moisture on Clay.** Clay as generally found in excavations is in a plastic condition due to the presence of moisture, the amount of moisture present varying greatly. On drying, the clay shrinks in volume and loses its plasticity, becoming a firm and coherent mass resembling in consistency a dried brick. Large masses of clay are liable to crack into a number of

ments during the process of drying, as the result of the shrinkage in volume. When these lumps are crushed or ground the clay becomes an extremely fine impalpable powder. The loss in volume due to the change in the condition of the clay from a moist, plastic state to a thoroughly air-dried condition may amount to from 10% to 20% of the original volume. Compact, moist clay is impervious to water in the sense that water cannot pass through it as it would through porous sand; but when clay is exposed to water the clay gradually absorbs the water, so that eventually the entire mass becomes saturated and absorbed by the water.

**Clay as a Foundation-Bed.** Clay is not a reliable material on which to build a building; first, because of the PLASTICITY of the clay when wet, and secondly, because of its TENDENCY TO SHRINK on losing its contained moisture. The plasticity of clay increases with the percentage of contained water, so that even hard clay may be converted into a liquid puddle by being agitated in the presence of a sufficient amount of water. The plasticity is also increased by heat, as is shown by the action of clay in a brick-machine. Clay, in a foundation-bed under moderate pressure imposed on it by the footings of a structure, gradually develops this QUALITY OF PLASTICITY, the clay moving out from beneath the footing and causing serious settlements and displacements of the footings. This movement of the clay may be a local movement, as referred to in a footing, in which case the clay flows from beneath the footing laterally toward the side and then upward, causing the surface of the adjacent material to rise and to form so-called BULGES or WAVES. If this motion is uniform from the center toward the sides, the footing may settle vertically, but more frequently the movement will not be symmetrical and the footing will settle more on one side than on the other. Such movements of the clay may be retarded or prevented in some cases by the simple device of loading the surrounding soil, as, for example, by a concrete floor.

**Movements of Clay Foundation-Beds.** The movement of the clay may occur on a larger scale, amounting to a general flow of the clay underlying the building toward some point where the pressure on the clay is less than the pressure resulting from the load of the building. Such general movements are more likely to happen if the building is located on the side of a hill, so that the clay finds some outlet at a point below the level of the footings. It frequently happens that adjoining excavations cause settlements to buildings at a considerable distance, by affording an outlet to a bed of clay. As noted elsewhere (pages 135 and 146), beds of clay resting on inclined strata of rock or other material are liable to move downward, sometimes with a slow, almost imperceptible movement, and at other times forming landslides of greater or less magnitude.

**Detection of Clay Foundation-Beds.** Where the foundation-bed is clay and contains a considerable amount of clay, it is advisable to protect it from erosion, so far as is possible, by a system of drains surrounding the site of the building and by diverting the surface-water from the building. Care should be taken in back-filling around exterior walls to prevent any accumulation of water which might affect the material under the footing. The neglect of such precaution has frequently resulted in serious settlements during, or immediately after, construction.

**Sand, Silt, Peat and Other Unstable Materials.** When the site of a structure is in a marsh or on materials which are not capable of affording a foundation, the only alternative is to resort to the use of wooden piles, sheet piles, or piers sunk to an underlying and firmer strata. Such special

constructions will be described under Subdivisions 27, 28 and 29, which cover wooden piles, concrete piles and piers sunk by the coffer-dam or other methods.

**Filled Ground.** All artificial fills and some natural fills are liable to a more or less uniform but continuous settlement or shrinkage due to the gradual consolidation of the material of which the fill is composed. Where the fill is on rock this consolidation may amount to little, but where the fill is of earth, especially where it is of mixed materials, the shrinkage will not only be large in amount but will continue for a very long period. For example, when gravel has been thrown on top of a rock-fill each rain-storm will wash some of the gravel into the voids in the rock-fill, and this action will be continuous until the voids are filled in. Any vegetable matter, or other matter liable to decay and shrinkage in volume, will increase the total shrinkage of the mass. Certain natural deposits, such as beds of peat or soils containing vegetable matter, are apt to shrink in volume from the same causes. When it is necessary to found a building on such material it is inevitable that the footings will settle with the mass, notwithstanding that the unit load on the foundation-bed may be small as to be negligible. In such cases the settlements may be vertically uniform; but if the depth of the fill under one part of the building is greater than the depth under another part, the settlements will not be uniform, and the shrinkage in the fill will, in general, be in proportion to the depth of the fill. No important building should be founded on such material and, where possible, the footings should be carried down through the filled-in material to some more reliable underlying stratum.

## 8. Allowable Loads on Materials of Foundation-Beds

**General Considerations.** Owing to the infinite number of variations in the materials encountered and the conditions affecting the reliability of such materials, no general or definite rule can be given, and every case should be carefully investigated before determining the allowable unit load on the foundation. If the material and conditions are uniform over the entire site of the building, a uniform unit load may be used, but in practice it is frequently found that entirely different conditions exist under different portions of the same building and in such cases great care must be exercised in determining the unit load. For instance, one section of a building may rest on rock and another section on a light compressible soil or on a clay of doubtful stability. In such cases the unit load on the compressible soil or on the clay must be reduced as much as possible so as to reduce the differences in settlements between the two sections of the building to a minimum. If the entire building were on a compressible soil a very considerable settlement might be allowable, provided it was uniform; but in this particular case it is known beforehand that the part of the building on rock will not settle at all and that any settlements of other parts of the building must be considered as unequal settlements, and, as such, liable to produce cracks and distortions in the building. It is also important to remember that a certain unit load on compressible soil may be safe, in that the soil can ultimately safely support that load; but the use of that load would nevertheless be inadvisable on account of the excessive settlements. In this connection it may be said that a considerable settlement, if uniform, in a detached building may be a matter of no importance; but that where a building is to be constructed in contact with adjoining buildings or where additions are to be made to an existing building, the total amount of settlement becomes a matter of prime importance. These and other considerations, such as the character

proposed building and of the material composing it, should be borne in mind in selecting the unit load for any given foundation-bed, irrespective of the soil pressure as given by building codes or by examples quoted in this chapter.

**Safe Loads on Rock.** The safe unit load on rock may often amount to more than the crushing strength of brickwork or stone masonry, and in nearly all cases any material worthy of the name of rock is capable of supporting from 10 to 30 tons per sq ft.

**Safe Loads on Sand, Gravel and Boulders.** When compact and consolidated, these materials are capable of supporting 10 tons per sq ft without appreciable settlement. It rarely happens, however, that it is advisable to load such materials with more than 5 tons per square foot.

**Safe Loads on Loose Sand.** By loose sand is meant sand which has been thoroughly compacted and which may settle by its own weight independently of a superimposed load. All such materials should be tested and the unit load reduced in accordance with the result of such tests.

**Safe Loads on Fine Sand or Quicksand.** It is probable that fine sand, if properly confined, will sustain as heavy a load as coarse sand, but in view of the fact that if afforded the slightest opportunity it is liable to lateral displacement, it is inadvisable to found any structure on such material. When it is necessary to place the footings on such material the unit load should be reduced as much as possible and preferably to less than 2 tons per sq ft, and great care should be taken to connect all footings with a continuous layer of concrete so as to prevent any flow of material into the cellar-excavation. Care should also be taken, also, that any sumps, pump-pits, drainage-arrangements and sewer-connections for the building do not permit the escape of any quicksand.

**Safe Loads on Hard-pan and certain cemented sands partaking of the nature of hard-pan** may approximate rock in hardness and reliability. Such materials, however, are liable to soften if exposed to water. If these materials, when uncovered, are dry, experiments should be made to determine how they behave when wet, and if the level of the water in the ground is liable to change so as to reach the layer of hard-pan, the load should be correspondingly reduced. Cemented hard-pan containing gravel has been frequently loaded with more than 10 tons per sq ft. Care should be taken, however, to determine that the layer of hard-pan is continuous to a solid substratum, as it frequently happens that layers of hard-pan and fine sand or clay are deposited alternately.

**Safe Loads on Clay.** Ordinary clay should not be loaded with more than 2 tons per sq ft. If soft and plastic, a load of 2 tons per sq ft may produce considerable settlements. Clay with so large a percentage of sand that it loses its plasticity has been loaded with from 4 to 6 tons per sq ft without undue settlements, and sand or gravel containing sufficient clay to act as a cementing material will partake of the qualities of hard-pan. In general, however, clay is the most dangerous of all the materials on which structures are founded and the unit load should be reduced to a minimum and every precaution taken to prevent the flow of material. Undue reliance should not be placed upon load-tests of clayey soils. It is probable that a loading on a large area which produces a movement of the clay will on a small area have no effect, so that it is unsafe to rely upon the results of a test-load applied to an area smaller than the actual supporting areas to be used. From the experience gained in the construction of large buildings in Chicago which were FLOATED on clay, the allowable unit load has been generally reduced to 2 tons per sq ft and, in the writer's experience, a load of less than 2 tons per sq ft on clay has produced settlements varying from nothing to 12 in.

## 9. Unit Loads on Foundation-Beds Allowed by Building Codes

**Variations in Building Codes.** Table I gives an outline of the requirements of different cities as to the allowable unit loads on different materials contained in their respective BUILDING CODES or REGULATIONS. When the allowed loads given may in some cases be based upon actual experience at respective localities, it is more likely that they are based upon the individual experience of the authors of the codes, or are copied from other codes. The architect should, therefore, not place too much reliance on the unit loads given by the codes, but should investigate each case and determine for himself the proper allowance to be made.

**Special Requirements of Some Building Codes.\*** The Boston code provides that "the footing shall not overload the material on which it rests."

The New Orleans code limits the maximum load to 1 400 lb per sq ft, the city being on an alluvial-delta formation.

The Buffalo code limits the load on SOIL to 3¼ tons per sq ft; if the SOIL is other than hard clay or gravel the supporting areas "shall be extended as directed."

The Cincinnati code limits the load on soils INFERIOR to those listed, to 1 000 lb per sq ft.

## 10. Investigation of the Site

**General Considerations.** To determine the character of the material that will be encountered at the level of a foundation-bed, the architect should get as definite information as possible from others as to their experience in making excavations and erecting buildings in that vicinity. In some localities the subsoil conditions are uniform over large areas, while in other localities important variations may occur within the limits of a city lot. Abrupt changes in surface-topography, changes in the character of the surface-soil or in the vegetation, proximity to old or existing water-courses are suggestive of subsurface irregularities. In such cases, and in all cases where there is any doubt as to subsurface conditions, a sufficient number of exploratory borings or pits should be made to determine the facts. This exploratory work should extend below the level of the proposed footings, should determine the ground level and insure that no unsuspected layer of quicksand or other unsound material underlies the foundation-bed. The methods in use for such explorations are as follows:

**Testing in an Open Pit.** For shallow work an open pit is the most satisfactory method as it allows actual inspection of the undisturbed material over a considerable area. If the excavation is in firm material, no sheet-piling or protection may be required; but if in flowing material, or if carried deeper than adjoining footings, timber sheeting or steel sheeting should be employed. If the excavation is carried no deeper than the proposed footing-level, the underlying material should be tested by one of the methods hereinafter described.

**Testing with Steel Bars.** A steel bar with a pointed end or a steel point provided with a steel point is driven to the required depth by a maul or falling weight. While no samples can be obtained by this crude method, it may determine the ground-water level, and a little practice will enable one to distinguish sandy from clayey soils by the sound given out when the bar is twisted. The difficulty of driving is a rough index of the degree of the compressibility of the soil. It should be remembered, however, that an unsound material will afford considerable resistance to the bar and that a small blow will stop it; so that not much reliance can be placed on a report that the bar DROVE HARD or that it REACHED ROCK.

\* As codes change, quotations must be verified.



**Table 1. Loads in Tons per Square Foot on Foundation-Beds Allowed by Building Codes\***

Character of foundation-bed	Richmond, Va.	Minneapolis, Minn.	Philadelphia, Pa.	Atlanta, Ga.	Portland, Ore.	Louisville, Ky.	St. Louis, Mo.	Cincinnati, O.	Cleveland, O.	San Francisco, Cal.
level soil					1½				1½	
in dry loam		3		2-3	2½	3				3
dry clay	1	1		1		1				1
stiff clay								2		
slightly dry clay									2	
solid natural clay										
in thick beds, always dry								4		
in thick beds, moderately dry								2		
dry clay								3		
in dry clay	3	3		2-3	2½	3				3
stiff clay	4	4		†8 3-4	4	4				4
in hard clay			3½	4					4	
in wet clay and sand					1½					
gravel mixed with clay							2			2
stiff clay and sand together										
loose, wet and springy	2	2		2						
slightly dry clay and sand					3					
stiff clay and stone							4			
stone					1½				1½	
in wet sand									1	
in sand							1			
in sand, firm and dry	3	3		2-3	4	2½	3			3
in dry fine sand								2		
in sand, compact and well cemented									4	
in sand							3			
in compact sand								4		
in coarse sand							4			
in fine coarse sand	4	4		3-4	4	4				4
in dry sand									2	
in gravel	4			3-4	4	4				
in gravel		4		†8						
in gravel			6							
in loose gravel			3½							
in sand and gravel								5		
in sand and gravel, well cemented								8		
in coarse sand and gravel							6			
in sand and coarse sand, well cemented					8				8	
in sand						0-15				
in shale, unexposed									8	10
in shale				†15	8				8	20

\* Some values may change with the changes in building codes.

† In caissons.

**Testing with Post-Hole Diggers.** For shallow explorations in easily excavated material, the ordinary post-hole digger used for fence-posts, and longer and larger ones used for telegraph-poles, can be used to depths of 6 to 8 ft.

**Testing with Augers.** In clay or similar material a single or double carpenter's auger welded to a long rod, or the so-called POD-AUGER may give satisfactory samples. In gravel or loose and sandy material, the sides of the hole fall in, clogging the operation and destroying the samples.

**Testing by Dry-Pipe Borings.** A POD-AUGER or the above-described CARPENTER'S AUGER can be used inside a casing-pipe. The pipe should be driven so as to keep close to the bottom of the hole made by the auger. The casing-pipe prevents the material falling from the sides of the hole and the auger excavates and loosens the material ahead of the pipe and facilitates driving. The above methods are not generally successful for deep holes or where gravel, boulders or compact material interferes with driving the pipe.

**Testing with Wash-Pipes.** For test-borings over 10 ft in depth the method in most frequent use is the WASH-PIPE METHOD. In this method a wrought iron or steel pipe known as the CASING-PIPE or DRIVE-PIPE is driven into the earth much the same way as in the DRY-PIPE METHOD, but the driving of the pipe is facilitated by the use of a JET OF WATER. The lower end of the casing-pipe is provided with a hollow SHOE or reinforcement, slightly larger in outside diameter than the casing. This serves to protect the pipe from injury in driving through gravel or hard-pan, and forms a hole slightly larger than the diameter of the casing. The upper end of the drive-pipe is protected from injury by an anvil drive-head which has a threaded part fitting the thread on the casing-pipe and a central hole to admit the jet-pipe. The jet-pipe is small enough to permit it to freely enter the casing-pipe. The lower end is contracted so as to produce a jet-action. The upper end is connected with a water-supply which maintains pressure under considerable pressure. The driving-mechanism consists of a casing weight with a central vertical hole large enough to admit the wash-pipe and stationary verticals supporting a BLOCK-AND-FALL and an arrangement which releases the weight when it has reached a predetermined height. With this arrangement, water is continuously pumped through the jet-pipe, the length of which is regulated so that the jet-action loosens the material immediately below or AHEAD of the casing. Some of the jetting water returns to the surface on the inside of the casing and thus lubricates the surface in contact with the material. Another part of the water returns to the surface in the annular space between the wash-pipe and the casing, carrying with it particles of material loosened by the jet. As the jet loosens and washes away the material immediately below the casing, the latter is driven deeper by repeated blows of the ram, the driving and washing being carried on at the same time. The operation is thus continuous until the top of the casing comes close to the surface of the ground, when the hammer drive-head and hose-connection are moved to permit additional lengths of pipe to be added to the casing and new jet-pipes, after which the hose-connection, drive-head and hammer are repositioned and the operation is resumed.

Borings can be made by this method to great depths in sand, clay or any suitable material. Samples of the material encountered are obtained by straining the water returning between the jet-pipe and wash-pipe. These samples are not accurate samples as the water separates the materials. The finer particles do not settle readily and the large and heavy particles may not be brought up at all. It is evident that such samples do not give any indication as to the solidity of the original deposits. If large gravel, hard-pan or boulders

encountered there will be great difficulty in forcing the casing past such obstructions. In such cases a DRILL-ROD is sometimes substituted for the JET and the obstruction broken up into small pieces or pushed to one side; but in most cases it is difficult to get any sample or real indication of the character of the obstruction. If solid rock or large boulders are encountered, no further progress can be made with the casing and no sample can be obtained by this method. Resort must then be had to one of the CORE-BORING METHODS described below, to determine the character of the obstruction encountered.

**Core-Borings.** These borings can be made through rock or soil and accurate samples obtained. In all core-boring methods the hole is made by rotating a pipe-like tool which makes an annular cut in the rock and leaves a cylindrical core which is afterwards detached and brought to the surface by a gripping-tool called the CORE-LIFTER. The cutting is done in several ways.

**Diamond Bits** are annular rings fitted on the lower end of the hollow pipe and on the rotating drill-rod and furnished with a number of small diamonds set so as to form cutting-edges, which, when rotated in contact with the rock, gradually wear away the required annular space. The diamonds employed are known as BORT, BLACK DIAMONDS, or CARBONS, and their only resemblance to stones used by jewelers is the necessary hardness. The carbons are usually secured in a soft metal bed, in sockets drilled in the bit, and they project above the bit and also sufficiently inside and outside to insure the cutting edge is large enough to provide clearance for the bit and the attached drill pipe.

**Shot-Drills.** The same result is arrived at by the SHOT-DRILL METHOD, by means of particles of chilled cast iron called SHOT are used as the abrasive or cutting-tool. The shot is poured loose into the hole and forced against the rock by the rotating bit.

**Efficiency of Drill-Methods.** Both of the drill-methods mentioned are expensive but as they are the only methods which will give an accurate sample of the rock, one or the other must be employed where the accurate determination of the rock is necessary. If the core corresponds to the known underlying rock-formation and the rock is continuous for a length of from 8 to 20 ft, it is safe to assume that solid rock has been reached. If, however, the core is of different character from the known underlying formation, the probability is that a boulder has been encountered. If the core is not continuous it may indicate that there are seams in the rock or that there are detached rock-masses. The above-described methods are used after the overlying earth has been penetrated by one of the PIPE-SINKING METHODS previously described.

**Results of Pipe-Borings** are frequently misleading and misinterpreted, and great care should be taken to compare the samples with samples obtained from other borings where the exact character of the materials tested is known.

## 11. Loading-Tests

**General Considerations.** Loading-tests of the materials forming the foundation are made to assist in determining its safe bearing capacity. It is not known to what extent the supporting power of a given soil varies with the area subjected to the unit load, and tests on small areas are not a safe guide for the load on large areas. On account of the expense involved, tests on large areas are rarely made, the usual test being on an area of about 1 sq ft. The test should be made on an undisturbed portion of the foundation-bed, leveled before the test-load, and for a space around the area tested, so that the

adjoining material is not reinforced or SURCHARGED by a bank of unexcavated material. The load should be applied with the least possible jar or motion of the surface in contact with the material of the foundation-bed.

**Explanation of Methods.** A convenient arrangement for this test consists of a vertical timber or post carrying a platform to receive the test load and having four horizontal guys at the top to keep the post in a vertical position. The bottom of the post, forming the loading-area should be approximately 12 in and its exact area should be known. The platform, sufficiently large to support the load to be applied, should be concentric with the post and close to the bottom of the post as practicable. The load may be pig iron, or sand in bags, or any other convenient material. The guys should be at least four in number, should be attached to the top of the post and should extend horizontally so as not to pull up or down on it. Levels should be run to a point on the post above or below the load, as may be most convenient. The load should be applied gradually and with the least possible jar, care being taken also, to keep the loading uniform on opposite sides of the post, which should always be vertical. Levels should be taken at frequent intervals during the application of the load. The level observed when the platform is first in position should be taken as zero and successive settlements referred to it. When the proposed unit load has been reached, no additional load should be added until no further settlement is observed. After this, first 50 and later 100% overload should be added and the total and periodic settlements observed. If the settlements under a test-load of twice the proposed load is not excessive, the test is considered satisfactory.

## 12. Topographical and Special Conditions

**Excavations over Inclined Strata.** In case the site of a proposed building is on a slope, and especially if the slope is steep, there may be danger of a slip of the material forming the foundation-bed. (See, also, page 135.) A slip may occur if there is an inclined plane of separation between layers of the underlying rock, or between the rock-surface and the material overlying it, or if inclined strata or beds of clay occur below the foundation-bed. At such locations are the more likely to occur if water is present, as this increases the weight of the soil and also reduces the COEFFICIENT OF FRICTION against sliding. Such conditions are frequently indicated by the appearance of springs or springy ground below the site. Where the base of the slope is a stream or river there may be danger from the washing away of bank material have been supporting the side slopes of the valley. In the case of deep excavations with steep clay banks, or in any location where landslides have been known to occur, great care should be taken to extend the footings to a bed that will not be affected by any landslide. It sometimes happens that there is a slow but continuous and general movement of the material forming the side slope of the valley toward the center of the valley; but such conditions are rare, fortunately. In general, no adequate protection is possible. In certain limestone formations there is danger from natural caves formed in the limestone by the action of water.

**Excavations Near Navigable Waters.** When buildings are located near navigable waters, it not infrequently happens that dredging-operations at a considerable distance induce a flow of fine sand or clay from strata underlying the adjoining banks. This has occurred where the existence of such conditions was not suspected. This danger is especially to be guarded against in excavations in localities adjoining waters which are, or may be, used as navigable streams. In locations near the water-front where it is likely that docks will be constructed

**Damage from Adjoining Excavations.** Common and statute laws make provision for the protection of property-owners against damage resulting from the acts of others in making such excavations; but an owner has usually no control over such operations, whether on adjoining properties or streets, and in general will prefer the assurance of safety to the possibility of damage to his building and the expense and uncertainty of a lawsuit. While it is not always possible to guard fully against the effects of adjoining excavations, and the expense of so doing is not always justifiable, due consideration should be given to the matter. The following suggestions, therefore, may be of value.

**Depth of Adjoining Excavations.** Footings adjacent to property-lines should be located where there is a probability of future additions to a building, or the corner of a building which adjoins property liable to become the site of building-operations, should go down at least as deep as the maximum probable depth of adjacent work. In estimating these probabilities, the character of the locality should be taken into account. In medium-priced residential sections excavations are rarely carried much deeper than 10 ft, a sufficient depth for a cellar of medium height below grade. In high-priced residential sections it is not unusual to have both a basement and a cellar, in which case a depth of cellar below grade up to 20 ft may be expected. Cellars for residences are rarely carried below 10 ft, if in reaching that depth the excavation goes below the water-level. In fact, a high water-level discourages deep excavation, not only on account of the increased difficulty and expense of excavation but also on account of the expense of waterproofing. In business sections, especially in sections of high ground-rents, there is an increasing tendency toward deep excavations, especially in boiler-rooms, where clear heights of 20 ft and over are desirable for modern water-tube boilers. The basements are frequently rentable for figures for restaurants, vaults, stores, etc., so that in many instances the mechanical equipment of the building is housed below the basement in a basement and boiler-pit, the excavation for which extends down at least 10 ft and in special cases 60 ft below the curb; and this notwithstanding the fact that the water-level may be only from 10 to 20 ft below the curb.

**Sewers and Trenches as Affecting Foundations.** In cities and towns consideration should be given to the possibility of the construction of trenches in the streets. For the majority of localities it will be sufficient to consider the probable depth of a sewer of the proper depth to serve the street. In other localities it will be necessary to consider the broader question as to the probability of deeper excavations for trunk sewers, subways, etc. As such construction is controlled by broad topographical considerations, no general rules can be given and the local city engineer should be consulted.

**Foundations Near Mines, Shafts, Wells, Etc.** In mining-districts local mining engineers should be consulted as to danger from the caving of OLD MINE-works. No adequate provision can be made in the foundation against widespread caving or subsidence as may result from mining-operations. In some cases, successive falls of rock-fragments from the roof may gradually fill the voids left by the mining-operations, as the loosely piled fragments of the roof occupy more space as FILL than they did as part of the solid roof-mass. Sometimes happens that where the original working is deep, progressive caving of the roof fills all voids, and no surface-settlements result. In other cases the overburden may settle as a solid mass, causing a settlement at the surface equal to the thickness of the old working. Precautionary measures may be taken by the filling in of the workings, a subject outside the limits of this chapter. In the case of an important building a local mining engineer should be consulted if possible, the location of the building changed to a safer site. MINING-

**SHAFTS, DEEP WELLS, SHAFTS FOR TUNNELS, etc.,** may cause disturbance of the soil, but in such cases the settlement is generally concentrated around the shaft or well, and buildings at a reasonable distance are slightly affected.

**Foundations Near Tunnels and Trenches for Railroads and Subways.** In large cities the necessities of transportation are increasingly calling for the construction of underground **RAILROADS, TUNNELS** and **SUBWAYS**. Such constructions are generally planned to follow streets. Railroad tunnels for trunk lines are expected to follow direct lines to centrally located stations or terminals. Routes which avoid, as far as possible, difficulties of construction, condemnation of real estate and damage to high-priced properties. The depth of excavation will generally be as shallow as practicable. Where the tunnel has to dip down underneath some obstruction, the approach-grades will probably be at the minimum or limiting grade of the particular section.

**Relation of Subways to Foundations of the Most Important Buildings.** In **SUBWAY-CONSTRUCTION** for rapid-transit passenger service, the subway can be operated on sharper curves and with steeper grades than would be possible in the case of a trunk-line railroad. This permits the lines to follow the lines of the city streets. For traffic-considerations the locations of stations, in general, follow the principal arteries of surface traffic, and stations will, in general, be located at intersections of important streets, where there is the greatest congestion of population. As such conditions are caused by the existence of trade-centers, and call for the construction of high buildings, it may be seen that the heaviest and most important buildings are most likely to have their foundations affected by the construction of a subway in their immediate vicinity. Where there is reason to apprehend the construction of **SUBWAYS OR TUNNELS**, information should be sought as to the probable location of the excavation, the depth at which water is encountered, the character of the material, the probable width of the construction as affecting the use of sub-basements, vaults, and the method to be employed in making excavations. Where excavations for such tunnels and subways have been carried below the level of the footings of adjoining buildings, as in Baltimore, Boston, Brooklyn, and New York City, buildings along the routes have been seriously damaged. Such results have not been limited to any particular methods used in the construction of the tunnels, as even where the excavations were wholly, or almost wholly, in rock, serious damage has been done.

### 18. Loads Coming on the Footings

**The Loads to be Considered in the design of the footings of a structure are:**

- (1) **The Dead Loads**, or the loads due to the actual weight of the construction, ready for occupancy.
- (2) **The Live Loads**, or the loads due to the occupancy of the building and to the weight of snow on the roof.
- (3) **The Wind-Loads**, or the vertical components of stresses in the structure produced by wind-pressure.

(1) **The Dead Load.** The dead load of any structure can be accurately calculated. If the structure is properly designed the part of the load supported by each element of the foundation can be definitely stated. The dead load becomes effective as soon as the building is completed, and remains constant thereafter unless additions or alterations are made to or in the structure.

**The Live Load.** The live load of any structure is the sum of the roof- and floor-loads. In designing the roof and floors the calculations for live load are based on an assumed unit load which should be the maximum load, but with the probable use of the structure, to which any portion of the floor may ever be subjected. The assumed live load is, therefore, probably greater than the average load for the entire area of a floor or the entire area of the roof. Moreover, as it is improbable that conditions of maximum load will ever occur simultaneously on the roof and on all of the several floors, it is probable that the maximum load on the footings will be less than the maximum loads on the roof and on the several floors.

**Minimum Live Load** for an unloaded building is zero.

**Actual Live Load** will vary from zero to a maximum, which maximum load will usually be less than the total assumed live load.

**Ratio of the Probable Maximum Live Load to the Assumed Live Load** varies in different buildings, so that no table or general rule can be given.

**Probable Maximum Live Load.** As it is important to know, approximately, at least, the maximum live loads to which the footings will be subjected, and as this maximum may be only a fraction of the assumed live loads, the designer should make a careful study of the conditions of loading to which the building will probably be subjected and estimate the probable maximum live load for the entire building.

**Methods for Estimating Live Loads.** (See, also, Chapter XXI, pages 718

1) In estimating the probable maximum live loads for different uses, the following notes may be of value. In certain buildings the assumed unit load on the roof and on parts of each floor may be reached at various times, but it is unlikely that the maximum loading of all parts of the building will be reached at the same time. In buildings of many stories the probability of having maximum loads on all of the floors at the same time decreases as the number of stories increases.

**Many Household and Office-Furniture** weighs from 5 to 10 lb per sq ft of floor-area occupied. While safes, bookcases or filing-cases may produce local loads of from 10 to 100 lb per sq ft, the average load on office-floors rarely reaches 10 lb per sq ft.

**Dances, Apartments and Parts of Hotels** not used for public assemblies are rarely loaded with more than 5 lb per sq ft of floor-area.

**Retail and Wholesale Stores** require a large percentage of the floor-area for the use of salespeople and customers, and not over 50% of the floor-area is used for the storage of stock. In estimating the weight of miscellaneous stocks, an average should be taken between the lightest and heaviest classes should be taken for the weight per cubic foot, and also, in figuring the total space occupied by stock, an average should be taken between the maximum and minimum amount of stock carried. **RETAIL DRY-GOODS STORES** the floor-load for the entire building may amount to more than 25 lb per sq ft, but in **WHOLESALE STORES**, and especially in **hardware stores**, the average load may greatly exceed this figure.

**Workshops, Loft-Buildings and Buildings for Manufacturing**, the actual loads will, of course, vary with the class of material handled and the weight of machinery used, and no general estimate can be made. Where the character of the occupancy to be expected is known it is possible to make a close estimation of the weights of machinery, fixtures and average stock on each floor.

**Warehouses.** In buildings used, in whole or in part, for **STORAGE PURPOSES** they may be used for light, bulky materials which, when stowed so as to leave



gangways and working-spaces, will give a resultant load much below assumed load. On the other hand, the heaviest materials may be piled from floor to ceiling in defiance of building regulations, posted no common sense. Raw materials or crated or baled materials can be closer than miscellaneous articles, and are therefore liable to increase the

The Ratio of the Total Probable Maximum Live Load to the Total Live Load having been determined for the entire building, the probable live load for any element of the footing may be readily obtained by multiplying the assumed or calculated live load for that element by this ratio.

(3) The Wind-Load is generally calculated on the assumption that it may exert a uniform pressure, frequently taken at 30 lb per sq ft, on the external area of any side of the building. This assumption makes no allowance for the protecting influences of adjoining buildings. In a building of average size it is improbable that the maximum pressure will be reached over the entire area at the same instant of time, and consequently, if the assumed pressure represents the maximum pressure, the average, at any time, will be less than the calculated total.

**General Effect of Wind-Pressure.** The horizontal pressure of the wind tends to increase the load on footings on the leeward side of the building and to decrease the load on footings on the windward side. In many buildings wind-bracing, called wind-bracing, or other special construction, is used to prevent the building from being deformed by the wind-pressure and to convert the horizontal stresses due to the wind-pressure into vertical components, acting along defined lines of support, that is, into either uplifts or loads on certain piers or columns. Where the uplift on any element of the structure is less than the dead load on the same element, the uplift is ignored. Where the wind component increases the compression in any element it is called the wind load on that element of construction and on the corresponding footing. This is generally based upon concentrating all of the wind-load on certain footings. If, on account of the general rigidity of the building, or on any other reason, the wind-stresses reach footings not designed to receive such loads, the amounts figured on the external footings will be reduced correspondingly. It is probable that the maximum effect of the wind results from a series of impulses of short duration and that the effect of such pulsations is partially overcome by the inertia and elasticity of the buildings; so that the resultant load reaching the footing may be only a part of the theoretical maximum at the instant during which the maximum pressure is exerted. (See, also, XXIX, Wind-Bracing of Tall Buildings.)

The Probable Maximum Wind-Load acting on the footing is, therefore, less than the theoretical load due to the maximum wind-pressure. If the wind-load represents approximately the maximum wind-pressure, as determined by a wind-gauge, it would appear safe to assume that only 50% of the wind-load would act to produce a settlement in the footings of a building. Some authors recommend that in proportioning footings all wind-load be ignored; but this, especially in the case of high and narrow buildings, is frequently improper. The minimum wind-load is negative, being actually an uplift from which the load may vary to the maximum, but the maximum is reached only at rare intervals and will endure for a short period only.

**The Combined Wind-Load and Live Load.** It is improbable that the maximum wind-load and the maximum live load will occur at the same time. This consideration should be borne in mind when the estimate is being made of the effective wind-load.



**M. Assumed Loads Specified by Building Codes\*****II. Requirements of Building Codes for Assumed Loads for Office-Buildings**

City	Requirements
Ala. Ga.....	Live load, 75 lb per sq ft above 1st floor; 150 lb per sq ft on 1st floor Footings designed for dead load and 60% of live load and wind-load
Mass.....	Live load, 100 lb per sq ft. Wind-load, 30 lb per sq ft where erected in open spaces; in built-up districts, 25 lb at the 10th story, 2½ lb more for each succeeding upper story, up to a maximum of 35 lb to the 14th story and above
N. Y.....	Live load, 70 lb per sq ft. Wind-load, 30 lb per sq ft. Foundations designed for the acting average loads in the completed and occupied building and not the theoretical or occasional loads
St. Paul, Minn....	Live load, 75 lb per sq ft above the first floor; 100 lb for first floor. Wind-load, 30 lb per sq ft. Roof and top floor, full live load. For each succeeding lower floor, a reduction of 5% until 50% is reached, such reduction being used for the remaining floors
Richmond, Va.*...	Foundations designed for 60% of the live load
St. Louis, Mo.*....	Live load, 70 lb per sq ft; first floor, 150 lb. Loads carried by the soil, total dead load and 10 lb per sq ft of all the floor-area. Wind-load, 30 lb per sq ft
St. Paul, Minn.....	Live load, 60 lb per sq ft above the first floor. First floor, 125 lb. Wind-load, 30 lb. Roof and top floor, full load; for each lower floor, a reduction of 5% until 50% of the full live load is reached, when such reduced load shall be used for the remaining floors. Footings designed for dead load and live load
Cincinnati, O.....	Live load, 50 lb per sq ft above first floor; 100 lb for first floor. Live load reduced by 5% for each floor below the top until 20% is reached, when such reduced loads shall be used for remaining floors. Wind-load, 20 lb per sq ft above surrounding buildings
Chicago, Ill.....	Live load, 50 lb per sq ft. 50% of the live load used for piles. Piers designed for 85% of live load on top floor and reduced by 5% for each lower floor until 50% is reached, when such reduced loads shall be used for the remaining floors. Wind-load 20 lb per sq ft
New York City*...	Footings designed for 60% of the live load
Cleveland, O.....	Live load 60 lb per sq ft in offices proper. 100 lb per sq ft in halls, lobbies, etc. Footings for walls designed for 50% of live load. Free-standing columns designed for 80% of 100-lb load and 75% of 60-lb load. Wind-load 30 lb per sq ft; for free-standing structures in built-up districts 25 lb per sq ft at the 10th story and 2½ lb less for each lower story, and 2½ lb more for each higher story, until 35 lb is reached

These are constantly changing. Richmond's new code gives floor-loads; St. Louis kept some values; New York City's new code gives floor-load values different from the former code.

**Reduction in Assumed Loads.** The building codes of various countries contain rules governing the assumptions to be made as to live loads and wind loads and these rules generally provide for some REDUCTION IN THE ASSUMED LOADS. Generally, it will be found possible to meet these requirements and at the same time arrange for the proper proportioning of the supporting areas. Page 151, gives briefly the requirements of the building codes of several countries as to assumed loads for office-buildings.

## 15. Proportioning the Supporting Areas for Equal Settlements

**The Minimum Areas of Support.** The actual dead loads and the live loads and wind-loads for each linear foot of wall and for each column or other supporting element of the building down to the level of the foundation having been calculated, a foundation-plan should be prepared giving the location and center of action of all loads. For safety under the worst possible combination of loads, each footing should be ample to support the total of the dead loads, live loads and wind-loads coming on it. The MINIMUM AREAS OF SUPPORT FOR ANY FOOTING are obtained by dividing the total of the dead loads, live loads and wind-loads by the safe supporting power of the foundation-bed. If the foundation-bed is rock, or can be considered as incompressible under load, the minimum areas so obtained may be used for the footings. If the foundation-bed is compressible materials, or generally on all materials other than rock, then these minimum areas will not result in uniform settlements owing to the fact that the actual live loads and wind-loads are not consistent with the assumed live loads and wind-loads.

**The Actual Loads on the Footings.** In accordance with what has been previously said, let us assume that the dead load is constant, and that for the building under consideration the probable maximum live load is 50% of the assumed live load, that the probable maximum wind-load is 40% of the assumed wind-load, and that on the completion of the building, for a short period the live loads and wind-loads reduce to zero. The ACTUAL LOADS ON THE FOOTINGS would then be:

- (1) Upon completion of the building, the dead load only;
- (2) Under the maximum load due to occupancy and to snow on the roof, the dead load plus 50% of the assumed live load;
- (3) When loaded as in (2) and subject, in addition, to the maximum probable wind-action,
  - (a) The footings on the leeward side of the building will sustain the dead load, plus 50% of the assumed live load, plus 40% of the assumed wind-load;
  - (b) The footings on the windward side of a building will sustain the dead load, plus 50% of the assumed live load, minus 40% of the assumed uplift;
  - (c) Other footings will support the total dead load, plus 50% of the assumed live load, plus zero wind-load;
- (4) Intermediate conditions as to live loads and wind-loads will result in loadings intermediate between (1) and (3).

**Variations in Unit Loads on Foundation-Beds.** With such knowledge of the actual loads it is, therefore, impossible to proportion the supporting areas so that the unit load on the foundation-bed shall be uniform at all times. If the supporting areas are proportioned in the ratio of the dead load only, the building, upon completion, and before occupancy, will uniformly load the supporting areas and at that time all of the footings should show equal settlements; but

When the supporting areas have been subjected to the full effects of the dead and wind-loads, certain supporting areas, having a high percentage of live loads, or of live loads and wind-loads, will be subject to a higher unit load and the corresponding footings will consequently settle more than other supporting areas having a low percentage of live loads, or live loads and wind-

**Non-Uniformity in Footing-Settlements.** If, on the other hand, the supporting areas are proportioned on the basis of the dead loads, plus the maximum live loads, plus the maximum wind-loads, even if the MAXIMUM LOADS are the ACTUAL MAXIMUM LOADS, and not the FICTITIOUS ASSUMED LOADS, it is probable that upon the completion of the building and before occupancy, the supporting areas having a lower percentage of live loads and wind-loads will be subject to a higher unit load, and the corresponding footings will have settled more than other footings supporting a high percentage of live loads and wind-loads. On this basis, the footings will not come to a uniform settlement until they have been subjected to the maximum live loads and wind-loads.

**Arbitrary Rules for Proportioning Supporting Areas.** Various ARBITRARY RULES have been recommended for the proportioning of the supporting areas to secure equal settlements. These rules generally provide for a reduction in the assumed live loads and wind-loads, but do not take into consideration the fact that a large proportion of the total settlement of certain footings may take place subsequently to the completion of the building and after other footings have reached practically their full settlement.

**Proposed Rule for Proportioning Supporting Areas.** The rule herein recommended provides not only for a reduction of the assumed loads on a rational basis, but also for the proportioning of the footings for the mean load instead of for the ultimate load, and it is believed that the resulting settlements will be as nearly uniform as possible. The rule is based on the proportioning of the footings in accordance with the loads which will act on the supporting areas at the time when all of the dead loads and one-half of the probable maximum live loads and wind-loads exist. The reason for taking one-half of the probable maximum wind-loads and live loads is that these loads vary from zero to a maximum, the average being one-half of the maximum.

**Provision for Variations in Loads.** On the completion of the building before the live loads or wind-loads have gone on the footings, the settlements will not be uniform, because areas designed for a high percentage of live loads and wind-loads will have much less than their average load and will therefore settle less than footings having a low percentage of live loads and wind-loads. When these same footings have been subjected to the maximum probable live loads and wind-loads, the settlements will again be unequal, because the areas have been proportioned for only one-half of the probable maximum live loads and wind-loads; but the footings which originally were the highest will now be the lowest. The inevitable movement due to the variation in the live loads and wind-loads will be equally divided, one-half of the settlement being required to bring the footing to the level of a footing having the dead loads only, the other half of the settlement carrying it an equal distance below the same level. In other words, the method provides for the least possible variation in settlements of footings having different proportions of live loads and wind-loads.

**Mean Load.** For lack of a better name, the loads taken for the proportioning of the footings, consisting of the total dead loads, one-half of the probable maximum live loads and one-half of the probable wind-loads coming on each footing, will be called the MEAN LOAD.

**The Mean Unit Load.** The areas will be made such that the load foundation-bed due to the mean loads will be uniform, and this uniformity, which, in general, will be considerably less than the allowable unit load foundation-bed will be called the **MEAN UNIT LOAD**.

**The Minimum Unit Load.** The necessity for providing for the possible condition of loading is satisfied if the supporting area for all is sufficiently large to support the total of the dead loads and the assumed loads and wind-loads at the allowable unit pressure. The resulting support areas are the **MINIMUM AREAS**, and any change in these areas necessary to make them proportionate to the mean loads must be effected by increasing the areas rather than by diminishing any. Any mean unit load which would, when divided into the mean loads, areas, all of which would be larger than the minimum areas, would serve as the mean unit load, but it is more economical to determine the **LOWEST POSSIBLE MEAN UNIT LOAD** which, when applied to the mean loads, will give the least possible increase of the areas. This is done by determining which one of the minimum areas carries the **LEAST LOAD PER SQUARE FOOT**. This area may be selected by calculating the load on each of the minimum areas, or more simply, by comparing the total of assumed loads and a table giving the mean loads, and noting which has the **LARGEST PERCENTAGE OF REDUCTION** between the assumed load and the mean load. The resulting mean load on this footing will be the **MINIMUM MEAN UNIT LOAD** which can be used as a **MEAN UNIT LOAD**.

**The Method Reduced to Rule.** The method can be reduced to the following:

(1) Prepare a table giving in vertical columns or table-divisions for each footing, the dead loads, the assumed live loads, the assumed wind-load and the total of these three loads. This table is called the **TABLE OF ASSUMED LOADS**.

(2) Prepare a similar table giving the dead loads, one-half of the maximum probable live loads, one-half the maximum probable wind-loads and the total of these three loads. This table will be called the **TABLE OF MEAN LOADS**.

(3) By a comparison of the two tables, find the supporting area which has suffered the greatest percentage of reduction between the total assumed load and the total mean loads and find the unit load resulting from the mean load on this area. This unit load will be called the **MEAN UNIT LOAD**.

(4) Divide the total mean load as given in the table of mean loads for each footing by the mean unit load. The result will be the required **AREA OF SUPPORT**.

**Short Method for Determining the Mean Unit Load.** From the foregoing it follows that the **MEAN UNIT LOAD** can be obtained more directly by the following rule. Find the supporting area which has suffered the largest percentage of reduction between the total assumed load and the total mean load and multiply the allowable unit load on the foundation-bed by the ratio obtained by dividing the total mean load by the total assumed load.

**Illustrative Example.** The following example is figured out more fully than is necessary in practice in order to fully explain the method and also to compare the method with other methods frequently used and recommended. Ordinarily the wind-loads on a building of the size and type assumed in the example would be ignored, but they have been considered here to make the example complete.

A factory-building (Fig. 2) is to have four floors above the basement capable of supporting an assumed unit load of 200 lb per sq ft. The load on the flat roof is assumed at 50 lb per sq ft. The horizontal wind-pressure is assumed as a uniform pressure of 40 lb per sq ft, on the sides *AB* and *CD*.

vertical component of the wind-pressure is to be taken care of by the footings of the side walls. There is also an interior self-supporting chimney and a main shaft which is protected from the wind and which carries no floor-loads. The foundation-bed is a uniform, sandy material which is expected to compress uniformly and at the rate of  $\frac{1}{2}$  in per ton of load per sq ft of supporting area.




Fig. 2. Foundation-plan and Section of Factory-building

MAXIMUM UNIT LOAD on the foundation-bed is taken at 4 tons, corresponding to a settlement of 2 in for the assumed load. The calculated dead loads of the building, including all construction down to the level of the footings, the portion of the assumed live loads and the vertical components of the assumed wind-loads are given in Table III.

Table III. Dead Loads and Assumed Live and Wind-Loads

Element of footing	Division 1, dead loads only, lb	Division 2, assumed live loads, lb	Division 3, assumed wind-loads, lb	Division 4, total dead, live and wind-loads, lb
Walls per lin ft....	14 000	8 400	2 000	24 400
Beams 1 and 5.....	137 500	160 000	.....	297 500
Beams 2, 3 and 4....	90 000	340 000	.....	430 000
Chimney.....	320 000	.....	.....	320 000

Columns are called divisions to avoid confusion with building-columns.

A careful study of the probable loading of the building shows that the maximum live loads at any one time will not exceed 60% of the total assumed live loads and that the maximum wind-loads will be less than 50% of the assumed loads, for the reason that the assumed wind-pressure is based upon the recorded pressure on a limited area in an exposed situation, whereas the proposed building will be in a sheltered situation. Having, therefore, determined the probable maximum live loads and wind-loads at 60% and 50% respectively of the assumed loads, the so-called mean loads, corresponding to loads between the minimum and maximum loads, will be one-half of the probable maximum loads, or  $60\% \times \frac{1}{2} = 30\%$  of the assumed live loads and  $50\% \times \frac{1}{2} = 25\%$  of the assumed wind-loads. Table IV gives the dead loads, mean live loads and wind-loads separately, and the total of the dead loads and mean loads, which total is to be used in proportioning the areas for least settlement. This is known as the total mean load.

Table IV. Dead Loads, Mean Live and Wind-Loads and Total Dead and Mean Loads

Element of footing	Division 5, dead loads, unchanged, lb	Division 6, one-half of 60% of as- sumed live loads, lb	Division 7, one-half of 50% of as- sumed wind- loads, lb	Division 8, total mean loads, lb
Side walls per lin ft....	14 000	2 520	500	17 020
Columns 1 and 5.....	137 500	48 000	.....	185 500
Columns 2, 3 and 4....	90 000	102 000	.....	192 000
Chimney.....	320 000	.....	.....	320 000

Table-columns are called divisions to avoid confusion with building-columns.

Comparing the two tables it will be seen that the interior columns of the building, columns 2, 3 and 4, had originally the largest percentage of live loads (no wind-loads), and have consequently suffered the greatest reduction in amount of total load. The minimum areas of support for columns 2, 3, 4 and also for the other elements of the footings, are obtained by dividing the total assumed loads given in division 4, Table III, by 8 000, the assumed unit load in pounds on the foundation-bed. The resulting areas are given in division 9, Table V. No reduction can be made in these areas without exceeding the limitation that the most disadvantageous combinations of loading ever improbable, shall not exceed the safe unit load. The adjustment of the areas to the probable mean loading, as given in Table IV, the table of mean loads, must be accomplished solely by increasing the sizes of certain footings. If we divide the total mean loads in division 8, Table IV, by the minimum areas given in division 9, Table V, we will get the mean load per square foot on the minimum areas for each element of the footing. The results given in division 10, Table V, show that the mean load for columns 2, 3 and 4 is 3 568 lb per sq ft, while under the chimney the load is 8 000 lb per sq ft. If no reduction in area is permissible it is necessary to increase the footings under the chimney, side walls and columns 1 and 5 until the mean unit load corresponds to the mean unit load for columns 2, 3 and 4. This is done by dividing the mean loads given in division 8, Table IV, by 3 568, the mean unit load

used for columns 2, 3 and 4. The resulting areas are given in division 9, and are the areas which should be used.

Method of calculation can be shortened and reduced to a rule as follows. Use Table IV, the table of mean loads, with Table III, the table of assumed loads, and find the element of support which has suffered the highest percentage reduction between the total assumed load and the total mean load, and note the corresponding minimum area of support at the allowable unit load on the foundation-bed. Divide the mean load for the same element of support by the number of square feet in the minimum area of support. The result will be the mean unit load for mean settlement. Then divide the mean loads for each element of support by the mean unit load. The results will be the required areas given in Table V.

Table V. Mean Loads on Minimum Areas and Areas for Mean Loads

Element of footing	Division 9, minimum areas, sq ft	Division 10, mean loads on minimum areas, lb per sq ft	Division 11, areas for mean loads, sq ft
walls per lin ft.....	3.05	5 590	4.7
columns 1 and 5.....	37.2	4 986	51.9
columns 2, 3 and 4.....	53.8	3 568	53.8
average.....	40.0	8 000	89.7

The columns are called divisions to avoid confusion with building-columns.

The mean unit load may be determined by multiplying the allowable unit load by the ratio obtained by dividing the mean load for the element of support which has suffered the highest percentage of reduction by the assumed load for the same element.

**Proportioning Settlements.** The following Tables VI, VII and VIII show the probable settlements which may be expected if the supporting areas are proportioned in accordance with different assumptions as to load. In all the tables it is assumed that the foundation-bed will settle  $\frac{1}{2}$  in per ton of load per square foot, and that the total assumed load will never load the foundation-bed to a stress of 4 tons per sq ft.

Table VI the footings are proportioned in the ratio of the DEAD LOADS only.

Table VII the footings are proportioned in the ratio of the TOTAL ASSUMED

LOADS. Table VIII the footings are proportioned in the ratio of the MEAN LOADS.

In each table, division 1 gives the dead load coming on the footings on the foundation of the building. Division 2 gives the load coming on the footings when the building is subjected to the maximum probable live loads and wind-loads. Division 3 gives the supporting areas in accordance with the assumed loads. Division 4 gives the settlements for the unloaded building. Division 5 gives the settlement after the addition of the maximum probable live and wind-loads.

**Explanation of Table VI.** The method of proportioning the areas in the tables is based on dead loads only, as recommended by C. C. Schneider\* may, in the form of a rule, be stated as follows:

\*Article on the Structural Design of Buildings, Trans. Am. Soc. C. E., vol. 54.

Compare the table-division of dead loads, Table VI, with the div assumed live loads, find the element of support which has the highest per of live loads to dead loads, and note the corresponding minimum area of at the allowable unit load on the foundation-bed. Divide the dead the same element of support by the number of square feet in this minim of support, and the result will be the unit load due to the dead load only. divide the dead loads for all other elements of support by this unit lo the results will be the areas required. Thus, in Table VI, it is seen by 1 to Table III that columns 2, 3 and 4 have the greatest percentage of 1 to dead load, and their minimum area of support, as in Table V, is 53. Then,  $90\,000 \div 53.8 = 1\,675$  lb, the unit load due to the dead load only. area for columns 1 and 5 is  $137\,500 \div 1\,675 = 82.1$  sq ft. The process lar for the other elements.

Table VI. Footings Proportioned in the Ratio of the Dead Loads (

Probable settlement where supporting areas are proportioned in the ratio of dead loads only					
Element of footing	Division 1	Division 2	Division 3	Division 4	Division 5
	Dead loads only, lb	Maximum probable loads, lb	Areas, sq ft	Settlements, in	
				Empty	Loaded
Side walls per lin ft.....	14 000	20 040	8.3	0.42	0.42
Columns 1 and 5.....	137 500	233 500	82.1	0.42	0.42
Columns 2, 3 and 4.....	90 000	294 000	53.8	0.42	0.42
Chimney.....	320 000	320 000	191.0	0.42	0.42
Maximum variation, empty.....			.....	0.00	.....
Maximum variation, loaded.....			.....	.....	.....

Table-columns are called divisions to avoid confusion with building-columns.

The calculations for settlements are readily made, when the amount of compressibility of the foundation-bed is known, by multiplying the unit load on the foundation-bed of each element of support by the amount of compressibility of the foundation-bed per unit of load. Thus, in the above example the amount of compressibility is given as ½ in per ton. In Table VI the unit load due to dead loads for each element of support, are the same, or 1 675 lb = 0.42 lb per sq ft, which, multiplied by ½ = 0.42 in. Similarly, the unit load due to maximum probable loads for each element of support are determined, and the settlements, in inches, multiplied by one-half, give the settlements in inches as given in division 5 of Table VI.

**Explanation of Table VII.** The areas given in Table VII are obtained by dividing the total maximum dead loads, live loads and wind-loads (Table V) by the allowed unit, 8 000 lb per sq ft, and are the minimum areas given in Table V. The settlements for the loaded building are based on the maximum loads as given in division 2 of Table VII.



**Table VII. Footings Proportioned in the Ratio of the Total Assumed Loads**

Probable settlement where supporting areas are proportioned in the ratio of total assumed loads					
Element of footing	Division 1	Division 2	Division 3	Division 4	Division 5
	Dead loads only, lb	Maximum probable loads, lb	Areas, sq ft	Settlements	
				Empty, in	Loaded, in
Side walls per lin ft.....	14 000	20 040	3.05	1.15	1.64
Columns 1 and 5.....	137 500	233 500	37.2	0.92	1.57
Columns 2, 3 and 4.....	90 000	294 000	53.8	0.42	1.36
Chimney.....	320 000	320 000	40.0	2.00	2.00
Minimum variation, empty.....			.....	1.58	.....
Minimum variation, loaded.....			.....	.....	0.64

Table-columns are called divisions to avoid confusion with building-columns.

**Table VIII. Footings Proportioned in the Ratio of the Mean Loads**

Probable settlement where supporting areas are proportioned in the ratio of total mean loads					
Element of footing	Division 1	Division 2	Division 3	Division 4	Division 5
	Dead loads only, lb	Maximum probable loads, lb	Areas, sq ft	Settlements	
				Empty, in	Loaded, in
Side walls per lin ft.....	14 000	20 040	4.7	0.74	1.06
Columns 1 and 5.....	137 500	233 500	51.9	0.66	1.12
Columns 2, 3 and 4.....	90 000	294 000	53.8	0.42	1.36
Chimney.....	320 000	320 000	89.7	0.89	0.89
Minimum variation, empty.....			.....	0.47	.....
Minimum variation, loaded.....			.....	.....	0.47

Table-columns are called divisions to avoid confusion with building-columns.

**Explanation of Table VIII.** The areas in Table VIII are obtained as previously explained and as given in division 11, Table V, and the methods used in determining the settlements are similar to those used for the preceding tables. In Table VIII it will be noted that columns 2, 3 and 4 have a settlement of  $1.36 - 0.42 = 0.94$  in, as a result of the addition of the live loads and dead loads. Half of this settlement is required to bring these footings down to the level of the chimney-footing, and the other half of the settlement brings

them below the chimney-footing. There is no way to prevent this settlement of 0.94 in, but its effect on the building is reduced to a minimum by having settlement of the footings of columns 2, 3 and 4 start above the chimney-footing and finish below it. The chimney-footing does not change its elevation at the completion of the building, and compared with it, the variation in settlement of the other footings is the minimum. In their mean position, half-way between the chimney-footing and the other footings, these other footings will be at the same level as the chimney-footing.

## 16. Determining the Supporting Areas

**General Requirements.** In laying out the AREAS OF SUPPORT for any structure it should be borne in mind, as previously explained, that (1) the total load, the dead loads, assumed live loads and assumed wind-loads should not load the foundation-bed in excess of the allowable load on it; (2) when the foundation-bed is compressible the areas of support should be calculated by the method of mean loads; and (3) the center of gravity of the supporting area should coincide with the center of action of the load to be supported. To these may be added a further condition that (4) economy will be furthered by keeping the supporting areas simple in outline and by arranging each area as compactly as possible around the center of the load to be supported.

(1) The first condition is necessary in order to provide that no possible condition of loading will exceed the allowable pressure on the foundation-bed.

(2) The second condition provides for making the settlements of different footings as nearly equal as possible.

(3) The third condition provides that the settlements of each footing should be uniform, that is, that the footing shall not settle out of level.

(4) The fourth condition provides for economy in design in the footing and for economy in making the excavation for the footing, especially in the case of deep excavations requiring sheathing for the protection of their sides.

In the case of a free-standing structure, the total load of which is not in excess of the supporting capacity of the entire area of the building at the same load on the foundation-bed, it will generally be possible to arrange simple supporting areas whose centers will correspond with the centers of the loads. The disposition of such areas is considered in succeeding paragraphs in the discussion of CONCENTRIC LOADING. In buildings having restricted sites, where walls or columns are placed close to adjoining property-lines, it will frequently be impossible to arrange for simple concentric loadings and necessary offset footings, cantilevers or other devices to transfer the loads to supporting areas located on the property. Such supporting areas are discussed in succeeding paragraphs relating to ECCENTRIC FOOTINGS.

**Footings with a Concentric Load.** In order to have the load on the foundation-bed uniform under a footing it is necessary that the center of gravity of the supporting area should coincide with the center of gravity of the load. Otherwise the area is said to be ECCENTRICALLY LOADED and the result is an uneven load on the foundation-bed will not be uniform. Any variation in the load on a compressible foundation-bed under a footing will result in an unequal settlement of the footing and this in turn will result in unequal stresses in the wall or column supported by the area.

**Wall-Footings with Concentric Load.** In the case of a WALL, the footing should project an equal distance on each side so that the center of gravity of the supporting area will coincide with the center of gravity of the wall. The loads transmitted by the wall. The width of the supporting area varies with the load on the wall, irrespectively of any change in the thickness of the wall.

**ing for a Concentric Isolated Load.** In the case of a **SIMPLE CONCENTRIC LOAD**, as, for example, a load from a **COLUMN** or **PIER**, the footing may be **CIRCULAR**, **SQUARE**, **RECTANGULAR**, or **IRREGULAR** in outline, but the center of gravity of the area must coincide with the center of gravity of the load. Usually the **CIRCULAR SHAPE** gives the most economical footing, as the supporting areas extend radially the least possible distance from the center of the load. Where deep excavation is necessary the circular form may lead to an economical method of excavation, as, for example, when cylindrical piers are sunk by the pneumatic method or by dredging. In general, however, for ordinary footings the **RECTANGULAR FORM** is preferable, in that it lends itself to an economical arrangement of grillage-beams. The **SQUARE** is not the most economical rectangle as the sum of the bending moments in the grillage and the excavation is reduced to a minimum.

**Elongated Supporting Areas.** When the required supporting area for an isolated load cannot be a circle or a square, for example, when the circle or the square would overlap an adjacent property-line or interfere with an adjacent supporting area, the necessary area frequently can be made **RECTANGULAR** in form, as  $ABDC$  (Fig. 3), having a width  $w$ , twice the distance  $a$  between the center of the load  $O$  and the nearest property-line  $AB$ .




Fig. 3. Elongated Supporting Area. Concentric Load

The required length  $l$  equals the required area divided by  $w$  and the area must be centered on  $O$ , that is,  $l_1$  must equal  $l_2$ .

**Combinations of Simple Areas. Two Adjacent Isolated Areas.** When the required supporting areas overlap or when, for other reasons, it is desirable to provide for **ADJACENT FOOTINGS**, the best arrangement may be obtained as follows: The required supporting area required for each of two adjacent concentrated loads and the distance between the centers of the loads, the sum of the two required areas should be divided by twice the distance between the load-centers. The result will be the width or the dimension of the required rectangle of support, taken at right-angles to the line connecting the load-centers; and the length of the rectangle will be twice the distance between the load-centers. The center of the area should be placed so as to coincide with the center of gravity of the two loads, when it will be found that each load will be concentric with its own area of support. Where a row of columns requires supporting areas which nearly overlap, the **COMBINATION OF THE AREAS** frequently results in a more economical excavation and form-work.

**Supporting Area for a Concentrated Load in the Line of a Wall.** When two or more concentrated loads are carried in the line of a wall the **ADDITIONAL SUPPORTING AREAS** required for such concentrated load may be provided in one of two ways.

If the concentrated loads rest on the wall, as, for example, when the wall carries the ends of girders and when the conditions are such that the concentrated loads are distributed along given lengths of it, then, all that is necessary is to increase the width of the footing for the given lengths sufficiently to carry the total of the uniformly distributed and concentrated loads.

If a concentrated load is on the center line of the wall but cannot be distributed by the wall, as when a considerable load is carried by a pier or column between the footings, then one-half the additional area for the concentrated load should be placed on either side of the wall-footing, so that a line connecting the centers of the two areas will pass through the center of the load. In general

It is desirable that the additional areas, together with the area for the wall between them, should APPROXIMATE A SQUARE. Knowing the width of footing required to support the wall and the additional area required to support the concentrated load, the length of the side of the required square can be determined by the following formula (Fig. 4):




Fig. 4. Square Supporting Area. Wall and Concentric Isolated Load

Let  $w$  = the width of the footing;

$A$  = the area required to support the concentrated load;

$f$  = the side of the square which will support a length of wall equal to  $f$ , and provide an additional area equal to  $A$ . Then

$$f = \frac{1}{2}w + \sqrt{A + \frac{1}{4}w^2}$$

**Supporting Area for Concentrated Load not in the Center Line of Wall.** The same additional supporting area is required for this as for a concentrated load on the center line of a wall, but the total area must be placed unequally between the two sides of the wall-footing, the larger portion being placed on the side of the wall-footing where the eccentric load is applied. The simplest way to determine the location of the supporting areas for this combination is to determine the size of the required square as if the concentrated load were concentric with the center line of the wall. The next step is to calculate the load due to the wall for the length of this square and determine the location of the center of gravity of the combined loads, that is, the center of gravity of this wall-load and the concentrated load. The center of the supporting area is placed concentrically with the center of gravity of the combined load (Fig. 5) let




Fig. 5. Square Supporting Area. Wall and Eccentric Isolated Load

$w$  = the required width of the wall-footing;

$O$  = the concentrated load;

$A$  = the area required for the support of the concentrated load.

as before, the length of the side of the required square will

$$f = AB = \frac{1}{2}w + \sqrt{A + \frac{1}{4}w^2}$$

The center of gravity of the wall-load contained between the lines  $AB$  and  $CD$  is at  $g$ , and the amount of the load is evidently the load per foot multiplied by the distance  $AB = f$ . Knowing the position and amount of the loads at  $O$  and  $g$ , the center of gravity of the combined loads is determined, say at  $G$ . This point  $G$  fixes the center for the square.




Fig. 6. Square Supporting Area. Isolated Load on End of Wall

**Supporting Area for a Concentrated Load at the End of a Wall.** A somewhat different treatment is required for this, but the supporting area can be best determined as follows (Fig. 6): Knowing the width  $w$  of the footing required for the support of the wall, the additional area required for the concentrated load  $O$  and the distance  $p$  from the center of the concentrated load from the end of the wall, proceed in this way. Determine the area whose area corresponds to the sum of the areas required for the supporting area of the wall and for a length of wall equal to twice the projection of the concentrated load. Plot this square  $ABCD$ .

whose area corresponds to the sum of the areas required for the supporting area of the wall and for a length of wall equal to twice the projection of the concentrated load. Plot this square  $ABCD$ .

plan and also the total area required for the support of the wall. The square  $ABCD$  includes an area sufficient for the support of the concentrated load for a section of the wall  $EFGH$  corresponding to a length of wall equal to the projection  $p$ , multiplied by the width of the footing. It is evident the area  $KEHR$  is loaded both by the wall and the concentrated load; in other words, that the square  $ABCD$  is too small by the amount of the rectangle  $EL$ . The required square  $LMNO$  will be approximately the square which contains the original area  $ABCD$  plus the area  $KEHR$ , plus twice the area  $EL$ . The length of the side  $LM = MN$  will be approximately the length of the original square plus one-half of the area  $KEHR$  divided by the length of the original square. The resulting square should be moved from the position shown on the drawing so that its center coincides with the center of gravity of the combined concentrated load and the wall-load back as far as the wall goes on the wall. A further approximation may be necessary where accuracy is required. The final result should be that the area of the square  $LMNO$  should be sufficient to support the concentrated load  $O$  and that portion of wall-load  $JFGQ$  resting on the square, and that the center of gravity of the square should coincide with the center of gravity of the combined loads.

## 17. Offset Footings

**Supporting Areas for Non-Concentric Loads.** When walls, columns, or other structures are placed close to property-lines the required supporting areas cannot be located concentrically with the loads without encroaching on the property-lines. In such cases there must be had to some method which will bring the loads to supporting areas not concentric with the loads. An attempt to accomplish this result, the method known as OFFSETTING THE SUPPORTING AREAS, has been largely used, especially for side walls adjoining property-lines. While theoretically, if not useless, it is indisputable that OFFSET FOOTINGS have generally served the purpose for which they were designed. In the typical situation a cellar wall rests on a course of concrete or of flat stones forming a footing course considerably wider than the wall, the projection being entirely on one side of the wall. The load is applied on one side of the center of the footing, thus making the supporting area unequal. The VARYING PRESSURE on the supporting area can be calculated as follows. In Fig. 7 let



--

--

Fig. 7. Offset Footing. Varying Pressure on Foundation-bed.

- $W$  = the total load per unit of length coming on the supporting area;
- $e$  = the eccentricity of load, that is, the distance between the center of the load and the center of the supporting area;
- $L$  = the width of the footing = the width of the supporting area =  $AB$ ;
- $P_1$  = the unit load, or pressure on the foundation-bed at  $A$ , the edge of the footing nearest the load;
- $P_2$  = the unit load, or pressure on the foundation-bed at  $B$ , the edge of the footing farthest from the load;
- $y$  = any ordinate, from  $A$  to  $B$ .

The AVERAGE PRESSURE on the foundation-bed will evidently be  $W/L$ . The pressure at  $A$ , the edge nearest to the point of application of the load, will

be  $K_1 = W/L (1 + 6 U/L)$ , or the MAXIMUM LOAD will equal the average plus six times the average load multiplied by the ratio of the ECCENTRICITY divided by the width of the footing.

Similarly, the pressure at  $B$ , the edge farthest from the point of application of the load, will be  $K_2 = W/L (1 - 6 U/L)$ , or the MINIMUM LOAD equal average load minus six times the average load multiplied by the ratio of eccentricity divided by the width of the footing.

When the ECCENTRICITY equals  $\frac{1}{6}$  the width, the pressure at  $B$  becomes zero. If the eccentricity exceeds  $\frac{1}{6}$  the width there will be an uplift at  $B$ , or the footing will have a tendency to overturn. This relation is generally expressed by saying that to avoid an upward reaction the line of the load must fall within the MIDDLE THIRD of the base.




Fig. 8. Pressure-diagrams for Footings

**Load-Diagrams for Offset Footings.** In the load diagram (Fig. 8) the figure  $ADEC$  represents the load diagram on the foundation-bed for a wall of width  $AD$  and the load  $AC$  is the maximum permissible load, then the area  $ADEC$  represents the maximum support afforded by the footing. If the width is increased until the load falls on the middle third or to the width  $AB$ , the load at  $B$  is zero and the support is represented by the triangle  $ADEC$ , the area of which is less than the area  $ADEC$ . Moreover, if the width of the footing is reduced until its center is concentric with the load-center, the load diagram becomes  $AFGC$ , the area of which is greater than either  $ADEC$  or  $ADEC$ . From the foregoing it is evident that any advantage gained by offsetting the footing must be obtained at the cost of concentrating the load given to the wall away from the center line of the wall.




Fig. 9




Fig. 10




Fig. 11



Fig. 12

Figs. 9, 10 and 11. Eccentric Loading and Tendencies to Failure Due to Offset Footings; Fig. 12. Improved Type of Construction

**Eccentric Loading Due to Offset Footings.** In Fig. 9, representing a simple case of ECCENTRIC LOADING due to OFFSET FOOTINGS, the load on the foundation-bed at  $E$  is perhaps twice the average load and at  $F$  about half. Under these conditions the projecting portion of the footing may shear,

along the line *DG*. If it does not shear and if there is any settlement under the load, the settlement will be unequal and the footing course will tend to rotate into the position shown in Fig. 10. The entire load will then be transmitted through the inner lower corner *D* of the cellar wall, rendering the wall unstable and developing a tendency to move in the direction *H*.

The cellar wall may successfully resist this tendency by its own rigidity aided by the first-floor beams acting as ties or by the external resistance offered by an abutting wall or bank of earth, or it may partially or completely fail, developing a horizontal crack as indicated in Fig. 11 at *J*.

In this figure it will be noted that the base of the wall itself is offset. This is done to prevent the separate rotation of the footing course; but this construction does not diminish the TENDENCY TO ROTATION of the entire base of the wall and to the formation of a crack at *J*.

An improved type of construction is illustrated in Fig. 12, in which the floor-beams are anchored into the wall and the cellar wall has a continuous stepped surface from the level of the footing up to the level of the beams. The beams should evidently be arranged as tension-members, should run across the building and should be anchored in the opposite wall. While this method may have some effect it is of doubtful efficacy and should never be used for piers.

### 18. The Use of Cantilevers in Foundations\*

**Application of the Principle of the Lever.** The use of the CANTILEVER, transferring a load to a supporting area not concentric with the load, is based on the PRINCIPLE OF THE LEVER and involves a girder or cantilever connecting two loads, and a supporting area or areas the CENTER OF ACTION of which lies between the two loads. Part or all of the load on one side counterbalances the load on the other side of the center of the supporting area.

**Illustrative Example.** If an exterior column *A* (Fig. 13) carrying a load of 400 tons and requiring 100 sq ft of supporting area, at 4 tons per sq ft, the column being 18 in from a property-line *PP* which forms the limit of the building lot, it is evidently impractical to employ a concentric footing 3 by 33½ ft for support. If, however, a sufficient counterweight can be found in the shape of an adjacent interior column-load, as at *B*, the exterior load can be transferred by a girder or cantilever construction *CDEF* to a supporting area *MN* lying between the two loads, and entirely within the limits of the property.

In Fig. 13 let *PP* represent the property-line, *A* the center of the load on column *A*, and *B* the center of the load on column *B*. Let the load on *A* be 400 tons, on *B*, 200 tons and the distance *AB* between centers, 20 ft. Assume that a rigid girder *CDEF* supports and connects the two columns. If now a POINT or point of support *G* is provided for the girder at some point between *A* and *B*, the load on that point can be readily determined from the PRINCIPLE OF THE LEVER by multiplying the load on *A*, 400 tons, by the distance *AB*, 20 ft, and dividing the product by the distance *BG*, 19 ft; or, the load on *G*  $400 \times 20 / 19 = 421$  tons +. The area required for the support of this load, at 4 tons per sq ft, is  $421 / 4 = 105\frac{1}{4}$  sq ft. The uplift at *B*, or the part of the load *B* required to counterbalance the overhanging load *A* is, from the principle of the lever, the product of the load *A* by the lever-arm *AG* divided by the lever-arm *BG*. The load on the footing for *B* is the difference between the original load and the uplift; but in view of the possibility of a reduction in the load *A*, it would decrease the uplift at *B*, it is well to provide for a possible increase in the load *B*.

See, also, Chapter XIX, pages 678 to 680, for an example of a Continuous Girder in a Foundation.

**Determination of the Area of Support.** In determining the **AREA SUPPORT** for *A*, having assumed one dimension of the supporting area twice the distance *GP*, or say 5 ft, the other dimension will be 105¼ sq ft/ft ¼ in. If the length 21 ft ¼ in, as determined, is found to be excessive



Fig. 13. Cantilever Foundation-construction

the point *G* must be moved to the left and the corresponding length of supporting area must be determined as before. When the length of the supporting area for the fulcrum of the cantilever is limited, so that the length parallel to the property-line is fixed, the width of the area can be determined experimentally or by the use of the formula

$$X = (L + u) - \sqrt{(L + u)^2 - 2WL/S}$$

in which

*L* = the distance between centers of the two loads;

*W* = the load nearest to the property-line;

*l* = the length of the supporting area;

*S* = the unit load on the supporting area; and

*u* = the distance between the center of action of the load to be carried and the edge of the supporting area nearest to the property-line.

If the position of the center of gravity of the load *A* combined with part of the load on *B* which is borne by the cantilever is determined, it is found to coincide with the fulcrum or point of support *G* of the cantilever, demonstrating that the use of the cantilever provides a means of carrying two loads so that their center of gravity falls on the center of a support not concentric with either load.

**The Grillage Fulcrum.** Of course in practice the **KNIFE-EDGE** shown in the diagram is not used. The bottom flange of the girder carrying the cantilever rests on the **DISTRIBUTING GRILLAGE** directly, as is shown in the diagram which may be considered a typical arrangement.

**The Girdering-Method for Two Equal Loads.** When it is desired to support two or more adjacent concentrated loads on a single support



A method called GIRDERING is employed. In the case of two concentrated loads, let  $A$  and  $B$  (Fig. 15) represent two columns. Let  $W_1$  represent the load on  $A$  and  $W_2$  represent the load on  $B$ . Let  $D$  represent the distance between the centers of the two loads. Let  $G$  represent the center of gravity of the combined loads. Let  $r$  represent the allowable unit load on the foundation-bed. The required area of support will be  $(W_1 + W_2)/r$ . This area may be of any

the distance  $D$  between the columns plus twice the extension  $a$ . Knowing length of the required area the width  $w$  is determined by simple division.

**The Girdering-Method for Two Unequal Loads.** In the case of columns not equally loaded, the SUPPORTING AREA may be a TRAPEZOID, as in Fig. 15 the center of gravity of which must coincide with the center of gravity of the loads. Knowing the sum and distance apart of the loads and the area for




FIG. 15. Girdering-method of Foundations. Two Equal Loads

support, and fixing the total length  $L$  of the footing in accordance with requirements that the footing shall not project beyond the line  $PP$ , the width of the footing at the small and large end,  $a$  and  $b$  respectively, can be determined as follows: Let  $B$  represent the distance from the small end of the trapezoid to the center of gravity of the two loads and let  $A$  represent the area of the trapezoid. Then

$$b = [2A/L] \times [(3B/L) - 1]$$

$$a = [2A/L] \times [2 - (3B/L)]$$

$$A = [(a + b)/2] \times L \quad \text{and} \quad a + b = 2A/L$$

For practical reasons the distance  $d$  should be made as small as possible.

**Cantering an Exterior Wall.** In the case of a wall the same principles apply, but the cantilevering effect must be distributed along the length of the wall. This can be accomplished by placing a girder under the wall, the girder resting on the cantilever, or by using a number of cantilevers arranged




Fig. 16. Girdering-method of Foundations. Two Unequal Loads

in shape and radiating from the interior load-center. In narrow buildings cantilevers may run from wall to wall.

**Double Cantilevering.** The considerations controlling the design of the bearing areas required are the same as outlined in the preceding paragraphs.

## 19. Stresses in Footing Courses

**Size and Form of Footing Courses.** The footing courses of all walls and should be larger than the superimposed construction in order to secure safety against overturning and to reduce the unit load on the foundation. When the change in size is accomplished abruptly as when a wall rests on a grillage or a slab of plain or reinforced concrete the footing is called a **step footing**. When the base of the wall is thickened by means of offset

courses so that its bottom course is substantially as large as the footing the construction is known as a **STEPPED FOOTING**. It is evident that a straight and fast line can be drawn between the two classes. Whatever the form of footing is it must be strong enough to distribute the more or less concentrated load coming on it, into a uniform pressure or load on the foundation-bed.

**The Unit Loads of Footing Courses.** If the load on the upper part of a footing course is uniformly distributed the intensity of the load, or in other words the **UNIT LOAD ON THE FOOTING**, is obtained by dividing the total load by the area of the base of the wall, pier, or other construction at that level. The load on the foundation-bed should be **UNIFORMLY DISTRIBUTED** and in the foundation-bed is compressible and the load concentric with the supporting area, it may safely be assumed as uniform, since a compressible material will adjust itself until the loading at different points is substantially uniform. The unit load on the foundation-bed is evidently the total load divided by the supporting area. If the area of the footing course varies between the top and bottom of the footing the **INTENSITY** of the load will vary, and if uniformly distributed the unit load at any level is obtained by dividing the total load by the area of the footing at that level.

**The Weight of the Footing Itself.** This is generally so small when compared with the superimposed loads that it may be ignored without serious error.

**The Transmitting of Loads by Footings.** If we neglect the weight of the footing we can consider the footing course as transmitting the imposed load to the foundation-bed or as being subject to two equal loads; one, the **IMPOSED LOAD**, more or less concentrated on the center line of the footing acting downward; the other, the **REACTION** due to the loading of the foundation-bed, uniformly distributed over the supporting area and acting upward. Since the loads or forces being equal and opposite in direction, the stresses developed in the footings are due to the differences in the distribution of these loads. The footing courses simply act to convert concentrated loads into distributed loads.




Fig. 17. Failure of Footing by Shearing

**Manner of Failure of Footings.** A footing may fail in several ways: (1) by **SHEARING**; (2) by **CRUSHING**; (3) by **SPREADING**; and (4) by **BULGING** or **RUPTURE**.

(1) **Failure of Footings by Shearing.** This is illustrated in Fig. 17, showing a wall the weight of which has caused it to **SHEAR** along the line **EF** and **FH**.

The force tending to cause **SHEAR** is the weight of the wall less the reaction of the foundation-bed acting on the under side of the section **EFGH**. Since the load is supposed to be uniformly distributed this is equivalent to the weight of the area corresponding to the width **CD** minus the width **GH** times the unit load on the foundation-bed.

For a 1-ft length of wall the force causing shear,  $S$ , is

$$S = W(l - w)/l$$

in which  $W$  = the load due to wall per foot of length in pounds;

$l$  = the width of footing;

$w$  = the width of base of wall.

Or, since

$W/l = U$  = the unit load on the foundation-bed in pounds per square foot

$$S = U(l - w)$$

is in terms of feet,  $l$  and  $w$  also must be in feet. The resistance to shear, under the conditions illustrated in Fig. 17, taken for a 1-ft length  $b$  of the wall is determined by the equation

$$R = 2 \times d \times b \times f$$

which  $f$  = the safe resistance of the material to shear, in pounds per square inch;

$d$  = the depth of the footing in inches; and

$b$  = the length of wall considered = 12 in.

Since  $S = R$ , we have

$$2 dbf = U (l - w)$$

Since  $(l - w)/2$  = the projection of the footing

$$UP = 12 df$$

depth of the footing, therefore, must not be less than

$$d = UP/12f$$

which  $P$  is in feet.

**Failure in Footings of Piers and Columns.** FAILURE BY SHEAR is most likely to occur in footings for piers and columns. The FORCE TENDING TO CAUSE FAILURE is the total load on the column or pier less the reaction of the foundation on the area immediately under the column-base. The resistance offered is obtained by multiplying the perimeter of the column-base by the depth of the footing and by the allowable unit shear. When the area of the column-base is small, the entire load may be taken as producing shear. When reinforced concrete is used for the footing, there must be a sufficient number of stirrups to take care of the shear. (See Chapters XXIV and XXV.) Where steel beams are employed the cross-section of the beams must be sufficient to take care of the shear, otherwise additional web-plates should be added, as is explained in Chapters XV and XX.

**Failure of Footings by Direct Crushing.** The failure of footings by DIRECT CRUSHING of the materials composing the footings rarely, if ever, occurs. Where, however, the concentrated load, due to a pier or column, is supported by beams or girders which have thin webs, the webs may fail by crushing. Such beams or girders should have their webs reinforced by vertical STIFFENERS and additional WEB-PLATES, and the spaces between the beams or girders should be filled with concrete or grout. Where the load transmitted by the column exceeds the safe unit load of the material of the footing, a base of the column-base may be crushed, or a block of granite may be interposed between the base of the column and the concrete or masonry footing and base of the columns. In some cases, however, such granite should be considered as a footing course and designed to resist bending by formulas hereinafter given.

Fig. 18. Failure of Footing by Spreading

**Failure of Footings by Spreading.** Failure of the footings by SPREADING may occur under walls or piers, as shown in Fig. 18, especially when the

foundation-bed is of clay or other yielding material, which has, under the weight of the footing, a tendency to FLOW along the lines indicated by arrows in the figure. This tendency should be provided against by making the bottom continuous and adequate to resist the tension. Vertical joints, such as those made in footings composed of masonry, are sources of weakness, and should be avoided. The TENDENCY TO SPREAD is greatest in footings having a spread which is wide compared with the width of the superimposed wall or other construction. The writer knows of at least one important footing which has failed in this manner, the cracks in general following the joints of the masonry substantially as shown in Fig. 18.

(4) **Failure of Footings by Bending or Rupture.** A footing may fail by BENDING or RUPTURE as a beam or girder. In the case of a wall, if the footing bends, as shown in Fig. 19, the concentration of the load on the lower




Fig. 19




Fig. 20




Fig. 21

Figs. 19, 20 and 21. Failures of Footings by Bending

of the wall, as at E and F may cause the base of the wall to fail. This possibility should be borne in mind in designing footings where the load on the wall approaches the allowable unit load for the material composing it, and especially where the width of the footing is much greater than its own width. If a footing fails by RUPTURE the rupture may occur either under the center of the wall, as in Fig. 20, or at points close to the outer edge of the wall, as in Fig. 21. Fig. 20 illustrates the objection to using a footing course composed of masonry or stones which do not extend the full width of the footing. The joints in such construction prevent the footing course from acting in tension and the footing as a whole from acting as a BEAM.

## 20. Methods of Calculating Bending-Stresses in Wall-Footing

### Assumptions Made in Determining Bending-Stresses in Footings

Two methods for the calculation of the BENDING STRESSES IN FOOTING COURSES are in general use. Both are based upon the assumption that the REACTION of the foundation-bed is UNIFORM. In the first method the methods differ in the assumption made as to how the footing course and the base of the wall act. Neither assumption can be wholly correct.

**The First Method of Determining Bending-Stresses in Footings.** This method is based upon the assumption that the pressure of the wall on the footing is uniform over the area and remains so throughout the life of the structure.




Fig. 22. Bending-stresses in Footings. First Method

If, in Fig. 22, ABCD represents a footing course supporting a centrally loaded wall EFGH, and if

$W$  = the load of the wall in pounds per linear foot;

$r$  = the width of the wall in feet;

$l$  = the width of the footing in feet;

$2(w-r)$  = the projection  $AE$  or  $FB$ ,

$W/l = U$  = the unit load per square foot on the foundation-bed.

Considering the forces acting on the right of the center line of the wall for a length of wall, it is evident that the uplift on the half-footing  $OD$  will equal that its CENTER OF ACTION will lie half-way between  $O$  and  $D$ , or at a distance  $\frac{1}{4}l$  from the center line  $OO$ ; and, similarly, that the load due to one-half the wall will be  $\frac{1}{2}W$  and that its CENTER OF ACTION will be at a distance  $\frac{1}{4}w$  from the center line  $OO$ . The resulting moments will be

$$M_1 = \frac{1}{2}W \times \frac{1}{4}l = \frac{1}{8}Wl$$

$$M_2 = \frac{1}{2}W \times \frac{1}{4}w = \frac{1}{8}Ww$$

As these two moments act in opposite directions, the resultant moment tending to produce bending in the footing will be the difference between the two, and the bending moment at the center line  $OO$  is

$$M_0 = M_1 - M_2$$

$$M_0 = \frac{1}{8}W(l - w)$$

Since

$$W/l = U \quad \text{and} \quad \frac{1}{2}(l - w) = P, \text{ the projection,}$$

Equation (1) may be written in either of the forms

$$\left. \begin{aligned} M_0 &= \frac{1}{8}U(l - w)l \\ M_0 &= \frac{1}{8}WP \end{aligned} \right\} \quad (1)$$

The error involved in this first method is due to the assumption that the load on the upper surface of the footing remains UNIFORMLY DISTRIBUTED, as if the base of the wall acted as a FLUID, in which case the distribution of the load would remain constant and the formula would be correct. But the base of the wall is not a FLUID, but a SOLID which will resist DEFORMATION. If, as in Fig. 23, the footing course  $ABCD$  deflects and the base of the wall is assumed to be incompressible, the entire load of the wall will be communicated to the footing through the edges  $E$  and  $F$ . While such a concentration is, of course, possible (as the edges  $E$  and  $F$  will crush or compress a considerable area of the base of the wall in contact with the footing) the result is that the weight of the wall is concentrated near the outer ends of its base. Equation (1) gives results which are too large; but as it errs on the side of safety, it is recommended for general use.

The Second Method of Determining Bending-stresses in Footings, also in common use, takes into consideration only the projecting portion of the footing as follows:

In Fig. 23  $ACBD$  represents a footing course supporting a centrally located wall  $EFGH$ , and if we use the notation of the preceding method, then, if we assume that the wall acts as a FIXED BEAM and the projections  $AE$  and  $FB$  as CANTILEVERS supported by the wall, and denote the projection of the footing on either




Fig. 23. Bending-stresses in Footings. Second Method

side of the wall by  $P$ , the reaction of the foundation-bed on this portion  $P$ , per unit length of wall, will be  $PU$ . The CENTER OF ACTION force will be at a distance  $\frac{1}{2} P$  from  $E$  or  $F$  and its moment at  $E$  or  $F$

$$M = PU \times \frac{1}{2} P = \frac{1}{2} UP^2$$

or, since

$$P = \frac{1}{2} (l - w)$$

the value of  $M$  may be given in the form

$$M = \frac{1}{8} U (l - w)^2$$

**The Error Involved** in this second method is due to the assumption that uplift on the projection  $P$  can be resisted by the extreme outer edge of the wall. If the uplift on the projecting part is concentrated on the edge then the edge must either compress or fail by crushing, which, in either case, would throw the center of support for the cantilever back from the edge of the wall; and this is contrary to the assumption used in calculating the moment. This method takes into consideration only the intensity of the reaction of the foundation-bed and the length of the projection, and is known as the PROJECTION-METHOD.

**Comparison of Results.** Comparing the results of the two methods, it can be seen that the load cannot act at the two edges  $E$  and  $F$  as assumed in the PROJECTION-METHOD (2), nor ordinarily can it be uniformly distributed as assumed in Equation (1), but that the INTENSITY OF THE LOAD PER UNIT OF AREA will vary, being a MINIMUM at the center and a MAXIMUM near the edges of the base of the wall. The exact positions of the CENTERS OF ACTION are affected by various conditions which cannot be fully discussed in this chapter.

**New Formula for Determining Bending Moments in Footings.** The writer has devised a formula which gives values for the bending moment half-way between the values given by Equations (1) and (2), and which corresponds to the assumption that, considering the forces on either side of the center of the wall, the CENTER OF ACTION of the half-load of the wall is at the center of the half-wall, when the projection equals zero, and, as the projection increases, moves toward a position which is two-thirds of the distance from the center of the wall to its edge. This formula may be expressed as follows:

$$M = \frac{1}{8} U (l - w) (l - \frac{1}{2} w)$$

Or, substituting the value of  $U$  in terms of  $W$ ,

$$M = \frac{1}{8} W (l - w) (1 - w/2 l)$$

**Weight and Pressure-Units.** In practice  $W$ , the weight due to the wall, is generally given in pounds per linear foot of wall, and the allowable pressure on the foundation-bed, while frequently given in tons per square foot, should be reduced to pounds per square foot.

**The Required Width of the Footing** in feet is obtained by dividing the weight of the wall in pounds per linear foot of wall by the allowable unit load on the foundation-bed expressed in pounds per square foot.

**Moment-Units.** The moment tending to produce rupture may be calculated in foot-pounds or inch-pounds. If in Equations (1), (2) and (3) the dimensions  $l$ ,  $w$  and  $P$  are in feet and  $U$  is in pounds per square foot, the resulting bending moment will be in foot-pounds per linear foot of wall. As the MOMENT OF RESISTANCE is generally stated in inch-pounds it is more convenient to have the MOMENT OF RESISTANCE in inch-pounds. The MAXIMUM BENDING MOMENT OR MOMENT OF RUPTURE\* in inch-pounds. The Equation (1)

\* In the flexure-formula the moment of resistance is made equal to the bending moment at any cross-section of the footing, and the maximum bending moment is sometimes called the moment of rupture.



$$M \text{ (in inch-pounds per foot of wall)} = 12 M \text{ in foot-pounds,} \\ M \text{ (in inch-pounds)} = \frac{3}{8} U (l - w) l \quad (1)'$$

Equation (1) in the same way becomes

$$M \text{ (in inch-pounds)} = \frac{3}{8} U (l - w)^2 \quad (2)'$$

Using the more convenient form,

$$M = \frac{1}{8} U P^2$$

where the projection  $P$  in inches, instead of in feet, we will have

$$M \text{ (in inch-pounds per foot of wall)} = \frac{3}{8} U P^2$$

Equation (3) becomes

$$M \text{ (in inch-pounds per foot of wall)} = \frac{3}{8} U (l - w) (l - \frac{1}{2} w). \quad (3)'$$

Although Equations (3) or (3)' are more generally accepted, an engineer or designer should be perfectly safe in using Equation (1), and in the following pages the writer will use Equations (1) or (1)' unless the contrary is stated.

**F** **I** in term of  $w$

Fig. 24. Graphical Comparison of Bending Moments in Footings

The following is an example illustrating the application of the formulas:

A wall transmits to the footing 42 000 lb per linear foot of wall. The unit load on the foundation-bed is 3 600 lb per sq ft. What is the required MOMENT OF RESISTANCE\* of the footing?

$$42\,000/3\,600 = 11\frac{2}{3} \text{ ft}$$

When the design-formula the moment of resistance is made equal to the bending moment at any cross-section of the footing, and the maximum bending moment is called the moment of rupture.

Then, by Equation (1), we have

$$M = \frac{1}{8} \times 3\,600 (11\frac{3}{4} - 2) 11\frac{3}{4} = 50\,750 \text{ ft-lb}$$

If Equation (2) is used, we have

$$M = \frac{1}{8} \times 3\,600 (11\frac{3}{4} - 2)^2 = 42\,050 \text{ ft-lb}$$

and by Equation (3)

$$M = \frac{1}{8} \times 3\,600 (11\frac{3}{4} - 2) (11\frac{3}{4} - 1) = 46\,400 \text{ ft-lb}$$

Comparing the results we see that the moment by Equation (3) is the average of the moments by Equations (1) and (2).

**Graphical Comparison of Bending Moments in Footings.** Fig. 24 is a graphical comparison of the moments for varying ratios of  $l$  to  $w$  calculated by Equations (1), (2) and (3) on the assumption that

$w$  = the width of wall = 1 ft;

$U$  = the unit load on the foundation-bed = 1 000 lb per sq ft; and

$r = l/w$ .

The load on the wall, in pounds, for any value of  $l$ , is 1 000  $l$ .

Comparing the curves of Equations (1) and (2) it will be seen that they are widely apart, the percentage of variation being highest in the case of small projections. When  $l$  is less than twice  $w$ , or in other words, when the projection is less than one-half the width of the wall, Equation (2) gives moments less than half the moments given by Equation (1). Equation (2) may be used for small projections. Equation (1) gives results which are too large, especially for small projections. Equation (3), giving results half-way between those of Equations (1) and (2) and in accordance with a reasonable hypothesis, appears to be preferable, but is not in accordance with present practice.

## 21. Bending Moments in Footings of Columns and Piers

**General Statement of the Problem.** Fig. 25 represents in plan a column resting on a footing which projects on four sides. The base of the column or pier is represented by  $ABCD$ , the footing and its area of support by  $EFGH$ . The four corner-areas of the footing included in the areas  $MNQR$  and  $QRST$  can be considered as acting in the same manner as projecting footings under a wall, but the uplift on the four corners  $EQMA$ , etc., on which no supposed wall-load is imposed, also causes bending moments.




Fig. 25. Plan of Column-footing with Four Equal Projections

**Different Theories.** There are several theories for determining the uplift on the four corner-areas. The discussion of these theories would be out of place in this chapter. In a column footing, the projection is not over one-half the width of the supporting base, the four corner-areas will not aggregate over 25% of the area of the footing, and it may then be assumed that the bending moment is the same as if the base of the column or pier extended like a wall over the entire footing, as is shown in Fig. 26. To insure these conditions, the projection of the footing exceeds  $\frac{1}{2} w$ , and in all cases when the footing is homogeneous, as when a grillage of steel is used, the load of the column is distributed over the width of the footing by a GIRDER OR BOLSTER OR extension of the column-base. In case the footing is in several layers

must extend the full width of the underlying layer. With such construction it is evident that the bending moment will be the same as if the GIRDER or WALL were a wall and Equation (1) will be applicable.

**Bending Moments in Column-Footings.** For column-footings Equation (1) can be used, taking the total load in place of the load per foot, and the result will be the total bending moment.

**Example.** A column carrying a load of 192 tons is to be supported on a concrete slab. The cast-iron base is 2 ft square. The allowable pressure on the foundation-bed is 6 tons per sq ft. What is the MAXIMUM BENDING MOMENT in the slab?

The area of support =  $96/6 = 16$  sq ft = 4 by 4 ft. The projection is  $\frac{1}{2}(4 - 2) = 1$  ft, or one-half the width of the base, and by the foregoing rule we can calculate the bending moment as if the base of the column acted in one direction across the footing. Applying a convenient form of Equation (1)




Fig. 28. Column-footing Treated Like Wall-footing

$$M = \frac{1}{8} \times 192\,000 \text{ lb} (4 - 2) = 48\,000 \text{ ft-lb, or } 576\,000 \text{ in-lb}$$

The footing must therefore be of sufficient depth to resist this bending moment.

In this example the allowable unit pressure on the foundation-bed is 2 tons per sq ft. If the supporting area and the area of the bottom concrete footing course will be  $96/2 = 48$  sq ft. If the footing course can be a square its dimensions will be, with sufficient exactness, 7 by 7 ft. By the rule, since the projection exceeds one-half the width of the base, there should be a BOLSTER extending across the footing. The bolster will be, therefore, 7 ft long and may properly be composed of two or more steel beams. The cast-iron base may be dispensed with, in which case the base of the column will be provided with a steel base or with flange-angles. Let us assume that the column is 1 ft 6 in square and the width of the bolster 2 ft.

The bending moment in the bolster is determined, then, by Equation (1). Taking  $1\frac{1}{2}$  ft, the width of the column-base, for  $w$ , and 7 ft, the length of the bolster, for  $l$ .

$$M = \frac{1}{8} \times 192\,000 (7 - 1\frac{1}{2}) = 132\,000 \text{ ft-lb} = 1\,584\,000 \text{ in-lb}$$

The bending moment in the slab is determined in the same way by Equation (1). Taking 2 ft, the width of the bolster, for  $w$ , and 7 ft, the length of the slab, for  $l$ .

$$M = \frac{1}{8} \times 192\,000 (7 - 2) = 120\,000 \text{ ft-lb} = 1\,440\,000 \text{ in-lb.}$$

**Footings Other Than Square in Plan.** In case it is necessary to use some shape other than a square for the supporting area the resulting moments in the bolster and bolster will vary from those calculated above. If in the foregoing example the supporting area, for any reason, is necessarily made 6 by 8 ft, giving 48 sq ft as the required area, and if the bolster is parallel with the 6-ft side, the bending moment in the bolster will be

$$M = \frac{1}{8} \times 192\,000 (6 - 1\frac{1}{2}) = 108\,000 \text{ ft-lb} = 1\,296\,000 \text{ in-lb}$$

The moment in the slab will be

$$M = \frac{1}{8} \times 192\,000 (8 - 2) = 144\,000 \text{ ft-lb} = 1\,728\,000 \text{ in-lb}$$

or, the moment in the bolster is less and the moment in the slab is greater in the case of the 7 by 7-ft supporting area. If the bolster runs parallel to the long side, the moments will be, for the bolster,

$$M = \frac{1}{8} \times 192\,000 (8 - 1\frac{1}{2}) = 156\,000 \text{ ft-lb}$$

and for the slab,

$$M = \frac{1}{8} \times 192\,000 (6 - 2) = 96\,000 \text{ ft-lb}$$

In footings having more than two layers, each layer must be investigated separately, using  $l$  for the length of the layer which is being determined for the width of the superimposed layer.

**Compound Footings.** In COMPOUND FOOTINGS where, for example, and a column or two or more columns are supported by a single footing where loads are cantilevered, the loads will in general be distributed to the supporting area by GIRDERS or CANTILEVERS. The shears and bending moments of such girders or cantilevers must be determined for each case by the methods used in the calculations of beams and girders in Chapters XV and XX.

## 22. Design of the Footings

**Materials used for Footings.** To possess the required strength the MOMENT OF RESISTANCE of the footing must be at least equal to the MOMENT OF RUPTURE, calculated as explained in the preceding paragraphs. Mortar, whether of brickwork or stone, is not generally suitable for any but the lightest buildings, as its tensional strength is low. Concrete, plain or reinforced, or grillages of steel embedded in concrete, are generally employed. (See Chapter III for footings for light buildings.)

**Footings of Homogeneous Slabs.** If the footing is composed of HOMOGENEOUS MATERIAL, as a block of granite or other reliable building material or a single layer of concrete, the MOMENT OF RESISTANCE is, by the well-known flexure-formula for rectangular cross-sections,  $M_r = \frac{1}{6} b d^2 S$  (see Chapters XV and XVI) in which

$d$  = the depth or thickness of the footing, in inches;

$b$  = the breadth of the footing, in inches;

$S$  = the allowable unit tensile stress of the material, in pounds per square inch;

$M_r$  = the moment of resistance.

Placing  $M$ , the moment of the forces tending to cause rupture, equal to the moment of resistance for a length of wall equal to 1 foot we have

$$b = 12 \text{ in}$$

and

$$d^2 = \frac{1}{6} M/S$$

Substituting in Equation (4) the value for  $M$  in inch-pounds as determined by formulas (1), (2) and (3) and a value for  $S$  as given in the following paragraphs, the required depth  $d$  can be determined.

**Safe Tensional Strength for Materials in Footings.** The value of the ALLOWABLE UNIT TENSILE STRESS, for concrete or stone must include a FACTOR OF SAFETY, as experiments show wide variations in the tensional strength and in the MODULUS OF RUPTURE or FLEXURAL STRENGTH of such materials. The following values for  $S$  in pounds per square inch include a factor of safety of from 8 to 10 and should not be exceeded. (See, also, Table III, page 180, Chapter XVI.)

	<i>S</i> in lbs per sq in
brickwork or masonry in lime mortar.....	from 0 to 10
brickwork or masonry in cement mortar.....	from 10 to 40
concrete, 1 : 3 : 6.....	from 15 to 25
concrete, 1 : 2½ : 5.....	from 20 to 40
concrete, 1 : 2 : 4.....	from 30 to 50
sandstone or limestone in monolithic blocks....	from 75 to 150
granite in monolithic blocks.....	from 100 to 250

**Example of Concrete-Footing Design.** Concrete Cast as a Unit. A concrete footing 4 ft wide supports a wall 2 ft thick. The load on the foundation is 28 000 lb per lin ft of wall, or 7 000 lb per sq ft. Assuming a value for *S* of 15 lb per sq in, what is the required depth for the concrete footing course? The moment of rupture from one form of Equation (1)' is

$$M = \frac{3}{2} W (l - w), \quad \text{or} \quad \frac{3}{2} \times 28\,000 (4 - 2) = 84\,000 \text{ in-lb}$$

Putting in Equation (4)

$$d^2 = \frac{3}{2} \times 84\,000 / 35 = 1\,200, \quad \text{or} \quad d = 35 \text{ in}$$

Equation (2)' the moment of rupture is

$$M = \frac{3}{4} U P^2 = \frac{3}{4} \times 7\,000 \times 12 \times 12 = 42\,000 \text{ in-lb}$$

$$d^2 = \frac{3}{2} \times 42\,000 / 35 = 600, \quad \text{or} \quad d = 24 \text{ in} +$$

Depth determined by Equations (1) or (1)', as previously noted, errs on the side of safety. The result by Equations (2) or (2)' conforms more nearly with practice, and as the projection is small compared with the width of wall, it may be used, or an intermediate value, as determined by Equations (1)', may be considered amply safe.

**Stepped Footings.** If the concrete footing is cast in one uninterrupted form so as to act as a SINGLE GIRDER for its entire depth, a considerable saving of material may be effected by forming steps, as shown in Fig. 27. If the steps are of equal width, the total projection should be equally divided among the steps. If the footing is cast in several layers, or if a granite slab is superimposed on a bed of concrete then each layer must be figured separately and the width of the superimposed layer used in place of the width of the wall.

**Errors in Design of Footings of Several Layers.** Equation (2) should not be used where the footing consists of several layers, as the error from the erroneous assumption is cumulative and may result in a serious concentration on the outer edge of the upper layers.

**Design of Footings of Several Layers.** In the design of footings cast in separate layers the calculations should be made as follows: Let  $l_1$  = the length of the footing having a load  $M$ . From Equation (1), reduced to inch-pounds,

$$l_1 = \frac{2M}{3W} + w$$

If decided on the depth of each layer, say 15 in, and a value of *S*, say 15 lb per sq in, then, from the flexure-formula,  $M = M_r = \frac{1}{6} \times 12 \times 15^2$ .




Fig. 27. Concrete Stepped Wall-footing

$\times 35 = 15\,750$  in-lb, which, substituted in the above equation, will give the value of  $l_1$ , or the length of the top course. Having determined  $l_1$ , the length of the second course,  $l_2$ , is found in the same way, using  $l_1$  for  $w$ , and so on until the required width of the footing is reached. The dimensions  $l$  and  $w$  are taken in feet.

**Comparison of Unit and Separate-Layer Footings.** Footings of separate layers are very uneconomical in the amount of material required compared with those cast in one operation. If the footing in the example is designed on the separate-layer basis and the courses assume a thickness of 15 in thick, their lengths are as follows:

$$l_1 = \frac{2M}{3W} + w = [(2 \times 15\,750) / (3 \times 28\,000)] + 2 = 2.375 \text{ ft}$$

Also

$$l_2 = 2.75 \text{ ft}, \quad l_3 = 3.125 \text{ ft}, \quad l_4 = 3.50 \text{ ft} \quad \text{and} \quad l_5 = 3.875 \text{ ft}$$

As  $l_5$  is nearly 4 ft, the required length, it may be made so by increasing the thickness of the bottom course to 16 in. The total thickness of the footing is therefore  $(4 \times 15 \text{ in}) + 16 \text{ in} = 76 \text{ in}$  instead of 35 in, as previously determined by Equation (1) for the footing cast as a unit.




Fig. 28. Diagram Showing Ratio of Projection to Depth of Footings

**Rule-of-Thumb Methods for Projections and Steps in Footings.** Various ARBITRARY RULES are in use which purport to give for different methods of construction so-called SAFE PROJECTIONS for given depths of footing. These rules give the SAFE RATIO between the projection and the depth of a footing. These rules ignore the fact that the uplift varies and they are entirely unreliable, though such RULES-OF-THUMB are often incorporated in the building codes of cities. (See Chapter III, page 224.)

**Example.** The safe projection for offsets in brickwork is frequently given in building codes and in text-books as 3 in for a double course of brick

of about 5 inches, the corresponding ratio being 0.6. If we assume the  $S$  for brickwork at 20 lb per sq in, this offset will be safe when the uplift is less than 2 666 lb per sq ft, but not safe when the uplift is over 2 666 lb per sq ft.

**Ratio of Projection to Depth of Footing.** For footings of homogeneous material, however, having a small projection and where Formula (2) can be used, it is possible to calculate a so-called **SAFE RATIO OF PROJECTION** for a unit load. From Equation (2)' and Equation (4), derived from the **MOMENT OF RESISTANCE** for beams of homogeneous material and rectangular cross-section, the following formula may be derived:

$$p/d = \sqrt{48S/U} \quad (5)$$

in which all dimensions are in inches,  $S$  in pounds per square inch, and  $U$  in pounds per square foot. The quantity  $p/d$  is the ratio of the projection to the depth of the beam or footing. For a given value of  $S$  the ratio will vary inversely as the square root of  $U$ .

Diagram (Fig. 28) shows curves for different values of  $S$  and  $U$  from which the ratio of projection to depth of footing may be taken. Thus, for a concrete footing for which the allowable unit stress,  $S$ , in tension is, say 30 lb per sq in, and the load,  $U$ , on the foundation-bed is 3 000 lb per sq ft, the allowable projection will be 0.69 times the depth of the footing course. If the concrete is 8 in. thick, the allowable offset will be 8.3 in. Conversely, for a given offset, say 8 in, when the unit load is 3 000 lb and  $S = 30$  lb as before, the required depth will be 1.45 times the offset.

## 23. Steel Grillages in Foundations\*

**Advantages in the Use of Steel-Beam Grillages.** When it is desirable to avoid the deep excavation required for concrete or masonry footings, and the load of a wall has to be distributed over a wide area of support, **STEEL BEAMS** or **STEEL GRILLAGES** are frequently advantageously used to give the required **MOMENT OF RESISTANCE** with a minimum of depth. Steel beams are generally stronger and preferable to rails, although second-hand rails have frequently been used as an expedient.

**Preparing the Bed and Setting the Beams.** The foundation-bed should be covered with a layer of concrete not less than 6 in in thickness and so well compacted as to be as nearly impervious to moisture as possible. The beams should be placed on this layer, the upper surfaces brought to a line and the lower flanges carefully grouted so as to secure an even bearing. Subsequently, concrete should be placed between and around the beams so as to fully protect them.

**Requirements for Steel Grillages.** In determining the number and size of beams for any given footing the following points should be considered:

The beams must resist the **MAXIMUM BENDING MOMENT**, and this without **DEFLECTION**.

The beams must resist the **SHEARING-STRESSES**, the meeting of which is ordinarily provides against **CRUSHING**.

The beams must not be spaced so far apart that there is danger of the filling between the beams failing to **DISTRIBUTE THE LOAD**.

The beams must not be spaced so near together as to prevent the placing of concrete between them. The clear space between the flanges of the top layer preferably be not less than 2 in and should be somewhat more for the lower layers.

Pages 678 to 680 for an example of a continuous girder in grillage foundation.

(5) Where the **BENDING MOMENT** is the governing feature, of two equal weight, the deeper beam should be used. Thus, if the required **MODULUS** is 147, a 20-in 81.4-lb beam might be used; but a 24-in 79-lb is stiffer and stronger in bending.

(6) Where the **SHEAR** is the governing feature, of two beams of equal weight, the smaller beam is the stronger. Thus, the **SHEARING VALUE** of a 20-in beam is greater than that of a 24-in 80-lb beam and is nearly equivalent to a 24-in 90-lb beam. However, on account of the greater **STIFFNESS** of a deeper beam it is sometimes advisable to use it even though the cost is

**Spacing of Beams in Grillage.** Table IX gives the **LIMITING SPACING** of steel beams, based upon the safe capacity of the concrete filling a beam, for loads of from 1 to 6 tons per sq ft. Since, however, in spans there is considerable **ARCHING EFFECT**, the concrete will safely carry the load on larger spans than those given in the table, provided a number of tie-rods of proper size are used to take up the **THRUST** of the

**Table IX. The Limiting Spacing for Steel Beams Used With Concrete**

Depths of beams	Spacing of beams for the following pressures per square foot									
	1 ton		2 tons		3 tons		4 tons		5 tons	
	ft	in	ft	in	ft	in	ft	in	ft	in
6	1	3	0	11	0	10	0	9	0	8
7	1	6	1	1	0	11	0	10	0	9
8	1	8	1	3	1	1	0	11	0	10
9	1	11	1	5	1	2	1	0	0	11
10	2	1	1	6	1	4	1	2	1	1
12	2	5	1	10	1	6	1	4	1	3
15	3	0	2	3	1	10	1	8	1	6
18	3	8	2	8	2	3	1	11	1	9
20	4	0	2	11	2	5	2	2	1	11
24	4	9	3	6	2	11	2	7	2	4

**The Design of a Wall-Footing** of steel beams is illustrated by the following example: A 24-in wall carries 42 000 lb per lin ft. What should be the width and spacing of steel beams to distribute the load over the foundation so that the pressure is 3 600 lb per sq ft? The required width of the footing is  $42\,000/3\,600 = 11.67$  ft or 140 in and the bending moment by Equation (3) is 556 800 in-lb per lin ft of wall. The amount of shear, by the formula given on page 170, is  $S = W/2$  or 34 800 lb. As the beams are in double shear the single shear per lin ft of wall is 17 400 lb. The required section-modulus per linear foot of wall is obtained by dividing the bending moment by the allowed fiber-stress in steel, or  $556\,800/16\,000$  (assumed fiber-stress) = 34.8. By referring to Table I, page 355, giving the section-moduli of steel beams, we find that a 12-in 31.8-lb beam has a section-modulus of 36. To satisfy the condition of bending, the beams must not be spaced more than  $36/34.8 = 1.03$  ft, center to center. To satisfy the condition of web-crippling due to direct compression, the compressive stress must not exceed the value of  $S_b$ , Table II, page 57. For a 12-in 31.8-lb beam,  $S_b$  is 13 060 lb per sq in. The area of the beam in compression is the length over which the load is distributed, times the thickness. Some authorities consider that the load is distributed over



to the loaded portion of the beam plus one-half the depth of the beam, and in the following example the length of only the loaded portion is 1.03 ft. In this case the area is therefore  $24 \times 0.35 = 8.4$  sq in. If the beams are spaced 1.03 ft on centers the unit direct compression is  $42,000 \times 1.03/8.4 = 5,100$  lb, which is well within the allowed stress given by Table II, page 575. To check the condition of web-crippling due to shear, the shearing-stress must be compared with the value as derived from the formula for allowable shear. (See, Chapter XV, paragraphs and foot-notes relating to Buckling of Beam-Webs and the Illustrative Example 15 in that chapter.) The approximate, allowed, shearing value may be obtained by dividing the value of  $S_b$  (Table II, page 575) by the factor  $F$ , the values of which are given in Table IX A, page 182. For example, for a 12-in 31.8-lb beam this shearing value =  $13,060/1.65 = 7,915$  lb per sq in. The shearing capacity of the beam is obtained by multiplying this unit stress by the depth of beam times the web-thickness, or  $12 \times 0.35 = 33,240$  lb, or much more than required. Only one of the conditions of web-crippling need be considered by applying the following rule: If the shear divided by the depth of the beam is greater than the total load divided by the product of the distance (over which the load is distributed) by the factor  $F$ , investigate for shear; if otherwise, investigate for direct compression.

This rule may also be expressed as follows: According as  $(l - w)/l$  is greater or less than  $1/D/w'F$ , investigate for shear or for compression. Here  $l$  = length of beam,  $w$  = loaded portion of beam,  $D$  = depth of beam,  $w'$  = length of beam over which the load is assumed to be distributed (often taken =  $w + \frac{1}{2}D$ ) and  $F$  = factor for the given beam obtained from Table IX A. All dimensions must be taken in the same unit. If, instead of the 12-in beams, 15-in 42.9-lb beams having a section-modulus of 58.9 are used, the spacing will be  $58.9/34.8 = 1.69$  ft, or nearly, say 1 ft 8 in. By referring to Table IX, page 182, it is seen that the spacing of the beams is well within the safe limit of the concrete and no tie-rods are theoretically necessary. It is preferable, however, to use at least one tie-rod.

Table IX A. Values of Factor  $F^*$  for Shearing Values for Various Beams

Beams	For standard-weight beams	For heavy-weight beams
12-in beam	1.65	1.52
15-in beam	1.71	1.50
18-in beam	1.76	1.58
20-in beam	1.77	1.62
24-in beam	1.91	1.67

The factors,  $F$ , which have been deduced to be used in connection with  $S_b$ , Table II, page 575, to give the safe unit shearing value based on web-crippling, will help greatly in the design of shears in case tables of safe shears are not obtainable. It is to be noted, however, that the values derived from the use of  $F$  are approximate only, as this factor is a little different for every beam; and to give its value for every beam would require much space as complete tables of safe shears. The values of  $F$  are not given for the light sections of beams as they are not usually good sections for grillages. It is mentioned that the standard weight for each size of beam for which  $F$  is given is the next weight higher than the minimum weight given in Table II, pages 574-5, for the 20-in beams, for which the minimum weight, 65.4 lb, is also the standard weight.

The rule given above for determining whether web-crippling based on shear or direct compression is the determining condition eliminates one of the calculations to be made in investigating grillages.

**The Design of a Column-Footing** of steel beams is illustrated following example: A column carries 576 tons. The allowable pressure foundation-bed is 3 tons per sq ft. What should be the arrangement, and size of the steel beams composing the grillage? The required area  $\text{port} = 576/3 = 192 \text{ sq ft}$ . In order to make the problem as general as let it be supposed that practical considerations limit the width of the foot to 12 ft. The dimensions of the concrete mat on which the lower layer of rests will be 12 by 16 ft. By referring to the diagram (Fig. 28) we find the mat is made 12 in thick an offset of 6 in is permissible. The dimension of the lower layer of beams will therefore be 11 by 15 ft. A suitable grillage under the given conditions may be designed of two or of three layers. If two layers are used the length of the top beams will be 11 ft. Assuming the column diameter = 30 in, the loaded portion =  $2\frac{1}{2}$  ft, and by Formula (1), the bending moment  $M = \frac{1}{4} \times 1\,152\,000 \text{ lb} \times (11 - 2\frac{1}{2}) \times 12 \times \frac{1}{2} = 14\,688\,000 \text{ in-lb}$ , from which the required section-modulus (at 16 000-lb maximum fiber-stress) = 918. Referring to Table IV, Chapter X, five 24-in 90-lb beams have a section-modulus of 929 and consequently satisfy the condition of bending. By applying the rule given in the preceding paragraph for the design of a wall-footing, the condition of web-crippling due to shear or to compression is to be investigated,  $l/w = 11/30 = 0.773$  and  $2D/w'P = 0.958$ , which, being greater than 0.773, shows that the condition of web-crippling due to compression, by the rule explained in the previous example. It will be found that the five 24-in 90-lb beams also satisfy this condition and will therefore be used. Their width is about  $7\frac{1}{8}$  in, so they should be spaced about  $9\frac{1}{4}$  in on centers making the length of the column-base to be about 3 ft 9 in. The calculation for the lower layer is similar, the length of the beams being 15 ft and the loaded portion, 3 ft 9 in. It is rarely necessary to investigate the lower layer of beams for web-crippling, the condition of bending, except for the top layer, being usually the governing feature. If, owing to conditions of bending, it is not practical to make the beams of the top layer sufficiently long to extend across the full width of the concrete mat, it is then necessary to make the grillage of three layers. The calculation for a three-layer grillage for the same problem as the preceding is as follows:

**Calculation of the Top Layer.** For web-crippling due to compression  $1\,152\,000 \text{ lb} = S_b \times w' \times l \times n$ , where  $S_b$  = the allowable unit stress,  $w'$  = length of beam over which the load is assumed to be distributed,  $l$  = thickness and  $n$  = the number of beams. Referring to Table II, Chapter X, and assuming a 20-in 75-lb beam to be used,  $S_b = 13\,660 \text{ lb per sq in}$ ,  $w' = 0.641 \text{ in}$ . Taking  $w = 30 \text{ in}$  (the width of the column-base),  $13\,660 \times 0.641 = 262\,682 \text{ lb}$  and the value for five beams is  $1\,313\,410 \text{ lb}$ , which is less than enough. But it is found that five 20-in 70-lb beams would not be sufficient. It will be economical to make these beams of the greatest length for which they will resist bending. The section-modulus of one beam is 126.3; total  $M_r = 5 \times 126.3 \times 16\,000$  (assumed fiber-stress). This may be determined also, by Formula (1) in which  $M = \frac{1}{4} WP$ . From these equations the reaction  $P = 35\frac{1}{4} \text{ in}$ , and the length of the beams is therefore  $(2 \times 35\frac{1}{4}) + \text{width of the base} = 100\frac{1}{2} \text{ in}$ , or approximately 8 ft 4 in. By applying the foregoing rule to see if web-crippling due to shear must be considered  $(100 - 30)/100 = 0.7$  which is less than  $40/(30 \times 1.62) = 0.82$ , and the condition need not be investigated.

\* It is to be noted that the bending moment is the same as for a beam uniformly loaded with 576 tons on a span of  $8\frac{1}{2} \text{ ft}$ ,  $(l - w)$ , and that the number and size of the beams, as far as bending is concerned, may be taken from the tables giving the section-modulus of beams. See Table IV, Chapter XV.

width of the flanges of these beams is nearly  $6\frac{1}{4}$  in, so that they should extend from  $8\frac{1}{4}$  to 9 in, thus making the required length of column-base  $3\text{ ft } 6\text{ in}$ .

**Design of the Second Layer.** Since the length of the top layer is limited to 4 ft and the width of the lowest layer is 11 ft, it will be necessary to have a second layer. This

must cover the area given by the length of beams of the top layer and the width of the second layer, or 8 ft 4 in by 11 ft. The beams will of course be light-angles to those of the first layer, so their length will be 11 ft, and they are to be spaced as not to exceed 3 ft. Since the width of the second course is  $3\frac{1}{4}$  ft, their number  $n = (11\text{ ft} - 3\frac{1}{4}\text{ ft})/2\text{ ft} = 3$ , the amount of single angle  $1152000 \times 3.75/11 = 396000\text{ lb}$  and the bending stress  $R = 3/4 \times 1152000 \times 45 = 396000\text{ in-lb}$ . Using 15 in as the fiber-stress the required section-modulus is found by referring to Table Chapter X, for section-modulus and determining the number of beams as above explained, we find that ten 15-in beams will have a total section-modulus of 812, and will also be ample for shear.

Furthermore, ten 15-in beams spaced to cover a width of 11 ft will give a spacing, between center of beams, of 10 in, which is sufficient. It will be better, however, to use 18-in 54.7-lb beams. **Design of the Bottom Layer.** Taking the effective length of the middle layer as 8 ft, the projection of the bottom layer  $(15\text{ ft} - 8\text{ ft})/2 = 3\frac{1}{2}$  ft is similarly to the top layer = 368 800 lb.

2096 000 in-lb, from

section-modulus = 756, and thirteen 15-in 42.9-lb beams, spaced 10  $\frac{1}{4}$  in, will be required, or two 15-in 60.8-lb beams and ten 15-in 42.9-lb beams may be used, increasing the spacing between the beams. In this case the beams should be placed nearest to the center of the footing. This is illustrated in Fig. 29.




Fig. 29. Steel-beam Grillage Column-footing

## 24. Reinforced-Concrete Footings

**Advantages and Disadvantages.** Reinforced concrete has in recent years been largely used for footings. The arguments in favor of its use are:

- (1) Low cost of the footing-construction;
- (2) Reduction in the amount of excavation required,
- (3) Convenience, as compared with the use of steel-beam grillages, the reinforcing-steel is readily obtainable, can be cut to length on the work and handled without derricks.

The objections urged are:

- (1) Danger of defective workmanship, as the strength of the footing depends upon the proper mixing and placing of the concrete, the proper placing of the reinforcement and the complete union of the concrete with the reinforcement. The danger of defective workmanship is increased by reason of the usual conditions of foundation-work, in that water and mud are generally present and the difficulty of careful work and inspection is greater.

- (2) Danger of the deterioration of the steel reinforcement either by rusting or by electrolysis. This danger is increased by the presence of moisture and the relatively small cross-section of the reinforcing-bars. In this connection it is well to remember that in reinforced-concrete girders as usually constructed the concrete on the tension side is stressed beyond its elastic limit, as a result of which, numerous fine cracks are developed under the figured load.

**Use of Reinforced Concrete for Foundations.** From the foregoing it is apparent that great care should be used in connection with reinforced concrete in foundations, especially as any defect is difficult to detect or repair. Reinforced concrete is used not only for so-called MATS or SLABS but is frequently used for DISTRIBUTING-GIRDERS, BOLSTERS and even for CANTILEVER BEAMS. The author's preference is against reinforced concrete for foundations for important structures.

**The Methods Used in Calculating the Strength of Reinforced Concrete Slabs, Girders, etc.,** are explained in Chapters XXIV and XXV. The stresses coming on the reinforced-concrete construction are to be determined in the same way as explained for footings of other materials.

## 25. Timber Footings for Temporary Buildings

**Timber Footings.** For buildings of moderate height timber may be used to give the necessary spread to the footings, provided water is always kept out. The footings should be built by covering the bottom of the trench with planks which should be perfectly level, with 2-in planks laid close together and longitidinally with the wall. Across these planks heavy timbers should be laid, spaced at 12 in on centers, the size of the timbers being proportioned to the transverse stress. On top of these timbers again should be spiked a floor of 3-in planks of the same width as the masonry footings which are laid upon it. A cross-section of such a footing is shown in Fig. 30. All of the timber-work must be placed below low-water mark, and the space between the transverse timbers should be filled with sand, broken stone, or concrete. The best woods for such foundations are oak, long-leaf yellow pine and Norway pine. Many of the footings in Chicago rest on timber footings.

**Calculations for the Sizes of the Cross-Timbers.** The sizes of the transverse timbers should be computed by the following formula:

$$\text{Breadth in inches} = \frac{2 \times w \times p^2 \times s}{d^2 \times A},$$

giving the bearing resistance of the foundation-bed in pounds per square foot,  $p$  the projection of the transverse timbers beyond the 3-in planks, in feet,  $s$  the distance on centers of the timbers in feet, and  $d$  the assumed depth of the timbers in inches.  $A$  is the constant for strength.\* The values recommended for  $A$  for long-leaf yellow pine and white oak, 44 for Norway pine, and 39 for white pine or spruce, all increased from 30 to 40% for temporary buildings (see Table II, page 628.)

Fig. 30. Spread Footing of Timber

94. The side walls of a given building impose on the foundation a load of 20 000 lb per lin ft; the soil will only support, without excessive settlement, 2 000 lb per sq ft. It is decided for economy to build the footings as in Fig. 30, using long-leaf yellow-pine timber. What should be the size of the transverse timbers?

95. Dividing the total pressure per linear foot by 2 000 lb, we have the width of the footings. The masonry footing we will make of granite or hard stone, 4 ft wide, and solidly bedded on the planks in Portland cement mortar. The projection  $p$  of the transverse beams will then be 3 ft. Space the beams 12 in on centers, so that  $s = 1$ , and will assume 10 in depth of the beams. Then, by the formula,

$$\text{the breadth in inches} = \frac{2 \times 2000 \times 9 \times 1}{100 \times 90} = 4 \text{ in}$$

should use 4- by 10-in timbers, spaced 12 in on centers. If spruce timber were used we should substitute 55 for 90, and the result would be  $6\frac{1}{2}$  in. (See p. 628, for  $A$  increased from 30 to 40%.)

**Foundations for Temporary Buildings.** When temporary buildings are built on a compressible soil, the foundations may, in some parts of the world, be constructed more cheaply of timber than of any other material, and even the durability of the timber need not be considered, as when it is used for only two or three years in almost any place, if thorough ventilation is provided. The World's Fair buildings at Chicago (1893) were, as a rule, built on timber platforms, proportioned so that the maximum load on the platform did not exceed  $1\frac{1}{4}$  tons per sq ft. Only in a few places over MUD-HOLE foundations were used.

\*The values given to the term  $A$  of the formula vary in different building codes.

## 26. General Conditions Affecting Foundations and Footings

**General Considerations.** Where the footings of a building rest on sand or on clay, it is important that any movement of the material from the foundation-bed be prevented if possible. In many cases it is advisable to connect all footings with a concrete floor to prevent any UPLIFT of the foundation-bed between the footings. Where unequal settlement is apprehended, it is inadvisable to have long columns firmly attached to the footings, as any unequal settlement of the footings develops a BENDING-STRESS in the columns. In the case of long columns, bending-stresses may become extremely large, resulting possibly in the rupture or distortion of the columns. In such cases it has even been proposed to design the bases of the columns with BALL-AND-SOCKET joints which would allow unequal settlement of the footings without distortion or bending of the columns. Such connections, however, could not be used because of the necessity of bracing the structure against the horizontal pressure of the wind, but they would be entirely practicable in the case of interior columns.

**The Minimum Depth of Footings** is limited by the depth of the cellar, by the requirements of the cellar as to whether part of the footings can be above the cellar-floor level, and by the depth of the footing itself. The depth will be advantageously exceeded if, by a slight increase in depth, a footing capable of sustaining a higher unit load is found on which to rest the building, or if, as explained in previous articles of this chapter, greater security is obtained by locating the footing at a greater depth. These considerations will govern the design of a footing and in all cases should be taken into consideration. In some cases it may be cheaper to abandon the use of a SPREAD FOOTING and resort to PILES or MASONRY CONSTRUCTION going to ROCK or to some other solid substratum. Where there is any question on this point, careful comparison should be made of the advantages and costs of the two methods. In most cases, however, it will be cheaper to spread footings immediately below the excavation level than to employ any of the various deep-foundation methods.

**Deep Foundations** are necessary when the material at the level where SPREAD FOOTINGS would ordinarily be constructed is not suitable, or if it is desirable for any reason to carry the foundations of the building down to an underlying stratum of greater supporting power. Recourse must then be had to one or more of the following expedients:

- (1) Wooden piles;
- (2) Concrete piles;
- (3) Piers or walls constructed in pits or trenches, or by other methods going down to the required depth to reach a solid stratum.

## 27. Wooden-Pile Foundations

**The Use of Wooden Piles.** When it is required to build upon a soft or silt-laden soil that is constantly saturated with water and of considerable depth, the most practicable method of obtaining a solid and enduring foundation for buildings of moderate height is by driving wooden piles. Many buildings in the city of Boston, Mass., and several tall office-buildings of New York and Chicago, rest on wooden piles, and they are extensively used for bridges, buildings, grain-elevators, etc., erected along the water-front of coastal cities. The durability of wooden piles in ground constantly saturated with water is beyond question, as they have been found in a perfectly sound condition after the lapse of from six to seventeen centuries.

**Principal Requirements.** The laws of Boston require that wooden piles be capped with block-granite levelers or with Portland-cement concrete, but the spacing shall not exceed 3 ft between centers. The laws of Chicago require that wooden piles shall be driven to rock or hard-pan and capped with pile of timber, concrete, or steel, or a combination of these. The laws of New York specify a minimum diameter of 5 inches and a maximum spacing of 6 ft between centers.

**Maximum Loads Allowed on Wooden Piles** in various cities are as follows: Atlanta, 20 tons; Philadelphia, 20 tons; Buffalo, 25 tons; Minneapolis, 25 tons; Richmond, 25 tons; St. Louis, as many tons as the piles will safely carry; Chicago, 25 tons; Louisville, 20 tons; St. Paul, 25 tons; New York, 25 tons; Portland, Ore., 25 tons; Cleveland, 25 tons. Most of the above cities limit the allowed load by Wellington's formula which is hereinafter given under 193, under the heading, Bearing-Power of Piles.

**Selection of Wood Used for Piles.** Wooden piles are made from the trunks of trees and should be as straight as possible and not less than 5 in in diameter at small end for light buildings, or 8 in for heavy buildings. The woods commonly used for piles are spruce, hemlock, white pine, Norway pine, long-leaf yellow pine, pitch-pine, cypress, Douglas fir, and occasionally oak, white elm, black gum and basswood. There does not appear to be much difference in the woods as to their behavior under water, but the harder and stronger woods are preferred, especially where piles are to be driven to great depths and heavily loaded.

### Preparing Wooden Piles for Driving

The piles should be prepared for driving by cutting off all limbs close to the trunk and sawing the ends square. It is probably better to remove the bark, although piles are more often driven with bark on, and it is doubtful if bark makes much difference one way or the other. For piles in soft and silty soils, experience has shown that the piles drive better with a square head. When the penetration is slow, 6 in at each blow the pile should be prepared by putting on a RING, about 1 in in diameter than the head of the pile and from 2½ to 3 in thick. The head should be chamfered to fit the ring. When driven into compact soil, such as sand, gravel, or stiff clay, the point of the pile should be sharpened with iron or steel. The method shown at A, Fig. 31, is very well for all but very hard soils, and for these a CAST CONICAL POINT, 5 in in diameter, secured by a long DOWEL, with a RING around the end of the pile, as shown at B, makes the best shoe. Piles that are to be driven in or

Fig. 31. Points of Wooden Piles Prepared for Driving

exposed to salt water should be thoroughly impregnated with creosote, or coal-tar, or some mineral poison to protect them from the TEREDO WORM, which will completely honeycomb an ordinary pile in three or four years.

**Driving Wooden Piles with the Drop-Hammer.** The piles should be driven to an even bearing, which is determined by the PENETRATION of the last four or five blows of the hammer. The usual method of driving for the support of buildings is by a succession of blows given with a heavy cast iron or steel, called the HAMMER, which slides up and down between the uprights of a machine called a PILE-DRIVER. The machine is placed over the pile, so that the hammer descends fairly on its head, the piles always being driven with the small end down. The hammer is generally raised by steam and is dropped either automatically or by hand. The usual weight of hammers used for driving piles for building foundations is from 1 500 to 2 000 pounds and the fall varies from 5 to 20 ft, the last blows being given with a short fall. Occasionally, hammers weighing up to 4 000 pounds and over are used.

**Driving Wooden Piles with the Steam-Hammer.** Steam-hammers are to a considerable extent taking the place of the ordinary drop-hammers in large cities, as they will drive many more piles in a day, and with less waste to the piles. The steam-hammer delivers short, quick blows, from a few seconds to the minute, and seems to jar the piles down, the short intervals between the blows not giving time for the soil to settle around them.† In driving piles care should be taken to keep them plumb, and when the penetration becomes small, the fall should be reduced to about 5 ft, the blows being given in rapid succession. Whenever a pile refuses to sink under several blows reaching the average depth, it should be cut off and another pile driven beside it. When several piles have been driven to a depth of 20 ft or more and refuse to sink more than ½ in under five blows of a 1 200-pound hammer falling 10 ft, it is useless to try them further, as the additional blows only result in breaking and crushing the heads and points of the piles, and splitting and crushing intermediate portions to an unknown extent.

**Spacing Wooden Piles.** Piles should be spaced not less than 2 ft on centers, unless iron, wooden, or reinforced-concrete grouting is used. When long piles are driven closer than 2 ft on centers there is danger they may force each other up from their solid bed on the bearing surface. Driving the piles close together also breaks up the ground and diminishes the bearing power. When three rows of piles are used the most satisfactory spacing is 2 ft 6 in on centers across the trench and 3 ft on centers longitudinally, provided this number of piles will carry the weight of the building. If it will not, then the piles must be spaced closer together longitudinally, or more rows of piles driven; but in no case should the piles be less than 2 ft on centers, unless driven by means of a water-jet. The number of piles used in different portions of the building should be proportioned to the weight they are to support, so that each pile will receive very nearly the same load.

**Capping Wooden Piles.** The tops of the piles should invariably be cut off at or a little below low water-mark, otherwise they will soon commence decay. They should then be capped, either with large stone blocks, or with timber or steel grillage.

**Granite Capping.** Wooden piles are sometimes capped with blocks of granite. LEVELERS which rest directly on the tops of the piles. If the stone does not

\* See Table XI, page 204.

† The 5 000 piles, averaging 48 ft in net length, under the Chicago Post Office, were driven with a steam-hammer weighing 4 400 lb and delivering 60 blows per minute.



top of the pile, or a pile is a little low, it is wedged up with oak or stone. In capping with stone a section of the foundation should be laid out by drawings showing the arrangement of the capping stones. A single stone may rest on one, two, or three, but not on four piles, nor on three piles in a straight line, as in the two last-mentioned cases it is practically impossible to make the stones bear evenly. Fig. 32 shows the best arrangement of the capping for three rows of piles. Under dwellings and light buildings the piles are often driven in two rows, STAGGERED, in which case each stone should rest on three piles. When the piles are capped, large footing stones, laid in single pieces across the wall, should be set in cement mortar on the capping. Fig. 33 shows a partial piling-plan, with the arrangement of the capping stones, of the Boston Chamber of Commerce Building. It may be seen that most of the stones rest on three piles, and very few on two piles.

**Concrete Capping.** In many buildings a very common method of capping is to excavate to a depth of 1 ft below the tops of the piles and 1 ft wide of them and to fill the space thus excavated solid with Portland-cement concrete, laid in layers and well rammed. After the concrete is brought level with the tops of the piles, additional layers are deposited over the concrete until the concrete is to a depth of 18 in above the piles. On this foundation brick or stone footings are laid as on solid earth. If long bars of twisted steel, about  $\frac{3}{4}$  in in cross-section are embedded in the concrete about 3 in above the tops of the piles, the construction makes, in the opinion of the author, the best capping, the twisted bars giving great transverse strength to the concrete.

**Timber-Grillage Capping.** The pile foundations of many buildings have timber grillages bolted to the tops of the piles and stone or concrete footings laid on top of the grillages. The timbers for the grillages should be at least 12 in in cross-section, and should have sufficient transverse strength to carry the load from center to center of piles, using a low fiber-stress. They are laid longitudinally on top of the piles and fastened to them by means of bolts, which are plain bars of iron, either round or square in section, driven into holes about 20% smaller in section than the bolts themselves. For square bars 1 in in section are generally used, the holes being bored with an auger for the round bolts and by a  $\frac{3}{8}$ -in auger for the square bolts. The bolts should enter the piles at least 1 ft. If heavy stone or concrete footings are used and the space between the piles and timbers is filled with concrete level with the tops of the timbers, no more timbering is required; but if the footings are made of small stones and no concrete is used, a solid floor of cross-timbers, 12 in thick for heavy buildings, should be laid on top of the longitudinal timbers and drift-bolted to them. Where timber grillage is used it should, if possible, be kept entirely below the lowest recorded water-line, as otherwise it will rot and allow the building to settle. It has been proved conclusively, however, that any kind of sound timber will last practically forever if completely submerged in water.




Fig. 32. Stone Capping for Three Rows of Wooden Piles

The Advantages of Timber Grillage are that it is easily laid and effectively holds the tops of the piles in place. It also tends to distribute the pressure evenly over the piles, as the transverse strength of the timber will help to




Fig. 33. Piling-plan, Chamber of Commerce Building, Boston, Mass.

the load over a single pile, which for some reason may not have the same capacity as the others. Steel beams, embedded in concrete, are sometimes used to distribute the weight over piles, but some other form of construction generally be employed at less expense and with equally good results.\*

\* For a description of the pile foundations and capping of the Chicago Post Office, see Freitag's Architectural Engineering, pages 350 to 352.

**Instructions for Wooden-Pile Foundations.** This contractor is to furnish and drive the piles indicated on sheet No. 1.

The piles are to be of sound spruce (hemlock, long-leaf yellow pine) perfectly straight from end to end, trimmed close, and cut off square to the axis at both

ends. They are to be not less than 6 in in diameter at the small end, 10 in at the large end, when cut off, and of sufficient length to reach solid bottom, the necessary length of piles to be determined by driving test-piles in different parts of the foundation.

The piles are to be driven vertically, in the exact positions shown by the plan, and they do not move more than 5 in under the last five blows of a hammer weighing 2000 lb and falling 20 ft. All split or shattered piles are to be removed if possible and a good one driven in place of each imperfect one. In cases where such piles cannot be removed an additional pile is to be driven for each imperfect one. If the piles show a tendency to BROOM, they are to be reinforced with wrought-iron rings, 2½ in wide and ½ in thick.

The piles, when driven to the required depth, are to be sawed off square for a full bearing at the grade indicated on the drawings.

**Bearing Power of Piles.** In regard to their use for supporting buildings, piles may be divided into two classes: (1) Those which are driven to hard-pan, that is, firm GRAVEL or CLAY and (2) those which do not reach hard-pan.

A pile belonging to this class when driven through a soil that is sufficiently plastic to brace the pile at every point, may be computed to sustain a load equal to its resistance to crushing on the least cross-section. If the surrounding soil is not plastic the bearing power of the pile will be its safe load computed as a pile having a length equal to the length of the pile when capped. Test-piles driven on the site of the Chicago Public Library Building, through 27 ft of plastic clay, 23 ft of tough, compact clay and 2 ft into hard-pan, sustained a load of 50.7 tons per pile for two weeks without apparent settlement. In many instances where piles driven to the depth of 20 ft in hard clay sustain from 20 to 40 tons, and a few instances where they sustain up to 80 tons.

A pile belonging to this class depends for its bearing power upon the COHESION, COHESION and BUOYANCY of the soil into which it is driven. The safe load for such piles is usually determined by the average penetration of the pile under the last four or five blows of the hammer. Several engineers have formulated rules for determining the safe loads for piles of this class, but there are so many conditions that modify the amount of the penetration, and so many varying conditions of driving and of soil that it is considered impossible to formulate any rule that can be considered satisfactory for all the conditions under which such piles are driven.

**Engineering News Formula.** The formula generally used by engineers is given by M. A. Wellington, and is often referred to as the ENGINEERING NEWS FORMULA:

$$\text{The safe load in tons} = 2wh / (S + 1)$$

which

$w$  = the weight of the hammer in tons;

$h$  = the height of fall of the hammer in feet;

$S$  = the penetration in inches under the last blow or the average under the last five blows.

The loads are based on this formula the piles should be driven until the penetration does not exceed the limit assumed, or if this is found to be impracticable,

new calculations must be made based on the smallest average penetration that can be obtained, and a greater number of piles used. In localities where is commonly used for foundations, the least penetration that can be obtained within practical limits of length of pile can generally be ascertained by observation, or by consulting somebody who is experienced in driving piles. The the pile the less, as a rule, will be the final set or penetration. Where the experience to guide one it will be necessary to drive a few piles to determine the length of pile required, or the least set for a given length of pile. piles will have to be driven further than others to bring them to bear equal resistance. When the piles are to be loaded to more than 50% assumed safe load, the final set of each pile should be carefully measured by inspector, the BROOM and SPLINTERS being removed from the head of pile for the last blow.

**Safe Loads for Piles.** Table X, computed by the above formula, gives safe loads for different penetrations, under different falls of a hammer weighing 1 ton. FOR A HAMMER OF DIFFERENT WEIGHT multiply the safe load in tons by the actual weight of the hammer in tons. Thus, for a hammer weighing 1000 lb, the values in the table should be multiplied by  $\frac{1}{2}$  and for a 2000 lb hammer, by  $\frac{3}{4}$ .

**Table X. Safe Loads in Tons for Piles**  
For hammer weighing 1 ton

Penetration of pile in inches	Height of the fall of the hammer in feet											
	3	4	5	6	8	10	12	14	16	18	20	25
0.25	4.8	6.4	8.0	9.6	12.0	16.0	19.2	22.4	25.6	28.8	32.0	40.0
0.50	4.0	5.3	6.4	7.7	9.6	12.0	14.4	16.8	19.2	21.6	24.0	30.0
0.75	3.4	4.5	5.3	6.4	7.7	9.6	11.5	13.4	15.3	17.2	19.1	23.8
1.00	3.0	4.0	4.8	5.8	7.0	8.0	9.6	11.2	12.8	14.4	16.0	20.0
1.25	2.7	3.6	4.3	5.1	6.2	7.1	8.5	10.0	11.5	13.0	14.5	18.1
1.50	2.4	3.2	3.9	4.6	5.6	6.4	7.7	9.1	10.4	11.8	13.2	16.5
1.75	2.2	2.9	3.5	4.2	5.1	5.8	7.0	8.3	9.6	10.9	12.2	15.3
2.00	2.0	2.7	3.2	3.8	4.6	5.3	6.4	7.7	8.9	10.1	11.3	14.1
2.50	1.6	2.1	2.5	3.0	3.6	4.2	5.0	5.9	6.8	7.7	8.6	10.8
3.00	1.4	1.8	2.2	2.6	3.1	3.6	4.3	5.0	5.8	6.6	7.4	9.3
3.50	1.2	1.6	1.9	2.3	2.7	3.1	3.7	4.4	5.1	5.8	6.5	8.2
4.00	1.1	1.4	1.7	2.0	2.4	2.8	3.3	3.9	4.5	5.1	5.7	7.2
5.00	0.9	1.1	1.4	1.6	1.9	2.2	2.6	3.1	3.6	4.1	4.5	5.7
6.00	0.8	1.0	1.2	1.5	1.7	2.0	2.3	2.7	3.1	3.5	3.9	4.9

**Example of Computations for Pile Foundation.** Suppose that from observations of the pile-driving for an adjacent building it is found that piles driven from 20 to 30 ft take a set of 1 in under a 1200-lb hammer falling 20 ft and that additional blows result in about the same set.

From Table X we find that the safe load for a fall of 20 ft and a penetration of 1 in is 20 tons. Multiplying by the weight of the hammer in tons we have 12 tons as the safe load per pile. Suppose that the total load on the ft of footing is 13 tons. As we must have at least two rows of piles, each two piles will support 24 tons, it follows that the spacing of piles longitudinally should be  $24/13 = 1$  ft 10 in. As this is too close, we shall use three rows of piles, spaced 2 ft apart laterally, and the longitudinal

then be  $36/13 = 2$  ft 9 in. The width of the capping would be about 11 ft. If the load on the piles under the interior columns, for example, is 105.8 tons, divided by 12, the safe load for one pile, gives nine piles, or three rows of three piles each, which should be spaced 2 ft 6 in apart, each way.

**Actual Loads on Wooden Piles.** The following examples of the loads supported by piles, under well-known buildings, and of loads which have borne for a short time without settlement, should be of value when designing pile foundations.

**NEW YORK.** At the Southern Railroad Station three piles were loaded with 60 tons of pig iron, 20 tons per pile, without settlement. The allowed load was 10 tons per pile.

At 12 in in diameter at the butt and 6 in at the point, driven 31 ft into hard, blue clay near Haymarket Square, failed to show movement under 30 tons, ultimate load being probably 60 tons.\* Other piles driven 17.9 ft sustained loads of 31 tons each. The average penetration under the last ten blows of a 2 000-lb hammer falling from 9 to 12 ft varied from 0.4 to 0.95 in per blow for 10 piles.

At 25 ft long under the Chamber of Commerce Building penetrated about 15 ft under the last blow of a 2 000-lb hammer falling about 15 ft.

**CHICAGO.** In the Public Library Building the piles were proportioned to carry 50 tons each and were tested to 50.7 tons without settlement.

At the Schiller Building the estimated load was 55 tons per pile; the building settled from  $1\frac{1}{2}$  to  $2\frac{1}{4}$  in.

At the Passenger Station of the Northern Pacific Railroad, at Harrison Street, 30 ft long were designed to carry 25 tons each and did so without perceptible settlement.

At the Art Institute Building, parts of the Stock Exchange Building and also a number of warehouses and other buildings on the banks of the river are on piles.

**NEW YORK CITY.** The Ivins (Park Row) Building is supported by about 124 in spruce piles, arranged in clusters of fifty or sixty, for single columns, and a corresponding number under piers supporting two or more columns. The piles were driven to refusal of 1 in under a 20-ft fall of a 2 000-lb hammer. The material is fine, dense sand to a depth of over 90 ft. But few piles could be driven more than 15 or 20 ft. The average maximum load per pile is 9 tons.† The American Tract Society's Building is supported on piles.

**BROOKLYN.** Piles under the Government Graving Dock, driven 32 ft, on average, into fine sand mixed with fine mica and a little vegetable loam, are said to sustain from 10 to 15 tons each.

**NEW ORLEANS.** Piles driven from 25 to 40 ft into a soft alluvial soil carry from 15 to 25 tons, with a factor of safety of from 6 to 8.‡

**Cost of Driving Wooden Piles.**§ The cost of driving piles naturally varies with the character of the soil, and the conditions under which they are driven.

**NEW YORK CITY.** A 2 500-lb drop-hammer drove 4 piles per day of 10 hours. A steam-hammer, 13 piles per day were driven, for the same foundation. The piles were 70 ft long, 8 in in diam at the point and 15 in at the head. The average cost of driving 800 piles with the steam-hammer was \$2 each. In New York Harbor 1 800 piles were driven by a steam-hammer, from 24 to 26 ft into gravel and hard-pan, at a cost of 80 cts each.

See J. Howe, American Architect, June 11, 1898.

For description of this foundation, see the Engineering Record of July 23, 1898. See also M. Patton.

But prices are now (1920) considerably higher.

**CHICAGO.** Forty Norway-pine piles were driven by a firm of contractors 15 ft deep every ten hours at a cost, for driving, of 55 cts each. Another drove from 60 to 65 piles, each 45 ft long and 15 ft deep, into hard sand east at a cost of about 30 cts each. In both cases steam-hammers were used.

**BOSTON.** Spruce piles from 30 to 45 ft long cost from \$3 to \$5, in Long-leaf yellow pine piles, as long as 70 ft, cost about \$15 apiece for the themselves, and \$2 or more each for the driving. Oak piles from 40 to long cost from \$8 to \$10 each, in place.†

**Some Other References to Wooden Piles and Pile-Driving.** A valuable paper on "Some Instances of Piles and Pile-Driving, New and by Horace J. Howe, was published in the American Architect and Building commencing June 11, 1898. The paper records a great many tests and several formulas and many experiences of distinguished engineers. *Paper Building Construction and Superintendence*, by F. E. Kidder, gives additional information in regard to pile foundations and experiments on the bearing of piles. Much valuable information on piles is given in "A Practical Treatise on Foundations," by W. M. Patton. The recent *Engineers' Handbook* should be consulted for additional data.

## 28. Concrete-Pile Foundations

**Durability of Wooden and Concrete Piles.** Concrete piles, either or reinforced, possess many advantages over wooden piles and, in general, be used in all places where wooden piles can be driven. Concrete piles compared with wooden piles, have primarily the advantage of greater PERMANENCE. Timber piles, kept constantly wet and protected from the action of the water or other destructive influences, may be practically everlasting, but cannot be counted upon above water level; whereas concrete piles should be proof against all deteriorating actions, whether wet or dry, except the action of freezing wet concrete.

**Strength of Wooden and Concrete Piles.** Concrete piles without reinforcement, if made of good concrete, should have nearly the same CRUSHING STRENGTH per square inch as ordinary yellow-pine piles, and with properly placed reinforcement concrete piles should have a much higher crushing strength per square inch than timber piles. Moreover, timber piles do not have uniform CROSS-SECTIONS. For instance, a slender timber pile 40 ft in length 12 in in diameter at the butt, is probably not over 6 in in diameter at the top. In direct compression the load on a point-bearing pile of the above dimensions is limited to the safe load on the point of the pile, where it is 6 in in diameter and a cylindrical concrete pile, 12 in in diameter and under similar conditions will have a cross-section of 113 sq in at all points, compared with the cross-section of 28 sq in at the point of the timber pile. Moreover, if we consider both piles as LONG COLUMNS, it must be borne in mind that a timber pile must be straight and that it may, therefore, be subject to STRESSES and DEFORMATIONS due to ECCENTRIC LOADING, which are avoided in a straight, concrete pile.

**Reinforced-Concrete Piles.** In practice concrete piles are generally reinforced, and if a pile is to be considered as a long column the reinforcement must be increased at the center, so as to provide for stresses due to handling when its acting as a long column. The concrete piles may be formed circular above ground, in which case they may be straight or tapered, with square or other cross-sections. The reinforcement may consist of a number

\* American Architect, June 4, 1898, page 78.

† George B. Francis, in American Architect, July 23, 1898.

bars are generally disposed symmetrically around the axis of the pile. The bars should be connected by horizontal wiring or by spiral reinforcement. As stated, the reinforcement may be increased at the central section so as to provide against stresses due to the use of the pile as a LONG COLUMN, in which case the additional reinforcement should be placed near the periphery of the cross-section.

**Types of Concrete-Pile Reinforcement.** There are many TYPES OF REINFORCEMENT, one method even employing a woven-wire fabric which is laid out on a table and covered with a thin layer of concrete, the entire mat comprising wire fabric and the concrete being then rolled into a solid cylindrical form which, when set, forms the finished pile. The concrete piles may be FORMED IN PLACE by any one of several different methods.

**The Raymond System of Concrete Piling.** In this system of concrete piling a permanent form is provided for each pile. The Raymond system consists of a collapsible steel mandrel or core, tapering from 8 in in diameter at the point at the rate of 0.4 in per foot in length, until in a length of 37 ft the diameter equals 23.2 in. Upon this expanded mandrel or core is placed a spirally reinforced sheet-metal shell, the reinforcement of which is grooved into the metal on 3-in centers the entire length of the core or pile. This reinforcement imparts rigidity and stiffness to the shell, renders it capable of withstanding very severe soil-pressure and prevents admixture of foreign substances with the green concrete. The combined mandrel and shell is driven into the ground to a proper refusal; the mandrel is then collapsed and withdrawn from the shell, leaving the shell permanently in the ground; and the interior of the shell is then inspected, and when perfect from tip to top, is filled with concrete. Thus the pile is completed. The extreme taper of the shell, combined with the friction between the shell and the surrounding soil, increases the carrying capacity of the pile. The safe load on a Raymond pile varies from 15 to 30 tons.

**The Simplex Method of Forming Concrete Piles in Place.** THE SIMPLEX method differs from the Raymond method and may be briefly described as follows: A steel pipe, generally cylindrical in form, of the required size and diameter fitted with a detachable cast-iron conical DRIVING-POINT, is driven into the ground to the required depth; the pipe is then partially filled with concrete. A piston-like PLUNGER, smaller in diameter than the inside diameter of the pipe, is then placed on the concrete and the pipe is partially withdrawn, leaving the driving-point and part of the superimposed concrete in the ground. This operation is repeated until the pile is built up to the required height. In certain cases, instead of using a detachable driving-point, the driving-point consists of two jaws hinged to the lower end of the pipe, so arranged that while driving they form a driving-point, when the pipe is withdrawn they spread and form an extension of the cylindrical pipe. In other words, the jaws are made of steel plates previously bent to the same radius as the radius of the pipe and so hinged that when they are in their open-position the plates together with the jaws constitute an extension of the cylindrical surface of the pipe. It is evident that plain reinforcing-bars can be placed in position before concrete is poured into the pipe.

**Precautions for Concrete Piles Built in Place.** Care should be taken in designing and placing the reinforcing for all concrete piles BUILT IN PLACE, that the method of placing of the concrete does not throw the reinforcement out of position and that all voids between the reinforcement and the shell are completely filled.

**The Pedestal Pile** is designed to give an ENLARGED CROSS-SECTION at the base of the pile. The method is similar to that of the RAYMOND METHOD, the increase in diameter being obtained as follows: After the pipe has been driven, the driving-core is withdrawn and the pipe partially filled with concrete. Then the concrete in the pipe is rammed, forcing the concrete out of the pipe and pressing the material below the pipe, so that the concrete is forced into the soil. A repetition of this operation results in forming a BASE or MUSHROOM below the pipe larger in diameter than the diameter of the pipe. Finally the pipe is withdrawn, the filling and ramming-operations continuing meanwhile, until the pile is carried up to the required height.

**Composite Piles.** Protected piles, for use in localities where the water affects the life of timber piles under water, are composed of timber piles with concrete coatings held in position by steel reinforcements in the shape of expanded metal or wire netting. Such piles are to be considered as timber piles rather than as concrete piles.

**Timber Piles with Concrete Caps.** In some localities where the permanent water-level is considerably below the level of the required excavation, timber piles have been driven with a FOLLOWER, the follower consisting of a steel or cylindrical shell. When the head of the pile is driven to a safe distance below low water the PIPE-FOLLOWER is filled with concrete and withdrawn, leaving the concrete pier resting on a timber pile. This composite pile appears to possess the advantage of combining the cheapness of a timber pile below the water-level with the permanency of a concrete pile above the water-level. Great care, however, should be used in adopting this method on account of the difficulty of securing proper connection between the concrete and the wooden pile.

**The Methods used in Driving Built-up Piles** are practically the same as are used in driving wooden piles, except that a CUSHION of wood, rock or other material is placed on the head of the pile to be driven to cushion the blow of the hammer. Steam-driven or air-driven RECIPROCATING HAMMERS are preferable to the ordinary DROP-HAMMERS. In stiff materials the use of a WATER-JET is advisable and, in fact, in many cases indispensable. In lifting coffer piles use is made of a special SLING which is attached to a pile at two points, one point one-quarter of the length of the pile from the end. The sling should be attached to a SPREADER so that the stress due to the oblique pull of the CHAIN-SLING is taken up by the spreader rather than by the pile.

**The Casting of Concrete Piles.** Concrete piles should be CAST IN ONE PIECE by a continuous operation so that there will be no PLANE OF WEAKNESS formed between partially set concrete and fresh concrete. They may be cast either in a vertical position, in forms, or in a horizontal position. Square concrete piles have been cast in a horizontal position and side-forms, when used, the previously cast concrete pile, protected by paper, forming the bottom form. In some cases, where it is intended to use a WATER-JET in sinking the pile, the latter is cast around an iron pipe which is afterwards used for the water-jet. In general, however, this is dispensed with and an external detail pipe used for the water-jet.

**Incidental Advantages of Concrete Piles.** In many cases, where coffer piles are more expensive than timber piles, the saving in excavation and shoring more than offsets the increased cost. For example, if the excavation for the cellar of a building does not go down to water-level, the use of timber piles will necessitate excavating down to a point below water-level in order that the piles may be cut off low enough to keep their heads always wet. Con-



however, can be driven from the level of the bottom of the cellar-excavation, and this additional excavation and the necessary construction between excavation-level and the level of the cut-off for the timber piles thus avoided. However, as one concrete pile may have a SUPPORTING POWER equal to the supporting power of four wooden piles, the size of the footings will be much smaller with concrete piles than with wooden piles.

**Comparison of Wooden and Concrete Piles under Piers.** The footings for a column or pier 24 in sq in section, requiring for its support, say, sixteen wooden piles, spaced 2 ft 6 in from center to center, will be, allowing for slight variations in driving, approximately 10 ft square, the projections being 4 ft beyond the size of the base. Such a footing will ordinarily require a steel plate or reinforced-concrete base, or, if made of ordinary concrete, will be of considerable depth; whereas, if four concrete piles, placed 3 ft from center to center, are used, instead of wooden piles, the area of the base will be a little over 4 ft square and the projection will be only 1 ft. A suitable footing would consist of a reinforced-concrete cap not over 2 ft in thickness. The saving in cost of excavation, concrete and steel in the footing is all in favor of the use of concrete piles.

**Concrete Piles under Walls.** In the case of a continuous wall, where the load per linear foot of wall is not great, a single row of concrete piles is often sufficient to support the weight of the wall. In such cases, the piles should be placed in straight lines but should be STAGGERED, and a sufficient footing should be constructed connecting the heads of the piles, so as to afford stability to the wall.

**The Method Employed in Calculating Reinforcement for Concrete Piles** is the same as that employed in calculating ordinary reinforced-concrete beams, the only difference being that where a pile is not point-bearing, but is dependent on the surrounding material for its support, it need not be considered as LONG COLUMN. POINT-BEARING PILES deriving their support from some material on which their lower extremity rests, must be considered as LONG COLUMNS, on the assumption that the material surrounding the piles may fail and support them. In the case of FRICTION-PILES, depending for their support on the surrounding material, this assumption cannot be made, as any failure of the material will involve a settlement of the pile. It should be borne in mind that any structure supported on piles supported by SKIN-FRICTION is dependent for its stability upon the continued supporting power of the material surrounding the piles. In many cases buildings resting on piles driven into soft ground have settled as the result of the consolidation and settlement of the material surrounding the piles, notwithstanding the fact that the piles when driven were fully able to support the loads for which they were designed.

**Iron-Pipe Piles with Concrete or Reinforced-Concrete Filling** have been used in place of wooden or concrete piles, especially in UNDERPINNING-WORK. Objection to the use of such piles is that the iron pipe forming the external shell may rust, in which case the strength of the pile is reduced to the strength of the concrete filling and the reinforcement contained therein. The writer believes that they should not be used for permanent work.

**Loads Allowed on Concrete Piles.** The building laws of most cities allow on concrete piles from 350 to 500 lb per sq in on the concrete plus from 100 to 750 lb per sq in on the vertical reinforcement. On this statement it would appear possible to design a short concrete pile 12 in square, on which a loaded load would be 100 tons, and it is possible that such a pile, tested as a SHORT COLUMN, would develop in a testing-machine a strength justifying

the use of such construction; but, bearing in mind that the character of support for the base of such a column is underground and cannot be inspected and bearing in mind also the uncertainties attending the manufacture of pile, it is evident that it would be improper to load a pile to this extent in practice. It would, however, be considered good practice to load concrete piles up to one-third of a test-load applied to not less than 3% of the piles used. In ordinary practice, reinforced-concrete piles are loaded up to 500 lb per sq in of cross-section.

## 20. Foundation Piers and Foundation Walls

**Foundation Piers and Walls** as distinguished from ordinary CELLAR WALLS, extend from the level of the underside of the cellar-floor to rest on other solid foundation-bed. (See page 129, Subdivision 1, and also Chapter III, pages 228-9.) In general, such piers and walls are composed of concrete and are of such dimensions that the safe unit loads on the concrete for them are not exceeded. If the foundation-bed is rock, compact hard-packed gravel, there need be little or no enlargement of the base of the pier or wall; the safe unit loads on such natural foundation-beds are generally equal to the safe unit loads on the concrete forming the body of the pier or wall. The design of such piers and walls is therefore an entirely simple matter governed by the principles already outlined, and by certain considerations mentioned here.

**The Methods used in the Construction of Foundation Piers and Walls** are, however, necessarily varied to suit different materials and to different conditions encountered, and the design of a pier necessarily differs according to different methods of construction. For example, if the construction is executed by means of the ordinary SHEET-PILING METHOD, piers and walls will have in general rectangular outlines. But if the CHICAGO METHOD or the MATIC CAISSON is employed, it will generally be cheaper to use piers having a circular cross-section and the support for walls may be a succession of cylinders rather than continuous walls. The detailing of the concrete structure supporting the piers or walls is simple after a determination is made of the method by which the construction is to be put in place. This subject is discussed in the following chapter-subdivision, Methods of Excavating for Foundations.

## 20. Methods of Excavating for Foundations

**Simple and Complex Excavations.** Excavations in earth for footings, walls and piers may vary from simple trenches and pits of the required width and depths to accommodate the footings, up to deep subaqueous excavations requiring all the resources of engineering skill.

**The Sides of Excavations.** If the earth is firm and the depth not excessive, the sides of the excavation may be self-supporting, in which case the excavation may be made the neat size of the footing and the sides of the excavation take the place of forms for the concrete deposited to form the footing. If the excavation is deep, and especially where the earth is not firm, the sides of the excavation must be sloped or, if made vertical, must be supported by sheet-piling or by some form of sheet-piling. Where the excavation is over 8 ft in depth it will generally be cheaper to support the sides of the excavation than to slope them. Where the excavation adjoins a property-line it will generally be advisable to slope the excavation on account of damage to the adjoining property and in such cases it will be necessary to use sheeting, even if sloping the sides would be cheaper.

bracing in many cases will serve to support the sides of the excavation with the necessity of close SHEETING. The BRACING may consist simply of short pieces of PLANK placed against opposite sides of the excavation and held in place by horizontal timber STRUTS secured by WEDGES; or, especially in narrow trenches, some form of

EXTENSIBLE SEWER-BRACE may be used. Fig. 34 represents a usual form of EXTENSIBLE BRACE. Generally, however, the sides of an excavation will not stand with a vertical face, even if braced in this manner, for any length of time, and if the material is




Fig. 34. Extensible Brace for Narrow Excavations

hard or soft clay, such bracing is entirely inadequate. In such cases, in fact generally, some form of CONTINUOUS SHEET-PIILING must be employed.

**Ordinary Wooden Sheet-Piling** consists of a continuous line of vertical planks held against the sides of the excavation by horizontal timbers known as WALES, WALING OR BREAST-TIMBERS, these wales, or breast-timbers being in turn supported either by CROSS-BRACES extending across the excavation to an opposite wall or side of the excavation, or by inclined struts known as SHORES OR STAYS, extending to the bottom of the excavation where HEELS or inclined shores are sunk in the undisturbed material to afford points of support.

**Earth-Pressure on Sheet-Piling.** The load on the sheeting due to the EARTH-PRESSURE may be calculated on the assumptions made for the design of RETAINING-WALLS, but the thickness of the sheeting planks, the sizes and spacing of the breast-pieces and braces, if figured on this basis, will in general exceed the sizes constantly used with success and safety in such work. The probable reason for this is that an earth bank, when steadied and in part supported by the sheet-piling does not, for a considerable time, lose the COHESION between its particles and to most earth banks in their original and undisturbed state. Or, in other words, under these conditions no real ANGLE OF FRICTION is developed in the earth-mass. Local experience and practice should be consulted and will usually serve as a guide. Earth banks apparently similar will, however, act differently and no general rule can be given. It should be borne in mind that the earth composing a bank should be, as far as possible, protected from the action of water and from alternating freezing and thawing; and that permanent work should be completed as rapidly as possible so as to avoid the deteriorating effects of time and exposure on the structure of the

**The Thickness of the Sheeting Planks** required may be calculated on the assumption that the earth bank is composed of loose material having a definite PERCENTAGE OF SLOPE and COEFFICIENT OF FRICTION; but practically, under favorable conditions, 2-in planks may be used for a depth of drive of 16 ft, 3-in planks up to 24 ft and 4-in planks up to 32 ft; and timbers, 8 by 12 in, have been driven in loose material to a depth of over 40 ft.

**Wales and Numbers of Drives.** Ordinarily the depth to which a plank is driven is limited by its ability to resist the shock due to driving, and in loose material a plank may become shattered before it is driven to the required depths. If the required depth cannot be reached by the first planks, a second, and sometimes a third and fourth set of planks are employed. The BREAST-PIECES supporting the first line of planks must remain in place,

the planks in the second set or DRIVE have to be placed inside of the first pieces, thus reducing the size of the excavation by the amount of the necessary offset. Where more than one drive is required the first drive should be set at a sufficient distance outside to allow the planks forming the second and third drives to be placed outside of the required area for the bottom of the excavation.

**Cutting and Fitting Sheeting Planks.** The sheeting planks may be SQUARE-EDGED where there is no water or fine loose sand, but where water or running sand is to be excluded the planks should be TONGUED AND GROOVED, or SPLINED. The use of tongued and grooved planks has the additional advantage that the planks are more readily kept in line.

Fig. 35. Small Power-hammer  
for Driving Sheeting Planks

Fig. 36. Large-size Power-hammer  
and Sheeting Planks

It is usual to cut the bottom edge of each plank on a slight angle, so that in driving it is WEDGED against the preceding plank. The top of each plank may be fitted to receive an iron DRIVING-CAP; or, if this is not used, the upper corners of each plank should be cut off so that the effect of the blows will be concentrated along its vertical axis, and the tendency of the plank to SPLIT, due to a blow on one corner, thus diminished.

**The Means Employed for Driving the Sheeting** vary with the depth and the size of the sheeting. For small jobs and for moderate depth of drive, the primitive method of DRIVING BY HAND with ringed wooden mallets still prevails. For work involving a considerable amount of driving, and in cases for long drives, POWER-HAMMERS driven either by steam or compressed air are preferably employed. A small-sized power-hammer (Fig. 35) resembles a STEAM-DRILL and may be handled by two or three men without any special lifting

places. The larger sizes of power-hammers (Figs. 36 and 37) are practically all power, pile-driving hammers arranged with a special DRIVING-HEAD to the sheeting employed. Such hammers are handled by DERRICKS or are held in a frame similar to a pile-driver frame. Ordinary DROP-HAMMERS are sometimes used, but are not as advantageous as the RECIPROCATING POWER-HAMMERS, as the blow struck by the drop-hammer jars the plank, while the frequent light blows of the power-hammer tend to keep the planks and adjacent material in motion and accomplish the desired work with less damage to the sheet-piling. Weights and dimensions of several types of pile-driving hammers are given in Table XI, page 204.

**Manner of Driving Sheet-piling Piles.** In practice a shallow excavation is first made to the upper line for the outside of the sheeting planks. The top BREAST-TIMBER is temporarily secured in place and the lower end of the planks placed between this timber and the bank. If the planks are long, temporary TOP GUIDES or STAY-BRACES are used so as to keep the planks vertical until they have been driven well into the ground and held by the permanent BREAST-PIECES. The planks are then driven as the excavation progresses, each plank being driven a few inches in at a time. As the driving goes on the material under the lower edge of the planks is loosened with a shovel or with a crowbar, the operation being so directed that the planks are held true to line. The horizontal breast timbers and their braces are moved in position as the excavation progresses. Inclined braces are to be used the excavation in the center is taken out first, leaving a sloping bank just the sides of the excavation. This permits the placing of the inclined braces and of the planks for their points of support before there is any danger to the bank. After the first breast piece and its inclined brace are set in place, the second and subsequent breast-pieces and braces are put in place and the excavation proceeds.

#### Sheet-Piling for Excavations Below Water-level.

These excavations may be made by the SHEET-PILING METHOD if there is not too much water and if water can be pumped out of the material without inducing a flow of sand or clay below the bottom of the sheet-piling. In some cases, where unfavorable conditions exist, but where there is an underlying stratum of impervious material, it is possible to drive the sheeting in advance of the excavation, so that the bottom of the sheeting makes a tight joint with the impervious stratum, cutting off the water and material. Where a considerable amount of water finds its way into the excavation, the water must be led to a SUMP or depression from which it is ejected by means of a PUMP or a STEAM-SYPHON. Where the foundation is below water-level and the material is sand, clay, or other material that would be softened by the action of the water, it should be protected by the sump at a considerable distance from the area to be used for the sup-




Fig. 37. Large-size Power-hammer for Driving Sheet-piling Planks

Table XI. Weights and Dimensions of Pile-Driving Hammers

Size-No.	Total net weight lb	Weight of ram lb	Dimensions over all			Cylinder			Steam-boiler H. P. required	Comp. air, free air per min cu ft	Size of hose in	Distance be- tween jaws in	Width of jaws in	Duty, size of or piling ham- mer will drive
			Height in	Width in	Depth in	Diam. in	Stroke in	Strokes per min						
Warrington Steam Pile-Hammers Manufactured by Vulcan Iron Works, Chicago, Ill.														
0	16 000	7 500	180	....	....	16½	48	60	60	....	2½	26	9¼	Hvy concrete
1	9 850	5 000	144	....	....	13½	42	65	40	....	2	20	8¼	18" sq or rd p
2	6 500	3 000	138	....	....	10½	36	70	25	....	1½	19	7¼	14" sq or rd p
3	3 800	1 800	96	....	....	8	30	80	18	....	1¼	18	6¼	10" sq or rd p
4	1 350	550	84	....	....	4	24	80	8	....	1	14	4¼	4"X12" sheet
5	800	....	68	10	10	4	7½	300	10	....	1	....	....	3"X12" sheet
Cram Steam Pile-Hammers Manufactured by A. F. Bartlett & Co., Saginaw, Mich.														
B	8 400	5 500	144	....	....	....	40	70	25	....	2½	27	8¼	18" sq or rd p
C	5 500	3 090	144	....	....	....	40	70	18	....	2	20	8¼	14" sq or rd p
D	4 200	2 250	102	....	....	....	24	80	15	....	1¾	20	8¼	10" sq or rd p
E	1 000	430	78	....	....	....	12	80	15	....	1¼	12	5¼	4"X12" sheet
Union Pile-Hammers Manufactured by Union Iron Works, Hoboken, N. J.														
0	12 100	2 550	118	28	20	10½	24	100	50	750	2	28	8½	Hvy concrete
1	8 000	1 548	94	28	18	9½	21	110	30	600	1½	28	8½	18" sq or rd p
2	5 500	890	81	25	15	7¼	16	130	18	300	1¼	25	6½	14" sq or rd p
3	4 500	663	74	23	13	6¼	14	135	15	200	1¼	23	5½	10" sq or rd p
4	2 500	363	60	20	11	5¼	12	150	10	150	1	20	4½	6"X12" sheet
5	1 400	214	47	17	9	4¼	9	200	8	100	1	17	4½	4"X12" sheet
6	850	129	40	14	8	3¼	7	250	5	60	¾	14	3¾	2"X12" sheet
7	365	70	31	10	6	2¾	5	300	3	40	¾	10	3¾	1"X6" sheet
Goubert Steel-Pile Driving-Hammer Manufactured by A. A. Goubert, New York, N. Y.														
3	5 000	1 500	76	29	17	8	14	150	50	660	2	24	8¼	18" sq or rd p
2	3 400	800	62	24	14	6½	10	160	25	340	1½	22	6¼	12" sq or rd p
1	950	200	43	16	10½	4	8	200	10	150	1¼	....	....	4" sheeting
New Monarch Steam Pile-Hammer Manufactured by Henry J. McCoy Co., New York, N. Y.														
1	7 000	1 500	90	24	24	9	12½	125	35	600	2	24	8¼	18" sq or rd p
2	4 600	850	72	20	20	7¼	11	150	20	300	1½	20	8¼	14" sq or rd p
3	2 800	450	54	18	18	4¾	7	175	15	150	1	18	8¼	6"X12" sheet
4	800	125	48	14	14	3¼	6	250	10	65	¾	....	....	3"X12" sheet
McKiernan-Terry Pile-Hammers Manufactured by McKiernan-Terry Drill Co., New York, N. Y.														
9	7 500	1 500	77	21	27½	15	12	200	60	600	2	21	6½	18" sq or rd p
7	5 000	800	67	21	22½	12½	10	225	35	350	1½	21	6½	14" sq or rd p
5	1 500	200	56	11	14¾	7	8½	300	20	200	1¼	11	4¼	4"X12" sheet
3	640	68	54	9	9½	3¼	5¾	300	15	150	1	9	3½	3"X12" sheet
1	145	21	42	8	6½	2¼	3¾	500	10	100	¾	8	2¼	2"X10" sheet
Ingersoll-Rand Sheet Pile-Driver Manufactured by Ingersoll-Rand Co., New York, N. Y.														
G1	1 200	200	80	11¼	11	4	7¼	300	10	110	1¼	....	....	4"X12" sheet

of the footing. This may be accomplished by making the area to be sheeted excavated large enough to accommodate the sump outside of the support-area, or by sinking a separate excavation to be used exclusively as a sump; the same result may in some cases be accomplished by the use of DRIVE-PILES, driven to a point below the level of the footing in which continued pumping may reduce the level of the water to a point below the footing. Care should be taken, when the level for the footing is reached, to prevent the foundation-bed from being disturbed and softened by unnecessary tramping of workmen over the surface of the excavation.

The foundation-bed should be left as nearly as possible in its original or natural condition.

**Steel Sheet-piling** has been largely employed recently in place of wooden sheet-piling. It has the advantage that it can be driven in advance of the excavation, thereby reducing the likelihood of any flow of material under the sheeting. It also has the advantages of affording greater strength for a given thickness of piling, of being driven to a greater depth, and in many cases of being withdrawn and used over again. As generally manufactured, it has the further advantage of being INTERLOCKING, so that there is less danger of its getting out of the ground leaving openings between adjacent pieces.

All of these advantages have been considered by engineers in using steel sheet-piling instead of wooden sheeting.

**The Use of Steel Sheet-piling.** The fundamental idea of steel sheet-piling is not new, as CAST-IRON SHEET-PIILING was used in England as far back as 1822 and various combinations of steel plates have been used in coffer-dams. The general use of steel sheet-piling started in this country in 1899 when Luther P. Friestedt introduced the experimental INTERLOCKING CHANNEL-BAR SECTIONS. Since that time it has come into general use, and with its aid many excavations have been made which could not have been made with STEEL SHEET-PIILING which would have been impracticable with timber sheet-piling.

**Earth-Pressure on Steel Sheet-piling.** In using STEEL SHEETING, it should be borne in mind that the EARTH-PRESSURE coming on the steel sheeting is the same as the earth-pressure coming on timber sheeting, and the breast-pieces and braces should be as strong as in the case of timber sheeting. Certain forms of steel sheeting offer considerable resistance to bending due to the lateral earth-pressure. With such forms the horizontal breast-pieces may be spaced farther apart than with ordinary timber sheeting or steel sheeting not having this property; but the strength of the breast-pieces and of their braces must be sufficient to take up the entire load coming on the sheeting, irrespective of the spacing between such breast-pieces, for in case there is a failure in these the entire sheeting will fail.

**Different Forms of Steel Sheet-piling.** Various TYPES OF STEEL SHEETING are on the market. In making a selection between different forms of sheeting, the character of the material to be encountered should be borne in mind, as the thicker, more compact sections will penetrate hard or gravelly soils with less lateral deformation than the more complicated sections made up of thin plates and shapes. The various companies manufacturing different forms of sheet-piling publish catalogues containing data as to the weight and also giving the properties of the different sections. These catalogues may be obtained from the manufacturers, but for convenience illustrations of some of the principal types, with their dimensions and weights and other details, are given in the following pages.

There are other types of steel sheeting than those shown in Figs. 38 to 44.




Fig. 38. Lackawanna Steel Sheet-piling

Lackawanna Steel Sheet-Piling \*

Composition and Dimensions of Sections

Sections	Per linear foot, lb	Per square lb
Straight-web, 3/4 in thick .....	12.54	21.5
Straight-web, 3/8 in thick.....	37.187	35
Straight-web, 1/2 in thick.....	42.5	40
Arched-web, 14 in long.....	40.83	35
Arched-web, 15 in long.....	60	48

This piling is adapted to straight or circular work.

\* Manufactured by the Lackawanna Steel Company.






Fig. 39. United States Steel Sheet-piling

**United States Steel Sheet-Piling \***

**Composition and Dimensions of Sections**

Size	Web in	b in	h/2 in
12½ in, 38 lb.....	¾	12½	13¼
9 in, 16 lb.....	¼	9	9¼

This piling is adapted to straight or circular work.

\* Manufactured by the Carnegie Steel Company.




Fig. 40. Friestedt Interlocking Channel-bar Piling

**Friestedt Interlocking Channel-Bar Piling \***

**Composition and Dimensions of Sections**

No.	Description	Channels		Zees		h/2, in
		In	Lbs per ft	In	Lbs per ft	
1	10 in, 28 lb	10	15	3½ × ¾	4.8	9
2	10 in, 34 lb	10	20	3½ × ¾	4.8	9
3	12 in, 34 lb	12	20.5	3½ × ¾	8.6	10¾
4	12 in, 39 lb	12	25	3½ × ¾	8.6	10¾
5	15 in, 39 lb	15	33	4½ × ¾	9.2	13½
6	15 in, 45 lb	15	40	4½ × ¾	9.2	13½

\* Manufactured by the Carnegie Steel Company.




Fig. 41. Standard Sheet-piling

**Standard Sheet-Piling \***  
**Composition and Dimensions of Sections**

No.	Size, in	Weight per square foot, lb	A	B	C	D
1	12×5	35.0	12	3.94	5	0.2
2	12×5	36.25	12	3.97	5	0.3
3	15×6	37.20	15	4.75	6	0.2
4	15×6	39.75	15	4.81	6	0.4
5	15×6	42.25	15	4.87	6	0.5

An interlocking bar is wedged to each beam at the mill and the two pieces are as a unit.

\* Manufactured by the Jones & Laughlin Steel Company.




Fig. 42. Spring-lock Sheet-piling

**Spring-Lock Sheet-Piling \***  
**Composition and Dimensions of Sections**

Distance, A.....	15¼ in	19¼ in	23¼ in
¾-in plate, weight per square foot, in pounds.	17	14½	13
¼-in plate, weight per square foot, in pounds..	20	17	16

Plates may be obtained curved to any radius for circular work.

\* Manufactured by the Mitchell-Tappen Company.



Fig. 43. Slip-joint Sheet-piling

**Slip-Joint Steel Sheet-Piling \***  
**Composition and Dimensions of Sections**

Distance, A.....	6 in	9 in	12 in
No. 14-gauge, weight per square foot, in pounds.	5.4	5.8	5.7
No. 16-gauge, weight per square foot, in pounds.	4.3	4.0	3.9

\* Manufactured by the Mitchell-Tappen Company.




Fig. 44. Wemlinger Steel Sheet-piling

**Wemlinger Steel Sheet-Piling \***  
Composition and Dimensions of Sections

	1	2	3	4	5	6	7	8	9	10
Depth of corrugation.....	2	2	2	2½	2½	2½	2½	4	4	4
Thickness.....	⅜	⅝	⅝	⅝	⅝	⅝	⅝	⅝	⅝	⅝
Dist. center to center of lap.....	12	12	12	12	12	12	12	18	18	18
Weight per square foot in pounds...	5	7.5	8.5	8	9.5	11.5	13.5	15	19	23.5

\* Dimensions given are in inches.

\* Manufactured by the Wemlinger Steel Piling Company.

**The Poling-Board or Chicago Method** is a special method of excavation in general use in Chicago and in occasional use elsewhere for excavations which go to a great depth in clay or in other suitable material. It has the advantage over the ordinary sheet-piling method that the lining of the excavation is driven. The method is not generally used for trenches or for square excavations as a circular excavation is more readily handled. The success of the method depends entirely upon the character of the material to be encountered, the excavation is first made and the sides of the excavation afterwards lagged. The method in detail for a circular excavation for a pier-foundation may be described as follows:

1) A circular excavation slightly in excess of the size required for the pier is made down to a depth of 5 ft, great care being taken to have the sides of the excavation vertical and true to the circle.

2) Vertical planks called LAGGING-PIECES, 5 ft in length and slightly beveled at their edges so that each piece may be considered as a stave with radial joints depending to the size of the required circle, are set in place against the walls of the excavation. These planks are held in place by two or more steel rings, usually made in quadrants, so that they may be conveniently handled and put together. The planks are wedged firmly against the walls of the excavation by means of wooden wedges driven between the planks and the iron rings.

3) As soon as the first set of lagging is complete, the excavation is carried down for another section, 5 ft in depth, and another section of lagging is put in place and secured in the same manner.

**Depth and Character of Excavations in the Poling-Board Method.** In the method described above the excavation may be carried down for an indefinite depth, a depth of 100 ft having frequently been attained. In many cases the bottom of the excavation is BELLED OUT to a larger diameter than the excavation for the main shaft of the pier with the object of reducing the load of the foundation-bed to a unit load less than the safe unit load on the main shaft of the pier. This method is not adapted for running sand nor for clay that is not strong enough to stand with vertical sides during the necessary interval between the excavation and placing the lagging. In some cases where a stratum of hard sand has been encountered, the excavation has been carried past it

by the use of a cylindrical shell of steel, forced by jacks through it to an lying impervious layer of clay; but in general this method is dependent success upon a continuous body of impervious material.

**The Open-Caisson Method or Well-Curb Method** is used for pier carried to a considerable depth, and has advantages over the sheet-piling in certain materials. It is a development of the old method used in masonry wells and, in its modern form, consists of a structure which ever forms part of the pier itself and which is arranged with an open chamber base in which men may excavate the material under the structure and to settle as the excavation proceeds. It is evident that a central open shaft must be left in the structure to permit of the passage of men and m

**Details of the Open-Caisson Method.** In detail, the method may be described as follows: First a CURB or CUTTING-EDGE of timber or steel, following the line of the pier, is constructed on the surface of the ground. The outer edge of this curb is generally vertical and is protected with a steel plate which extends below the main section of the curb, so as to form a cutting-edge or downward projection serving to penetrate the soil slightly in advance of excavation. On this curb a wall of timber, concrete, or masonry is constructed inside of which the so-called WORKING-CHAMBER affords room for the workmen to be employed in excavating. Above the working-chamber the walls must continue to a height corresponding to the required height of the pier, leaving a central space to be filled in after the required depth is reached; or a roof may be built over the working-chamber and the entire cross-section of the pier filled with concrete or masonry excepting only a small central opening large enough to accommodate a HOISTING-TUB or BUCKET and to permit of the ingress and egress of the men employed in sinking the construction. In practice, the excavation is started before the pier-structure is carried up to its final height, after which the excavation and the building up of the pier progresses simultaneously, the constantly increasing weight of the structure aiding the sinking of the pier. When the excavation has reached rock or a firm substratum, further excavation is stopped and the working-chamber and the central opening are filled full of concrete, leaving finally a complete pier-structure extending from the rock to the proper level to receive the steel grillage or other construction resting on the pier.

**Advantages of the Open-Caisson Method.** This method of construction has the advantages that the workmen at all times are protected, that obstructions such as boulders or logs, may be removed from under the cutting-edge of the curb; that when rock is encountered, ample opportunity is afforded for the preparation of the rock-surface to receive the final concrete filling. If a considerable amount of water is encountered, not accompanied by a flow of material, it may generally be taken care of by means of pumps.

**Dredged Wells** are similar to the open caissons described in the preceding paragraphs and are used where large quantities of water are encountered. The construction of the piers is similar to that of the piers used in the open-caisson method; but the central shaft and working-chamber are designed to permit of the use of a CLAM-SHELL DREDGE or other form of dredge, and the water is allowed to rise to its natural level in the working-chamber and shaft. This method can be used to advantage when a considerable amount of water, sand or other material is found overlying level rock or other firm foundation bed. When the dredging and the sinking of the pier-structure have been completed down to the hard underlying strata it is sometimes possible to pump out the water. If this is not practicable the bottom may be prepared by divers or by the reception of the concrete filling, and the concrete may be deposited through

being taken to use some special arrangement to protect the concrete from injured by loss of its cement-content, in the process of deposition.

The **Well-Digger's Method** is also occasionally used in making **PIT-EXCAVATION** under walls or in cramped locations. By this method the sides of the excavation are supported by planks placed horizontally. The method of placing the planks is as follows: A shallow excavation, the depth of a plank, made by ordinary methods, and a **SET**, consisting of four planks fitting the sides of the excavation, is secured in place. Before proceeding with the excavation of the pit a trench is dug directly alongside and underneath the side planks of the **FIRST SET**. As soon as this trench is deep enough to accommodate the planks for the **SECOND SET**, the side of the trench under the plank already in place is cut to a vertical face, the plank placed in position and the earth temporarily back-filled against it. As soon as the four planks making the **SECOND SET** have been put in place by this method, the two side planks are wedged against the bank, the end-planks being used as struts. The planks are wedged into position and nailed or cleated to the side planks making a **PRESSURE-RESISTING FRAME** supporting the side of the excavation. Continuation of this method enables the excavation to be carried on indefinitely, provided there is no flow of water or run of material causing an inflow of material into the excavation.

The **Pneumatic-Caisson Method**. Where piers or foundation walls have to be carried to a considerable depth through water-bearing materials, and especially where large bodies of quicksand are encountered, the **PNEUMATIC-CAISSON** must be resorted to. This method is based upon the **PRINCIPLE OF A DIVING-BELL** and may be briefly described as follows: The construction of the caisson is similar to the piers previously described as used in the open-caisson and the well construction, except that the working-chamber and shaft are made airtight and connected with a device called an **AIR-LOCK**, so that compressed air can be introduced into the working-chamber. The object of the compressed air is to prevent water entering into the working-chamber. This is accomplished in accordance with the well-known **PRINCIPLE OF THE DIVING-BELL** by having the compressed air constantly kept at a pressure which will counterbalance the water-pressure at the level of the cutting-edge of the working-chamber. The pressure of the air evidently must vary with the depth of the cutting-edge below water-level. A column of water 1 in square in cross-section weighs  $.43\frac{1}{2}$  lb per sq ft, and it will therefore be counterbalanced by an air-pressure of  $.43\frac{1}{2}$  lb per sq in over the normal air-pressure. If the column of water is 30 ft in height, it will weigh thirty times  $.43\frac{1}{2}$  lb, or will be counterbalanced by an air-pressure of 13 lb per sq in above the atmospheric pressure.

The **Maximum Air-Pressure** in the **Pneumatic Caisson** in which men can work for short periods is about 43 lb per sq in above atmospheric pressure, corresponding to a depth below water-level of about 100 ft. At this depth the work is done in shifts of from two to three hours duration, and great care must be exercised in coming out of the **AIR-PRESSURE**. The physiological effects of compressed air are often serious; pains in the joints, damage to the ear-drums leading to deafness, and the so-called **CAISSON-DISEASE** render work at high pressure extremely hazardous.

The **Air-Lock Used in Connection with the Pneumatic Caisson** is a device for the purpose of retaining the air in the caisson and at the same time permitting the passage of men and material in and out. It consists essentially of a metallic **AIR-LOCK CHAMBER** or **SHELL** connected to the working-chamber either directly by an air-tight lining or extension of the central shaft-opening. This air-lock has two doors, one at the bottom, opening downward into the shaft

and the other in the upper head of the air-lock chamber, also opening upward and affording a direct connection to the open air. In the operation of the air-lock one of these two doors must at all times be closed so as to prevent free escape of air through the air-lock. If the bottom door is closed, it is held firmly to its seat by the uplift of the compressed air in the shaft, which is at all times in direct communication with the working-chamber. If, under these conditions, the upper door is open, the interior of the air-lock will be in communication with the open air and the air contained in the lock will eventually be at atmospheric pressure. Workmen and materials may then enter the air-lock. In order to pass into the shaft and working-chamber, it is necessary first, to close the upper door, and secondly, to shift the so-called EQUALIZING VALVE and admit compressed air into the space between the two doors. When the air-pressure is brought up to the air-pressure in the working-chamber and shaft. Pressure on the upper side of the lower door will then equal the pressure on the lower side and the lower door may be opened, the upper door being held against its seat by the compressed air in the air-lock. As soon as the lower door opens, the men and material may be passed into the shaft and working-chamber. In coming out the operations are reversed; men and material pass through the air-lock through the open lower door, the lower door is closed and held against its seat, and the equalizing valve is shifted, affording a connection between the interior of the air-lock and the external air. The compressed air escapes through the equalizing valve, reducing the pressure in the air-lock to atmospheric pressure, and the upper door has atmospheric pressure on both sides of it. It may then be opened, giving free connection with the outside.

**The Design of Pneumatic Caissons.** The first consideration is, of course, to have the final structure a permanent and sufficient pier to carry the load imposed upon it. To this end the cross-section of the pier at all points from top to bottom should be capable of carrying safely the maximum load. The cross-section of the pier is generally, in the finished pier, composed of solid concrete, the cross-section will be determined by the allowable load on the concrete. For piers the cross-section will generally be square or circular; for working-chambers the caisson will generally be not less than 6 ft in width, as it is difficult to construct caissons having a width less than 6 ft. If the caisson is to be carried through rock, the bearing on the rock need be no larger than the cross-section of the concrete pier; but if the excavation does not go to rock, it is frequently possible to BELL OUT the base of the pier so as to reduce the loading on the foundation bed to a unit load less than that allowable on concrete. The operation of BELLING OUT is difficult in some materials; in a compact material it can be generally accomplished without serious difficulty.

**Piers Sunk by the Pneumatic-Caisson Method** may be constructed of various combinations of materials. The side walls and roof of the working-chamber were formerly frequently constructed of timber. In many cases they are now formed of steel; but in recent designs the working-chamber is generally constructed of reinforced concrete, the only structural steel used being an angle or two and an angle composing the cutting-edge. The outside of the caisson is generally made vertical. The superimposed pier is generally of the same size as the working-chamber, at least it is generally so in piers sunk for buildings.

**A Typical Design for a Caisson Built of Reinforced Concrete** is given in Fig. 1, in which *AB* is the angle-iron and plate forming the so-called CUTTING-EDGE and *C* is the WORKING-CHAMBER formed by the side walls *DE* and *DF* and the roof *EE*. The concrete side walls are reinforced with steel rods attached to the cutting-edge, and extending upward into the body of the pier, and the body of the pier are reinforced to take care of stresses due to compression.

**Sinking.** In building up the working-chamber, the **INTERIOR FORMS** are put in to support the concrete which makes the roof. These are subsequently removed. The exterior forms may constitute a permanent part of the pier, in which case they are called a **CORRER-DAM**, or they may be removed as the concrete has sufficiently set. At the center of the pier an opening

is left to serve as the air opening connecting the working-chamber with the surface. The sides of this opening of the upper part of the pier, are lined with an **IRON STEEL SHELL**. To the lower end of the steel shell an air-lock is connected. The height of the pier does not exceed 40 ft the construction of it may be completed as the excavation is completed. Generally, however, the construction of the pier is not continued as soon as the working-chamber and from 5 to 10 ft of the superimposed pier is constructed; then the excavation is done, at the use of compressed air, to carry the cutting-edges to water-level. This is

**SINKING THE CAISSON** done so that the caisson does not have some slight lateral movement from the soil before construction is carried up enough to make it top-

heavy. When the entire pier of the first section is finished, the sinking is resumed and the structure is sunk as the sinking progresses, care being taken to remove any obstructions from beneath the cutting-edge. During the progress of sinking compressed air is conducted to the working-chamber through the **SUPPLY-PIPE G**, the excavated material being removed through the **SHAFT F**. The shaft **F** is fitted with a **LADDER** for the use of workmen.

**Method of Caisson-Sinking and Filling.** In sinking the caisson and superimposed pier, care must be taken to maintain it in a vertical position. This may be accomplished in large caissons by means of the excavation itself. On one side of the caisson is high the excavation on that side will be carried out in advance of the excavation on the low side, and the material under the cutting-edge of the high side will be removed while a bank of material is left for the cutting-edge of the low side. These methods, however, are of little avail when the caisson is narrow. In such cases that part of the caisson above ground is held in position by **GUIDES** or other devices; but it




Fig. 45. Typical Form of Reinforced-concrete Caisson

frequently happens that the caisson in its final condition is considerably out of its correct location and considerably out of plumb. In general, the size of the caisson should be made larger than the minimum size necessary in order to allow for errors in its final location. When the caisson has reached the required depth the foundation-bed is prepared for the reception of the filling and the working-chamber filled with it, care being taken that it fills all voids and is in perfect contact with the roof. Finally, the air-lifts and the steel lining of the shaft are removed and the shaft-opening filled with concrete to the proper level to receive the GRILLAGE or other construction at the base of the column which is to rest on the caisson.

**The Height of Caisson-Piers.** The height of a pier cannot be fixed until it is known to what depth the caisson must sink in order to reach the foundation-bed. If the rock is found at a greater depth than anticipated, an additional height is added to the top of the pier after the caisson is in its position; but if, on the other hand, the rock is found unexpectedly near the top of the pier will have to be cut off. If the finished elevation of the pier is to be below the level of the general excavation, it is usual to extend the surface of the pier to the required height by means of a temporary structure called a COFFER-DAM, the height of which corresponds to the difference between the finished surface below the level of the general excavation. Inside the COFFER-DAM some STEEL GRILLAGES may conveniently be set.

**The Freezing Process for Excavations.** This method has seldom been employed in making excavations. In this country its use has been limited to one or two mining-shafts, but in Germany it has been resorted to in making excavations for building-foundations. The method consists in driving pipes into the ground. These pipes are closed at the bottom and at the top, and are connected to smaller pipes through which brine, at an extremely low temperature, is made to circulate. The refrigerating effect results in freezing the water contained in the soil, converting quicksand to a frozen mass resembling soft sandstone. When the freezing has progressed sufficiently to form a wall or coffer-dam around the excavation, the material inside the frozen wall may be excavated. This method has the advantage, theoretically, of being applicable to excavations of any depth. There are many precautions necessary and for the present, at any rate, it should only be considered as a possible method.

### 31. Protection of Adjoining Structures

**General Considerations.** The COMMON LAW provides that any person making an excavation is responsible for resulting damage to adjoining structures. STATUTE LAWS as embodied in the building codes of different cities may modify or limit this responsibility, but in general, excavations should be made in a manner as to cause the least possible damage to surrounding property. Where there are no adjoining structures it is generally sufficient to slope the sides of the excavation so as to prevent the sliding of material into the excavation. At the least, to sheet-pile and brace the sides of the excavation; but where the excavation is to be made alongside of an existing structure, and carried below the footings of such structure, it is necessary to take special measures for its protection. Such work is described as SHORING, UNDERPINNING and PROTECTING ADJOINING STRUCTURES, and may involve the carrying of the weight of part of the buildings on temporary supports, the removal of the old footings, and the construction of new footings at lower elevations.

**Shoring.** When the excavation for the new building does not extend below the adjoining footings and when the material is fairly solid, it may be necessary to transfer a portion of the load of the wall to temporary footings. This



aided by means of heavy inclined posts called **SHORES**, arranged to act as **COLUMNS** or **STRUTS**. Each **SHORE** consists of a post, the lower end of which rests on a **PLATFORM**, generally consisting of planks and timbers laid so as to form a temporary spread footing. This platform should be of a depth which will insure that subsequent operations will not undermine it. The upper end of the post fits into a hole or niche cut into the wall to be supported. The post itself may be a timber with a square cross-section, 12 by 12 in. and of the required length. Provision is made, between the wall and the lower end of the post, for **WEDGES** or **JACKS**, so that when their lifting effect transfers part of the weight of the wall from its own footing to the temporary foundation or platform. During this operation all the members of the temporary structure are in compression and brought into bearing, and the material under the platform is compressed and solidified as much as possible.

**Use of Shores.** If the **SHORE** is to act preferably for **LIFTING** only, it is made nearly vertical as possible and is known as a **LIFTING SHORE**. If it is preferred to combine a horizontal **PUSHING** action with the lifting action, it is placed at a considerable angle from the vertical and is then known as a **PUSHING SHORE** or **STEADYING SHORE**. In arranging such shores care should be taken to have the niche cut close to a floor-level of the building to be supported, so otherwise the horizontal component of the thrust of the shores might pull the wall.

**Number and Sizes of Shores.** Where a wall is light, a number of smaller shores should be used in preference to a few large ones. Where a wall is high, many more shores of varying sizes may be used, and these should be placed in the vertical plane and rest on the same platform.

#### Wedges and Screw-Jacks.

In transferring the load of a wall from its own footing to the temporary platform, use is made of wooden or steel **WEDGES**, **SCREW-JACKS**, or **HYDRAULIC**



Standard Type of Steel Screw-Jack



Fig. 47. Standard Type of Steel Screw-Jack

or, wedges and jacks may be used in combination. Wooden wedges may be made of hard wood and are generally arranged in pairs, both being driven at the same time. The lifting effect of such wooden wedges is powerful, but where a considerable settlement of the temporary platform is anticipated, it is more convenient to use screw-jacks, as they prevent a considerable settlement.

**Details and Types of Screw-Jacks.** The **SCREW-JACKS** usually manufactured for this purpose are made of cast iron and have rough threads, with a steep pitch to have much lifting effect. Screw-jacks of a better kind are made of steel and have a machine-thread of small pitch. Such jacks can be used for lifting weights up to 100 tons. Figs. 46 and 47 represent

standard forms of screw-jacks. When a single screw-jack is used in connection with a post or shore, a hole to receive the threaded portion of the post is bored in the end of the timber used for the shore, the end being square to receive the nut. Such an arrangement is called a **PUMP** and is illustrated in Fig. 48. When a lifting effect greater than that exerted by a single jack is required, the jacks are arranged in pairs in connection with a short timber cross-



Fig. 48. Pump, or  
Screw-jack let into  
End of Shore




Fig. 49. Shore, Screw-jacks and Timber  
head

**HEAD.** Such an arrangement is illustrated in Fig. 49. It has the advantage that after operating the jacks, blocking and wedges can be placed between platform-timbers and the cross-head so that the post resting on the cross-head has a direct and solid bearing on the platform. By this method the load on the wall can be thrown on the platform by the jacks and after the blocking and wedging is in position the jacks can be removed.

**Hydraulic Jacks.** Where excessively heavy loads are to be lifted, **HYDRAULIC JACKS** may be used in place of screw-jacks but an objection to them is that they are liable to **SLACK BACK** under the load. While the load, therefore, should not be permanently supported on hydraulic jacks, they may be used to support the load temporarily while the blocking and wedging are being placed between the cross-head and the temporary footing. In this way an indefinite number of shores may be set and taken care of with a single pair of hydraulic jacks.

**Example of Shoring.** Fig. 50 shows the method used in shoring the interior front wall of a heavy building, advantage having been taken of numerous deep margin-drafts shown in the section. In order to avoid the expense of cutting niches for the tops of the shores, nine hardwood blocks, *a, a*, were fitted to the margin-draft grooves in the masonry. Nine similar blocks, *b, b*, etc., were gained into and bolted to the vertical timber. *V V*, spacers,




Fig. 50. Shoring an Ornamental Wall

the *a* blocks and the *b* blocks for adjusting wedges *w*, *w*, etc. Three shores, *T*<sub>1</sub>, *T*<sub>2</sub> and *T*<sub>3</sub> were keyed and bolted to *VV* and transmitted to it the pressure of the three shores, *S*<sub>1</sub>, *S*<sub>2</sub> and *S*<sub>3</sub>. Each shore had a 60-ton screw-jack at its base. Each shore is shown fitted with a pump or detached extension-rod for the screw-jack.

**Needling.** NEEDLES or GIRDERS are employed when part or all of the wall has to be carried, as when the old footing is to be removed wall UNDERPINNED or carried down to a new footing at a greater depth.

**Example of Needling and Underpinning.** Fig. 51 represents a typical UNDERPINNING, the several operations being as follows:

(1) The General Excavation is carried down to within a few inches of the bottom of the footing *BB* under the wall *W*.

(2) The Pit *DDDD*, properly braced and protected by sheet piling, to approximately the level of the proposed excavation, this pit being at a safe distance from the existing wall. In good material it may be




Fig. 51. Wall-needling and Underpinning

have this pit approach to within a few feet of the footing course of the wall in material which is liable to run it should not approach the wall closer than its depth. No hard and fast rule can be given, and in every case great care should be taken to prevent any movement of the material from under the existing footing.

(3) The Platforms. On the bottom of this pit-excavation, a PLATFORM is placed, generally composed of heavy timbers resting on a base of planks, and acting as a support for the outer end of the needle. During the construction of this pit a similar pit may be dug on the inside of the wall wide for the support of the inside end of the needle; but as this involves the destruction of the cellar-floor the method of procedure inside the building is generally different from this. If the material is solid it is sometimes sufficient to place the platform for the support of the inside end of the needle on the cellar-floor and at such a distance from the wall that the new excavation for the new footing will not disturb it; or the platform may be placed on the cellar-floor and a line of sheeting *LL*, properly braced, so that the excavation can be made for the new footing. This is generally sufficient to prevent any serious settlement of the temporary platform for the support of the needle.

**The Insertion of the Needles.** Having provided a support for each end of the wall it only remains to cut a hole through the wall, as at *A*, insert the needle *GG*, put the post and blocking *MN* under the outside end of the needle, and blocking and jacks under the inside end. The post *MN* may be fitted as shown at *K*, or with one or more screw-jacks. The needle *GG* must be made of one or more heavy timbers or one or more steel I beams. In any case the load to come on this needle should be figured and its strength made to safely support such load. As soon as the weight of the wall *W* is transferred to the needles and to the temporary platforms prepared to receive it, that part of the wall which is below the needles and all of the footing is removed and all of the excavation for the new footing made.

the footing is removed. The hanging parts of the wall may be removed pended by rods and chains to the needles. If they are not so suspended a crack will form along the line AAAAAA.

**Transferring the Load to the New Underpinning.** As soon as footing has been put in place and the new wall carried up ready to receive old wall, provision must be made for REVERSING THE OPERATION, that is, transferring the load onto the new underpinning wall and footing. This is generally done by means of a number of GRANITE BLOCKS set in pairs between the needles and fitted with STEEL WEDGES. After setting these blocks, the

in with brickwork mortar in the latter being compacted by means of PIECES OF SLAT in so as to wedge mortar between the bricks. This brickwork is laid up in Portland mortar so as to resist the time of setting.

As it is sufficiently wedged, the wedges are driven in as to throw at least a portion of the weight of the wall on the new wall. As a result of this the footing settles, the footing being restored to its original position. This necessitates continued driving of wedges until it has its final settlement. The settlement will be evidenced by the settling of the wall sufficiently to partially relieve the pressure in the needles and the fact that the wall remains tight.

#### **Removal of Needles, etc.**

As the entire weight of the wall has been transferred

**Fig. 53. The Figure-four Method of Needling**

to the footing and the footing has demonstrated that it is capable of supporting the weight of the wall without further settlement, all of the temporary work, including the needles, can be removed, the needle-holes bricked up, and the repairs made to the cellar of the adjoining building.

**The Figure-Four Method of Needling.** In certain cases it is impossible to employ a NEEDLE-BEAM projecting on both sides of the wall, as for example when the occupancy of the adjoining building is such as to make it impossible to have a needle-beam projecting into the cellar space. In such cases the FIGURE-FOUR NEEDLE has been employed (Fig. 53). In this method the needle AB acts as a CANTILEVER. Part of the load of the wall is carried

**Fig. 54. The Spring-needle Method of Underpinning**

When the needle-beam acts on both walls, but on account of its being nearer to the wall to be lifted, a large proportion of its effect is felt thereon.

**Beams or Cylinders for Underpinning** are frequently used for the support of walls and have many advantages, as they not only afford a support for the wall through the operations affecting the stability of the wall, but also form a permanent support. The operation in brief is as follows: A hole or niche is made in the wall and footing to be supported, of sufficient size to permit the introduction of a section of STEEL PIPE, in such manner that the center of the pipe is below the center of the wall to be supported, the height being sufficient to accommodate a section of pipe and also the means employed to drive it. The pipe may be driven (1) by HYDRAULIC JACKS or by SCREW-JACKS, placed on the top of the pipe and the wall itself, as by the patented BREUCHAUD method; (2) it may be driven by means of a POWER-HAMMER driven either by steam or compressed air; or (3) in some cases, where the material is fine sand or soft soil, the pipe may be JETTED or the JET-METHOD may be used in combination with jacks or power-hammers. In any case the first section of pipe is driven into the ground and additional sections are added until the lower end of the pipe encounters rock or some material possessing sufficient stability to insure a permanent support. The material entering the pipe is removed by a WATER-JET or by other means and the space filled with concrete. As soon as the concrete is set sufficiently the pipe is capped with a special casting on which short I-beams are arranged to distribute the support of the pipe over a considerable part of the base of the wall to be supported. These I-beams correspond

to the wedging blocks used in the ordinary methods before described. A provision is frequently made for **STEEL WEDGES** between the cap and the base of steel beam, but it is generally found sufficient to thoroughly grout in the space between the base of the wall and the steel beams after the niche itself has bricked up.

**Cylinders for Underpinning Very Heavy Walls.** The description in the preceding paragraph is intended to cover the use of pipes varying in size from 6 to 20-in in diameter, according to the load to be carried. In the case of especially heavy walls, **CAST-IRON CYLINDERS** are used in place of steel pipes. These cylinders are arranged in sections, each section making a water-tight joint with the preceding section, and are generally used where water is encountered where it is necessary to carry down the underpinning to rock at great depths. Under such conditions these cylinders are sunk by the **PNEUMATIC-CAMBRIDGE METHOD**. Such cylinders have been sunk to a depth of 70 ft below water and have been designed to carry as much as 400 tons.



## CHAPTER III

MASONRY WALLS. FOOTINGS FOR LIGHT BUILDINGS.\*  
CEMENTS AND CONCRETES

By

THOMAS NOLAN

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

## 1. Footings for Light Buildings

**footing Courses in General.**† Every foundation or bearing wall overlying any except solid rock should rest on a footing or base projecting beyond the wall on each side. On wet or very compressible soils these footings may be made of steel beams or of reinforced concrete, as described in Chapter II, but on reasonably firm soils and for buildings of moderate size and weight the footings are generally of concrete, stone, or brick. Footings answer two important purposes:

By distributing the weight of a structure over a larger area of bearing soil, the pressure per square foot on the foundation-bed is diminished and the tendency to vertical settlement correspondingly lessened.

By increasing the area of the base of a wall, footings add to its stability and furnish a protection against the danger of the work being thrown out of plumb by any forces that may act on it. Nearly every building law requires that every foundation wall or pier and every cellar or basement wall or pier have a footing at least 12 in wider, that is, 6 in on each side, than the thickness of the wall or pier, and this may be considered as the minimum projection, although in rare instances where there may be a special reason for making it less. On firm soils and for comparatively light buildings a projection of 6 in on each side of a wall will generally reduce the unit pressure, that is, the pressure per square foot, to the safe resistance of the soil, but it is always wise to proportion the footings to a uniform unit pressure, as explained in Chapter II, Subdivision 1. To have any useful effect, footings must be well bedded and have sufficient lateral strength to resist the upward reactions on the projections.

**Stone Footings for Walls with Ordinary Loads.** Stone cellar walls and basement walls generally have stone footings, although if the walls are heavily loaded a bottom footing of coarse concrete is advisable under the stone footing. If practicable, stone footings should consist of stones having a width equal to the thickness of the footing. If impracticable to obtain stones of this size, then two courses should be used, meeting under the middle line of the wall. In any event the footing course should extend inside of the course above, a distance equal to at least one and one-half times the projection, otherwise the stones will not properly transmit the loads and reactions and the footing courses will tend to separate at the joints, as in Fig. 1.

For a complete discussion of foundations in general and the mechanical principles involved in their strength and stability, for walls, piers, etc., below the basement or cellar, see Chapter II.

For a complete discussion of footing courses for heavy buildings and of the theories and stresses developed in offset, projecting, or cantilever footings, see Chapter II, especially Subdivisions 17 to 23.

Stone footings should be of hard, strong and durable stones, always their natural bed and solidly bedded in mortar. As a general rule, for buildings, and where the loads per unit of foundation-bed are much less than the allowable pressure, the thickness of the footing course is made about equal to its projection beyond the course above. The most common defect in large-stone footings is that the stones are not properly bedded, and it is more difficult to bed a large stone than a small one. The stones should be bedded in a thick bed of mortar and worked sideways with a bar until firmly settled in place.




Fig. 1. Stone Footing. Openings at Joints

For great strength of the stone, brick, or concrete, the footing will be as shown in Fig. 2. The proper offset for each course depends upon the vertical load, the transverse strength of the material, the resisting power of the foundation-bed and the thickness of the course.†

**Tables for Offsets for Masonry Footing Courses.**‡ As stated in Chapter II, in the discussion of the design of stepped footings, there are rule-of-thumb methods giving so-called safe projections for given depths of footings or giving the ratios between the projections and the depths of the courses. Tables of offsets for footing courses of different materials have been computed from the flexure-formula applied to the projecting footing courses considered as **CANTILEVER BEAMS** uniformly loaded by the upward pressures on the underside. Although these tables, so computed, are incorporated in some building codes, they cannot be safely used without numerous restrictions, exceptions and modifications, and hence they are, in general, unreliable and of use only as rough approximations. As these tables are still inserted in engineers' and architects' books, the table of offsets for masonry footing courses, in a revised form, is retained in this chapter with the recommendation that for footings of great importance it be used with caution and that for such footings the methods given in Chapter II be used when greater accuracy of results is required.




Fig. 2. Crack in Footing from Excessive Cantilever Action

**Notes Regarding Use of Table I.** The values in Table I are computed from the formula  $l = \frac{1}{6} d \sqrt{S_f / wf}$  which is derived from the **FLEXURE-FORMULA** for a uniformly loaded cantilever beam, and slightly changed to make  $w$  a numerical coefficient of the second member of the equation the value of which is unity. In this equation,  $l$  = the maximum allowed offset of the footing course in inches,  $d$  = the thickness of the footing course in inches,  $S_f$  = the modulus of

\* See Offset Footings, Chapter II, especially Subdivisions 17 and 22.

† See Chapter II, Subdivision 22, for a complete discussion of the principles in the design of projecting footings, ratio of projection to depth of footing, etc., for homogeneous slabs, separate-layer footings, etc.

‡ See Chapter II, Subdivision 22, page 180.

§ See, also, formula in Chapter II, Subdivision 22.

**Table I. Approximate Values of Offsets for Masonry Footing Courses in Terms of the Thickness of the Course**

The values are computed with a factor of safety of 10.

Material of the footings	$S_f$ in pounds per square inch	$w$ in tons per square foot		
		0.5	1.0	2.0
North River Bluestone (ordinary run).....	3 000	4.1	2.9	2.0
Limestone (average).....	1 850	3.2	2.2	1.6
Sandstone (average).....	1 375	2.8	2.0	1.4
Brickwork (good bricks in natural-cement mortar, 1:2, 60 days old).....	1 375	2.8	2.0	1.4
Brickwork (hard-burned bricks in Portland-cement mortar, 1:3, 60 days old).....	125	0.8	0.6	0.4
Concrete (Portland cement, 1:2:4, 1 month old).....	400	1.6	1.1	0.7
Concrete (Portland cement, 1:2:4, 6 months old).....	300	1.3	0.9	0.6
	400	1.6	1.1	0.7

the materials in pounds per square inch,  $w$  = the determined or assumed pressure on the bottom surface of the footing course considered, in tons of 2 000 per sq ft, and  $f$  = the factor of safety used. The table gives the values of  $l/d$  for three unit pressures  $w$ . For example, if  $w$  is taken at 2 tons per sq ft, then for limestone or sandstone footings  $l/d = 1.4$ , and if  $d$ , the thickness of the footing course, is 12 in, the offset or projection should be 16 or 17 in. The values given in the table for  $S_f$ , the modulus of rupture for the materials, differ slightly from those given in Subdivision 22 of Chapter II, in Table I of Chapter XV and in Table III of Chapter XVI. If results are required based upon different fiber-stresses, upon a different factor of safety, or upon different pressures per square foot, the formula may be used instead of the table. It should always be borne in mind that as each footing course transmits the entire weight of the wall and its load, the pressure will be greater per square foot on the upper courses, and that the offsets should be made proportionately less; that the values in Table I, when applied to stone-masonry footings, are only valid for the lower offset only, and then only when the footing is built in concrete of the thickness of which is equal to the thickness of the course, which is a projection of less than half their length, and which are well bedded in concrete mortar.

**Concrete Footings.\*** For buildings of great weight, except the very heaviest, especially for those built on a clay soil, concrete generally makes the best footing, and it is even preferable to and generally cheaper than large slabs of stone. When the concrete is properly made and used, it attains a strength equal to that of most stones, and under walls, being devoid of joints, it is like a continuous beam, having sufficient strength to span any soft spots that may be in the foundation-bed. When deposited in thin layers and well bedded, concrete becomes firmly bedded on the bottom of the trenches, so that there is no possible chance for settlement except that due to the compression of soil.

For an example of concrete-footing design, see Chapter II, Subdivision 22. For stone-and-concrete-footing design, see Chapter II, Subdivision 24. See, also, Chapter II, paragraphs relating to footings, pages 978 to 982.

**Preparing the Trenches.** For footings, concrete made with Port cement is preferable, and it should have a thickness of at least 8 in, even for light buildings; and for buildings of more than two stories, a thickness of at least 12 in. On firm soils, such as hard clay, the trenches should be accurately dug and trimmed to the exact width of the footings, so that the concrete will fill them. When the foundation-bed is of loose gravel or sand it is generally necessary to set up planks to confine the concrete and form the sides of the footings. These planks may be held in place by stakes; they should be kept in place until the concrete has become hard, which generally requires from two to four days, after which they may be pulled up and dirt filled in again with concrete. The proportions and manner of mixing concrete are described in the latter part of this chapter.

**Depositing the Concrete.** Concrete should be used as soon as mixed, and should always be deposited in layers, which as a rule should not exceed 6 in thickness, especially for the first layer. On small jobs where the work is done by hand the concrete is usually carried to the trenches in wheel-barrow and dumped into the trenches. The height from which the concrete is dumped, however, should not exceed 4 ft above the bottom of the trench, because when it falls from a greater height the heavy particles are apt to separate from the lighter ones. As soon as the concrete has been deposited in the trench it should be leveled off and then tamped with a wooden rammer weighing about 20 lb, until the water in the concrete is brought to the surface. Concrete should not be permitted to dry too quickly, and if twenty-four hours elapse between the deposits of the successive layers, the top of each layer should be sprinkled with water before the next is put in place. For buildings over five stories high, it is a good idea to place a stone footing course above the concrete footing, if suitable stone for the purpose can be obtained.

**Brick Footings.** Where the foundation walls are of bricks, the footings are usually brick or concrete. For interior walls on dry ground, and in




Fig. 3. Brick Footing. Wall One Brick Thick




Fig. 4. Brick Footing. Wall One and One-half Bricks Thick

localities for outside walls, brick footings are fully as good as stone footings, provided good, hard bricks are used and the footings are properly built. For footings should always start with a DOUBLE COURSE on the foundation-bed, and then be laid in single course for ordinary footings, the outside of the work should be laid all HEADERS, as in the accompanying illustrations, and no course should project more than one-fourth the length of a brick beyond the one above it, except in the case of an 8-in or 9-in wall. For brick footings under high or heavily loaded walls, each projecting course should be made double, the HEADER-COURSE on top and the STRETCHER-COURSE below. Figs. 3, 4, 5 and 6 show footings for

ing from one brick to three bricks in thickness. The bricks used for footings should be the hardest and soundest that can be obtained, should be laid in mortar and should be either grouted or thoroughly slushed up, so that the joint shall be entirely filled with mortar. The writer favors GROUTING

thick footings, that is, the use of a thin mortar to fill the joints, as he has always found that it gives very satisfactory results. The bottom course of the footing should always be in a bed of mortar spread at the bottom of the trench in the latter has been carefully leveled. All bricks laid in wet or dry weather should be thoroughly wet before laying, for, if dry, they rob the mortar of a large percentage of the mois-

ture it contains, greatly weakening the adhesion and strength of the mortar. Special attention should be given to the laying of the footing courses of bricks, as upon them the stability of the work largely depends. If the bottom courses are not solidly bedded, if any rents or voids are left in the joints of the masonry, or if the materials themselves are unsound or badly




Fig. 5. Brick Footing. Wall Two Bricks Thick

Fig. 6. Brick Footing. Wall Three Bricks Thick

together, defects in the superstructure are almost sure to show themselves sooner or later, and almost always at a period when remedial efforts are both and expensive.

**Inverted Arches.\*** In a few buildings in which the external walls are built into piers with wide openings between them, and in which the support of the soil is not more than 2 or 3 tons per sq ft, it was thought desirable to connect the bases of the piers by means of **INVERTED ARCHES**, for the purpose of distributing the weight of the piers over the whole length of the footings. Plans of inverted-arch footings are shown in Figs. 7 † and 8, † which represent exactly the construction employed in the Drexel Building in Philadelphia

as an example worked out in full, showing the method of proportioning inverted arches. See Chapter III, Building Construction and Superintendence, Part I, Masons' by F. E. Kidder.

See the Engineering Record, May, 1899, and Nov., 1899.

and the World Building in New York City. Unless the piers are about equally loaded, however, it is generally impossible to distribute the weight evenly if the arches extend to an angle of the building, the end-arch must be provided with ties of sufficient strength to resist the thrust of the arch, as others may push out the corner-pier. It is usually better to build the piers with wide footings, projecting equally on all sides of the pier, and each proportioned

Fig. 7. Inverted-arch Footing. Drexel Building, Philadelphia

Fig. 8. Inverted-arch Footing. Building, New York

to the load supported. The intermediate wall may be supported by steel or by arches. About the only advantage over ordinary masonry is in the resulting shallower foundations.

The following, relating to inverted arches, is taken from the New York building law: "If, in place of a continuous foundation wall, isolated piers are built to support the superstructure, where the nature of the ground or character of the building make it necessary, in the opinion of the Commissioner of Buildings having jurisdiction, inverted arches resting on a proper concrete, both designed to transmit with safety the superimposed loads, be turned between the piers. The thrust of the outer piers shall be taken by suitable wrought-iron or steel rods and plates." (Law of 1906.)

## 2. Cellar Walls and Basement Walls

**Definitions.** These terms are generally applied to walls which are below the surface of the ground or below the water-table or first-floor level which support the superstructure and which go down to the foundation properly so called. (See Chapter II, Divisions 1 and 29.) Walls whose office is to withhold a bank of earth, such as the walls around areas, are RETAINING-WALLS. (For retaining-walls, see Chapter IV.)

**Materials for Cellar and Basement Walls.** These walls may be built of brick, stone or concrete. BRICK is suitable only in very dry soils or for a wall with a cellar or basement on each side of it. PORTLAND-CEMENT CONCRETE is an excellent material for foundation walls, and is being more extensively used in their construction every year. The concrete may be filled in by wooden forms, which hold it in place until it has set, or concrete blocks may be used so as to form a solid wall may be used. If POURED CONCRETE is used the

will be removed as soon as the concrete has set and the walls should be watered once or twice a day, if the weather is dry, so that the concrete will not shrink too quickly. Good hard **LEDGE-STONE**, especially if it comes from the quarry beds, makes not only a strong wall but, if well built, one that will stand the effects of moisture and the pressure of the earth much better than a brick wall. Between a good stone wall and a wall of Portland-cement concrete, there is probably not much choice, except perhaps in the matter of expense, the relative cost of stonework and concrete varying in different localities. A wall made of soft stones, or stones that are very irregular in shape, with no flat surfaces, is greatly inferior to a concrete wall, or even to a wall of good hard bricks, and should be used only for dwellings or light buildings. Stone walls should never be less than 18 in thick, and should be well bonded, with full and three-quarter courses, and all spaces between the stones should be filled solid with mortar and broken stones or spalls. The **MORTAR** for stonework should be made of best and sharp and rather coarse sand. The outside walls of cellars and basements should be **PLASTERED** smooth on the outside with 1 : 2, or 1 : 1½ best mortar, from ½ to ¾ in thick. In heavy-clay soils it is a good idea to plaster the walls on the outside, making them from 6 in to 1 ft thicker at the bottom than at the top.

**Thickness of Cellar and Basement Walls.** This is usually governed by the thickness of the walls above, and also by the depth of the wall. Nearly all building codes require that the thickness of the cellar and basement wall, to the depth of 12 ft below the grade-line, shall be 4 in greater than the thickness of the wall above for bricks, and 8 in greater for stone, and that for every additional foot or part thereof in depth, the thickness shall be increased 4 in. In all large buildings the thickness of the walls of buildings is controlled by law. For buildings in which the thickness of the walls is not so governed, the following table will serve as a guide:

**Table II. Thickness of Cellar and Basement Walls**

Height of building	Dwellings, hotels, etc.		Warehouses	
	Brick, in	Stone, in	Brick, in	Stone, in
one stories.....	12 or 16	20	16	20
two stories.....	16	20	20	24
three stories.....	20	24	24	28
four stories.....	24	28	24	28
five stories.....	28	32	28	32

### 3. Walls of the Superstructure

**Brick and Stone Walls.** Very little is known regarding the **STABILITY** of walls of buildings beyond what has been gained by practical experience. The stresses in any horizontal sections of such walls, which can be determined with any accuracy, are the direct weight of the walls above and the pressure of the floors and roof. In most walls, however, there is a tendency to bulge out, to overcome which it is necessary to make them thicker than would be required to resist the **DIRECT CRUSHING STRESS**. The resistance to fire should also be taken into account in deciding upon the thickness of any given wall.

The strength of a wall depends also very much upon the quality of the masonry used and upon the way in which the wall is built. A wall bonded every course in height, and with every joint slushed full with good rich mortar, is as strong as a poorly built wall 4 in thicker. Walls laid with cement mortar are much stronger than those laid with lime mortar, and a brick wall built with bricks that have been well wet just before laying is very much stronger than one built with dry bricks.

**Thickness of External Walls.** In nearly all the larger cities of the country the minimum thickness of the walls is prescribed by law or ordinance, and these requirements are generally ample they are commonly adhered to by architects when designing brick buildings. Table III \* gives the thickness of walls required for **MERCANTILE BUILDINGS** in representative cities of different sections of the United States, and affords about as good a guide as one could have, because the values given, as a rule, represent the judgment of qualified and experienced persons. Walls for **DWELLINGS** are generally permitted to be 4 in less in thickness than for warehouses, although in some cities little or no distinction is made between business blocks and dwellings.

Table IV gives the thickness required for the brick walls of dwellings, apartments, hotels and office-buildings † in Chicago. The thickness given is the minimum that should be allowed for the walls of such buildings, unless special conditions exist. For modifications for different classes of buildings see the building code. In St. Louis the two upper stories of dwellings are required to be 13 in, the next two below, 18 in, the next two 22 in, and the next two 26 in thick.

In compiling Table III the top of the second floor was taken at 19 ft above the sidewalk, and the height of the other stories at 13 ft 4 in, including the thickness of the floor, as the New York and Boston laws and the laws of many other cities give the height of the walls in feet instead of in stories. Where the height of stories exceeds these measurements the thickness of the walls in some cases will have to be increased. The Chicago ordinance (1916) specifies "where 12-in walls are used, the story-heights shall not exceed 18 ft, where 16-in walls are used, the story-heights shall not exceed 24 ft, and where 20-in walls are used, the story-heights shall not exceed 30 ft."

**General Rule for Thickness of Walls.** Although there are great differences in the thickness given in Table III, more indeed than there should be, a general rule might be formulated from it, for **MERCANTILE BUILDINGS** of four stories in height, which would be somewhat as follows:

For bricks equal to those used in Boston or Chicago, make the thickness of the three upper stories 16 in, of the next three below 20 in, the next three 24 in, and the next three 28 in. For a poorer quality of material make only the three upper stories 16 in thick, the next three 20 in, and so on down. In buildings of more than five stories in height the top story may be 12 in thick.

In determining the thickness of walls the following general principles should be recognized:

(1) That walls of warehouses and mercantile buildings should be thicker than those used for living or office purposes.

\* Since this table was compiled, some provisions of some laws have been changed. The requirements relating to the thicknesses of walls vary but little from those given. As building laws of different cities are amended from time to time, architects and engineers must be guided by the code in force in the city in which a building is to be erected. This table represents the average requirements and is useful for comparative purposes. It is also a guide for those building outside of cities, or where no special building laws are in force.

† For other than steel skeleton construction.



Table III.\* Thickness in Inches of Walls for Mercantile Buildings and, Except in Chicago, for All Buildings Over Five Stories in Height

Height and location of building	Stories							
	1st	2d	3d	4th	5th	6th	7th	8th
<b>Two stories</b>								
Boston .....	16	12	.....	.....	.....	.....	.....	.....
New York .....	12	12	.....	.....	.....	.....	.....	.....
Chicago .....	12	12	.....	.....	.....	.....	.....	.....
Minneapolis .....	12	12	.....	.....	.....	.....	.....	.....
St. Louis .....	18	13	.....	.....	.....	.....	.....	.....
Denver .....	13	13	.....	.....	.....	.....	.....	.....
San Francisco .....	17	13	.....	.....	.....	.....	.....	.....
New Orleans .....	13	13	.....	.....	.....	.....	.....	.....
<b>Three stories</b>								
Boston .....	20	16	16	.....	.....	.....	.....	.....
New York .....	16	16	12	.....	.....	.....	.....	.....
Chicago .....	16	12	12	.....	.....	.....	.....	.....
Minneapolis .....	16	12	12	.....	.....	.....	.....	.....
St. Louis .....	18	18	13	.....	.....	.....	.....	.....
Denver .....	17	17	13	.....	.....	.....	.....	.....
San Francisco .....	17	17	13	.....	.....	.....	.....	.....
New Orleans .....	13	13	13	.....	.....	.....	.....	.....
<b>Four stories</b>								
Boston .....	20	16	16	16	.....	.....	.....	.....
New York .....	16	16	16	12	.....	.....	.....	.....
Chicago .....	20	16	16	12	.....	.....	.....	.....
Minneapolis .....	16	16	12	12	.....	.....	.....	.....
St. Louis .....	22	18	18	13	.....	.....	.....	.....
Denver .....	21	17	17	13	.....	.....	.....	.....
San Francisco .....	17	17	17	13	.....	.....	.....	.....
New Orleans .....	18	18	13	13	.....	.....	.....	.....
<b>Five stories</b>								
Boston .....	20	20	20	20	16	.....	.....	.....
New York .....	20	16	16	16	16	.....	.....	.....
Chicago .....	20	20	16	16	16	.....	.....	.....
Minneapolis .....	20	16	16	12	12	.....	.....	.....
St. Louis .....	22	22	18	18	13	.....	.....	.....
Denver .....	21	21	17	17	13	.....	.....	.....
San Francisco .....	21	17	17	17	13	.....	.....	.....
New Orleans .....	18	18	18	13	13	.....	.....	.....
<b>Six stories</b>								
Boston .....	24	20	20	20	20	16	.....	.....
New York .....	24	20	20	20	16	16	.....	.....
Chicago .....	20	20	20	16	16	16	.....	.....
Minneapolis .....	20	20	16	16	16	12	.....	.....
St. Louis .....	26	22	22	18	18	13	.....	.....
Denver .....	26	21	21	17	17	13	.....	.....
San Francisco .....	21	21	17	17	17	13	.....	.....
New Orleans .....	22	18	18	18	13	13	.....	.....
<b>Seven stories</b>								
Boston .....	24	20	20	20	20	20	16	.....
New York .....	28	24	24	20	20	16	16	.....
Chicago .....	20	20	20	20	16	16	16	.....
Minneapolis .....	20	20	20	16	16	16	12	.....
St. Louis .....	26	26	22	22	18	18	13	.....
Denver .....	26	21	21	21	17	17	17	.....
New Orleans .....	22	22	18	18	18	13	13	.....
<b>Eight stories</b>								
Boston .....	28	24	20	20	20	20	20	16
New York .....	32	28	24	24	20	20	16	16
Chicago .....	24	24	20	20	20	16	16	16
Minneapolis .....	24	20	20	20	16	16	16	12
St. Louis .....	30	26	26	22	22	18	18	13
Denver .....	30	26	21	21	21	17	17	17
New Orleans .....	22	22	22	18	18	18	13	13

\* See paragraphs and foot-note on page 230.

**Table III (Continued).\*** Thickness in Inches of Walls for Mercantile Buildings and, Except in Chicago, for all Buildings Over Five Stories in Height

Height and location of building		Stories										
		1st	2d	3d	4th	5th	6th	7th	8th	9th	10th	11th
Nine stories	Boston.....	28	24	24	20	20	20	20	20	16	.....	...
	New York.....	32	32	28	24	24	20	20	16	16	....	...
	Chicago.....	24	24	24	20	20	20	16	16	16	....	...
	Minneapolis...	24	24	20	20	20	16	16	16	12	....	...
	St. Louis.....	30	30	26	26	22	22	18	18	13	....	...
	Denver.....	30	26	26	21	21	21	17	17	17	....	...
Ten stories	Boston.....	28	28	24	24	20	20	20	20	20	16	...
	New York.....	36	32	32	28	24	24	20	20	16	16	...
	Chicago.....	28	28	24	24	24	20	20	20	16	16	...
	Minneapolis...	24	24	24	20	20	20	16	16	16	12	...
	St. Louis.....	34	30	30	26	26	22	22	18	18	13	...
	Denver.....	30	30	26	26	21	21	21	17	17	17	...
Eleven stories	Boston.....	36	32	32	28	28	24	20	20	20	20	16
	New York.....	36	36	32	28	28	24	24	20	20	16	16
	Chicago.....	28	28	24	24	24	20	20	20	16	16	16
	St. Louis.....	34	34	30	30	26	26	22	22	18	18	13
	Denver.....	30	30	26	26	26	21	21	21	17	17	17
Twelve stories	Boston.....	36	36	32	32	28	28	24	20	20	20	20
	New York.....	40	36	36	32	32	28	24	24	20	20	16
	Chicago.....	28	28	28	24	24	24	20	20	20	16	16
	St. Louis.....	34	34	34	30	30	26	26	22	22	18	18
	Denver.....	30	30	30	26	26	26	21	21	21	17	17

\* See footnote on page 230.

**Table IV.†** Thickness of Enclosing Walls for Residences, Tenement Hotels and Office-Buildings.‡ Chicago Building Ordinance (1916)

Number of stories	Base-ment	Stories										
		1st	2d	3d	4th	5th	6th	7th	8th	9th	10th	11th
Basement and ...												
One-story.....	12	12	...	...	...	...	...	...	...	...	...	...
Two-story.....	16	12	12	...	...	...	...	...	...	...	...	...
Three-story.....	16	16	12	12	...	...	...	...	...	...	...	...
Four-story.....	20	20	16	16	12	...	...	...	...	...	...	...
Five-story.....	24	20	20	16	16	16	...	...	...	...	...	...
Six-story.....	24	20	20	20	16	16	16	...	...	...	...	...
Seven-story.....	24	20	20	20	20	16	16	16	...	...	...	...
Eight-story.....	24	24	24	20	20	20	16	16	16	...	...	...
Nine-story.....	28	24	24	24	20	20	20	16	16	16	...	...
Ten-story.....	28	28	28	24	24	24	20	20	16	16	16	...
Eleven-story....	28	28	28	24	24	24	20	20	20	16	16	16
Twelve-story...	32	28	28	28	24	24	24	20	20	20	16	16

† These thicknesses are allowed when certain requirements are fulfilled in lengths of walls, heights of stories, etc. For these modifying restrictions and classifications of buildings in regard to their uses the building laws must be consulted. This table is inserted in this form as a useful general guide and as an illustration of average contemporary practice. For modifications for different classes of buildings see.

‡ For other than steel skeleton construction.

That high stories and clear spans exceeding 25 ft require thicker

That the length of a wall is a source of weakness, and that the thickness be increased 4 in for every 25 ft over 100 or 125 ft in length. In New the thicknesses given in the table must be increased for buildings exceeding 125 ft in depth on the lot. In Western cities the tables are compiled for houses 125 ft in depth, as that is the usual depth of lots in those

That walls with over 33% of openings should be increased in thickness.

That partition walls may be 4 in less in thickness than the outside walls over 60 ft long, but that no partition should be less than 8 in thick.

**Walls Faced with Ashlar.** "Bearing walls faced with ashlar shall be at least 8 in thick. Ashlar shall not be included in reckoning the thickness of walls but it is either at least 8 in thick or alternately 4 in and 8 in to allow at least a 4-in bond. Ashlar not having at least a 4-in bond in alternate courses must be secured to the backing by metal anchors, one to each block 3 ft or less long, and one to each block over 3 ft long." \*

**Brick Walls** should generally be 4 in thicker than required for brick

**Hollow Walls.** Hollow walls are undoubtedly desirable for dwellings, and they will be used for other buildings not more than four or five stories in height, on account of the security afforded from the weather. Owing to the fact that they are usually more expensive than solid walls and occupy more space, they are not very extensively used in this country.

The Boston building law requires that vaulted walls shall contain, exclusive of the air-space, the same amount of material as is required for solid walls, and the parts on the inside of the air-space in walls over two stories in height shall be at least 8 in thick, and the parts on either side shall be securely tied together with ties not more than 2 ft apart in each direction.

**Walls of Concrete Blocks.** Blocks made of Portland-cement concrete, and cast in molds, are frequently used for building walls and partitions that are relatively thin and bear light loads. Patents have been taken out on various forms of blocks and on machines or processes for making the same. Many buildings have been erected with walls built of these blocks. Most of the blocks are molded so as to form hollow walls. Block construction of this kind has an advantage over poured walls, in that the blocks are thoroughly cured before they are set and hence no provision is required for expansion or contraction. For the thin, light walls above mentioned the concrete-block construction is better adapted than solid concrete. The expense of forms is avoided and also the tendency to crack and to leave an unsatisfactory surface. Concrete blocks may be substituted for any ordinary stone or brick wall. Building laws usually require the thickness of walls of hollow concrete blocks to be not less than that required for brick walls. They should not be used in party walls. (See, also, Chapter XXIII, Subdivision 2.)

**Walls of Hollow Tiles.** Hollow tiles are used for the external walls of houses and sometimes for factories in some locations and under certain conditions. For example, the building laws (1913) of the District of Columbia require approved hollow tiles, not less than 12 in in thickness, to be used for the

\* Boston Building Law, in force in 1915.

external walls of dwellings located not less than 3 ft from the side or part of the lot. The Philadelphia laws do not allow the use of hollow tiles in external wall or heavy bearing partition. As far as fire-resistance is concerned, construction of hollow tiles is, of course, superior to wooden construction, but its use is increasing, the outside walls being usually covered with cement or although occasionally left with the finished texture of the tile surface. For this reason hollow tiles are prohibited by building ordinances for certain buildings because when heated and then suddenly cooled by water they are apt to crack from the sudden contraction. Recent conflagrations have shown that burned terra-cotta will crack and fall to pieces under severe heat alone. (See also, Chapter XXIII, Subdivision 2.)

**Party Walls.** There is much diversity in building regulations regarding the thickness of party walls, although they all agree in that such walls never be less than 12 in thick. About one-half of the laws require that party walls shall be of the same thickness as external walls; the remainder are equally divided between making the party walls 4 in thicker or thinner than the side walls for independent side walls. When the walls are proportioned by the rules previously given the author believes that the thickness of the party wall should be increased 4 in in each story. The floor-load on party walls is often twice that on side walls, and the necessity for thorough fire-protection is greater in the case of party walls than in other walls.

**Enclosing Walls for Steel, Skeleton Construction.** In building skeleton type the outer masonry walls are usually supported either in every story or every other story by the steel framework, and carry nothing but their own weight. Such walls may, therefore, be considered as only one story high, and are usually made only 12 in thick for the whole height of a twelve-story or fifteen-story building. For SKELETON CONSTRUCTION the Chicago ordinance allows ENCLOSING WALLS of 12-in thickness for all buildings. The former New York City code\* required the use of 12-in enclosing walls for the full height of the uppermost height thereof, or to the nearest tier of beams to that height, and 4 in additional thickness for every lower 60-ft section or to the nearest tier of beams to such vertical measurement, down to the tier of beams nearest to the curb-level. But, on account of the severity of some of the provisions as applied to very high buildings of skeleton construction, permission was frequently given by the Commissioners of Buildings, who were empowered to modify the building laws within certain limits, to reduce the thickness of certain walls for very high buildings, according to the peculiar circumstances of each case, without endangering the strength and safety of the building. A few of the earlier tall buildings were built with SELF-SUSTAINING WALLS starting from the foundation, while columns were introduced merely to support the floors and to give additional stiffness. "The World Building, New York City, erected in 1890, is an extreme example of high-building construction with self-sustaining walls. The main roof is 191 ft above the street, making thirteen main stories, above which is a dome containing six stories in all, a height of 275 ft above the street. The self-sustaining walls are of sandstone, brick and terra-cotta, the thickness increasing from 2 ft at the top to as much as 11 ft 4 in near the bottom, where the walls are offset to a footing 15 ft wide. The walls are vertical on the outside faces, the thickness being varied by inside offsets, so that the columns are recessed into the walls at the bottom, but emerge and are some distance clear of the walls at the top.

\* The revised Code, 1916-17, allows 12-in curtain walls in skeleton buildings of any height of building, when supported on girders in each story. This practice is followed by about fifty other cities.

† From Architectural Engineering, by J. K. Freitag.

#### 4. Natural Cements and Mortars\*

**Properties and Uses of Natural Cements.** The first hydraulic cements in this country were NATURAL CEMENTS, manufactured by the calcination of siliceous limestone containing sufficient silica, alumina and iron oxide to give hydraulic properties when the burned rock was pulverized and gauged with water. These natural cements were very widely manufactured and used in recent years, when they have been practically completely replaced by Portland cement. Natural cements vary in color from light yellow to dark brown according to the content of oxide of iron, and in distinction to Portland cements they are not uniform in their composition or behavior. The chemical composition and physical characteristics of various natural cements vary within wide limits, not only between cements manufactured in different mills, but between the products of the same mill at different times. Natural cements set more rapidly than Portland cements and are slower in developing strength. The production of natural cement in the United States for 1913 was 800 000 barrels, while during the same year the production of Portland cement was 12 000 000 barrels; from which it is seen that the natural-cement industry is nearly almost extinct. Natural cement may be used in massive masonry where weight rather than strength is the essential feature. It is used, also, for certain special purposes, such as in the manufacture of safes and in certain cases where a quick-setting cement is necessary. Where economy is the governing factor, a comparison may be made between the use of natural cement and a leaner mixture of Portland cement that will develop the same strength.

**Weight.** The specifications of the American Society for Testing Materials require that a bag of natural cement shall contain 94 lb, net, of cement, and that a barrel of natural cement shall contain three bags of this NET WEIGHT.

**Strength.** A natural-cement mortar, in order to comply with the requirements of the standard specifications of the American Society for Testing Materials, must show a TENSILE STRENGTH, for the neat cement, of at least 150 lb per sq in. when one week old, and 250 lb at the end of 28 days; or, when mixed with three parts of standard Ottawa sand, 50 lb at the end of one week, and 125 lb at the end of 28 days. The strength of 1 : 2 natural-cement mortar is about equal to that of 1 : 4 Portland-cement mortar.

**Proportions of Natural Cement and Sand for Mortar and Concrete.** For mortar for rubble-stone masonry and ordinary brickwork, one part of natural cement may be mixed with three parts of sand, by measure.

**Hydraulic Lime.** A product closely related to natural cement is HYDRAULIC LIME. This is manufactured in the same way as natural cement, but the rock contains sufficient lime to permit it to slake like quicklime. When the lime product is pulverized, it sets and hardens as an hydraulic cement. Hydraulic limes are largely manufactured in Europe, and especially in France and Belgium, but in the United States they have been manufactured only in a few localities. This is due to the fact that while rock of suitable composition may be found, the impurities are not uniformly distributed through it, but are found in layers or seams which prevent the material from being uniformly burned. The portion of the rock immediately adjacent to and including the seams of impurities overburns, frequently melting like a slag, while the purer portions consist simply of quicklime; and while the resulting mass slakes partly, the product when pulverized is unreliable as a cement.

\*Statistical data relating to Cements, Limes and Plasters were furnished the Editor by the Charles Warner Company of Wilmington, Del. For Limes and Plasters, see Part I, pp. 1548 to 1558.

**Grappier Cement** is a BY-PRODUCT produced during the calcination of **HYDRAULIC LIME**.

**La Farge Cement** is an imported NON-STAINING GRAPPIER CEMENT which develops nearly the same strength as the Portland cements.

### 5. Artificial Cements and Mortars

The Artificial Cements used in the United States include Portland and Puzzolan or slag cement.

**Portland Cement.** The principal artificial cement in this country is PORTLAND CEMENT. It is manufactured from two raw materials well ground to extreme fineness to secure an intimate mix before burning, is from this fact that it derives its name, ARTIFICIAL CEMENT. The raw materials must be so proportioned that in the finished cement, silica, alumina, oxide and lime will be present in a certain ratio which must be maintained within close limits. In the Lehigh Valley region of Pennsylvania, there are located some of the leading Portland-cement mills of the United States. The raw materials used are limestone and cement-rock. The cement-rock is a pure limestone carrying argillaceous or clay-matter. In order to bring the lime content up to the required percentage, it is usually found necessary in this region to add limestone. In other districts the raw materials used are cement stone and clay, limestone and shale, marl and clay and also blast-furnace slag and limestone. The product from the last-mentioned mixture should not be confused with the common slag cement or Puzzolan cement, as the slag is used as a raw material supplying silica, alumina, iron oxide and lime; and in the exception of the use of slag to furnish these ingredients, the process of manufacture and the properties are substantially the same as for the other Portland cements. The raw mix in a Portland cement mill is analyzed at least several times each hour to keep the composition of the cement within the required limits. The raw material, which is pulverized as fine as the finished cement, is burned in rotary kilns, the fuel used in most instances being powdered coal. From the kiln it issues in the form of CLINKER, the name given to the partially sintered product. After cooling, calcium sulphate in the form of gypsum is added to control the set and the product is pulverized and packed for shipment. The manufacture and properties of Portland cement have been made the subject of careful study by the American Society for Testing Materials and the American Society of Civil Engineers. The result of this study is embodied in the standard specifications of the American Society for Testing Materials, from which are given in the paragraphs following. These specifications furnish a reliable guide for the acceptance or rejection of any shipment of cement and have been very widely adopted by the leading architects and engineers of this country. These specifications do not stipulate that Portland cement must consist of any one particular composition, but in this respect confine the manufacturer to the limitation of the magnesia ( $MgO$ ) and anhydrous sulphuric acid ( $SO_3$ ) content. The reason for this is that with different raw materials it is found necessary to vary the composition of the cement to obtain the correct properties in the finished material. Different cements which satisfy the requirements of these standard specifications are generally considered satisfactory for use, although the composition of one may vary in some particulars from that of another. The CHEMICAL COMPOSITION of a good brand of Portland cement is about as follows: Lime, 62; silica, 23; alumina, 8; and iron oxide, 1; such as iron oxide, magnesia, and sulphuric acid, 7.

**STANDARD SPECIFICATIONS FOR PORTLAND CEMENT.\*** The following give the most important requirements for Portland cement:

\* From the Standard Specifications and Tests for Portland Cement, revised, 1917, effective, January 1, 1917, by the American Society for Testing Materials.

**DEFINITION.** Portland cement is the product obtained by finely pulverizing a mixture produced by calcining to incipient fusion an intimate and properly proportioned mixture of argillaceous and calcareous materials, with no additions subject to calcination excepting water and calcined or uncalcined gypsum. (2)

**PHYSICAL LIMITS.** The following limits shall not be exceeded:

Loss on ignition, per cent.,.....	4.00
Insoluble residue, per cent.....	0.85
Sulphuric anhydride (SO <sub>3</sub> ), per cent.....	2.00
Magnesia (MgO), per cent.....	5.00

**SPECIFIC GRAVITY.** The specific gravity of cement shall be not less than 3.07 for white Portland cement). Should the test of cement as received fall below this requirement a second test may be made upon an ignited sample. The specific-gravity test will not be made unless specifically ordered. (4)

**FINENESS.** Residue on a standard No. 200 sieve shall not exceed 22 per cent by weight.

**SOUNDNESS.** A pat of neat cement shall remain firm and hard, and show no signs of distortion, cracking, checking, or disintegration in the steam test for soundness.

**(6) TIME OF SETTING.** The cement shall not develop initial set in less than 45 minutes when the Vicat needle is used, or 60 minutes when the cone needle is used. Final set shall be attained within 10 hours. (7)

**TENSILE STRENGTH.** The average tensile strength in pounds per square inch of not less than three standard mortar briquettes composed of 1 part cement and 3 parts standard sand, by weight, shall be equal to or higher than the following:

Age at test, days	Storage of briquettes	Tensile strength, lb per sq in
7	1 day in moist air, 6 days in water.....	200
28	1 day in moist air, 27 days in water.....	300

**(8)** The average tensile strength of standard mortar at 28 days shall be higher than the strength at 7 days. (9)

**PACKAGES AND MARKING.** The cement shall be delivered in suitable bags or barrels with the brand and name of the manufacturer plainly marked thereon, unless shipped in bulk. A bag shall contain 94 lb net. A barrel shall contain 376 lb net. (10)

**STORAGE.** The cement shall be stored in such a manner as to permit easy access for proper inspection and identification of each shipment, and in a suitable weather-tight building which will protect the cement from dampness. (11)

**INSPECTION.** Every facility shall be provided the purchaser for careful sampling and inspection at either the mill or the site of the work, as may be specified by the purchaser. At least 10 days before the time of sampling shall be allowed for the completion of the 7-day test, and at least 31 days shall be allowed for the completion of the 28-day test. The cement shall be tested in accordance with the methods hereinafter prescribed. The 28-day test shall be waived only when specifically so ordered. (12)

**REJECTION.** The cement may be rejected if it fails to meet any of the requirements of these specifications.

Sections (13) to (15), also, relate to Rejection. (See complete Specification.)

**Pulverized or Slag Cements** are not used extensively and never in important structures. Their manufacture and properties may be briefly described as follows:

**Pulverized** basic slag is granulated by running it in a molten condition into water. This accomplishes two objects. The slag is broken up into fine particles and the sudden chilling enhances its hydraulic properties. These particles are then

mixed and ground with hydrated lime, in the proportion of from 15 to 25% hydrated lime and from 75 to 85% of granulated slag. Such cement, known as **SLAG CEMENT**, is slow-setting and slow-hardening, and does not develop as

much strength as natural or Portland cement. Slag cements are characterized by their light lilac color, their extreme fineness and their low specific gravity. They are considered unreliable for use except for foundation-work under ground where they are not exposed to air or running water.

**Stainless Cements.** Any ordinary Portland or natural cement will stain limestones, some porous marbles, some granites and some other light-colored stones. The best non-staining material is lime, that is, lime free from excess iron oxide. There are some Portland cements, however, which are called **STAINING CEMENTS**, and where care is used in their manufacture and they are free or comparatively free from iron oxide, they cause no trouble. As for the non-staining cements which have been extensively used for masonry, which staining would be objectionable, is La Farge Cement, before mentioned. It is made at Teil, France, is light-colored and contains a small percentage of iron and soluble salts. There are other non-staining cements on the market. For setting stones, and in order to **RETARD THE SETTING** of the cement until the stones are well bedded, 1 part by volume of lime-paste is usually mixed with 4 parts of the cement.

**Cost of Portland Cement.\*** Portland cement can now (1915) be purchased in this country at prices ranging from 90 cents to \$2.50 per barrel, free on board cars at the mills. The cost of the sacks and the freight are extra. The price for single barrels varies from about \$2.00 to \$2.50 per barrel. As a rule, the cost of cement in carload lots is about 85 cts per bbl at the mills. An extra charge of 10 cts per bbl for bags is made when the cement is delivered in paper bags. The extra charge is 40 cts, if delivered in cloth, but the mills refund 40 cts when the bags are returned in good condition. There is a charge of 10 cts when the cement is furnished in wooden barrels and no allowance is made for barrels returned. It is generally cheaper in the end to buy the cement in cloth bags and return the empty bags. For about 500 miles, the freight charges are about 40 cts per bbl of cement, making the total cost per bbl at this distance \$1.25, when purchased in cloth bags and when the 40 cts per bbl are refunded. Testing costs from 3 to 5 cts per bbl, or from \$5 to \$6 per carload. Unloading and storing near the station cost about 3 cts per bbl, and about 2 cts per bbl are usually added to the costs to allow for handling, returning empty sacks, and freight-charges for and damage to same. Total costs about 5 cts per bbl per mile. The total cost, therefore, according to these average costs, is about \$1.38 per bbl for the cement ready for use in mortar or concrete. (For Cost of Concrete, see page 249; also foot-note for same.)

**Water Required in Mixing Cement Mortar.** Good Portland cement requires relatively little water to make a good mortar. Neat cement will require from 20 to 22% (by weight) of water to produce the normal consistency. Quick-setting cement requiring more water than one that is slow-setting. If a greater quantity of water is required, it indicates the presence of an excess of free lime. When sand is mixed with cement, in the proportion of 3 to 1, more than from 9 to 12½% (by weight) of water will be required. Natural cements and slag cements require more water than do Portland cements. Too much water drowns the cement, retards the setting and weakens the mortar. Cements can also be weakened or even spoiled by a deficiency of water.

**Portland-Cement Mortar.** For first-class mortar not more than 3 bbl of sand should be added to 1 bbl of cement. For rubble stonework under ordinary conditions a mortar composed of 4 parts of sand to 1 of cement will answer the purpose, and be much stronger than lime mortar. For the top surface of foot-

\* See foot-note, page 249.



walks, from 1 to  $1\frac{1}{2}$  parts of sand may be mixed with 1 part of cement. Portland-cement mortar has about the same strength at the end of one year as 1 to 1 natural-cement mortar. Mortar made with fine sand requires a larger quantity of cement to obtain a given strength than mortar made with coarse sand. (See page 276 for ideal mortar with hydrated lime for brickwork.)

**Effects of Low Temperatures and Freezing on Cement Mortars.** The setting and hardening of cement mortar is greatly affected by the temperature, and the exposure and loading of new work often depends upon the prevailing temperature. The freezing of natural-cement mortars should be entirely avoided as it seriously injures them. Although freezing greatly retards the hardening of Portland-cement mortars and concretes, it does not appear to injure them. Thin coats of mortar, such as plaster, and troweled surfaces on which free moisture is formed should not be applied in freezing weather as they are apt to scale. In general, it is undesirable to work with mortar or concrete in freezing weather, as the difficulties of properly mixing and placing the materials are then increased; it must be admitted, however, that successful work with Portland-cement mortar and concrete has been done at temperatures considerably below freezing.

**The Effect of Salt in Mortar.** When salt is added to the water of mixing, the freezing-point is lowered, and, within certain limits, the freezing of mortar or concrete is prevented. The ultimate strength of mortar does not appear to be reduced when the amount of salt does not exceed 10%. Tetmajer gives the amount of salt required to lower the freezing-temperature as equal to 1 lb of the weight of the water per degree F. below 32°. The rule for the proportion of salt used in the works at Woolwich Arsenal, is said to have been as follows: "Dissolve 1 lb of rock-salt in 18 gal of water when the temperature is 32° F., and add 3 oz of salt for every three degrees of lower temperature."

**Effect of Hot Water and of Soda.** Hot water hastens the setting of natural-cement mortar, and 2 lb of carbonate of soda in 1 gal of water, boiled and mixed in mortar, hastens the setting and lessens the danger of freezing.

**Quantity of Mortar required for Masonry and Plastering.\*** "One bbl of Portland cement and 3 bbl of sand, thoroughly and properly mixed, will make  $3\frac{1}{4}$  bbl, or 12 cu ft of good strong mortar. This will be sufficient to lay  $1\frac{1}{2}$  cu yd of rough stone, or about 750 bricks, with from  $\frac{1}{4}$  to  $\frac{3}{8}$ -in joints, or cover 125 sq ft of surface, 1 in thick, or 250 sq ft,  $\frac{1}{2}$  in thick."

"One bbl of natural cement and 2 bbl of lime, mixed with about  $\frac{1}{2}$  bbl of sand, will make 8 cu ft of mortar, sufficient to lay 522 common bricks, with from  $\frac{1}{4}$  to  $\frac{3}{8}$ -in joints, or about 1 cu yd of rough rubble."

For the top coat of walks or floors, 1 bbl of Portland cement and 1 of sand will cover from 75 to 80 sq ft,  $\frac{1}{2}$  in thick, or from 50 to 56 sq ft,  $\frac{3}{4}$  in thick. One bbl of Portland cement and  $1\frac{1}{4}$  bbl of sand will cover from 110 to 120 sq ft of floor,  $\frac{1}{2}$  in thick, or from 75 to 80 sq ft,  $\frac{3}{4}$  in thick.

**The Mixing of Mortar.** Mortar may be mixed by hand or by mechanical means, the latter being preferable for the mixing of large quantities. When mixing is by hand, it should be done on platforms made water-tight to prevent the loss of cement. The cement and sand should be mixed dry in small batches and in the proportions required, the platform being clean. Water is added and the whole mass remixed until it is homogeneous and leaves the mixing platform clean when drawn out. Mortar should never be retempered after it has begun to set.

\*These figures can be considered as approximate only, as the amount of mortar will vary on different jobs.

**Adhesive Strength of Portland Cement, Sulphur and Lead for Anchoring Bolts.\*** "Fourteen holes were drilled in a ledge of solid limestone, 10 in wide, 18 in long and 12 in thick, two of them having 1¼-in holes, and of them 2¾-in holes drilled in them. Into the small holes 1-in bolts were cemented, one of them being perfectly plain round iron, and the other having thread cut on the portion which was embedded in the cement. Into the 2¾-in holes were cemented 2-in bolts similarly treated, and the four specimens were allowed to stand 13 days before completing the experiment. At the end of time they were put into a standard testing-machine and pulled. The plain bolt began to yield at 20 000 lb and the threaded one at 21 000 lb. The plain bolt began to yield at 34 000 lb and the threaded one at 32 000 lb, force in all cases being very slowly applied. The pump was then run at a great speed, and the stones holding the 2-in bolts split at 67 000 lb in the case of smooth one and at 50 000 lb in the case of the threaded one.

"Four were anchored with sulphur, four with lead and six with cement mixed neat. Half the number of the ¾-in and 1-in bolts being thus anchored each of the three materials, all stood until the cement was two weeks old. Then a lever was rigged and the bolts pulled, with the following results.

"Sulphur: Three bolts out of four developed their full strength 16 000 to 31 000 lb. One 1-in bolt failed by drawing out, under 12 000 lb. Lead: Three bolts out of four developed their full strength, as above. One 1-in bolt pulled out, under 13 000 lb. Cement: Five of the bolts out of six broke by pulling out. One 1-in bolt began to yield in the cement at 26 000 lb, sustained the load a few seconds before it broke.

"While this experiment demonstrated the superiority of cement, both in strength and ease of application, it did not give the strength per square inch of area. To determine this, four specimens of limestone were prepared, 10 in wide, 18 in long and 12 in thick, two of them having 1¼-in holes, and of them 2¾-in holes drilled in them. Into the small holes 1-in bolts were cemented, one of them being perfectly plain round iron, and the other having thread cut on the portion which was embedded in the cement. Into the 2¾-in holes were cemented 2-in bolts similarly treated, and the four specimens were allowed to stand 13 days before completing the experiment. At the end of time they were put into a standard testing-machine and pulled. The plain bolt began to yield at 20 000 lb and the threaded one at 21 000 lb. The plain bolt began to yield at 34 000 lb and the threaded one at 32 000 lb, force in all cases being very slowly applied. The pump was then run at a great speed, and the stones holding the 2-in bolts split at 67 000 lb in the case of smooth one and at 50 000 lb in the case of the threaded one.

"It is thus seen that for anchoring bolts in stone, cement is more reliable, stronger and easier of application than either lead or sulphur, and that its resistance is from 400 to 500 lb per sq in of surface exposed. It is also an ascertained fact that it preserves iron rather than corrodes it. The cement used throughout the experiment was an English Portland cement."

## 6. Concrete †

**Properties and Uses of Concrete.‡** There is probably no material so enduring or better adapted for foundations, walks and basement floors, than cement concrete, and for certain classes of buildings it is used with advantage for the walls, floors and interior supports. There are now thousands of buildings in this and other countries in which all of the structural portions are formed of reinforced concrete, and the use of Portland-cement concrete is

\* The test of these materials is reported in the *American Architect*, page 105, xxiv.

† The subject of concrete in general, including plain or mass-concrete and reinforced concrete, is to-day so important, and the available data so vast in amount that only a few brief statements of general principles and of the best engineering practice that are the most important for the architect and builder to know can be included in a handbook of this kind. For full treatments of the subject, the readers are referred to the numerous recent treatises, tests, proceedings of engineering societies, etc.

‡ For reinforced Concrete, see Chapter XXIV; for Concrete Foundations, Chapter XXV; for Reinforced-Concrete Factory Construction, Chapter XXV; and for Strength of Concrete, Chapter V. See, also, Chapter XXIII, pages 817 and 843.

variety of purposes is rapidly extending, due to the reduced price of cement, and to a better appreciation and understanding of its proper merits. Concrete may be defined as an artificial stone, made by cement, water and what is called an aggregate, consisting of small particles of sand or screenings and gravel or broken stone; and when mixed with good Portland cement, in proper proportions, it becomes so hard that when pieces of it are broken, the line of fracture often passes between the particles of stone, showing that the adhesion of the cement to the stone is greater than the cohesive strength of the stone itself.

**Aggregates.\*** "Extreme care should be exercised in selecting the aggregate for mortar and concrete, and careful tests made of the materials for the purpose of determining their qualities and the grading necessary to secure a uniform density or a minimum percentage of voids. A convenient coefficient of uniformity is the ratio of the sum of the volumes of materials contained in a unit volume to the total unit volume. (See, also, pages 908 and 909.)

**Fine Aggregates** should consist of sand, crushed stone, or gravel screened from fine to coarse and passing when dry a screen having  $\frac{1}{4}$ -in diam holes; it preferably should be of siliceous material, and should be clean, coarse, free from dust, soft particles, vegetable loam or other deleterious matter, and less than 6% should pass a sieve having 100 meshes per lin in. Fine aggregates should always be tested. Fine aggregates should be of such quality that mortar composed of one part Portland cement and three parts fine aggregate by weight when made into briquettes will show a tensile strength at least equal to the strength of 1 : 3 mortar of the same consistency made with the cement and standard Ottawa sand. This is a natural sand obtained at Ottawa, Ill., passing a screen having 20 meshes and retained on a screen having  $\frac{1}{4}$ -in per lin in. It is prepared and furnished by the Ottawa Silica Company at 2 cts per lb, free on board cars, at Ottawa, Ill., under the direction of the Joint Committee on Uniform Tests of Cement of the American Society of Civil Engineers. If the aggregate be of poorer quality the proportion of cement should be increased in the mortar to secure the desired strength. If the strength developed by the aggregate in the 1 : 3 mortar is less than 70% of the strength of the Ottawa-sand mortar, the material should be rejected. To insure the removal of any coating on the grains, which may affect the strength, aggregates should not be dried before being made into mortar, but should contain natural moisture. The percentage of moisture may be determined upon a representative sample for correcting weight. From 10 to 40% more water may be required in mixing bank or artificial sands than for standard Ottawa sand to obtain the same consistency.

**Coarse Aggregates** should consist of crushed stone or gravel which is retained on a screen having  $\frac{1}{4}$ -in diam holes and graded from the smallest to the largest particles; they should be clean, hard, durable and free from all deleterious matter. Aggregates containing dust and soft, flat or elongated particles should be excluded from important structures."

No kind of stone is suitable for the coarse aggregate which has such strength. The strength of the concrete is not limited by the strength of the stone. The strength is of little advantage beyond this minimum. The stones generally employed are granites, traps and limestones. Shales and sandstones of

Read the matter of this paragraph, and of following paragraphs relating to concrete, and the data and conclusions formulated by the joint committees of the Am. Soc. C. E., the Test. Mats., Am. Ry. Eng. and Maint. of Way Asso., and Asso. of Am. Cement Manfrs. In regard to Aggregates, etc., see, also, the same subjects in Part XXIV, pages 908 and 909, and foot-notes on page 908 in that chapter.

deficient strength should be tested before use. Screened gravel generally a good coarse aggregate. "The maximum size of the coarse aggregate is given by the character of the construction. For reinforced concrete and for masses of unreinforced concrete, the aggregate must be small enough to mix with the mortar a homogeneous concrete of viscous consistency which will readily flow between and easily surround the reinforcement and fill all parts of the forms. For concrete in large masses the size of the coarse aggregate may be increased, as a large aggregate produces a stronger concrete than a fine one, although it should be noted that the danger of separation from the mortar becomes greater as the size of the coarse aggregate increases."

The use to be made of the concrete determines the maximum size of the aggregate. When used in mass-concrete construction, such as heavy foundations, the maximum size may run up to 2½ and 3 in with good results. For reinforced work and thin walls, however, it is necessary to reduce the maximum size to 1 in or less. It has been found that the following are the maximum sizes of coarse aggregate of plain or mass-concrete in the best practice: for foundations, 2½ in; for abutments, 2 in; for arch-rings, 1½ in; and for copings, thin walls, etc., 1 in.

"Cinder concrete should not be used for reinforced-concrete structures. It may be allowable in mass for very light loads or for fire-protection purposes. The cinders used should be composed of hard, clean, vitreous clinkers, free from sulphides, unburned coal, or ashes. (See, also, page 909.)

"Water for Mixing Concrete. The water used in mixing concrete should be free from oil, acid, alkalies, or organic matter."

**Preparing and Placing Mortar and Concrete.** "(1) Proportions. Materials to be used in concrete should be carefully selected, of uniform quality, and proportioned with a view to securing as nearly as possible a uniform density.

"(a) Unit of Measure. The unit of measure should be the cubic foot. A bag of cement, containing 94 lb, net, should be considered the equivalent of 1 cu ft. The measurement of the fine and coarse aggregates should be by volume.

"(b) Relation of Fine and Coarse Aggregates. The fine and coarse aggregates should be used in such relative proportions as will insure maximum strength. In unimportant work it is sufficient to do this by individual judgment, using correspondingly higher proportions of cement; for important work the proportions should be carefully determined by density-experiments. The sizing of the fine and coarse aggregates should be uniformly maintained and proportions changed to meet the varying sizes.

"(c) Relation of Cement and Aggregates. For reinforced-concrete construction, one part of cement to a total of six parts of fine and coarse aggregates, measured separately, should generally be used. For columnar concrete mixtures are generally preferable, and in massive masonry or rubble concrete a mixture of 1 : 9 or even 1 : 12 may be used. These proportions should be determined by the strength or the wearing-qualities required in the construction at the critical period of its use. Experienced judgment based on observation and tests of similar conditions in similar localities is an excellent guide as to the proper proportions for any particular case. For all important construction, advance tests should be made of concrete, of the materials and proportions and consistency to be used in the work. These tests should be made under laboratory conditions to obtain uniformity in mixing, proportions,

\* See, also, in Chapter XXIV, paragraphs relating to these subjects on page 908 and foot-note relating to the same, on page 908 of that chapter.

and in case the results do not conform to the requirements of the work, a better quality should be chosen or richer proportions used to obtain the desired results."

Professor Turneaure of the University of Wisconsin gives the following as proportions of cement, sand and coarse aggregate generally used for various kinds of work:

Reinforced columns and structural parts requiring extra strength.....	from 1 : 1 : 2 to 1 : 1½ : 3
Buildings, thin walls, reinforced concrete, drains and impervious construction.....	from 1 : 2 : 4 to 1 : 2½ : 4½
Structures requiring great strength rather than mass.....	from 1 : 2½ : 5 to 1 : 3 : 6
Structures requiring mass rather than strength, foundations, etc.....	from 1 : 3 : 6 to 1 : 4 : 8

**Mixing Concrete.** The ingredients of concrete should be thoroughly mixed and the mixing should continue until the cement is uniformly distributed and the mass is uniform in color and homogeneous. As the maximum density and greatest strength of a given mixture depend largely on thorough and complete mixing, it is essential that the work of mixing should receive special attention. Inasmuch as it is difficult to determine, by visual inspection, whether the concrete is uniformly mixed, especially where limestone or aggregate having the color of cement are used, it is essential that the mixing should continue for a definite period of time. The minimum time will depend on whether the mixing is done by machine or hand.

**Measuring Ingredients.** Methods of measurement of the proportions of various ingredients should be used which will secure separate and uniform measurements of cement, fine aggregate, coarse aggregate and water at all times.

**Machine-Mixing.** When the conditions will permit, a machine-mixer of the type which insures the uniform proportioning of the materials throughout the batch should be used, as a more uniform consistency can be thus obtained. The mixing should continue for a minimum time of at least one minute after all ingredients are assembled in the mixer.

**Hand-Mixing.** When it is necessary to mix by hand, the mixing should be done on a water-tight platform and especial precautions should be taken to turn all ingredients together at least six times and until they are homogeneous in mass and color."

The most satisfactory method\* of mixing concrete by hand is to first prepare a platform for mixing of the materials, a tight floor of planks, or, better still, of sheet metal with the edges turned up about 2 in. Upon this platform should first be spread the sand, and upon this the cement. The two should then be thoroughly and immediately mixed by means of shovels or hoes until of an even color. Then water should be added to make a thin mortar which is then spread over the sand. The gravel, if used, should then be added, and then the broken stone. The sand and stone should be first thoroughly wet, if originally dry. The mass should be turned until all the ingredients are thoroughly incorporated and all the sand and gravel covered with mortar, this requiring from four to six turn-

**Consistency.** The materials should be mixed wet enough to result in a concrete of such a consistency that it will flow into the forms and about the metal reinforcement when used, and which, at the same time, can be conveyed from

\* This paragraph is condensed from several recent specifications.

the mixer to the forms without separation of the coarse aggregate from the mortar.

“(e) Retempering. Mortar or concrete should not be remixed with after it has partly set.”

(3) **Placing Concrete.** “(a) **Methods.** Concrete after the completion of the mixing should be handled rapidly, and in as small masses as is practicable from the place of mixing to the place of final deposit, and under no circumstances should concrete be used that has partly set. A slow-setting concrete should be used when a long time is likely to occur between mixing and depositing. Concrete should be deposited in such a manner as will permit the most thorough compacting, such as can be obtained by working with a straight shovel or trowel tool kept moving up and down until all the ingredients have settled into their proper places by gravity and the surplus water has been forced to the surface. Special care should be exercised to prevent the formation of LAITANCE, which hardens very slowly and forms a poor surface on which to deposit fresh concrete. All LAITANCE should be removed. When suspended work is resumed, concrete previously placed should be roughened, thoroughly cleansed of laitance, thoroughly wetted and then slushed with a mortar consisting of one part Portland cement and not more than two parts fine aggregate. The faces of concrete exposed to premature drying should be kept wet for a period of at least seven days.”

“(b) **Mixing and Depositing Concrete in Freezing Weather.** Concrete should not be mixed or deposited at a freezing temperature, unless special precautions are taken to avoid the use of materials covered with ice-cry, containing frost, and to provide means to prevent the concrete from freezing after being placed in position and until it has thoroughly hardened. Where coarse aggregate forms the greater portion of the concrete, it is particularly important that this material be heated to well above the freezing-point.

“(c) **Rubble Concrete.** Where the concrete is to be deposited in place, its value may be improved and its cost materially reduced by the use of clean stones thoroughly embedded in the concrete and as near together as possible while still entirely surrounded by concrete.

“(d) **Depositing Concrete Under Water.** In placing concrete under water it is essential to maintain still water at the place of deposit. The use of a tremie, properly designed and operated, is a satisfactory method of placing concrete through water. The concrete should be mixed very wet (more so than is ordinarily permissible) so that it will flow readily through the tremie into the places with practically a level surface. The coarse aggregate should be smaller than ordinarily used, and never more than 1 in. in diameter. The use of gravel facilitates mixing and assists the flow of concrete through the tremie. The mouth of the tremie should be buried in the concrete so that it is at all times entirely sealed and the surrounding water prevented from forcing its way into the tremie; the concrete will then discharge without coming in contact with the water. The tremie should be suspended so that it can be raised or lowered quickly when it is necessary either to choke off or prevent a too rapid discharge.

\* Laitance is a whitish, gelatinous substance of about the same composition as mortar but with little tendency to harden. It accompanies a disintegration of some of the cement from the surface of concrete which is exposed to the action of water immediately after it is deposited. The concrete is thus weakened and the laitance, also, weakens the bond between old and new material and should be removed before fresh concrete is deposited.

† A tremie is a round or square box or tube of wood or plate iron open at the top and closed at the bottom. The diameter varies from 12 to 24 in. The tremie rests in the deposit of concrete, extends above the water-level and is kept full of concrete, which escapes from the bottom as the tube is shifted over the surface.

flow should preferably be not over 15 ft. The flow should be continuous in order to produce a monolithic mass and to prevent the formation of laitance on the interior. In large structures it may be necessary to divide the mass of concrete into several small compartments or units, filling one at a time. With care it is possible in this manner to obtain as good results under water as in air."

**Forms for Concrete.** "Forms should be substantial and unyielding, so that concrete will conform to the designed dimensions and contours, and should be tight in order to prevent the leakage of mortar. The time for removal of forms is one of the most important considerations in the erection of a structure of concrete or reinforced concrete. Care should be taken to inspect the concrete and determine its hardness before removing the forms. So many conditions affect the hardening of concrete, that the proper time for the removal of the forms will be decided by some competent and responsible person, especially where atmospheric conditions are unfavorable. It may be stated, in a general way, that forms should remain in place longer for reinforced concrete than for plain massive concrete, and that the forms for floors, beams and similar horizontal structures should remain in place much longer than for vertical walls. When the concrete gives a distinctive ring under the blow of a hammer, it is usually an indication that it has hardened sufficiently to permit the removal of the forms with safety. If, however, the temperature is such that there is a possibility that the concrete is frozen, this test is not a safe reliance, as concrete may appear to be very hard."

**Shrinkage of Concrete and Temperature-Changes.** "Shrinkage of concrete, due to hardening and contraction from temperature-changes, causes a reduction in the size of which depends on the extent of the mass. The resulting cracks are important in monolithic construction and should be considered carefully by the designer; they cannot be counteracted successfully, but the effects may be minimized. Large cracks produced by quick hardening or wide ranges of temperature can be broken up to some extent into small cracks by placing reinforcement in the concrete; in long continuous lengths of concrete, it is better to provide shrinkage-joints at points in the structure where they will do little or no harm. Reinforcement is of assistance and permits longer distances between shrinkage-joints than when no reinforcement is used. Small masses or bodies of concrete should not be joined to larger or thicker masses without providing for shrinkage at such points. Fillets similar to those used in metal work, but of larger dimensions, for gradually reducing from the thicker to the thinner body, are of advantage. Shrinkage-cracks are likely to occur at points where fresh concrete is joined to that which is set, and hence in placing concrete, construction-joints should be made on horizontal and vertical planes, and, if possible, at points where joints would naturally occur in dimensioned masonry."

**Effect of Heat on Concrete Fireproofing.\*** "The actual fire-tests of plain and reinforced concrete have been limited, but experience, together with the results of tests thus far made, indicates that concrete, on account of its low rate of heat-conductivity and the fact that it is incombustible, may be relied upon for fireproofing purposes. The dehydration of concrete probably begins at about 500° F. and is completed at about 900° F.; but experience indicates that the volatilization of the water absorbs heat from the surrounding mass, and, together with the resistance of the air-cells, tends to increase the heat-resistance of the concrete, so that the process of dehydration is very much re-

\* See, also, Chapter XXIII, page 817.



tarded. The concrete that is actually affected by fire remains in position and affords protection to the concrete beneath it. The thickness of the protective coating required depends on the probable duration of a fire which is likely to occur in the structure and should be based on the rate of heat-conduction. The question of the conductivity of concrete is one which requires further study and investigation before a definite rate for different classes of concrete can be fully established. However, for ordinary conditions it is recommended that the metal in girders and columns be protected by a minimum of 2 in of concrete; that the metal in beams be protected by a minimum of  $1\frac{1}{2}$  in of concrete and the metal in floor-slabs be protected by a minimum of 1 in of concrete. It is recommended that in monolithic concrete columns, the concrete to a depth of  $1\frac{1}{2}$  in be considered as protective covering and not included in the effective section. It is recommended that the corners of columns, girders and beams be beveled or rounded, as a sharp corner is more seriously affected by fire than a round one."

**Waterproofing Concrete.** "Many expedients have been used to make concrete impervious to water under normal conditions, and also under special conditions that exist in reservoirs, dams and conduits of various kinds. Experience shows, however, that where mortar or concrete is proportioned to give the greatest practicable density and is mixed to a rather wet consistency, the resulting mortar or concrete is impervious under moderate pressure. Concrete of dry consistency is more or less pervious to water, and compounds of various kinds have been mixed with the concrete, or applied as a wash on the surface for the purpose of making it water-tight. Many of these compounds are of but temporary value, and in time lose their power of imparting imperviousness to the concrete. In the case of subways, long retaining-walls and reservoirs, provided the concrete itself is impervious, cracks may be so reduced in size that horizontal and vertical reinforcement properly proportioned and located so that they are too minute to permit leakage or are soon closed by infiltration. Coal-tar preparations applied either as a mastic or as a coating on felt or other fabric are used for waterproofing, and should be proof against injury by acids or gases. For retaining-walls and similar walls in direct contact with the earth, the application of one or two coatings of hot coal-tar pitch to the thoroughly dried surface of concrete is an efficient method of preventing the absorption of moisture from the earth." (See, also, Waterproofing for Foundations, Part III.

**Surface-Finish of Concrete.** "Concrete is a material of an individual character and should not be used in imitation of other structural materials. One of the important problems connected with its use is the character of the finish of the exposed surfaces. The finish of the surface should be determined before the concrete is placed, and the work conducted so as to make possible the desired finish. For many forms of construction the natural surface of the concrete is unobjectionable; but frequently the marks of the boards and the flat surface are displeasing, thus making some special treatment desirable. The treatment of the surface either by scrubbing it while green or by tooling it when it is hard, which removes the film of mortar and brings the aggregates of concrete into relief, is frequently used to remove the form-markings, break the monotonous appearance of the surface, and make it more pleasing. The plastering of surfaces should be avoided, for even if carefully done, the plaster is liable to peel off under the action of frost or temperature-changes."

**Design of Massive Concrete.** "In the design of massive or plain concrete no account should be taken of the tensile strength of the material, and it should usually be proportioned, so as to avoid tensile stresses, except in



to resist indirect stresses. This will generally be accomplished, in case of rectangular shapes, if the line of pressure is kept within the middle of the section, but in very large structures, such as high masonry dams, a exact analysis may be required. Structures of massive concrete are able resist unbalanced lateral forces by reason of their weight; hence the element weight rather than strength often determines the design. A relatively cheap weak concrete, therefore, will often be suitable for massive concrete structures. It is desirable generally to provide joints at intervals to localize the effect of contraction. Massive concrete is suitable for dams, retaining-walls, piers and short columns in which the ratio of length to least width is relatively small. Under ordinary conditions this ratio should not exceed six. It is also suitable for arches of moderate span, where the conditions as to foundations are favorable."

**Quantities of Materials Required per Cubic Yard of Concrete.\*** The following tables give the quantities of Portland cement required to make 1 cu yd of mortar and the quantities of cement, sand and stone required to make 1 cu yd of concrete. They are based upon formulas deduced by Halbert P. Gillette.

#### Barrels of Portland Cement per Cubic Yard of Mortar

Voids in sand, 35%, 1 bbl of cement yielding 3.65 cu ft of cement paste

Proportion of cement to sand	1 to 1	1 to 1½	1 to 2	1 to 2½	1 to 3	1 to 4
	bbl	bbl	bbl	bbl	bbl	bbl
and specified to be 3.5 cu ft	4.22	3.49	2.97	2.57	2.28	1.76
and specified to be 3.8 cu ft	4.09	3.33	2.81	2.45	2.16	1.62
and specified to be 4.0 cu ft	4.00	3.24	2.73	2.36	2.08	1.54
and specified to be 4.4 cu ft	3.81	3.07	2.57	2.27	2.00	1.40
cu yd of sand per cu yd of mortar .....	0.6	0.7	0.8	0.9	1.0	1.0

#### Barrels of Portland Cement per Cubic Yard of Mortar

Voids in sand, 45%, 1 bbl of cement yielding 3.4 cu ft of cement paste

Proportion of cement to sand	1 to 1	1 to 1½	1 to 2	1 to 2½	1 to 3	1 to 4
	bbl	bbl	bbl	bbl	bbl	bbl
and specified to be 3.5 cu ft	4.62	3.80	3.25	2.84	2.35	1.76
and specified to be 3.8 cu ft	4.32	3.61	3.10	2.72	2.16	1.62
and specified to be 4.0 cu ft	4.19	3.46	3.00	2.64	2.05	1.54
and specified to be 4.4 cu ft	3.94	3.34	2.90	2.57	1.86	1.40
cu yd of sand per cu yd of mortar .....	0.6	0.8	0.9	1.0	1.0	1.0

In using these tables remember that the proportion of cement to sand is by volume and not by weight. If the specifications state that a barrel of cement is to be considered to hold 4 cu ft, for example, and that the mortar shall be

\* Adapted, by permission, from the Handbook of Cost Data for Contractors and Engineers, by Halbert P. Gillette, published by The Myron C. Clark Publishing Company, Chicago, Ill. See 1914 revised edition, pages 538 to 540. This handbook contains comprehensive and voluminous data on quantities, costs, etc., of building materials and operations.

1 part cement to 2 parts sand, then 1 bbl of cement is mixed with 8 cu ft of regardless of what is the actual size of the barrel, and regardless of how cement paste can be made with a barrel of cement. If the specifications state what the size of a barrel will be, then the contractor is left to guess.

"If the specifications call for proportions by weight, assume a Portland cement barrel to contain 380 lb of cement, and test the actual weight of a foot of the sand to be used. Sand varies extremely in weight, due both to variation in the per cent of voids, and to the variation in the kind of material of which the sand is composed. A quartz sand having 35% voids weighs 130 lb per cu ft; but a quartz sand having 45% voids weighs only 91 lb per cu ft. If the specifications require a mixture of 1 part of cement to 2 parts of sand, by weight we will have 380 lb (or 1 bbl) of cement mixed with 2 times 380, or 760 lb of sand; and if the sand weighs 91 lb per cu ft, we shall have 760 divided by 91 = 8.44 cu ft of sand to every barrel of cement. In order to use the tables given, we may specify our own size of barrel; let us say 4 cu ft; then, 8.44 divided by 4 gives 2.11 parts of sand by volume to 1 part of cement. Without material error we may call this a 1 to 2 mortar, and use the tables, remembering that the barrel is now 'specified to be' 4 cu ft. If we have a brand of cement that yields 3.4 cu ft of paste per bbl and sand having 45% voids, we find that approximately 3 bbl of cement per cu yd of mortar will be required.

"It should be evident from the foregoing discussions that no table can be made, and no rule can be formulated that will yield accurate results unless a brand of cement is tested and the percentage of voids in the sand determined. This being so, the sensible plan is to use the tables merely as a rough guide, and, where the quantity of cement to be used is very large, to make a few batches of mortar, using the available brands of cement and sand in the proportions specified. Ten dollars spent in this way may save a thousand, even on a comparatively small job, by showing what cement and sand to select."

#### Ingredients in One Cubic Yard of Concrete \*

Sand-voids, 40%; stone-voids, 45%; Portland-cement barrel yielding 3.65 cu ft paste. Barrel specified to be 3.8 cu ft.

Proportions by volume	1 : 2 : 4	1 : 2 : 5	1 : 2 : 6	1 : 2½ : 5	1 : 2½ : 6	1 : 3
Barrels cement per cu yd concrete.....	1.46	1.30	1.18	1.13	1.00	1.00
Cubic yard sand per cu yd concrete.....	0.41	0.36	0.33	0.40	0.35	0.30
Cubic yard stone per cu yd concrete.....	0.82	0.90	1.00	0.80	0.84	0.90
Proportions by volume	1 : 3 : 5	1 : 3 : 6	1 : 3 : 7	1 : 4 : 7	1 : 4 : 8	1 : 5
Barrels cement per cu yd concrete.....	1.13	1.05	0.96	0.82	0.77	0.60
Cubic yard sand per cu yd concrete.....	0.48	0.44	0.40	0.46	0.43	0.36
Cubic yard stone per cu yd concrete.....	0.80	0.88	0.93	0.80	0.86	0.96

\* This table is to be used where cement is measured packed in the barrel, if an ordinary barrel holds 3.8 cu ft.

It will be seen that the above table can be condensed into the following:  
 Rule. Add together the number of parts and divide this sum into ten, the result will be, approximately, the number of barrels of cement per cubic yard. For a 1 : 2 : 5 concrete, the sum of the parts is 1 plus 2 plus 5, which is 8; 8 divided by 8 is 1.25 bbl, which is approximately equal to the 1.30 bbl in the table. Neither this rule nor this table is applicable if a different cement-barrel is specified, or if the voids in the sand or stone differ materially from 40% and 45% respectively. There are such innumerable combinations of varying voids, and varying sizes of barrels, that the author does not deem it worth while to give other tables."

### Ingredients in One Cubic Yard of Concrete \*

\* Sand-voids, 40%; stone-voids, 45%; Portland-cement barrel yielding 3.65 cu ft of paste. Barrel specified to be 4.4 cu ft

Proportions by volume	1 : 2 : 4	1 : 2 : 5	1 : 2 : 6	1 : 2½ : 5	1 : 2½ : 6	1 : 3 : 4
bags cement per cu yd concrete.....	1.30	1.16	1.00	1.07	0.96	1.08
cu yd sand per cu yd concrete.....	0.42	0.38	0.33	0.44	0.40	0.53
cu yd stone per cu yd concrete.....	0.84	0.95	1.00	0.88	0.95	0.71

Proportions by volume	1 : 3 : 5	1 : 3 : 6	1 : 3 : 7	1 : 4 : 7	1 : 4 : 8	1 : 4 : 9
bags cement per cu yd concrete.....	0.96	0.90	0.82	0.75	0.68	0.64
cu yd sand per cu yd concrete.....	0.47	0.44	0.40	0.49	0.44	0.42
cu yd stone per cu yd concrete.....	0.78	0.88	0.93	0.86	0.88	0.95

Cost of Concrete.† (For Cost of Cement, see page 238.) The average cost of sand may be taken at 30 cts per cu yd to cover digging and loading, but if washed or screened the cost averages between 40 and 55 cts per cu yd. Digging and freight-charges generally raise the cost of sand, ready to unload at the job, to from 90 cts to \$1.10 per cu yd, and about 15 cts per yd additional should be added, if unloaded from cars. Gravel costs from \$1.20 to \$1.40 per cu yd loaded at the job, and crushed stone from \$1.45 to \$1.60. These prices are, of course, average prices only, and include moderate-haul teaming and unloading. For hand-mixing and placing of soft concrete, and spreading without teaming, the labor-cost varies from 90 cts to \$1.30 per cu yd. This is the cost of digging in barrows materials that are conveniently at hand. This cost is much higher for dry concrete, and hand-mixing costs may reach \$2 or more per cu yd. For machine-mixing alone and with machines taking four bags per batch, the cost of mixing may be even as low as 50 or 60 cts per cu yd. Machine-mixing alone, the cost is about 75 cts per cu yd; this includes wheeling the material, dumping it in place and spreading and spading it into forms. This cost could be almost doubled where unusual care had to be exercised to obtain a smooth surface and where there was an extra amount of spading. The costs in this table is to be used when the cement is measured loose, after dumping it into the mixer; under such conditions a barrel of cement yields 4.4 cu ft of loose cement. If conditions changed many costs. Values given are retained temporarily for purpose of comparison.

are reduced for heavy mass-concrete, and have been as low as 50 or 60 cts per cu yd for machine-mixing and placing together, by mixer and derrick tracks and cars. The following approximate schedule \* of labor-costs for mixing and placing concrete is given by L. H. Allen of the Aberthaw Construction Company, in Professor Hool's excellent treatise:

For footings.....	\$1.50 per cu yd
For floor-slabs not exceeding 4½ in in thickness....	\$1.60 per cu yd
For floor-slabs exceeding 5 in in thickness.....	\$1.00 per cu yd
For columns and thin walls.....	\$1.50 per cu yd
For walls exceeding 18 in in thickness.....	\$1.00 per cu yd
For dams and thick retaining-walls.....	\$0.70 per cu yd

For the unit cost due to the cost of the tools, plant and supplies, \$1 is taken as an average for jobs requiring from 4 000 to 10 000 cu yd of concrete. It varies, of course, with the character and magnitude of the work. The cost for this item is reduced in larger jobs, falling to 80 or even 70 cts per cu yd, and it is increased in operations of less magnitude to from \$1 to \$1.50 per cu yd, for, say, 3 000 cu yd of concrete. When the amount of concrete required is small as 600 or 700 cu yd, hand-mixing is generally more economical than machine-mixing. Mr. Allen summarizes \* the cost of 1 cu yd of concrete for building requiring 5 000 cu yd of reinforced-concrete work in floors and columns as follows, the cost of forms and steel and finishing of the surface not included:

Cement, 1¾ bbl, at \$1.38 per bbl.....	\$2.
Sand, ½ cu yd, at \$1 per cu yd.....	0.
Stone, 1.35 tons, at \$1.40 per ton.....	1.
Labor, per cu yd.....	1.
Plant, per cu yd.....	1.
Total, per cu yd.....	\$7.

In this summary the exact theoretical proportions or quantities of cement, sand and stone required for 1 cu yd of concrete, and deduced from formulas, are not adhered to, the author stating that the exact theoretical proportions are the net quantities of the materials determined by careful experiments. "conditions on actual construction work do not approach those of laboratory work and that there is always a considerable waste of cement, sand and stone. In view of these facts, he states that, "when estimating quantities, it is customary to allow less than the following amounts of cement for different proportions of mix:

1 : 1½ : 3 mix .....	2.00 bbl per cu yd
1 : 2 : 4 mix.....	1.66 bbl per cu yd
1 : 2½ : 5 mix.....	1.40 bbl per cu yd
1 : 3 : 6 mix.....	1.20 bbl per cu yd

It is customary to allow ½ cu yd of sand and 1 cu yd of crushed stone for 1 cu yd of concrete, and to estimate the weight of crushed stone at 100 lb per cu ft.

**The Weight of Concrete** varies from 110 to 155 lb per cu ft, according to the material used. Concrete of the usual proportions weighs from 140 to 150 lb per cu ft. Trap-rock concrete weighs from 148 to 155; limestone concrete, from 142 to 148; and cinder concrete from 80 to 115 lb per cu ft.

\* Reinforced Concrete Construction, by George A. Hool, McGraw-Hill Book Company, New York.

**Strength of Concrete.** See Chapter V.

**Other Examples of Portland-Cement Concrete.** From the foregoing it is seen that for foundation-work to-day, mass-concrete varies in proportions from a 1 : 3 : 6 to a 1 : 4 : 8 mix. Some of the earlier examples are added for comparison.

**Foundations of the United States Naval Observatory, Georgetown, D. C.:** 1 part cement, 2½ parts sand, 3 parts gravel, 5 broken stone. (1 bbl of cement, 380 lb, makes 1.13 yd of concrete.)

**Foundations of the Cathedral of St. John the Divine, New York:** 1 part cement, 2 parts sand, 3 parts quartz gravel of pieces from 1½ to 2 in diameter. (17 000 bbl of cement made 11 000 yd of concrete.)

**Manhattan Life Insurance Building, New York, filling of caissons:** 1 part Portland cement, 2 parts sand, 4 parts broken stone.

**Manhattan Building (15 stories), New York, filling of caissons:** 1 part Portland cement, 3 parts sand, 7 parts stone, finished on top for brickwork with 1 part cement and 3 parts gravel.

**Professor Baker states that the concrete foundations under the Washington Monument were made of 1 part Portland cement, 2 parts sand, 3 parts gravel and 4 parts broken stone, and that this mixture stood, when six months old, a load of 1 000 lb per sq in, or 144 tons per sq ft.**

## CHAPTER IV

# RETAINING-WALLS, BREAST-WALLS AND VAULT-WALLS

By  
GRENVILLE TEMPLE SNELLING  
MEMBER OF AMERICAN INSTITUTE OF ARCHITECTS

### 1. Mechanical Principles Involved

**General Principles.** Before discussing more in detail the problems relative to masonry structures, in which, if improperly constructed, a tendency to slide or overturn on their bases may be developed, a familiarity with what are known as the **THEOREM OF FRICTION** and the **THEOREM OF THE MIDDLE THIRD** is of assistance in comprehending the methods indicated for rendering such structures stable.

**Theorem of Friction.** If a body rests on an inclined plane it will remain stationary until the angle  $\phi$ , that the plane makes with the horizontal, becomes so great that the




Fig. 1




Fig. 2




Fig. 3




Fig. 4

Figs. 1, 2, 3 and 4. Body on Inclined Plane. Graphical Representation of

friction becomes so great that the **FRICTION** developed between the surfaces of the body and the plane is no longer sufficient to prevent the body from sliding down the plane (Fig. 1).

Assume the body *HIJ* resting on the plane *EF*. The weight, *W*, of the body is shown graphically by the line *AB*, applied at its center of gravity *A* (

weight can be resolved into two component forces, one,  $AC$ , normal to the plane and the other,  $AD$ , parallel to it. It is the parallel or tangential component which tends to pull the body down the plane and which is resisted by the friction developed between the two surfaces. The friction developed between two surfaces in contact depends upon the nature of the materials of which they are composed and the intensity of the forces pressing them together; and it is the tendency to slide only up to a certain point. As the angle  $\phi$ , which the inclined plane makes with the horizontal, increases, the tangential component  $T$ , of the weight  $W$ , increases, until it becomes greater than the frictional resistance, and the body moves down the plane (Fig. 3). From trigonometry,

$$T = W \sin \phi$$
$$N = W \cos \phi, \text{ or, } T = N \tan \phi$$

There is evidently a position of the plane, intermediate between the positions in Figs. 1 and 3, in which the component force  $T$  is just balanced by the friction and in which the body remains at rest although just on the point of sliding (Fig. 4). If the angle which the inclined plane makes with the horizontal at the moment when the body is just about to slide, be designated by  $\phi$ , the friction developed between the two surfaces will be equal to  $N \tan \phi$ , since, as the angle of inclination of the plane to the horizontal is  $\phi$ , the tangential component of the weight just balances the friction. From the equation  $T = N \tan \phi$  it is evident that the friction is directly proportional to  $N$  and to  $\tan \phi$ . This is then known as the COEFFICIENT OF FRICTION and  $\phi$  as the ANGLE OF FRICTION. In the case of stone surfaces, it is often known as the ANGLE OF REPOSE.

Following Table I gives the average values of these constants as determined by experiment.

Table I. Coefficients and Angles of Friction

Kind of surface	Coefficient of friction, $\tan \phi$	Angle of friction, $\phi$
Stone, limestone and marble:		
Soft dressed upon soft dressed.....	0.70	35° 00'
Hard dressed upon hard dressed.....	0.55	28 50
Soft dressed upon soft dressed.....	0.65	33 00
Brick or concrete:		
Soft upon masonry.....	0.65	33 00
Soft upon wood (with the grain).....	0.60	31 00
Soft upon wood (across the grain).....	0.50	26 40
Soft upon dry clay.....	0.50	26 40
Soft upon wet or moist clay.....	0.33	18 20
Soft upon sand.....	0.40	21 50
Soft upon gravel.....	0.60	31 00
Steel upon steel or iron.....	0.40	21 50
Ice upon steel or iron.....	0.30	16 40

In the discussion only the weight  $AB$  (Figs. 2, 3 and 4), of the body has been considered; but the body might be subjected to the action of other forces besides the force of gravity, in which case these other forces would be combined with the weight in order to find the resultant, this resultant being again resolved into a tangential and a normal component. Since the angle  $BAC$  is equal to the

angle  $FEG$  (Figs. 2, 3 and 4), given a certain normal pressure exerted by a body on the plane, the amount of the tangential pressure  $T$  depends on the angle  $FEG$ . The problem in actual practice reduces itself to so arrange conditions that no matter what the position of the plane may be, the angle which the resultant  $W$ , makes with the normal  $N$ , to the plane, will not be greater than the **ANGLE OF FRICTION OR REPOSE**.

**Theorem of the Middle Third.** When any surface is subjected to a pressure from the action of any force or forces, this **TOTAL PRESSURE** may be considered as a **SYSTEM OF AN INFINITE NUMBER OF PARALLEL FORCES**, unequal in intensity. These forces will have a **RESULTANT**, whose **MAGNITUDE, DIRECTION AND POINT OF APPLICATION** can be determined, either graphically or by moments, as explained in Chapter VI. The determination of the elements of this resultant force may at times become of the utmost importance to the engineer.

Pressure of this nature is technically known as the **STRESS** to which the surface in question is subjected. (See Chapter I.) When the **INTENSITY OF STRESS** is not the same at different points of a surface, it is called a **VARIABLE STRESS**, while if, on the contrary, its intensity remains the same at every point of the surface, it is called a **UNIFORM STRESS**.

When a stress varies it may do so in one or two ways. It may vary **UNIFORMLY**, that is to say, in a uniform manner, following some definite law of variation, so that, knowing this law, its intensity may be determined at any given point of the surface; or **NON-UNIFORMLY**, following no law. When a stress varies in the former manner it is called a **UNIFORMLY VARYING STRESS**. This is the case most frequently met with in engineering problems.

Fig. 5. Resultant within Middle Third

Fig. 6. Resultant at Middle Third

In dealing with **ISOLATED FORCES**, such as concentrated loads on a beam, engineers are usually interested in determining the **MAGNITUDE AND POINT OF APPLICATION** of the **RESULTANT** of these forces. When, however, the question is one of a system of or of an unlimited number of forces, the problem that usually presents itself is one in which the resultant is known, in magnitude, direction and point of application, and in which it is required to determine the **DISTRIBUTION OF STRESS** to which the surface is subjected. Or, in actual practice, it is to so arrange the parts of the structure that this resultant shall have such a magnitude, direction and point of application that the stress to which the surface under consideration is subjected shall not exceed certain **LIMITS** of stress determined beforehand by experience. For example, when the resultant of a known amount of pressure or stress acts at the **CENTER OF GRAVITY** of the surface subjected to the stress, this stress is **UNIFORMLY DISTRIBUTED** over the surface.



the resultant acts at a distance of two-thirds the total width of the surface from one edge or boundary line of the surface, and at one-third the distance from the other edge, the stress is **UNIFORMLY VARYING**; and its intensity at the edge farthest from the point of application of the resultant is **ZERO** and at the other edge is **MAXIMUM** or twice the average stress. When, however, the total width of the stress remaining the same, the point of application of the resultant is at a greater distance from one edge than two-thirds the width of the surface, a certain part of the surface adjacent to the edge farthest from the resultant is subjected to a **STRESS OF A CONTRARY KIND** to that distributed over the remainder of the area; that is to say, if the stress to which the major part of the surface is subjected is a **COMPRESSIVE** stress, the stress acting on the remainder of the surface is a **TENSILE** stress. The stresses in a surface resulting from three positions of the resultant force may be illustrated graphically, as shown in Figs. 6 and 7. (See, also, Chapter XXXI, pages 1225 and 1234.)

Fig. 7. Resultant beyond Middle Third

## 2. Retaining-Walls

**Definition.** A **RETAINING-WALL** is a wall built to resist the pressure of earth, sand, or other filling or backing deposited behind it after it is built, as distinguished from a **BREAST-WALL** or **FACE-WALL**, which is a similar structure built to prevent the fall of earth which is in its undisturbed, natural position, and which part has been excavated, leaving a vertical or inclined face. Fig. 8 illustrates the two kinds of wall.




Fig. 8. Retaining-wall and Breast-wall

**Theory of Retaining-Walls.** A great deal has been written on the **THEORY OF RETAINING-WALLS**, and many theories, involving elaborate calculations for finding the **CONJUGATE PRESSURES** in the earth-backing behind the wall, have been developed for computing the **THRUST** which a bank of earth exerts against a wall, and for determining the **FORM** of wall which offers the greatest resistance with the least amount of material. There are so many conditions, however, upon which the thrust exerted by the backing depends, such as the composition of the earth, the dryness of the material, the mode of backing up, etc., that in practice it is impossible to determine the exact thrust which is exerted against a wall of a given height. It is necessary, therefore, in the construction of retaining-walls, to be guided by experience rather than by theory. As the theories of retaining-walls are so vague and unsatisfactory, we shall not

include any in this work, but offer, rather, such suggestions, rules and as have been established by practice and experience. A construction suggested from empirical data, which has been found to work well in practice, determining the THRUST OF THE EARTH-BACKING and the DIMENSIONS WALL to properly resist this thrust, is given on page 257.

In designing a retaining-wall the backing as well as the wall itself is carefully considered. THE TENDENCY OF THE BACKING TO SLIP is very less when the material is in a dry state than when it is saturated with water, and hence every precaution should be taken to secure good drainage. For surface-drainage, there should be openings left in the wall for the water which may accumulate behind it to escape.

The manner in which the material is filled against the wall, also, affects the stability of the backing. If the ground is made irregular, with steps as shown in Fig. 8, and the earth well rammed in layers inclined DOWN towards the wall, the pressure will be very trifling, provided that attention is given to drainage. If, on the other hand, the earth is tipped in the usual manner in layers sloping DOWN TOWARDS the wall, almost the full pressure of the earth will be exerted against it, and it must be made strong enough to withstand such pressure.

**Slopes of Repose and Angles of Repose.** Cases may occur in practice in which the conditions are not such as are shown in Fig. 8, which show a limited amount of fill or new material put in behind the wall on top of the original slope of the grade; cases in which, on the contrary, the wall is built on the natural surface of the ground with a view to creating an artificial new terrace or embankment and where all the material back of the wall is new.

All of this material does not beat upon the wall and tend to overturn it. sand or loose earth taken from an excavation and deposited on the surface of the ground does not spread itself out like a liquid but piles up in a mound. This PILING UP is due to the FRICTION developed between the separate particles as they slide one over the other while being dumped. This phenomenon is common in the action of any solid material broken up into separate particles; and the SLOPE OF THE SIDES of such a mound varies with different materials. In general, the same for the same material. The angle of this slope is known as the ANGLE OF NATURAL SLOPE of the material. This angle for the materials generally used for fill is given in the following Table II.


Table II. Slopes of Repose, Angles of Repose and Weights of Loose Materials

Kind of earth	Slope of repose*	Angle of repose	Weight per cubic foot, lb
Sand, clean.....	1.5 to 1	33° 41'	
Sand and clay.....	1.33 to 1	36 53	
Clay, dry.....	1.33 to 1	36 53	
Clay, damp, plastic.....	2 to 1	26 34	
Gravel, clean.....	1.33 to 1	36 53	
Gravel and clay.....	1.33 to 1	36 53	
Gravel, sand and clay .....	1.33 to 1	36 53	
Soil.....	1.33 to 1	36 53	
Soft rotten rock.....	1.33 to 1	36 53	
Hard rotten rock.....	1 to 1	45 00	
Bituminous cinders.....	1 to 1	45 00	
Anthracite ashes.....	1 to 1	45 00	

\* The slope is that of horizontal to vertical projection.

**Pressures on Retaining-Walls.** Even under the conditions shown in Fig. 8, a part of the filled-in material will exert a pressure on the wall. It would be natural to suppose that the part of the fill exerting pressure on the wall will be determined by the ANGLE OF NATURAL SLOPE, all material from a horizontal grade up to this angle being able to take care of itself, and the material above the angle needing the wall to hold it in place. Experiment shows that this is not strictly true, for as the earth settles into place certain forces of INTERNAL ELASTICITY and tendencies toward a state of EQUILIBRIUM come into play creating INTERNAL STRESSES which produce the CONJUGATE STRESSES already referred to. The exact determination of these INTERNAL STRESSES demands relatively complicated calculations which would be out of place in a book of this character. The construction given in the following graphs for determining the SLOPE OF THE CLEAVAGE-PLANE, between that of the backing which sustains itself and the triangular fill which actually rests on the wall, is sufficiently accurate, however, for all practical purposes.

**The Slope of the Cleavage-Plane.** The following construction (Figs. 9 and 10), based upon empirical data, for determining first, the PRISM OF EARTH



**Fig. 9. Method of Determining the Prism of Earth**

It exerts pressure on the back of the wall and secondly, the proper DIMENSIONS for the wall, has been found to work well in practice, when certain necessary precautions are taken. These include proper DRAINAGE behind the wall, proper RAMPING of the fill and efficient BRACING of the wall during its construction.

In the calculations to determine the pressure of the earth and the weight of wall, a slice 1 ft thick is first considered. Then the area of the triangle is proportional to the volume and weight of the slice of earth causing pressure on the wall, and as the area of the cross-section of the wall is proportional to the volume and weight of the slice of the wall itself.

to determine the PRISM OF EARTH which exerts pressure against the back of wall, decide first upon the BATTER to be given to the back of the wall. In this case it made  $80^\circ$  with the horizontal, an angle slightly greater than that used by Trautwine. Draw  $BH$  (Fig. 9), making an angle  $ABH$ , equal to that with the back of the wall; continue this line until it meets at  $H$  the slope surface of the earth back of the wall, prolonged. From  $A$ , the top of the wall, draw  $AJ$  parallel to  $BF$  the natural slope of the fill. This has been taken as a fair average value. Erect a perpendicular from the middle of  $JB$ . With any point,  $O$ , as a center, on this perpendicular, describe an arc passing

through  $J$  and  $B$ . Draw  $HO$  and bisect it, and with  $O'$  as a center and  $O'O$  as a radius, describe the arc cutting the arc  $JKB$  at  $K$ . Again, with a radius and with  $H$  as center, describe the arc  $KL$ , and finally, from  $L$ , draw  $LE$  parallel to  $JA$ . The intersection of this line with the surface of the ground locates




Fig. 10. Method of Determining Dimensions of Retaining-wall

point  $E$ . The line  $EB$  is the line of the CLEAVAGE-PLANE which separates part of the backing which bears against the wall from the part which exerts lateral pressure.

Having found the DIMENSIONS OF THE VOLUME OF EARTH, the thrust of which must be resisted by the wall, the next step is to determine what the DIMENSIONS OF THE WALL should be to properly resist this thrust. Usually one or two trials are necessary before the proper solution of the problem is found. In the example given, a preliminary trial was made with a thickness at the base of 1' 6". This construction is shown with the green lines (Fig. 10).

After drawing the triangle representing the base of the PRISM OF EARTH, find its center of gravity,  $G$  (Chap. VI). From this point draw two normals, one to the back of the wall and the other to the line of the CLEAVAGE-PLANE. Draw the two lines,  $GM$  and  $GN$ , making angles  $\phi$  with these normals. Lay off distances from the center of gravity, at any convenient scale of so many s

to the linear inch, the area of the triangle of the base of the prism, the area is already explained, being proportional to the volume of the prism and weight. Resolve this weight-line along the two lines  $GM$  and  $GN$  (Chap. 1). This will give the **MAGNITUDE** and **DIRECTION** of the **THRUST** or pressure of the earth against the wall. Apply this pressure at a point on the back of the wall one-third of the distance from the bottom, as shown by the arrow. This is the force which may tend to **OVERTURN** the wall and which tends to make it slide along the base. (See Fig. 6.)

To resist these **OVERTURNING** and **SLIDING-TENDENCIES**, the weight of the wall combined with the pressure of the earth behind it should produce a resultant which satisfies the following conditions. First, its **MAGNITUDE** should not be great enough to cause a unit pressure on the foundation-bed greater than the masonry can safely bear; secondly, it should pass within the **MIDDLE THIRD** of the base so that the stress over the entire area of the base will be a **COMPRESSIVE** stress; and thirdly, it should make an angle with a normal to the plane of the foundation-bed not greater than the **ANGLE OF FRICTION** between the stone, brickwork, mortar, or other masonry of the footings and the sand, clay, or rock of the foundation-bed.

In order to determine these conditions, the **CENTER OF GRAVITY** of the cross-section of the wall must be determined and a vertical line drawn through this point until it intersects the line of the **EARTH-THRUST** produced. It is at this intersection of the **LINES OF ACTION** of the two forces that their **RESULTANT** is found. To find the **CENTER OF GRAVITY** of the cross-section of the wall, the method of dividing the trapezoid into two triangles has been followed, the center of gravity of each triangle being found and these two points being joined by a line. The intersection of this line with the median line drawn between the base and top of the wall is the center of gravity of the trapezoid. In this example, for convenience, the scale used for the composition of the forces of the pressure of the earth and the weight of the wall is one-half the scale used for the resolution of the forces representing the weight of the earth-prism.

In the first trial, shown by the green lines, the first and third conditions necessary to insure stability are fulfilled; but the second is not, the resultant passes outside the **MIDDLE THIRD** of the base. This indicates, theoretically, a **TENSILE** stress or a tendency for the joints at the back of the wall to open. Another trial, therefore, is shown with the red lines, the thickness of the wall being increased as shown by the rectangle  $CC'D'D$ . In this second trial the **WEIGHT OF THE WALL** is necessarily increased while the **EARTH-THRUST** remains the same. As in this case the resultant passes within the middle third, it is concluded that a wall of these dimensions, 5 ft base by 10 ft height and with 10° batter, will be safe and will properly resist the thrust of the earth-lining.

**Details of Construction.** Retaining-walls are generally built with a **BATTER**, that is, a **SLOPING** face, as walls of this form are the strongest for a given amount of material; and if the courses are **INCLINED DOWN TOWARDS THE BACK**, the tendency to slide on each other will be resisted, and it will not be necessary to depend upon the adhesion of the mortar. The importance of making the resistance independent of the adhesion of the mortar is obviously very great, as it would otherwise be necessary to delay the backing up of the wall until the mortar is thoroughly set, which might require several months.

In brickwork it is advisable to let every third or fourth course below the frost-line project an inch or two. This increases the friction of the earth against the wall and causes the resultant of the forces acting behind the wall to become nearly vertical, and to fall farther within the base, increasing the stability.

It also conduces to strength to make the courses of varying heights through the thickness of the wall, and to have some of the stones, especially those at the back, sufficiently high to extend through two or three courses. By means the whole masonry becomes more effectually interlocked or bolted together as one mass and is less liable to bulge. The courses of masonry are often laid with their beds *SLOPING IN*, as in Fig. 15, to overcome the tendency of the courses to slide on each other.

Where the ground freezes to a great depth, the back of the wall should be *SLOPED FORWARD* for three or four feet below its top surface, as at *OC* (Fig.

O




Fig. 11. Retaining-wall for Deep-freezing Earth

Fig. 12. Retaining-wall with Rectangular Cross-section



Fig. 13. Retaining-wall with Triangular Cross-section

and this slope should be quite smooth, so as to lessen the hold of the frost and prevent displacement.

Figs. 12, 13, 14 and 15 show the approximate *RELATIVE VERTICAL SECTION AREAS* of walls of different shapes that would be required to resist the pressure of a bank of earth 12 ft high. The first three examples are calculated to resist the maximum thrust of wet earth, while the last shows the modified form usually adopted in practice.




Fig. 14. Retaining-wall with Triangular Cross-section

**Notes on the Thickness of Retaining-Walls.** As has been stated, about the only practical rules for retaining-walls are the empirical rules based upon experience and tests. Trautwine\* gives the following Table III for the thickness at the base of vertical retaining-walls with a sand backing deposited in the usual manner. The first column contains the vertical height *CD* (Fig. 16) of the earth as compared with the vertical height of the



Fig. 15. Retaining-wall with Sand Back

wall, *AB*. The latter is assumed to be 1, so that the table begins with a backing of the same height as the wall. These vertical walls may be built to any extent not exceeding 1 1/4 in to 1 ft, or 1 in 8, without affecting stability and without increasing the base.


If the wall is built as in Fig. 17, with the ground practically level with the top, the top of the wall should be not less than 18 in thick, and the thickness at *a*, *c*, etc., just above each step, should be from one-third to two-fifths

\* The Civil Engineer's Pocket-Book, John C. Trautwine.

**Table III. Proportions of Retaining-Walls**  
(Thickness of wall at the base in parts of the height, *AB*, Fig. 16)

Height of the earth measured with the height of the wall above ground	Wall of cut stone in mortar	Wall of rubble or brick, good mortar	Wall of good, dry rubble
1	0.35	0.40	0.50
1.1	0.42	0.47	0.57
1.2	0.46	0.51	0.61
1.3	0.49	0.54	0.64
1.4	0.51	0.56	0.66
1.5	0.52	0.57	0.67
1.6	0.54	0.59	0.69
1.7	0.55	0.60	0.70
1.8	0.56	0.61	0.71
2	0.58	0.63	0.73
2.5	0.60	0.65	0.75
3	0.62	0.67	0.77
4	0.63	0.68	0.78
6	0.64	0.69	0.79
14	0.65	0.70	0.80
25	0.66	0.71	0.81
or more	0.68	0.73	0.83

from the top of the wall to each of these levels. If the earth is banked to the top of the wall, the thicknesses should be increased as indicated by the table given above. If built upon ground that is affected by frost or surmounter, the footings should be carried sufficiently below the surface of the ground at the base to insure against heaving or settling.



**Fig. 17. Retaining-wall with Stepped Back**

With the constantly increasing purposes, there has come, also, the material. Figs. 18,\* 19\* and 20\* for retaining-walls to satisfy the

, Taylor and Thompson.

requirements of banks 5, 10 and 20 ft high. The wall shown in Fig. 18 is reinforced at intervals with COUNTERFORTS. The walls themselves in Figs. 18 and 19 act as CANTILEVER BEAMS. The FOOTINGS, in all three cases, are subjected to two principal external forces, the resultant of the pressure




Fig. 18. Reinforced-concrete Retaining-wall, 5 ft High



Fig. 19. Reinforced-concrete Retaining-wall, 10 ft High

upward pressure of the foundation-bed and the resultant of the lateral pressures of the fill. In Fig. 20 the COPING acts as a BEAM IN BOTH ENDS, with a span equal to the distance between the counterforts and loaded with the proper proportion of the load due to the pressure of the fill behind the wall and transmitted to the coping by the wall. The coping itself in this case acts as a FLOOR-SLAB supported on all four sides and subjected to an approximately evenly distributed load. The counterforts are in the form of cantilever beams. The MAXIMUM BENDING MOMENTS for these various cases can be determined (Chapter IX) and the necessary DIMENSIONS and REINFORCEMENT to be provided decided by the rules given in Chapter XXIV.

### 3. Breast-Walls

**Breast-Walls.** Where the ground to be supported is firm, and the surface is horizontal, the office of a BREAST-WALL (Fig. 8) is more to protect than to retain the earth. It should be borne in mind that a trifling force skillfully applied to broken ground will keep in its place a mass of material, which, if once allowed to move, would crush a heavy wall. Great care, therefore, should be taken



the newly opened ground to the influence of air and water longer than is for sound work, and to avoid leaving the smallest space for motion between the back of the wall and the ground. The strength of a breast-wall must proportionately increased when the strata to be supported incline down

1-3'0"

14'0"

Fig. 20. Reinforced-concrete Retaining-wall with Counterforts and Apron

the wall; where they incline down from it, the wall need be little more than facing to protect the ground from disintegration. The preservation of the NATURAL DRAINAGE is one of the most important points to be noted in the erection of breast-walls, as upon this their stability in a measure depends. No rule can be given for the best way to do this; it must be for attentive consideration in each particular case.

#### 4. Vault-Walls

**Vault-Walls.** In large cities it is customary to utilize the space under the street for storage or other purposes. This necessitates a wall at the curb-side to hold back the earth and the street-pressures and also the weight of the pavement. Where practicable the space should be divided by partition-walls every 10 ft, and when this is done the outer wall may be advantageously constructed of bricks in the form of arches, as shown in Fig. 21. The THICKNESS

of the arch should be at least 16 in for a depth of 9 ft and the rise of arch from one-eighth to one-sixth of the span. If partitions are not y




Fig. 21. Vault-wall with Partitions

cable, each sidewalk-bearing be supported by a heavy I column, with either flat or mental arches between, of brick or concrete. Fig. shows a detail of the outer of the vault under the sidewalk around the Singer building in New York City. These walls are of a core formed by two brick arches with vertical built between the flanges 8-in vertical steel I spaced about 5 ft apart bedded at the bottom in concrete footing. Their top

joined by 6-in horizontal I beams and braced laterally by the sidewalk-5 ft apart. The arches themselves are segmental, with a rise of about

Fig. 22. Vault-walls of Singer Building, New York City

and are built up solid against an 8-in outside face-wall. A 4-in plain wall is built inside against the flanges of the vertical beams, inclosing mental air-chambers in front of each arch.

\* From The Engineering Record, Feb. 16, 1898.

## CHAPTER V

## STRENGTH OF BRICKS, STONE, MASS-CONCRETE AND MASONRY

By

THOMAS NOLAN

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

## 1. Crushing Strength of Stonework, Brickwork, Bricks, etc.

**Stresses in Masonry.** By the term **STRENGTH OF MASONRY** is generally meant its resistance to a direct **COMPRESSIVE** force or load, and this is the only stress to which masonry should be subjected. Stone lintels and footings are subjected to a **TRANSVERSE** or **BENDING** stress, but they can hardly be included in the term masonry, as they consist of single pieces. There are also stresses due to bend and to split apart in brick walls and piers, as they are usually built in proportion to their lateral dimensions, but the stresses thus developed cannot be accurately determined and should be avoided as much as possible. It is impossible to fix values for the strength of brickwork or stonework with the same exactness possible for wooden or steel members, for the reason that there is not only a great variation in the strength of different kinds of brick and stone, even when taken from the same kiln or quarry, but the strength of walls and piers is also greatly affected by the kind and quality of the mortar used, the way in which the work is built and bonded, and the amount of moisture in the materials when they are laid. All that can be done, therefore, is to give values which will be safe for the different kinds of masonry built in the usual manner.

**Working Compressive Strength of Masonry.** The building laws of most of the larger cities of this country specify the maximum loads per square foot to be placed upon different kinds of masonry, and these laws must govern architects in such cities. When there is no restriction of this kind, Table I gives a pretty good idea of the maximum loads which it is safe to put upon the different kinds of work mentioned. Table II gives the maximum safe loads specified in the building laws of several cities, and the remaining tables of the book give records of numerous tests made to determine the ultimate compressive strengths of various kinds of bricks, building stones, mortars and concrete, and are of value in determining the safe loads for special cases. In determining the safe compressive resistance of masonry from tests on the ultimate compressive strength of work of the same kind, a factor of safety of at least 20 should be allowed for piers and 20 for arches.

Table I. Safe Working Loads for Masonry

## BRICKWORK IN WALLS OR PIERS

	Tons per square foot	
	Eastern	Western
Bricks in lime mortar.....	7	5
Bricks in hydraulic-lime mortar.....	...	6
Bricks in natural-cement mortar, 1 : 3.....	10	8
or pressed bricks in lime mortar.....	8	6
or pressed bricks in natural-cement mortar.....	12	9
or pressed bricks in Portland-cement mortar....	15	12½

Piers exceeding in height six times their least lateral dimensions should be increased 4 in in lateral dimensions for each additional 6 ft.

STONEWORK

	Total square
Rubble walls, irregular stones.....	
Rubble walls, coursed, soft stone.....	
Rubble walls, coursed, hard stone.....	5 to 10
Dimension-stone, squared, in cement mortar:*	
Sandstone and limestone.....	10 to 15
Granite.....	20 to 30
Dressed stone, with 1/4-in dressed joints, in Portland-cement mortar: *	
Granite.....	
Marble or limestone, best.....	
Sandstone.....	

The height of columns should not exceed eight times the least diameter, the least diameter is sufficiently greater than necessary for the strength of material used.

CONCRETE †

Portland-cement mortar, 1 : 8, 6 months, 10 tons; 1 year, 15 to 20 tons  
Natural-cement mortar, 1 : 6, 6 months, 3 tons; 1 year, 5 to 8 tons

HOLLOW TILE

Safe loads per square inch of effective bearing parts

Hard fire-clay tiles.....	80
Hard ordinary clay tiles.....	60
Porous terra-cotta tiles.....	40

MORTAR

In 1/2-in joints, 3 months old

	Total square
Portland-cement mortar, 1 : 4.....	
Natural-cement mortar, 1 : 3.....	
Lime mortar, best.....	8 to 10
Portland-cement mortar, 1:2, 1/4-in joints, bedding iron plates	

The values given above are generally very conservative. The leading architects and engineers of Chicago recommended for that city in 1908 the following SAFE WORKING PRESSURES for brick and stone masonry and concrete:

Common bricks, crushing strength 1 800 lb. per sq in:	Lb per sq in	Total
In lime mortar.....	100	
In lime-and-cement mortar.....	125	
In natural-cement mortar.....	150	
In Portland-cement mortar.....	175	

\* Limestone ashlar is usually set in (1) lime mortar, (2) puzzolan, natural mortar, or other non-staining cement mortar, or (3) mortar composed of lime and Portland cement.

† See pages 283 to 287.

	Lb per sq in	Tons per sq ft
Hard, common bricks, crushing strength equal to 7500 lb per sq in:		
1 part Portland cement, 1 lime-paste and 3 sand..	175	12 $\frac{3}{4}$
1 : 3 Portland-cement mortar.....	200	14 $\frac{3}{4}$
Round and sewer-bricks, crushing strength equal to 5000 lb per sq in: 1 : 3 Portland-cement mortar..	250	18
Facing bricks, in 1 : 3 Portland-cement mortar.....	350	25 $\frac{1}{4}$
Concrete, natural cement, 1 : 2 : 5.....	150	10 $\frac{1}{4}$
Concrete, Portland cement, 1 : 3 : 6, machine-mixed..	300	21 $\frac{3}{4}$
Concrete, Portland cement, 1 : 3 : 6, hand-mixed.....	250	18
Concrete, Portland cement, 1 : 2 : 4, machine-mixed...	400	28 $\frac{1}{4}$
Concrete, Portland cement, 1 : 2 : 4, hand-mixed.....	350	25 $\frac{1}{4}$
Brick, uncoursed, in lime mortar.....	60	4 $\frac{1}{4}$
Brick, uncoursed, in Portland-cement mortar.....	100	7 $\frac{1}{4}$
Brick, coursed, in lime mortar.....	120	8 $\frac{3}{4}$
Brick, coursed in Portland-cement mortar.....	200	14 $\frac{3}{4}$
Ashlar, limestone, in Portland-cement mortar.....	400	28 $\frac{1}{4}$
(See note on limestone ashlar, page 266.)		
Ashlar, granite, in Portland-cement mortar.....	600	43 $\frac{1}{4}$
Committee on Code Requirements for Indiana limestone recommends:		
Limestone-ashlar masonry, in lime mortar, equivalent to 1 : 3 cement-and-lime mortar.....	200 to 250	14 $\frac{3}{4}$ to 18
Natural-cement-and-lime mortar, 1 : 3.....	400 to 500	28 $\frac{1}{4}$ to 36

Table II. Comparison of Building Laws \*

Materials	Boston, 1915	Buffalo, 1909	New York, 1917	Chicago, 1916	St. Louis, 1907	Philadelphia, 1914	Denver, 1898
Allowable pressures in tons per sq ft							
Granite, cut.....	60-72	.....	72	43	.....	.....	40
Granite and limestone, cut...	40	.....	43-50	29	.....	.....	.....
Limestone, hard cut.....	30	.....	29	29	.....	.....	12
Hard-burned bricks in Portland-cement mortar.....	18-20	12	18	12 $\frac{1}{2}$	21 $\frac{1}{2}$	.....	.....
Hard-burned bricks in natural-cement mortar.....	.....	9	15	10 $\frac{1}{2}$	.....	15	9
Hard-burned bricks in cement-and-lime mortar...	12-14	.....	11 $\frac{1}{2}$	.....	11 $\frac{1}{2}$	12	.....
Hard-burned bricks in lime mortar.....	6-8	6	8	7	11	8	8
Hard-burned bricks in Portland-cement mortar.....	.....	12	.....	18	.....	.....	.....
Hard-burned bricks in natural-cement mortar.....	.....	9	.....	.....	.....	.....	12
Granite stone in natural-cement mortar.....	.....	5†	8†	.....	.....	10	12
Portland-cement concrete in foundations, 1 : 2 : 4.....	25-30	4	36	18-28§	18	15	10
Natural-cement concrete in foundations, 1 : 2 : 4.....	.....	.....	15	10 $\frac{1}{2}$	.....	.....	4

\* Notes, page 287, relating to building laws and working loads for masonry, etc.

† Portland-cement mortar. § In Portland-cement mortar, 10; in lime-cement mortar, 8.

|| According to mixture. || 1 : 2 : 5 mixture.

**Brick Piers.** As a rule brickwork is subject to its full safe resistance when used in piers, and in small sections of walls, under bearing-plates. In the latter case but a few courses receive the full load, and hence a greater stress may be allowed than for piers. Values for computing the area of bearing plates are given in Chapter XIII. Aside from the quality of the work and materials the two elements which most influence the strength of brick piers are the ratio of height to least lateral dimension and the method of bearing. When the height of a brick pier exceeds six times its least lateral dimension the load per square foot should be reduced from the values given in Table I.

**Formulas for the Safe Strength of Brick Piers exceeding six diameters in height.** From the records of numerous tests on the strength of brick piers, from some formulas published \* by Ira O. Baker, and also from personal observation, Mr. Kidder deduced the following formulas for the maximum working loads for first-class brickwork in piers whose height exceeds six times the least lateral dimension.

For piers laid with rich lime mortar:

$$\text{Safe load per square inch} = 110 - 5 H/D$$

For piers laid with 1 : 2 natural-cement mortar:

$$\text{Safe load per square inch} = 140 - 5 \frac{1}{2} H/D$$

For piers laid with 1 : 3 Portland-cement mortar:

$$\text{Safe load per square inch} = 200 - 6 H/D$$

$H$  representing the height in feet, and  $D$  the least lateral dimension in feet.

For a pier 20 ft high and 2 ft square these formulas will reduce the safe load to 4.3 tons per sq ft for lime mortar, 6.1 tons for natural-cement mortar, and 10 tons for Portland-cement mortar. No pier over 8 ft high should be less than 12 by 12 in in cross-section and when from 6 to 8 ft high piers should be at least 8 by 12 in in cross-section.

The following is the Chicago law (1914): "Isolated piers of concrete or masonry shall not be higher than six times their smallest dimension and the above unit stresses ‡ are reduced according to the following formula

$$P = C (1.25 - H/20 D)$$

in which  $P$  is the reduced allowed unit load,  $C$  the unit stress above which failure occurs,  $H$  the height of the pier in feet and  $D$  the least dimension of the pier. No pier shall exceed in height twelve times the least dimension. The weight of the pier shall be added to other loads in computing the load on the pier.

Brick piers intended to carry more than 50% of the safe loads given in Table I should not be built in freezing weather nor with dry bricks. Lime mortar should not be used for building piers that are to receive their full load for more than three months.

**Effect of Bond on the Strength of Brickwork.** Brick piers, at the point of destruction, always fail by the splitting and bulging out.

\* In the Brickbuilder, April, 1898.

† For piers faced with pressed bricks, laid with joints  $\frac{1}{4}$  in or less in thickness and backed with common bricks in lime mortar, only the dimensions of the backing are considered in figuring their strength. If the backing is laid in cement mortar and the face-bricks are well tied to the backing, the full section of the pier may be considered. For piers veneered with stone or terra-cotta, 4 in thick, only the strength of the backing is considered.

‡ These are in general the "safe working pressures" for brickwork previously recommended by the Chicago architects and engineers in 1908.

themselves, and not by direct crushing of the bricks or mortar, showing joints are weakest in their bond and in the tensile or transverse strengths of bricks. It is very important, therefore, to have the brickwork well bonded, all joints filled with mortar or grouted. The strength of a brick pier intended to carry an extreme load would probably be increased by bonding frequently with hoop-iron in addition to the regular brick-bond.\*

**Bond-Stones in Brick Piers.** Many competent architects and builders believe that the strength of a brick pier is increased by inserting bond-stones, 15 to 18 in in thickness and the full size of the pier in cross-section, every 3 or 4 in in height.

For example, the Building Laws for the City of New York (1916) require piers every 30 in in height, and at least 4 in in thickness, to be built into walls which contain less than 9 superficial feet of section, and which support any beam, girder, arch, or column on which a wall rests, or lintel spanning over 10 ft and supporting a wall. The New York laws allow perpendicular steel or cast-iron plates of the full cross-section of the pier to be used instead of the bond-stones. On the other hand, there are many first-class masons who consider that bond-stones in a brick pier do more harm than good. The author is of the opinion that this is generally the case. The Boston Building Laws do not require intermediate bond-stones. If bond-stones are used, they should be bedded so as to bear rather more heavily on the inner core of the pier than on the outer 4 in, for unless this is done the outer shell will take most of the load, and will be likely to bulge away from the core. A pier which supports a girder or column should have a cap-stone or iron plate of great strength to distribute the pressure over the cross-section of the pier.

**Walls Faced with Stone, Terra-Cotta, or Cement Blocks.** Brick walls faced with blocks or ashlar of any material should always have the backing laid in cement mortar or in cement-and-lime mortar, unless the backing is very thick, that is, 30 in or more. The aggregate thickness of the mortar joints in the backing is so much greater than in the facing, that any shrinkage or contraction of the mortar tends to throw undue weight on the facing and to separate it from the backing. Veneering generally should be tied to the backing with iron rods every 18 in in height. Stone courses, up to about 36 in in height, should have anchors in the bed-joints only. Anchors are placed in the side joints also, when the height of the courses is more than 36 in. The Building Laws of several large cities require that all bearing walls faced with brick be laid in running bond, and all walls faced with stone ashlar less than 8 in thick shall be of such thickness as to make the wall independent of the facing and of the thickness required for unfaced walls. Ashlar 8 in thick and bonded into the backing may be counted as part of the thickness of the wall.

**Grouting.**† It is contended by persons having large experience in building masonry carefully grouted, when the temperature is not lower than 40° F., will give the most efficient result. Many of the largest buildings in New York have grouted walls. The Mersey docks and warehouses at Liverpool, and, one of the greatest pieces of masonry in the world, were grouted about 1850. There are many engineers and others who do not believe in grouting, claiming that the materials tend to separate and form layers.

**Crushing Height of Bricks and Stone.** If we assume that the weight of brickwork is 120 lb per cu ft, and that it would commence to crush under 700 lb

per sq in, the manner in which brick piers fail is excellently shown by illustrations on page 79 of *Brickbuilder* for May, 1896.

† *American Architect*, July 21, 1887, page 11.

per sq in, then a wall of uniform thickness would have to be 840 ft high the bottom courses would commence to crush from the weight of the brick above. Average sandstones, at 145 lb per cu ft, would require a column 5 ft high to crush the bottom stones, and an average granite, at 165 lb per cu ft, would require a column 10 470 ft high. The Merchants' shot-tower at New York is 246 ft high, and its base sustains a pressure of 6½ tons per sq ft, the weight being long tons of 2 240 lb. The base of the granite pier of Saltash Bridge (designed by Brunel), of solid masonry to the height of 96 ft, and supporting the ends of iron spans of 455 ft each, sustains 9½ tons per sq ft.

**Stone Piers.** Piers of good strong building stone laid in courses with the cross-sections of the piers, with the top and bottom courses bedded true and even, may be built to support very heavy loads. The height of such piers, however, should not exceed ten times the least lateral dimension, and when it exceeds eight times the thickness, the load should be reduced. The thickness should not exceed ¾ in in thickness and should be spread with 1 : 2 Portland cement mortar, kept back 1 in from the face of the pier to prevent spalling the edges. A test of the strength of a limestone pier 12 in square is described under Marbles and Limestones, in this chapter. Rubble-work should not be used for piers whose height exceeds five times the least dimension, or in which the latter is less than 20 in.

**Records of Tests on the Crushing Resistance of Bricks.** Table III gives the results of some tests on bricks, made under the direction of Mr. J. B. in behalf of the Massachusetts Charitable Mechanics' Association.

Table III. Ultimate and Cracking Strengths of Bricks

Kind of brick	Size of test-specimen	Area of face, sq in	Commenced to crack under lb per sq in	Ultimate strength, lb per sq in
Philadelphia face-bricks.....	Whole bricks	33.7	4 303	6 000
Philadelphia face-bricks.....	Whole bricks	32.2	3 400	5 000
Philadelphia face-bricks.....	Whole bricks	34.03	2 879	4 000
Average.....	.....	.....	3 527	5 000
Cambridge bricks (Eastern).....	Half-bricks	10.89	3 670	5 000
Cambridge bricks (Eastern).....	Whole bricks	25.77	7 760	10 000
Cambridge bricks (Eastern).....	Half-bricks	12.67	3 393	5 000
Cambridge bricks (Eastern).....	Half-bricks	13.43	3 797	5 000
Average.....	.....	.....	4 655	5 000
Boston Terra-Cotta Co.'s bricks..	Half-bricks	11.46	11 518	15 000
Boston Terra-Cotta Co.'s bricks..	Whole bricks	25.60	8 593	10 000
Boston Terra-Cotta Co.'s bricks..	Whole bricks	28.88	3 530	5 000
Average.....	.....	.....	7 880	10 000
New England pressed bricks.....	Half-bricks	12.95	3 862	5 000
New England pressed bricks.....	Half-bricks	13.2	8 180	10 000
New England pressed bricks.....	Half-bricks	13.30	2 480	5 000
New England pressed bricks.....	Half-bricks	13.45	4 535	5 000
Average.....	.....	.....	4 764	5 000



specimens were tested in the government testing-machine at Watertown, and great care was exercised to make the tests as perfect as possible. The parallel plates between which the bricks are crushed are fixed in one position, it is necessary that each specimen tested should have perfectly parallel faces. The bricks which were tested were rubbed on a revolving bed until the top and bottom faces were perfectly true and parallel. The preparation of the specimens in this way required a great deal of time and expense; and it was so difficult to prepare some of the harder bricks that they had to be broken and only one-half a brick prepared at a time.

The Philadelphia bricks used in these tests were obtained from a Boston manufacturer, and were fair samples of what is known in Boston as Philadelphia Face-bricks. They were very soft bricks.

The Cambridge bricks were the common bricks, such as are made around Boston. They are about the same as the Eastern bricks.

The Boston Terra-Cotta Company's bricks were manufactured of a rather heavy body, and were such as are often used for face-bricks.

The New England pressed bricks were hydraulic-pressed bricks, and were as hard as iron.

Some tests made on the same machine by the United States Government in 1881, the average strength of three (M. W. Sands) Cambridge, Mass., face-bricks was 13 925 lb, and of his common bricks, 18 337 lb per sq in, one brick showing the enormous strength of 22 351 lb per sq in. This was a very hard brick. Three bricks of the Bay State (Mass.) manufacture showed an average strength of 11 400 lb per sq in. The New England bricks are among the hardest and strongest in the country, those in many parts of the West not being one-fourth the strength given above; so that in heavy buildings, where the strength of the bricks to be used is not known by actual tests, it is advisable to use the bricks tested. Ira O. Baker reported some tests on Illinois bricks, made on the 100 000-pound testing-machine at the University of Illinois in 1880 and 1889, which give for the crushing strength of soft bricks, 674 lb per sq in, the average of three face-bricks, 3 070 lb per sq in, and for four paving-bricks, 4 975 lb per sq in. In nearly all makes of bricks it will be found that the soft bricks are not as strong as the common bricks.

#### Tests of the Strength of Brick Piers Laid with Various Mortars.\*

Tests were made for the purpose of testing the strength of brick piers laid up with different cement mortars, as compared with those laid up with ordinary mortar. The bricks used in the piers were procured at M. W. Sands's yard, Cambridge, Mass., and were good ordinary bricks. They were from the same lot as the samples of common bricks described above. The piers were 12 in in cross-section, and nine courses, or about 22½ in high, except the first, which was but eight courses high. They were built Nov. 29, 1881, at the storehouses at the United States Arsenal in Watertown, Mass. In order to have the two ends of the piers perfectly parallel surfaces, a coat of pure cement, about ½ in thick, was put on the top of each pier and the foot was coated in the same cement. On March 3, 1882, three months and five days later, the tops of the piers were dressed to plane surfaces at right-angles to the sides of the piers. On attempting to dress the lower ends of the piers, the cement grout peeled off, and it was necessary to remove it entirely and put on a new coat of cement similar to that on the tops of the piers. This was allowed to set for one month and sixteen days, when the piers were tested. At that time the piers were four months and twenty-six days old. As the piers were in cold weather, the bricks were not wet. They were built by a skilled

\* Made under the direction of F. E. Kidder.

bricklayer and the mortars were mixed under his superintendence. They were made with the government testing-machine at the Arsenal. The following table is arranged so as to show the result of these tests, and to afford a means of comparison of the strength of brickwork with different mortars. The piers generally failed by cracking longitudinally, and some of the bricks were crushed. The Portland cement used in these tests was made by Brooks & Company, of England. Roman cement is a European natural cement, usually, although not always, containing a low percentage of magnesia. It sets rapidly, has about one-third the strength of true Portland cement, and is much weakened by the addition of sand.

Table IV.    Tests of Piers of Common Bricks Laid in Different Mortars

Piers 8 by 12 in in section, built of common bricks.	Ultimate strength of pier,  lb	Pressure per sq in under which pier commenced to crack,  lb	Ultimate strength,  lb
Lime mortar.....	150 000	833	
Lime mortar, 3 parts; Portland cement, 1 part.....	290 000	1 875	
Lime mortar, 3 parts; Newark and Rosendale cements, 1 part.....	245 000	1 354	
Lime mortar, 3 parts; Roman cement, 1 part.....	195 000	1 041	
Portland cement, 1 part; sand, 2 parts.....	240 000	1 302	
Newark and Rosendale cements, 1 part; sand, 2 parts.....	205 000	708	
Roman cement, 1 part; sand, 2 parts.....	185 000	1 770	

As the actual strength of brick piers is a very important consideration in building-construction, some tests, made by the United States Government at Watertown, Mass., and contained in the report of the tests made on the government testing-machine for the year 1884, are given as being of much interest. Three kinds of bricks were represented in the construction of the piers, and mortars of different composition, ranging in strength from lime mortar to Portland-cement mortar. The piers ranged in cross-section dimensions from 8 by 8 to 16 by 16 in, and in height from 16 in to 10 ft. They were of the age of from 18 to 24 months.

Table V gives the results obtained and memoranda regarding the character of the piers.

Table VI gives the results obtained from tests of the strength of bricks made at the McGill University, Montreal, laboratories, in March, 1897.

**Recent Tests of Brick Piers.\*** Elaborate tests of brick piers, with the results,† were made in 1908 by A. N. Talbot and D. A. Abrams at the University of Illinois Experiment Station. Table VII is a summary of these tests. The tests were made on sixteen brick piers, the lengths of which varied from 4 to 10 ft.

\* See, also, results of important tests made in 1914 and 1915 at Columbia University, New York, by J. S. Macgregor.

† Bulletin 27, University of Illinois Engineering Experiment Station, Sept. 2, 1909.

# Crushing Strength of Stonework, Brickwork, Bricks

Number of test	Nominal dimensions		Composition of mortar	Weight per cubic foot lb	Sectional area sq in	First crack lb	Ultimate strength			
	Height ft	Cross-section in					Total lb	Lb per sq in	Tons per sq ft	Per cent of single brick
Built of face-bricks (M. W. Sands, Cambridge, Mass.)										
11	1	4	1 lime mortar, 3 sand	137.4	57.00	85 000	143 600	2 520	181.4	18.1
320	6	8	1 lime mortar, 3 sand	133.5	57.76	50 000	108 400	1 877	135.1	13.5
12	1	4	1 Portland-cement mortar, 2 sand	136.3	57.76	200 000	218 100	3 776	271.8	27.1
321	6	8	1 Portland-cement mortar, 2 sand	133.5	57.76	85 000	129 900	2 249	161.9	16.2
283	2	0	1 lime mortar, 3 sand	.....	132.25	140 000	257 100	1 940	139.7	13.9
284*	2	0	1 lime mortar, 3 sand	.....	113.76	90 000	226 100	1 990	143.3	14.3
332	10	0	1 lime mortar, 3 sand	131.7	132.25	70 000	199 800	1 511	108.8	10.9
334†	10	0	1 lime mortar, 3 sand	125.0	115.44	100 000	208 600	1 807	130.1	13.0
286	2	0	1 Portland-cement mortar, 2 sand	.....	132.25	200 000	486 000	3 670	264.2	26.4
326	10	0	1 Portland-cement mortar, 2 sand	132.2	132.25	200 000	298 000	2 253	162.2	16.2
Built of common bricks (M. W. Sands)										
10	1	4	1 lime mortar, 3 sand	135.6	60.80	66 000	148 800	2 440	175.6	13.3
12½	6	8	1 lime mortar, 3 sand	133.6	62.40	.....	96 100	1 540	110.8	8.4
281	2	0	1 lime mortar, 3 sand	.....	138.06	75 000	296 400	2 150	154.8	11.7
282‡	2	0	1 lime mortar, 3 sand	.....	119.58	120 000	244 600	2 050	147.6	11.2
331	9	9	1 lime mortar, 3 sand	131.5	138.06	70 000	154 300	1 118	80.5	6.1
330§	10	0	1 lime mortar, 3 sand	136.0	115.50	70 000	183 300	1 587	114.3	8.6
329	10	0	1 Portland-cement mortar, 2 sand	131.0	138.06	.....	276 600	2 003	144.2	10.9
387	2	8	1 Portland-cement mortar, 2 sand	.....	256.00	460 000	696 000	2 720	195.8	14.8
328	10	0	1 Portland-cement mortar, 2 sand	.....	256.00	340 000	483 100	1 887	135.8	10.3

Number test	Nominal dimensions		Composition of mortar	Weight per cubic foot lb	Sectional area sq in	First crack lb	Ultimate strength			
	Height ft	Cross- section in					Total lb	Lb per sq in	Tons per sq ft	Per cent of single brick
Built of common bricks (Bay State)										
285	2	0	1 lime mortar, 3 sand	.....	146 41	95 000	201 000	1 370	98 6	12.0
288	6	0	1 lime mortar, 3 sand	.....	144 00	70 000	163 200	1 133	81 6	9 9
289	6	0	1 lime mortar, 3 sand	119 7	144 00	100 000	174 300	1 210	87 1	10.6
291*	6	0	1 lime mortar, 3 sand	118.2	144 00	80 000	191 600	1 331	95 8	11 7
292†	6	0	1 lime mortar, 3 sand	118 1	156 25	110 000	189 200	1 211	87.2	10.6
293	7	10	1 lime mortar, 3 sand	120.0	144 00	100 000	169 100	1 174	84 6	10.3
297	10	0	1 lime mortar, 3 sand	118.0	144 00	90 000	133 100	924	66 6	8.1
335	10	0	1 lime mortar, 3 sand	107.0	96 00	35 000	90 200	940	67.7	8.2
333	10	0	1 lime mortar, 3 sand	118.7	192 00	80 000	148 500	773	55 7	6.8
301	6	0	1 Rosendale-cement mortar, 2 lime mortar. ....	120.6	144 00	160 000	237 000	1 646	118 5	14.4
293	6	0	1 Rosendale-cement mortar, 2 sand	123 0	144 00	250 000	264 000	1 972	142.0	17.3
300	6	0	1 Portland-cement mortar, 2 lime mortar . . . . .	120.3	144 00	190 000	203 200	1 481	101.6	12 4
294	6	0	1 Portland-cement mortar, 2 sand	119 7	144 00	220 000	258 000	1 792	129 0	15 7
290	6	0	Neat Portland-cement mortar	126 6	144 00	280 000	342 000	2 375	171.0	20.8

\* Joints broken every six courses.

† Bricks laid on edge.

Table VI. Tests of Brick Piers, McGill University Laboratories, March, 1897

Dimensions of piers	Composition of mortar	Kind of bricks	Crushing strength, lb per sq in		Age
			At first crack	Maximum load	
by 8.1 in, 11.6 in high; joints 1 in thick	1 Canadian Portland-cement mortar, 3 sand	Ordinary well-burned flat bricks	822	1 234	3 weeks
by 8.1 in, 11.6 in high; joints 1 in thick	1 German Portland-cement mortar, 3 sand	Ordinary well-burned flat bricks	990	1 230	3 weeks
by 8.3 in, 10.5 in high; joints 1 in thick	1 English Portland-cement mortar, 3 sand	La Prairie pressed bricks, keyed on one side	1 130	1 524	3 weeks
by 8.4 in, 10.75 in high; joints 1 in thick	1 Belgian Portland-cement mortar, 3 sand	La Prairie pressed bricks, keyed on one side	1 204	1 985	3 weeks

Table VII. Tests of Brick Piers, Made at the University of Illinois  
The amounts given are average values

Characteristics of piers	Average unit load lb per sq in	Ratio of strength of pier to strength of brick	Ratio of strength of pier to strength of first of series	Crushing strength of 6-in mortar-cubes lb per sq in	Ratio of strength of pier to strength of cubes
Shale building bricks					
1 in. bid, 1 : 3 Portland-cement mortar, 67 days	3 363	0.31	{ Standard 1.00 }	2 870*	1.17
1 in. bid, 1 : 3 Portland-cement mortar, 6 months	3 950	0.37	1.18	.....	.....
1 in. bid, 1 : 3 Portland-cement mortar, eccentrically loaded, 68 days	2 800	0.26	0.83	.....	.....
1 in. bid, 1 : 3 Portland-cement mortar, 67 days	2 920	0.27	0.87	2 870*	1.05
1 in. bid, 1 : 5 Portland-cement mortar, 65 days	2 225	0.21	0.66	1 710	1.30
1 in. bid, 1 : 3 natural-cement mortar, 67 days	1 750	0.16	0.52	305	5.75
1 in. bid, 1 : 2 lime mortar, 67 days	1 450	0.14	0.43	.....	.....
Underburned clay bricks					
1 in. bid, 1 : 3 Portland-cement mortar, 63 days	1 060	0.27	0.31	2 870*	0.37

\*Average value based on thirteen tests of 1 : 3 Portland-cement mortar-cubes, 60 days

10 to 10½ ft. The lateral dimensions were 12¼ by 12¼ in. Two of bricks were used, an excellent class of building bricks and a soft grade se as representative of inferior bricks. Different qualities of mortar and di grades of workmanship were employed. Compression-tests of single gave these average results. For hard, shale building bricks, bedded in p crushing strength, flatwise, 10 700 lb per sq in; modulus of rupture, edge 6-in span, 1 670 lb per sq in. For soft or underburned clay bricks, cr strength, flatwise, 3 900 lb per sq in; modulus of rupture, 480 lb per The Macgregor tests showed that maximum strength with minimum c for brickwork is obtained with mortar made of ½ cu ft of Portland c ½ cu ft of hydrated lime and 3 cu ft of sand, or a 1: 1: 6 mixture.

**Tensional Strength of Brickwork.** See Chapter II, page 179.

2. Strength of Terra-Cotta and Terra-Cotta Piers

**General Properties of Terra-Cotta.** The lightness of terra-cotta, cor with its great compressive strength, together with its relatively high res to the effects of heat and fire, renders it an especially valuable building m Terra-cotta for building purposes, whether plain or ornamental, is ge made of hollow blocks formed with webs to give extra strength and ke work true while drying. This is necessary because good, well-burned, cotta cannot safely be made more than about 1 ½ in thick, whereas, w quired to bond with brickwork, it must be at least 4 in thick. When the cotta work does not project beyond the face of the wall these hollow spa generally filled with concrete or brickwork. For additional data regard fire-resisting properties and strength of ornamental and structural terra see Chapter XXIII, pages 814, 815, and 816.

**Crushing Strength of Terra-Cotta Blocks.** Some exhaustive expe made by the Royal Institute of British Architects give the following re the crushing strengths of terra-cotta blocks:

	Crushin per
Solid block of terra-cotta.....	523
Hollow block of terra-cotta, unfilled.....	186
Hollow block of terra-cotta, lightly made and unfilled.....	80

Tests of terra-cotta manufactured by a New York Company, whi made at the Stevens Institute of Technology in April, 1888 gave these

	Crushing weight per cu in	Crushin per
Terra-cotta block, 2-in square, red.....	6 840 lb or	492
Terra-cotta block, 2-in square, buff.....	6 236 lb or	449
Terra-cotta block, 2-in square, gray.....	5 126 lb or	369

In tests for the New York Building Department, made at Columbia Un dense terra-cotta blocks developed a net crushing strength of 4 721 lb p or 340 tons per sq ft, and semiporous, 2 168 lb per sq in or 156 tons p these results being in each case the averages of a series of tests. (See p

From these results, the writer would place the safe working strength cotta blocks in the wall at 5 tons per sq ft when unfilled, and 10 tons when filled solid with brickwork or concrete.

**Tests of Terra-Cotta Piers.** Tests \* of terra-cotta block piers were made at the same time (January, 1907, and January, 1908) that the brick piers listed in Table VII were made. The tests were made on terra-cotta piers, heights of which varied from 9 ft 9 in to 12 ft 7¾ in. The lateral dimensions varied from 8½ by 8½ in to 17½ by 17½ in. "The piers were built and tested in two lots, an interval of about one year separating the times of making the piers. The two lots of piers were built of blocks which came in different shapes. The cement used was the same brand in both years, although the lots

**Table VIII. Tests of Terra-Cotta Piers, Made at the University of Illinois**  
The amounts given are average values. The table gives results of tests of piers of uniform shape, except for the concave-end blocks. The piers recorded in this table had heights of 12 ft 6 in by 12 ft 6 in.

Characteristics of piers	load lb per sq in	to strength of block, gross area	to strength of first of series	mortar- cubes lb per sq in	of pier to strength of cubes
Well laid, 3 : 3 Portland- cement mortar, concentric- ally loaded . . . . .	4 300*	0.83*	{Stand- ard 1 00*}	. . . . .	1.26*
Well laid, 1 : 3 Portland- cement mortar, eccentric- ally loaded . . . . .	3 470	0.65	0.81*	3 090	1.12
Poorly laid, 1 : 3 Portland- cement mortar, concentric- ally loaded . . . . .	3 305	0.64	0.76	3 130	1.05
Poorly laid, 1 : 3 Portland- cement mortar, eccentric- ally loaded . . . . .	3 110	0.60	0.75	3 025	1.06
Well laid, 1 : 3 Portland- cement mortar, concentric- ally loaded . . . . .	3 050	0.59	0.71	3 370	0.88
Well laid 1 : 5 Portland- cement mortar, concentric- ally loaded, inferior burned blocks † . . . . .	3 350	0.65	0.78	. . . . .	. . . . .
Well laid with concave ends, 3 : 1 Portland-cement mortar . . . . .	2 970	0.86	0.69	. . . . .	. . . . .

\* Estimated.

† Blocks of good quality, but underburned.

different. The terra-cotta block piers were generally made in sets of two, one of which was constructed and loaded similarly. Three of the piers were laid up poorly (poorly laid); the remainder were built with the usual care given to masonry work. The load was applied to the piers in different ways, although generally continued continuously to failure." Some piers were loaded eccentrically and one was loaded both concentrically and eccentrically, but the eccentric load was not sufficient to cause failure.

Revised Bulletin No. 27, University of Illinois Engineering Experiment Station, Sept. 1908.

**Comparison of Results of Tests of Brick and Terra-Cotta Piers**—the tests summarized in Tables VII and VIII, “both the brick piers and terra-cotta block piers gave high strengths in all cases where strong mortar and care in building were used. The effect of the strength of the mortar was apparent in the carrying capacity developed in the piers, smaller loads being indicated for piers built with 1 : 5 Portland-cement mortar than for those with Portland-cement mortar, and still smaller loads for those with 1 : 2 lime mortar. The effect of the quality of the bricks is shown in the piers made with inferior bricks, these piers carrying only 31% as much as piers built with the best grade of bricks. In the case of the terra-cotta piers, the blocks which were culled out as somewhat inferior gave a pier-strength which was perhaps less than the piers built with superior blocks. The effect of the attempt to represent hurried or careless workmanship in two brick piers and in three terra-cotta block piers was a loss in strength of about 15% and 25% respectively.”

“In the well-built brick piers, concentrically loaded, the ratio of strength of pier to compressive strength of individual brick ranged from 31 to 37% in the underburned clay-brick pier the ratio was 27%. In the terra-cotta block piers, concentrically loaded, the ratio of strength of pier to that of individual block was 74% (an incompleting test) and 83, 85 and 89% for the others. The higher ratio found for the terra-cotta block piers than for brick piers suggests that the ability of individual pieces to resist transverse forces is an element in the strength of the completed pier; and this suggestion may have an important bearing on the advantageous size of the component blocks which may be used in a compression-piece where great strength is required.

“The strength of the pier is greater than that of the mortar-cubes in both brick and terra-cotta block piers, except the soft-brick piers, which had blocks of low compressive strength. Both the strength of the individual brick blocks and the strength of the mortar affect the resistance of the pier, and the relative effect of the two depends upon the character of the materials. It is evident, however, that the better the individual piece the more important it is to have a mortar of high resisting strength.

“The results obtained in applying the loads eccentrically were found to agree very well with those obtained from ordinary analysis.

“The quality of workmanship in laying up such columns has an important bearing upon the resisting strength. The work of building piers, however, is not difficult and requires only ordinary care. Full joints and an even bed are important, and the ordinary workman ought to be able to construct piers of great strength. In the tests made on piers intended to represent poor or careless workmanship, the decrease in strength was not as much as anticipated. However, it must be understood that careful and trustworthy work is essential and that a few poor joints will materially reduce the strength of the structure. Wherever good material and good workmanship are insured the strength of masonry of this kind may be utilized with advantage.”

**Strength of Terra-Cotta Brackets or Consoles.** A cornice-modelling made by the Northwestern Terra-Cotta Company, 11½ in high at the wall and 8 in wide on the face, and with a projection of 2 ft, was built into a wall and its upper surface loaded with 2 tons of pig iron without any effect upon the modelling. Another bracket, 5½ in high, 6 in wide and with a 14-in projection, made at the East, broke at the wall-line under 2 650 lb, while a duplicate of it sustained 2 400 lb for one month without breaking.\*

**The Weight of Terra-Cotta.** The weight of terra-cotta in solid blocks is 120 or 122 lb per cu ft. When made in hollow blocks 1½ in thick the weight

\* See *The Brickbuilder*, Vol. 7, page 142.



from 65 to 85 lb per cu ft, the smaller pieces weighing the most. For 12 by 18 in or larger on the face, 70 lb per cu ft will probably be a fair average. The tables in the manufacturers' catalogues give the various bearing-weights per square foot, thicknesses of parts, sizes of blocks, etc., for porous and semiporous blocks for all purposes.

## 2. Crushing Strength of Building Stones

### (1) Sandstones

**Longmeadow, Mass., Stone.\*** Reddish-brown sandstone, two blocks about 17 1/4 in in cross-section and 8 in in height.

Block No. 1 commenced to crack at 10 333 lb per sq in, and flew from the line in fragments at 13 596 lb per sq in.

Block No. 2 commenced to crack at 3 012 lb per sq in and failed completely at 121 lb per sq in.

**Sandstone from Norcross Brothers' Quarries, East Longmeadow, Mass.,**

**Sauksbury Stone.\*** Block No. 1, 4 by 4 by 8 in high, commenced to crack at 7 350 lb and failed at 8 812 lb per sq in.

Block No. 2, 4 by 4 by 8 in high, commenced to crack at 6 500 lb and failed at 692 lb per sq in.

**And Sauksbury Stone.\*** Block No. 1, 4 by 4 by 8 in high (about), commenced to crack at 12 716 lb and failed at 13 520 lb per sq in.

Block No. 2, same size as No. 1, commenced to crack at 13 953 lb and failed at 1650 lb per sq in.

**White Stone.\*** Block No. 1, 6 by 6 by 6 in, commenced to crack at 12 590 lb and failed at 12 619 lb per sq in.

Block No. 2, same size as No. 1, commenced to crack at 12 185 lb and failed at 1874 lb per sq in.

**Green Stone from the Shaler & Hall Quarry Company, Portland, Conn.†** Results of the tests are as follows:

**Table IX. Crushing Strength of Brown Sandstone**

Dimensions			Sectional area	First crack	Ultimate strength	Classification
Height	Compressed, surface					
in	in		sq in	lb	lb per sq in	
5	2.50	2.45	6.13	84 800	13 980	1st quality
5	2.48	2.47	6.13	81 700	13 330	1st quality
5	3.00	2.95	8.85	123 200	13 920	2d quality
5	2.98	2.97	8.85	122 000	15 020	3d quality
5	2.55	2.53	6.45	63 850	9 900	Bridge
5	2.48	2.52	6.25	58 340	9 330	Bridge

**Green Stone from the Middlesex Quarry Company, Portland, Conn.†** Four cubical blocks, about 1 1/2 in square. Pressure per square inch at time of failure: No. 1, 10 928 lb; No. 2, 10 322 lb; No. 3, 8 252 lb and No. 4, 6 322 lb.

These tests were made with the United States testing-machines at Watertown, Mass.

These tests were made by Colt's Patent Fire-arms Manufacturing Company.

These tests were made with the United States testing-machines at Watertown, Mass.

Red Sandstone \* from Greenlee & Son's Quarries at Manitou, Col. specimen failed at 11 000 lb per sq in; weight, 140 lb per cu ft.

Light-Red Laminated Sandstone,† from St. Vrain Cañon, Col., a very stone, excellent for walks and foundations. Crushing strength on bed, 1 lb per sq in; weight, 150 lb per cu ft.

Gray Sandstone † (free-working) from Trinidad, Col. Crushing str 10 000 lb per sq in; weight, 145 lb per cu ft.

Gray Sandstone † from Fort Collins, Col. (laminated and similar in q to the St. Vrain stone). Crushing strength on bed, 11 700 lb per sq in; w 140 lb per cu ft. One ton of this stone measures just a perch in the wall.

(a) Granite

Red Granite † from Platte Cañon, Col. Crushing strength per square 14 600 lb; weight per cubic foot, 164 lb.

(3) Lava Stones

Lava Stone from the Kerr Quarries, near Salida, Col. Four cubical bl The results of the tests are as follows:

Table X.    Crushing Strength of Lava Stone

Dimensions			Sectional area  sq in	First crack  lb	Ultimate streng	
Height  in	Compressed surface  in				lb	lb 1 sq
4.00	4.00	4.00	16.00	165 900	165 000	10
4.00	4.00	4.00	16.00	174 100	174 100	10
2.00	2.00	1.99	3.98	36 400	37 100	9
1.99	1.99	1.99	3.96	38 200	38 200	9

Lava Stone,‡ Curry's Quarry, Douglas County, Col. Crushing str 10 675 lb per sq in; weight, 119 lb per cu ft. Experience has shown th stone is not suitable for piers, or where any great strength is required cracks \ ery easily.

(4) Marble and Limestone

White marble quarried at Sutherland Falls, Vt. Two cubical blocks 6 in square.§

Block No. 1 commenced to crack at 9 750 lb per sq in and failed sudd 11 250 lb per sq in.

Block No. 2 did not crack until it suddenly gave way at 10 243 lb per

Test of a Limestone Pier. A pier of Lemont limestone, 1 sq ft in cross- and 9 ft in height, composed of seven stones with bearing surfaces plane- fectly true and parallel to the natural bed and the joints washed with grout of the best English Portland cement, was tested at the Watertown A for William Sooy Smith, and only commenced to crack when the full of the machine, 400 tons, was exerted.

\* These tests were made with the United States testing-machines at Wat Arsenal, Mass.

† From tests made for the Board of Capitol Managers of Colorado by State E E. S. Nettleton, in 1885, on 2-in cubes.

‡ From tests made by the Denver Society of Civil Engineers, in 1884, also cubes.

§ Tested at the United States Arsenal, Watertown, Mass.

## (5) Bricks and Various Stones

Table XI gives the crushing strength of various kinds of bricks and building stones, the pressure being normal to the plane of the bed.

**Table XI. Crushing Strength of Bricks and Stone \***  
Pressure at right-angles to bed

Kind of brick or stone	Crushing strength, lb per sq in
<b>Bricks:</b>	
Common, Massachusetts.....	10 000
Common, St. Louis, Mo.....	6 417
Common, Washington, D. C.....	7 370
Paving, Illinois.....	6 000 to 13 000
<b>Granite:</b>	
Barre, Fox Island, Me.....	14 875
Bay, Vinal Haven, Me.....	13 000 to 18 000
Westerly, R. I.....	15 000
Exeter and Quincy, Mass.....	17 750
Wford, Conn.....	22 600
Green Island, N. Y.....	22 250
East St. Cloud, Minn.....	28 000
Garrison, Col.....	13 000
Red Platte Cañon, Col.....	14 600
<b>Sandstones:</b>	
Glass Falls, N. Y.....	11 475
Rock, Ill.....	12 775
Bedford, Ind.....	6 000 to 10 000
Water, Ind.....	8 625
Red Wing, Minn.....	23 000
Millwater, Minn.....	10 750
<b>Limestones:</b>	
Dorchester, N. B. (brown).....	9 150
Mary's Point, N. B. (fine grain, dark brown).....	7 700
Connecticut brown stone, † (on bed).....	7 000 to 13 000
Longmeadow, Mass. (reddish brown).....	7 000 to 14 000
Longmeadow, Mass. (average, for good quality).....	12 000
Little Falls, N. Y.....	9 850
Medina, N. Y.....	17 000
Madison, N. Y. (red).....	18 000 to 42 000
Cleveland, Ohio.....	6 800
North Amherst, Ohio.....	6 212
Mass, Ohio.....	8 000 to 10 000
Lancaster, Pa.....	12 810
Mad du Lac, Minn.....	8 750
Mad du Lac, Wis.....	6 237
Madison, Col. (light red).....	6 000 to 11 000
St. Vrain, Col. (hard laminated).....	11 505
<b>Schists:</b>	
Mass.....	22 900
Bedford, Vt.....	10 746
Montgomery Co., Pa.....	10 000
Albion, Cal.....	17 783
Albion.....	12 156
<b>Slates:</b>	
North River, N. Y.....	13 425

For more complete tables of the strength, weight and composition of building stones, see data, tables, etc. by Professor Thomas Nolan in Kidder's Building Construction, Part I, Masons' Work.  
The stone should not be set on edge.

**(6) Additional Data on the Strength of Building Stones**

**Average Data for Building Stones of Good Quality.** The following average relative values\* are given by R. P. Miller.† **SANDSTONE:** weight, 150 lb per cu ft; specific gravity, 2.40; crushing strength, 8 000 lb per sq in; shearing strength, 1 500 lb per sq in; modulus of rupture, 1 200 lb per sq in; modulus of elasticity, 3 000 000 lb per sq in. **GRANITE:** weight, 170; specific gravity, 2.72; crushing strength, 15 000; shearing strength, 2 000; modulus of rupture, 1 500; modulus of elasticity, 7 000 000. **LIMESTONE:** weight, 170; specific gravity, 2.72; crushing strength, 6 000; shearing strength, 1 000; modulus of rupture, 1 200; modulus of elasticity, 7 000 000. **MARBLE:** weight, 170; specific gravity, 2.72; crushing strength, 10 000; shearing strength, 1 400; modulus of rupture, 1 400; modulus of elasticity, 8 000 000. **SLATE:** weight, 185; specific gravity, 2.80; crushing strength, 15 000; modulus of rupture, 1 200; modulus of elasticity, 14 000 000. **TRAP-ROCK:** weight, 185; specific gravity, 2.96; crushing strength, 20 000.

The following average relative values are given by A. I. Frye.‡ The following are the results of tests made on small cubes of the materials. **SANDSTONE:** crushing strength, 9 000 lb per sq in; **GRANITE and GNEISS:** crushing strength, 17 733 lb per sq in. **LIMESTONES and MARBLES:** crushing strength, 14 000 lb per sq in. **SLATE:** crushing strength, 10 000; ultimate tensional strength, 3 000; modulus of rupture, 5 000 lb per sq in.

When stones are not tested, Frye recommends the following average values for ultimate strengths to be used in determining the safe stresses. **SANDSTONE:** crushing strength, 5 000; ultimate tensional strength, 150; modulus of rupture, 1 200 lb per sq in. **GRANITE and GNEISS:** crushing strength, 12 000; modulus of rupture, 1 600 lb per sq in. **LIMESTONES and MARBLES:** crushing strength, 8 000; ultimate tensional strength, 800; modulus of rupture, 1 200 lb per sq in.

The following working unit stresses in pounds per square inch for stone or single blocks of stone are recommended by W. J. Douglass.§ **SANDSTONE:** compression, 700; tension (direct and flexural), 75; shear, 150. **GRANITE, SYENITE and GNEISS:** compression for hard, 1 500; for medium, 1 200; for soft, 1 000; tension (direct and flexural), 150; shear, 200. **LIMESTONES:** compression for hard, 1 000; for medium, 800; for soft, 700; tension (direct and flexural), 125; shear, 150. **MARBLE:** compression for hard, 900; for soft, 700; tension (direct and flexural), 125; shear, 150. **BLUESTONE FLAGGING:** compression, 1 500; tension (direct and flexural), 200.

**4. Compressive Strength of Mortars and Concretes**

**The Compressive Strength of Lime Mortar.** The crushing strength of a common lime mortar, six months old and composed of 1 part lime to 3 parts sand by measure, varies from 150 to 300 lb per sq in or from 10.8 to 21.6 lb per sq ft. Lime mortar alone should never be used where any but moderate loads are to bear upon the work, nor where the full loading is to be applied until the mortar has had time to harden.

\* The values in all cases are as follows: weight, in lb per cu ft; strength, modulus of rupture and modulus of elasticity, in lb per sq in.

† American Civil Engineers' Pocket Book (1912), page 357.

‡ Civil Engineers' Pocket-Book (1913), page 511.

§ American Civil Engineers' Pocket Book (1912), page 575.

**Compressive Strength of Natural-Cement Mortar.** The crushing strength of natural-cement mortar, neat, averaged, for 7 days, 2 010; for 28 days, 2 689; for 3 months, 3 646; and for 6 months, 5 052 lb per sq in. When mixed with 2 parts of standard quartz sand, the mortar averaged in crushing strength, for 7 days, 940; for 28 days, 1 390; for 3 months, 1 730; and for 6 months, 2 012 lb per sq in. For 2 years, an additional increase of 18% and may be assumed for the neat and sanded mortars, respectively, of natural cement.

**Compressive Strength of Portland-Cement Mortar.** The crushing strength of Portland-cement mortar, neat, averaged, for 7 days, 5 915; for 28 days, 7 041; for 3 months, 7 347; and for 6 months, 9 760 lb per sq in. When mixed with 3 parts of standard quartz sand, the mortar averaged, in crushing strength, for 7 days, 941; for 28 days, 1 290; for 3 months, 1 490; and for 6 months, 1 529 lb per sq in. When mixed with 3 parts of Ottawa sand, the mortar averaged, in crushing strength, for 7 days, 1 199; for 28 days, 1 796; for 3 months, 1 887; and for 6 months, 2 181 lb per sq in. For 2 years, an additional increase of about 16% and 18% may be assumed for the neat and sanded mortars, respectively, of Portland cement.

**Relation of Compressive to Tensile Strength of Mortars.** While it is stated as a very general guide that the compressive strength of hydraulic-cement mortars is from six to ten times the tensile strength, these ratios are variable and cannot be used as a reliable basis for calculations. The tensile strength of Portland-cement mortars, under normal conditions, increases rapidly during the first few days, the rate of change gradually falling off. In the case of the tensile strength is generally from one-half to two-thirds of the ultimate strength, which is practically reached in 2 or 3 months. The compressive strength, however, continues to increase with age and the rate of increase varies according to a somewhat different law.

**Compressive Strength of Concrete.** There are many reasons for variations in the values of the compressive strength of concrete and the principal factors are (1) the quality of the cement, (2) the size and character of the aggregates, (3) the quantity of the cement to a unit volume of the concrete, (4) the manner of mixing, (5) the density of the mixture, (6) the conditions under which it seasons, and (7) its age; and of these various conditions governing the determination of the compressive strength the most important are generally the proportions of the different ingredients of the mixture and its quality. Although tables of average values of ultimate crushing strengths of concrete are published and are of general value, they may be misleading unless used with caution. In important operations it is advisable to have the concrete tested and to adjust by trial the character and proportions of the ingredients until the required strength is obtained.

**Specimen for Compression-Tests.** For compression-tests of concrete in general, 4 to 12-in cubes of the mixture have been the standard test-specimens; but since the advent of reinforced-concrete construction and the growth of the importance of determining the elastic properties of concrete, it has been found that a cylindrical test-specimen gives more definite results than a cube. A common shape of such cylinder is one in which the height is about three times the diameter, and the cylinders are not less than 12 in. It is found that the compressive strengths of these cylinders of concrete are from 10 to 15% less than those of the cubes, but for cylinders of

Some compression-tests made by W. P. Taylor on cylindrical specimens 1 in in height, 1 1/4 in in diameter and 1 sq in in cross-section.

still greater slenderness the compressive strengths remain about constant heights up to about seven diameters.

**Compression-Tests on Concrete Cubes.** From some tests made for the Boston Elevated Railway Company at the Watertown Arsenal, on cubes of concrete made with five brands of Portland cement, coarse sand and broken stone up to  $2\frac{1}{2}$ -in size, having 49.5% voids, the following average values of the compressive strengths were obtained:

**Table XII.    Compression-Tests on Concrete Cubes**

Mixtures	7 days lb per sq in	1 month lb per sq in	3 months lb per sq in	6 months lb per sq in
1 : 2 : 4	1 560	2 400	2 900	3 820
1 : 3 : 6	1 310	2 160	2 520	3 090

**Compression-Tests on Concrete-Cylinders.** For cylindrical test specimens of concrete, made under reasonably good conditions as to character of materials and care in mixing, an average compressive strength of about 1 600 lb per sq in is usually developed in a 1 : 2 : 4 Portland-cement concrete 1 to 2 months; and of about 1 600 lb per sq in in a 1 : 3 : 6 mixture. Under the conditions are unusually favorable somewhat higher values than those obtained, but when the materials and workmanship are poor the ultimate compressive stresses are lower.

**Increase in Compressive Strength of Portland-Cement Concrete.** With regard to the increase of compressive strength of Portland-cement concrete with age, tests show that the ultimate compressive strength is nearly reached in 60 days, at which time the strength varies from 80 to 90% of its value in 1 year.

**Ultimate Strengths of Natural-Cement Concrete.** For natural-cement concrete, the ultimate compressive, tensile and shearing strengths and modulus of rupture may be taken at about one-half the corresponding values for Portland-cement concrete, unless natural cements of known and tested strength are employed.

**Strength of Unreinforced Concrete Columns.** Short concrete columns of lengths up to 10 or 15 diameters, develop a crushing strength of from

**Table XIII.    Compression-Tests on Unreinforced Concrete Columns**

Kind of concrete	Average age days	Average ultimate compressive stress lb per sq in
1 : 1 : 2	60	3 600*
1 : 1½ : 3	60	2 270
1 : 2 : 4	60	1 600
1 : 2½ : 5	60	1 200
1 : 3 : 6	60	935
1 : 3½ : 7	60	745
1 : 4 : 8	60	600

\* This value was estimated as it was beyond the range of the tests.

less than that for short prismatic or cylindrical specimens. In Table XIII the results obtained by A. N. Talbot \* on short, round, unreinforced stone-cement columns, 12 in in diameter and 10 ft in length. A wet-mixture concrete of the different proportions shown, the forms were removed after 14 days and the columns were tested through 60 days. The values given in the table were deduced from the straight-line formula

$$\text{Ultimate compressive strength, lb per sq in} = \frac{12\,000}{S_a + S_t} - 400$$

which formula

$S_a$  = the ratio of sand to cement

$S_t$  = the ratio of stone to cement

For example, in the 1 : 3 : 6 mixture,  $S_a = 3$  and  $S_t = 6$

**Crushing Strength of Concrete Affected by Area of Bearing Surface.** George Hool states † that if a load is applied over the central part, only, of the bearing surface of a concrete test-specimen in compression, the unit load is greater than if it is applied over the entire surface; and this is due to the fact that the outer parts tend to assist the inner part to resist the stress. This is shown by tests made on some of the 12-in concrete cubes used in the tests for the Boston Elevated Railway Company and referred to in the preceding paragraphs. Thirty-six of these concrete cubes were crushed by applying a load over the entire upper bearing-surface of 144 sq in and an equal number of similar concrete cubes were then crushed by applying the stress over a smaller area, 10 by 10 in, or 100 sq in. After this, the cubes of a third set were crushed by the application of the stress over the still smaller area, 8 by 8¼ in, or 66 sq in. The tests of the second set gave unit crushing strengths 12% higher than those of the first, and those of the third set unit crushing strengths 28% higher than those of the first.

**Working Stress for Bearing on Concrete.** "When compression is applied over a surface of concrete of at least twice the loaded area, a stress of 32.5% of the ultimate compressive strength may be allowed." ‡

**Working Stress for Axial Compression on Concrete.** "For concentric compression on a plain concrete column or pier, the length of which does not exceed 12 diameters, 22.5 % of the compressive strength may be allowed." \* (For the strength of reinforced-concrete columns, see Chapter XXIV, page 945.)

**Recommended Ultimate Compressive Strengths of Portland-Cement Concrete.** † Table XIV, of ultimate compressive strengths of concrete of different mixtures gives the values recommended by the American Society for Testing Materials, even though occasional tests show higher results. The values given are recommended as the maximum ultimate unit compressive strengths that should be used in design and on which the permissible working stresses should be based as a proper percentage of the same. The report referred to states, also, that "in selecting the permissible working stresses to be allowed for concrete, we should be guided by the working stresses usually allowed for other materials of construction, so that all structures of the same class, but composed of different materials, may have approximately the same degree of safety." (For working stresses for concretes, masonry, etc., see this chapter, pages 265 to 276.)

See University of Illinois Bulletin, No. 20, 1907, and Engineering News, Sept. 26,

see Reinforced Concrete Construction, Vol I., page 18, by George A. Hool.

Report of Committee on Concrete and Reinforced Concrete, of the American Society for Testing Materials, Nov. 20, 1912.

**Table XIV.    Ultimate Compressive Strengths of Different Mixtures of Portland-Cement Concretes**

Aggregates	Mixtures				
	1 : 1 : 2 lb per sq in	1 : 1½ : 3 lb per sq in	1 : 2 : 4 lb per sq in	1 : 2½ : 5 lb per sq in	1 : 3 lb sq
Granite, trap-rock.....	3 300	2 800	2 200	1 800	1
Gravel, hard limestone and hard sandstone.....	3 000	2 500	2 000	1 600	1
Soft limestone and sand- stone.....	2 200	1 800	1 500	1 200	1
Cinders .....	800	700	600	500	

**Effect of Consistency on the Crushing Strength of Concrete.**    Co  
that is mixed fairly dry and tamped until the moisture is brought to the su  
develops a somewhat greater compressive strength than concrete mixed  
more water. From a large number of tests \* average compressive streng  
wet, plastic and dry concretes were determined. The age of the concret  
1 year and 8 months, and five brands of cements were used. The mean  
pressive strengths were, for the wet concrete, 2 130; for the plastic,  
and for the dry, 2 350 lb per sq in.

In another series of tests † greater differences appeared. At the ag  
month the mean compressive strengths in pounds per square inch were, f  
wet concrete: granite, 3 155; gravel, 2 300; limestone, 4 195. For the m  
concrete: granite, 4 090; gravel, 3 545; limestone, 2 975. For the damp  
crete: granite, 4 520; gravel, 4 610; limestone, 4 365. At the end of 3 m  
the values for the granite aggregates were, for the wet concrete, 4 755; f  
medium, 4 990; and for the damp, 5 445.

**Effect of Size of Stone on the Compressive Strength of Concrete**  
may be stated, generally, that the use of stones of a maximum size cons  
with convenience generally results in a maximum compressive strength  
concrete. Stones of the larger sizes are generally more uniformly graded  
the smaller stones, and consequently grade better with the sand and give g  
strength. From tests ‡ made by W. B. Fuller, the average compressive stre  
at 140 days, of 1 : 9 concrete, were, for maximum size of stone ½ in, 1  
per sq in; for 1-in stone, 1 150 lb per sq in; and for 2¼-in stone, 1 400  
sq in.

**Comparison of Compressive Strengths of Gravel and Stone Conc**  
Concretes made with broken stone have, generally, a somewhat greater  
pressive strength than those made with gravel. From tests made by E. C  
the average compressive strength at 30 and 180 days, of concrete mad  
1½-in maximum-size broken stone, was 20% greater than that of concrete  
of gravel of about the same size, the percentage of voids being nearly the  
40% voids for the gravel and 47.4% voids for the broken stone. The a  
difference at 12 months, however, was reduced to 9%.

\* Made for G. W. Rafter. See "Tests of Metals," 1898.  
† Made in 1908. See Bulletin No. 344, United States Geological Survey.  
‡ See Trans. Am. Soc. C. E., Vol. 59, 1907.



**Effect of the Strength of the Aggregate on the Compressive Strength of Concrete.** The compressive strength of trap-rocks, granites and most limestones is relatively so great that it cannot reduce the strength of the concrete itself. Some sandstones, however, have a much lower average compressive strength, and if they are friable and soft may lower relatively the final strength of the concrete. A concrete of low strength results from using cinders for the aggregate.

**Building Laws for Working Loads on Masonry.\*** As previously mentioned (page 265) the building codes of most cities specify working loads to be used for masonry and as shown in Table II (page 267) these loads vary greatly. It is important, therefore, that the architect should be acquainted with the municipal code by which the construction of his building is governed. As building laws and regulations are constantly changing this information should be obtained from the code itself, care being taken that the latest edition and all supplements be consulted. A few requirements, peculiar to the codes in which they are found, will be cited.

The Chicago code (1916) gives for eight classes of brickwork bearing values ranging from 100 lb per sq in for common brick with good lime mortar to 350 lb per sq in for paving brick with 1 to 3 Portland-cement mortar. This code eliminates between concrete mixed by hand and by machine, values of from 100 to 350 lb per sq in being given for hand-mixed concrete and from 300 to 350 lb per sq in for the same mixture if mixed by machine. The values in the Chicago code are exceptionally low, common brick laid in lime mortar being rated but 3 tons and concrete in foundations but 4 tons per sq ft. The Louisville code introduces values for "Louisville-cement mortar." The practice of testing values of local material is to be commended. The Denver code gives values of 3 tons per sq ft on common brick with coal-dust in lime mortar, 3 tons for hollow tile in cement mortar and 8 tons for terra-cotta, solid, in cement. The Seattle code gives for the allowable compressive stress of mass concrete 80 per cent of its compressive strength in twenty-eight days. The building code recommended by the National Board of Fire Underwriters is followed by a number of cities. This code includes in its list of allowable compression values, 1000 lb per sq in for Portland-cement grout, neat, and 1500 lb per sq in for Portland-cement grout, neat, not over  $\frac{1}{2}$  in thick, between steel members in foundations. Natural-cement concrete values are given of 125 lb per sq in for a 1 : 2 : 4 mixture and 80 lb per sq in for a 1 : 2 : 5 mixture. The average ultimate compressive strength for terra-cotta blocks designed to be normally laid with the cells vertical, and which are tested with the cells in that position, must not be less than 1200 lb per sq in. The allowable working stress on such blocks must not exceed 120 lb per sq in. The average ultimate compressive strength for terra-cotta blocks designed to be normally laid with the cells horizontal, and which are tested with the cells in that position, must not be less than 800 lb per sq in. The allowable working stress on such blocks must not exceed 80 lb per sq in. Hollow building blocks may be filled solidly with Portland-cement mortar or cement mortar to increase the stability and to aid in distributing the load, but the allowable working stress on such blocks must not be greater than that permitted for unfilled blocks.

\*Compiled from valuable data from Robins Fleming. See, also, pages 265 to 267 of Table II, page 267.

## CHAPTER VI

### FORCES AND MOMENTS

By

MALVERD A. HOWE

PROFESSOR OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

#### 1. Composition and Resolution of Forces

**Composition and Resolution of Forces.** Imagine a round ball placed on a horizontal, frictionless surface at  $A$  (Fig. 1), the surface being perfectly level,




Fig. 1. Composition of Forces

the ball has no tendency to move until some force is applied to it. If, now, the force,  $P$ , is applied to the ball in the direction indicated by the line  $AB$ , the ball will move in that direction. If, instead of one force only, two forces,  $P$  and  $P_1$ , are applied to the ball, it will not move in the direction of either of the forces, but will move in the direction of the **RESULTANT** of these forces, or in the direction indicated by the line  $DA$ . If the magnitudes of the forces  $P$  and  $P_1$  are indicated by the lengths of the lines, then by completing the parallelogram  $ABDC$ , the diagonal  $DA$  represents the direction and magnitude of a single force which has the same effect on the ball as that resulting from the two forces  $P$  and  $P_1$ .

If, in addition to the two forces  $P$  and  $P_1$ , the third force,  $P_2$ , is applied, the ball will move in the direction of the resultant of all three forces, and this resultant is obtained by completing the parallelogram  $ADEF$ , of which the resultant  $DA$  and the force  $P_2$  are two adjacent sides. The diagonal  $R$  of this second parallelogram is the resultant of all three forces, and the ball will move in the direction  $Ae$ . In the same way the resultant of any number of forces may be found. Again, suppose a ball, whose weight is indicated by the length of the line  $W$  (Fig. 2), is suspended by two inclined cords. What are the magnitudes of the pulls or stresses which are developed in the cords and which keep the ball suspended at the point  $A$ ? This is the converse of the last case. Instead of finding the diagonal or the resultant, the diagonal, which is the line  $W$ , is given, and the sides of the parallelogram are to be found. To find these the lines representing the directions of  $P$  and  $P_1$  are prolonged and from  $B$  lines parallel to them are drawn to complete the parallelogram. Then  $CA$  is the required magnitude of the stress in cord  $P$ , and  $BC$  of that in cord  $P_1$ . Thus one force may have the same effect as many, or many may have the same effect as one.




Fig. 2. Resolution of Forces

**Forces Represented by Straight Lines.** In considering the action of forces it is convenient to represent them graphically by straight lines with heads, as in Fig. 3. The length of the line, if drawn to a scale of pounds, represents the **MAGNITUDE OF THE FORCE** in pounds; the position of the line indicates the direction of the force.

OF ACTION; the arrow-head indicates its SENSE or the direction in which it acts, and the point  $A$  its POINT OF APPLICATION. Thus the magnitude,




Fig. 3. Force Represented by a Straight Line

direction and point of application are indicated and the force is completely represented.

### Parallelogram of Forces.

If two forces acting at one point are represented in magnitude and direction by two straight lines inclined to each other, their resultant is the diagonal of the PARALLELOGRAM formed on those lines. Thus, if the lines  $AB$  and  $AC$  (Fig. 4) represent two forces acting at a point  $A$ , to find the force which will have the same effect as the two forces, the parallelogram is completed and the diagonal  $AD$  drawn. This represents the RESULTANT of the two forces. When the two given forces act at right angles to each other, the magnitude of the resultant is equal to the square root of the sum of the squares of the magnitudes of the other two forces.




Fig. 4. Parallelogram of Forces

**Triangle of Forces.** If three forces acting at a point are represented in magnitude and direction by the sides of a TRIANGLE taken in order, they are in EQUILIBRIUM. Let  $P$ ,  $Q$  and  $R$  (Fig. 5) represent three forces acting at the point  $O$ . If a triangle is drawn, like that shown at the right in Fig. 5, having sides respectively parallel to the directions of the forces and taken in the same order, the forces are in equilibrium. If such a triangle cannot be drawn, the forces are not in equilibrium.




Fig. 5. Triangle of Forces

**Polygon of Forces.** If any number of forces acting at a point can be represented in magnitude and direction by the sides of a POLYGON taken in order, they are in equilibrium. This follows directly from the preceding principles.

## 2. Moments of Forces

**Moments.** In considering the stability of structures and the strength of materials, we are often obliged to take into consideration the moments of forces acting on a structure or on some part of a structure; and a knowledge of the general PRINCIPLES OF MOMENTS is essential to the proper understanding of these subjects. When we speak of the MOMENT OF A FORCE, we must have in mind some fixed point or line with respect to which the moment is taken. The moment of a force with respect to any given point, or CENTER OF MOMENTS, is the product of the magnitude of the force and the perpendicular distance from the point to the LINE OF ACTION of the force; or, in other words, the moment of a force is the product of the magnitude of the force by



with which it acts. Thus if we have the force  $F$  (Fig. 6), and wish to find its moment with respect to the point  $P$ , we determine the perpendicular distance  $Pa$ , between the point and the line of action of the force, and multiply it by the magnitude of the force. For example, if the magnitude

of the force  $F$  is 500 lb and the distance  $Pa$  is 2 in, the moment of  $F$  with respect to the point  $P$  is  $500 \text{ lb} \times 2 \text{ in} = 1\,000 \text{ in-lb.}^*$

**Parallel Forces.** If any body is in a state of rest or equilibrium under the action of parallel forces, the sum of the forces acting in one direction equals the sum of the forces acting in the opposite direction.




Fig. 7. Algebraic Sum of Unlike Parallel Forces

Thus if we have the forces  $P^1, P^2, P^3$  and  $P^4$  acting on  $AB$  (Fig. 7), in a direction opposite to the forces  $P_1, P_2$  and  $P_3$ , then, if the body is in equilibrium, the sum of the forces  $P^2, P^3$  and  $P^4$  must equal the sum of the forces  $P_1, P_2$  and  $P_3$ .

**Parallel Forces Opposite in Direction.** If any number of parallel forces, acting in the same direction, act on a body in equilibrium, the sum of the moments of the forces tending to turn the body in one direction about any point is equal to the sum of the moments of the forces tending to turn the body in the opposite direction.

Let  $F_1, F_2$  and  $F_3$  (Fig. 8) represent three forces acting on the rod  $AB$ . If the rod is in equilibrium, the sum of the forces  $F_2$  and  $F_3$  is equal to  $F_1$ . Also, if we take the end of the rod,  $A$ , for the center of moments, the moment of  $F_1$  is equal to the sum of the moments of  $F_2$  and  $F_3$  about that point, because the moment of  $F_1$  measures the tendency to turn the rod CLOCKWISE, and the sum of the moments of  $F_2$  and  $F_3$  measure the tendency to turn the rod CONTRA-CLOCKWISE, and there is no more tendency to turn the rod one way than the other. For example, let the magnitude of forces  $F_2, F_3$  each be represented by 5 force-units, the distance  $Aa$  by 2 length-units and the distance  $AB$  by 4 length-units. The magnitude of the force  $F_1$  must equal the sum of the magnitudes of the forces  $F_2$  and  $F_3$ , or 10 force-units, and its moment with respect to any point in the plane of the forces must equal the sum of the moments of  $F_2$  and  $F_3$  with respect to the same point. If we take  $a$  as the center of moments, the moment of  $F_2 = 5 \times 2 = 10$ , and of  $F_3 = 5 \times 4 = 20$ . Their sum equals 30; hence the moment of  $F_1$  must be 30. Dividing 30 by the force  $F_1 = 10$  force-units, we have for the arm, 3 length-units; hence the force  $F_1$  must act at a distance of 3 units from  $A$  to keep the rod in equilibrium. If we take  $b$  as the center of moments, the force  $F_1$  has no moment, for the length of its lever-arm is zero; and, for equilibrium, the moment of  $F_2$  must equal the moment of  $F_3$  about the same point; or, as in this case, the magnitudes of the forces  $F_2$  and  $F_3$  are equal, they must both be applied at the same distance from  $b$ , showing that  $b$  must be half-way between  $a$  and  $F_1$ , as demonstrated before.




Fig. 8. Algebraic Sum of Moments of Unlike Parallel Forces

**Three Parallel Forces. THE PRINCIPLE OF THE LEVER.** This principle is based upon the two preceding propositions and is of great importance.

\* The expressions POUND-FEET and POUND-INCHES are often given to these units to distinguish them from FOOT-POUNDS and INCH-POUNDS, by which WORK is measured.

ex. If a body is in equilibrium under the action of three parallel forces in the same plane, each force is proportional to the normal distance between the other two. Thus, if, as in Figs. 9, 10 and 11, three forces,  $P_1$ ,  $P_2$ , and




Fig. 9. Principle of the Lever




Fig. 10. Principle of the Lever

on the rod  $AB$ , in order that it may be in equilibrium, the following must obtain between the magnitudes of the forces and the distances from their points of application;

$$\frac{P_1}{CB} : \frac{P_2}{AB} : \frac{P_3}{AC}$$

$$P_1 : P_2 : P_3 :: CB : AB : AC$$

is the case of the COMMON LEVER and shows the method of determining weight a given lever will raise. The proportion is also true for any arrangement of the forces (as shown in Figs. 9, 10 and 11), provided, of course, the forces are lettered in the order shown in the

example, let the distance  $AC$  be 6 in and the distance  $CB$  be 12 in. If a weight of 500 lb is applied at the point  $B$ , how much will it raise at the other end and what support will be required at point  $C$ ?

Applying the rule just given, we have the proportion:

$$P_3 : P_1 :: AC : CB \quad \text{or} \quad 500 : P_1 :: 6 : 12$$

$P_1 = 1000$  lb; or 500 lb applied at  $B$  will raise 1000 lb resting on or suspended at  $A$ . The supporting force at  $C$  must, by the principles of PARALLEL FORCES IN EQUILIBRIUM, be equal to the sum of the forces  $P_1$  and  $P_3$ , or 1500 lb in this case.




Fig. 11. Principle of the Lever

## 2. Center of Gravity

**General Principles.** The LINES OF ACTION of the force of gravity converge to the center of the earth; but the distance of the center of the earth from the bodies which we have occasion to consider, compared with the size of those bodies, is so great, that we may consider the lines of action of the forces as parallel. The number of the forces of gravity acting upon a body may be considered as equal to the number of particles composing the body. The CENTER OF GRAVITY of a body may be defined as the point through which the resultant of all the forces of gravity, acting upon the body, passes for every position of the body. If a body is supported at its center of gravity and turned about

that point, it will remain in equilibrium in all positions. The resultant of parallel forces of gravity acting upon a body is obviously equal to the weight of the body; and if a force, equal in magnitude to the resultant, is acting in a line passing through the center of gravity of the body, and in a direction opposite to that of the resultant, the body will be in equilibrium.

**Center of Gravity of a Straight Line.** The word LINE here means a material line whose transverse section is very small, such as a very fine wire. The center of gravity of a straight line or rod of uniform size and material is at its middle point. This proposition is too evident to require demonstration.

**The Center of Gravity of the Perimeter of a Triangle is at the center of the circle inscribed in the triangle formed by the lines joining the middle points of the sides of the given triangle.**




Fig. 12. Center of Gravity of Perimeter of Triangle

Let  $ABC$  (Fig. 12) be the given triangle.  $D$ ,  $E$  and  $F$  are the middle points of the sides  $AB$ ,  $AC$  and  $BC$  respectively. Connect the points  $D$ ,  $E$  and  $F$  by straight lines. The center of the circle inscribed in the triangle formed by these lines will be the center of gravity sought.

### Center of Gravity of Symmetrical Figures

The center of gravity of a line which is symmetrical with reference to a point is at that point. Thus the center of gravity of the circumference of a circle or of an ellipse is at the geometrical center of the figure. The center of gravity of the perimeter of an equilateral triangle, of a regular polygon, is at the center of the inscribed circle. The center of gravity of the perimeter of a square, rectangle, or parallelogram is at the intersection of the diagonals of those figures.

**Center of Gravity of a Surface.** A SURFACE here means a very thin plate or shell. If a surface can be divided by a line into two symmetrical halves, the center of gravity will be on that line; if it can thus be divided by two lines, the center of gravity will be at their intersection.

**Center of Gravity of Regular Figures.** The center of gravity of the surface of a circle or an ellipse is at the geometrical center of the figure. The center of gravity of the surface of an equilateral triangle or regular polygon, at the center of the inscribed circle. The center of gravity of the surface of a parallelogram, at the intersection of the diagonals; of the surface of a cylinder or of an ellipsoid of revolution, at the geometrical center of the body. The center of gravity of the convex surface of a right cylinder, at the middle point of the axis of the cylinder.

**Center of Gravity of Irregular Figures.** Any figure bounded by straight lines may be divided into rectangles and triangles, and, the center of gravity of each part being found, the center of gravity of the whole figure may be determined by treating the centers of gravity of the separate parts as particles. The weights are proportional to the areas of the parts they represent. (See Fig. 13.)

**Center of Gravity of Triangles.** To find the center of gravity of a triangle, draw a line from each of two angles to the middle of the opposite side. The intersection of the two lines is the center of gravity.

**Center of Gravity of Quadrilaterals.** To find the center of gravity of a quadrilateral, draw the diagonals, and from that end of each diagonal farthest from the intersection, lay off, toward the intersection, the distance equal to its shorter segment. The two points thus formed, together with the intersection of the diagonals, form a triangle, the center of gravity of which is the center of gravity of the quadrilateral.

tion, will form a triangle whose center of gravity is that of the quadrilateral. Thus, let Fig. 13 be a quadrilateral whose center of gravity is to be found. Draw the diagonals  $AD$  and  $BC$ , and from  $A$  lay off  $AF = DE$ , and from  $B$  lay off  $BH = CE$ . From  $E$  draw a line to the middle of  $FH$ , and from  $F$  a line to the middle of  $EH$ . The point of intersection of these two lines is the center of gravity of the quadrilateral. This is a method commonly used for finding the centers of gravity of the voussoirs of an arch.




Fig. 13. Center of Gravity of Quadrilateral

**Table of Centers of Gravity.** Let  $a$  be a line drawn from the vertex of a figure to the middle point of the base, and  $D$  the distance from the vertex to the center of gravity of the figure. Then (Fig. 14):

In an isosceles triangle.....	$D = \frac{3}{8} a$
In a segment of a circle, vertex at center of circle	$D = \frac{\text{chord}^3}{12 \times \text{area}}$
In a sector of a circle, vertex at center of circle	$D = R \times \frac{2 \times \text{chord}}{3 \times \text{arc}}$
In a semicircle, vertex at center of circle.....	$D = \frac{4R}{3\pi} = 0.4244 R$
In a quadrant of a circle.....	$D = \frac{3}{8} R$
In a semiellipse, vertex at center of circle.....	$D = 0.4244 a$
In a parabola, vertex at intersection of axis with curve.....	$D = \frac{3}{8} a$
In a cone or pyramid.....	$D = \frac{3}{4} a$







Fig. 14. Center of Gravity of Triangle, Segment and Sector

frustum of a cone or pyramid, let  $h$  = the height of the complete cone or pyramid,  $h_1$  = the height of the frustum, and let the vertex be at the apex of the complete cone or pyramid; then,

$$D = \frac{3(h^4 - h_1^4)}{4(h^3 - h_1^3)}$$



#### Center of Gravity of Two Heavy Particles

Let  $P$  be the weight of a particle at  $A$  (Fig. 15), and  $W$  that of a particle at  $C$ . The center of gravity is at some point,  $B$ , on the line joining  $A$  and  $C$ . The point  $B$  must be so situated that if the two particles were held by a stiff wire and supported at  $B$  by a force equal in magnitude to the sum of  $P$  and  $W$  they would be in equilibrium. The problem then is

#### Center of Gravity of Two Heavy Particles.

solved by the **PRINCIPLE OF THE LEVER**, and we have the proportion **Three Parallel Forces**. The Principle of the Lever),

$$P + W : P :: AC : BC$$

or

$$BC = \frac{P \times AC}{P + W}$$

If  $W = P$ , then  $BC = AB$ , or the center of gravity will be half-way between two particles. This problem is of great importance and has many practical applications.

**Center of Gravity of Several Heavy Particles.** Let  $W_1, W_2, W_3$  and  $W_4$  (Fig. 16) be the weights of the particles. Join  $W_1$  and  $W_2$  by a straight line and find their center of gravity  $A$ , as in preceding problem. Join  $A$  with  $W_3$  and find center of gravity  $B$ , which will be the center of gravity of the three weights  $W_1, W_2, W_3$ . Proceed in the same way with each weight. The last center of gravity found will be the center of gravity of the particles. In both of these cases the lines joining the particles are supposed to be horizontal lines or the horizontal projections of the straight lines which join the points.




Fig. 16. Center of Gravity of Several Heavy Particles

**Center of Gravity of Compound Sections Found by Moments.** To determine the center of gravity of a beam having an unsymmetrical cross-section

it is first necessary to determine the distance of the center of gravity of this section from the upper or lower surface of the beam. Various other computations also, involve finding the center of gravity of an irregular figure, so this problem is one of practical importance. If the figure of which the center of gravity is to be found can be divided into parts which are themselves regular figures, the readiest and simplest method of finding the distance of the center of gravity from one edge of the section is by means of **MOMENTS**. To explain this method assume a T-shaped section of uniform thickness, hinged on a wire  $XX$ , as in Fig. 17. The T section is made up of two rectangles, one forming the flange, the other the web. The center of gravity of each rectangle is at its own center of figure and may be readily found. If the T section is placed horizontally, as in the figure, the axis  $XX$  being fixed, it will immediately, by the force of gravity, revolve about the axis until it becomes vertical, and the sum of the moments of the forces causing the revolution is  $A' \times d' + A'' \times d''$ ,  $A'$  representing the weight of the web and  $A''$  the weight of the flange. To hold the T section in a horizontal position, there must be a moment of some force acting opposite, or upward, vertical direction and just equal to the sum of the two moments causing revolution downwards. If the force  $A$ , of this moment tending to cause revolution upward, is equal to the weight of the entire section, it must be applied at the center of gravity of the entire figure to maintain equilibrium. The moment just equal to the sum of the moments of the two downward




Fig. 17. Center of Gravity of Compound Sections by Moments



Moment of  $A$  is  $A \times d$ , therefore  $d$  is the distance from the end of the web, on the axis  $XX$ , to the center of gravity of the entire figure. Therefore,  $A \times d = A' \times d' + A'' \times d''$ ,

$$d = \frac{A' \times d' + A'' \times d''}{A} \quad (1)$$

Weight of any homogeneous material of uniform thickness is proportional to area.  $A$ ,  $A'$  and  $A''$  may be used to represent areas as well as weights. Using formula (1) as a rule, we have:

**Center of Gravity of Compound Figures.** The distance of the center of gravity of a compound figure from any line of reference is equal to the sum of products, obtained by multiplying the area of each of the simple parts into the distance of its center of gravity from the line of reference, divided by the area of the entire figure. This rule applies to any compound figure.

**Example I.** Assume that the T section shown in Fig. 17 has the dimensions indicated. Then  $A'$  equals 6,  $A''$  equals 8, and  $A$  equals 14 sq in; and  $d'$  equals 3 and  $d''$  equals  $6\frac{1}{2}$  in. The sum of the products of  $A'$  by  $d'$  and

Center of Gravity of Tees, Angles, Channels, etc.

$A''$  by  $d''$  is  $18 + 52$  or  $70$  sq in  $\times$  in, and this divided by  $14$  sq in, the area of the entire figure, gives  $5$  in for the distance  $d$ . The distance  $d$  of the center of gravity from the top of the webs, in each of the figures shown in Fig. 20, is found by the following formula:

$$d = \frac{\text{area of the web or webs} \times d'/2 + \text{area of flange} \times d''}{\text{area of the web or webs} + \text{area of flange}} \quad (2)$$

For a section like that shown in Fig. 18, in which  $A'$ ,  $A''$  and  $A'''$  represent the areas of the respective rectangles, the distance  $d$  of the center of gravity from the top may be found by the formula

$$d = \frac{A' \times d' + A'' \times d'' + A''' \times d'''}{A' + A'' + A'''} \quad (3)$$

**Example II.** To show the application of the rule for finding the center of gravity of compound figures, take the one shown in Fig. 19. The distance  $d$




Fig. 19. Center of Gravity of Irregular I Section




Fig. 20. Center of Gravity of Irregular Figures

The center of gravity of the entire figure from the vertex  $O$  is found as follows: The area of the triangle is  $36$  sq in and of the semicircle  $56.5$  sq in. From the Centers of Gravity (page 293) the distance of the center of gravity of the triangle from the vertex is two-thirds its height, which gives  $4$  in as

the value for  $d'$ . The center of gravity for a semicircle is  $0.4244 R$  from the base, so that  $d''$  equals 8.54 in. Then,

$$d = \frac{36 \times 4 + 56.5 \times 8.54}{36 + 56.5} = 6.77 \text{ in}$$

This method of finding the center of gravity is similar to that explained in Chapter IX for finding the supporting forces or reactions. In the latter case, however, the problem is to find the balancing forces instead of the lever-

**Additional Methods of Determining Graphically the Center of Gravity of Irregular Plane Figures.\*** The center of gravity may be obtained graphically by means of the FORCE-POLYGON and the EQUILIBRIUM-POLYGON. The figure or section considered, Fig. 21, is divided into parts whose cen-




Fig. 21. Center of Gravity Determined Graphically.




Fig. 22. Center of Gravity Determined Graphically. Second Method.

gravity can be located and areas calculated. The force-polygon (b) and equilibrium-polygon (c) are drawn. The figure (a) is divided into rectangles and triangles, A, B, C and D, and vertical lines are drawn through their centers of gravity. In (b) the vertical lines  $a, b, c$  and  $d$  are respectively proportional in length to the areas A, B, C and D. The pole, O, is located by the intersection of lines drawn at angles of  $45^\circ$  from the extremities of the line  $abcd$ . Lines 1, 2, 3, 4 and 5 are drawn from O, as shown, and the corresponding parallel lines are drawn in (c). (See Figs. 3 and 5, pages 299 and 300; Figs. 12 to 14, pages 314 to 320; and page 345.) The vertical line through Y, produced, is a GRAVITY-AXIS and its intersection G with the horizontal gravity-axis is the center of gravity of the figure. If the figure is not symmetric about XX a second gravity-axis may be found by turning the figure through  $90^\circ$  and repeating the construction. The intersection of the two gravity-axes will be the center of gravity of the figure. ANOTHER METHOD is shown in Fig. 22. If the centers of gravity of two areas A and B be at the points  $C_a$  and  $C_b$  respectively. From  $C_a$  the line  $C_a D$  is drawn in any direction, and its length on some given scale represents the area A. From  $C_b$  the line  $C_b E$  is drawn parallel to  $C_a D$  and its length on the same scale represents the area B. The intersection of the line joining D and E with  $C_a C_b$  is at the center of gravity of the areas A and B. For three areas A, B and C, the construction can be repeated by considering A and B as a single area; and so on for any number of areas.

\* Condensed from data by Robins Fleming.

## CHAPTER VII

## STABILITY OF PIERS AND BUTTRESSES \*

By

GRENVILLE TEMPLE SNELLING

LATE MEMBER OF AMERICAN INSTITUTE OF ARCHITECTS

**Mechanical Principles.** A pier or buttress may be considered **STABLE** when the forces acting upon it do not cause it to **ROTATE** or **TIP** OVER nor cause any part of the masonry to **SLIDE** on its bed; some parts, however, of the masonry may be **CRUSHED**. When a pier sustains a vertical load only, it might be considered **STABLE**, but it might not have sufficient **STRENGTH**. It is only when the pier receives a **THRUST**, as from a rafter or an arch, that its stability must be considered. In order that there may be no rotation, the **MOMENT OF THE THRUST** (Chapter VI) against the pier about any point in its outside edge must be equal to the **MOMENT OF THE WEIGHT** of the pier about the same point.

To illustrate let us consider the pier shown in Fig. 1. Let us suppose that this pier receives the thrust of a rafter which exerts a **THRUST**  $T$  in the line  $AB$ . The tendency of this thrust is to make the pier rotate about the outer edge  $b_1$ , the **MOMENT OF THE THRUST** about this point, is the measure of this tendency to rotate,  $T \times a'b_1$ ,  $a'b_1$  being the lever-arm of the moment.

For **STABLE EQUILIBRIUM**, only, the **MOMENT OF THE WEIGHT** of the pier about the same edge must just equal  $T \times a'b_1$ . The weight force representing the weight of the pier acts vertically through its center of gravity which in this case is equidistant from its sides; and its lever-arm is, or one-half its thickness.

For equilibrium of moments, we must have the equation

$$T \times a'b_1 = W \times b_1c$$

In this condition the least additional thrust, or the crushing of the outer edge will cause the pier to rotate; hence, for safety, we must use some **FACTOR OF SAFETY**. This is sometimes done by making the moment of the weight equal to half of the thrust when referred to a point in the bottom of the pier, a certain distance in from the outer edge. This distance for piers or buttresses should be not less than one-fourth the thickness of the pier.

Representing this point in the figure by  $b$ , we have the necessary equation for the stability of the pier

$$T \times ab = W \times l/4$$

where  $l$  is the width of the pier.

We cannot from this equation determine the dimensions of a pier to resist a thrust, because we have the distance  $ab$ ,  $l$  and  $W$ , all unknown quantities. We must first assume a tentative size for the pier, find the length of the thrust and see if the **MOMENT OF THE WEIGHT** of the pier is equal to the **MOMENT OF THE THRUST**. If it is not we must assume another size for the pier. In fact the steps of the problem usually present themselves in the




Fig. 1. Pier with Thrust

\* See, also, Chapter XXXI, Section 2, Vaults.

inverse order, the pier or buttress being given and the determinative stability being required. The size of the pier or buttress is usually fixed rather from the architectural exigencies of the design than from engineering requirements for the stability of the structure. If upon inspection these are not in accord, it is the duty of the designers to use their judgment in seeing that both conditions are fulfilled.

**The Stability of Piers and Buttresses.** When it is desired to determine if a given pier or buttress is capable of resisting a given thrust, the problem can be solved GRAPHICALLY in the following manner. Let  $ABCD$  (Fig. 2) represent a pier which sustains a thrust  $T$  at  $B$ . To determine whether the pier will sustain this thrust, we proceed as follows:




Fig. 2. Graphical Determination of Thrust on Pier

Draw the indefinite line  $BX$  in the direction of the thrust. Through the center of gravity of the pier in this case is midway between  $AD$  and  $BC$ , draw a vertical line intersecting the line of the thrust at point  $e$ . The resultant of the thrust and the weight may be considered to act anywhere along this line of action, we may consider that the thrust and the weight act at the point  $e$ . The resultant of these two forces is obtained by laying off the thrust  $T$  from  $e$  on  $eX$  and the weight of the pier  $W$ , from  $e$  on  $eY$ , both to the same scale of so many pounds to the inch, completing the parallelogram and drawing the diagonal. If this diagonal, prolonged, cuts the base of the pier at less than one-third the width of the base from the left edge, the pier is generally considered unstable and its dimensions are inadequate. (See Chapter IV, Theorem of the Middle Third.)

**The Stability of Buttress with Offsets.** THE STABILITY OF A PIER can be increased by adding to its weight by placing some heavy material on top of it, for example, or by increasing its width at the base by means of OFFSETS. Fig. 3. Figs. 3 and 4 show the method of determining the stability of a buttress with offsets. The first step is to find the vertical line passing through the center of gravity of the whole pier. This is best done by dividing the pier into quadrilaterals, as  $ABCD$ ,  $DEFG$  and  $GHIK$  (Fig. 3), finding the center of gravity of each quadrilateral by either the method of diagonals or the method explained in Chapter VI, and then measuring the perpendicular distances  $X_1$ ,  $X_2$ ,  $X_3$  from the different centers of gravity to the line  $KI$ . (See, also Chapter VIII, page 313).

Multiply the area of each quadrilateral by the distance of its center of gravity from the line  $KI$  and add together the areas and the products. The sum of the products divided by the sum of the areas and the result will be the distance of the center of gravity of the whole buttress from  $KI$ . This distance is denoted by  $X_0$ . This calculation is a practical application of the theorem in Chapter VI that the MOMENT OF THE RESULTANT of any number of forces about a point is equal to the SUM OF MOMENTS of the individual forces about the same point.

**Example 1.** Let the buttress shown in Fig. 3 have the dimensions given. Then the areas of the quadrilaterals and the distances from their centers of gravity to  $KI$  are as follows:

First area	=	35 sq ft	$X_1 = 0'.95$	First area	$\times$	$X_1 =$
Second area	=	23 sq ft	$X_2 = 2'.95$	Second area	$\times$	$X_2 =$
Third area	=	11 sq ft	$X_3 = 4'.95$	Third area	$\times$	$X_3 =$
Total area, 69 sq ft			Total moments,			

The sum of the moments of the areas is 155.55, and dividing this by the total  $n$ , we have 2.25 as the distance  $Ka$ . Measuring this to the scale of the drawing from  $KI$ , we have a point through which the vertical line passing through the center of gravity must pass.

This line, passing through the center of gravity of the buttress, can be found GRAPHICALLY, also, by the method of the EQUILIBRIUM FOLIOON (Fig. 3). (See




Fig. 3. Buttress with Offsets




Fig. 4. Resultant Thrust on Buttress with Offsets

296 and 314 to 320.) In order to do this, lay off at any convenient beginning at some convenient point  $M$ ,  $Mw_1$ ,  $w_1w_2$ , and  $w_2w_3$ , the  $w$  of the various quadrilaterals composing the buttress. Through the center of gravity of each quadrilateral draw a vertical (green) line. Draw the lines  $MO$  and  $MO$ , intersecting at some conveniently chosen POINT,  $O$ . Through  $O$ , draw  $Ow_1$  and  $Ow_2$ . Through  $a$ , where  $MO$  intersects the vertical line drawn through the center of gravity of the first quadrilateral, draw  $ab$  parallel to  $Ow_1$ , and through  $b$ , where  $ab$  intersects the (green) line through the center of gravity of the second quadrilateral, draw  $bc$  parallel to  $Ow_2$ . Finally draw  $cd$  parallel to  $Ow_3$ . Where this line intersects  $MO$  will be the point through which the (heavy red) line, passing through the center of gravity of the buttress taken as a whole, should be drawn. The distance

$X_0$ , measured from  $AK$ , should then be 2.25 ft or very nearly this, allowing slight errors of drawing, and the same as that found by MOMENTS. Fig. 5




Fig. 5. Center of Gravity of Wall and Buttress

**CENTER OF PRESSURE** of each joint. The **CENTER OF PRESSURE** of any joint is the point in which the resultant of the forces acting on that portion of the pier above the joint cuts it. The line of pressure, or of resistance, when drawn in a pier, shows how near the greatest stress on any joint comes to the edges of that joint. It can be drawn by the following method.

Let  $ABCD$  (Fig. 6) be a pier whose **LINE OF PRESSURE** we wish to draw. Let  $T$  be the thrust against the pier divide the height of the pier into several parts, each 2 or 3 feet high, as by the horizontal dotted lines. It is more convenient to make the or

\* This line is called, interchangeably, the line of pressure, the line of resistance-line, etc.

the same method of determining the position of the center of gravity of a buttress similar to the one illustrated in Fig. 5

After this line is found, the method of determining the stability of the pier is the same as that given for the pier in Fig. 2 and Fig. 4. If the buttress is more than one foot thick, that is, right-angles to the plane of the pier, the cubic contents must be determined in order to find its weight. It is, however, to divide the total thrust by the thickness of the buttress. This gives the thrust per foot of thickness of buttress.

**The Line of Pressure or Line of Resistance.\*** The **LINE OF RESISTANCE** or the **LINE OF PRESSURE** of a pier or buttress is a line drawn through




Fig. 6. Line of Pressure in a Pier

total in height. Prolong the **LINE OF THE THRUST**, and draw a vertical through the center of gravity of the pier, intersecting the line of thrust at point *a*. From *a* lay off to a scale the thrust *T*, and the weights of the different parts of the pier, commencing with the weight of the upper portion. *w*<sub>1</sub> represents the weight of the portion above the first joint; *w*<sub>2</sub> represents the weight of the second part; and so on. The sum of the *w*'s will be the weight of the whole pier.

Draw a parallelogram, with *T* and *w*<sub>1</sub> for its two sides. Draw the diagonal and prolong it beyond the parallelogram, if necessary. Its point of intersection with the base of the pier will be a point in the line of pressure. Draw a second parallelogram, with *T* and *w*<sub>1</sub> + *w*<sub>2</sub> for its two sides. Draw the diagonal intersecting the base of the pier at the point 2. Continue in this way with the rest of the partial

weights, the last diagonal intersecting the base *AD*, in the point 4. Join the points 1, 2, 3 and 4. The resulting broken line *C1234* is the **LINE OF PRESSURE** OR **LINE OF RESISTANCE**.

We have taken the simplest case as an example; but the same principles are true for any case. If the line of pressure of the pier at any point falls at a distance from the outside edge of the joint less than **ONE-THIRD THE WIDTH OF THE JOINT**, the pier is generally considered unsafe.

**The Stability of a Wall and Buttress. By Moments and Graphical Method.** The following example illustrates the application of these principles.

**Example 2.** Let Fig. 7 represent the section of a side wall of a church, with a buttress against it. Opposite the buttress, on the hammer-beam truss, which we will suppose exerts an equal and opposite thrust against the wall of the church, amounting to about 9 600 lb. We will suppose the resultant of the thrust acts at *P*, and at an angle of 45°. The dimensions of the wall and buttress are given in Fig. 8. The wall is 2 ft thick, at right-angles with the plane of the drawing. It is the proper size and form to enable the wall to resist

Fig. 8. Stability of Wall and Buttress

The question is whether or not the **LINE OF PRESSURE** cuts the wall in from *C*. To ascertain this we must determine the center of gravity of the wall and buttress above the joint *CD*. To determine this is by the **METHOD OF MOMENTS**, the moments being taken about the line *KM* as an axis, or line of reference, as has been already explained. The distance *X*<sub>1</sub> is, of course, half the width of the wall, or 1 ft. We next find the center of gravity of the part

*CEFG* (Fig. 8) by the method of diagonals; and scaling the distance  $X_2$ , it to be 2.95 ft.

The area  $CEFG = A_2 = 10$  sq ft; and the area  $GIKL = A_1 = 26$  sq ft.  $A$  = the total area above  $CL$ .

Then we have

$X_1 = 1$ ft	$A_1 = 26$ sq ft	$A_1 \times X_1 = 26$ sq ft $\times$ ft
$X_2 = 2.95$ ft	$A_2 = 10$ sq ft	$A_2 \times X_2 = 29.5$ sq ft $\times$ ft
	<hr style="width: 50px; margin: 0 auto;"/> A = 36 sq ft	<hr style="width: 50px; margin: 0 auto;"/> 36)55.5 sq ft $\times$ ft
		<hr style="width: 50px; margin: 0 auto;"/> $X_0 = 1.5$ ft

Expressed in EQUATIONS OF MOMENTS OF AREAS, this may be written as  $A \times X_0$  representing the total area above the line  $CL$  (Fig. 8):

$$A \times X_0 = (A_1 \times X_1) + (A_2 \times X_2)$$

Hence,

$$X_0 = \frac{(A_1 \times X_1) + (A_2 \times X_2)}{A}$$

The center of gravity is at a distance 1.5 ft from the line  $ED$  (Fig. 7) measure the distance  $X_0 = 1.5$  ft, and through the point  $a$  draw a line intersecting the line of the thrust prolonged at  $O$ . If the thrust is 4 800 lb for example, for a buttress 2 ft thick, it will be half that, or 4 800 lb for a buttress 1 ft thick. We will call the weight of the masonry of which the buttress and wall is built, 150 lb per cu ft. Then the thrust is equivalent to 4 800/150 = 32 cu ft of masonry. Laying this off to a scale from  $O$ , in the direction of the thrust, and the area of the masonry, 36 sq ft, from  $O$  on the vertical line completing the rectangle, and drawing the diagonal, we find that the diagonal intersects the joint  $CD$  at  $t$ , within the limits of safety. We must next find where the LINE OF PRESSURE cuts the base  $AB$ .

First, determine the position of the center of gravity of the whole buttress. This is determined by finding, as explained for the distances  $X_1$  and  $X_2$ , the distances  $X_1'$ ,  $X_2'$ , in Fig. 8, and making the following computation, letting  $A'$  be the total area above  $AM$ .

$X_1' = 1$ ft	$A_1' = 40$ sq ft	$A_1 \times X_1 = 40$ sq ft $\times$ ft
$X_2' = 2.98$ ft	$A_2' = 24$ sq ft	$A_2 \times X_2 = 71.52$ sq ft $\times$ ft
$X_3' = 4.95$ ft	$A_3' = 12$ sq ft	$A_3 \times X_3 = 59.40$ sq ft $\times$ ft
	<hr style="width: 50px; margin: 0 auto;"/> A' = 76 sq ft	<hr style="width: 50px; margin: 0 auto;"/> 76)170.92 sq ft $\times$ ft
		<hr style="width: 50px; margin: 0 auto;"/> $X_0' = 2.25$ ft

This, also, may be expressed in EQUATIONS OF MOMENTS OF AREAS, as explained for the part above the line  $CL$ .

Then from the line  $EB$  (Fig. 7) lay off the distance  $X_0' = 2.25$  ft, and through  $d$  a vertical line intersecting the line of the thrust at  $O'$ . On this vertical line, measure down from  $O'$  the whole area 76, to scale, as explained for the first part, and from the lower extremity of this line representing the area, lay off to a proper angle, the thrust  $T = 32$ . Draw the line  $O'e$ , intersecting the base at  $e$ . This is the point where the LINE OF PRESSURE cuts the base; and, as long as  $e$  is at a safe distance in from  $A$ , the buttress has sufficient stability. If there are more offsets, we should proceed in the same way, finding where the LINE OF PRESSURE cuts the joint at the top of each offset. The reason for doing



the **LINE OF PRESSURE** might cut the base at a safe distance from the edge, while higher up it might come outside of the buttress or too near outside face, thus making the buttress unstable. The method given in these notes is applicable to piers of any shape or material. If the **LINE OF PRESSURE** makes an angle of less than  $30^\circ$  with any horizontal joint, the stones at the joint may **SLIDE** at this joint, or at least have a strong tendency to **SLIDING** can be prevented either by doweling, or bolting the joints. Such conditions, however, are not in architectural construction.

**Stability of a Wall and Buttress. Graphical Method.** This same example, which has been solved in foregoing case partly by **MOMENTS** and partly by **MECHANICAL METHODS**, can be solved entirely by **GRAPHICAL METHODS**. In this case it is not necessary to determine position of the line (the heavy red lines in Figs. 3 and 4) passing through the center of gravity of the buttress as a whole. It is necessary, only, to determine

(red) lines passing through the center of gravity of the various trapezoids or rectangles into which it has been divided. To determine the position of the **LINE OF PRESSURE** and the various **FORCES OF PRESSURE** on the different joints, the method shown in Fig. 6 may be used. The construction shown in Fig. 9, in which the complete diagrams of the forces acting at each joint are drawn, may be simplified. Only the parallelogram, only, or the triangle of the **FORCES** acting at each joint may be drawn and the whole construction placed at one side of the wall and afterwards transferred to the wall itself by means of parallel lines. Draw the joint-planes *FG*, *EJ*, *CK* and *BN* and calculate the areas of the various parts of the wall and buttress, as *IKGF*, *FGJE*, *EJKC*, *CKNB* and *BNMA*, Fig. 9. These are respectively 14 sq ft, 6 sq ft, 16 sq ft, 10 sq ft and 30 sq ft. Lay off these areas to a scale so many square units to a linear




Fig. 9. Line of Pressure in Wall and Buttress

unit  $Pw_1$ ,  $w_1 w_2$ ,  $w_2 w_3$ ,  $w_3 w_4$  and  $w_4 w_5$ , along the line *KM*, beginning at the point of application of the **THRUST**. Lay off, at the same scale, the **THRUST** for one foot of thickness of the wall, and let this thrust be 4 800 lb. Draw *Ow 1*, *Ow 2*, *Ow 3*, etc. Then *Ow 1* will be the resultant of the thrust and the weight of the buttress above the joint *FG*, *Ow 2* will be the resultant of the resultant and the weight of that part of the buttress between the joints *EJ*, and so on until *Ow 5* is reached, which is the resultant of the total weight of the buttress and the thrust as well as the resultant of the rectangle and the previous resultant. Prolong the thrust *OP*, until it cuts the line through the center of gravity of the first rectangle *IKGF*, at *a*. At this point draw a (green) line parallel to *Ow 1* and prolong it backward

until it intersects the joint  $FG$  at the point within the small (red) circle. This determines the CENTER OF PRESSURE on this joint. Next, draw  $ab$  (green) parallel to  $Ow$  2 and prolong it backward until it intersects the joint  $EJ$ , a CENTER OF PRESSURE on that joint. Repeat this operation to obtain CENTERS OF PRESSURE on each successive joint, drawing  $bc$ ,  $cd$  and  $de$  parallel respectively to  $Ow$  3,  $Ow$  4 and  $Ow$  5.

It must be remembered, however, that  $cd$  does not have to be prolonged backward, as it cuts the joint  $CK$  below and to the left of the line passing through the center of gravity of  $EJKC$ . Finally, join the various CENTERS OF PRESSURE by the (red) broken line, which is the LINE OF PRESSURE in the buttress. If this line lies within the MIDDLE THIRD of the construction, and the resultant of the pressures on the various joint-planes do not make with the normals to the joint-planes angles greater than the ANGLE OF FRICTION, the condition of stability may be considered to be satisfied.

# CHAPTER VIII

## THE STABILITY OF MASONRY ARCHES\*

By  
GRENVILLE TEMPLE SNELLING

LATE MEMBER OF AMERICAN INSTITUTE OF ARCHITECTS

### 1. Arches

**The Lintel and the Arch.** When an opening is made in a masonry wall it is necessary to provide some means of spanning such opening to support the imposed masonry. Two methods have been employed by constructors for this purpose. The first involves the use of the BEAM, GIRDER, CAP, or LINTEL, and the second the throwing of an ARCH from one side of the opening to the other. LINTELS are made of various materials, as wood, stone, reinforced concrete, cast iron and steel, and have cross-sections of different shapes. They are placed across the tops of the openings and transfer laterally the loads above, being VERTICAL REACTIONS, only, in the side supports. An ARCH, on the contrary, is a particular arrangement of blocks of stone or other material, put together, generally along a curved line, in such a way that they resist the load by a balancing of certain THRUSTS and COUNTERTHRUSTS. An arch exerts on its supports an OUTWARD THRUST as well as a VERTICAL PRESSURE; and it is this outward thrust which requires that the arch should be used with caution where the abutments are not amply large and strong. The mechanical principles involved in the spanning of an opening by a lintel are much simpler than those of the arch and, historically, the lintel very considerably antedates the arch.

**Definitions.** Before taking up the principles of the arch, we will define the principal terms relating to it. The distance  $cc$  (Fig. 1) is called the SPAN of the arch;  $a$ , the rise;  $b$ , the CROWN; the lower boundary of the arch, the SOFFIT or INTRADOS; the outer boundary, the BACK or EXTRADOS. The terms SOFFIT and BACK are also applied to the entire lower and upper surfaces of the whole arch. The sides of the arch which are seen are called the FACES. The blocks of which the arch itself is composed are called STONES; the center one,  $K$ , is called the KEYSTONE; the lowest ones,  $SS$ , the SPRINGERS. In SEGMENTAL arches, or those of which the intrados is not a complete semicircle, the springers generally rest upon two stones, as  $RR$ , which have their upper surfaces cut to receive them; these stones are called SKEWBACKS. The line connecting the lower edges of the springers is called the SPRINGING; the sides of the arch are called the HAUNCHES; and the loads in the triangular spaces, between the haunches and a horizontal line drawn from the crown, are called the SPANDRELS. The blocks of masonry, or other material, which support two successive arches, are called PIERS; and the extreme blocks, in the case of stone bridges, generally support, on one side, embankments of earth, are called ABUTMENTS. A pier strong enough to resist the thrust of one of two successive arches, in case the other one falls down, is some-




Fig. 1. Diagram of Segmental Arch

\* See, also, Chapter XXXI.

times called an **ABUTMENT-PIER**. Besides their own weight, arches usually port permanent loads or **SURCHARGES** of masonry or of earth.

**Forms of Arches.** In using arches in architectural constructions **FORMS** of the arches are generally governed by the style of the building, a limited amount of space, rather than by engineering considerations. problem, therefore, that usually presents itself to the architect is not to the form and dimensions of an arch that will most economically and, from engineering point of view, efficiently bear its load, but rather to determine an arch of a certain form and of certain dimensions will be stable and under its load. The **SEMICIRCULAR** and **SEGMENTAL** forms of arches are best as regards stability, and are the simplest to construct. **ELLIPTICAL** **THREE-CENTERED** arches are not as strong as circular arches, and should be used where they can be given all the strength desirable.

**The Strength of an Arch** depends very much upon the care with which built and upon the quality of the materials. In stone arches, special care is to be taken to cut and lay the beds of stones accurately, and to make the joints thin and close, in order that the arches may be stressed as little as possible in settling. To insure this, arches are sometimes built **DRY**, grout or mortar being afterwards run into the joints; but the advantage of this method is doubtful.

**Brick Arches.\*** (See Figs. 2, 3, 4 and 5.) These may be built either with **WEDGE-SHAPED** bricks, molded or rubbed so as to fit to the radius of the




Fig. 2

Fig. 3

Fig. 4

Fig. 5

Brick Arches

or of bricks of **COMMON SHAPE**. The former method is undoubtedly the best, as it enables the bricks to be thoroughly bonded, as in a wall; but, as it involves considerable expense to make the bricks of the proper shape, it is very seldom employed. When bricks of the ordinary shape are used, they are accommodated to the curved figure of the arch by making the bed-joints thicker towards the intrados than they are at the extrados; or, if the curvature is small, by driving thin pieces of slate into the outer edges of those joints; and different methods are followed for **BONDING** them.

The usual method is to build the arch in concentric rings, each one-half brick thick; that is, to lay all the bricks as **STRETCHERS** and depend upon the tenacity of the mortar for the connection of the several rings. Brick masonry constructed in this way is deficient in strength, unless the bricks are laid in a strong mortar which is at least as tenacious as themselves. Another way is to introduce courses of **HEADERS** at intervals, and to connect pairs of half-brick

\* For illustrations of the different methods of building brick arches, see Chapter on Building Construction and Superintendence, Part I, *Masons' Work*, F. E. Kidder.

This may be done either by thickening with pieces of slate the outer ring of a pair of half-brick rings, so that there will be the same number of courses of stretchers in each ring between two courses of headers; or by placing the courses of headers at such distances apart, that between each pair of them there will be one course of stretchers more in the outer than in the inner ring. The former method is best suited to arches of large radius; the latter, to those of short radius. HOOP-IRON laid around the arch between half-brick rings, as well as longitudinally and radially, is very useful for strengthening brick arches. The bands of hoop-iron which traverse the arch radially may also be bent, and prolonged into the bed-joints of the bricks and spandrels. By the aid of HOOP-IRON BOND, Sir Marc-Isambard Brunel built a half-arch of bricks, laid in strong cement mortar, which stood, leaning from its abutment like a bracket to the distance of 60 ft, until it was destroyed by the undermining of its foundations.

The only requirements in the New York City Building Laws for brick and arches is that "openings for doors and windows in all buildings shall have good and sufficient arches of stone, brick, or terra-cotta, well built and keyed with good and sufficient abutments."

**Rule for the Radius of Brick Arches.** A good RULE for the radius of small brick arches over windows, doors and other small openings is to

make the RADIUS EQUAL TO THE RISE OF THE OPENING. This gives a good rise to the arch and is a true proportion. In common brickwork, when no particular architectural effect is required, such as in the rowlock arch thrown over the openings between walls, a RULE in very common use is to make the RISE of the arch at the crown AN INCH FOR EVERY FOOT OF SPAN.

### Segmental Arches with Tie-rods

It is often desirable to make openings in a wall by means of arches when there are not a sufficient number of abutments to stand the thrusts. In

arches of this kind each arch can be sprung from two cast-iron SKEWBLOCKS, held together by IRON RODS, as is shown in Fig. 6. When this is done, it is necessary to proportion the size of the rods to the THRUST of the arch. The HORIZONTAL THRUST of the arch may be very closely determined by the following formula:

$$\text{Horizontal thrust} = \frac{\text{load on arch} \times \text{span}}{8 \times \text{rise of arch in feet}}$$

If the load is concentrated at the center of the arch, the thrust will be twice that given by this formula.

TENSIONAL STRESS in the rod or rods will equal the HORIZONTAL THRUST of the arch and if there are two rods, the stress in each will be one-half the thrust. If there are three rods, then each must resist one-third the thrust. Knowing the stresses in the rods, the size of each may be determined from Table II, Chapter XI.




Fig. 6. Segmental Brick Arch, Cast-iron Skew-back and Wrought-iron Tie-rod

**Example 1.** Let us assume that a brick arch, like the one shown in Fig. 1, has a span of 15 ft, a rise at the center of 1 ft 6 in, and that it supports a brick wall. The weight of all the brick masonry above the arch does not rest upon it. Usually only an EQUILATERAL TRIANGLE of brickwork is considered, the base of the triangle being the span. Assume, therefore, an equilateral triangle the sides of which are each 15 ft long. The altitude of this triangle is about 12.6 ft and its area will equal  $15 \text{ ft} \times 12.6 \text{ ft} \times \frac{1}{2} = 94\frac{1}{2} \text{ sq ft}$ . If the wall is 12 in thick there will be  $97\frac{1}{2} \text{ cu ft}$  of brickwork within this triangle. A brick wall; and since ordinary brickwork weighs about 115 lb per cu ft, its weight will be about 10 867 lb. Substituting these values in the formula,

$$\text{The horizontal thrust} = \frac{10\,867 \times 15}{8 \times 1.5} = 13\,584 \text{ lb}$$

Looking in Table II, page 388, it appears that one 1½-in or two 1¼-in round, wrought-iron rods, or one 1½-in or two ¾-in round, upset, steel rods should be used.

**Centers for Arches.** A CENTER is a temporary structure, generally of timber, on which the voussoirs of an arch are supported while the arch is built. It consists of parallel frames or ribs, placed at convenient distances apart, curved on the outside to a line parallel to that of the soffit of the arch, and supporting series of transverse planks, upon which the arch-stones are laid. The center commonly used is one which can be lowered, or STRUCK all at once, by driving out wedges from below it, so as to remove at once the support from every point of the arch. The center of an arch should not be struck until the solid part of the backing has been built and the mortar has had time to set and harden; and when an arch forms one of a series of arches with piers between them, no center should be struck so as to leave a pier with a face abutting against one side of it only, unless the pier has sufficient stability as an abutment. When possible, the STRIKING of the center of large brick arches should be delayed for two or three months after the arch is built, and during the period that they are in place they should be EASED from time to time. This is done by EASING OUT the wedges under the centers a little at a time, so as to let them down gradually and thus adjust any slight settling or shrinking of the masonry as it occurs.

**Mechanical Principles of the Arch.** In designing an arch, the first question to be settled is the FORM of the arch; and in regard to this, as already stated, there is generally little choice. When the abutments are of ample size, the FLAT ARCH is the strongest; but when it is necessary to make the abutments of the arch as small as possible, the SEMICIRCULAR or the POINTED ARCH should be used.

**Depth of Keystone.** Having decided upon the form of the arch, the next question OF THE ARCH-RING must next be decided. This is generally determined by computing the required DEPTH OF THE KEYSTONE and making the depth of the whole ring the same or a little larger. In considering the strength of an arch, the depth of the keystone is considered to be only the distance from the extrados to the intrados of the arch; and if the keystone projects above the ring, as in Fig. 1, the projection is considered a part of the load on the arch. There are several rules for determining the depth of the keystone, but they are all empirical; and they differ so greatly that it is difficult to recommend any particular one.

**Rankine's Formula for Depth of Keystone.** Professor Rankine's formula is often quoted, and gives results which are probably true enough for

It applies to both CIRCULAR and ELLIPTICAL ARCHES and is as follows. It is the mean proportional between the inside radius at the crown, and 0.12 of the span for a single arch, and 0.17 of a span for an arch forming one of a series:

Depth in feet of keystone for single arch =  $\sqrt{(0.12 \times \text{radius at crown})}$

Depth in feet of keystone for arch of a series =  $\sqrt{(0.17 \times \text{radius at crown})}$

The dimensions given by this formula seem to agree very well with those actually used in practice in arches of a certain kind. The formula, however, gives the same depth of keystone for spans of any length, provided the radius is the same; and in this particular it would seem that the rule is not satisfactory.

**Trautwine's Formula for Depth of Keystone.** Trautwine, from calculations made for a large number of arches, deduced a formula for the depth of keystone, which seems to agree with theory more closely than Rankine's formula. It is, for CUT STONE,

$$\text{Depth of key in feet} = \left( \frac{\sqrt{\text{radius} + \text{half span}}}{4} \right) + 0.2 \text{ ft}$$

For SECOND-CLASS work this depth may be increased about one-eighth part, for BRICKWORK OF FAIR RUBBLE, about one-third.

**Tables for Depths of Keystones.** Table I gives a few examples of the DEPTHS OF THE KEYSTONES of some bridges, together with the depths which would be required by Trautwine's or Rankine's formula. From this table it appears that the results of both formulas agree very well with dimensions used in actual practice.

Table I. Depths of Keystones of Some Arches of Circular Arc

Name or location of structure	Span	Rise	Radius	Actual depth of key	Calculated depth of key		Engineer
					Trautwine's Rule	Rankine's Rule	
					ft	ft	
John, Washington aqueduct.....	220.0	57.25	134.25	4.16	4.11	4.00	Meigs
Penryn bridge, Chester, England....	200.0	42.00	140.00	4.00	4.07	4.10	Hartley
Riparia, Turin, Italy.....	148.0	18.00	160.10	4.92	4.03	4.38	Mosca
Waglan, England, an bridge, Scotland, in a series.....	118.0	38.20	64.80	3.50	3.00	2.79	Telford
90.0	6.20	48.90	3.00	2.62	2.88	Telford	
Philadelphia & Reading Railroad.....	78.0	25.00	43.00	3.00	2.46	2.27	Steele
Market St. bridge, Philadelphia, brick pavement.....	60.0	18.00	34.00	2.50	2.20	2.00*	Kneass
Philadelphia & Reading Railroad.....	44.0	8.00	34.30	2.50	2.08	2.02	Steele
Philadelphia & Reading Railroad.....	31.2	5.00	26.80	1.66	1.83	1.79	Steele

\* For first-class cut-stone work.

Table II\* gives the DEPTHS OF KEYSTONES for arches of first-class cut st according to Trautwine's Formula. For second-class cut stone, add about eighth part and for fair rubble or for brickwork about one-third part, as st with formula.

Table II. Depths of Keystones for Arches of First-Class Cut-Stone Masonry

Span	Rise, in parts of the span						
	½	⅓	¼	⅕	⅙	⅛	⅑
ft	ft	ft	ft	ft	ft	ft	ft
2	0.55	0.56	0.58	0.60	0.61	0.64	0.6
4	0.70	0.72	0.74	0.76	0.79	0.83	0.8
6	0.81	0.83	0.86	0.89	0.92	0.97	1.
8	0.91	0.93	0.96	1.00	1.03	1.09	1.
10	0.99	1.01	1.04	1.07	1.11	1.18	1.
15	1.17	1.19	1.22	1.26	1.30	1.40	1.
20	1.32	1.35	1.38	1.43	1.48	1.59	1.
25	1.45	1.48	1.53	1.58	1.64	1.76	1.
30	1.57	1.60	1.65	1.71	1.78	1.91	2.
35	1.68	1.70	1.76	1.83	1.90	2.04	2.
40	1.78	1.81	1.88	1.95	2.03	2.18	2.
50	1.97	2.00	2.08	2.16	2.25	2.41	2.
60	2.14	2.18	2.26	2.35	2.44	2.62	2.
80	2.44	2.49	2.58	2.68	2.78	2.98	3.
100	2.70	2.75	2.86	2.97	3.09	3.32	3.
120	2.94	2.99	3.10	3.22	3.35	3.61	3.
140	3.16	3.21	3.33	3.46	3.60	3.87	4.
160	3.36	3.44	3.58	3.72	3.87	4.17	...
180	3.56	3.63	3.75	3.90	4.06	4.38	...
200	3.74	3.81	3.95	4.12	4.29	.....	...
220	3.91	4.00	4.13	4.30	4.48	.....	...
240	4.07	4.15	4.30	4.48	.....	.....	...
260	4.23	4.31	4.47	4.66	.....	.....	...
280	4.38	4.46	4.63	.....	.....	.....	...
300	4.53	4.62	4.80	.....	.....	.....	...

Example 2. Having decided what the thickness of the arch-ring will remains to determine whether such an arch would be stable if built. following example will illustrate the method of determining this.

Consider an unloaded semicircular arch of 20-ft span.  
First, to find the depth of the keystone, we will use Rankine's Formul

Depth of key =  $\sqrt{0.12 \times 10} = \sqrt{1.2} = 1.1 \text{ ft}$

Trautwine's Formula gives nearly the same result,

Depth of key =  $\frac{\sqrt{10 + 10}}{4} + 0.2 \text{ ft} = 1.3 \text{ ft}$

But if we should compute the stability of a 20-ft semicircular arch keystone 1.3 ft deep, we should find that the arch is very unstable; in this case, we cannot use the formula and must act upon our own jud In the opinion of the author, the arch-ring of such an arch should be 2½ ft deep and the stability of the arch should be tested for that th In all calculations on the arch, it is customary to consider it 1 ft t

\* Taken from The Civil Engineer's Pocket-Book, John C. Trautwine.



angles to its face. This allows the **AREAS OF THE FACES** to be substituted for the **ACTUAL WEIGHTS** of the voussoirs and their loads. This method was used in the discussion of Retaining-Walls, Chapter IV, and Piers and Buttresses, Chapter VII. Furthermore, it is evident that if an arch 1 ft thick is stable, any number of arches of the same dimensions built alongside of it would be stable. In determining the stability of masonry arches it is also customary to neglect any increase in the strength of the arch from the mortar in the joints, in other words, to consider the arch as laid up dry.

**Graphic Determination of the Stability of Arches.** An arch has already been defined as a particular arrangement of blocks of stone or other material, the blocks being called the **VOUSSOIRS**. For the sake of simplicity consider an **UNLOADED ARCH**. In such an arch each voussoir is subjected to the action of three forces, (1) the thrust that it receives from the voussoir next above it in the arch-ring, (2) the force of gravitation, its own weight and (3) the reaction of the resultant thrust. The first two




Fig. 7. Equilibrium of Forces on Voussoir

combine into one and form a resultant thrust that this voussoir exerts on the one next below it in the arch-ring (Fig. 7). The points in which these various thrusts cut the joints are called the **CENTERS OF PRESSURE** of the joints, while the line joining these centers of pressure is called the **LINE OF PRESSURE** or **LINE OF RESISTANCE**.\* In order that an arch may be absolutely stable, this line of resistance must fall within the **MIDDLE THIRD** of the arch-ring. (See Theorem of the Middle Third, Chapter IV) If an arch is stable the centers of pressure on the various joint-lines are within the middle third of the voussoir-depths and the angles made by the different thrusts with the normals to the joints are less than the **ANGLE OF FRICTION** of the material of which the arch is constructed. If these conditions are not ful-




Fig. 8. Failure of Semicircular Arch. Haunches Sliding Down




Fig. 9. Failure of Semicircular Arch. Haunches Sliding Up

If the **CRITERIA OF SAFETY**, explained in Chapter VII in the discussion of the stability of a Buttress, will not be satisfied; and at any joint where these conditions do not obtain, the voussoir above the joint will tend to **SLIDE** along the joint-plane if the angle made by the thrust with a normal to the joint is greater than the angle of friction. If the center of pressure lies outside the middle third, there will be a tendency for the voussoir to **OVERTURN**. When these tendencies reach extreme limits actual **FAILURE** may occur. Figures 8, 9, and 11 illustrate some of the ways in which an arch may fail, Figs. 8 and 9, this line is called, interchangeably, the **LINE OF PRESSURE**, the **LINE OF RESISTANCE**, the **STABILITY-LINE**, etc. (See, also, Chapter XXXI, pages 1225 and 1234.)

showing different parts of the masonry sliding on the joints and Figs. 10 11 the failures caused by the passing of the line of pressure near the intrados extrados.

Before passing to the actual discussion of the GRAPHIC METHOD for determining the stability of arches, a consideration of the action of the STRESSES developed in a construction of this kind will assist in a clearer understanding of the subject.

Fig. 8 shows how, if the line of resistance along the HAUNCHES of the arch should turn sharply downward and in so doing make with a normal to the joints an angle greater than the angle of friction, the voussoirs at this




Fig. 10. Failure of Semicircular Arch.  
Opening of Arch-ring




Fig. 11. Failure of Pointed Arch.  
Opening of Arch-ring

would tend to slide inward on their joint-planes, forcing outward the voussoirs at the spring and crown of the arch. Fig. 9 shows how failure of the arch may occur under similar conditions, but with the line of resistance turning sharply upward instead of downward. In these two cases it is conceivable that though the RESISTANT THRUST at the joint where failure takes place makes an angle with the normal greater than the angle of friction, its point of application is still within the middle third of the joint.

Figs. 10 and 11, on the contrary, illustrate methods of failure in which though the angle made by the thrust may be such as to cause no SLIPPING of one joint on another, its point of application is sufficiently outside the middle third of the arch-ring itself at the crown to cause OVERTURNING. In Fig. 10 the line of resistance passes high up, or perhaps entirely outside of the arch-ring, and the voussoirs at the CROWN of the arch and low down along the HAUNCHES. In Fig. 11 exactly contrary conditions exist.

The ten ways in which a masonry arch may fail have been classified as follows:—  
“(1) By CRUSHING of the masonry; (2) By SLIDING of one voussoir upon another; (3) By one voussoir or section of masonry OVERTURNING about an adjacent voussoir or section; (4) By SHEARING in a horizontal or vertical plane, applying to solid concrete arches and not to voussoirs; (5) As A COLUMN, where the ratio of the unsupported length of an arch to its least width is greater than twelve; (6) From STRIKING THE CENTERING before the mortar is hard or the arch, although stable under the full load, is not stable under its own weight alone; (7) By STRIKING THE CENTERING or loading the arch during construction unsymmetrically; (8) By SETTLEMENT of the foundations; (9) By sliding upon the foundations; (10) By OVERTURNING about any point in the abutment. Methods (8) and (9) are the most common ways of failure. Methods of failure, however, must be guarded against in design.”

While some of these ways of failure may seem other than those illustrated in the foregoing figures, they may be perhaps more properly considered

\* W. J. Douglas in American Civil Engineering Pocket-Book, page 625.

FAILURE than WAYS OF FAILURE; and all, with the exception of the first, require a position of the line of resistance in the arch-ring which causes it to fail in one of the ways noted.

In regard to the method of failure (1), the conditions may be such that the arch, although symmetrical, is so excessive that although the line of resistance lies within the middle third, the total pressure on a joint is sufficient to crush the MATERIAL of which the arch is constructed. Such conditions, however, are not common.

From the foregoing discussion it is evident that in order to determine whether a given arch is stable, it is necessary to find the TRUE LINE OF RESISTANCE according to the conditions of loading, form and dimensions of that particular arch. It is always possible, in every arch-ring, to pass one MAXIMUM or MINIMUM LINE OF RESISTANCE. The TRUE LINE OF RESISTANCE will lie somewhere between these two. The method of procedure, therefore, is to pass tentatively, a line of resistance, either a maximum or a minimum one, and see if it remains within the middle third. If it does not, as it may not be the true line of resistance, it does not mean necessarily that the arch is not stable. The next step then, is to note where it departs farthest from the middle third, and pass a second line of resistance through the same point on the crown-joint and the point on the line of the middle third where the original line departs farthest from the middle third. If this second line of resistance remains within the middle third it is reasonable to assume that the arch is stable. In these operations it is only necessary to consider half the arch when the loading is symmetrical, and this is usually the case in architectural problems. The ORDER OF VOUSSOIRS, also, into which we divide the half-arch, is immaterial; the joints need not coincide with those of the actual arch.

In order to pass a line of resistance through an arch-ring, the THRUST exerted by the other half AT THE CROWN-JOINT on the half-arch is first determined. This thrust is then combined with the resultant of the weight of the first voussoir to find the load to determine the thrust exerted by this voussoir on the one next to it, and this thrust, in turn, is combined in the same way with the resultant of the weight and the load of the second voussoir, and so on down to the spring-joint, for each succeeding voussoir. The points in which the various lines representing the thrusts cut the joints are known as the CENTERS OF PRESSURE, and the line joining them is the LINE OF PRESSURE or LINE OF RESISTANCE. In carrying out this operation, the CENTER OF GRAVITY of each voussoir as well as the line passing through the center of gravity of the whole half-arch must be found. The face of each voussoir may be considered a TRAPEZOID, and any one of the methods for finding the center of gravity of this figure may be used to find the center of gravity of each voussoir. The method of dividing the trapezoid into TRIANGLES is here employed and is shown at the side of the arch in Fig. 12. (See, also, in Chapters VI and VII.) As the determination of the position of the line passing through the center of gravity of the half-arch is a problem of finding the RESULTANT OF A SYSTEM OF PARALLEL FORCES, the method involving the drawing of the EQUILIBRIUM-POLYGON may be used. The most convenient way to determine the stability of an arch is to use the GRAPHIC METHOD. The STEPS in this method are outlined in the preceding paragraph. Each of the operations will now be considered in detail.

**1st Step.** Draw one-half the arch to as large a scale as convenient, and divide it into voussoirs of equal size. In the example shown in Fig. 12, the arch is divided into ten voussoirs of equal face-areas. As already pointed out, it is not necessary that these should represent the actual voussoirs of which the arch is built. Next, the face-area of each of these voussoirs is to be found.

Where the arch-ring is divided into voussoirs of equal size, this is most done by computing the total area of the arch-ring and dividing this total by the number of voussoirs. The FORMULA for finding the area of one-half arch-ring is as follows:

$$\text{Area in square feet} = 0.7854 (r^2 - r_1^2)$$

In this formula  $r$  is the outside radius and  $r_1$  the inside radius in feet. In this problem, for example, if the

$$\text{Area of the arch-ring} = 0.7854 (12.5^2 - 10^2) = 44.2 \text{ sq ft}$$

as there are ten equal voussoirs, the area of each voussoir is 4.42 sq ft. ing drawn out one-half of the arch-ring, divide the crown-joint into three

Method of finding center of gravity of voussoir




Fig. 12. Line of Pressure in Unloaded Semicircular Arch-ring

ably passes nearer the OUTER THIRD at the CROWN and nearer the INNER at the HAUNCH. To determine this MINIMUM LINE OF RESISTANCE the MU THRUST, applied at the point  $E$  of the crown-joint, must first be determined.

The half-arch is in equilibrium under the action of three forces: (1) THRUST AT THE CROWN, acting horizontally, applied at the point  $E$  and preventing the half-arch from overturning inward; (2) the WEIGHT OF THE HALF-ARCH, considered as a vertical force, acting through its center of gravity and tending to overturn it inwards about the point  $D$ ; and (3) A FORCE EQUAL AND OPPOSITE TO THE RESULTANT of these two forces and passing from  $H$  to  $I$ . The intersection of the weight-line through the center of gravity of the half-arch with the line of action of the thrust at the crown, prolonged. It is thus possible to construct the TRIANGLE OF THESE THREE FORCES and determine the magnitude of the thrusts, when the position of the weight-line of the half-arch is determined. It is first necessary to draw a vertical line through the center of gravity of each voussoir. The center of gravity of one of the voussoirs may be determined by the METHOD OF TRIANGLES, as shown in the supplementary figure at the top left of the arch-ring.

Having determined the positions of the centers of gravity of the voussoirs,

parts, and with the line of action of  $O'E$  and  $O'F$  determined, the arcs dividing the arch-ring into three

Second Step. Construct the points  $E$  and  $F$  through which to draw a MINIMUM LINE OF RESISTANCE. The line of action of  $F$  and  $G$ , through which to draw a MAXIMUM LINE OF RESISTANCE can be determined. It could equally well have been chosen. It should be noted that a loaded semicircular arch is more apt to fail by opening at the intrados at the haunch, and at the extrados at the crown, and at the extrados at the haunch, and at the intrados at the crown.

lay them on the voussoirs as shown. From the point  $E$  (Fig. 12) lay off vertically to a scale of so many SQUARE UNITS TO A LINEAR UNIT, the area of each voussoir, one below the other, commencing with the top voussoir. The length of the line  $EK$  will then equal the total area of the arch-ring. From  $E$  and (Fig. 12) draw  $45^\circ$  lines intersecting at  $O$ . Draw  $Ow_1$ ,  $Ow_2$ ,  $Ow_3$ , etc. where  $OE$  intersects the first vertical line through the center of gravity of the first voussoir at  $a$ , draw a line parallel to  $Ow_1$ , intersecting the second vertical at  $b$ . Draw  $bc$  parallel to  $Ow_2$ ,  $cd$  parallel to  $Ow_3$  and so on to  $k$ . Draw  $kl$  parallel to  $Ow_{10}$  and prolong it downward until it intersects  $EO$  prolonged, at  $L$ . A vertical line drawn through  $L$  will pass through the center of gravity of the half arch-ring. This is an application to a practical problem of the method of finding, by the EQUILIBRIUM-POLYGON, the line of action of the resultant of a SYSTEM OF PARALLEL FORCES. The weights of the individual voussoirs act along parallel vertical lines and the weight of the half-arch is their resultant in magnitude.

**Third Step.** To determine the THRUST AT THE CROWN and the REACTION AT THE SPRING, draw a horizontal line through  $E$ , the upper part of the middle voussoir, and a vertical line through  $L$ , the two lines intersecting at  $I$  (Fig. 12). For the arch to be stable, it is, in general, considered necessary for the LINE OF RESISTANCE to pass within the MIDDLE THIRD. First, assume that the line of pressure or resistance starts at  $E$  and comes out at  $H$ . Draw a line  $IH$  in the direction of the line of action of the resultant of the thrust at the crown and the weight of the half-arch, and draw, also, a horizontal line opposite the thrust at  $H$ , between  $N$  and  $M$ . This horizontal line  $MN$  represents the magnitude of the horizontal thrust at the crown, for  $INM$  is the TRIANGLE OF THE THREE FORCES in equilibrium, the THRUST at the crown, the WEIGHT of the half-arch and the REACTION at the spring. Draw  $w_{10}O^p$  parallel to  $HI$ , and draw lines  $O^pw_1$ ,  $O^pw_2$ ,  $O^pw_3$ , etc.  $O^pE$ , equal to  $NM$ , is the thrust at the crown, and  $w_{10}O^p$ , equal to  $MI$ , the reaction at the spring.  $INM$  and  $EKO^p$  are similar triangles.

**Fourth Step.** It is required next, to determine the LINE OF RESISTANCE through the arch-ring. The thrust at  $E$  is combined with the weight of the first voussoir; their resultant is found and in turn combined with the weight of the second voussoir; and so on for all the voussoirs. The intersections of these resultants with the joint-lines are the CENTERS OF PRESSURE; the line joining the centers of pressure is the LINE OF RESISTANCE.

These resultants could be determined by drawing a series of PARALLELOGRAMS OF FORCES over each voussoir. This would complicate the figure and involve unnecessary labor. It is found more convenient to draw the TRIANGLES OF FORCES one after the other, at the right-hand side of the figure and then transfer the results thus obtained by means of parallel lines to the figure on the left, especially as the weights of the voussoirs have already been laid off along the line  $EK$ , at  $Ew_1$ ,  $w_2$ ,  $w_3$ ,  $w_4$ ,  $w_5$ , etc.

Then from the point where  $O^pE$  prolonged intersects the first vertical in the figure number 1, draw a (green) line to the second vertical, parallel to  $O^pw_1$ ; from this point, a (green) line to the third vertical, parallel to  $O^pw_2$  and so on. The last line should pass through  $H$ . Join the various points, where these (green) lines cut the joints at the centers of pressure, by the broken (red) line. This broken line drawn is the LINE OF RESISTANCE. If this line lies entirely within the MIDDLE THIRD of the arch-ring, the arch may be considered to be stable. Suppose that the line of resistance passes not only outside of the middle third but also outside of the arch-ring itself; it is still possible that the arch may be stable. This is the case in Fig. 12 and we will next determine if a

line of resistance can be drawn which will remain within the limits of the mid third of the arch-ring.

**Fifth Step. The Second Trial.** Reproducing the condition of Fig. 12 Fig. 13, without the construction lines, it is seen that the LINE OF RESISTANCE




Fig. 13. Line of Fracture in Unloaded Semi-circular Arch-ring

leaves the arch-ring at R enters it again at S, while furthest from it at U. If, at a perpendicular is erected straight line joining the points R and S, this perpendicular line VW, called the LINE OF FRACTURE, will be approximately the trace of the path along which, with the line of resistance under consideration the arch will tend to fail, assumedly by TURNING OVER the right about the point V. This shows that the THRUST THE CROWN, assumed to be applied at the point E, which is sufficient intensity to maintain equilibrium about H, is not sufficient intensity to maintain equilibrium about V. If a SECOND THRUST, of sufficient

intensity to maintain equilibrium about V, or better, about X, can be applied at E without being so great in magnitude that it will OVERTURN THE ARCHWARD about G, or some other point on the outer line of the middle third



Fig. 14. Second Line of Pressure in Unloaded Semicircular Arch-ring

is reasonable to conclude that the line of resistance resulting from this is very nearly the TRUE LINE OF RESISTANCE in the arch-ring and that it is stable.

In order to determine this NEW LINE OF RESISTANCE the NEW THRUST,

must be found (Fig. 14). The preliminary steps required for this are the same as before until the seventh voussoir is reached. This is divided into two parts by the line  $VW$  (Fig. 14), one being  $w6\ w6^a$  and the other the remainder of this seventh voussoir, and this division must be allowed for along the line  $EK$ , at  $w6\ w6^a$ . The line  $w6\ w6^a$  represents the area of voussoir 6, and the line  $w6^a\ w7$  the area of the remainder of the seventh voussoir. The vertical line  $IL$ , passing through the center of gravity of that part of the arch above the line  $VW$ , is found by prolonging backwards the line  $kg$ , parallel to  $O\ w6^a$ , until it intersects  $OE$  at  $L$ . To find the NEW THRUST AT THE KEY by completing the TRIANGLE OF FORCES for this thrust and the force  $W$  and opposite to their resultant, the inclined (blue) line must be drawn through the point  $X$  and the horizontal (blue) line through  $w6^a$ . The new thrust  $N$  is as before  $NM$ , equal to  $O^pE$ . This thrust is laid off at  $O^pE$ , the (green) lines  $O^p\ w\ 1$ ,  $O^p\ w\ 2$ ,  $O^p\ w\ 3$ , etc., being drawn as before and the new line of resistance being drawn through the points where the parallels to these (green)




Fig. 15. Line of Pressure in Loaded Semicircular Arch-ring

cut the joints. This NEW LINE OF RESISTANCE, if drawn correctly, should pass through  $X$ . It lies within the middle third, except for a short distance at springing, and hence it is justifiable to consider the arch stable. If it had passed outside the middle third to any great extent, in this second trial, this assumption would not have been justified.

This discussion explains the method of determining the stability of an UNLOADED SEMICIRCULAR ARCH. Such cases very seldom occur in practice, but they serve to illustrate the methods which apply generally to all other cases. In LOADED ARCH-RINGS there is slight difference in the method of determining position of the center of gravity.

**Example 3.** A LOADED OR SURCHARGED SEMICIRCULAR ARCH (Fig. 15) will be considered next. Assume the same arch shown in Figs. 12, 13 and 14, and suppose it to be loaded with a wall of masonry of the same thickness and weight per square foot as that of the arch-ring, the upper surface of the wall being an inclined plane, 1 ft above the arch-ring at the crown, and 8 ft above it at the springing. The assumption of the particular load in this case is a purely arbitrary

one for the purpose of illustrating the method of solution. The determination of the ACTUAL LOAD that comes upon an arch in any given case is by no means easy, so numerous are the uncertain elements that affect the transmission of this load to the arch-ring.

The customary procedure is to assume that the load is itself transmitted to the arch-ring VERTICALLY DOWNWARD. Each voussoir thus receives that portion of the load which is included between two vertical lines drawn to the points of intersection of the joints on either side of that voussoir with the extrados. In making this assumption it is necessary next to determine how much of the total superimposed masonry bears upon the arch-ring.

It is a matter of common observation that if an opening is made in a wall, especially in a wall that has stood for some time, the major portion of the masonry above this opening is self-supporting, limited portions only, bounded by a somewhat irregular line, falling down into the opening, as shown in Fig. 16.




Fig. 16. Triangle of Loading over Opening

The profile of this boundary-line depends upon the nature of the material of which the wall is constructed, the size of the stones or bricks, etc., the character of the joints, and the quality of the mortar. In the worst case, all the masonry above the arch should not be considered as a load on it. Some authorities recommend considering as the proper load, for design work, a TRIANGULAR PART of the masonry above the arch, the sides of which triangle have an inclination to the horizontal of  $45^\circ$ ; others assume an inclination of  $60^\circ$  (Fig. 16). (See, also, Chapter XV, page 612.)

The exact determination of this load by the mechanical laws is difficult if not impossible. It is better to consider each case separately and by a careful study of the conditions to determine as far as possible just what portion of the weight of the superimposed masonry is transmitted to the arch. Having assumed a load for this particular arch (Fig. 15), the procedure is as follows:


**First Step of Example 3.** This involves the finding of the CENTER OF GRAVITY of the ARCH-RING AND LOAD COMBINED. Divide the arch-ring into five voussoirs of equal size. In this case the area of each voussoir is equal to 44.2 sq ft - 8.8 sq ft. (See under First Step, Fig. 12, preceding example.) The surcharge or load, also, is divided into five parts, not necessarily equal, by drawing vertical lines to the points of intersection of the joints and the extrados. The approximate area of each one of these surcharges is found by multiplying the sum of the lengths of the two parallel vertical sides by the length of the horizontal distance between them.

The positions of the center of gravity of each voussoir and of the center of gravity of each voussoir-surcharge are determined as in the preceding example. The CENTERS OF GRAVITY of these SURCHARGES can be found by dividing the TRAPEZOIDAL FIGURE into TRIANGLES as shown, remembering that the MEDIAN LINE in this case joins the middle points of the two parallel faces. As the joints are vertical, the medial lines approach a horizontal direction. This condition is shown on surcharge 1<sup>a</sup>, Fig. 15. Having drawn the lines of action of the weights of the various voussoirs and of their loads through their respective centers of gravity, the lines of action of the combined weight of each voussoir and its load must be found. The construction for this operation is shown



left of Fig. 15. The method used, that of the EQUILIBRIUM-POLYGON, is the same as that employed in the previous example to find the line passing through the center of gravity of the half-arch, only in this case the forces are reduced to two. Furthermore, as the areas of the various voussoirs are equal it is possible to superimpose the different FORCE-DIAGRAMS, one over the other, to save considerable labor. Begin, therefore, by laying off along the line  $AK$  at the left of the loaded arch, and at any convenient scale,  $f w$ , the area of a voussoir; then from  $w$ , in turn, the distances  $w_1^a$ ,  $w_2^a$ ,  $w_3^a$ , etc., representing the areas of the successive surcharges,  $1^a$ ,  $2^a$ ,  $3^a$ , etc., always at the same scale. The scale to be employed later for laying off the combined weights of the voussoirs and their loads along the line  $AK$  is the best one to choose, but a difference in scales is not important. In this particular instance the two scales  $1^a$  and  $5^a$  coincide because the two areas  $1^a$  and  $5^a$ , although of different shapes, are each equal to 6.7 sq ft. This is a mere coincidence. Next draw  $O'w$  and  $O'1^a$  at  $45^\circ$  to  $RS$ , and in turn,  $O''w$ ,  $O''1^a$ ,  $O''2^a$ , etc. As the problem presents itself is to combine the weight of each voussoir with its individual surcharge, and as the weights of all the voussoirs are equal, and, furthermore, the forces which are to be combined to find their resultant are only two, the POLE-LINES or RAYS  $O'f$  and  $O''w$  in the FORCE-DIAGRAM serve in each case, and the FUNICULAR POLYGON is reduced to a TRIANGLE. Draw  $gh$ ,  $ik$ ,  $lm$ ,  $np$  parallel to  $O''w$ , and  $ht$ ,  $ku$ ,  $mv$ ,  $px$  and  $sy$  parallel to  $O'f$ ; and draw  $gl$ ,  $ku$  and  $ry$  parallel respectively to  $O''1^a$ ,  $O''2^a$ ,  $O''3^a$ ,  $O''4^a$  and  $O''5^a$ . The points  $t$ ,  $u$ ,  $v$ ,  $x$  and  $y$  are the points through which to draw the heavy (red) line of action of the combined weights of the voussoirs and their surcharges. Having found and drawn these lines, the procedure for finding the line  $IN$  is the same as in the previous example, except that the distances  $Ew_1 1^a$ ,  $w_1 1^a$ ,  $2^a$ , etc., instead of being equal to the weights of the voussoirs alone, are equal to the combined weights of each voussoir and its surcharge,  $Ew_1 1^a$ , being equal to  $f 1^a$ ,  $w_1 1^a$  to  $w_2 2^a$  being equal to  $f 2^a$ , etc. The line  $EO$  is drawn at  $45^\circ$  to  $AO'$ , but as the position of the POLE-POINT,  $O$ , is entirely arbitrary, the line  $Ow_5 5^a$  has been drawn in this case in such a way that  $O$  falls well over toward the left of the figure, thus avoiding a certain amount of confusion in the drawing which would have resulted if  $Ow_5 5^a$  made an angle of  $45^\circ$  with  $AO'$ . The lines  $ab$ ,  $bc$ ,  $cd$  and  $de$  are drawn respectively parallel to  $w_1 1^a O$ ,  $w_2 2^a O$ , etc., and  $eL$  is produced backward parallel to  $w_5 5^a$  until it intersects  $EO$  at  $L$ , which is the point through which the heavy (red) line  $IN$ , passing through the center of gravity of the whole half-arch and its surcharge, should be drawn. A vertical line drawn through  $L$  will pass through the center of gravity of the arch-ring and its load. If this were an arch used for a building and if the only abutments possible were of such size and position that it was essential for the thrust exerted by the last or fifth voussoir on the abutments to approach more nearly the vertical, the architectural expedient of increasing slightly the weight of the surcharge,  $5^a$ , on this voussoir by adding a piece of ornament, such as a cartouche, could be resorted to. A case of this kind in actual practice is the archway over the entrance to the service-court of the Grand Opera House in Paris, where the pyramidal stone ornaments which surmount the cornice on either side of the central motive were added after the original design was made, with this end in view. In the example illustrated in Fig. 15 the areas of the faces of the surcharges are shown by the figures on the faces. For the second surcharge from the crown, for example, the area is 6.7 sq ft.

**Second Step of Example 3.** This involves the determination of the THRUST AT THE CROWN and the LINE OF RESISTANCE. The method of finding this thrust



The crown is similar to that employed in the previous example. In that example, however, it was found that this thrust, applied at  $E$  and determined using  $H$  as the point of application of the reaction at the spring, produced a line of resistance which fell considerably below the middle third. But instead of repeating the operations required by a second trial, as in the previous example, the expedient is tried of slightly increasing the inclination to the vertical (blue) line  $IM$ , and so assuming a somewhat greater THRUST AT THE CROWN. As the line of resistance, as shown in Fig. 15, passed with this thrust only slightly from the middle third near the springing, we are justified in assuming that this arch is stable under the given conditions. The method for this example may be used, also, for a SEMIELLIPTICAL ARCH.

Example 4. This example (Fig. 17) illustrates the application of the preceding methods, with some variations, to the determination of the position of the center of gravity of a LOADED SEGMENTAL ARCH, the thrusts at the crown and springing, and the line of pressure or resistance through the arch-ring. In this case, instead of dividing the arch-ring into a certain number of voussoirs with joints radiating from a center and considering the surcharge on each individual voussoir, the method of dividing the arch-ring and its load into VERTICAL SLICES, in this case 1 foot wide, and computing the areas of the entire slices has been adopted. Having computed the areas of the slices, including in each case the combined area of the sliced part of the arch-ring and its surcharge, we lay them off in order from  $E$  to a convenient scale, and then proceed as in the previous examples. The remaining steps required to determine the thrusts at the crown and at the springing and the line of resistance are also the same as explained in the foregoing examples. In a FLAT SEGMENTAL ARCH there is practically no need of dividing the arch-ring into voussoirs by JOINTS RADIATING FROM A CENTER, in order to determine its stability. Of course, when built, they must be made to radiate. Fig. 17 shows the GRAPHICAL ANALYSIS of an arch of 40-ft span and carrying a load 13½ ft high at the crown. The depth of the arch-ring is 2 ft 6 in. It is found that the line of resistance lies entirely within the middle third, and that the arch is therefore stable. It is to be noted that the line of resistance in a SEGMENTAL ARCH should be drawn through the LOWER OR INNER EDGE of the middle third at the springing. It is to be noted, also, that the horizontal thrust at the crown and the thrust  $T$  against the supports are very great when compared with those in a SEMICIRCULAR ARCH; and hence, although the SEGMENTAL ARCH is the stronger of the two, it requires much heavier abutments. The foregoing examples serve to show the various methods of determining the stability of any arch used in buildings.

## CHAPTER IX

## REACTIONS AND BENDING MOMENTS FOR BEAMS

By

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. Reactions for Simple Beams

**Definition of Reaction.** One of the fundamental principles of static equilibrium is that the sum of all the forces acting upon a body in one direction is balanced by the sum of another set of forces acting in the opposite direction. Therefore, in the case of a beam or girder, the loads acting downward are balanced by an equal set of forces at the supports, acting upward. These upward forces are called **THRUSTS**, or **REACTIONS** and in computing the reactions of beams one of the first steps is to determine them, since the loads are given in intensity and position.

**The Principle of Moments.** The reactions may be determined by the application of another fundamental principle of static equilibrium for forces acting in the same plane. The algebraic sum of the moments of all the




Fig. 1. Simple Beam. One Concentrated Load

taken about any point in the plane in which they act must be zero. The **MOMENT OF A FORCE** about a point is the product of the magnitude or intensity of the force by the perpendicular distance between the **LINE OF ACTION** of the force and the point. The perpendicular distance is called the **LEVER-ARM**, and the point is the **CENTER OF MOMENTS**. Forces acting upward are considered **POSITIVE** and those acting downward are considered **NEGATIVE**. The center of moments may be taken at any point in the plane of action of the forces, but it is convenient to take it at one of the reactions. For example, the beam supports a concentrated load  $P$  at the distance  $m$  from the left support. If we take the left reaction  $R_1$  as the center of moments at the right reaction  $R_2$ , the **EQUATION OF MOMENTS** is

$$R_1 l - P n = 0.$$

from which

$$R_1 = P n / l$$

In like manner, to find  $R_2$  the center of moments is taken at  $R_1$  and the equation of moments is

$$R_2 l - Pm = 0, \text{ from which } R_2 = Pm/l \quad (1)'$$

By the first principle of statics mentioned,  $R_1 + R_2$  must equal  $P$ ; hence, to check,  $(Pn/l) + (Pm/l) = P$ .

**Example 1.** Let a beam 15 ft in span support a concentrated load of 700 lb, 6 ft from the left end; or,  $P = 700$ ,  $m = 6$  and  $n = 9$ . Then, from Formula (1),  $R_2 = (700 \times 9)/15 = 420$  lb.  $R_1 = (700 \times 6)/15 = 280$  lb, and  $420 + 280 = 700$  lb, for a concentrated load at the middle, or for a uniform load over a simple beam, it is evident without applying the conditions of equilibrium, that each reaction is one-half the load, for, in Formulas (1) and (1)',  $m$  and  $n$  each equal  $l/2$  and  $R_1$  and  $R_2 = \frac{1}{2} P$ .

For any number of concentrated loads (Fig. 2) the reactions may be found by adding together the reactions found by Formula (1) due to each load separately, they may be computed in one operation by the following formula:




Fig. 2. Simple Beam. Three Concentrated Loads

To find the right reaction, the center of moments is taken at the left support, the equation of moments is

$$R_2 l - P_1 m_1 - P_2 m_2 - P_3 m_3 = 0$$

$$R_2 = \frac{P_1 m_1 + P_2 m_2 + P_3 m_3}{l} \quad (2)$$

In like manner, to find  $R_1$  the center of moments is taken at  $R_2$  and the equation of moments is

$$R_1 l - P_1 n_1 - P_2 n_2 - P_3 n_3 = 0$$

$$R_1 = \frac{P_1 n_1 + P_2 n_2 + P_3 n_3}{l} \quad (3)$$

**Example 2.** Suppose the beam in Fig. 2 is 20 ft in length. Let there be three concentrated loads of 500, 800 and 600 lb placed 5, 9 and 12 ft respectively from the left support. Then  $l = 20$ ,  $m_1 = 5$ ,  $m_2 = 9$ ,  $m_3 = 12$ ,  $P_1 = 500$ ,  $P_2 = 800$ ,  $P_3 = 600$ . Substituting in Formulas (2) and (3),

$$R_2 = \frac{500 \times 5 + 800 \times 9 + 600 \times 12}{20} = 845 \text{ lb}$$

$$R_1 = \frac{500 \times 15 + 800 \times 11 + 600 \times 8}{20} = 1055 \text{ lb}$$

$$500 + 800 + 600 = 845 + 1055 = 1900 \text{ lb}$$

To find the reactions for a combination of uniformly distributed and concentrated loads, to each of the reactions obtained by Formulas (1) or (2) for concentrated loads, add one-half the distributed load. Thus, suppose a 20-ft beam in this example weighs 40 lb per linear ft. This is considered a uniformly distributed load and for the entire beam it is  $40 \text{ lb} \times 20 = 800 \text{ lb}$ . By the rule, one-half of this is added to each reaction, so that the total reactions are,  $R_2 = 845 + 400 = 1245 \text{ lb}$  and  $R_1 = 1055 + 400 = 1455 \text{ lb}$ .

**Example 3.** For a distributed load applied over only a part of the span, Fig. 3, assume the load to be CONCENTRATED AT THE MIDDLE of the part




Fig. 3. Simple Beam. Distributed Load over Part of Span

which it acts and use Formulas (1) and (1)'. For example, let  $w$  (Fig. 3) equal 50 lb per linear ft, applied for a distance of 5 ft over the beam. Then  $W$ , the load, is  $50 \text{ lb} \times 5 = 250 \text{ lb}$ . This may be assumed to be concentrated at its center, 4.5 ft from the left support. Then  $P = 250$ ,  $m = 4.5$  and  $n = 5.5$  from Formulas (1) and (1)',

$$R_1 = \frac{250 \times 5.5}{10} = 137.5 \text{ lb}$$

and

$$R_2 = \frac{250 \times 4.5}{10} = 112.5 \text{ lb}$$

Therefore, for any combination of concentrated and uniform loads distributed over the entire beam, or over only part of it, find the reactions due to the concentrated loads by Formulas (1) or (2), and to them add the reactions due to the uniformly distributed loads.

## 2. Bending Moments in Cantilever and Simple Beams\*

**Definitions.** The bending moment is a measure of the tendencies of force to break a beam by BENDING or FLEXURE. Fig. 4 shows the manner in which a simple beam, supported at the ends, breaks when subjected to a load greater than it can bear. The effect of a load upon a beam is to cause it to SAG or BEND. The bending of the beam shortens, or compresses, the upper fibers and stretches, or elongates, the lower fibers. So long as the resistance of the

\* See, also, Chapter XV, pages 555 to 564.

stretching, or compression, and to stretching, or tension, is greater than tendency of the load to disrupt them, the beam carries the load; but, when load causes a greater tension, or compression, on the fibers than they are capable of resisting, the beam breaks. The stretching of the fibers before breaking allows the beam to bend; hence, the name **BENDING MOMENT** has been given to the forces causing a beam to **BEND** and perhaps ultimately to **BREAK**.



Fig. 4. Manner of Rupture of Simple Beam

In order to calculate the **FLEXURAL STRENGTH** OF A BEAM, it is necessary to determine the nature and extent, first, of the **EXTERNAL FORCES** acting to break the beam, and secondly of the **INTERNAL FORCES** or **STRESSES** tending to resist them.\* The external forces tending to break the beam by flexure are the **DOWNWARD LOADS** and the **UPWARD REACTIONS**. Each acts with a **LEVERAGE** equal to the perpendicular distance from its **LINE OF ACTION** to the section at which the beam tends to break. The algebraic sum of the moments of these external forces on the left, or right, of any section is called the **BENDING MOMENT** at that section, since it is the **MOMENT OF THE RESULTANT OF THE FORCES** which tends to bend the beam at that section. It is generally designated by  $M$ . Then, in the definition, the **BENDING MOMENT** for any section of a beam resting on supports and in a state of flexure under a load or loads is  $M =$  the moment of either reaction minus the sum of the moments of the loads between that reaction and the section. The moment of the reaction is **UPWARD**, or **POSITIVE**, and the moment of any load **DOWNWARD**, or **NEGATIVE**, if the part of the beam on the left of the section is considered.

## Bending Moments in Beams for Different Kinds of Loading

### Case I

Beam Fixed at One End and Loaded with a Concentrated Load  $P$ , Near the Free End (Fig. 5).

Maximum bending moment, at wall  $= P \times l$

Bending moment at any other section  $x = Px$

Note. If  $l$  is in feet, the bending moment will be in foot-pounds; if  $l$  is in inches, the bending moment will be in inch-pounds.

Fig. 5. Cantilever Beam. Concentrated Load near Free End

### Case II

Beam Fixed at One End and Loaded with a Uniformly Distributed Load  $W$  (Fig. 6)

Maximum bending moment, at wall  $= W \times l/2$

At any other section  $x$ ,  $M = wx \times x/2 = wx^2/2$

Note.  $W = wl$  and  $w =$  the load per unit of length.

\* See Chapter X for a discussion of these internal stresses and of the resisting moment.

## Case III

Beam Fixed at One End and Loaded with Both a Concentrated and a Uniformly Distributed Load (Fig. 7).

Maximum bending moment, at wall =  $P \times l + W \times l/2$

Fig. 6. Cantilever Beam. Uniformly Distributed Load

Fig. 7. Cantilever Beam. Distributed Load and Load at Free End

## Case IV

Beam Supported at Both Ends and Loaded with a Concentrated Load Middle (Fig. 8).

Maximum bending moment, under the load =  $Pl/4$




Fig. 8. Simple Beam. Concentrated Load at the Middle

## Case V

Beam Supported at Both Ends and Loaded with a Uniformly Distributed Load  $W$  (Fig. 9).

Maximum bending moment, at the middle =  $Wl/8$



Fig. 9. Simple Beam. Uniformly Distributed Load



### Case VI

Beam Supported at Both Ends and Loaded with a Concentrated Load not at the Middle (Fig. 10).

Maximum bending moment, under the load =  $Pmn/l$

Fig. 10. Simple Beam. Concentrated Load not at the Middle

### Case VII

Beam Supported at Both Ends and Loaded Symmetrically with Two Equal Concentrated Loads (Fig. 11).

Maximum bending moment =  $Pm$  and is the same for any section of the beam between the two loads.



Fig. 11. Simple Beam. Two Concentrated Loads Symmetrically Placed

From these examples it will be seen that all the quantities which enter into computation of the bending moment are the load, the span and the distance from point of application of the load from the center of moments.

### Case VIII

Beam Supported at Both Ends and Loaded with a Distributed Load Over Part of Span (Fig. 12).




Fig. 12. Simple Beam. Distributed Load over Part of Span

Maximum bending moment under the center of the load,  $M_{\max} = Wmn/l - Wl_1/8$

If  $m$  and  $n$  are equal the bending moment =  $W \times l/4 - W \times l_1/8$

This is only approximately correct when  $m$  and  $n$  are unequal. For the exact value, find the section of zero shear; the maximum bending moment will be at that section. (See, Example 5, page 561.)

**Example 4.** In Fig. 12 let  $W = 800$  lb,  $m = 8$  ft,  $n = 12$  ft,  $l = 20$  ft and  $l_1 = 4$  ft. Then the bending moment

$$= \frac{800 \times 8 \times 12}{20} - \frac{800 \times 8}{8} = 3840 - 800 = 3040 \text{ ft-lb, or } 36480$$

**Example 5.** In Fig. 12 let  $m = n = 10$  ft,  $l = 20$  ft,  $l_1 = 4$  ft and  $W = 600$  lb. Then the bending moment


$$= \frac{600 \times 20}{4} - \frac{600 \times 4}{8} = 3000 - 300 = 2700 \text{ ft-lb, or } 32400 \text{ in-lb}$$

The Bending Moment for any Case Other Than the Above may easily be obtained by the GRAPHIC METHOD, which will now be explained.

#### 4. Graphic Method of Determining Bending Moments in Beams

##### Beam with One Concentrated Load (Fig. 13).

The BENDING MOMENT of a beam supported at both ends and loaded with a concentrated load may be determined GRAPHICALLY, as follows:



Let  $P$  be the load applied as shown. By the rule under Case 1, the MAXIMUM BENDING MOMENT is under the load and  $= Pmn/l$ .

Draw the beam, to the given span, according to scale, and measure the line  $AB$ , to a scale of FEET-POUNDS to the INCH, a distance to the bending moment. Connect  $B$  with each end of the beam.

Fig. 13. Bending-moment Diagram. One Concentrated Load

To find the bending moment at any other point of the beam, as at  $o$ , draw the vertical line  $y$  to  $BC$ . Its length, measured to the scale to which  $AB$  is drawn, will give the bending moment at  $o$ . The  $DBCAD$  is called the BENDING-MOMENT DIAGRAM and the lines  $BD$  and  $BC$  are called INFLUENCE LINES for the bending moments.




Fig. 14. Bending-moment Diagram. Two Concentrated Loads

##### Beam with Two Concentrated Loads (Fig. 14).

To draw the bending-moment diagram for a beam with two concentrated loads, draw the dotted lines  $ABD$  and  $ACD$ , giving the BENDING-MOMENT

for each load separately.  $EB$  is laid out to scale, equal to  $Pmn/l$  and equal to  $Pvs/l$

The bending moment at the point  $E$  is equal to  $EB$  (from the load  $P$ ) +  $Eb$  (from the load  $P_1$ ), or  $M = EB + Eb = EB_1$ ; and at  $F$  the bending moment is equal to  $FC + Fc = FC_1$ . The BENDING-MOMENT DIAGRAM for both loads is  $ECF$  and the MAXIMUM BENDING MOMENT is, in this particular case, the line  $ECF$  measured to scale.

Beam with Any Number of Concentrated Loads (Fig. 15.)

Proceed as in the last case, and draw the BENDING-MOMENT DIAGRAM for each load separately. Make  $AD = A_1 + A_2 + A_3$ ,  $BE = B_1 + B_2 + B_3$  and




Fig. 15. Bending-moment Diagram. Three Concentrated Loads

$= C_1 + C_2 + C_3$ . The figure  $HDEFIH$  will then be the BENDING-MOMENT DIAGRAM corresponding to all the loads. The BENDING-MOMENT DIAGRAM for a beam with any number of concentrated loads may be drawn in the same way.

Beam with a Uniformly Distributed Load (Fig. 16.)

Draw the beam with the given span, accurately to a scale as before, and at the middle of the beam draw the vertical line  $AB$ , to a scale of a certain number of FOOT-POUNDS to

LINEAR INCH, equal to  $Wl/8$ , from the  $V$ ,  $W$  represent the whole distributed load. Connect points  $C, B, D$  by a PARABOLA to obtain the BENDING-MOMENT DIAGRAM. To find the bending moment at any point  $a$ , draw a vertical line  $ab$ , compare it to the




Fig. 16. Bending-moment Diagram. Distributed Load over Whole Beam

scale to which  $AB$  is drawn, and it will be the bending moment desired. Methods for drawing the PARABOLA will be found in Part I, page 79.

Beam Loaded with Both Distributed and Concentrated Loads (Fig. 17.)

To determine the bending moments in this case, combine the BENDING-MOMENT DIAGRAMS for the concentrated loads and for the distributed load, as shown in

Fig. 17. The bending moment at any section of the beam will then be limited by the line  $ABC$  on top and by the line  $CDEFA$  on the bottom; and the MAXIMUM BENDING MOMENT will be the longest vertical line that can be drawn




Fig. 17. Bending-moment Diagram. Distributed and Concentrated Loads

between these bounding lines.

For example, the maximum bending moment is  $BE$ . The position of the MAXIMUM BENDING MOMENT depends upon the position of the concentrated loads and their relative magnitudes to the distributed load. It may or may not occur at the middle of the beam or under one of the concentrated loads.

#### Example 6.

is the greatest bending moment in a beam

20 ft span (Fig. 18), loaded with a distributed load of 800 lb, a concentrated load of 500 lb 6 ft from one end, and a concentrated load of 600 lb 7 ft from the other

**Solution.** (1) The maximum bending moment due to the distributed load from Case V, is  $Wl^2/8$ , or  $800 \times 20^2/8 = 2000$  ft-lb. Lay off vertically over the middle of the beam, and at any convenient scale, say 4000 ft-lb to the inch,  $B_1 = 2000$  ft-lb, and draw a parabola through the points  $A$ ,  $B_1$  and  $C$ . (See page 79.)

(2) The maximum bending moment for the concentrated load of 500 lb, from Case VI, is  $500 \times 6 \times 14/20$ , or 2100 ft-lb. Draw  $B_2 = 2100$  ft-lb to the same scale as  $B_1$ , and then draw the lines  $AE$  and  $CE$ .

(3) The maximum bending moment for the concentrated load of 600 lb, in like manner, is  $600 \times 7 \times 13/20$ , or 2730 ft-lb. Draw  $D_3 = 2730$  ft-lb and connect  $D$  with  $A$  and  $C$ .

(4) Make  $EH$  equal to the distance from 2 to 4, and  $DG$  to the distance from 3 to 5, and draw  $AHGC$ .

The MAXIMUM BENDING MOMENT will be represented by the longest vertical line which can be drawn between the parabola  $ABC$  and the broken line  $AHGC$ . In this example the longest vertical line which can be drawn is  $XY$ , which should scale 5645 ft-lb.




Fig. 18. Bending-moment Diagram. Distributed and Concentrated Loads

The position of the line  $Xy$  is determined by drawing the line  $TT_1$  parallel to  $BC$  and tangent to  $ABC$ . Draw  $Xy$  vertically through point of tangency.

### Reactions and Bending Moments for Beams with Triangular Loading and for Beams Fixed at Both Ends.\*

Beams with Triangular Loading have reactions and bending moments as follows:

#### Beam Supported at Both Ends, Fig. 19 (a)


Reactions:  $R_1 = R_2 = \frac{1}{2} W$   
 Bending moment at any point  $= Wx(\frac{1}{2} - \frac{2x^2}{3l^2})$   
 Maximum bending moment, at center  $= Wl/6$

#### Beam Supported at Both Ends, Fig. 19 (b)

Reactions:  $R_1 = \frac{1}{3} W, R_2 = \frac{2}{3} W$   
 Bending moment at any point  $= (Wx/3)(1 - x^2/l^2)$   
 Maximum bending moment (at  $x = 0.58 l$ )  $= .128 Wl$

#### Cantilever Beam, Fig. 19 (c)

Reactions:  $R_1 = W$   
 Bending moment at any point  $= Wx^2/3 l^2$   
 Maximum bending moment (at  $R_1$ )  $= Wl/3$



Reactions and bending moments for Beams of Cases IV, V, and VI, with Fixed Ends, Fig. 19. Triangular Loading on Beams

#### Case IV A. Beam Fixed at Both Ends, with a Concentrated Load $P$ at the Middle (Fig. 8)

End-reactions:  $R_1 = R_2 = \frac{1}{2} P$   
 Maximum positive bending moment, under the load  $= Pl/8$   
 Maximum negative bending moment, at ends  $= Pl/8$

#### Case V A. Beam Fixed at Both Ends, with a Uniformly Distributed Load $W$ (Fig. 9)

End-reactions:  $R_1 = R_2 = \frac{1}{2} W$   
 Maximum negative bending moment, at ends  $= Wl/12$   
 Maximum positive bending moment, at center  $= Wl/24$

#### Case VI A. Beam Fixed at Both Ends, with a Concentrated Load $P$ at Distance $m$ from Left End and Distance $n$ from Right End (Fig. 10)

End-reactions:  $R_1 = Pn^2(3m + n)/l^3; R_2 = Pm^2(3n + m)/l^3$   
 Maximum bending moment, negative, at left end,  $M_1 = Pmn^2/l^2$   
 at right end,  $M_2 = Pm^2n/l^2$   
 Bending moment under load, positive  $= R_1m - M_1$

\* From notes by Robins Fleming.

## CHAPTER X

# PROPERTIES OF CROSS-SECTIONS OF STRUCTURAL SHAPES. MOMENT OF INERTIA, MOMENT OF RESISTANCE, SECTION-MODULUS, AND RADIUS OF GYRATION

By

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. The Properties of Cross-Sections

**The Moment of Inertia.** The strength of a cross-section to resist stress in either a beam or a column, depends not only upon the area but also upon the form of the cross-section. The parts of the cross-section farthest from the neutral axis, which always passes through the center of gravity of the section, are much more efficient in resisting bending stresses than those adjacent to the axis; so that some mathematical expression must be obtained that will represent the efficiency of the entire cross-section to resist bending stresses when compared with that of any other cross-section. This expression is called the **MOMENT OF INERTIA** and is usually designated by the letter  $I$ .

**The Moment of Inertia** of any cross-section may be defined as the sum of the products obtained by multiplying each of the elementary areas of which the section is composed by the square of its normal distance from the neutral axis of the section.

By an **ELEMENTARY AREA** is meant an area smaller than any dealt with in simple mathematics, and it is, therefore, impossible to find an exact expression for the moment of inertia of a cross-section by such methods. By means of calculus, however, exact formulas have been deduced from which the moment of inertia of simple geometrical forms, such as rectangles, triangles, circles, etc., may be found, with respect to different axes.

The **NEUTRAL AXIS** of the cross-section of a beam, girder, column, etc., when it is in a state of flexure, is the line on which there is neither tension nor compression in the fibers, and when the unit stresses do not exceed the **ELASTIC LIMIT** of the material, it can be shown that this neutral axis passes through the **CENTER OF GRAVITY** of the cross-section. The normal distance of the extreme fibers from the neutral axis is usually designated by the letter  $c$  or the letter  $y$ . The formulas used in the notation of this book.

Since for all sections except squares and circles, there are, in general, two principal axes corresponding to the more common positions of the sections, it follows that there are also two moments of inertia commonly used; for a rectangular example, a **GREATEST MOMENT OF INERTIA** about an axis perpendicular to the long side and a **LEAST MOMENT OF INERTIA** about an axis perpendicular to the short side. The moments of inertia of the cross-sections of all rolled structural shapes have been calculated and are tabulated in the manufacturers' handbooks. For example, the moments of inertia of the cross-section of a 12-in, 31.5-lb I-beam with respect to axes perpendicular to the web and parallel to the web, are given in Table IV, equal to 215.8 and 9.5 biquadratic inches respectively. Formulas for calculating the moments of inertia of other simple sections are given on the following pages.

**The Moment of Resistance.** In Chapter IX, under the chapter-subdividing of the BENDING MOMENTS in beams, page 325, it was stated that in order to calculate the FLEXURAL STRENGTH of a beam it is necessary to obtain the nature and extent, first, of the external forces tending to break the beam by flexure, and, secondly, of the internal forces or stresses tending to resist rupture. The external forces cause the BENDING MOMENTS,\* and the internal stresses the MOMENTS OF RESISTANCE, at the various cross-sections of the beam.

The MOMENT OF RESISTANCE or the RESISTING MOMENT at any cross-section of a beam is the algebraic sum of all the moments of the internal horizontal stresses in that section with reference to a point in that section. It is usually denoted by the expression  $SI/c$ , in which  $S$  is the horizontal unit stress, either tensile or compressive, as the case may be, upon the fiber most remote from the neutral axis of the section, and called the FIBER-STRESS;  $I$  is the MOMENT OF INERTIA of the area of the section with reference to the NEUTRAL AXIS; and  $c$  is the shortest distance from the most remote fiber to that axis. Since, for equilibrium of forces and stresses at any cross-section of a beam, the bending moment equals the resisting moment for that section, if  $M$  represents the bending moment we have the equation

$$M = SI/c \quad (1)$$

This is known as the FLEXURE FORMULA and is universally used for investigating the flexural strength of beams.

**The Section-Modulus or Section-Factor.** That expression  $I/c$  in the above formula is generally known as the SECTION-MODULUS or SECTION-FACTOR. A quantity for the principal rolled sections is given in Tables IV, V, VI, VII, VIII, XI, XII, XIII and XIV. Corresponding to the two moments of inertia usually used for all sections (except for squares and circles) there are two section-moduli also, one for each axis. Thus, the section-modulus of the 12-in.  $\times$  30-lb I beam, with respect to a neutral axis perpendicular to the web, is  $715.8/6 = 36$ ; and for the axis parallel to the web, it is  $I/c = 9.5/2.5 = 3.8$ . For other shapes the section-modulus may be found by dividing the moment of inertia by the normal distance of the extreme fiber from the neutral axis.

**The Radius of Gyration.** The effect of the form of the cross-section of a beam on its strength is determined by a quantity called the RADIUS OF GYRATION, which is as necessary in the determination of the strength of a column as the moment of inertia is in the determination of the strength of a beam. It is denoted by the letter  $r$ . The value of the radius of gyration for any section is determined by the formula

$$r = \sqrt{I/A} \quad (2)$$

in which  $I$  is the MOMENT OF INERTIA of the section and  $A$  the SECTION-AREA. The RADIUS OF GYRATION is the normal distance from the NEUTRAL AXIS to the CENTER OF GYRATION, and the center of gyration of a section is the point where the entire area might be concentrated and have the same moment of inertia as the actual distributed area. The radius of gyration of a section is a DISTANCE which is always less than the distance,  $c$ , from the neutral axis to the remotest fiber. For the two moments of inertia above referred to, and commonly used, there are two corresponding radii of gyration. The least of these is the one to be used in the investigation of the strength of a column as it is referred to the axis about which the column is most likely to fail. The radii of gyration of the rolled

\* See Chapter IX, page 325, for definition of "bending moment."

shapes are given in the tables of the properties of sections, mentioned a For the 12-in 31.5-lb I beam,  $r = 4.83$  in and  $r' = 1.01$  in. The radius of gyration of any other section may be found by Formula (2).

Formulas for the moments of inertia, radii of gyration and section-moduli of the principal elementary sections are given on the following pages. In case of a hollow section or a section with a reentering hollow part, the moment of inertia of the hollow part is to be subtracted from that of the enclosing shape. Moments of inertia when referred to the same axis can be added or subtracted like any other quantities which are of the same kind.

## 2. Areas, Moments of Inertia, Section-Moduli and Radii of Gyration of Elementary Sections

$I$  = the moment of inertia

$I/c$  = the section-modulus

$r$  = the radius of gyration


$A$  = the area of the section

$c$  = the normal distance of most remote fiber from neutral axis

The position of axis referred to in each case is represented by the broken line in the diagrams.

### SQUARE

Axis of moments through center



$$A = d^2$$

$$c = \frac{d}{2}$$


$$I = \frac{d^4}{12}$$

$$\frac{I}{c} = \frac{d^3}{6}$$

$$r = \frac{d}{\sqrt{12}} = 0.288675 d$$

### SQUARE

Axis of moments on base



$$A = d^2$$

$$c = d$$

$$I = \frac{d^4}{3}$$


$$\frac{I}{c} = \frac{d^3}{3}$$

$$r = \frac{d}{\sqrt{3}} = 0.577350 d$$



### RECTANGLE

Moments through center



$$A = bd$$

$$c = \frac{d}{2}$$


$$I = \frac{bd^3}{12}$$

$$\frac{I}{c} = \frac{bd^2}{6}$$

$$r = \frac{d}{\sqrt{12}} = 0.288675 d$$

### RECTANGLE

Moments on base



$$A = bd$$

$$c = d$$


$$I = \frac{bd^3}{3}$$

$$\frac{I}{c} = \frac{bd^2}{3}$$

$$r = \frac{d}{\sqrt{3}} = 0.577350 d$$

### HOLLOW SQUARE

Moments through center



$$A = d^2 - d_1^2$$

$$c = \frac{d}{2}$$


$$I = \frac{d^4 - d_1^4}{12}$$

$$\frac{I}{c} = \frac{d^4 - d_1^4}{6d}$$

$$r = \sqrt{\frac{d^2 + d_1^2}{12}}$$

### HOLLOW RECTANGLE

Moments through center



$$A = bd - b_1d_1$$

$$c = \frac{d}{2}$$


$$I = \frac{bd^3 - b_1d_1^3}{12}$$

$$\frac{I}{c} = \frac{bd^3 - b_1d_1^3}{6d}$$

$$r = \sqrt{\frac{bd^3 - b_1d_1^3}{12(bd - b_1d_1)}}$$

## HOLLOW RECTANGLE AND I BEAM

Axis of moments through center



$$A = bd - b_1 d_1$$

$$c = \frac{d}{2}$$


$$I = \frac{bd^3 - b_1 d_1^3}{12}$$

$$\frac{I}{c} = \frac{bd^3 - b_1 d_1^3}{6d}$$

$$r = \sqrt{\frac{bd^3 - b_1 d_1^3}{12 (bd - b_1 d_1)}}$$

## TRIANGLE

Axis of moments through  
center of gravity



$$A = \frac{bd}{2}$$

$$c = \frac{2d}{3} \quad c_1 = \frac{d}{3}$$


$$I = \frac{bd^3}{36}$$

$$\frac{I}{c} = \frac{bd^3}{24}$$

$$r = \frac{d}{\sqrt{18}} = 0.235702 d$$

## TRIANGLE

Axis of moments on base



$$A = \frac{bd}{2}$$

$$c = d$$


$$I = \frac{bd^3}{12}$$

$$\frac{I}{c} = \frac{bd^3}{12}$$

$$r = \frac{d}{\sqrt{6}} = 0.408248 d$$

## TRAPEZOID

Axis of moments through  
center of gravity



$$A = \frac{d(b + b_1)}{2}$$

$$c^* = \frac{d(b_1 + 2b)}{3(b + b_1)} \quad *c_1 = \frac{d(b + b_1)}{3(b + b_1)}$$

$$I = \frac{d^3(b^3 + 4bb_1 + b_1^3)}{36(b + b_1)}$$


$$\frac{I}{c} = \frac{d^3(b^3 + 4bb_1 + b_1^3)}{12(b_1 + 2b)}$$

$$r = \frac{d}{6(b + b_1)} \sqrt{2(b^3 + 4bb_1 + b_1^3)}$$

\* To find  $c$  and  $c_1$ , see Chapter VI, page 295.

**TRAPEZOID**

Axis of moments on base



$$A = \frac{d(b + b_1)}{2}$$

$$c = d$$


$$I = \frac{d^3(b + 3b_1)}{12}$$

$$\frac{I}{c} = \frac{d^3(b + 3b_1)}{12}$$

$$r = \frac{d}{\sqrt{6}} \sqrt{\frac{b + 3b_1}{b + b_1}}$$

**T SECTION AND CHANNEL**

Axis of moments through center of gravity



$$A = td + t_1(b - t)$$


$$c^* = \frac{td \times \frac{1}{2}d + t_1(b - t)(d - \frac{1}{2}t_1)}{A}$$

$$I = \frac{tc^3 + bt_1^3 - (b - t)(c_1 - t_1)^3}{3}$$

$$r = \sqrt{\frac{I}{A}}$$

**CIRCLE**

Axis of moments through center



$$A = \frac{\pi d^2}{4} = 0.785398 d^2$$

$$c = \frac{d}{2}$$


$$I = \frac{\pi d^4}{64} = 0.049087 d^4$$

$$\frac{I}{c} = \frac{\pi d^3}{32} = 0.098175 d^3$$

$$r = \frac{d}{4}$$

**HOLLOW CIRCLE**

Axis of moments through center



$$A = \frac{\pi(d^2 - d_1^2)}{4} = 0.785398(d^2 - d_1^2)$$

$$c = \frac{d}{2}$$

$$I = \frac{\pi(d^4 - d_1^4)}{64} = 0.049087(d^4 - d_1^4)$$


$$\frac{I}{c} = \frac{\pi(d^4 - d_1^4)}{32d} = 0.098175 \frac{(d^4 - d_1^4)}{d}$$

$$r = \frac{\sqrt{d^3 + d_1^3}}{4}$$

\* To find the values of  $c$  and  $c_1$ , see Chapter VI, page 295.

## CHANNEL

Axis of moments through  
center of gravity



$$A = t_1 b + 2 t (d - t_1)$$


$$c^* = \frac{2 d^3 + d_1 t_1^2}{2 A}$$

$$I = \frac{2 t d^3 + b_1 t_1^3}{3} - A c^2$$

$$r = \sqrt{\frac{I}{A}}$$

## CROSS-SECTION

Axis of moments through  
center of gravity



$$A = t d + t_1 (b - t)$$

$$c = \frac{d}{2}$$


$$I = \frac{t d^3 + t_1^3 (b - t)}{12}$$

$$\frac{I}{c} = \frac{t d^3 + t_1^3 (b - t)}{6 d}$$

$$r = \sqrt{\frac{t d^3 + t_1^3 (b - t)}{12 (t d + t_1 (b - t))}}$$

## IRREGULAR I SHAPE

Axis of moments through  
center of gravity



$$A = b t_1 + d t + b_1 t_1$$

$$c^* = \frac{t d^3 + t_1^3 (b_1 - t) + t_1 (b - t) (2 d - t_1)}{2 A}$$

$$c_1 = \frac{t d^3 + t_1^3 (b - t) + t_1 (b_1 - t) (2 d - t_1)}{2 A}$$

$$I = \frac{b_1 c^2 - (b_1 - t) \times (c - t_1)^2}{3} + \frac{b c_1^2 - (b - t) \times (c_1 - t_1)^2}{3}$$

$$r = \sqrt{\frac{I}{A}}$$

\* To find  $c$  and  $c_1$ , see Chapter VI, page 295.

### 3. Transferring Moments of Inertia to Other Parallel Axes

**Explanation of Formula.** It is often necessary to determine the moment of inertia with respect to some other axis than the one passing through the center of gravity of the section, such, for example, as one passing through the base and parallel to the other. Suppose it is desired to find the moment of inertia of a rectangle about an axis passing through the lower base, as the second figure on page 335. It may be demonstrated by the principles of mechanics that the moment of inertia of any section with respect to an axis is equal to the moment of inertia of the section with respect to a parallel axis through the center of gravity, plus the product of the area of the section multiplied by the square of the normal distance between the axes. This rule is expressed by the formula

$$I_1 = I + A h^2$$

which  $I_1$  is the required moment of inertia,  $I$  the moment of inertia of the figure with respect to the axis through its center of gravity and parallel to the  $XX$  axis,  $A$  the area of the section and  $h$  the normal distance between the axes. In this it is seen that the moment of inertia of any section-area is less for an axis through its center of gravity than for any other parallel axis.

For example, consider the rectangle shown on page 335, of breadth  $b$  and depth  $d$ , the  $I$  of which is known to be  $bd^3/12$  for an axis passing through the center of gravity and parallel to the base. Then, for a parallel axis through the base, the above formula

$$I_1 = \frac{bd^3}{12} + bd \times \left(\frac{d}{2}\right)^2 = \frac{bd^3}{12} + \frac{bd^3}{4} = \frac{bd^3}{3}$$

gives the moment of inertia of the cross-section of the steel angle shown in Fig. 1, about the axis  $XX$ , is equal to the moment of inertia about the  $XX$  plus the product of its area multiplied by the square of the distance  $h$ . The moments of inertia for the sections of standard rolled shapes of structural steel may be found from the tables given in this chapter. The distance  $c_1$ , also, may be found from the same tables; this distance subtracted from  $d$  will give the distance  $h$  of Formula (3).

Suppose, for example, that it is desired to find the moment of inertia of the cross-section of a 4 by 3  $\frac{1}{2}$ -in angle, placed, with the long leg horizontal, about an axis  $MN$ , 12 in from the back (Fig. 1). Turning to Table XI, the moment of inertia of the angle-section = 3.25 sq in.  $I$ , the moment of inertia of the angle-section about an axis  $2-2$ , or  $XX$  of Fig. 1, parallel to the long leg = 2.4,  $c_1$ , the distance of this axis from the back of the long leg = 0.83 in and  $h$ , the distance between the axes =  $(d - c_1) = 12 - 0.83$  in = 11.17 in. Substituting these values in Formula (3)

$$I_1 = 2.4 + 3.25 \times 11.17^2 = 2.4 + 405.50 = 407.9$$

#### 4. Moments of Inertia of Compound Sections

The Moment of Inertia of a Compound Section made up of a number of smaller sections may be found by the same formula,  $I_1 = I + Ah^2$ . Denote the sum of the moments of inertia of the separate sections making up the compound section, with respect to an axis through the center of gravity of that section, by  $\Sigma I_1$ . Formula (3) then becomes

$$\Sigma I_1 = \Sigma (I + Ah^2) \quad (4)$$

It is, to find the moment of inertia of any compound section made up of a number of smaller sections:

(1) Find the moment of inertia of each of the smaller sections about an axis passing through its own center of gravity and parallel to the neutral axis of the compound section;

(2) Multiply the area of each of the smaller sections by the square of the distance between its center of gravity and the center of gravity of the whole figure;

(3) Add the results found by (1) and (2) for the moment of inertia of the compound figure.

For example, consider the cast-iron beam or lintel shown in section in Fig. 2:




Fig. 1. Moment of Inertia of Cross-section of Steel Angle.

(1) $I$ of upper flange-section	$= 4 \times 1^3/12 = 4/12$
$I$ of web-section	$= 1 \times 18^3/12 = 5\,832/12$
$I$ of lower flange-section	$= 16 \times 1^3/12 = 16/12$
Total	$= 5\,852/12 = 487.6$
(2) $Ah^2$ for the upper flange	$= 4 \times (12.5)^2 = 625$
$Ah^2$ for the web	$= 18 \times 3^2 = 162$
$Ah^2$ for the lower flange	$= 16 \times (6.5)^2 = 676$
Total	$= 1\,463$

(3) Total of (1) and (2)  $= 487.6 + 1\,463 = I_1$  of compound section  $= 1\,950.6$

The moment of inertia of the cross-section of any compound beam, then, can generally be readily found by using the tables of properties of sections




Fig. 2. Moment of Inertia of Cross-section of Cast-iron Lintel

give the numerical values of  $I$  for the various rolled shapes of which the beam is composed, with respect to the axis through the center of gravity.

#### The Moment of Inertia of a Single-Web Girder-Section.

Consider, for example, the single-web girder shown in section in Fig. 3, and made up of one  $\frac{1}{2}$  by 24-in web and four 4 by 3 by  $\frac{1}{2}$ -in flange-angles with the long legs placed horizontally.

According to Table XI, the moment of inertia of the cross-section of one of these angles about an axis  $XX$  (2-2 in the table) parallel to the long leg  $= 2.4$ , and the distance of this axis from the back of the long leg (see table)  $= 0.83$  in; hence  $h$ , the distance between the axis of the angles and the axis of the girder-section  $= 12 - 0.83 = 11.17$  in.  $A$ , from the table  $= 3.25$  sq in. The moment of inertia of the cross-section of each angle about the axis of the girder, therefore, from Formula (3), is  $I_1 = 2.4 + 3.25 \times (11.17)^2 = 407.9$ , and for the four angles  $= 1631.6$ . Since the axis of the cross-section




Fig. 3. Moment of Inertia of Cross-section of Plate Girder. No Flange-plates

web-plate is coincident with the axis of the section of the girder, its moment of inertia  $= bd^3/12 = \frac{1}{2} \times (24)^3/12 = 576$ . This may be found directly from Table I, page 346, Moments of Inertia of Rectangles. The moment of inertia, therefore, of the section of the compound girder  $= 1631.6 + 576 = 2207.6$ .

**The Moment of Inertia of a Section of a Compound Girder with Flange-Plates** is found in the same way, except that the moments of inertia of the cross-sections of the flange-plates with respect to the axis of the girder-section must be added to the moments of inertia of the cross-sections of the other members. The girder in Fig. 4 is composed of one 30 by  $\frac{3}{8}$ -in web-plate, four 4 by  $\frac{7}{8}$ -in angles, with the longer leg horizontal, and two 12 by  $\frac{1}{2}$ -in flange-plates.

$I_1$  for cross-section of web (from Table I, page 346)  $= 843.75$   
 $I_2$  for each angle-section  $= I + Ah^2$   
 (Formula 3)

From Table XI, for each flange-angle,  $b = 4$ ,  $d = 4.75$  and the perpendicular distance from center of gravity to back leg  $= 1.10$  in. Hence  $h = 15 - 1.10 = 13.90$  in.  $I_1 = 6.6 + 4.75 \times (4.75)^2 = 924.35$ ; and for four angles  $3697.4$ .  $I$  for the cross-section of flange-plate  $= 12 \times (\frac{1}{2})^3/12 = 0.125$ ,  $A = \frac{1}{2} \times 12 = 6$  sq in and  $h = 15 + \frac{1}{4} = 15.25$  in. For each flange-plate, then,  $0.125 + 6 \times (15.25)^2 = 1395.125$ ; for the two plates, 2790.25. The moment of inertia for the cross-section of the whole girder, therefore, with respect to the horizontal axis passing through the center of gravity of the section  $= 843.75 + 3697.4 + 2790.25 = 7304.75$ .

It will be noticed that the moments of inertia of the cross-sections of the flange-plates and angles about their own axes is so small, compared with their moments of inertia about the axis of the girder-section, that they might be omitted without any appreciable error. Therefore, in calculating the moments of inertia for riveted girders, it is the custom of many engineers to let  $I_1 = Ah^2$  for flange-plate and angle sections. In that case, for the girder-section in Fig. 4,

$I$ for web	$= 843.75$
$I_1$ for angles $= Ah^2$	$= 3671.00$
$I_1$ for flange-plates $= Ah^2$	$= 2790.00$
Moment of inertia of entire girder-section	$= 7304.75$




Fig. 4. Moment of Inertia of Cross-section of Plate Girder with Flange-plates

**Moment of Inertia of a Section of a Box Girder.** Let the box shown in Fig. 5 be composed of two  $\frac{3}{4}$  by 30-in webs, two 16 by  $\frac{1}{2}$ -in flange plates and four 4 by 3 by  $\frac{1}{2}$ -in angles with the long legs horizontal.

$I$  for each flange-plate  $= bd^3/12 = 16 \times (1\frac{1}{2})^3/12 = 0.16$ ;  $A = 1\frac{1}{2} \times 16$  in  $= 8$  and  $h = 15 + \frac{1}{4} = 15.25$  in.  $I_1 = I + Ah^2 = 0.16 + 8 \times (15.25)^2 = 1860.64$ ; for the two flange-plates, 3721.28.  $I$  for angle  $= 2.4$ ,  $A = 3.25$  and the distance from back of the long leg to an axis through center of gravity of the angle, parallel to long leg  $= 0.83$  in; so that  $h = 15 - 0.83 = 14.17$  in.  $I_1$  for the four angles is  $(4 \times 2.4) + 3.25 \times (14.17)^2 = 2619$ .  $I$  for each web (I, page 346)  $= 843.75$  and for the two  $= 1687.5$ . The moment of inertia, therefore, for the entire girder-section  $= 3721.28 + 2619 + 1687.5 = 8027.78$ .




Fig. 5. Moment of Inertia of Cross-section of Plate-and-angle Box Girder

The Moment of Inertia of the Section of a Channel Box Column. Fig. 6 shows the cross-section of a column made up of two 10-in 15.3-lb channels, set 6.33 in apart, back




Fig. 6. Moment of Inertia of Cross-section of Channel Box Column

to back, and two  $\frac{1}{2}$  by 12-in side plates. Let it be required to find the moment of inertia of the section about the two axes  $AB$  and  $CD$ .

(1) Find the moment of inertia about the axis  $AB$ .  $I$ , for one of the plates with respect to an axis through its own center of gravity and parallel to  $AB = 12 \times (\frac{1}{2})^3/12 = 0.125$ ,  $A = \frac{1}{2} \times 12$  in  $= 6$  sq in and the distance of its center of gravity from  $AB$  is 5.25 in. Therefore, with respect to  $AB$ ,  $I_1 = 0.125 + 6 \times (5.25)^2 = 165.5$ . The moment of inertia of a 10-in 15.3-lb channel with respect to an axis through its center of gravity and perpendicular to the web (Table VIII, page 359)  $= 66.9$ . Hence the moment of inertia of the whole column-section with respect to the axis  $AB = (2 \times 165.5) + (2 \times 66.9) = 464.8$ .




Fig. 7. Moment of Inertia of Cross-section of Web Plate-and-angle Box Column

(2) Find the moment of inertia about the axis  $CD$ .  $I$ , for one of the side plates (Table I, page 346)  $= 72$ .  $I$ , for one of the channels with respect to an axis parallel to the web  $= 2.30$ ,  $A = 4.47$  and the distance of the center of gravity from the back of the web  $= 0.64$  in, approximately. Hence  $h = 3.165 + 0.64 = 3.805$  in.  $I_1 = 2.30 + 4.47 \times (3.805)^2 = 66.8$  and the moment of inertia of the whole section with respect to the axis  $CD = (2 \times 72) + (2 \times 66.8) = 277.6$ .



**The Moment of Inertia of the Section of a Heavy Plate-and-Angle Column.** Fig. 7 shows the cross-section of one of the basement-columns in Bankers' Trust Company Building, New York City. It is made up of six flange-plates, each 27 by  $\frac{3}{4}$  in section; two flange-plates, each 27 by  $1\frac{1}{4}$  in; four flange-angles, each 6 by 6 by  $1\frac{1}{4}$  in; eight outer web-plates, each 18 by 2.75 in; four web-angles, each 6 by  $3\frac{1}{4}$  by  $1\frac{1}{4}$  in; and two middle web-plates each 18 by  $\frac{9}{16}$  in. What is its moment of inertia of the entire column-section with respect to the axis  $AB$ ?

$I$ for each 27 by $\frac{3}{4}$ -in flange-plate (Table I) =	1 230.19
$I$ for six 27 by $\frac{3}{4}$ -in flange-plates =	1 230.19 $\times$ 6 =
	7 381.14
$I$ for each 27 by $1\frac{1}{4}$ -in flange-plate (Table I) =	1 127.67
$I$ for two 27 by $1\frac{1}{4}$ -in flange-plates =	1 127.67 $\times$ 2 =
	2 255.34
$I$ for both flanges	9 636.48

For the flange-angles (Table XII, page 366) the area of a 6 by  $1\frac{1}{4}$ -in angle = 10.37, its  $I$  with respect to an axis parallel to  $AB$  (Fig. 7) and passing through its center of gravity = 33.7 and the distance of this axis from the back of the leg = 1.84 in. Its  $I_1$  with respect to the axis  $AB$  is found by Formula (3), page 338,  $I_1 = I + Ak^2$ .  $k = 13.5 - (0.12 + 4.16) =$  the distance from the axis  $AB$  to the parallel axis through the center of gravity of the angle = 9.22 in. Hence, substituting in Formula (3),

$$I_1 = 33.7 + 10.37 \times (9.22)^2 = 915.15$$

$$I_1 \text{ for the four flange-angles} = 915.15 \times 4 = 3 660.60$$

Each outer web is  $4 \times 1\frac{1}{4}$  in =  $2\frac{3}{4}$  in thick. Hence the  $I$  for each outer web about the horizontal axis through its center of gravity =  $18 \times (2.75)^3 / 12 = 31.2$ .  $A = 18 \times 2.75$  in = 49.5 sq in. The distance from its center of gravity to the axis  $AB$  is  $13.5 - (1.38 + 1.84 + 4.16 + 0.12) = 6.01$  or, say 6 in.

Hence, from Formula (3), therefore,  $I_1 = 31.2 + 49.5 \times 6^2 = 1 813.2$  and for both outer webs  $I_1 = 1 813.2 \times 2 =$

$$3 626.4$$

For the four web-angles, from Table XI, page 363, the area of a  $3\frac{1}{4}$  by  $1\frac{1}{4}$ -in angle = 8.03, its  $I$  with respect to an axis through its center of gravity and parallel to the long leg = 6.9 and the distance of this axis from the back of the long leg = 0.99 in.  $h$ , the total distance between the two axes =  $\frac{9}{16}$  in, or 0.5625 in (thickness of one of the middle web-plates) + 0.99 = 1.55 in, approximately. Therefore, for one web-angle, from Formula (3),

$$I_1 = 6.9 + 8.03 \times (1.55)^2 = 26.17$$

$$\text{for the four angles, } I_1 = 26.17 \times 4 =$$

$$104.68$$

The middle web-plates are together  $\frac{9}{16}$  in  $\times$  2 =  $1\frac{1}{8}$  in = 1.125 in thick. The  $I$  ( $= I_1$ ) for the two plates is  $18 \times (1.125)^3 / 12 =$

$$2.14$$

Hence the moment of inertia of the entire column-section for the axis  $AB$  is, therefore, the sum of these moments of inertia for the different parts:

$I$ for the eight flange-plates	9 636.48
$I$ for the four flange-angles	3 660.60
$I$ for the eight outer web-plates	3 626.40
$I$ for the four web-plates	104.68
$I$ for the middle web-plates	2.14
The moment of inertia for the entire section	17 030.30

### 5. Radii of Gyration of Compound Sections

The Radius of Gyration of any Compound Section may be found by Formula (2), page 333, by dividing the moment of inertia of the section by the total area of the section and taking the square root of the quotient. The radii of gyration of the channel-column section shown in Fig. 6, about axes  $AB$  and  $CD$ , are found as follows:  $A$  = (the sum of the areas of two 12-in plates, or 12 sq in) + (the sum of the areas of the two channels, or 8.94 sq in) = 20.94 sq in.  $I$  about  $AB$  = 464.8 and about  $CD$  = 277.6.

Therefore,  $r$ , with respect to the axis  $AB$  =  $\sqrt{\frac{464.8}{20.94}} = 4.71$

and  $r_1$ , with respect to the axis  $CD$  =  $\sqrt{\frac{277.6}{20.94}} = 3.64$

Since  $r_1$  is the smaller, it is the value to be used in the column-formula. It is to be noted that this value of  $r$  agrees with the  $r$  of the 10-in channel-column in Table XXV, on page 533. The value of  $r_1$  does not, however, agree exactly with the  $r_1$  in the same table, the variation being caused by a difference in the spacing of the channels, back to back.

**The Least Radius of Gyration of a Section of a Plate-and-Angle Column.** As another example, let it be required to find the least radius of gyration of the cross-section of the plate-and-angle column shown in Fig. 8, made up of




Fig. 8. Least Radius of Gyration of Cross-section of Plate-and-angle Column

angle column shown in Fig. 8, made up of 3/16 by 12-in web-plate, two 3/16 by 12-in side plates, and four 4 by 4 by 1/2-in angles.

(1) Find the moment of inertia about the axis  $AB$ . For the axis  $AB$ ,  $I$  for each one of the plates with respect to an axis through its center of gravity and parallel to the axis  $AB$  is  $I_1 = 12 \times (3/16)^3 / 12 = 0.05$ .  $A = 3/16 \times 12 = 4.5$  sq in.  $h = 6 3/16$  in.  $I_1 = 0.05 + 4.5 \times (6 3/16)^2 = 172.33$ .  $I$  for each one of the angles with respect to an axis through its center of gravity and parallel to the axis  $AB$  is 5.6,  $A = 3.75$  and the distance of the center of gravity from the back of the flange of the angle = 1.18. Hence,  $h = 1.18$  in = 4.82 in and  $I_1$  for each angle =  $5.6 + 3.75 \times (4.82)^2 = 92.71$ .  $I$  for the web-plate = 0.05.

54. The moment of inertia of the whole column-section, therefore, about axis  $AB$  =  $(2 \times 172.33) + (4 \times 92.71) + 54 = 769.50$ .

(2) Find the moment of inertia about the axis  $CD$ .  $I$  for each side plate = 54.  $I$  for each angle = 5.6 and  $A$  for each angle = 3.75. The distance of the center of gravity of each angle from the back of the flange of the angle = 1.18 in and hence,  $h = 1.18$  in +  $3/16$  in = 1.36 in, approximately.  $I_1$  for each angle =  $5.6 + 3.75 \times (1.36)^2 = 12.54$ .  $I$  for each web-plate = 0.05. The moment of inertia of the whole column-section, therefore, about the axis  $CD$  =  $(2 \times 54) + (4 \times 12.54) + 0.05 = 158.21$ .

Since this is the least moment of inertia the least radius of gyration will be about the axis  $CD$ . The area of the cross-section of the column =  $3.75$ , the area of the angles +  $(3 \times 4.5)$ , the area of each plate = 28.5.  $158.21 / 28.5 = 5.55$  and  $r$ , the least radius of gyration = 2.35.

**The Radius of Gyration of the Cross-Section of a Hollow Rectangular Column.** As another example, let it be required to find the radius of gyration of a hollow rectangular cast-iron column with outside dimensions 6 by 6 in and with a shell  $\frac{1}{4}$  in thick. (See figures and formulas for hollow squares and rectangles, page 335.)  $A = 6^2 - (5.5)^2 = 36 - 30.25 = 5.75$  sq in.  $\frac{6^4 - 5.5^4}{12} = \frac{[6^4 - (5.5)^4]}{12} = \frac{(1296 - 910)}{12} = 386/12 = 32.2$ .  $r^2 = 32.2/5.75 = 5.6$  and  $r = 2.37$  in.

The radii of gyration of round-section columns and square-section columns, ranging from 2 to 20 in in diameter and of metal varying from  $\frac{1}{4}$  to 2 in thick, are given in Tables II and III, see pages 348 to 351. For example: the radius of gyration of a 6 by 6-in square-section cast-iron column with a shell  $\frac{1}{4}$  in thick, from Table III, 2.35 in.

### Graphical Method of Determining the Moment of Inertia of Plane Figures \*

**The Moment of Inertia may be Determined Graphically as follows:** Divide the shape in question, Fig. 9,† into strips parallel to  $BC$ . Through the

centers of gravity of the strips draw indef-

inite lines  $f_1, f_2$ , etc.

Along a line  $ab$  lay off

distances  $f_1, f_2$ , etc., pro-

portional respectively

to the areas  $f_1, f_2$ , etc.

Since the strips are

of equal width and of equal

length, each strip may

be assumed propor-

tional to the length of

the strip measured

along its center of

gravity. Through a

point  $b$  draw lines at

distances  $ab$  to deter-

mine the pole  $O$ , from

which the rays  $Od, Oe$ ,

etc. are drawn. Con-




Fig. 9. Graphical Determination of Moments of Inertia†

Construct the EQUILIBRIUM-POLYGON  $gsf$ . (See page 296.) A line  $sS$  parallel to  $gsf$  will be a GRAVITY-AXIS. The MOMENT OF INERTIA about this axis is equal to the area of the given figure  $ABC$  multiplied by the area of the polygon  $gsf$ . The square root of this area  $gsf$  is the RADIUS OF GYRATION of the figure  $ABC$  with regard to the axis  $sS$ . A graphic method especially adapted to irregular figures is given in detail in Goodman's *Mechanics Applied to Engineering*. See, also, Merriman's *American Civil Engineers' Handbook*.

See notes by Robins Fleming.

Figure from Ott's *Graphic Statics* (Clark's Translation, London, 1876). See, also, Ott's *Notes and Examples in Mechanics*.

Table I.\* Moments of Inertia of Rectangles


 Neutral axis through center and normal to depth

Depth in inches	Widths of rectangles in inches						
	$\frac{1}{4}$	$\frac{3}{16}$	$\frac{1}{2}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{1}{2}$
2	0.17	0.21	0.25	0.29	0.33	0.38	0.42
3	0.56	0.70	0.84	0.98	1.13	1.27	1.41
4	1.33	1.67	2.00	2.33	2.67	3.00	3.33
5	2.60	3.26	3.91	4.56	5.21	5.86	6.51
6	4.50	5.63	6.75	7.88	9.00	10.13	11.25
7	7.15	8.93	10.72	12.51	14.29	16.08	17.86
8	10.67	13.33	16.00	18.67	21.33	24.00	26.67
9	15.19	18.98	22.78	26.58	30.38	34.17	37.96
10	20.83	26.04	31.25	36.46	41.67	46.87	52.08
11	27.73	34.66	41.59	48.53	55.46	62.39	69.31
12	36.00	45.00	54.00	63.00	72.00	81.00	90.00
13	45.77	57.21	68.66	80.10	91.54	102.98	114.42
14	57.17	71.46	85.75	100.04	114.33	128.63	142.92
15	70.31	87.89	105.47	123.05	140.63	158.20	175.78
16	85.33	106.67	128.00	149.33	170.67	192.00	213.33
17	102.35	127.94	153.53	179.12	204.71	230.30	255.89
18	121.50	151.88	182.25	212.63	243.00	273.38	303.75
19	142.90	178.62	214.34	250.07	285.79	321.52	359.25
20	166.67	208.33	250.00	291.67	333.33	375.00	416.67
21	192.94	241.17	289.41	337.64	385.88	434.11	485.83
22	221.83	277.29	332.75	388.21	443.67	499.13	555.83
23	253.48	316.85	380.22	443.59	506.96	570.33	633.75
24	288.00	360.00	432.00	504.00	576.00	648.00	720.00
25	325.52	406.90	488.28	569.66	651.04	732.42	819.17
26	366.17	457.71	549.25	640.79	732.33	823.88	919.17
27	410.06	512.58	615.09	717.61	820.13	922.64	1022.50
28	457.33	571.67	686.00	800.33	914.67	1029.00	1144.17
29	508.10	635.13	762.16	889.18	1016.21	1143.23	1275.00
30	562.50	703.13	843.75	984.38	1125.00	1265.63	1416.67
32	682.67	853.33	1024.00	1194.67	1365.33	1536.00	1716.67
34	818.83	1023.54	1228.25	1432.96	1637.67	1842.38	2054.17
36	972.00	1215.00	1458.00	1701.00	1944.00	2187.00	2430.00
38	1143.17	1428.96	1714.75	2000.54	2286.33	2572.13	2895.83
40	1333.33	1666.67	2000.00	2333.33	2666.67	3000.00	3333.33
42	1543.50	1929.38	2315.25	2701.13	3087.00	3472.88	3895.83
44	1774.67	2218.33	2662.00	3105.67	3549.33	3993.00	4441.67
46	2027.83	2534.79	3041.75	3548.71	4055.67	4562.63	5083.33
48	2304.00	2880.00	3456.00	4032.00	4608.00	5184.00	5760.00
50	2604.17	3255.21	3906.25	4557.29	5208.33	5859.38	6554.17
52	2929.33	3661.67	4394.00	5126.33	5858.67	6591.00	7333.33
54	3280.50	4100.63	4920.75	5740.88	6561.00	7381.13	8222.50
56	3658.67	4573.33	5488.00	6402.67	7317.33	8232.00	9141.67
58	4064.83	5081.04	6097.25	7113.46	8129.67	9145.87	10100.00
60	4500.00	5625.00	6750.00	7875.00	9000.00	10125.00	11250.00

\* This table may be used in computing the moments of inertia of plate columns and other compound sections in which plates are used. See pages 342.

Table I\* (Continued). Moments of Inertia of Rectangles.


Neutral axis through center and normal to depth

## Widths of rectangles in inches

$\frac{1}{16}$	$\frac{3}{16}$	$\frac{1}{2}$	$\frac{3}{4}$	$1\frac{1}{2}$	I
0.46	0.50	0.54	0.58	0.63	0.67
1.55	1.69	1.83	1.97	2.11	2.25
3.67	4.00	4.33	4.67	5.00	5.33
7.16	7.81	8.46	9.11	9.77	10.42
12.38	13.50	14.63	15.75	16.88	18.00
19.65	21.44	23.22	25.01	26.80	28.58
29.33	32.00	34.67	37.33	40.00	42.67
41.77	45.56	49.36	53.16	56.95	60.75
57.29	62.50	67.71	72.92	78.13	83.33
76.26	83.19	90.12	97.05	103.98	110.92
99.00	108.00	117.00	126.00	135.00	144.00
125.87	137.31	148.75	160.20	171.64	183.08
157.21	171.50	185.79	200.08	214.38	228.67
193.36	210.94	228.52	246.09	263.67	281.25
234.67	256.00	277.33	298.67	320.00	341.33
281.47	307.06	332.65	358.24	383.83	409.42
334.13	364.50	394.88	425.25	455.63	486.00
392.96	428.69	464.41	500.14	535.86	571.58
458.33	500.00	541.67	583.33	625.00	666.67
530.58	578.81	627.05	675.28	723.52	771.75
610.04	665.50	720.96	776.42	831.87	887.33
697.07	760.44	823.81	887.18	950.55	1013.92
792.00	864.00	936.00	1008.00	1080.00	1152.00
895.18	976.56	1057.94	1139.32	1220.70	1302.08
1006.96	1098.50	1190.04	1281.58	1373.13	1464.67
1127.67	1230.19	1332.70	1435.22	1537.73	1640.25
1257.67	1372.00	1486.33	1600.67	1715.00	1829.33
1397.29	1524.31	1651.34	1778.36	1905.39	2032.42
1546.88	1687.50	1828.13	1968.75	2109.38	2250.00
1717.33	2048.00	2218.67	2389.33	2560.00	2730.67
2251.79	2456.50	2661.21	2865.92	3070.63	3275.33
2673.00	2916.00	3159.00	3402.00	3645.00	3888.00
3143.71	3429.50	3715.29	4001.08	4286.88	4572.67
3666.67	4000.00	4333.33	4666.67	5000.00	5333.33
4244.63	4630.50	5016.38	5402.25	5788.13	6174.00
4880.33	5324.00	5767.67	6211.33	6655.00	7098.67
5576.54	6083.50	6590.46	7097.42	7604.38	8111.33
6336.00	6912.00	7488.00	8064.00	8640.00	9216.00
7161.46	7812.50	8463.54	9114.58	9765.63	10416.67
8055.67	8788.00	9520.33	10252.67	10985.00	11717.33
9021.38	9841.50	10661.63	11481.75	12301.88	13122.00
10061.33	10976.00	11890.67	12805.33	13720.00	14634.67
11178.29	12194.50	13210.71	14226.92	15243.12	16250.33
12375.00	13500.00	14625.00	15750.00	16875.00	18000.00

This table may be used in computing the moments of inertia of plate girders, and other compound sections in which plates are used. See pages 341 and

Table II.\* Areas and Radii of Gyration of Hollow-Round Sections



$$\text{Area} = \frac{\pi (D^2 - d^2)}{4} = 0.7854 (D^2 - d^2) \text{ sq in}$$

$$\text{Radius of gyration} = \frac{\sqrt{D^2 + d^2}}{4} \text{ in}$$

Diam. D, inches	A and r	Thickness t in inches							
		1/16	1/8	3/16	1/2	5/8	3/4	7/8	1
2	A	1.37	1.66	.....	.....	.....	.....	.....	.....
	r	0.63	0.61	.....	.....	.....	.....	.....	.....
3	A	2.16	2.64	.....	.....	.....	.....	.....	.....
	r	0.98	0.96	.....	.....	.....	.....	.....	.....
4	A	2.95	3.62	4.27	5.50	.....	.....	.....	.....
	r	1.33	1.31	1.29	1.25	.....	.....	.....	.....
5	A	3.73	4.60	5.45	7.07	8.59	10.01	.....	.....
	r	1.68	1.66	1.64	1.60	1.56	1.53	.....	.....
6	A	4.52	5.58	6.63	8.64	10.55	12.37	14.09	.....
	r	2.03	2.01	1.99	1.95	1.91	1.88	1.84	.....
7	A	5.30	6.57	7.80	10.21	12.52	14.73	16.84	.....
	r	2.39	2.37	2.35	2.30	2.27	2.23	2.19	.....
8	A	6.09	7.55	8.98	11.78	14.48	17.08	19.59	.....
	r	2.74	2.72	2.70	2.66	2.62	2.58	2.54	.....
9	A	6.87	8.53	10.16	13.35	16.44	19.44	22.33	.....
	r	3.09	3.07	3.05	3.01	2.97	2.93	2.89	.....
10	A	7.66	9.51	11.34	14.92	18.41	21.79	25.08	.....
	r	3.45	3.43	3.41	3.36	3.32	3.28	3.24	.....
11	A	8.44	10.49	12.52	16.49	20.37	24.15	27.83	.....
	r	3.80	3.78	3.76	3.72	3.67	3.63	3.59	.....
12	A	9.23	11.47	13.70	18.06	22.33	26.51	30.58	.....
	r	4.16	4.13	4.11	4.07	4.03	3.99	3.95	.....
13	A	10.01	12.46	14.87	19.63	24.30	28.86	33.33	.....
	r	4.51	4.49	4.47	4.42	4.38	4.34	4.30	.....
14	A	10.80	13.44	16.05	21.21	26.26	31.22	36.08	.....
	r	4.86	4.84	4.82	4.78	4.73	4.69	4.65	.....
15	A	11.58	14.42	17.23	22.78	28.23	33.58	38.83	.....
	r	5.22	5.19	5.17	5.13	5.09	5.05	5.00	.....
16	A	12.37	15.40	18.41	24.35	30.19	35.93	41.58	.....
	r	5.57	5.55	5.53	5.48	5.44	5.40	5.36	.....
17	A	13.16	16.38	19.59	25.92	32.15	38.29	44.33	.....
	r	5.92	5.90	5.88	5.84	5.79	5.75	5.71	.....
18	A	13.94	17.36	20.76	27.49	34.12	40.64	47.07	.....
	r	6.28	6.25	6.23	6.19	6.15	6.10	6.06	.....
19	A	14.73	18.35	21.94	29.06	36.08	43.00	49.82	.....
	r	6.63	6.61	6.59	6.54	6.50	6.46	6.42	.....
20	A	15.51	19.33	23.12	30.63	38.04	45.36	52.57	.....
	r	6.98	6.96	6.94	6.90	6.85	6.81	6.77	.....

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

# Properties of Structural Shapes, etc.

hF (Continued). Areas and Radii of Gyration of Hollow-Round



$$\text{Area} = \frac{\pi (D^2 - d^2)}{4} = 0.7854 (D^2 - d^2) \text{ sq in}$$

$$\text{Radius of gyration} = \frac{\sqrt{D^2 + d^2}}{4} \text{ in}$$

In. D. thick	A and r	Thickness t in inches						
		1/8	1/4	3/8	1/2	5/8	3/4	7/8
2	A	.....	.....	.....	.....	.....	.....	.....
	r	.....	.....	.....	.....	.....	.....	.....
1	A	.....	.....	.....	.....	.....	.....	.....
	r	.....	.....	.....	.....	.....	.....	.....
1/2	A	.....	.....	.....	.....	.....	.....	.....
	r	.....	.....	.....	.....	.....	.....	.....
3/8	A	.....	.....	.....	.....	.....	.....	.....
	r	.....	.....	.....	.....	.....	.....	.....
1/4	A	.....	.....	.....	.....	.....	.....	.....
	r	.....	.....	.....	.....	.....	.....	.....
3/16	A	20.76	22.58	.....	.....	.....	.....	.....
	r	2.12	2.08	.....	.....	.....	.....	.....
1/8	A	24.30	26.51	28.62	30.63	.....	.....	.....
	r	2.46	2.43	2.39	2.36	.....	.....	.....
1/16	A	27.83	30.43	32.94	35.34	37.65	39.86	.....
	r	2.81	2.78	2.74	2.70	2.67	2.64	.....
1/32	A	31.37	34.36	37.26	40.06	42.76	45.36	47.86
	r	3.16	3.13	3.09	3.05	3.02	2.98	2.95
1/64	A	34.90	38.29	41.58	44.77	47.86	50.85	53.75
	r	3.51	3.48	3.44	3.40	3.36	3.33	3.29
1/128	A	38.44	41.22	45.90	49.48	52.97	56.35	59.64
	r	3.87	3.83	3.79	3.75	3.71	3.68	3.64
1/256	A	41.97	46.14	50.22	54.19	58.07	61.85	65.53
	r	4.22	4.18	4.14	4.10	4.06	4.03	3.99
1/512	A	45.50	50.07	54.54	58.91	63.18	67.35	71.42
	r	4.57	4.53	4.49	4.45	4.41	4.38	4.34
1/1024	A	49.04	54.00	58.86	63.62	68.28	72.85	77.31
	r	4.92	4.88	4.84	4.80	4.76	4.73	4.69
1/2048	A	52.57	57.92	63.18	68.33	73.39	78.34	83.20
	r	5.27	5.23	5.19	5.15	5.11	5.08	5.04
1/4096	A	56.11	61.85	67.50	73.04	78.49	83.84	89.09
	r	5.63	5.59	5.55	5.51	5.47	5.43	5.39
1/8192	A	59.64	65.78	71.82	77.75	83.60	89.34	94.98
	r	5.98	5.94	5.90	5.86	5.82	5.78	5.74
1/16384	A	63.18	69.70	76.13	82.47	88.70	94.84	100.87
	r	6.33	6.29	6.25	6.21	6.17	6.13	6.09
1/32768	A	66.71	73.63	80.45	87.18	93.81	100.33	106.77
	r	6.69	6.64	6.60	6.56	6.52	6.48	6.44

Table III. Areas and Radii of Gyration of Hollow-Square Sections



Area =  $(D^2 - d^2)$  sq in

Radius of gyration =  $\sqrt{\frac{D^2 + d^2}{12}}$  in

Side <i>D</i> , inches	<i>A</i> and <i>r</i>	Thickness <i>t</i> in inches							
		$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	
2	<i>A</i>	1.75	2.11	.....	.....	.....	.....	.....	
	<i>r</i>	0.72	0.70	.....	.....	.....	.....	.....	
3	<i>A</i>	2.75	3.36	.....	.....	.....	.....	.....	
	<i>r</i>	1.13	1.10	.....	.....	.....	.....	.....	
4	<i>A</i>	3.75	4.61	5.44	7.00	.....	.....	.....	
	<i>r</i>	1.53	1.51	1.49	1.44	.....	.....	.....	
5	<i>A</i>	4.75	5.86	6.94	9.00	10.94	12.75	.....	
	<i>r</i>	1.94	1.92	1.89	1.85	1.80	1.76	.....	
6	<i>A</i>	5.75	7.11	8.44	11.00	13.44	15.75	17.94	
	<i>r</i>	2.35	2.33	2.30	2.25	2.21	2.17	2.12	
7	<i>A</i>	6.75	8.36	9.94	13.00	15.94	18.75	21.44	
	<i>r</i>	2.76	2.73	2.71	2.66	2.62	2.57	2.53	
8	<i>A</i>	7.75	9.61	11.44	15.00	18.44	21.75	24.94	
	<i>r</i>	3.17	3.14	3.12	3.07	3.02	2.98	2.93	
9	<i>A</i>	8.75	10.86	12.94	17.00	20.94	24.75	28.44	
	<i>r</i>	3.57	3.55	3.53	3.48	3.43	3.38	3.34	
10	<i>A</i>	9.75	12.11	14.44	19.00	23.44	27.75	31.94	
	<i>r</i>	3.98	3.96	3.93	3.88	3.84	3.79	3.74	
11	<i>A</i>	10.75	13.36	15.94	21.00	25.94	30.75	35.44	
	<i>r</i>	4.39	4.37	4.34	4.29	4.24	4.20	4.15	
12	<i>A</i>	11.75	14.61	17.44	23.00	28.44	33.75	38.94	
	<i>r</i>	4.80	4.77	4.75	4.70	4.65	4.60	4.56	
13	<i>A</i>	12.75	15.86	18.94	25.00	30.94	36.75	42.44	
	<i>r</i>	5.21	5.18	5.16	5.11	5.06	5.01	4.96	
14	<i>A</i>	13.75	17.11	20.44	27.00	33.44	39.75	45.94	
	<i>r</i>	5.61	5.59	5.56	5.51	5.47	5.42	5.37	
15	<i>A</i>	14.75	18.36	21.94	29.00	35.94	42.75	49.44	
	<i>r</i>	6.02	6.00	5.97	5.92	5.87	5.83	5.78	
16	<i>A</i>	15.75	19.61	23.44	31.00	38.44	45.75	52.94	
	<i>r</i>	6.43	6.41	6.38	6.33	6.28	6.23	6.19	
17	<i>A</i>	16.75	20.86	24.94	33.00	40.94	48.75	56.44	
	<i>r</i>	6.84	6.81	6.79	6.74	6.69	6.64	6.59	
18	<i>A</i>	17.75	22.11	26.44	35.00	43.44	51.75	59.94	
	<i>r</i>	7.25	7.22	7.20	7.15	7.10	7.05	7.00	
19	<i>A</i>	18.75	23.36	27.94	37.00	45.94	54.75	63.44	
	<i>r</i>	7.66	7.63	7.61	7.56	7.51	7.46	7.41	
20	<i>A</i>	19.75	24.61	29.44	39.00	48.44	57.75	66.94	
	<i>r</i>	8.06	8.04	8.01	7.96	7.91	7.87	7.82	

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa



# Properties of Structural Shapes, etc.

Table II\* (Continued). Areas and Radii of Gyration of Hollow-Square



$$\text{Area} = (D^2 - d^2) \text{ sq in}$$

$$\text{Radius of gyration} = \sqrt{\frac{D^2 + d^2}{12}} \text{ in}$$

Side D, inches	A and r	Thickness t in inches						
		1/8	1/4	3/8	1/2	5/8	3/4	7/8
1	A r	.....	.....	.....	.....	.....	.....	.....
2	A r	.....	.....	.....	.....	.....	.....	.....
3	A r	.....	.....	.....	.....	.....	.....	.....
4	A r	.....	.....	.....	.....	.....	.....	.....
5	A r	.....	.....	.....	.....	.....	.....	.....
6	A r	.....	.....	.....	.....	.....	.....	.....
7	A r	26.44 2.44	28.75 2.40	.....	.....	.....	.....	.....
8	A r	30.94 2.84	33.75 2.80	36.44 2.76	39.00 2.72	.....	.....	.....
9	A r	35.44 3.25	38.75 3.20	41.94 3.16	45.00 3.12	47.94 3.08	50.75 3.05	.....
10	A r	39.94 3.65	43.75 3.61	47.44 3.57	51.00 3.52	54.44 3.48	57.75 3.44	60.94 3.40
11	A r	44.44 4.06	48.75 4.01	52.94 3.97	57.00 3.93	60.94 3.88	64.75 3.84	68.44 3.80
12	A r	48.94 4.46	53.75 4.42	58.44 4.37	63.00 4.33	67.44 4.29	71.75 4.25	75.94 4.20
13	A r	53.44 4.87	58.75 4.82	63.94 4.78	69.00 4.74	73.94 4.69	78.75 4.65	83.44 4.61
14	A r	57.94 5.28	63.75 5.23	69.44 5.18	75.00 5.14	80.44 5.10	85.75 5.05	90.94 5.01
15	A r	62.44 5.68	68.75 5.64	74.94 5.59	81.00 5.55	86.94 5.50	92.75 5.46	98.44 5.41
16	A r	66.94 6.09	73.75 6.04	80.44 6.00	87.00 5.95	93.44 5.91	99.75 5.86	105.94 5.82
17	A r	71.44 6.50	78.75 6.45	85.94 6.40	93.00 6.36	99.94 6.31	106.75 6.27	113.44 6.23
18	A r	75.94 6.90	83.75 6.86	91.44 6.82	99.00 6.78	106.44 6.72	113.75 6.67	120.94 6.63
19	A r	80.44 7.31	88.75 7.26	96.94 7.22	105.00 7.17	112.94 7.12	120.75 7.08	128.44 7.03
20	A r	84.94 7.72	93.75 7.67	102.44 7.62	111.00 7.58	119.44 7.53	127.75 7.49	135.94 7.44

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, P.


## 7. Dimensions, Moments of Inertia, Radii of Gyration and Section Moduli of Standard Structural Shapes

**Explanation of Tables.** As in using structural-steel shapes the choice is practically confined to such shapes as are rolled by the mills, it is essential to have at hand the dimensions and properties of those shapes in order to calculate the necessary sizes to meet special requirements for strength and proper conditions of economy and framing. Since 1890 great changes have been made both in the materials and in the shapes of the standard sections. The mills which manufacture the most complete assortment of structural shapes are those of the Carnegie Steel Company, the Cambria Steel Company, the Jones & Laughlin Steel Company and the Bethlehem Steel Company. In general the products of these mills, especially beams and channels, are respectively standard in shape. This is particularly true of the shapes rolled by the first three companies named.

The standard steel beams and channels considered in the following pages are rolled by all of these mills, with the exception of those of the Bethlehem Steel Company. With a few exceptions the following tables of properties of standard structural shapes have been adopted by permission from the Pocket Companion of the Carnegie Steel Company. It may be well to state that the tables of properties for the various structural shapes, published by the companies named above, do not agree exactly, even for the same weight, but the differences are not of practical importance. The tables of the Cambria Steel Company and of the Carnegie Steel Company for beams and channels agree more closely. As angles are very extensively used for a great many purposes, the properties are given for all sizes rolled and a table showing from which mills the different sizes may be obtained. Usually it will generally be advantageous to use a size that is rolled by the same mills.

Tables XV, XVI and XVII will be found very convenient when computing the strength of struts formed of pairs of angles, and Table XVIII when computing the same for pairs of channels.

### Standard Steel Beams and Channels.\* Common Dimensions



$$n = \text{minimum web} = t$$


$$R = \text{minimum web} + 0.10''$$

$$t = \frac{1}{10} \text{ minimum web}$$

$$h = \text{distance between flange-fillets}$$

$$\text{Slope of flange, } 1 : 6 = 16\frac{2}{3}\% = 9^\circ 27' 44''$$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



$r$  = minimum web =  $t$


$R$  = minimum web + 0.10"

$r$  =  $\frac{9}{10}$  minimum web

Slope of flange, 1 : 6 = 16 $\frac{2}{3}$ % = 9° 27' 44"

Dimensions for Structural Beams are those adopted by the Association of American Steel Manufacturers and apply to all Structural Beams, except American Standard Sections B 1, B 2 and B 3, also Sections B 24 and B 81. The dimensions of the Supplementary Beams, B 61 to B 68, inclusive, cannot be readily reduced to formulas. Slope of flange is 1 : 11 = 5° 11' 40". Dimensions for Structural Channels are those adopted by the Association of American Steel Manufacturers and apply to all Structural Channels, except the C 10, the 13-in sizes, which are Car Building Channels.

Table IV.\* Properties of I-Beam Sections




Section-index	Depth of beam	Weight per foot	Area of section	Width of flange	Thickness of web	Axis 1-1			Axis 2-2	
						<i>I</i>	<i>r</i>	<i>I/c</i>	<i>I</i>	<i>r</i>
	in	lb	sq in	in	in	in <sup>4</sup>	in	in <sup>3</sup>	in <sup>4</sup>	in
B 61	27	90.0	26.34	9.000	0.524	2958.3	10.60	219.1	75.3	1.69
B 18	24	115.0	33.67	7.987	0.737	2940.5	9.35	245.0	82.8	1.57
		110.0	32.18	7.925	0.675	2869.1	9.44	239.1	80.6	1.58
		105.9	30.98	7.875	0.625	2811.5	9.53	234.3	78.9	1.60
		100.0	29.25	7.247	0.747	2571.8	9.05	197.6	48.4	1.29
B 1	24	95.0	27.79	7.186	0.686	2301.5	9.08	191.8	47.0	1.30
		90.0	26.30	7.124	0.624	2230.1	9.21	185.8	45.5	1.32
		85.0	24.84	7.063	0.563	2159.8	9.33	180.0	44.2	1.33
		79.9	23.33	7.000	0.500	2087.2	9.46	173.9	42.9	1.36
B 62	24	74.2	21.70	9.000	0.476	1950.1	9.48	162.5	61.2	1.68
B 63	21	60.4	17.68	8.250	0.428	1235.5	8.36	117.7	43.5	1.57
		100.0	29.20	7.273	0.873	1648.3	7.51	164.8	52.4	1.34
		95.0	27.74	7.200	0.800	1599.7	7.59	160.0	50.5	1.35
B 2	20	90.0	26.26	7.126	0.726	1550.3	7.68	155.0	48.7	1.36
		85.0	24.80	7.053	0.653	1501.7	7.78	150.2	47.0	1.37
		81.4	23.74	7.000	0.600	1466.3	7.86	146.6	45.8	1.38
		75.0	21.90	6.391	0.641	1263.5	7.60	126.3	30.1	1.11
B 3	20	70.0	20.42	6.317	0.567	1214.2	7.71	121.4	28.9	1.12
		65.4	19.08	6.250	0.500	1169.5	7.83	116.9	27.9	1.13
		90.0	26.29	7.236	0.796	1256.5	6.91	139.6	51.9	1.41
B 19	18	85.0	24.81	7.154	0.714	1216.6	7.00	135.2	49.8	1.42
		80.0	23.34	7.072	0.632	1176.8	7.10	130.8	47.9	1.43
		75.6	22.04	7.000	0.560	1141.8	7.20	126.9	46.3	1.44
		70.0	20.46	6.251	0.711	917.5	6.70	101.9	24.5	1.01
B 4	18	65.0	18.98	6.169	0.629	877.7	6.80	97.5	23.4	1.02
		60.0	17.50	6.087	0.547	837.8	6.92	93.1	22.3	1.03
		54.7	15.94	6.000	0.460	795.5	7.07	88.4	21.2	1.04
		48.2	14.09	7.500	0.380	737.1	7.23	81.9	30.0	1.05
B 64	18	75.0	21.85	6.278	0.868	687.2	5.61	91.6	30.6	1.06
		70.0	20.38	6.180	0.770	659.6	5.69	87.9	28.8	1.07
		65.0	18.91	6.082	0.672	632.1	5.78	84.3	27.2	1.08
		60.8	17.68	6.000	0.590	609.0	5.87	81.2	26.0	1.09
B 6	15	55.0	16.06	5.738	0.648	508.7	5.63	67.8	17.0	0.91
		50.0	14.59	5.640	0.550	481.1	5.74	64.2	16.0	0.92
		45.0	13.12	5.542	0.452	453.6	5.88	60.5	15.0	0.93
		42.9	12.49	5.500	0.410	441.8	5.95	58.9	14.6	0.94
B 65	15	37.3	10.91	6.750	0.332	405.5	6.10	54.1	19.9	0.95

NOTE. The exponential figures used with *I* and *I/c* denote the mathematical "dimensions" of these quantities, that is, the number of times the linear unit is a factor in the quantities.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table IV\* (Continued). Properties of I-Beam Section




Depth of beam	Weight per foot	Area of section	Width of flange	Thick-ness of web	Axis 1-1			Axis 2-2		
					<i>I</i>	<i>r</i>	<i>I/c</i>	<i>I</i>	<i>r</i>	<i>I/c</i>
					in <sup>4</sup>	in	in <sup>3</sup>	in <sup>4</sup>	in	in <sup>3</sup>
in	lb	sq in	in	in						
12	55.0	16.04	5.600	0.810	319.3	4.46	53.2	17.3	1.04	6.2
	50.0	14.57	5.477	0.687	301.6	4.55	50.3	16.0	1.05	5.8
	45.0	13.10	5.355	0.565	284.1	4.66	47.3	14.8	1.06	5.5
	40.8	11.84	5.250	0.460	268.9	4.77	44.8	13.8	1.08	5.3
12	35.0	10.20	5.078	0.428	227.0	4.72	37.8	10.0	0.99	3.9
	31.8	9.26	5.000	0.350	215.8	4.83	36.0	9.5	1.01	3.8
12	27.9	8.15	6.000	0.284	199.4	4.95	33.2	12.6	1.24	4.2
	40.0	11.69	5.091	0.741	158.0	3.68	31.6	9.4	0.90	3.7
10	35.0	10.22	4.944	0.594	145.8	3.78	29.2	8.5	0.91	3.4
	30.0	8.75	4.797	0.447	133.5	3.91	26.7	7.6	0.93	3.2
	25.4	7.38	4.660	0.310	122.1	4.07	24.4	6.9	0.97	3.0
	22.4	6.54	5.500	0.252	113.6	4.17	22.7	9.0	1.17	3.3
10	35.0	10.22	4.764	0.724	111.3	3.30	24.7	7.3	0.84	3.0
	30.0	8.76	4.601	0.561	101.4	3.40	22.5	6.4	0.85	2.8
	25.0	7.28	4.437	0.397	91.4	3.54	20.3	5.6	0.88	2.5
	21.8	6.32	4.330	0.290	84.9	3.67	18.9	5.2	0.90	2.4
8	25.5	7.43	4.262	0.532	68.1	3.03	17.0	4.7	0.80	2.2
	23.0	6.71	4.171	0.441	64.2	3.09	16.0	4.4	0.81	2.1
	20.5	5.97	4.079	0.349	60.2	3.18	15.1	4.0	0.82	2.0
	18.4	5.34	4.000	0.270	56.9	3.26	14.2	3.8	0.84	1.9
8	17.5	5.13	5.000	0.220	58.4	3.38	14.6	6.2	1.10	2.5
	20.0	5.83	3.860	0.450	41.9	2.68	12.0	3.1	0.74	1.6
7	17.5	5.09	3.755	0.345	38.9	2.77	11.1	2.9	0.76	1.6
	15.3	4.43	3.660	0.250	36.2	2.86	10.4	2.7	0.78	1.5
	17.25	5.02	3.565	0.465	26.0	2.28	8.7	2.3	0.68	1.3
6	14.75	4.29	3.443	0.343	23.8	2.36	7.9	2.1	0.69	1.2
	12.5	3.61	3.330	0.230	21.8	2.46	7.3	1.8	0.72	1.1
	14.75	4.29	3.284	0.494	15.0	1.87	6.0	1.7	0.63	1.0
5	12.25	3.56	3.137	0.347	13.5	1.95	5.4	1.4	0.63	0.91
	10.0	2.87	3.000	0.210	12.1	2.05	4.8	1.2	0.65	0.82
	10.5	3.05	2.870	0.400	7.1	1.52	3.5	1.0	0.57	0.70
4	9.5	2.76	2.796	0.326	6.7	1.56	3.3	0.91	0.58	0.65
	8.5	2.46	2.723	0.253	6.3	1.60	3.2	0.83	0.58	0.61
	7.7	2.21	2.660	0.190	6.0	1.64	3.0	0.77	0.59	0.58
	7.5	2.17	2.509	0.349	2.9	1.15	1.9	0.59	0.52	0.47
3	6.5	1.88	2.411	0.251	2.7	1.19	1.8	0.51	0.52	0.43
	5.7	1.64	2.330	0.170	2.5	1.23	1.7	0.46	0.53	0.40

\*Note with table on preceding page.

\*From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table V.\* Properties of H-Beam Sections



These may be employed as columns, using the axis 2-2

Sec- tion- index	Depth of beam	Weight per foot	Area of section	Width of flange	Thick- ness of web	Axis 1-1			Axis 2-2	
						<i>I</i>	<i>r</i>	<i>I/c</i>	<i>I</i>	<i>r</i>
						in <sup>4</sup>	in	in <sup>3</sup>	in <sup>4</sup>	in
H 4	8	34.3	10.01	8.0	0.375	115.4	3.40	28.9	35.1	1.87
H 3	6	24.1	7.01	6.0	0.313	45.1	2.54	15.0	14.7	1.45
H 2	5	18.9	5.47	5.0	0.313	23.8	2.08	9.5	7.9	1.20
H 1	4	13.8	4.00	4.0	0.313	10.7	1.63	5.3	3.6	0.95

See " Note " with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table VI.\* Properties of Bethlehem I-Beam Sections

Depth of beam	Weight per foot	Area of section	Thick- ness of web	Width of flange	Increase of web and flange for each lb increase of weight	Neutral axis perpendicular to web at center			Neutral axis coin- cident with center line of web	
						<i>I</i>	<i>r</i>	<i>I/c</i>	<i>I</i>	<i>r</i>
in	lb	sq in	in	in	in	in <sup>4</sup>	in	in <sup>3</sup>	in <sup>4</sup>	in
30	120.0	35.30	0.540	10.500	0.010	5239.6	12.18	349.3	165.0	2.16
28	105.0	30.88	0.500	10.000	0.011	4014.1	11.40	286.7	131.5	2.06
26	90.0	26.49	0.460	9.500	0.011	2977.2	10.60	229.0	101.2	1.95
24	84.0	24.80	0.460	9.250	0.012	2331.9	9.80	198.5	91.1	1.92
24	83.0	24.59	0.520	9.130	0.012	2240.9	9.55	186.7	78.0	1.78
24	73.0	21.47	0.390	9.000	0.012	2091.0	9.87	174.3	74.4	1.86
22	82.0	24.17	0.570	8.890	0.015	1559.8	8.03	156.0	79.9	1.82
22	72.0	21.37	0.430	8.750	0.015	1466.5	8.28	146.7	75.9	1.88
20	69.0	20.26	0.520	8.145	0.015	1268.9	7.91	126.9	51.2	1.59
20	64.0	18.86	0.450	8.075	0.015	1222.1	8.05	122.2	49.8	1.62
20	59.0	17.36	0.375	8.000	0.015	1172.2	8.22	117.2	48.3	1.66
18	59.0	17.40	0.495	7.675	0.016	883.3	7.12	98.1	39.1	1.50
18	54.0	15.87	0.410	7.590	0.016	842.0	7.28	93.6	37.7	1.54
18	52.0	15.24	0.375	7.555	0.016	825.0	7.36	91.7	37.1	1.56
18	48.5	14.25	0.320	7.500	0.016	798.3	7.48	88.7	36.2	1.59
15	71.0	20.95	0.520	7.500	0.020	796.2	6.16	106.2	61.3	1.71
15	64.0	18.81	0.605	7.195	0.020	664.9	5.95	88.6	41.9	1.49
15	54.0	15.88	0.410	7.000	0.020	610.0	6.20	81.3	38.3	1.55
15	46.0	13.52	0.440	6.810	0.020	484.8	5.99	64.6	25.2	1.36
15	41.0	12.02	0.340	6.710	0.020	456.7	6.16	60.9	24.0	1.41
15	38.0	11.27	0.290	6.660	0.020	442.6	6.27	59.0	23.4	1.44
12	36.0	10.61	0.310	6.300	0.025	269.2	5.04	44.9	21.3	1.42
12	32.0	9.44	0.335	6.205	0.025	228.5	4.92	38.1	16.0	1.30
12	28.5	8.42	0.290	6.120	0.025	216.2	5.07	36.0	15.3	1.35
10	28.5	8.34	0.390	5.990	0.029	134.6	4.02	26.9	12.1	1.21
10	23.5	6.94	0.250	5.850	0.029	122.9	4.21	24.6	11.2	1.27
9	24.0	7.04	0.365	5.555	0.033	92.1	3.62	20.5	8.8	1.12
9	20.0	6.01	0.250	5.440	0.033	85.1	3.76	18.9	8.2	1.17
8	19.5	5.78	0.325	5.325	0.037	60.6	3.24	15.1	6.7	1.08
8	17.5	5.18	0.250	5.250	0.037	57.4	3.33	14.3	6.4	1.11

See "Note" with Table IV, page 354.

\*Adapted from Catalogue of Structural Shapes, 1911 Edition, Bethlehem Steel Company, Bethlehem, Pa. See nine Additional Sections, for 24-in, 22-in, and 18-in beam shapes S-10, published March, 1, 1921, by this Company.

Table VII.\* Properties of Bethlehem Girder-Beam Sections


Depth of beam	Weight per foot	Area of section	Thick- ness of web	Width of flange	Increase of web and flange for each pound increase of weight	Neutral axis perpendicular to web at center			Neutral axis coin- cident wit center lin of web	
						<i>I</i>	<i>r</i>	<i>I/c</i>	<i>I</i>	<i>r</i>
in	lb	sq in	in	in	in	in <sup>4</sup>	in	in <sup>3</sup>	in <sup>4</sup>	in
30	200.0	58.71	0.750	15.00	0.010	9150.6	12.48	610.0	630.2	3.0
30	180.0	53.00	0.690	13.00	0.010	8194.5	12.43	546.3	433.3	2.8
28	180.0	52.86	0.690	14.35	0.011	7264.7	11.72	518.9	533.3	3.1
28	165.0	48.47	0.660	12.50	0.011	6562.7	11.64	468.8	371.9	2.7
26	160.0	46.91	0.630	13.60	0.011	5620.8	10.95	432.4	435.7	3.0
26	150.0	43.94	0.630	12.00	0.011	5153.9	10.83	396.5	314.6	2.8
24	140.0	41.16	0.600	13.00	0.012	4201.4	10.10	350.1	346.9	2.9
24	120.0	35.38	0.530	12.00	0.012	3607.3	10.10	300.6	249.4	2.7
20	140.0	41.19	0.640	12.50	0.015	2934.7	8.44	293.5	348.9	2.9
20	112.0	32.81	0.550	12.00	0.015	2342.1	8.45	234.2	239.3	2.7
18	98.0	27.12	0.480	11.50	0.016	1591.4	7.66	176.8	182.6	2.7
15	140.0	41.27	0.800	11.75	0.020	1592.7	6.21	212.4	331.0	2.9
15	104.0	30.50	0.600	11.25	0.020	1220.1	6.32	162.7	213.0	2.7
15	73.0	21.49	0.430	10.50	0.020	883.4	6.41	117.8	123.2	2.7
12	70.0	20.58	0.460	10.00	0.025	538.8	5.12	89.8	114.7	2.7
12	55.0	16.18	0.370	9.75	0.025	432.0	5.17	72.0	81.1	2.7
10	44.0	12.95	0.310	9.00	0.030	244.2	4.34	48.8	57.3	2.7
9	38.0	11.22	0.300	8.50	0.033	170.9	3.90	38.0	44.1	2.7
8	32.5	9.54	0.290	8.00	0.037	114.4	3.46	28.6	32.9	2.7

See " Note " with Table IV, page 354.

\* Adapted from Catalogue of Structural Shapes, 1911 Edition, Bethlehem Company, Bethlehem, Pa.




Table VIII.\* Properties of Channel Sections



Depth of channel in	Weight per foot lb	Area of section sq in	Width of flange in	T web in	Axis 1-1			r in	d <sub>f</sub> in	J
					I	r	I/c			
					in <sup>4</sup>	in	in <sup>3</sup>			
15	55.0	16.11	3.814	0	12.1	0.87	4.1	0.82	8.53	11
	50.0	14.64	3.716	0	11.2	0.87	3.8	0.80	8.71	12
	45.0	13.17	3.618	0	10.3	0.88	3.6	0.79	8.92	12
	40.0	11.70	3.520	0	9.3	0.89	3.4	0.78	9.15	12
	35.0	10.23	3.422	0	8.4	0.91	3.2	0.79	9.43	12
	33.9	9.90	3.400	0	8.1	0.91	3.2	0.78	9.90	12
13	40.0	11.73	3.413	0	6.6	0.75	2.5	0.72	6.60	9
	35.0	10.26	3.292	0	5.9	0.76	2.3	0.69	6.81	9
	30.0	8.79	3.170	0	5.2	0.77	2.1	0.68	7.07	9
	25.0	7.32	3.047	0	4.5	0.79	1.9	0.68	7.36	10
	20.7	6.03	2.940	0	3.9	0.81	1.7	0.70	7.67	10
	35.0	10.27	3.180	0	4.6	0.67	1.9	0.69	5.17	8
20	30.0	8.80	3.033	0	4.0	0.67	1.7	0.65	5.40	8
	25.0	7.33	2.885	0	3.4	0.68	1.5	0.62	5.67	8
	20.0	5.86	2.739	0	2.8	0.70	1.3	0.61	5.97	8
	15.3	4.47	2.600	0	2.3	0.72	1.2	0.64	6.33	8
	35.0	7.33	2.812	0	3.0	0.64	1.4	0.61	4.84	7
	20.0	5.86	2.648	0	2.4	0.65	1.2	0.59	5.12	7
9	15.0	4.39	2.485	0	1.9	0.67	1.0	0.59	5.49	7
	13.4	3.89	2.430	0	1.8	0.67	0.97	0.61	5.63	8
	21.25	6.23	2.619	0	2.2	0.60	1.1	0.59	4.23	6
	18.75	5.49	2.527	0	2.0	0.60	1.0	0.57	4.38	6
	16.25	4.76	2.435	0	1.8	0.61	0.94	0.56	4.54	6
	13.75	4.02	2.343	0	1.5	0.62	0.86	0.56	4.72	7
8	11.5	3.36	2.260	0	1.3	0.63	0.79	0.58	4.94	7
	19.75	5.79	2.509	0	1.8	0.56	0.96	0.58	3.48	5
	17.25	5.05	2.404	0	1.6	0.56	0.86	0.55	3.64	5
	14.75	4.32	2.299	0	1.4	0.57	0.79	0.53	3.80	6
	12.25	3.58	2.194	0	1.2	0.58	0.71	0.53	3.99	6
	9.8	2.85	2.090	0	0.98	0.59	0.63	0.55	4.22	6
7	15.5	4.54	2.279	0	1.3	0.53	0.73	0.55	2.91	5
	13.0	3.81	2.157	0	1.1	0.53	0.65	0.52	3.09	5
	10.5	3.07	2.034	0	0.87	0.53	0.57	0.50	3.28	5
	8.2	2.39	1.920	0	0.70	0.54	0.50	0.52	3.52	5
	17.5	5.36	2.032	0	0.82	0.49	0.54	0.51	2.34	4
	9.0	2.63	1.883	0	0.64	0.49	0.45	0.48	2.56	4
6	8.7	1.95	1.750	0	0.48	0.50	0.38	0.49	2.79	4
	7.25	2.12	1.730	0	0.44	0.46	0.35	0.46	1.85	3
	6.25	1.82	1.647	0	0.38	0.45	0.32	0.46	1.96	3
	5.4	1.56	1.580	0	0.32	0.45	0.29	0.46	2.06	4
	6.0	1.75	1.596	0	0.31	0.42	0.27	0.46	1.07	3
	5.0	1.46	1.498	0	0.25	0.41	0.24	0.44	1.19	3
5	4.7	1.19	1.470	0	0.20	0.41	0.27	0.44	1.11	3

\* Arranged from Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.  
 † These values make r the same for both axes.

**Table IX.\* Dimensions of Sections and Weights of Small Grooved Steel Channels**



Section-index	Size of section, in	Width of flange, in	Thickness of web, in	Weight, foot, lb
C-164	2 $\frac{1}{8}$	1 $\frac{3}{16}$	$\frac{1}{8}$	2.55
C-165	2 $\frac{1}{8}$	$\frac{3}{4}$	$\frac{3}{16}$	2.09
C-166	2 $\frac{1}{8}$	1 $\frac{1}{16}$	$\frac{1}{8}$	1.63
C-183	2	$\frac{5}{8}$	$\frac{1}{4}$	2.11
C-184	2	$\frac{9}{16}$	$\frac{3}{16}$	1.68
C-185	2	$\frac{1}{2}$	$\frac{1}{8}$	1.26
C-190	1 $\frac{3}{4}$	1 $\frac{1}{16}$	$\frac{3}{16}$	1.71
C-191	1 $\frac{3}{4}$	$\frac{5}{8}$	$\frac{1}{8}$	1.33
C-193	1 $\frac{3}{4}$	1 $\frac{7}{32}$	$\frac{5}{32}$	1.33
C-195	1 $\frac{3}{4}$	$\frac{3}{8}$	$\frac{1}{8}$	0.96
C-197	1 $\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{16}$	1.47
C-199	1 $\frac{1}{4}$	$\frac{1}{2}$	$\frac{1}{8}$	0.93
C-200	1 $\frac{1}{8}$	$\frac{9}{16}$	$\frac{3}{16}$	1.12
C-203	1	$\frac{1}{2}$	$\frac{1}{8}$	0.83
C-207	1	2 $\frac{5}{64}$	$\frac{1}{8}$	0.71
C-213	$\frac{7}{8}$	$\frac{7}{16}$	$\frac{1}{8}$	0.66
C-217	$\frac{7}{8}$	$\frac{3}{8}$	$\frac{1}{8}$	0.58
C-219	$\frac{3}{4}$	$\frac{3}{8}$	$\frac{1}{8}$	0.54
C-221	$\frac{3}{4}$	1 $\frac{1}{32}$	$\frac{3}{32}$	0.40
C-223	$\frac{5}{8}$	$\frac{5}{16}$	$\frac{1}{8}$	0.43

\* Rolled by the Jones & Laughlin Steel Company, Pittsburgh, Pa.

Table X. Sizes and Makes of Rolled Steel Angles

The following table has been compiled to show angles of various sizes rolled by steel companies. The word "all" indicates that angles of the sizes mentioned are rolled by all the companies included in the list. The abbreviations refer to the following companies: Cam., Cambria Steel Company; Car., Carnegie Steel Company; J. & L., Jones & Laughlin Steel Company.

Angles with unequal legs		Angles with equal legs	
Sizes in inches	Companies	Sizes in inches	Companies
8 X6	Cam. and Car.	8 X8	All
8 X3½	Car.	6 X6	All
7 X3½	All	5 X5	All
6 X4	All	4½ X4½	Cam.
6 X3½	All	4 X4	All
5 X4	All	3½ X3½	All
5 X3½	All	3¼ X3¼	J. & L.
5 X3	All	3 X3	All
4½ X3	Car. and J. & L.	2¾ X2¾	Cam. and J. & L.
4 X3½	All	2½ X2½	All
4 X3	All	2¼ X2¼	Cam. and J. & L.
3½ X3	All	2 X2	All
3¼ X2½	All	1¾ X1¾	All
3¼ X2	J. & L.	1½ X1½	All
3¼ X1½	J. & L.	1¾ X1¾	J. & L.
3 X2½	All	1¼ X1¼	All
3 X2	All	1¾ X1¾	J. & L.
2½ X2	All	1 X1	All
2¼ X1¾	J. & L.	¾ X¾	J. & L.
2¼ X1½	Car. and J. & L.		
2¼ X1¼	Cam.		
2¼ X1¾	J. & L.		
2¼ X1½	Car. and J. & L.		
2 X1½	Car. and J. & L.		
1 X1¾	J. & L.		
1 X1¼	Car.		
1 X1	J. & L.		
¾ X1½	J. & L.		
¾ X1¼	Car.		
¾ X1¾	J. & L.		
¾ X1¼	Car.		
¾ X1	J. & L.		
¾ X¾	J. & L.		
½ X1½	J. & L.		
½ X¾	J. & L.		

Table XI.\* Properties of Angle-Sections. Unequal Legs.



			Axis 1-1				Axis 2-2				A
			<i>I</i>	<i>r</i>	<i>I/c</i>	<i>z</i>	<i>I</i>	<i>r</i>	<i>I/c</i>	<i>z</i>	
			in <sup>4</sup>	in	in <sup>3</sup>	in	in <sup>4</sup>	in	in <sup>3</sup>	in	
8X6	X1	44.2	13.00	80.8	2.49	15.1	2.65	38.8	1.73	8.9	1.65
8X6	X1 1/16	41.7	12.25	76.6	2.50	14.3	2.63	35.8	1.73	8.4	1.63
8X6	X1/8	39.1	11.48	72.3	2.51	13.4	2.61	34.9	1.74	7.9	1.61
8X6	X3/16	36.5	10.72	67.9	2.52	12.5	2.59	32.8	1.75	7.4	1.59
8X6	X1/4	33.8	9.94	63.4	2.53	11.7	2.56	30.7	1.76	6.9	1.56
8X6	X5/16	31.2	9.15	58.8	2.54	10.8	2.54	28.6	1.77	6.4	1.54
8X6	X3/8	28.5	8.36	54.1	2.54	9.9	2.52	26.3	1.77	5.9	1.52
8X6	X7/16	25.7	7.56	49.3	2.55	8.9	2.50	24.0	1.78	5.3	1.50
8X6	X1/2	23.0	6.75	44.3	2.56	8.0	2.47	21.7	1.79	4.8	1.47
8X6	X3/4	20.2	5.93	39.2	2.57	7.1	2.45	19.3	1.80	4.2	1.45
8X3 1/2	X1	35.7	10.50	66.2	2.51	13.7	3.17	7.8	0.86	3.0	0.92
8X3 1/2	X1 1/16	33.7	9.90	62.9	2.52	12.9	3.14	7.4	0.87	2.9	0.89
8X3 1/2	X1/8	31.7	9.30	59.4	2.53	12.2	3.12	7.1	0.87	2.7	0.87
8X3 1/2	X3/16	29.6	8.68	55.9	2.54	11.4	3.10	6.7	0.88	2.5	0.85
8X3 1/2	X1/4	27.5	8.06	52.3	2.55	10.6	3.07	6.3	0.88	2.3	0.82
8X3 1/2	X5/16	25.3	7.43	48.5	2.56	9.8	3.05	5.9	0.89	2.2	0.80
8X3 1/2	X3/8	23.2	6.80	44.7	2.57	9.0	3.03	5.4	0.90	2.0	0.78
8X3 1/2	X7/16	21.0	6.15	40.8	2.57	8.2	3.00	5.0	0.90	1.8	0.75
8X3 1/2	X1/2	18.7	5.50	36.7	2.58	7.3	2.98	4.5	0.91	1.6	0.73
8X3 1/2	X3/4	16.5	4.84	32.5	2.59	6.4	2.95	4.1	0.92	1.5	0.70
7X3 1/2	X1	32.3	9.50	45.4	2.19	10.6	2.71	7.5	0.89	3.0	0.96
7X3 1/2	X1 1/16	30.5	8.97	43.1	2.19	10.0	2.69	7.2	0.89	2.8	0.94
7X3 1/2	X1/8	28.7	8.42	40.8	2.20	9.4	2.66	6.8	0.90	2.6	0.91
7X3 1/2	X3/16	26.8	7.87	38.4	2.21	8.8	2.64	6.5	0.91	2.5	0.89
7X3 1/2	X1/4	24.9	7.31	36.0	2.22	8.2	2.62	6.1	0.91	2.3	0.87
7X3 1/2	X5/16	23.0	6.75	33.5	2.23	7.6	2.60	5.7	0.92	2.1	0.85
7X3 1/2	X3/8	21.0	6.17	30.9	2.24	7.0	2.57	5.3	0.93	2.0	0.82
7X3 1/2	X7/16	19.1	5.59	28.2	2.25	6.3	2.55	4.9	0.93	1.8	0.80
7X3 1/2	X1/2	17.0	5.00	25.4	2.25	5.7	2.53	4.4	0.94	1.6	0.78
7X3 1/2	X3/4	15.0	4.40	22.6	2.26	5.0	2.50	4.0	0.95	1.4	0.75
7X3 1/2	X1	13.0	3.80	19.6	2.27	4.3	2.48	3.5	0.96	1.3	0.73
6X4	X1	30.6	9.00	30.8	1.85	8.0	2.17	10.8	1.09	3.8	1.17
6X4	X1 1/16	28.9	8.40	29.2	1.86	7.6	2.14	10.3	1.10	3.6	1.14
6X4	X1/8	27.2	7.98	27.7	1.86	7.2	2.12	9.8	1.11	3.4	1.12
6X4	X3/16	25.4	7.47	26.1	1.87	6.7	2.10	9.2	1.11	3.2	1.10
6X4	X1/4	23.6	6.94	24.5	1.88	6.2	2.08	8.7	1.12	3.0	1.08
6X4	X5/16	21.8	6.40	22.8	1.89	5.8	2.06	8.1	1.13	2.8	1.06
6X4	X3/8	20.0	5.86	21.1	1.90	5.3	2.03	7.5	1.13	2.5	1.03
6X4	X7/16	18.1	5.31	19.3	1.90	4.8	2.01	6.9	1.14	2.3	1.01
6X4	X1/2	16.2	4.75	17.4	1.91	4.3	1.99	6.3	1.15	2.1	0.99
6X4	X3/4	14.3	4.18	15.5	1.92	3.8	1.96	5.6	1.16	1.8	0.96
6X4	X1	12.3	3.61	13.5	1.93	3.3	1.94	4.9	1.17	1.6	0.94

See "Note" with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XI\* (Continued). Properties of Angle-Sections. Unequal Legs



Size	Weight per foot	Area of section	AXIS 1-1				AXIS 2-2				3-3	
			<i>I</i>	<i>r</i>	<i>I/c</i>	<i>x</i>	<i>I</i>	<i>r</i>	<i>I/c</i>	<i>y</i>	<i>r<sub>min</sub></i>	
in	lb	sq in	in <sup>4</sup>	in	in <sup>3</sup>	in	in <sup>4</sup>	in	in <sup>3</sup>	in	in	in
3½ X 1	28.9	8.50	29.2	1.85	7.8	3.26	7.2	0.92	2.9	1.01	0.74	
3½ X 1½	27.3	8.03	27.8	1.86	7.4	2.24	6.9	0.93	2.7	0.99	0.74	
3½ X 1¾	25.7	7.55	26.4	1.87	7.0	2.22	6.6	0.93	2.6	0.97	0.76	
3½ X 1½	24.0	7.06	24.9	1.88	6.6	2.20	6.2	0.94	2.4	0.95	0.75	
3½ X 1¾	22.4	6.56	23.3	1.89	6.1	2.18	5.8	0.94	2.3	0.93	0.76	
3½ X 1½	20.6	6.06	21.7	1.89	5.6	2.15	5.5	0.95	2.1	0.90	0.75	
3½ X 1¾	18.9	5.55	20.1	1.90	5.2	2.13	5.1	0.96	1.9	0.88	0.75	
3½ X 1½	17.1	5.03	18.4	1.91	4.7	2.11	4.7	0.96	1.8	0.86	0.75	
3½ X 1¾	15.3	4.50	16.6	1.92	4.2	2.08	4.3	0.97	1.6	0.83	0.76	
3½ X 1½	13.5	3.97	14.8	1.93	3.7	2.06	3.8	0.98	1.4	0.81	0.76	
3½ X 1¾	11.7	3.42	12.9	1.94	3.3	2.04	3.3	0.99	1.2	0.79	0.77	
3½ X 1½	9.8	2.87	10.9	1.95	2.7	2.01	2.9	1.00	1.0	0.76	0.77	
4 X 1½	24.2	7.11	16.4	1.52	5.0	1.71	9.2	1.14	3.3	1.21	0.84	
4 X 1¾	22.7	6.65	15.5	1.53	4.7	1.69	8.7	1.15	3.1	1.18	0.84	
4 X 1¾	21.1	6.19	14.6	1.54	4.4	1.66	8.2	1.15	2.9	1.16	0.84	
4 X 1½	19.5	5.72	13.6	1.54	4.1	1.64	7.7	1.16	2.7	1.14	0.84	
4 X 1¾	17.8	5.23	12.6	1.55	3.7	1.62	7.1	1.17	2.5	1.12	0.84	
4 X 1½	16.2	4.75	11.6	1.56	3.4	1.60	6.6	1.18	2.3	1.10	0.85	
4 X 1¾	14.5	4.25	10.5	1.57	3.1	1.57	6.0	1.18	2.0	1.07	0.85	
4 X 1½	12.8	3.75	9.3	1.58	2.7	1.55	5.3	1.19	1.8	1.05	0.85	
4 X 1¾	11.0	3.23	8.1	1.59	2.3	1.53	4.7	1.20	1.6	1.03	0.86	
3½ X 3½	22.7	6.67	15.7	1.53	4.9	1.79	6.2	0.95	2.5	1.04	0.75	
3½ X 3½	21.3	6.25	14.8	1.54	4.6	1.77	5.9	0.97	2.4	1.02	0.75	
3½ X 3½	19.8	5.81	13.9	1.55	4.3	1.75	5.6	0.98	2.2	1.00	0.75	
3½ X 3½	18.3	5.37	13.0	1.56	4.0	1.72	5.2	0.98	2.1	0.97	0.75	
3½ X 3½	16.8	4.92	12.0	1.56	3.7	1.70	4.8	0.99	1.9	0.95	0.75	
3½ X 3½	15.2	4.47	11.0	1.57	3.3	1.68	4.4	1.00	1.7	0.93	0.75	
3½ X 3½	13.6	4.00	10.0	1.58	3.0	1.66	4.0	1.01	1.6	0.91	0.75	
3½ X 3½	12.0	3.53	8.9	1.59	2.6	1.63	3.6	1.01	1.4	0.88	0.76	
3½ X 3½	10.4	3.05	7.8	1.60	2.3	1.61	3.2	1.02	1.2	0.86	0.76	
3½ X 3½	8.7	2.56	6.6	1.61	1.9	1.59	2.7	1.03	1.0	0.84	0.76	
3 X 3½	20.9	5.84	14.6	1.55	4.5	1.86	3.7	0.80	1.7	0.86	0.64	
3 X 3½	18.8	5.44	13.2	1.55	4.2	1.84	3.5	0.80	1.6	0.84	0.64	
3 X 3½	17.1	5.03	12.3	1.56	3.9	1.82	3.3	0.81	1.5	0.82	0.64	
3 X 3½	15.7	4.61	11.4	1.57	3.5	1.80	3.1	0.81	1.4	0.80	0.64	
3 X 3½	14.3	4.18	10.4	1.58	3.2	1.77	2.8	0.82	1.3	0.77	0.65	
3 X 3½	12.8	3.75	9.5	1.59	2.9	1.75	2.6	0.83	1.1	0.75	0.65	
3 X 3½	11.3	3.31	8.4	1.60	2.6	1.73	2.3	0.84	1.0	0.73	0.65	
3 X 3½	9.8	2.86	7.4	1.61	2.2	1.70	2.0	0.84	0.89	0.70	0.65	
3 X 3½	8.2	2.40	6.3	1.61	1.9	1.68	1.8	0.85	0.75	0.68	0.66	

\* Note " with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XI\* (Continued). Properties of Angle-Sections. Unequal Legs




4 1/4	18.5	5.43	10.3	1.38	3.6	1.65	3.6	0.81	1.7	0.90	0
4 1/2	17.3	5.06	9.7	1.39	3.4	1.63	3.4	0.82	1.6	0.88	0
4 3/4	16.0	4.68	9.1	1.39	3.1	1.60	3.2	0.83	1.5	0.85	0
4 1/2	14.7	4.30	8.4	1.40	2.9	1.58	3.0	0.83	1.4	0.83	0
4 1/2	13.3	3.90	7.8	1.41	2.6	1.56	2.8	0.85	1.3	0.81	0
4 1/2	11.9	3.50	7.0	1.42	2.4	1.54	2.5	0.85	1.1	0.79	0
4 1/2	10.6	3.09	6.3	1.43	2.1	1.51	2.3	0.85	1.0	0.76	0
4 1/2	9.1	2.67	5.5	1.44	1.8	1.49	2.0	0.86	0.88	0.74	0
4 1/2	7.7	2.25	4.7	1.44	1.5	1.47	1.7	0.87	0.75	0.72	0
4	18.5	5.43	7.8	1.19	2.9	1.36	5.5	1.01	2.3	1.11	0
4	17.3	5.06	7.3	1.20	2.8	1.34	5.2	1.01	2.1	1.09	0
4	16.0	4.68	6.9	1.21	2.6	1.32	4.9	1.02	2.0	1.07	0
4	14.7	4.30	6.4	1.22	2.4	1.29	4.5	1.03	1.8	1.04	0
4	13.3	3.90	5.9	1.23	2.1	1.27	4.2	1.03	1.7	1.02	0
4	11.9	3.50	5.3	1.23	1.9	1.25	3.8	1.04	1.5	1.00	0
4	10.6	3.09	4.8	1.24	1.7	1.23	3.4	1.05	1.3	0.98	0
4	9.1	2.67	4.2	1.25	1.5	1.21	3.0	1.06	1.2	0.96	0
4	7.7	2.25	3.6	1.26	1.3	1.18	2.6	1.07	1.0	0.93	0
4 X 3 X 1 1/4	17.1	5.03	7.3	1.21	2.9	1.44	3.5	0.83	1.7	0.94	0
4 X 3 X 3/4	16.0	4.69	6.9	1.22	2.7	1.42	3.3	0.84	1.6	0.92	0
4 X 3 X 1 1/8	14.8	4.34	6.5	1.23	2.5	1.39	3.1	0.84	1.5	0.89	0
4 X 3 X 3/8	13.6	3.98	6.0	1.23	2.3	1.37	2.9	0.85	1.4	0.87	0
4 X 3 X 1/2	12.4	3.62	5.6	1.24	2.1	1.35	2.7	0.86	1.2	0.85	0
4 X 3 X 1/4	11.1	3.25	5.0	1.25	1.9	1.33	2.4	0.86	1.1	0.83	0
4 X 3 X 1/8	9.8	2.87	4.5	1.25	1.7	1.30	2.2	0.87	1.0	0.80	0
4 X 3 X 1/16	8.5	2.48	4.0	1.26	1.5	1.28	1.9	0.88	0.87	0.78	0
4 X 3 X 1/32	7.2	2.09	3.4	1.27	1.3	1.26	1.7	0.89	0.74	0.76	0
4 X 3 X 1/64	5.8	1.69	2.8	1.28	1.0	1.24	1.4	0.89	0.60	0.71	0
3 1/2 X 3 X 1 1/8	15.8	4.62	5.0	1.04	2.2	1.23	3.3	0.85	1.7	0.98	0
3 1/2 X 3 X 3/4	14.7	4.31	4.7	1.04	2.1	1.21	3.1	0.85	1.5	0.96	0
3 1/2 X 3 X 1 1/4	13.6	4.00	4.4	1.05	1.9	1.19	3.0	0.86	1.4	0.94	0
3 1/2 X 3 X 3/8	12.5	3.67	4.1	1.06	1.8	1.17	2.8	0.87	1.3	0.92	0
3 1/2 X 3 X 1/2	11.4	3.34	3.8	1.07	1.6	1.15	2.5	0.87	1.2	0.90	0
3 1/2 X 3 X 1/4	10.2	3.00	3.5	1.07	1.5	1.13	2.3	0.88	1.1	0.88	0
3 1/2 X 3 X 1/8	9.1	2.65	3.1	1.08	1.3	1.10	2.1	0.89	0.98	0.85	0
3 1/2 X 3 X 1/16	7.9	2.30	2.7	1.09	1.1	1.08	1.8	0.90	0.85	0.83	0
3 1/2 X 3 X 1/32	6.6	1.93	2.3	1.10	0.96	1.06	1.6	0.90	0.72	0.81	0
3 1/2 X 3 X 1/64	5.4	1.56	1.9	1.11	0.78	1.04	1.3	0.91	0.58	0.79	0
3 1/2 X 2 1/2 X 1 1/4	12.5	3.65	4.1	1.06	1.9	1.27	1.7	0.69	0.99	0.77	0
3 1/2 X 2 1/2 X 3/4	11.5	3.36	3.8	1.07	1.7	1.25	1.6	0.69	0.92	0.75	0
3 1/2 X 2 1/2 X 1 1/8	10.4	3.06	3.6	1.08	1.6	1.23	1.5	0.70	0.84	0.73	0
3 1/2 X 2 1/2 X 3/8	9.4	2.75	3.2	1.09	1.4	1.20	1.4	0.70	0.76	0.70	0
3 1/2 X 2 1/2 X 1/2	8.3	2.43	2.9	1.09	1.3	1.18	1.2	0.71	0.68	0.68	0
3 1/2 X 2 1/2 X 1/4	7.2	2.11	2.6	1.10	1.1	1.16	1.1	0.72	0.59	0.66	0
3 1/2 X 2 1/2 X 1/8	6.1	1.78	2.2	1.11	0.93	1.14	0.94	0.73	0.50	0.64	0
3 1/2 X 2 1/2 X 1/16	4.9	1.44	1.8	1.12	0.75	1.11	0.78	0.74	0.41	0.61	0

See "Note" with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XI\* (Continued). Properties of Angle-Sections. Unequal Legs



Size in	Weight per foot lb	Area of section sq in	Axis 1-1				Axis 2-2				Axis 3-3
			<i>I</i>	<i>r</i>	<i>I/c</i>	<i>z</i>	<i>I</i>	<i>r</i>	<i>I/c</i>	<i>y</i>	<i>y</i> <sub>min</sub>
			in <sup>4</sup>	in	in <sup>3</sup>	in	in <sup>4</sup>	in	in <sup>3</sup>	in	in
X2½ X 3½	9.5	2.78	2.3	0.91	1.2	1.02	1.4	0.72	0.82	0.77	0.52
X2½ X 3½	8.5	2.50	2.1	0.91	1.0	1.00	1.3	0.72	0.74	0.75	0.52
X2½ X 3½	7.6	2.21	1.9	0.92	0.93	0.98	1.2	0.73	0.66	0.73	0.52
X2½ X 3½	6.6	1.92	1.7	0.93	0.81	0.96	1.0	0.74	0.58	0.71	0.52
X2½ X 3½	5.6	1.62	1.4	0.94	0.69	0.93	0.90	0.74	0.49	0.68	0.53
X2½ X 3½	4.5	1.31	1.2	0.95	0.56	0.91	0.74	0.75	0.40	0.66	0.53
X2 X 3½	7.7	2.25	1.9	0.92	1.0	1.08	0.67	0.55	0.47	0.58	0.43
X2 X 3½	6.8	2.00	1.7	0.93	0.89	1.06	0.61	0.55	0.42	0.56	0.43
X2 X 3½	5.9	1.73	1.5	0.94	0.78	1.04	0.54	0.56	0.37	0.54	0.43
X2 X 3½	5.0	1.47	1.3	0.95	0.66	1.02	0.47	0.57	0.32	0.52	0.43
X2 X 3½	4.1	1.19	1.1	0.95	0.54	0.99	0.39	0.57	0.25	0.49	0.43
X2 X 3½	6.8	2.00	1.1	0.75	0.70	0.88	0.64	0.56	0.46	0.63	0.42
X2 X 3½	6.1	1.78	1.0	0.76	0.62	0.85	0.58	0.57	0.41	0.60	0.42
X2 X 3½	5.3	1.55	0.91	0.77	0.55	0.83	0.51	0.58	0.36	0.58	0.42
X2 X 3½	4.5	1.31	0.79	0.78	0.47	0.81	0.45	0.58	0.31	0.56	0.42
X2 X 3½	3.62	1.06	0.65	0.78	0.38	0.79	0.37	0.59	0.25	0.54	0.42
X2 X 3½	2.75	0.81	0.51	0.79	0.29	0.76	0.29	0.60	0.20	0.51	0.43
X2 X 3½	1.86	0.53	0.35	0.80	0.20	0.74	0.20	0.61	0.13	0.49	0.43
X1½ X 3½	3.92	1.15	0.71	0.79	0.44	0.90	0.19	0.41	0.17	0.40	0.32
X1½ X 3½	3.19	0.94	0.59	0.79	0.36	0.83	0.16	0.41	0.14	0.38	0.32
X1½ X 3½	2.44	0.72	0.46	0.80	0.28	0.85	0.13	0.42	0.11	0.35	0.33
X1½ X 3½	5.6	1.63	0.75	0.68	0.54	0.86	0.26	0.40	0.26	0.48	0.32
X1½ X 3½	5.0	1.45	0.68	0.69	0.48	0.83	0.24	0.41	0.23	0.46	0.32
X1½ X 3½	4.4	1.27	0.61	0.69	0.42	0.81	0.21	0.41	0.20	0.44	0.32
X1½ X 3½	3.66	1.07	0.53	0.70	0.36	0.79	0.19	0.42	0.17	0.42	0.32
X1½ X 3½	2.98	0.88	0.44	0.71	0.30	0.77	0.16	0.42	0.14	0.39	0.32
X1½ X 3½	2.28	0.67	0.34	0.72	0.23	0.75	0.12	0.43	0.11	0.37	0.33
X1½ X 3½	3.99	1.17	0.43	0.61	0.34	0.71	0.21	0.42	0.20	0.46	0.32
X1½ X 3½	3.39	1.00	0.38	0.62	0.29	0.69	0.18	0.42	0.17	0.44	0.32
X1½ X 3½	2.77	0.81	0.32	0.62	0.24	0.66	0.15	0.43	0.14	0.41	0.32
X1½ X 3½	2.12	0.62	0.25	0.63	0.18	0.64	0.12	0.44	0.11	0.39	0.32
X1½ X 3½	1.44	0.42	0.17	0.64	0.13	0.62	0.09	0.45	0.08	0.37	0.33
X1½ X 3½	2.55	0.75	0.30	0.63	0.23	0.71	0.09	0.34	0.10	0.33	0.27
X1½ X 3½	1.96	0.57	0.23	0.64	0.18	0.69	0.07	0.35	0.08	0.31	0.27
X1½ X 3½	2.34	0.69	0.20	0.54	0.18	0.60	0.09	0.35	0.10	0.35	0.27
X1½ X 3½	1.80	0.53	0.16	0.55	0.14	0.58	0.07	0.36	0.08	0.33	0.27
X1½ X 3½	1.23	0.36	0.11	0.56	0.09	0.56	0.05	0.37	0.05	0.31	0.27
X1½ X 3½	2.59	0.76	0.16	0.45	0.16	0.52	0.10	0.35	0.11	0.40	0.26
X1½ X 3½	2.13	0.63	0.13	0.46	0.13	0.50	0.08	0.36	0.09	0.38	0.26
X1½ X 3½	1.64	0.48	0.10	0.46	0.10	0.48	0.07	0.37	0.07	0.35	0.26

See "Note" with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XII.\* Properties of Angle-Sections. Equal Legs




Size	Weight per foot	Area of section	Axis 1-1 and Axis 2-2				Axis 3-3
			<i>I</i>	<i>r</i>	<i>I/c</i>	<i>s</i>	
in	lb	sq in	in <sup>4</sup>	in	in <sup>3</sup>	in	in
8×8×1¼	56.9	15.73	98.0	2.42	17.5	2.41	1.5
8×8×1¼a	54.0	15.07	93.5	2.43	16.7	2.39	1.5
8×8×1	51.0	15.00	89.0	2.44	15.8	2.37	1.5
8×8×¾a	48.1	14.12	84.3	2.44	14.9	2.34	1.5
8×8×¾	45.0	13.23	79.6	2.45	14.0	2.32	1.5
8×8×¾a	42.0	12.34	74.7	2.46	13.1	2.30	1.5
8×8×¾	38.9	11.44	69.7	2.47	12.2	2.28	1.5
8×8×½a	35.8	10.53	64.6	2.48	11.3	2.25	1.5
8×8×½	32.7	9.61	59.4	2.49	10.3	2.23	1.5
8×8×¾a	29.6	8.68	54.1	2.50	9.3	2.21	1.5
8×8×¾	26.4	7.75	48.6	2.51	8.4	2.19	1.5
6×6×1	37.4	11.00	35.5	1.80	8.6	1.86	1.1
6×6×¾a	35.3	10.37	33.7	1.80	8.1	1.84	1.1
6×6×¾	33.1	9.73	31.9	1.81	7.6	1.82	1.1
6×6×¾a	31.0	9.09	30.1	1.82	7.2	1.80	1.1
6×6×¾	28.7	8.44	28.2	1.83	6.7	1.78	1.1
6×6×½a	26.5	7.78	26.2	1.83	6.2	1.75	1.1
6×6×½	24.2	7.11	24.2	1.84	5.7	1.73	1.1
6×6×¾a	21.9	6.43	22.1	1.85	5.1	1.71	1.1
6×6×¾	19.6	5.75	19.9	1.86	4.6	1.68	1.1
6×6×¾a	17.2	5.06	17.7	1.87	4.1	1.66	1.1
6×6×¾	14.9	4.36	15.4	1.88	3.5	1.64	1.1
5×5×1	30.6	9.00	19.6	1.48	5.8	1.61	0.9
5×5×¾a	28.9	8.50	18.7	1.48	5.3	1.59	0.9
5×5×¾	27.2	7.98	17.8	1.49	5.2	1.57	0.9
5×5×¾a	25.4	7.47	16.8	1.50	4.9	1.55	0.9
5×5×¾	23.6	6.94	15.7	1.50	4.5	1.52	0.9
5×5×½a	21.8	6.40	14.7	1.51	4.3	1.50	0.9
5×5×½	20.0	5.86	13.6	1.52	3.9	1.48	0.9
5×5×¾a	18.1	5.31	12.4	1.53	3.5	1.46	0.9
5×5×¾	16.2	4.75	11.3	1.54	3.2	1.43	0.9
5×5×¾a	14.3	4.18	10.0	1.55	2.8	1.41	0.9
5×5×¾	12.3	3.61	8.7	1.56	2.4	1.39	0.9
4×4×1¼a	19.9	5.84	8.1	1.18	3.0	1.39	0.7
4×4×¾a	18.5	5.44	7.7	1.19	2.8	1.27	0.7
4×4×¾	17.1	5.03	7.2	1.19	2.6	1.25	0.7
4×4×¾a	15.7	4.61	6.7	1.20	2.4	1.23	0.7
4×4×¾	14.3	4.18	6.1	1.21	2.2	1.21	0.7
4×4×½a	12.8	3.75	5.6	1.22	2.0	1.18	0.7
4×4×½	11.3	3.31	5.0	1.23	1.8	1.16	0.7
4×4×¾a	9.8	2.86	4.4	1.23	1.5	1.14	0.7
4×4×¾	8.2	2.40	3.7	1.24	1.3	1.12	0.7
4×4×¾a	6.6	1.94	3.0	1.25	1.0	1.09	0.7

See "Note" with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XX\* (Continued). Properties of Angle-Sections. Equal Legs




Size in	Weight per foot lb	Area of section sq in	Axis 1-1 and Axis 2-2				Axis 3-3
			$I$ in <sup>4</sup>	$r$ in	$I/c$ in <sup>3</sup>	$x$ in	$y_{max}$ in
10 1/2 x 10 1/2	17.1	5.03	5.3	1.02	2.3	1.17	0.67
10 1/2 x 10	16.0	4.69	5.0	1.03	2.1	1.15	0.67
10 1/2 x 10 1/8	14.8	4.34	4.7	1.04	2.0	1.12	0.67
10 1/2 x 9 1/2	13.6	3.98	4.3	1.04	1.8	1.10	0.68
10 1/2 x 9	12.4	3.62	4.0	1.05	1.6	1.08	0.68
10 1/2 x 8 1/2	11.1	3.25	3.6	1.06	1.5	1.06	0.68
10 1/2 x 8	9.8	2.87	3.3	1.07	1.3	1.04	0.68
10 1/2 x 7 1/2	8.5	2.48	2.9	1.07	1.2	1.01	0.69
10 1/2 x 7	7.2	2.09	2.5	1.08	0.98	0.99	0.69
10 1/2 x 6 1/2	5.8	1.69	2.0	1.09	0.79	0.97	0.69
10 x 10	11.5	3.36	2.6	0.88	1.3	0.98	0.57
10 x 10 1/8	10.4	3.06	2.4	0.89	1.2	0.95	0.58
10 x 10 1/2	9.4	2.75	2.2	0.90	1.1	0.93	0.58
10 x 9 1/2	8.3	2.43	2.0	0.91	0.95	0.91	0.58
10 x 9	7.2	2.11	1.8	0.91	0.83	0.89	0.58
10 x 8 1/2	6.1	1.78	1.5	0.92	0.71	0.87	0.59
10 x 8	4.9	1.44	1.2	0.93	0.58	0.84	0.59
10 1/4 x 10 1/4	7.7	2.25	1.2	0.74	0.73	0.81	0.47
10 1/4 x 10 1/8	6.8	2.00	1.1	0.75	0.65	0.78	0.48
10 1/4 x 10	5.9	1.73	0.98	0.75	0.57	0.76	0.48
10 1/4 x 9 1/2	5.0	1.47	0.85	0.76	0.48	0.74	0.49
10 1/4 x 9	4.1	1.19	0.70	0.77	0.39	0.72	0.49
10 1/4 x 8 1/2	3.07	0.90	0.55	0.78	0.30	0.69	0.49
10 1/4 x 8	2.08	0.61	0.38	0.79	0.20	0.67	0.50
10 1/4 x 7 1/2	5.3	1.56	0.54	0.59	0.40	0.66	0.39
10 1/4 x 7	4.7	1.36	0.48	0.59	0.35	0.64	0.39
10 1/4 x 6 1/2	3.92	1.15	0.42	0.60	0.30	0.61	0.39
10 1/4 x 6	3.19	0.94	0.35	0.61	0.25	0.59	0.39
10 1/4 x 5 1/2	2.44	0.71	0.28	0.62	0.19	0.57	0.40
10 1/4 x 5	1.65	0.48	0.19	0.63	0.13	0.55	0.40
10 1/4 x 4 1/2	4.6	1.34	0.35	0.51	0.30	0.59	0.33
10 1/4 x 4	3.99	1.17	0.31	0.51	0.26	0.57	0.34
10 1/4 x 3 1/2	3.39	1.00	0.27	0.52	0.23	0.55	0.34
10 1/4 x 3	2.77	0.81	0.23	0.53	0.19	0.53	0.34
10 1/4 x 2 1/2	2.12	0.62	0.18	0.54	0.14	0.51	0.35
10 1/4 x 2	1.44	0.42	0.13	0.55	0.10	0.48	0.35
10 1/4 x 1 1/2	3.35	0.98	0.19	0.44	0.19	0.51	0.29
10 1/4 x 1	2.80	0.84	0.16	0.44	0.16	0.49	0.29
10 1/4 x 3/4	2.34	0.69	0.14	0.45	0.13	0.47	0.29
10 1/4 x 1/2	1.80	0.53	0.11	0.46	0.10	0.44	0.29
10 1/4 x 1/4	1.23	0.36	0.08	0.46	0.07	0.42	0.30
10 1/4 x 1/8	2.33	0.68	0.09	0.36	0.11	0.42	0.24
10 1/4 x 1/16	1.92	0.56	0.08	0.37	0.09	0.40	0.24
10 1/4 x 1/32	1.48	0.43	0.06	0.38	0.07	0.38	0.24
10 1/4 x 1/64	1.01	0.30	0.04	0.38	0.05	0.35	0.25
10 1/4 x 1/128	1.49	0.44	0.04	0.29	0.06	0.34	0.19
10 1/4 x 1/256	1.16	0.34	0.03	0.30	0.04	0.32	0.19
10 1/4 x 1/512	0.80	0.23	0.02	0.31	0.03	0.30	0.19

\*Note " with Table IV, page 354.

\*From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XIII.\* Properties of T Sections. Flange and Stem Equal




Size				Weight per foot	Area of sec- tion	Axis 1-1				Axis 2-2	
Flange	Stem	Minimum thickness				I	r	I/c	z	I	r
		Flange	Stem								
in	in	in	in	lb	sq in	in <sup>4</sup>	in	in <sup>3</sup>	in	in <sup>4</sup>	in
6½	6½	0.40	0.45	19.8	5.80	23.5	2.01	5.0	1.76	10.1	1.31
4	4	½	½	13.5	3.97	5.7	1.20	2.0	1.18	2.8	0.84
4	4	¾	¾	10.5	3.09	4.5	1.21	1.6	1.13	2.1	0.81
3½	3½	½	½	11.7	3.44	3.7	1.04	1.5	1.05	1.9	0.74
3½	3½	¾	¾	9.2	2.68	3.0	1.05	1.2	1.01	1.4	0.71
3	3	½	½	9.9	2.91	2.3	0.88	1.1	0.93	1.2	0.64
3	3	⅞	⅞	8.9	2.59	2.1	0.89	0.98	0.91	1.0	0.61
3	3	¾	¾	7.8	2.27	1.8	0.90	0.86	0.88	0.90	0.61
3	3	⅞	⅞	6.7	1.95	1.6	0.90	0.74	0.86	0.75	0.61
2½	2½	¾	¾	6.4	1.87	1.0	0.74	0.59	0.76	0.52	0.51
2½	2½	⅞	⅞	5.5	1.60	0.88	0.74	0.50	0.74	0.44	0.51
2¼	2¼	⅞	⅞	4.9	1.43	0.65	0.67	0.41	0.68	0.33	0.41
2¼	2¼	¾	¾	4.1	1.19	0.52	0.66	0.32	0.65	0.25	0.41
2	2	⅞	⅞	4.3	1.26	0.44	0.59	0.31	0.61	0.23	0.41
2	2	¾	¾	3.56	1.05	0.37	0.59	0.26	0.59	0.18	0.41
1¾	1¾	¾	¾	3.09	0.91	0.23	0.51	0.19	0.54	0.12	0.31
1½	1½	¾	¾	2.47	0.73	0.15	0.45	0.14	0.47	0.08	0.31
1½	1½	⅞	⅞	1.94	0.57	0.11	0.45	0.11	0.44	0.06	0.31
1¼	1¼	¾	¾	2.02	0.59	0.08	0.37	0.10	0.40	0.05	0.21
1¼	1¼	⅞	⅞	1.59	0.47	0.06	0.37	0.07	0.38	0.03	0.21
1	1	⅞	⅞	1.25	0.37	0.03	0.29	0.05	0.32	0.02	0.21
1	1	¾	¾	0.89	0.26	0.02	0.30	0.03	0.29	0.01	0.21

See "Note" with Table IV, page 354.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XIV.\* Properties of T Sections. Flange and Stem Unequal




Stem	thickness		foot	section	$I$	$r$	$I/c$	$x$	$I$	$r$	$I/c$
	Flange	Stem									
$b$	$m$	$t$	$in$	$lb$	$sq\ in$	$in^4$	$in$	$in^4$	$in$	$in^4$	$in^2$
1	3/4	1 3/16	11.5	3.37	2.4	0.84	1.1	0.76	3.9	1.20	1.6
1 3/4	3/4	1 3/16	10.9	3.18	1.5	0.68	0.78	0.63	4.1	1.14	1.6
1 3/4	3/4	1 3/16	15.7	4.60	5.1	1.05	2.1	1.11	3.7	0.90	1.7
1	3/4	1 3/16	9.8	2.88	2.1	0.84	0.91	0.74	3.0	1.02	1.3
1	3/4	1 3/16	8.4	2.46	1.8	0.85	0.78	0.71	2.5	1.01	1.1
1 3/4	3/4	1 3/16	9.2	2.68	1.2	0.67	0.63	0.59	3.0	1.05	1.3
1 3/4	3/4	1 3/16	7.8	2.39	1.0	0.68	0.54	0.57	2.5	1.05	1.1
1	3/4	1 3/16	15.3	4.50	10.8	1.35	3.1	1.36	2.8	0.79	1.4
1	3/4	1 3/16	11.9	3.49	8.5	1.56	2.4	1.51	2.1	0.78	1.1
1 3/4	3/4	1 3/16	14.4	4.23	7.9	1.37	2.5	1.37	2.8	0.81	1.4
1 3/4	3/4	1 3/16	11.2	3.29	6.3	1.39	2.0	1.31	2.1	0.80	1.1
1	3/4	1 3/16	9.2	2.68	2.0	0.86	0.90	0.78	2.1	0.89	1.1
1	3/4	1 3/16	7.8	2.39	1.7	0.87	0.77	0.75	1.8	0.88	0.88
1 3/4	3/4	1 3/16	8.5	2.48	1.2	0.69	0.62	0.62	2.1	0.92	1.0
1 3/4	3/4	1 3/16	7.2	2.12	1.0	0.69	0.53	0.60	1.8	0.91	0.88
1	3/4	1 3/16	7.8	2.27	0.80	0.52	0.40	0.48	2.1	0.96	1.1
1	3/4	1 3/16	6.7	1.95	0.53	0.52	0.34	0.46	1.8	0.95	0.88
1	3/4	1 3/16	12.6	3.70	5.5	1.21	2.0	1.24	1.9	0.72	1.1
1	3/4	1 3/16	9.8	2.88	4.3	1.23	1.5	1.19	1.4	0.70	0.81
1	3/4	1 3/16	10.8	3.17	2.4	0.87	1.1	0.88	1.9	0.77	1.1
1	3/4	1 3/16	8.5	2.48	1.9	0.88	0.89	0.83	1.4	0.75	0.81
1	3/4	1 3/16	7.5	2.20	1.8	0.91	0.85	0.85	1.2	0.74	0.68
1	3/4	1 3/16	11.7	3.44	5.2	1.23	1.9	1.32	1.2	0.59	0.81
1	3/4	1 3/16	10.5	3.06	4.7	1.23	1.7	1.29	1.1	0.59	0.70
1	3/4	1 3/16	9.2	2.68	4.1	1.24	1.5	1.27	0.90	0.58	0.60
1 3/4	3/4	1 3/16	10.8	3.17	3.5	1.06	1.5	1.12	1.2	0.62	0.80
1 3/4	3/4	1 3/16	9.7	2.83	3.2	1.06	1.3	1.10	1.0	0.60	0.69
1 3/4	3/4	1 3/16	8.5	2.48	2.8	1.07	1.2	1.07	0.93	0.61	0.81
1 3/4	3/4	1 3/16	7.1	2.07	1.1	0.72	0.60	0.71	0.89	0.66	0.59
1 3/4	3/4	1 3/16	6.1	1.77	0.94	0.73	0.52	0.68	0.75	0.65	0.50
1	3/4	1 3/16	7.1	2.07	1.7	0.91	0.84	0.95	0.53	0.51	0.42
1	3/4	1 3/16	6.1	1.77	1.5	0.92	0.72	0.92	0.44	0.50	0.35
1 3/4	3/4	1 3/16	2.87	0.84	0.08	0.31	0.09	0.32	0.29	0.38	0.23
1 3/4	3/4	1 3/16	3.09	0.91	0.16	0.42	0.15	0.42	0.18	0.45	0.18
1	3/4	1 3/16	2.45	0.72	0.27	0.61	0.19	0.63	0.06	0.92	0.08
1 3/4	3/4	1 3/16	1.85	0.37	0.05	0.37	0.05	0.33	0.04	0.32	0.05
1 3/4	3/4	1 3/16	0.88	0.16	0.01	0.16	0.01	0.16	0.02	0.31	0.04

\*From Table IV, page 354.

\*From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XV.\* Properties of Double-Angle Sections. Equal Legs, ANGLES PLACED BACK TO BACK



Single angle		Two angles	Radii of gyration, r, in inches				
Size, in	Weight per foot, lb		Axis 1-1	Axis 2-2			
		Area, sq in		In contact	1/4-in apart	3/8-in apart	1/2-in apart
8 X 8 X 1 1/8	56.9	33.46	2.42	3.42	3.51	3.55	3.60
1 3/16	42.0	24.68	2.46	3.37	3.46	3.50	3.55
1/2	26.4	15.50	2.50	3.33	3.41	3.45	3.50
6 X 6 X 1	37.4	22.00	1.80	2.59	2.68	2.72	2.77
1 1/8	26.5	15.56	1.83	2.54	2.63	2.67	2.71
3/8	14.9	8.72	1.88	2.49	2.58	2.62	2.66
5 X 5 X 1	30.6	18.00	1.48	2.19	2.28	2.33	2.38
1 1/8	21.8	12.80	1.51	2.13	2.22	2.26	2.31
3/8	12.3	7.22	1.56	2.09	2.17	2.21	2.26
4 X 4 X 1 3/16	19.9	11.68	1.18	1.75	1.85	1.89	1.94
1/2	6.6	3.88	1.25	1.66	1.75	1.79	1.84
3 1/2 X 3 1/2 X 1 3/16	17.1	10.06	1.02	1.55	1.65	1.70	1.75
1/2	5.8	3.38	1.09	1.46	1.55	1.59	1.64
3 X 3 X 5/8	11.5	6.72	0.88	1.32	1.41	1.46	1.51
1/2	4.9	2.88	0.93	1.25	1.34	1.38	1.43
2 1/2 X 2 1/2 X 1/2	7.7	4.50	0.74	1.09	1.19	1.24	1.29
1/2	4.1	2.38	0.77	1.05	1.14	1.19	1.24
2 X 2 X 7/16	5.3	3.12	0.59	0.88	0.98	1.03	1.08
1/4	3.19	1.88	0.61	0.85	0.94	0.99	1.04

This table and the two following are employed in computing the safe resistance to compressive stress of two angles, back to back, used as struts or as the compression chords of roof-trusses, etc., by the following rule:

Obtain from the compression-formula in use the allowed stress per square inch corresponding to the ratio of slenderness of the section, and multiply that value by the area. The result will be the allowable compressive stress.

Example 1. Section given. Required the safe load in compression, as per foot of length, on a strut composed of two angles, 4 by 4 by 1/2 in, back to back with an unsupported length of 9 ft.

Area of section, A = 3.88 sq in; least radius of gyration, r = 1.25 in.

Ratio of slenderness, l/r = 9 X 12 + 1.25 = 86.4.

Allowed unit stress, S = 19 000 - 100 X 86.4 = 10 360 lb per sq in.

Safe load, AS = 3.88 X 10 360 = 40 200 lb.

Example 2. Stress given. Required a section for a member in compression, 12 ft 3 in long, made of two angles separated by 1/2-in gusset-plates, to resist a stress of 35 000 lb; ratio of slenderness not to exceed 120.

Assume two angles, 5 by 3 by 5/16 in, long legs back to back.

Area of section, A = 4.80 sq in; least radius of gyration, r = 1.26 in.

Ratio of slenderness, l/r = 12.25 X 12 + 1.26 = 116.7.



Allowed unit stress, S = 19 000 - 100 X 116.7 = 7 330 lb per sq in.

Safe load, AS = 4.80 X 7 330 = 35 200 lb.

In the first case the least radius of gyration is that about the axis 1-1; in the second case, about the axis 2-2; in all cases the least radius of gyration determines the ratio of slenderness and therewith the allowed safe compressive stress. In all cases the two angles are to be secured together by stay-rivets, so spaced as to insure that the section acts as a unit. The ratio of slenderness of any single angle between rivets must always be less than that of the strut or compression-chord.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XVI.\* Properties of Double-Angle Sections. Long Legs Vertical  
ANGLES PLACED BACK TO BACK



Single angle		Two angles	Radii of gyration, $r$ , in inches					
Size, in	Weight per foot, lb	Area, sq in	Axis 1-1	Axis 2-2				
				In contact	1/4-in apart	3/8-in apart	1/2-in apart	3/4-in apart
2X1	44.2	26.00	2.49	2.39	2.48	2.52	2.57	2.66
3/4	33.8	19.88	2.53	2.35	2.44	2.48	2.52	2.61
1/2	20.2	11.86	2.57	2.31	2.39	2.43	2.48	2.56
3X1/2	35.7	21.00	2.51	1.26	1.35	1.40	1.45	1.55
3/4	27.5	16.12	2.55	1.20	1.29	1.34	1.39	1.49
1/2	16.5	9.68	2.59	1.15	1.23	1.28	1.32	1.41
3X3/4	32.3	19.00	2.19	1.31	1.40	1.45	1.50	1.60
1 1/4	23.0	13.50	2.23	1.25	1.34	1.39	1.44	1.53
3/4	13.0	7.60	2.27	1.20	1.28	1.33	1.37	1.46
2X1 1/4	30.6	18.00	1.85	1.60	1.69	1.74	1.79	1.89
1 1/4	21.8	12.80	1.89	1.55	1.63	1.68	1.73	1.82
3/4	12.3	7.22	1.93	1.50	1.58	1.62	1.67	1.76
3X3/4	28.9	17.00	1.85	1.37	1.47	1.51	1.56	1.66
1 1/4	20.6	12.12	1.89	1.31	1.41	1.45	1.49	1.60
3/4	9.8	5.74	1.95	1.25	1.33	1.37	1.42	1.50
2X3/4	24.2	14.22	1.58	1.66	1.76	1.80	1.85	1.95
3/4	11.0	6.46	1.59	1.58	1.66	1.70	1.75	1.85
3X1/2	22.7	13.34	1.53	1.42	1.51	1.56	1.61	1.71
3/4	8.7	5.12	1.61	1.33	1.41	1.45	1.50	1.59
3X1 1/4	19.9	11.68	1.55	1.18	1.27	1.32	1.37	1.47
3/4	8.2	4.80	1.61	1.09	1.17	1.22	1.26	1.35
3X1 3/4	18.5	10.86	1.38	1.21	1.31	1.36	1.41	1.51
3/4	7.7	4.50	1.44	1.13	1.22	1.26	1.30	1.40
3X3/4	18.5	10.86	1.19	1.50	1.59	1.64	1.69	1.79
3/4	7.7	4.50	1.26	1.42	1.51	1.55	1.60	1.69
3X1 3/4	17.1	10.06	1.21	1.25	1.35	1.40	1.45	1.55
3/4	5.8	3.38	1.28	1.16	1.24	1.28	1.33	1.43
3X1 3/4	15.8	9.24	1.04	1.30	1.40	1.45	1.50	1.60
3/4	5.4	3.12	1.11	1.20	1.29	1.34	1.38	1.48
3X3/4	12.5	7.30	1.06	1.03	1.13	1.18	1.23	1.33
3/4	4.9	2.88	1.12	0.95	1.04	1.09	1.13	1.23
3X3/4	9.5	5.56	0.91	1.05	1.15	1.20	1.25	1.35
3/4	4.5	2.64	0.95	1.00	1.09	1.13	1.18	1.28
2X1/2	7.7	4.50	0.92	0.80	0.89	0.94	1.00	1.10
3/4	4.1	2.38	0.95	0.74	0.84	0.88	0.93	1.03
2X1/2	6.8	4.00	0.75	0.84	0.94	0.99	1.04	1.15
3/4	3.62	2.12	0.78	0.80	0.89	0.93	0.98	1.08

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XVII.\* Properties of Double-Angle Sections Short Legs Vertical  
ANGLES PLACED BACK TO BACK




Single angle		Two angles		Radii of gyration, $r$ , in inches				
Size, in	Weight per foot, lb	Area, sq in	Axis 1-1	Axis 2-2				
				In contact	1/4-in apart	3/8-in apart	1/2-in apart	
8 X6 X1	44.2	26.00	1.73	3.64	3.73	3.78	3.83	
	33.8	19.88	1.76	3.60	3.69	3.73	3.78	
	20.2	11.86	1.80	3.55	3.64	3.68	3.73	
8 X3 1/2 X1	35.7	21.00	0.86	4.04	4.14	4.19	4.24	
	27.5	16.12	0.88	3.99	4.09	4.13	4.18	
	16.5	9.68	0.92	3.93	4.02	4.07	4.12	
7 X3 1/2 X1	32.3	19.00	0.89	3.48	3.58	3.63	3.68	
	23.0	13.50	0.92	3.42	3.52	3.57	3.62	
	13.0	7.60	0.96	3.36	3.46	3.50	3.55	
6 X4 X1	30.6	18.00	1.09	2.85	2.95	2.99	3.04	
	21.8	12.80	1.13	2.79	2.89	2.93	2.98	
	12.3	7.22	1.17	2.74	2.83	2.87	2.92	
6 X3 1/2 X1	28.9	17.00	0.92	2.92	3.02	3.07	3.12	
	20.6	12.12	0.95	2.87	2.96	3.01	3.06	
	9.8	5.74	1.00	2.81	2.90	2.95	3.00	
5 X4 X3/8	24.2	14.22	1.14	2.29	2.38	2.43	2.48	
	11.0	6.46	1.20	2.20	2.29	2.34	2.38	
5 X3 1/2 X3/8	22.7	13.34	0.96	2.36	2.45	2.50	2.55	
	8.7	5.12	1.03	2.26	2.35	2.39	2.44	
5 X3 X1 3/16	19.9	11.68	0.80	2.42	2.52	2.57	2.62	
	8.2	4.80	0.85	2.33	2.42	2.47	2.52	
4 1/2 X3 X1 3/16	18.5	10.86	0.81	2.15	2.25	2.30	2.35	
	7.7	4.50	0.87	2.06	2.15	2.20	2.25	
4 X3 1/2 X1 3/16	18.5	10.86	1.01	1.81	1.91	1.96	2.01	
	7.7	4.50	1.07	1.73	1.81	1.86	1.91	
4 X3 X1 3/16	17.1	10.06	0.83	1.88	1.98	2.03	2.08	
	5.8	3.38	0.89	1.78	1.87	1.92	1.96	
3 1/2 X3 X1 3/16	15.8	9.24	0.85	1.61	1.71	1.76	1.81	
	5.4	3.12	0.91	1.52	1.61	1.65	1.70	
3 1/2 X2 1/2 X1 1/16	12.5	7.30	0.69	1.66	1.75	1.80	1.86	
	4.9	2.88	0.74	1.58	1.67	1.71	1.76	
3 X2 1/2 X3/16	9.5	5.56	0.72	1.37	1.46	1.51	1.56	
	4.5	2.64	0.75	1.31	1.40	1.45	1.50	
3 X2 X1/2	7.7	4.50	0.55	1.42	1.52	1.57	1.62	
	4.1	2.38	0.57	1.38	1.47	1.52	1.57	
2 1/2 X2 X1/2	6.8	4.00	0.56	1.15	1.25	1.30	1.35	
	3.62	2.12	0.59	1.11	1.20	1.25	1.30	

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XVIII. Properties of Double-Channel Sections

STANDARD CHANNELS PLACED BACK TO BACK




Radii of gyration given correspond to directions indicated by the arrow-heads

Depth, in	Thick- ness of web, in	Weight per foot of one channel, lb	Area of two channels, sq in	Radii of gyration, $r$ , in inches			
				Axis 1-1	Axis 2-2 *		
					$\frac{1}{2}$ -in apart	$\frac{3}{4}$ -in apart	1-in apart
	0.40	33.90	19.80	5.62	1.38	1.48	1.58
	0.42	35.00	20.46	5.58	1.38	1.47	1.57
	0.52	40.00	23.40	5.44	1.37	1.46	1.56
	0.62	45.00	26.34	5.32	1.37	1.45	1.56
	0.72	50.00	29.28	5.24	1.37	1.46	1.56
	0.81	55.00	32.22	5.16	1.38	1.47	1.58
	0.28	20.57	12.06	4.61	1.24	1.34	1.44
	0.39	25.00	14.64	4.43	1.21	1.31	1.41
	0.51	30.00	17.58	4.28	1.20	1.30	1.40
	0.63	35.00	20.52	4.18	1.21	1.31	1.41
	1.76	40.00	23.46	4.09	1.23	1.32	1.43
	0.24	15.30	8.94	3.87	1.14	1.24	1.34
	0.38	20.00	11.72	3.66	1.10	1.20	1.31
	0.53	25.00	14.66	3.52	1.10	1.20	1.31
	0.67	30.00	17.60	3.42	1.12	1.22	1.33
	0.82	35.00	20.54	3.34	1.16	1.26	1.37
	0.23	13.40	7.78	3.49	1.09	1.19	1.29
	0.29	15.00	8.78	3.40	1.07	1.17	1.28
	0.45	20.00	11.72	3.22	1.05	1.15	1.26
	0.61	25.00	14.66	3.10	1.07	1.17	1.28

There are very slight variations from these values caused by slight changes in weights, but the values are sufficiently exact for all practical uses.

Table XVIII (Continued). Properties of Double-Channel Sections  
STANDARD CHANNELS PLACED BACK TO BACK



The radii of gyration given correspond to directions indicated by the arrow

Depth, in	Thick- ness of web, in	Weight per foot of one channel, lb	Area of two channels, sq in	Radii of gyration, $r$ , in inches			
				Axis 1-1	Axis 2-2 *		
					$\frac{1}{2}$ -in apart	$\frac{3}{4}$ -in apart	$s$
8	0.22	11.50	6.72	3.10	1.04	1.14	1
8	0.30	13.75	8.04	2.99	1.04	1.14	1
8	0.40	16.25	9.52	2.89	1.03	1.14	1
8	0.49	18.75	10.98	2.82	1.03	1.14	1
8	0.58	21.25	12.46	2.77	1.03	1.14	1
7	0.21	9.75	5.70	2.72	0.99	1.09	1
7	0.31	12.25	7.16	2.59	0.99	1.09	1
7	0.42	14.75	8.64	2.51	0.99	1.10	1
7	0.52	17.25	10.10	2.44	1.00	1.10	1
7	0.63	19.75	11.58	2.39	1.00	1.10	1
6	0.20	8.20	4.78	2.34	0.94	1.05	1
6	0.31	10.50	6.14	2.22	0.94	1.05	1
6	0.44	13.00	7.62	2.13	0.95	1.06	1
6	0.56	15.50	9.08	2.07	0.95	1.06	1
5	0.19	6.70	3.90	1.95	0.89	1.00	1
5	0.33	9.00	5.26	1.83	0.90	1.00	1
5	0.47	11.50	6.72	1.76	0.91	1.01	1
4	0.18	5.40	3.12	1.56	0.84	0.95	1
4	0.25	6.25	3.64	1.50	0.84	0.95	1
4	0.32	7.25	4.24	1.47	0.84	0.95	1
3	0.17	4.10	2.38	1.17	0.80	0.91	1
3	0.26	5.00	2.92	1.12	0.81	0.92	1
3	0.36	6.00	3.50	1.08	0.83	0.93	1

\* See note on page 373.



## CHAPTER XI

## RESISTANCE TO TENSION. PROPERTIES OF IRON AND STEEL

By

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

## 1. Definitions, Working Stresses and Examples

**The Ultimate Tensile Strength** of a material is the amount of internal stress which a section one square inch in area is capable of exerting against an equal axial force. It is the **UNIT STRESS** or **INTENSITY OF STRESS**, expressed in pounds per square inch, which the material can withstand. It is often called **ULTIMATE STRENGTH** or **ULTIMATE STRESS** of the material. Its value for any material depends on the tenacity of the fibers or the cohesion of the particles of which the material is composed.

**An Axial Force** is one which acts uniformly over the section of a prismatic body so that the resultant of the distributed forces coincides with the axis of the body. Hence the total **AXIAL FORCE** which any cross-section of a body will resist is the product of the ultimate strength of the material and the area of the cross-section, in square inches.

**The Working Stress.** The ultimate strength of different building materials has been found by pulling apart bars of known dimensions and dividing the minimum load each sustained by the area of the bar before testing. This ultimate strength, however, must not be used to proportion the size of members of structures, because of variations in material, hidden defects and imperfect workmanship; and, especially, because of indefiniteness as to the maximum load that may be imposed on the structure. To provide safety against the rupture of a member and the consequent failure of the structure from any of these causes, the proportions of the members must be based on **SAFE WORKING STRESSES** which are usually some fractional part of the ultimate strength found by experiment to provide proper security against failure.

**The Factor of Safety** is the ratio of the ultimate strength to this safe working stress for that material. Its value ranges generally from 2 to 10, depending upon the nature of the material and the service to which it is applied.

**The Working Stress in Tension.** Table I gives these values for various building materials. The total **SAFE LOAD** that may be applied to a piece of material of uniform section is found by multiplying the cross-section of the piece, in square inches, by the safe working stress opposite the name of the material of which the piece is composed.

Let if  $P$  = the safe load in lb,

$S_t$  = the allowable safe working stress in tension,

$b$  = the width of a rectangular bar,

$h$  = the depth of a rectangular bar,

$d$  = the diameter of a round bar,

results, for a rectangular bar,

$$P = bhS_t \quad (1)$$

for a round bar,

$$P = 0.7854 d^2 S_t \quad (2)$$

The area of cross-section to support a load  $P$  is, for a rectangular bar,

$$A = \frac{P}{S_t}$$

and for a round bar

$$d = \sqrt{\frac{P}{0.7854 S_t}}$$

Table I.    Safe Working Stress in Tension for Building Materials \*

Material	Safe stress lb per sq in (
Cast iron.....	3 000
Wrought iron.....	12 000
Steel, medium.....	16 000
Chestnut.....	850
Douglas fir.....	800
Hemlock.....	600
Pine, long-leaf yellow.....	1 200
Pine, short-leaf yellow.....	900
Pine, Norway.....	800
Pine, white.....	700
Redwood.....	700
Spruce.....	800
White oak.....	1 200

\* Note. For woods these values may be increased up to 30% for selected, protected, commercially dry timber, not subject to impact, that is, for ideal cond (See, also, pages 637 and 647.)

Example 1. What size of medium-steel angle should be used to sust tensile force of 64 000 lb?

Answer. By Formula (3),

$$\text{the net sectional area} = \frac{64\,000}{16\,000} = 4.00 \text{ sq in}$$

From the Table of the Properties of Angles (Chapter X) we find that a 4 by 3½-in angle has an area of 4.61 sq in, which is to be reduced by a ¾-in for a ¾-in rivet, leaving 4.61 - (¾ × ¾) = 4.06 sq in, net area. This is sl in excess of the required amount.

The SAFE LOAD for angles commonly used in roof-trusses is given in Tal and the REDUCTION IN SECTIONAL AREA caused by rivet-holes, in Tabl this chapter, and in Table I, Chapter XX. See also, Chapter XII, pag paragraph on Punching Rivet-Holes.

Example 2. What size of white-pine tie-beam should be used to sus tensile force of 60 000 lb?

Answer. By Formula (3),

$$\text{the net sectional area} = \frac{60\,000}{700} = 85.7 \text{ sq in}$$

If the depth is taken at 12 in, the net width must be  $\frac{85.7}{12} = 7.2$  in. Allo must be made for the increase in tension on the lower side of the beam, its own weight, and also for any cutting that may be necessary in makin connections or holes for truss-rods. If there is a 2-in hole through the b

by 12-in timber must be used. This makes allowance for the weight of the beam itself. If the unsupported length of the beam is great, the allowance for weight must be made according to the methods explained in Chapter XV, p. 572, for the calculation of tie-beams subjected to transverse loading.

## 2. Wrought Iron

**Manufacture.** Wrought iron is a mixture of pure iron and slag, about  $\frac{1}{2}\%$  iron and  $3\%$  slag, together with from  $\frac{1}{2}$  to  $\frac{3}{4}\%$  of other elements including boron, phosphorus, sulphur and manganese. It is made from pig iron and scrap-iron, or mill-scale, in a reverberatory furnace consisting of a firebox, a heating or working-chamber, and the necessary dampers and flues. The impurities are removed from the iron at different stages in the process, silicon and manganese during the melting-down stage, part of the phosphorus and sulphur during the clearing-stage and the carbon and remainder of the phosphorus and sulphur during the boiling-stage. The iron is then in a pasty condition ready for thorough stirring by the workman, who collects it into balls of about 80 lb weight and takes it to a squeezer or forge where the greater part of the slag is removed. It is then rolled out into MUCK-BARS. These bars are cut into pieces which are piled into bundles suited to the size of the finished bar. The piles are reheated and rolled again. The rolling reduces the amount of slag and makes the material denser. The process of rerolling may be repeated a number of times to produce double or triple-refined MERCHANT-BAR IRON.

**The Appearance of Wrought Iron** is very much like that of steel. It may be distinguished from steel by nicking one side of the bar and bending it away from the nick. Iron will split along the slag-laminations and show the COARSELY FIBROUS nature of the material; while steel will bend or rupture at the nick without splitting, any fracture being FINELY FIBROUS or CRYSTALLINE. When tested in a tension-test wrought iron shows a dark fibrous fracture. If the specimen is grooved before testing or broken in impact the fracture will be only crystalline.

**Welds.** Wrought iron is more easily welded than steel because the work may be accomplished through a wider range of temperature than with steel. Wrought iron may develop the full strength of the bar, but tests on hand-forged welds on high tie-bars reported by Kirkaldy gave average values of about 60% of the strength of the bar.

**Use.** Wrought iron is no longer used for the manufacture of structural members, such as angles, channels and beams, its use for structural work being practically limited to bars, rods and bolts. It can be worked more easily than steel in threading-machines; and on this account, unless steel is specified, some companies will furnish truss-rods, bolts, etc., in wrought iron.

**Specifications \* for Wrought Iron.** Wrought iron may be purchased under the Specifications of the American Society for Testing Materials.

**Material Covered.** 1. These specifications cover two classes of wrought-iron material, as determined by the kind of material used in their manufacture, namely:

Class A, as defined in Section 2 (b);

Class B, as defined in Section 2 (c);

**These Specifications for Wrought-Iron Plates** are issued by the Society under the designation A 42. They were adopted in 1913 and revised in 1918. There are also A.S.T.M. Standard Specifications for Staybolt Iron, Refined Wrought-Iron Bars, Iron and Steel Chain, etc.

**I. Manufacture**

**Process.** 2. (a) All plates shall be rolled from piles entirely free from admixture of steel.

(b) Piles for Class A plates shall be made from puddle-bars made wholly pig iron and such scrap as emanates from rolling the plates.

(c) Piles for Class B plates shall be made from puddle-bars made wholly pig iron or from a mixture of pig iron and cast-iron scrap, together with wrought-iron scrap.

**II. Physical Properties and Tests**

**Tension-tests.** 3. (a) The plates shall conform to the following minimum requirements as to tensile properties:

Properties considered	Class A		Class B	
	6 in to 24 in incl, in width	Over 24 in to 90 in incl, in width	6 in to 24 in incl, in width	Over to 90 in in width
Tensile strength, lb per sq in.....	49 000	48 000	48 000	47 000
Yield-point, lb per sq in ..	26 000	26 000	26 000	26 000
Elongation in 8 in, per cent.....	16	12	14	10

(b) The yield-point shall be determined by the drop of the beam of the testing machine. The speed of the cross-head of the machine shall not exceed  $\frac{3}{4}$  inch per minute.

**Modifications in Elongation.** 4. For plates under  $\frac{3}{16}$  in in thickness a deduction of 1 from the percentages of elongation specified in Section 3 shall be made for each decrease of  $\frac{1}{16}$  in in thickness below  $\frac{3}{16}$  in.

**Bend Tests.** 5. (a) **COLD-BEND TESTS.** The test-specimen shall be bent cold through  $90^\circ$  without fracture on the outside of the bent portion, as follows: For Class A plates, around a pin the diameter of which is equal to  $1\frac{1}{2}$  times the thickness of the specimen; and for Class B plates, around a pin the diameter of which is equal to three times the thickness of the specimen.

(b) **NICK-BEND TESTS.** The test-specimen, when nicked on one side and broken, shall show for Class A plates, a wholly fibrous fracture, and for Class B plates, not more than 10% of the fractured surface to be crystalline.

**Test-specimens.** 6. Tension and bend-test specimens shall be taken from the finished plates and shall be of the full thickness of plates as rolled. The longitudinal axis of the specimen shall be parallel to the direction in which the plates are rolled.

**Number of Tests.** 7. (a) One tension, one cold-bend and one nick-bend test shall be made for each variation in thickness of  $\frac{1}{8}$  in and not less than one test for every ten plates as rolled.

(b) If any test-specimen fails to conform to the requirements specified, for any reason of an apparent local defect, a retest shall be made. If the retest also fails, the plates represented by such test will be rejected.

**III. Finish**

**Finish.** 8. The plates shall be straight, smooth, and free from cinder, scale, and holes, injurious flaws, buckles, blisters, seams, and laminations.

#### IV. Marking

**Marking.** 9. The plates shall be stamped or otherwise marked as designated by the purchaser.

#### V. Inspection and Rejection

**Inspection.** 10. (a) The inspector representing the purchaser shall have access, at all times while work on the contract of the purchaser is being performed, to all parts of the manufacturer's works which concern the manufacture of the plates ordered. (See complete Specifications for Sections 10, 11 and 12.)

### 3. Cast Iron

**Cast Iron** has been defined as a saturated solution of carbon in iron, the carbon-content varying from  $1\frac{1}{2}$  to 4% according to the other impurities contained. It is hard, brittle, non-malleable and very fluid when melted, so that it is well adapted for casting into complex forms.

**Manufacture.** It is produced in the blast-furnace, which is essentially a refractory-lined stack, with a valve-charging device at the top, tuyeres and openings in the lower part for the introduction of the air-blast, and a hearth at the bottom with a tap-hole for the periodic withdrawal of the iron and slag. **FURNACE-IRON** is cast into **PIGS** about 3 ft long and weighing about 100 lb each. **FOUNDRY-CASTINGS** are made from **PIG IRON** and **SCRAP** melted in a cupola and poured into green-sand molds. The charge is made up of different quantities of the different grades of pig so as to control the physical properties of the castings, principally through control of the silicon-content.

**Appearance.** **CASTINGS** have a gray or white fracture according to the condition of the contained carbon, the gray fracture indicating graphitic or separated carbon and the white the combined carbon. **GRAY IRON** is softer and tougher and is specified for ordinary **CASTINGS**.

**Strength.** Cast iron does not have a definite **ELASTIC LIMIT**. A relatively low stress will produce some permanent deformation. Its **ULTIMATE TENSILE STRENGTH** varies from 15 000 to 20 000 lb per sq in; and in some iron is as high as 25 000 lb per sq in. Its **COMPRESSIVE STRENGTH** varies over a wide range, 10 000 lb per sq in being a fair average value.

**Defects.** Castings are liable to several common **DEFECTS** the chief of which are blow-holes due to the formation of steam from the damp molds, sand-holes due to misplaced sand, rough surfaces, cold shuts due to chilling of the iron, failure to fill the parts of the mold, shrinkage-cracks due to uneven cooling of the castings in parts of different thickness. In cored castings, also, the walls are frequently of variable thickness because of the shifting of the cores. This is especially frequent in case of hollow columns cast in a horizontal position. Because of these defects and on account of the low **ULTIMATE STRENGTH**, cast iron should never be used where it is subjected to any great tensile stress.

**Specifications\* for Cast Iron.** The specifications of the American Society for Testing Materials, for **GRAY-IRON CASTINGS**, include the following requirements:

Unless **FURNACE-IRON** is specified, all **GRAY CASTINGS** are understood to be made by the **CUPOLA-PROCESS**.

The **SULPHUR-CONTENTS** are to be:

For light castings, not over 0.10 per cent.

For medium castings, not over 0.10 per cent.

For heavy castings, not over 0.12 per cent.

These specifications are issued under the fixed designation A 48. They were adopted in 1913 and revised in 1918. The complete specification can be obtained from the Society.

3. In dividing castings into **LIGHT**, **MEDIUM** and **HEAVY** classes, the following standards have been adopted:

Castings having any section less than  $\frac{1}{2}$  in thick shall be known as **CASTINGS**.

Castings in which no section is less than 2 inches thick shall be known as **HEAVY CASTINGS**.

**MEDIUM CASTINGS** are those not included in the above classification.

4. **TRANSVERSE TEST**. The minimum **BREAKING STRENGTH** of the **TRANSMISSION-BAR** under transverse load shall be:

For light castings, not under 2 500 lb.

For medium castings, not under 2 900 lb.

For heavy castings, not under 3 300 lb.

In no case shall the **DEFLECTION** be under 0.10 in.

**TENSION-TEST**. Where specified this shall be:

For light castings, not less than 18 000 lb per sq in.

For medium castings, not less than 21 000 lb per sq in.

For heavy castings, not less than 24 000 lb per sq in.

The specifications give explicit directions for casting the **TRANSMISSION-BAR** which is  $1\frac{1}{4}$  in in diameter and 15 in long. Two of these are cast for every twenty tons of castings. One of each pair must fulfill the requirements to permit acceptance of the castings. The bar is loaded at the middle at a rate which will cause a 0.10-in deflection in from twenty to forty seconds. The test is not recommended.

11. **CASTINGS** shall be true to pattern, free from cracks, flaws and excessive shrinkage. In other respects they shall conform to whatever points shall be specially agreed upon.

#### 4. Steel

**Steel** is a mixture of compounds of iron and carbon with small quantities of other elements, including manganese, phosphorus, sulphur, silicon, etc. The carbon-content controls the hardness and strength of the steel. Less than 0.10% of carbon is present in the soft steels, which have most of the characteristics of wrought iron; while steel with more than 0.40% carbon is called **high-carbon steel**, cannot be welded and is very much stronger. Manganese acts as a cleanser during the process of manufacture, and increases the malleability of the steel. Phosphorus and sulphur are harmful in their effects, phosphorus making steel brittle under sudden loading and sulphur making it hot or brittle when heated.

**Manufacture**. **STRUCTURAL STEEL** is manufactured by the **BESSEMER** and the **OPEN-HEARTH PROCESSES**. In the first, molten cast iron is charged into the Bessemer converter, an air-blast is driven through the charge from perforances in the false bottom of the converter and the silicon, sulphur and carbon are burned out. Carbon in the form of ferro-manganese is then added to deoxidize the charge and give the proper content of carbon in the finished steel, which is quickly drawn off and poured into ingots. Phosphorus is not removed primarily by the Bessemer process; but if the lining of the converter is of a basic material, such as dolomite limestone, and if lime is added with the iron, the phosphorus will unite with it and be poured off with the slag.

**The Open-Hearth Process**. In this process scrap-steel, pig-iron or furnace-iron and limestone flux are charged on the hearth of a Siemens furnace. A reducing gas-flame is directed onto the charge and the carbon and other impurities are gradually removed. When the reduction is about complete

are taken and carbon determined so that the charge may be withdrawn at proper time. The process thus permits of much more accurate control of product. The material is more uniform and consequently more dependable service than BESSEMER STEEL. OPEN-HEARTH STEEL is used for most structural work.

Phosphorus may be removed by the basic process as in case of Bessemer steel. Ores running low in phosphorus are generally used in America so that basic process is little employed here.

**The Effect of Carbon and Phosphorus on the STATIC STRENGTH** of steel. The limits of carbon included in structural steel is an increase in strength of about 1 000 lb per sq in for each 0.01% increase in either element. Cunniff's formula

$$S_t = 40\,000 + 100\,000 (C + P)$$

is the approximate relation between the strength and the chemical composition.  $C$  and  $P$  are respectively the amounts of carbon and phosphorus expressed in percentage. For example, the **ULTIMATE STRENGTH** of a steel having 0.15% carbon and 0.07% phosphorus is, approximately,

$$S_t = 40\,000 + 100\,000 (0.15 + 0.07) = 62\,000 \text{ lb per sq in}$$

**The Percentage of Elongation** decreases as the carbon-content and **ULTIMATE STRENGTH** increase. An approximate relation is

$$\text{percentage of elongation} = \frac{1\,400\,000}{S_t}$$

The **TOTAL ELONGATION** of a ruptured specimen is due to the local stretch at the point of rupture and the uniform elongation over the whole gauge-length. It is necessary to report the gauge-length when reporting this result. If the **LOCAL ELONGATION** is the same for a 2 or an 8-in length, the **PERCENTAGE ELONGATION** for the same material, tested on a 2-in gauge-length, is greater than if measured on an 8-in length.

The **Elastic Behavior** of a specimen of steel loaded to rupture is best shown by a **STRESS-STRAIN DIAGRAM** on which the stresses are plotted as vertical ordinates and the elongations or strains as abscissas, as in Fig. 1. Five significant points are shown:

1) **The Modulus of Elasticity ( $E$ )**. The relation between the stress and the strain or elongation is called the **MODULUS OF ELASTICITY**. It is equal to the stress divided by the unit strain or deformation and is represented graphically by the tangent of the angle of the initial line with the horizontal. Its value for steel for tension is about 30 000 000 lb per sq in.


2) **The Elastic Limit ( $E.L.$ )** is that unit stress beyond which the ratio of stress to strain ceases to be constant, or beyond which the curve ceases to be a straight line.

3) **The Yield-Point ( $Y.P.$ )**, slightly above or beyond the **ELASTIC LIMIT**, is that unit stress at which the specimen begins to stretch without increase in load. This stress may be determined from a test without the use of delicate measuring-apparatus by the **DROP OF THE BEAM** or **HALT IN THE GAUGE** of the testing-machine.

4) **The Ultimate Strength ( $U.S.$ )** is the greatest unit stress the specimen can sustain.

5) **The Rupture-Stress ( $R$ )** is the unit stress at the time of failure. This is the unit stress at the point of failure after the area of the cross-section of the

specimen has been reduced; and because of the rapid dropping off of the  $\frac{1}{2}$  it is difficult to determine. It is not regularly observed in testing, attention being called to it merely to emphasize the fact that the **ULTIMATE STRENGTH** steel is not the stress at the time of failure of the specimen. This is true, for wrought iron and ductile materials in general.



The horizontal scale for the distance  $a$   $b$  is ten times greater than for the remaining distance

Fig. 1. Stress-strain Diagram of Test on Steel Specimens.

**Effect of Punching and Shearing.** Structural steel is hardened by action of the punch and shear in the process of manufacture in the shop; the die-side the metal is forced to flow from the tool and this cold work hardens and injures it as may be shown by a cold-bend test. The effect can be removed by annealing; but in the best work it is usually specified that rivet-holes shall be reamed during the assembling of the parts. This removes the injured metal and brings the parts into better alignment for the insertion of the rivets. The injury from shearing may be removed by milling the all edges.

**The Coefficient of Expansion** of steel is 0.000 006 5 per degree Fahrenheit. The **ELONGATION** in a length  $l$ , due to a change in temperature of  $t$  degrees, then

$$e = 0.000\ 006\ 5\ lt$$

in which  $l$  is expressed in inches and  $t$  in degrees Fahrenheit.

**The Weight of Steel** is taken at 489.6 lb per cu ft. The sectional area of a member in square inches multiplied by 3.4 equals the weight in pounds per linear foot.

**The Working Stress** for structural steel in tension in buildings and bridges



to lb per sq in in most specifications and building laws. For members  
et to constant load some designers use a WORKING STRESS of 20 000 lb  
q in.

1. Standard Specifications for Structural Steel for Buildings

edifications. These specifications are issued by the American Society for  
g Materials under the fixed designation A 9. They were adopted in 1901  
vised in 1909, 1913, 1914 and 1916. Extracts from these specifications  
E

I. Manufacture

cess. 1. (a) Structural steel, except as noted in Paragraph (b), may be  
by the Bessemer or the open-hearth process.  
Rivet steel, and steel for plates or angles over ¼ in in thickness which are  
punched, shall be made by the open-hearth process.

II. Chemical Properties and Tests

emical Composition. 2. The steel shall conform to the following re-  
ments as to chemical composition:

Chemical content	Structural steel	Rivet steel
phorus { Bessemer..... { open-hearth....	not over 0.10 per cent not over 0.06 per cent	..... not over 0.06 per cent
br.....	.....	not over 0.045 per cent

le Analyses. 3. An analysis of each melt of steel shall be made by the  
cturer to determine the percentages of carbon, manganese, phosphorus  
ulphur. This analysis shall be made from a test-ingot taken during the  
g of the melt. The chemical composition thus determined shall be re-  
l to the purchaser or his representative, and shall conform to the require-  
specified in Section 2.

ck Analyses. 4. Analyses may be made by the purchaser from finished  
el representing each melt. The phosphorus and sulphur-content thus  
ined shall not exceed that specified in Section 2 by more than 25 per cent.

III. Physical Properties and Tests

nion-Tests. 5. (a) The material shall conform to the following require-  
as to tensile properties:

Properties considered	Structural steel	Rivet steel
le strength, lb per sq in.....	55 000-65 000	46 000-56 000
point, min, lb per sq in.....	0.5 tens. strength 1 400 000*	0.5 tens. strength 1 400 000
ation in 8 in, min, per cent.....	tens. strength	tens. strength
ation in 2 in, min, per cent.....	22	.....

\* See Section 6.

The yield-point shall be determined by the drop of the beam of the testing-  
pe.

**Modifications in Elongation.** 6. (a) For structural steel over  $\frac{3}{4}$  in in. thickness, a deduction of 1 from the percentage of elongation in 8 in, specified in Section 5 (a), shall be made for each increase of  $\frac{1}{8}$  in in thickness above to a minimum of 18 per cent.

(b) For structural steel under  $\frac{3}{16}$  in in thickness, a deduction of 2.5 from the percentage of elongation in 8 in, specified in Section 5 (a), shall be made for each decrease of  $\frac{1}{16}$  in in thickness below  $\frac{3}{16}$  in.

**Bend Tests.** 7. (a) The test-specimen for plates, shapes and bars, except as specified in Paragraphs (b) and (c); shall bend cold through  $180^\circ$  without cracking on the outside of the bent portion, as follows: For material  $\frac{3}{4}$  in or under in thickness, flat on itself; for material over  $\frac{3}{4}$  in, to and including  $1\frac{1}{4}$  in in thickness, around a pin the diameter of which is equal to the thickness of the specimen; and for material over  $1\frac{1}{4}$  in in thickness, around a pin the diameter of which is equal to twice the thickness of the specimen.

(b) The test-specimen for pins, rollers, and other bars, when prepared as specified in Section 8 (e), shall bend cold through  $180^\circ$  around a 1-in pin without cracking on the outside of the bent portion.

(c) The test-specimen for rivet steel shall bend cold through  $180^\circ$  flat on itself without cracking on the outside of the bent portion.

**Test-Specimens.** 8. (a) Tension and bend-specimens shall be taken from rolled steel in the condition in which it comes from the mill, except as specified in Paragraph (b).

(b) Tension and bend-specimens for pins and rollers shall be taken from finished bars after annealing is specified.



(c) Tension and bend-specimens for plates, shapes and bars, except as specified in Paragraphs (d); (e) and (f), shall be of the full thickness of the material as rolled; and shall be machined to the form and dimensions shown in Fig. 1A, or with both ends parallel.

Fig. 1A. Form of Specimen for Steel-test

(f), shall be of the full thickness of the material as rolled; and shall be machined to the form and dimensions shown in Fig. 1A, or with both ends parallel.

(d) Tension and bend-test specimens for plates over  $1\frac{1}{2}$  in in thickness may be machined to a thickness or diameter of at least  $\frac{3}{4}$  in for a length of at least 9 in.

(e) Tension-test specimens for pins, rollers and bars over  $1\frac{1}{2}$  in in thickness or diameter may conform to the dimensions shown in Fig. 2. In this case, the ends shall be of a form to fit the holders of the testing-machine in such a way that the load shall be the axial. Bend-test specimens may be 1 by  $\frac{1}{2}$  in in section. The axis of the specimen shall be located any point midway between the center and surface and shall be parallel to the axis of the bar.



**Note:** The Gage Length, Parallel Portions and Radii shall be as shown, but the ends may be of a form which will fit the Holders of the Testing Machine.

Fig. 2. Form of Specimen for Pins, Rollers, etc., Over  $1\frac{1}{2}$  inches Thick

Tension and bend-test specimens for rivet steel shall be of the full-size of bars as rolled.

Number of Tests. 9. (a) One tension and one bend-test shall be made from each melt; except that if material from one melt differs  $\frac{1}{8}$  in or more in thickness, one tension and one bend-test shall be made for both the thickest and the lightest material rolled.

If any test-specimen shows defective machining or develops flaws, it may be discarded and another specimen substituted.

If the percentage of elongation of any tension-test specimen is less than specified in Section 5 (a) and any part of the fracture is more than  $\frac{1}{8}$  in from the center of the gauge-length of a 2-in specimen or is outside the middle of the gauge-length of an 8-in specimen, as indicated by scribe-scratches made on the specimen before testing, a retest shall be allowed.

#### IV. Permissible Variations in Weight and Thickness

Permissible Variations. 10. The cross-section or weight of each piece of steel shall not vary more than 2.5 per cent from that specified; except in case of steel plates, which shall be covered by the following permissible variations. One cubic inch of rolled steel is assumed to weigh 0.2833 lb.

WHEN ORDERED TO WEIGHT PER SQUARE FOOT: The weight of each lot in shipment shall not vary from the weight ordered more than the amount shown in Table I.\*

WHEN ORDERED TO THICKNESS: The thickness of each plate shall not vary more than 0.01 in under that order.

The overweight of each lot in each shipment shall not exceed the amount shown in Table II.\*

#### V. Finish

Finish. 11. The finished material shall be free from injurious defects and shall have a workmanlike finish.

#### VI. Marking

Marking. 12. The name or brand of the manufacturer and the melt-number shall be legibly stamped or rolled on all finished material, except that rivet and other small sections shall, when loaded for shipment, be properly marked and marked for identification. The identification-marks shall be stamped on the end of each pin and roller. The melt-number shall be marked, by stamping if practical, on each test-specimen.

#### VII. Inspection and Rejection

Inspection. 13. (See complete Specifications for Sections 13, 14 and 15.)

#### 6. Tension-Members

Notes. The best section for tension-members of relatively small size depends on the kind of end-connections used. Angles or channels are generally used for riveted connections. For very small members rectangular bars, such as T-bars, may be used. The strength of such members is computed on the net section through the rivet-holes. Angles used in tension should have lugs riveted to the outstanding legs and the tie-plate for the better distribution of the stress over the section. Tests on angles with riveted connections reported by F. Kibben† gave from 77 to 86% of the strength of the material as shown by

Tables I and II are omitted here for lack of space. The complete specifications can be obtained from the Society.

Proceedings of the American Society for Testing Materials, Vol. VI, 1906.

tension-tests on standard specimens cut from these angles. Lugs increase strength from 4.7 to 8.7%. It was also shown that a connection giving center of the pull on the center of gravity of the section gave considerably higher strengths than when the center of pull was in line with the gauge-line of rivets. In computing the NET SECTIONAL AREA as reduced by rivet and holes Table XI will be found very convenient.

**Eye-Bars** are used for the main tension-members of pin-connected trusses. They are rectangular in section with a forged head upset in dies and of the same thickness as the bar. The eye is accurately drilled in position in the axis of the bar, true to diameter and exact central distance. Because of its advantage for forging, soft steel is used in making eye-bars. They are also carefully annealed before drilling. Table VI gives the dimensions of STANDARD EYE-BARS manufactured by the mills of the American Bridge Company. These are of practically the same dimensions as the standard bars of other companies. There is from 34 to 42% excess material in the section through the head to insure in the forged part the development of the full strength of the bar. Standard bars should be used in design to avoid the expense of making special dies in which to form the heads. Bars of less than the given minimum thickness are liable to fail, when loaded, by buckling in the head. Thick heads increase the BENDING-STRESSES in the pins and thus, indirectly, the necessary size of the eye. Except for very large structures they are limited to 2 in.

**Tests of Full-Size Eye-Bars** are generally required when a great number of them are to be used in a structure, one in every fifty bars being usually tested. The specifications for carbon-steel bars require that an **ULTIMATE TENSILE STRENGTH** of 56 000 lb per sq in shall be developed, that the **ELONGATION** in the whole length shall be 10% and that failure shall occur in the body of the bar. Nickel steel has been used for tension-members on a few long-span bridges. **WORKING STRESS** on the eye-bars was increased about one-half over that used for carbon steel.




Fig. 3. Eye-bar with Screw-ends for Sleeve-nut or Turn-buckle

carbon steel, and the requirements of the test-bars made correspondingly. The eye is made  $\frac{1}{30}$  in greater than the diameter of the pin. Bars packed with the same pins are drilled at the same setting so as to be of exactly the same length. Bars must be true to length within  $\frac{1}{32}$  in. Small eye-bars are sometimes made with UPSET SCREW-ENDS and SLEEVE-NUTS or TURNBUCKLES in the middle for adjustment, as shown in Fig. 3 and Table VI, page 395.




Fig. 4. Loop-eyes and Sleeve-nuts

**Loop-Rods** (Fig. 4, and Table VII) of round or square section with loop-ends are used for counterties and bracing. Because of the well-known fact that they are not so dependable as other types of tension-members, but, because of their ease of adjustment, are well adapted for this service as secondary members.

**Forked-Loop Rod, Fig. 5,** may be used for one of two tension-rods so as to avoid eccentricity where two rods balance each other on a pin. A CLEVIS at each end of one of the rods accomplishes the same object.

#### **Turnbuckles and Sleeve-Nuts.**

Dimensions of these for adjustable lengths and initial stress in are given in Table VIII, page

The open turnbuckle has the advantage of being easily inspected so that the thread has sufficient length and that the ends of the rods do not butt together.




Fig. 5. Forked Loop

**Upset Screw-Ends** are threaded enlargements on the ends of rods or bolts used to give to the threaded portions a strength as great as that of the body of the bar. Because of effects of forging it is necessary to make the area of the section of the upset end at the root of the thread a little larger than that of the rod itself. A standard upset rod will fail in the body of the bar without enlarging the threaded portion enough to prevent the turning of the nuts. Dimensions given are nearly the same with all manufacturers. If upset cannot be obtained the section-area at the root of the thread must be used in computing the safe load.

**Tables.** Table IX, page 398, gives the dimensions and other details for rods according to the latest standards of the American Bridge Company.

**Notes.** The following tables will be found useful in designing tension-members, or for drawing turnbuckles, sleeve-nuts, clevises, etc. The strength of rods in Table II is based on the area at the root of the thread. For loads and weights of tie-rods and anchors for steel beams, see Table XIX, page XV.

Table II. Safe Loads in Pounds on Round Rods

Diameter inches	Plain rods Load in pounds based on area at root of thread			Upset rods Load in pounds based on f area of rod		
	Stress in lb per sq in			Stress in lb per sq in		
	10 000	12 000	16 000	10 000	12 000	16 000
$\frac{1}{4}$	270	324	432	491	590	
$\frac{5}{16}$	450	540	720	767	920	1
$\frac{3}{8}$	680	816	1 088	1 104	1 320	1
$\frac{7}{16}$	930	1 116	1 488	1 503	1 800	2
$\frac{1}{2}$	1 260	1 513	2 016	1 963	2 360	3
$\frac{9}{16}$	1 620	1 944	2 592	2 485	2 970	3
$\frac{5}{8}$	2 020	2 424	3 232	3 068	3 680	4
$\frac{3}{4}$	3 020	3 624	4 832	4 418	5 300	7
$\frac{7}{8}$	4 200	5 040	6 720	6 013	7 210	9
1	5 500	6 600	8 800	7 854	9 420	12
$1\frac{1}{8}$	6 940	8 328	11 104	9 940	11 930	15
$1\frac{1}{4}$	8 930	10 716	14 288	12 270	14 720	19
$1\frac{3}{8}$	10 570	12 680	16 910	14 840	17 810	23
$1\frac{1}{2}$	12 950	15 540	20 720	17 670	21 200	28
$1\frac{5}{8}$	15 150	18 180	24 240	20 730	24 880	31
$1\frac{3}{4}$	17 440	20 930	27 900	24 050	28 860	36
$1\frac{7}{8}$	20 480	24 580	32 760	27 610	33 130	41
2	23 020	27 620	36 830	31 420	37 700	51
$2\frac{1}{8}$	26 340	31 610	42 150	35 460	42 550	59
$2\frac{1}{4}$	30 230	36 280	48 370	39 760	47 710	69
$2\frac{3}{8}$	33 000	39 600	52 800	44 300	53 160	79
$2\frac{1}{2}$	37 150	44 630	59 440	49 080	58 900	79
$2\frac{3}{4}$	46 190	55 430	73 900	59 390	71 270	99
3	54 280	65 140	86 850	70 680	84 820	119
$3\frac{1}{4}$	65 100	78 120	104 160	82 950	99 540	139
$3\frac{1}{2}$	75 480	90 570	120 770	96 210	115 450	159
$3\frac{3}{4}$	86 410	103 690	138 250	110 450	132 540	179
4	99 930	119 920	159 890	125 660	150 790	209
$4\frac{1}{4}$	113 290	135 900	181 300	141 800	170 160	229
$4\frac{1}{2}$	127 430	152 900	203 900	159 000	190 800	259
$4\frac{3}{4}$	142 200	170 600	227 500	177 200	212 640	289
5	157 630	189 100	252 200	196 300	235 560	319
$5\frac{1}{4}$	175 720	210 800	281 100	216 400	259 680	349
$5\frac{1}{2}$	192 670	231 200	308 300	237 500	285 000	389
$5\frac{3}{4}$	212 620	255 100	340 200	259 600	311 000	419
6	230 980	277 200	369 600	282 700	339 200	449

Table III. Safe Loads in Pounds for Flat Rolled Bars

Computed for a stress of 16 000 pounds per square inch

Thickness in inches	Width in inches									
	1	1¼	1½	1¾	2	2¼	2½	2¾	3	3¼
1/16	1 000	1 250	1 500	1 750	2 000	2 250	2 500	2 750	3 000	3 250
1/8	2 000	2 500	3 000	3 500	4 000	4 500	5 000	5 500	6 000	6 500
3/16	3 000	3 750	4 500	5 250	6 000	6 750	7 500	8 250	9 000	9 750
1/4	4 000	5 000	6 000	7 000	8 000	9 000	10 000	11 000	12 000	13 000
5/16	5 000	6 250	7 500	8 750	10 000	11 250	12 500	13 750	15 000	16 250
3/8	6 000	7 500	9 000	10 500	12 000	13 500	15 000	16 500	18 000	19 500
7/16	7 000	8 750	10 500	12 250	14 000	15 750	17 500	19 250	21 000	22 750
1/2	8 000	10 000	12 000	14 000	16 000	18 000	20 000	22 000	24 000	26 000
5/8	9 000	11 250	13 500	15 750	18 000	20 250	22 500	24 750	27 000	29 250
3/4	10 000	12 500	15 000	17 500	20 000	22 500	25 000	27 500	30 000	32 500
7/8	11 000	13 750	16 500	19 250	22 000	24 750	27 500	30 250	33 000	36 750
1	12 000	15 000	18 000	21 000	24 000	27 000	30 000	33 000	36 000	39 000
1 1/16	13 000	16 250	19 500	22 750	26 000	29 250	32 500	35 750	39 000	42 250
1 1/8	14 000	17 500	21 000	24 500	28 000	31 500	35 000	38 500	42 000	45 500
1 1/4	15 000	18 750	22 500	26 250	30 000	33 750	37 500	41 250	45 000	48 750
1 3/8	16 000	20 000	24 000	28 000	32 000	36 000	40 000	44 000	48 000	52 000
1 1/2	17 000	21 250	25 500	29 750	34 000	38 250	42 500	46 750	51 000	55 250
1 5/8	18 000	22 500	27 000	31 500	36 000	40 500	45 000	49 500	54 000	58 500
1 3/4	19 000	23 750	28 500	33 250	38 000	42 750	47 500	52 250	57 000	61 750
1 7/8	20 000	25 000	30 000	35 000	40 000	45 000	50 000	55 000	60 000	65 000
2	22 000	27 500	33 000	38 500	44 000	49 500	55 000	60 500	66 000	71 500
2 1/16	24 000	30 000	36 000	42 000	48 000	54 000	60 000	66 000	72 000	78 000
2 1/8	26 000	32 500	39 000	45 500	52 000	58 500	65 000	71 500	78 000	84 500
2 1/4	28 000	35 000	42 000	49 000	56 000	63 000	70 000	77 000	84 000	91 000
2 3/8	30 000	37 500	45 000	53 500	60 000	67 500	75 000	83 500	90 000	97 500
2 1/2	32 000	40 000	48 000	56 000	64 000	72 000	80 000	88 000	96 000	104 000

Table III (Continued). Safe Loads in Pounds for Flat Rolled Bars  
Computed for a stress of 16 000 pounds per square inch

Thick- ness in inches	Width in inches									
	3½	3¾	4	4¼	4½	4¾	5	5½	6	6½
3/16	3 500	3 750	4 000	4 250	4 500	4 750	5 000	5 500	6 000	6 500
1/8	7 000	7 500	8 000	8 500	9 000	9 500	10 000	11 000	12 000	13 000
5/16	10 500	11 250	12 000	12 750	13 500	14 250	15 000	16 500	18 000	19 500
1/4	14 000	15 000	16 000	17 000	18 000	19 000	20 000	22 000	24 000	26 000
5/8	17 500	18 750	20 000	21 250	22 500	23 750	25 000	27 500	30 000	32 500
3/8	21 000	22 500	24 000	25 500	27 000	28 500	30 000	33 000	36 000	39 000
7/16	24 500	26 250	28 000	29 750	31 500	33 250	35 000	38 500	42 000	45 500
1/2	28 000	30 000	32 000	34 000	36 000	38 000	40 000	44 000	48 000	52 000
9/16	31 500	33 750	36 000	38 250	40 500	42 750	45 000	49 500	54 000	58 500
5/8	35 000	37 500	40 000	42 500	45 000	47 500	50 000	55 000	60 000	65 000
11/16	38 500	41 250	44 000	46 750	49 500	52 250	55 000	60 500	66 000	71 500
3/4	42 000	45 000	48 000	51 000	54 000	57 000	60 000	66 000	72 000	78 000
13/16	45 500	48 750	52 000	55 250	58 500	61 750	65 000	71 500	78 000	85 000
7/8	49 000	52 500	56 000	59 500	63 000	66 500	70 000	77 000	84 000	91 000
15/16	52 500	56 250	60 000	63 750	67 500	71 250	75 000	82 500	90 000	97 500
1	56 000	60 000	64 000	68 000	72 000	76 000	80 000	88 000	96 000	104 000
1 1/16	59 500	63 750	68 000	72 250	76 500	80 750	85 000	93 500	102 000	110 500
1 1/8	63 000	67 500	72 000	76 500	81 000	85 500	90 000	99 000	108 000	117 000
1 5/16	66 500	71 250	76 000	80 750	85 500	90 250	95 000	104 500	114 000	123 500
1 1/4	70 000	75 000	80 000	85 000	90 000	95 000	100 000	110 000	120 000	130 000
1 3/8	77 000	82 500	88 000	93 500	99 000	104 500	110 000	121 000	132 000	143 000
1 1/2	84 000	90 000	96 000	102 000	108 000	114 000	120 000	132 000	144 000	156 000
1 5/8	91 000	97 500	104 000	110 500	117 000	123 500	130 000	143 000	156 000	169 000
1 3/4	98 000	105 000	112 000	119 000	126 000	133 000	140 000	154 000	168 000	182 000
1 7/8	105 000	112 500	120 000	127 500	135 000	142 500	150 000	165 000	180 000	195 000
2	112 000	120 000	128 000	136 000	144 000	152 000	160 000	176 000	192 000	208 000



**Table IV. Safe Loads in Pounds for Flat Rolled Bars**  
 Computed for a stress of 10 000 lb per square inch\*

Thick- ness in inches	Width in inches									
	1	1½	1½	1¾	2	2¼	2½	2¾	3	3½
½	630	780	940	1 090	1 250	1 410	1 560	1 720	1 880	2 030
⅝	1 250	1 560	1 880	2 190	2 500	2 810	3 130	3 440	3 750	4 060
¾	1 880	2 340	2 810	3 280	3 750	4 220	4 690	5 160	5 630	6 090
⅞	2 500	3 130	3 750	4 380	5 000	5 630	6 250	6 880	7 500	8 130
1	3 130	3 910	4 690	5 470	6 250	7 030	7 810	8 590	9 380	10 200
1 ⅛	3 750	4 690	5 630	6 560	7 500	8 440	9 380	10 300	11 300	12 200
1 ¼	4 380	5 470	6 560	7 660	8 750	9 840	10 900	12 000	13 100	14 200
1 ½	5 000	6 250	7 500	8 750	10 000	11 300	12 500	13 800	15 000	16 300
1 ⅞	5 630	7 030	8 440	9 840	11 300	12 700	14 100	15 500	16 900	18 300
2	6 250	7 810	9 380	10 900	12 500	14 100	15 600	17 200	18 800	20 300
2 ⅛	6 880	8 590	10 300	12 000	13 800	15 500	17 200	18 900	20 600	22 300
2 ¼	7 500	9 380	11 300	13 100	15 000	16 900	18 800	20 600	22 500	24 400
2 ½	8 130	10 200	12 200	14 200	16 300	18 300	20 300	22 300	24 400	26 400
2 ⅞	8 750	10 900	13 100	15 300	17 500	19 700	21 900	24 100	26 300	28 400
3	9 380	11 700	14 100	16 400	18 800	21 100	23 400	25 800	28 100	30 500
3 ⅛	10 000	12 500	15 000	17 500	20 000	22 500	25 000	27 500	30 000	32 500
3 ¼	10 600	13 300	15 900	18 600	21 300	23 900	26 600	29 200	31 900	34 500
3 ½	11 300	14 100	16 900	19 700	22 500	25 300	28 100	30 900	33 800	36 600
3 ⅞	11 900	14 800	17 800	20 800	23 800	26 700	29 700	32 700	35 600	38 600
4	12 500	15 600	18 800	21 900	25 000	28 100	31 300	34 400	37 500	40 600
4 ⅛	13 800	17 200	20 600	24 100	27 500	30 900	34 400	37 800	41 300	44 700
4 ¼	15 000	18 800	22 500	26 300	30 000	33 800	37 500	41 300	45 000	48 800
4 ½	16 300	20 300	24 400	28 400	32 500	36 600	40 600	44 700	48 800	52 800
4 ⅞	17 500	21 900	26 300	30 600	35 000	39 400	43 800	48 100	52 500	56 900
5	18 800	23 400	28 100	32 800	37 500	42 200	46 900	51 600	56 300	60 900
5 ⅛	20 000	25 000	30 000	35 000	40 000	45 000	50 000	55 000	60 000	65 000

\* For unit stresses of 12 000, 12 500, and 15 000 lb increase by ⅙, ¼, and ⅓ respectively.

For working strength of wrought iron and steel, see pages 376 and 382.

Table IV (Continued). Safe Loads in Pounds for Flat Rolled Bars  
Computed for a stress of 10 000 lb per square inch

Thick- ness in inches	Width in inches									
	3½	3¾	4	4¼	4½	4¾	5	5½	6	6½
1/16	2 190	2 340	2 500	2 660	2 810	2 970	3 130	3 440	3 750	4 060
1/8	4 380	4 690	5 000	5 310	5 630	5 940	6 250	6 880	7 500	8 120
3/16	6 560	7 030	7 500	7 970	8 440	8 910	9 380	10 300	11 300	12 280
1/4	8 750	9 380	10 000	10 600	11 300	11 900	12 500	13 800	15 000	16 300
5/16	10 900	11 700	12 500	13 300	14 100	14 800	15 600	17 200	18 800	20 300
3/8	13 100	14 100	15 000	15 900	16 900	17 800	18 800	20 600	22 500	24 400
7/16	15 300	16 400	17 500	18 600	19 700	20 800	21 900	24 100	26 300	28 400
1/2	17 500	18 800	20 000	21 300	22 500	23 800	25 000	27 500	30 000	32 500
9/16	19 700	21 100	22 500	23 900	25 300	26 700	28 100	30 900	33 800	36 600
5/8	21 900	23 400	25 000	26 600	28 100	29 700	31 300	34 400	37 500	40 600
11/16	24 100	25 800	27 500	29 200	30 900	32 700	34 400	37 800	41 300	44 700
3/4	26 300	28 100	30 000	31 900	33 800	35 600	37 500	41 300	45 000	48 800
13/16	28 400	30 500	32 500	34 500	36 600	38 600	40 600	44 700	48 800	52 800
7/8	30 600	32 800	35 000	37 200	39 400	41 600	43 800	48 100	52 500	56 900
15/16	32 800	35 200	37 500	39 800	42 200	44 500	46 900	51 600	56 300	60 900
1	35 000	37 500	40 000	42 500	45 000	47 500	50 000	55 000	60 000	65 000
1 1/16	37 200	39 800	42 500	45 200	47 800	50 500	53 100	58 400	63 800	69 100
1 1/8	39 400	42 200	45 000	47 800	50 600	53 400	56 300	61 900	67 500	73 100
1 3/16	41 600	44 500	47 500	50 500	53 400	56 400	59 400	65 300	71 300	77 200
1 1/4	43 800	46 900	50 000	53 100	56 300	59 400	62 500	68 800	75 000	81 300
1 5/8	48 100	51 600	55 000	58 400	61 900	65 300	68 800	75 600	82 500	89 400
1 1/2	52 500	56 300	60 000	63 800	67 500	71 300	75 000	82 500	90 000	97 500
1 7/8	56 900	60 900	65 000	69 100	73 100	77 200	81 300	89 400	97 500	105 600
1 3/4	61 300	65 600	70 000	74 400	78 800	83 100	87 500	96 300	105 000	113 800
1 7/8	65 600	70 300	75 000	79 700	84 400	89 100	93 800	103 100	112 500	121 900
2	70 000	75 000	80 000	85 000	90 000	95 000	100 000	110 000	120 000	130 000

\* See foot-note, preceding table.

Table V. Standard Proportions of Upset Screw-Ends for Round and Square Bars

Nom. of rod or size of square bar in	Round bars				Square bars			
	Diam. of upset screw- end in	Diam. of screw at root of thread in	Number of threads per inch	Excess of effec- tive area of screw- end over bar %	Diam. of upset screw- end in	Diam. of screw at root of thread in	Number of threads per inch	Excess of effec- tive area of screw- end over bar %
$\frac{1}{2}$	$\frac{3}{4}$	0.620	10	54	$\frac{3}{4}$	0.620	10	21
$\frac{7}{16}$	$\frac{3}{4}$	0.620	10	21	$\frac{7}{16}$	0.731	9	33
$\frac{3}{8}$	$\frac{7}{8}$	0.731	9	37	1	0.837	8	41
$\frac{11}{16}$	1	0.837	8	48	1	0.837	8	17
$\frac{5}{8}$	1	0.837	8	25	$1\frac{1}{8}$	0.940	7	23
$\frac{15}{16}$	$1\frac{1}{8}$	0.940	7	34	$1\frac{1}{4}$	1.065	7	35
$\frac{3}{4}$	$1\frac{1}{4}$	1.065	7	48	$1\frac{3}{8}$	1.160	6	38
$\frac{17}{16}$	$1\frac{1}{4}$	1.065	7	29	$1\frac{3}{8}$	1.160	6	20
1	$1\frac{3}{8}$	1.160	6	35	$1\frac{1}{2}$	1.284	6	29
$1\frac{1}{8}$	$1\frac{3}{8}$	1.160	6	19	$1\frac{5}{8}$	1.389	$5\frac{1}{2}$	34
$1\frac{1}{4}$	$1\frac{1}{2}$	1.284	6	30	$1\frac{5}{8}$	1.389	$5\frac{1}{2}$	20
$1\frac{3}{8}$	$1\frac{1}{2}$	1.284	6	17	$1\frac{3}{4}$	1.490	5	24
$1\frac{1}{2}$	$1\frac{5}{8}$	1.389	$5\frac{1}{2}$	23	$1\frac{7}{8}$	1.615	5	31
$1\frac{5}{8}$	$1\frac{3}{4}$	1.490	5	29	$1\frac{7}{8}$	1.615	5	19
$1\frac{3}{4}$	$1\frac{3}{4}$	1.490	5	18	2	1.712	$4\frac{1}{2}$	22
$1\frac{7}{8}$	$1\frac{7}{8}$	1.615	5	26	$2\frac{1}{8}$	1.837	$4\frac{1}{2}$	28
$1\frac{1}{2}$	2	1.712	$4\frac{1}{2}$	30	$2\frac{1}{8}$	1.837	$4\frac{1}{2}$	18
$1\frac{5}{8}$	2	1.712	$4\frac{1}{2}$	20	$2\frac{1}{4}$	1.962	$4\frac{1}{2}$	24
$1\frac{3}{8}$	$2\frac{1}{8}$	1.837	$4\frac{1}{2}$	28	$2\frac{3}{8}$	2.087	$4\frac{1}{2}$	30
$1\frac{11}{16}$	$2\frac{1}{8}$	1.837	$4\frac{1}{2}$	18	$2\frac{3}{8}$	2.087	$4\frac{1}{2}$	20
$1\frac{3}{4}$	$2\frac{1}{4}$	1.962	$4\frac{1}{2}$	26	$2\frac{1}{2}$	2.175	4	21
$1\frac{15}{16}$	$2\frac{1}{4}$	1.962	$4\frac{1}{2}$	17	$2\frac{5}{8}$	2.300	4	26
$1\frac{7}{8}$	$2\frac{3}{8}$	2.087	$4\frac{1}{2}$	24	$2\frac{5}{8}$	2.300	4	18
$1\frac{15}{16}$	$2\frac{1}{2}$	2.175	4	26	$2\frac{3}{4}$	2.425	4	23
2	$2\frac{1}{2}$	2.175	4	18	$2\frac{7}{8}$	2.550	4	28
$2\frac{1}{16}$	$2\frac{3}{8}$	2.300	4	24	$2\frac{7}{8}$	2.550	4	20
$2\frac{1}{8}$	$2\frac{3}{8}$	2.300	4	17	3	2.629	$3\frac{1}{2}$	20
$2\frac{1}{4}$	$2\frac{3}{4}$	2.425	4	23	$3\frac{1}{8}$	2.754	$3\frac{1}{2}$	24

Table V (Continued). Standard Proportions of Upset Screw-Ends for Round and Square Bars

Diam. of round or side of square bar in	Round bars				Square bars			
	Diam. of upset screw-end in	Diam. of screw at root of thread in	Number of threads per inch	Excess of effective area of screw-end over bar %	Diam. of upset screw-end in	Diam. of screw at root of thread in	Number of threads per inch	Exce of eff tive s of scr end o ba %
2¼	2⅞	2.550	4	28	3⅞	2.754	3½	11
2⅝	2⅞	2.550	4	22	3¾	2.879	3½	21
2⅞	3	2.629	3½	23	3⅞	3.004	3½	21
2⅞	3⅞	2.754	3½	28	3⅞	3.004	3½	11
2½	3⅞	2.754	3½	21	3½	3.100	3¼	21
2⅞	3¼	2.879	3½	26	3⅞	3.225	3¼	21
2⅞	3¼	2.879	3½	20	3⅞	3.225	3¼	11
2⅞	3⅞	3.004	3½	25	3⅞	3.317	3	21
2¾	3⅞	3.004	3½	19	3⅞	3.442	3	21
2⅞	3⅞	3.100	3¼	22	3⅞	3.442	3	11
2⅞	3⅞	3.225	3¼	26	4	3.567	3	21
2⅞	3⅞	3.225	3¼	21	4⅞	3.692	3	21
3	3¼	3.317	3	22	4⅞	3.692	3	11
3⅞	3⅞	3.442	3	21	4⅞	3.923	2⅞	21
3¼	4	3.567	3	20	4⅞	4.028	2¾	21
3⅞	4⅞	3.692	3	20	4⅞	4.153	2¾	11
3½	4¼	3.798	2⅞	18	...	.....	...	.
3⅞	4⅞	4.028	2¾	23	...	.....	...	.
3¾	4⅞	4.153	2¾	23	...	.....	...	.
3⅞	4¾	4.255	2⅞	21	...	.....	...	.

REMARKS. As upsetting reduces the strength of iron, bars having the same diam at the root of the thread as that of the bar invariably break in the screw-end tested to destruction, without developing the full strength of the bar. It is then necessary to make up for this loss in strength by an excess of metal in the upset s ends over that in the bar.

Table V is the result of numerous tests on finished bars made at the Keystone B Company's Works in Pittsburgh, Pa., and gives proportions that will cause the b break in the body rather than in the upset end.


The screw-threads in the above table are the Franklin Institute standards.

To make one upset end for a 5-in length of thread, allow 6 in in length of rod, tional.



Table VII.\* Loop-Rods

AMERICAN BRIDGE COMPANY STANDARD



Pitch and shape of thread A. B. Co standard  
 Additional length A, in feet and inches, for one loop.  $A = 4.17p + 5.89$

Diam. of pin, p. in	Diameter or side r of rod in inches									
	$\frac{3}{4}$	$\frac{7}{8}$	1	$1\frac{1}{8}$	$1\frac{1}{4}$	$1\frac{3}{8}$	$1\frac{1}{2}$	$1\frac{5}{8}$	$1\frac{3}{4}$	$1\frac{7}{8}$
$1\frac{1}{8}$	0- 9½	0-10	0-11	0-11½	....	....	....	....	....	....
$1\frac{1}{4}$	0-10	0-10½	0-11½	1- 0	1- 1	....	....	....	....	....
$1\frac{1}{2}$	0-11	0-11½	1- 0½	1- 1	1- 2	1- 2½	....	....	....	....
$1\frac{3}{4}$	1- 0	1- 0½	1- 1½	1- 2	1- 3	1- 3½	1- 4½	1- 5	1- 6	....
2	1- 1	1- 1½	1- 2½	1- 3	1- 4	1- 4½	1- 5½	1- 6	1- 7	1- 7½
$2\frac{1}{4}$	1- 2	1- 3	1- 3½	1- 4½	1- 5	1- 5½	1- 6½	1- 7	1- 8	1- 8½
$2\frac{1}{2}$	1- 3	1- 4	1- 4½	1- 5½	1- 6	1- 7	1- 7½	1- 9	1- 9	1- 9½
$2\frac{3}{4}$	1- 4	1- 5	1- 5½	1- 6½	1- 7	1- 8	1- 8½	1- 9½	1-10	1-11
3	1- 5	1- 6	1- 6½	1- 7½	1- 8	1- 9	1- 9½	1-10½	1-11	2- 0
$3\frac{1}{4}$	1- 6	1- 7	1- 7½	1- 8½	1- 9	1-10	1-10½	1-11½	2- 0	2- 1
$3\frac{1}{2}$	1- 7½	1- 8	1- 8½	1- 9½	1-10	1-11	1-11½	2- 0½	2- 1	2- 2
$3\frac{3}{4}$	1- 8½	1- 9	1-10	1-10½	1-11	2- 0	2- 0½	2- 1½	2- 2	2- 3
4	1- 9½	1-10	1-11	1-11½	2- 0½	2- 1	2- 2	2- 2½	2- 3	2- 4
$4\frac{1}{4}$	....	1-11	2- 0	2- 0½	2- 1½	2- 2	2- 3	2- 3½	2- 4½	2- 5
$4\frac{1}{2}$	....	2- 0	2- 1	2- 1½	2- 2½	2- 3	2- 4	2- 4½	2- 5½	2- 6
$4\frac{3}{4}$	....	2- 1	2- 2	2- 2½	2- 3½	2- 4	2- 5	2- 5½	2- 6½	2- 7
5	....	2- 2½	2- 3	2- 3½	2- 4½	2- 5	2- 6	2- 6½	2- 7½	2- 8
$5\frac{1}{4}$	....	....	2- 4	2- 5	2- 5½	2- 6	2- 7	2- 7½	2- 8½	2- 9
$5\frac{1}{2}$	....	....	2- 5	2- 6	2- 6½	2- 7½	2- 8	2- 9	2- 9½	2-10
$5\frac{3}{4}$	....	....	2- 6	2- 7	2- 7½	2- 8½	2- 9	2-10	2-10½	2-11½
6	....	....	2- 7	2- 8	2- 8½	2- 9½	2-10	2-11	2-11½	3- 0½
$6\frac{1}{4}$	....	....	....	2- 9	2- 9½	2-10½	2-11	3- 0	3- 0½	3- 1½
$6\frac{1}{2}$	....	....	....	2-10	2-10½	2-11½	3- 0	3- 1	3- 1½	3- 2½
$6\frac{3}{4}$	....	....	....	2-11	3- 0	3- 0½	3- 1	3- 2	3- 2½	3- 3½
7	....	....	....	3- 0	3- 1	3- 1½	3- 2½	3- 3	3- 3½	3- 4½


Pins marked † are special. Maximum shipping length of l = 35 ft.  
 \* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table VIII.\* Turnbuckles and Sleeve-Nuts

AMERICAN BRIDGE COMPANY STANDARD

All dimensions in inches

## TURNBUCKLES



F:  $\frac{1}{4}$ " for turnbuckles marked  $\frac{1}{4}$ "  
 and shape of thread, A. B. Co standard

## SLEEVE-NUTS



Pitch and shape of thread, A. B. Co  
 standard

**Table III.\*    Clowies**  
**AMERICAN BRIDGE COMPANY STANDARD**

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



**Table X. Safe Loads in Tension for Common Sizes of Angles with One  $\frac{7}{8}$ -Inch Rivet-Hole for a  $\frac{3}{4}$ -Inch Rivet**  
Load in pounds for a stress of 16 000 lb per sq in

Size of angle	Load	Size of angle	Load
$6 \times 4 \times \frac{5}{8}$	100 500	$3\frac{1}{2} \times 2\frac{1}{2} \times \frac{5}{8}$	45 000
$\frac{5}{8}$	85 000	$\frac{5}{16}$	41 100
$\frac{1}{2}$	68 900	$\frac{1}{2}$	37 000
		$\frac{3}{8}$	28 500
$5 \times 3\frac{1}{2} \times \frac{5}{8}$	82 500	$\frac{1}{4}$	19 500
$\frac{5}{8}$	69 900		
$\frac{1}{2}$	57 000	$3 \times 3 \times \frac{5}{8}$	45 000
		$\frac{1}{2}$	37 000
$5 \times 3 \times \frac{5}{8}$	76 500	$\frac{3}{8}$	28 500
$\frac{5}{8}$	64 900	$\frac{1}{4}$	19 500
$\frac{1}{2}$	53 000		
$\frac{3}{8}$	40 500	$3 \times 2\frac{1}{2} \times \frac{1}{2}$	33 000
		$\frac{3}{8}$	25 400
$4 \times 4 \times \frac{5}{8}$	76 500	$\frac{5}{16}$	21 600
$\frac{5}{8}$	40 500	$\frac{1}{4}$	17 400
$4 \times 3\frac{1}{2} \times \frac{5}{8}$	60 000		
$\frac{5}{8}$	37 600	$3 \times 2 \times \frac{7}{16}^*$	25 900
		$\frac{3}{8}^*$	25 600
$4 \times 3 \times \frac{5}{8}$	55 000	$\frac{5}{16}^*$	21 800
$\frac{1}{2}$	45 000	$\frac{1}{4}^*$	17 600
$\frac{3}{8}$	34 400		
		$2\frac{1}{2} \times 2\frac{1}{2} \times \frac{7}{16}$	25 900
$3\frac{1}{2} \times 3\frac{1}{2} \times \frac{5}{8}$	64 500	$\frac{3}{8}$	22 400
$\frac{5}{8}$	54 900	$\frac{5}{16}$	19 200
$\frac{1}{2}$	45 000	$\frac{1}{4}$	15 500
$\frac{3}{8}$	34 400		
		$2\frac{1}{2} \times 2 \times \frac{7}{16}$	22 400
$3\frac{1}{2} \times 3 \times \frac{5}{8}$	50 100	$\frac{3}{8}$	19 500
$\frac{1}{2}$	41 000	$\frac{5}{16}$	16 600
$\frac{3}{8}$	31 500	$\frac{1}{4}$	13 400

\*These are special angles. It is better not to use them in ordinary work because of delay in delivery.

The End-Connections often determine the strength of ANGLE TENSION-MEMBERS. Some specifications for structural work require angles subject to net tension to be connected by both legs if the section of both legs is connected; and if connected by one leg, the section of one leg only is considered effective. Reliable tests (page 385) show this requirement to be needlessly true. For single angles connected by one leg, the Specifications for the Structural Steelwork of Buildings, Chapter XXX, allow the net area of the connected leg and one-half that of the outstanding leg to be considered effective. (Waterbury, Stresses in Structural Steel Angles, John Wiley & Sons, Inc., New York, 1917.)

Table XI. Sectional Area to be Deducted from Plates and Angles for One Round Hole

NOTE. Bolt-holes should be  $\frac{1}{16}$  in larger than the diameter of the bolt; rivet-holes are usually  $\frac{1}{8}$  in larger than the diameter of the rivet.\*

Thickness of plate	Diameter of hole in fractions of an inch and inches															
	$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	1	$\frac{1}{8}$	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	1	$1\frac{1}{8}$	$1\frac{1}{4}$	$1\frac{3}{8}$
$\frac{1}{16}$	0.05	0.06	0.07	0	09	0.11	13	0.14	0			18	0.19	0.20	0.23	0.27
$\frac{1}{8}$	0.06	0.08	0.09	0	13	0.14	17	0.19	0			23	0.25	0.27	0.30	0.36
$\frac{3}{16}$	0.08	0.10	0.12	0	16	0.18	21	0.23	0			29	0.31	0.33	0.37	0.45
$\frac{1}{4}$	0.09	0.12	0.14	0	19	0.21	26	0.28	0			35	0.38	0.40	0.45	0.54
$\frac{5}{16}$	0.11	0.14	0.16	0	22	0.25	30	0.33	0			41	0.44	0.46	0.52	0.63
$\frac{3}{8}$	0.13	0.16	0.19	0	25	0.28	34	0.38	0.41	0.44	0.47	0.50	0.53	0.59	0.72	0
$\frac{7}{16}$	0.14	0.18	0.21	0	28	0.32	39	0.42	0.46	0.49	0.53	0.56	0.60	0.67	0.81	0
$\frac{1}{2}$	0.16	0.20	0.23	0	31	0.35	43	0.47	0.51	0.55	0.59	0.63	0.66	0.74	0.90	0
$\frac{9}{16}$	0.17	0.21	0.26	0	34	0.39	47	0.52	0.56	0.60	0.64	0.69	0.73	0.82	0.99	1
$\frac{5}{8}$	0.19	0.23	0.28	0	38	0.42	52	0.56	0.61	0.66	0.70	0.75	0.80	0.89	1.08	1
$1\frac{1}{16}$	0.20	0.25	0.30	0	41	0.46	56	0.61	0.66	0.71	0.76	0.81	0.86	0.97	1.17	1
$\frac{3}{4}$	0.22	0.27	0.33	0	44	0.49	60	0.66	0.71	0.77	0.82	0.87	0.93	1.04	1.26	1
$1\frac{1}{8}$	0.23	0.29	0.35	0	47	0.53	64	0.70	0.76	0.82	0.88	0.94	1.00	1.11	1.35	1
1	0.25	0.31	0.38	0	50	0.56	69	0.75	0.81	0.88	0.94	1.00	1.06	1.19	1.44	1

\* See also Table I, Chapter XX and paragraph, Punching Rivet-Holes, page 414.

## 7. Wire

**Manufacture.** Iron and steel wires are made from BILLETS about 4 in. square. These are rolled into long rods which are dipped in acid to remove the scale and furnish lubrication for the drawing process. This consists in pulling rods while cold through steel dies having a series of holes of gradually decreasing diameters. The cold working of the metal hardens it and makes it brittle so that it is necessary to anneal it at intervals during the process. The drawing increases the strength of the material, so that wires of different sizes, although made of the same material, differ greatly in ULTIMATE STRENGTH.

**Finish.** The common grades of iron and steel wire are furnished in several different finishes: plain black, bright tinned, copper-coated, japanned and with single and double coats of zinc galvanizing. The last is applied by passing wire through the melted zinc which is deposited as a coating and forms one of the best-known protections against corrosion.

**Wire-Gauges.** Table XIII gives, according to several GAUGES, the diameters of the different numbers of wire that have come into use for different purposes and have been brought out by different manufacturers. In ordering wire by number it is best to specify which GAUGE is meant.

**Strength.** Table XIV gives the sizes according to the J. A. Roebling's Standard Gauge, with the weight and length and the strength on an assumed basis of 100 000 lb per sq in. The different kinds of wire vary so widely in ULTIMATE STRENGTH, on account of both the difference in quality of the material and the effect of the drawing, that in order to obtain the approximate strength of

reference must be made to Table XII in connection with the foot-note to Table XIV. The following table is arranged from values which were published in the Catalogue of the J. A. Roebling's Sons Company:

**Table XII. Approximate Ultimate Strength of Different Sizes of Iron and Steel Wire**

Kind of wire	Ultimate strength	
	Large size lb per sq in	Small size lb per sq in
Soft iron.....	45 000	60 000
Telegraph and telephone (steel).....	60 000	80 000
Special aviator.....	247 000	285 000
Piano wire.....	307 000	340 000
High steel wire.....	200 000	345 000
Hard-drawn copper trolley wire.....	50 000	not used
Hard-drawn telegraph and telephone copper.....	56 000	66 000

The Uses of Wire are so many and varied that a bulky treatise would be required to adequately cover the subject. The catalogues of the American Steel and Wire Company mention electrical wires and cables of many kinds, telephone and telegraph wires, ignition-wires and cables for automobiles, motor-boats and aeroplanes, wire rope, wire tacks, wire fences, piano-wire, barbed wire, flat wire and so on, through a long list. The magnitude of the wire-output of the United States is seen from the fact that of the total production of 32 000 000 tons of all kinds of finished rolled iron and steel for the year 1916, 3 500 000 tons were wire rods. For electrical purposes copper wire is mostly used. See *Our Work for Buildings*, Part III, for information regarding wires and wire-connections.

The Brown & Sharpe Gauge is followed in the United States as the standard for copper wire, though there is a growing tendency to distinguish between electrical wires by their diameters, expressed in mils. (One mil =  $\frac{1}{1000}$  in. A circular mil is the area of a circle 0.001 in in diameter.)

The American Steel and Wire Company's Gauge is almost universally followed throughout the United States for steel wire. The Birmingham gauge, or English gauge, is the only wire-gauge recognized in successive Acts of Congress establishing tariffs, and for many years has been used as the basis of duties assessed on imported wire. Aside from these purposes its use is not extensive. The American Steel and Wire Company's Music-Wire-Gauge, known as the Music-Wire-Gauge, upon recommendation of the United States Bureau of Standards, has been adopted as the standard for piano-wire.

\* See, also, pages 402, 403, 1469, 1473, 1509, 1510, 1512, and 1600.

Table XIII. Comparison of Standard Gauges for Wire and Sheet Metal

Number of gauge	Diameter or thickness in decimals of an inch						
	Birmingham or Stubs iron-wire-gauge	American or Brown & Sharpe wire-gauge	United States standard gauge for sheet and plate iron and steel	Washburn & Moen, Roebling, American Steel & Wire Co., steel-wire-gauge	Stubs steel-wire-gauge	American Screw Co. wire-gauge	British or English standard wire-gauge
∞	.....	.....	0.5	0.4900	.....	.....	0.5
∞	.....	0.580000	0.46875	0.4615	.....	.....	0.4
∞	0.500	0.516500	0.4375	0.4305	.....	.....	0.4
∞	0.454	0.460000	0.40625	0.3938	.....	.....	0.4
∞	0.425	0.409642	0.375	0.3625	.....	0.0315	0.3
∞	0.380	0.364796	0.34375	0.3310	.....	0.0447	0.3
∞	0.340	0.324861	0.3125	0.3065	.....	0.0578	0.3
1	0.300	0.289297	0.28125	0.2830	0.227	0.0710	0.3
2	0.284	0.257627	0.265625	0.2625	0.219	0.0842	0.3
3	0.259	0.229423	0.25	0.2437	0.212	0.0973	0.3
4	0.238	0.204307	0.234375	0.2253	0.207	0.1105	0.3
5	0.220	0.181940	0.21875	0.2070	0.204	0.1236	0.3
6	0.203	0.162023	0.203125	0.1920	0.201	0.1368	0.3
7	0.180	0.144285	0.1875	0.1770	0.199	0.1500	0.3
8	0.165	0.128490	0.171875	0.1620	0.197	0.1632	0.3
9	0.148	0.114423	0.15625	0.1443	0.194	0.1763	0.3
10	0.134	0.101897	0.140625	0.1350	0.191	0.1894	0.3
11	0.120	0.090742	0.125	0.1205	0.188	0.2026	0.3
12	0.109	0.080808	0.109375	0.1055	0.185	0.2158	0.3
13	0.095	0.071962	0.09375	0.0915	0.182	0.2289	0.3
14	0.083	0.064084	0.078125	0.0800	0.180	0.2421	0.3
15	0.072	0.057068	0.0703125	0.0720	0.178	0.2552	0.3
16	0.065	0.050821	0.0625	0.0625	0.175	0.2684	0.3
17	0.058	0.045257	0.05625	0.0540	0.172	0.2826	0.3
18	0.049	0.040303	0.05	0.0475	0.168	0.2947	0.3
19	0.042	0.035890	0.04375	0.0410	0.164	0.3079	0.3
20	0.035	0.031961	0.0375	0.0348	0.161	0.3210	0.3
21	0.032	0.028462	0.034375	0.0317	0.157	0.3342	0.3
22	0.028	0.025346	0.03125	0.0286	0.155	0.3474	0.3
23	0.025	0.022572	0.028125	0.0258	0.153	0.3605	0.3
24	0.022	0.020101	0.025	0.0230	0.151	0.3737	0.3
25	0.020	0.017900	0.021875	0.0204	0.148	0.3868	0.3
26	0.018	0.015941	0.01875	0.0181	0.146	0.4000	0.3
27	0.016	0.014195	0.0171875	0.0173	0.143	0.4132	0.3
28	0.014	0.012641	0.015625	0.0162	0.139	0.4263	0.3
29	0.013	0.011257	0.0140625	0.0150	0.134	0.4395	0.3
30	0.012	0.010025	0.0125	0.0140	0.127	0.4526	0.3
31	0.010	0.008928	0.0109375	0.0132	0.120	0.4658	0.3
32	0.009	0.007950	0.01015625	0.0128	0.115	0.4790	0.3
33	0.008	0.007080	0.009375	0.0118	0.112	0.4921	0.3
34	0.007	0.006305	0.00859375	0.0104	0.110	0.5053	0.3
35	0.005	0.005615	0.0078125	0.0095	0.108	0.5184	0.3
36	0.004	0.005000	0.00703125	0.0090	0.106	0.5316	0.3
37	.....	0.004453	0.006640625	0.0085	0.103	0.5448	0.3
38	.....	0.003965	0.00625	0.0080	0.101	0.5579	0.3
39	.....	0.003531	.....	0.0075	0.099	0.5711	0.3
40	.....	0.003144	.....	0.0070	0.097	0.5842	0.3

The United States Standard Gauge was legalized by Act of Congress, March 3, 1875, as a standard gauge for sheet and plate iron and steel, and is used by the Custom Department and by sheet-plate and tin-plate manufacturers.

\* See also, pages 401, 403, 1469, 1473, 1509, 1510, 1512, and 1600.

Table XIV. Weight, Length and Strength of Steel Wire \*

Gauge of J. A. Roebling's Sons Company †

Number of gauge	Diameter in	Area sq in	Breaking-load in pounds at rate of 100 000 lb per sq in	Weight in pounds		Number of feet in 2 000 pounds
				Per 1 000 ft	Per mile	
000000	0.460	0.166191	16 619	558.4	2 948	3 582
00000	0.430	0.145221	14 522	487.9	2 576	4 099
0000	0.394	0.121304	12 130	407.6	2 152	4 907
000	0.362	0.102922	10 292	345.8	1 826	5 783
00	0.331	0.086049	8 605	289.1	1 527	6 917
0	0.307	0.074023	7 402	248.7	1 313	8 041
1	0.283	0.062902	6 290	211.4	1 116	9 463
2	0.263	0.054325	5 433	182.5	964	10 957
3	0.244	0.046760	4 676	157.1	830	12 730
4	0.225	0.039761	3 976	133.6	703	14 970
5	0.207	0.033654	3 365	113.1	597	17 687
6	0.192	0.028953	2 895	97.3	514	20 559
7	0.177	0.024606	2 461	82.7	437	24 191
8	0.162	0.020612	2 061	69.3	366	28 878
9	0.148	0.017203	1 720	57.8	305	34 600
10	0.135	0.014314	1 431	48.1	254	41 584
11	0.120	0.011310	1 131	38.0	201	52 631
12	0.105	0.008659	866	29.1	154	68 752
13	0.092	0.006648	665	22.3	118	89 525
14	0.080	0.005027	503	16.9	89.2	118 413
15	0.072	0.004071	407	13.7	72.2	146 198
16	0.063	0.003117	312	10.5	55.3	191 022
17	0.054	0.002290	229	7.70	40.6	259 909
18	0.047	0.001735	174	5.83	30.8	343 112
19	0.041	0.001320	132	4.44	23.4	450 856
20	0.035	0.000962	96	3.23	17.1	618 620

This table was calculated on a basis of 483.84 lb per cu ft for steel wire. Iron wire is lighter.

The breaking strengths were calculated for 100 000 lb per sq in throughout, simply for convenience, so that the breaking strengths per square inch of wires of any strength may be quickly determined by multiplying the values given in the table by the ratio of the strength per square inch and 100 000. Thus, a No. 15 wire, with a strength per square inch of 150 000 pounds, has a breaking strength of

$$407 \times \frac{150\,000}{100\,000} = 610.5 \text{ lb.}$$

It must not be inferred from this table that steel wire invariably has a strength of 100 000 lb per sq in. As a matter of fact its strength ranges from 45 000 lb per sq in for annealed wire to over 400 000 lb per sq in for hard wire.

\* See, also, pages 401, 402, 1469, 1473, 1509, 1510, 1512, and 1600

† Also American Steel & Wire Company, etc.

### 8. Wire Rope

**Kinds of Wire Rope.** There are several kinds of WIRE ROPE in common use. In each there are three or more qualities depending on the kind of use and the kind of core about which the strands are laid. The Trenton Company lists the following:

(1) **Haulage or Transmission-Rope**, composed of six strands of seven wires each, laid about a hemp core. It is used for haulage, transmission of power in places where surface-wear is of chief consideration and where sheaves of sufficient diameter may be used.

(2) **Hoisting-Rope**, composed of six strands of nineteen wires each. It is used for elevator service, shafts and derricks, and in places where it is not subject to abrasion and where flexibility is of chief consideration.

(3) **Seale Rope**, composed of six strands of nineteen wires each, the inner coils of the strands being of finer wire. It is intermediate in flexibility between the first and second kinds of rope.

(4) **Non-Spinning Hoisting-Rope**, having eighteen strands of seven wires each. Twelve of the strands are laid in reverse direction to the inner six, making it well adapted for hoisting in free suspension without untwisting and turning the load.

(5) **Extra-Flexible Hoisting-Rope**, having eight strands of nineteen wires each.

(6) **Special Flexible Hoisting-Rope**, having six strands of thirty-seven wires each.

(7) **Hawser-Rope and Flexible Running-Rope**, having six strands of twenty galvanised wires each, laid about a hemp core.

(8) **Tiller-Rope**, composed of six small seven-strand ropes laid about a hemp core. It is the most flexible of wire ropes and is used to operate tillers and hand-ropes in elevators.

**The Lay of Wire Rope** is the twist of the wires in the strands relative to the strands in the rope. In the **ORDINARY LAY** the twist of the strands is the reverse of that of the wires, while in the **LANG LAY** the strands are laid in the same direction as the twist of the wires. This latter gives a greater distribution of the wearing-surface and a somewhat greater flexibility; but it has the disadvantage of a tendency to untwist and for this reason should not be used for hoisting weights in free suspension. Wire rope is also made up in **FLAT** or **BON FORM**. For large sizes it is more flexible than standard rope and may be run over smaller drums.

**Materials for Rope.** Nearly all of the above kinds of rope are made from the following materials:

(1) **Best Grade of Wrought Iron.** This is used in high-speed **PASSENGER ELEVATOR SERVICE** as it seems to suffer less from the effects of the stresses to the starting and stopping of the cars.

(2) **Cast-Steel Wire**, with an ultimate strength of from 160 000 to 210 000 lb per sq in, according to the size used.

(3) **Extra-Strong Cast-Steel Wire**, with an ultimate strength of from 190 000 to 230 000 lb per sq in.

(4) **Plow-Steel Wire** with an ultimate strength of from 200 000 to 230 000 lb per sq in.

Ordinary **GALVANIZED-WIRE ROPE** should not be used for other than stationary rope. A short service running through sheaves will break the coating and

**Table XV. Strength of Wire Rope**  
 Arranged from the 1912 list of John A. Roebling's Sons Company

Trade number	Diameter inches	Weight per foot, hemp core	Approximate breaking-load in pounds		Minimum diameter of drum or sheave in feet	
			Iron	Cast steel	Iron	Cast steel
HOISTING-ROPE						
Six strands of nineteen wires each, about a hemp core						
1	2¼	8.00	144 000	266 000	14	9
2	2	6.30	110 000	212 000	12	8
2½	1¾	5.55	100 000	192 000	12	8
3	1¾	4.85	88 000	170 000	11	7
4	1½	4.15	76 000	144 000	10	6.5
5	1½	3.55	66 000	128 000	9	6
5½	1¾	3	56 000	112 000	8.5	5.5
6	1¾	2.45	45 600	94 000	7.5	5
7	1½	2	37 200	76 000	7	4.5
8	1	1.58	29 000	60 000	6	4
9	¾	1.20	23 600	46 000	5.5	3.5
10	¾	0.89	17 000	35 000	4.5	3
10½	¾	0.62	12 000	25 000	4	2.5
10½	¾	0.50	9 400	20 000	3.5	2.25
10¾	½	0.39	7 800	16 800	3	2
10a	¾	0.30	5 800	13 000	2.75	1.75
10b	¾	0.22	4 800	9 600	2.25	1.5

#### STANDING ROPE

Six strands of seven wires each

11	1½	3.55	64 000	126 000	16	11
12	1¾	3	56 000	106 000	15	10
13	1¾	2.45	46 000	92 000	13	9
14	1½	2	38 000	74 000	12	8
15	1	1.58	30 000	62 000	10.5	7
16	¾	1.20	24 000	48 000	9	6
17	¾	0.89	17 600	37 200	7.5	5
18	1¼	0.75	14 600	30 800	7.25	4.75
19	¾	0.62	12 000	26 000	7	4.50
20	¾	0.50	9 600	20 000	6	4
21	½	0.39	7 400	15 400	5.5	3.5
22	¾	0.30	5 200	11 000	4.5	3
23	¾	0.22	4 400	9 200	4	2.75
24	¾	0.15	3 400	7 000	3.5	2.25
25	¾	0.125	2 400	5 000	3	1.75

The working load is to be taken at one-fifth the breaking-load. This is assumed in selecting the diameter of the sheaves.

rapid corrosion of the rope. Because of the many kinds and qualities of it is well to consult the manufacturers as to which kind will best suit the conditions for any particular service. The John A. Roebling's Sons Company, Trenton, N. J., the Trenton Iron Company, Trenton, N. J., and A. Leschen & Son Rope Company, St. Louis, Mo., are among the largest manufacturers of lines of ropes.

**Coils.** Wire rope should not be coiled like hemp rope, and in order to avoid kinking, should be taken from the reels without twisting. If it is not shipped on a reel, to avoid injury it must be rolled over the ground like a wheel.

**Lubrication.** It is very important that running ropes be properly lubricated, since, if proper care is not taken, the wear on the interior parts, between the wires, may be almost as great as the outside abrasion. The oil should penetrate to the core of the rope and yet not drip off a few days after application. Information as to the care of rope may be obtained of the Wire Rope Lubricating Company, Newark, N. J.

**Sheaves.** The size of sheaves recommended in the tables are calculated for a working-load of one-fifth the given breaking-load. If smaller sheaves are used, the life of the rope will be greatly shortened, because of the excessive bending of the outer wires.

**Table XVI. Galvanized, Steel-Wire Strands**  
For guys, signal-cords, trolley-line span wire, etc. Taken from the American Steel & Iron Company's list

Diameter in inches	List price per 100 feet *	Weight per 100 feet	Approximate breaking-load in pounds
$\frac{5}{8}$	\$7.25	80	14 000
$\frac{9}{16}$	5.75	63	11 000
$\frac{1}{2}$	4.50	52	8 500
$\frac{7}{16}$	3.75	41	6 500
$\frac{3}{8}$	2.75	30	5 000
$\frac{5}{16}$	2.25	22	3 800
$\frac{1}{4}$	1.75	13	2 300
$\frac{7}{32}$	1.50	$9\frac{1}{2}$	1 800
$\frac{3}{16}$	1.25	$7\frac{1}{2}$	1 400
$\frac{5}{32}$	1.15	$5\frac{1}{2}$	900
$\frac{1}{8}$	1.00	$3\frac{1}{4}$	600
$\frac{3}{32}$	.80	2	400

### 9. Cotton, Hemp and Manila Rope

Rope is made of cotton, hemp, and Manila fiber. Cotton is used for small sizes, only, and for such purposes as sash-cord, etc.

**Manufacture.** In the manufacture of rope the fiber is first spun into threads. From twenty to eighty threads are twisted together into STRANDS and three or four strands, three or four, are laid together, opposite in direction to the twist of the strands, but in the same direction as the THREADS. This causes the rope to be twisted as the rope untwists and produces a balancing of forces that tends to keep the rope in shape.

**Cables and Hawsers** are made up of strands of rope.

\* These pre-war prices must be increased as per current price-lists.



rope used for Hoisting wears rapidly from the action of the pulleys and from the bending which causes a slight internal motion between the fibers causing and grinding away of the interior.

**Livore-Rope**, of the C. W. Hunt Company, is filled with a tallow and slag lubricant which decreases the internal friction, lubricates the outside of the rope and thus greatly prolongs its life.

**Strength.** The values of the strength of new rope, given in Table XVII, are from the Specifications of the United States Navy Department, issued June, 1910, at the Boston Navy-Yard. Manufacturers generally adopt these standard weights and claim a strength equal to or a little greater than the values given. The UNIT STRENGTH for the different sizes varies, being about 14 000 lb per sq in for the smaller and about 10 000 for the largest size. The approximate formula, offered by C. W. Hunt, of 720 times the square of the circumference in inches, is equivalent to about 9 000 lb per sq in. American hemp rope has about 5% greater strength than Manila rope of the same size. The specifications give for two-strand American-hemp rope, 85% of the strength of the three-strand rope of the same material.

**Table XVII. Strength and Weight of Rope**  
Specifications of the United States Navy, June, 1910

Circumferences in	Diameters in	Manila hemp, plain-laid		American hemp, tarred, plain-laid, three strands	
		Weights lb per ft	Breaking-loads lb	Weights lb per ft	Breaking-loads lb
$\frac{1}{8}$	0.24	0.02	700	0.051	750
1	0.32	0.033	1 000	0.06	1 060
$1\frac{1}{4}$	0.40	0.05	1 800	0.067	1 670
$1\frac{1}{2}$	0.48	0.083	2 500	0.083	2 340
$1\frac{3}{4}$	0.56	0.10	3 000	0.103	3 325
2	0.64	0.14	4 000	0.16	3 955
$2\frac{1}{4}$	0.72	0.17	5 000	0.21	4 720
$2\frac{1}{2}$	0.80	0.21	5 500	0.26	5 770
$2\frac{3}{4}$	0.87	0.26	6 600	0.32	7 000
3	0.95	0.305	7 800	0.37	8 400
$3\frac{1}{4}$	1.03	0.36	9 200	0.44	9 800
$3\frac{1}{2}$	1.16	0.42	10 500	0.51	11 200
$3\frac{3}{4}$	1.19	0.47	12 200	0.59	13 000
4	1.27	0.54	13 700	0.67	14 550
$4\frac{1}{2}$	1.43	0.67	17 400	....	.....
5	1.59	0.83	21 800	....	.....
$5\frac{1}{2}$	1.75	1.00	27 700	....	.....
6	1.90	1.21	31 000	....	.....
7	2.22	1.63	36 200	....	.....
8	2.54	2.17	47 300	....	.....
9	2.87	2.70	60 000	....	.....
10	3.14	3.33	74 200	....	.....

Manila-hemp rope is made in three strands and in sizes up to 3 in in circumference. Four strands are used for sizes larger than 3 in in circumference.

**Working Load.** The WORKING LOAD for slow-speed derrick and hoist service is usually taken at one-seventh the BREAKING-LOAD. This makes allowance for the loss of strength at splices and connections. The deterioration of rope exposed to the weather is very rapid. For Manila rope from 1 to 12 in diameter, running over sheaves of the diameters given, C. W. Hunt in Trans. Am. Soc. M. E., Vol. XXIII, gives a table embodying approximately the following results of experience:

**Table XVIII. Working Loads for Manila Rope**

Working load =  $C \times$  breaking-load of new rope

$D$  = minimum diameter of sheave in inches

Speed	Feet per minute	Kind of work	Value of $C$	$D$ for rope diameter	
				1 in	1 ft
Slow.....	50 to 100	Derrick, crane, quarry, etc.	0.014	8	
Medium...	150 to 300	Wharf, cargo, etc.	0.056	12	
Rapid.....	400 to 800	.....	0.028	40	

The wear in such service is very rapid, a 1½-in rope wearing out in lifting 7 000 to 10 000 tons of coal. On the other hand, a 1½-in transmission rope running at 5 000 ft per min and carrying 1 000 horse-power over sheaves 17 ft in diameter, lasts for years, the difference being due to the stress and larger sheaves.

## 10. Chains

**Manufacture.** Large chains are made by hand-welding from best wrought iron bar, and small chains up to ½ in are best made of mild open-hearth steel, electric-welded. The bending and welding reduce the strength so that the chain is not twice but only from 1.55 to 1.70 times as strong as the original bar from which it was made. STUD CHAIN having a bar welded across each link to stiffen it and prevent fouling in handling, is not as strong as OPEN CHAIN, but has a higher elastic limit and working strength. G. A. Goode in a Bulletin from the Illinois Engineering Experiment-Station, finds the minimum stresses at the elastic limit of the material to be as follows: If  $P$  the load,  $d$  the diameter of the bar, and  $S$  the stress, the formulas are:

$$P = 0.5 d^2 S \text{ for stud-link, and}$$

$$P = 0.4 d^2 S \text{ for open link.}$$

**Proof-Tests.** A proof-test is applied to chains by the manufacturers. The load applied is one-half the average BREAKING-LOAD. It serves to detect defective welds and gives a chain a slight permanent set, so that for working loads after there will be little stretching of the chain.

**Care of Chains.** Chains in constant use require lubrication and frequent annealing. They harden in service and are liable to unexpected failure if not annealed. It is recommended that hoisting chains and sling chains be annealed at least once a year.

**Table XIX. Sizes, Weights, Proof-Tests and Average Breaking-Loads for Chains**  
Bradlee and Company, Philadelphia

Size of chains in	Approximate weight per foot	D.B.G. special crane		Crane	
		Proof-test lb	Average breaking-load lb	Proof-test lb	Average breaking-load lb
$\frac{1}{4}$	$\frac{3}{4}$	1 932	3 864	1 680	3 360
$\frac{5}{16}$	$1\frac{1}{2}$	4 186	8 372	3 640	7 280
$\frac{1}{2}$	2.5	7 728	15 456	6 720	13 440
$\frac{5}{8}$	4.1	11 914	23 828	10 360	20 720
$\frac{3}{4}$	6.2	17 388	34 776	15 120	30 240
$\frac{7}{8}$	8.4	22 484	44 968	20 440	40 880
1	10.5	29 568	59 136	26 880	53 760
$1\frac{1}{8}$	13.6	37 576	75 152	34 160	68 320
$1\frac{1}{4}$	16	46 200	92 400	42 000	84 000
$1\frac{3}{8}$	19.2	55 748	111 496	50 680	101 360
$1\frac{1}{2}$	23	66 528	133 056	60 480	120 960
$1\frac{5}{8}$	28	74 382	148 764		
$1\frac{3}{4}$	31	82 320	164 640		
$1\frac{7}{8}$	35	94 360	188 720		
2	40	107 520	215 040		
$2\frac{1}{8}$	46.5	121 240	242 480		

The specifications of the United States Navy Department require the same proof-test as given above for crane-chain and a breaking-strength 10% greater than that given for special crane-chain.

**Table XX. Proof-Tests and Average Breaking-Loads for Studded Chain-Cables**  
Specifications of the United States Navy Department

Size of cable in	Proof-test lb	Average breaking-load lb	Size of cable in	Proof-test lb	Average breaking-load lb
1	34 607	67 526	$1\frac{15}{16}$	130 202	225 687
$1\frac{1}{8}$	43 812	82 686	2	138 739	239 732
$1\frac{1}{4}$	54 194	100 630	$2\frac{1}{16}$	147 544	254 223
$1\frac{1}{2}$	59 784	109 771	$2\frac{1}{8}$	156 622	269 160
$1\frac{3}{8}$	65 574	119 355	$2\frac{1}{4}$	175 591	300 373
$1\frac{7}{16}$	71 672	129 385	$2\frac{1}{2}$	216 779	368 153
$1\frac{1}{2}$	78 041	139 861	$2\frac{5}{8}$	238 995	404 719
$1\frac{1}{2}$	84 678	150 783	$2\frac{3}{4}$	262 302	443 069
$1\frac{3}{4}$	91 588	162 152	$2\frac{7}{8}$	286 692	483 203
$1\frac{7}{8}$	106 222	186 228	3	312 165	525 121
$1\frac{3}{4}$	121 937	212 188	$3\frac{1}{8}$	339 102	567 823

**Factors of Safety.** For dead loads the **FACTOR OF SAFETY** may be as low as four provided the breaking of the chain would not imperil life. This factor is generally quoted in catalogues, but is too low for most purposes. **MAXIMUM FIBER-STRESS** is then well above the **ELASTIC LIMIT** of chain. Where loads are to be raised repeatedly with machinery which can be operated without jerks or sudden change of speed, the use of a factor of six is in practice. If a chain must be used where shocks occur, the **INSTANTANEOUS LOAD** should be calculated, and a high factor of safety employed.

**Grades of Chain.** Chains up to 1 1/4 in are usually made in three grades called **PROOF**, **BB**, and **BBB**. The **proof** is the cheapest grade, and is made of longer links than the others. This is not ordinarily proof-tested. **BB** is the next grade, somewhat shorter linked, and is proof-tested. **BBB** is of shorter link and more carefully made.

**Crane Chain** is finished in such a way as to be without twist when hauled with one end free, so that hooks and fittings are always facing their proper direction.

**Dredge Chain** is straightened as is **Crane Chain**, and made with uniform links to run over a wheel.

**Steel Loading Chain** is made mostly in small sizes for use where the weight compared to the strength is to be a maximum. It is the highest grade of hand-made chain.

**Block Chain** is fitted to the pocket-wheel in which it is to run. In small sizes it is usually electric-welded.

**Electric-Welded Chain** is made in small sizes and is rapidly replacing hand-made below 1/2 in. It is stronger and more uniform.

**Sizes of Chain.** Chain is ordinarily made of wire or rod, 1/32 in larger than the **NOMINAL DIAMETER**, by which it is called. If chain is desired made of the size by which it is called, it must be specified as **EXACT SIZE**. **Steel I Chain**, **Block Chain**, and frequently **Dredge Chain**, are made **EXACT**. **Link Anchor Chain** is made of wire, 3/64 in above its **NOMINAL DIAMETER**.

## CHAPTER XII

### RESISTANCE TO SHEAR. RIVETED JOINTS, PINS AND BOLTS

By

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

#### 1. Shear

Shear is the internal stress in a body which resists the tendency of two adjacent parts to slide on each other, due to the action of two equal and parallel forces, called SHEARING-FORCES, acting on opposite sides of the plane of shear.

If the piece *abcd* of Fig. 1 represents a short simple beam of this material on which a sufficient load is applied, it will fail in **VERTICAL SHEAR** at *f* and *g*, as shown, by a sliding on the sections of the beam at these points, because the upward force of the pin at *S* and the downward force of the load adjacent to *S*, which it acts across the

Fig. 1. Shearing-failure of Beam




Fig. 2. Example of Single Shear

pin at *S*, is greater than the total SHEARING RESISTANCE of the section. This is present over the entire length of the beam, and at any section is equal to the reaction at *S* minus the weight of the load between the reaction and the section in question. In general, the **VERTICAL SHEAR** at any section of a beam loaded to vertical loads is equal to the algebraic sum of all the vertical forces acting on the beam on either side of the section.

**Single and Double Shear.** A rivet connecting two bars under tension (Fig. 2) is subjected to a SHEARING-STRESS. If one section of

a rivet transmits the force the rivet is said to be in **SINGLE SHEAR**; if two rivets, it is in **DOUBLE SHEAR**.

**Distribution of Shear.** Shear is considered to be **UNIFORMLY DISTRIBUTED** over the section except in cases of torsion and of complex stresses, but in the ordinary cases of shear in rivets, etc., if

$S_s$  = the allowable unit stress in shear,

$A$  = the area under stress,

$P$  = the safe shearing-load;

$$P = AS_s \quad (1)$$

The **Ultimate Strength in Shear** has been determined for building materials by testing suitably prepared specimens and dividing the maximum load ob-

served by the area under stress. For material like wood, in which there are planes of weakness, tests must be made which take these into account. The direction of the force with respect to these planes must be considered in choosing the SAFE WORKING STRESS from the tables.

**Safe Working Stresses in Shear.** Table I gives SAFE WORKING STRESSES in SHEAR for those building materials usually subjected to such stresses.

Table I. Safe Working Stress in Shear for Building Materials \*

Material	Safe stress in lb per sq in	
Cast iron (New York).....	3 000	
Wrought iron.....	7 500	
Steel, bolts, rivets.....	10 000 (average)	
	With the grain	Across the grain
White oak.....	200	1 000
White pine.....	100	500
Long-leaf yellow pine.....	150	1 250
Short-leaf yellow pine.....	130	1 000
Douglas fir.....	100	900
Hemlock.....	100	600
Spruce.....	100	750

\* Note. For woods, these values may be increased up to 30% for selected, perfectly protected, commercially dry timber, not subject to impact, that is, for ideal conditions. (See, also, pages 637 and 647.)

**Shear in Wooden Tie-Beams.** There are a few cases in architectural construction in which the weakness of wood in shear must be provided for.




Fig. 3. Shearing-failure in Wood

one most frequently arising in the framing of the end of the tie-beams in wooden trusses.

Fig. 3 was made from a photograph of a SHEARING FAILURE of a tie-beam from the thrust of the rafter.

**Horizontal Shear in Wooden Beams.** Failure of horizontal shear is that shown in Fig. 1. It occurs in wood; but rectangular wooden beams, the length of which is less than about twenty times the depth, are liable to fail in HORIZONTAL SHEAR along the middle, under about the same loads that would give the allowable working stresses in bending.

**Shear at the End of a Tie-Beam.** In the case of the truss-joint (Fig. 3) the thrust  $S$  of the rafter tends to shear off the part  $ABCD$  along the plane  $CD$  which is the trace. This area under stress must offer a SHEARING RESISTANCE equal to the horizontal component  $H$  of the thrust  $S$ . The width of the beam  $b$ , being fixed, formula (1) gives

$$H = (CD \times b) S_s \quad \text{or} \quad CD = H / b S_s$$

The shear being in the same direction as the grain of the wood, the lower value in Table I must be used.

**Example 1 (Fig. 4).** The horizontal component of the thrust of a rafter is 2000 lb. The long-leaf yellow pine tie-beam is 10 in wide. How far should the beam extend beyond the point *D*?

**Solution.** In this case  $H = 20\,000$  lb. From Table I,  $S_s = 150$  lb per

sq. in. Then  $CD = \frac{20\,000}{10 \times 150} = 13.3$

in. and should be made at least 14 in.

As actually constructed a large part of the thrust is generally taken up by a bolt or strap at the foot of the rafter to hold it in place. As

the bolt and shoulder seldom act together, either the length  $CD$  on the tie-beam should be made long enough to resist the entire thrust, or the bolt or strap should be designed to do so without relying on the shearing resistance in the plane of  $CD$ . The design of such joints is more fully considered under Subdivision 4, pages 439 to 439 of this chapter.




Fig. 4. Truss-joint

## 2. Riveted Joints

**Use of Rivets.** Rivets almost exclusively are used in connecting the plates and shapes which make up the members of framed steel construction.

**Rivet-Definitions.** A rivet is a piece of cylindrical rod with a HEAD forged at one end and usually with a slight taper at the other end of the SHANK. The GRIIP (Table IV) of the rivet is the length between the under sides of the heads for driving, or the thickness of the parts joined. The LENGTH (Table IV) of a rivet is equal to the grip plus enough of the stock to form a head, and is measured from the end of the shank to the under surface of the head. The DIAMETER OF THE SHANK of a rivet is made equal to its NOMINAL DIAMETER,

but rivets are driven into holes  $\frac{1}{8}$  in larger in diameter and upset by the driving so as to completely fill the holes. The shearing values and bearing values are based upon the NOMINAL AREA and not upon the area of the hole.




Fig. 5. Forms of Rivet-heads

are usually made by use of compressed-air-operated hand-hammers or large riveting-machines which form the head and cause the shank to completely fill the hole by heavy pressure on a die.

**Material of Rivets.** Rivets are made of soft steel and of wrought iron. Soft-steel is generally used. The head may have any of the forms shown in Fig. 5, although the first, called the BUTTON-HEAD, is the standard for structural work. The fourth or COUNTERSUNK HEAD is used where it is necessary to have a smooth surface, as over a bearing-plate.

**Riveting** consists in heating the rivet to a welding-heat, passing it through holes in the parts to be joined and forging another head out of the projecting shank. This may be done by hand-hammering; but

**The Sizes of Rivet-Heads** differ slightly at different mills. The Standards of the American Bridge Company give for the DIAMETER OF THE HEAD, one and one-half times the diameter of the shank plus  $\frac{1}{8}$  in, and for the HEIGHT of head, 0.425 times the diameter of the head. Countersunk heads have a SLOPE of  $30^\circ$  and a DEPTH equal to one-half the diameter of the shank.

**The Pitch of Rivets.** By this is meant the center-to-center distance between them in a line of riveting. The distance between lines of rivets, from the back of an angle or channel to a rivet-line is called the GAUGE-DISTANCE. By STAGGERED PITCH is meant the arrangement of rivets midway between others on successive rivet-lines in order to decrease the section required than when they are arranged in rectangular rows, and at the same time to permit a greater number of rivets in a definite area. The PITCH should not be more than one and one-half times the diameter of the rivet and the DISTANCE FROM THE EDGE OF plate not less than one and one-half diameters, although it may be necessary to make the distance less when small angles are used. The pitch of countersunk rivets must be greater than that of button-head rivets because of the greater amount of material removed.

**Punching Rivet-Holes.** Rivet-holes are made with power-punches. SPACING is marked on the different parts to be fastened together by means of wooden templates with holes drilled to locate the position of the rivets. When the different parts are assembled, the holes are laid out by the same TEMPLATE REGISTER, so that the rivets may be inserted without difficulty. Punching makes a ragged hole. The flow of the metal under the great pressure hardens it and causes a loss in strength of from 11 to 33% as reported by W. C. Unwin for soft steel. The injury may be removed by ANNEALING or by REAMING of the injured part of the metal. Enlarging a  $\frac{1}{8}$ -in. hole by reaming to  $\frac{1}{4}$  in. has been found to remove all the injurious effects of punching. One method practiced in the best work is to punch the holes  $\frac{1}{16}$  in less in diameter than the diameter of the rivets, and to ream them to a diameter  $\frac{1}{16}$  in greater, after the parts are assembled and bolted together. This removes the greater part of the injury from punching and corrects the alinement of the holes. (See Table XI, page 400, and Table I, page 702.)

**Drift-Pins.** When the alinement of a hole is such as to prevent the insertion of the rivet, it is the practice in some shops to drive in a tapered DRIFT-PIN to distort the holes in some of the plates sufficiently to set the rivet. This causes LOCAL STRESSES and injury to the plates and should not be permitted.

**Shop-Riveting** is done with powerful air or hydraulic riveting-machines which may exert a pressure of from 30 to 50 tons, sufficient to upset a pin-head on the projecting end of the shank and to completely fill the hole although the alinement is imperfect. Contraction on cooling causes great pressure between the parts, so that it is probable that in good work the rivet is under little or no shearing-stress, the force being transmitted through the friction and resistance of the plates.

**Clearance.** It is important that the designer place the rivets so they may be inserted from one side and pounded on the other for HAND-WORK, or so that the machine may reach them for MACHINE-RIVETED WORK. For example, the minimum distance from the inside face of the leg of one angle to a line of rivets in the other leg must not be less than  $1\frac{1}{8}$  in for  $\frac{7}{8}$ -in rivets, 1 in for  $\frac{3}{4}$ -in rivets, etc. In general, a distance  $\frac{3}{8}$  in greater than the diameter of the head should be allowed for CLEARANCE.

**Inspection.** The common imperfections in riveting are LOOSE RIVETS and ECCENTRIC HEADS. Loose rivets may be detected by holding the hand against the rivet head.



side of the rivet-head and tapping the other side with a light hammer. When a slight slip may be felt. The loose rivets should be marked to be cut and replaced. The inspector should also carefully check open holes left field-connections, and see that flattened and countersunk rivets are as called for, because such work may be done at less expense in the shop than in the field, where it may cause delay.

**The Failure of Riveted Joints** may occur

- (1) In **TENSION**, by the tearing of the plate through the line of rivets (Fig. 8).
- (2) In **SHEAR**, by the cutting of the rivets (Fig. 7).
- (3) In **BEARING**, by the crushing of the plate in front of the rivets, the splitting of the plate, or, in some cases, by the shearing out of the sections in front of the rivets. In a careful design of a joint the strength against failure by each of these methods must be investigated (Fig. 6 and Fig. 9).




Fig. 6



Fig. 7




Fig. 8




Fig. 9

Figs. 6 to 9. Methods of Failure in Riveted Joints

**The Steps in the Design** of any type of riveted joint are, (1) the selection of the size of the rivet to be used, (2) the determination of its shearing and bearing strength and the use of the smaller value of the two to divide into the total load to be transmitted and thus determine the number of rivets, (3) the arrangement of the rivets in the plate and the investigation of its strength in tension at the dangerous section.

**The Size of Rivets** is determined in part by **SHOP-PRACTICE**. Holes can be punched in plates which are thicker than the diameter of the punch. The following table gives the size of rivets used with plates of different thickness. The specifications for structural work require all rivets to be  $\frac{3}{4}$  in, except the thickest plates require larger ones.

Thickness of plates	Size of rivets
$\frac{1}{4}$ to $\frac{7}{16}$ in	$\frac{5}{8}$ in
$\frac{1}{2}$ to $\frac{5}{8}$ in	$\frac{3}{4}$ in
$1\frac{1}{16}$ to $1\frac{3}{16}$ in	$\frac{7}{8}$ in
$\frac{7}{8}$ to 1 in	1 in

Tables II and III give the **SHEARING** and **BEARING** VALUES for different sizes of rivets in plates of different thickness for two values of working stresses each; one at 7 500 and 10 000 lb per sq in and bearing at 15 000 and 18 000 lb per sq in. Values for higher stresses can be figured by proportion from these tables. Lower stresses should be used with wrought iron or in parts subjected to shocks; the higher stresses where only constant or dead loads are present.

The **SHEARING VALUE** is equal to the area of the rivet multiplied by the working stress; the **BEARING VALUE** is equal to the area of the projected surface under pressure multiplied by the working stress in bearing, or, if

$t$  = the thickness of the plate;

$d$  = the diameter of the rivet;


and

$S_b$  = the working stress in bearing;

then the bearing value  $P = d t S_b$

The **Shearing and Bearing Values** may be taken directly from the table and if a rivet is in double shear, twice the quantity in the table is to be used for its **SHEARING VALUE**. Quantities above the heavy broken lines are **BEARING VALUES** greater than the values in single shear, so that for these conditions, the number of rivets necessary in a joint required to transmit a certain load is determined by dividing the load by the value in single shear. If rivets are in double shear, the number of rivets required is found by dividing the load by the **BEARING VALUE**.

**Rivet-Proportions.\*** The following diagrams show various rivet-proportions including the dimensions of shanks and of finished and countersunk heads:



FINISHED HEADS









Diam head =  $1\frac{1}{2}$  diam of shank +  $\frac{1}{8}$ " depth of head  
=  $\frac{5}{16}$ " diam of head










COUNTERSUNK HEADS

Depth of head =  $\frac{1}{2}$  diam of shank. Bevel of head =  $60^\circ$

\* These proportions vary slightly at different mills and in different handbooks

**Conventional Signs for Riveting.** The following diagrams show some conventional signs for riveting:

	SHOP	FIELD
<b>Two Full Heads</b>		
<b>Countersunk Inside (Farside) and Chipped</b>		
<b>Countersunk Outside (Nearside) and Chipped</b>		
<b>Countersunk both Sides and Chipped</b>		

	INSIDE (FAR SIDE)	OUTSIDE (NEAR SIDE)	BOTH SIDES
<b>Flattened to <math>\frac{1}{8}</math> in high or Countersunk and not Chipped</b>			
<b>Flattened to <math>\frac{1}{4}</math> in high</b>			
<b>Flattened <math>\frac{3}{8}</math> in high</b>			

This system, designed by F. C. Osborn, has for its foundation a diagonal cross for a countersunk, a blackened circle for a field-rivet and a diagonal stroke for a flattened head. The position of the cross with respect to the circle, inside, outside, or on both sides, indicates the location of the countersink; and the number and position of the diagonal strokes indicate the height of the flattened heads. Any combination of field, countersunk or flattened-head rivets liable to be used may be readily indicated by the combination of the above signs.

Table II. Shearing and Bearing Values\* of Rivets  
For Riveted Girders and Wrought Iron

Diameter of rivet in inches		Area of rivet	Single shear at 7 500 lb per sq in	Bearing values for different thicknesses in inches of plate at 15 000 lb per sq in (=diameter of rivet X thickness of plate X 15 000 lb per sq in)									
Fractions	Decimals			1/4	5/16	3/8	7/16	1/2	5/8	3/4	7/8	1 1/8	1 1/4
5/16	0.3125	0.1104	828	1 410	1 640	1 880	2 110	2 340	2 580	2 810	3 050	3 280	3 520
3/8	0.375	0.1503	1 130	1 640	2 050	2 340	2 640	2 930	3 230	3 520	3 810	4 100	4 390
1/2	0.5	0.1963	1 470	1 880	2 340	2 810	3 230	3 650	4 070	4 490	4 910	5 330	5 750
5/8	0.625	0.2485	2 860	2 110	2 640	3 160	3 690	4 220	4 750	5 270	5 800	6 330	6 860
3/4	0.75	0.3068	2 300	2 340	2 930	3 520	4 100	4 630	5 160	5 690	6 220	6 750	7 280
7/8	0.875	0.3712	2 780	2 580	3 230	3 810	4 390	4 920	5 450	5 980	6 510	7 040	7 570
1 1/8	1.125	0.4418	3 310	3 520	3 810	4 100	4 390	4 680	4 970	5 260	5 550	5 840	6 130
1 1/4	1.25	0.5185	3 890	3 810	4 100	4 390	4 680	4 970	5 260	5 550	5 840	6 130	6 420
1 3/8	1.375	0.6013	4 510	3 280	4 100	4 920	5 740	6 560	7 380	8 200	9 020	9 840	10 660
1 1/2	1.5	0.6903	5 180	3 520	4 390	5 270	6 150	7 030	7 910	8 790	9 670	10 550	11 430
1 5/8	1.625	0.7854	5 890	3 750	4 630	5 510	6 390	7 270	8 150	9 030	9 910	10 790	11 670
1 3/4	1.75	0.8866	6 650	3 980	4 960	5 940	6 920	7 900	8 880	9 860	10 840	11 820	12 800
1 7/8	1.875	0.9940	7 460	4 220	5 270	6 330	7 380	8 440	9 490	10 550	11 600	12 650	13 700
2	2.0	1.1075	8 310	4 450	5 570	6 680	7 790	8 910	10 020	11 130	12 240	13 350	14 470


\* Values for higher or lower unit stresses for shear or bearing to satisfy particular building laws can be figured by proportion from the table. See, The Cambria Handbook gives values of from 12 000 to 20 000.

## Riveted Joints

Fraction		Decimals	Area of rivet	Bin she 10-00 per sq	of plate nt 18 000 lb per sq in plate X 18 000 lb per sq in)														
$\frac{3}{16}$	0.375	0.1104	1.100	1.680	2.450	3.370	4.310	5.280	6.280	7.320	8.400	9.520	10.680	11.880	13.120	14.400	15.720	17.080	
$\frac{7}{16}$	0.4375	0.1503	1.500	1.960	2.450	3.370	4.310	5.280	6.280	7.320	8.400	9.520	10.680	11.880	13.120	14.400	15.720	17.080	
$\frac{1}{2}$	0.5	0.1963	1.960	2.240	2.800	3.370	4.310	5.280	6.280	7.320	8.400	9.520	10.680	11.880	13.120	14.400	15.720	17.080	
$\frac{9}{16}$	0.5625	0.2485	2.480	2.520	3.150	3.790	4.420	5.050	5.680	6.310	6.940	7.570	8.200	8.830	9.460	10.090	10.720	11.350	
$\frac{5}{8}$	0.625	0.3068	3.060	2.800	3.500	4.210	4.910	5.610	6.310	7.010	7.710	8.410	9.110	9.810	10.510	11.210	11.910	12.610	
$1\frac{1}{16}$	0.6875	0.3712	3.710	3.090	3.860	4.640	5.420	6.200	6.980	7.760	8.540	9.320	10.100	10.880	11.660	12.440	13.220	14.000	
$\frac{3}{4}$	0.75	0.4418	4.420	3.370	4.210	5.060	5.900	6.740	7.580	8.420	9.260	10.100	10.940	11.780	12.620	13.460	14.300	15.140	
$1\frac{1}{4}$	0.8125	0.5185	5.180	3.650	4.560	5.480	6.390	7.300	8.210	9.120	10.030	10.940	11.850	12.760	13.670	14.580	15.490	16.400	
$\frac{7}{8}$	0.875	0.6013	6.010	3.930	4.910	5.900	6.880	7.860	8.840	9.820	10.800	11.780	12.760	13.740	14.720	15.700	16.680	17.660	
$1\frac{1}{2}$	0.9375	0.6903	6.900	4.210	5.260	6.330	7.370	8.420	9.470	10.520	11.570	12.620	13.670	14.720	15.770	16.820	17.870	18.920	
1	1.000	0.7854	7.850	4.500	5.600	6.750	7.850	8.900	9.950	11.000	12.050	13.100	14.150	15.200	16.250	17.300	18.350	19.400	
$1\frac{1}{8}$	1.0625	0.8866	8.860	4.780	5.970	7.170	8.360	9.550	10.740	11.930	13.120	14.310	15.500	16.690	17.880	19.070	20.260	21.450	
$1\frac{1}{4}$	1.125	0.9940	9.940	5.060	6.320	7.590	8.850	10.120	11.380	12.650	13.910	15.180	16.440	17.710	18.980	20.250	21.520	22.790	
$1\frac{3}{8}$	1.1875	1.1075	11.075	5.340	6.670	8.010	9.330	10.650	11.970	13.290	14.610	15.930	17.250	18.570	19.890	21.210	22.530	23.850	

7. Length of Field-Rivets for Various Grips. Length of Rivet-Sh to Form Head

American Bridge Company Standard. Dimensions in Inches



Diameter					Grip b	Diameter				
1/2	5/8	3/4	7/8	1		1/2	5/8	3/4	7/8	
1 1/2	1 3/4	1 7/8	2	2 1/8	1 1/2	1 1/8	1 1/4	1 1/4	1 3/8	1
1 5/8	1 7/8	2	2 1/8	2 1/4	5/8	1 1/4	1 3/8	1 3/8	1 1/2	1
1 3/4	2	2 1/8	2 1/4	2 3/8	3/4	1 3/8	1 1/2	1 1/2	1 5/8	1
1 7/8	2 1/8	2 1/4	2 3/8	2 1/2	7/8	1 1/2	1 3/8	1 3/8	1 3/4	1
2	2 1/4	2 3/8	2 1/2	2 5/8	1	1 3/8	1 3/4	1 3/4	1 7/8	1
2 1/8	2 3/8	2 1/2	2 5/8	2 3/4	1 1/8	1 3/4	1 7/8	1 7/8	2	2
2 1/4	2 1/2	2 5/8	2 3/4	2 7/8	1/4	1 7/8	2	2	2 1/8	2
2 3/8	2 5/8	2 3/4	2 7/8	3	3/8	2	2 1/8	2 1/8	2 1/4	2
2 5/8	2 7/8	3	3 1/8	3 1/4	1/2	2 1/8	2 1/4	2 3/8	2 3/8	2
2 3/4	3	3 1/8	3 1/4	3 3/8	5/8	2 1/4	2 3/8	2 1/2	2 1/2	2
3	3 1/4	3 3/8	3 1/2	3 7/8	3/4	2 1/2	2 3/8	2 3/4	2 3/4	2
3 1/8	3 3/8	3 1/2	3 3/8	3 3/4	7/8	2 3/8	2 3/4	2 7/8	2 7/8	2
3 1/4	3 1/2	3 5/8	3 3/4	3 7/8	2	2 3/4	2 7/8	3	3	2
3 3/8	3 5/8	3 3/4	3 7/8	4	1 1/8	2 7/8	3	3 1/4	3 3/8	2
3 1/2	3 3/4	3 7/8	4	4 1/8	1/4	3	3 1/8	3 1/4	3 3/4	2
3 5/8	3 7/8	4	4 1/8	4 1/4	3/8	3 1/8	3 1/4	3 3/8	3 3/8	2
3 3/4	4	4 1/8	4 1/4	4 3/8	1/2	3 1/4	3 3/8	3 1/2	3 1/2	2
3 7/8	4 1/8	4 1/4	4 3/8	4 1/2	5/8	3 3/8	3 1/2	3 3/4	3 3/4	2
4	4 1/4	4 3/8	4 1/2	4 5/8	3/4	3 1/2	3 3/8	3 3/4	3 3/4	2
4 1/8	4 3/8	4 1/2	4 5/8	4 3/4	7/8	3 5/8	3 3/4	3 7/8	3 7/8	2
4 3/8	4 5/8	4 3/4	4 7/8	5	3	3 7/8	4	4	4 1/8	2
4 1/2	4 3/4	4 7/8	5	5 1/8	1 1/8	4	4 1/8	4 1/8	4 1/4	2
4 5/8	4 7/8	5	5 1/8	5 1/4	3/4	4 1/8	4 1/4	4 1/4	4 3/8	2
4 3/4	5	5 1/8	5 1/4	5 3/8	5/8	4 1/4	4 3/8	4 3/8	4 1/2	2
4 7/8	5 1/8	5 1/4	5 3/8	5 1/2	1/2	4 3/8	4 1/2	4 1/2	4 3/8	2
5	5 1/4	5 3/8	5 1/2	5 5/8	5/8	4 1/2	4 3/8	4 3/8	4 3/4	2
5 1/8	5 3/8	5 1/2	5 3/8	5 3/4	3/4	4 3/8	4 3/4	4 3/4	4 7/8	2
5 1/4	5 1/2	5 7/8	5 3/4	5 7/8	7/8	4 3/4	4 7/8	4 7/8	5	2
5 3/8	5 5/8	5 3/4	5 7/8	6	4	4 3/8	5	5	5 1/8	2
5 7/8	5 7/8	6	6 1/8	6 1/4	1 1/8	5 1/8	5 1/4	5 1/4	5 3/8	2
5 3/4	6	6 1/8	6 1/4	6 3/8	1/4	5 1/4	5 3/8	5 3/8	5 1/2	2
6	6 1/4	6 3/8	6 1/2	6 5/8	3/8	5 1/2	5 3/8	5 3/8	5 3/8	2
6 1/8	6 3/8	6 1/2	6 3/8	6 3/4	1/2	5 3/4	5 3/4	5 3/4	5 3/4	2
6 1/4	6 1/2	6 3/8	6 3/4	6 7/8	5/8	5 3/4	5 7/8	5 7/8	5 7/8	2
6 3/8	6 3/4	6 3/4	6 7/8	7	3/4	5 7/8	6	6	6	2
6 1/2	6 3/4	6 7/8	7	7 1/8	7/8	6	6 1/8	6 1/8	6 3/8	2
6 3/8	6 7/8	7	7 1/8	7 1/4	5	6 1/8	6 1/4	6 1/4	6 1/4	2
....	....	7 1/8	7 1/4	7 3/8	1 1/8	....	....	6 3/8	6 3/8	2
....	....	7 1/4	7 3/8	7 1/2	1/4	....	....	6 1/2	6 1/2	2
....	....	7 3/8	7 1/2	7 5/8	3/8	....	....	6 3/8	6 3/8	2
....	....	7 5/8	7 3/4	7 7/8	1/2	....	....	6 7/8	6 7/8	2
....	....	7 3/4	7 7/8	8	5/8	....	....	7	7	2
....	....	7 7/8	8	8 1/4	3/4	....	....	7 1/8	7 1/8	2
....	....	8	8 1/8	8 1/4	1 1/8	....	....	7 1/4	7 1/4	2

For weight of rivets, see page 1528.

**Use of Riveted Joints.** Riveted joints are used in building-construction (1) in tie-bar splices, (2) in floor-beam connections, (3) in the joints of trusses, (4) in riveted girders, and (5) in column-connections.




Fig. 10. Lap-joint




Fig. 11. Butt-joint with Single Cover-plate

**Splicing of Tie-Bars.** Tie-bars may be spliced by a LAP-JOINT (Fig. 10); a BUTT-JOINT with a single cover-plate (Fig. 11); or by a BUTT-JOINT with two cover-plates (Fig. 12).

The Butt-Joint is symmetrical and more efficient than others because of the absence of any tendency to bend when under a load. The net area of the cover-plates at the section through the rivets at the end of the main plate must be equal to the net area of the main plate through the rivets at the end of the cover-plate.

Fig. 11 shows a better arrangement of rivets than that in Fig. 13, because less material is removed at the critical section of the cover-plates. In some cases it may be necessary to make the aggregate thickness of the cover-plates greater than the thickness of the main plates.

A joint with one line of rivets is said to be SINGLE-RIVETED, one with two lines DOUBLE-RIVETED, and one with more than two lines, CHAIN-RIVETED.

**Example 2.** It is required to determine the number of rivets in the splice of a 12 by 1/2-in tie-bar which is subject to a tensile force of 65 000 lb.

**Solution.** Assuming that the load is constant, the stresses in Table III may be used. Assuming, also, a lap-joint like that in Fig. 15, and 3/4-in rivets, the stress in shear of one rivet is found to be 4 420 lb and the bearing value for a 1/2-in plate, 6 740 lb. The number of rivets is determined by the load to be equal to 65 000 divided by 4 420, or fifteen. Since sixteen rivets are required to complete a figure similar but similar in arrangement to that shown in Fig. 15, this number is used.

There is some latitude possible in the spacing of the rivets, but with a pitch of 12 in, the horizontal gauge-lines are placed 1 1/2 in apart for symmetry. The pitch  $P$ , as shown in Fig. 15, is required to be three times the diameter of the rivet, this diagonal pitch across the rivet-spacing must be 2.25 in, or




Fig. 12. Butt-joint with Two Cover-plates




Fig. 13. Cover-plate. Six Rivets at Critical Section




Fig. 14. Cover-plate. Four Rivets at Critical Section

greater. The length of the horizontal or third side of the right-angled triangle having an hypotenuse of 2.25 in and a vertical altitude of 1.5 in, is 1.68

which requires that this distance  $ED$ , etc., be 1.75 in, if measured in multiples of  $\frac{1}{4}$  in.

#### Floor-Beam Connection

The two following examples illustrate common types of floor-beam connections.

**Example 3.** It is required to determine the number of  $\frac{3}{4}$ -in rivets to connect a 10-in 25.4-lb I beam supporting 24 000 lb to a 15-in 42.9-lb I beam, using a shearing-stress of 10 000 lb per sq in and a bearing-stress of 18 000 lb per sq in.

**Solution.** From the table of properties of standard I beams, pages 354-5, the thickness of the web of the 10-in 25.4-lb beam is found to be 0.31 in, say  $\frac{3}{16}$  in, and of the 15-in 42-lb beam, 0.41 in, say  $\frac{1}{4}$  in. Referring to Table III, p. 419, the bearing values for a  $\frac{3}{4}$ -in rivet for these thicknesses of webs are respectively 4 210 lb and 5 890 lb. The shearing value of the rivet is 4 420 lb. The rivets in the 10-in beam are in double shear; hence the bearing value governs. The number of rivets, then, is 12 000, the end-reaction, divided by 4 210, or 3. For the 15-in beam the shearing value is less, and the number of rivets required is 12 000 divided by 4 420, or 3. Hence two standard connection angles, 6 by 4 by  $\frac{3}{8}$  in and 5 in long, may be used. Each has three holes in leg and two in the other. The leg with three holes is placed on the 10-in beam with the rivets in double shear, and the leg with two holes is connected to the 15-in beam; thus, in the latter case there are four rivets where only three are required for strength. They are driven in the field during the erection of the structure and the working stress is accordingly made less in most specifications because of the better work possible with the heavy machines used in shop-work than with the tools available in the field.

**Example 4.** It is required to determine the number of  $\frac{3}{4}$ -in rivets to connect a 4 by 4 by  $\frac{1}{2}$ -in angle-bracket attached to an 18-in 54.7-lb beam and supporting a 10 by 12-in wooden beam on which there is a load of 18 000 lb.

**Solution.** The rivets are in single shear with a shearing-resistance of 4 420 lb taken from Table III. The thickness of the web of the I beam is  $\frac{1}{4}$  in, giving a bearing value of 5 890 lb. Dividing 9 000 lb, the end-reaction, by 4 420 lb, the controlling value, we find that two rivets are insufficient. The bracket must be fastened with three  $\frac{3}{4}$ -in rivets with a spacing of 4 in. Two  $\frac{3}{8}$ -in rivets are sufficient to hold the bracket.

**Rivets in Plate Girders.** The methods of determining the rivets in plate and box girders are given in Chapter XX.

**Bending Stress in Rivets.** While the BENDING STRENGTH of PINS at joints of articulated trusses is always investigated, this is never done in the case of RIVETS. A hot rivet properly driven is, when cold, under a tensile stress which is nearly equal to the elastic limit of the material. This causes a great pressure between the plates and a consequent frictional resistance to movement, which, under the usual conditions, equals the allowed shearing-stress on the rivet; and so, until an INITIAL SLIP occurs, there can be no BENDING STRESSES in the rivet. In the case of very long rivets driven in holes with




Fig. 15. Rivet-spacing in Cover-plate



but is an imperfect alinement of the plates and a consequent difficulty in making the rivets fill the holes completely, it is not probable that any large working stresses can occur in the rivets of a structure. This has been avoided in a few structures for which long TAPER RIVETS were specified to be used in the BEAMED with TAPERED REAMERS, thus insuring a perfect filling of the holes.

**Working Stresses.** Tables II and III are based on stresses which approximate those used in the best practice. Table II is used for the few structures made of WROUGHT IRON and for those places in steel structures that are subject to severe conditions of service, as in the floor-systems of bridges. Table III is used for ordinary structural work made under the conditions governing in modern shop-practice. For comparison, the following stresses taken from the specifications of Theodore Cooper for Steel Railroad Bridges and Steel Highway Bridges are given:

Specification for	Allowable stresses on rivets, lb per sq in	
	Bearing	Shear
Steel railroad bridges	15 000 (12 000 on floors) 22 500 for laterals	9 000 (7 200 on floors) 13 500 for laterals
Steel highway bridges	18 000 (14 400 on floor-beams) 27 000 for laterals	10 000 (8 000 on floor-beams) 14 000 for laterals

Rivets driven in the field are allowed two-thirds the value of shop-driven rivets.

## 2. Strength of Pins in Trusses\*

**Truss-Pins.** In the design of the PINS at the joints of trusses the stresses in **BEARING, BEARING FLEXURE OR BENDING** must be investigated.

**The Shearing-Force** at any section of the pin is the algebraic sum of all the forces acting on the pin on either side of the section. The stress is considered to be uniformly distributed over the cross-section of the pin. When the forces do not act in the same plane they must be resolved into vertical and horizontal components and the resultant of these components taken as the shear at any desired section. This may be done by the principles of GRAPHIC STATICS, or by TRIGONOMETRICAL and ALGEBRAICAL METHODS, the graphic method being, for some, the more rapid.

**The Bearing Area** on the pin is taken as the PROJECTION OF THE AREA OF CONTACT, the area of this projection being equal to the diameter of the pin multiplied by the thickness of the plate. The bearing is assumed to be uniformly distributed; hence for any load the intensity of the pressure may be increased by increasing the thickness of the plate or the diameter of the pin.

**The Bending Moments** on the pin may be found by the PRINCIPLE OF MOMENTS or by methods involving the principles of GRAPHIC STATICS explained in Chapter IX in finding the bending moments of beams. The forces are considered to be concentrated at the middle of the bearing-plates. If they do not lie in a plane with the pin they must be resolved into their vertical and horizontal components.

\*Since the introduction of rolled-steel shapes and riveted joints, pin-joints for trusses of moderate span in buildings have fallen into disuse. The general principles of their design, however, are given here.

zontal components and these component forces in the two planes treated separately. The resultants in both planes at any section may be combined and single resultant force acting on the section obtained, and also the consequent stresses due to it.

Table V. Shearing and Bearing Values of Pins for One-Inch Thickness of Plate, in Pounds per Square Inch

Diam-eter of pin, in	Area of pin, sq in	Bearing value at 12 000 lb per sq in, lb	Single shear 7 500 lb persq in, lb	Diam-eter of pin, in	Area of pin, sq in	Bearing value at 12 000 lb per sq in, lb	Single shear 7 500 lb persq in, tons
1	0.785	12 000	5 890	4	12.57	48 000	47.0
1 1/8	0.994	13 500	7 455	4 1/8	13.36	49 500	50.1
1 1/4	1.227	15 000	9 202	4 1/4	14.19	51 000	53.2
1 3/8	1.485	16 500	11 132	4 3/8	15.03	52 500	56.3
1 1/2	1.767	18 000	13 252	4 1/2	15.90	54 000	59.6
1 5/8	2.074	19 500	15 555	4 5/8	16.80	55 500	63.0
1 3/4	2.405	21 000	18 037	4 3/4	17.72	57 000	66.3
1 7/8	2.760	22 500	20 707	4 7/8	18.67	58 500	70.0
2	3.142	24 000	23 565	5	19.64	60 000	73.6
2 1/8	3.547	25 500	26 600	5 1/8	20.63	61 500	77.3
2 1/4	3.976	27 000	29 820	5 1/4	21.65	63 000	81.2
2 3/8	4.430	28 500	33 225	5 3/8	22.69	64 500	85.1
2 1/2	4.909	30 000	36 817	5 1/2	23.76	66 000	89.1
2 5/8	5.412	31 500	40 590	5 5/8	24.85	67 500	93.2
2 3/4	5.940	33 000	44 550	5 3/4	25.97	69 000	97.3
2 7/8	6.492	34 500	48 690	5 7/8	27.11	70 500	101.1
3	7.069	36 000	52 910	6	28.27	72 000	106
3 1/8	7.670	37 500	57 210	6 1/8	29.46	73 500	110
3 1/4	8.296	39 000	61 590	6 1/4	30.68	75 000	115
3 3/8	8.946	40 500	66 050	6 3/8	31.92	76 500	119
3 1/2	9.621	42 000	70 590	6 1/2	33.18	78 000	124
3 5/8	10.32	43 500	75 210	6 5/8	34.47	79 500	129
3 3/4	11.05	45 000	79 910	6 3/4	35.79	81 000	134
3 7/8	11.79	46 500	84 690	6 7/8	37.12	82 500	139

In the Method of Moments a section is taken at each force in succession and the moment of the forces about a point in the section found, due consid




Fig. 16. Pin-joint

ation being given to the direction of turning. This is done at each force on one side of pin, if the bars are arranged symmetrically, and in both vertical and horizontal planes. Inspection of the results usually indicate which section

has the GREATEST RESULTANT MOMENT when the horizontal and vertical components,  $H$  and  $V$ , are combined. This is done by using the formula  $R^2 = H^2 + V^2$  since, graphically, the resultant  $R$  is the diagonal of the rectangle

**Table VI. Maximum Bending Moments in Inch-Pounds to be Allowed on Pins for Maximum Fiber-Stresses of 15 000, 20 000 and 22 500 Pounds per Square Inch**

Diameter of pin, in	Moment for $S = 15\ 000$ in-lb	Moment for $S = 20\ 000$ in-lb	Moment for $S = 22\ 500$ in-lb	Diameter of pin, in	Moment for $S = 15\ 000$ in-lb	Moment for $S = 20\ 000$ in-lb	Moment for $S = 22\ 500$ in-lb
1	1 470	1 960	2 210	4	94 200	125 700	141 400
1 $\frac{1}{8}$	2 100	2 800	3 140	4 $\frac{1}{8}$	103 400	137 800	155 000
1 $\frac{1}{4}$	2 830	3 830	4 310	4 $\frac{1}{4}$	113 000	150 700	169 600
1 $\frac{3}{8}$	3 830	5 100	5 740	4 $\frac{3}{8}$	123 300	164 400	185 000
1 $\frac{1}{2}$	4 970	6 630	7 460	4 $\frac{1}{2}$	134 200	178 900	201 300
1 $\frac{3}{4}$	6 320	8 430	9 480	4 $\frac{5}{8}$	145 700	194 300	218 500
1 $\frac{7}{8}$	7 890	10 500	11 800	4 $\frac{7}{8}$	157 800	210 400	236 700
1 $\frac{7}{8}$	9 710	12 900	14 600	4 $\frac{7}{8}$	170 600	227 500	255 900
2	11 800	15 700	17 700	5	184 100	245 400	276 100
2 $\frac{1}{8}$	14 100	18 800	21 200	5 $\frac{1}{8}$	198 200	264 300	297 300
2 $\frac{1}{4}$	16 800	22 400	25 200	5 $\frac{1}{4}$	213 100	284 100	319 600
2 $\frac{3}{8}$	19 700	26 300	29 600	5 $\frac{3}{8}$	228 700	304 900	343 000
2 $\frac{1}{2}$	23 000	30 700	34 500	5 $\frac{1}{2}$	245 000	326 700	367 500
2 $\frac{3}{4}$	26 600	35 500	40 000	5 $\frac{5}{8}$	262 100	349 500	393 100
2 $\frac{7}{8}$	30 600	40 800	45 900	5 $\frac{7}{8}$	280 000	373 300	419 900
2 $\frac{7}{8}$	35 000	46 700	52 500	5 $\frac{7}{8}$	298 600	398 200	447 900
3	39 800	53 000	59 600	6	318 100	424 100	477 100
3 $\frac{1}{8}$	44 900	59 900	67 400	6 $\frac{1}{8}$	338 400	451 200	507 600
3 $\frac{1}{4}$	50 600	67 400	75 800	6 $\frac{1}{4}$	359 500	479 400	539 300
3 $\frac{3}{8}$	56 600	75 500	84 900	6 $\frac{3}{8}$	381 500	508 700	572 300
3 $\frac{1}{2}$	63 100	84 200	94 700	6 $\frac{1}{2}$	404 400	539 200	606 600
3 $\frac{3}{4}$	70 100	93 500	105 200	6 $\frac{5}{8}$	428 200	570 900	642 300
3 $\frac{7}{8}$	77 700	103 500	116 500	6 $\frac{7}{8}$	452 900	603 900	679 400
3 $\frac{7}{8}$	85 700	114 200	128 500	6 $\frac{7}{8}$	478 500	638 000	717 800

**Remarks.** The following is the formula for flexure,  $M = SI/c$ , with the reductions made to adapt it to a beam of circular section:

$$M = S\pi d^3/32 = SA d/8$$

$M$  = the moment of forces for any section through the pin;  
 $S$  = the stress per sq in in extreme fibers of pin at that section;  
 $A$  = the area of the section;  
 $d$  = the diameter;  
 $\pi = 3.14159$ .

The forces are assumed to act in a plane passing through the axis of the pin. The above table gives the values of  $M$  for different diameters of pin, and for three values of  $S$ . If the maximum value of  $M$  is known, an inspection of the table will show what the diameter of the pin must be so that  $S$  will not exceed 15 000, 20 000, or 22 500 lb, as the requirements of the case may be.

**H and V.** Example 6 illustrates the method for the condition of INCLINED FORCES acting on the pin. In Example 5 the same method is employed to determine the size of the pin in a simple joint.

**Example 5.** It is required to determine the size of the pin for the joint shown in Fig. 16 in the lower chord of a steel truss. The middle bar is a vertical suspension-rod to hold the chord in place.

**Solution.** Beginning at the section between the outer bars, the algebraic sum of the forces on either side of the section is 40 000 lb, hence this is the shear. At the section next to the suspender the sum is zero; therefore there is no shear at the middle of the pin. The bearing pressure is 40 000 lb. The intensity depends on the diameter of the pin and the thickness of the bars. To find the bending moment on the pin the forces are considered concentrated at the middle of the bars and moments taken about sections through the force. The moment at the section through the second bar is  $40\,000\text{ lb} \times 1\text{ in}$ , equal to 40 000 in-lb. If moments are taken about a point between the inner forces the same result is obtained. From Table VI it is found that a  $2\frac{3}{4}$ -in pin under 20 000 lb per sq in is sufficient. From Table V the bearing value of a  $2\frac{3}{4}$ -in pin is found to be only 33 000 lb at a stress of 12 000 lb per sq in, which makes it necessary to increase the size of the pin to  $3\frac{3}{8}$  in. The shearing value of this pin is 67 000 lb. In this case the diameter of the pin is determined by the bearing-stress, but it is necessary to investigate the other stresses to be sure of the correct size, especially in case of heavy bearing-plates.

**Bending Moments on Pins.** The finding of the BENDING MOMENT due to the forces acting on a pin is usually the most difficult part of the work of determining its proper size. In the case of a simple pin, properly packed and lying in the plane of the forces acting on it, the GREATEST MOMENT is usually the product obtained by multiplying the outer force by the central distance between the outer bars; but when the forces act in several planes the work is more complicated. The GRAPHICAL METHOD illustrated in the solution of the following examples has some advantages; but the METHOD OF MOMENTS applied at the end of the solution of the first example is equally rapid in practical hands and capable of greater refinement in the results.

**Example 6.** It is required to find the bending moment on the pin of the joint, one-half of which is shown in Fig. 17. The bars are each 1 in thick; the channel of the vertical member  $\frac{1}{2}$  in thick and the center of the hanger is  $\frac{3}{4}$  in from the center of the channel.

**Solution.** Since the joint is symmetrical it is necessary to construct but one-half of the force-diagram and equilibrium-polygon which really apply to the joint. From the conditions of equilibrium of forces, the vertical component of the inclined force is upward, and equal to the sum of the downward forces, 34 000 lb; and its horizontal component acts with the 60 000-lb force to the amount of 17 000 lb, a sufficient amount to close the force-diagram. The following construction is special, in that but one-half of the entire graphical diagram is shown. This is made possible because of the symmetry of the joint, the bending moment being constant over the middle of the pin.

In the diagram (Fig. 18)  $AB$  is drawn at an angle of  $45^\circ$  with the horizontal and commencing at  $c$ , the distances are laid off to scale between the bars, and the lines 1-2, 2-3, etc., drawn parallel to the forces they represent at the joint. The oblique force is resolved into its components 1-4 and 1-5.

The stress-diagram (Fig. 19) is drawn as follows: On a horizontal line the forces are laid off to scale in the order they occur on the pin, 1-2, 2-3, 3-4 and 4-1, the closing of the diagram being a check on the correctness of the values of the forces. Beginning at 1, 1-5, 5-6 and 6-1 are laid off to scale, parallel to the forces in the vertical plane. From 1 the line 1-0 is drawn at an angle of  $45^\circ$ , for convenience in making good intersections, and equal to a convenient number, say 20 000 lb, in the same scale to which the loads are drawn. 7

Let  $O$  be the pole of the stress-diagram, the pole-distance being 20 000 lb. In the principles of graphics the bending moment at any point on the pin is equal to the intercept between the proper ray of the equilibrium-polygon and the closing line, multiplied by the pole-distance. To complete the figures,  $o-3$  and  $o-4$  are drawn from  $O$ , and from  $c$   $cd$  is drawn parallel to  $o-2$ ,  $de$  parallel to  $o-3$ ,  $ef$  parallel to  $o-4$  and  $fa$  parallel to  $o-1$ . In the same way  $g$  is drawn parallel to  $o-5$ ,  $h$  to  $o-6$  and  $ib$  to  $o-1$ . Then according to the principles, the moment at any section due to the forces in the horizontal chord is proportional to the ordinate at that section drawn from the line  $AB$  to the line  $cdefa$  bounding the equilibrium-polygon; and the moments due to the vertical forces are proportional to the ordinates drawn to the line  $rsib$ , the numerical value being the length of the ordinate times 20 000, the pole-distance.




Fig. 18




Fig. 19




Fig. 20

Figs. 17 to 20. Pin-joint and Moment-diagrams

As both moments are present, the resultant or true moment is proportional to the hypotenuse of the right-angled triangle having for its sides the ordinates to two planes at the point in question. At  $X$  this is shown by the line  $mn$ .  $mn$  measures 1.42 in., and being the longest diagonal or hypotenuse that can be drawn in the figure, it follows that the maximum bending moment on the pin is  $1.42 \times 20\,000 = 48\,400$  in.-lb.

To find the effect of changing the arrangement of the members on the pin, it may be assumed that the inclined bar is placed outside the inner chord-bar. The horizontal stress-diagram then becomes 1-2, 2-3, 3-4', 4'-1. The equilibrium-polygons become  $cdef'h'$  and  $r's't'w$ , as shown in Fig. 20. In these polygons the longest diagonal measures  $3\frac{3}{4}$  in., which gives a bending moment of  $3\frac{3}{4} \times 20\,000$  lb. = 75 000 in.-lb., showing that the arrangement of the eye-bars in Fig. 17 is better. As a rule the bending moment is less when those forces that

oppose each other are placed together. It may be further reduced by making the outside bar one-half the thickness of the main horizontal bars.

To check by the METHOD OF MOMENTS the value of the maximum bending moment obtained by the GRAPHIC METHOD for the first arrangement, the moments of the forces in the horizontal plane are taken about  $r$ . This gives

$$M_h = 38\,500 \text{ lb} \times 3.0 \text{ in} + 38\,500 \text{ lb} \times 1.0 \text{ in} - 60\,000 \text{ lb} \times 2.0 \text{ in} \\ = 34\,000 \text{ in-lb},$$

which is the value of the moment in the horizontal plane across the middle of the pin.

In the vertical plane moments are taken about a point  $t$ , giving

$$M_v = 34\,000 \text{ lb} \times 1.5 \text{ in} - 22\,000 \text{ lb} \times 0.75 \text{ in} \\ = 34\,500 \text{ in-lb}$$

From these component moments the resultant maximum bending moment

$$M = \sqrt{34\,000^2 + 34\,500^2} = 48\,400 \text{ in-lb}$$

**Example 7.** Another illustration of the GRAPHICAL METHOD of finding bending moment on a pin is given for the joint  $A$  of the truss-diagram shown




Fig. 21




Fig. 22




Fig. 23




Fig. 24

Figs. 21 to 24. Force-polygons and Equilibrium-polygons for Bending Moment on a Pin

Fig. 21. Fig. 22 shows the arrangement and size of the members. The forces given in Fig. 21 are for one-half the number of members at the joint. In Example 6, the symmetrical arrangement makes it unnecessary to draw

one-half of the force-polygon and equilibrium-polygon. The web of the end is reinforced to make it  $\frac{5}{8}$  in thick.

**Method.** The line  $AB$  (Fig. 24) is drawn at an angle of  $45^\circ$  and  $ab$ , etc., are laid off to scale, equal to the distances between the members. At each point of application of a force a line is drawn parallel and to scale, to represent that force. The inclined forces are then resolved into their horizontal and vertical components. The force-diagram (Fig. 23) is then drawn, the horizontal forces being laid off to scale in the order in which they occur, 1-2, 2-3, 3-4 and 4-1. A pole-distance is then laid off at an angle of  $45^\circ$  and equal to 20 000 lb to the same scale of forces. The pole  $o$  is then joined with 2, 3, 4 and 1. Then in Fig. 24,  $ab$  is drawn parallel to  $o-2$ ,  $bc$  to  $o-3$ ,  $cd$  to  $o-4$  and  $de$  to  $o-1$ . In the same way the line  $hjkB$  is drawn. From inspection it is seen that  $hb$  is the greatest intercept, even longer than any diagonal that may be drawn from the vertices of the horizontal and vertical intercepts at any point along  $AB$ . On the same scale that makes  $o-1$  represent 20 000 lb,  $hb$  represents 31 800 in-lb; therefore the bending moment on the pin is 31 800 in-lb. In Table VI a pin  $\frac{1}{2}$  in in diameter, at a fiber-stress of 20 000 lb per sq in, has an allowable bending moment of 35 500 in-lb, and in Table V a bearing value on 1 in of 31 500 lb. A force of 31 800 lb on  $\frac{5}{8}$  in is equal to 42 400 for a 1-in bar; so it is necessary to use a larger pin to accommodate the bearing requirement. From Table V a  $3\frac{1}{2}$  in in diameter is found to be necessary. The shearing value of this is 72 000 lb more than twice the load, so, again, it is the bearing that controls the size of the pin. If the thickness of the bars is increased the diameter of the pin may be reduced to 3 in.

#### 4. Strength of Bolts in Wooden Trusses and Girders

**The Working Stresses for Bolts** on which Table VII and Table VIII are based are based on a FACTOR OF SAFETY of five applied to the average of the test results on dry timber. In some specifications it is permitted to increase the BEARING PRESSURE between timber and bolts as much as 50% above that permitted for short struts. The values in the tables are somewhat less than the values for large trusses made at the Massachusetts Institute of Technology, in 1900, would indicate as safe values. These were reported in the Engineering Record, November 17, 1900. Table IX gives the allowable maximum tension, shear and bending moments for wrought-iron and steel bolts.

**Methods of Stress in Bolts.** BOLTS in wooden trusses are subject to the same kinds of stress as the RIVETS and PINS in steel structures. When the timber is joined are less than 2 in thick and the bolts are tightly drawn up so as to develop considerable frictional resistance between the pieces, the bolts are not required to resist the total force in SHEAR and in BEARING. When the timber is more than 2 in thick the BENDING is taken into account and the bolts must be investigated for stresses in SHEAR, in BEARING and in BENDING. The stress is assumed to be uniformly distributed over the cross-section of the bolt, the BEARING AREA is the area of the projection of the bolt on the timber, and this area is equal to the diameter of the bolt multiplied by the length in contact. The BEARING STRENGTH is given as a property of the bolt although it depends upon the crushing strength of the timber. The BENDING MOMENT on the bolt is found in the same manner as for pins in steel trusses, although the cases are usually less complicated.

**Illustrations of the Use of Bolts.** The principles involved in the use of bolts in wooden trusses and girders and in the use of the tables may be best illustrated by the solution of examples in each of the following cases:

- (1) Bolts in tie-beams, thin pieces.
- (2) Bolts in girders to support brackets.
- (3) Bolts as pins in the joints of trusses.
- (4) Bolt-and-strap joints in trusses.
- (5) Bolts under tension to hold the foot of a rafter.

(See, also, " Joints in Wooden Trusses," Chapter XXVIII, pages 1149 to

**Case 1. Bolts in Tie-Beams, Thin Pieces.** Tie-beams of wooden trusses when longer than 30 ft, are usually made up of a number of pieces. This construction is cheaper than the use of a single stick. Two-inch planks bolted together are generally used. The location of the joints in the courses of planks and the number and size of the bolts are the special considerations in the design of such a joint. In general, the joints in adjacent courses are placed as far apart as possible and not more than two joints are placed opposite each other in the same section. The simplest case is that of a plain FISH-PLATE JOINT or a common BUTT-JOINT with two cover-plates as shown in Fig. 12. The number of BOLTS for such a joint is found in the same way as the number of RIVETS in steel tie-bars. The bolts must be spaced as required in the second column of Table VII, to provide against shearing in front of the bolt.

**Table VII.\* Safe Bearing Value of Bolts per Inch of Length Parallel to the Grain in Timber and Distance from Center to Center of Bolts or to End of Timber**

Diam-eter of bolt, in	Long-leaf yellow pine		White pine and short-leaf yellow pine		Douglas fir		White oak	
	Bearing at 1 400 lb per sq in, lb	Dis-tance, in	Bearing at 1 100 lb per sq in, lb	Dis-tance, in	Bearing at 1 200 lb per sq in, lb	Dis-tance, in	Bearing at 1 400 lb per sq in, lb	Dis-tance, in
3/4	1 050	4 1/2	825	5 1/4	900	4 1/4	1 050	4 1/2
7/8	1 225	5	960	5 3/4	1 050	5	1 225	5
1	1 400	5 3/4	1 100	6 1/2	1 200	5 1/2	1 400	5 3/4
1 1/8	1 575	6 1/2	1 237	7 1/2	1 350	6 1/4	1 575	6 1/2
1 1/4	1 750	7	1 375	8	1 500	7	1 750	7
1 3/8	1 925	7 3/4	1 512	9	1 650	7 3/4	1 925	7 3/4
1 1/2	2 100	8 1/2	1 650	9 3/4	1 800	8 1/2	2 100	8 1/2
1 3/4	2 450	10	1 925	11 1/2	1 950	9 1/4	2 450	10
2	2 800	11 1/2	2 200	13	2 400	11 1/4	2 800	11 1/2
2 1/4	3 150	12 3/4	2 475	14 3/4	2 700	12 1/2	3 150	12 3/4
2 1/2	3 500	14 1/4	2 750	16 1/4	3 000	14	3 500	14
2 3/4	3 850	15 1/4	3 025	18	3 300	15 1/2	3 850	15 1/4
3	4 200	17	3 300	19	3 600	17	4 200	17

The distance from the end is equal to the diameter of the bolt plus the length of the bolt. The distance from the end to the center of the bolt plus twice the SHEAR is equal to the BEARING VALUE of the bolt against the end-fiber of the timber. See Table XVI, Chapter XVI, for increase in allowed stresses.

\* When the effect of the inclined surfaces upon the unit stresses is taken into account, the formula for the normal intensity of stress for cylindrical pins or bolts, given in Chapter XXVIII, page 1138, may be used. This formula will give lower values than those in Table VII.



**Table VIII.\* Safe Bearing Value of Bolts per Inch of Length Across the Grain in Timber**

Diameter of bolt, in	Long-leaf yellow pine, lb	Short-leaf yellow pine and Douglas fir, lb	White pine, lb	White oak, lb
$\frac{3}{4}$	262	187	150	375
$\frac{7}{8}$	306	218	175	437
1	350	250	200	500
$1\frac{1}{8}$	394	281	225	562
$1\frac{1}{4}$	437	312	250	625
$1\frac{3}{8}$	482	343	275	687
$1\frac{1}{2}$	525	375	300	750
$1\frac{3}{4}$	612	437	350	875
2	700	500	400	1000

**Table IX. Maximum Allowable Tension, Shear and Bending Moment for Wrought-Iron and Steel Bolts**

Diameter of bolt, in	Net area, sq in	Wrought iron			Steel		
		Tension at 12 000 lb per sq in, lb	Shear at 7 500 lb per sq in, lb	Bending moment at 15 000 lb per sq in, in-lb	Tension at 16 000 lb per sq in, lb	Shear at 10 000 lb per sq in, lb	Bending moment at 20 000 lb per sq in, in-lb
$\frac{3}{4}$	0.302	3 620	3 310	620	4 830	4 420	830
$\frac{7}{8}$	0.420	5 040	4 510	980	6 720	6 010	1 310
1	0.550	6 600	5 890	1 470	8 800	7 850	1 960
$1\frac{1}{8}$	0.694	8 328	7 460	2 100	11 100	9 940	2 800
$1\frac{1}{4}$	0.893	10 716	9 200	2 880	14 290	12 270	3 830
$1\frac{3}{8}$	1.057	12 680	11 140	3 830	16 910	14 850	5 100
$1\frac{1}{2}$	1.295	15 540	13 250	4 970	20 720	17 670	6 630
$1\frac{3}{4}$	1.746	20 930	18 040	7 890	27 910	24 050	10 500
2	2.302	27 620	23 560	11 800	36 830	31 420	15 700
$2\frac{1}{8}$	3.023	36 280	29 820	16 800	48 370	39 760	22 400
$2\frac{1}{4}$	3.719	44 630	36 820	23 000	59 510	49 090	30 700
$2\frac{3}{8}$	4.620	55 430	44 550	30 600	73 910	59 400	40 800
$2\frac{1}{2}$	5.428	65 140	53 010	39 800	86 850	70 690	53 000
$2\frac{3}{4}$	6.510	78 120	62 220	50 600	104 160	82 960	67 400

**Example 8.** A typical tie-beam used as a lower chord of a Howe truss is shown in Fig. 25. It is 50 ft long, of Douglas fir and subject to the tension in different panels shown in the figure.

**Notes.** The thickness of the plank is drawn out of scale in the figure to show the joints more clearly. The black circles show the vertical tension-rods, which so nearly cut the middle plank in two that it is not considered a part of the main member. The arrangement of the planks and the lengths to be used must be determined for each case. In the one shown there is but one plank in the middle panels where there is the greatest tension. The distance

$XY$  is 12 ft, which is about as small as will serve for the transfer of the tension from  $A'$  to  $B$ . In this beam the two outer planks,  $A$  and  $A'$ , must be strong enough to resist the whole tensile stress in the middle panels because of the joints in  $B$  and  $C$ . At the inner end of the second panel there is 58 000 lbs. tension which must be carried to the end of the first panel. Because of




Fig. 25. Plan of Built-up Tie-beam

joints in  $A$  and  $A'$  this must be transmitted to  $B$  and  $C$  in order to pass point  $X$ .

Assuming that 29 000 lb, one-half the tension, is carried on plank  $A$  and transmitted to  $C$  by the shear and bearing on the bolts, and dividing this by 7 850 lb, the allowable shear on a 1-in bolt, four bolts are found to be necessary. But the bearing value of a 1-in bolt in Douglas fir 2 in thick, is only 2 400 lb, which makes twelve bolts necessary. These are required in the distance of 12 ft.

From the distances in Table VII, it is found that the end-bolts must be 6 in from the ends of the planks, say 6 in; this leaves 11 ft, in which distance the bolts are to be arranged. If four bolts are placed in pairs, two at each end




Fig. 26. Elevation of Beam Opposite  $X$  of Fig. 25

shown in Fig. 26, the intermediate spaces are  $14\frac{2}{3}$  in. The bolts bind the planks together better if they are staggered, as indicated in Fig. 26, and not placed on the middle line.

The number of bolts mentioned is sufficient to make the splice, but there should be bolts in the distance  $YY'$ , and between the ends and  $X$  and  $X'$  to bind the planks together. These need not be as large or as close together as the others;  $\frac{3}{4}$ -in bolts spaced 2 ft are sufficient. There should be two bolts at the end of the beam. Each bolt should be driven through a hole of the same size as the bolt and the nuts should be screwed up tight.

**Case II. Bolts in Girders to Support Brackets.** The construction shown in Figs. 27 and 28 is commonly used in cases in which the requirements allow the girder to project its full depth below the joists. The BOLTS shown in Fig. 27 must be investigated for BEARING and SHEAR, and those shown in Fig. 28 for BEARING, SHEAR and BENDING. In either case the SHEARING VALUE of the bolts in single shear must equal or be greater than the greater of the forces  $S$  or  $S'$ .

The BEARING per inch on the wood of the girder, when  $B$  is in inches, is

$$(S + S')/B$$

This must be kept within the values given in Table VII for the timber used. For the case shown in Fig. 28 the BENDING MOMENT in pound-inches is

$$M = SL/2 \quad \text{or} \quad M = S'L/2$$

whichever is the larger.  $B$  and  $L$  are measured in inches and  $S$  in pounds.




Fig. 27



Fig. 28

Figs. 27 and 28. Bolts Supporting Brackets on Girders

**Example 9.** For the construction shown in Fig. 27 it is required to determine number and size of bolts, the Douglas fir girder being 8 by 14 in, with a span of 14 ft, and the Douglas fir joists 3 by 12 in, with a span of 20 ft, center to center of girders. The floor-load, including the floor, is 60 lb per sq ft. The joists are 4 by 3½ by ¾ in.

**Solution.** The floor-area supported by the girder is 14 by 20 ft. At 60 lb per sq ft, the load is  $14 \times 20 \times 60 = 16\,800$  lb. The load  $S$ , on one side, is 8400 lb.

A ¾-in bolt has a shearing-value of 4420 lb. Hence two bolts are necessary to satisfy the shearing condition. The bearing value of the bolt in the wood, across the grain, is, from Table VIII, 187 lb per inch of length, or 1496 lb for 8 in width of the girder. The number of bolts required, then, is 16800 divided by 1496 or approximately 11, which gives a spacing of about 15 in.

**Example 10.** In the construction shown in Fig. 28, the girder is 6 by 14 in, of Douglas fir and has a span of 12 ft. The joists are 2 by 12 in and have an 18-ft span, center to center of girders. The floor-load is 65 lb per sq ft. There are 1½-in strips on the sides of the girder. The distance  $L$  is 3 in. It is required to find the number and size of bolts to be used.

**Solution.** The total load on the girder is

$$12 \times 18 \times 65 = 14\,040 \text{ lb}$$

$$S = 7\,020 \text{ lb}$$

The bearing load per inch of thickness of the girder is

$$\frac{14\,040}{6} = 2\,340 \text{ lb}$$

The bending moment on one side of the girder is

$$\frac{7\,020 \times 3}{2} = 10\,530 \text{ in-lb}$$

the force  $S$  acts at the center of pressure on the bracket-strip, 1½ in from edge of the girder.

The shear is 7020 lb, which requires two ¾-in steel bolts at 4420 lb for one bolt in Table IX.

The bearing (Table VIII) on a ¾-in bolt is 187 lb per inch of length; therefore thirteen bolts for bearing.

The allowable bending moment on a  $\frac{3}{4}$ -in steel bolt is 830 in-lb, from Table To take care of the 10 530 in-lb requires thirteen bolts. A  $\frac{7}{8}$ -in steel bolt an allowable bending moment of 1 310 lb-in, making eight of them sufficient. The 3 by 4-in pieces may be held in place by thirteen  $\frac{3}{4}$ -in bolts spaced 12 on centers, if two of them are placed 6 in from the ends.

**Case III. Bolts as Pins in the Joints of Trusses.** For TIES

STRUTS joined by BOLTS in manner indicated in Figs. 30 and 31 and having thickness  $B$  exceeding .2 the diameter of the bolt the number of bolts must be computed for SHEARING, BEARING and FLEXURE.

For any of these joints the forces are as follows:

The single shear =  $S/2$

On the sections between  $B'$  and  $B'$  (Fig. 30)

The bearing on the pin 1 inch of length =  $S/B$  or  $S/2$

The greater is to be used.

The bending moment =  $S \times L$

on the assumption of a CONJOINED BEAM, uniformly loaded

If there are more bolts than one, the quantities obtained

by the above formulas are to be divided by the number of bolts to find the load to be taken care of by one bolt.

In Fig. 29,  $S$  is the horizontal component of the thrust  $T$ .

**Example 11.** It is required to determine the diameter of a bolt for a joint like that shown in Fig. 29. The rafter is 6 by 10 in, of Douglas fir, the tie-beams 3 by 10 in, of the same material, the thrust in the rafter 30 000 lb, and its inclination  $30^\circ$ .

**Solution.** The horizontal component of 30 000 lb at  $30^\circ$  is practically 26 000 lb. Then  $S = 26$  000 lb and the shear = 13 000 lb.  $B = 6$  in and  $L = 9$  in.

Bearing per inch of length on the bolt =  $26\ 000/6 = 4\ 333$  lb  
Bending moment =  $26\ 000 \times 9/12 = 19\ 500$  in-lb

In Table IX, a  $1\frac{1}{8}$ -in steel bolt is found to be necessary to resist a shear of 13 000 lb, and a  $2\frac{1}{4}$ -in bolt for a bending moment of 19 500 in-lb. To resist 4 333 lb end-bearing pressure on 1 in a larger bolt is required than is given in Table VII. Dividing 4 333 by 1 200, the allowable bearing on Douglas fir, a  $3\frac{1}{2}$ -in bolt is found to be necessary. This is larger than it is desirable to use so the joint must be redesigned with a view to reduce the bearing pressure.




Fig. 29. Bolt through Rafter and Tie-beam




Fig. 30. Bolt in Wooden Tie-beam

bolt. If an 8 by 8-in strut and 4 by 8-in tie-beams are used,  $B$  becomes 12 in. This gives

Bearing pressure =  $26\ 000/8 = 3\ 250$  lb per inch of length of the bolt

Bending moment =  $26\ 000 \times 12/12 = 26\ 000$  in-lb

The total shear at the section on one side of the strut is the same as before.

From Table VII it is found that a  $2\frac{3}{4}$ -in bolt is large enough to provide for bearing and that a  $2\frac{1}{2}$ -in bolt is sufficient for the bending as given in Table I. Hence if an 8 by 8-in strut is used, there must be a  $2\frac{3}{4}$ -in bolt and the distance  $D$  must be  $15\frac{1}{2}$  in (Table I).

**Example 12.** For the same construction as in Fig. 29 and the same conditions as in the first part of Example 11, it is required to determine the size of the bolts when it is necessary to use three.

**Solution.** The shear, bearing, and bending moment are the same as in Example 11, but because there are three bolts each quantity is divided by 3 to determine the force resisted by each.

Shear =  $13\ 000/3 = 4\ 333$  lb and requires a  $\frac{3}{4}$ -in steel bolt (Table IX)

Bearing =  $4\ 333/3 = 1\ 444$  lb and requires a  $1\frac{1}{4}$ -in bolt (Table VII)

Bending moment =  $19\ 500/3 = 6\ 500$  in-lb, and requires a  $1\frac{1}{2}$ -in steel bolt (Table IX).

In this case the bending moment determines the size of the bolts, which may be arranged as shown by the dotted circles in Fig. 29.

**Example 13.** It is required to determine the diameter of the bolt for the construction shown in Fig. 30, in which the inner beam is of Douglas fir and 7 by 8 in in section, and the outer beams 3 by 8 in, the tension being 24 000 lb.

**Solution.**  $S = 24\ 000$ ;  $B = 6$  in;  $L = 9$  in.

Single shear on the bolt =  $24\ 000/2 = 12\ 000$  lb

Bearing-pressure per inch of length of bolt =  $24\ 000/6 = 4\ 000$  lb

Bending moment =  $24\ 000 \times 9/12 = 18\ 000$  in-lb

From Table IX a  $1\frac{1}{4}$ -in steel bolt is found sufficient to resist the shear, and a  $1\frac{1}{2}$ -in bolt large enough to resist the bending. In Table VII the largest bolt considered, 3 in, is too small in bearing value. Dividing the load to be resisted by 1200 gives  $3\frac{1}{2}$  in, as the diameter necessary to resist the bearing. The distance  $D$  must be  $4\ 000/(2 \times 130) + 3\frac{1}{2}$  in or  $18\frac{3}{4}$  in.

**Example 14.** If two bolts are used, one behind the other, it is required to determine the diameter of the bolt that should be used, the conditions and loading being the same as in Example 13.

**Solution.** Dividing the quantities obtained in Example 13 by 2,

Single shear = 6 000 lb and requires a  $\frac{7}{8}$ -in steel bolt

Bearing = 2 000 lb and requires a 2-in bolt

Bending moment = 9 000 in-lb and requires a  $1\frac{1}{4}$ -in steel bolt

The allowable bearing on a  $1\frac{1}{4}$ -in bolt is ( $2\frac{1}{2}\%$ ) less than the required amount, but in general, since the other requirements are more than satisfied, the  $1\frac{1}{4}$ -in bolt would be used. For the  $1\frac{1}{4}$ -in bolt, the distance  $D$  is  $9\frac{1}{4}$  in. The distance between the bolts may be increased somewhat beyond the value given in




Fig. 31. Bolts in Wooden Tie-beam

Table VII, and they may be located out of the same line as a further protection against splitting.

**Case IV. Bolt-and-Strap Joints in Trusses.** The construction shown in Fig. 32 is sometimes used to connect the foot of the rafter of a wooden truss to the tie-beam. When the distance  $D$  is sufficient to resist the shear due to the thrust of the rafter, the strap is of value only in holding the rafter in place and there are no greater pressures brought upon the BOLT. When it is impossible to make  $D$  the necessary length, the BOLT and STRAP must be designed to resist the full force in the direction of the STRAP.

As the STRAP is usually not more than from  $\frac{1}{2}$  to  $\frac{3}{4}$  in thick, its width is such that the bearing between it and the rafter is small compared with that between the BOLT and the rafter. The forces acting on the joint are the only ones that need consideration. These are:

SINGLE SHEAR =  $S/2$  = the tension in the strap on one side

BEARING PRESSURE per inch of length =  $S/B$ , where  $B$  is the width of the tie-beam in inches

BEARING PRESSURE per inch of length between strap and bolt =  $S/t$

To find the value of  $S$ , the force-polygon is drawn as shown at the right in Fig. 32.  $T$  is drawn parallel to the axis of the rafter and with a length, to a




Fig. 32. Strap and Bolt at Foot of Rafter

venient scale, equal to the thrust. From the end  $a$  an indefinite line is drawn parallel to the axis of the strap, and from  $b$  another line perpendicular to the SEAT of the rafter. These intersect at  $c$ , so that  $ac$ , measured by the scale used in laying off  $T$ , is the magnitude of the force  $S$  in the strap. If the rafter rests on top of the beam,  $bc$  is vertical, but if the tie-beam is dapped, as shown by the dotted line, the line from  $b$  is drawn perpendicular to the bolt of the notch, making the intersection at  $c'$ . It is seen that notching the beam in this way increases the stress in the strap.

**Example 15.** It is required to determine the size of a strap and pin to hold the rafter without notching into the tie-beam of a long-leaf yellow-pine truss. The rafter is 6 by 6 in, is inclined at an angle of  $45^\circ$  and is under a compressive stress of 18 000 lb. The tie-beam is 6 by 8 in in section.

**Solution.** Since the inclination is  $45^\circ$ , a consideration of the force-polygon in Fig. 32 shows  $ab$  equal to  $ac$ , so that

The force  $S$  = the thrust  $T$  = 18 000 lb

Single shear on bolt =  $18\,000/2 = 9\,000$  lb

Tension in strap on one side = 9 000 lb

Bearing pressure per inch of bolt against wood =  $18\,000/6 = 3\,000$  lb

Bearing pressure in pounds per inch between strap and bolt =  $9\,000/t$ , in which  $t$  equals the thickness of the strap.

The allowable pressure between the strap and the top of the rafter is 350 lb per sq in (Table VII), which, on the 6-in rafter, gives

Allowable load per inch of width of strap =  $6 \times 350 = 2\,100$  lb

The strap then must be  $18\,000/2\,100$  or 8.6 in wide. At 10 000 lb per sq in in tension the necessary section of the strap is 0.9 sq in, requiring a thickness

at 0.1 in, a sufficient thickness if the strap were strong enough to develop a uniform pressure over the rafter. It is not good practice, however, to use such material, because of the danger of loss of strength due to corrosion. No material less than  $\frac{3}{8}$  in thick should be used in such places.

The bearing-pressure per inch, between the strap and the bolt, for a  $\frac{3}{8}$ -in bolt  $p = 9\,000 / \frac{3}{8} = 24\,000$  lb

The bolt, then, must take a single shear of 9 000 lb, a bearing pressure of 24 000 lb against the wood for each inch of length, and a bearing of 24 000 lb per inch of length against the strap. From Table IX a  $1\frac{1}{8}$ -in steel bolt is found to resist the shear, from Table V a 2-in bolt is large enough to resist the bearing from the strap, and from Table VII a  $2\frac{1}{4}$ -in bolt is found necessary to resist the 3 000-lb bearing from the wood per inch of length of bolt. This makes the  $2\frac{1}{4}$ -in bolt satisfactory for the joint.

The pressure from the bolt to the wood, however, is not parallel with the grain but inclined at  $45^\circ$ . The allowable pressure against wood across the grain is about one-fourth of that with the grain. According to the formula in Chapter XXVIII, page 1138, the allowable pressure per square inch for this case is 612 lb instead of the 1 400 per sq in allowed for direct compression with the grain. The reduced allowable pressure makes it necessary to use a larger bolt, say a 5-in bolt, which would be impracticable, for it would almost cut the tie-beam in two. It thus appears that this form of joint is not good design for a truss of this span. For shorter spans the joint may be made in accordance with the requirements of Table I. It has the advantage of not requiring any projections below the tie-beam.

**Case V. Bolts in Tension to Hold the Foot of a Rafter.** In the joint shown in Fig. 33 the bolt is subject to DIRECT TENSION only. The amount of the tension  $S$  is found by the construction explained in Case IV. The rafter may be let into the tie-beam or rest on top of it, the tension in the bolt being less in the latter case;




Fig. 33. Bolt in Tension at Foot of Rafter

but it is easier to erect the truss if the rafter is NOTCHED INTO the tie-beam from  $1\frac{1}{4}$  to  $1\frac{1}{2}$  in for ordinary spans and loads, to hold it while the pieces are fitted. After this is done, the holes may be bored exactly where required.

Whenever  $S$  exceeds about 10 000 lb for trusses made of timber for which the highest bearing stresses are allowed, a CAST PLATE, as shown in Fig. 34 and made to fit the inclination of the bolt, should be let into the tie-beam at the head of the bolt to distribute the pressure. The diameter of the hole for the bolt should be  $\frac{1}{8}$  in larger than the diameter of the bolt. The distance  $D$  must be sufficient to provide for the horizontal component of  $S$ , at the allowed shearing stress of the material for shear with the grain.

The horizontal component is found by drawing a vertical line from  $c$  and a horizontal line from  $a$  and measuring  $ad$  to the scale of the diagram. For this force must be less than the product of the distance  $D$ , the width of the tie-beam and the allowed shearing-stress given in Table I, page 412.




Fig. 34. Special Washer

**Example 16.** For the same conditions as in Example 15, for the size of members and the thrust in the rafter, it is required to determine the diameter of the bolt and the distance  $D$  for a joint of the type shown in Fig. 33.

**Solution.** To find  $S$ , draw  $T$  equal to 18 000 lb, at a convenient scale, parallel to the rafter. At  $a$ , draw an indefinite line perpendicular to the rafter and at  $b$  a line perpendicular to THE SEAT of the rafter. This makes  $S$  greater than in Example 15, as  $ac$  now scales 27 000 lb. From Table IX, a  $1\frac{3}{4}$ -in. bolt is sufficient to take this in direct tension. The horizontal component found as directed above, scales 19 000 lb. The width of the tie-beam is 6 in, which at the allowed shearing-stress, 150 lb per sq in, gives 900 lb as the strength that must be cared for by each inch of  $D$ . 19 000 lb divided by 900 gives 21.1, the required distance  $D$ . (See, also, Chapter XXVIII, Joints in Wood Trusses.)

The compression against the grain on the end of the cast-iron washer must also be investigated. 19 000 lb divided by the width, 6 in, gives 3 166 lb per inch must be resisted per inch of width of beam. At 1 400 lb per sq in, as an allowable working stress, this makes it necessary to set the casting  $2\frac{1}{4}$  in into the lower side of the beam, which exceeds the depth usual in ordinary practice. Some tests made at the Massachusetts Institute of Technology on large timbers and reported in 1897, indicated that for a TEST CARRIED TO RUPTURE the stresses prescribed for usual designs might safely be more than doubled. Tests on timber under LONG-CONTINUED LOADING indicate that rupture finally occurred for stresses approximating one-half of those developed in TESTS CARRIED TO IMMEDIATE FAILURE. This, and the fact that decay may affect the strength of the members, emphasizes the wisdom of using CONSERVATIVE WORKING-STRESS in this material.




Fig. 35. Joint with Two Bolts in Direct Tension

**Example 17.** It is required to determine the size of bolts for the joint shown in Fig. 35, the thrust being 65 500 lb and the truss-members being made of long-leaf yellow pine.

**Solution.** The tension in the bolts is found first by drawing the force-polygons as shown at the right in the figure. To the same scale that  $ab$  represents 65 500 lb,  $ac$  represents 96 500 lb. If the load is equally divided between the bolts, each has a tension of 48 250 lb. From Table IX this force requires a  $2\frac{1}{4}$ -in. bolt.

The horizontal component  $ad$  is 68 350 lb, which must be resisted by the shearing strength of the wood between the end of the cast-iron washer on the



of the tie-beam and the end of the beam resting on the wall. At 150 lb per sq in, this requires  $68\,350/150$ , or 455 sq in. If the beam is 8 in wide, this gives a length of 57 in along the beam from the washer to the end.

The bearing of the cast-iron washer against the end-fibers of the tie-beam is 63 250 lb. At an allowable pressure of 1 400 lb per sq in the depth of washer should be  $68\,350/(8 \times 1\,400) = 6.1$  in. This would almost cut the beam in two. The ultimate strength of the wood in compression is about five times the working stress, and since a considerable part of the horizontal force is resisted by the body of the bolt as well as by the friction of the washer, it is probable that with washers  $\frac{3}{4}$  in thick there would be little sign of weakness at the joint even when the truss is fully loaded.

Theoretically the washers on the top surface of the rafter should be determined by the allowable working stress in compression across the fibers. This for long-leaf pine is taken at 350 lb per sq in (Table VI, page 454). The area,  $A$ , is  $48\,250/350$ , or 138 sq in. This requires a washer  $11\frac{3}{4}$  in square. The 8 by 8-in washer used, assumes a pressure of 755 lb per sq in, but as the tests of the Forest Service of the United States Department of Agriculture give 3 480 lb per sq in as the elastic limit for long-leaf yellow pine, it is very likely that there would be no signs of injury at this point, other than a SLIGHT INDENTATION, when the truss is fully loaded.

CHAPTER XIII

BEARING-PLATES AND BASES FOR COLUMNS, BEAMS AND GIRDERS. BRACKETS ON CAST-IRON COLUMNS\*

By

HERMAN CLAUDE BERRY

PROFESSOR OF MATERIALS OF CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

1. Bearing-Plates and Bases

**The Purpose of Bearing-Plates or Bases.** When a heavily loaded column, beam or girder is supported on a masonry wall or pier, a BEARING-PLATE or BASE of suitable dimensions must be used to distribute the load so that the pressure will not exceed the safe BEARING STRENGTH of the masonry (Table I).




Fig. 1. Simple Bearing-plate






Fig. 2. Beveled Cast-iron Plate with Pin



SECTION



PLAN

Fig. 3. Ribbed Cast-iron Plate

The BEARING-PLATE is designed to be stiff enough to distribute the pressure under it uniformly, and its area is determined by dividing the load on the allowable pressure per unit of area (Table II).

**Simple Bearing-Plates.** Fig. 1 shows a SIMPLE BEARING-PLATE under a beam. It may be a steel or cast-iron rectangular plate of sufficient thickness to prevent its bending at the edge of the beam from the pressure of

\* See, also, Chapter XIV, Subdivisions 8 to 11.

ary below. For anchors for steel beams on bearing-plates, see Chapter I, page 619.

**Cast-Iron Plates with Pin.** Fig. 2 is a cast-iron PLATE WITH A DOWEL-PIN fit inside the shell of a cast-iron column, or into a recess cut in the bottom of a wooden one. The pin holds the base-plate in position.

**Cast-Iron Ribbed Bases.** Fig. 3 is a cast-iron RIBBED BASE for a large cylindrical cast-iron column, capable of supporting a load heavy enough to sink a plate similar to the one shown in Fig. 2, at the edges of the column, unless the plate were made unduly thick.

**Table I. Allowable Bearing Pressure on Different Kinds of Masonry**

Kind of masonry	Allowable pressures	
	Lb per sq in	Tons per sq ft
From the building laws of New York, 1917		
brick, in lime mortar . . . . .	110	8
in lime-and-cement mortar . . . . .	160	11½
in Portland-cement mortar . . . . .	250	18
rubble masonry, in Portland-cement mortar . . . . .	140	10
concrete, Portland cement, 1 : 2 : 4 . . . . .	500	36
From the building laws of Chicago, 1916		
rubble, in lime mortar . . . . .	60	4.32
in Portland-cement mortar . . . . .	100	7.2
coarse rubble, in lime mortar . . . . .	120	8.6
in Portland-cement mortar . . . . .	200	14.4
shell, limestone, in Portland-cement mortar . . . . .	400	28.8
granite, in Portland-cement mortar . . . . .	600	43.2
concrete, Portland-cement, 1 : 2 : 4, hand-mixed . . . . .	350	25.4
machine-mixed . . . . .	400	28.8

**The Bases of the Steel Cores of Composite Columns** used in reinforced-concrete construction have areas sufficient to distribute the loads of the columns on the concrete in the footings at the allowable working stress of the concrete. (See also, page 474, Figs. 14 and 15.)

**Example 1.** The basement-columns of a warehouse are designed for a load of 12 000 lb each. It is required to determine the size of the base-plates to use on the concrete foundations. (Table II used.)

**Solution.** At an allowable pressure of 208 lb per sq in, the required area is 12 000/208 or 1 020 sq in, or about 32½ in square. The plan and section of the base-plate is shown in Fig. 3.

**Forms of Base-Plates.** For small columns and wooden posts with light loads, PLAIN FLAT PLATES of cast iron or steel are generally used. The cast-iron plate may have a raised ring or cross to fit inside a hollow metal column, or be of a height from 1½ to 2 in in height for a wooden one. If the plate is very thick the edges may be beveled to save weight, as shown in Fig. 2, but no part should be less than about ¼ in thick.

Table II. Allowable Loads on Standard, Steel Bearing-Plates on Walls

Bearing on wall, in	Size of plate, in	Safe bearing value of plate in pounds		
		Bricks laid in mortar of		
		Lime, 112* lb per sq in	Lime and cement, 162* lb per sq in	Cement, 216* lb per sq in
6	6×6	4 070	5 800	7 500
	6×8	5 400	7 800	10 000
	6×10	6 700	9 700	12 500
8	8×8	7 200	10 200	13 300
	8×10	9 000	12 100	16 600
	8×12	10 700	15 500	20 000
10	10×10	11 200	16 200	20 800
	10×12	13 450	19 500	25 200
	10×14	15 700	22 700	27 900
12	12×12	16 150	23 300	30 000
	12×14	18 800	27 400	35 000
	12×16	22 000	31 200	40 100
	12×18	24 200	34 500	45 000
14	14×14	22 100	31 800	40 800
	14×16	25 000	36 300	46 600
	14×18	28 200	40 800	52 400
	14×20	31 400	45 400	58 200
16	16×16	28 700	41 500	53 200
	16×18	32 300	46 600	59 800
	16×20	35 800	51 900	66 700
	16×22	39 500	57 000	73 200

\* These values are slightly different from those of the New York Code (1916)

**Ribbed Bases.** If the calculated size of a bearing-plate is so large the projection beyond the edge of the column would be more than about 6 RIBBED BASE similar to that shown (Fig. 3) for a cylindrical column is. For such bases it is unnecessary to consider the transverse stresses. If these bases are bolted to the columns they add greatly to the general strength of the supporting members because of the greater width of such bases.

**Proportions of Ribbed Bases.** The HEIGHT *H* of this type of base should be approximately equal to the PROJECTION *P*, and the DIAMETER *D* equal to the diameter of the column. The projection *C* should be at least 3 in to permit the bolting of the column to the base. The THICKNESS of all parts of the base should be the same and approximately equal to the thickness of the column shell. There must be no thin webs as they result in breakage from shrinkage stresses.

**Base-Plates for Steel Columns** are usually made of STEEL PLATES and are as shown on the channel-columns in Chapter XIV, Figs. 17, 18 and 19. Cast iron bases are sometimes used for very heavy columns. If conditions are favorable to the action of corrosion the cast iron is to be preferred.

The Area of Bearing-Plates under Beams and Girders is found in the same manner as the area of plates under columns. If the load on the beam is uniformly distributed over the beam or concentrated at its middle, the required area of the plate is one-half the total load on the beam divided by the allowable bearing per unit of area on the masonry; but if the load is a moving load, the greatest possible end-reaction must be divided by the allowable bearing. For example, a heavily loaded truck standing near the end of the beam causes a pressure on the bearing-plate much greater than one-half its weight. The reaction for the actual conditions must be found by the methods explained in Chapter IX.

The Thickness of the Bearing-Plate is found by the formula used to determine the flexure of beams. It must be determined in each case. For a typical case the forces acting are shown in Fig. 5, which represents a transverse




Fig. 4. Simple Bearing-plate under I-Beam




Fig. 5. Forces Acting on Half of Bearing-plate

vertical section through one-half the plate. The vertical section at  $C$ , and through and parallel with the web of the I beam, is taken through the center of the plate, which is the dangerous section, or section of maximum bending moment.

In Figs. 4 and 5,  $b'$  is the bearing depth on the wall;

$l$  is the length of the plate, parallel with the wall;

$b$  is the width of the flange of the beam;

$R$  is the load on the bearing-plate.

Replacing the uniform loads by the equivalent forces at the center of gravity of each, these forces are represented by the longer arrows. The bending moment at the section at  $c$  is the same as the moment of the concentrated forces, viz.,

$$M = (R/2 \times l/4) - (R/2 \times b/4)$$

$$M = R/2 \times (l - b)/4$$

This is equal to the resisting moment at the same section  $c$ , or, at stress  $S$ , in which  $I/c$  is the section-factor. (See Chapter XV.) This reduces to  $Sb'/6$ . Equating the bending moment and the resisting moment there results

$$Sb'/6 = R(l - b)/8$$

$$t = 0.866 \sqrt{R(l - b)/Sb'}$$

or  $S = 3000$  for cast iron, this reduces to

$$t = 0.0158 \sqrt{R(l - b)/b'} \quad (1)$$

or  $S = 16000$  for steel plates, it becomes

$$t = 0.00685 \sqrt{R(l - b)/b'} \quad (2)$$

**Example 2.** It is required to determine the length and thickness of a cast iron bearing-plate under a wooden beam which is 10 in wide and supports a load of 24 000 lb. The plate is 8 in wide and bears that width on a brick wall laid up in lime mortar.

**Solution.** The load on the plate is  $24\,000/2 = 12\,000$  lb. From Table I the area of the plate is  $12\,000/112 = 108$  sq in. Hence, if the width of the plate is 8 in, its length must be  $13\frac{1}{2}$  in. Then, from Formula (1)

$$t = 0.0158 \sqrt{12\,000 (13\frac{1}{2} - 10)/8} = 1.15 \text{ in}$$

A plate  $1\frac{1}{4}$  in thick would be used.

**Example 3.** It is required to determine the length and thickness of a steel bearing-plate under the end of a 24-in 79.9-lb I beam supported on a 12-in brick wall laid up in lime-and-cement mortar and carrying a load of 60 000 lb. The width of the flange of the beam is 7 in. (See Table I.)

**Solution.** The load on the plate is  $60\,000/2 = 30\,000$  lb

The area of the plate =  $30\,000/160 = 187\frac{1}{2}$  sq in

The length of the plate is  $187.5/12 = 15.6$  in

Then, from Formula (2)

$$t = 0.00685 \sqrt{30\,000 (15.6 - 7)/12} = 1 \text{ in}$$

**Standard Sizes of Steel, Wall Bearing-Plates.** These are given in Table II, and are based upon ALLOWABLE PRESSURES of 112, 162 and 208 lb per sq in. These UNIT PRESSURES are based upon the ALLOWABLE PRESSURES of the New York and Philadelphia building laws which are

expressed in tons per square foot. Because of the complicated formula on which the thickness depends, it is best to compute the thickness for each case.

**Bearing-Plates under Columns.** The general rules already given for the proportions of RIB BASES similar to that shown in Fig. 3 are a sufficient guide for detailing such bases; but in case where FLAT PLATES are used under columns, their thickness must be computed according to the principles governing bending. The stress in a FLAT PLATE supported at the middle and subjected to a uniform load can be determined by the ordinary methods of mechanics.

The approximate solution here given is generally

used in the design of BASE-PLATES and COLUMN-FOOTINGS. It gives values found to be safe in practice.




Fig. 6. Flat Bearing-plate for Column

In Fig. 6, let  $B$  = the length of the side of the plate as determined by allowable pressure on the supporting masonry;

$D$  = the side or diameter of the column;

$P = (B - D)/2$  = the projection of the plate;

$t$  = the thickness of the plate;

$A'$  = the area of the plate outside the column;

$w$  = the allowable bearing pressure on the masonry due to load on the column.

Then in Fig. 6, the pressure on one-fourth of  $A'$ , shown enclosed by the dashed lines in the figure, causes shearing and bending stresses in the section of plate along the line  $ab$ . Considering the part enclosed and taking moments about the section  $ab$ , the following equation is obtained from the usual

moment formula. (See Chapter XV, page 557.) That is, the resisting moment equals the bending moment, or

$$SI/c = \frac{1}{4} A' P w$$

For the rectangular section at  $ab$ , this may be written

$$S t^2 D / 6 = \frac{1}{4} A' P w$$

hence

$$t = \sqrt[3]{3 A' P w / 2 S D}$$

which becomes for  $S = 3000$

$$t = 0.0224 \sqrt{A' P w / D}$$

and for

$$S = 16000$$

$$t = 0.0097 \sqrt{A' P w / D}$$

**Example 4.** It is required to determine the size and thickness of a cast-iron bearing-plate to be used under a wooden post 12 in square in cross-section and designed for a load of 115 200 lb. The plate is to be set on brickwork laid in cement mortar in New York. (See Table I.)

**Solution.** The required area of the base is  $115\,200 / 250 = 461$  sq in.  $\sqrt{461} = 21.47$  and a 22-in. square plate would be used.

Then

$$A' = 461 - 144 = 317 \text{ sq in}$$

$$P = (22 - 12) / 2 = 5 \text{ in}$$

$$D = 12 \text{ in}$$

$$w = 250 \text{ lb per sq in}$$

hence

$$t = 0.0224 \sqrt{317 \times 5 \times 250 / 12} = 4 \text{ in}$$

This thickness may be beveled to  $1\frac{1}{2}$  in at the edge. The computed thickness is greater than is usual for such plates, some formulas having more practical constants which really assume a stress of about 10 000 lb per sq in in cast iron bending.

If the plate is made of steel

$$t = 0.0097 \sqrt{317 \times 5 \times 250 / 12} = 1\frac{3}{4} \text{ in}$$

## 2. Bearing-Brackets on Cast-Iron Columns

**The Usual Column-Connections** for fastening beams and girders to cast-iron columns are shown in Fig. 7.\* The end of the beam or girder is set on **PLATE P**, under which is a **BRACKET-SUPPORT C**, cast on the side of the column. For a single beam, one bracket is sufficient; for wide beams or girders there should be two ribs. The ends of the beams are fastened to the column by **bolts to LUGS L**, cast on the column above the bracket. Sometimes a column is fastened by bolts passing through the bottom flange of the beam and through a **shelf-plate**. This connection greatly decreases the lateral stability of a column and should not be used.

**The Shelf and Brackets**, when loaded, are subject to **SHEARING** and **BENDING-STRESSES**. The **SHEAR** at the outer surface of the column-shell is equal to the end-reaction of the beam it supports. The **BENDING-STRESS** is due to the location of the load on the shelf-plate at some distance from the surface of the column. It causes a tension at the top of the bracket which tends to tear the shell of the column, and causes, also, a compression at the foot of the bracket. The **THICKNESS OF THE RIB** must be great enough to withstand the compression from the load above; and since the stress is variable along a section,

\* See also, Figs. 5 and 7, pages 457 and 458.

as along the line  $X$ , a rough approximation may be made by assuming the stress at the extreme edge to be twice the average stress, and by further assuming that the section in the rib takes care of all the compression. This makes unnecessary to find the CENTER OF GRAVITY and the MOMENT OF INERTIA of the section at  $X$ , both of which must be known if the FLEXURE-FORMULA is used. This procedure, also, makes unnecessary any assumption as to the true position of the CENTER OF PRESSURE on the top surface of the bracket. With the thickness of rib given in the tables there is an ample FACTOR OF SAFETY for any load.




Fig. 7. Cast-iron Columns with Bearing-brackets

that may be applied through a beam. The double ribs are required when beams are used, not for strength, but to prevent the failure of the shelf under ECCENTRIC LOADING.

**Tests of Cast-Iron Brackets.** Brackets of cast-iron columns tested by the New York Building Department gave a SHEARING STRENGTH of 4 200 lb per sq in on the section at the column when the load was applied at the end of the bracket, and an average of 8 000 lb per sq in when the load was distributed over the bracket-shelf. The RANGE OF STRESS in the first case was from 2 450 to 5 600 and in the second from 4 100 to 10 900 lb per sq in. In seventeen out of twenty-two tests the MANNER OF FAILURE was the tearing out of a hole in the body of the column. It appears that when the thickness of the rib and shelf is the same as that of the shell of the column, there is generally ample strength for the support of beams and girders; but that in the case of very heavily loaded beams, the SHEARING and CRUSHING STRENGTH should be investigated. From the results of the tests mentioned, a low WORKING STRESS FOR SHEAR must be assumed.

**The Bevel of Brackets.** If the shelf  $P$  (Fig. 7), on which the beam rests, is cast SQUARE with the column, when the beam deflects, the load is brought to the extreme end of the bracket, causing an increased bending-stress in




socket and connections and tending to tear a hole in the column-shell. To avoid this the bracket-shell should be sloped downward, away from the column and should have a BEVEL of  $\frac{1}{4}$  in to the foot.

**Standard Connections for Cast-Iron Columns.** Table III, published originally in the Passaic Rolling Mill Handbook, and widely used by other manufacturers, will be found useful when detailing cast-iron columns.

**Table III. Standard Connections for Cast-Iron Columns**

All dimensions are in inches

Depth of base	A	B	C	D	E	F	G	H	K	Thickness of lugs	Holes cored for $\frac{3}{4}$ -in bolts
24	5	5	6	$10\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$	2	$1\frac{1}{2}$	2	1	Holes cored for $\frac{3}{4}$ -in bolts
18	4	5	6	$10\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{2}$	2	$1\frac{1}{2}$	2	1	
15	4	$3\frac{1}{2}$	$5\frac{1}{2}$	$9\frac{1}{2}$	$1\frac{1}{2}$	$1\frac{1}{4}$	2	$1\frac{1}{2}$	$1\frac{3}{4}$	1	
12	3	3	$4\frac{1}{2}$	$7\frac{3}{4}$	$1\frac{1}{4}$	$1\frac{1}{4}$	2	$1\frac{1}{2}$	$1\frac{1}{2}$	1	



Depth of base	A	B	C	D	E	F	G	H	K	Thickness of lugs	Holes cored for $\frac{3}{4}$ -in bolts
18	$3\frac{1}{4}$	$3\frac{1}{2}$	4	7	$1\frac{1}{4}$	1	2	$1\frac{1}{2}$	$1\frac{1}{2}$	1	Holes cored for $\frac{3}{4}$ -in bolts
9	3	3	4	7	1	1	2	$1\frac{1}{2}$	$1\frac{1}{2}$	1	
8	$2\frac{1}{2}$	3	4	7	1	1	2	$1\frac{1}{2}$	$1\frac{1}{2}$	$\frac{3}{4}$	
7	$2\frac{1}{2}$	$2\frac{1}{2}$	4	7	1	1	2	$1\frac{1}{2}$	$1\frac{1}{4}$	$\frac{3}{8}$	

## CHAPTER XIV

# STRENGTH OF COLUMNS, POSTS AND STRUTS

By  
CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

### 1. General Principles and Definitions

**Slenderness-Ratio.** The manner in which a material fails under compression or pressure depends not only upon its nature, but also upon its dimensions and form. The ratio of its length, in inches, to its diameter or least lateral dimension, in inches,  $l/d$ , or the ratio of its length to its least radius of gyration is its **SLENDERNESSE-RATIO**.

The following average limits of slenderness-ratios are generally recognized in engineering practice:

Solid wooden columns,  $l/d$  from about 8 to 30;  
Solid wooden columns,  $l/r$  from about 30 to 100;  
Hollow cast-iron columns,  $l/d$  from about 8 to 20;  
Hollow cast-iron columns,  $l/r$  from about 10 to 70;  
Steel columns,  $l/r$  from about 30 to 130.

**Three Classes of Columns.** (1) The actual compressive strength of a material must be determined on very short specimens in which there is no tendency to bend or to buckle. (2) The load required to break the specimen does not change much until  $l/d$  is about 8 or 10, or  $l/r$  is about 25 or 30. When these ratios are exceeded, the specimens tend to fail partly by direct compression and partly by bending. (3) When  $l/r$  is greater than about 200, the column fails entirely by bending.

### 2. Strength of Short Wooden Columns

**The Safe Load for a Short Wooden Column,** the length of which is not more than 10 times the least dimension, may be computed by the formula

$$\text{Safe load} = \frac{\text{area of cross-section} \times S}{\text{factor of safety}}$$

in which  $S$  denotes the crushing strength of the given material as stated in Table I.

**The Factor of Safety** to be selected depends upon the place where the column is used, the load which comes upon it, the quality of the material and the size of the column. In large measure, upon the value given to  $S$ . For lumber of ordinary quality containing no very bad knots, a **FACTOR OF SAFETY** of five may be used; or, in other words, the safe stress per square inch of section-area may be taken as one-fifth of the values given in Table I. If the column is badly season-checked, warped, grained, or contains bad knots, a larger factor, say six or seven, should be used. The character of the load, also, should be taken into consideration in determining the factor of safety. Thus for a wooden post supporting a brick wall a larger factor should be used than for one supporting a floor, as in the former case the full load is at all times on the post, and the least reduction of its section-

of fire might cause it to give way. Wooden posts supporting machinery, or struts in railway bridges, should have a factor of safety of from six to eight, if the values of  $S$  given in Table I are used.

Table I.\* Average Crushing-Loads in Pounds per Square Inch, for Building Materials

Materials	Crushing-loads, lb per sq in	Materials	Crushing-loads, lb per sq in
	$S$		$S$
Stone, brick, concrete		Woods (continued)	
and masonry, see Chapter V		Cypress.....	3 500
		Hemlock.....	4 000
Metals		Oak, white.....	5 000
Cast iron.....	80 000	Pine, long-leaf yellow.....	5 000
Wrought iron.....	55 000	Pine, short-leaf yellow.....	4 000
Steel, rolled shapes.....	60 000	Douglas fir.....	4 500
		Pine, Norway.....	3 500
Woods, with the grain†		Pine, white.....	4 000
Aspen.....	3 500	Redwood, California.....	4 000
Walnut.....	4 000	Spruce.....	4 500
		Whitewood.....	3 000

\* See, also, Table XVI, page 647, and Table I, page 1138.

† These are values for wooden columns under 15 diameters in height and are, of course, average values. For the safe loads, per sq in, on timbers, perpendicular to grain, see Table VI.

Example 1. What is the safe load for a long-leaf yellow-pine column, 10 by 10 in cross-section and 12 ft long, using a factor of safety of 5?

Solution. Area of cross-section = 100 sq in; safe load per sq in =  $5\ 000/5 = 1\ 000$ ;  $1\ 000 \times 100 = 100\ 000$  lb.

Example 2. It is required to support a brick wall weighing 80 000 lb by a Douglas-fir column 11 ft long. What should be the cross-section of the column?

Solution. As previously stated, for these conditions it would be wise to use a factor of safety of 6. Then the safe resistance per square inch of section-area =  $5\ 000/6 = 750$ ;  $80\ 000/750 = 106$  sq in required, about equivalent to a 10 by 10 in cross-section.

## Strength of Wooden Columns or Struts Over Ten Diameters in Length. Formulas

**Formulas for Wooden Columns.** If the length of a solid column exceeds ten times its least cross-dimension it is liable to bend under the load, and not to break under a less load than would break it if it were shorter and of same cross-section. To deduce a formula which will make the proper allowance for the length of a column has been the aim of many engineers, but their formulas have not always been exactly verified by actual results.

Until recently the formulas of Lewis Gordon and C. Shaler Smith have been generally used by engineers, but the extensive series of tests made by the Government at Watertown, Mass., on full-sized wooden columns, showed that these formulas did not agree with the results there obtained. James H. Stanwood in the year 1891 plotted the values of all the tests made at the Watertown Arsenal up to date on full-size wooden columns. From the results thus obtained

he deduced the following STRAIGHT-LINE FORMULA for long-leaf yellow-pine and white-oak columns:

$$\text{Safe load per square inch} = 1000 - 10 \times \frac{\text{length in inches}}{\text{breadth in inches}}$$

The author has carefully compared this formula with the results of actual tests, and with other formulas,\* and believes that for timber without serious defects and with not more than 10 or 12% of moisture, it meets the actual conditions as nearly as any other formula. He has therefore prepared Tables III, IV and V for the strength of round and square columns of the sizes generally used in practice. Of course other formulas must be used when required by certain city building laws. For other sizes the loads can easily be computed by the formulas. For columns having bad knots or other defects, or more than 10 or 12% of moisture, or which are to be exposed to the weather or known to be eccentrically loaded, a deduction of from 10 to 25% should be made from the values given in the tables.

The loads for columns of other species of wood were computed by the following formulas of the same form as that of Formula (2):

For Douglas fir and spruce,

$$\text{Safe load per square inch} = 850 - 8.5 \times \frac{\text{length in inches}}{\text{breadth in inches}}$$

For chestnut, hemlock, short-leaf yellow pine and white pine,

$$\text{Safe load per square inch} = 750 - 7.5 \times \frac{\text{length in inches}}{\text{breadth in inches}}$$

For cedar, cypress, redwood, Norway pine and whitewood,

$$\text{Safe load per square inch} = 625 - 6 \times \frac{\text{length in inches}}{\text{breadth in inches}}$$

In these formulas the breadth is the least side of a rectangular column, or the diameter of a round column. The round columns were computed for the least inch, to allow for being turned out of a square column, of the next size larger. The formulas were used only for columns with a diameter or least side exceeding 12 diameters for yellow pine and white oak, and exceeding 10 diameters for other woods.

#### 4. Tables of Safe Loads for Wooden Columns

Tables II, III, IV and V give the safe loads in pounds for round and square wooden columns of different cross-sections and lengths and of different kinds of wood. They were computed from formulas as explained above and under favorable conditions of material, seasoning and position in buildings.

\* There are many formulas for the safe loads per square inch of cross-section of wooden columns. Among those frequently used are the following:

American Railway Engineering and Maintenance of Way Association,

$$P/A = S(1 - l/60d)$$

Department of Agriculture,

$$P/A = S(700 + 15l/d)/(700 + 15l/d + l^2/d^2)$$

Winslow Formula (Chicago Law),

$$P/A = S(1 - l/80d)$$

In these formulas,  $P$  is the safe load in pounds,  $A$  the area of the cross-section in square inches,  $P/A$  the safe load in pounds per square inch,  $S$  the safe end-bearing capacity per square inch,  $l$  the length in inches and  $d$  the least side or diameter in inches. The formulas give smaller safe loads than those of Tables II, III, IV and V; but as the loads of these tables are to be DECREASED for unfavorable conditions and the loads determined from the three formulas mentioned INCREASED for favorable conditions, the results are about the same.

Table II. Safe Loads in Pounds for Long-Leaf Yellow-Pine and White-Oak Columns, Round and Square

Size of column in inches	Length of column in feet								
	8	10	12	14	15	16	18	20	24
4X6.....	18 200	16 800	15 360	.....	.....	.....	.....	.....	.....
5½ round.....	19 590	18 760	17 550	16 500	.....	.....	.....	.....	.....
6X6.....	30 200	28 800	27 400	25 900	25 200	24 500	.....	.....	.....
6X8.....	40 300	38 400	36 500	34 600	33 600	32 600	.....	.....	.....
6X10.....	50 400	48 000	45 600	43 200	42 000	40 800	.....	.....	.....
7½ round.....	38 540	37 130	35 710	34 300	33 590	32 890	.....	.....	.....
8X8.....	64 000	54 400	52 500	50 600	49 600	48 600	46 700	.....	.....
8X10.....	80 000	68 000	65 600	63 200	62 000	60 800	53 400	.....	.....
8X12.....	96 000	81 600	78 700	76 800	74 400	73 000	70 100	.....	.....
9½ round.....	70 900	61 970	60 190	58 350	57 429	56 580	54 800	.....	.....
10X10.....	100 000	100 000	85 600	83 200	82 000	80 800	78 400	76 000	.....
10X12.....	120 000	120 000	102 700	99 800	98 400	97 000	94 100	91 200	.....
10X14.....	140 000	140 000	119 800	116 500	114 800	113 100	109 800	106 400	.....
11½ round.....	103 900	103 900	90 912	88 730	87 690	86 550	84 160	82 290	.....
12X12.....	144 000	144 000	144 000	123 800	122 400	121 000	118 100	115 200	109 440
12X14.....	168 000	168 000	168 000	144 500	142 800	141 100	137 800	134 400	127 680
12X16.....	192 000	192 000	192 000	165 100	163 200	161 300	157 400	153 600	145 920
14X14.....	196 000	196 000	196 000	196 000	170 900	169 100	165 800	162 400	155 800
16X16.....	256 000	256 000	256 000	256 000	229 100	225 300	221 400	217 600	209 900
18X18.....	324 000	324 000	324 000	324 000	324 000	289 400	285 100	280 800	272 160
20X20.....	400 000	400 000	400 000	400 000	400 000	400 000	356 800	352 000	342 400

Table III. Safe Loads in Pounds for Douglas-Fir and Spruce Columns, Round and Square

Size of column in inches	Length of column in feet								
	8	10	12	14	15	16	18	20	24
4X6.....	15 500	14 280	13 050	.....	.....	.....	.....	.....	.....
5½ round.....	16 650	15 790	14 900	14 030	.....	.....	.....	.....	.....
6X6.....	25 704	24 480	23 256	22 032	21 420	20 808	.....	.....	.....
6X8.....	34 272	32 640	31 008	29 376	28 560	27 744	.....	.....	.....
6X10.....	42 840	40 800	37 760	36 720	35 700	34 680	.....	.....	.....
7½ round.....	32 740	31 540	30 340	29 140	28 540	27 940	26 740	.....	.....
8X8.....	47 870	46 240	44 600	42 970	42 160	41 340	39 710	.....	.....
8X10.....	59 840	57 800	55 760	53 720	52 700	51 680	49 640	.....	.....
8X12.....	71 808	69 360	66 910	64 460	63 240	62 000	59 560	.....	.....
9½ round.....	54 150	52 650	51 150	49 580	48 820	48 070	46 570	.....	.....
10X10.....	85 000	74 800	72 760	70 720	69 700	68 680	66 640	64 600	.....
10X12.....	102 000	89 760	87 300	84 860	83 640	82 400	80 000	77 500	.....
10X14.....	119 000	104 700	101 860	99 000	97 580	96 150	93 300	90 400	.....
11½ round.....	88 290	79 100	77 250	75 400	74 470	73 550	71 700	69 850	66 160
12X12.....	122 400	110 160	107 700	105 260	104 040	102 800	100 360	97 920	93 000
12X14.....	142 800	128 520	125 660	122 800	121 380	119 950	117 100	114 240	108 520
12X16.....	163 200	146 880	143 600	140 350	138 720	137 080	133 800	130 560	124 030
14X14.....	166 600	166 600	149 450	146 600	145 180	143 760	140 900	138 080	132 400
16X16.....	190 400	190 400	170 800	167 500	165 900	164 300	161 000	157 800	151 300
18X18.....	217 600	217 600	217 600	194 700	193 000	191 400	188 200	184 900	178 400

Table IV. Safe Loads in Pounds for Chestnut, Hemlock, Short-Leaf Yellow-Pine and White-Pine Columns, Round and Square

Size of column in inches	Length of column in feet								
	8	10	12	14	15	16	18	20	22
4X6.....	13 680	12 600	11 520	.....	.....	.....	.....	.....	.....
5½ round.....	14 700	13 900	13 160	12 370	.....	.....	.....	.....	.....
6X6.....	22 630	21 600	20 520	19 440	18 900	18 360	.....	.....	.....
6X8.....	30 240	28 800	27 360	25 920	25 200	24 480	.....	.....	.....
6X10.....	37 800	36 000	34 200	32 400	31 500	30 600	.....	.....	.....
7½ round.....	28 900	27 850	26 780	25 720	25 190	24 660	.....	.....	.....
8X8.....	42 240	40 768	39 360	37 880	37 120	36 480	35 000	.....	.....
8X10.....	52 800	50 960	49 200	47 360	46 400	44 600	43 760	.....	.....
8X12.....	63 360	61 152	59 040	56 830	55 680	54 720	52 500	.....	.....
9½ round.....	47 960	46 440	45 160	43 740	43 100	42 400	41 120	.....	.....
10X10.....	75 000	66 000	64 200	62 400	61 500	60 600	58 800	57 000	.....
10X12.....	90 000	79 200	77 040	74 880	73 800	72 720	70 560	68 400	.....
10X14.....	105 000	92 400	89 880	87 360	86 100	84 840	82 320	79 800	.....
11½ round.....	77 925	69 820	68 160	66 490	65 770	64 833	63 170	61 600	.....
12X12.....	103 000	108 000	95 040	92 880	91 700	90 700	88 560	86 400	84 240
12X14.....	126 000	126 000	110 800	108 300	107 000	105 840	103 300	100 800	98 260
12X16.....	144 000	144 000	126 700	123 800	122 300	120 900	118 000	115 200	112 400
14X14.....	147 000	147 000	147 000	129 300	128 100	127 000	124 400	121 900	119 400
16X16.....	192 000	192 000	192 000	192 000	176 500	168 900	166 100	163 000	159 800
18X18.....	243 000	243 000	243 000	243 000	243 000	217 000	213 800	210 600	207 400
20X20.....	300 000	300 000	300 000	300 000	300 000	300 000	267 600	264 000	260 400

Table V. Safe Loads in Pounds for Cedar, Cypress, Redwood, Norway Pine and Whitewood Columns, Round and Square

Size of column in inches	Length of column in feet								
	8	10	12	14	15	16	18	20	22
4X6.....	11 520	10 550	9 800	8 700	.....	.....	.....	.....	.....
5½ round.....	12 350	11 730	11 180	10 470	.....	.....	.....	.....	.....
6X6.....	19 080	18 216	17 352	16 490	16 050	15 620	.....	.....	.....
6X8.....	25 440	24 290	23 140	21 990	21 400	20 830	.....	.....	.....
6X10.....	31 800	30 360	28 920	27 480	26 760	26 040	.....	.....	.....
7½ round.....	24 220	23 380	22 540	21 660	21 260	20 820	.....	.....	.....
8X8.....	35 450	34 300	33 150	32 000	31 420	30 850	29 700	.....	.....
8X10.....	44 320	42 480	41 440	40 000	39 230	38 560	37 120	.....	.....
8X12.....	53 180	51 450	49 730	48 000	47 140	46 270	44 544	.....	.....
9½ round.....	40 000	39 000	37 860	36 800	36 230	35 730	34 670	.....	.....
10X10.....	62 500	55 400	53 960	52 520	51 800	51 080	49 640	48 200	.....
10X12.....	75 000	66 480	64 800	63 000	62 160	61 300	59 570	57 840	.....
10X14.....	87 500	77 560	75 600	73 500	72 520	71 510	69 500	67 480	.....
11½ round.....	64 930	58 390	57 140	55 800	55 170	54 550	53 100	51 950	.....
12X12.....	90 000	90 000	79 780	78 000	77 180	76 320	74 590	72 860	.....
12X14.....	105 000	105 000	93 170	91 050	90 050	89 000	87 020	85 000	.....
12X16.....	120 000	120 000	106 300	104 000	102 900	101 700	99 400	97 150	.....
14X14.....	122 500	122 500	110 350	108 350	107 400	106 400	104 460	102 300	.....
16X16.....	160 000	160 000	160 000	143 870	142 590	141 570	139 260	136 960	.....
18X18.....	202 500	202 500	202 500	202 500	183 060	181 760	179 170	176 580	.....
20X20.....	250 000	250 000	250 000	250 000	250 000	250 000	224 500	221 200	.....

### 5. Eccentric Loading of Wooden Columns

**General Principles.** When the load on a short column or post is not axial, as, when the column supports a girder on one side only, or when the weight on one girder is much more than that from the others, the load is said to be *eccentric*, and the distance from the point of application of the load to the axis of the column, denoted by  $p$ , is called the *eccentricity* of the load. It is evident that the stress in the column will increase with  $p$ , and that the total unit stress  $S$ , on the side of the column in which the compression is the greatest, will be greater than for equal axial load.

**Formula for Eccentric Load.** Suppose the eccentric load to be applied as shown in Fig. 1, then the sectional area of the required square or rectangular column may be computed by the following formula (See, also, page 486):

The sectional area of the column in square inches is

$$A = (P + P_1)/S + 6 P_1 p / S d \quad (6)$$

which  $A$  = sectional area in square inches

$P$  = concentric load on column in pounds

$P_1$  = eccentric load in pounds

$S$  = safe stress in pounds per square inch

$p$  = distance from axis of column to center of bearing in inches

$d$  = side of column parallel with girder, in inches

Assuming the value of  $S$ , the probable ratio of side to the length of the column should be taken account. Thus if it is probable that the length will not exceed 12 times the side, both being measured in inches, for oak, long-leaf yellow-pine or white-fir columns, or 10 times the side for other woods, then the value of  $S$  for short columns may be taken. If the ratio will probably be greater than this, then the probable ratio should be roughly stated and  $S$  computed for that ratio by the formula given for columns more than 10 or 12 diameters in length, as noted in preceding paragraphs.

**Example 3.** The lower post in Fig. 1 supports a total load on its cap-plate of 60 000 lb, including the reaction of 12 000 lb from girder A. What should be the size of the column if made of Douglas fir and if 12 ft in height?

**Solution.** As it is probable that the column will have to be 10 in square  $S$  may be taken from Table I. With a factor of safety of 5, this is equal to  $4\,500/5 = 900$  lb per sq in.  $P_1 = 12\,000$  lb,  $d = 10$  in and  $p$ , the distance from the axis of column to the center of bearing of the girder = 7 in. Then from Formula (6), the sectional area of the column is

$$A = \frac{60\,000}{900} + \frac{6 \times 12\,000 \times 7}{900 \times 10} = 66.6 + 56 = 122.6 \text{ sq in.}$$

Equivalent to a 12 by 12-in square column. From Table III, it may be seen that an 8 by 10-in column concentrically loaded will carry almost 60 000 lb.




Fig. 1. Eccentric Load on Wooden Column

Hence, the eccentric load from the girder increases the dimensions of the cross section of the column from 8 by 10 to 12 by 12 in.

For wooden columns having a length of over 12 diameters for Douglas fir and spruce and over 10 diameters for other woods the safe load per square inch should be found by using Formulas (3), (4) or (5).

**Example 4.** What size will be required for a white-oak column, 14 ft in length to carry a total load of 56 000 lb, 16 000 lb of which act as an eccentric load from a girder, the distance from the center of bearing of the girder to the column being 2 in.

**Solution.** From Table II, it is probable that at least a 10 by 10-in column will be required, so that *S* must be calculated by Formula (2).

$$S = 1\,000 - 10 \times \frac{\text{length in in}}{\text{breadth in in}}$$

Substituting,  $S = 1\,000 - 10 \times \frac{168}{10} = 832 \text{ lb per sq in}$

Substituting in Formula (6),

$$A = \frac{56\,000}{832} + \frac{6 \times 16\,000 \times 7}{832 \times 10} = 68 + 80 = 148 \text{ sq in}$$

equivalent to a 12 by 12-in column.

6. Metal Caps and Bolsters for Wooden Columns

**Use of Metal Post-Caps.** Whenever wooden posts are used in tiers, one above another, each post except the top one should have an iron cap-plate and the upper post should be set on the cap of the post below and not on the girder. Where a wooden post supports a girder, only, a wooden bolster may be used in place of the cap but modern approved metal post-caps are always preferable to wooden bolsters. Details of post-caps and bolsters are shown in Chapter XXII.

7. Crushing of Wood Perpendicular to the Grain

**Safe Unit Stresses.** The bearing of wooden girders, the ends of columns resting on girders, and washers on truss-rods, should be proportioned so that the quotient obtained by dividing the load by the bearing area will not exceed the safe unit stresses given in Table VI.

Table VI. Safe Loads for Wood Perpendicular to the Grain

Kind of wood	Safe loads, lb per sq in	Kind of wood	Safe loads, lb per sq in
White oak.....	500	Cedar.....	200
Long-leaf yellow pine.....	350	Spruce.....	200
Douglas fir.....	200	Hemlock.....	150
Norway pine.....	200	Cypress.....	150
White pine.....	200	Redwood.....	150
Short-leaf yellow pine.....	250	Chestnut.....	150



## 8. Cast-Iron Columns\*

**Cast-Iron Versus Steel Columns.** Although steel is being used more and more every year for columns in buildings, it will probably never entirely supplant cast iron for buildings of moderate height. For skeleton construction, however, when the height of the building exceeds twice its width, riveted steel columns, with riveted connections with the beams and girders, are unquestionably better; but for the larger proportion of buildings of moderate height, cast iron will probably have the preference for some time to come because it is more economical.

**Advantages of Cast-Iron Columns.** The commercial advantages which favor the use of cast-iron columns are these:

(1) **Cheapness.** As far as the cost of production is concerned, cast iron is cheaper than steel. This consideration alone often decides in favor of its employment. The raw material is easily transported as pig iron is sometimes bought over as ballast; so that competition with foreign countries keeps down the price.

(2) **Availability.** Cast iron is the most available form of iron. An iron-foundry requires no very elaborate plant, scarcely more than a few furnaces and sand molds, and moreover, no very extensive capital is required to operate it; consequently, the product may be obtained in almost any locality. In rolling-mills, on the contrary, the machinery must be very heavy in order that it may overcome the enormous pressure due to the resistance of the steel in rolling, and to operate it requires a great amount of power.

(3) **Readiness with Which it May be Obtained.** Columns and other structural members if made of cast iron may be obtained much more quickly than if made of steel. After the pattern has once been prepared, a dozen castings may be made almost as quickly as one, and with but very little extra cost, except that of the additional raw material and the expense of remelting it. On the other hand, columns and girders built up of rolled sections take considerably longer to make. Sections can be punched only one at a time, and if they do not happen to be of some standard length, they must be cut and fitted separately before all can be finally riveted together.

(4) **Physical Advantages.** Cast iron is one of the best materials to resist compression, its ultimate compressive strength being as high as 80 000 lb per sq in and even higher. Moreover, it can be molded into almost any desired form, and lugs, brackets and flanges may be cast upon a column all in one piece thus greatly simplifying the cost of erection. In fact, the ease with which the beam and girder-connections can be made is one of the chief reasons for the popularity of cast iron. Finally, it resists fire better than steel and it corrodes less easily. Because of this, its use is advocated by many for the wall columns of skeleton structures, as these columns are particularly liable to corrode. In the Mutual and Manhattan Life Insurance Company's Buildings in New York City, for example, the wall columns are of cast iron, whereas the interior ones are of steel.

**Disadvantages of Cast-Iron Columns.** The disadvantages of cast iron for columns are as follows:

(1) **Physical Disadvantages.** Cast iron is hard and brittle and cannot be punched or riveted, as the blows required in driving the rivets would very likely fracture the castings; consequently, all connections have to be made with bolts. A bolted connection even under the most favorable conditions is not very rigid,

\* See, also, Chapter XIII, pages 445 to 447.

as it allows more or less lateral movement, which, in the case of a tall, narrow building, is a serious matter. Owing to the low tensile and shearing strength of cast iron, the brackets supporting beams and girders are unreliable and require great skill in designing. (See pages 445 to 447.)

(2) **Defects in the Castings and the Difficulties of Thorough Inspection.** The castings themselves are subject to a number of serious defects. In the first place, owing to the shifting or floating of the cores, variations in the thickness of hollow castings are not infrequent; in fact, it is very difficult to avoid them even with the best care and workmanship. Moreover, there are apt to be concealed cavities, blow-holes or honeycomb, and foreign substances, such as cinders and sand, any of which may be on the inside of a casting, where a careful examination often fails to reveal them. The most critical condition, however, is that due to the uneven contraction of the metal during the process of cooling, the thin parts of the casting cooling and contracting more quickly than the thick ones, thereby giving rise to INITIAL STRESSES, at times of sufficient intensity to fracture the casting before any external loads whatever have been placed upon it. In many cases this trouble is due to faulty designing or to carelessness in handling the molds; yet, even under the most favorable conditions, it is difficult to secure equal radiation from the molds in all directions that castings entirely free from inherent shrinkage-stresses are probably seldom produced.

## 9. Design of Cast-Iron Columns

**Common Forms of Cast-Iron Columns.** Figs. 2, 3 and 4 show some common forms of cross-sections of cast-iron columns. Columns of circular and rectangular cross-sections are always made hollow and the diameter should be made as large as possible, within reason of course; because of two columns




Fig. 2




Fig. 3




Fig. 4

Figs. 2, 3 and 4. Cross-sections of Cast-iron Columns

having the same area of cross-section, the one which, within certain limits, has the greater diameter, and consequently the thinner shell, is the stronger. The maximum thickness of shell is  $1\frac{3}{4}$  or 2 in, because of the difficulty of keeping the core from shifting in columns of greater thickness; and the minimum thickness is  $\frac{3}{4}$  in. The latter is a requirement of most municipal building codes. As the maximum limit of diameter, 16 in may be taken; beyond this, built-up steel columns can be used to better advantage and are less expensive. The minimum diameter permitted by most building codes is 5 in, and the unsupported length of the column is limited to 20 times the least diameter.

**Hollow, Cylindrical Cast-Iron Columns.** The most economical form of cross-section, as far as structural requirements are concerned, is the HOLLOW CIRCLE (Fig. 2). This form is generally used for interior columns; but for exterior columns it is not so desirable, because such columns cannot be bonded to walls so readily, and do not present the same facilities for the design of the beam and girder-connections as columns having the other forms of cross-section.



**Cast-Iron Columns with Hollow-Square Cross-Section.** The column



Fig. 6. H-shaped Cross-section of Cast-iron Column

next in point of economy of cross-section are the with the HOLLOW-SQUARE cross-section (Fig. 3). They are generally used for wall columns because it is easier to bond them into the masonry than they had a circular section. Columns of hollow rectangular cross-section of unequal sides are sometimes found to be more available than those of square section.

The H-Shape Column (Fig. 4) ranks third regard to economy of material. It is particularly well adapted for wall column in skeleton construction for the following reasons:

"Where bolts go through beveled flanges, beveled washers to match shall be used, so that the head and nut of the bolt will be parallel."

#### TOP PLATES.

"Steel top plates, not less than  $\frac{3}{8}$ " thick, of the size required by the dimensions of the joint, and to afford full bearings for the angle-brackets, shall be placed between the ends of all columns cast with one side or with one back open, and whenever a column of less diameter is placed upon top of another. They shall also be used to make up any shortage in length of cast-iron columns. Plates for double columns shall be cast with top and bottom flanges. After the plates have been drilled with the proper holes for connections, they shall be truly flat and of uniform thickness."

Note: These H columns are particularly well adapted for wall columns in skeleton construction. Only the edges come near the face of the wall and there are no projecting rims or flanges to be in the way.




Fig. 7. Connections for H-shaped Cast-iron Column

(1) Being entirely open, with both the interior and exterior surfaces exposed, any inequalities in thickness can be readily discovered and the thickness is

ly measured, thus obviating any necessity for drilling, and rendering the inspection of the columns much easier.

(2) The entire surface of the column may be protected by paint.

(3) When built in brick walls the masonry fills all voids, so that no open space left; and if the column is placed as shown in Fig. 6, only its edges come near the face of the wall.

(4) Lugs and brackets can be cast on such columns more readily and effectively than on cylindrical columns, especially for wide and heavy girders, and the sections do not require projecting flanges, which are often in the way on cylindrical columns.

(5) An eccentric load may be applied to the web where its effect is less and where it is more evenly distributed than when it is applied to the outer rim or bell.

Details of connections and brackets for H-shaped cast-iron columns are shown in Fig. 7.

**Details of Connections of Cast-Iron Columns.** The bearings of a cast-




Fig. 8. Cast-iron Column with Cap and Base. Wrong Method

iron column should always be faced true to the axis of the column, and the columns should be bolted together by four  $\frac{3}{4}$ -in bolts for columns 10 in in diameter or less, and by six bolts for 12-in and larger columns. Faced plates, as shown in Fig. 5, are inserted between the flanges of columns to make up for any shortage in length and also when a column of smaller diameter is placed over one of greater diameter. For convenience in erecting columns, the joint is generally placed just above the beams or girders supported by the columns.

**Projecting Caps and Bases.** A column with ornamental cap and base should

never be cast as shown in Fig. 8, that is, if it is to support load. In every bearing column, the core should extend in a straight line from end to end. Plain molded caps and bases may be cast as in Fig. 9; but if more ornamental caps are desired, or heavy projecting ones, they should be cast separately and attached to the straight columns by bolts.




Fig. 9. Cast-iron Column with Cap and Base. Slight Projections

## 10. Strength of Cast-Iron Columns. Formulas

**Formulas for Cast-Iron Columns.** The ULTIMATE RESISTANCE of cast iron crushing is generally taken at 80 000 lb per sq in, and for posts, pintels, etc., where the length is not more than six times the diameter or breadth, it will fully be safe to assume a WORKING STRENGTH of six tons per square inch of metal. For longer posts or columns, the strength is affected by the ratio of

length to diameter, but to just what extent is not known with absolute certainty hence all formulas for columns must be more or less theoretical. The consequence is that while a great many formulas have been published, there is not one that is universally accepted. The two following Formulas \* (7) and (8), for many years more commonly adopted than any others, as they appear to agree as well as any with actual tests.

**Formula for Hollow, Cylindrical, Cast-Iron Columns with Square End**  
Ultimate strength, in pounds.

$$= \text{metal-area} \times \left[ 80\,000 + \left( 1 + \frac{\text{sq of length in in}}{800 \times \text{sq of diam in in}} \right) \right]$$

or

$$\text{Ultimate strength, in pounds} = \frac{80\,000 A}{1 + l^2/800 d^2}$$

in which  $A$  is the area of the cross-section in square inches.

\* The tables in the handbook of the Cambria Steel Company (1913) are based on Formulas (7) and (8), and they were adopted in some building laws. They are based on the form of Gordon's formula, which, in turn, is Rankine's formula with  $d$ , the diameter or least lateral dimension, substituted for  $r$ , the least radius of gyration of the section. Rankine's formula is sometimes referred to as Gordon's formula. The results obtained by these formulas will be slightly in excess of those given in the old Chicago building law (see tabulation in this foot-note), and considerably less than those permitted by the former building law of New York City,  $S = 11\,300 - 30 l/r$ . (Present New York City law  $S = 9\,000 - 40 l/r$ .)

In 1898 Professor W. H. Burr made an analysis of the results of a number of experiments on full-size, hollow, cylindrical cast-iron columns made at the Watertown Arsenal, Mass., and at Phoenixville, Pa., and by plotting the results found that a straight-line formula having the equation  $S = 30\,500 - 160 l/d$ , in which  $S$  is the ultimate strength of the metal per square inch of column-area, represented the average of the experimental results. With a factor of safety of 4 this would become  $S = 7\,625 - 40 l/d$  and with a factor of safety of 5,  $S = 6\,100 - 32 l/d$ .

According to Professor Burr's analysis the values for  $S$  given in the fourth column of Table VII represent a factor of safety of a little over 4 for  $l/d = 20$ , and of nearly 5 for  $l/d = 36$ .

Formulas for finding the value of  $S$  according to the former codes of Chicago and Boston

Cylindrical columns		Rectangular columns	
Old Chicago Code	Old Boston Code	Old Chicago Code	Old Boston Code
$\frac{10\,000}{1 + \frac{l^2}{600 d^2}}$	$\frac{10\,000}{1 + \frac{l^2}{800 d^2}}$	$\frac{10\,000}{1 + \frac{l^2}{800 d^2}}$	$\frac{10\,000}{1 + \frac{l^2}{1066 d^2}}$

The former New York City Building Code Formula was

$$S = 11\,300 - 30 l/r$$

Compared with the results of tests that have been made on full-size cast-iron columns it has been shown that while in Chicago a factor of safety of 8 was allowed, the actual factor of safety was a little over 4, that in Boston it was slightly under 4, while in New York it was a trifle over 6. The formula in the new (1916) Chicago code is  $S = 10\,000 - 30 l/r$  while the new (1915) Boston code gives the values of  $S$  for  $l/r$  from 10 to 70.

A series of tests on full-size cast-iron columns and brackets was made under the direction of Stevenson Constable, in December, 1897, a report of which, with illustrations, may be found in the Engineering Record for January 8 and 22, 1898.

**Formula for Hollow, Rectangular, Cast-Iron Columns with Square Ends**

Ultimate strength, in pounds

$$= \text{metal-area} \times \left[ 80\,000 + \left( 1 + \frac{\text{sq of length in in}}{1\,067 \times \text{sq of least side in in}} \right) \right] \quad (8)$$

$$\text{Ultimate strength, in pounds} = \frac{80\,000 A}{1 + l^2 / 1\,067 d^2}$$

which  $A$  is the area of the cross-section in square inches

**Formula for Solid, Cylindrical, Cast-Iron Columns**

Ultimate strength, in pounds

$$= \text{metal-area} \times \left[ 80\,000 + 1 + \frac{\text{sq of length in in}}{266 \times \text{sq of diam in in}} \right] \quad (9)$$

$$\text{Ultimate strength, in pounds} = \frac{80\,000 A}{1 + l^2 / 266 d^2}$$

which  $A$  is the area of the cross-section in square inches.

For H-shaped columns use formula (7), taking  $d$  as the least side.

THE SAFE LOAD is generally taken at one-eighth of the ultimate strength or working-load.

**Eccentric Loading.** Cast-iron columns should not be loaded with a heavy, **eccentric load**, that is, a load applied on one side of the column without a corresponding load on the other side, as cast iron is unable to resist very great bending stresses. (See, also, eccentric loading of wooden and steel columns, pp 453 and 485.)

**II. Tables of Safe Loads for Cast-Iron Columns. Examples**

**Explanation of Tables.** As the allowable pressure PER SQUARE INCH OF metal depends upon the ratio of length to diameter, without regard to actual dimensions (that is, it would be the same for a column 6 in in diameter and 12 ft long, as for one 8 in in diameter and 16 ft long), it is practicable to prepare a table which will give the value of the terms of Formulas (7) and (8) inclosed in brackets for all ratios of diameter to length, and thus simplify very much the computation for any particular column. Table VII has been computed by means of Formulas (7) and (8) for ratios of length to diameter varying from 8 to 16, and the same result will be obtained by using the values given in this table as by using the corresponding formula. To use this table it is only necessary to divide the length of the column by the least thickness or diameter, both in inches, and opposite the number in the first column of the table coming nearest the quotient, find the SAFE STRENGTH PER SQUARE INCH for the column. This load is multiplied by the METAL-AREA in the cross-section of the column and the result is the SAFE LOAD for the column. Examples (5) and (6) will illustrate the use of Tables VII to X.

**Example 5.** What is the safe load for a 10-in hollow, cylindrical cast-iron column, 15 ft long, the shell being 1 in thick?

**Solution.** In this case the ratio  $l/d$ , which is the length of the column divided by the diameter, both in inches, is 18, and opposite 18 in Table VII the safe strength per square inch for a cylindrical column is found to be 7 117 lb. The metal-area of the column, from the table of areas on pages 42 and 463, is equal to the area of a 10-in circle minus the area of an 8-in circle, or,  $78.53 - 50.26 = 28.27$  sq in. Multiplying these two together, for the safe load of the column the result is  $28.27 \text{ sq in} \times 7\,117 \text{ lb per sq in} = 201\,917 \text{ lb}$ , or about 100.5 tons.

**Tables VIII, IX and X.** To still further facilitate computations, Tables VIII, IX and X, have been prepared, which give at a glance the safe load based on a factor of safety of 8, for columns of the more common sizes and lengths. For lengths between those given in the tables sufficiently accurate results may be obtained by interpolation. For any other factor of safety multiply the safe load given in the table by 8, and divide by the new factor of safety.

**Example 6.** What is the safe load for a 9-in hollow, cast-iron column of square cross-section 12 ft long, the shell being 1 in thick?

**Solution.** From Table IX, the safe load is 129 tons. The same result may be obtained by using Table VII. The ratio  $l/d$  in this case is  $144/9 = 16$  and the corresponding safe load in pounds per square inch is 8 064. The area of the column is 32 sq in. Hence, the safe load is 32 sq in  $\times$  8 064 lb per sq in = 258 048 lb, or 129 tons, which agrees with the safe load given in Table IX for the same column.

**Table VII. Breaking-Loads and Safe Loads in Pounds per Square Inch for Hollow, Cylindrical and Hollow, Rectangular, Cast-Iron Columns**

Calculated by Formulas (7) and (8)

Length in inches divided by external breadth or diameter	Breaking-weight in pounds per square inch		Safe loads in pounds per square inch. Safety-factor 8	
	Cylindrical	Rectangular	Cylindrical	Rectangular
8	74 074	75 470	9 259	9 433
9	72 661	74 350	9 082	9 293
10	71 110	73 126	8 888	9 140
11	69 505	71 870	8 688	8 983
12	67 800	70 487	8 475	8 811
13	66 060	69 084	8 257	8 635
14	64 257	67 567	8 032	8 446
15	62 450	66 060	7 806	8 257
16	60 606	64 516	7 576	8 064
17	58 780	62 942	7 347	7 867
18	56 940	61 360	7 117	7 670
19	55 134	59 745	6 892	7 468
20	53 333	58 180	6 666	7 272
21	51 580	56 610	6 447	7 076
22	49 843	55 020	6 230	6 877
23	48 163	53 470	6 020	6 684
24	46 512	51 950	5 814	6 494
25	44 918	50 440	5 614	6 305
26	43 360	48 960	5 420	6 120
27	41 862	47 530	5 233	5 940
28	40 404	46 110	5 050	5 764
29	39 000	44 742	4 875	5 592
30	37 647	43 390	4 706	5 424
31	36 347	42 080	4 543	5 260
32	35 090	40 816	4 386	5 102
33	33 884	39 580	4 235	4 947
34	32 720	38 380	4 090	4 797
35	31 608	37 244	3 951	4 655
36	30 534	36 120	3 817	4 515



Table VIII. Safe Loads in Tons of 2 000 pounds for Hollow, Cylindrical,  
Cast-Iron Columns with Square Ends

Based on Formula (7). Safety-factor 8

Height, ft.	Thick- ness, in	Length of column in feet											
		6	8	10	12	14	16	18	20	22	24	26	28
5	3½	39	34									10 0	31 3
	3½	45	38									11 3	35 3
5½	3½	46	40									11 3	35 0
	3½	52	46	40	34	29						12 7	39 7
6	3½	52	47	41	36	31	27	24				12 4	38 7
	3½	60	53	47	41	36	31	27				14 1	44 0
	1	66	57	51	45	39	34	30				15 7	49 0
7	3½	65	61	55	48	43	38	34					
	3½	74	61	55	55	49	43	38					
	1	83	71	61	61	54	48	43					
8	3½	78	77	70	61	55	50	45	40	36	31		
	3½	89	88	79	70	63	57	51	46	41	35		
	1	100	99	89	79	71	64	58	52	47	41		
9	3½	103	99	89	85	80	71	65	59	54	49		
	1	117	111	99	95	90	80	73	67	61	55		
	1½	129	122	110	105	99	89	81	74	67	61		
10	3½	118	111	100	93	86	79	73	67	61	55		
	1	133	127	112	105	97	89	82	76	70	64		
	1½		14	125	116	107	99	91	84	77	71		
	1¾		15	136	127	118	109	100	92	85	78		
11	1		14	129	122	114	106	98	91	84	77		
	1½		19	144	135	126	118	109	101	93	86		
	1¾		17	158	148	139	129	120	111	102	94		
	1¾		19	171	161	151	140	130	121	111	102		
12	1½		17	163	154	146	137	128	120	111	102		
	1½		19	179	170	160	150	141	132	122	113		
	1¾		21	194	184	174	163	153	143	133	123		
	1¾		23	210	199	187	176	165	154	144	133		
13	1½		19	182	174	165	156	147	138	128	118		
	1½		21	200	191	181	172	162	152	142	132		
	1¾		23	218	208	197	187	176	166	155	145		
	1¾		25	235	224	213	201	190	179	168	157		
14	1½		23	221	212	203	193	183	173	163	153		
	1½		25	241	231	221	210	199	189	179	169		
	1¾		27	260	250	238	227	215	204	193	183		
	1¾		29	279	268	256	243	231	219	207	196		
15	1½		28	264	254	244	234	223	212	201	191		
	1½		30	285	275	264	253	241	229	218	207		
	1¾		32	306	295	283	271	259	246	235	224		
	1¾		34	327	315	302	288	276	263	251	239		
16	1½		32	310	300	290	278	267	255	243	231		
	1½		35	333	322	311	299	286	273	261	249		
	1¾		37	356	344	332	319	306	292	279	267		
	1¾		44	423	410	395	380	364	347	332	317		

**Table IX. Safe Loads in Tons of 2 000 Pounds for Hollow, Square and Rectangular, Cast-Iron Columns, with Square Ends**

Based on Formula (8). Safety-factor 8

Size, in	Thick- ness, in	Length of column in feet								Area of metal, sq in	Weight lin ft
		8	10	12	14	16	18	20	24		
4×6	¾	41	34	28	.....	.....	.....	.....	.....	12.75	39.8
4×8	¾	51	42	35	.....	.....	.....	.....	.....	15.75	49.2
4×9	¾	56	46	39	.....	.....	.....	.....	.....	17.25	53.9
4×10	¾	60	50	42	.....	.....	.....	.....	.....	18.75	58.6
4×12	¾	70	59	49	.....	.....	.....	.....	.....	21.75	68.0
5×8	¾	64	55	48	41	.....	.....	.....	.....	17.25	53.9
	I	81	71	61	53	.....	.....	.....	.....	22.00	68.8
5×9	¾	69	60	52	45	.....	.....	.....	.....	18.75	58.6
	I	89	78	67	58	.....	.....	.....	.....	24.00	75.0
5×10	¾	75	65	57	49	.....	.....	.....	.....	20.25	63.3
	I	96	84	73	63	.....	.....	.....	.....	26.00	81.3
5×12	¾	86	74	65	56	.....	.....	.....	.....	23.25	72.7
	I	111	97	84	72	.....	.....	.....	.....	30.00	93.8
6×6	¾	63	57	51	45	40	35	.....	.....	15.75	49.2
	I	80	72	65	57	51	45	.....	.....	20.00	62.5
6×8	¾	75	68	60	54	47	42	.....	.....	18.75	58.6
	I	96	87	78	69	61	54	.....	.....	24.00	75.0
6×9	¾	81	73	65	58	51	45	.....	.....	20.25	63.3
	I	104	94	84	75	66	58	.....	.....	26.00	81.3
6×10	¾	87	79	70	62	55	49	.....	.....	21.75	68.0
	I	112	101	91	80	71	63	.....	.....	28.00	87.1
6×12	¾	99	90	80	71	63	55	.....	.....	24.75	77.1
	I	129	116	104	92	81	72	.....	.....	32.00	100.0
6×15	¾	117	106	95	84	74	66	.....	.....	29.25	91.1
	I	153	138	123	109	97	85	.....	.....	38.00	118.1
7×7	¾	80	73	67	61	55	49	44	.....	18.75	58.6
	I	102	94	85	78	70	63	57	.....	24.00	75.0
7×9	¾	92	85	77	70	63	57	51	.....	21.75	68.0
	I	119	109	100	91	82	74	66	.....	28.00	87.1
7×12	¾	111	102	93	85	77	69	62	.....	26.25	82.1
	I	144	133	121	110	99	89	80	.....	34.00	106.1
8×8	¾	95	90	83	77	70	64	59	49	21.75	68.0
	I	124	115	107	99	91	83	76	63	28.00	87.1
	1¼	148	140	129	119	109	100	91	76	33.75	105.1
8×10	¾	109	103	95	87	80	73	67	55	24.75	77.1
	I	141	132	122	113	104	95	86	72	32.00	100.0
	1¼	170	161	148	137	125	115	105	87	38.75	121.1
8×12	¾	122	115	106	98	90	82	75	62	27.75	86.1
	I	158	148	138	127	116	107	97	81	36.00	112.1
	1¼	192	181	167	154	142	130	118	98	43.75	136.1


Table IX (Continued). Safe Loads in Tons of 2 000 Pounds for Hollow, Square and Rectangular, Cast-Iron Columns, with Square Ends

Based on Formula (8). Safety-factor 8

Size, in	Thick- ness, in	Length of column in feet								Area of metal, sq in	Weight, lin ft
		8	10	12	14	16	18	20	24		
8X16	1	193	181	168	155	142	130	119	99	44.00	137.5
	1 1/4	236	221	206	190	174	159	145	121	53.75	168.0
9X9	3/4	111	106	99	93	86	80	74	63	24.75	77.3
	1	144	137	129	120	112	103	96	85	32.00	100.0
9X12	1	171	162	153	143	133	123	114	97	38.00	118.8
	1 1/4	209	198	186	174	162	149	138	118	46.25	144.5
9X16	1	207	196	185	173	161	149	138	117	46.00	143.8
	1 1/4	254	240	226	212	197	182	168	143	56.25	175.8
10X10	1	165	158	150	142	133	125	117	101	36.00	112.5
	1 1/4	201	193	183	172	162	152	142	123	43.75	136.7
10X12	1	184	176	167	158	148	139	129	112	40.00	125.0
	1 1/4	224	214	204	192	181	169	158	137	48.75	152.3
10X15	1	211	202	192	181	170	160	149	129	46.00	143.8
	1 1/4	258	247	235	222	209	195	182	158	56.25	175.8
10X16	1	220	211	200	189	178	167	155	135	48.00	150.0
	1 1/4	270	258	245	232	218	204	190	165	58.75	183.6
10X18	1	239	228	217	205	193	181	168	146	52.00	162.5
	1 1/4	293	280	266	251	236	221	207	179	63.75	199.2
10X20	1	257	246	234	221	208	194	181	157	56.00	175.0
	1 1/4	316	302	287	271	255	239	223	193	68.75	214.9
10X24	1	294	281	267	252	237	222	207	180	64.00	200.0
	1 1/4	362	346	329	311	292	274	255	221	78.75	246.1
12X12	3/8	183	177	171	164	156	149	141	126	38.90	121.7
	1	207	201	193	185	177	168	159	142	44.00	137.5
	1 1/4	253	245	236	223	216	206	195	174	53.75	168.0
	1 1/2	296	288	277	265	253	241	228	204	63.00	196.9
12X15	1	235	228	220	211	201	191	181	162	50.00	156.3
	1 1/4	288	280	269	258	246	234	222	198	61.25	191.4
12X16	1	245	237	228	219	209	199	188	168	52.00	162.5
12X18	1	263	256	246	236	225	214	203	181	56.00	175.0
12X20	1	282	274	264	253	241	229	217	194	60.00	187.5
12X24	1	320	310	299	287	274	260	246	220	68.00	212.5
14X16	1	268	261	254	246	238	229	219	200	56.00	175.0
14X20	1	307	298	290	281	272	261	250	228	64.00	200.0
14X24	1	345	336	326	316	306	294	280	257	72.00	225.0
14X16	1	300	284	278	271	264	256	247	229	60.00	187.5
14X24	1	380	360	352	344	334	324	313	291	76.00	237.5
14X18	1	340	340	320	314	307	299	291	274	68.00	212.5
14X20	1	380	380	361	356	349	342	334	317	76.00	237.5
14X24	1	420	420	399	393	386	378	369	351	84.00	262.5

Table X. Safe Loads in Tons of 2 000 Pounds for H-Shaped, Cast-Iron Columns


Based on Formula (7). Safety-factor 8

Size, in			Area of metal, in	Length of column in feet							
a	b	t		10	12	13	14				
6X 6X ¾	I	¾	12¾	41	36	33	31	15	16	18	20
		I	16	53	46	43	40				
		1¼	19¾	64	56	52	48				
6X 8X ¾	I	¾	13¾	46	40	37	34				
		I	18	60	52	48	45				
		1¼	21¾	73	63	59	54				
7X 7XI	I¼		19	69	62	58	55	52	49	43	38
			23¾	84	75	71	67	63	59	53	46
7X 9XI	I¼		21	76	68	64	61	57	54	48	42
			25¾	93	83	79	74	70	66	59	51
8X 8X ¾	I	¾	16¾	66	60	57	54	51	49	44	39
		I	22	86	78	74	70	67	64	57	51
		1¼	26¾	105	95	91	86	82	78	70	63
8X 10XI	I¼		24	93	85	81	77	73	69	62	56
			29¾	114	104	99	94	90	85	76	69
		1½	34½	134	122	117	111	105	100	89	81
9X 9XI	I¼		25	102	94	91	87	83	79	72	66
			30¾	125	116	111	106	102	97	89	81
		1½	36	147	136	130	125	120	114	104	95
9X 10XI	I¼		26	106	98	94	90	86	83	75	69
			31¾	130	120	115	111	106	101	92	84
		1½	37½	153	142	136	130	125	119	108	99
10X 10XI	I¼		28	118	111	107	103	99	95	88	81
			34¾	145	136	131	127	122	127	108	100
		1½	40½	171	160	155	149	144	138	128	117
		1¾	46¾	196	184	177	171	165	158	146	134
10X 12XI	I¼		30	127	119	115	111	106	102	94	87
			36¾	156	146	141	136	131	126	116	109
		1½	43½	184	172	166	160	154	148	137	128
		1¾	49¾	211	198	191	184	177	170	157	144
		2	56	236	222	214	207	199	191	176	162
12X 12XI	I¼		34	151	144	140	136	132	128	121	113
			41¾	186	177	172	167	163	158	149	139
		1½	49½	220	209	203	198	193	187	177	165
		1¾	56¾	252	241	234	227	221	216	202	189
		2	64	284	271	263	256	249	242	227	213
12X 14XI¼	I¼		44¾	197	188	183	177	173	168	158	148
			52½	233	222	216	210	204	199	186	174
		1¾	60¾	268	255	248	241	235	228	214	201
		2	68	302	288	280	272	265	257	241	226
		2½	75¾	335	319	310	301	292	285	268	251


## 12. Types, Forms and Connections of Steel Columns

**Use of Steel Columns, Struts, Trusses, etc.** Owing to the many advantages of built-up steel columns over cast-iron columns, especially for all buildings, and to the great reduction that has taken place in the cost of steel construction, built-up columns are now very extensively used in buildings of moderate height; and for skeleton construction, or for buildings exceeding stories in height, they are certainly much to be preferred to cast-iron columns. Steel trusses, also, are now much more commonly used in buildings than in former years, so that the architect must have at hand data for designing them and for computing their strength. In the following pages the author has endeavored to cover the subject of columns and struts quite completely, to furnish such data as will enable the designer to decide upon the shape of column or truss it is best to use, and also to determine the sizes and sections of such columns with the least labor.


**Types and Forms of Steel Columns.** The following are cross-sections of the majority of steel columns in general use, arranged in the order of their simplicity of construction, that is, the number of rows of rivets they require:



Bethlehem H column  
No rivets



Channel-column  
with plates or  
lattice-bars  
Four rows of  
rivets



Lally steel-con-  
crete column  
No rivets




Plate-and-angle  
column with  
side plates  
Six rows of rivets





Plate-and-angle  
column  
Two rows of  
rivets



Box column  
Eight rows of  
rivets

**Considerations Governing the Selection of Steel Columns.** There are considerations other than simplicity of construction which sometimes govern the selection of a column. Some of the most important of these are explained in the following paragraphs:

(1) **Cost and Availability of Material.** I beams, channels, plates and angles are the most common commercial sections. They are easily rolled and are manufactured by all of the large mills. They are reasonable in price and may be obtained promptly in large numbers in any locality where a steel building is to be erected. Patented sections, or the product of one mill, do not, as a rule, fulfill these conditions.

(2) **Amount of Labor Required and Facility With Which it can be Performed in Shop and Field.** In the shop the complexity of the column-section and the number of pieces of which it is composed greatly affect the cost of labor. If there are numerous small pieces such as lattice-bars, splice-plates, etc., each of which requires cutting and fitting together, with frequent handling, the cost is proportionately great. The cost of a column depends, also, largely upon the number of rivets required and whether they can all be driven by machine so as to avoid the slower and more expensive hand-riveting. The same general remarks apply to labor in the field; the connections should be as simple as possible, the rivets easy of access and as few in number as is consistent with strength.

(3) **Simplicity of Connections Between Column and Supported Member.** This is quite an important consideration in the design of a large building and sometimes governs the choice of the section to be used. Where there are four beams to a column, on opposite sides, and all of the same height, a satisfactory connection can be made with almost any section; but where the beams are spaced irregularly, both in regard to position in plan and to height, and where eccentric loads must be provided for, it is very important that the section of the column itself affords as great an opportunity as possible for the connection of the beams. In this respect, possibly, closed sections are inferior to open sections having a central web.

(4) **Adaptability to Connections Which Transfer Compressive Stress Directly to Axis of Column.** In this respect, also, sections of an open construction, in which the girders transmit their loads almost directly to the central axis of the column, thus avoiding the disadvantage of eccentric loading, are superior to those of a closed construction.

(5) **Adaptability to Changes in Thickness of Metal in Members of Column to Suit Different Loads in Different Stories.** It is not desirable to make the columns carrying the upper floors of a building very small, since the beams and girders supporting the upper floors are usually of the same dimensions as those of the lower floors and consequently require just as heavy and secure connections. It is almost impossible to make such connections with small columns and consequently, in order to reduce the area of a column in proportion to the lighter load to be carried, it is better to reduce the thickness of the material used and to keep the general dimensions of the section the same.

(6) **Adaptability to Fire-Proof Covering.** Closed sections in general can be more compactly fireproofed than open sections.

**General Considerations Affecting the Choice of Steel Columns.** It is almost impossible to say that any one of the foregoing types of steel column is superior to the others. Each has its own good points, and the column whose section has theoretically the best distribution of material may not always be the best one to use, because of the eccentric loads to be carried, or because of other conditions. The choice in most cases will depend upon the personal view of the designer, as well as upon the local conditions as to cost and manufacturing promptness of delivery and the details of the problem. Further descriptions of the different columns, and also the special advantages claimed for them, are given in the following pages.

**Steel-Column Connections.** When steel columns were first designed it was customary to use cap-plates to connect the story-lengths, and the beams and girders often rested upon these plates. In modern practice, however, the column-joint is generally placed just above the beams and girders for convenience in erection and the plates are often omitted. The columns are closely fit-

together with milled ends, and splice-plates are riveted to the sides or flanges as shown in the illustrations of typical steel-column details, Figs. 17 and 18. As it is impossible in these pages to include the subject of column-connections in anything but a general way, the only attempt that has been made in this direction is to illustrate common forms of connections that have been used with different kinds of columns. These will be found in the description of columns in the following pages.

**Number of Rivets Required.** No general rule can be given for the number of rivets and size of the brackets required for column-connections, as the loads to be supported vary in different buildings and in different parts of the same building. The number of rivets required in each connection must therefore be determined by the rules given in Chapter XII for designing riveted joints. Connections for single beams, however, will generally require the same number of rivets as are given for beam-connections (Chapter XV, page 617). The allowable stress for rivets in column-connections is generally taken at 10 000 lb per sq in for single shear and 18 000 or 20 000 lb per sq in for bearing. (See Tables II and III, pages 418 and 419, Chapter XII.)

**Spacing of Rivets.** Steel columns fail either by deflecting bodily out of a straight line or by the buckling of the metal between rivets or other points of support. Both actions may take place at the same time, but if the latter occurs alone, it may be an indication that the rivet-spacing or the thickness of the metal is insufficient. The rule has been deduced from actual experiments upon riveted columns that the distance between centers of rivets should not exceed, in the line of stress, sixteen times the thickness of metal of the parts joined, with a maximum spacing of 6 in, and that the distance between rivets or other points of support, at right-angles to the line of stress, should not exceed thirty-two times the thickness of the metal. The usual practice in designing columns is to space the rivets the minimum distance on centers at both ends, for a length equal to twice the least dimension of the column, with the maximum spacing of 6 in between.

**Steel-Pipe Columns.\*** Steel-pipe columns are used for interior construction to carry beams and girders supporting floors, walls and chimneys in all classes of buildings, such as tenements and apartment-houses, factories, garages, churches, warehouses, etc. A particular demand for steel-pipe columns is at the angles of show-windows in mercantile buildings. In buildings of moderate height the floor-joists are usually supported by the side walls and the columns have to support only a relatively light wall above. For such places wrought-steel pipes may be advantageously used for the columns. They may be used, also, for the columns supporting the roof of one-story buildings. In the Borough of Brooklyn, New York City, pipe-columns were formerly calculated by the formula  $S = 14\,000 - 80l/r$ , in which  $S$ ,  $l$  and  $r$  have values as explained below for New York and Chicago formula. If the columns are filled with concrete, the area of the cross-section of the concrete is multiplied by 500 and the product added to the load supported by the pipe. (See, also, page 477 and the Tables on page 466). This formula gave a factor of safety of four. New York and Chicago codes now use the formula,  $S = 16\,000 - 70l/r$  in which  $S$  is the permissible unit fiber-stress,  $l$  the length in inches and  $r$  the radius of gyration of the cross-section of the pipe. This gives a carrying capacity greater than the former formulas gave. In Philadelphia, pipe-columns are allowed to carry

\* Much valuable data relating to steel-pipe columns was furnished the editor-in-chief by P. C. Patterson and J. A. McCullough of the National Tube Company, Pittsburgh.

about 6% more than is allowed in New York. Where pipe-columns are filled with concrete the cast cap and base are secured to the pipe in each case by concrete which is reinforced internally by a pipe of smaller diameter. When




Fig. 10. Connections, Caps and Bases for Steel-pipe Columns

these steel-pipe columns filled with concrete are used, care should be taken that the pipes are entirely filled, and that there are no air-spaces in the concrete. These concrete-filled columns, sometimes reinforced with smaller pipes,



large carrying capacity. Pipe-columns may have their supporting power about doubled in many cases by concrete filling. (See, also, paragraph on Lally Columns, page 477). One type of steel post-cap used in connection with pipe.




Fig. 11. Connections, Caps and Bases for Steel-pipe Columns

to carry wooden girders is shown in Figs. 62 and 63 of Chapter XXII. There are many other forms of cast and wrought caps for pipe-columns. The selection of proper caps and bases is the most difficult part of adapting tubular columns to practical problems in building-construction. Figs. 10 and 11 show

various forms of steel-pipe column-connections, caps and bases sufficiently suggestive to enable a designer to properly develop their details.

**Advantages of Steel-Pipe Columns.** A wrought-steel pipe when used as a column generally has the following advantages:

(1) It will support a greater load per square inch of cross-section than other shapes and styles of mild-steel columns of the same **SLENDERNESS-RATIO**,  $l/r$ , for most of the columns of different slenderness-ratios recently tested (1898 and 1909) at the Watertown Arsenal.

(2) Its section has the greatest possible **LEAST RADIUS OF GYRATION**,  $r$ , for the same outside diameter and section-area. This makes pipe-columns especially advisable when it is desired to obstruct the view as little as possible, as in the corners of show-windows, in balcony-supports, etc.

(3) It may be used with greater slenderness-ratio,  $l/r$ , than any other section without reducing the load per square inch in order to conform to permissible loading-rules, such as those of the New York City and the Chicago building codes.

(4) Its curved walls permit the use of relatively thinner material than can be used with columns with flat surfaces; that is, its thickness,  $t$ , divided by its outside diameter,  $d$ , may be  $t/d = 1/80$  with as great security from **WRINKLING**, called also **BUCKLING**, **BULGING** OR **LOCAL FAILURE**, as the box column, with the good practice of competent engineers limits to  $1/80$  of the unsupported width of flat surfaces. The ratio  $t/d = 1/80 = 1/4''/20''$  is about the limit of practical working of the ordinary lap-weld process, and all commercial pipes have a smaller ratio.

(5) Manufacturers are now regularly making pipes for sizes up to and including 16 in outside diameter, in lengths up to 40 ft.

**Notes on the Use of Steel-Pipe Columns.** The following general notes and suggestions should be observed in the use of steel pipe for columns:

(1) As in the case of columns of any construction, it is obvious that competent designing and detailing as well as proper fabrication of the **END-CONNECTIONS** for pipe-columns be insisted upon. Otherwise the advantages of circular section may be nullified.

(2) When the loading must be **ECCENTRIC** care must be exercised in the proper selection and size of pipe to be used. The relative economy in the use of circular section, however, increases with the length and slenderness of the column.

(3) A **CAPITAL** OR **BASE** should never be screwed to a pipe, because cutting the thread reduces the section. Where screw-threads must be used, only the area below the root of the threads should be considered as available for the supporting power.

(4) The ends of a pipe to be used for a column should always be **FACED** in a lathe, the facing being normal to the general axis. A pipe should not be turned nor bored in fitting capitals or bases but, if possible, the capital or base should always be **FORCED** OR **SHRUNK** to an even bearing on the faced end of the pipe. Where the capital or base must be inserted, it is liable to start a wrinkle or buckle and the load should be adjusted to the probable lessening of supporting power. The bearing surfaces in capitals and bases should be, of course, also **LATHE-FACED**. It may be found that with careful foundry-work it is not necessary to bore the castings; but it may, in some cases, be cheaper to use relatively poor foundry-work and bore the castings, as well as face the seats.

(5) **PIN-ENDS** OR **BALL-AND-SOCKET ENDS** are generally preferable to fixed ends for a slenderness-ratio  $l/r$ , of 100 or less, because tests show columns so fitted usually carry heavier loads before failure. This is increased

as  $l/r$  decreases. Any form of end-connection of column that may be a source of failure from a falling floor may endanger the whole structure.




Fig. 12. Connections for Bethlehem H Columns

"All columns should have sufficient STIFFNESS to safely withstand the deflecting forces to which they may be exposed. This usually involves considerations of eccentricity as well as of flexure due to transverse load.

"It is desirable to adhere always to the trade sizes of pipe known as THIN-WALL, STANDARD, EXTRA STRONG, DOUBLE-EXTRA STRONG, CASING, BOILER-

TUBES, etc., and avoid special production which usually entails delays and special prices.

(8) Tables XII and XIII give the safe loads which STANDARD and EXTRA STRONG steel-pipe columns are permitted to carry under the New York and Chicago codes. Philadelphia laws permit slightly greater loads. Supplementary tables of safe loads for DOUBLE EXTRA STRONG steel-pipe columns are furnished by the manufacturer and may be useful in cases where a minimum diameter is required; but it should be remembered that such pipe always costs more per pound, owing to the greater cost of manufacture.



Fig. 13. Section of Bethlehem H Column Showing Variation in Area

**H-Beam and I-Beam Struts and Columns.** For struts and columns carrying light loads, H BEAMS and I BEAMS are probably the most economical, as they require very little riveting except for the splices and connections. Owing, however, to the narrow flanges of

even the deepest I beams it is not practicable to rivet very heavy girders to them nor can they ordinarily be riveted to the web, because the latter is generally a




Fig. 14. Concrete-filled Lally Steel Column

Fig. 15. Lally Column. Typical Connections

thin that too many rivets will be required for the connection. Tables XVII and XVIII give a table of safe loads for the Carnegie steel H BEAMS or I BEAMS used as columns.

**Bulldozing Columns.** As far as shop-work is concerned the **Bulldozing** columns are just as economical as the ordinary H-beam or I-beam columns as they, also, are rolled and not built up or assembled. The only fabrication required is that for the splice-plates and connections. Typical connections are shown in Fig. 12 from which the simplicity of detail and small amount of fabrication required are apparent. They are, moreover, superior to the I-beam columns because they afford a wider flange for attaching the beams and girders, besides being



Fig. 18. Section of Steel Plate-and-angle Column



Section A-A



Section B-B



Section A-A



Section B-B

#### TYPICAL ANGLE-COLUMN


Bearing on masonry

Bearing on steel

Fig. 17.\* Connections for Steel Plate-and-angle Columns

\*From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

more economical of cross-section. Bethlehem columns are rolled in five sizes 6, 8, 10, 12, and 14 in. in width, but by spreading the rolls, as shown in Fig. 13, the section-area of each width can be increased considerably. The




**TYPICAL SPLICE**  
Angle-column to Channel-column



**TYPICAL SPLICE**  
Angle-columns, different sizes

**TYPICAL CHANNEL-COLUMN**  
Bearing on steel



**TYPICAL SPLICE**  
Channel-columns, different sizes

Fig. 18.\* Connections for Steel Plate-and-channel Columns

section-areas of columns of the largest size may also be increased by riveting plates to the flanges. Tables of DIMENSIONS and PROPERTIES of Bethlehem rolled steel columns and of the SAFE LOADS they will carry are given in Tables XVIII to XXI. Although these columns have been rolled in Germany and

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

302, it was not until the establishment in 1908 of the larger improved mills at Bethlehem, Pa., that these sections became available for use in this country. They are gradually superseding plate-and-angle and box columns, particularly those of the smaller sizes. The 6-in columns have been rolled since 1920.

**Lally Columns.** LALLY COLUMNS (see, also, pages 469 to 474 and Tables on page 516) are patented columns made with a circular steel shell, as shown in Fig. 14, and filled with a concrete composed of sand, cement and blue trap-rock, and thoroughly compressed. The larger columns have, in addition, a steel reinforcement, which makes a light, but strong support. They are in many buildings replacing masonry piers for supporting girders because of the saving in space, and are extensively used in mill-construction. Typical connections are shown in Fig. 15. The Lally formula for the safe loads in tons is given with Tables XXII and XXIII, page 516.

**Plate-and-Angle Columns.** Four angles and a plate riveted together as shown in Fig. 16 are now being extensively used in building-construction;

particularly for columns having an unsupported length of less than 90 radii; also for the outer columns in steel-mill buildings, and for light columns supporting the roofs of railway stations, etc. Columns with this form of cross-section are especially convenient for making beam and girder-connections and for splicing, and are also well adapted to resist eccentric loads. The width of the plate is generally such that the LEAST RADIUS OF GYRATION is in the direction  $r_2$ , and this radius may be obtained directly from Tables XVI and XVII, pages 370 and 372.




Fig. 18. Spacing of Lattice-bars in Channel-columns




Fig. 19. Steel Channel-column with Lattice-bars

**Channel-Columns.** Typical COLUMN-DETAILS for plate-and-angle and channel-columns, taken from the Carnegie Pocket Companion, 1915 edition, are shown in Figs. 17 and 18 and represent most practice in office-building construction.

**Lattice-Columns.** Two channels, set back to back, at such a distance that the radii of gyration will be equal about both axes, and connected by lattice-bars, as shown in Fig. 19, make a very desirable column for moderate loads, as the upper stories, or in buildings of three or four stories in height. For larger loads, short cover-plates may be riveted to the flanges in place of the lattice-bars. Such columns are very satisfactory, especially for making connections.

**Rule for Latticing of Channels and Angles.** When channels are connected by lattice-work, as in Fig. 20, in order that there may not be a tendency

in the channels to bend between the points of bracing, the distance  $l$  should be made equal to the total length of the strut multiplied by the least radius of gyration of a single channel, and the product divided by the least radius of gyration for the whole section; or,

$$l = r l_1 / r_1$$

- in which
- $l$  = length between points of bracing;
  - $l_1$  = total length of strut;
  - $r$  = least radius of gyration for a single channel;
  - $r_1$  = least radius of gyration for the whole section.

This same rule will also apply to angles, although with them the lattice-work is generally doubled, as in Fig. 21.




Fig. 21. Double Lattice-bars on Angle-columns

It is generally found desirable to make the distance  $l$  less than that obtained by the above formula. The inclination of the lattice-bars with the axis of the column or strut is usually about  $60^\circ$  for single and  $45^\circ$  for double bars.

The proper distance for  $d$  or  $D$ , Fig. 20, for a pair of channels, so that the radius of gyration will be the same in both directions, is given in Table VII page 359.


The following tabulations are taken from the Handbook of the Cambrian Steel Company, 1915 edition.

Sizes of Lattice-Bars to be Used with Latticed Channel-Columns

Depth of channels	Dimensions of lattice-bars		Weight of lattice-bars per foot	Center of hole to end of bar, $a$	Distance center to center of rivets, $d$	
	$w$	Thickness			Maximum	Minimum
in	in	in	lb	in	ft in	in
6	1½	¼	1.28	1½	0 11½	6½
7	1¾	¼	1.49	1½	1 1½	7½
8	2	5/16	2.12	1¾	1 3	8 1½
9	2	5/16	2.12	1¾	1 4½	9½
10	2	¾	2.55	1¾	1 6½	10 1½
12	2½	¾	2.87	1¾	1 10½	13
15	2½	¾	3.19	1¾	2 2½	15 1½



Size of Stay-Plates to be Used with Latticed Channel-Columns

Minimum size of stay-plates at ends of columns			Weight of minimum stay-plates	Diameter of rivets	
b	Thickness	t			
in	in	in	lb	in	
8 1/4	3/4	7 1/4	4.38	5/8	
9 1/4	3/4	10	6.55	5/8	
10 1/4	3/4	9	8.37	5/8	
11 1/4	3/4	12	11.95	5/8	
12 1/4	3/4	12	15.62	5/8	
14 1/4	3/4	15	23.73	5/8	
16 1/4	3/4	15	25.90	5/8	

**Plate-and-Angle and Box Columns.** Plate-and-angle columns, as shown in Fig. 16, requiring but two rows of rivets are very economical columns for buildings of moderate height, as they afford excellent opportunities for connecting the beams and girders. Tables of SAFE LOADS are given in Table XXIV of this chapter. When a more compact section is required than that afforded by the larger sizes, the section-area may be increased by riveting plates to the angles as shown in Fig. 22 which is a section of one of the columns in the Munic-

Fig. 23. Heavy Plate-and-angle Two-web Column

Fig. 24. Heavy Plate-and-angle Three-web Column

York City. This, however, greatly increases the expense and it is therefore usually more economical to substitute s, or channel or box columns. For high buildings or heavy sized sectional areas of columns are greater than can be unnel-columns or Bethlehem columns without flange-plates, f plates and angles, as shown in Fig. 23, which is one of the ers' Trust Company Building, New York City, will prob-ore satisfactory. The thickness and number of web-plates be varied with the load to be supported. Ordinary con- pments are the same as those for CHANNEL-COLUMNS, shown : tallest buildings and heaviest loads box columns with n in Fig. 24 are the best. They are used in the highest h as the Masonic Temple in Chicago, and the Bankers'

Trust Building, the Municipal Building, the Woolworth Building and the Metropolitan Tower in New York City. Fig. 24 is a cross-section of one of the columns in the last-mentioned building. Details of a similar column used in the Bankers' Trust Company Building are shown in Fig. 7 on page 342. It is of course impracticable to give tables of SAFE LOADS for PLATE-AND-ANGLE COLUMNS with flange-plates and for BOX COLUMNS, owing to the great variety of combinations that can be used, but Example 10 of this chapter shows how columns are designed and their strength determined. (See page 485.)

**Steel Struts in Trusses.** These are generally made of a pair of lattice channels, or of channels and plates for heavy trusses with pin-connections, or of either a pair of light channels or a pair of angles with uneven legs for light trusses. For roof-trusses having a span not exceeding 80 ft, a pair of 4 by 6  $\frac{3}{4}$ -in angles is generally sufficient for any of the compression-members unless they are subjected to TRANSVERSE STRESS; and the minor struts are very often made of a pair of 3 $\frac{1}{2}$  by 2 $\frac{1}{4}$  by  $\frac{3}{4}$ -in angles. The angles are placed from 3 to 4 in apart to permit the filler-plates used at the joints to go between them. For compression-members subject to transverse stress a pair of channels generally offers the best section. If necessary the channels can be reinforced with plates at the top and bottom. A pair of angles, with a deep web-plate riveted between, is often used for the principles of Fink trusses where they are subjected to a slight transverse stress. (See, also, Fig. 6, page 1146.) For very heavy compressive stresses and for short members a single angle is sometimes used; this is not considered good practice, as it causes eccentric loading on the gusset plates at the truss-joints. A pair of small angles, or some other combination with a symmetrical cross-section should always be used for truss-members.

Where angles are used in pairs they should be connected by a rivet and a filler-plate or separator every two feet in length, to prevent them from spreading apart. In regard to the maximum length of steel struts in trusses it is not considered good practice to use a strut whose unsupported length exceeds 150 times its least radius of gyration, or 50 times its least width.

### 13. Strength of Steel Columns. Formulas

**Principles Governing the Resistance of Built-up Steel Columns.** Professor William H. Burr states \* that "the general principles which govern the resistance of built-up columns may be summed up as follows: the material should be disposed as far as possible from the neutral axis of the cross-section thereby increasing the radius of gyration,  $r$ ; there should be no initial bending stress; the individual portions of the column should be so firmly secured to each other that no relative motion can take place, in order that the column may act as a whole, thus maintaining the original value of  $r$ ." The experiments by Professor Burr indicate that a closed column is stronger than an open one. It should also be remembered that any column such as an I beam, channel, or angle, the cross-section of which has a maximum and a minimum radius of gyration, is not economical for use under a single concentric load, as the minimum radius of gyration must be used in the calculation, and part of the material is to a certain extent wasted when the ideal efficiency of the column is considered.

**Formulas for Steel Columns.** A great many FORMULAS are used in calculating the strength of steel columns and struts, of the lengths usually employed in practice, but scarcely any two authorities agree upon the same. These formulas may all be grouped into two general classes, those for

\* Elasticity and Resistance of the Materials of Engineering, by William H. Burr.

**RANKINE'S FORMULA** \* (11) and those founded on the **STRAIGHT-LINE FORMULA** (See the following paragraphs.) In the different formulas different values are assigned to the **ARBITRARY CONSTANTS**. Previous to 1888 **RANKINE'S** or **GORDON'S FORMULAS** were almost universally used for all columns, although with more or less variation in the constants employed. About 1885 Professor Burr, after having conducted a series of tests upon full-size column-sections deduced what is now known as the **STRAIGHT-LINE FORMULA**. As this is easier of application than **RANKINE'S FORMULA**, it has gradually found favor with engineers, especially as the results differ but little from those obtained by the older formula.

**Formulas Compared.** Which one, of all the formulas in use, should be employed in calculating the safe load for columns is an open question, but the author, after careful deliberation, has decided to recommend **RANKINE'S FORMULA** for the following reasons. In the first place it is safe and conservative and if it errs at all, it is on the side of safety; and in the second place it has a wider application, as the values assigned to the arbitrary constants have been generally agreed upon, whereas there is a greater variety in the values of the constants employed in the **STRAIGHT-LINE FORMULA**. Of course one is not free to choose when city laws compel the use of certain formulas. No tables of **SAFE LOADS** for columns, satisfying the requirements of all cities, could be compiled. The author has accordingly thought it best to insert the various tables of **SAFE LOADS** for different forms of columns as computed in the very latest handbooks although not necessarily based upon **RANKINE'S FORMULA**, and to insert Table XI, specially computed and giving the comparative **SAFE LOADS IN POUNDS PER SQUARE INCH OF METAL-AREA** for columns, as determined by seven different formulas. (See pages 493 to 495.)

**Formulas Used in Building Codes.** **RANKINE'S FORMULA** (called **GORDON'S FORMULA** in many codes) is specified in the building codes of the following cities: Philadelphia, Pittsburgh, Baltimore, and Milwaukee; and in the Cambria handbook. The **STRAIGHT-LINE FORMULA** is specified in the building codes of New York City, Chicago, St. Louis, Minneapolis, Boston, and in many other places, and is used in the Carnegie and Bethlehem handbooks.

**Formulas Used in Practice.** The following formulas, in the opinion of the author, represent the best current practice. They are **FORMULAS FOR SAFE LOAD, S**, in pounds per square inch of cross-section, on steel columns and struts. In these formulas  $l$  is the **LENGTH** of the column in inches and  $r$  the **LEAST RADIUS OF GYRATION** of the cross-section. (See, also, Chapter X, pages 333, 344, etc.) The **SAFE LOAD, P**, for any column is equal to  $S$ , obtained by one of the following formulas, multiplied by the **SECTION-AREA** of the column in square inches;

$$P = AS \quad (10)$$

**Rankine's formula**, used in the Cambria handbook, is

$$S = \frac{12\,500}{1 + l^2/36\,000\,r^2} \quad (11)$$

**Formula recommended by Professor Burr** is

$$S = 10\,000 - 40\,l/r \quad (12)$$

**Formula used by the American Bridge Company and Carnegie's Pocket Companion** is

$$S = 19\,000 - 100\,l/r \quad (13)$$

a maximum of 13 000 lb per sq in.

**Rankine's formula** is sometimes referred to as **Gordon's formula**, but Gordon used the lateral dimension or the diameter of the column instead of the least radius of the cross-section.

The formula used by the American Railway Engineering Association and the New York and Chicago building codes is

$$S = 16\,000 - 70l/r$$

with a maximum of 16 000 lb per sq in for New York and 14 000 for the others.

The formula used in the New York City building code previous to 1916

$$S = 15\,200 - 58l/r$$

The formulas used in the Catalogue of the Bethlehem Steel Company are

$$S = 16\,000 - 55l/r, \text{ for } l/r \text{ over } 55$$

and

$$S = 13\,000 \text{ lb per sq in, for } l/r \text{ under } 55$$

Fowler's slightly modified formula for steel struts in trusses is

$$S = 12\,500 - 50l/r$$

The value 50 in Fowler's formula is  $41\frac{2}{3}$  when  $l$  is in inches, and 500 when  $l$  is in feet.

For a comparison of most of these formulas, see Table XI, pages 493 to 496, and the COMPARATIVE DIAGRAM OF FORMULAS, page 496.

#### 14. Design of Steel Columns. Examples

**Practical Use of Column-Formulas.** Unlike the beam-formula the column-formulas in general use do not give a direct method of calculating the dimensions of a column that will support a given load, owing to the presence in the column-formula of two unknown quantities,  $A$  and  $r$ , which are dependent upon each other. Hence in designing columns, the section must be first assumed and then tested for the safe load  $P$ , or for the maximum unit fiber-stress  $S$ . This is an apparently roundabout method of designing columns, but unfortunately there seems to be no more direct way. When a column is to be selected for design, its axial load  $P$  is given and also its length and the condition of its ends. A proper allowable unit stress,  $S$ , is assumed, suitable for the material and for the conditions under which it is to be used, or in accordance with the requirements of the local building code; or the value of  $S$  is given in the specification according to which the column is to be designed. A section is then selected in accordance with the principles explained on pages 467 to 469. For this assumed cross-section  $A$  and  $r$  are determined and then substituted in the formula, which is solved for  $P$ . If the assumed dimensions give a value for  $P$  that agrees with the actual load, they are correct. If, however, the resulting value of  $P$  is smaller than the actual load, the assumed size is too small, and it will be necessary to choose a larger size and solve again. On the contrary, the actual load is less than the safe calculated load, a column of a smaller element of cross-section is assumed and a new value of  $P$  obtained. After a few trials a size that gives a satisfactory result for the required conditions will be found.

**Examples Illustrating the Use of Column-Formulas and Tables.** The column-tables in the last half of this chapter give the safe loads of the various types of column-sections of current practice, having determined which section is most advisable to use under any given conditions, it is merely necessary to consult the tables and select the column of the required size to support the load.

**Example 7.** The following is an example showing the method of selecting a BETHLEHEM ROLLED H COLUMN for buildings.

### Example Showing the Method of Selecting Bethlehem Rolled H Columns for Buildings

For illustration, the interior columns of an actual sixteen-story building are taken as example. The story-heights and the loads on the columns are given in the following relation:

Stories	Heights of stories, ft	Loads on columns, tons	Safe loads, tons	H column-section required				
				Dimensions			Weights of sections, lb per lin ft	Section-numbers
				D, in	T, in	B, in		
16th	12	27	55.0	7 $\frac{1}{8}$	$\frac{3}{16}$	8.00	31.5	H8
15th	13	53	81.5	8 $\frac{3}{8}$	1 $\frac{1}{16}$	8.12	48.0	H8
14th	14	79						
13th	13	104	132.2	10 $\frac{3}{8}$	1 $\frac{9}{16}$	10.12	71.0	H10
12th	13	128						
11th	13	151	174.8	12 $\frac{1}{4}$	$\frac{7}{8}$	12.08	91.5	H12
10th	13	174						
9th	13	197	219.1	14 $\frac{1}{4}$	1 $\frac{5}{16}$	14.08	114.5	H14
8th	13	219						
7th	13	241	263.8	14 $\frac{5}{8}$	1 $\frac{3}{8}$	14.19	138.0	H14
6th	13	261						
5th	13	281	310.1	15	1 $\frac{9}{16}$	14.31	162.0	H14
4th	13	301						
3d	13	321	341.3	15 $\frac{1}{4}$	1 $\frac{7}{16}$	14.39	178.5	H14
2d	15	341						
1st	17	363	403.5	15 $\frac{3}{4}$	1 $\frac{1}{2}$	14.54	211.0	H14
Basement	12	395						

$D$  is the depth of the column,  $T$  the thickness of the flanges and  $B$  the breadth of the flanges.

Columns for buildings are usually selected in lengths of two stories. By inspection of the tables of safe loads for H columns, it is found that no columns smaller than 14-in H sections have sufficient capacity for the lower stories. Where there is no limitation as to the size of the column, the column with the largest dimensions and having the required capacity will be the most economical. The unsupported length of a column should not exceed 150 radii of gyration, which is the limit of length for which safe loads are given in the tables. In the best practice the unsupported length of a column is frequently required not to exceed 120 or 125 times the least radius of gyration; various limits for  $L/r$  are indicated in the tables by zigzag lines. The safe loads given in the tables are for eccentric or symmetric loading. When the loads are not centrally or symmetrically applied, the size of the column should be calculated by Formula (18), page 486.

**Example 8.** Suppose that in a 20-story office-building to be erected in Chicago, the load on each of the first-story columns, which are 16 feet in length, is 700 tons. What columns should be used?

Turning to Table XXI, page 515, giving the safe loads for Bethlehem 14-in H columns it is seen that a 14-in 287.5-lb column, the heaviest rolled, will support only 549.3 tons; this type of column, therefore, cannot be used. More-

over a casual inspection of the tables of safe loads for plate-and-angle and channel-columns shows that they are not suitable because of the thick flange and web-plates required. Consequently the columns in the lower stories probably have to be of the box type, with double or triple webs, as shown in Figs. 23 and 24. The upper columns, however, may be of the plate-and-angle or channel-type, whichever will be the more economical. The heaviest plate-and-angle column, without flange-plates (Table XXIV, page 522), composed of four 6 by 4 by  $\frac{3}{4}$ -in angles and one 12 by  $\frac{1}{2}$ -in web, will support, for a length of 14 feet, the height of most of the upper stories, 469 000 lb; and a channel-column (Table XXVI, page 541) composed of two 12-in 30-lb channels and 14 by  $\frac{3}{4}$ -in plates will support 502 000 lb. The former weighs 125 and the latter 131.4 lb per lin ft, so there is not much choice as far as economy of material is concerned. The channel-column, however, requires four rows of rivets while the plate-and-angle column requires only two rows, so this added expense of fabrication would have to be considered. Assuming, however, that the plate-and-angle type is more desirable, the next step is to design the individual columns.

The load upon each of the uppermost columns, which are 20 ft in length, is 70 000 lb. Turning to Table XXIV, page 518, it will be seen that a column composed of four 4 by 3 by  $\frac{3}{8}$ -in angles and one 8 by  $\frac{3}{8}$ -in web will support for a length of 20 ft, 77 000 lb; but this load is below the lower zigzag line, hence the slenderness-ratio of the column exceeds 120. Assuming, for the purpose of illustration, that the limit of  $l/r$  is 120, a heavier section must be selected. On page 519 of Table XXIV, continued, it is seen that the lightest 20-ft column, for which  $l/r$  does not exceed the required ratio, is one composed of four 5 by  $3\frac{1}{2}$  by  $\frac{3}{8}$ -in angles and one 10 by  $\frac{3}{8}$ -in web, and that for a length of 20 ft it will support 121 000 lb, or 51 000 lb more than will come upon it.

Continuing the design of the columns, suppose that one in the 14th story, 14 ft in length, supports 175 tons, or 350 000 lb. From Table XXIV, page 518, it is found that a column composed of four 6 by 4 by  $\frac{3}{8}$ -in angles and one 12 by  $\frac{1}{2}$ -in web-plate, for a length of 14 ft, will carry 373 000 lb. In the table, the safe load is calculated by Formula (13), whereas the Chicago Building Code specifies Formula (14). Hence, as this building is to be erected in Chicago, the chosen column must be tested by the latter formula. Its  $A$  is 29.44 sq in., its least  $r$ , 2.65 in. To test it by the formula,  $l = 14 \text{ ft} \times 12 = 168 \text{ in}$ , and  $l/r = 168 \text{ in} / 2.65 \text{ in} = 63$ . Substituting in Formula (14),  $S = 16 000 - (70 \times 63) = 16 000 - 4 410 = 11 590 \text{ lb per sq in}$ . From Formula (10), the safe load for the column,  $P = AS = 29.44 \text{ sq in} \times 11 590 \text{ lb per sq in} = 341 209 \text{ lb}$ , which is less than the actual load. Therefore, the next heavier column, with angles  $1\frac{1}{2}$  by 1 $\frac{1}{2}$  by  $\frac{3}{8}$ -in thick, should be selected.

**Example 9.** In an office-building to be erected in Philadelphia, the use of Bethlehem rolled-steel H columns has been decided upon. One of these columns, 15 ft in length, supports 170 000 lb, or 85 tons. What should be the size of this column?

According to Table XIX, page 508, giving the safe loads for Bethlehem rolled-steel H columns, a 10-in 49-lb column, 15 ft in length, will carry 86.3 tons, an apparent safe load. Bethlehem-column loads, however, are calculated by the straight-line formula, whereas in Philadelphia, Rankine's (called Gordon's) formula is standard. This formula with the arbitrary constants inserted is

$$S = \frac{16\,250}{1 + \frac{l^2}{11\,000} (1/r)^2} \quad (\text{See Table XI, page 493.})$$

From Table XIX,  $A = 14.37$  sq in and the least  $r = 2.49$  in;  $l$  is 15 ft or 180 in  
 $l/r = 180 \text{ in}/2.49 \text{ in} = 72.3$ .

Substituting in the formula,

$$S = \frac{16\,250}{1 + \frac{1}{11\,000} (72.3)^2} = \frac{16\,250}{1 + 5\,227/11\,000} = \frac{16\,250}{16\,227/11\,000}$$

$$= \frac{16\,250 \times 11\,000}{16\,227} = \frac{178\,750\,000}{16\,227} = 11\,015 \text{ lb per sq in}$$

and from Formula (10), page 481,

$$P = AS = 14.37 \text{ sq in} \times 11\,015 \text{ lb per sq in} = 158\,285 \text{ lb or } 79.1 \text{ tons,}$$

which is less than the tabular load. Hence the next heavier column, weighing 54 lb per sq ft, would have to be used.

**Example 10.** Figure 7, page 342, shows the cross-section of one of the basement-columns in the Bankers' Trust Company's Building, New York City. It is 20 ft in length and supports 2 230 tons. Is the column safe?

The first step is to find its least radius of gyration which is equal to  $\sqrt{I/A}$ . The least moment of inertia of this section was found to be 17 030. (See page 343.) The area is made up as follows:

**FLANGES.** The flanges are composed of six 27 by  $\frac{3}{4}$ -in plates and two 27 by  $1\frac{1}{16}$ -in plates. The area of the cross-section of each 27 by  $\frac{3}{4}$ -in plate is 20.25 sq in and of the six plates, 121.50 sq in. The area of the section of each 27 by  $1\frac{1}{16}$ -in plate is 18.56 sq in and of the two plates, 37.12 sq in. Hence the total sectional flange-area is  $121.50 + 37.12 =$

158.62 sq in

**FLANGE-ANGLES.** Each flange-angle is 6 by 6 by  $1\frac{1}{16}$  in. Its section-area is 10.38 sq in. Hence for the four,  $A = 10.38 \times 4 =$

41.52 sq in

**OUTER WEB.** The outer web-plates are each 18 by  $1\frac{1}{16}$  in. The area of each one is 12.375 sq in and of the eight

99.00 sq in

**WEB.** Each web-angle is 6 by  $3\frac{1}{2}$  by  $1\frac{1}{16}$  in with a section-area of 8.03 sq in; and for four angles the section-area is

32.12 sq in

**WEB.** The web is composed of two 18 by  $\frac{9}{16}$ -in plates, each with a section-area of 10.125 sq in. For two the area is

20.25 sq in

The area of the entire section, therefore, is

351.51 sq in

$$r^2 = I/A = 17\,030/351.5 = 48.5 \text{ and } r = \sqrt{48.5} = 7 \text{ in}$$

$$l = 20 \text{ ft} = 240 \text{ in and } l/r = 240 \text{ in}/7 \text{ in} = 34.3$$

Substituting in the former New York City building code Formula (15), page 482,

$$S = 15\,200 - 58 \times 34.3 = 15\,200 - 1\,989 = 13\,211 \text{ lb per sq in}$$

From Formula (10)

$$P = AS = 351.5 \text{ sq in} \times 13\,211 \text{ lb per sq in} = 4\,643\,666 \text{ lb, or } 2\,321 \text{ tons.}$$

Hence the column is perfectly safe.

## 15. Eccentric Loading of Steel Columns

**General Principles.** Where columns are used in tiers, one above another, the beams and girders which they support must necessarily rest upon brackets projecting or extending varying distances beyond the shell or section-areas or ends of the columns. Such connections cause BENDING MOMENTS in the columns. If equal loads are applied at equal distances on opposite sides of a column,

the bending moments caused by them in the column balance each other, and the CENTER OF STRESS may be considered as coinciding with the axis of the column. When, however, a load is applied on one side (Fig. 25) without corresponding load on the opposite side, it is called an **ECCENTRIC LOAD** and the area of the cross-section of the column should be increased correspondingly. There is unfortunately no direct method by which this additional area can be determined. The usual method of procedure is to assume a section in excess of that required to support the total load and then compute the fiber-stress due to the combined balanced and eccentric loads. If this works out too large or too small another trial is made.

**Formula for Eccentric Loads on Steel Columns.** The following formula (compare with Fig. 25) is used to determine the combined fiber-stresses due to the concentric and eccentric loads (See, also, page 453):

Let  $P$  = the concentric or balanced load in pounds,

$P_1$  = the eccentric load in pounds,

$M$  = the bending moment due to the eccentric load in inch-pounds =  $P_1 x$

$x$  = the eccentricity of the load  $P_1$  in inches. (See note below:)

$I$  = the moment of inertia of the area of the cross-section of the column about an axis at right-angles to the direction of the bending,

$c$  = the distance of the outermost fiber of the cross-section from the same axis

$A$  = the area of column-section in square inches and

$S$  = the actual fiber-stress in pounds per square inch

$$S = (P + P_1)/A + Mc/I$$

Fig. 25. Channel-column with Eccentric Load. Elevation

**Note.** In measuring the **ECCENTRICITY**, the distance,  $x$ , is generally measured from the axis of the column to the center line or half-breadth line of the bracket or bearing.

**Examples of Eccentric Loading of Steel Columns.** The following examples illustrate the use of the formula and tables in determining the safe eccentric loads for steel columns.

**Example 11.** The total load on the top of a column 32 ft in length is 194 000 lb, of which 30 000 lb come from the end of a girder. There is no corresponding load on the opposite side. (See Fig. 26.) It is proposed to use a channel-column. What is the size of the required column?

By referring to Table XXVI, page 539, it is seen that a column composed of two 12-in 20.7-lb channels and two 14 by  $\frac{3}{8}$ -in plates will support, for a length of 32 ft, 227 000 lb, a somewhat greater load than will come on the column. For the section of this column,  $I_x = 415$ ,  $A = 22.56$  sq in,  $r = 4.29$  in and  $I_y = 14.7$




Fig. 26. Channel-column with Eccentric Load. Section



$34/4.39 = 89$ . Substituting in Formula (11), page 481, to find the safe unit fiber-stress

$$S = \frac{12\,500}{1 + \frac{1}{36\,000} (l/r)^2} = \frac{12\,500}{1 + (89)^2/36\,000} = \frac{12\,500}{1 + 7\,921/36\,000} = \frac{12\,500}{43\,921/36\,000}$$

$$= \frac{12\,500 \times 36\,000}{43\,921} = \frac{450\,000\,000}{43\,921} = 10\,245 \text{ lb per sq in}$$

The actual stress in pounds per square inch of the column-section is found by Formula (18),  $S = (P + P_1)/A + Mc/I$ .  $P = 164\,000$  lb,  $P_1 = 30\,000$  lb,  $A = 22.56$  sq in and  $M = P_1 x$  in-lb.  $x$  = the distance in inches from the axis  $x-x$  of the column to the outside of the web, plus the distance from the outside of the web to the center of the bracket. The former distance can be found from Table XXVI. It is 4 in. Let the distance from the outside of the web of the channel to the center of the bracket riveted to the web of the channel be 2 in, the projection of the bracket being 4 in; then  $x$ , the lever-arm of the moment of the load  $P_1$ , or the eccentricity, is 4 in + 2 in = 6 in.  $M$ , therefore, is  $P_1 x$  or  $30\,000$  lb  $\times$  6 in.  $c$  is 7 in, since the plates are 14 in wide.  $I_{x-x} = 415$ . Substituting in Formula (18)

$$S = \frac{164\,000 + 30\,000}{22.56} + \frac{30\,000 \times 6 \times 7}{415} = 8\,600 + 3\,036 = 11\,636 \text{ lb per sq in}$$

As this exceeds the safe unit fiber-stress of 10 245 lb per sq in, the column-section is too small.

For a second trial, consider a 12-in, 20.7-lb channel-column with 14 by  $\frac{1}{2}$ -in plates. For this section,  $I_{x-x} = 473$ ,  $A = 26.66$  sq in,  $r_{x-x} = 4.26$  in and  $l/r = 34/4.26 = 90$ .

$$S = \frac{12\,500}{1 + (90)^2/36\,000} = \frac{12\,500}{1 + 8\,100/36\,000} = \frac{12\,500}{44\,100/36\,000}$$

$$= \frac{12\,500 \times 36\,000}{44\,100} = 10\,204 \text{ lb per sq in.}$$

The actual stress from Formula (18), as before, is

$$S = \frac{164\,000 + 30\,000}{26.66} + \frac{30\,000 \times 6 \times 7}{473} = 7\,444 + 2\,664 = 10\,108 \text{ lb per sq in}$$

As this is less than the safe stress of 10 204 lb, the second selection is safe.

**Example 12.** A Bethlehem H column 14 ft long carries 90.56 tons, of which 15.52 tons are eccentric, being applied to the flange of the column as shown in Fig. 27, the distance from the outside of the flange to the center of the bearing being 2 in. What is the size of the column required?

Try a 12-in, 84.5-lb column, which, for a length of 14 ft, or 168 in, will carry 161.4 tons (Table XX). For this column,  $A = 24.92$ ,  $r_{x-x} = 3.03$ ,  $I_{x-x} = 676.1$ ,  $I_{y-y} = 228.5$  and  $l$  is 14 ft, or 168 in; hence  $l/r = 168/3.03 = 55$ . Substituting in Formula (15), assuming that that formula is specified,  $S = 15\,200 - 58 \times 55 = 12\,010$  lb per sq in. Since the eccentric load causes bending in a direction at right-angles to the axis  $x-x$ , Fig. 27, the bending moment due to the eccentric load is  $P_1$ , or 15.52 tons or 31 040 lb, multiplied by its lever arm  $x$ , which is the distance from the axis  $x-x$  to the outside of the flange plus the distance from this surface to the center of bearing. The former dimension, taken from the Bethlehem Catalogue, is  $6\frac{1}{8}$  in and the latter is 2 in; hence  $x = 8\frac{1}{8}$  in or for convenience, 8 in. The distance,  $c$ , also, of the outermost fiber from the axis

1-1 is  $6\frac{1}{8}$  in, which for convenience will be considered 6 in.  $I_{1-1}$  about the axis 1-1 is 676.1. Substituting in Formula (18),  $S = (150\,080 + 31\,040)/24.92 + (31\,040 \times 8 \times 6)/676.1 = 7\,268 + 2\,204 = 9\,472$  lb per sq in. As this is far below the safe stress of 12 010 lb, the column selected is too large, and a smaller one, probably a 12-64.5-lb column would prove sufficient.




Fig. 27. Bethlehem H Column with Eccentric Load

Suppose, on the other hand, the eccentric load were applied to the web and the balanced loads to the flanges. The safe unit fiber stress, as before, is 12 010 lb per sq in, for no matter how the loads are applied, the safe unit stress determined by reference to the least radius of gyration,  $r_{2-2}$ , should not be exceeded. Under the second condition of loading the eccentric load, also, will cause bending about this same axis 2-2; hence in Formula (18) the  $I$  for this axis, which is 228.5, must be used.  $x = 2$  in + 0.25 in = 2.25 in, 0.25 in being one-half the thickness

of the web. (See the Bethlehem Catalogue.) Hence, from Formula (18), the actual unit fiber-stress is  $S = (150\,080 + 31\,040)/24.92 + (31\,040 \times 6 \times 2.25)/228.5 = 7\,268 + 1\,835 = 9\,103$  lb per sq in.

## 16. Tables of Safe Loads for Steel Columns

**Safe Loads per Square Inch of Metal-Area for Steel Columns and Struts.** To lessen the labor of calculating the strength of steel columns and struts, of whatever shape, the author has computed Table XI, which gives SAFE VALUES of  $S$  for ratios of  $l/r$  varying from 30 to 120. For ratios of  $l/r$  which are not whole numbers, the values can be readily interpolated. The values in the table should correspond exactly with the results obtained by using the corresponding formulas.

**Safe Loads for Steel-Pipe Columns.** Tables XII and XIII give the SAFE LOADS for STEEL-PIPE COLUMNS. These loads are based upon the formula recommended by the New York and Chicago Codes,  $S = 16\,000 - 70\,l/r$ . (See Steel Pipe Columns, pages 469 to 474.)

**Safe Loads for Channel and Angle-Struts.** Tables XIV, XV, and XVI give the SAFE LOADS for standard CHANNELS and ANGLES used as STRUTS. On those sizes that are most commonly used are given. In Table XIV the SAFE LOADS for both the minimum and the maximum RADIUS OF GYRATION are given. If the strut is used also as a beam, or is stayed so that it cannot bend sideways, the larger value may be taken; but if free to bend in either direction, then the smaller value should be taken. If the struts are subjected to a TRANSVERSE STRESS they should be computed as explained under the heading Strut-Beam, pages 571 and 572.

**Safe Loads for Steel-Beam Columns, Bethlehem Columns, Lally Columns, Plate-and-Angle and Channel Columns.** Tables XVII to XXV, giving the SAFE LOADS for these columns, were not computed by the author but by the different manufacturers; they are, however, believed to be perfectly safe, provided that an increase in area is made for ECCENTRIC LOADS.

**Use of Table XI for Determining Safe Loads for Steel Columns.** This table will be found of great assistance in calculating the strength of columns.

gus and of struts and also in making calculations for eccentric loads. To use Table XI to find the strength of a column, it is merely necessary to multiply the value corresponding to the **SLENDERNESS-RATIO** of the column, by the **SECTION-AREA**, the result being the **SAFE LOAD** the column can support. As an illustration of this, the column considered in Example 8 has a slenderness-ratio of 63 and a section-area of 29.44 sq in. Its strength is to be calculated by the Chicago Building Code formula, the results of which are tabulated in the sixth column of Table XI. From this the value of a slenderness-ratio of 63 is 11 590 lb per sq in. Therefore, by the rule stated above, the safe load is 11 590 lb per sq in  $\times$  29.44 sq in = 341 209 lb. In Example 10, the column in the Bankers' Trust Company Building has a slenderness-ratio of 34.3, and an area of 351.5 sq in. The value corresponding to 34, from column 5 of Table XI, is 13 228 and for 35 it is 13 170 lb per sq in; hence for 34.3 it would be about 13 211 lb per sq in. Accordingly, the safe load is 13 211 lb per sq in  $\times$  351.5 sq in = 4 643 666 lb. Column 5 of Table XI gives values for old New York code.

**Example 13.** What is the safe resistance of a strut composed of two 5-in 9-lb channels, separated  $\frac{3}{4}$  in and free to bend in either direction, the length of the strut being 7 ft 6 in?

**Solution.** From Table XVIII, page 374, the least radius of gyration for this section is 1, hence  $l/r = 90/1 = 90$ . From the eighth column of Table XI, the value of  $S$  opposite 90 is 8 000 lb per sq in; the safe load, then, is equal to 8 000 lb per sq in, multiplied by the area of the two channels, 5.26 sq. in, or 42 080 lb.

**Example 14.** What is the safe stress for a 7-in 15.3-lb I beam when used as a strut? It is 90 in in length and free to bend in either direction.

**Solution.** From Table IV, page 355, the least radius of gyration of this section is 0.78, and the area is 4.43 sq in.  $l/r = 90/0.78 = 115.4$ . From the eighth column of Table XI, the value opposite 115 is 6 750 and opposite 116 it is 6 700 lb per sq in; so for 115.4 it would be about 6 730 lb per sq in. The safe load, therefore, is 6 730 lb per sq in  $\times$  4.43 sq in = 29 814 lb.

By means of the tables and rules given in Chapter X the **SECTION-AREA** and **LEAST RADIUS OF GYRATION** of any standard section or any combination of sections may be found; and once these are determined the strength of a strut or column may be readily computed, as in the above examples.

**Use of Table XI for Eccentric Loads for Steel Struts.** As an illustration of its application to determine eccentric loads, refer again to Example 11. The value of  $l/r$  for this column is 89. The safe unit fiber-stress was found to be, by Formula (11), 10 245 lb per sq in. The practically identical result can be obtained by looking for the value opposite 89 in column 2 of Table XI. It is found to be 10 250 lb.

**Proportion of Floor-Loads Borne by Columns.** (See, also, pages 148 to 152.) In tall buildings it is customary to reduce the **COLUMN-LOADS** somewhat from the loads used in calculating the floor-beams. This is done on the theory that it is quite impossible for the entire floor-area of every story to be loaded to the maximum limit at the same time. For all buildings except warehouses it would seem, in general, to be good practice to design the columns to carry all the **DEAD LOAD** and 75% of the assumed **LIVE LOAD**. Of course city laws vary in these requirements. Thus, if in an office-building, the dead load, or weight of the floor-construction, is 80, and the live load 80 lb per sq ft, the load on the columns would be  $80 + 60 = 140$  lb per sq ft times the floor-area supported by the column. In some cases the reduction might be even greater, depending upon the live load assumed and the position of the column in the building, the reductions being greater in the lower than in the upper stories.

The Building Code of New York City specifies that for buildings exceeding five stories in height the COLUMN-LOADS shall be made up as follows: For the roof and top floor the full live loads shall be used; for each succeeding lower floor it shall be permissible to reduce the live load by 5% until 50% of the full load is reached, when such reduced loads shall be used for all remaining floors. (For assumed loads for office-buildings, required by the building codes of several cities, see page 151).

**Column-Sheets.** In a high building the COLUMN-LOADS vary to such an extent and are made up of so many elements, that to avoid omissions and errors it is necessary to make a TABULATED LIST of all the loads transferred through the columns to the footings. In a building of skeleton construction the COLUMN-LOADS include floor and roof-loads, wind-loads, spandrel and pier-loads, the weight of the columns themselves and their fire-proof covering, and in some cases special loads, such as tanks, vaults, safes and elevator-loads. In tabulating the FLOOR-LOADS it is advisable to separate the dead and live loads for convenience in proportioning the footings. (See, also, pages 148 to 160.) Formulas for computing the WIND-LOADS on columns are given in Chapter XXIX; the loads, also, are considered as live loads. ECCENTRIC LOADS should always be tabulated separately from the balanced column-loads. On page 491 is shown a form of COLUMN-SHEET which combines all ordinary requirements. The TOTAL LOAD for each story is the sum of all of the loads above. The SCHEDULE on page 492 shows a very convenient form for column-lengths and column-pairs.

**Important Notes Regarding Safe Loads on Columns.** (See pages 504 and 505, and 517 to 554.) "For ratios of  $l/r$  up to 120 and for greater ratios up to 200, use the values given in the following table for the allowable stress in pounds per square inch. For intermediate ratios, use proportional amounts.

Ratio	Amount	Ratio	Amount
60	13 000	130	6 500
70	12 000	140	6 000
80	11 000	150	5 500
90	10 000	160	5 000
100	9 000	170	4 500
110	8 000	180	4 000
120	7 000	190	3 500

"(5). For bracing and combined stresses due to wind and other loading the permissible working stresses may be increased 25 per cent, provided the section thus found is not less than that required by the dead and live loads alone."

"(6). General. The effective or unsupported length of main compression members shall not exceed 120 times, and for secondary members 200 times, the least radius of gyration."

The values for ratios of  $l/r$  above 120 are computed from the formula

$$S = 13\,000 - 50\,l/r,$$

but the important condition should be observed, that for  $l/r$  above 120, compression-members should never be used for main members but only as secondary members subject to wind-stresses, etc. (See, also, page 495 for maximum ratio of  $l/r$  for main members and for secondary members, such as bracing struts, etc.)

\* From the Construction Specifications of the American Bridge Company.

## Form of Column-Sheet

Story	Character of loading	Column No. 1		Column 2
		Load on column, concentric	Load on column, eccentric	
1st or	Roof and ceiling, dead load.....			
	Roof and ceiling, live load.....			
	Masonry piers.....			
	Spandrels, cornice, etc.....			
	Elevators.....			
2nd or	Tanks.....			
	Column and casing.....			
	Wind-load.....			
	Total.....			
	Sectional area required.....	sq in	sq in	
3rd or	From column above.*			
	Floor, dead load.....			
	Floor, live load.....			
	Masonry piers.....			
	Spandrels.....			
4th or	Saves, vaults, etc.....			
	Column and casing.....			
	Wind-load.....			
	Total.....			
	Sectional area required.....	sq in	sq in	
Basement	From column above.*			
	Floor, dead load.....			
	Floor, live load.....			
	Masonry piers.....			
	Spandrels.....			
Footings	Sidewalk.....			
	Column and casing.....			
	Wind-load.....			
	Total.....			
	Sectional area required.....	sq in	sq in	
Footings	Deduct ( $\frac{1}{2}$ ) live load.....			
	Total footing-load.....			
	Area of footing required.....	sq ft		

\* In bringing down the load from the column above, the eccentric loads may be added to the concentric loads and their sum placed in the first column.

Schedule of Column-Lengths and Parts

	Column No. 1	Column No. 2	
Roof-line			
Top of columns	↑ 1' 6½" ↓		
7th story	↑ ½"		
7th Floor-line	23' 4"	Four angles 4" X 3" X ¾" One plate 7" X ¾"	
6th Story	↓		
6th Floor-line	↑ 2' 2" ↓		
5th Story	13' 10"	Four angles 5" X 3" X ¾" One plate 7" X ¾"	
	↓ ¾"		
5th Floor-line	↑ 4½" ↓		
	↑		
	↓ ¾"		
1st Floor-line	↑ 1' 2¼" ↓		
Basement	11' 2"	Four Z's 4" X ¾" One plate 7" X ¾"	
Top of stool	↓		
Grade 15.0	↑ 8½" ↓		

III. Safe Loads in Pounds per Square Inch of Metal Area for Steel Columns and Struts

$l$  = length in inches

$r$  = least radius of gyration in inches

Rankine's (Gordon's) and Cambria	Phila- delphia	Boston, before 1919	Wash- ington, D. C.†	Chi- cago ‡ and N. Y.	Am. Bridge Co. and Carnegie	Powder's formula for struts	$l/r$
$\frac{18,000}{1 + \frac{l^2}{36,000 r^2}}$	$\frac{16,350}{1 + \frac{l^2}{11,000 r^2}}$	$\frac{16,000}{1 + \frac{l^2}{20,000 r^2}}$	$15,200 - 58 l/r$	$16,000 - 70 l/r$ Chi. 14,000 max N. Y. 16,000 max	$19,000 - 100 l/r$ 13,000 max	$12,500 - \frac{1}{4} \frac{l^2}{r^2}$	
II	III	IV	V	VI	VII	VIII	IX
12 195	15 020	15 310	13 460	13 900	13 000	11 000	30
12 170	14 945	15 265	13 402	13 830	13 000	10 950	31
12 155	14 865	15 220	13 344	13 760	13 000	10 900	32
12 135	14 785	15 175	13 286	13 690	13 000	10 850	33
12 110	14 705	15 125	13 228	13 620	13 000	10 800	34
12 090	14 620	15 075	13 170	13 550	13 000	10 750	35
12 065	14 535	15 025	13 112	13 480	13 000	10 700	36
12 045	14 450	14 975	13 054	13 410	13 000	10 650	37
12 020	14 365	14 925	12 996	13 340	13 000	10 600	38
11 995	14 275	14 870	12 938	13 270	13 000	10 550	39
11 970	14 185	14 815	12 880	13 200	13 000	10 500	40
11 945	14 095	14 760	12 822	13 130	13 000	10 450	41
11 920	14 005	14 705	12 764	13 060	13 000	10 400	42
11 890	13 915	14 650	12 706	12 990	13 000	10 350	43
11 860	13 820	14 590	12 648	12 920	13 000	10 300	44
11 835	13 725	14 530	12 590	12 850	13 000	10 250	45
11 805	13 630	14 470	12 532	12 780	13 000	10 200	■
11 780	13 535	14 410	12 474	12 710	13 000	10 150	47
11 750	13 440	14 350	12 416	12 640	13 000	10 100	48
11 720	13 340	14 285	12 358	12 570	13 000	10 050	49
11 690	13 240	14 220	12 300	12 500	13 000	10 000	50
11 660	13 145	14 160	12 242	12 430	13 000	9 950	51
11 620	13 045	14 095	12 184	12 360	13 000	9 900	52
11 585	12 945	14 030	12 126	12 290	13 000	9 850	53
11 565	12 845	13 965	12 068	12 220	13 000	9 800	54
11 530	12 745	13 900	12 010	12 150	13 000	9 750	55
11 500	12 645	13 835	11 952	12 080	13 000	9 700	56
11 465	12 545	13 770	11 894	12 010	13 000	9 650	57
11 430	12 445	13 700	11 836	11 940	13 000	9 600	58
11 400	12 345	13 630	11 778	11 870	13 000	9 550	59
11 365	12 240	13 560	11 720	11 800	13 000	9 500	60
11 330	12 140	13 490	11 662	11 730	12 900	9 450	61
11 295	12 040	13 420	11 604	11 660	12 800	9 400	■
11 260	11 940	13 350	11 546	11 590	12 700	9 350	63
11 225	11 840	13 280	11 488	11 520	12 600	9 300	■
11 185	11 740	13 210	11 430	11 450	12 500	9 250	65
11 150	11 640	13 140	11 372	11 380	12 400	9 200	66
11 115	11 540	13 070	11 314	11 310	12 300	9 150	67
11 080	11 440	13 000	11 256	11 240	12 200	9 100	68
11 040	11 340	12 925	11 198	11 170	12 100	9 050	69

■ AISC Code, 20,000—100  $l/r$ ; maximum, 17,000.

New York Code, Newark, N. J., Atlanta, Ga., Worcester, Mass., etc.

† Engrg. Ass'n the same up to  $l/r$ , 100, for main members. Maximum, 14,000.

Table XI (Continued). Safe Loads in Pounds per Square Inch of Metal for Steel Columns and Struts

 $l$  = length in inches $r$  = least radius of gyration in inches

	Rankine's (Gordon's) and Cambria	Phila- delphia	Boston,* before 1919	Wash- ington, D. C.†	Chi- cago ‡ and N. Y.	Am. Bridge Co. and Carnegie	Fowler's formula for struts
$l/r$	$\frac{12,500}{1 + \frac{l^2}{36,000r^2}}$	$\frac{16,250}{1 + \frac{l^2}{11,000r^2}}$	$\frac{16,000}{1 + \frac{l^2}{20,000r^2}}$	$15,200 - 58l/r$	$16,000 - 70l/r$ Chi. 14,000 max N. Y. 16,000 max	$19,000 - 100l/r$ 13,000 max	$17,500 - 50l/r$
I	II	III	IV	V	VI	VII	VIII
70	11 000	11 240	12 850	11 140	11 100	12 000	9 000
71	10 965	11 140	12 780	11 082	11 030	11 900	8 950
72	10 930	11 040	12 710	11 024	10 960	11 800	8 900
73	10 890	10 940	12 640	10 966	10 890	11 700	8 850
74	10 850	10 845	12 565	10 908	10 820	11 600	8 800
75	10 810	10 750	12 490	10 850	10 750	11 500	8 750
76	10 770	10 655	12 420	10 792	10 680	11 400	8 700
77	10 735	10 560	12 345	10 734	10 610	11 300	8 650
78	10 695	10 465	12 270	10 676	10 540	11 200	8 600
79	10 655	10 370	12 195	10 618	10 470	11 100	8 550
80	10 615	10 275	12 120	10 560	10 400	11 000	8 500
81	10 575	10 180	12 045	10 502	10 330	10 900	8 450
82	10 535	10 085	11 970	10 444	10 260	10 800	8 400
83	10 495	9 990	11 895	10 386	10 190	10 700	8 350
84	10 450	9 900	11 825	10 328	10 120	10 600	8 300
85	10 410	9 810	11 755	10 270	10 050	10 500	8 250
86	10 370	9 720	11 680	10 212	9 980	10 400	8 200
87	10 330	9 630	11 605	10 154	9 910	10 300	8 150
88	10 290	9 540	11 530	10 096	9 840	10 200	8 100
89	10 250	9 450	11 460	10 038	9 770	10 100	8 050
90	10 205	9 360	11 390	9 980	9 700	10 000	8 000
91	10 165	9 270	11 315	9 922	9 630	9 900	8 950
92	10 125	9 185	11 240	9 864	9 560	9 800	8 900
93	10 085	9 100	11 165	9 806	9 490	9 700	8 850
94	10 040	9 015	11 095	9 748	9 420	9 600	8 800
95	9 995	8 930	11 025	9 690	9 350	9 500	7 750
96	9 955	8 845	10 950	9 632	9 280	9 400	7 700
97	9 915	8 760	10 880	9 574	9 210	9 300	7 650
98	9 875	8 675	10 810	9 516	9 140	9 200	7 600
99	9 830	8 590	10 740	9 458	9 070	9 100	7 550
100	9 785	8 510	10 670	9 400	9 000	9 000	7 500
101	9 740	8 430	10 595	9 342	8 930	8 900	7 450
102	9 695	8 350	10 525	9 284	8 860	8 800	7 400
103	9 650	8 270	10 455	9 226	8 790	8 700	7 350
104	9 610	8 190	10 385	9 168	8 720	8 600	7 300
105	9 570	8 115	10 315	9 110	8 650	8 500	7 250
106	9 525	8 040	10 245	9 052	8 580	8 400	7 200
107	9 480	7 965	10 175	8 994	8 510	8 300	7 150
108	9 435	7 890	10 105	8 936	8 440	8 200	7 100
109	9 395	7 815	10 035	8 878	8 370	8 100	7 050

\* New Boston Code, 20 000—100  $l/r$ ; maximum  $l/r$ , 160; maximum stress, 12

† Also old New York Code, Newark, N. J., Atlanta, Ga., Worcester, Mass., et

‡ Am. R'y Engrg. Ass'n the same up to  $l/r$ , 100, for main members. Maximum,



Table XI (Continued). Safe Loads in Pounds per Square Inch of Metal-Area for Steel Columns and Struts

$l$  = length in inches       $r$  = least radius of gyration in inches

$l/r$	Rankine's (Gordon's) and Cambria	Phila- delphia	Boston,* before 1919	Wash- ington, D. C.†	Chi- cago ‡ and N. Y.	Am. Bridge Co. and Carnegie	Fowler's formula for struts	$l/r$
	$\frac{12,500}{1 + \frac{l^2}{36,000 r^2}}$	$\frac{16,250}{1 + \frac{l^2}{11,000 r^2}}$	$\frac{16,000}{1 + \frac{l^2}{29,000 r^2}}$	15,200 — 38 $l/r$	16,000 — 70 $l/r$ Chi. 14,000 max N.Y. 16,000 max	19,000 — 100 $l/r$ 13,000 max	12,500 — 50 $l/r$	
I	II	III	IV	V	VI	VII	VIII	IX
110	9 355	7 740	9 970	8 820	8 300	8 000	7 000	110
111	9 310	7 665	9 900	8 762	8 230	7 900	6 950	111
112	9 265	7 590	9 830	8 704	8 160	7 800	6 900	112
113	9 220	7 520	9 760	8 646	8 090	7 700	6 850	113
114	9 180	7 450	9 695	8 588	8 020	7 600	6 800	114
115	9 140	7 380	9 630	8 530	7 950	7 500	6 750	115
116	9 095	7 310	9 560	8 472	7 880	7 400	6 700	116
117	9 050	7 240	9 495	8 414	7 810	7 300	6 650	117
118	9 010	7 170	9 430	8 356	7 740	7 200	6 600	118
119	8 970	7 100	9 365	8 298	7 670	7 100	6 550	119
120	8 930	7 035	9 300	8 240	7 600	7 000	6 500	120


In the COMPARATIVE DIAGRAM (page 496) OF COMPRESSION FORMULAS the lines of the formulas and the maximum ratio of  $l/r$  for main members and secondary members are as follows:

Compression-formulas	Maximum ratio of $l/r$ §	
	Main members	Secondary members
American Bridge Company.....	120	200
American Railway Engineering Association....	100	120
Chicago Building Laws.....	120	150
Rankine's (Gordon's) formula.....	200	200
New York Building Laws.....	120	120
Philadelphia Building Laws.....	140	140
Boston Building Laws (before 1919).....	120	120
Boston Building Laws (since 1919).....	160	160

\* See foot-notes on pages 493 and 494.

§ See important notes on page 490.

Comparative Diagram of Compression-Formulas



**Table XII.\* Safe Loads in Tons of 2 000 Pounds for Standard Steel-Pipe Columns.** See National Tube Company's Handbook for Values of  $r$  Used

Loads in tons of 2 000 pounds. Table based on New York and Chicago laws. Formula used,  $S = 16\ 000 - 70\ l/r$ , in which

$S$  = allowable compressive stress for steel in pounds per square inch,  
 $l$  = length of column in inches,  
 $r$  = least radius of gyration in inches.

Loads above or to the left of the zigzag lines correspond to values of  $l/r$  greater than 120.

		Nominal sizes of pipe. Inside diameters in inches								
Length ft.	ft.	2	2½	3	3½	4	4½	5	6	7
		Thickness in decimal parts of an inch								
		0.154	0.103	0.216	0.226	0.237	0.247	0.258	0.280	0.301
40	36	.....	.....	.....	.....	.....	.....	.....	.....	15.00
38	34	.....	.....	.....	.....	.....	.....	.....	10.20	18.37
36	32	.....	.....	.....	.....	.....	.....	.....	13.33	21.73
34	30	.....	.....	.....	.....	.....	.....	8.43	16.46	25.10
32	28	.....	.....	.....	.....	.....	7.41	11.32	19.60	28.47
30	26	.....	.....	.....	.....	5.96	91.5	13.24	21.68	30.71
28	24	.....	.....	.....	4.60	7.73	11.09	15.16	23.77	32.96
26	22	.....	.....	.....	6.28	9.50	12.94	17.09	25.86	35.20
24	20	.....	.....	4.96	7.97	11.16	14.78	19.01	27.95	37.45
22	18	.....	3.06	6.57	9.05	13.03	16.62	20.93	30.04	39.69
20	16	.....	3.81	7.37	10.49	13.91	17.54	21.90	31.08	40.81
18	14	.....	4.57	8.18	11.33	14.79	18.46	22.86	32.12	41.94
16	12	2.39	5.32	8.98	12.18	15.68	19.38	23.81	33.17	43.06
14	10	2.86	6.08	9.78	13.01	16.56	20.30	24.78	34.21	44.18
12	8	3.44	6.83	10.59	13.86	17.44	21.13	25.74	35.26	45.30
10	6	4.01	7.59	11.39	14.70	18.33	22.14	26.71	36.30	46.43
8	4	4.58	8.34	12.20	15.54	19.21	23.06	27.67	37.34	47.55
6	2	5.16	9.10	13.00	16.38	20.09	23.98	28.63	38.39	48.68
4	0	5.73	9.86	13.81	17.23	20.98	24.90	29.59	39.07	48.68

		Nominal sizes of pipe. Inside diameters in inches.							
Length ft.	ft.	8	9	10	11	12	13	14	15
		Thickness in decimal parts of an inch							
		0.312	0.342	0.365	0.375	0.375	0.375	0.375	0.375
40	36	19.16	28.77	40.81	51.26	60.68	71.45	81.88	91.30
38	34	23.96	33.81	46.34	56.85	66.27	78.05	87.47	96.89
36	32	27.57	37.70	50.34	61.05	70.47	81.25	91.67	101.09
34	30	31.17	41.53	54.43	65.24	74.67	86.44	95.87	105.29
32	28	34.77	45.35	58.51	69.44	78.86	90.61	100.06	109.49
30	26	38.37	49.18	62.59	73.61	83.06	94.84	104.26	113.68
28	24	40.78	51.73	65.34	76.43	85.86	97.64	107.06	116.48
26	22	43.18	54.38	68.04	79.13	88.65	100.43	109.86	119.28
24	20	45.58	56.83	70.76	82.03	91.45	103.23	112.65	122.08
22	18	47.98	59.38	73.48	84.83	94.25	106.03	115.45	124.88
20	16	50.38	61.93	76.21	87.62	97.05	108.83	118.25	127.67
18	14	52.58	63.21	77.57	89.02	98.45	110.23	119.65	128.85
16	12	54.78	64.49	78.93	90.42	99.85	111.62	120.61	128.85
14	10	56.99	65.76	80.29	91.82	101.24	112.36	120.61	128.85
12	8	59.19	67.04	81.65	93.22	102.05	112.36	120.61	128.85
10	6	61.39	68.32	83.01	94.61	102.05	112.36	120.61	128.85
8	4	63.59	69.59	84.36	95.91	102.05	112.36	120.61	128.85
6	2	65.79	70.82	85.61	97.21	102.05	112.36	120.61	128.85
4	0	67.99	72.05	86.86	98.51	102.05	112.36	120.61	128.85

\* Furnished by the National Tube Company, Pittsburgh, Pa.

Table XIII.\* Safe Loads in Tons of 2 000 Pounds for Extra-Strong Steel Pipe Columns. See National Tube Company's Handbook for Values of *r* Used

Loads in tons of 2 000 pounds. Table based on New York and Chicago laws. Formula used  $S = 16\,000 - 70\,l/r$ , in which  
*S* = allowable compressive stress for steel in pounds per square inch,  
*l* = length of column in inches,  
*r* = least radius of gyration in inches.  
Loads above or to the left of the zigzag lines correspond to values of *l/r* greater than 1

Lengths, ft	Nominal sizes of pipe. Inside diameters in inches								
	2	2½	3	3½	4	4½	5	6	7
	Thickness in decimal parts of an inch								
	0.218	0.276	0.300	0.318	0.337	0.355	0.375	0.432	0.500
40	.....	.....	.....	.....	.....	.....	.....	.....	22
36	.....	.....	.....	.....	.....	.....	.....	.....	28
33	.....	.....	.....	.....	.....	.....	.....	14.16	33
30	.....	.....	.....	.....	.....	.....	.....	18.99	39
27	.....	.....	.....	.....	.....	.....	11.21	23.81	44
24	.....	.....	.....	.....	.....	9.74	15.39	28.64	48
22	.....	.....	.....	.....	7.68	12.38	18.19	31.86	52
20	.....	.....	.....	5.78	10.19	15.02	20.98	35.07	56
18	.....	.....	.....	8.14	12.69	17.66	23.77	38.29	59
16	.....	.....	6.29	10.51	15.20	20.31	26.56	41.51	63
14	.....	3.69	8.52	12.87	17.71	22.95	29.35	44.72	65
13	.....	4.71	9.64	14.06	18.96	24.27	30.75	46.33	67
12	.....	5.74	10.75	15.24	20.22	25.59	32.15	47.94	69
11	2.91	6.76	11.87	16.42	21.47	26.91	33.54	49.55	70
10	3.72	7.79	12.98	17.60	22.72	28.23	34.94	51.16	72
9	4.53	8.81	14.09	18.79	23.98	29.55	36.33	52.76	74
8	5.34	9.83	15.21	19.97	25.23	30.88	37.73	54.37	76
7	6.15	10.86	16.32	21.15	26.48	32.20	39.12	55.98	78
6	6.96	11.88	17.44	22.33	27.74	33.32	40.52	57.79	78
5	7.77	12.91	18.55	23.52	28.99	34.84	41.92	58.83	78

Lengths, ft	Nominal sizes of pipe. Inside diameters in inches								
	8	9	10	11	12	13	14	15	16
	Thickness in decimal parts of an inch								
	0.500	0.500	0.500	0.500	0.500	0.500	0.500	0.500	0.500
40	27.60	40.14	54.25	66.80	79.36	95.06	107.62	120	120
36	35.05	47.59	61.71	74.26	86.82	102.52	115.08	127	127
33	40.64	53.18	67.30	79.85	92.41	108.11	120.67	133	133
30	46.23	58.77	72.89	85.45	98.00	113.70	126.27	139	139
27	51.81	64.36	78.48	91.04	103.60	119.30	131.86	144	144
24	57.40	69.95	84.07	96.63	109.19	124.89	137.45	150	150
22	61.13	73.68	87.80	100.36	112.92	128.62	141.18	153	153
20	64.85	77.40	91.53	104.09	116.65	132.35	144.71	157	157
18	68.58	81.13	95.26	107.82	120.38	136.08	148.64	161	161
16	72.30	84.86	98.98	111.54	124.11	139.81	152.37	164	164
14	76.03	88.58	102.71	115.27	127.84	143.54	156.10	168	168
13	77.89	90.45	104.58	117.14	129.70	145.40	157.97	170	170
12	79.75	92.31	106.44	119.00	131.56	147.27	159.44	170	170
11	81.61	94.17	108.30	120.87	133.43	148.44	159.44	170	170
10	83.48	96.04	110.17	122.73	134.70	148.44	159.44	170	170
9	85.34	97.90	112.03	123.70	134.70	148.44	159.44	170	170
8	87.20	99.76	112.70	123.70	134.70	148.44	159.44	170	170
7	89.06	100.33	112.70	123.70	134.70	148.44	159.44	170	170
6	89.34	100.33	112.70	123.70	134.70	148.44	159.44	170	170
5	89.31	100.33	112.70	123.70	134.70	148.44	159.44	170	170

\*Furnished by the National Tube Company, Pittsburgh, Pa.


Table XIV. Safe Loads\* in Tons of 2 000 Pounds for Struts Formed of a Pair of Steel Channels.

Distance between webs,  $\frac{3}{4}$  in

If strut is free to bend in either direction, use smaller load given

Stresses in pounds per square inch:

12 000 for lengths of 30 radii and under;


13 500 — 50  $l/r$  for lengths over 30 radii

Depth, in	Weight per lin foot, lb †	Thick- ness of web, in	Area of two chan- nels, sq in	$r_{x-x}$ $r_{y-y}$ in	Length in feet					
					8	9	10	11	12	14
15	33.9	0.40	19.80	1.48	101.57	97.56	93.55	89.54	85.48	77.44
				5.62	118.80	118.80	118.80	118.80	118.80	118.80
	35.0	0.42	20.46	1.47	105.32	101.13	96.93	92.73	88.54	80.09
				5.58	123.48	123.48	123.48	123.48	123.48	123.00
	40.0	0.52	23.10	1.46	120.13	115.30	110.48	103.66	100.78	91.14
				5.44	141.12	141.12	141.12	141.12	141.12	140.41
	45.0	0.62	26.34	1.45	134.91	129.48	123.99	118.50	113.00	102.08
				5.33	158.88	158.88	158.88	158.88	158.88	157.82
	50.0	0.72	29.28	1.46	150.36	144.23	138.20	132.17	126.06	114.00
				5.24	176.52	176.52	176.52	176.52	176.52	174.75
	55.0	0.81	32.22	1.47	165.60	159.00	152.40	145.78	139.22	126.10
				5.16	194.16	194.16	194.16	194.16	194.16	192.00
12	20.7	0.28	12.06	1.34	59.81	57.10	54.40	51.70	49.02	43.62
				4.61	72.36	72.36	72.36	72.36	71.99	70.43
	25.0	0.39	14.64	1.31	72.32	68.95	65.60	62.21	58.83	52.03
				4.43	88.20	88.20	88.20	88.20	87.28	85.26
	30.0	0.51	17.58	1.30	86.52	82.46	78.36	74.30	70.25	62.09
				4.28	105.84	105.84	105.84	105.48	104.25	101.78
	35.0	0.63	20.52	1.31	101.25	96.52	91.78	87.10	82.37	72.90
				4.18	123.48	123.48	123.48	122.65	121.16	118.33
	40.0	0.76	23.46	1.32	116.01	110.66	105.31	99.96	94.66	83.96
				4.09	141.12	141.12	141.12	139.82	138.06	134.65
10	15.3	0.24	8.94	1.24	42.94	40.78	38.64	36.48	34.32	30.01
				3.87	53.52	53.52	53.29	52.62	51.91	50.43
	20.0	0.38	11.72	1.26	55.86	52.92	49.98	47.04	44.10	38.22
				3.66	70.56	70.56	69.73	68.79	67.82	65.85
	25.0	0.53	14.66	1.26	69.82	66.15	62.47	58.80	55.12	47.77
				3.52	88.20	87.94	86.69	85.44	84.19	81.69
	30.0	0.67	17.60	1.28	84.40	80.04	75.71	71.35	67.03	58.34
				3.42	105.84	105.13	103.63	102.04	100.20	97.41
	35.0	0.82	20.54	1.26	99.76	94.82	89.93	85.04	80.16	70.33
				3.34	123.48	122.34	120.49	118.64	116.79	113.13
9	13.4	0.23	7.78	1.19	36.83	34.87	32.91	30.94	28.98	25.07
				3.49	46.68	46.48	45.82	45.16	44.50	43.15
	15.0	0.29	8.78	1.17	41.45	39.18	36.93	34.66	32.41	27.89
				3.40	52.92	52.52	51.81	50.98	50.10	48.64
	20.0	0.45	11.72	1.15	54.85	51.77	48.71	45.65	42.57	36.42
				3.22	70.56	69.50	68.38	67.29	66.20	64.00
	25.0	0.61	14.66	1.17	69.09	65.31	61.55	57.77	54.00	46.48
				3.10	87.83	86.43	85.00	83.56	82.17	79.30

\* The values vary slightly with slight changes in section-areas of channels.

† Of single channel.

Table XIV (Continued). Safe Loads\* in Tons of 2 000 Pounds for Struts Formed of a Pair of Steel Channels

Distance between webs, 1/2 in										
If strut is free to bend in either direction, use smaller load given										
Stresses in pounds per square inch:										
11 000 for lengths of 50 radii and under;										
13 500 — 50 l/r for lengths over 50 radii										
										
Depth, in	Weight per lin foot, lb †	Thick- ness of web, in	Area of two chan- nels, sq in	r <sub>2-2</sub> r <sub>1-1</sub> , in	Length in feet					
					6	7	8	9	10	11
8	11.50	0.22	6.72	1.04	33.63	31.70	29.76	27.83	25.91	23.98
				3.10	36.85	36.85	36.85	36.85	36.85	36.85
	13.75	0.30	8.04	1.04	40.56	38.23	35.89	33.57	31.24	28.91
				2.99	44.44	44.44	44.44	44.44	44.44	44.44
	16.25	0.40	9.52	1.03	47.82	45.05	42.25	39.48	36.68	33.88
				2.89	52.58	52.58	52.58	52.58	52.58	52.58
	18.75	0.49	10.98	1.03	55.12	51.93	48.70	45.51	42.29	39.06
				2.82	60.61	60.61	60.61	60.61	60.61	60.61
	21.25	0.58	12.46	1.03	62.53	58.90	55.25	51.62	47.96	44.30
				2.77	68.75	68.75	68.75	68.75	68.75	68.75
7	9.80	0.21	5.70	0.99	28.11	26.39	24.66	22.94	21.20	19.47
				2.72	31.35	31.35	31.35	31.35	31.35	31.35
	12.25	0.31	7.16	0.99	35.51	33.33	31.15	28.98	26.78	24.58
				2.59	39.60	39.60	39.60	39.60	39.60	39.60
	14.75	0.42	8.64	0.99	42.71	40.18	37.56	34.93	32.28	29.63
				2.51	47.74	47.74	47.74	47.74	47.74	47.74
	17.25	0.52	10.10	1.00	50.19	47.15	44.10	41.06	38.02	34.98
				2.44	55.77	55.77	55.77	55.77	55.77	55.77
	19.75	0.63	11.58	1.00	57.52	54.03	50.54	47.06	43.57	40.08
				2.39	63.91	63.91	63.91	63.91	63.91	63.91
6	8.02	0.20	4.78	0.94	23.02	21.50	19.98	18.46	16.94	15.42
				2.34	26.18	26.18	26.18	26.18	26.02	25.86
	10.50	0.31	6.14	0.94	29.89	27.91	25.94	23.97	22.00	20.03
				2.22	33.99	33.99	33.99	33.99	33.32	32.65
	13.00	0.44	7.62	0.95	37.11	34.68	32.27	29.87	27.44	25.01
				2.13	42.02	42.02	42.02	41.88	40.81	39.74
	15.50	0.56	9.08	0.95	44.30	41.40	38.53	35.66	32.78	29.91
				2.07	50.16	50.16	50.16	49.68	48.33	46.98
5	6.70	0.19	3.90	0.89	18.43	17.13	15.81	14.49	13.18	11.86
				1.95	21.45	21.45	21.45	20.92	20.32	19.72
	9.00	0.33	5.26	0.90	25.17	23.41	21.65	19.87	18.11	16.35
				1.83	29.15	29.15	28.83	27.97	27.10	26.23
	11.50	0.47	6.72	0.91	32.26	30.03	27.81	25.58	23.35	21.12
				1.76	37.18	37.18	36.36	35.20	34.03	32.87
4	5.40	0.18	3.12	0.84	14.28	13.17	12.07	10.96	9.85	8.74
				1.56	17.05	16.75	16.15	15.55	14.96	14.36
	6.25	0.25	3.64	0.84	16.95	15.64	14.33	13.02	11.70	10.39
				1.50	20.24	19.72	18.99	18.26	17.53	16.80
	7.25	0.32	4.24	0.84	19.62	18.10	16.59	15.07	13.54	12.02
				1.47	23.43	22.63	21.75	20.87	19.98	19.09

\* The values vary slightly with slight changes in section-areas of channels.  
† Of single channel.

Table XV. Safe Loads in Tons of 2 000 Pounds for Single-Steel-Angle Struts

ANGLES WITH UNEQUAL LEGS Stresses in pounds per square inch: 11 000 for lengths of 50 radii and under; 13 500 — 50 l/r for lengths over 50 radii										
Size, in.	Thick- ness, in	r axis 3-3,* in	Area, sq in	Length in feet						
				4	5	6	7	8	9	10
6 X4	3/8	0.88	3.61	....	....	....	....	....	....	....
	3/4	0.86	7.99	42.78	40.00	37.21	34.44	31.64	28.86	26.07
5 X3 1/2	3/8	0.76	3.05	....	....	....	....	....	....	....
	3/4	0.75	5.81	....	....	....	....	....	....	....
5 X3	5/16	0.66	2.40	....	....	....	....	....	....	....
	3/4	0.64	5.44	....	....	....	....	....	....	....
4 1/2 X3	5/16	0.66	2.25	....	....	....	....	....	....	....
	3/4	0.64	5.06	24.66	22.29	19.92	17.55	15.18	....	....
4 X3 1/2	5/16	0.73	2.25	11.49	10.57	9.65	8.72	7.79	6.86	....
	3/4	0.72	5.06	25.73	23.62	21.51	19.40	17.29	15.18	....
4 X3	5/16	0.65	2.09	10.25	9.28	8.32	7.36	6.39	....	....
	3/4	0.64	4.69	22.86	20.67	18.47	16.27	14.07	....	....
3 1/2 X3	5/16	0.63	1.93	9.35	8.43	7.51	6.59	....	....	....
	3/8	0.62	2.30	11.07	9.96	8.84	7.74	....	....	....
	3/4	0.62	3.67	17.67	15.90	14.12	12.35	....	....	....
3 1/2 X2 1/2	1/4	0.54	1.44	6.52	5.72	4.92	....	....	....	....
	3/8	0.54	2.11	9.55	8.38	7.21	....	....	....	....
	1/2	0.53	2.75	12.34	10.78	9.22	....	....	....	....
3 X2 1/2	1/4	0.53	1.31	5.88	5.13	4.39	....	....	....	....
	3/8	0.52	1.92	8.52	7.42	6.31	....	....	....	....
	1/2	0.52	2.50	11.10	9.66	8.22	....	....	....	....
3 X2	1/4	0.43	1.19	4.71	3.88	....	....	....	....	....
	3/8	0.43	1.73	6.85	5.64	....	....	....	....	....
	1/2	0.43	2.25	8.91	7.34	....	....	....	....	....
2 1/2 X2	1/4	0.42	1.06	4.13	3.37	....	....	....	....	....
	3/8	0.42	1.55	6.03	4.93	....	....	....	....	....
	1/2	0.42	2.00	7.79	6.36	....	....	....	....	....

\* This is the least radius of gyration with reference to the diagonal axis 3-3. (See Table XI, pages 362 to 365.)

**Table XV (Continued). Safe Loads in Tons of 2 000 Pounds for Single-Steel-Angle Struts**

<b>ANGLES WITH EQUAL LEGS</b> Stresses in pounds per square inch: 11 000 for lengths of 50 radii and under; 13 500 — 50 $l/r$ for lengths over 50 radii										
Size, in	Thick- ness, in	$r$ axis 3-3,* in	Area, sq in	Length in feet						
				4	5	6	7	8	9	10
6 X 6	$\frac{3}{8}$	1.19	4.36	23.98	23.93	22.83	21.74	20.64	19.54	18
	$\frac{5}{8}$	1.18	7.11	39.10	38.96	37.14	35.35	33.54	31.72	29
	$\frac{7}{8}$	1.17	9.74	53.57	53.27	50.77	48.28	45.77	43.26	40
5 X 5	$\frac{3}{8}$	0.99	3.61	19.85	18.89	17.80	16.71	15.64	14.53	13
	$\frac{5}{8}$	0.97	5.86	32.23	30.50	28.68	26.86	25.06	23.24	21
	$\frac{7}{8}$	0.96	7.99	43.94	41.44	38.95	36.45	33.95	31.46	28
4 X 4	$\frac{3}{8}$	0.79	2.86	14.96	13.88	12.79	11.71	10.61	9.53	..
	$\frac{1}{2}$	0.78	3.75	19.54	18.10	16.65	15.22	13.78	12.33	..
	$\frac{5}{8}$	0.77	4.61	23.93	22.13	20.33	18.55	16.75	14.95	..
	$\frac{3}{4}$	0.77	5.44	28.24	26.12	23.99	21.89	19.77	17.65	..
$3\frac{1}{2} \times 3\frac{1}{2}$	$\frac{5}{16}$	0.69	2.09	10.47	9.56	8.65	7.74	6.83	....	..
	$\frac{1}{2}$	0.68	3.25	16.20	14.77	13.34	11.90	10.47	....	..
	$\frac{5}{8}$	0.67	3.98	19.74	17.95	16.17	14.39	12.61	....	..
	$\frac{3}{4}$	0.67	4.69	13.26	21.16	19.06	16.96	14.86	....	..
3 X 3	$\frac{1}{4}$	0.59	1.44	6.79	6.06	5.32	4.59	....	....	..
	$\frac{3}{8}$	0.58	2.11	9.88	8.78	7.69	6.60	....	....	..
	$\frac{1}{2}$	0.58	2.75	12.87	11.45	10.03	8.60	....	....	..
	$\frac{5}{8}$	0.57	3.36	15.60	13.84	12.07	10.30	....	....	..
$2\frac{1}{2} \times 2\frac{1}{2}$	$\frac{5}{16}$	0.49	0.90	3.87	3.32	2.76	....	....	....	..
	$\frac{1}{4}$	0.49	1.19	5.10	4.39	3.66	....	....	....	..
	$\frac{3}{8}$	0.48	1.73	7.35	6.27	5.19	....	....	....	..
	$\frac{1}{2}$	0.47	2.25	9.44	8.01	6.57	....	....	....	..
$2\frac{1}{4} \times 2\frac{1}{4}$	$\frac{5}{16}$	0.44	0.81	3.26	2.70	....	....	....	....	..
	$\frac{1}{4}$	0.44	1.06	4.26	3.54	2.80	....	....	....	..
	$\frac{3}{8}$	0.43	1.55	6.13	5.05	3.95	....	....	....	..
	$\frac{7}{16}$	0.43	1.78	7.14	5.80	4.53	....	....	....	..
2 X 2	$\frac{5}{16}$	0.40	0.72	2.70	2.16	....	....	....	....	..
	$\frac{1}{4}$	0.39	0.94	3.45	2.72	2.00	....	....	....	..

\* This is the least radius of gyration, with reference to the diagonal axis 3-3. Table XII, pages 366 and 367.)




**Table XVI. Safe Loads in Tons of 2 000 Pounds for Double-Steel-Angle Struts**

**LONG LEGS PARALLEL AND ONE-HALF INCH APART**

Stresses in pounds per square inch:


11 000 for lengths of 50 radii and under;

13 500 — 50  $l/r$  for lengths over 50 radii



Size, in	Thick- ness, in	Least $r$ , in	Area two angles, sq in	Length in feet						
				5	6	7	8	10	11	12
X6	1	2.49	13.52	74.36	74.36	74.36	74.36	74.36	73.34	71.72
		2.65	26.82	147.51	147.51	147.51	147.51	147.51	147.51	144.62
X4	3/8	1.67	7.22	39.71	39.71	39.65	38.35	35.77	34.47	33.14
		1.74	14.94	82.17	82.17	82.17	80.26	75.07	72.50	69.91
X3 1/2	3/8	1.43	6.84	37.62	37.57	36.13	34.69	31.82	30.38	29.00
	1/2	1.46	9.00	49.50	49.50	47.81	45.97	42.27	40.41	38.56
	5/8	1.49	11.10	61.05	61.05	59.27	57.05	52.51	50.29	48.07
	1 1/8	1.52	14.12	77.66	77.66	75.82	73.03	67.42	64.65	61.88
X4	3/8	1.59	6.46	35.53	35.53	35.07	33.86	31.41	30.20	28.99
	1/2	1.54	12.38	68.09	68.09	66.69	64.28	59.45	57.04	54.62
X3 1/2	3/8	1.51	6.10	33.55	33.55	32.70	31.42	29.05	27.84	26.64
	1/2	1.55	11.62	63.91	63.91	62.69	60.45	55.95	53.71	51.44
X3	3/8	1.27	5.72	31.46	30.50	29.15	27.80	25.09	23.75	22.39
	1/2	1.30	7.50	41.25	40.23	38.51	36.78	33.32	31.59	29.85
	5/8	1.33	9.22	50.71	49.76	47.69	45.59	41.40	39.30	37.29
	1 1/8	1.36	10.88	59.84	58.94	56.63	54.23	49.42	47.05	44.66
X3 1/2	3/8	1.25	5.34	29.37	28.35	27.07	25.79	23.23	21.94	20.66
	1/2	1.20	10.12	55.66	53.13	50.60	48.07	43.01	40.48	39.95
X3	3/8	1.26	4.96	27.28	26.28	25.12	24.00	21.64	20.49	19.30
	1/2	1.22	9.38	51.59	49.47	47.18	44.85	40.24	37.94	35.64
X3 1/2	1/4	1.12	2.88	15.58	14.81	14.03	13.26	11.72	10.95	10.18
	3/8	1.10	4.22	22.73	21.59	20.42	19.28	16.97	15.82	14.67
	1/2	1.09	5.50	29.56	28.05	26.53	25.02	21.98	20.47	18.96
	1 1/8	1.06	7.30	38.92	36.86	34.78	32.74	28.58	26.51	24.43
X2	1/4	0.93	2.38	12.22	11.45	10.69	9.92	8.39	7.62	....
	3/8	0.92	4.50	23.04	21.58	20.10	18.64	15.70	14.23	....
X2	1 1/8	0.79	1.62	7.86	7.24	6.63	6.01	....	....	....
	1 1/4	0.75	4.00	19.00	17.40	15.80	14.20	....	....	....
X2	1 1/8	0.62	1.44	6.22	5.54	4.82	4.13	....	....	....
X2	1 1/4	0.61	1.88	8.08	7.14	6.20	5.26	....	....	....

Table XVII.\* Safe Loads in Units of 1,000 Pounds for Steel-Beam Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$S = 19\,000 - 100l/r$


Weights do not include details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Depth and weight of sections						
	H beams				I beams		
	8-in 34.3-lb	6-in 24.1-lb	5-in 18.9-lb	4-in 13.8-lb	15-in 42.9-lb	12-in 31.8-lb	10-in 25.3-lb
2	130.0	91.0	71.5	52.0	162.2	120.4	90.0
3	130.0	91.0	71.5	52.0	162.2	120.4	90.0
4	130.0	91.0	71.5	52.0	162.2	120.4	90.0
5	130.0	91.0	71.5	50.7	162.2	120.4	90.0
6	130.0	91.0	71.5	45.7	153.9	109.9	80.0
7	130.0	91.0	66.0	40.6	140.1	98.9	70.0
8	130.0	86.7	60.5	35.6	126.2	87.9	60.0
9	130.0	80.9	55.0	30.5	112.3	76.9	50.0
10	125.8	75.1	49.5	26.7	98.5	65.9	40.0
11	119.4	69.3	44.0	24.2	86.0	59.9	35.0
12	113.0	63.5	38.5	21.7	79.0	54.4	30.0
13	106.6	57.7	35.8	19.2	72.1	48.9	25.0
14	100.2	51.9	33.0	16.6	65.2	43.4	20.0
15	93.8	47.6	30.3	14.1	58.2	37.9	15.0
16	87.3	44.7	27.5	.....	51.3	32.4	10.0
17	80.9	41.8	24.8	.....	44.4	26.9	.....
18	74.5	38.9	22.0	.....	37.4	.....	.....
19	69.0	36.0	19.3	.....	.....	.....	.....
20	65.8	33.1	16.5	.....	.....	.....	.....
21	62.6	30.2	.....	.....	.....	.....	.....
22	59.4	27.3	.....	.....	.....	.....	.....
23	56.2	24.4	.....	.....	.....	.....	.....
24	53.0	21.5	.....	.....	.....	.....	.....
25	49.8	.....	.....	.....	.....	.....	.....
26	46.6	.....	.....	.....	.....	.....	.....
27	43.4	.....	.....	.....	.....	.....	.....
28	40.2	.....	.....	.....	.....	.....	.....
29	37.0	.....	.....	.....	.....	.....	.....
30	33.7	.....	.....	.....	.....	.....	.....
31	30.5	.....	.....	.....	.....	.....	.....
Area, sq in	10.01	7.01	5.47	4.00	12.49	9.26	7.26
$I_{1-1}$ , in <sup>4</sup> ....	115.4	45.1	23.8	10.7	441.8	215.8	109.8
$r_{1-1}$ , in. ....	3.40	2.54	2.08	1.63	5.95	4.83	3.92
$I_{2-2}$ , in <sup>4</sup> ....	35.1	14.7	7.9	3.6	14.6	9.5	4.8
$r_{2-2}$ , in. ....	1.87	1.45	1.20	0.95	1.08	1.01	0.85
Weight, lb per lin ft	34.3	24.1	18.9	13.8	42.9	31.8	25.3

Safe load-values above the upper heavy line are for ratios of  $l/r$  not over those between the heavy lines for ratios up to 120  $l/r$ ; and those below lower heavy line are for ratios not over 200  $l/r$ .

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XVII \* (Continued). Safe Loads in Units of 1 000-Pounds for Steel-Beam Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100l/r$$

Weights do not include details


For values for  $l/r$  above 120, see notes on page 490

Depth and weight of sections

Effective length, ft	I beams					
	9-in 21.8-lb	8-in 18.4-lb	7-in 15.3-lb	6-in 12.5-lb	5-in 10-lb	4-in 7.7-lb
2	82.0	69.3	57.5	46.9	37.3	28.7
3	82.0	69.3	57.5	46.9	37.3	28.5
4	82.0	69.3	56.8	44.5	33.3	24.0
5	77.8	63.2	50.0	38.5	28.0	19.5
6	69.4	55.6	43.2	32.5	23.7	15.2
7	61.0	48.0	36.4	26.5	18.8	13.0
8	52.6	40.4	30.3	22.9	16.1	10.8
9	44.2	35.0	26.9	19.9	13.5	8.5
10	40.0	31.2	23.5	16.8	10.8	.....
11	35.8	27.4	20.1	13.8	.....	.....
12	31.5	23.6	16.7	10.8	.....	.....
13	27.3	19.8	13.3	.....	.....	.....
14	23.1	16.0	.....	.....	.....	.....
15	18.9	.....	.....	.....	.....	.....
16	.....	.....	.....	.....	.....	.....
17	.....	.....	.....	.....	.....	.....
18	.....	.....	.....	.....	.....	.....
19	.....	.....	.....	.....	.....	.....
20	.....	.....	.....	.....	.....	.....
21	.....	.....	.....	.....	.....	.....
22	.....	.....	.....	.....	.....	.....
23	.....	.....	.....	.....	.....	.....
24	.....	.....	.....	.....	.....	.....
25	.....	.....	.....	.....	.....	.....
26	.....	.....	.....	.....	.....	.....
27	.....	.....	.....	.....	.....	.....
28	.....	.....	.....	.....	.....	.....
29	.....	.....	.....	.....	.....	.....
30	.....	.....	.....	.....	.....	.....
31	.....	.....	.....	.....	.....	.....
sq in	6.32	5.34	4.43	3.61	2.87	2.21
in <sup>4</sup> ....	84.9	56.9	36.2	21.8	12.1	6.00
in <sup>3</sup> ....	3.67	3.27	2.86	2.46	2.05	1.64
in <sup>2</sup> ....	5.2	3.8	2.7	1.9	1.2	0.77
in....	0.90	0.84	0.78	0.72	0.65	0.59
Weight, lb per lin ft	21.8	18.4	15.3	12.5	10	7.7


\* The load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
between the heavy lines for ratios up to 120  $l/r$ ; and those below the  
lower heavy line of ratios not over 200  $l/r$ .

**Table XVIII.\* Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled Steel 8-Inch H Columns with Square Ends**

Unsupported length, ft	<div style="display: flex; align-items: center; justify-content: center;">  <div style="margin-left: 20px;">           Allowable stress in pounds per square inch            13 000 for lengths under 55 radii;            16 000 — 55 <math>l/r</math> for lengths over 55 radii         </div> </div>						
8	59.7	66.1	74.8	83.4	92.2	101.0	110.0
9	59.7	66.1	74.8	83.4	92.2	101.0	110.0
10	58.1	64.7	73.3	81.9	90.6	99.5	108.0
11	56.5	63.0	71.4	79.8	88.3	97.0	105.0
12	55.0	61.3	69.6	77.7	86.1	94.5	102.0
13	53.5	59.7	67.7	75.7	83.8	92.1	100.0
14	52.0	58.0	65.8	73.6	81.5	89.6	98.0
15	50.4	56.3	64.0	71.5	79.2	87.1	96.0
16	48.9	54.6	62.1	69.4	76.9	84.6	94.0
17	47.4	53.0	60.2	67.4	74.6	82.2	92.0
18	45.9	51.3	58.4	65.3	72.4	79.7	90.0
20	42.8	48.0	54.6	61.1	67.8	74.7	86.0
22	39.7	44.6	50.9	57.0	63.2	69.8	82.0
24	36.7	41.3	47.1	52.8	58.7	64.8	78.0
26	.....	38.0	43.4	48.7	54.1	59.9	74.0
Area, sq in	9.17	10.17	11.50	12.83	14.18	15.53	16.90
$I_{1-1}$ , in <sup>4</sup> .....	105.7	121.5	139.5	158.3	177.7	197.8	218.0
$r_{1-1}$ , in.....	3.40	3.46	3.48	3.51	3.54	3.57	3.60
$I_{2-2}$ , in <sup>4</sup> .....	35.8	41.1	47.2	53.4	59.8	66.3	73.0
$r_{2-2}$ , in.....	1.98	2.01	2.03	2.04	2.05	2.07	2.08
Weight of section, lb per lin ft	32.0	34.5	39.0	43.5	48.0	53.0	58.0
Loads below the heavy line are for lengths greater than 125 radii							


\* See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Company in March, 1921.

Table XVIII \* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 8-Inch H Columns with Square Ends

Unsupported length, ft	<div><div></div><div>Allowable stress in pounds per square inch: 13 000 for lengths under 55 radii; 16 000 — <math>55 l/r</math> for lengths over 55 radii</div></div>						
	8	118.8	127.8	136.8	146.0	154.6	163.8
9	118.8	127.8	136.8	146.0	154.6	163.8	173.2
10	117.3	126.5	135.6	144.9	153.6	163.1	172.6
11	114.4	123.5	132.4	141.4	149.9	159.3	168.6
12	111.5	120.4	129.1	137.9	146.2	155.4	164.5
13	108.7	117.3	125.8	134.4	142.6	151.6	160.5
14	105.8	114.2	122.5	131.0	138.9	147.7	156.4
15	102.9	111.2	119.2	127.5	135.2	143.9	152.4
16	100.0	108.1	116.0	124.0	131.6	140.0	148.3
17	97.1	105.0	112.7	120.5	127.9	136.1	144.3
18	94.2	101.9	109.4	117.0	124.2	132.3	140.2
20	88.5	95.8	102.9	110.1	116.9	124.6	132.1
22	82.7	89.6	96.3	103.1	109.6	116.9	124.0
24	76.9	83.5	89.8	96.2	102.2	109.2	115.9
26	71.2	77.3	83.2	89.2	94.9	101.5	107.8
Area, sq in	18.27	19.66	21.05	22.46	23.78	25.20	26.64
$I_{T-L}$ in <sup>4</sup> .....	240.2	262.5	285.6	309.5	333.5	359.0	385.3
$r_{T-L}$ in.....	3.63	3.65	3.68	3.71	3.75	3.77	3.80
$I_{L-L}$ in <sup>4</sup> .....	80.0	87.1	94.4	101.9	109.2	117.2	125.1
$r_{L-L}$ in.....	2.09	2.11	2.12	2.13	2.14	2.16	2.17
Weight of section, lb per lin ft	62.0	67.0	71.5	76.5	81.0	85.5	90.5
Loads below the heavy line are for lengths greater than 125 radii							


\* See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Steel Company in March, 1921.

Table XIX.\* Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled Steel 10-Inch H Columns with Square Ends

Unsupported length, ft	<div></div>						
	Allowable stress in pounds per square inch: 13000 for lengths under 55 radii; 16 000 — 55 l/r for lengths over 55 radii						
10	93.5	103.4	114.2	125.0	135.9	146.8	157
11	93.5	103.4	114.2	125.0	135.9	146.8	157
12	92.1	102.2	113.1	123.9	134.9	145.9	157
13	90.2	100.1	110.8	121.4	132.2	143.0	153
14	88.3	98.0	108.5	118.9	129.5	140.1	150
15	86.3	95.9	106.2	116.4	126.9	137.2	147
16	84.5	93.8	103.9	113.9	124.2	134.3	144
18	80.7	89.6	99.3	108.9	118.8	128.5	138
20	76.9	85.4	94.7	103.9	113.4	122.7	132
22	73.1	81.3	90.1	98.9	108.0	116.9	126
24	69.3	77.1	85.6	93.9	102.6	111.1	119
26	65.4	72.9	81.0	88.9	97.2	105.3	113
28	61.6	68.7	76.4	83.9	91.8	99.5	107
30	57.8	64.5	71.8	78.9	86.4	93.7	101
32	54.0	60.3	67.2	73.9	80.1	87.9	94
Area, sq in	14.37	15.91	17.57	19.23	20.91	22.59	24.
I <sub>1-1</sub> , in <sup>4</sup> .....	263.5	296.8	331.9	368.0	405.2	443.6	483
r <sub>1-1</sub> , in.....	4.28	4.32	4.35	4.37	4.40	4.43	4.
I <sub>2-2</sub> , in <sup>4</sup> .....	89.1	100.4	112.2	124.2	136.5	149.1	162
r <sub>2-2</sub> , in.....	2.49	2.51	2.53	2.54	2.56	2.57	2.
Weight of section, lb per lin ft	49.0	54.0	59.5	65.5	71.0	77.0	84
Loads below the heavy line are for lengths greater than 125 radii							

\* See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Company in March, 1921.

Table XIX \* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 10-Inch H Columns with Square Ends


Unsupported length, ft	<div><div></div><div>Allowable stress in pounds per square inch: 13 000 for lengths under 55 radii; 16 000 — 55 <math>l/r</math> for lengths over 55 radii</div></div>						
10	168.9	180.1	190.6	201.9	213.2	224.6	236.1
11	168.9	180.1	190.6	201.9	213.2	224.6	236.1
12	168.3	179.6	190.2	201.9	213.2	224.6	236.1
13	165.0	176.1	186.6	198.0	209.3	220.7	232.2
14	161.7	172.6	182.9	194.1	205.2	216.4	227.7
15	158.4	169.1	179.2	190.3	201.2	212.1	223.2
16	155.1	165.6	175.5	186.4	197.0	207.8	218.7
18	148.5	158.6	168.1	178.6	188.9	199.2	209.8
20	142.0	151.6	160.7	170.8	180.7	190.7	200.8
22	135.4	144.6	153.3	163.1	172.5	182.1	191.8
24	128.8	137.6	145.9	155.3	164.4	173.5	182.8
26	122.2	130.6	138.5	147.5	156.2	165.0	173.8
28	115.6	123.6	131.2	139.8	148.0	156.4	164.9
30	109.0	116.6	123.8	132.0	139.9	147.8	155.9
32	102.4	109.6	116.4	124.2	131.7	139.2	146.9
Area, sq in	25.99	27.71	29.32	31.06	32.80	34.55	36.32
$r_x$ , in.....	523.5	565.2	607.0	651.0	696.2	742.7	790.4
$r_y$ , in.....	4.49	4.52	4.55	4.58	4.61	4.64	4.67
$r_{xy}$ , in.....	175.1	188.6	201.7	215.6	229.9	244.4	259.3
$r_{yz}$ , in.....	2.60	2.61	2.62	2.64	2.65	2.66	2.67
Weight of section, lb per lin ft	88.5	94.0	99.5	105.5	111.5	117.5	123.5
Loads below the heavy line are for lengths greater than 125 radii							

See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Steel Company in March, 1921.






**Table IX\* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 12-Inch H Columns with Square Ends**

Unsupported length, ft	<div style="display: flex; align-items: center; justify-content: center;">  <div style="margin-left: 20px;">           Allowable stress in pounds per square inch:            13 000 for lengths under 55 radii;            16 000 — 55 <math>l/r</math> for lengths over 55 radii         </div> </div>						
10	226.7	239.9	253.3	266.7	280.2	293.7	307.3
12	226.7	239.9	253.3	266.7	280.2	293.7	307.3
14	226.7	239.9	253.3	266.7	280.2	293.7	307.3
16	219.6	232.6	246.0	259.3	272.6	286.0	299.7
18	212.1	224.8	237.8	250.6	263.5	276.6	289.9
20	204.7	217.0	229.6	242.0	254.5	267.1	280.1
22	197.3	209.1	221.4	233.4	245.5	257.7	270.3
24	189.9	201.3	213.2	224.8	236.4	248.3	260.5
26	182.5	193.5	204.9	216.1	227.4	238.8	250.7
28	175.0	185.6	196.7	207.5	218.4	229.4	240.9
30	167.6	177.8	188.5	198.9	209.3	219.9	231.0
32	160.2	170.0	180.3	190.3	200.3	210.5	221.2
34	152.8	162.1	172.1	181.6	191.3	201.1	211.4
36	145.3	154.3	163.9	173.0	182.3	191.6	201.6
38	137.9	146.5	155.6	164.4	173.2	182.2	191.8
Area, sq in	34.87	36.91	38.97	41.03	43.10	45.19	47.28
$I_x$ , in <sup>4</sup> .....	1 000.0	1 069.8	1 141.3	1 214.5	1 289.4	1 366.0	1 444.3
$I_y$ , in <sup>4</sup> .....	5.36	5.38	5.41	5.44	5.47	5.50	5.63
$I_{xx}$ , in <sup>4</sup> .....	335.0	357.7	380.7	404.1	428.0	452.2	477.0
$I_{yy}$ , in <sup>4</sup> .....	3.10	3.11	3.13	3.14	3.15	3.16	3.18
Weight of section, lb per lin ft	118.5	125.5	132.5	139.5	146.5	153.5	161.0
Loads below the heavy line are for lengths greater than 125 radii							


\*See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Steel Company in March, 1921.

**Table XXI.\* Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled Steel 14-Inch H Columns with Square Ends**

Unsupported length, ft	<div style="display: flex; align-items: center; justify-content: center;">  <div style="margin-left: 20px;"> <p>Allowable stress in pounds per square inch  13 000 for lengths under 55 radii;  16 000 — 55 <math>l/r</math> for lengths over 55 radii</p> </div> </div>						
10	159.0	173.9	188.9	204.0	219.1	234.3	249.4
12	159.0	173.9	188.9	204.0	219.1	234.3	249.4
14	159.0	173.9	188.9	204.0	219.1	234.3	249.4
16	158.5	173.9	188.6	204.0	219.1	234.3	249.4
18	153.8	168.5	183.2	198.1	212.9	228.0	243.1
20	149.2	163.4	177.7	192.2	206.6	221.3	236.4
22	144.5	158.4	172.2	186.3	200.3	214.6	230.7
24	139.9	153.3	166.7	180.4	194.0	207.9	225.8
26	135.2	148.2	161.2	174.6	187.7	201.2	220.9
28	130.5	143.2	155.8	168.7	181.4	194.5	216.0
30	125.9	138.1	150.3	162.8	175.1	187.8	211.1
32	121.2	133.1	144.8	156.9	168.8	181.1	206.2
36	111.9	122.9	133.8	145.1	156.2	167.7	191.3
40	102.6	112.8	122.9	133.4	143.6	154.3	181.4
44	.....	.....	111.9	121.6	131.0	140.9	171.5
Area, sq in	24.46	26.76	29.06	31.38	33.70	36.04	38.36
$I_{1-1}$ , in <sup>4</sup> .....	884.9	976.8	1 070.6	1 166.6	1 264.5	1 364.6	1 466.7
$r_{1-1}$ , in.....	6.01	6.04	6.07	6.10	6.13	6.16	6.19
$I_{2-2}$ , in <sup>4</sup> .....	294.5	325.4	356.9	387.8	420.3	453.4	487.1
$r_{2-2}$ , in.....	3.47	3.49	3.50	3.52	3.53	3.55	3.57
Weight of section, lb per lin ft	83.5	91.0	99.0	106.5	114.5	122.5	130.5
Loads below the heavy line are for lengths greater than 125 radii							


\* See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Company in March, 1921.

Table XXI\* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 14-Inch H Columns with Square Ends

Unsupported length, ft	 <p>Allowable stress in pounds per square inch: 13 000 for lengths under 55 radii; 16 000 — 55 <math>l/r</math> for lengths over 55 radii</p>					
10	263.8	279.2	294.7	310.1	325.7	341.3
12	263.8	279.2	294.7	310.1	325.7	341.3
14	263.8	279.2	294.7	310.1	325.7	341.3
16	263.8	279.2	294.7	310.1	325.7	341.3
18	257.4	272.5	288.1	303.4	319.0	334.6
20	249.9	264.6	279.8	294.7	309.9	325.1
22	242.4	256.7	271.5	286.0	300.8	315.6
24	234.9	248.9	263.2	277.3	291.7	306.1
26	227.4	241.0	254.9	268.6	282.6	296.6
28	220.0	233.1	246.6	259.9	273.5	287.1
30	212.5	225.2	238.3	251.2	264.4	277.6
32	205.0	217.3	230.0	242.5	255.3	268.1
36	190.0	201.5	213.5	225.1	237.1	249.1
40	175.1	185.7	196.9	207.7	218.9	230.1
44	160.1	170.0	180.3	190.3	200.7	211.1
Area, sq in	40.59	42.95	45.33	47.71	50.11	52.51
1st moment, in <sup>4</sup> .....	1 568.4	1 674.7	1 783.3	1 894.0	2 007.0	2 122.3
2nd moment, in <sup>6</sup> .....	6.21	6.24	6.27	6.30	6.33	6.36
3rd moment, in <sup>4</sup> .....	519.7	554.4	589.5	626.1	662.3	699.0
4th moment, in <sup>6</sup> .....	3.58	3.59	3.61	3.62	3.64	3.65
Weight of section, per lin ft	138.0	146.0	154.0	162.0	170.5	178.5
Loads below the heavy line are for lengths greater than 125 radii						


See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Steel Company in March, 1921.

**Table XXI \* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 14-Inch H Columns with Square Ends**

Unsupported length, ft	<div><div></div><div>Allowable stress in pounds per square inch 13 000 for lengths under 55 radii; 16 000 — 55 <math>l/r</math> for lengths over 55 radii</div></div>						
10	357.0	372.8	388.6	403.5	419.4	435.4	451.2
12	357.0	372.8	388.6	403.5	419.4	435.4	451.2
14	357.0	372.8	388.6	403.5	419.4	435.4	451.2
16	357.0	372.8	388.6	403.5	419.4	435.4	451.2
18	350.3	366.1	381.9	396.9	412.9	429.0	444.8
20	340.4	355.8	371.2	385.8	410.5	417.2	433.0
22	330.5	345.5	360.5	374.8	390.0	405.3	420.5
24	320.6	335.2	349.8	363.7	378.5	393.4	408.0
26	310.7	324.9	339.1	352.6	367.1	381.6	396.0
28	300.8	314.6	328.4	341.6	355.6	369.7	383.5
30	290.9	304.3	317.7	330.5	344.1	357.8	371.5
32	281.0	294.0	307.0	319.4	332.6	345.9	359.0
36	261.2	273.4	285.6	297.3	309.7	322.2	334.5
40	241.4	252.8	264.2	275.1	286.8	298.5	310.0
44	221.6	232.2	242.8	253.0	263.8	274.8	285.5
Area, sq in	54.92	57.35	59.78	62.07	64.52	66.98	69.45
$I_{1-1}$ , in <sup>4</sup> .....	2 239.8	2 359.7	2 481.9	2 603.3	2 730.2	2 859.6	2 991.5
$r_{1-1}$ , in.....	6.39	6.41	6.44	6.48	6.51	6.53	6.56
$I_{2-2}$ , in <sup>4</sup> .....	736.3	744.2	812.6	849.8	889.3	929.4	970.1
$r_{2-2}$ , in.....	3.66	3.67	3.69	3.70	3.71	3.73	3.74
Weight of section, lb per lin ft	186.5	195.0	203.5	211.0	219.5	227.5	235.5
Loads below the heavy line are for lengths greater than 125 radii							

\* See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Company in March, 1921.

Table XII\* (Continued). Safe Loads in Tons of 2 000 Pounds for Bethlehem Rolled-Steel 14-Inch H Columns with Square Ends

Unsupported length, ft	<div></div> <div>Allowable stress in pounds per square inch: 13 000 for lengths under 55 radii; 16 000 — 55 <math>l/r</math> for lengths over 55 radii</div>					
10	467.6	483.8	500.0	516.4	532.8	549.3
12	467.6	483.8	500.0	516.4	532.8	549.3
14	467.6	483.8	500.0	516.4	532.8	549.3
16	467.6	483.8	500.0	516.4	532.8	549.3
18	461.5	477.9	494.4	510.9	527.6	544.3
20	448.9	464.8	480.9	497.0	513.3	529.6
22	436.2	451.8	467.4	483.2	499.1	515.0
24	423.6	438.7	454.0	469.3	484.8	500.4
26	410.9	425.7	440.5	455.5	470.6	485.7
28	398.2	412.6	427.1	441.6	456.3	471.1
30	385.6	399.6	413.6	427.8	442.1	456.4
32	372.9	386.5	400.2	413.9	427.8	441.8
36	347.6	360.4	373.3	386.3	399.4	412.5
40	322.2	334.3	346.4	358.6	370.9	383.3
44	296.9	308.1	319.5	330.9	342.4	354.0
Area, sq in	71.94	74.43	76.93	79.44	81.97	84.50
14 in <sup>2</sup> .....	3 125.8	3 262.7	3 402.1	3 544.1	3 688.8	3 836.1
14 in <sup>2</sup> .....	6.59	6.62	6.65	6.68	6.71	6.74
14 in <sup>2</sup> .....	1 011.3	1 053.2	1 095.6	1 138.7	1 182.4	1 226.7
14 in <sup>2</sup> .....	3.75	3.76	3.77	3.79	3.80	3.81
Weight of section, per lin ft	244.5	253.0	261.5	270.0	278.5	287.5

Loads below the heavy line are for lengths greater than 125 radii

See Supplementary Sections in Pamphlet S-10, published by the Bethlehem Steel Company in March, 1921.

**Table XXII. Safe Loads in Tons of 2 000 Pounds for Light-Weight Columns \***


Factor of safety between 4.5 and 5											
Calculated by the formula, $P = A_s(13\ 500 - 140\ l/d) + A_c(1\ 000 - 11\ l/d)$ in which $A_s$ and $A_c$ are the areas of steel pipe and concrete, in square inches, length in inches, and $d$ the outside diameter of pipe, in inches											
Outside diam- eter, in	Weight per linear foot, in	Length of column in feet									
		6	7	8	9	10	11	12	13	14	15
3	9.64	6	6	5	.....	....	....	....	....	....	....
3½	13.09	9	9	8	8	7	....	....	....	....	....
4	17.02	13	13	12	12	11	10	....	....	....	....
4½	21.05	14	14	13	13	12	11	10	....	....	....
5	25.90	20	20	19	19	18	18	17	17	16	....
6	36.82	28	28	27	27	26	26	25	24	23	23

**Table XXIII. Safe Loads in Tons of 2 000 Pounds for Heavy-Weight Lally Columns \***

Factor of safety between 4.5 and 5								
These loads can be greatly increased by reinforcing the concrete								
Calculated by the formula, $P = A_s(13\ 500 - 140\ l/d) + A_c(1\ 000 - 11\ l/d)$ in which $A_s$ and $A_c$ are the areas of steel pipe and concrete, in square inches, length in inches, and $d$ the outside diameter of pipe, in inches								
Outside diameter, in	Weight per linear foot, lb	Length of columns in feet						
		6	8	10	12	14	16	18
3½	15	12	11	10	9	.....	.....	.....
4	20	16	15	14	13	11	.....	.....
4½	24	20	18	17	16	15	.....	.....
5	29	27	26	24	22	21	19	.....
5½	36	32	31	29	28	26	24	22
6	49	45	43	41	40	38	35	34
7	64	58	56	54	52	51	49	46
8	81	74	72	69	67	65	62	60
9	100	93	89	87	85	82	79	77
10	123	111	109	107	104	101	99	96
11	146	131	128	124	122	119	117	113
12	169	150	146	144	141	139	135	133

\*For areas of cross-sections of metal and concrete, and for other data used in calculations for determining safe loads by formula, see Handbook of the United States Steel Company, Cambridge, Mass. (See, also, pages 469 to 474, and page 477.)

Table XXIV.\* Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Web-plate 6" X 1/4"			Web-plate 8" X 1/4"			
	4 angles 2 1/2" X 2" X 1/4"	4 angles 3" X 2" X 1/4"	4 angles 3" X 2 1/2" X 1/4"	4 angles 3" X 2 1/2" X 1/4"	4 angles 3" X 2 1/2" X 5/16"	4 angles 3 1/2" X 2 1/2" X 1/4"	4 angles 3 1/2" X 2 1/2" X 5/16"
6	69	81	88	94	110	101	119
7	63	78	82	86	103	101	119
8	56	72	76	79	95	96	115
9	49	66	69	72	87	89	107
10	43	60	63	65	78	83	100
11	38	54	56	57	70	76	92
12	35	49	50	50	62	70	85
13	32	43	45	47	56	63	78
14	28	40	42	43	52	57	70
15	25	37	39	39	48	52	63
16	22	34	35	36	44	49	60
17	18	32	32	32	40	46	56
18	.....	29	29	28	36	43	52
19	.....	26	26	25	32	39	49
20	.....	23	22	.....	28	36	45
21	.....	20	.....	.....	.....	33	41
22	.....	.....	.....	.....	.....	30	38
23	.....	.....	.....	.....	.....	27	34
24	.....	.....	.....	.....	.....	23	30
25	.....	.....	.....	.....	.....	.....	.....
26	.....	.....	.....	.....	.....	.....	.....
27	.....	.....	.....	.....	.....	.....	.....
28	.....	.....	.....	.....	.....	.....	.....
29	.....	.....	.....	.....	.....	.....	.....
30	.....	.....	.....	.....	.....	.....	.....
1/4 in	5.74	6.26	6.74	7.24	8.48	7.76	9.12
1/2 in	34.3	39.1	42.6	81.2	96.9	90.1	107
3/4 in	2.45	2.50	2.51	3.35	3.38	3.41	3.43
1 in	6.2	10.3	10.3	10.3	12.9	16.0	20.2
1 1/4 in	1.04	1.28	1.24	1.19	1.23	1.44	1.49
1 1/2 in	19.6	21.5	23.1	24.8	29.2	26.4	31.2

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
 between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower  
 line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table XXIV\* (Continued). Safe Loads in Units of 1,000 Pounds for Flat and-Angle Columns**


<div style="display: flex; align-items: center;"> <div style="text-align: center; margin-right: 20px;">  </div> <div> <p>Allowable fiber-stress in pounds per square inch  13 000 for lengths of 60 radii or under  Reduced for lengths between 60 and 120 radii,  Formula (13),  <math>S = 19\,000 - 100\,l/r</math>  Weights do not include rivet-heads or other details  For values for <math>l/r</math> above 120, see notes on page 490</p> </div> </div>							
Effective length, ft	Web-plate 8" X 3/16"				Web-plate 8" X 3/8"		
	4 angles 3 1/2" X 3 1/2" X 3/16"	4 angles 3 1/2" X 2 1/2" X 3/8"	4 angles 4" X 3" X 3/16"	4 angles 4" X 3" X 3/8"	4 angles 4" X 3" X 3/8"	4 angles 4" X 3" X 3/16"	4 angles 4" X 2 1/2" X 1/4"
6	125	142	141	161	168	188	201
7	125	142	141	161	168	188	201
8	120	138	141	161	168	188	201
9	112	130	136	158	163	183	201
10	104	121	128	149	154	175	19
11	96	112	121	140	145	165	18
12	89	104	113	131	136	155	17
13	81	95	105	123	127	145	16
14	73	86	97	114	118	135	15
15	66	77	89	105	109	124	14
16	62	73	81	97	100	114	13
17	58	68	75	88	90	104	12
18	54	64	71	83	86	98	11
19	50	60	67	79	81	93	10
20	47	55	63	74	77	88	10
21	43	51	59	70	72	83	9
22	39	47	55	66	68	78	8
23	35	42	51	61	63	73	8
24	31	38	48	57	59	68	7
25	.....	34	44	53	54	63	7
26	.....	.....	40	48	49	58	6
27	.....	.....	36	44	45	53	6
28	.....	.....	.....	39	40	48	.....
29	.....	.....	.....	.....	.....	.....	.....
30	.....	.....	.....	.....	.....	.....	.....
Area, sq in	9.62	10.94	10.86	12.42	12.92	14.48	16
$I_{1-1}$ , in <sup>4</sup> .....	110	127	122	141	143	161	1
$r_{1-1}$ , in.....	3.38	3.40	3.35	3.36	3.33	3.34	3
$I_{2-2}$ , in <sup>4</sup> .....	20.7	24.9	30.3	36.3	37.2	43.5	3
$r_{2-2}$ , in.....	1.47	1.51	1.67	1.71	1.70	1.73	1
Weight, lb per lin ft..	32.9	37.3	37.3	42.5	44.2	49.4	5

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 13\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Web-plate 10" x 1/4"			Web-plate 10" x 3/16"			Web-plate 10" x 1/2"		
	angles 1 1/2" x 1 1/4"	angles 2 1/2" x 1 1/4"	angles 2 1/2" x 3/4"	angles 2 1/2" x 3/4"	angles 3" x 3/4"	...	angles 3" x 3/4"	4 angles 4" x 3" x 3/4"	4 angles 5" x 3 1/2" x 3/4"
								198	207
								198	207
								198	207
								192	207
								181	207
								170	203
								160	194
								149	185
								138	175
								127	166
								116	157
								106	148
								101	139
								95	130
								90	121
								84	112
								79	107
								74	103
								68	98
								63	93
								57	89
								52	84
								47	80
									75
									71
								15.23	15.90
								267	275
								4 19	4.44
								43.5	70.4
								1 69	2.44
								52.0	54.1

$l/r$  not over 60  
below the lower

inch, ft.

Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate and-Angle Columns



Allowable fiber-stress in pounds per square inch  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13),

$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 10'' $\times$ 3/8''				Web-plate 10'' $\times$ 1/2''			Web- 10'' $\times$
	4 angles 5'' $\times$ 3 1/2'' $\times$ 7/16''	4 angles 6'' $\times$ 4'' $\times$ 3/8''	4 angles 6'' $\times$ 4'' $\times$ 7/16''	4 angles 6'' $\times$ 4'' $\times$ 1/2''	4 angles 6'' $\times$ 4'' $\times$ 1/2''	4 angles 6'' $\times$ 4'' $\times$ 9/16''	4 angles 6'' $\times$ 4'' $\times$ 3/8''	4 angles 6'' $\times$ 4'' $\times$ 3/8''
6	232	236	266	296	312	341	370	386
7	232	236	266	296	312	341	370	386
8	232	236	266	296	312	341	370	386
9	232	236	266	296	312	341	370	386
10	232	236	266	296	312	341	370	386
11	230	236	266	296	312	341	370	386
12	220	236	266	296	312	341	370	386
13	210	235	266	296	312	341	370	386
14	200	226	257	288	302	333	363	378
15	190	218	248	278	291	321	350	365
16	180	209	238	267	280	309	337	351
17	170	201	229	257	269	297	325	338
18	160	192	220	247	258	285	312	325
19	150	184	210	237	247	274	299	312
20	140	175	201	226	236	262	287	298
21	130	167	191	216	225	250	274	285
22	123	158	182	206	214	238	261	272
23	118	150	172	195	203	226	249	258
24	113	141	163	185	192	214	236	245
25	108	132	154	175	181	203	223	232
26	103	126	144	164	170	191	210	218
27	98	121	139	157	164	181	198	207
28	93	117	134	152	158	175	192	200
29	88	113	130	146	153	169	186	193
30	83	109	125	141	147	164	179	187
Area, sq in	17.87	18.19	20.47	22.75	24.00	26.24	28.44	29.69
-1, in <sup>4</sup> .....	315	319	361	401	412	451	489	500
-1, in <sup>4</sup> .....	4.20	4.19	4.20	4.20	4.14	4.15	4.15	4.10
-1, in <sup>4</sup> .....	82.3	119	139	160	165	186	206	213
-1, in <sup>4</sup> .....	2.15	2.56	2.61	2.65	2.62	2.66	2.69	2.68
Weight, per lin ft..	60.8	62.0	70.0	77.6	81.8	89.4	97.0	101.2

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60; those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns

allowable fiber-stress in pounds per square inch:  
10 for lengths of 60 radii or under

Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details

For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 12" X 1/2"			Web-plate 12" X 3/8"		Web-plate 12" X 3/4"			
	4 angles 3 1/2" X 3 1/2" X 1/4"	4 angles 3 1/2" X 2 1/2" X 3/16"	4 angles 4" X 3" X 3/16"	4 angles 4" X 3" X 3/16"	4 angles 4" X 3" X 3/8"	4 angles 4" X 3" X 1/2"	4 angles 5" X 3 1/2" X 3/8"	4 angles 5" X 3 1/2" X 1/2"	4 angles 5" X 3 1/2" X 1/2"
6	114	132	148	157	178	187	217	242	266
7	112	132	148	157	178	187	217	242	266
8	104	123	148	157	178	187	217	242	266
9	96	115	140	147	169	177	217	242	266
10	89	106	131	138	159	167	217	242	266
11	81	98	123	129	149	156	210	237	264
12	73	89	114	120	139	145	201	226	253
13	65	80	106	111	129	134	191	215	241
14	59	72	97	101	119	124	181	205	229
15	55	67	89	93	109	113	171	194	218
16	52	63	80	84	99	102	162	184	206
17	48	58	76	79	92	96	152	173	195
18	44	54	71	75	87	91	142	162	184
19	40	50	67	70	82	85	132	152	172
20	36	45	63	65	77	80	123	141	161
21	32	41	59	61	72	75	115	130	149
22	28	37	55	56	67	69	110	125	141
23	.....	33	50	52	62	64	105	120	135
24	.....	.....	46	47	57	58	100	114	129
25	.....	.....	42	42	52	53	95	109	123
26	.....	.....	38	38	47	48	91	104	118
27	.....	.....	.....	.....	42	.....	86	98	112
28	.....	.....	.....	.....	.....	.....	81	93	106
29	.....	.....	.....	.....	.....	.....	76	88	101
30	.....	.....	.....	.....	.....	.....	71	82	95
Area, sq in	8.76	10.12	11.36	12.11	13.67	14.42	16.70	18.62	20.50
$I_{xx}$ , in <sup>4</sup>	222	264	295	304	350	359	421	476	526
$r_{xx}$ , in	5.01	5.11	5.09	5.01	5.06	4.99	5.02	5.05	5.07
$I_{yy}$ , in <sup>4</sup>	16.0	20.2	29.6	30.3	36.3	37.3	70.6	82.3	94.6
$r_{yy}$ , in	1.35	1.41	1.61	1.58	1.63	1.61	2.06	2.10	2.15
Weight, lb per lin ft	39.8	34.6	39.0	41.6	46.8	49.1	56.9	63.3	69.7

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60; those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower heavy line are for ratios not over 200  $l/r$ .

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXIV • (Continued). Safe Loads in Units of 1 000 Pounds for Plain and-Angle Columns

Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13),

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 12"×3/8"		Web-plate 12"×1/2"						Web-plate 12"×3/4"	
	4 angles 6"×4"×3/16"	4 angles 6"×4"×1/2"	4 angles 6"×4"×1/2"	4 angles 6"×4"×9/16"	4 angles 6"×4"×5/8"	4 angles 6"×4"×11/16"	4 angles 6"×4"×3/4"	4 angles 6"×4"×3/4"	4 angles 6"×4"×3/4"	
6	276	305	325	354	383	411	439	458	478	
7	276	305	325	354	383	411	439	458	478	
8	276	305	325	354	383	411	439	458	478	
9	276	305	325	354	383	411	439	458	478	
10	276	305	325	354	383	411	439	458	478	
11	276	305	325	354	383	411	439	458	478	
12	276	305	325	354	383	411	439	458	478	
13	274	305	323	354	383	411	439	458	478	
14	264	295	312	342	373	403	433	451	469	
15	254	284	300	330	359	389	418	435	452	
16	244	274	288	317	346	375	403	419	436	
17	234	263	277	305	333	361	388	404	420	
18	224	252	265	292	319	347	373	388	403	
19	214	241	253	280	306	333	358	378	387	
20	204	230	242	267	293	318	344	357	370	
21	194	220	230	255	279	304	329	341	354	
22	184	209	218	242	266	290	314	325	338	
23	174	198	207	230	253	276	299	310	321	
24	164	187	195	217	239	262	284	294	305	
25	155	176	183	204	226	248	269	278	288	
26	147	166	173	192	213	234	254	262	272	
27	142	160	167	185	203	220	239	247	256	
28	137	154	162	179	196	213	230	239	248	
29	132	149	156	173	189	206	223	231	240	
30	127	143	150	166	183	199	215	223	232	
Area, sq in	21.22	23.50	25.00	27.24	29.44	31.60	33.76	35.26	36.76	
$I_{1-1}$ , in <sup>4</sup> .....	544	605	623	683	741	794	849	867	885	
$r_{1-1}$ , in.....	5.06	5.07	4.99	5.01	5.02	5.01	5.01	4.96	4.91	
$I_{2-2}$ , in <sup>4</sup> .....	139	160	165	186	206	228	249	257	266	
$r_{2-2}$ , in.....	2.56	2.61	2.57	2.61	2.65	2.69	2.72	2.70	2.69	
Weight, lb per lin ft..	72.5	80.1	85.2	92.8	100.4	107.6	114.8	119.9	125.0	

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60  
those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower  
heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXIV • (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under

Reduced for lengths between 60 and 120 radii, by  
Formula (13),

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details

For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Web-plate 12"X $\frac{3}{8}$ "				Web-plate 12"X $\frac{1}{2}$ "	
	4 angles 6"X4"X $\frac{3}{8}$ " 2 plates 14"X $\frac{3}{8}$ "	4 angles 6"X4"X $\frac{3}{8}$ " 2 plates 14"X $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{7}{16}$ " 2 plates 14"X $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{3}{8}$ "
11	383	428	458	487	507	553
12	383	428	458	487	507	553
13	383	428	458	487	507	553
14	383	428	458	487	507	553
15	383	428	458	487	507	553
16	379	428	458	487	506	553
17	368	419	447	475	491	542
18	357	407	434	461	476	526
19	346	395	421	447	461	510
20	334	383	407	433	447	495
21	323	370	394	419	432	479
22	312	358	381	405	417	463
23	301	346	368	391	403	448
24	289	334	355	377	388	432
25	278	322	342	363	373	416
26	267	310	329	349	358	401
27	256	297	316	335	344	385
28	244	285	303	321	329	369
29	233	273	290	307	314	354
30	222	261	277	293	299	338
31	211	249	264	279	285	323
32	203	237	250	265	272	307
33	197	228	242	257	264	294
34	191	221	235	250	257	287
35	186	215	229	243	249	279
Area, sq in	29.44	32.94	35.22	37.50	39.00	42.50
Weight, lb. per lin. ft.	100.2	112.1	120.1	127.7	132.8	144.7

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower  
heavy line are for ratios not over 200  $l/r$

Table XXIV • (Continued). Safe Loads in Units of 1 000 Pounds for Plate and-Angle Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$S = 19\,000 - 100\,l/r$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 12"×1/2"		Web-plate 12"×3/8"			
	4 angles 6"×4"×9/16" 2 plates 14"×5/8"	4 angles 6"×4"×3/8" 2 plates 14"×5/8"	4 angles 6"×4"×3/8" 2 plates 14"×5/8"	4 angles 6"×4"×3/8" 2 plates 14"×3/4"	4 angles 6"×4"×3/8" 2 plates 14"×7/8"	4 angles 6"×4"×3/8" 2 plates
11	582	610	630	675	721	766
12	582	610	630	675	721	766
13	582	610	630	675	721	766
14	582	610	630	675	721	766
15	582	610	630	675	721	766
16	582	610	630	675	721	766
17	569	596	613	663	714	763
18	553	579	594	644	694	742
19	536	562	576	625	674	721
20	520	544	558	606	654	700
21	503	527	540	587	634	679
22	487	509	522	568	614	658
23	470	492	504	548	594	637
24	454	475	486	529	574	616
25	437	457	468	510	554	595
26	421	440	450	491	534	574
27	404	422	431	472	514	553
28	388	405	413	453	494	532
29	371	388	395	434	474	511
30	354	370	377	415	454	490
31	338	353	359	396	434	469
32	321	336	341	377	414	448
33	309	323	331	361	394	427
34	301	315	322	351	381	406
35	293	306	313	342	371	395
Area, sq in	44.74	46.94	48.44	51.94	55.44	58.94
$I_{1-1}$ , in <sup>4</sup> .....	1 437	1 495	1 513	1 682	1 856	2 030
$r_{1-1}$ , in.....	5.67	5.64	5.59	5.69	5.79	5.89
$I_{2-2}$ , in <sup>4</sup> .....	472	492	499	556	613	670
$r_{2-2}$ , in.....	3 25	3.24	3.21	3.27	3.33	3.39
Weight, lb per lin ft..	152.3	159.9	165.0	176.9	188.8	200.7

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower heavy line are for ratios not over 200  $l/r$

• From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 17"X $\frac{5}{8}$ "					
	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "
11	812	857	903	948	994	1 039
12	812	857	903	948	994	1 039
13	812	857	903	948	994	1 039
14	812	857	903	948	994	1 039
15	812	857	903	948	994	1 039
16	812	857	903	948	994	1 039
17	812	857	903	948	994	1 039
18	791	840	888	937	986	1 034
19	769	817	864	912	960	1 007
20	747	794	840	887	934	980
21	725	771	817	862	908	953
22	703	748	793	837	882	926
23	681	725	769	812	856	899
24	659	702	745	787	830	872
25	637	679	721	762	805	845
26	615	657	697	738	779	818
27	593	634	673	713	753	791
28	571	611	649	688	727	764
29	549	588	625	663	701	737
30	527	565	601	638	675	710
31	505	542	577	613	649	684
32	483	519	553	588	623	657
33	461	496	529	563	597	630
34	439	473	505	538	571	603
35	427	456	484	513	545	576
Area, sq in	62.44	65.94	69.44	72.94	76.44	79.94
4 in <sup>2</sup> .....	2 224	2 418	2 618	2 825	3 038	3 259
4 in <sup>2</sup> .....	5.97	6.06	6.14	6.22	6.30	6.38
4 in <sup>2</sup> .....	728	785	842	899	956	1014
4 in <sup>2</sup> .....	3.41	3.45	3.48	3.51	3.54	3.56
Weight, per lin ft..	212.6	224.5	236.4	248.3	260.2	272.1

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower  
heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.


Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns

	<p>Allowable fiber-stress in pounds per square inch: 13 000 for lengths of 60 radii or under Reduced for lengths between 60 and 120 radii, by Formula (13).</p>		$S = 19\,000 - 100\,l/r$					<p>Weights do not include rivet-heads or other details For values for <math>l/r</math> above 120, see notes on page 490</p>	
	Web-plate 12" X 3/8"		Web-plate 14" X 3/8"						
Effective length, ft	4 angles 6" X 4" X 3/8" 2 plates 14" X 1 1/8"	4 angles 6" X 4" X 5/8" 2 plates 14" X 2"	4 angles 6" X 4" X 3/8" 2 plates 14" X 3/8"	4 angles 6" X 4" X 7/16" 2 plates 14" X 3/8"	4 angles 6" X 4" X 1/2" 2 plates 14" X 3/8"	4 angles 6" X 4" X 1/2" 2 plates 14" X 7/16"	4 angles 6" X 4" X 1/2" 2 plates 14" X 7/16"	4 angles 6" X 4" X 1/2" 2 plates 14" X 7/16"	4 angles 6" X 4" X 1/2" 2 plates 14" X 7/16"
11	1 085	1 130	392	422	452	474	497		
12	1 085	1 130	392	422	452	474	497		
13	1 085	1 130	392	422	452	474	497		
14	1 085	1 130	392	422	452	474	497		
15	1 085	1 130	392	422	452	474	497		
16	1 085	1 130	387	415	444	470	497		
17	1 085	1 130	375	403	431	456	482		
18	1 082	1 130	363	390	417	442	468		
19	1 054	1 101	352	377	404	428	453		
20	1 026	1 072	340	365	390	415	439		
21	998	1 043	328	352	377	401	425		
22	970	1 014	317	340	363	387	410		
23	942	985	305	327	350	373	396		
24	914	956	293	314	336	359	381		
25	886	927	281	302	323	345	367		
26	858	898	270	289	309	331	353		
27	830	869	258	276	296	317	338		
28	802	840	246	264	282	303	324		
29	774	811	235	251	269	289	309		
30	746	782	223	239	255	275	295		
31	718	753	211	227	243	261	281		
32	690	725	205	220	236	251	271		
33	662	696	200	214	229	244	266		
34	634	667	194	208	222	237	253		
35	606	638	188	201	216	230	248		
Area, sq in	83.44	86.94	30.19	32.47	34.75	36.50	38.1		
$I_{1-1}$ , in <sup>4</sup> .....	3 486	3 721	1 261	1 351	1 436	1 539	1 6		
$r_{1-1}$ , in.....	6.46	6.54	6.46	6.45	6.43	6.49	6.5		
$I_{2-2}$ , in <sup>4</sup> .....	1071	1128	291	311	331	360	3		
$r_{2-2}$ , in.....	3.58	3.60	3.10	3.09	3.09	3.14	3.1		
Weight, lb per lin ft..	284.0	295.9	102.8	110.8	118.4	124.3	130		

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over those between heavy lines are for ratios up to 120  $l/r$ , and those below the lower heavy line are for ratios not over 200  $l/r$ .

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



**Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns**

Allowable fiber-stress in pounds per square inch:  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13),


$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 14"X $\frac{3}{8}$ "		Web-plate 14"X $\frac{1}{2}$ "		
	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{9}{16}$ "	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{5}{8}$ "	4 angles 6"X4"X $\frac{1}{2}$ " 2 plates 14"X $\frac{3}{8}$ "	4 angles 6"X4"X $\frac{9}{16}$ " 2 plates 14"X $\frac{3}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X $\frac{3}{8}$ "
11	520	543	566	595	623
12	520	543	566	595	623
13	520	543	566	595	623
14	520	543	566	595	623
15	520	543	566	595	623
16	520	543	566	595	623
17	507	533	551	578	605
18	493	517	535	561	587
19	478	502	518	544	569
20	463	487	502	527	551
21	448	472	486	510	533
22	433	456	470	493	515
23	418	441	454	476	497
24	403	426	437	459	479
25	388	410	421	442	461
26	374	395	405	424	443
27	359	380	389	407	425
28	344	364	373	390	407
29	329	349	356	373	390
30	314	334	340	356	372
31	299	318	324	339	354
32	284	303	308	322	336
33	275	290	298	312	327
34	267	282	290	304	318
35	260	275	282	295	309
Area, sq in	40.00	41.75	43.50	45.74	47.94
$I_{x-x}$ , in <sup>4</sup> .....	1 749	1 857	1 885	1 970	2 053
$r_{x-x}$ , in.....	6.61	6.67	6.58	6.56	6.54
$I_{y-y}$ , in <sup>4</sup> .....	417	446	451	472	492
$r_{y-y}$ , in.....	3.23	3.27	3.22	3.21	3.20
Weight, lb per lin ft..	136.2	142.2	148.1	155.7	163.3

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
 those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the  
 lower heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate and-Angle Columns**

Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Web-plate 14"X $\frac{5}{8}$ "						
	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X $\frac{5}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X $\frac{3}{4}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X $\frac{7}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1"	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{4}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{3}{4}$ "
11	646	691	737	732	828	873	919
12	646	691	737	782	828	873	919
13	646	691	737	782	828	873	919
14	646	691	737	782	828	873	919
15	646	691	737	782	828	873	919
16	643	691	737	782	828	873	919
17	624	675	726	776	826	873	919
18	606	655	705	754	803	852	901
19	587	635	684	733	780	829	876
20	568	615	664	711	758	805	851
21	549	596	643	690	735	782	827
22	530	576	622	668	713	758	802
23	511	556	602	646	690	734	778
24	493	536	581	625	667	711	753
25	474	517	560	603	645	687	728
26	455	497	540	581	622	664	704
27	436	477	519	560	600	640	679
28	417	457	498	538	577	617	655
29	399	438	477	516	554	593	630
30	380	418	457	495	532	569	605
31	361	398	436	473	509	546	581
32	345	378	415	452	487	522	556
33	336	365	396	430	464	499	532
34	326	356	385	415	444	475	507
35	317	346	375	404	432	461	489
Area, sq in	49.69	53.19	56.69	60.19	63.69	67.19	70.69
$I_{1-1}$ , in <sup>4</sup> .....	2 081	2 302	2 529	2 764	3 006	3 255	3 511
$r_{1-1}$ , in.....	6.47	6.58	6.63	6.78	6.87	6.96	7.05
$I_{2-2}$ , in <sup>4</sup> .....	499	556	613	671	728	785	841
$r_{2-2}$ , in.....	3.17	3.23	3.29	3.34	3.38	3.42	3.46
Weight, lb per lin ft..	169.3	181.2	193.1	205.0	216.9	228.8	240.7

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60; those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower heavy line are for ratios not over 200  $l/r$ .

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Web-plate 14"X $\frac{5}{8}$ "					
	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{1}{2}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{5}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{3}{4}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X1 $\frac{3}{8}$ "	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 14"X2"	4 angles 6"X4"X $\frac{5}{8}$ " 2 plates 16"X1 $\frac{7}{8}$ "
11	964	1 010	1 055	1 101	1 146	1 198
12	964	1 010	1 055	1 101	1 146	1 198
13	964	1 010	1 055	1 101	1 146	1 198
14	964	1 010	1 055	1 101	1 146	1 198
15	964	1 010	1 055	1 101	1 146	1 198
16	964	1 010	1 055	1 101	1 146	1 198
17	964	1 010	1 055	1 101	1 146	1 198
18	949	998	1 046	1 095	1 144	1 198
19	924	971	1 018	1 067	1 114	1 198
20	898	945	991	1 038	1 084	1 198
21	872	918	963	1 010	1 055	1 174
22	847	892	935	981	1 025	1 146
23	821	865	908	953	996	1 119
24	796	839	880	924	966	1 091
25	770	812	853	895	937	1 064
26	744	786	825	867	907	1 035
27	719	759	797	838	877	1 009
28	693	732	770	810	848	981
29	668	706	742	781	818	954
30	642	679	715	753	789	926
31	617	653	687	724	759	899
32	591	626	659	696	730	871
33	565	600	632	667	700	843
34	540	573	604	639	671	816
35	517	546	577	610	641	788
Area, sq in	74.19	77.69	81.19	84.69	88.19	92.19
$I_{x-x}$ , in <sup>4</sup> .....	3 776	4 048	4 327	4 615	4 910	5 120
$I_{y-y}$ , in <sup>4</sup> .....	7.13	7.22	7.30	7.38	7.46	7.45
$I_{x-x}$ , in <sup>4</sup> .....	899	956	1 014	1 071	1 128	1 493
$I_{y-y}$ , in <sup>4</sup> .....	3.48	3.51	3.53	3.56	3.58	4.02
Weight, lb per lin ft..	252.6	264.5	276.4	288.3	300.2	313.8

The safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60; those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the lower heavy line are for ratios not over 200  $l/r$



Table XXIV \* (Continued). Safe Loads in Units of 1 000 Pounds for Plate-and-Angle Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).


$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Two web-plates 14" X 1/2"						
Effective length, ft.	4 angles 6" X 6" X 5/8" 2 plates 16" X 2 1/2"	4 angles 8" X 6" X 5/8" 2 plates 16" X 2 1/2"	4 angles 8" X 6" X 5/8" 2 plates 18" X 2 3/8"	4 angles 8" X 6" X 5/8" 2 plates 18" X 2 1/2"	4 angles 8" X 6" X 5/8" 2 plates 18" X 2 3/8"	4 angles 8" X 6" X 5/8" 2 plates 18" X 2 1/4"
11	1 592	1 657	1 728	1 787	1 845	1 904
12	1 592	1 657	1 728	1 787	1 845	1 904
13	1 592	1 657	1 728	1 787	1 845	1 904
14	1 592	1 657	1 728	1 787	1 845	1 904
15	1 592	1 657	1 728	1 787	1 845	1 904
16	1 592	1 657	1 728	1 787	1 845	1 904
17	1 592	1 657	1 728	1 787	1 845	1 904
18	1 592	1 657	1 728	1 737	1 845	1 904
19	1 592	1 657	1 728	1 787	1 845	1 904
20	1 590	1 657	1 728	1 787	1 845	1 904
21	1 553	1 653	1 728	1 787	1 845	1 904
22	1 516	1 616	1 728	1 787	1 845	1 904
23	1 479	1 580	1 728	1 787	1 845	1 904
24	1 443	1 543	1 695	1 756	1 818	1 879
25	1 406	1 507	1 661	1 721	1 781	1 842
26	1 369	1 470	1 626	1 685	1 744	1 804
27	1 332	1 434	1 592	1 650	1 708	1 766
28	1 295	1 397	1 557	1 614	1 671	1 729
29	1 258	1 360	1 522	1 578	1 635	1 691
30	1 222	1 324	1 488	1 543	1 598	1 653
31	1 185	1 287	1 453	1 507	1 561	1 616
32	1 148	1 251	1 419	1 471	1 525	1 578
33	1 111	1 214	1 384	1 436	1 488	1 541
34	1 074	1 177	1 349	1 400	1 451	1 503
35	1 038	1 141	1 315	1 365	1 415	1 465
Area, sq in	122.44	127.44	132.94	137.44	141.94	146.44
$I_{x-x}$ , in <sup>4</sup> .....	7 014	7 254	7 559	7 991	8 415	8 859
$I_{y-y}$ , in <sup>4</sup> .....	7.57	7.54	7.54	7.62	7.70	7.78
$I_{x-x}$ , in <sup>4</sup> .....	1 946	2 229	2 831	2 953	3 074	3 196
$I_{y-y}$ , in <sup>4</sup> .....	3.99	4.18	4.61	4.63	4.65	4.67
Weight, lb per lin ft..	416.4	433.6	452.3	467.6	482.9	498.2


Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below heavy line are for ratios not over 120  $l/r$

Table XXIV\* (Continued). Safe Loads in Units of 1 000 Pounds for Plate and-Angle Columns

	Allowable fiber-stress in pounds per square inch: 13 000 for lengths of 60 radii or under Reduced for lengths between 60 and 120 radii, by Formula (13). $S = 19\,000 - 100\,l/r$ Weights do not include rivet-heads and other details For values for $l/r$ above 120, see notes on page 490					
	Two web-plates 14"X5/8"					
Effective length, ft	4 angles 8"X6"X5/8" 2 plates 18"X23/4"	4 angles 8"X6"X5/8" 2 plates 20"X25/8"	4 angles 8"X6"X5/8" 2 plates 20"X23/4"	4 angles 8"X6"X5/8" 2 plates 20"X27/8"	4 angles 8"X6"X5/8" 2 plates 20"X3"	4 angles 8"X6"X5/8" 2 plates 20"X31/8"
11	1 949	2 027	2 092	2 157	2 222	2 287
12	1 949	2 027	2 092	2 157	2 222	2 287
13	1 949	2 027	2 092	2 157	2 222	2 287
14	1 949	2 027	2 092	2 157	2 222	2 287
15	1 949	2 027	2 092	2 157	2 222	2 287
16	1 949	2 027	2 092	2 157	2 222	2 287
17	1 949	2 027	2 092	2 157	2 222	2 287
18	1 949	2 027	2 092	2 157	2 222	2 287
19	1 949	2 027	2 092	2 157	2 222	2 287
20	1 949	2 027	2 092	2 157	2 222	2 287
21	1 949	2 027	2 092	2 157	2 222	2 287
22	1 949	2 027	2 092	2 157	2 222	2 287
23	1 949	2 027	2 092	2 157	2 222	2 287
24	1 718	2 027	2 092	2 157	2 222	2 287
25	1 879	2 027	2 092	2 157	2 222	2 287
26	1 841	2 009	2 077	2 146	2 214	2 283
27	1 802	1 972	2 039	2 107	2 175	2 242
28	1 763	1 935	2 002	2 068	2 135	2 202
29	1 724	1 899	1 964	2 029	2 095	2 161
30	1 686	1 862	1 926	1 991	2 055	2 120
31	1 647	1 825	1 889	1 952	2 016	2 079
32	1 608	1 789	1 851	1 913	1 976	2 039
33	1 569	1 752	1 813	1 874	1 936	1 998
34	1 530	1 715	1 775	1 836	1 896	1 957
35	1 492	1 679	1 738	1 797	1 857	1 916
Area, sq in	149.94	155.94	160.94	165.94	170.94	175.94
$I_{1-1}$ , in <sup>4</sup> .....	8 916	9 248	9 741	10 248	10 767	11 298
$r_{1-1}$ , in.....	7.71	7.70	7.78	7.86	7.94	8.01
$I_{2-2}$ , in <sup>4</sup> .....	3 222	4 049	4 216	4 383	4 549	4 716
$r_{2-2}$ , in.....	4.64	5.10	5.12	5.14	5.16	5.18
Weight, lb per lin ft..	510.1	530.5	547.5	564.5	581.5	598.5
Safe load-values above the heavy line are for ratios of $l/r$ not over 60; the below the heavy line are for ratios not over 120 $l/r$						

\* From Pocket Companion, Carnegie Steel Company Pittsburgh, Pa.

Table XXV.\* Safe Loads in Units of 1 000 Pounds for 10-Inch Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Two 10-in channels latticed			Two 10-in channel, two 12-in plates					
	15.3-lb chan'ls, single lattice	20-lb channels, single lattice	25-lb channels, single lattice	15.3-lb chan'ls, 3/16-in plates	15-lb channels, 3/16-in plates	15.3-lb chan'ls, 7/16-in plates	15.3-lb chan'ls, 1/2-in plates	20-lb channels, 7/16-in plates	20-lb channels, 1/2-in plates
11	116	153	191	213	233	252	272	289	309
12	116	153	191	213	233	252	272	289	309
13	116	153	191	213	233	252	272	289	309
14	116	153	191	213	233	252	272	289	309
15	116	153	191	213	233	252	272	289	309
16	116	153	191	213	233	252	272	289	309
17	116	153	191	213	233	252	272	289	309
18	116	152	186	213	233	252	271	286	305
19	115	148	181	208	227	245	264	278	297
20	112	144	176	203	221	239	257	271	289
21	109	140	171	197	215	232	250	263	280
22	106	136	165	192	209	226	243	256	272
23	103	132	160	186	203	219	236	248	264
24	100	128	155	181	197	213	229	240	256
25	98	124	150	175	191	206	222	233	248
26	95	120	145	170	185	200	215	225	240
27	92	116	140	164	179	193	208	217	231
28	89	112	134	159	173	187	201	210	223
29	86	108	129	153	167	180	194	202	215
30	83	104	124	148	161	174	187	195	207
31	80	100	119	142	155	167	180	187	199
32	77	96	114	137	149	161	173	179	191
33	75	92	109	131	143	154	166	172	183
34	72	88	103	126	137	148	159	164	174
35	69	84	101	120	131	141	152	157	166
Area, sq in	8.92	11.76	14.70	16.42	17.92	19.42	20.92	22.26	23.76
1 1/2 in <sup>4</sup> ...	134	158	182	333	376	420	465	444	489
2 in <sup>4</sup> .....	3.87	3.66	3.52	4.30	4.58	4.65	4.71	4.46	4.53
3 in <sup>4</sup> .....	123	148	171	213	231	249	267	274	292
4 in <sup>4</sup> .....	3.72	3.55	3.41	3.60	3.51	3.58	3.58	3.51	3.50
Weight, lb per lin ft..	37.8	47.8	57.8	55.5	60.6	65.7	70.8	75.7	80.8

Safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
line between the heavy lines are for ratios up to 120  $l/r$ ; and those below the  
lower heavy line are for ratios not over 200  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.


Table XXV\* (Continued). Safe Loads in Units of 1 000 Pounds for 10-in Channel-Columns

	Allowable fiber-stress in pounds per square inch 13 000 for lengths of 60 radii or under Reduced for lengths between 60 and 120 radii, by Formula (13). $S = 19\,000 - 100\,l/r$ Weights do not include rivet-heads or other details For values for $l/r$ above 120, see notes on page 490							
Two 10-in channels, two 12-in plates								
Effective length, ft	20-lb channels, 9/16-in plates	20-lb channels, 5/8-in plates	25-lb channels, 9/16-in plates	25-lb channels, 5/8-in plates	30-lb channels, 9/16-in plates	30-lb channels, 5/8-in plates	35-lb channels, 9/16-in plates	35-lb channels, 5/8-in plates
11	328	348	367	386	405	424	443	462
12	328	348	367	386	405	424	443	462
13	328	348	367	386	405	424	443	462
14	328	348	367	386	405	424	443	462
15	328	348	367	386	405	424	443	462
16	328	348	367	386	405	424	443	462
17	328	348	367	386	403	423	437	451
18	324	343	359	378	392	411	424	441
19	315	334	349	367	381	399	412	431
20	307	325	339	357	370	388	400	419
21	298	316	329	347	359	376	387	406
22	289	307	319	336	348	364	375	394
23	281	297	310	326	337	353	362	381
24	272	288	300	316	326	341	350	369
25	263	279	290	305	314	330	338	357
26	255	270	280	295	303	318	325	344
27	246	261	270	285	292	306	313	332
28	237	252	260	274	281	295	301	320
29	229	242	251	264	270	283	288	307
30	220	233	241	253	259	271	276	295
31	211	224	231	243	248	260	263	282
32	203	215	221	233	237	248	251	270
33	194	206	211	222	226	237	239	258
34	185	196	201	212	216	227	232	251
35	177	187	194	205	211	221	226	246
Area, sq in	25.26	26.76	28.20	29.70	31.14	32.64	34.08	35.58
$I_{1-1}$ , in <sup>4</sup> .....	534	581	559	606	583	630	608	655
$r_{1-1}$ , in.....	4.60	4.66	4.45	4.52	4.33	4.39	4.22	4.14
$I_{2-2}$ , in <sup>4</sup> .....	310	328	333	351	354	372	372	390
$r_{2-2}$ , in.....	3.50	3.50	3.44	3.44	3.37	3.37	3.30	3.23
Weight, lb per lin ft..	85.9	91.0	95.9	101.0	105.9	111.0	115.9	121.0
Safe load-values above the upper heavy line are for ratios of $l/r$ not over those between the heavy lines are for ratios up to 120 $l/r$ ; and those below lower heavy line are for ratios not over 200 $l/r$								

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XXV • (Continued). Safe Loads in Units of 1 000 Pounds for 10-Inch Channel-Columns



Allowable fiber-stress in pounds per square inch:  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13),


$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Two 10-in channels, latticed				Two 10-in channels, two 14-in plates			
	15.3-lb chan'ls, single lattice	20-lb channels, single lattice	25-lb channels, single lattice	30-lb channels, single lattice	15.3-lb chan'ls, 3/8-in plates	15.3-lb chan'ls, 7/16-in plates	15.3-lb chan'ls, 1/2-in plates	20-lb channels, 7/16-in plates
11	116	153	191	229	252	275	298	312
12	116	153	191	229	252	275	298	312
13	116	153	191	229	252	275	298	312
14	116	153	191	229	252	275	298	312
15	116	153	191	229	252	275	298	312
16	116	153	191	229	252	275	298	312
17	116	153	191	229	252	275	298	312
18	116	153	189	224	252	275	298	312
19	116	150	184	218	252	275	298	312
20	114	146	179	211	252	275	298	312
21	111	142	174	205	252	275	298	312
22	109	139	169	199	251	273	295	308
23	106	135	164	193	246	267	289	302
24	103	131	159	187	241	261	282	295
25	100	127	154	180	235	256	276	288
26	98	123	149	174	230	250	270	282
27	95	119	144	168	225	244	263	275
28	92	115	139	162	219	238	257	268
29	89	112	134	156	214	232	250	261
30	87	108	129	149	209	226	244	255
31	84	104	124	143	203	220	238	248
32	81	100	119	137	198	214	231	241
33	78	96	114	131	193	209	225	235
34	75	92	109	125	187	203	219	228
35	73	88	104	121	182	197	212	221
Area, sq in	8.92	11.76	14.70	17.64	19.42	21.17	22.92	24.01
$I_{x-x}$ , in <sup>4</sup> .....	134	158	182	207	416	468	520	491
$r_{x-x}$ , in.....	3.87	3.66	3.52	3.42	4.63	4.70	4.76	4.52
$I_{y-y}$ , in <sup>4</sup> .....	197	241	284	323	369	398	426	442
$r_{y-y}$ , in.....	4.70	4.53	4.39	4.28	4.36	4.33	4.31	4.29
Weight, lb per lin ft..	39.3	49.4	59.4	69.4	65.7	71.7	77.6	81.7

Safe load-values above the upper heavy line are for ratios of  $l/r$  not over 60;  
 those between the heavy lines are for ratios up to 120  $l/r$ ; and those below the  
 lower heavy line are for ratios not over 200  $l/r$

Table XXV \* (Continued). Safe Loads in Units of 1 000 Pounds for 10-in Channel-Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii,  
Formula (13),

$S = 19\,000 - 100\,l/r$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 10-in channels, two 14-in plates						
	20-lb channels, 1/2-in plates	20-lb channels, 3/16-in plates	20-lb channels, 1/2-in plates	25-lb channels, 3/16-in plates	25-lb channels, 1/2-in plates	25-lb channels, 1 1/16-in plates	25-lb channels, 1 1/2-in plates
11	335	358	380	396	419	441	463
12	335	358	380	396	419	441	463
13	335	358	380	396	419	441	463
14	335	358	380	396	419	441	463
15	335	358	380	396	419	441	463
16	335	358	380	396	419	441	463
17	335	358	380	396	419	441	463
18	335	358	380	396	419	441	463
19	335	358	380	396	419	441	463
20	335	358	380	396	419	441	463
21	335	358	380	396	419	441	463
22	330	352	374	388	410	432	454
23	323	344	365	379	401	422	444
24	316	337	357	371	392	412	434
25	308	329	349	362	382	403	425
26	301	321	341	353	373	393	415
27	294	313	332	345	364	383	405
28	287	306	324	336	355	373	395
29	279	298	316	327	346	364	385
30	272	290	308	319	336	354	375
31	265	282	299	310	327	344	365
32	258	275	291	301	318	335	355
33	251	267	283	293	309	325	345
34	243	259	274	284	300	315	335
35	236	251	266	275	291	306	325
Area, sq in	25.76	27.51	29.26	30.45	32.20	33.95	35.70
$I_{1-1}$ , in <sup>4</sup> .....	544	597	652	622	676	732	788
$r_{1-1}$ , in.....	4.59	4.66	4.72	4.52	4.58	4.64	4.70
$I_{2-2}$ , in <sup>4</sup> .....	470	499	527	541	570	598	626
$r_{2-2}$ , in.....	4.27	4.26	4.24	4.22	4.21	4.20	4.19
Weight, lb per lin ft..	87.6	93.6	99.5	103.6	109.5	115.5	121.4

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; and the values below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XIV\* (Continued). Safe Loads in Units of 1 000 Pounds for 10-Inch Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Two 10-in channels, two 14-in plates					
	30-lb channels, 1 1/16-in plates	30-lb channels, 3/4-in plates	30-lb channels, 1 3/16-in plates	30-lb channels, 7/8-in plates	30-lb channels, 1 5/16-in plates	30-lb channels, 1-in plates
11	480	502	525	548	571	593
12	480	502	525	548	571	593
13	480	502	525	548	571	593
14	480	502	525	548	571	593
15	480	502	525	548	571	593
16	480	502	525	548	571	593
17	480	502	525	548	571	593
18	480	502	525	548	571	593
19	480	502	525	548	571	593
20	480	502	525	548	571	593
21	477	500	522	544	567	589
22	467	488	510	532	554	575
23	456	477	499	520	541	562
24	446	466	487	508	529	549
25	435	455	475	495	516	536
26	424	444	464	483	503	522
27	414	432	452	471	490	509
28	403	421	440	459	478	496
29	392	410	429	446	465	483
30	382	399	417	434	452	469
31	371	388	405	422	440	456
32	360	377	394	410	427	443
33	350	365	382	398	414	430
34	339	354	370	385	401	416
35	328	343	359	373	389	403
Area, sq in	36.89	38.64	40.39	42.14	43.89	45.64
Weight, lb per lin ft...	125.5	131.4	137.4	143.3	149.3	155.2
1 in <sup>4</sup> .....	757	814	873	932	994	1 056
1 in <sup>3</sup> .....	4.53	4.59	4.65	4.70	4.76	4.81
1 in <sup>2</sup> .....	637	666	695	723	752	780
1 in.....	4.16	4.15	4.15	4.14	4.14	4.13

\* Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXV\* (Continued). Safe Loads in Units of 1 000 Pounds for 10-in Channel-Columns

Allowable fiber-stress in pounds per square inch  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13),


$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 10-in channels, two 14-in plates					
	35-lb channels, 1 5/16-in plates	35-lb channels, 1-in plates	35-lb channels, 1 1/4-in plates	35-lb channels, 1 1/8-in plates	35-lb channels, 1 3/16-in plates	35-lb channels, 1 1/2-in plates
11	609	632	654	677	700	723
12	609	632	654	677	700	723
13	609	632	654	677	700	723
14	609	632	654	677	700	723
15	609	632	654	677	700	723
16	609	632	654	677	700	723
17	609	632	654	677	700	723
18	609	632	654	677	700	723
19	609	632	654	677	700	723
20	609	632	654	677	700	723
21	602	624	647	669	691	714
22	588	610	632	654	675	697
23	575	596	617	639	660	681
24	561	582	603	624	644	665
25	547	568	588	608	628	648
26	533	553	573	593	612	632
27	520	539	559	578	596	616
28	506	525	544	563	581	599
29	492	511	529	547	565	583
30	479	496	514	532	549	567
31	465	482	500	517	533	550
32	451	468	485	502	517	534
33	437	454	470	487	502	518
34	424	440	455	471	486	502
35	410	425	441	456	470	485
Area, sq in	46.83	48.58	50.33	52.08	53.83	55.5
$I_{1-1}$ , in <sup>4</sup> .....	1 018	1 080	1 144	1 209	1 275	1 34
$r_{1-1}$ , in.....	4.66	4.72	4.77	4.82	4.87	4.9
$I_{2-2}$ , in <sup>4</sup> .....	788	816	845	874	902	93
$r_{2-2}$ , in.....	4.10	4.10	4.10	4.10	4.09	4.0
Weight, lb per lin ft..	159.3	165.2	171.2	177.1	183.1	189.

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those low the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table XXVL.\* Safe Loads in Units of 1 000 Pounds for 12-Inch Channel-Columns**

Allowable fiber-stress in pounds per square inch:  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, $l/r$	Two 12-in channels, latticed				Two 12-in channels, two 14-in plates		
	20.7-lb chan'ls, single lattice	25-lb channels, single lattice	30-lb channels, single lattice	35-lb channels, single lattice	20.7-lb chan'ls, 3/8-in plates	20.7-lb chan'ls, 7/16-in plates	20.7-lb chan'ls, 1/2-in plates
11	157	191	229	268	293	316	339
12	157	191	229	268	293	316	339
13	157	191	229	268	293	316	339
14	157	191	229	268	293	316	339
15	157	191	229	268	293	316	339
16	157	191	229	268	293	316	339
17	157	191	229	268	293	316	339
18	157	191	229	268	293	316	339
19	157	191	229	268	293	316	339
20	157	191	229	268	293	316	339
21	157	191	229	265	293	316	339
22	157	190	225	259	290	312	334
23	155	186	220	253	283	305	326
24	152	182	215	248	277	298	319
25	149	178	210	242	271	291	312
26	146	174	205	236	265	284	304
27	142	170	200	230	258	277	297
28	139	166	195	224	252	271	290
29	136	162	190	218	246	264	282
30	133	158	185	212	239	257	275
31	129	154	180	206	233	250	268
32	126	150	175	200	227	243	260
33	123	146	170	194	220	236	253
34	120	142	165	188	214	230	246
35	117	138	160	182	208	223	238
Area, sq in	12.06	14.70	17.64	20.58	22.56	24.31	26.06
$I_x$ , in <sup>4</sup> .....	256	288	323	359	658	730	803
$I_y$ , in <sup>4</sup> .....	4.61	4.43	4.28	4.17	5.40	5.48	5.55
$I_{xy}$ , in <sup>4</sup> .....	244	279	316	351	415	444	473
$I_{xy}$ , in <sup>4</sup> .....	4.50	4.36	4.23	4.13	4.29	4.27	4.26
Weight, per lin ft.	50.4	59.4	69.4	79.4	76.7	82.7	88.6

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVI\* (Continued). Safe Loads in Units of 1 000 Pounds for 12-in Channel-Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13),

$S = 19\,000 - 100\,l/r$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 12-in channels, two 14-in plates						
	20.7-lb chan'ls, 9/16-in plates	20.7-lb chan'ls, 5/8-in plates	25-lb channels, 9/16-in plates	25-lb channels, 5/8-in plates	25-lb channels, 1 1/16-in plates	25-lb channels, 3/4-in plates	25-lb channels, 1 3/16-in plates
11	362	384	396	419	441	464	487
12	362	384	396	419	441	464	487
13	362	384	396	419	441	464	487
14	362	384	396	419	441	464	487
15	362	384	396	419	441	464	487
16	362	384	396	419	441	464	487
17	362	384	396	419	441	464	487
18	362	384	396	419	441	464	487
19	362	384	396	419	441	464	487
20	362	384	396	419	441	464	487
21	362	384	396	418	440	463	485
22	355	377	387	409	431	453	474
23	347	369	378	400	421	443	464
24	339	360	370	390	411	432	453
25	332	352	361	381	401	422	442
26	324	344	352	372	392	412	431
27	316	335	344	363	382	402	421
28	308	327	335	354	372	391	410
29	300	318	326	344	362	381	399
30	292	310	318	335	353	371	388
31	284	302	309	326	343	361	377
32	277	293	300	317	333	350	365
33	269	285	291	307	323	340	354
34	261	277	283	298	314	330	344
35	253	268	274	289	304	320	333
Area, sq in	27.81	29.56	30.45	32.20	33.95	35.70	37.4
$I_{1-1}$ , in <sup>4</sup> .....	878	954	910	986	1 063	1 142	1 2
$r_{1-1}$ , in.....	5.62	5.68	5.47	5.53	5.60	5.66	5.7
$I_{2-2}$ , in <sup>4</sup> .....	501	530	537	565	594	622	6
$r_{2-2}$ , in.....	4.24	4.23	4.20	4.19	4.18	4.18	4.1
Weight, lb per lin ft..	94.6	100.5	103.6	109.5	115.5	121.4	127

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; th below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVI\* (Continued). Safe Loads in Units of 1 000 Pounds for 12-Inch Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 12-in channels, two 14-in plates							
	30-lb channels, 3/4-in plates	30-lb channels, 1 1/16-in plates	30-lb channels, 7/8-in plates	30-lb channels, 1 1/4-in plates	30-lb channels, 1-in plates	35-lb channels, 1 1/16-in plates	35-lb channel, 1-in plates	35-lb channels, 1 1/16-in plates
11	502	525	548	571	593	609	632	654
12	502	525	548	571	593	609	632	654
13	502	525	548	571	593	609	632	654
14	502	525	548	571	593	609	632	654
15	502	525	548	571	593	609	632	654
16	502	525	548	571	593	609	632	654
17	502	525	548	571	593	609	632	654
18	502	525	548	571	593	609	632	654
19	502	525	548	571	593	609	632	654
20	502	525	548	571	593	609	632	654
21	498	521	543	565	588	601	623	645
22	487	509	531	553	575	587	609	631
23	476	497	518	540	561	573	594	616
24	465	486	506	527	548	559	580	601
25	453	474	494	514	535	545	566	586
26	442	462	482	502	522	532	552	571
27	431	451	469	489	508	518	537	557
28	420	439	457	476	495	504	523	542
29	409	427	445	463	482	490	509	527
30	397	415	432	450	468	477	494	512
31	386	404	420	438	455	463	480	497
32	375	392	408	425	442	449	466	483
33	364	380	396	412	428	435	452	468
34	352	368	383	399	415	421	437	453
35	341	357	371	386	402	408	423	438
Area, sq in	38.64	40.39	42.14	43.89	45.64	46.83	48.58	50.33
$I_{xx}$ , in <sup>4</sup> .....	1 174	1 258	1 340	1 424	1 509	1 459	1 544	1 630
$I_{yy}$ , in <sup>4</sup> .....	5.52	5.58	5.64	5.70	5.75	5.58	5.64	5.69
$I_{xx}$ , in <sup>4</sup> .....	659	688	717	745	774	779	808	837
$I_{yy}$ , in <sup>4</sup> .....	4.13	4.13	4.12	4.12	4.12	4.08	4.08	4.08
Weight, per lin ft..	131.4	137.4	143.3	149.3	155.2	159.3	165.2	171.2

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVI\* (Continued). Safe Loads in Units of 1 000 Pounds for 12-in Channel-Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).  
 $S = 19\,000 - 100\,l/r$   
Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490


Effective length, ft	Two 12-in channels, two 14-in plates						
	35-lb channels, 1 1/4-in plates	35-lb channels, 1 3/8-in plates	35-lb channels, 1 1/2-in plates	35-lb channels, 1 5/8-in plates	35-lb channels, 1 3/4-in plates	35-lb channels, 1 7/8-in plates	35-lb channels, 2-in plates
11	677	700	723	745	768	791	814
12	677	700	723	745	768	791	814
13	677	700	723	745	768	791	814
14	677	700	723	745	768	791	814
15	677	700	723	745	768	791	814
16	677	700	723	745	768	791	814
17	677	700	723	745	768	791	814
18	677	700	723	745	768	791	814
19	677	700	723	745	768	791	814
20	677	700	723	745	768	791	814
21	668	689	712	734	757	779	801
22	653	674	695	717	739	761	783
23	637	658	679	700	722	743	765
24	622	642	663	684	704	725	747
25	607	626	646	667	687	707	728
26	591	610	630	650	670	689	709
27	576	594	614	633	652	672	691
28	561	578	597	616	635	654	673
29	545	563	581	599	617	636	654
30	530	547	564	582	600	618	636
31	515	531	548	565	583	600	617
32	499	515	532	548	565	582	599
33	484	499	515	531	548	564	580
34	469	483	499	515	530	546	561
35	453	467	482	498	513	528	543
Area, sq in	52.08	53.83	55.58	57.33	59.08	60.83	62.58
$I_{1-1}$ , in <sup>4</sup> .....	1 719	1 808	1 899	1 992	2 087	2 183	2 280
$r_{1-1}$ , in.....	5.74	5.80	5.85	5.89	5.94	5.99	6.04
$I_{2-2}$ , in <sup>4</sup> .....	865	894	922	951	980	1 008	1 037
$r_{2-2}$ , in.....	4.08	4.07	4.07	4.07	4.07	4.07	4.07
Weight, lb per lin ft..	177.1	183.1	189.0	195.0	200.9	206.9	212.8

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XXVI\* (Continued). Safe Loads in Units of 1 000 Pounds for 12-Inch Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).


$$S = 19\,000 - .100\,l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Two 12-in channels, two 16-in plates									
	30-lb channels, 1 1/2-in plates	30-lb channels, 1-in plates	30-lb channels, 1 1/2-in plates	30-lb channels, 1 1/4-in plates	30-lb channels, 1 3/16-in plates	30-lb channels, 1 1/4-in plates	35-lb channels, 1 1/2-in plates	35-lb channels, 1 1/4-in plates	35-lb channels, 1 1/2-in plates	35-lb channels, 1 3/8-in plates
11	619	645	671	697	723	749	762	788	814	840
12	619	645	671	697	723	749	762	788	814	840
13	619	645	671	697	723	749	762	788	814	840
14	619	645	671	697	723	749	762	788	814	840
15	619	645	671	697	723	749	762	788	814	840
16	619	645	671	697	723	749	762	788	814	840
17	619	645	671	697	723	749	762	788	814	840
18	619	645	671	697	723	749	762	788	814	840
19	619	645	671	697	723	749	762	788	814	840
20	619	645	671	697	723	749	762	788	814	840
21	619	645	671	697	723	749	762	788	814	840
22	619	645	671	697	723	749	762	788	814	840
23	619	645	671	697	723	749	762	788	814	840
24	619	645	671	697	723	749	762	787	813	838
25	610	635	660	686	711	736	747	772	797	822
26	599	623	648	673	697	721	732	756	781	805
27	587	611	635	659	683	707	718	741	766	789
28	575	599	622	646	669	693	703	726	750	773
29	563	586	609	633	655	678	688	711	734	757
30	552	574	596	619	642	664	674	696	719	741
31	540	562	583	606	628	649	659	681	703	724
32	528	549	571	593	614	635	644	665	687	708
33	516	537	558	579	600	621	630	650	672	692
34	504	525	545	566	586	606	615	635	656	676
35	493	512	532	553	572	592	600	620	640	660
Area, sq in	47.64	49.64	51.64	53.64	55.64	57.64	58.58	60.58	62.58	64.58
$I_x$ , in <sup>4</sup> .....	1 581	1 678	1 777	1 878	1 980	2 084	2 015	2 119	2 225	2 333
$I_y$ , in <sup>4</sup> .....	5.76	5.81	5.87	5.92	5.97	6.01	5.87	5.91	5.96	6.01
$I_{xy}$ , in <sup>4</sup> .....	1 121	1 164	1 206	1 249	1 292	1 334	1 349	1 392	1 434	1 477
$I_{xx}$ , in <sup>4</sup> .....	4.85	4.84	4.83	4.83	4.82	4.81	4.80	4.79	4.79	4.78
Weight, lb per lin ft.	162.0	168.8	175.6	182.4	189.2	196.0	199.2	206.0	212.8	210.6

\*The load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

Table XXVI \* (Continued). Safe Loads in Units of 1 000 Pounds for 12-in Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).


$S = 19\,000 - 100\,l/r$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 12-in channels, two 16-in plates									
	35-lb channels, 1 1/16-in plates	35-lb channels, 1 1/4-in plates	35-lb channels, 1 9/16-in plates	35-lb channels, 1 5/8-in plates	35-lb channels, 1 11/16-in plates	35-lb channels, 1 3/4-in plates	35-lb channels, 1 7/8-in plates	35-lb channels, 1 15/16-in plates	35-lb channels, 2-in plates	35-lb channels, 2 1/8-in plates
11	866	892	918	944	970	996	1 022	1 048	1 074	1 100
12	866	892	918	944	970	996	1 022	1 048	1 074	1 100
13	866	892	918	944	970	996	1 022	1 048	1 074	1 100
14	866	892	918	944	970	996	1 022	1 048	1 074	1 100
15	866	892	918	944	970	996	1 022	1 048	1 074	1 100
16	866	892	918	944	970	996	1 022	1 048	1 074	1 100
17	866	892	918	944	970	996	1 022	1 048	1 074	1 100
18	866	892	918	944	970	996	1 022	1 048	1 074	1 100
19	866	892	918	944	970	996	1 022	1 048	1 074	1 100
20	866	892	918	944	970	996	1 022	1 048	1 074	1 100
21	866	892	918	944	970	996	1 022	1 048	1 074	1 100
22	866	892	918	944	970	996	1 022	1 048	1 074	1 100
23	866	892	918	944	970	996	1 022	1 048	1 074	1 100
24	864	889	915	940	966	992	1 017	1 042	1 068	1 093
25	847	872	897	922	947	972	997	1 022	1 047	1 072
26	830	854	879	903	928	953	977	1 002	1 027	1 051
27	814	837	862	885	909	934	957	981	1 006	1 030
28	797	820	844	867	891	914	937	961	985	1 009
29	780	803	826	848	872	895	917	941	964	988
30	764	785	808	830	853	876	897	920	943	966
31	747	768	791	812	834	857	878	900	922	944
32	730	751	773	794	815	837	858	880	901	923
33	713	734	755	775	797	818	838	859	881	902
34	697	716	737	757	778	799	818	839	860	881
35	680	699	720	739	759	779	798	819	839	860
Area, sq in	66.58	68.58	70.58	72.58	74.58	76.58	78.58	80.58	82.58	84.58
I <sub>1-1</sub> , in <sup>4</sup> .....	2 443	2 555	2 668	2 783	2 901	3 020	3 141	3 264	3 389	3 514
r <sub>1-1</sub> , in.....	6.06	6.10	6.15	6.19	6.24	6.28	6.32	6.36	6.41	6.45
I <sub>2-2</sub> , in <sup>4</sup> .....	1 520	1 562	1 605	1 648	1 690	1 733	1 776	1 818	1 861	1 904
r <sub>2-2</sub> , in.....	4.78	4.77	4.77	4.76	4.76	4.76	4.75	4.75	4.75	4.75
Weight, lb per lin ft..	226.4	233.2	240.0	246.8	253.6	260.4	267.2	274.0	280.8	287.6

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table XXVII.\* Safe Loads in Units of 1 000 Pounds for 15-Inch Channel-Columns**

Allowable fiber-stress in pounds per square inch:  
 13 000 for lengths of 60 radii or under  
 Reduced for lengths between 60 and 120 radii, by  
 Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
 For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 15-in channels, latticed				Two 15-in channels, two 16-in plates		
	33.9-lb chan'ls, single lattice	35-lb channels, single lattice	40-lb channels, single lattice	45-lb channels, single lattice	33.9-lb chan'ls, 3/4-in plates	33.9-lb chan'ls, 7/8-in plates	33.9-lb chan'ls, 1 1/2-in plates
11	257	268	306	344	413	439	465
12	257	268	306	344	413	439	465
13	257	268	306	344	413	439	465
14	257	268	306	344	413	439	465
15	257	268	306	344	413	439	465
16	257	268	306	344	413	439	465
17	257	268	306	344	413	439	465
18	257	268	306	344	413	439	465
19	257	268	306	344	413	439	465
20	257	268	306	344	413	439	465
21	257	268	306	344	413	439	465
22	257	268	306	344	413	439	465
23	257	268	306	344	413	439	465
24	257	268	306	343	413	439	465
25	257	266	301	336	407	432	457
26	252	261	295	329	400	424	448
27	247	256	289	322	392	415	440
28	243	251	284	316	384	407	431
29	238	246	278	309	376	399	422
30	233	241	272	302	368	390	413
31	228	236	266	296	360	382	404
32	224	231	260	289	352	373	395
33	219	226	254	282	345	365	386
34	214	221	249	276	337	357	377
35	209	216	243	269	329	348	368
Area, sq in	19.80	20.58	23.52	26.48	31.80	33.80	35.80
4 in.....	625	640	695	750	1 334	1 459	1 586
4 in.....	5.62	5.58	5.43	5.32	6.48	6.57	6.66
4 in.....	491	504	552	597	747	789	832
4 in.....	4.98	4.95	4.84	4.75	4.85	4.83	4.82
Weight, per lin ft.	80.2	84.2	92.1	102.2	106.8	113.6	120.4

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVII\* (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns




Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).  
 $S = 19\,000 - 100\,l/r$   
Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 15-in channels, two 16-in plates						
	33.9-lb chan'ls, 9/16-in plates	33.9-lb chan'ls, 3/8-in plates	35-lb channels, 5/8-in plates	35-lb channels, 1 1/16-in plates	35-lb channels, 3/4-in plates	35-lb channels, 1 3/16-in plates	35-lb channels, 7/8-in plates
11	491	517	528	554	580	606	632
12	491	517	528	554	580	606	632
13	491	517	528	554	580	606	632
14	491	517	528	554	580	606	632
15	491	517	528	554	580	606	632
16	491	517	528	554	580	606	632
17	491	517	528	554	580	606	632
18	491	517	528	554	580	606	632
19	491	517	528	554	580	606	632
20	491	517	528	554	580	606	632
21	491	517	528	554	580	606	632
22	491	517	528	554	580	606	632
23	491	517	528	554	580	606	632
24	491	517	527	552	578	604	629
25	482	507	517	542	567	592	617
26	473	498	507	531	555	580	605
27	464	488	497	520	544	569	594
28	454	478	486	510	533	557	582
29	445	468	476	499	522	545	570
30	435	458	466	488	511	533	558
31	426	448	456	478	499	522	547
32	416	438	446	467	488	510	535
33	407	428	436	456	477	498	523
34	398	418	425	446	466	487	512
35	388	408	415	435	454	475	499
Area, sq in	37.80	39.80	40.58	42.58	44.58	46.58	48.58
$I_{1-1}$ , in <sup>4</sup> .....	1 715	1 847	1 861	1 994	2 129	2 267	2 401
$r_{1-1}$ , in.....	6.74	6.81	6.77	6.84	6.91	6.98	7.05
$I_{2-2}$ , in <sup>4</sup> .....	875	917	930	973	1 016	1 058	1 101
$r_{2-2}$ , in.....	4.81	4.80	4.79	4.78	4.77	4.77	4.76
Weight, lb per lin ft..	127.2	134.0	138.0	144.8	151.6	158.4	165.2

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; the below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVII\* (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490


## Two 15-in channels, two 16-in plates

Effective length, ft	40-lb channels, 1 1/2-in plates	40-lb channels, 1 1/2-in plates	40-lb channels, 1 1/2-in plates	40-lb channels, 1-in plates	40-lb channels, 1 1/2-in plates	40-lb channels, 1 1/2-in plates	45-lb channels, 1 1/2-in plates
11	644	670	696	722	748	774	786
12	644	670	696	722	748	774	786
13	644	670	696	722	748	774	786
14	644	670	696	722	748	774	786
15	644	670	696	722	748	774	786
16	644	670	696	722	748	774	786
17	644	670	696	722	748	774	786
18	644	670	696	722	748	774	786
19	644	670	696	722	748	774	786
20	644	670	696	722	748	774	786
21	644	670	696	722	748	774	786
22	644	670	696	722	748	774	786
23	644	670	696	722	748	774	786
24	639	665	690	715	741	767	777
25	627	651	677	701	727	752	761
26	614	638	663	687	712	737	746
27	602	625	649	673	697	721	730
28	589	612	636	659	683	706	715
29	577	599	622	645	668	691	699
30	564	586	609	631	653	676	684
31	551	573	595	616	639	661	668
32	539	560	581	602	624	646	653
33	526	547	568	588	609	630	637
34	514	534	554	574	595	615	622
35	501	520	541	560	580	600	606
Area, sq in	49.52	51.52	53.52	55.52	57.52	59.52	60.48
$I_x$ , in <sup>4</sup> .....	2 322	2 461	2 602	2 746	2 891	3 039	2 946
$I_y$ , in <sup>4</sup> .....	6.85	6.91	6.97	7.03	7.09	7.15	6.98
$I_{xy}$ , in <sup>4</sup> .....	1 106	1 149	1 192	1 234	1 277	1 320	1 322
$r_x$ , in.....	4.73	4.72	4.72	4.71	4.71	4.71	4.68
Weight, lb per lin ft..	168.4	175.2	182.0	188.8	195.6	202.4	205.6

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVII\*. (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns




Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13),  
 $S = 19\,000 - 100\,l/r$   
Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 15-in channels, two 16-in plates						
	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 3/8-in plates
11	812	838	864	890	916	942	968
12	812	838	864	890	916	942	968
13	812	838	864	890	916	942	968
14	812	838	864	890	916	942	968
15	812	838	864	890	916	942	968
16	812	838	864	890	916	942	968
17	812	838	864	890	916	942	968
18	812	838	864	890	916	942	968
19	812	838	864	890	916	942	968
20	812	838	864	890	916	942	968
21	812	838	864	890	916	942	968
22	812	838	864	890	916	942	968
23	812	838	864	890	916	942	968
24	802	827	853	879	904	930	956
25	786	811	836	861	886	912	937
26	770	794	819	844	868	893	918
27	754	778	802	826	850	874	898
28	738	761	785	808	832	856	879
29	722	745	768	791	814	837	860
30	705	728	751	773	796	818	841
31	689	711	734	756	778	800	822
32	673	695	716	738	760	781	803
33	657	678	699	720	741	763	784
34	641	662	682	703	723	744	764
35	625	645	665	685	705	725	745
Area, sq in	62.48	64.48	66.48	68.48	70.48	72.48	74.4
$I_{1-1}$ , in <sup>4</sup> .....	3 094	3 244	3 396	3 550	3 707	3 865	4 02
$r_{1-1}$ , in.....	7.04	7.09	7.15	7.20	7.25	7.30	7.3
$I_{2-2}$ , in <sup>4</sup> .....	1 365	1 408	1 450	1 493	1 536	1 578	1 62
$r_{2-2}$ , in.....	4.67	4.67	4.67	4.67	4.67	4.67	4.6
Weight, lb per lin ft..	212.4	219.2	226.0	232.8	239.6	246.4	253.

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; the below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table XXVII \* (Continued). Safe Loads in Units of 1 000 Pounds for 15-Inch Channel-Columns**



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

**Two 15-in channels, two 18-in plates**

Effective length, ft.	33.9-lb chan'ls, 5/8-in plates	33.9-lb chan'ls, 7/8-in plates	33.9-lb chan'ls, 1 1/2-in plates	33.9-lb chan'ls, 1 3/4-in plates	33.9-lb chan'ls, 2-in plates	35-lb channels, 5/8-in plates	35-lb channels, 1 1/4-in plates	35-lb channels, 1 3/4-in plates
11	433	462	491	521	550	560	589	619
12	433	462	491	521	550	560	589	619
13	433	462	491	521	550	560	589	619
14	433	462	491	521	550	560	589	619
15	433	462	491	521	550	560	589	619
16	433	462	491	521	550	560	589	619
17	433	462	491	521	550	560	589	619
18	433	462	491	521	550	560	589	619
19	433	462	491	521	550	560	589	619
20	433	462	491	521	550	560	589	619
21	433	462	491	521	550	560	589	619
22	433	462	491	521	550	560	589	619
23	433	462	491	521	550	560	589	619
24	433	462	491	521	550	560	589	619
25	433	462	491	521	550	560	589	619
26	433	462	491	521	550	560	589	619
27	433	462	491	521	550	560	589	619
28	433	462	491	520	549	558	586	615
29	428	456	484	512	539	549	577	605
30	421	449	476	503	530	540	567	594
31	414	441	468	494	521	530	557	584
32	407	433	459	486	512	521	547	574
33	400	426	451	477	503	512	537	563
34	393	418	443	469	494	502	527	553
35	386	411	435	460	485	493	518	543
Area, sq in	33.30	35.55	37.80	40.05	42.30	43.08	45.33	47.58
$I_{x-x}$ , in <sup>4</sup> .....	1 423	1 564	1 707	1 852	1 999	2 014	2 164	2 316
$r_{x-x}$ , in.....	6.54	6.63	6.72	6.80	6.87	6.84	6.91	6.98
$I_{y-y}$ , in <sup>4</sup> .....	1 069	1 130	1 190	1 251	1 312	1 332	1 393	1 453
$r_{y-y}$ , in.....	5.67	5.64	5.61	5.59	5.57	5.56	5.54	5.53
Weight, lb per lin ft..	111.9	119.6	127.2	134.9	142.5	146.5	154.2	161.8

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVII\* (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns


Effective length, ft	Two 15-in channels, two 18-in plates							
	35-lb channels, 1 1/4-in plates	35-lb channels, 3/4-in plates	40-lb channels, 1 3/8-in plates	40-lb channels, 3/4-in plates	40-lb channels, 1 1/4-in plates	40-lb channels, 1-in plates	40-lb channels, 1 1/8-in plates	40-lb channels, 1 1/4-in plates
11	648	677	686	715	745	774	803	83
12	648	677	686	715	745	774	803	83
13	648	677	686	715	745	774	803	83
14	648	677	686	715	745	774	803	83
15	648	677	686	715	745	774	803	83
16	648	677	686	715	745	774	803	83
17	648	677	686	715	745	774	803	83
18	648	677	686	715	745	774	803	83
19	648	677	686	715	745	774	803	83
20	648	677	686	715	745	774	803	83
21	648	677	686	715	745	774	803	83
22	648	677	686	715	745	774	803	83
23	648	677	686	715	745	774	803	83
24	648	677	686	715	745	774	803	83
25	648	677	686	715	745	774	803	83
26	648	677	686	715	745	774	803	83
27	648	677	686	715	745	774	803	83
28	643	671	680	708	736	764	793	82
29	632	660	668	696	723	751	779	80
30	621	649	657	684	711	738	766	79
31	610	637	645	673	698	725	752	77
32	599	626	634	662	685	712	738	76
33	589	615	622	648	673	698	725	75
34	578	603	610	636	660	685	711	73
35	567	592	599	624	648	672	698	72
Area, sq in	49.83	52.08	52.77	55.02	57.27	59.52	61.77	64.
$I_{1-1}$ , in <sup>4</sup> .....	2 470	2 627	2 525	2 682	2 841	3 002	3 166	3 3
$r_{1-1}$ , in.....	7.04	7.10	6.92	6.98	7.04	7.10	7.16	7.
$I_{2-2}$ , in <sup>4</sup> .....	1 514	1 575	1 589	1 649	1 710	1 771	1 832	1 8
$r_{2-2}$ , in.....	5.51	5.50	5.49	5.48	5.46	5.45	5.45	5.
Weight, lb per lin ft.	169.5	177.1	179.5	187.1	194.8	202.4	210.1	217

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; the below the heavy line are for ratios not over 120  $l/r$ .

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XXVII\* (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns



Allowable fiber-stress in pounds per square inch:  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100\,l/r$$


Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft.	Two 15-in channels, two 18-in plates						
	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 1/8-in plates
11	841	871	900	929	958	988	1 017
12	841	871	900	929	958	988	1 017
13	841	871	900	929	958	988	1 017
14	841	871	900	929	958	988	1 017
15	841	871	900	929	958	988	1 017
16	841	871	900	929	958	988	1 017
17	841	871	900	929	958	988	1 017
18	841	871	900	929	958	988	1 017
19	841	871	900	929	958	988	1 017
20	841	871	900	929	958	988	1 017
21	841	871	900	929	958	988	1 017
22	841	871	900	929	958	988	1 017
23	841	871	900	929	958	988	1 017
24	841	871	900	929	958	988	1 017
25	841	871	900	929	958	988	1 017
26	841	871	900	929	958	988	1 017
27	841	871	900	929	958	987	1 015
28	829	857	885	913	942	970	998
29	814	843	870	897	926	953	980
30	800	828	855	882	909	936	963
31	786	813	839	866	893	919	945
32	771	798	824	850	877	902	928
33	757	783	809	834	860	885	911
34	743	768	793	818	844	868	893
35	728	754	778	802	827	852	876
Area, sq in	64.73	66.98	69.23	71.48	73.73	75.98	78.23
$I_{x-x}$ , in <sup>4</sup> .....	3 221	3 387	3 556	3 727	3 900	4 076	4 255
$r_{x-x}$ , in.....	7.05	7.11	7.17	7.22	7.27	7.32	7.37
$I_{y-y}$ , in <sup>4</sup> .....	1 903	1 964	2 025	2 086	2 146	2 207	2 268
$r_{y-y}$ , in.....	5.42	5.42	5.41	5.40	5.40	5.39	5.38
Weight, lb per lin ft...	220.1	227.7	235.4	243.0	250.0	258.3	266.0

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; those below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XXVII\* (Continued). Safe Loads in Units of 1 000 Pounds for 15-in Channel-Columns



Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under  
Reduced for lengths between 60 and 120 radii,  
Formula (13),

$$S = 19\,000 - 100\,l/r$$

Weights do not include rivet-heads or other details  
For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 15-in channels, two 18-in plates						
	45-lb channels, 1 1/4-in plates	45-lb channels, 1 1/8-in plates	45-lb channels, 1 3/8-in plates	45-lb channels, 1 1/2-in plates	45-lb channels, 1 3/4-in plates	45-lb channels, 1 7/8-in plates	45-lb channels, 2-in plates
11	I 046	I 075	I 105	I 134	I 163	I 222	I 281
12	I 046	I 075	I 105	I 134	I 163	I 222	I 281
13	I 046	I 075	I 105	I 134	I 163	I 222	I 281
14	I 046	I 075	I 105	I 134	I 163	I 222	I 281
15	I 046	I 075	I 105	I 134	I 163	I 222	I 281
16	I 046	I 075	I 105	I 134	I 163	I 222	I 281
17	I 046	I 075	I 105	I 134	I 163	I 222	I 281
18	I 046	I 075	I 105	I 134	I 163	I 222	I 281
19	I 046	I 075	I 105	I 134	I 163	I 222	I 281
20	I 046	I 075	I 105	I 134	I 163	I 222	I 281
21	I 046	I 075	I 105	I 134	I 163	I 222	I 281
22	I 046	I 075	I 105	I 134	I 163	I 222	I 281
23	I 046	I 075	I 105	I 134	I 163	I 222	I 281
24	I 046	I 075	I 105	I 134	I 163	I 222	I 281
25	I 046	I 075	I 105	I 134	I 163	I 222	I 281
26	I 046	I 075	I 105	I 134	I 163	I 222	I 281
27	I 044	I 073	I 102	I 131	I 159	I 216	I 271
28	I 026	I 054	I 083	I 112	I 139	I 195	I 251
29	I 009	I 036	I 064	I 092	I 119	I 174	I 231
30	991	I 017	I 045	I 073	I 099	I 153	I 201
31	973	999	I 026	I 053	I 079	I 132	I 181
32	955	980	I 007	I 034	I 059	I 111	I 161
33	937	962	988	I 014	I 039	I 090	I 141
34	919	943	969	995	I 019	I 069	I 121
35	901	925	950	975	999	I 048	I 091
Area, sq in	80.48	82.73	84.98	87.23	89.48	93.98	98.48
$I_{1-1}$ , in <sup>4</sup> .....	4 436	4 619	4 805	4 994	5 185	5 575	5 971
$I_{2-2}$ , in <sup>4</sup> .....	7.42	7.47	7.52	7.57	7.61	7.70	7.79
$I_{3-3}$ , in <sup>4</sup> .....	2 329	2 389	2 450	2 511	2 572	2 693	2 814
$I_{4-4}$ , in <sup>4</sup> .....	5.38	5.37	5.37	5.37	5.36	5.35	5.34
Weight, lb per lin ft..	273.6	281.3	288.9	296.6	304.2	319.5	334.1

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; the values below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table XXVII\* (Concluded). Safe Loads in Units of 1 000 Pounds for 15-lb Channel-Columns

Allowable fiber-stress in pounds per square inch  
13 000 for lengths of 60 radii or under

Reduced for lengths between 60 and 120 radii, by  
Formula (13).

$$S = 19\,000 - 100l/r$$

Weights do not include rivet-heads or other details

For values for  $l/r$  above 120, see notes on page 490

Effective length, ft	Two 15-in. 45-lb channels					
	2 flange-plates 20" X 3/4" 2 web-plates 1 1/2" X 3/4"	2 flange-plates 20" X 2 1/2" 2 web-plates 1 1/2" X 3/4"	2 flange-plates 20" X 3/4" 2 web-plates 1 1/2" X 3/4"	2 flange-plates 20" X 2 1/2" 2 web-plates 1 1/2" X 3/4"	2 flange-plates 18" X 3/4" 2 web-plates 1 1/2" X 3/4"	2 flange-plates 20" X 3/4" 2 web-plates 1 1/2" X 3/4"
11	1 807	1 872	1 937	2 002	2 067	2 132
12	1 807	1 872	1 937	2 002	2 067	2 132
13	1 807	1 872	1 937	2 002	2 067	2 132
14	1 807	1 872	1 937	2 002	2 067	2 132
15	1 807	1 872	1 937	2 002	2 067	2 132
16	1 807	1 872	1 937	2 002	2 067	2 132
17	1 807	1 872	1 937	2 002	2 067	2 132
18	1 807	1 872	1 937	2 002	2 067	2 132
19	1 807	1 872	1 937	2 002	2 067	2 132
20	1 807	1 872	1 937	2 002	2 067	2 132
21	1 807	1 872	1 937	2 002	2 067	2 132
22	1 807	1 872	1 937	2 002	2 067	2 132
23	1 807	1 872	1 937	2 002	2 067	2 132
24	1 807	1 872	1 937	2 002	2 067	2 132
25	1 807	1 872	1 937	2 002	2 067	2 132
26	1 807	1 872	1 937	2 002	2 067	2 132
27	1 807	1 872	1 937	2 002	2 067	2 132
28	1 807	1 872	1 937	2 002	2 067	2 132
29	1 807	1 872	1 937	2 002	2 067	2 132
30	1 798	1 863	1 928	1 991	2 054	2 118
31	1 770	1 834	1 896	1 960	2 022	2 085
32	1 742	1 805	1 866	1 929	1 989	2 052
33	1 714	1 776	1 836	1 897	1 957	2 019
34	1 686	1 747	1 806	1 866	1 925	1 985
35	1 658	1 718	1 775	1 835	1 893	1 952
Area, sq in	138.98	143.98	148.98	153.98	158.98	163.9
$I_{x-x}$ , in <sup>4</sup> .....	8 251	8 744	9 251	9 770	10 301	10 84
$r_{x-x}$ , in.....	7.70	7.79	7.88	7.97	8.05	8.1
$I_{y-y}$ , in <sup>4</sup> .....	4 907	5 073	5 240	5 407	5 573	5 74
$r_{y-y}$ , in.....	5.94	5.94	5.93	5.93	5.92	5.9
Weight, lb per lin ft..	472.5	489.5	506.5	523.5	540.5	557.

Safe load-values above the heavy line are for ratios of  $l/r$  not over 60; the  
below the heavy line are for ratios not over 120  $l/r$

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

## CHAPTER XV

## STRENGTH OF BEAMS AND BEAM GIRDERS. FRAMING AND CONNECTING STEEL BEAMS

By

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. General Principles of the Flexure of Beams

**Definitions.** A structural member placed in a generally horizontal position for two or more supports or projecting from some other construction is called a **BEAM**. A **GIRDER** is a beam carrying smaller or secondary beams. A **CANTILEVER BEAM** is a beam supported at the middle, or having one end fixed, as in a wall, and the other end free; or it is the part of a beam which overhangs, or projects, beyond a support. A **SIMPLE BEAM** is one which rests upon two supports, one at each end. A **CONTINUOUS BEAM** rests upon more than two supports. The distance between the supports of a simple beam, or, when so specially designated from center to center of the bearings, is the **SPAN**. It is usually designated by  $l$ . The loads on beams are either **UNIFORMLY DISTRIBUTED** or **CONCENTRATED**. A uniformly distributed or **UNIFORM** load includes the weight of the beam itself and any load spread evenly over it, such as the weight of a wall. Uniform loads are estimated by their intensity per unit of length of the beam, in pounds per linear foot. A uniform load per linear foot is represented by  $w$ , and the total uniform load by  $wl$  or  $W$ . A concentrated load is a single applied weight, such as a column and its load, or the load from another beam, and is designated by  $P$ .

**Stresses and Deformations.** A load on a simple beam causes the fibers to bend or deflect, and eventually to break across, or in other words, a load induces **TRANSVERSE** or **FLEXURAL STRESSES** in the fibers. Since it is impossible to bend or deflect a simple beam without causing a shortening of the fibers on the upper or concave side and an elongation of the fibers on the lower or convex side, a load on a beam causes **COMPRESSION** in the upper fibers and **TENSION** in the lower fibers, while between the two there is a neutral layer or surface of fibers which is unchanged in length and which is called the **NEUTRAL SURFACE** of the beam. In a cantilever beam the reverse is the case, the upper fibers being in tension and the lower ones in compression.

**Laws Determined by Experiment.** From experiments it has been found that the amount of elongation or shortening of any fiber is directly proportional to its distance from the neutral surface of a beam; hence, if the **ELASTIC LIMIT** is not exceeded, the stresses, also, are proportional to their distances from the neutral surface. The trace of the neutral surface on a cross-section of a beam is called the **NEUTRAL AXIS** of the cross-section. Within the elastic limit of a material the neutral surface passes through the **CENTERS OF GRAVITY** of the cross-sections of a beam for all materials.

**Bending Moments and Resisting Moments.\*** To determine the strength of any beam to resist the effects of any load or series of loads, two things must

\* See, also, Chapter IX, pages 324 to 331.

be determined: first, the moment or moments of the external destructive forces or forces tending to bend and break the beam, which is called the **MAXIMUM BENDING MOMENT**; and, secondly, the moments of the combined resistance of all the fibers in the **DANGEROUS SECTION** of the beam to being broken, which, in their summation, are called the **MOMENT OF RESISTANCE** or the **RESISTING MOMENT**.

**The Methods of Finding the Bending Moments** for any load or series of loads are explained in Chapter IX. The moment of resistance is equal to the **SECTION-MODULUS** or **SECTION-FACTOR**, denoted by  $I/c$ , multiplied by the unit stress on the outermost fiber of the material, denoted by  $S$ , and it equals the bending moment.

Hence

$$M = SI/c$$

This is known as the **FLEXURE-FORMULA** and it is the fundamental formula for designing beams. Formulas for finding the section-moduli of common shapes are given in Chapter X, and the values of  $I/c$  or the section-moduli of standard rolled shapes, are given in the tables in the same chapter.

**The Coefficient of Strength**,\* sometimes given in tables of steel beams, is the maximum distributed load that a beam of one foot span would support without producing a fiber-stress exceeding the safe limit, generally 16 000 lb per sq in. As the strength of a beam varies inversely as its span, the safe load for any span may be obtained by dividing this coefficient by the span in feet.

**Factors of Safety.** In order that a beam shall just be able to carry a given load and not break, that condition of equilibrium must exist, in which the maximum bending moment in the beam is equal to the section-modulus multiplied by the ultimate strength of the material. In order that a beam may be abundantly **SAFE** to carry a given load, the product of the section-modulus and the ultimate strength of the material must be several times greater than the maximum bending moment; and the ratio which this product bears to the maximum bending moment, or which the **BREAKING-LOAD** bears to the **SAFE LOAD**, is known as the **FACTOR OF SAFETY**, that is,

$$\text{Factor of safety} = \frac{\text{ultimate strength}}{\text{working stress}}$$

**Ultimate Strengths and Safe Fiber-Stresses.** By the **STRENGTH OF MATERIAL** is meant a certain constant quantity which is determined by experiment, and which is known as the **ULTIMATE BREAKING STRENGTH**. This value is of course different for each material. Table I gives the values of the ultimate strength divided by the factor of safety, or in other words, the **WORKING STRESS** for most of the materials used in building-construction. The section-modulus multiplied by these values will give the **SAFE RESISTING MOMENTS** for the beams. The values of  $S$  in Table I for steel are about one-fourth those of the breaking loads; for cast iron, about one-sixth; for average specimens of wood, one-eighth; and for stone and concrete, one-tenth. The safe compressive strength of iron for the compression-side of beams is 16 000 lb per sq in, in the New Building Code. This is considered too high by some engineers and the American Institute of Steel Construction recommends 10 000 lb per sq in. This value has been used in calculating safe loads for cast-iron columns. (See Chapter XIV, page 461.) The safe loads for the steel shapes given in the tables in this chapter are all computed

\* The values for coefficients of strength have been omitted from most of the tables following the policy of some of the latest handbooks, as the safe loads for beams, for example, can be as readily determined from the data of the tables directly, as by the process of dividing such coefficients by the spans. See, however, pages 586 to 596 and 623 to 628.

the value of 16 000 lb per sq in for *S*, but these full loads should be used with caution, and reduced when necessary to satisfy any unusual conditions. For riveted steel girders 14 000 lb per sq in was the value formerly given to *S*, but the usual value now is 16 000 lb per sq in.

Table I. Safe Unit Fiber-Stresses, *S*, for Flexure of Beams \*

It is to be noted that these are average values, especially those for wood. For allowable higher stresses for timber, see also, notes on pages 628, 637 and 647.

Materials	Values of <i>S</i> , lb per sq in	Materials	Values of <i>S</i> , lb per sq in
Wood unseasoned †		Wood unseasoned †	
Cast iron, tension-side.....	3 000	Redwood, California.....	750
Cast iron, compression-side.....	16 000	Short-leaf yellow pine.....	1 000
Wrought iron (rolled beams).....	12 000	Spruce.....	700
Steel (rolled beams).....	16 000	White oak.....	1 200
Steel (riveted girders) both flanges.....	16 000	White pine.....	700
Steel (pins, rivets and bolts).....	24 000	Bluestone flagging (North River).....	305
Aluminum.....	700	Brick (common).....	50
Cast nut.....	800	Brickwork (in cement)....	30
Aluminum.....	800	Granite (average).....	180
Douglas fir.....	1 000	Limestone (average).....	145
.....	900	Marble (average).....	125
Wallock.....	600	Sandstone (average).....	110
.....	1 200	Slate (average).....	400
Short-leaf yellow pine.....	1 200	Concrete (Portland) 1 : 2 : 4.....	30
Gray pine.....	800	Concrete (Portland) 1 : 2 : 5.....	20
		Concrete (natural) 1 : 2 : 4... ..	16
		Concrete (natural) 1 : 2 : 5... ..	10

For a comparison of values given in different building laws see Table XVII, page 648, Chapter XVI. Compare, also, with Table XVI, page 647, Chapter XVI. For ultimate stresses for woods, see Tables XVIII and XIX, pages 650 and 651, Chapter XVI. For loads for unit beams, see Tables II and III, page 628, Chapter XVI.

Add from 30 to 40% for seasoned, protected timber, used without impact.

**Beams Unsymmetrically Loaded or of Irregular Cross-Section.** There are certain loadings and cross-sections of beams that occur most frequently in building construction, and for which tables have been worked out that give the loads directly; but for a beam unsymmetrically loaded, or for a beam of irregular cross-section, it is impossible to compute tables for strength, as in each case the values must be computed by determining either the section-modulus, required to resist the maximum bending moment, or the maximum bending moment that may be allowed for a given value of the section-modulus.

**General Formulas for the Flexure of Beams.\*** The general formula for a beam in a state of flexure under any system of loading is

Maximum bending moment in INCH-POUNDS = section-modulus × *S* (2)

$M_{max} = SI/c$  (2)'

Section-modulus =  $\frac{\text{maximum bending moment in in-lb}}{S}$  (3)

$I/c = M_{max}/S$  (3)'

\* See, also, Chapters IX, X and XVI.

If the bending moment is computed in foot-pounds, these formulas become

$$\text{Maximum bending moment} = \frac{\text{section-modulus} \times S}{12}$$

or

$$M_{\max} = SI/12c$$

and

$$\text{Section-modulus} = \frac{12 \times \text{maximum bending moment}}{S}$$

or

$$I/c = 12 M_{\max}/S$$

By substituting for the bending moments their values in terms of the load and the spans, the following formulas which apply to beams of any cross-section are readily deduced.

## 2. Formulas for Safe Loads for Beams for Different Conditions of Loading and Support

$I/c$  = the section-modulus,

$S$  = the safe unit fiber-stress in pounds per square inch;

$W$  = the total uniform load in pounds;

$P$  = the concentrated load in pounds;

$l$  = the span in feet.

Values of  $I/c$  for the various shapes and sizes of structural-steel shapes given in the tables of Chapter X.

### Case I

**Beam Fixed at One End and Loaded with a Concentrated Load  $P$ , Near the Other End (Fig. 1).**

From Formula (4)',

$$M_{\max} = SI/12c$$

From Case I, Chapter IX,

$$M_{\max} = Pl$$

Hence

$$Pl = SI/12c$$

and the safe load in pounds is

$$P = SI/12cl$$

**Fig. 1. Cantilever Beam. Load  $P$  and the section-modulus is near Free End**

$$I/c = 12 Pl/S$$

**Example 1.** A steel T bar is fixed at one end in a brick wall, and loaded at the other end with 600 lb, the distance  $l$  being 4 ft. What is the size of the T bar required to support the load with safety? (In all examples the weights of beams are neglected, unless particularly mentioned.)

**Solution.** Allowing 16 000 lb per sq in for the value of  $S$ , Formula (6)',

$$I/c = (12 \times 600 \times 4)/16\,000 = 1.8$$

The next step is to ascertain what T bar has a section-modulus equal to 1.8. In Table XIV, page 369, the nearest section-modulus to this is 1.9, corresponding to a 3 by 4 by  $\frac{1}{4}$ -in T bar.

For an I beam, by Table IV, page 355,  $I/c = 1.8$ , the same as for the T bar, and calls for a 3-in 6.5-lb I beam.



## Case II

Beam Fixed at One End and Loaded with a Uniformly Distributed Load  $W$  (Fig. 1).

From Formula (4)'

$$M_{\max} = SI/12c$$

In Case II, Chapter IX,

$$M_{\max} = Wl/2$$

Hence

$$Wl/2 = SI/12c$$

and the safe load in pounds is

$$W = SI/6cl \quad (7)$$

or

$$I/c = 6Wl/S \quad (7)' \quad \text{Fig. 2. Cantilever Beam. Distributed Load over Entire Span}$$

Example 2. What is the size of a cantilever steel I beam required to carry a uniformly distributed load of 150 lb per ft over a length of 6 ft?

Solution.  $W = 150 \times 6 = 900$  lb. Substituting in Formula (7)',

$$I/c = \frac{6 \times 900 \times 6}{16,000} = 2.025$$

In Table IV, page 355, the nearest section-modulus to this is 1.9, which is that of a 3-in 7.5-lb beam, the heaviest of that depth. However, as the next 4-in beam, also, weighs 7.5 lb per ft it probably would be selected because of its greater stiffness, although its section-modulus is 3, still greater than required.

## Case III

Beam Supported at Both Ends and Loaded with a Concentrated Load at the Middle (Fig. 3).




Fig. 3. Simple Beam. Load at Middle of Span

From Formula (4)'

$$M_{\max} = SI/12c$$

From Case IV, Chapter IX,

$$M_{\max} = Pl/4$$

Hence

$$Pl/4 = SI/12c$$

and the safe load in pounds is

$$P = SI/3cl \quad (8)$$

and

$$I/c = 3Pl/S \quad (8)'$$

Example 3. What steel I beam will safely support a concentrated load of 7 tons applied at the middle of a 15-ft span?

Solution.  $P = 7$  tons = 14,000 lb. Substituting in Formula (8)',

$$I/c = \frac{3 \times 14,000 \times 15}{16,000} = 39.3$$

Turning again to Table IV, page 355, it is seen that a 12-in 35-lb beam has

a section-modulus of 37.8, while a 12-in 40.8-lb beam, the next larger, has a section-modulus of 44.8. The 35-lb beam, however, would undoubtedly be safe.

### Case IV

**Beam Supported at Both Ends and Loaded with a Uniformly Distributed (Fig. 4).**




Fig. 4. Simple Beam. Distributed Load over Entire Span

From Formula (4)'

$$M_{\max} = SI/12c$$

From Case V, Chapter IX,

$$M_{\max} = Wl/8$$

Hence

$$Wl/8 = SI/12c$$

and the safe load in pounds is

$$W = 2SI/3cl$$

and

$$I/c = 3Wl/2S$$

**Example 4.** What steel I beam will safely carry a uniformly distributed load of 1 000 lb per ft over a span of 25 ft?

**Solution.**  $W = wl = 1\,000 \times 25 = 25\,000$  lb. Substituting in Formula

$$I/c = \frac{3 \times 25\,000 \times 25}{2 \times 16\,000} = 58.6$$

From Table IV, page 354, the nearest section-modulus is 58.9, which is that of a 15-in 42.9-lb beam.

### Case V

**Beam Supported at Both Ends and Loaded with a Distributed Load Over Part of the Span (Fig. 5).**




Fig. 5. Simple Beam. Distributed Load over Part of Span

In this case the load is generally given, and the problem is to determine the size of the required beam. This can be done accurately only by com

the maximum bending moment as explained for Case VIII, Chapter IX, and substituting the value thus found in Formulas (3)' or (5)'.

**Example 5.** What steel I beam will safely carry a uniformly distributed load of 1 200 lb per ft over part of the span, beginning at a point 5 ft from the left reaction and extending over a distance of 6 ft, the span of the beam being 18 ft?

**Solution.** The first step is to find the point of maximum bending moment, which is the point of no shear. Obviously the maximum shear is just at the right of the reaction nearest the load, which in this case is the left reaction. To find the left reaction (see Chapter IX, page 324) the center of moments is taken at the right reaction and the equation of moments is  $R_1 \times 18 \text{ ft} - (1\,200 \text{ lb} \times 6 \text{ ft}) \times 10 \text{ ft} = 0$ .  $18 R_1 = 72\,000$  and  $R_1 = 4\,000 \text{ lb}$ . The shear just to the right of  $R_1$  is therefore +4 000 lb which, if the weight of the beam itself is not considered, remains unchanged for every section of the beam between the left reaction and the uniformly distributed load of 1 200 lb per ft. From there on in passing to the right, the shear is diminished at the rate of 1 200 lb per ft; and it becomes zero, therefore, at a point  $4\,000 \text{ lb} / 1\,200 \text{ lb per ft} = 3.3 \text{ ft}$  to the right of the 5-ft point. Hence the point of no shear and consequently the point of maximum bending moment is at  $5 \text{ ft} + 3.3 \text{ ft}$ , or 8.3 ft, from the left end. The equation for the maximum bending moment at this point is, therefore,

$$\begin{aligned} M_{\max} &= 4\,000 \text{ lb} \times 8.3 \text{ ft} - (1\,200 \text{ lb} \times 3.3 \text{ ft}) \times 3.3/2 \text{ ft} \\ &= 33\,200 \text{ ft-lb} - 6\,534 \text{ ft-lb} = 26\,666 \text{ ft-lb, or } 319\,992 \text{ in-lb} \end{aligned}$$

From Formula (3),  $I/c = 319\,992 \text{ in-lb} / 16\,000 \text{ lb per sq in} = 20$ . From Table 7, page 355, the nearest section-modulus corresponding to this is 20.3, that of a 10-in 25-lb beam. A 10-in 25.4-lb beam, however, being stronger and stiffer, will probably be used. The 10-in 22.24-lb beam is what is termed a **SUPPLEMENTARY BEAM**. (See Case VIII, Chapter IX, and pages 352 and 353.)

### Case VI

**Beam Supported at Both Ends and Loaded with a Concentrated Load, not at the Middle (Fig. 6).**

**Fig. 6. Simple Beam. Concentrated Load at any Point**

From Formula (4)',

$$M_{\max} = Sl/12c$$

In Case VI, Chapter IX,

$$M_{\max} = Pmn/l$$

we

$$Pmn/l = Sl/12c$$

The safe load in pounds is

$$P = Sl/12cmn \quad (10)$$

$$I/c = 12Pmn/Sl \quad (10)'$$

and  $l$  being in feet.

**Example 6.** A steel I beam 20 ft in span is to support a concentrated load of 24 000 lb at a distance of 6 ft from the left support. What must be the weight of the beam?

**Solution.** In this case  $P = 24\,000$  lb,  $l = 20$  ft,  $m = 6$  ft,  $n = 14$  ft and 16 000 lb per sq in.

Then Formula (10)' gives

$$I/c = \frac{12 \times 24\,000 \times 6 \times 14}{20 \times 16\,000} = 75.6$$

Table IV, page 354, the nearest value for the section-modulus  $I/c$  for 1-1 is above 75.6, or 81.2 for a 15-in 60.8-lb beam. An 18-in 55-lb beam has a section-modulus of 88.4 would be used, unless conditions fix the head-rail as it weighs 5 lb per ft less, and being deeper is consequently stiffer.

### Case VII

**Beam Supported at Both Ends and Loaded Symmetrically with Two Equal Concentrated Loads (Fig. 7).**




Fig. 7. Simple Beam. Equal Concentrated Loads Symmetrically Placed

From Formula (4)' and Case VII, Chapter IX, each of the safe loads in pounds is

$$P = SI/12cm$$

and

$$I/c = 12Pm/S$$

**Example 7.** A 12-in steel channel, 12 ft in span, supports half the load of two 10-in beams 4 ft from each end. Each beam is designed to carry 16 000 lb. What is the size and the weight of the channel required?

**Solution.** The channel supports only one-half the load on each beam;  $P = 8\,000$  lb,  $m = 4$  ft,  $S = 16\,000$  lb per sq in, and by Formula (11)',

$$I/c = \frac{12 \times 8\,000 \times 4}{16\,000} = 24,$$

which is the section-modulus of a 12-in 25-lb channel. (See Table on page 359.) Exact table-value, 23.9.

**Weights of Beams in Flexure-Formulas.** It will be noticed that in Formulas (11) and (11)' the span of the beam is not taken into account, and if the beam itself had no weight there would be no difference in the fiber-stress no matter how far apart the loads  $P$  were placed. In reality, however, beams have considerable weight, and to be absolutely correct an example such as the one above should include the weight of the beam, which would, of course, be a uniformly distributed load. The maximum bending moment of the beam can be found graphically as explained on page 329, and the value of  $I/c$  computed by Formulas (3)' or (5)'. Where, however, the loads are spaced to divide the beam into three equal parts, as in the last example, one-third the weight of the beam may be added to  $P$  with sufficient accuracy. Thus


light of the channel in the above example between the supports would be  $100 \text{ lb} \times 12$ , or 300 lb, and  $P$  would be 8 100 lb, which would give a value for  $s$  of 24.1. The factor of safety in the loads allowed is generally large enough to offset the slight effect produced by the weight of the beam; but if the full load assumed is likely to be imposed on the beam, then allowance must be made for the weight of the beam itself.

### Case VIII

**Beam Supported at Both Ends and Loaded Symmetrically with Several Concentrated Loads (Fig. 8).**

In this case it is necessary to compute the maximum bending moment in the beam and proportion the beam by Formulas (3)' or (5)'.

**Example 8.** A steel-beam girder is to be designed to support a brick wall, 22 ft thick and weighing 138 000 lb, over an opening 22 ft wide. The girder must also support the ends of four 10-in floor-beams spaced as in Fig. 8, each beam carrying 16 000 lb. What is the size and weight of the girder required?



**Solution.** The first step is to make an allowance for the weight of the girder.

The total load on the girder (neglecting the weight of the girder itself) = 138 000 lb +  $4 \times 8 000$  lb (one-half the load on each beam) = 170 000 lb, or 85 tons. This is much more than the heaviest single rolled beam will carry, it will be necessary to use a pair of beams and the load on each beam, therefore, will be 42.5 tons. Considering for the present the entire load as uniformly distributed, Table IV, page 577, shows that to support 42.5 tons, or 85 000 lb, over a span of 22 ft requires a 24-in 85-lb beam. The girder then will weigh between supports  $1 \times 85 \times 22 = 3 740$  lb, or about 4 000 lb. This added to the weight of the wall makes, for the total distributed load, 142 000 lb. The next step is to determine the maximum bending moment.

By the formulas given in Chapter IX the maximum bending moments for the various loads may be found as follows:

for the wall and girder (Case V, page 326),

$$M_{\max} = \frac{22 \times 142 000}{8} = 390 500 \text{ ft-lb}$$

for the beam  $B_1$  (Case VI, page 327),

$$M_{1 \max} = \frac{8 000 \times 3 \frac{1}{4} \times 18 \frac{1}{4}}{22} = 23 545 \text{ ft-lb}$$

for the beam  $B_2$  (Case VI, page 327),

$$M_{2 \max} = \frac{8 000 \times 8 \frac{1}{2} \times 13 \frac{1}{2}}{22} = 41 727 \text{ ft-lb}$$

As the beams being spaced symmetrically from the middle of the span, the bending moments for  $B_3$  and  $B_4$  will be equal to those of  $B_2$  and  $B_1$  respectively. Putting the bending moments to a scale, in the manner explained for Figs. 17 and 18 on page 330, the diagram shown in Fig. 9 is obtained. The greatest bending moment is the ordinate  $M_{\max}$ , which scales 486 500 ft-lb, or 5 838 000 in-lb.

**Note.** Since the loads are symmetrically placed, this ordinate is over the middle point of the girder, but it is drawn to one side in the figure in order to confuse it with the ordinate  $M$ , the maximum bending moment for the uniformly distributed load. Substituting this value of  $M_2$  in formula (3)',

$$I/c = \frac{5\,838\,000 \text{ in-lb}}{16\,000 \text{ lb per sq in}} = 365$$

the section-modulus for both beams, or 182.5 for one beam. From Table on page 354, it is found that a 24-in 90-lb beam has a section-modulus of 182.5

and two 90-lb beams will just answer. The assumption of a uniform distribution of such a loading over every foot of girder usually results in the selection of lighter beams than are indicated by the second solution, in which each concentrated load is considered as really concentrated at a point. The two beams should be securely bolted together with separators near each connection of beams  $B_1, B_2, B_3, B_4$ , and at each end of the girder.

A DOUBLE-BEAM GIRDER, however, is not considered the best kind of girder to use under this condition of loading, as it is not good construction nor economical material. As a general rule BEAM GIRDERS should be used only when the load can be applied to the upper flange of both beams. Transferring a load directly to the web of one beam, even though it is connected with the other beam by means of separators, does not insure




Fig. 9. Bending-moment Diagram for Beam Shown in Fig. 8.

equal distribution of the loading. The author, therefore, recommends in this case a RIVETED BEAM GIRDER or a RIVETED PLATE GIRDER. The method as indicated applies to any method of loading, the only difference in the calculation being in the determination of the maximum bending moments.

**Inclined Beams.** The strength of beams inclined to the horizontal may be computed, with sufficient accuracy for most purposes, by using the formulas given for horizontal beams, and taking the HORIZONTAL PROJECTIONS of the beams as the spans.

### 3. Steel Beams and Girders \*

**Materials Used for Beams.** Practically the only materials used in structural work for beams, at the present day, are wood, steel and reinforced concrete. As wooden beams are always rectangular in cross-section, the general formulas used in this chapter can be much simplified by substituting for  $I/c$  its value in terms of the breadth and depth of the beam. Formulas for wooden beams may therefore be found in Chapter XVI. Cast iron, also, is occasionally used for beams or lintels, but as this material is much stronger in resisting compression than tension, the beam must be of a special shape in order to use the material to advantage. The strength of cast-iron beams is therefore considered in

\* For the deflection of steel beams, see Chapter XVIII.

special heading in Chapter XVI. Formulas for reinforced-concrete beams are given in Chapter XXIV, pages 924 to 939; and Chapter XXV, page 992.

**Forms of Steel Beams.** Since 1893, steel beams have superseded wrought-iron beams, and the latter are now never used. Any shape of rolled steel may be used as a beam, but the I shape is the most economical, as it possesses the greatest resistance for a given weight of metal. Next to the I beam, in economy, is the channel, then the deck beam; angles and tees are the least economical of all shapes. The following values show the safe loads per pound of steel, for various shapes, for a 10-ft span; the same ratio would hold for other spans.

20-in I beam	10-in channel	10-in deck-beam	4 by 6-in angle	4 by 5-in tee
104	94.6	83.0	28.7	21.6

**The Deepest Beams, the Strongest, Stiffest and Most Economical.** The STRENGTH of a wooden or steel beam of rectangular cross-section varies as the SQUARE OF THE DEPTH, directly as the breadth and inversely as the length, and the STIFFNESS varies directly as the CUBE OF THE DEPTH, directly as the breadth and inversely as the cube of its length; hence the deeper beam will have the greater strength and stiffness in proportion to its sectional area. With beams these relations do not hold strictly, because of the variation in the forms of the cross-sections, but they are approximately true. It therefore follows that, for any given span, it is more economical in floors, where other conditions will permit, to use deep beams spaced farther apart or to use one deep beam in place of two shallower beams. Thus if a distributed load of 39 tons is to be supported over a span of 16 ft, one 20-in 65-lb beam, two 15-in 42-lb beams, or three 12-in 40-lb beams, could be used; but the 20-in beam would support only 1 105 lb, allowing for 6-in bearings, as compared with 1 428 lb for the 15-in beams and 2 040 lb for the 12-in beams, and the bolts and separators could be saved.

**Light and Heavy Steel Beams.** LIGHT BEAMS are more economical than heavy beams OF THE SAME DEPTH, except when the span is so short that the load is governed by the resistance of the web to buckling, in which case the heavy beams are the more economical.

**Maximum Safe Loads for Steel Beams.** All loaded beams are, in general, subjected to three kinds of stresses. The most destructive are generally those due to the BENDING MOMENTS, and have already been considered. The second are those which tend to SHEAR a beam, or to make one part slide on another vertically. (See paragraph on Shearing-Stresses in Steel Beams and Girders, page 567.) These stresses, however, seldom need to be considered except in the case of riveted girders and short beams with very thick webs. The third kind of stress is that which tends to cause the web of a beam to buckle; and in a steel beam over a span very short in proportion to the depth of the beam, the resistance of the web to buckling generally determines the maximum load that the beam, without stiffeners on the web, will support. (See also, pages 182, 183 and 567.)

**Safe Loads for Steel Beams.\*** To save time in calculating, tables of safe loads for structural and supplementary beams and channels used as beams under conditions of transverse loading, have been prepared, which give the UNIFORMLY DISTRIBUTED SAFE LOADS in thousands of pounds for spans customary

A part of the matter of the following paragraphs relating to steel I beams has been taken by permission, from the Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

in building-construction. They are based upon an extreme FIBER-STRESS of 16 000 lb per sq in on the fibers farthest from the neutral surface of the beam.

The Tables of Safe Loads for Angles and Tees, pages 586 to 591, give the values at the same fiber-stress on spans of one foot, from which the safe load for any span-length may be obtained by direct division, and also the values of those spans at which the allowed safe load will produce a deflection of  $\frac{1}{16}$  in. of the span-length. The loads in all cases include the weight of the beam, which should be deducted in order to arrive at the net load which the beam will support. For several concentrated loads or for a combination of distributed and concentrated loads it will be necessary to use the methods previously explained under Case VIII, page 563.

**Use of Tables for Concentrated Loads.** To use any of the following tables for CONCENTRATED LOADS, find the equivalent distributed load by multiplying the concentrated load by the factor given in Table IV, page 632, then use the beam having a safe load equal to the load thus found.

In addition to the conversion-factors in that table the following, also, will be found convenient:

For two equal loads applied at one-third the span from each end, multiply the load by  $2\frac{1}{2}$ .

For two equal loads applied at one-fourth the span from each end multiply the load by 2.

For a beam fixed at one end, and loaded at the other, multiply by 8.

For a beam fixed at one end, and uniformly loaded over the entire length, multiply by 4.

**Unusual Conditions of Loading of Beams.\*** It is assumed in all the tables that the loads are applied normal to the axis 1-1 as shown in the tables of properties of sections in Chapter X, and that the beam deflects vertically in the PLANE OF BENDING ONLY. If the conditions of loading involve the introduction of forces outside this plane of loading, the allowable safe loads may be determined from the general theory of flexure in accordance with the mode of application of the load and its character. This applies particularly to UNUSUAL METRICAL SECTIONS, such as angles, which should be used under those conditions of loading where the section can deflect vertically only, being rigidly secured against LATERAL DEFLECTION or twisting throughout the entire length. In all such cases of eccentric loading, the actual safe loads would be considerably lower than the tabulated safe loads, which have been based upon the favorable conditions of loading.

**Vertical Deflection of Steel Beams.\*** In the case of beams intended to carry plastered ceilings, experience indicates that the VERTICAL DEFLECTION to avoid cracking the plaster, should be limited to not more than  $\frac{1}{16}$  in. of span-length. This SPAN-LIMIT for steel beams is approximately, in feet, equal to the depth in inches and is indicated in the tables by the lower, broken, horizontal lines. Beams intended for such purposes should not be used for greater spans unless the allowable tabular safe load exceeds the actual load to be supported. As the dead load of a floor is supported by the floor-beams before the plaster is applied, only the deflection due to the live load really needs to be considered. The vertical deflection of beams is explained in Chapter XV.

**Lateral Deflection of Steel Beams.\*** The tabular safe loads are based upon the assumption that the compression-flanges of the various sections

\* Part of the matter of this paragraph has been adapted, by permission, from the Steel Beam Companion, Carnegie Steel Company, Pittsburgh, Pa.



used at proper intervals, against LATERAL DEFLECTION, by the use of tie-rods or by other means. The LATERAL UNBRACED LENGTH of steel beams and girders should not exceed forty times the width of the compression-flanges. When the unbraced length exceeds ten times the width, the tabular safe loads should be reduced. An explanation of the method of reducing the tabular loads when the unsupported length exceeds ten times the flange-width is given in Chapter XVIII, page 670. (See Bethlehem Handbook for sidewise deflection.)

**Shearing-Stresses in Steel Beams and Girders.\*** The safe-load tables for I-beams and channels are computed solely with reference to SAFE UNIT STRESSES IN FLEXURE, and the safe loads uniformly distributed on the spans given will not cause average SHEARING-STRESSES in the web greater than the 10 000 lb per sq in, the average SAFE WORKING STRENGTH of steel in SHEAR. When, however, beams are loaded with heavy loads concentrated near the supports, or when beams of short span are loaded with uniformly distributed loads to their full carrying capacity as regards flexure, the bending moments may be small in comparison with the reactions at the supports, and the beams may fail along the neutral surface as a result of LONGITUDINAL SHEARING-STRESSES, or they may buckle as a result of the combined longitudinal and vertical web-stresses. In such spans the safe shearing or buckling strength of the web rather than the resistance of the flanges to bending-stresses may limit the carrying capacity of the beam.

**Buckling Values of Beam-Webs.\*** The VERTICAL SHEARING-STRESSES or the vertical compressive components of the web-stresses may under some conditions exceed the safe resistance of the beam to BUCKLING, and there remains the possibility that a web or web-plate, which is amply secure against the safe shear of 10 000 lb per sq in, will not be of sufficient strength when considered as a column. In such cases provision must be made for security against buckling either by stiffeners or by an increased thickness of the web or web-plate. (For the determining conditions for web-buckling of steel beams in grilling, based on direct compression, see page 183.)

**Conditions of Web-Buckling of Steel Beams.** There are two conditions of web-buckling (see, also, foot-note for paragraphs relating to Tables II and III).


1. The part of the beam bearing on the support is subject to DIRECT COMPRESSION, and the web over this part must be capable of resisting it. If this part is too small the end of the beam will fail, as a column, causing the web to buckle. It is therefore necessary to calculate the required length of the bearing.

2. The beam throughout its length between the supports, or in case of a cantilever beam, from its end to the support, is subject to SHEAR. It is generally supposed that the shear develops stresses of TENSION and COMPRESSION in the web; that these stresses act at right-angles to each other in the plane of the web and at an angle of  $45^\circ$  with the neutral surface of the beam; and that the DIAGONAL STRESSES are equal in magnitude or intensity to the VERTICAL STRESSES at any point. It is the COMPRESSIVE STRESS that tends to BUCKLE the web.

**Formulas for Safe Buckling Resistance of Steel Beams.\*** In regard to the first condition of buckling a series of experiments has been made on beams of various depths and web-thicknesses to arrive at a basis for a simpler method of computation to use in the investigation of the safe BUCKLING RESISTANCE of steel beams.

Part of the matter of this paragraph has been adapted, by permission, from the Steel Beam Companion, Carnegie Steel Company, Pittsburgh, Pa.

beams with unsupported webs, and from these experiments the following formulas \* have been deduced:



$$\text{Safe end-reaction } R = S_b \times t \left( a + \frac{d}{4} \right)$$

$$\text{Safe interior load } P = 2 S_b \times t \left( a_1 + \frac{d}{4} \right)$$

In these formulas,  $R$  is the end-reaction,  $P$  the concentrated load,  $t$  the thickness,  $d$  the depth of the beam,  $a_1$  half the distance over which the concentrated load is applied and  $a$  the whole distance over which the end-reaction is applied; while  $S_b$  is the SAFE RESISTANCE OF THE WEB TO BUCKLING, in pounds per square inch, by the straight-line formula

$$S_b = 19\,000 - 100 d/2r$$

$d/2 = l$  in the column-formula †. The first formula is general and applies to any condition of loading. The second formula covers the case of a single concentrated load at the middle of a span; it can be extended to cover a system of concentrated loads provided the sum of the distances  $a_1$  is not less than  $a$ .

Tables II † and III † give for beams and channels with unsupported webs:

\* These formulas, in order to satisfy the first condition, are used in the Pocket Companion, 1915 Edition, Carnegie Steel Company, Pittsburgh, Pa.

† This is the column-formula used by the American Bridge Company and in Carnegie's Pocket Companion,  $S$  being the allowable COMPRESSIVE UNIT STRESS in pounds per square inch within the usual limits of  $l/r$ . See Formula (13), page 481.

‡ In regard to the shearing of steel beams, allowable web-shears, etc., the value used in the example (see Example 15, this chapter, and on pages 182 and 183 of Chapter I) 42 000 lb per sq in for a 12-in, 31.8-lb I beam, given in Table II, page 575, taken from Carnegie's Pocket Companion, is based on the allowed direct shear without including the condition of web-crippling. That is, the 42 000 lb is determined by taking the area of the web,  $0.35 \times 12 = 4.2$  sq in and multiplying it by 10 000 lb per sq in, which is the value there used for the safe unit shearing-stress.

The beam is therefore calculated as being good for 42 000 lb SHEAR, but it is necessary to make a further investigation to ascertain whether the stresses due to shear will cause the web of the beam to buckle. As stated in the paragraph on page 567, on the Buckling Values of Beam-Webs there are two conditions of web-buckling or web-crippling.

In the case of a plate girder the end-stiffeners provide for the first condition, and intermediate stiffeners for the second condition. The web itself may then be counted on for its full shearing value. In the case of beams, however, it is not generally economical to use stiffeners, so that the web alone must meet every condition.

The Carnegie Pocket Companion gives a formula, reproduced in the preceding paragraph, and gives the derived lengths of bearings in Tables II and III, to satisfy the first condition. Some of the formulas used in the manufacturers' handbooks, for maximum safe shear based on web-buckling for the second condition, are as follows:

$$\text{Passaic Steel Company, } V = \frac{10\,000\,dt}{1 + \frac{h^2}{3\,000\,l^2}}$$

$$\text{Cambria Steel Company, } V = \frac{12\,000\,dt}{1 + \frac{h^2}{1\,500\,l^2}}$$

$$\text{Bethlehem Steel Company, } V = \frac{13\,000\,dt}{1 + \frac{h^2}{3\,000\,l^2}}$$

- (1) "The allowed WEB-RESISTANCE  $S_b$ , in pounds per square inch, computed from this compression-formula. (See, also, page 183.)
- (2) "The distance  $a$ , or the distance over which the end-reaction must be distributed when the shearing-stress  $V$  in the web is the maximum allowable stress of 10 000 lb per sq in.
- (3) "The allowable END-REACTION  $R$ , when  $a$  is taken at 3½ in, which is the usual length of beam actually resting on the 4-in angles ordinarily used in building-construction for beam-seats.
- (4) "The allowable SHEAR  $V$ , on the gross area of the cross-section of the beam channel-webs, at 10 000 lb per sq in."
- In regard to the second condition of WEB-BUCKLING, the MAXIMUM ALLOWABLE SHEAR may be calculated by the formula,

$$V = \frac{12\,000\,dl}{1 + \frac{h^2}{1\,500\,l^2}}$$

in which  $V$  = the maximum safe web-shear in pounds;  $d$  = the depth of the beam;  $l$  = the thickness of the web; and  $h$  = the height between the flange-fillets. (See Example 15, this chapter and also example on pages 182 and 183.)

"In addition to these data which have to do with the MAXIMUM LOADS on beams and channels as computed from the WEB-RESISTANCE, Tables II and III give, also, the MAXIMUM BENDING MOMENTS in foot-pounds, obtained by the multiplication of the SECTION-MODULUS of each section by the allowed FIBER-STRESS of 16 000 lb per sq in and the division of the product by 12 in order to reduce to a foot-pound basis. These maximum bending moments may be used on the table instead of the table of properties to ascertain the proper size of section to be used in any particular instance."

of which  $V$  = the maximum safe web-shear in pounds;  $d$  = the depth of the beam;  $l$  = the thickness of web; and  $h$  = the distance between the flange-fillets.

It is to be noted that the length of the element in compression on the 45° line is  $h\sqrt{2}$ , that the square of this length is  $2h^2$ . It is this value,  $2h^2$ , that is substituted for  $h^2$  in the column-formula used by the Cambria Steel Company in deducing its formula for shear based on web-buckling. The tensile stress, however, tends to keep the compressive stress from buckling the web, and for this reason the Passaic and Bethlehem engineers used the more liberal value of 3 000  $\rho$  instead of 1 500  $\rho$ . The Passaic Steel Company, however, used the more conservative unit value of 10 000 lb, reduced, instead of the 16 000 lb used by the others. The Passaic and Cambria formulas give about the same results, a 12-in, 31½-lb I beam by the former having a safe shear of 33 352 lb and by the latter, 33 188 lb.

The Passaic Steel Company is no longer in existence and their handbook is out of print. The Bethlehem Steel Company's handbook has tables for Bethlehem shapes only. If, for any case, no table of maximum shears of beams, based on web-crippling, is at hand, it is suggested that the values may be determined from the formula,

$$V = \frac{12\,000\,dl}{1 + \frac{h^2}{1\,500\,\rho}}$$

which, as before,  $V$  = the maximum safe web-shear in pounds;  $d$  = the depth of the beam;  $l$  = the thickness of the web; and  $h$  = the distance between the flange-fillets. The beam mentioned and used in Example 15, page 571, in this chapter and in the example on pages 182 and 183,  $d$  = 12 in,  $l$  = 0.35 in,  $h$  = 9.762 in,  $\rho$  = 0.1225,  $S_b$  = 95.956644 and  $V$  = 33 188 lb. This formula is recommended as being the most conservative, although there is not a great difference in the results, and the formula of the former Passaic Steel Company is retained elsewhere in Kidder's Pocket-Book. See, for example, page 686 and Table III of Chapter XX. Editor-in-chief.

Table VII is a table computed by Mr. Kidder, giving the strength of small rectangular steel channels or grooved steel. These are often used supporting metal lath in suspended ceilings, and the table will be found useful in determining the size to use for any given span and spacing.

#### 4. Tables of Safe Loads for Steel Beams and Girders. Example 9.

**Example 9. Direct Bending from a Uniformly Distributed Load.** As an illustration of the use of these tables let it be required to determine the proper size and weight of an I beam to carry safely a uniformly distributed load of 34 000 lb over a span of 20 ft, the weight of the beam not being included.

**Solution.** From Table IV, page 579, a 15-in 50-lb beam will carry 34 400 lb. The weight of this beam is  $50 \text{ lb} \times 20 \text{ ft} = 1\,000 \text{ lb}$ , making a total load of 35 000 lb. This is so little in excess of the safe load that the extra weight need not be considered. Had the difference been more, however, the heavier beam should be used.

**Example 10. Direct Bending from a Concentrated Load.** To illustrate the use of the tables to determine the size and weight of beams required to carry concentrated loads, Examples 10 and 11 are given. What I beam, 15 ft in span, will safely support 8 000 lb, concentrated at a point 5 ft from the left support?

**Solution.** The distance 5 ft is one-third of the span, and the conversion factor for this (Table IV, page 632) is 1.78. The equivalent uniformly distributed load, therefore, is  $8\,000 \times 1.78 = 14\,240 \text{ lb}$ , and from Table IV, page 581, a 9-in 25-lb I beam will carry 14 500 lb for a span of 15 ft, and will answer the purpose.

**Example 11. Direct Bending from Two Equal Concentrated Loads.** What I beam, 15 ft in span, will safely support two equal concentrated loads of 6 000 lb each, applied 5 ft from each end?

**Solution.** The distance 5 ft is one-third the span, but the multiplier in this case is  $2\frac{2}{3}$  (page 566). Hence, the equivalent uniformly distributed load is  $6\,000 \times 2\frac{2}{3} = 16\,000 \text{ lb}$  and the beam required (Table IV, page 580) is a 10-in 25.4-lb I beam which will carry 17 400 lb. The same result is obtained using Formula (11)', page 562. This formula is,  $I/c = 12 Pm/S$ . Substituting,  $I/c = 12 \times 6\,000 \times 5/16\,000 = 22.5$ . The nearest section-modulus to this is that of a 10-in 25.4-lb I beam.

**Example 12. Maximum Bending Moment from a Distributed Load Over the Span.** The beam in Example 5, Case V, page 561, has a maximum bending moment of 26 666 ft-lb. What beam is required?

**Solution.** The nearest bending moment to this in the first column of Table II, page 575, is 27 240 ft-lb, which corresponds to a 9-in 25-lb I beam.

**Example 13. Allowable Web-Shear.\*** The maximum shear in the beam in Example 12 is just at the right of the left reaction or bearing, and equals 16 000 lb. Is the beam safe for shear?

**Solution.** From Table II, page 575, in the column for  $V$ , the allowable shear for a 9-in 25-lb beam is 36 540 lb. Hence, the beam is safe if web-buckling is not taken into account.

**Example 14. Shear.\*** It is required to determine the maximum load that a 9-in 25-lb I beam can support without exceeding the safe web-resistance of the section.

\* See paragraphs and foot-note relating to buckling of beam-webs, pages 567 to 570.

**Solution.** From Table IV, page 581, the maximum load for this beam, given small figures above the heavy, horizontal lines, is 73 100 lb.

**Example 15. Safe Buckling Resistance.** See, also, paragraphs and foot-note relating to buckling of beam-webs on pages 567 to 569 and also example on pages 182 and 183. According to Table II, page 575, the allowable web-shear for a 12-in, 31.8-lb I beam is 42 000 lb. Will this shear cause the web of the beam to buckle?

**Solution.** The web-shear is determined by multiplying the area of the web, that is, 0.35 in  $\times$  12 in = 4.2 sq in, by 10 000 lb per sq in, the safe unit shearing-stress. The maximum shear which will not cause the web to fail by buckling may be found by the formula given on page 569 for the second condition of web-buckling.

$$V = \frac{12\,000\,dt}{1 + \frac{h^2}{1\,500\,l^2}}$$

From the dimensions of structural beams (see Carnegie's Pocket Companion, Beams, Profiles, Weights, etc.) the thickness  $t$  of the web of a 12-in, 31.8-lb beam is 0.35 in, the depth of the beam is  $d = 12$  in and  $h$ , the distance between flange-fillets, is 9.762 in. Substituting these values in the formula,

$$V = \frac{12\,000 \times 12 \times 0.35}{1 + \frac{9.762^2}{1\,500 \times 0.35^2}} = \frac{50\,400}{1 + \frac{95.296644}{1\,500 \times 0.1225}} = \frac{50\,400}{1 + \frac{95.296644}{183.75}} = \frac{50\,400}{\frac{279.046644}{183.75}} = \frac{50\,400 \times 183.75}{279.046644} = \frac{9\,261\,000}{279.046644} = 33\,188, \text{ or about } 33\,190 \text{ lb}$$

As this is less than the allowable web-shear of 42 000 lb given in the tables, account is to be taken of the web-buckling from the second condition mentioned in the preceding pages, a larger or heavier beam should be used or the shear reduced, so that the maximum shear will not exceed 33 190 lb. (For determining conditions for web-buckling of steel beams in grillages, based on direct compression, see page 183.)

**Example 16. Safe End-Reactions for Web-Buckling.** In Example 8, page 56, the two 24-in 90-lb I beams carry 170 000 lb + (4 000 lb, the weight of the beams) = 174 000, lb or 87 000 lb for each beam. Assuming that they rest on 4-in brackets riveted to columns at each end of the span, are the end-reactions excessive?

**Solution.** Since the loading is symmetrical, each reaction for each beam is half the total load on each beam, or 43 500 lb. From the last column in Table II, page 574, the maximum end-reaction  $R$ , for a 24-in 90-lb beam, is 40 000 lb. Hence, the beam is safe as far as the compression from the end-reactions is concerned.

**Strut-Beams.** It is not considered good construction to subject a strut to a reverse loading, causing a certain amount of flexure in it and thus adding to the compressive stress. Conditions often exist, however, where practical considerations make it desirable to use a strut as a beam, also, as in the top chord or in the principals of a truss. To determine the size of a member in a case of this kind the following method should be used:

(a) Find the section-modulus  $I/c$ , for the member for the transverse load by formulas (2)' to (11)', using 12 000 lb per sq in as the value of  $S$ , and find the size of the cross-section of a steel shape corresponding to the value of  $I/c$  thus found. See note at end of Example 17, relating to value of  $S$ .

(2) Find the section-area required to resist the compressive stress, by dividing that stress by the value opposite  $l/r$  in column VIII of Table XI, page 493.

(3) Add together the two areas and use for the required member a piece of material having a section-area next larger than the total area found.

**Example 17. Strut-Beam. Combined Bending and Compression.** A principal rafter in a truss, 8 ft 6 in long between joints, supports the end purlin at the middle of the span. The weight from the purlin is 2 800 lb and the compressive stress in the rafter 30 000 lb. It is proposed to use a pair of angles for the rafter, set with the long legs vertical and  $\frac{1}{2}$  in apart. What are the dimensions of the angles, the strut being braced laterally?

**Solution.** (1) By Formula (8)',  $I/c = 3 \times 2\,800 \times 8.5 / 12\,000 = 5.95$  for a pair of angles, or 2.98 for each angle. (See note at end of this example.) From Table XI, page 363, the nearest value to this with reference to the axis 1-1 is 3.0, the section-modulus for a 5 by  $3\frac{1}{2}$  by  $\frac{1}{4}$ -in angle. The section-area of one angle is 4 sq in and of two angles, 8 sq in.

(2) From Table XVI, page 371, the least  $r$  for a pair of 5 by  $3\frac{1}{2}$  by  $\frac{1}{4}$ -in angles, which would be about the axis 1-1, since the strut is braced laterally, is about 1.58 (between 1.53 and 1.61). Then the slenderness-ratio  $l/r = 6\text{ in} / 1.58\text{ in} = 102\text{ in} / 1.58\text{ in} = 64.5$ . From column VIII, Table XI, page 493,  $S = 9\,250\text{ lb per sq in}$ . Hence,  $30\,000\text{ lb} / 9\,250\text{ lb per sq in} = 3.24\text{ sq in}$  approximately.

(3) The section-area required, therefore, is  $8 + 3.24 = 11.24\text{ sq in}$ , which, from Table XI, page 363, is about equivalent to that of two 5 by 4 by  $\frac{1}{4}$ -in angles. As the section-area in both calculations exceeds that actually required, no allowance for the weight of the angles need be made.

**Note.** Because of the increase in the tendency of the strut to deflect, caused by the combined stresses of flexure and compression, lower values of  $S$  are required than in the cases of simple flexure, or of simple compression.

**Tie-Beams.** Steel beams subject to combined tensile and transverse stresses should be calculated in a way similar to that explained above for strut-beams. The section necessary to resist the transverse stress should be found first, then the section necessary to resist the tensile stress, and the two added together.

**Example 18. Tie-Beam. Combined Bending and Tension.** One span of a tie-beam, 10 ft between joints, supports a load of 6 000 lb at the middle, and at the same time is under a tensile stress of 84 000 lb. It is proposed to use two steel channels for the tie-beam. What size and weight are required for the channels?

**Solution.** A load of 6 000 lb applied at the middle of a beam has the same effect as a load of 12 000 lb uniformly distributed, or 6 000 lb for each channel. From Table V, page 584, a 7-in, 9.8-lb channel will be required, its section-area (Table VIII, page 359) being 2.85 sq in. The additional area required to resist the tensile stress is  $84\,000\text{ lb} / 16\,000\text{ lb per sq in} = 5.25\text{ sq in}$ , or 2.62 sq in for each channel. The total area for each channel, therefore, should be  $2.85 + 5.25 = 8.10\text{ sq in}$ . A 7-in, 19.75-lb channel has a section-area of 5.79 sq in and an 8-in, 18.75-lb channel has a section-area of 5.49 sq in. Either one would be sufficient, but the 8-in channel will probably be more economical, as it weighs 1 lb per ft less.

**Example 19. Channel, Set Flatwise.** What is the size of the channel, set flatwise, required to support a uniformly distributed load of 180 lb per ft over a span of 10 ft, or 120 in?

**Solution.**  $W = 180 \times 10 = 1\,800\text{ lb}$ . From Case V, page 326,  $M_{\max} = Wl^2 / 8 = 1\,800 \times 120^2 / 8 = 27\,000\text{ in-lb}$ . From Formula (3)', page 557,  $I/c = M / S$

$16000/16000 = 1.7$ . From Table VIII, page 359, the  $I/c$  about the axis  $z-z$  corresponding to this is that of a 12-in, 20.7-lb channel.

**Example 20. Rectangular Steel Bar with Long Side Vertical.** In a suspended, plastered ceiling it is proposed to use 2 by  $\frac{3}{8}$ -in steel bars, 4 ft or 48 in long, to carry the plaster. What is the safe load each bar will support, if set with the long side vertical?

**Solution.** From Table I, page 346, the  $I$  for a 2 by  $\frac{3}{8}$ -in bar is 0.250.  $c =$  half the depth = 1 in.  $I/c = 0.250/1 = 0.250$ . Also, from Formula (2)', p. 557,  $M_{\max} = SI/c$ . Substituting,  $M_{\max} = 16000 \times 0.250 = 4000$  in-lb. From Case V, page 326,  $M_{\max} = Wl/8$ , and hence,  $4000 = W \times 48/8 = W/2$ , and  $W = 4000/2 = 2000$  lb.

### Oblique Loading of I Beams and Channels \*

**Oblique Loading of Purlins on Sloping Roofs.** (See, also pages 593, 695 and 1170.) In Tables II to V it is assumed that I beams and channels are set with webs vertical and carry vertical loads. This is not the case when they are used as PURLINS ON SLOPING ROOFS. There are then fiber-stresses due to the components of the bending moment both at right-angles and parallel to the slope of the roof. The resultant fiber-stress may be calculated from the equation on page 1170. This equation is used in determining the values given in Table I A. It may be noted that the second term causes the fiber-stresses to increase rapidly with the slope of the roof. If purlins were proportioned according to the equation given or from the Table I A, they would often be much larger than those commonly used. For small slopes the second term of the equation may be reduced or eliminated by the stiffness of the roofing, and for other slopes by connecting the purlins with SAG-RODS running across the sloping sides of the roof to an unyielding connection at the peak.

**Table I A. Ratio of Maximum Fiber-Stress to Bending Moment for I-Beams and Channel Purlins Set at Right-Angles to Rafters and Free to Move in Any Direction. Loading Vertical and Oblique to Web**

Purlin	Slope of roof in inches per foot †						
	0	1	2	4	5	6	8
12-in I beam 12.5 lb.....	0.14	0.21	0.28	0.42	0.47	0.53	0.61
12-in I beam 15.3 lb.....	0.10	0.15	0.21	0.31	0.35	0.39	0.46
12-in I beam 18.4 lb.....	0.07	0.11	0.16	0.23	0.27	0.30	0.35
12-in I beam 21.8 lb.....	0.05	0.09	0.12	0.18	0.21	0.24	0.28
12-in I beam 25.4 lb.....	0.04	0.07	0.10	0.15	0.17	0.19	0.22
12-in I beam 31.8 lb.....	0.03	0.05	0.07	0.11	0.13	0.14	0.17
12-in channel 8.2 lb.....	0.23	0.40	0.56	0.85	0.98	1.10	1.30
12-in channel 9.8 lb.....	0.17	0.30	0.42	0.66	0.76	0.85	1.01
12-in channel 11.5 lb.....	0.12	0.23	0.33	0.52	0.60	0.68	0.80
12-in channel 13.4 lb.....	0.10	0.18	0.26	0.42	0.48	0.55	0.65
12-in channel 15.3 lb.....	0.08	0.15	0.21	0.34	0.40	0.45	0.54
12-in channel 20.7 lb.....	0.05	0.09	0.14	0.23	0.26	0.30	0.36

\* From Notes by Robins Fleming.

† Values vary slightly for slight variations in weights and section-areas of beams and channels.

Table II.\*† Maximum Bending Moments and Web-Resistance of I Beams

$M_{\max}$	$d$	$w$	$t$	$V$	$S_b$ †	$a$	$R$
Maximum bending moment	Depth of beam	Weight per lin ft	Thickness of web	Allowable web-shear	Allowable buckling resistance	Minimum end-bearing	End reaction $a = 3\frac{1}{2}$
ft-lb	in	lb	in	lb	lb per sq in	in	lb
292 130	27	90.0	0.524	141 480	10 080	20.0	54 1
328 390		113.0	0.737	180 000	13 460	11.8	95 8
320 390		110.0	0.675	165 120	12 960	12.5	84 6
312 390		105.0	0.625	150 000	12 350	13.4	73 3
264 400		100.0	0.747	180 960	13 490	11.8	96 6
256 560	24	95.0	0.686	166 320	13 000	12.5	85 6
248 710		90.0	0.624	151 440	12 410	13.3	74 4
240 870		85.0	0.563	136 800	11 710	14.5	63 4
231 920		80.0	0.500	120 000	10 690	16.5	50 7
216 670		74.2	0.476	114 240	10 260	17.4	46 4
156 930	21	60.4	0.428	89 880	10 500	14.8	39 1
220 750		100.0	0.873	176 800	15 080	8.3	113 1
214 210		95.0	0.800	162 000	14 720	8.6	101 1
207 680		90.0	0.726	147 400	14 300	9.0	89 1
201 140		85.0	0.653	132 600	13 780	9.5	77 0
195 510	20	80.4	0.600	120 000	13 230	10.1	67 1
169 170		75.0	0.641	129 800	13 660	9.6	75 1
162 640		70.0	0.567	115 000	12 980	10.4	63 1
155 930		65.4	0.500	100 000	12 080	11.6	51 1
186 720		90.0	0.796	145 260	15 140	7.4	97 1
180 840		85.0	0.714	130 500	14 700	7.7	85 1
174 960		80.0	0.632	115 920	14 160	8.2	72 1
169 080		75.6	0.560	101 160	13 450	8.9	60 1
136 480	18	70.0	0.711	129 420	14 670	7.8	84 1
130 590		65.0	0.629	114 660	14 110	8.3	71 1
124 710		60.0	0.547	99 900	13 380	9.0	59 1
117 860		55.0	0.460	82 800	12 220	10.2	44 1
109 200		48.2	0.380	68 400	10 800	12.2	32 1
122 890		75.0	0.868	132 300	16 050	5.6	*102 1
117 980		70.0	0.770	117 600	15 690	5.8	89 1
113 080		65.0	0.672	102 900	15 210	6.1	75 1
108 270		60.8	0.590	88 500	14 600	6.5	62 1
90 850	15	55.0	0.648	98 400	15 040	6.2	71 1
85 940		50.0	0.550	83 700	14 340	6.7	58 1
81 040		45.0	0.452	69 000	13 350	7.5	44 1
78 530		42.9	0.410	61 500	12 670	8.1	37 1
72 130		37.3	0.332	49 800	11 180	9.7	26 1

$V$  is computed at 10 000 lb per sq in of gross area of web-section.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† See, also, foot-note on page 568, with paragraphs relating to this table and to III, and paragraphs on page 567, relating to web-buckling of steel beams. See page 181.



# Tables of Safe Loads for Steel Beams and Girders

3

Table H \* † (Continued). Maximum Bending Moments and Web-Resistance of I Beams

<i>M<sub>max</sub></i>	<i>d</i>	<i>w</i>	<i>t</i>	<i>V</i>	<i>S<sub>x</sub></i> †	<i>a</i>	<i>R</i>
Maximum bending moment	Depth of beam	Weight per lin ft	Thickness web	Allowable web- shear	Allowable buckling resistance	Minimum end- bearing	End- reaction <i>a</i> = 3½ in
ft-lb	in	lb	in	lb	lb per sq in	in	lb
71 330	12	55.0	0.810	98 530	16 470	12	No Res
67 410		50.0	0.687	83 880	16 030		
63 490		45.0	0.565	69 120	15 390		
59 770		40.8	0.460	55 200	14 480		
56 130		35.0	0.428	52 320	14 230		
52 560		31.8	0.350	42 000	13 060		
44 270		27.9	0.284	34 080	11 680		
42 310	10	40.0	0.741	74 900	16 690	10	
39 050		35.0	0.594	60 200	16 120		
35 780		30.0	0.447	43 500	15 190		
32 560		25.4	0.310	31 000	13 410		
28 270		22.4	0.253	25 200	12 130		
23 120	9	35.0	0.714	65 880	16 870	9	
21 150		30.0	0.561	51 210	16 260		
19 240		25.0	0.397	36 510	15 160		
15 160		21.8	0.290	26 100	13 620		
22 810	8	25.5	0.532	43 280	16 440	8	
21 520		23.0	0.441	35 920	15 910		
19 190		20.5	0.349	28 560	15 120		
18 960		18.4	0.270	21 600	13 870		
17 470		17.5	0.220	17 600	12 700		
16 270	7	20.0	0.450	32 060	16 350	7	
14 330		17.5	0.345	24 710	15 370		
12 800		15.3	0.250	17 500	14 150		
11 630	6	17.25	0.465	28 500	16 810	6	
10 660		14.75	0.343	21 120	16 050		
9 580		13.5	0.230	13 800	14 480		
8 080	5	14.75	0.404	25 200	17 280	5	
7 260		12.25	0.347	17 850	16 580		
6 430		10.00	0.210	10 500	14 870		
4 760	4	10.5	0.400	16 400	17 510	4	
4 900		9.5	0.326	13 480	16 940		
4 240		8.5	0.253	10 520	16 360		
3 980		7.7	0.190	7 600	15 360		
2 390	3	7.5	0.349	10 830	17 560	3	
2 390		6.5	0.251	7 890	17 020		
2 210		5.7	0.170	5 100	15 950		

*V* is computed at 10 000 lb per sq in of gross area of web-section.

From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

See also, foot-note on page 468, with paragraphs relating to this table and to Table I. See also, paragraphs on page 567, relating to web-buckling of steel beams. See, also,

Table III.\*† Maximum Bending Moments and Web-Resistances of Channels

$M_{max}$	$d$	$w$	$t$	$V$	$S_x$ †	$a$	$R$
Maximum bending moment	Depth of channel	Weight per lin ft	Thick-ness of web	Allowable web-shear	Allowable buckling resistance	Minimum end-bearing	End reaction $a=3/4$
ft-lb	in	lb	in	lb	lb per sq in	in	lb
76 490	15	55.0	0.814	122 700	15 820	5.7	93 800
71 590		50.0	0.716	108 000	15 390	6.0	80 300
66 680		45.0	0.618	93 300	14 820	6.4	66 800
61 780		40.0	0.520	78 600	14 040	6.9	53 300
56 880		35.0	0.422	63 900	12 900	7.9	39 800
55 570		33.9	0.400	60 000	12 510	8.2	36 200
64 360	13	50.0	0.787	102 830	16 150	4.8	86 200
60 110		45.0	0.673	88 140	15 630	5.0	71 700
55 870		40.0	0.560	73 450	15 020	5.4	57 200
53 320		37.0	0.492	64 610	14 470	5.7	48 500
51 620		35.0	0.447	58 760	14 020	6.0	42 700
48 740		31.8	0.375	48 750	13 000	6.8	32 900
43 760	12	40.0	0.755	90 960	16 260	4.4	80 000
39 840		35.0	0.632	76 320	15 730	4.6	65 000
35 920		30.0	0.510	61 560	14 950	5.0	49 800
32 000		25.0	0.387	46 800	13 670	5.8	34 600
28 470		20.7	0.280	33 600	11 570	7.4	21 000
30 800		35.0	0.820	82 300	16 900	3.4	83 400
27 530	10	30.0	0.673	67 600	16 440	3.6	66 600
24 260		25.0	0.526	52 900	15 730	3.9	49 500
20 990		20.0	0.379	38 200	14 470	4.4	33 100
17 840		15.3	0.240	24 000	11 780	6.0	16 500
20 950		25.0	0.612	55 350	16 470	3.2	58 200
18 010		20.0	0.448	40 680	15 550	3.5	40 400
15 070	9	15.0	0.285	25 920	13 590	4.4	22 500
14 080		13.4	0.230	20 700	12 220	5.1	16 100
15 920		21.25	0.579	46 560	16 620	2.8	53 200
14 610		18.75	0.487	39 200	16 170	2.9	43 100
13 310		16.25	0.395	31 920	15 530	3.2	34 000
12 000		13.75	0.303	24 560	14 490	3.5	24 000
10 770	8	11.50	0.220	17 600	12 700	4.3	15 000
12 640		19.75	0.629	44 310	17 090	2.3	56 000
11 490		17.25	0.524	36 960	16 700	2.4	46 000
10 350		14.75	0.419	29 610	16 130	2.6	35 000
9 210		12.25	0.314	22 260	15 190	2.9	25 000
8 030		9.80	0.210	14 700	13 230	3.5	14 000
8 680	6	15.5	0.559	33 780	17 150	2.0	48 000
7 700		13.0	0.437	26 400	16 640	2.1	36 000
6 720		10.5	0.314	19 080	15 730	2.3	25 000
5 780		8.2	0.200	12 000	13 810	2.8	13 000
5 550		11.5	0.472	23 850	17 180	1.7	38 000
4 730		9.0	0.325	16 500	16 380	1.8	25 000
3 960	5	6.7	0.190	9 500	14 450	2.2	13 000
3 050		7.25	0.320	13 000	16 870	1.4	24 000
2 790		6.25	0.247	10 030	16 250	1.5	18 000
2 530		5.40	0.180	7 200	15 150	1.6	12 000
1 840		6.0	0.356	10 860	17 560	1.0	27 000
1 640		5.0	0.258	7 920	17 030	1.0	19 000
1 450	3	4.1	0.170	5 100	15 940	1.1	11 000

$V$  is computed at 10 000 lb per sq in of gross area of web-section.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† See, also, foot-note on page 568, with paragraphs relating to this table and to III, and paragraphs on page 567, relating to web-buckling of steel beams. See page 183.

**Table IV.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel I Beams**  
 maximum bending stress, 16 000 lb per sq in. Beams secured against yielding sidewi

Span, ft	Depth and weight of sections											Coeffi- cient of deflection .
	27-in	24-in									21-in	
	90 lb	115 lb	110 lb	105.9 lb	100 lb	95 lb	90 lb	85 lb	79.9 lb	74.2 lb	60.4 lb	
6	...	...	...	...	31.1	...	...	...	...	...	...	...
7	...	...	...	...	32.5	...	...	...	...	...	...	0.60
8	...	...	...	...	32.2	...	...	...	...	...	...	0.81
9	...	...	...	...	32.2	...	...	...	...	...	...	1.06
10	...	...	...	...	32.2	...	...	...	...	...	...	1.34
11	...	...	...	...	32.2	...	...	...	...	...	...	1.66
12	...	...	...	...	32.2	...	...	...	...	...	...	2.00
13	...	...	...	...	32.2	...	...	...	...	...	...	2.38
14	...	...	...	...	32.2	...	...	...	...	...	...	2.80
15	...	...	...	...	32.2	...	...	...	...	...	...	3.24
16	...	...	...	...	32.2	...	...	...	...	...	...	3.72
17	...	...	...	...	32.2	...	...	...	...	...	...	4.24
18	...	...	...	...	32.2	...	...	...	...	...	...	4.78
19	...	...	...	...	32.2	...	...	...	...	...	...	5.36
20	...	...	...	...	32.2	...	...	...	...	...	...	5.98
21	...	...	...	...	32.2	...	...	...	...	...	...	6.62
22	...	...	...	...	32.2	...	...	...	...	...	...	7.30
23	...	...	...	...	32.2	...	...	...	...	...	...	8.01
24	...	...	...	...	32.2	...	...	...	...	...	...	8.76
25	...	...	...	...	32.2	...	...	...	...	...	...	9.53
26	...	...	...	...	32.2	...	...	...	...	...	...	10.35
27	...	...	...	...	32.2	...	...	...	...	...	...	11.19
28	...	...	...	...	32.2	...	...	...	...	...	...	12.07
29	...	...	...	...	32.2	...	...	...	...	...	...	12.98
30	...	...	...	...	32.2	...	...	...	...	...	...	13.92
31	...	...	...	...	32.2	...	...	...	...	...	...	14.90
32	...	...	...	...	32.2	...	...	...	...	...	...	15.91
33	...	...	...	...	32.2	...	...	...	...	...	...	16.95
34	...	...	...	...	32.2	...	...	...	...	...	...	18.03
35	...	...	...	...	32.2	...	...	...	...	...	...	19.13
36	...	...	...	...	32.2	...	...	...	...	...	...	20.28
37	...	...	...	...	32.2	...	...	...	...	...	...	21.45
38	...	...	...	...	32.2	...	...	...	...	...	...	22.66
39	...	...	...	...	32.2	...	...	...	...	...	...	23.90
40	...	...	...	...	32.2	...	...	...	...	...	...	25.18
41	...	...	...	...	32.2	...	...	...	...	...	...	26.48
42	...	...	...	...	32.2	...	...	...	...	...	...	27.82
43	...	...	...	...	32.2	...	...	...	...	...	...	29.20
44	...	...	...	...	32.2	...	...	...	...	...	...	30.60
45	...	...	...	...	32.2	...	...	...	...	...	...	32.04
46	...	...	...	...	32.2	...	...	...	...	...	...	33.52
47	...	...	...	...	32.2	...	...	...	...	...	...	35.02
48	...	...	...	...	32.2	...	...	...	...	...	...	36.56
49	...	...	...	...	32.2	...	...	...	...	...	...	38.14
50	...	...	...	...	32.2	...	...	...	...	...	...	39.74
51	...	...	...	...	32.2	...	...	...	...	...	...	41.38

Loads above the upper heavy lines will cause maximum allowable shears in  
 lbs. See, also, paragraphs in text and foot-note with same, page 567, relating to  
 buckling in beams

Loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table IV \* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel I Beams**

Maximum bending stress, 16 000 lb per sq in. Beams secured against yielding side

Span, ft	Depth and weight of sections												Con cier del ti
	20-in								18-in				
	100 lb	95 lb	90 lb	85 lb	81.4 lb	75 lb	70 lb	65.4 lb	90 lb	85 lb	80 lb	75.6 lb	
....	<u>353.6</u>	...	...	...	...	...	...	...	...	...	...	...	...
5	353.2	...	...	...	...	...	...	...	...	...	...	...	0
....	....	<u>324.0</u>	<u>294.8</u>	...	...	<u>259.6</u>	<u>230.0</u>	...	<u>200.5</u>	<u>171.0</u>	...	...	...
6	294.3	285.6	276.9	<u>265.2</u>	<u>240.0</u>	225.6	216.8	<u>200.0</u>	249.0	241.1	<u>221.8</u>	<u>208.3</u>	0.
7	252.3	244.8	237.7	229.9	223.4	193.3	185.9	178.2	213.4	206.7	200.0	193.2	0.
8	220.7	214.2	207.7	201.1	195.5	169.2	162.6	155.9	186.7	180.8	175.0	169.1	1.
9	196.2	190.4	184.6	178.8	173.8	150.4	144.6	138.6	166.0	160.7	155.5	150.3	1.
10	176.6	171.4	166.1	160.9	156.4	135.3	130.1	124.7	149.4	144.7	140.0	135.3	1.
11	160.5	155.8	151.0	146.3	142.2	123.0	118.3	113.4	135.8	131.5	127.2	123.0	2
12	147.2	142.8	138.5	134.1	130.3	112.8	108.4	104.0	124.5	120.6	116.6	112.7	2
13	135.8	131.8	127.8	123.8	120.3	104.1	100.1	96.0	114.9	111.3	107.7	104.1	2
14	126.1	122.4	118.7	114.9	111.7	96.7	92.9	89.1	106.7	103.3	100.0	96.6	3
15	117.7	114.2	110.8	107.3	104.3	90.2	86.7	83.2	99.6	96.4	93.3	90.2	3
16	110.4	107.1	103.8	100.6	97.7	84.6	81.3	78.0	93.4	90.4	87.5	84.5	4
17	103.9	100.8	97.7	94.1	92.0	79.6	76.5	73.4	87.9	85.1	82.3	79.6	4
18	98.1	95.2	92.3	89.4	86.9	76.3	72.3	69.3	83.0	80.4	77.8	75.1	5
19	92.9	90.2	87.4	84.7	82.3	71.2	68.5	65.7	78.6	76.1	73.7	71.2	5
20	88.3	85.7	83.1	80.5	78.2	67.7	65.1	62.4	74.7	72.3	70.0	67.6	6
21	84.1	81.6	79.1	76.6	74.5	64.4	62.0	59.4	71.1	68.9	66.7	64.4	7
22	80.3	77.9	75.5	73.1	71.1	61.5	59.1	56.7	67.9	65.8	63.6	61.5	8
23	76.8	74.5	72.2	70.0	68.0	58.8	56.6	54.2	64.9	62.9	60.9	58.8	8
24	73.6	71.4	69.2	67.0	65.2	56.4	54.2	52.0	62.2	60.3	58.3	56.4	9
25	70.6	68.5	66.5	64.4	62.6	54.1	52.0	49.9	59.8	57.9	56.0	54.1	10
26	67.9	65.9	63.9	61.9	60.2	52.1	50.0	48.0	57.5	55.6	53.8	52.0	11
27	65.4	63.5	61.5	59.6	57.9	50.1	48.2	46.2	55.3	53.6	51.8	50.1	12
28	63.1	61.2	59.3	57.5	55.9	48.3	46.5	44.6	53.3	51.7	50.0	48.3	13
29	60.9	59.1	57.3	55.5	53.9	46.7	44.9	43.0	51.5	49.9	48.3	46.6	14
30	58.9	57.1	55.4	53.6	52.1	45.1	43.4	41.6	49.8	48.2	46.7	45.1	15
31	57.0	55.3	53.6	51.9	50.5	43.7	42.0	40.2	48.2	46.7	45.2	43.6	16
32	55.2	53.6	51.9	50.3	48.9	42.3	40.7	39.0	46.7	45.2	43.7	42.3	17
33	53.5	51.9	50.4	48.8	47.4	41.0	39.4	37.8	45.3	43.8	42.4	41.0	18
34	51.9	50.4	48.9	47.3	46.0	39.8	38.3	36.7	43.9	42.6	41.2	39.8	19
35	50.5	49.0	47.5	46.0	44.7	38.7	37.2	35.6	42.7	41.3	40.0	38.6	20
36	49.1	47.6	46.2	44.7	43.4	37.6	36.1	34.7	41.5	40.2	38.9	37.6	21
37	47.7	46.3	44.9	43.5	42.3	36.6	35.2	33.7	40.4	39.1	37.8	36.6	22
38	46.5	45.1	43.7	42.3	41.2	35.6	34.2	32.8	39.3	38.1	36.8	35.6	23
39	45.3	43.9	42.6	41.3	40.1	34.7	33.4	32.0	...	...	...	...	24
40	44.1	42.8	41.5	40.2	39.1	33.8	32.5	31.2	...	...	...	...	25
41	43.1	41.8	40.5	39.2	38.1	33.0	31.7	30.4	...	...	...	...	26
42	42.0	40.8	39.6	38.3	37.2	32.2	31.0	29.7	...	...	...	...	27

Loads above the upper heavy lines will cause maximum allowable shear webs. See, also, paragraphs in text and foot-note with same, page 567, re to web-buckling in beams

Loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

# Tables of Safe Loads for Steel Beams and Girders

**Table IV - (Continued). Safe Uniform Loads in Units of 1 000 Pound for Steel I Beams**

Maximum bending stress, 16 000 lb per sq in. Beams secured against yielding at ends.

Span, ft	Depth and weight of sections												
	18-in					15-in							
	70 lb	65 lb	60 lb	54.7 lb	48.2 lb	75 lb	70 lb	65 lb	60.8 lb	55 lb	50 lb	45 lb	42.9 lb
4	251.8	229.9	209.8	...	...	261.6	...	...	...	196.8	...	...	...
5	218.4	208.9	199.5	...	...	245.8	235.2	205.8	177.0	181.7	167.4	148.0	...
6	...	...	...	165.6	...	196.6	188.8	180.9	173.2	145.4	137.5	129.7	121.0
7	182.0	174.1	166.3	157.1	136.8	163.8	157.3	150.8	144.4	121.1	114.6	108.1	104.7
8	156.0	149.2	142.5	134.7	124.8	140.4	134.8	129.2	123.7	103.8	98.2	92.6	89.8
9	136.5	130.6	124.7	117.9	109.2	122.9	118.0	113.1	108.3	90.8	85.9	81.0	78.5
10	121.3	116.1	110.9	104.8	97.1	109.2	104.9	100.5	96.2	80.8	76.4	72.0	69.8
11	109.2	104.5	99.8	94.3	87.4	98.3	94.4	90.5	86.6	72.7	68.8	64.8	62.8
12	99.3	95.0	90.7	85.7	79.4	89.4	85.8	82.2	78.7	66.1	62.5	58.9	57.1
13	91.0	87.1	83.1	78.6	72.8	81.9	78.7	75.4	72.2	60.6	57.3	54.0	52.4
14	84.0	80.4	76.7	72.5	67.2	75.6	72.6	69.6	66.6	55.9	52.9	49.9	48.3
15	78.0	74.6	71.3	67.3	62.4	70.2	67.4	64.6	61.9	51.9	49.1	46.3	44.9
16	72.8	69.6	66.5	62.9	58.2	65.5	62.9	60.3	57.7	48.5	45.8	43.2	41.9
17	68.2	65.3	62.4	58.9	54.6	61.4	59.0	56.5	54.1	45.4	43.0	40.5	39.3
18	64.2	61.5	58.7	55.5	51.4	57.8	55.5	53.2	50.9	42.8	40.4	38.1	37.0
19	60.7	58.0	55.4	52.4	48.5	54.6	52.4	50.3	48.1	40.4	38.2	36.0	34.9
20	57.5	55.0	52.5	49.6	46.0	51.7	49.7	47.6	45.6	38.3	36.2	34.1	33.1
21	54.6	52.2	49.9	47.1	43.7	49.2	47.2	45.2	43.3	36.3	34.4	32.4	31.4
22	52.0	49.7	47.5	44.9	41.6	46.8	44.9	43.1	41.2	34.6	32.7	30.9	29.9
23	49.6	47.5	45.3	42.9	39.7	44.7	42.9	41.1	39.4	33.0	31.3	29.5	28.6
24	47.5	45.4	43.4	41.0	38.0	42.7	41.0	39.3	37.7	31.6	29.9	28.2	27.3
25	45.5	43.5	41.6	39.3	36.4	41.0	39.3	37.7	36.1	30.3	28.6	27.0	26.2
26	43.7	41.8	39.9	37.7	34.9	39.3	37.8	36.2	34.6	29.1	27.5	25.9	25.1
27	42.0	40.2	38.4	36.3	33.6	37.8	36.3	34.8	33.3	28.0	26.4	24.9	24.2
28	40.4	38.7	37.0	34.9	32.4	36.4	35.0	33.5	32.1	26.9	25.5	24.0	23.3
29	39.0	37.3	35.6	33.7	31.2	35.1	33.7	32.3	30.9	26.0	24.6	23.2	22.4
30	37.6	36.0	34.4	32.5	30.1	33.9	32.5	31.2	29.9	25.1	23.7	22.4	21.7
31	36.4	34.8	33.3	31.4	29.1	32.8	31.5	30.2	28.9	24.2	22.9	21.6	20.9
32	35.2	33.7	32.2	30.4	28.2	31.7	30.4	29.2	27.9	23.4	22.2	20.9	20.3
33	34.1	32.6	31.2	29.5	27.3	30.7	29.5	28.3	27.1	22.7	21.5	20.3	19.6
34	33.1	31.7	30.2	28.6	26.5	...	...	...	...	...	...	...	...
35	32.1	30.7	29.3	27.7	25.7	...	...	...	...	...	...	...	...
36	31.2	29.8	28.5	26.9	25.0	...	...	...	...	...	...	...	...
37	30.3	29.0	27.7	26.2	24.3	...	...	...	...	...	...	...	...
38	29.5	28.2	27.0	25.5	23.6	...	...	...	...	...	...	...	...
39	28.7	27.5	26.3	24.8	23.0	...	...	...	...	...	...	...	...

Loads above the upper heavy lines will cause maximum allowable shear. See, also, paragraphs in text and foot-note with same, page 567, relative to web-buckling in beams.

Loads below the lower broken lines will cause excessive deflections.

Table IV \* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel I Beams

Maximum bending stress, 16 000 lb per sq in. Beams secured against yielding sid

Span, ft	Depth and weight of sections												
	15-in	12-in							10-in				
	37.3 lb	55 lb	50 lb	45 lb	40.8 lb	35 lb	31.8 lb	27.9 lb	40 lb	35 lb	30 lb	25.4 lb	22.4 lb
..	...	177.0	...	...	...	...	...	...	147.8	120.4	...	...	...
3	...	190.2	167.8	133.2	...	114.6	...	...	112.8	104.1	91.0	...	...
4	...	142.7	134.8	127.0	110.4	101.5	84.0	...	84.6	78.1	71.6	62.0	...
5	...	114.1	107.9	101.6	95.6	81.2	76.7	...	67.7	62.5	57.2	52.1	50.4
..	90.6	...	...	...	...	...	...	68.2	...	...	...	...	48.5
6	96.1	95.1	89.9	84.7	79.7	67.6	63.9	59.1	56.4	52.1	47.7	43.4	40.4
7	82.4	81.5	77.0	72.6	68.3	58.0	54.8	50.6	48.4	44.6	40.9	37.2	34.6
8	72.1	71.3	67.4	63.5	59.8	50.7	48.0	44.3	42.3	39.0	35.8	32.6	30.3
9	64.1	63.4	59.9	56.4	53.1	45.1	42.6	39.4	37.6	34.7	31.8	28.9	26.9
10	57.7	57.1	53.9	50.8	47.8	40.6	38.4	35.5	33.9	31.2	28.6	26.0	24.2
11	52.4	51.9	49.0	46.2	43.5	36.9	34.9	32.2	30.8	28.4	26.0	23.7	22.0
12	48.1	47.6	44.9	42.3	39.8	33.8	32.0	29.5	28.2	26.0	23.9	21.7	20.2
13	44.4	43.9	41.5	39.1	36.8	31.2	29.5	27.3	26.0	24.0	22.0	20.0	18.6
14	41.2	40.8	38.5	36.3	34.2	29.0	27.4	25.3	24.2	22.3	20.4	18.6	17.3
15	38.4	38.0	36.0	33.9	31.9	27.1	25.6	23.6	22.6	20.8	19.1	17.4	16.2
16	36.0	35.7	33.7	31.7	29.9	25.4	24.0	22.2	21.2	19.5	17.9	16.3	15.1
17	33.9	33.6	31.7	29.9	28.1	23.9	22.6	20.9	19.9	18.4	16.8	15.3	14.3
18	32.0	31.7	30.0	28.2	26.6	22.5	21.3	19.7	18.8	17.4	15.9	14.5	13.5
19	30.4	30.0	28.4	26.7	25.2	21.4	20.2	18.7	17.8	16.4	15.1	13.7	12.8
20	28.8	28.5	27.0	25.4	23.9	20.3	19.2	17.7	16.9	15.6	14.3	13.0	12.1
21	27.5	27.2	25.7	24.2	22.8	19.3	18.3	16.9	16.1	14.9	13.6	12.4	11.5
22	26.2	25.9	24.5	23.1	21.7	18.4	17.4	16.1	15.4	14.2	13.0	11.8	11.0
23	25.1	24.8	23.4	22.1	20.8	17.6	16.7	15.4	...	...	...	...	...
24	24.0	23.8	22.5	21.2	19.9	16.9	16.0	14.8	...	...	...	...	...
25	23.1	22.8	21.6	20.3	19.1	16.2	15.3	14.2	...	...	...	...	...
26	22.2	21.9	20.7	19.5	18.4	15.6	14.8	13.6	...	...	...	...	...
27	21.4	...	...	...	...	...	...	...	...	...	...	...	...
28	20.6	...	...	...	...	...	...	...	...	...	...	...	...
29	19.9	...	...	...	...	...	...	...	...	...	...	...	...
30	19.2	...	...	...	...	...	...	...	...	...	...	...	...
31	18.6	...	...	...	...	...	...	...	...	...	...	...	...
32	18.0	...	...	...	...	...	...	...	...	...	...	...	...

Loads above the upper heavy lines will cause maximum allowable shear webs. See, also, paragraphs in text and foot-note with same, page 567, rels to web-buckling in beams.

Loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table IV • (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel I Beams

Maximum bending stress 16 000 lb per sq in. Beams secured against yielding sidewise

Span, ft	Depth and weight of sections												Coeffi- cient of deflec- tion
	9-in				8-in					7-in			
	35 lb	30 lb	25 lb	21.8 lb	25.5 lb	23 lb	20.5 lb	18.4 lb	17.5 lb	20 lb	17.75 lb	15.3 lb	
....	131.8	102.4	73.1	...	81.6	71.8	57.8	...	...	61.1	49.4	...	.....
3	88.3	80.5	72.6	57.2	60.8	57.3	53.9	43.2	...	42.9	39.8	35.0	0.15
4	66.2	60.4	54.5	50.3	45.6	43.0	40.4	37.9	35.2	32.1	29.9	27.6	0.27
5	53.0	48.3	43.6	40.3	36.5	34.4	32.3	30.3	31.1	25.7	23.9	22.1	0.41
6	44.2	40.2	36.3	33.6	30.4	28.7	26.9	25.3	25.9	21.4	19.9	18.4	0.60
7	37.9	34.5	31.1	28.8	26.1	24.6	23.1	21.7	22.2	18.4	17.1	15.8	0.81
8	33.1	30.2	27.2	25.2	22.8	21.5	20.2	19.0	19.5	16.1	14.9	13.8	1.06
9	29.4	26.8	24.2	22.4	20.3	19.1	18.0	16.9	17.3	14.3	13.3	12.3	1.34
10	26.5	24.1	21.8	20.1	18.2	17.2	16.2	15.2	15.6	12.9	11.9	11.0	1.66
11	24.1	22.0	19.8	18.3	16.6	15.6	14.7	13.8	14.2	11.7	10.9	10.0	2.00
12	22.1	20.1	18.2	16.8	15.2	14.3	13.5	12.6	13.0	10.7	10.0	9.2	2.38
13	20.4	18.6	16.8	15.5	14.0	13.2	12.4	11.7	12.0	9.9	9.2	8.5	2.80
14	18.9	17.2	15.6	14.4	13.0	12.3	11.5	10.8	11.1	9.2	8.5	7.9	3.24
15	17.7	16.1	14.5	13.4	12.2	11.5	10.8	10.1	10.4	8.6	8.0	7.4	3.72
16	16.6	15.1	13.6	12.6	11.4	10.8	10.1	9.5	9.7	8.0	7.5	6.9	4.24
17	15.6	14.2	12.8	11.8	10.7	10.1	9.5	8.9	9.2	...	...	...	4.78
18	14.7	13.4	12.1	11.2	10.1	9.6	9.0	8.4	8.6	...	...	...	5.36
19	13.9	12.7	11.5	10.6	...	...	...	...	...	...	...	...	5.98
20	13.3	12.1	10.9	10.1	...	...	...	...	...	...	...	...	6.62

Span, ft	Depth and weight of sections													Coeffi- cient of deflec- tion
	6-in			5-in			4-in				3-in			
	17½ lb	14¾ lb	12½ lb	14¾ lb	12½ lb	10 lb	10½ lb	9½ lb	8½ lb	7.7 lb	7½ lb	6½ lb	5.7 lb	
.....	...	...	...	...	...	...	...	...	...	...	21.7	...	...	.....
1	57.0	...	...	50.4	35.7	...	32.8	27.0	21.0	...	20.7	15.8	10.2	0.02
2	46.6	42.2	27.6	32.3	29.1	21.0	19.0	18.0	16.9	15.1	10.4	9.6	8.8	0.07
3	31.0	28.4	25.8	21.5	19.4	17.2	12.7	12.0	11.3	10.6	6.9	6.4	5.9	0.15
4	23.3	21.3	19.4	16.2	14.5	12.9	9.5	9.0	8.5	8.0	5.2	4.8	4.4	0.27
5	18.6	17.1	15.5	12.9	11.6	10.3	7.6	7.2	6.8	6.4	4.1	3.8	3.5	0.41
6	15.5	14.2	12.9	10.8	9.7	8.6	6.3	6.0	5.6	5.3	3.5	3.2	2.9	0.60
7	13.3	12.2	11.1	9.2	8.3	7.4	5.4	5.1	4.8	4.5	3.0	2.7	2.5	0.81
8	11.6	10.7	9.7	8.1	7.3	6.4	4.8	4.5	4.2	4.0	2.6	2.4	2.2	1.06
9	10.3	9.5	8.6	7.2	6.5	5.7	4.2	4.0	3.8	3.5	..	..	..	1.34
10	9.3	8.5	7.7	6.5	5.8	5.2	3.8	3.6	3.4	3.2	..	..	..	1.66
11	8.5	7.8	7.0	5.9	5.3	4.7	...	..	..	..	..	..	..	2.00
12	7.8	7.1	6.5	5.4	4.8	4.3	...	..	..	..	..	..	..	2.38
13	7.2	6.6	6.0	...	...	...	...	..	..	..	..	..	..	2.80
14	6.7	6.1	5.5	...	...	...	...	..	..	..	..	..	..	3.24

Loads above the upper heavy lines will cause maximum allowable shears in webs. See, also, paragraphs in text and foot-note with same, page 567, relating to web-buckling in beams

Loads below the lower broken lines will cause excessive deflections

Table V.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel Channels

Maximum bending stress, 16 000 lb per sq in. Beams secured against yielding

Span, ft	Depth and weight of sections												Co eff of defl
	15-in						13-in						
	55 lb	50 lb	45 lb	40 lb	35 lb	33.9 lb	50 lb	45 lb	40 lb	37 lb	35 lb	31.8 lb	
....	245.4	216.0	186.0	...	...	...	205.7	176.3	...	...	...	...	...
3	204.0	190.9	177.8	157.3	127.8	120.0	171.6	160.3	146.9	122.2	117.5	97.5	0
4	153.0	143.2	133.4	123.6	113.8	111.1	128.7	120.2	111.7	106.6	103.2	97.5	0
5	122.4	114.5	106.7	98.9	91.0	88.9	103.0	96.2	89.4	85.3	82.6	78.0	0
6	102.0	95.4	88.9	82.4	75.8	74.1	85.8	80.2	74.5	71.1	68.8	65.0	0
7	87.4	81.8	76.2	70.6	65.0	63.5	73.6	68.7	63.8	60.9	59.0	55.7	0
8	76.5	71.6	66.7	61.8	56.9	55.6	64.4	60.1	55.9	53.3	51.6	48.7	1
9	68.0	63.6	59.3	54.9	50.6	49.4	57.2	53.4	49.7	47.4	45.9	43.3	1
10	61.2	57.3	53.3	49.4	45.5	44.5	51.5	48.1	44.7	42.7	41.3	39.0	1
11	55.6	52.1	48.5	44.9	41.4	40.4	46.8	43.7	40.6	38.8	37.5	35.4	2
12	51.0	47.7	44.5	41.2	37.9	37.0	42.9	40.1	37.2	35.5	34.4	32.5	2
13	47.1	44.1	41.0	38.0	35.0	34.2	39.6	37.0	34.4	32.8	31.8	30.0	2
14	43.7	40.9	38.1	35.3	32.5	31.8	35.8	34.4	31.9	30.5	29.5	27.9	3
15	40.8	38.2	35.6	33.0	30.3	29.6	34.3	32.1	29.8	28.4	27.5	26.0	3
16	38.2	35.8	33.3	30.9	28.4	27.8	32.2	30.1	27.9	26.7	25.8	24.4	4
17	36.0	33.7	31.4	29.1	26.8	26.1	30.3	28.3	26.3	25.1	24.3	22.9	4
18	34.0	31.8	29.6	27.5	25.3	24.7	28.6	26.7	24.8	23.7	22.9	21.7	5
19	32.2	30.1	28.1	26.0	23.9	23.4	27.1	25.3	23.5	22.4	21.7	20.5	5
20	30.6	28.6	26.7	24.7	22.8	22.3	25.7	24.0	22.3	21.3	20.6	19.5	6
21	29.1	27.3	25.4	23.5	21.7	21.2	24.5	22.9	21.3	20.3	19.7	18.6	7
22	27.8	26.0	24.3	22.5	20.7	20.2	23.4	21.9	20.3	19.4	18.8	17.7	8
23	26.6	24.9	23.2	21.5	19.8	19.3	22.4	20.9	19.4	18.5	18.0	17.0	8
24	25.5	23.9	22.2	20.6	19.0	18.5	21.5	20.0	18.6	17.8	17.2	16.2	9
25	24.5	22.9	21.3	19.8	18.2	17.8	20.6	19.2	17.9	17.1	16.5	15.6	10
26	23.5	22.0	20.5	19.0	17.5	17.1	19.8	18.5	17.2	16.4	15.9	15.0	11
27	22.7	21.2	19.8	18.3	16.9	16.5	19.1	17.8	16.6	15.8	15.3	14.4	12
28	21.9	20.5	19.1	17.7	16.3	15.9	18.4	17.2	16.0	15.2	14.7	13.9	12
29	21.1	19.7	18.4	17.0	15.7	15.3	...	...	...	...	...	...	13
30	20.4	19.1	17.8	16.5	15.2	14.8	...	...	...	...	...	...	14
31	19.7	18.5	17.2	15.9	14.7	14.3	...	...	...	...	...	...	15
32	19.1	17.9	16.7	15.4	14.2	13.9	...	...	...	...	...	...	16

Loads above the upper heavy lines will cause maximum allowable shear webs. See, also, paragraphs in text and foot-note with same, page 567, re: web-buckling in beams

Loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



Table V • (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel Channels

Minimum bending stress, 16 000 lb per sq in. Beams secured against yielding sideways

Span, ft	Depth and weight of sections										Coeffi- cient of deflec- tion
	12-in					10-in					
	40 lb	35 lb	30 lb	25 lb	20.7 lb	35 lb	30 lb	25 lb	20 lb	15.3 lb	
1	181.9	.....	.....	.....	.....	164.6	135.2	103.8	.....	.....	.....
2	175.1	152.6	127.1	97.6	.....	123.2	110.1	97.0	76.4	49.0	0.07
3	116.7	106.2	95.8	85.3	67.2	82.1	73.4	64.7	56.0	47.6	0.15
4	87.5	79.7	71.8	64.0	56.9	61.6	55.1	48.5	42.6	35.7	0.27
5	70.0	63.7	57.5	51.2	45.5	49.3	44.0	38.8	33.6	28.5	0.41
6	58.4	53.1	47.9	42.7	38.0	41.1	36.7	32.3	28.0	23.8	0.60
7	50.0	45.5	41.1	36.6	32.5	35.2	31.5	27.7	24.0	20.4	0.81
8	43.8	39.8	35.9	32.0	28.5	30.8	27.5	24.3	21.0	17.8	1.06
9	38.9	35.4	31.9	28.4	25.3	27.4	24.5	21.6	18.7	15.9	1.34
10	35.0	31.9	28.7	25.6	22.8	24.6	22.0	19.4	16.8	14.3	1.66
11	31.8	29.0	26.1	23.3	20.7	22.4	20.0	17.6	15.3	13.0	2.00
12	29.2	26.6	23.9	21.3	19.0	20.5	18.4	16.2	14.0	11.9	2.38
13	26.9	24.5	22.1	19.7	17.5	19.0	16.9	14.9	12.9	11.0	2.80
14	25.0	22.8	20.5	18.3	16.3	17.6	15.7	13.9	12.0	10.2	3.24
15	23.3	21.2	19.2	17.1	15.2	16.4	14.7	12.9	11.2	9.5	3.72
16	21.9	19.9	18.0	16.0	14.2	15.4	13.8	12.1	10.5	8.9	4.24
17	20.6	18.7	16.9	15.1	13.4	14.5	13.0	11.4	9.9	8.4	4.78
18	19.5	17.7	16.0	14.2	12.7	13.7	12.2	10.8	9.3	7.9	5.36
19	18.4	16.8	15.1	13.5	12.0	13.0	11.6	10.2	8.8	7.5	5.98
20	17.5	15.9	14.4	12.8	11.4	12.3	11.0	9.7	8.4	7.1	6.62
21	16.7	15.2	13.7	12.2	10.8	11.7	10.5	9.2	8.0	6.8	7.30
22	15.9	14.5	13.1	11.6	10.4	11.2	10.0	8.8	7.6	6.5	8.01
23	15.2	13.9	12.5	11.1	9.9	.....	.....	.....	.....	.....	8.76
24	14.6	13.3	12.0	10.7	9.5	.....	.....	.....	.....	.....	9.53
25	14.0	12.8	11.5	10.2	9.1	.....	.....	.....	.....	.....	10.35
26	13.5	12.3	11.1	9.8	8.8	.....	.....	.....	.....	.....	11.19

Loads above the upper heavy lines will cause maximum allowable shears in webs. See, also, paragraphs in text and foot-note with same, page 567, relating to web-buckling in beams.

Loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table V\* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel Channels**

assuming bending stress, 16 000 lb per sq in. Beams secured against yielding sideways

Sections													Coefficient of deflection
7-in													
3 1/2	10 1/2	17 1/2	24 1/2	31 1/2	38 1/2	45 1/2	52 1/2	59 1/2	66 1/2	73 1/2	80 1/2	87 1/2	
lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	
88.6	71.1	59.2	47.9	36.8	27.4	19.2	14.4	10.8	8.6	7.1	5.9	4.8	0.07
55.9	48.0	40.2	37.4	31.8	29.2	26.6	24.0	21.5	20.2	18.4	16.7	15.1	0.15
41.9	36.0	30.1	28.0	25.5	23.4	21.3	19.2	17.2	16.9	15.3	13.8	12.3	0.27
33.5	28.8	24.1	22.4	20.5	19.5	17.7	16.0	14.4	13.1	11.8	10.5	9.2	0.41
27.9	24.0	20.1	18.7	16.7	15.2	13.7	12.3	11.4	10.2	9.2	8.2	7.1	0.60
23.9	20.6	17.3	16.0	14.6	13.3	12.0	10.8	10.2	9.2	8.2	7.1	6.0	0.81
20.9	18.0	15.1	14.0	12.8	11.8	10.7	9.6	8.6	7.7	6.7	5.8	5.0	1.06
18.6	16.0	13.4	12.5	11.2	10.6	9.6	8.6	7.7	6.7	5.8	5.0	4.3	1.34
16.8	14.4	12.1	11.2	10.2	9.7	8.7	7.8	6.9	6.0	5.2	4.6	4.0	1.66
15.2	13.1	11.0	10.2	9.3	8.6	7.8	7.0	6.3	5.5	4.9	4.3	3.7	2.00
14.0	12.0	10.1	9.3	8.6	7.8	7.0	6.3	5.5	4.9	4.3	3.7	3.1	2.38
12.9	11.1	9.3	8.6	7.8	7.0	6.3	5.5	4.9	4.3	3.7	3.1	2.6	2.80
12.0	10.3	8.6	8.0	7.1	6.4	5.7	5.0	4.4	3.8	3.2	2.6	2.1	3.24
11.2	9.6	8.0	7.5	6.5	5.8	5.1	4.4	3.8	3.2	2.6	2.1	1.7	3.72
10.5	9.0	7.5	7.0	6.0	5.3	4.6	4.0	3.4	2.8	2.2	1.7	1.4	4.24
9.9	8.5	7.1	6.6	5.5	4.8	4.1	3.5	2.9	2.3	1.8	1.4	1.1	4.78
9.3	8.0	6.7	6.2	5.1	4.4	3.7	3.1	2.5	2.0	1.5	1.1	0.9	5.36
8.8	7.6	6.3	5.9	4.8	4.1	3.4	2.8	2.2	1.7	1.3	0.9	0.7	5.98
8.4	7.2	6.0	5.6	4.5	3.8	3.1	2.5	2.0	1.5	1.1	0.8	0.6	6.66

**Depth and weight of sections**

6-in				5-in			4-in			3-in			Coefficient of deflection
15 1/2	13	10 1/2	8.2	11 1/2	9	6 7/8	7 1/2	6 1/2	5 1/2	5	4 1/2	4.1	
lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	lb	
67.6	52.8	38.7	24.0	47.7	33.0	19.0	26.0	21.4	17.2	14.7	13.1	10.8	0.08
34.7	30.8	26.9	23.1	22.2	18.9	15.8	12.2	11.1	10.1	7.4	6.6	5.8	0.07
23.2	20.5	17.9	15.4	14.8	12.6	10.5	8.1	7.4	6.7	4.9	4.4	3.9	0.15
17.4	15.4	13.4	11.6	11.1	9.5	7.9	6.1	5.6	5.1	3.7	3.3	2.9	0.27
13.9	12.3	10.8	9.2	8.9	7.6	6.3	4.9	4.5	4.1	2.9	2.6	2.3	0.41
11.6	10.3	9.0	7.7	7.4	6.3	5.3	4.1	3.7	3.4	2.5	2.2	1.9	0.60
9.9	8.8	7.7	6.6	6.3	5.4	4.5	3.5	3.2	2.9	2.1	1.9	1.7	0.81
8.7	7.7	6.7	5.8	5.5	4.7	4.0	3.0	2.8	2.5	1.8	1.6	1.5	1.06
7.7	6.8	6.0	5.1	4.9	4.2	3.5	2.7	2.5	2.2	1.6	1.4	1.3	1.34
6.9	6.2	5.4	4.6	4.4	3.8	3.2	2.4	2.2	2.0	1.4	1.2	1.1	1.66
6.3	5.6	4.9	4.2	4.0	3.4	2.9	2.1	1.9	1.7	1.2	1.0	0.9	2.00
5.8	5.1	4.5	3.9	3.7	3.2	2.6	1.9	1.7	1.5	1.1	0.9	0.8	2.38
5.3	4.7	4.1	3.6	3.4	2.9	2.4	1.8	1.6	1.4	1.0	0.8	0.7	2.80
5.0	4.4	3.8	3.3	3.1	2.7	2.2	1.7	1.5	1.3	0.9	0.7	0.6	3.24

loads above the upper heavy lines will cause maximum allowable shears in beams

See, also, paragraphs in text and foot-note with same, page 567, relation to buckling in beams

loads below the lower broken lines will cause excessive deflections

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table VI.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel H Beams**

Maximum bending stress, 16 000 lb per sq in. Secured against yielding sidewise

Span, ft	Depth and weight of sections				Coefficients of deflection
	8-in 34.3-lb	6-in 24.1-lb	5-in 18.9-lb	4-in 13.8-lb	
.....	.....	.....	.....	25.0	.....
3	.....	.....	21.3	19.0	0.15
4	.....	27.6	25.4	14.3	0.27
5	.....	32.1	20.3	11.4	0.41
.....	60.0	.....	.....	.....	.....
6	51.3	26.7	16.9	9.5	0.60
7	44.0	22.9	14.5	8.1	0.81
8	38.5	20.1	12.7	7.1	1.06
9	34.2	17.8	11.3	6.3	1.34
10	30.8	16.0	10.1	5.7	1.66
11	28.0	14.6	9.2	.....	2.00
12	25.6	13.4	8.5	.....	2.38
13	23.7	12.3	.....	.....	2.80
14	22.0	11.5	.....	.....	3.24
15	20.5	.....	.....	.....	3.72
16	19.2	.....	.....	.....	4.24
17	18.1	.....	.....	.....	4.78
18	17.1	.....	.....	.....	5.36

**Table VII.† Safe Uniform Loads in Pounds for Small Steel Channels, or Grooved Steel**Computed for a fiber-stress of 16 000 lb per sq in  
Secured against yielding sidewise

Section- number	Depth, in	Weight per foot, lb	Span in feet							
			2	2.5	3	3.5	4	4.5	5	6
1	2½	3.80	3 785	3 028	2 523	2 163	1 892	1 682	1 514	1 261
2	2	2.90	2 560	2 048	1 706	1 463	1 280	1 138	1 024	853
3	2	3.60	2 880	2 304	1 920	1 643	1 440	1 280	1 152	960
4	2	3.60	3 120	2 496	2 080	1 783	1 560	1 386	1 248	1 040
5	2	2.60	2 256	1 804	1 504	1 289	1 128	1 000	902	752
6	2	2.00	1 418	1 134	945	810	709	630	567	472
7	1¾	1.13	907	726	605	518	454	403	363	302
8	1½	1.32	768	614	512	439	384	341	307	256
9	1½	1.46	868	694	578	496	434	386	347	286
10	1¼	0.94	475	380	316	271	237	211	190	....
11	1¾	1.12	469	375	313	268	234	208	188	....
12	1¾	1.00	437	350	291	250	218	194	175	....
13	1	0.83	336	268	224	192	168	....	....	....
14	1	0.68	266	212	177	152	133	....	....	....
15	¾	0.67	224	180	149	128	112	....	....	....
16	¾	0.69	229	183	152	130	....	....	....	....
17	¾	0.53	133	106	88	....	....	....	....	....

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† Compiled by F. E. Kidder. See note on page 570.

**Table VIII.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel Angles with Equal Legs. (See page 566.)**

Neutral Axis Parallel to Either Leg

Maximum bending stress, 16 000 lb per sq in. Secured against yielding sidewise

in	in	Safe load	Maximum span, 360 × deflection		Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection	
			Safe load	Length, ft				Safe load	Length, ft
		186.99	8.31	22.5	3½×3½	1½	24.00	2.55	9.4
		177.81	7.87	22.6	3½×3½	¾	22.51	2.37	9.5
		168.53	7.43	22.7	3½×3½	1½	20.91	2.18	9.6
		159.15	6.98	22.8	3½×3½	¾	19.31	2.00	9.7
		149.55	6.53	22.9	3½×3½	¾	17.60	1.81	9.7
		139.84	6.08	23.0	3½×3½	¾	15.89	1.62	9.8
		130.03	5.63	23.1	3½×3½	¾	14.08	1.42	9.9
		120.00	5.18	23.2	3½×3½	¾	12.27	1.23	10.0
		109.87	4.73	23.2	3½×3½	¾	10.45	1.04	10.1
		99.63	4.28	23.3	3½×3½	¾	8.43	0.83	10.2
		89.28	3.83	23.4	3×3	¾	13.87	1.69	8.2
					3×3	¾	12.69	1.53	8.3
					3×3	¾	11.41	1.37	8.3
					3×3	¾	10.13	1.21	8.4
		91.41	5.48	16.7	3×3	¾	8.85	1.04	8.5
		86.51	5.16	16.8	3×3	¾	7.57	0.88	8.6
		81.39	4.84	16.8	3×3	¾	6.19	0.71	8.7
		76.27	4.51	16.9					
		71.04	4.18	17.0	2½×2½	¾	7.79	1.15	6.8
		65.81	3.85	17.1	2½×2½	¾	6.93	1.01	6.9
6×6	¾	60.37	3.51	17.2	2½×2½	¾	6.08	0.87	7.0
6×6	¾	54.83	3.17	17.3	2½×2½	¾	5.12	0.72	7.1
6×6	¾	49.17	2.83	17.4	2½×2½	¾	4.16	0.58	7.2
6×6	¾	43.41	2.48	17.5	2½×2½	¾	3.20	0.44	7.3
6×6	¾	37.65	2.14	17.6	2½×2½	¾	2.23	0.29	7.4
					2×2	¾	4.27	0.79	5.4
5×5	1	61.87	4.55	13.6	2×2	¾	3.73	0.68	5.5
5×5	1½	58.56	4.28	13.7	2×2	¾	3.20	0.57	5.6
5×5	¾	55.15	4.00	13.8	2×2	¾	2.67	0.46	5.7
5×5	1½	51.73	3.73	13.9	2×2	¾	2.03	0.35	5.8
5×5	¾	48.32	3.45	14.0			1.39	0.24	5.8
5×5	1½	44.80	3.18	14.1	1¾×1¾	¾	3.20	0.68	4.7
5×5	¾	41.17	2.90	14.2	1¾×1¾	¾	2.77	0.60	4.7
5×5	¾	37.44	2.62	14.3	1¾×1¾	¾	2.45	0.51	4.8
5×5	¾	33.60	2.34	14.4	1¾×1¾	¾	2.03	0.41	4.9
5×5	¾	29.76	2.06	14.5	1¾×1¾	¾	1.49	0.30	5.0
5×5	¾	25.81	1.78	14.5	1¾×1¾	¾	1.07	0.21	5.1
					1½×1½	¾	2.03	0.51	4.0
					1½×1½	¾	1.71	0.42	4.1
4×4	1½	32.11	2.95	10.9	1½×1½	¾	1.39	0.33	4.2
4×4	¾	29.97	2.73	11.0	1½×1½	¾	1.07	0.25	4.3
4×4	1½	27.84	2.51	11.1	1½×1½	¾	0.77	0.17	4.4
4×4	¾	25.60	2.29	11.2	1¼×1¼	¾	1.17	0.36	3.3
4×4	¾	23.26	2.07	11.3	1¼×1¼	¾	0.97	0.29	3.4
4×4	¾	21.01	1.85	11.4	1¼×1¼	¾	0.76	0.22	3.5
4×4	¾	18.67	1.63	11.4	1¼×1¼	¾	0.52	0.14	3.6
4×4	¾	16.21	1.41	11.5					
4×4	¾	13.76	1.19	11.6	1×1	¾	0.60	0.22	2.6
4×4	¾	11.20	0.96	11.7	1×1	¾	0.47	0.17	2.7
					1×1	¾	0.33	0.12	2.8

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table IX.\* Safe Uniform Loads in Units of 1 000 Pounds of Steel Angles with Unequal Legs. (See page 566.)

Neutral Axis Parallel to Shorter Leg

Bending stress, 16 000 lb per sq in. Secured against yielding sidewise

Size, in	k- ness, in	1-ft span	Maximum span, 360 × deflection		Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection	
		Safe load	Safe load	Length, ft			Safe load	Safe load	Length, ft
	1	161.17	7.49	21.5	6×3½	1	83.52	5.57	15.0
	1½	152.21	7.04	21.6	6×3½	1½	79.04	5.24	15.1
	¾	143.04	6.59	21.7	6×3½	¾	74.45	4.90	15.2
	1¾	133.87	6.14	21.8	6×3½	1¾	69.87	4.57	15.3
	¾	124.48	5.68	21.9	6×3½	¾	65.07	4.23	15.4
	1½	114.88	5.22	22.0	6×3½	1½	60.27	3.89	15.5
	¾	105.28	4.76	22.1	6×3½	¾	55.36	3.55	15.6
	1½	95.47	4.30	22.2	6×3½	1½	50.35	3.21	15.7
	¾	85.55	3.84	22.3	6×3½	¾	45.23	2.86	15.8
	1½	75.41	3.37	22.4	6×3½	1½	40.00	2.52	15.9
	1	146.03	7.53	19.4	6×3½	¾	34.67	2.17	16.0
	1½	138.03	7.08	19.5		1½	29.23	1.83	16.0
6×3½	¾	129.92	6.63	19.6					
6×3½	1½	121.60	6.17	19.7	5×4	¾	53.23	4.00	13.3
6×3½	¾	113.17	5.72	19.8	5×4	1½	50.03	3.73	13.4
6×3½	1½	104.58	5.23	19.9	5×4	¾	46.61	3.46	13.5
6×3½	¾	95.79	4.78	20.0	5×4	1½	43.20	3.19	13.5
6×3½	1½	86.93	4.32	20.1	5×4	¾	39.79	2.92	13.6
6×3½	¾	77.97	3.86	20.2	5×4	1½	36.16	2.65	13.7
6×3½	1½	68.80	3.39	20.3	5×4	¾	32.53	2.38	13.8
	1	112.85	6.52	17.3	5×4	1½	28.80	2.07	13.9
6×3½	1½	106.67	6.13	17.4	5×4	¾	24.96	1.76	14.0
6×3½	¾	100.48	5.75	17.5					
6×3½	1½	94.08	5.36	17.6	5×3½	¾	52.05	4.04	12.9
6×3½	¾	87.68	4.97	17.6	5×3½	1½	48.85	3.76	13.0
6×3½	1½	81.07	4.58	17.7	5×3½	¾	45.65	3.49	13.1
6×3½	¾	74.35	4.18	17.8	5×3½	1½	42.35	3.21	13.2
6×3½	1½	67.52	3.77	17.9	5×3½	¾	38.93	2.93	13.3
6×3½	¾	60.59	3.37	18.0	5×3½	1½	35.41	2.64	13.4
6×3½	1½	53.44	2.96	18.1	5×3½	¾	31.89	2.36	13.5
6×3½	¾	46.19	2.54	18.2	5×3½	1½	28.16	2.07	13.6
	1	85.55	5.56	15.4	5×3½	¾	24.43	1.79	13.7
6×4	1½	80.96	5.22	15.5	5×3½	1½	20.69	1.51	13.7
6×4	¾	76.27	4.89	15.6	5×3	1½	47.47	3.77	12.6
6×4	1½	71.47	4.55	15.7	5×3	¾	44.37	3.49	12.7
6×4	¾	66.67	4.20	15.8	5×3	1½	41.17	3.20	12.8
6×4	1½	61.65	3.88	15.9	5×3	¾	37.87	2.94	12.9
6×4	¾	56.64	3.54	16.0	5×3	1½	34.45	2.65	13.0
6×4	1½	51.52	3.20	16.1	5×3	¾	31.04	2.37	13.1
6×4	¾	46.19	2.85	16.2	5×3	1½	27.52	2.09	13.2
6×4	1½	40.85	2.51	16.3	5×3	¾	23.89	1.80	13.3
6×4	¾	35.41	2.16	16.4	5×3	1½	20.16	1.51	13.4

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table IX \* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel Angles with Unequal Legs. (See page 566.)**

**Neutral Axis Parallel to Shorter Leg**

**Maximum bending stress, 16 000 lb per sq in. Secured against yielding sidewi**

Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection		Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection	
		Safe load	Safe load	Length, ft			Safe load	Safe load	Length, ft
4½×3	1¾	38.61	3.36	11.5	3 ×2½	¾	12.27	1.53	
4½×3	¾	36.05	3.11	11.6	3 ×2½	½	11.09	1.37	
4½×3	1¼	33.49	2.87	11.7	3 ×2½	⅞	9.92	1.22	
4½×3	⅝	30.83	2.62	11.8	3 ×2½	¾	8.64	1.06	
4½×3	⅞	28.16	2.38	11.8	3 ×2½	⅝	7.36	0.89	
4½×3	½	25.28	2.13	11.9	3 ×2½	¼	5.97	0.71	
4½×3	⅞	22.40	1.87	12.0					
4½×3	¾	19.52	1.61	12.1	3 ×2	½	10.67	1.39	
4½×3	⅝	16.43	1.35	12.2	3 ×2	⅞	9.49	1.22	
4 ×3½	1¾	31.15	2.94	10.6	3 ×2	¾	8.32	1.05	
4 ×3½	¾	29.23	2.73	10.7	3 ×2	⅝	7.04	0.88	
4 ×3½	1¼	27.20	2.52	10.8	3 ×2	¼	5.76	0.71	
4 ×3½	⅝	25.07	2.30	10.9					
4 ×3½	⅞	22.93	2.08	11.0	2½×2	½	7.47	1.15	
4 ×3½	½	20.69	1.86	11.1	2½×2	⅞	6.72	1.02	
4 ×3½	⅞	18.35	1.64	11.2	2½×2	¾	5.87	0.88	
4 ×3½	¾	16.00	1.41	11.3	2½×2	⅝	5.01	0.74	
4 ×3½	⅝	13.44	1.18	11.4	2½×2	¼	4.05	0.59	
4 ×3	1¾	30.61	2.97	10.3	2½×2	¾	3.09	0.44	
4 ×3	¾	28.59	2.75	10.4	2½×2	⅝	2.13	0.30	
4 ×3	1¼	26.56	2.53	10.5					
4 ×3	⅝	24.53	2.31	10.6	2½×1½	⅝	4.69	0.73	
4 ×3	⅞	22.40	2.09	10.7	2½×1½	¼	3.84	0.59	
4 ×3	½	20.16	1.87	10.8	2½×1½	⅞	2.99	0.45	
4 ×3	⅞	17.92	1.64	10.9					
4 ×3	¾	15.57	1.42	11.0	2½×1½	½	5.76	1.02	
4 ×3	⅝	13.12	1.19	11.0	2½×1½	⅞	5.12	0.90	
4 ×3	¼	10.67	0.96	11.1	2½×1½	¾	4.48	0.77	
3½×3	1¾	23.47	2.57	9.1	2½×1½	⅝	3.84	0.65	
3½×3	¾	21.87	2.38	9.2	2½×1½	¼	3.20	0.53	
3½×3	1¼	20.37	2.19	9.3	2½×1½	⅞	2.45	0.40	
3½×3	⅝	18.77	2.00	9.4					
3½×3	⅞	17.17	1.81	9.5	2 ×1½	¾	3.63	0.70	
3½×3	½	15.47	1.62	9.5	2 ×1½	⅝	3.09	0.58	
3½×3	⅞	13.76	1.43	9.6	2 ×1½	¼	2.56	0.47	
3½×3	¾	12.05	1.24	9.7	2 ×1½	⅞	1.92	0.35	
3½×3	⅝	10.24	1.05	9.8	2 ×1½	¼	1.39	0.24	
3½×3	¼	8.32	0.84	9.9	2 ×1½	⅞	2.45	0.47	
3½×2½	1¾	19.73	2.19	9.0	2 ×1½	¼	1.92	0.36	
3½×2½	¾	18.24	2.00	9.1					
3½×2½	⅞	16.64	1.82	9.1	1¾×1¼	¼	1.92	0.42	
3½×2½	½	15.04	1.63	9.2	1¾×1¼	⅞	1.49	0.32	
3½×2½	⅞	13.44	1.44	9.3	1¾×1¼	¾	1.00	0.21	
3½×2½	¾	11.73	1.24	9.4	1½×1¼	⅝	1.71	0.44	
3½×2½	⅝	9.92	1.04	9.5	1½×1¼	¼	1.39	0.35	
3½×2½	¼	8.00	0.83	9.6	1½×1¼	⅞	1.07	0.26	

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table X.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel Angles with Unequal Legs. (See page 564.)****Neutral Axis Parallel to Longer Leg****Maximum bending stress, 16 000 lb per sq in. Secured against yielding sidewise**

Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection		Size, in	Thick- ness, in	1-ft span	Maximum span, 360 × deflection	
			Safe load	Length, ft				Safe load	Length, ft
6X6	1	95 15	5 44	17.5	6X3½	1			
	1½	89 92	5 11	17 6	6X3½	1½			
	¾	84 69	4 79	17 7	6X3½	¾			
	1¾	79 36	4 45	17 8	6X3½	1¾			
	¾	73 92	4 13	17.9	6X3½	¾			
	1½	68 37	3 80	18 0	6X3½	1½			
	¾	62 72	3 48	18 0	6X3½	¾			
	9/16	56 96	3 15	18 1	6X3½	9/16			
6X6	¾	51 09	2 81	18 2	6X3½	¾			
	3/16	45 12	2 47	18 3	6X3½	3/16			
					6X3½	¾			
					6X3½	9/16			
6X3½	1	32 21	3 10	10 4					
6X3½	9/16	30 40	2 90	10 5					
6X3½	¾	28 69	2 71	10 6					
6X3½	1¾	26 88	2 52	10.7	5X4	¾			
6X3½	¾	25 07	2 33	10.8	5X4	1¾			
6X3½	1¾	23 15	2 13	10.9	5X4	¾			
6X3½	¾	21 33	1 94	11 0	5X4	1¾			
6X3½	9/16	19 41	1 74	11 1	5X4	¾			
6X3½	¾	17 49	1 57	11.2	5X4	9/16			
6X3½	3/16	15 57	1 38	11 3	5X4	¾			
					5X4	3/16			
6X3½	1	31 57	3 10	10.2	5X4	¾			
6X3½	1¾	29 87	2 90	10.3					
6X3½	¾	28 16	2 71	10.4	5X3½	¾			
6X3½	1¾	26.45	2 52	10.5	5X3½	1¾			
6X3½	¾	24.64	2 33	10 6	5X3½	¾			
6X3½	1¾	22.83	2 14	10.7	5X3½	1¾			
6X3½	¾	21.01	1 95	10 8	5X3½	¾			
6X3½	9/16	19 20	1 76	10.9	5X3½	9/16			
6X3½	¾	17.28	1 57	11 0	5X3½	¾			
6X3½	3/16	15 36	1 38	11 1	5X3½	3/16			
6X3½	¾	13 44	1 19	11 2	5X3½	¾			
					5X3½	9/16			
6X4	1	40 43	3 55	11.4					
6X4	1¾	38 29	3 33	11 5					
6X4	¾	36 16	3 12	11.6	5X3	1¾			
6X4	1¾	33 92	2 90	11 7	5X3	¾			
6X4	¾	31.68	2.69	11.8	5X3	1¾			
6X4	1¾	29 44	2 47	11.9	5X3	¾			
6X4	¾	27 09	2 26	12 0	5X3	9/16			
6X4	9/16	24.64	2 05	12 0	5X3	¾			
6X4	¾	22.19	1 84	12.1	5X3	3/16			
6X4	3/16	19.73	1 62	12.2	5X3	¾			
6X4	¾	17.07	1 39	12.3	5X3	9/16			

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Table X\* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Steel Angles with Unequal Legs. (See page 566.)**

**Neutral Axis Parallel to Longer Leg**

**Maximum bending stress, 16 000 lb per sq in. Secured against yielding sideways**

Size, in	Thick- ness, in	1-ft span	Maximum span, 360 X deflection		Size, in	Thick- ness, in	1-ft span	Maximum span, 360 X deflection	
			Safe load	Length, ft				Safe load	Length, ft
4½X3	1¾	18.24	2.15	8.5	3 X2½	¾	8.75	1.25	7
4½X3	¾	17.07	1.99	8.6	3 X2½	½	7.89	1.12	7
4½X3	1¼	15.89	1.83	8.7	3 X2½	⅞	7.04	0.99	7
4½X3	⅝	14.61	1.67	8.8	3 X2½	¾	6.19	0.85	7
4½X3	⅞	13.33	1.51	8.8	3 X2½	⅞	5.23	0.72	7
4½X3	½	12.05	1.35	8.9	3 X2½	¼	4.27	0.58	7
4½X3	⅞	10.77	1.19	9.0					
4½X3	¾	9.39	1.03	9.1	3 X2	½	5.01	0.88	5
4½X3	⅞	8.00	0.87	9.2	3 X2	⅞	4.48	0.77	5
4 X3½	1¾	24.53	2.56	9.6	3 X2	¾	3.95	0.67	5
4 X3½	¾	22.93	2.37	9.7	3 X2	⅞	3.41	0.57	6
4 X3½	1¼	21.33	2.18	9.8	3 X2	¼	2.77	0.46	6
4 X3½	⅝	19.63	1.98	9.9					
4 X3½	⅞	17.92	1.79	10.0	2½X2	½	4.91	0.89	5
4 X3½	½	16.21	1.60	10.1	2½X2	⅞	4.37	0.78	5
4 X3½	⅞	14.40	1.41	10.2	2½X2	¾	3.84	0.67	5
4 X3½	¾	12.59	1.22	10.3	2½X2	⅞	3.31	0.57	5
4 X3½	⅞	10.67	1.03	10.4	2½X2	¼	2.67	0.46	5
4 X3	1¾	17.92	2.15	8.3	2½X2	¾	2.13	0.35	6
4 X3	¾	16.75	1.99	8.4	2½X2	⅞	1.49	0.23	6
4 X3	1¼	15.57	1.83	8.5					
4 X3	⅝	14.40	1.67	8.6	2½X1½	⅞	1.81	0.41	5
4 X3	⅞	13.12	1.51	8.7	2½X1½	¼	1.49	0.33	5
4 X3	½	11.84	1.35	8.8	2½X1½	⅞	1.17	0.25	5
4 X3	⅞	10.56	1.19	8.9					
4 X3	¾	9.28	1.03	8.9	2¼X1½	½	2.77	0.67	5
4 X3	⅞	7.89	0.87	9.0	2¼X1½	⅞	2.45	0.58	5
4 X3	¼	6.40	0.70	9.1	2¼X1½	¾	2.13	0.50	5
3½X3	1¾	17.60	2.17	8.1	2¼X1½	⅞	1.81	0.41	5
3½X3	¾	16.43	2.01	8.2	2¼X1½	¼	1.49	0.33	5
3½X3	1¼	15.36	1.85	8.3	2¼X1½	⅞	1.17	0.25	5
3½X3	⅝	14.19	1.69	8.4					
3½X3	⅞	12.91	1.53	8.5	2 X1½	¾	2.13	0.51	5
3½X3	½	11.73	1.36	8.6	2 X1½	⅞	1.81	0.42	5
3½X3	⅞	10.45	1.20	8.7	2 X1½	¼	1.49	0.34	5
3½X3	¾	9.07	1.04	8.7	2 X1½	⅞	1.17	0.26	5
3½X3	⅞	7.68	0.87	8.8	2 X1½	¼	0.80	0.17	5
3½X3	¼	6.19	0.70	8.9	2 X1½	⅞	1.04	0.28	5
3½X2½	1¼	10.56	1.51	7.0	2 X1½	¼	0.80	0.21	5
3½X2½	⅝	9.81	1.39	7.1	1¾X1¼	¼	1.01	0.28	5
3½X2½	⅞	8.96	1.26	7.1	1¾X1¼	⅞	0.80	0.22	5
3½X2½	½	8.11	1.13	7.2	1¾X1¼	¼	0.56	0.15	5
3½X2½	⅞	7.25	0.99	7.3					
3½X2½	¾	6.29	0.85	7.4	1½X1¼	⅞	1.17	0.34	5
3½X2½	⅞	5.33	0.71	7.5	1½X1¼	¼	0.99	0.28	5
3½X2½	¼	4.37	0.58	7.6	1½X1¼	⅞	0.78	0.22	5

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.



# Tables of Safe Loads for Steel Beams and Girders

**Table XL.\* Safe Uniform Loads in Units of 1 000 Pounds for Steel Tee**  
Neutral Axis Parallel to Flange. (See page 566.)

Maximum bending stress, 16 000 lb per sq in. Secured against yielding sides

## EQUAL FLANGE AND STEM

Size		Weight per foot, lb	1-ft span	Maximum span, 360 × deflec- tion		Size		Weight per foot, lb	1-ft span	Maxim span, × de tic
Flange in	Stem in			Safe load	L'gth ft	Flange in	Stem in			
6½	6½	19.8	52.80	2.77	19.1	2½	2½	4.9	4.37	0.69
4	4	13.5	21.55	1.89	11.4	2½	2½	4.1	3.41	0.53
4	4	10.5	16.85	1.45	11.6	2	2	4.3	3.31	0.59
3½	3½	11.7	16.32	1.65	9.9	2	2	3.56	2.77	0.49
3½	3½	9.2	12.69	1.27	10.0	1¾	1¾	3.09	2.03	0.41
3	3	9.9	11.73	1.41	8.3	1½	1½	2.47	1.49	0.36
3	3	8.9	10.45	1.24	8.4	1½	1½	1.94	1.17	0.27
3	3	7.8	9.17	1.08	8.5	1¾	1¾	2.02	1.01	0.30
3	3	6.7	7.89	0.92	8.6	1¾	1¾	1.59	0.78	0.22
2½	2½	6.4	6.29	0.90	7.0	1	1	1.25	0.49	0.18
2½	2½	5.5	5.33	0.75	7.1	1	1	0.89	0.35	0.12
2½	2½	4.9	4.37	0.69	6.3	....	....	.....	....	...

## UNEQUAL FLANGE AND STEM

Size		Weight per foot, lb	1-ft span	Maximum span, 360 × deflec- tion		Size		Weight per foot, lb	1-ft span	Maxim span, × de tic
Flange in	Stem in			Safe load	L'gth ft	Flange in	Stem in			
5	3	13.4	11.41	1.25	9.1	3½	3	10.8	12.05	1.42
5	2½	10.9	8.96	1.20	7.5	3½	3	8.5	9.49	1.09
4½	3½	15.7	22.72	2.37	9.6	3½	3	7.5	9.07	1.04
4½	3	9.8	9.71	1.07	9.1	3	4	11.7	20.69	1.92
4½	3	8.4	8.32	0.90	9.2	3	4	10.5	18.35	1.68
4½	2½	9.2	6.72	0.87	7.7	3	4	9.2	16.11	1.47
4½	2½	7.8	5.76	0.74	7.8	3	3½	10.8	15.89	1.66
4	5	15.3	33.39	2.40	13.9	3	3½	9.7	14.19	1.46
4	5	11.9	25.92	1.84	14.1	3	3½	8.5	12.37	1.26
4	4½	14.4	27.09	2.13	12.6	3	2½	7.1	6.40	0.89
4	4½	11.2	21.12	1.65	12.8	3	2½	6.1	5.55	0.76
4	3	9.2	9.60	1.08	8.9	2½	3	7.1	8.96	1.08
4	3	7.8	8.21	0.90	9.1	2½	3	6.1	7.68	0.91
4	2½	8.5	6.61	0.87	7.6	2½	1¾	2.87	0.93	0.25
4	2½	7.2	5.65	0.73	7.7	2	1½	3.09	1.60	0.36
4	2	7.8	4.27	0.70	6.1	1½	2	2.45	2.03	0.37
4	2	6.7	3.63	0.59	6.2	1½	1¾	1.25	0.57	0.15
3½	4	12.6	21.12	1.90	11.1	1¾	¾	0.88	0.14	0.07
3½	4	9.8	16.53	1.46	11.3	....	....	.....	....	...

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Bethlehem I Beams.\*** BETHLEHEM I BEAMS from 8 to 24 in in depth inclusive, have the same strength, or section-modulus, as STANDARD BEAMS of same depth. Bethlehem beams, due to the proportions of the sections, weigh generally 10% less than standard beams of the same depth and strength. For example (Table VI, page 357), a Bethlehem 15-in I beam, weighing 54 lb per ft, has a section-modulus of 81.3. The corresponding standard section (Table IV, page 354) is a 15-in I beam weighing 60.8 lb per ft, with a section-modulus of 81.2. Therefore, for equal strength, the Bethlehem beam weighs 6.8 lb per ft less than the standard beam, or saving over 10% in weight. Similar comparisons with other sizes of the standard beams previously rolled by the mills of this country show that the Bethlehem I beams afford an equal carrying capacity, but with practically 10% less weight of metal.

**Thickness of Webs and Flanges.** It is claimed that the WEBS of standard beams are much thicker than required for a scientifically proportioned section. It is impossible to reduce the WEB-THICKNESS in the ordinary mill, but with the Grey Mill webs of the desired thickness can be produced. By adding the FLANGES part of the metal thus saved, the strength of the beam is maintained, thereby affording a lighter section of the same strength. The wide FLANGES give increased lateral stiffness, which commends the use of such beams in many cases, where the NARROW FLANGES and lack of sufficient lateral rigidity prevent the use of ordinary standard beams.

**Depth and Weight of Bethlehem Beams.** Formerly the heaviest beams rolled in this country were 24 in deep, weighed 115 lb per ft, and had a section-modulus of 246.3. Whenever greater strength was required, a riveted girder was necessary. Bethlehem beams are rolled to a maximum depth of 36 in, weigh 200 lb per ft, and have a section-modulus of 610, or two and one-half times the strength of the largest beam previously rolled. The opportunity of using ROLLED BEAMS instead of BUILT-UP RIVETED GIRDERS is, therefore, greatly increased. These rolled beams and girders afford a saving in WEIGHT OF METAL and also a large economy in COST OF FABRICATION, as they do not require punching, assembling and riveting necessary for building a riveted girder.

**Bethlehem Girder Beams.\*** BETHLEHEM GIRDER BEAMS, from 8 to 36 in in depth, inclusive, have a strength, or section-modulus, equal to that of minimum-weight STANDARD I BEAMS of the same depth. The girder beam, however, weighs generally 12½% less than the combined weight of the standard beams, not considering the saving in weight of separators needed in assembling the standard beams into a girder. For example, a Bethlehem girder beam, weighing 73 lb per ft has a section-modulus of 117.8 (Table VI, page 358). Two standard 15-in I beams, each weighing 42 lb per ft, together a like section-modulus of 117.8 (Table IV, page 354). Thus, for equal depth and strength, the girder beam weighs 11 lb per ft less than the standard beams. This is a saving of 13% in weight, not including separators which would add at least 2½ lb per ft more to the weight of the assembled girder. In this case a total saving of 16% in weight is afforded by the Bethlehem girder beam, besides the saving in the cost of assembling the standard beams into a girder.

**Safe Uniformly Distributed Loads for Bethlehem I Beams and Girder Beams.** Tables XII \* and XIII,\* pages 594 to 602, give the SAFE UNIFORM DISTRIBUTED LOADS in tons of 2 000 lb, on Bethlehem girder beams and I beams for a maximum fiber-stress of 16 000 lb per sq in. The tabular loads in

\* Adapted by permission from the Catalogue of Bethlehem Structural Shapes, Bethlehem Steel Company, South Bethlehem, Pa.

weight of the beam, which must be deducted to obtain the net load a beam will support. Safe loads for INTERMEDIATE or HEAVIER WEIGHTS of beams can be obtained from the separate COLUMN OF CORRECTIONS, given for each size. This last column of the table states the increase in safe load for each pound increase in weight per foot of beam. If the load is CONCENTRATED AT THE MIDDLE OF THE SPAN, the safe load is one-half the safe uniformly distributed load for the same span. The SAFE LOADS ON SHORT SPANS may be limited by the shearing strength of the web, instead of by the maximum fiber-stress allowed in the flanges. This limit is indicated in the tables by the heavy horizontal lines. The loads given above these lines are greater than the SAFE CRIPPLING or BUCKLING STRENGTH OF THE WEB, and must not be used unless the webs are stiffened.\* In such cases it will generally be advisable to select a heavier beam with a thicker web. To use these tables for other spans, or for other distribution of the loading, see explanation, page 566. To use these tables for beams YIELDING Laterally, see Lateral Deflection, pages 566 and 670.

Oblique Loading of Angles Used as Beams †

**Oblique Loading of Purlins on Sloping Roofs.** (See, also, pages 1169 and 1170.) The preceding tables VIII, IX and X for safe loads on angles are based on the neutral axis being parallel to one of the legs. When this is not the case, as in roof-purlins (Fig. 10), the strength of a given angle may be found by taking its section-modulus from Table XI A and using the fundamental formula for flexure (page 557). It should be noted that purlins set as at (a) are stronger than (b), Fig. 9A.




Fig. 9A. Strong and Weak Setting of Angle-Purlins on Sloping Roofs

Table XI A. Section-Moduli of Angle-Purlins Set at Right-Angles to Rafters, as in (a) Fig. 9A, and Free to Move in Any Direction. Loading Vertical.

Purlin	Slope of roof in inches per foot						
	0	1	2	4	5	6	8
2 X 2 X 1/4 angle.....	0.18	0.19	0.20	0.22	0.24	0.26	0.31
2 1/2 X 2 X 1/4 angle.....	0.30	0.31	0.33	0.38	0.41	0.44	0.49
3 X 2 1/2 X 1/4 angle.....	0.31	0.32	0.33	0.37	0.39	0.42	0.48
3 1/2 X 2 1/2 X 3/8 angle.....	0.42	0.44	0.46	0.52	0.55	0.60	0.68
4 X 2 1/2 X 1/4 angle.....	0.44	0.46	0.49	0.56	0.60	0.65	0.74
4 X 2 1/2 X 3/8 angle.....	0.64	0.67	0.71	0.82	0.89	0.95	1.06
4 1/2 X 2 1/2 X 1/4 angle.....	0.56	0.59	0.64	0.76	0.83	0.89	0.84
4 1/2 X 2 1/2 X 3/8 angle.....	0.84	0.89	0.96	1.14	1.22	1.29	1.19
5 X 3 X 1/4 angle.....	0.75	0.80	0.86	1.02	1.11	1.18	1.27
5 X 3 X 3/8 angle.....	1.11	1.18	1.26	1.47	1.58	1.70	1.76
5 1/2 X 3 1/2 X 5/16 angle.....	1.48	1.55	1.66	1.96	2.12	2.30	2.06
5 1/2 X 3 1/2 X 3/8 angle.....	1.76	1.86	1.99	2.34	2.52	2.71	2.42
6 X 4 X 3/8 angle.....	2.50	2.66	2.87	3.41	3.70	4.00	3.17
6 X 4 X 1/2 angle.....	3.30	3.52	3.79	4.52	4.84	5.18	4.09

\* See paragraphs and foot-note, page 567, relating to web-buckling of beams.

† From Notes by Robins Fleming.

Table XII. Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem Girder Beams

Beams secured against yielding sidewise

Span, ft	30-in G		Add for each lb increase in weight	28-in G		Add for each lb increase in weight	26-in G		Add for each increas in weight
	G30 a	G30		G28 a	G28		G26 a	G26	
	200 lb	180 lb		180 lb	165 lb		160 lb	150 lb	
18	180.75	161.87	0.44	153.75	138.89	0.41	128.11	117.47	0.3
19	171.24	153.35	0.41	145.66	131.58	0.39	121.37	111.29	0.3
20	162.68	145.68	0.39	138.38	125.00	0.37	115.30	105.72	0.3
21	154.93	138.74	0.37	131.79	119.05	0.35	109.81	100.69	0.3
22	147.89	132.44	0.36	125.80	113.64	0.33	104.82	96.11	0.3
23	141.46	126.68	0.34	120.33	108.70	0.32	100.26	91.93	0.3
24	135.56	121.40	0.33	115.31	104.17	0.31	96.08	88.10	0.2
25	130.14	116.55	0.31	110.70	100.00	0.29	92.24	84.58	0.2
26	125.14	112.06	0.30	106.44	96.16	0.28	88.69	81.32	0.2
27	120.50	107.91	0.29	102.50	92.60	0.27	85.41	78.31	0.2
28	116.20	104.06	0.28	98.84	89.29	0.26	82.36	75.52	0.2
29	112.19	100.47	0.27	95.43	86.21	0.25	79.52	72.91	0.2
30	108.45	97.12	0.26	92.25	83.34	0.24	76.87	70.48	0.2
31	104.95	93.99	0.25	89.27	80.65	0.24	74.39	68.21	0.2
32	101.67	91.05	0.25	86.48	78.13	0.23	72.06	66.08	0.2
33	98.59	88.29	0.24	83.86	75.76	0.22	69.88	64.07	0.2
34	95.69	85.70	0.23	81.40	73.53	0.22	67.82	62.19	0.2
35	92.96	83.25	0.22	79.07	71.43	0.21	65.88	60.41	0.1
36	90.38	80.93	0.22	76.88	69.45	0.20	64.05	58.73	0.1
37	87.93	78.75	0.21	74.80	67.57	0.20	62.32	57.15	0.1
38	85.62	76.67	0.21	72.83	65.79	0.19	60.68	55.64	0.1
39	83.42	74.71	0.20	70.96	64.10	0.19	59.13	54.22	0.1
40	81.34	72.84	0.20	69.19	62.50	0.18	57.65	52.86	0.1
41	79.35	71.06	0.19	67.50	60.98	0.18	56.24	51.57	0.1
42	77.47	69.37	0.19	65.89	59.53	0.17	54.90	50.34	0.1
43	75.66	67.76	0.18	64.36	58.14	0.17	53.63	49.17	0.1
44	73.94	66.22	0.18	62.90	56.82	0.17	52.41	48.06	0.1
45	72.30	64.75	0.17	61.50	55.56	0.16	51.24	46.99	0.1
46	70.73	63.34	0.17	60.16	54.35	0.16	50.13	45.97	0.1
47	69.22	61.99	0.17	58.88	53.19	0.16	49.06	44.99	0.1
48	67.78	60.70	0.16	57.66	52.09	0.15	48.04	44.05	0.1

Safe loads given include weight of beam  
Maximum fiber-stress, 16 000 lb per sq in  
The section-numbers are given for convenience in identification and order

**Table XII (Continued). Safe Uniform Loads in Tons of 2 000 Pounds  
for Bethlehem Girder Beams**

Beams secured against yielding sidewise

Span, ft	24-in G		Add for each lb increase in weight	20-in G		Add for each lb increase in weight	18-in G	Add for each lb increase in weight
	G24 a	G24		G20 a	G20		G18	
	140 lb	120 lb		140 lb	112 lb		92 lb	
12	155.61	133.60	0.52	130.43	104.09	0.44	78.59	0.39
13	143.64	123.33	0.48	120.40	96.09	0.40	72.54	0.36
14	133.38	114.52	0.45	111.80	89.23	0.37	67.36	0.34
15	124.48	106.88	0.42	104.34	83.28	0.35	62.87	0.31
16	116.71	100.20	0.39	97.82	78.07	0.33	58.94	0.29
17	109.84	94.31	0.37	92.07	73.48	0.31	55.47	0.28
18	103.74	89.07	0.35	86.95	69.40	0.29	52.39	0.26
19	98.28	84.38	0.33	82.38	65.74	0.28	49.63	0.25
20	93.37	80.16	0.31	78.26	62.46	0.26	47.15	0.24
21	88.92	76.35	0.30	74.53	59.48	0.25	44.91	0.22
22	84.88	72.88	0.29	71.14	56.78	0.24	42.87	0.21
23	81.19	69.71	0.27	68.05	54.31	0.23	41.00	0.20
24	77.80	66.80	0.26	65.22	52.05	0.22	39.29	0.20
25	74.69	64.15	0.25	62.61	49.97	0.21	37.72	0.19
26	71.82	61.66	0.24	60.20	48.04	0.20	36.27	0.18
27	69.16	59.38	0.23	57.97	46.26	0.19	34.93	0.17
28	66.69	57.26	0.22	55.90	44.61	0.19	33.68	0.17
29	64.39	55.29	0.22	53.97	43.07	0.18	32.52	0.16
30	62.24	53.44	0.21	52.17	41.64	0.17	31.43	0.16
31	60.24	51.72	0.20	50.49	40.30	0.17	30.42	0.15
32	58.35	50.10	0.20	48.91	39.04	0.16	29.47	0.15
33	56.58	48.58	0.19	47.43	37.85	0.16	28.58	0.14
34	54.92	47.15	0.18	46.04	36.74	0.15	27.74	0.14
35	53.35	45.81	0.18	44.72	35.69	0.15	26.94	0.13
36	51.87	44.54	0.17	43.48	34.70	0.15	26.20	0.13
37	50.47	43.33	0.17	42.30	33.76	0.14	25.49	0.13
38	49.14	42.19	0.17	41.19	32.87	0.14	24.82	0.12
39	47.88	41.11	0.16	40.13	32.03	0.13	24.18	0.12
40	46.68	40.08	0.16	39.13	31.23	0.13	23.58	0.12

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb per sq in

Loads given above the heavy lines are greater than safe loads for web-crippling. See paragraphs and accompanying foot-note, page 567, relating to web-buckling of beams

Safe loads given below the lower, broken line cause deflections exceeding  $\frac{1}{800}$  of the span

The section-numbers are given for convenience in identification and ordering

Table XII (Continued). Safe Uniform Loads in Tons of 2 000 Pounds  
for Bethlehem Girder Beams

Beams secured against yielding sidewise

Span, ft	15-in G			Add for each lb increase in weight	12-in G		A s in w
	G15 b	G15 a	G15		G12 a	G12	
	140 lb	104 lb	73 lb		70 lb	55 lb	
10	113.26	86.76	62.83	0.39	47.89	38.40	
11	102.96	78.88	57.12	0.36	43.54	34.91	
12	94.38	72.30	52.36	0.33	39.91	32.00	
13	87.12	66.74	48.33	0.30	36.84	29.54	
14	80.90	61.97	44.88	0.28	34.21	27.43	
15	75.51	57.84	41.89	0.26	31.93	25.60	
16	70.79	54.23	39.27	0.25	29.93	24.00	
17	66.62	51.04	36.96	0.23	28.17	22.59	
18	62.92	48.20	34.91	0.22	26.61	21.33	
19	59.61	45.67	33.07	0.21	25.21	20.21	
20	56.63	43.38	31.42	0.20	23.95	19.20	
21	53.93	41.32	29.92	0.19	22.81	18.28	0.1
22	51.48	39.44	28.56	0.18	21.77	17.45	0.1
23	49.24	37.72	27.32	0.17	20.82	16.69	0.1
24	47.19	36.15	26.18	0.16	19.95	16.00	0.1
25	45.30	34.71	25.13	0.16	19.16	15.36	0.1
26	43.56	33.37	24.17	0.15	18.42	14.77	0.1
27	41.95	32.13	23.27	0.15	17.74	14.22	0.1
28	40.45	30.99	22.44	0.14	17.10	13.71	0.1
29	39.05	29.92	21.67	0.14	16.51	13.24	0.1
30	37.75	28.92	20.94	0.13	15.96	12.80	0.1
31	36.54	27.99	20.27	0.13	15.45	12.39	0.1
32	35.39	27.11	19.63	0.12	14.97	12.00	0.1
33	34.32	26.29	19.04	0.12	14.51	11.64	0.1
34	33.31	25.52	18.48	0.12	14.09	11.29	0.1
35	32.36	24.79	17.95	0.11	13.68	10.97	0.1

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb  
sq in

Load given above the heavy line is greater than a safe load for web-crip  
See paragraphs and accompanying foot-note, page 567, relating to web-buc  
of beams.

Safe loads given below the lower, broken lines cause deflections exceeding  
of the span.

The section-numbers are given for convenience in identification and orde

Table XII (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem Girder Beams

Beams secured against yielding sidewise

Span, ft	10-in G	Add for each lb increase in weight	Span, ft	9-in G	Add for each lb increase in weight	8-in G	Add for each lb increase in weight
	G10			G9		G8	
	44 lb			38 lb		32.5 lb	
10	26.05	0.26	5	40.50	0.47	30.51	0.42
11	23.68	0.24	6	33.75	0.39	25.42	0.35
12	21.71	0.22	7	28.93	0.34	21.79	0.30
13	20.04	0.20	8	25.31	0.29	19.07	0.26
14	18.61	0.19	9	22.50	0.26	16.95	0.23
15	17.37	0.17	10	20.25	0.23	15.25	0.21
16	16.28	0.16	11	18.41	0.21	13.87	0.19
17	15.32	0.15	12	16.88	0.20	12.71	0.17
18	14.47	0.15	13	15.58	0.18	11.73	0.16
19	13.71	0.14	14	14.47	0.17	10.90	0.15
20	13.03	0.13	15	13.50	0.16	10.17	0.14
21	12.40	0.12	16	12.66	0.15	9.53	0.13
22	11.84	0.12	17	11.91	0.14	8.97	0.12
23	11.33	0.11	18	11.25	0.13	8.47	0.12
24	10.85	0.11	19	10.66	0.12	8.03	0.11
25	10.42	0.10	20	10.13	0.12	7.63	0.10
26	10.02	0.10	21	9.64	0.11	7.26	0.10
27	9.65	0.10	22	9.21	0.11	6.93	0.09
28	9.30	0.09	23	8.80	0.10	6.63	0.09
29	8.98	0.09	24	8.44	0.10	6.36	0.08
30	8.68	0.09	25	8.10	0.09	6.10	0.08
31	8.40	0.08	26	7.79	0.09	.....	.....
32	8.14	0.08	27	7.50	0.09	.....	.....
33	7.89	0.08	28	7.23	0.08	.....	.....
34	7.66	0.08	29	6.98	0.08	.....	.....
35	7.44	0.07	30	6.75	0.07	.....	.....

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb per sq in

Loads given above the heavy lines are greater than safe loads for web-crippling. See paragraphs and accompanying foot-note, page 567, relating to web-buckling of beams

Safe loads given below the lower, broken lines cause deflections exceeding  $\frac{1}{800}$  of the span.

The section-numbers are given for convenience in identification and ordering

Table XIII. Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem I Beams

Beams secured against yielding sidewise

Span, ft	30-in I	Add for each lb increase in weight	28-in I	Add for each lb increase in weight	26-in I	Add for each lb increase in weight
	B30		B28		B26	
	120 lb		105 lb		90 lb	
18	103.50	0.44	84.95	0.41	67.86	0.38
19	98.05	0.41	80.48	0.39	64.29	0.36
20	93.15	0.39	76.46	0.37	61.07	0.34
21	88.71	0.37	72.82	0.35	58.16	0.32
22	84.68	0.36	69.51	0.33	55.52	0.31
23	81.00	0.34	66.49	0.32	53.11	0.30
24	77.62	0.33	63.72	0.31	50.89	0.28
25	74.52	0.31	61.17	0.29	48.86	0.27
26	71.65	0.30	58.81	0.28	46.98	0.26
27	69.00	0.29	56.64	0.27	45.24	0.25
28	66.54	0.28	54.61	0.26	43.62	0.24
29	64.24	0.27	52.73	0.25	42.12	0.23
30	62.10	0.26	50.97	0.24	40.71	0.23
31	60.10	0.25	49.33	0.24	39.40	0.22
32	58.22	0.25	47.79	0.23	38.17	0.21
33	56.45	0.24	46.34	0.22	37.01	0.21
34	54.79	0.23	44.98	0.22	35.92	0.20
35	53.23	0.22	43.69	0.21	34.90	0.19
36	51.75	0.22	42.48	0.20	33.93	0.18
37	50.35	0.21	41.33	0.20	33.01	0.18
38	49.03	0.21	40.24	0.19	32.14	0.17
39	47.77	0.20	39.21	0.19	31.32	0.17
40	46.57	0.20	38.23	0.19	30.54	0.16
41	45.44	0.19	37.30	0.18	29.79	0.16
42	44.36	0.19	36.41	0.18	29.08	0.15
43	43.33	0.18	35.56	0.17	28.41	0.15
44	42.34	0.18	34.75	0.17	27.76	0.14
45	41.40	0.17	33.98	0.16	27.14	0.14
46	40.50	0.17	33.24	0.16	26.55	0.13
47	39.64	0.17	32.54	0.16	25.99	0.13
48	38.81	0.16	31.86	0.15	25.45	0.12

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb sq in  
The section-numbers are given for convenience in identification and order



Table XIII • (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem I Beams

Beams secured against yielding sidewise

Span, ft	24-in I		Add for each lb increase in weight	20-in I					Add for each lb increase in weight
	B24 a	B24		B20 a		B20			
	84 lb	73 lb		82 lb	72 lb	69 lb	64 lb	59 lb	
12	88.22	77.45	0.52	69.33	65.18	56.40	54.32	52.10	0.44
13	81.43	71.49	0.48	63.99	60.17	52.06	50.14	48.09	0.40
14	75.62	66.38	0.45	59.42	55.87	48.34	46.56	44.65	0.37
15	70.58	61.96	0.42	55.46	52.14	45.12	43.45	41.68	0.35
16	66.16	58.08	0.39	51.99	48.88	42.30	40.74	39.07	0.33
17	62.27	54.67	0.37	48.94	46.01	39.81	38.34	36.77	0.31
18	58.81	51.63	0.35	46.22	43.45	37.60	36.21	34.73	0.29
19	55.72	48.91	0.33	43.78	41.17	35.62	34.31	32.90	0.28
20	52.93	46.47	0.31	41.60	39.11	33.84	32.59	31.26	0.26
21	50.41	44.26	0.30	39.61	37.25	32.23	31.04	29.77	0.25
22	48.12	42.24	0.29	37.81	35.55	30.76	29.63	28.42	0.24
23	46.03	40.41	0.27	36.17	34.01	29.42	28.34	27.18	0.23
24	44.11	38.72	0.26	34.66	32.59	28.20	27.16	26.05	0.22
25	42.35	37.17	0.25	33.28	31.29	27.07	26.07	25.01	0.21
26	40.72	35.74	0.24	32.00	30.08	26.03	25.07	24.04	0.20
27	39.21	34.42	0.23	30.81	28.97	25.07	24.14	23.15	0.19
28	37.81	33.19	0.22	29.71	27.93	24.17	23.28	22.33	0.19
29	36.50	32.05	0.22	28.69	26.97	23.34	22.48	21.56	0.18
30	35.29	30.98	0.21	27.73	26.07	22.56	21.73	20.84	0.17
31	34.15	29.98	0.20	26.84	25.23	21.83	21.03	20.17	0.17
32	33.08	29.04	0.20	26.00	24.44	21.15	20.37	19.54	0.16
33	32.08	28.16	0.19	25.21	23.70	20.51	19.75	18.94	0.16
34	31.14	27.33	0.19	24.47	23.00	19.90	19.17	18.39	0.15
35	30.25	26.55	0.18	23.77	22.35	19.34	18.62	17.86	0.15
36	29.41	25.82	0.17	23.11	21.73	18.80	18.11	17.37	0.15
37	28.61	25.12	0.17	22.48	21.14	18.29	17.62	16.90	0.14
38	27.86	24.46	0.17	21.89	20.58	17.81	17.15	16.45	0.14
39	27.14	23.83	0.16	21.33	20.06	17.35	16.71	16.03	0.13
40	26.47	23.23	0.16	20.80	19.55	16.92	16.30	15.63	0.13

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb per sq in

Loads given above the heavy lines are greater than safe loads for web-crippling. See paragraphs and accompanying foot-note, page 567, relating to web-buckling of beams

The section-numbers are given for convenience in identification and ordering

\* See data for Additional Sections, for 22-in and 24-in beams, in Pamphlet S-10, published March 1, 1921, by the Bethlehem Steel Company.

**Table XIII \* (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem I Beams**

**Beams secured against yielding sidewise**

Span, ft	18-in I			Add for each lb increase in weight	15-in I					Add each incre in weig
	B18				B15 b	B15 a	B15			
	59 lb	54 lb	48.5 lb				71 lb	54 lb	46 lb	
12	43.62	41.58	39.42	0.39	47.18	36.15	28.73	27.06	26.23	0.3
13	40.26	38.38	36.39	0.36	43.55	33.37	26.52	24.98	24.21	0.3
14	37.39	35.64	33.79	0.34	40.44	30.99	24.62	23.19	22.48	0.2
15	34.90	33.26	31.54	0.31	37.75	28.92	22.98	21.65	20.98	0.2
16	32.71	31.18	29.56	0.29	35.39	27.11	21.55	20.30	19.67	0.2
17	30.79	29.35	27.83	0.28	33.30	25.52	20.28	19.10	18.51	0.2
18	29.08	27.72	26.28	0.26	31.45	24.10	19.15	18.04	17.49	0.2
19	27.55	26.26	24.90	0.25	29.80	22.83	18.14	17.09	16.56	0.2
20	26.17	24.95	23.65	0.24	28.31	21.69	17.24	16.24	15.74	0.2
21	24.93	23.76	22.53	0.22	26.96	20.66	16.42	15.46	14.99	0.1
22	23.79	22.68	21.50	0.21	25.74	19.72	15.67	14.76	14.31	0.1
23	22.76	21.70	20.57	0.21	24.62	18.86	14.99	14.12	13.68	0.1
24	21.81	20.79	19.71	0.20	23.59	18.07	14.36	13.53	13.11	0.1
25	20.94	19.96	18.92	0.19	22.65	17.35	13.79	12.99	12.59	0.1
26	20.13	19.19	18.19	0.18	21.78	16.68	13.26	12.49	12.11	0.1
27	19.39	18.48	17.52	0.17	20.97	16.07	12.77	12.03	11.66	0.1
28	18.69	17.82	16.89	0.17	20.22	15.49	12.31	11.60	11.24	0.1
29	18.05	17.21	16.31	0.16	19.52	14.96	11.89	11.20	10.85	0.1
30	17.45	16.63	15.77	0.16	18.87	14.46	11.49	10.82	10.49	0.1
31	16.88	16.10	15.26	0.15	18.26	13.99	11.12	10.47	10.15	0.1
32	16.36	15.59	14.78	0.15	17.69	13.56	10.77	10.15	9.84	0.1
33	15.86	15.12	14.33	0.14	17.16	13.15	10.45	9.84	9.54	0.1
34	15.40	14.68	13.91	0.14	16.65	12.76	10.14	9.55	9.26	0.1
35	14.96	14.26	13.52	0.13	16.18	12.39	9.85	9.28	8.99	0.1
36	14.54	13.86	13.14	0.13	15.73	12.05	9.58	9.02	8.74	0.1
37	14.15	13.49	12.78	0.13	15.30	11.72	9.32	8.78	8.51	0.1
38	13.77	13.13	12.45	0.12	14.90	11.42	9.07	8.55	8.28	0.1
39	13.42	12.79	12.13	0.12	14.52	11.12	8.84	8.33	8.07	0.1
40	13.09	12.47	11.83	0.12	14.15	10.84	8.62	8.12	7.87	0.1

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb sq in

Load given above the heavy line is greater than safe load for web-crippled beams. See paragraphs and accompanying foot-note, page 567, relating to web-buckling of beams

Safe loads given below the broken lines cause deflections exceeding  $\frac{1}{360}$  of span

The section-numbers are given for convenience in identification and ordering

\* See data for Additional Sections, for 18-in beams, in Pamphlet S-10, pub March 1, 1921, by the Bethlehem Steel Company.

**Table XIII (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem I Beams****Beams secured against yielding sidewise**

Span, ft	12-in I			Add for each lb increase in weight	10-in I		Add for each lb increase in weight
	B12 a	B12			B10		
	36 lb	32 lb	28.5 lb		28.5 lb	23.5 lb	
9	26.59	22.57	21.36	0.35	15.95	14.57	0.29
10	23.93	20.31	19.22	0.31	14.35	13.11	0.26
11	21.76	18.46	17.47	0.29	13.05	11.92	0.24
12	19.94	16.92	16.02	0.26	11.96	10.92	0.22
13	18.41	15.62	14.79	0.24	11.04	10.08	0.20
14	17.09	14.51	13.73	0.22	10.25	9.36	0.19
15	15.95	13.54	12.81	0.21	9.57	8.74	0.17
16	14.96	12.69	12.01	0.20	8.97	8.19	0.16
17	14.08	11.95	11.31	0.19	8.44	7.71	0.15
18	13.30	11.28	10.68	0.17	7.97	7.28	0.15
19	12.60	10.69	10.12	0.17	7.55	6.90	0.14
20	11.97	10.15	9.61	0.16	7.18	6.55	0.13
21	11.40	9.67	9.15	0.15	6.84	6.24	0.12
22	10.88	9.23	8.74	0.14	6.52	5.96	0.12
23	10.41	8.83	8.36	0.14	6.24	5.70	0.11
24	9.97	8.46	8.01	0.13	5.98	5.46	0.11
25	9.57	8.12	7.69	0.13	5.74	5.24	0.10
26	9.20	7.81	7.39	0.12	5.52	5.04	0.10
27	8.86	7.52	7.12	0.12	5.32	4.86	0.10
28	8.55	7.25	6.86	0.11	5.13	4.68	0.09
29	8.25	7.00	6.63	0.11	4.95	4.52	0.09
30	9.98	6.77	6.41	0.11	4.78	4.37	0.09
31	7.72	6.55	6.20	0.10	.....	.....	.....
32	7.48	6.35	6.01	0.10	.....	.....	.....
33	7.25	6.15	5.82	0.10	.....	.....	.....
34	7.04	5.97	5.65	0.09	.....	.....	.....
35	6.84	5.80	5.49	0.09	.....	.....	.....

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb per sq in

Safe loads given below the broken lines cause deflections exceeding  $\frac{1}{800}$  of the span

The section-numbers are given for convenience in identification and ordering

**Table XIII (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Bethlehem I Beams**

**Beams secured against yielding sidewise**

Span, ft	9-in I		Add for each lb increase in weight	8-in I		Add for each lb increase in weight
	B9			B8		
	24 lb	20 lb		19.5 lb	17.5 lb	
5	21.83	20.18	0.47	16.16	15.30	0.42
6	18.19	16.81	0.39	13.46	12.75	0.35
7	15.60	14.41	0.34	11.54	10.93	0.30
8	13.65	12.61	0.29	10.10	9.57	0.26
9	12.13	11.21	0.26	8.98	8.50	0.23
10	10.92	10.09	0.24	8.08	7.65	0.21
11	9.92	9.17	0.21	7.34	6.96	0.19
12	9.10	8.41	0.20	6.73	6.38	0.17
13	8.40	7.76	0.18	6.21	5.89	0.16
14	7.80	7.21	0.17	5.77	5.47	0.15
15	7.28	6.73	0.16	5.39	5.10	0.14
16	6.82	6.31	0.15	5.05	4.78	0.13
17	6.42	5.93	0.14	4.75	4.50	0.12
18	6.07	5.61	0.13	4.49	4.25	0.12
19	5.75	5.31	0.13	4.25	4.03	0.11
20	5.46	5.04	0.12	4.04	3.83	0.11
21	5.20	4.80	0.11	3.85	3.64	0.10
22	4.96	4.59	0.11	3.67	3.48	0.10
23	4.75	4.39	0.10	3.51	3.33	0.09
24	4.55	4.20	0.10	3.37	3.19	0.09
25	4.37	4.04	0.10	3.23	3.06	0.08
26	4.20	3.88	0.09	.....	.....	.....
27	4.04	3.74	0.09	.....	.....	.....
28	3.90	3.60	0.09	.....	.....	.....
29	3.76	3.48	0.08	.....	.....	.....
30	3.64	3.36	0.08	.....	.....	.....

Safe loads given include weight of beam. Maximum fiber-stress, 16 000 lb sq in

Safe loads given below the broken lines cause deflections exceeding  $\frac{1}{4}$  in of span

The section-numbers are given for convenience in identification and ordering

**Riveted Single-Beam and Double-Beam Girders.\*** Where a SINGLE BEAM is insufficient to carry a load, the required capacity may be secured by fabrication in various ways. TWO BEAMS can be used, connected by bolts and separators. The total strength of these is twice that of the SINGLE BEAM of the same depth and weight. Care should be taken, however, to see that the loads are apportioned to them equally, and where it is necessary for the beams to act as a unit, the separators should consist of plates and angles and not made of cast iron. If the loading is not uniformly distributed over the two beams, the strength of each must be computed separately. The use of a SINGLE-BEAM GIRDER with plates at top and bottom to sustain a given load is often more economical in material than the use of TWO BEAMS connected by bolts and separators. The beam girders in Table XIV, pages 605-6, have about twice the carrying capacity of the single beams of which they are built.

Tables XIV and XV give the SAFE LOADS for the SINGLE AND DOUBLE-BEAM GIRDERS commonly used. The values given in the tables are founded upon the moments of inertia of the various sections, deductions being made for the rivet-holes in both flanges. In Table XIV, taken by permission from Carnegie's Pocket Companion, the safe loads are based upon a fiber-stress for flange-bending of 16 000 lb per sq in, and in Table XV, retained from the former edition of Kidder's Pocket-Book, upon a fiber-stress of 13 000 lb per sq in. For other fiber-stresses, as 14 000 or 15 000 lb per sq in, the safe loads in Tables XIV or XV may be decreased or increased by PROPORTION as the LOADS vary as the FIBER-STRESSES.†

\* For tables of riveted plate girders, see Chapter XX.

† The editors decided to retain Table XV for the safe uniformly distributed loads for riveted steel-beam box girders, based upon a bending fiber-stress of 13 000 lb per sq in. For this table for fiber-stresses of 14 000, 15 000 or 16 000 lb per sq in, divide the safe loads by 13 and multiply the quotients by 14, 15 or 16, respectively, for the safe loads at the required fiber-stress. In regard to Table XV, Mr. Kidder said, in the earlier editions of this pocket-book, "in order to amply compensate for the deterioration of the metal around the rivet-holes from punching, and also because these girders were often used to support permanent loads, such as brick or stone walls, the maximum fiber-stress [for riveted double-beam girders] was limited to 13 000 lb per sq in, although it is but right to state that most of the latest handbooks of the steel-manufacturers give tables of safe loads for such girders based upon a fiber-stress of 15 000 lb per sq in. The author advises that for loads of masonry, which usually come very close to the estimated loads, and which are constantly applied, the girders be not loaded beyond the values given in the following tables (that is, based upon 13 000 lb per sq in), while for ordinary floor-loads, which seldom reach the estimated loads, an addition of 1/6th may be added to the values given in the tables."

Girders fabricated of single steel I beams and plates riveted to the upper and lower flanges, as shown in Table XIV, are not often used to support masonry walls, because of their relatively narrow flange-width and lack of lateral stiffness. In case they are used to support masonry walls and are not thoroughly braced laterally, it is recommended that the safe loads be reduced as explained, from those given in Table XIV, to agree with a fiber-stress of 13 000 or 14 000 lb per sq in, according to the span, bracing, character of loading, etc. It is recommended, also, that for girders fabricated of two steel I beams and plates riveted to the flanges, as shown in Table XV, and carrying masonry walls, the safe loads, given in this table and computed for a fiber-stress of 13 000 lb per sq in, be used, or, if increased, that the fiber-stress be taken not greater than 14 000 lb per sq in.

Recent handbooks have contained tables of safe uniformly distributed loads for fabricated steel girders computed from safe unit fiber-stresses, in pounds per square inch, for flange-bending as follows. For RIVETED SINGLE-BEAM GIRDERS: Carnegie Steel Company, 1903 Edition, no tables; Carnegie, 1915 Edition, 16 000, based upon the section-modulus of the gross area of the cross-section; Cambria Steel Company, 1912 Edition, no tables; (former) Passaic Steel Company, 1903 Edition, no tables; Kidder's Pocket-Book, previous editions, no tables. For RIVETED DOUBLE-BEAM GIRDERS: Car-

**Example 21.** A 13-in brick wall, 15 ft high, is to be built over an opening 24 ft. What is the size of the double-beam girder required?

**Solution.** Assuming 25 ft as the distance, center to center of bearings and 150 lb per cu ft as the weight of brickwork, the weight of the wall is  $25 \times 15 \times 150 = 56250$  lb, or about 22.68 tons. From Table XV, page 610, a girder composed of two 12-in steel beams, each weighing 31.5 lb per ft, and two 14 by  $\frac{1}{2}$ -in flange plates will carry safely, for a span of 25 ft, a uniformly distributed load of 23.2 tons, including its own weight. Deducting the latter, 1.42 tons, given in the next column, the result is 21.8 tons for the safe net load, which is 0.87 tons less than required. From the following column of the table it is seen that by increasing the thickness of the flange-plates  $\frac{1}{8}$  in it is safe to add 1.52 tons to the allowable load. This will more than make up the difference. Hence the required DOUBLE-BEAM GIRDER will be composed of two 12-in 31.5-lb beams and two 14 by  $\frac{9}{16}$ -in steel flange-plates.

A SINGLE-BEAM GIRDER (according to Table XIV, page 606), composed of one 15-in 42-lb I beam and two 8 by  $\frac{1}{2}$ -in flange-plates will carry, at 150 lb per sq ft, 49 000 lb over a span of 25 ft, and as it is lighter, weighing 69.2 lb per ft to the others 113.6 lb, it would be more economical. The DOUBLE-BEAM GIRDER is, however, more suitable in this particular case, for a 13-in wall should have a wider bearing than 8 in, and, also, the safe load should be decreased from the tabular load to correspond to a fiber-stress of 13 000 lb per sq in because of the nature of the loading, the long span, etc., or, what amounts to the same thing, the strength of the girder should be increased to correspond to the decreased fiber-stress. (See foot-note, page 606.) A 49 000-lb load at 16 000 lb per sq in fiber-stress corresponds to a 49 000  $\times \frac{13}{16} = 60\,307$ -lb load at 13 000 fiber-stress, as far as selecting a corresponding girder from table is concerned. A SINGLE-BEAM GIRDER (Table XIV) composed of one 15-in 60-lb I beam and two 9 by  $\frac{1}{2}$ -in flange-plates will carry 68 000 lb and weighs only 98.3 lb per ft. Therefore, as far as strength is concerned, to suit the conditions of loading, this would be the proper SINGLE-BEAM GIRDER to use, and it would also be cheaper than the DOUBLE-BEAM GIRDER determined by Table XV; but the width of bearing for the 13-in wall is only 9 in compared to 14 in with the DOUBLE-BEAM GIRDER.





**Notes.** For SINGLE-WEB, PLATE-AND-ANGLE GIRDERS (see Chapter XX): Carnegie, 1903, 15 000,  $\frac{13}{16}$ -in rivet-holes deducted; Carnegie, 1915, no tables; Cambria, 15 000,  $\frac{13}{16}$ -in rivet-holes deducted; Passaic, 15 000,  $\frac{13}{16}$  or  $\frac{1}{2}$ -in rivet-holes deducted; Kidder, previous and new editions, 13 000,  $\frac{13}{16}$ -in rivet-holes deducted. For RIVETED MULTIPLE-WEB, PLATE-AND-ANGLE GIRDERS (see Chapter XX): Carnegie, 1903, 15 000,  $\frac{13}{16}$ -in rivet-holes deducted; Carnegie, 1915, 16 000, based upon section-modulus of the gross area of cross-section; Cambria, 15 000,  $\frac{13}{16}$  or  $\frac{1}{2}$ -in rivet-holes deducted; Passaic, 15 000,  $\frac{13}{16}$  or  $\frac{1}{2}$ -in rivet-holes deducted; Kidder, previous editions, 13 000 for flanges,  $\frac{13}{16}$  or  $\frac{1}{2}$ -in rivet-holes deducted (also contained the tables). For RIVETED MULTIPLE-WEB, PLATE-AND-ANGLE GIRDERS (see Chapter XX): Carnegie, 1903, 15 000,  $\frac{13}{16}$ -in rivet-holes deducted; Carnegie, 1915, 16 000, based upon section-modulus of the gross area of cross-section (the elements, only, of these girders are given); Cambria, no tables; Passaic, 15 000,  $\frac{13}{16}$  or  $\frac{1}{2}$ -in rivet-holes, deducted; Kidder, previous editions, same as for single-web plate girders.

The revised edition of Kidder's Handbook uses, by permission, the Carnegie tables for all but the riveted double-beam girders, for which the old Kidder tables are retained.

The limiting conditions of use are fully explained in the text and foot-notes. The designer is in-chief.

**Table XIV.\* Safe Uniform Loads in Units of 1 000 Pounds for Riveted Steel-Beam Girders**

Maximum bending stress, 16 000† lb per sq in

Span, ft									Co- effi- cients of de- flec- tion
	27-in 50-lb beam 12 by 3/4-in plates		24-in 79.9-lb beam, 12 by 3/4-in plates		24-in 79.9-lb beam, 10 by 3/4-in plates		20-in 79.9-lb beam, 10 by 3/4-in plates		
	Safe loads	Increase in safe loads for 1/16-in increase in thick- ness of flange- plates	Safe loads	Increase in safe loads for 1/16-in increase in thick- ness of flange- plates	Safe loads	Increase in safe loads for 1/16-in increase in thick- ness of flange- plates	Safe loads	Increase in safe loads for 1/16-in increase in thick- ness of flange- plates	
13	370	15.9	312	14.2	259	11.7	235	9.7	2.80
14	343	14.8	289	13.2	240	10.9	218	9.0	3.24
15	321	13.8	270	12.3	224	10.1	204	8.4	3.72
16	301	13.0	253	11.5	210	9.5	191	7.9	4.24
17	283	12.2	238	10.9	198	9.0	180	7.4	4.78
18	267	11.5	225	10.3	187	8.4	170	7.0	5.36
19	253	10.9	213	9.7	177	8.0	161	6.6	5.98
20	240	10.4	203	9.2	168	7.6	153	6.3	6.62
21	229	9.9	193	8.8	160	7.2	146	6.0	7.30
22	219	9.4	184	8.4	153	6.9	139	5.7	8.01
23	209	9.0	176	8.0	146	6.6	133	5.5	8.76
24	200	8.6	169	7.7	140	6.3	127	5.3	9.53
25	192	8.3	162	7.4	135	6.1	122	5.0	10.35
26	185	8.0	156	7.1	129	5.9	118	4.8	11.19
27	178	7.7	150	6.8	125	5.6	113	4.7	12.07
28	172	7.4	145	6.6	120	5.4	109	4.5	12.98
29	166	7.1	140	6.4	116	5.2	105	4.3	13.92
30	160	6.9	135	6.2	112	5.1	102	4.2	14.90
31	155	6.7	131	6.0	109	4.9	99	4.1	15.91
32	150	6.5	127	5.8	105	4.8	96	3.9	16.95
33	146	6.3	123	5.6	102	4.6	93	3.8	18.03
34	141	6.1	119	5.4	99	4.5	90	3.7	19.13
35	137	5.9	116	5.3	96	4.3	87	3.6	20.28
Area	44.33 in <sup>2</sup>		41.33 in <sup>2</sup>		35.83 in <sup>2</sup>		38.73 in <sup>2</sup>		....
Wt.	450.8 lb per ft		380.0 lb per ft		315.5 lb per ft		286.7 lb per ft		....
	152.2 lb per ft		141.1 lb per ft		122.4 lb per ft		132.4 lb per ft		....

\* Safe loads above the heavy, horizontal lines exceed the resistance of the web and girders should be provided with stiffeners; for limiting conditions, see explanatory notes on page 567. See Pocket Companion for 13 and 14-ft spans.

Weights given for girders do not include stiffeners, rivet-heads or other details





\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† See paragraph on Riveted Single-Beam and Double-Beam Girders, page 603, and the note for same regarding fiber-stresses.

‡ is the section-modulus or section-factor of the cross-section with reference to the

**Table XIV\* (Continued). Safe Uniform Loads in Units of 1 000 Pounds for Riveted Steel-Beam Girders**

Maximum bending stress, 16 000† lb per sq in

Span, ft									C e f f i c i e n c y
	20-in 65.4-lb beam, 10 by 1/2-in plates		18-in 54.7-lb beam, 9 by 1/2-in plates		15-in 60.8-lb beam, 9 by 1/2-in plates		15-in 42.9-lb beam, 8 by 1/2-in plates		
	Safe loads	Increase in safe loads for 1/8-in increase in thick- ness of flange- plates	Safe loads	Increase in safe loads for 1/8-in increase in thick- ness of flange- plates	Safe loads	Increase in safe loads for 1/8-in increase in thick- ness of flange- plates	Safe loads .	Increase in safe loads for 1/8-in increase in thick- ness of flange- plates	
9	279	14.2	218	11.5	189	9.4	137	8.5	1
10	251	12.7	196	10.3	170	8.5	123	7.6	1
11	228	11.6	178	9.4	155	7.7	112	6.9	2
12	209	10.6	164	8.6	142	7.1	102	6.4	2
13	193	9.8	151	7.9	131	6.5	95	5.9	2
14	179	9.1	140	7.4	122	6.1	88	5.5	3
15	167	8.5	131	6.9	113	5.7	82	5.1	3
16	157	8.0	123	6.5	106	5.3	77	4.8	4
17	148	7.5	115	6.1	100	5.0	72	4.5	4
18	139	7.1	109	5.7	95	4.7	68	4.2	4
19	132	6.7	103	5.4	90	4.5	65	4.0	5
20	125	6.4	98	5.2	85	4.3	61	3.8	6
21	119	6.1	93	4.9	81	4.0	59	3.6	7
22	114	5.8	89	4.7	77	3.9	56	3.5	7
23	109	5.5	85	4.5	74	3.7	53	3.3	7
24	105	5.3	82	4.3	71	3.5	51	3.2	7
25	100	5.1	79	4.1	68	3.4	49	3.1	7
26	97	4.9	76	4.0	65	3.3	47	2.9	7
27	93	4.7	73	3.8	63	3.1	46	2.8	7
28	90	4.6	70	3.7	61	3.0	44	2.7	7
29	87	4.4	68	3.6	59	2.9	42	2.6	7
30	84	4.2	65	3.4	57	2.8	41	2.5	7
Area $I/c_1$ -† Wgt	31.58 in <sup>2</sup> 235.2 in <sup>3</sup> 107.9 lb per ft		27.19 in <sup>2</sup> 184.1 in <sup>3</sup> 93.0 lb per ft		28.93 in <sup>2</sup> 159.5 in <sup>3</sup> 99.1 lb per ft		20.49 in <sup>2</sup> 115.3 in <sup>3</sup> 70.1-lb per ft		

Safe loads above the heavy, horizontal lines exceed the resistance of the web girders should be provided with stiffeners; for limiting conditions, see explanation notes on page 567. See Pocket Companion, 1915 for 9-ft. span

Weights given for girders do not include stiffeners, rivet-heads or other details



\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† See paragraph on Riveted Single-Beam and Double-Beam Girders, page 603, foot-note for same regarding fiber-stresses.

‡  $I/c$  is the section-modulus or section-factor of the cross-section with reference axis 1-1.





**Table XV. Safe Uniform Loads in Tons of 2 000 Pounds for Riveted Steel-Beam Box Girders**Two 20-in steel I beams and two 16 by  $\frac{3}{4}$ -in steel plates

Distance, center to center of bearings, ft	<div>Two steel plates, 16 by <math>\frac{3}{4}</math> in</div>  <div>Two 20-in beams, 80.4 lb per ft</div>			<div>Two steel plates, 16 by <math>\frac{3}{4}</math> in</div>  <div>Two 20-in beams, 65.04 lb per ft</div>			Increase in weight of girder for $\frac{1}{8}$ -in increase in thickness of flange-plates
	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Increase in safe loads for $\frac{1}{8}$ -in increase in thickness of flange-plates	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Increase in safe loads for $\frac{1}{8}$ -in increase in thickness of flange-plates	
10	199.67	1.22	7.22	176.72	1.06	7.34	0.03
11	181.51	1.34	6.56	160.66	1.16	6.68	0.04
12	166.39	1.46	6.02	147.26	1.27	6.12	0.04
13	153.60	1.58	5.56	135.95	1.37	5.65	0.04
14	142.64	1.70	5.16	126.24	1.48	5.25	0.05
15	133.12	1.83	4.81	117.82	1.58	4.90	0.05
16	124.80	1.95	4.51	110.45	1.69	4.59	0.05
17	117.47	2.07	4.25	103.96	1.79	4.32	0.06
18	110.94	2.19	4.01	98.18	1.90	4.08	0.06
19	105.10	2.31	3.80	93.01	2.01	3.86	0.06
20	99.83	2.43	3.61	88.36	2.11	3.67	0.07
21	95.08	2.56	3.44	84.15	2.22	3.50	0.07
22	90.77	2.68	3.28	80.33	2.32	3.34	0.07
23	86.82	2.80	3.14	76.84	2.43	3.19	0.08
24	83.20	2.92	3.01	73.64	2.53	3.06	0.08
25	79.87	3.04	2.89	70.69	2.64	2.94	0.08
26	76.80	3.16	2.78	67.97	2.75	2.82	0.09
27	73.96	3.29	2.68	65.46	2.85	2.72	0.09
28	71.32	3.41	2.58	63.12	2.96	2.62	0.09
29	68.86	3.53	2.49	60.94	3.06	2.53	0.10
30	66.56	3.65	2.41	58.91	3.17	2.45	0.10
31	64.41	3.77	2.33	57.01	3.27	2.37	0.10
32	62.41	3.89	2.26	55.22	3.38	2.29	0.11
33	60.51	4.02	2.19	53.56	3.48	2.22	0.11
34	58.73	4.14	2.12	51.98	3.59	2.16	0.11
35	57.05	4.26	2.06	50.50	3.70	2.10	0.12
36	55.46	4.38	2.01	49.09	3.80	2.04	0.12
37	53.96	4.50	1.95	47.77	3.91	1.98	0.12
38	52.54	4.62	1.90	46.51	4.01	1.93	0.13
39	51.20	4.75	1.85	45.32	4.12	1.88	0.13

These values are based on a maximum fiber-stress of 13 000 lb per sq in, rivet-holes in flanges deducted. See paragraph on Riveted Single-Beam and Double-Beam on page 603, and the foot-note for same regarding fiber-stresses. Weights of girders are given in tons per foot, center to center of bearings.

Table XV (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Riveted Steel-Beam Box Girders

Two 18-in steel I beams and two 16 by 3/4-in steel plates




Distance, center to center of bearings, ft	 Two 18-in beams, 70 lb per ft Two 16 by 3/4-in steel plates			 Two 18-in beams, 54 7 lb per ft Two 16 by 3/4-in steel plates			Add wt of 1 or 1/2 inch thickness
	Safe loads in tons, including weight of girder	Weight of girder, lb	Add to safe loads for 3/4-in increase in thickness of plates	Safe loads in tons, including weight of girder	Weight of girder, lb	Add to safe loads for 5 pounds increase in weight of beam	
12	132.2	2 712	5.43	123.0	2 352	2.81	
13	122.0	2 933	5.01	113.5	2 548	2.61	
14	113.3	3 164	4.66	105.3	2 744	2.43	
15	105.7	3 390	4.35	98.3	2 940	2.27	
16	99.1	3 616	4.07	92.2	3 136	2.12	
17	93.3	3 842	3.83	86.8	3 332	2.00	
18	88.1	4 068	3.62	82.0	3 528	1.90	
19	83.5	4 294	3.43	77.6	3 724	1.80	
20	79.3	4 520	3.26	73.8	3 920	1.70	
21	75.5	4 746	3.10	70.2	4 116	1.62	
22	72.1	4 972	2.96	67.0	4 312	1.54	
23	69.0	5 198	2.83	64.1	4 508	1.47	
24	66.1	5 424	2.72	61.5	4 704	1.41	
25	63.5	5 650	2.61	59.0	4 900	1.36	
26	61.0	5 876	2.51	56.7	5 096	1.30	
27	58.8	6 102	2.41	54.6	5 292	1.26	
28	56.6	6 328	2.33	52.7	5 488	1.21	
29	54.7	6 554	2.25	50.9	5 684	1.17	
30	52.9	6 780	2.17	49.2	5 880	1.13	
31	51.8	7 006	2.10	47.6	6 076	1.10	
32	49.6	7 232	2.04	46.1	6 272	1.06	
33	48.1	7 458	1.98	44.7	6 468	1.03	
34	46.7	7 684	1.92	43.4	6 664	1.00	
35	45.3	7 910	1.86	42.1	6 860	0.97	
36	44.1	8 136	1.81	41.0	7 056	0.94	
37	42.9	8 362	1.76	39.9	7 252	0.92	
38	41.2	8 588	1.72	38.8	7 448	0.90	

The above values are based on a maximum fiber-stress of 13 000 lb per sq in., 11 in both flanges deducted. See paragraph on Riveted Single-Beam and Dual Girders, page 603, and the foot-note for same regarding fiber-stresses. Weights correspond to lengths, center to center of bearings.

# Tables of Safe Loads for Steel Beams and Girders

**Table XV (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Riveted Steel-Beam Box Girders**



Two 15-in steel I beams and two 14 by 5/8-in steel plates

Distance between bearings, ft	Two 15-in beams, 75.0 lb per ft  Steel Plates, 14 by 5/8 in		Two 15-in beams, 60.8 lb per ft  Steel Plates, 14 by 5/8 in		Two 15-in beams, 42.9 lb per ft  Steel Plates, 14 by 5/8 in		Increase in safe load for 1/8-in increase in thickness of flange-plates	Increase in weight of girder for 1/8-in increase in thickness of flange-plates
	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb		
10	122.33	1.06	111.01	0.91	90.29	0.72	4.63	0.03
11	111.21	1.17	100.92	1.00	82.08	0.79	4.21	0.03
12	101.95	1.27	92.51	1.09	75.24	0.86	3.86	0.03
13	94.10	1.38	85.40	1.18	69.45	0.93	3.57	0.04
14	87.38	1.48	79.30	1.27	64.50	1.00	3.31	0.04
15	81.56	1.59	74.01	1.36	60.19	1.08	3.09	0.04
16	76.46	1.70	69.38	1.45	56.43	1.15	2.90	0.05
17	71.95	1.80	65.30	1.54	53.11	1.22	2.72	0.05
18	67.96	1.91	61.67	1.63	50.16	1.29	2.57	0.05
19	64.39	2.01	58.43	1.72	47.52	1.36	2.43	0.05
20	61.17	2.12	55.50	1.81	45.14	1.44	2.32	0.06
21	58.25	2.22	52.86	1.90	42.99	1.51	2.21	0.06
22	55.60	2.33	50.46	2.00	41.04	1.58	2.11	0.06
23	53.19	2.43	48.27	2.09	39.25	1.65	2.02	0.07
24	50.97	2.54	46.25	2.18	37.62	1.72	1.93	0.07
25	48.93	2.65	44.40	2.27	36.12	1.79	1.85	0.07
26	47.05	2.76	42.70	2.36	34.72	1.87	1.78	0.08
27	45.31	2.86	41.12	2.45	33.44	1.94	1.71	0.08
28	43.69	2.96	39.65	2.54	32.25	2.01	1.66	0.08
29	42.18	3.07	38.28	2.63	31.13	2.08	1.60	0.08
30	40.78	3.17	37.00	2.72	30.09	2.15	1.54	0.09
31	39.46	3.28	35.81	2.81	29.12	2.23	1.49	0.09
32	38.23	3.38	34.69	2.80	28.21	2.30	1.45	0.09
33	37.07	3.46	33.64	2.99	27.36	2.37	1.41	0.10
34	35.98	3.60	32.65	3.08	26.55	2.44	1.37	0.10
35	34.95	3.70	31.72	3.17	25.80	2.51	1.33	0.10
36	33.98	3.81	30.84	3.27	25.08	2.58	1.29	0.10
37	33.06	3.91	30.00	3.36	24.40	2.66	1.25	0.11
38	32.20	4.02	29.21	3.45	23.76	2.73	1.22	0.11
39	31.37	4.13	28.47	3.54	23.15	2.80	1.19	0.11

Above values are based on a maximum fiber-stress of 13 000 lb per sq in, rivet-hole flanges deducted. See paragraph on Riveted Single-Beam and Double-Beam, page 603, and the foot-note for same regarding fiber-stresses. Weights of girders based on lengths, center to center of bearings.

Table XV (Continued). Safe Uniform Loads in Tons of 2 000 Pounds  
for Riveted Steel-Beam Box Girders



Two 12-in steel I beams and two 14 by  $\frac{1}{2}$ -in steel plates

Dis- tance, center to center of bear- ings, ft	 Two 12-in beams, 40.8 lb per ft  Two steel plates, 14 by $\frac{1}{2}$ in			 Two 12-in beams, 31.8 lb per ft  Two steel plates, 14 by $\frac{1}{2}$ in			Increas- in web of girder for $\frac{1}{4}$ -in increase in the new flange plate
	Safe loads, uniformly distrib- uted (in- cluding weight of girder), in tons of 2 000 lb	Weight of girder (includ- ing rivet- heads), in tons of 2 000 lb	Increase in safe loads for $\frac{1}{4}$ -in in- crease in thickness of flange- plates	Safe loads, uniformly distrib- uted (in- cluding weight of girder), in tons of 2 000 lb	Weight of girder (includ- ing rivet- heads), in tons of 2 000 lb	Increase in safe loads for $\frac{1}{4}$ -in in- crease in thickness of flange- plates	
10	64.94	0.65	3.75	58.08	0.57	3.81	0.
11	59.02	0.71	3.40	52.80	0.63	3.45	0.
12	54.12	0.78	3.12	48.40	0.68	3.17	0.
13	49.95	0.84	2.88	44.68	0.74	2.93	0.
14	46.39	0.91	2.68	41.48	0.80	2.72	0.
15	43.29	0.97	2.50	38.72	0.85	2.53	0.
16	40.59	1.04	2.34	36.30	0.91	2.38	0.
17	38.20	1.10	2.21	34.16	0.97	2.24	0.
18	36.08	1.17	2.08	32.27	1.03	2.11	0.
19	34.18	1.23	1.97	30.57	1.08	2.00	0.
20	32.47	1.30	1.87	29.04	1.14	1.90	c
21	30.93	1.36	1.78	27.66	1.20	1.81	c
22	29.52	1.43	1.70	26.40	1.25	1.73	c
23	28.23	1.49	1.63	25.25	1.31	1.65	c
24	27.06	1.56	1.56	24.20	1.37	1.58	c
25	25.98	1.62	1.50	23.23	1.42	1.52	c
26	24.98	1.69	1.44	22.34	1.48	1.46	c
27	24.05	1.75	1.38	21.51	1.54	1.41	c
28	23.19	1.82	1.34	20.74	1.60	1.36	c
29	22.39	1.88	1.29	20.03	1.65	1.31	c
30	21.65	1.95	1.25	19.36	1.71	1.27	c
31	20.95	2.01	1.21	18.73	1.77	1.23	c
32	20.29	2.08	1.17	18.15	1.82	1.19	c
33	19.68	2.14	1.14	17.60	1.88	1.15	c
34	19.10	2.21	1.10	17.08	1.94	1.12	c
35	18.55	2.27	1.07	16.59	1.99	1.09	c
36	18.04	2.34	1.04	16.13	2.05	1.06	c
37	17.55	2.40	1.01	15.70	2.11	1.03	c
38	17.09	2.47	0.99	15.28	2.17	1.00	c
39	16.65	2.53	0.96	14.89	2.22	0.98	c

The above values are based on a maximum fiber-stress of 13 000 lb per sq in., riv in both flanges deducted. See paragraph on Riveted Single-Beam and Double Girders, page 603, and the foot-note for same regarding fiber-stresses. Weights correspond to lengths, center to center of bearings.

Table XV (Continued). Safe Uniform Loads in Tons of 2 000 Pounds for Riveted Steel-Beam Box Girders

Two 10-in steel I Beams and two 12 by ½-in steel plates

Distance, center to center of bearings, ft	 <p>Two 10-in beams, 35.0 lb per ft</p> <p>Two steel plates, 12 by ½ in</p>			 <p>Two 10-in beams, 25.4 lb per ft</p> <p>Two steel plates, 12 by ½ in</p>			Increase in weight of girder for ½-in increase in thickness of flange-plates
	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Increase in safe loads for ½-in increase in thickness of flange-plates	Safe loads, uniformly distributed (including weight of girder), in tons of 2 000 lb	Weight of girder (including rivet-heads), in tons of 2 000 lb	Increase in safe loads for ½-in increase in thickness of flange-plates	
10	44.35	0.55	2.59	39.23	0.47	2.64	0.03
11	40.32	0.60	2.36	35.66	0.52	2.40	0.03
12	36.96	0.65	2.16	32.69	0.56	2.20	0.03
13	34.12	0.71	1.99	30.18	0.61	2.03	0.03
14	31.68	0.76	1.85	28.02	0.66	1.89	0.03
15	29.57	0.82	1.73	26.15	0.71	1.76	0.04
16	27.72	0.87	1.62	24.52	0.75	1.65	0.04
17	26.09	0.93	1.52	23.08	0.80	1.55	0.04
18	24.64	0.98	1.44	21.79	0.85	1.47	0.04
19	23.34	1.04	1.36	20.65	0.89	1.39	0.05
20	22.18	1.09	1.30	19.62	0.94	1.32	0.05
21	21.12	1.15	1.23	18.68	0.99	1.26	0.05
22	20.16	1.20	1.18	17.83	1.04	1.20	0.05
23	19.28	1.26	1.13	17.06	1.08	1.15	0.06
24	18.48	1.31	1.08	16.35	1.13	1.10	0.06
25	17.74	1.36	1.04	15.69	1.18	1.06	0.06
26	17.06	1.42	1.00	15.09	1.22	1.02	0.06
27	16.43	1.47	0.96	14.53	1.27	0.98	0.07
28	15.84	1.53	0.93	14.01	1.32	0.94	0.07
29	15.29	1.58	0.89	13.53	1.37	0.91	0.07
30	14.78	1.64	0.86	13.08	1.41	0.88	0.07
31	14.31	1.69	0.84	12.65	1.46	0.85	0.08
32	13.86	1.75	0.81	12.26	1.51	0.82	0.08
33	13.44	1.80	0.78	11.89	1.55	0.80	0.08
34	13.04	1.86	0.76	11.54	1.60	0.78	0.08
35	12.67	1.91	0.74	11.21	1.65	0.75	0.09
36	12.32	1.96	0.72	10.90	1.70	0.73	0.09
37	11.99	2.02	0.70	10.60	1.74	0.71	0.09
38	11.67	2.07	0.68	10.32	1.79	0.69	0.09
39	11.37	2.13	0.66	10.06	1.84	0.67	0.10

The above values based on a maximum fiber-stress of 13 000 lb per sq in, rivet-hole with flanges deducted. See paragraph on Riveted Single-Beam and Double-Beam on page 603, and the foot-note for same regarding fiber-stresses. Weights of girder based on lengths, center to center of bearings.

**Beams Supporting Brick Walls.** In calculating the size of a girder to support a brick wall, the structure of the wall should be carefully considered. If the wall is without openings and does not support floor-beams, only that part of the wall included within the dotted lines, Fig. 10, need be considered as being supported by the girder. The beams in that case, however, should be made very **STIFF**, so as to have little **DEFLECTION**. If there are several openings above the girder, and especially if there is a pier over the middle part of it, as shown in Fig. 11, then the manner in which the loading is distributed should be carefully considered. In a case of this kind, only the dead weight included between the dotted lines *AA* and *BB* should be considered




Fig. 10. Triangular Loading of Beams under Brick Walls

Fig. 11. Loading of Beams under Walls with Openings


as coming upon the girder, and proper allowance made for the **CONCENTRATION** of the greater part of the load at or near the middle. If, however, the windows are two-thirds their total width, or more, above the girder, it is more reasonable to suppose that the wall included between the lines rests upon the girder, and also to consider that this load is **UNIFORMLY TRIBUTED** over it. When beams extend under the entire length of a wall which is more than 16 or 18 ft long, the weight of the entire wall rather than the weight of a triangular part of it should be taken as coming upon the beams; for, if they should bend, the wall would settle, and might push the supports and cause the whole structure to fall. (See, also, page 318.)

#### 5. Framing and Connecting Steel Beams and Girders

**Standard Separators.** When beams are used to support walls, or as girders to carry floor-beams, they are often placed side by side; and should in such cases be connected by means of **BOLTS** and cast-iron **SEPARATORS** placed closely between the flanges of the beams. The office of these separators is to measure, to hold in position the compression-flanges of the beams by preventing **SIDE DEFLECTION** or **BUCKLING**, and also to unite the beams so as to enable them to act in unison as regards **VERTICAL DEFLECTION**. Separators should be provided at the supports, at points where heavy concentrated loads are imposed, and at regular intervals of from 5 to 6 ft between. The illustrations, dimensions, etc., given in Table XVI, are for the **STANDARD SEPARATORS** in common use.

Table XVI.\* Separators for Steel Beams

AMERICAN BRIDGE COMPANY STANDARD

Beams			Separators						3/4-in bolts			Diagrams
Weight per foot, lb	Center to center of beams, in	Out to out of flanges, in	Dimensions				Weight, lb	Increase in weight for 1" add. width	Increase in weight for 1" add. length			
			g in	h in	d in	t in						
85, 100, 105, 100	8 1/2	16 3/4	8	20	12	3/8	31	3.6	10 1/4	3.4	0.25	
95 and 90	8	15 3/4	7 1/2	20	12	3/8	28	3.6	10	3.2	0.25	
85	8	15 3/4	7 1/2	20	12	3/8	29	3.6	9 1/2	3.1	0.25	
79 9	8	15	7 1/2	20	12	3/8	29	3.6	9 1/2	3.1	0.25	
70 and 95	8	13 3/4	7	16	12	3/8	22	2.9	10	3.2	0.25	
90	7 1/2	14 1/4	6 3/4	16	12	3/8	22	2.9	9 1/4	3.1	0.25	
85 and 81 1/2	7 1/2	14 1/2	6 3/4	16	12	3/8	22	2.9	9	3.0	0.25	
75	7 1/2	14	6 3/4	16	12	3/8	22	2.9	9	3.0	0.25	
70	7	13 1/4	6 3/4	16	12	3/8	21	2.9	9	3.0	0.25	
65 1/2	7	13 1/4	6 3/4	16	12	3/8	21	2.9	8 1/2	3.0	0.25	
90	8	15 1/4	7	14	9	5/8	20	2.5	10	3.2	0.25	
85 and 80	8	15 1/4	7 1/2	14	9	5/8	21	2.5	10	3.2	0.25	
75 1/2	8	15	7 1/2	14	9	5/8	21	2.5	10	3.2	0.25	
70 and 65	7	13 1/4	6 1/2	14	9	5/8	18	2.5	9	3.0	0.25	
60	7	13 1/4	6 1/2	14	9	5/8	19	2.5	8 1/2	3.0	0.25	
51 1/2	7	13	6 1/2	14	9	5/8	19	2.5	8 1/4	3.0	0.25	
75	7	13 1/4	6	11	7 1/2	5/8	12	1.6	9	3.0	0.25	
70 and 65	7	13 1/4	6 1/4	11	7 1/2	5/8	12	1.6	9	3.0	0.25	
60 1/2	6 1/2	12 1/2	5 3/4	11	7 1/2	5/8	11	1.6	8	2.7	0.25	
55	6 1/2	12 1/2	5 3/4	11	7 1/2	5/8	11	1.6	8	2.7	0.25	
50 and 45	6 1/2	12 1/4	6	11	7 1/2	5/8	12	1.6	8	2.7	0.25	
42 9	6 1/2	12	6	11	7 1/2	5/8	12	1.6	8	2.		
55	6	11 3/4	5 3/4	8 3/4	5	3/4	9	1.3	8	2.		
50	6	11 3/4	5 1/4	8 1/4	5	3/4	9	1.3	8	2.		
45	6	11 3/4	5 1/4	8 1/4	5	3/4	9	1.3	7 3/4	2.		
40 and 35	6	11 3/4	5 1/4	8 1/4	5	3/4	9	1.3	7 3/4	2.		
31 1/2	6	11	5 1/4	8 3/4	5	3/4	9	1.3	7 1/4	2.		
40	5 1/4	10 3/4	4 3/4	7 1/4	...	1/2	6	1.1	7 1/2	1.		
35	5 1/4	10 3/4	4 3/4	7 1/4	...	1/2	6	1.1	7	1.		
30	5 1/4	10 1/2	5	7 1/4	...	1/2	7	1.1	7	1.		
25 1/2	5 1/4	10	5	7 1/4	...	1/2	7	1.1	7	1.		
35	5	10	4 3/4	6 1/2	...	1/2	5	0.9	7	1.		
30	5	9 1/4	4 1/4	6 1/4	...	1/2	5	0.9	6 1/4	1.		
25	5	9 1/4	4 1/4	6 1/4	...	1/2	5	0.9	6 1/4	1.		
22	5	9 1/4	4 3/4	6 1/4	...	1/2	5	0.9	6 1/4	1.2	0.13	
25 1/2	4 1/2	9	4	5 1/2	...	1/2	4	0.8	6	1.1	0.13	
25	4 1/2	8 3/4	4	5 1/4	...	1/2	4	0.8	6	1.1	0.13	
20 and 18 1/2	4 1/2	8 1/4	4	5 1/4	...	1/2	4	0.8	6	1.1	0.13	
20	4 1/2	8 1/4	4	5	...	1/2	4	0.7	6	1.1	0.13	
17 1/2	4 1/2	8 1/4	4	5	...	1/2	4	0.7	6	1.1	0.13	
15 1/2	4 1/2	8 1/4	4 1/4	5	...	1/2	4	0.7	6	1.1	0.13	
17 1/2	4	7 3/4	3 3/4	4 3/4	...	1/2	4	0.6	5 1/2	1.1	0.13	
14 1/2	4	7 3/4	3 3/4	4 3/4	...	1/2	4	0.6	5 1/2	1.1	0.13	
12 1/2	4	7 3/4	3 3/4	4 3/4	...	1/2	4	0.6	5 1/2	1.1	0.13	

1 1/8	1 1/8	15	40
1/2" spaced holes			

1 1/8	1 1/8	15	40
3/8" cored hole			

For 5-in, 4-in and 3-in beams, use 1-in gas-pipes, 3 1/4, 3 and 2 3/4-in long, respectively

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

**Gas-Pipe Separators.** Separators formed of pieces of GAS-PIPE, cut to desired lengths and slipped over the bolts are often used by contractors. (bottom of Table XVI.) Such separators permit the beams to act independent of each other, and should not be used in any place where one beam is liable to receive a greater load than the other; and as this condition exists in almost every case where two or more beams are used together, it follows that "cast iron separators, made to fit the space between the beams," should be specified in almost every instance. As noted in Table XVI, gas-pipe may sometimes be used for 5, 4 and 3-in beams. Separators with two bolts should be used on beams 12 in or more in depth. For 12-in beams one bolt is sometimes used when the load is light; for beams under 12 in in depth one bolt is sufficient.

## FRAMING

### DETAILS OF FRAMING BETWEEN COLUMNS





Fig. 12. Framing of Steel I Beams and Girders

"Connection-angles shall in no case be less in thickness than the web of the beam or girder to which they are fastened, nor shall the width be less than  $\frac{1}{3}$  the depth of the beam, except that no angle-knee shall be less than  $2\frac{1}{2}$ " wide nor required to be more than 6" wide. Web-angles, the full depth of the web, must be used for all girder connections."

**Beam-Connections.** Steel beams and channels are FRAMED together by means of short pieces of angles, which are usually riveted to the floor-beam or tail-beam and bolted to the girder. The angles are always used in pairs, one on each side of the beam. If the floor-beam is framed flush, either with the top or bottom of the girder, or if two beams of the same height are framed together, the end of the beam supported should be COPED, or cut to fit the shape of the girder or supporting beam. The maximum clearance-space allowed between the



sh with that of the beam girder and coped to fit it, except where the girder is on a  
 set  $2\frac{1}{4}$  in below the beams so the latter may be  
 and coped. All openings in the floor, except  
 all sides. Built-up girders are to be set with  
 necessary and required  $3\frac{1}{4}$  by  $3\frac{1}{4}$  by  $\frac{3}{4}$ -in or  
 , roof and vault-arching.



id channels between girders and not more than  $\frac{1}{4}$  at each  
 be true to the drawings and an error of more than  $\frac{1}{16}$  in  
 variation of more than  $\frac{1}{2}$  in in the length of beams sup-  
 sufficient cause for rejection.

“ Beam  
 line wit  
 are to b  
 of the l  
 above t  
 beams,

g to Riveted Plate Girder

on  $\frac{1}{16}$  in in the smaller beams to  $\frac{1}{8}$  in in the  
 w various details of beams framed together  
 beam rests on top of another beam or girder,  
 secured by means of a pair of wrought-iron

**CLIPS**, shown in Fig. 14, shaped so as to fit closely the top flange of the girder and either bolted or riveted to the opposite sides of the lower flange of the floor beam.

Fig. 16 shows one method of framing the ends of wooden floor-joists to steel beams, a 4 by 3 by  $\frac{3}{8}$ -in angle being riveted the whole length of the steel beam by  $\frac{3}{4}$ -in rivets, about 6 in apart. The joists are usually secured by iron



Fig. 14. Clip for Fastening Steel Beam on Top of Another




Fig. 15. Steel Beams Fastened One on the Other by Clips




Fig. 16. Framing of Wood Joists to Steel I Beam







**CLAMPS OR ANCHORS**, and framed about 1 in above the upper flange of the beam to allow for settlement. If these joists are over 3 ft apart, short lengths of angle may be placed under each one.\*

**Standard Connection-Angles for I Beams and Channels.** The size of the angles and the number of rivets used for connecting steel beams, varies somewhat with different shops and with different structural engineers, so that there cannot be said to be a universal standard. The variations in the different **STANDARDS**, however, are not very great, and as the connections adopted by the Carnegie Steel Company are perhaps the most used, the author has selected them for illustration in Table XVII. The **CONNECTIONS** have been proportioned with a view to covering most cases occurring in ordinary practice with the usual relations of depth of beam to length of span. In extreme instances, however, where beams of short relative span-lengths are loaded to their full capacity, or when beams frame opposite each other into another beam with web-thickness less than  $\frac{9}{16}$  in, it may be found necessary to make provision for additional strength in the connections. The **LIMITING SPAN-LENGTHS**, at and above which the standard connection-angles may be used with perfect safety, are also given in Table XVIII.

\* For details of the framing of floor-beams and girders, see Chapters XXI and XXII and also Professor Nolan's revised Chapters II and VII of Kidder's Building-Construction and Superintendence, Part II, Carpenters' Work.

Table XVII.\* Connections for Steel Beams

AMERICAN BRIDGE COMPANY STANDARD

27"	24"
<p>2 Ls 4' x 4' x <math>\frac{3}{8}</math>" x 1' 8<math>\frac{1}{2}</math>" Weight 46 lb</p> <p>21"</p>  <p>2 Ls 4' x 4' x <math>\frac{3}{8}</math>" x 1' 2<math>\frac{1}{2}</math>" Weight 33 lb</p> <p>12"</p>  <p>2 Ls 4' x 4' x <math>\frac{3}{8}</math>" x 0' 8<math>\frac{1}{2}</math>" Weight 17 lb</p> <p>7', 6', 5"</p>  <p>2 Ls 6' x 4' x <math>\frac{3}{8}</math>" x 0' 8"</p> <p>Weight 7 lb</p>	<p>2 Ls 4' x 4' x <math>\frac{3}{8}</math>" x 1' 5<math>\frac{1}{2}</math>" Weight 39 lb</p> <p>20", 18", 15"</p>  <p>2 Ls 4' x 4' x <math>\frac{3}{8}</math>" x 0' 11<math>\frac{1}{2}</math>" Weight 23 lb</p> <p>10", 9", 8"</p>  <p>2 Ls 6' x 4' x <math>\frac{3}{8}</math>" x 0' 5<math>\frac{1}{2}</math>" Weight 13 lb</p> <p>4", 3"</p>  <p>2 Ls 6' x 4' x <math>\frac{3}{8}</math>" x 0' 3"</p> <p>Weight 5 lb</p>

Rivets and bolts  $\frac{3}{4}$ " diameterWeights given are for  $\frac{3}{4}$ " shop rivets and angle-connections; about 20 per cent should be added for field-rivets or bolts

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

Table XVIII.\* Limiting Values of Connections for Steel Beams

I beams		Value of web-con- nection	Values of outstanding legs of connection-angles				
Depth, in	Weight, lb per ft		Field-rivets			Field-bolts	
		Shop- rivets in enclosed bearing, lb	3/4-in rivets or turned bolts, single shear, lb	Min. allow- able span, uniform load, ft	t, in	3/4-in rough bolts, single shear, lb	Min. allow- able span, uniform load, ft
27	90	82 530	61 900	18.9	5/8	49 500	23.6
24	{ 79.9	67 500	53 000	17.5	5/8	42 400	21.9
	{ 74.2	64 260	53 000	16.4	5/8	42 400	20.4
21	60.4	48 150	44 200	14.2	5/8	35 300	17.8
20	65.4	45 000	35 300	17.6	5/8	28 300	22.1
18	{ 54.7	41 400	35 300	13.3	5/8	28 300	16.7
	{ 48.2	34 200	35 300	12.8	9/16	28 300	15.4
15	{ 42.9	36 900	35 300	8.9	5/8	28 300	11.1
	{ 37.3	29 880	35 300	9.7	1/2	28 300	10.2
12	{ 31.8	23 600	26 500	8.1	9/16	21 200	9.0
	{ 27.9	19 170	26 500	9.2	7/16	21 200	9.2
10	{ 25.4	27 900	17 700	7.4	5/8	14 100	9.2
	{ 22.4	22 680	17 700	6.8	5/8	14 100	8.6
9	21.8	26 100	17 700	5.7	5/8	14 100	7.1
8	{ 18.4	24 300	17 700	4.3	5/8	14 100	5.4
	{ 17.5	18 900	17 700	4.4	5/8	14 100	5.5
7	15.3	11 300	8 800	6.2	5/8	7 100	7.8
6	12.5	10 400	8 800	4.4	5/8	7 100	5.5
5	10.0	9 500	8 800	2.9	5/8	7 100	3.6
4	7.7	8 600	8 800	2.2	9/16	7 100	2.7
3	5.7	7.700	8 800	1.3	1/2	7 100	1.4

## ALLOWABLE UNIT STRESS IN POUNDS PER SQUARE INCH †

Single shear	Rivets.....shop	12 000	Bearing	Rivets, enclosed..shop	30
	Rivets and turned			Rivets, one side..shop	24
	bolts.....field	10 000		Rivets and turned	
	Rough bolts.....field	8 000		bolts.....field	20
				Rough bolts.....field	16

t = Web-thickness, in bearing, to develop maximum allowable reactions, with beams frame opposite

Connections are figured for bearing and shear (no moment considered)

The above values agree with tests made on beams under ordinary conditions use

Where the web is enclosed between connection-angles (enclosed bearing), values are greater because of the increased efficiency due to friction and grip


Special connections must be used when any of the limiting conditions given above are exceeded, as when an end-reaction from a loaded beam is greater than the value of the connection of the shorter span with the beam fully loaded; or a thickness of web when maximum allowable reactions are used

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For slight variations from these values, see Chapter XXVIII, Table I and Chapter XXX, 4, Stresses.

Table XIX.\* Lengths and Weights of Tie-Rods and Anchors for Steel Beams

AMERICAN BRIDGE COMPANY STANDARD



## 3/4-INCH TIE-RODS

LENGTHS AND WEIGHTS FOR VARIOUS DISTANCES CENTER TO CENTER OF BEAMS  
Weights include two nuts

CtoC	L'th	Wgt	CtoC	L'th	Wgt	CtoC	L'th	Wgt	CtoC	L'th	Wgt
ft in	ft in	lb	ft in	ft in	lb	ft in	ft in	lb	ft in	ft in	lb
1 0	1 3	2.30	1 3	1 6	2.67	1 6	1 9	3.05	1 9	2 0	3.42
2 0	2 3	3.80	2 3	2 6	4.17	2 6	2 9	4.55	2 9	3 0	4.92
3 0	3 3	5.30	3 3	3 6	5.67	3 6	3 9	6.05	3 9	4 0	6.42
4 0	4 3	6.80	4 3	4 6	7.17	4 6	4 9	7.55	4 9	5 0	7.92
5 0	5 3	8.30	5 3	5 6	8.67	5 6	5 9	9.05	5 9	6 0	9.42
6 0	6 3	9.80	6 3	6 6	10.17	6 6	6 9	10.55	6 9	7 0	10.92
7 0	7 3	11.30	7 3	7 6	11.67	7 6	7 9	12.05	7 9	8 0	12.42
8 0	8 3	12.80	8 3	8 6	13.17	8 6	8 9	13.55	8 9	9 0	13.92

For strength of rods, see Table II, page 388.

## Anchors \*


## SWEDGE-BOLT



Weight includes nut  
BUILT-IN ANCHOR-BOLTS



Diameter	Length	Weight
in	ft in	lb
3/4	0 9	1.3
3/8	1 0	2.3
1	1 0	3.1
1 1/4	1 8	6.1

## GOVERNMENT ANCHOR



3/4-in rod, 1 ft 9 in long. Wt., 3 lb

## ANGLE-ANCHOR



When center to center of anchors is less than width of washer, use washer with two holes

Two angles, 6 by 4 by 7/16 by 2 1/2 in  
Weight with 3/4-in bolts, 7 lb

For bearing-plates, bases, etc., see Chapter XIII.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

## CHAPTER XVI

## STRENGTH OF CAST-IRON LINTELS AND WOODEN BEAMS

By

F. H. KINDL

LATE CORRESPONDING MEMBER AMERICAN INSTITUTE OF ARCHITECTS

## 1. Cast-Iron Lintels

**Form of Cross-Section.** Owing to the fact that the resistance of cast iron to tension is only about one-fifth of its resistance to compression, the shapes of beams most economical for wrought iron or steel would be wasteful for cast iron. The extreme brittleness of cast iron, and the danger of flaws in casting, render it an undesirable material for resisting transverse stress. About the only form in which cast-iron beams are now used in building-construction in this country is in the shape of LINTELS for supporting brick or stone walls,

places where a flat soffit is desired, and the walls are not to be plastered. CAST-IRON LINTELS are also occasionally used over store-fronts, the face of the lintel being paneled and molded for architectural effect.




Fig. 1. Cross-section of Cast-iron Lintel of Ideal Form

**Experiments on Cast-Iron Beams.** Before wrought-iron I beams were manufactured, CAST-IRON BEAMS were frequently used as the only available ones, other than those of wood or stone. Early in the nineteenth century Eaton Hodgkinson, an English engineer, made a series of experiments with cast-iron beams, from which he found that the form of cross-section of a beam of this material which will resist the greatest transverse

stress is that shown in Fig. 1, in which there is six times more metal in the bottom than in the top flange. The relative thicknesses of the three parts, web, the top flange and the bottom flange, may be, with advantage, as 5, 6 and 8, respectively.

**Strength of Cast-Iron Beams.** If made with these proportions, the width of the top flange will be equal to one-third that of the bottom flange. As a result of his experiments, Hodgkinson gave the following rule for the breaking weight at the middle for a cast-iron beam of this form:

$$\text{Breaking-load in tons} = \frac{\left( \frac{\text{area of bottom flange}}{\text{in square inches}} \right) \times \left( \frac{\text{depth}}{\text{in inches}} \right) \times 2.426}{\text{clear span in feet}}$$

This rule, although largely empirical, agreed very well with the few experiments that were made. Structural engineers, however, use the general formulas for the strength of beams, as given in Chapter XV, except that the SECTION MODULUS is found by dividing the MOMENT OF INERTIA by the distance of the neutral axis from the bottom of the beam, and the SAFE TENSILE STRENGTH


used in the FLEXURE-FORMULA. Thus the general formula for a beam supported at both ends and with the load uniformly distributed, as given in Chapter XV, page 560, is:

Safe load in pounds =  $2\frac{1}{2} \frac{I/c}{l} \times S_t$ . As  $S_t$ , the safe tensile strength for cast iron should be taken at 3 000 lb, this formula becomes

$$\text{Safe load in pounds} = \frac{2\,000\, I/c}{l} \quad (2)$$

and, for either section given below,

$$I/c = \frac{\text{Moment of inertia}}{d_1}$$



The MOMENT OF INERTIA is computed by the formula (see page 337)

$$I = \frac{bd^3 + b'd_1^3 - (b' - b)d_2^3}{3} \quad (3)$$

in which  $b$  denotes the combined thickness of the webs, and the distances  $d$ ,  $d_1$ , and  $d_2$  are measured from the NEUTRAL AXIS, which must pass through the CENTER OF GRAVITY of the section. The center of gravity may be found by the method explained in Chapter VI. This formula may be used for any of the above sections when the depth does not exceed the width, and the thickness of each web is at least equal to the thickness of the flange. In lintels with a single web it is well to make the thickness of the web  $\frac{1}{2}$  or  $\frac{1}{3}$  in greater than the thickness of the flange. For a lintel with a cross-section like that shown in Fig. 1, Formula (2) agrees very closely with Formula (1), when a factor of safety of six is used.

**Example.** The following example illustrates the application of Formula (2): It is required to compute the safe load for a cast-iron lintel having the cross-section shown in Fig. 2 and a clear span of 10 ft. The load is uniformly distributed, and the thickness of the metal 1 in.




Fig. 2. Cross-section of Cast-iron Lintel with Three Webs

**Solution.** The first step is the finding of distance  $d$ , that the center of gravity, through which the neutral axis of the cross-section passes, is below the top-face of the beam. This is found by taking the moments of the areas of the sections of webs and flange about the line  $XY$ , and dividing their sum by the area of the entire section. (See page 234.) Each web-section is 11 in deep and 1 in thick; hence the area of each is 11 sq in. The MOMENTS OF THE THREE WEBS about  $XY$  will then be  $3 \times 11 \times 5\frac{1}{2} = 181.5$   
 THE MOMENT OF THE FLANGE about  $XY = 28 \times 11\frac{1}{2} = 322$   
 503.5

The area of the entire cross-section = 61 sq in

$$503.5 + 61 = 8.25 = d \text{ in}$$

Then

$$d = 8.25 \text{ in}$$

$$d^3 = 561.5$$

$$b = 3 \text{ in}$$

$$d_1 = 3.75 \text{ in}$$

$$d_1^3 = 52.7$$

$$b' = 28 \text{ in}$$

$$d_2 = 2.75 \text{ in}$$

$$d_2^3 = 20.8$$

The MOMENT OF INERTIA is next found by Formula (3):

$$I = \frac{3 \times 561.5 + 28 \times 52.7 - 25 \times 20.8}{3} = 880$$

$I/c = 880/3.75$ . From Formula (2) the safe load =  $(2\,000 \times 234.6)/10 = 46\,920$  lb, or 23.4 tons.

**Ends and Brackets of Cast-Iron Lintels.** When a lintel, the cross-section of which has the shape of an inverted T ( $\perp$ ), is used over a single opening,




Fig. 3. Cast-iron Lintel with Tapering Web

web may be tapered towards the ends, as in Fig. 3, without affecting the strength. If the flange is more than 8 in wide, brackets should be cast in the middle, as shown at A, Fig. 3.

When CONTINUOUS LINTELS are used over store-fronts or similar places, the ends should be cast on the lintels, as in Fig. 4, and the ends of abutting lintels




Fig. 4. Cast-iron Lintel with Ends for Bolting

bolted together. All lintels with two or three webs should have solid ends connecting the webs.

**Tables of Strength of Cast-Iron Lintels.** The tables on the following pages have been computed in accordance with Formula (2). The weight of




lintel itself should be deducted from the safe load. In using these tables it should be remembered that the values are for loads UNIFORMLY DISTRIBUTED. If the load is CONCENTRATED AT THE MIDDLE, it should be multiplied by 2. If at some other point than the middle, the load should be multiplied by the value given on pages 566 and 632, which most nearly corresponds with the position of the load. For other spans than those given, the distributed load should be multiplied by the span, and the lintel used which has a COEFFICIENT OF STRENGTH (Table I) just above the product thus obtained. (For explanation of coefficient of strength, see Chapter XV, page 556.)

**Example.** It is required to support a 12-in brick wall, 10 ft high, over an opening 5 ft 6 in wide, with a cast-iron lintel. At a distance of 22 in from one support, a girder, which may bring a load of 9 600 lb on the lintel, enters the wall. What should be the dimensions of the lintel?

**Solution.** At 110 lb per cu ft, the wall above the lintel weighs  $10 \times 5\frac{1}{2} \times 110 = 6050$  lb. As 22 in is one-third of the span, the concentrated load is multiplied by 1.78 (page 632), making the load 17 088 lb. The total equivalent distributed load is then 23 138 lb. Multiplying this by the span there results 27 259 lb, or 63.6 tons, as the least value for the coefficient of strength  $C$ . From the table, it is found that a 12 by 10-in lintel, 1 in thick, with one web, has a coefficient of strength of 72.2; and that a 12 by 8 by  $1\frac{1}{4}$ -in lintel with two webs, has a coefficient of strength of 69.9. A lintel with two webs is best for a 12-in wall, and interpolating between the values of  $C$  for the 1-in and 2-in thicknesses of the 12 by 8-in lintel, 65.4 is found to be the value of  $C$  for a thickness of  $1\frac{1}{8}$  in. This exceeds the required value by enough to more than compensate for the weight of the lintel itself; hence a 12 by 8 by  $1\frac{1}{8}$ -in lintel with two webs is used.

**Flaws in Castings.** Owing to the liability of flaws in the castings, cast-iron lintels should always be carefully inspected before being accepted.


Table I. Safe Distributed Loads in Tons for Cast-Iron Lintels



Loads include weights of lintels. Maximum tensile stress 3 000 lb per sq in. remarks, pages 622 and 623.

Size, width by depth, in	Thick- ness of metal, in	Weight per foot, lb	C, tons	Span in feet							
				5	6	7	8	9	10	11	12
6× 6	¾	26.3	15.9	3.18	2.65	2.27	1.98	1.76	1.59	1.44	1.30
	1	34.4	19.0	3.80	3.16	2.71	2.37	2.11	1.90	1.72	1.57
	1¼	42.0	21.5	4.30	3.58	3.07	2.68	2.39	2.15	1.95	1.78
7× 6	¾	28.6	17.8	3.56	2.96	2.54	2.22	1.98	1.78	1.61	1.46
	1	37.5	21.3	4.26	3.55	3.04	2.66	2.36	2.13	1.93	1.77
	1¼	45.9	24.0	4.80	4.00	3.43	3.00	2.66	2.40	2.18	2.00
7× 7	¾	31.0	22.6	4.52	3.76	3.23	2.82	2.51	2.26	2.05	1.87
	1	40.6	27.5	5.50	4.58	3.93	3.43	3.05	2.75	2.50	2.28
	1¼	49.8	31.4	6.28	5.23	4.49	3.92	3.49	3.14	2.85	2.60
8× 6	¾	31.0	19.6	3.92	3.26	2.80	2.45	2.18	1.96	1.78	1.62
	1	40.6	23.4	4.68	3.90	3.34	2.92	2.60	2.34	2.12	1.94
	1¼	49.8	26.4	5.28	4.40	3.77	3.30	2.93	2.64	2.40	2.18
8× 7	¾	33.3	25.0	5.00	4.16	3.57	3.12	2.77	2.50	2.27	2.06
	1	43.7	30.3	6.06	5.05	4.33	3.79	3.36	3.03	2.75	2.50
	1¼	53.7	34.8	6.96	5.80	4.97	4.35	3.86	3.48	3.16	2.88
8× 8	¾	35.6	30.6	6.12	5.10	4.37	3.82	3.40	3.06	2.78	2.54
	1	46.8	37.6	7.52	6.26	5.37	4.70	4.18	3.76	3.41	3.12
	1¼	57.6	43.4	8.68	7.23	6.20	5.42	4.82	4.34	3.94	3.58
8× 9	¾	38.0	36.5	7.30	6.08	5.21	4.56	4.05	3.65	3.31	3.02
	1	50.0	45.2	9.04	7.53	6.45	5.65	5.02	4.52	4.11	3.76
	1¼	61.5	52.6	10.52	8.76	7.51	6.57	5.84	5.26	4.78	4.38
12× 6	¾	40.4	26.5	5.30	4.41	3.78	3.31	2.94	2.65	2.41	2.19
	1	53.1	31.6	6.32	5.26	4.51	3.95	3.51	3.16	2.87	2.60
	1¼	65.4	34.8	6.96	5.80	4.97	4.35	3.86	3.48	3.16	2.88
12× 8	¾	45.0	41.7	8.34	6.95	5.95	5.21	4.63	4.17	3.79	3.46
	1	59.4	51.2	10.24	8.53	7.31	6.40	5.69	5.12	4.65	4.28
	1¼	73.2	58.5	11.70	9.75	8.35	7.31	6.50	5.85	5.32	4.90
12× 10	¾	49.8	58.0	11.60	9.66	8.28	7.25	6.44	5.80	5.27	4.84
	1	65.6	72.2	14.44	12.03	10.31	9.02	8.02	7.22	6.56	6.06
	1¼	81.0	83.8	16.76	13.96	11.97	10.47	9.31	8.38	7.62	7.06
12× 12	¾	54.4	75.2	15.04	12.53	10.74	9.40	8.35	7.52	6.83	6.32
	1	71.9	94.8	18.96	15.80	13.54	11.85	10.53	9.48	8.62	7.98
	1¼	88.9	111.5	22.30	18.58	15.92	13.93	12.39	11.15	10.12	9.38


Table 1 (Continued). Safe Distributed Loads in Tons for Cast-Iron Lintels



Loads include weights of lintels. Maximum tensile stress 3 000 lb per sq in. See marks, pages 622 and 623.


Size, width by depth, in	Thick- ness of metal, in	Weight per foot, lb	C, tons	Span in feet							
				5	6	7	8	9	10	11	12
6X 6	¾	52.7	31.7	6.34	5.28	4.53	3.96	3.52	3.17	2.88	2.64
	1	68.8	37.6	7.52	6.26	5.37	4.70	4.18	3.76	3.42	3.13
	1¼	84.0	43.0	8.60	7.16	6.14	5.37	4.77	4.30	3.91	3.58
6X 8	¾	62.1	49.5	9.90	8.25	7.07	6.19	5.50	4.95	4.50	4.12
	1	81.3	60.9	12.18	10.15	8.70	7.61	6.76	6.09	5.53	5.07
	1¼	99.6	69.9	13.98	11.65	9.98	8.73	7.76	6.99	6.35	5.82
6X 6	¾	57.4	35.5	7.10	5.91	5.07	4.43	3.94	3.55	3.22	2.96
	1	75.0	42.0	8.40	7.00	6.00	5.25	4.66	4.20	3.82	3.50
	1¼	91.8	48.0	9.60	8.00	6.85	6.00	5.33	4.80	4.36	4.00
6X 8	¾	66.8	55.4	11.08	9.23	7.91	6.92	6.15	5.54	5.03	4.61
	1	87.5	68.1	13.62	11.35	9.73	8.51	7.56	6.81	6.19	5.67
	1¼	107.4	78.8	15.76	13.13	11.25	9.85	8.75	7.88	7.16	6.56
6X 6	¾	62.1	39.1	7.82	6.51	5.58	4.88	4.34	3.91	3.55	3.25
	1	81.3	46.8	9.36	7.80	6.68	5.85	5.20	4.68	4.25	3.90
	1¼	99.6	52.9	10.58	8.81	7.55	6.61	5.88	5.29	4.81	4.40
6X 8	¾	71.5	61.4	12.28	10.23	8.77	7.67	6.82	6.14	5.58	5.11
	1	93.8	74.6	14.92	12.43	10.65	9.32	8.29	7.46	6.78	6.21
	1¼	115.2	86.8	17.36	14.46	12.40	10.85	9.64	8.68	7.89	7.23
6X 6	¾	71.5	47.2	9.44	7.86	6.74	5.90	5.24	4.72	4.29	3.93
	1	93.8	55.1	11.02	9.18	7.87	6.88	6.12	5.51	5.01	4.59
	1¼	115.2	62.0	12.40	10.33	8.85	7.75	6.88	6.20	5.63	5.16
6X 8	¾	80.8	72.6	14.52	12.10	10.37	9.07	8.06	7.26	6.60	6.05
	1	106.2	89.5	17.90	14.91	12.78	11.18	9.94	8.95	8.13	7.45
	1¼	130.8	102.5	20.50	17.08	14.64	12.81	11.39	10.25	9.31	8.54
6X 10	¾	90.2	100.5	20.10	16.75	14.35	12.56	11.16	10.05	9.13	8.37
	1	118.8	125.4	25.08	20.90	17.91	15.67	13.93	12.54	11.40	10.45
	1¼	146.5	146.8	29.36	24.46	20.97	18.35	16.31	14.68	13.34	12.23
6X 12	¾	99.6	122.6	24.52	20.43	17.51	15.32	13.62	12.26	11.14	10.21
	1	131.3	158.0	31.60	26.33	22.57	19.75	17.55	15.80	14.36	13.16
	1¼	162.1	189.5	37.90	31.58	27.07	23.68	21.05	18.95	17.22	15.79
6X 8	¾	90.2	83.4	16.68	13.90	11.91	10.42	9.26	8.34	7.58	6.95
	1	118.8	102.4	20.48	17.06	14.63	12.80	11.37	10.24	9.31	8.53
	1¼	146.5	117.0	23.40	19.50	16.71	14.62	13.00	11.70	10.63	9.75

Table I (Continued). Safe Distributed Loads in Tons for Cast-Iron Lintels




Loads include weights of lintels. Maximum tensile stress 3 000 lb per sq in. remarks, pages 622 and 623.

Size, width by depth, in	Thick- ness of metal, in	Weight per foot, lb	C, tons	Span in feet							
				5	6	7	8	9	10	11	12
24×10	¾	99.6	116.0	23.20	19.33	16.57	14.50	12.88	11.60	10.54	9.60
	I	131.3	144.4	28.88	24.06	20.63	18.05	16.04	14.44	13.12	12.00
	1¼	162.1	167.6	33.52	27.93	23.94	20.95	18.62	16.76	15.23	13.80
24×12	¾	109.0	150.4	30.08	25.06	21.48	18.80	16.71	15.04	13.67	12.40
	I	143.8	189.6	37.92	31.60	27.08	23.70	21.06	18.96	17.23	15.60
	1¼	177.7	223.0	44.60	37.16	31.85	27.87	24.77	22.30	20.27	18.40
28×8	¾	99.6	95.5	19.10	15.91	13.64	11.93	10.61	9.55	8.68	7.90
	I	131.3	115.0	23.00	19.16	16.43	14.37	12.77	11.50	10.45	9.50
	1¼	162.1	130.5	26.10	21.75	18.64	16.31	14.50	13.05	11.86	10.80
28×10	¾	109.0	130.0	26.00	21.67	18.57	16.25	14.44	13.00	11.82	10.80
	I	143.8	164.8	32.96	27.46	23.54	20.60	18.31	16.48	14.98	13.60
	1¼	177.7	188.5	37.70	31.41	26.93	23.56	20.94	18.85	17.14	15.60
28×12	¾	118.3	162.5	32.50	27.08	23.21	20.31	18.06	16.25	14.77	13.40
	I	156.3	211.8	42.36	35.30	30.26	26.48	23.53	21.18	19.25	17.60
	1¼	193.3	252.0	50.40	42.00	36.00	31.50	28.00	25.20	22.91	21.00



16×6	¾	74.4	43.3	8.66	7.21	6.18	5.41	4.81	4.33	3.93	3.60
	I	96.9	52.4	10.48	8.73	7.48	6.55	5.82	5.24	4.76	4.40
	1¼	118.1	59.3	11.86	9.88	8.47	7.41	6.59	5.93	5.39	4.90
16×8	¾	88.5	68.1	13.62	11.35	9.73	8.51	7.56	6.81	6.19	5.70
	I	115.6	83.9	16.75	13.98	11.98	10.48	9.32	8.39	7.62	7.00
	1¼	141.6	97.0	19.40	16.16	13.85	12.12	10.77	9.70	8.81	8.10
20×8	¾	97.8	80.2	16.04	13.36	11.45	10.02	8.91	8.02	7.29	6.70
	I	128.1	98.7	19.74	16.45	14.10	12.33	10.96	9.87	8.97	8.20
	1¼	157.2	113.9	22.78	18.98	16.27	14.23	12.65	11.39	10.35	9.50

Table I (Continued). Safe Distributed Loads in Tons for Cast-Iron Lintels



Loads include weights of lintels. Maximum tensile stress 3 000 lb per sq in. See remarks, pages 622 and 623.

Size, width by depth, in	Thick-ness of metal, in	Weight per foot, lb	C, tons	Span in feet							
				5	6	7	8	9	10	11	12
20 X 10	¾	111.9	112.0	22.40	18.66	16.00	14.00	12.44	11.20	10.18	9.33
	1	146.9	139.7	27.94	23.28	19.95	17.46	15.52	13.97	12.70	11.64
	1¼	180.7	163.5	32.70	27.25	23.35	20.43	18.16	16.35	14.86	13.62
20 X 12	¾	126.0	146.7	29.34	24.45	20.95	18.33	16.30	14.67	13.33	12.22
	1	165.6	184.8	36.96	30.80	26.40	23.10	20.53	18.48	16.80	15.40
	1¼	204.1	218.8	43.76	36.46	31.25	27.35	24.31	21.88	19.89	18.24
24 X 8	¾	107.2	91.9	18.38	15.31	13.12	11.49	10.21	9.19	8.35	7.66
	1	140.6	112.8	22.56	18.80	16.11	14.10	12.53	11.28	10.25	9.40
	1¼	172.6	130.2	26.64	21.70	18.57	16.27	14.47	13.02	11.83	10.85
24 X 10	¾	121.3	127.8	25.56	21.30	18.25	15.97	14.20	12.78	11.61	10.65
	1	159.4	159.5	31.90	26.58	22.78	19.94	17.72	15.95	14.50	13.29
	1¼	196.3	183.6	36.72	30.60	26.23	22.95	20.40	18.36	16.69	15.30
24 X 12	¾	135.3	166.6	33.32	27.76	23.80	20.82	18.51	16.66	15.14	13.88
	1	178.1	209.3	41.86	34.88	29.90	26.16	23.25	20.93	19.02	17.44
	1¼	219.7	247.7	49.54	41.28	35.39	30.96	27.52	24.77	22.51	20.64
28 X 10	¾	130.7	141.4	28.28	23.57	20.20	17.67	15.71	14.14	12.85	11.78
	1	171.9	177.4	35.48	29.57	25.34	22.17	19.71	17.74	16.12	14.78
	1¼	211.9	207.8	41.56	34.63	29.68	25.97	23.09	20.78	18.89	17.31
28 X 12	¾	144.7	186.0	37.20	31.00	26.57	23.25	20.66	18.60	16.91	15.50
	1	190.6	234.6	46.92	39.10	33.51	29.32	26.06	23.46	21.32	19.55
	1¼	235.3	277.9	55.58	46.31	39.70	34.74	30.88	27.79	25.26	23.16

2. Sections, Stresses, Buckling and Deflection of Wooden Beams and Girders

**Sections and Fiber-Stresses.** The cross-sections of wooden beams are almost invariably SQUARE or RECTANGULAR, and those shapes only are considered in the following rules and formulas. Beams should have such a cross-section, that the maximum fiber-stress due to transverse bending, the maximum horizontal shear and the compression across the grain at the end-bearings do not exceed the AVERAGE ALLOWABLE UNIT STRESSES as set forth in Table XVI.

**Buckling.** Wooden girders should be braced laterally to prevent BUCKLING when the ratio of length to breadth exceeds twenty, or designed with a reduced fiber-stress from that allowable, where this ratio is exceeded. Tables VII to XV assume such bracing. Joists should have bridging not over 8 ft on centers. THE PERCENTAGE OF REDUCTION of fiber-stress for girders should be as follows:

Ratio of length to width. . . . .	20 to 30	30 to 40	40 to 50	50 to 60
Percentage of reduction. . . . .	25	34	42	50

**Deflection.** It is also important that beams carry the loads without DEFLECTION beyond a limit fixed by the use to which the structure is applied; this limit is generally taken at  $\frac{1}{30}$  of an inch per foot of span for plastered ceilings.

**3. Constants and Coefficients for Beams**

**Value of the Constant, A.** The letter *A* in the following formulas (4) (16), denotes the SAFE LOAD for a UNIT BEAM, 1 in square in section and 1 ft span, loaded at the middle of the span. This is also one-eighteenth of the ALLOWABLE FIBER-STRESS in pounds per square inch. (See Table I, on page 557.) The following are the values of *A*, obtained by dividing by eighteen the RECOMMENDED UNIT STRESSES for TRANSVERSE BENDING, and those given in the building laws of New York, Chicago, Baltimore and Boston.

**Table II.\* Coefficients for Iron, Steel and Wooden Beams. Values for A in Formulas**

Materials	New York	Chicago	Baltimore	Boston	Recommended
Cast iron.....	167	167	167	167	167
Wrought iron.....	667	667	667	667	667
Steel.....	889	889	889	889	889
Yellow pine.....	90	72	100	83	67
White pine.....	67	44	56	56	39
Spruce.....	67	44	75	56	39
Hemlock.....	44	33	.....	.....	33
Chestnut.....	.....	.....	.....	.....	44
Oak.....	67	67	83	56	67
Douglas fir.....	67	72	.....	.....	56

\* For safe allowable working unit stresses for other woods, see Table XVI, page 647. From these values, *A* may be determined by dividing them by eighteen. See Table XVII, page 648, for other stresses for woods, taken from various building laws. Tables XVIII and XIX, pages 650 and 651, for the ultimate strength of woods.

† The values of *A* for wooden beams may be increased from 30 to 40% for temporary structures, and for commercially dry and protected timber, not subject to impact, or under ideal conditions.

**Table III. Coefficients Recommended for Stone † and Concrete Beams. Values of A**

Materials	Values of A	Materials	Values of A
Granite.....	10	Bluestone.....	17
Limestone.....	8	Slate.....	22
Marble.....	7	Concrete 1 : 2 : 4.....	1
Sandstone.....	6	Concrete 1 : 2 : 5.....	1

† Values of *A* for STONE BEAMS were taken from former Building Laws of New York and from the requirements of the Board of Fire Underwriters.

# 4. Flexural Strength of Wooden Beams

**Section-Modulus.** For beams with a rectangular cross-section, the formulas for strength can be simplified by substituting for the SECTION-MODULUS its value  $\frac{1}{6}bd^2$ , where  $b$  is the breadth and  $d$  the depth of the section.

Substituting this value in the general formulas for beams with rectangular cross-sections and of any material, the following formulas result:

**Beams Fixed at One End and Loaded at the Other (Fig. 5).**

$$\text{Safe load, in pounds} = \frac{\text{breadth} \times \text{square of depth} \times A^*}{4 \times \text{length in feet}} \quad (4)$$

$$\text{Breadth, in inches} = \frac{4 \times \text{load} \times \text{length in feet}}{\text{square of depth} \times A^*} \quad (5)$$

Fig. 5. Cantilever Beam. Load near Free End

Fig. 6. Cantilever Beam. Distributed Load over Entire Span

**Beams Fixed at One End and Loaded with a Uniformly Distributed Load (Fig. 6).**

$$\text{Safe load, in pounds} = \frac{\text{breadth} \times \text{square of depth} \times A^*}{2 \times \text{length in feet}} \quad (6)$$

$$\text{Breadth, in inches} = \frac{2 \times \text{load} \times \text{length in feet}}{\text{square of depth} \times A^*} \quad (7)$$




Fig. 7. Simple Beam. Load at Middle of Span

**Beams Supported at Both Ends and Loaded at the Middle (Fig. 7).**

$$\text{Safe load, in pounds} = \frac{\text{breadth} \times \text{square of depth} \times A^*}{\text{span in feet}} \quad (8)$$

$$\text{Breadth, in inches} = \frac{\text{span in feet} \times \text{load}}{\text{square of depth} \times A^*} \quad (9)$$

\* For values of  $A$ , see Tables II and III.

**Beams Supported at Both Ends and Loaded with a Uniformly Distributed Load Over Entire Span (Fig. 8).**




Fig. 8. Simple Beam. Distributed over Entire Span

$$\text{Safe load, in pounds} = \frac{2 \times \text{breadth} \times \text{square of depth} \times A^*}{\text{span in feet}}$$

or      Breadth, in inches =  $\frac{\text{span in feet} \times \text{load}}{2 \times \text{square of depth} \times A^*}$

**Beams Supported at Both Ends and Loaded with a Uniformly Distributed Load Over Only a Portion of the Span (Fig. 9).**




Fig. 9. Simple Beam. Distributed Load over Part of Span

In this case the dimensions of the beam required to carry the load can accurately determined only by computing the MAXIMUM BENDING MOMENT explained in Chapter IX, and substituting the value thus found in Formula following. If, however, the length  $l_1$  is very short in comparison with  $l$ , near the middle, then the load may be considered as CONCENTRATED at the middle of the span and the breadth of the beam may be found by Formula (9). Formula (13) is used if the load is at one side of the middle. The error will be on the safe side.

**Beams Supported at Both Ends and Loaded with Concentrated Load at the Middle of the Span (Fig. 10).**




Fig. 10. Simple Beam. Concentrated Load at Any Point

$$\text{Safe load, in pounds} = \frac{\text{breadth} \times \text{square of depth} \times \text{span} \times A^*}{4 \times m \times n}$$

or

$$\text{Breadth, in inches} = \frac{4 \times \text{load} \times m \times n}{\text{square of depth} \times \text{span} \times A^*}$$

\* For values of  $A$ , see Tables II and III.



Beams Supported at Both Ends and Loaded with  $P$  Pounds at a Distance  $m$  from each End (Fig. 11).




Fig. 11. Simple Beam. Two Equal Concentrated Loads Symmetrically Placed

$$\left. \begin{array}{l} \text{Safe load, } P, \text{ in pounds} \\ \text{at each point} \end{array} \right\} = \frac{\text{breadth} \times \text{square of depth} \times A^*}{4 \times m} \quad (14)$$

$$\text{Breadth, in inches} = \frac{4 \times \text{load at one point} \times m}{\text{square of depth} \times A^*} \quad (15)$$

**Note.** In the last two cases the lengths denoted by  $m$  and  $n$  should be in feet, as the spans are in feet.

## Application of Formulas for Flexural Strength of Wooden Beams

**Example 1.** What load, 6 ft out from the wall, will an 8 by 14-in long-leaf yellow pine beam, securely fastened at one end into a brick wall, sustain with safety?

**Solution.** The safe load in pounds (Formula 4) =  $\frac{8 \times 196 \times 67}{4 \times 6} = 4\,377$  lb

**Example 2.** It is desired to suspend two loads of 10 000 lb each, 4 ft from each end of an oak beam, 20 ft long. What should be the size of the beam?

**Solution.** Let the depth of the beam be assumed to be 16 in. Then (Formula 15)

$$\text{The breadth} = \frac{4 \times 10\,000 \times 4}{256 \times 67} = 9.3 \text{ in, nearly}$$

The beam, therefore, should be 10 by 16 in in cross-section.

**Beam with Several Loads.** It is required, next, to determine the size of a beam which is supported at both ends, and which will safely support several concentrated loads, or a distributed load and one or more concentrated loads. The correct method of finding the least size of a beam that will safely support a combination of loads, is to first find the MAXIMUM BENDING MOMENT, as explained in Chapter IX, page 329, and then substitute the value thus found for the BENDING MOMENT in the following formula:

$$\text{Breadth, in inches} = \frac{4 \times \text{maximum bending moment in ft-lb}}{\text{square of depth} \times A} \quad (16)$$

A shorter and easier method is to find the EQUIVALENT DISTRIBUTED LOAD for each concentrated load, and then find the size of a beam required to support the total equivalent distributed load thus found. The equivalent distributed loads for concentrated loads applied at different proportions of the span from each end, may be obtained by multiplying the concentrated loads by the following FACTORS:

\* For values of  $A$ , see Tables II and III.

**Table IV. Factors for Equivalent Distributed Loads**

	Position of load	Factor
For a concentrated load	Applied at middle of span	Multiply by 2.
For a concentrated load	Applied at one-third the span	Multiply by 1.5
For a concentrated load	Applied at one-fourth the span	Multiply by 1.33
For a concentrated load	Applied at one-fifth the span	Multiply by 1.25
For a concentrated load	Applied at one-sixth the span	Multiply by 1.17
For a concentrated load	Applied at one-seventh the span	Multiply by 1.1
For a concentrated load	Applied at one-eighth the span	Multiply by 1.04
For a concentrated load	Applied at one-ninth the span	Multiply by 1.0
For a concentrated load	Applied at one-tenth the span	Multiply by 0.9

(See, also, Chapter XV, Safe Loads for Steel Beams, page 366.)

Thus, a concentrated load of 900 lb, applied at one-sixth the span from support, will result in the same maximum bending moment as a distributed load of  $900 \times 1\frac{1}{6}$ , or 1 000 lb.

The above method for finding the size of a beam for a combination of several loads gives a larger beam than the correct method, by Formula (16), for reason that the maximum bending moment will not be equal to the sum of the individual bending moments. Hence, when there are several heavy loads to be supported, it is economical to compute maximum bending moment by the GRAPHIC METHOD explained in Chapter IX, page 329.

**Fig. 12. Girder with Three Concentrated Loads**

long-leaf yellow pine. The weight of the roof and allowance for snow is 7 lb. Each of the beams *A*, *B* and *C*, impose a load on the girder, due to weight of the tank and its contents, of 3 000 lb. What should be the size of girder?

**Solution.** The roof-load may be considered to be uniformly distributed. The load from beam, *A*, is applied at one-third the span from one end; the load from *B*, five-twelfths the span from the other end; and the load from *C*, sixth the span. The fraction five-twelfths is the mean of one-half and one-third; hence the load from *B* should be multiplied by 1.89. Multiplying the concentrated loads by their proper factors, the equivalent distributed load is found to be as follows:

Roof-load, distributed,	= 7 500
Load from <i>A</i> , $3\,000 \times 1.78$	= 5 340
Load from <i>B</i> , $3\,000 \times 1.89$	= 5 670
Load from <i>C</i> , $3\,000 \times 1\frac{1}{6}$	= 3 333

**Equivalent distributed load = 21 843 lb**

Assuming 16 in as the depth of the beam, and using Formula (11),

$$\text{The breadth} = \frac{12 \times 21\,843}{2 \times 256 \times 67} = 7.6 \text{ in}$$

Assuming 14 in for the depth, 10 in is obtained for the breadth; hence, the beam must be 10 by 14 in, or 8 by 16 in in cross-section.

**Strut-Beams and Tie-Beams.** A STRUT-BEAM is a beam that is subject to both a transverse and a compressive stress. A TIE-BEAM is one that is subject to direct tension in addition to the transverse stress. To find the strength of either, first find the size of a beam required to resist the transverse stress, and then the size of a timber, of the same depth as the beam, to resist the direct tension or compression, and add the two breadths together.

**Example 4.** A spruce tie-beam, 10 ft long between joints, sustains a ceiling-load of 2 000 lb and a direct tensile stress of 40 000 lb. What should be the dimensions of the beam?

**Solution.** As a ceiling-load is uniformly distributed, the size of the beam is determined by Formula (11), page 630. Assuming the depth to be 10 in

$$\text{The breadth} = \frac{10 \times 2\,000}{2 \times 100 \times 39}, \text{ or } 2\frac{1}{2} \text{ in, nearly}$$

The resistance of spruce to tension (see Table XVI, page 647) is 800 lb per sq in.  $40\,000/800 = 50$  sq in, which is equivalent to a 5 by 10-in section. It will require, therefore, a beam  $7\frac{1}{2}$  by 10 in in cross-section to resist both the transverse stress and the direct tension. If the tie-beam is cut in any way so as to reduce the section, except over a support, the dimensions must be increased accordingly.

**Example 5.** A strut-beam of white pine, 10 ft long, supports a distributed load of 6 000 lb, and is also subject to a direct compression of 64 000 lb. What should be the size of the beam?

**Solution.** Assuming 14 in for the depth, the breadth for the transverse load is found by Formula (11), page 630

$$\text{The breadth} = \frac{10 \times 6\,000}{2 \times 196 \times 39} = 3.9 \text{ in, nearly}$$

Using Formula (4), page 450, from which is computed Table IV, page 452, finding the safe loads for white-pine posts, it is found that a  $7\frac{1}{2}$  by 14-in post, 10 ft long will safely carry the compressive stress, 64 000 lb. Hence it will require a  $7\frac{1}{2}$  by 14-in beam to resist the compressive stress, and a 4 by 14-in beam to resist the transverse load. The beam, therefore, should be 12 by 14 in in cross-section to resist them both.

## 6. Relative Strengths of Beams

**Relative Strengths of Rectangular Beams.** From an inspection of the preceding formulas it is found that the RELATIVE STRENGTHS of beams of rectangular cross-sections, for the different cases is as shown in Table V.

**Strengths of Beams of Any Constant Cross-Section.** The STRENGTHS given in Table V are true for beams of any constant cross-section of whatever form.

**Beam on Edge.** When a beam of square cross-section is supported on its edge, that is, when one of its diagonals is vertical, it will bear about seven-tenths as great a breaking-load as it will when it is supported on one side.

Table V. Relative Strengths of Rectangular Beams

Kind of load	Position of load	Strength ratios
Beam supported at both ends		
Uniformly distributed	Over entire span	1
Concentrated	At middle of span	$\frac{1}{2}$
Concentrated	At one-third the span	$\frac{9}{16}$
Concentrated	At one-fourth the span	$\frac{3}{8}$
Concentrated	At one-fifth the span	$\frac{25}{64}$
Concentrated	At one-sixth the span	$\frac{9}{16}$
Concentrated	At one-seventh the span	$\frac{49}{128}$
Concentrated	At one-eighth the span	$\frac{3}{4}$
Concentrated	At one-ninth the span	$\frac{81}{64}$
Concentrated	At one-tenth the span	$\frac{25}{16}$
Beam fixed at one end, or cantilever beams		
Uniformly distributed	Over entire span	$\frac{1}{4}$
Concentrated	At the free end	$\frac{1}{8}$
Beam supported at one end and fixed at the other end		
Uniformly distributed	Over entire span	1
Concentrated	Near the middle of span	$1\frac{3}{20}$
Beam fixed at both ends		
Uniformly distributed	Over entire span	$1\frac{1}{2}$
Concentrated	At middle of span	1

The Strongest Beam Cut From a Cylindrical Log is one in which breadth is to the depth as 5 is to 7, very nearly, and the dimensions of such a beam can be found graphically, as shown in Fig. 13. Any diagonal, as *ab*, is drawn and divided into three equal parts by the points *c* and *d*; from these points lines perpendicular to *ab* are drawn and the points *e* and *f* connected with *a* and *b* shown.




Fig. 13. Strongest Beam of Rectangular Section Cut from Log

**Cylindrical Beams.** A CYLINDRICAL BEAM is ten-seventeenths as strong as a beam with a square cross-section, the side of the square being equal to the diameter of the circular section of the cylindrical beam. Hence, to find the safe load for a cylindrical beam, find the proper load for the corresponding square section beam, and divide this load by 1.7.

**The Bearing of the Ends of a Beam on a wall.** beyond a certain distance does not strengthen the beam. In general, a beam should have a bearing of 4 in. or if it is very long, 6 in.

**The Weight of the Beam Itself.** The formulas given for the strength of beams do not take into account the WEIGHT OF THE BEAMS THEMSELVES, hence the safe loads of the formulas include both the external loads and weights of the material in the beams. In small wooden beams, the weight

Each beam is generally so small, compared with the external load, that it need not be taken into account. But for larger wooden beams, and for metal and concrete beams, the weight of the beam should be subtracted from the safe load if the load is distributed; and if the load is applied at the middle, one-half the weight of the beam should be subtracted.

**The Weight of Timber.** The weight per cubic foot for different kinds of timber may be found in the table in Part III, pages 1501 to 1508, giving the Weights of Various Substances.

## 7. Tables for Strength and Stiffness of Wooden Beams

Tables VII to XV for the Strength and Stiffness of Wooden Beams are given on pages 638 to 646, for BEAMS ONE INCH IN BREADTH. To find the length for any other breadth, multiply the proper tabular value by the breadth of the beam in inches. To obtain the required breadth for any load, divide the given load in pounds by the proper tabular value. In heading the tables, prominence has been given to the values used for  $S$ , and the corresponding values of  $W$ , so that those who prefer to use for any wood a value different from that recommended, need only to look up the table based on the value they desire to employ. For certain cases and in some cities, the building laws specify 1 300, 1 500 and 1 800 pounds as values of  $S$  to be used for long-leaf yellow pine; hence Tables XIII, XIV and XV, based on these values, are added.

Since timber is weak in HORIZONTAL SHEAR compared with its strength in TENSION and COMPRESSION, the safe load a beam of short span can carry is governed, not by its resistance to CROSS-BREAKING, but by its RESISTANCE TO SHEARING along the NEUTRAL SURFACE. Wooden beams and joists, therefore, should be dimensioned to safely withstand this SHEARING ACTION. The ratio of the SHEARING to the FLEXURAL STRENGTH is not exactly the same for different kinds of wood, but for practical use and in the tables it has been assumed to be one-twelfth of the WORKING UNIT FIBER-STRESS. As it can be shown \* that the ratio of the span to the depth of a rectangular beam, uniformly loaded, is directly proportional to its CROSS-BREAKING STRESS and SHEARING WORKING STRESS, the tabular loads are figured for the PERMISSIBLE UNIT FIBER-STRESS, where the length of the span is twelve or more times the depth of the beam; while for shorter lengths, the tabular loads are governed by the SHEAR. To determine the safe load on beams for a deflection not exceeding  $\frac{1}{360}$  of the span, the tabular values have been placed directly underneath the safe loads for length. These values are based on the MODULUS OF ELASTICITY,  $E$ , given in the tables.

THE FORMULA FOR FLEXURE used in determining the safe uniformly distributed loads in the tables is (see Formulas (1), page 333 and (2)', page 557)

$$M = \frac{SI}{c} = \frac{Sbd^2}{6} = \frac{Wl}{8}$$

$$W = \frac{4bd^2S}{3l}, \text{ in which } l \text{ is the span in inches}$$

THE FORMULA FOR SHEAR is

$$W = \frac{4bdS_s}{3}$$

\* Materials of Construction, J. B. Johnson, page 55.

The **FORMULA FOR DEFLECTION** is (see, also, Formulas (1) to (17) and Table Chapter XVIII)

$$W = \frac{Ed^3}{8100l^3} \text{ in which } l \text{ is the span in feet;}$$

$M$  = maximum bending moment in inch-pounds;

$I$  = moment of inertia of the cross-section of the beam in biquadrates inches;

$c = d/2$  = one-half the depth of the beam in inches;

$SI/c$  = resisting moment of the cross-section in inch-pounds;

$W$  = total safe load in pounds, uniformly distributed;

$b$  = breadth of the beam in inches;

$d$  = depth of the beam in inches;

$l$  = span, in feet or inches, as noted for the different formulas;

$S$  = unit flexural fiber-stress in pounds per square inch;

$S_s = S/12$  = horizontal unit shearing-stress, in pounds per square inch, along neutral surface;

$E$  = modulus of elasticity in pounds per square inch.

**Example 6.** What is the safe, uniformly distributed load, corresponding to a fiber-stress of 1 500 lb per sq in, for an 8 by 14-in long-leaf yellow-pine beam supported at both ends, and having a 24-ft clear span?

**Solution.** From Table XIV, the load for a 1-in thickness is 1362 lb. Hence  $1362 \times 8 = 10896$  lb, the total load for the beam. If the deflection of the beam should not be more than  $1/160$  of the span, the safe load for 1-in thickness should not exceed 882 lb. Hence,  $882 \times 8 = 7056$  lb, is the maximum load to be used in this case. It is assumed that 1 500 lb per sq in is allowed for fiber-stress.

**Example 7.** What should be the size of a Norway-pine beam required to support a distributed load of 6 400 lb over a clear span of 18 ft?

**Solution.** From Table X, it is found that a beam 12 in deep and 1 in wide and with an 18-ft span, will support 711 lb. Dividing the load, 6 400 lb, by 711, the result is 9 for the breadth of the beam in inches. Hence the beam should be 9 by 12 in, to carry a distributed load of 6 400 lb over a span of 18 ft. As the deflection-load of 593 lb can be increased 20% for Norway pine, the load of 711 lb is safe for deflection; if, however, cypress is used, 593 must be taken in place of 711, to determine the breadth of the beam. This would result in a beam 10.8 by 12 in.

**Different Positions of Loads.** To find the safe load, concentrated at the middle of the span of a given beam, find the safe distributed load, as in Example 6, and divide this load by 2. To find the safe load concentrated at any point other than the middle of the span, find the safe distributed load for the given span, and divide this load by the proper factor taken from Table IV, page 632. To find the size of a beam to support a given concentrated load, multiply the given load by the factor corresponding to the position of the load, as given in Table IV, and then proceed as in Example 7.

**Use of Formulas.** If in doubt as to the application of the tables, in special cases, use one of the formulas, from (4) to (16), applying to the case. The formulas and tables should always give the same result.

**Nominal and Actual Sizes of Beams.** The tables may be used for beams the dimensions of which are less than the NOMINAL DIMENSIONS. In many localities, floor-joists carried in stock, are more scant of the nominal dimensions, and for such beams and joists a reduction in the safe load must be made to correspond with the reduction in size.

**REDUCED SIZES** are generally  $\frac{1}{4}$  in scant, up to 4 in in breadth, above which they are  $\frac{1}{2}$  in scant; while in depth they are all generally  $\frac{1}{2}$  in less than the nominal size. The safe loads may be obtained by multiplying the safe loads for the corresponding nominal sizes, as given in Tables VII to XV, by the factors given in the following table.

**Table VI. Conversion Factors for Actual Sizes of Wooden Beams**

Cross-sections of beams in inches	Factors	Cross-sections of beams in inches	Factors
$1\frac{3}{4} \times 5\frac{1}{2}$	1.47	$1\frac{3}{4} \times 11\frac{1}{2}$	1.61
$2\frac{3}{4} \times 5\frac{1}{2}$	2.31	$2\frac{3}{4} \times 11\frac{1}{2}$	2.53
$1\frac{3}{4} \times 6\frac{1}{2}$	1.51	$1\frac{3}{4} \times 13\frac{1}{2}$	1.63
$2\frac{3}{4} \times 6\frac{1}{2}$	2.51	$2\frac{3}{4} \times 13\frac{1}{2}$	2.56
$1\frac{3}{4} \times 7\frac{1}{2}$	1.54	$1\frac{3}{4} \times 15\frac{1}{2}$	1.65
$2\frac{3}{4} \times 7\frac{1}{2}$	2.42	$2\frac{3}{4} \times 15\frac{1}{2}$	2.58
$1\frac{3}{4} \times 9\frac{1}{2}$	1.53	$1\frac{3}{4} \times 17\frac{1}{2}$	1.65
$2\frac{3}{4} \times 9\frac{1}{2}$	2.48	$2\frac{3}{4} \times 17\frac{1}{2}$	2.60

**Example 8.** What is the safe load for a  $2\frac{3}{4}$  by  $13\frac{1}{2}$ -in spruce beam, with 18-ft span?

**Solution.** From Table VIII, the safe load for a 1 by 14-in beam is 847 lb. Multiplying this by 2.56, we have 2 178 lb as the safe distributed load for a  $2\frac{3}{4}$  by  $13\frac{1}{2}$  in in cross-section. For a full 3 by 14-in cross-section, the load would be 2 541 lb.

**Stone Beams.** The above formulas may be used for rectangular stone beams when the proper coefficients, recommended in Table III, page 628, are used. Sandstone beams should never be subjected to any heavy loads and stone lintels should be relieved by steel beams or by brick arches over them back of them.

**Concrete Beams** are generally reinforced with steel rods, but when used without reinforcement, the coefficient,  $A$ , given in Table III, is recommended.

**Use of Tables VII to XV.** The safe loads given in Tables VII to XV are correct for the fiber-stresses indicated; but for greater convenience in using the tables, each figure in the units-place of each value may be made a cipher, each figure in the tens-place may be increased by one when the unit-figure is 4 or greater. Thus, 505 would be 500, 506 would be 510, etc.

**Important Notes on Stresses and Loads for Wooden Beams.** In compiling and using the tables of safe loads for wooden beams, the following important considerations should be kept in mind:

- 1) Unseasoned timber is very much weaker than commercially dry timber, that is, timber containing from 10 to 15% of moisture.
- 2) Timber containing large or loose knots is much weakened.
- 3) When impact has to be considered, the stresses should be reduced.
- 4) For continuous, heavy loading, relatively low stresses should be used.
- 5) Commercial dimensions are smaller than nominal dimensions.
- 6) Timbers deteriorate and the factors of safety for strength grow smaller with time.
- 7) The modulus of elasticity,  $E$ , for unseasoned timber, should be reduced 50% from the value given for thoroughly seasoned timber.
- 8) It is better engineering practice to compute tables of safe loads based on conservative stresses for average or poor conditions, increasing the values given when conditions are ideal, than to recommend values for ideal conditions which usually do not exist. (See notes, pages 628 and 647, regarding increase in the table-values.) Editor-in-Chief.

Safe Distributed Loads \* in Pounds for Rectangular Wooden Beams  
Average Hemlock. Maximum Fiber-Stress,  $S = 600$  lb per sq in.

$E = 900\,000$  lb per sq in.  $A = 33$

The first horizontal line gives the depth of the beam in inches  
The loads are for beams one inch wide and supported at both ends

6	8	10	12	14	16	18
400	533	666	800	933	1 066	1 200
343	533	666	800	933	1 066	1 200
300	533	666	800	933	1 066	1 200
266	474	666	800	933	1 066	1 200
240	427	666	800	933	1 066	1 200
240						
218	388	605	800	933	1 066	1 200
199						
200	356	555	800	933	1 066	1 200
166						
185	328	513	738	933	1 066	1 200
143						
171	305	477	686	933	1 066	1 200
122	291					
160	285	445	640	871	1 066	1 200
107	253					
150	267	417	600	817	1 066	1 200
94	222					
.....	{ 251	{ 392	565	762	1 003	1 200
.....	{ 197	{ 384				
.....	{ 237	{ 371	534	726	948	1 200
.....	{ 175	{ 343				
.....	{ 225	{ 351	505	688	898	1 137
.....	{ 157	{ 308				
.....	{ 213	{ 333	480	653	854	1 084
.....	{ 142	{ 277	480			
.....	.....	{ 317	462	623	813	1 021
.....	.....	{ 252	435			
.....	.....	{ 303	436	594	776	98
.....	.....	{ 229	397			
.....	.....	{ 290	417	568	742	93
.....	.....	{ 211	363			
.....	.....	{ 278	400	545	712	90
.....	.....	{ 193	334			
.....	.....	.....	{ 384	523	683	86
.....	.....	.....	{ 308			
.....	.....	.....	{ 369	503	657	83
.....	.....	.....	{ 284			
.....	.....	.....	{ 356	482	633	80
.....	.....	.....	{ 264			
.....	.....	.....	{ 313	467	609	77
.....	.....	.....	{ 245			
.....	.....	.....	.....	451	589	74
.....	.....	.....	.....			
.....	.....	.....	.....	436	569	71
.....	.....	.....	.....			
.....	.....	.....	.....	339	505	7

..... zigzag lines calculated for horizontal shear. Where two loads are calculated for strength, the lower for deflection not to exceed  $\frac{1}{500}$  the span to 40% to strength-values for ideal conditions. See notes, pages 6 & 8. 63



**Table VIII. Safe Distributed Loads \* in Pounds for Rectangular Wooden Beams For Average White Pine, Spruce and Eastern Fir. Maximum Fiber-Stress,  $S = 700$  lb per sq in.  $E \dagger = 1\,000\,000$  lb per sq in.  $A = 39$**

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	467	622	777	933	1 089	1 244	1 400
7	400	622	777	933	1 089	1 244	1 400
8	350	622	777	933	1 089	1 244	1 400
9	311	552	777	933	1 089	1 244	1 400
10	{ 280 267 }	497	777	933	1 089	1 244	1 400
11	{ 255 221 }	453	707	933	1 089	1 244	1 400
12	{ 233 185 }	415	648	933	1 089	1 244	1 400
13	{ 216 158 }	383 374 }	598	861	1 089	1 244	1 400
14	{ 200 136 }	356 323 }	556	800	1 089	1 244	1 400
15	{ 187 119 }	332 281 }	518	747	1 016	1 244	1 400
16	{ 175 104 }	311 247 }	486 482 }	700	952	1 244	1 400
17	.....	{ 293 219 }	458 427 }	660	897	1 172	1 400
18	.....	{ 276 195 }	433 381 }	623	847	1 107	1 400
19	.....	{ 262 175 }	410 342 }	590	802	1 048	1 326
20	.....	.....	{ 389 308 }	560 534 }	762	996	1 260
21	.....	.....	{ 370 280 }	534 484 }	726	948	1 200
22	.....	.....	{ 354 255 }	509 441 }	692	906	1 144
23	.....	.....	{ 338 234 }	487 403 }	662 641 }	866	1 096
24	.....	.....	{ 324 215 }	468 371 }	635 588 }	830	1 050
25	.....	.....	.....	{ 448 342 }	610 542 }	796	1 008
26	.....	.....	.....	{ 430 316 }	586 502 }	766 750 }	970
27	.....	.....	.....	{ 415 293 }	565 465 }	738 695 }	934
28	.....	.....	.....	{ 400 272 }	544 432 }	711 646 }	900
29	.....	.....	.....	.....	{ 526 403 }	687 602 }	868 856 }
30	.....	.....	.....	.....	{ 508 377 }	664 562 }	840 800 }

Add 30 to 40% to strength-values for ideal conditions. See notes, pages 628, 637.

For first-class, dry spruce and Eastern fir,  $E = 1\,200\,000$ , could safely be used, making safe deflection-loads those given in Table XI. See, also, foot-note with Table VII.

**Table IX. Safe Distributed Loads \* in Pounds for Rectangular Wooden Beams**  
**For Average California Red Wood and Cedar. Maximum Fiber-Stress,**  
 **$S = 750$  lb per sq in.  $E = 700\,000$  lb per sq in.  $A = 41.7$**

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	500	667	833	1 000	1 167	1 333	1 500
7	{ 423 352 }	667	833	1 000	1 167	1 333	1 500
8	{ 375 292 }	667	833	1 000	1 167	1 333	1 500
9	{ 333 231 }	{ 592 547 }	833	1 000	1 167	1 333	1 500
10	{ 300 187 }	{ 533 443 }	833	1 000	1 167	1 333	1 500
11	{ 274 155 }	{ 485 365 }	{ 757 714 }	1 000	1 167	1 333	1 500
12	{ 250 130 }	{ 445 307 }	{ 641 600 }	1 000	1 167	1 333	1 500
13	{ 231 110 }	{ 410 262 }	{ 641 512 }	{ 923 825 }	1 167	1 333	1 500
14	{ 214 95 }	{ 382 226 }	{ 525 441 }	{ 857 763 }	1 167	1 333	1 500
15	.....	{ 356 197 }	{ 556 384 }	{ 800 665 }	{ 1 038 1 060 }	1 333	1 500
16	.....	{ 333 173 }	{ 521 337 }	{ 750 534 }	{ 1 020 929 }	1 333	1 500
17	.....	.....	{ 491 299 }	{ 706 518 }	{ 961 822 }	{ 1 254 1 223 }	1 500
18	.....	.....	{ 463 267 }	{ 667 462 }	{ 908 733 }	{ 1 184 1 090 }	1 500
19	.....	.....	{ 439 240 }	{ 632 414 }	{ 860 658 }	{ 1 122 952 }	1 421 1 396
20	.....	.....	.....	{ 600 374 }	{ 816 594 }	{ 1 066 886 }	1 350 1 258
21	.....	.....	.....	{ 572 339 }	{ 778 526 }	{ 1 016 803 }	1 288 1 144
22	.....	.....	.....	{ 547 309 }	{ 742 491 }	{ 970 732 }	1 227 1 042
23	.....	.....	.....	{ 522 282 }	{ 710 448 }	{ 928 670 }	1 174 954
24	.....	.....	.....	{ 500 260 }	{ 681 412 }	{ 890 616 }	1 123 876
25	.....	.....	.....	{ 480 239 }	{ 653 380 }	{ 854 567 }	1 082 861
26	.....	.....	.....	{ 463 221 }	{ 628 351 }	{ 821 525 }	1 038 741
27	.....	.....	.....	{ 444 205 }	{ 605 326 }	{ 791 487 }	1 000 691
28	.....	.....	.....	{ 428 190 }	{ 583 203 }	{ 762 452 }	961 661
29	.....	.....	.....	.....	{ 563 232 }	{ 736 421 }	923 621
30	.....	.....	.....	.....	{ 544 254 }	{ 712 393 }	885 581

\* Add 30 to 40% to strength-values for ideal conditions. See notes, pages 647. See, also, foot-note with Table VII.

**Table X. Safe Distributed Loads \* in Pounds for Rectangular Wooden Beam**  
**For Average Norway Pine, Cypress and Chestnut.**

Maximum Fiber-Stress,  $S = 800$  lb per sq in.  $E \dagger = 900\,000$  lb per sq in.  $A = 4$

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	533	711	889	1 066	1 244	1 422	1 600
7	457	711	889	1 066	1 244	1 422	1 600
8	{ 400 375 }	711	889	1 066	1 244	1 422	1 600
9	{ 356 296 }	632	889	1 066	1 244	1 422	1 600
10	{ 320 240 }	569 } 569	889	1 066	1 244	1 422	1 600
11	{ 291 199 }	517 } 470	809	1 066	1 244	1 422	1 600
12	{ 267 166 }	474 } 395	742	1 066	1 244	1 422	1 600
13	{ 246 142 }	438 } 337	684 } 658	985	1 244	1 422	1 600
14	{ 229 122 }	407 } 291	635 } 567	914	1 244	1 422	1 600
15	{ 214 107 }	379 } 253	593 } 494	854 } 854	1 161	1 422	1 600
16	{ 200 94 }	356 } 222	556 } 432	800 } 750	1 089	1 422	1 600
17	.....	{ 335 197 }	524 } 384	754 } 665	1 025	1 339	1 600
18	.....	{ 316 175 }	494 } 343	711 } 593	968 } 914	1 264	1 600
19	.....	{ 300 157 }	468 } 308	674 } 532	917 } 846	1 198	1 517
20	.....	{ 284 142 }	445 } 277	640 } 480	871 } 752	1 138 } 1 138	1 441
21	.....	.....	{ 423 252 }	609 } 435	830 } 692	1 084 } 1 032	1 372
22	.....	.....	{ 404 229 }	512 } 377	792 } 630	1 035 } 941	1 309
23	.....	.....	{ 387 211 }	557 } 363	758 } 577	990 } 860	1 253 } 1 225
24	.....	.....	{ 371 193 }	534 } 334	726 } 529	949 } 790	1 200 } 1 126
25	.....	.....	.....	{ 512 308 }	697 } 488	911 } 728	1 152 } 1 037
26	.....	.....	.....	{ 492 284 }	670 } 452	876 } 675	1 108 } 960
27	.....	.....	.....	{ 474 264 }	646 } 418	843 } 625	1 068 } 890
28	.....	.....	.....	{ 457 245 }	622 } 389	813 } 582	1 029 } 827
29	.....	.....	.....	.....	{ 601 353 }	785 } 542	993 } 770
30	.....	.....	.....	.....	{ 581 339 }	759 } 506	960 } 720

\* Add 30 to 40 % to strength-values for ideal conditions. See notes, pages 628, 637, 647  
 † Also foot-note with Table VII.

† For safe deflection-loads for Norway pine, add 20 % to the above values.

Uniformly Distributed Loads \* in Pounds for Rectangular Wooden Beams of Douglas Fir and Short-Leaf Yellow Pine. Fiber-Stress,  $S = 1\,000$  lb per sq in.  $E \dagger = 1\,200\,000$  lb per sq in.  $A = 55.6$

The first horizontal line gives the depth of the beam in inches  
The loads are for beams one inch wide and supported at both ends

6	8	10	12	14	16	18
567	889	1 111	1 333	1 556	1 778	2 000
571	889	1 111	1 333	1 556	1 778	2 000
500 } 500 }	889	1 111	1 333	1 556	1 778	2 000
444 } 395 }	790	1 111	1 333	1 556	1 778	2 000
400 } 320 }	711	1 111	1 333	1 556	1 778	2 000
364 } 265 }	647 } 628 }	1 010	1 333	1 556	1 778	2 000
333 } 222 }	593 } 527 }	926	1 333	1 556	1 778	2 000
308 } 190 }	547 } 449 }	855	1 231	1 556	1 778	2 000
286 } 163 }	508 } 388 }	794 } 757 }	1 143	1 556	1 778	2 000
267 } 143 }	474 } 337 }	741 } 659 }	1 067	1 452	1 778	2 000
250 } 125 }	445 } 296 }	695 } 578 }	1 000 } 1 000 }	1 361	1 778	2 000
..... }	419 } 263 }	654 } 512 }	942 } 886 }	1 281	1 674	2 000
..... }	395 } 234 }	618 } 457 }	890 } 790 }	1 210	1 581	2 000
..... }	374 } 210 }	585 } 410 }	843 } 710 }	1 146 } 1 126 }	1 498	1 895
..... }	356 } 190 }	556 } 370 }	800 } 641 }	1 088 } 1 016 }	1 423	1 800
..... }	..... }	528 } 336 }	762 } 581 }	1 037 } 922 }	1 355	1 714
..... }	..... }	505 } 306 }	727 } 529 }	990 } 841 }	1 293 } 1 254 }	1 636
..... }	..... }	483 } 281 }	696 } 484 }	947 } 770 }	1 237 } 1 147 }	1 561
..... }	..... }	463 } 258 }	667 } 445 }	908 } 706 }	1 186 } 1 053 }	1 501
..... }	..... }	..... }	640 } 410 }	871 } 650 }	1 138 } 972 }	1 441
..... }	..... }	..... }	615 } 380 }	838 } 602 }	1 094 } 900 }	1 381
..... }	..... }	..... }	593 } 352 }	807 } 558 }	1 054 } 834 }	1 331
..... }	..... }	..... }	572 } 327 }	778 } 518 }	1 016 } 776 }	1 281
..... }	..... }	..... }	..... }	751 } 484 }	982 } 725 }	1 241
..... }	..... }	..... }	..... }	726 } 452 }	949 } 674 }	1 201

\* 40% to strength-values for ideal conditions. See notes, pages 628, 631  
† Reaction-loads for Douglas fir, add 25%. See, also, foot-note with Table

# Tables for Strength and Stiffness of Wooden Beam

**Table XII. Safe Distributed Loads \* in Pounds for Rectangular Wood For Average White Oak and Long-Leaf Yellow Pine†. Maximum Stress,  $S = 1200$  lb per sq in.  $E = 1\,500\,000$  lb per sq in.  $A =$**

Span in feet	The first horizontal line gives the depth of the beam in in. The loads are for beams one inch wide and supported at both ends					
	6	8	10	12	14	16
6	800	1 067	1 333	1 600	1 867	2 133
7	686	1 067	1 333	1 600	1 867	2 133
8	600	1 067	1 333	1 600	1 867	2 133
9	{ 533 495 }	949	1 333	1 600	1 867	2 133
10	{ 480 400 }	854	1 333	1 600	1 867	2 133
11	{ 437 332 }	776	1 212	1 600	1 867	2 133
12	{ 400 278 }	{ 711 658 }	1 111	1 600	1 867	2 133
13	{ 369 247 }	{ 656 561 }	1 026	1 477	1 867	2 133
14	{ 343 204 }	{ 610 485 }	{ 953 946 }	1 371	1 867	2 133
15	{ 320 179 }	{ 569 422 }	{ 890 824 }	1 280	1 741	2 133
16	{ 300 156 }	{ 533 371 }	{ 834 724 }	1 200	1 633	2 133
17	.....	{ 502 329 }	{ 785 642 }	{ 1 130 1 108 }	1 537	2 009
18	.....	{ 474 293 }	{ 741 572 }	{ 1 067 990 }	1 452	1 898
19	.....	{ 449 263 }	{ 702 513 }	{ 1 010 886 }	1 375	1 795
20	.....	{ 426 237 }	{ 666 462 }	{ 960 802 }	{ 1 306 1 272 }	1 708
21	.....	.....	{ 634 420 }	{ 914 726 }	{ 1 245 1 154 }	1 626
22	.....	.....	{ 606 383 }	{ 872 662 }	{ 1 188 1 051 }	1 552
23	.....	.....	{ 579 351 }	{ 835 605 }	{ 1 136 962 }	{ 1 484 1 435 }
24	.....	.....	{ 556 322 }	{ 800 557 }	{ 1 090 882 }	{ 1 423 1 318 }
25	.....	.....	.....	{ 768 513 }	{ 1 045 813 }	{ 1 366 1 215 }
26	.....	.....	.....	{ 738 473 }	{ 1 006 753 }	{ 1 313 1 125 }
27	.....	.....	.....	{ 711 440 }	{ 969 698 }	{ 1 265 1 043 }
28	.....	.....	.....	{ 686 410 }	{ 933 648 }	{ 1 218 970 }
29	.....	.....	.....	.....	{ 902 605 }	{ 1 178 903 }
30	.....	.....	.....	.....	{ 871 566 }	{ 1 138 843 }

\* Add 30 to 40% to strength-values for ideal conditions. See notes, pag 647. See, also, foot-note with Table VII.

† For safe loads for fiber-stresses of 1300, 1500 and 1800 lb per sq in, see I XIV and XV, respectively.

Table XIII. Safe Distributed Loads in Pounds for Rectangular Wooden Beams

Maximum Fiber-Stress,  $S = 1\,300$  lb per sq in.  $A = 72.2$

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	867	1 155	1 444	1 733	2 022	2 311	2 600
7	743	1 155	1 444	1 733	2 022	2 311	2 600
8	650	1 155	1 444	1 733	2 022	2 311	2 600
9	567	1 027	1 444	1 733	2 022	2 311	2 600
10	520	924	1 444	1 733	2 022	2 311	2 600
11	473	840	1 311	1 733	2 022	2 311	2 600
12	433	770	1 200	1 733	2 022	2 311	2 600
13	400	711	1 111	1 600	2 022	2 311	2 600
14	371	660	1 032	1 486	2 022	2 311	2 600
15	347	616	963	1 387	1 887	2 311	2 600
16	325	578	903	1 300	1 770	2 311	2 600
17	.....	544	849	1 224	1 664	2 175	2 600
18	.....	514	802	1 156	1 572	2 054	2 600
19	.....	487	760	1 095	1 490	1 946	2 463
20	.....	462	722	1 040	1 415	1 849	2 340
21	.....	.....	688	990	1 348	1 761	2 229
22	.....	.....	657	945	1 286	1 681	2 127
23	.....	.....	628	904	1 230	1 608	2 035
24	.....	.....	602	867	1 179	1 541	1 950
25	.....	.....	.....	832	1 132	1 479	1 872
26	.....	.....	.....	800	1 088	1 422	1 800
27	.....	.....	.....	770	1 048	1 369	1 733
28	.....	.....	.....	743	1 011	1 321	1 671
29	.....	.....	.....	.....	976	1 275	1 614
30	.....	.....	.....	.....	943	1 232	1 560

Loads above the heavy, black zigzag lines are calculated for resistance to shear.

For safe deflection-loads, see values in Tables VII to XII, according to the value of  $E$  used, and determined by the deflection-formula, page 636.

**Table XIV. Safe Distributed Loads in Pounds for Rectangular Wooden Beams****Maximum Fiber-Stress,  $S = 1\,500$  lb per sq in.  $A = 83.3$** 

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	1 000	1 333	1 667	2 000	2 333	2 667	3 000
7	857	1 333	1 667	2 000	2 333	2 667	3 000
8	750	1 333	1 667	2 000	2 333	2 667	3 000
9	667	1 185	1 667	2 000	2 333	2 667	3 000
10	600	1 067	1 667	2 000	2 333	2 667	3 000
11	548	970	1 515	2 000	2 333	2 667	3 000
12	500	890	1 390	2 000	2 333	2 667	3 000
13	462	820	1 282	1 846	2 333	2 667	3 000
14	428	764	1 190	1 714	2 333	2 667	3 000
15	.....	712	1 112	1 600	2 178	2 667	3 000
16	.....	667	1 042	1 500	2 042	2 667	3 000
17	.....	.....	982	1 412	1 974	2 510	3 000
18	.....	.....	926	1 334	1 815	2 370	3 000
19	.....	.....	878	1 264	1 720	2 246	2 842
20	.....	.....	.....	1 200	1 632	2 133	2 700
21	.....	.....	.....	1 144	1 556	2 032	2 571
22	.....	.....	.....	1 094	1 484	1 940	2 455
23	.....	.....	.....	1 044	1 420	1 856	2 348
24	.....	.....	.....	1 000	1 362	1 780	2 250
25	.....	.....	.....	960	1 306	1 708	2 150
26	.....	.....	.....	926	1 256	1 642	2 076
27	.....	.....	.....	888	1 210	1 582	2 000
28	.....	.....	.....	856	1 166	1 524	1 930
29	.....	.....	.....	.....	1 126	1 472	1 862
30	.....	.....	.....	.....	1 088	1 422	1 800

Loads above the heavy, black zigzag lines are calculated for resistance to shear.

For safe deflection-loads, see values in Tables VII to XII, according to the value of  $E$  used, and determined by the deflection-formula, page 636.

Table XV. Safe Distributed Loads in Pounds for Rectangular Wooden Beam

Maximum Fiber-Stress,  $S = 1\,800$  lb per sq in.  $A = 100$ 

Span in feet	The first horizontal line gives the depth of the beam in inches The loads are for beams one inch wide and supported at both ends						
	6	8	10	12	14	16	18
6	1 200	1 600	2 000	2 400	2 800	3 200	3 600
7	1 030	1 600	2 000	2 400	2 800	3 200	3 600
8	900	1 600	2 000	2 400	2 800	3 200	3 600
9	800	1 422	2 000	2 400	2 800	3 200	3 600
10	720	1 280	2 000	2 400	2 800	3 200	3 600
11	655	1 164	1 818	2 400	2 800	3 200	3 600
12	600	1 067	1 667	2 400	2 800	3 200	3 600
13	554	985	1 539	2 215	2 800	3 200	3 600
14	514	914	1 428	2 057	2 800	3 200	3 600
15	480	853	1 333	1 920	2 613	3 200	3 600
16	450	800	1 250	1 800	2 450	3 200	3 600
17	.....	753	1 176	1 694	2 306	3 012	3 600
18	.....	711	1 111	1 600	2 178	2 844	3 600
19	.....	674	1 053	1 516	2 063	2 695	3 411
20	.....	640	1 000	1 440	1 960	2 560	3 240
21	.....	.....	.....	1 371	1 867	2 438	3 086
22	.....	.....	.....	1 309	1 782	2 327	2 945
23	.....	.....	.....	1 252	1 704	2 226	2 817
24	.....	.....	.....	1 200	1 633	2 133	2 700
25	.....	.....	.....	1 152	1 568	2 048	2 592
26	.....	.....	.....	1 108	1 508	1 969	2 492
27	.....	.....	.....	1 067	1 452	1 896	2 400
28	.....	.....	.....	1 029	1 400	1 829	2 314
29	.....	.....	.....	.....	1 352	1 766	2 235
30	.....	.....	.....	.....	1 307	1 707	2 160

Loads above the heavy, black zigzag lines are calculated for resistance to shear.

For safe deflection-loads, see values in Tables VII to XII, according to the value of used, and determined by the deflection-formula, page 636.



### 8. Working Unit Stresses for Average, Unseasoned Woods

Safe Working Unit Stresses for unseasoned woods (except for *E*) are given in Table XVI. They are compiled and adapted largely from recommended UNIT STRESSES adopted by the Association of Railway Superintendents of Bridges and Buildings and by the American Railway Engineering Association. (See, also, page 449.)

Table XVI. Safe Working \* Unit Stresses for Unseasoned Woods, in Pounds per Square Inch

Kind of wood	Tension		Compression			Bending †		Shearing	
	With the grain ‡	Across the grain	With the grain		Across the grain	Ex-treme fiber-stress §	Modu-lus of elasti-city,    <i>E</i> /1 000	With the grain	Across the grain
			End-bearing	Col-umnst under 15 diams					
Factor of safety	Ten	Ten	Five	Five	Four	Six	One	Four	Four
White oak.....	1 200	200	1 400	1 000	500	1 200	1 500	200	1 000
White pine.....	700	50	1 100	800	200	700 ¶	1 000	100	500
Long-leaf yellow pine.....	1 200	60	1 400	1 000	350	1 200	1 500	150	1 250
Douglas fir.....	800	....	1 200	900	200	800 ¶	1 500	130	900
Short-leaf yellow pine.....	900	50	1 100	800	250	1 000	1 200	100	1 000
Red pine and Norway pine..	800	50	1 000	750	200	800	1 100	....	750
Spruce and eastern fir.....	800	50	1 200	900	200	700 ¶	1 200	100	750
Hemlock.....	600	....	1 100	800	150	600	900	100	600
Cypress.....	600	....	1 000	750	200	800	900	....	....
Cedar.....	700	....	1 100	750	200	700	700	100	400
Chestnut.....	850	....	....	800	250	800	1 000	150	500
Cal. red wood....	700	....	900	800	150	750	700	100	....
Cal. spruce.....	....	....	....	800	....	800	1 200	....	....

\* The stresses given, except for *E*, may be increased 30% for protected, commercially dry timber, not subject to impact, as in most buildings.

† See also, Table I, page 557, Table XVII, page 648, and Table I, page 1138.

‡ The larger end-bearing stresses are frequently used for short columns and for column-bases. (See tables, pages 449, 1138.) Lower factors of safety give higher stresses.

§ Some of these values are considered too low, relatively, by some building codes.

|| These values of *E* are for seasoned timber. For unseasoned timber, reduce *E* 20%.

¶ The New York Building Code (1917) stresses for these are 1 200 lb per sq in.

### 9. Working Unit Stresses for Woods. Taken from Building Laws.

The Allowable Working Unit Stresses for different woods, taken from the building laws of four cities, are given in Table XVII. The UNIT STRESSES are for TENSION, COMPRESSION, BENDING and SHEAR.

**Table XVII. Working Unit Stresses for Woods, in Pounds per Square Inc**

Kind of stress	Kind of wood	New York *	Chicago	Baltimore §	Boston ¶
Tension . . . . .	Yellow pine† . .	1 200	1 300	1 800LLYP	....
	White pine . . . .	700	800	1 000	....
	Spruce† . . . . .	800	800	1 200	....
	Hemlock . . . . .	600	800	800	....
	Douglas fir . . . .	800	1 300	.....	....
	Oak . . . . .	1 200	1 200	1 500	....
	Locust . . . . .	.....	.....	.....	....
			1 000SLYP	1 200VP	....
Compression with the grain	Yellow pine† . .	1 600	1 100	1 000LLYP	1 60
	White pine . . . .	1 000	700	800	1 00
	Spruce† . . . . .	1 200	700	800	1 00
	Hemlock . . . . .	800	500	600	....
	Douglas fir . . . .	1 200	1 100	.....	1 50
	Oak . . . . .	1 400	900	1 000	1 40
	Locust . . . . .	1 200	.....	1 200	....
			800SLYP	800NC or YP	....
Compression across the grain	Yellow pine† . .	350	250	600LLYP	50
	White pine . . . .	250	200	400	25
	Spruce† . . . . .	200	200	400	25
	Hemlock . . . . .	150	150	500	....
	Douglas fir . . . .	200	.....	.....	40
	Oak . . . . .	500	500	600	60
	Locust . . . . .	.....	.....	1 000	....
			250SLYP	400NC or VP	....
Transverse bending	Yellow pine† . .	1 600	1 300	1 800LLYP	1 60
	White pine . . . .	1 200	800	1 000	1 00
	Spruce† . . . . .	1 200	800	1 350	1 00
	Hemlock . . . . .	800	600	1 000	....
	Douglas fir . . . .	1 200	1 300	.....	1 50
	Oak . . . . .	1 200	1 200	1 500	1 40
	Locust . . . . .	.....	.....	.....	....
			1 000SLYP	.....	....
Shear with the grain	Yellow pine† . .	150	130	100LLYP	15
	White pine . . . .	100	80	85	10
	Spruce† . . . . .	100	80	90	10
	Hemlock . . . . .	100	60	75	....
	Douglas fir . . . .	100	130	.....	12
	Oak . . . . .	200	200	100	15
	Locust . . . . .	.....	.....	.....	....
			120SLYP	90VP	....
Shear across the grain	Yellow pine† . .	1 000	.....	500LYP	1 20
	White pine . . . .	500	.....	350	80
	Spruce† . . . . .	500	.....	350	80
	Hemlock . . . . .	600	.....	350	....
	Douglas fir . . . .	1 000	.....	.....	1 00
	Oak . . . . .	1 000	.....	720	1 20
	Locust . . . . .	.....	.....	.....	....
			.....	400VP	....

\* Stresses named by N. Y. are given in the 1917 Building Code of the Borough of Manhattan. Exception: Dist. of Columbia omits hemlock, omits chestnut in cross grain and puts spruce and Virginia pine under one caption; Cincinnati omits white pine and spruce, with N. Y. white-pine values, and gives 270 for hemlock or shear across grain. † Chicago, "Douglas fir and long-leaf yellow pine." ‡ Chicago values for spruce; spruce-values apply to Norway pine. || Chicago, values for short-leaf yellow pine, SLYP. § Baltimore, LLYP is long-leaf yellow pine; VP, N. Carolina or Virginia pine. ¶ Boston, yellow pine is "yellow pine (long-leaf)".

**10. Ultimate Unit Stresses for Woods**

**The Average Ultimate Unit Stresses** for the CONIFEROUS or SOFTWOODS and for the BROAD-LEAVED or HARDWOODS, together with the AVERAGE WEIGHTS of the woods per cubic foot are given in Tables XVIII and XIX. The values given are compiled from many tests on numerous species of timber. In regard to the range of values for the same kind of wood, it may be stated that the higher values are for specimens which contained a percentage of water varying from 15 to 20%; and that tests on laboratory specimens showed greater strength than the actual pieces used in construction. The WEIGHTS PER CUBIC FOOT are averages of the weights of many specimens tested and agree generally with average values given in other tables of weights of materials.

Table XVIII.\* Average Ultimate Unit Stresses for the Coniferous or Softwoods, in Pounds per Square Inch

Kind of wood	Weight in lb per cu ft, dry	Tension	Compression		Bend- ing (mod- ulus of rup- ture)	Shear	
			With the grain	Across the grain		With the grain	Across the grain
Cedar (white).....	19.72	8 000	4 000	700	5 000	400	1 300
	to	to	to				to
	20.70	11 400	6 000				1 515
Cedar (red).....	23.66	8 000	4 000	700	5 000	.....	1 500
			to				
			7 000				
Cypress.....	29.80	4 000	4 000	700	5 000	500	.....
		to	to	to	to		
		6 000	8 000	800	11 700		
Hemlock.....	26.42	6 000	4 000	600	3 500	350	2 500
	to	to	to	to			to
	32.29	8 700	7 420	700			2 750
Pine (white).....	25.55	3 000	3 000	700	4 000	225	2 480
		to	to	to	to	to	
		12 000	6 650	1 000	10 000	423	
Pine (red), (Norway pine).....	30.25	5 000	6 000	800	5 000	500	.....
		to	to	to	to		
		13 000	8 000	1 000	12 300		
Pine (yellow), (long- leaf).....	43.62	6 000	5 000	1 000	7 000	300	4 340
		to	to	to	to	to	to
		13 000	9 500	1 400	14 200	700	5 000
Pine (yellow), (short- leaf).....	38.40	5 000	4 000	900	6 000	400	4 000
		to	to	to	to	to	to
		10 000	9 000	1 000	12 400	700	5 000
Douglas fir (Oregon pine).....	32.14	9 000	4 880	800	6 500	500	.....
		to	to	to	to	to	
		14 000	9 800	1 200	12 100	600	
Redwood (California)	26.23	7 000	3 000	800	4 500	400	.....
		to	to				
		10 853	4 000				
Spruce (black).....	28.57	5 000	4 000	700	4 000	250	3 255
		to	to		to	to	
		19 500	7 850		12 000	400	
Spruce (white).....	25.25	5 000	4 000	700	4 000	250	3 255
		to	to		to	to	
		19 500	7 850		12 000	400	

\* The higher values of tensile and compressive strengths are for "dry" or "seasoned" timber containing from 10 to 15% of water. For safe fiber-stresses in flexure, see Table I, page 557.

**Table XIX.\*** Average Ultimate Unit Stresses for the Broad-Leaved or Hardwoods, in Pounds per Square Inch

Kinds of wood	Weight in lb per cu ft, dry	Tension	Compression		Bend- ing (mod- ulus of rup- ture)	Shear	
			With the grain	Across the grain		With the grain	Across the grain
Ash (white) . . . . .	40.77	11 000 to 17 000	4 000 to 9 000	1 900	6 300 to 14 200	450 to 1 100	6 280
Ash (red) . . . . .	38.96	.....	6 800	.....	.....	.....	.....
Ash (green) . . . . .	44.35	.....	8 000 to 9 800	1 700	5 100 to 16 000	1 000	6 280
Chestnut . . . . .	41.00	9 000 to 13 000	5 000	900	5 000	600	1 500
Elm (white) . . . . .	45.26	8 000 to 13 000	6 000 to 10 000	1 200	7 300 to 13 600	800	.....
Gum . . . . .	36.83	15 000 to 18 000	5 600 to 8 500	1 400	6 000 to 12 700	800	5 890
Hickory . . . . .	46.16 to 52.17	12 800 to 18 000	7 000 to 10 000	2 700 to 3 200	5 400 to 24 300	1 000 to 1 200	6 000 to 7 800
Locust . . . . .	45.70	10 500 to 24 800	7 000 to 11 700	.....	.....	.....	7 176
Lignum-vitæ . . . . .	77.12	11 000	8 800	.....	.....	.....	.....
Maple (hard) . . . . .	43.08	8 000 to 10 000	7 000 to 9 940	.....	.....	.....	6 355
Maple (white) . . . . .	32.84	8 000 to 10 000	6 000 to 7 500	1 700 to 1 900	.....	399 to 537	6 355
Mahogany (Central America) . . . . .	35.00	2 300 to 17 900	6 000	.....	10 800	.....	.....
Oak (white) . . . . .	46.35	10 000 to 19 500	4 500 to 11 300	2 000	6 000	750 to 1 000	4 425
Oak (chestnut) . . . . .	53.63	10 000	7 500	.....	.....	.....	.....
Oak (live) . . . . .	59.21	13 000	9 000	.....	.....	.....	8 480
Oak (red and black) . . . . .	40.75	10 000	4 000 to 8 500	2 300	9 100 to 15 400	1 100	.....
Poplar (whitewood) . . . . .	30.00	7 000	4 000 to 5 700	.....	.....	.....	4 418
Walnut (white) (but- ternut) . . . . .	25.46	.....	5 000 to 6 800	.....	.....	.....	2 830
Walnut (black) . . . . .	38.11	12 000	7 500	.....	.....	.....	4 728

\* The higher values of the tensile and compressive strengths are for "dry" or "seasoned" timber containing from 10 to 15% of water. For safe fiber-stresses for re, see Table I, page 557.

## CHAPTER XVII

STRENGTH OF BUILT-UP, FLITCHED AND TRUSSED  
WOODEN GIRDERS

By

F. H. KINDL

LATE CORRESPONDING MEMBER AMERICAN INSTITUTE OF ARCHITECTS

## 1. Built-Up Wooden Girders

**Built-Up Wooden Beams.** Wooden beams or girders built up of planks spiked or bolted together side by side, will generally be somewhat stronger than solid girders of the same dimensions, because the planks will be better seasoned and freer from check-cracks and other defects. For beams or girders 10 in or less in depth, spikes will usually be sufficient to bind the planks together, but for deeper beams, bolts should be used in addition to the spikes, to prevent the planks from separating and the outer planks from warping or curling away from the others.

**Bolts.** Two bolts should be placed at each end of the beam and every 10 feet of its length.

**Lengths of Planks.** When a beam is built up in this way each plank should extend the full length of the beam. In a CONTINUOUS BEAM, the planks should break joints over the supports. The planks of BUILT-UP BEAMS should always be set on edge, never flatwise.

**Compound Wooden Beams.** It is sometimes necessary to use a wooden beam for a longer span or greater load than is safe for the deepest SINGLE BEAM that can be obtained, or for a beam built up of planks. In such cases COMPOUND WOODEN BEAMS may be used.

**Definition.** By a COMPOUND WOODEN BEAM or GIRDER is meant a beam built up by placing two or more single beams over another one, with the view




Fig. 1. Two Simple Wooden Beams, One Over the Other,  
Loaded in Middle

of having them act as a SINGLE BEAM having the same depth as the combined beams.

**Strength of Compound Beams.** If two 10 by 10-in beams are placed one on top of the other, and the upper beam is loaded at the middle, the beams would act as two separate beams (Fig. 1) and their combined strength would be no greater than if the two beams were placed side by side. If, however, the two beams can be joined so that the fibers of the lower beam will be extended as much as would be the case in a single beam of the same depth, or, in other words so that the two beams will not slip on each other, the COMPOUND BEAM will have four times the strength of the SINGLE BEAM.

**Tests of Compound Beams.** Various attempts have been made to test beams thus placed so as to prevent the two parts slipping on each other,

During the years 1896-7, Edgar Kidwell, of the Michigan College of Mines, made an extended series of tests of the efficiency of COMPOUND BEAMS of different patterns. From these tests much valuable data was obtained. A full description of the tests, accompanied by the conclusions of the author, and the plans and data for proportioning the bolts and keys, of KEYED BEAMS, is published in the Trans. Am. Soc. M. E., vol. 27.

**Simple Form of Compound Beam.** A form of COMPOUND BEAM, sometimes used in American building-construction, is shown in Fig. 2, diagonal struts in opposite directions being nailed to each side of the two timbers to prevent their slipping on each other. T. M. Clark, in his Building Superintendence, advocates this as one of the best forms of compound beams, and




Fig. 2. Simple Form of Compound Wooden Beam

gives its EFFICIENCY at about 95% of that of a solid beam of the same depth. Professor Kidwell made nine tests of this type of beam. In six of the beams the ratio of span to depth was as 12 to 1, and in three of the beams, as 24 to 1. The shorter beams gave an average EFFICIENCY, without much variation, of 44%, and the longer beams an EFFICIENCY of 80.7%.

It was found that the beams failed by the splitting of the diagonal pieces or the drawing of the nails; "in every case, long before the beam broke, the struts came open or the nails were partly drawn out or bent over in the wood, thereby permitting the component beams to slide on each other." When built with equal boards, 1 1/4 in thick, nailed with tenpenny nails, as in Fig. 2, the BREAKING STRENGTH of such a beam may be taken at 65% of the strength of




Fig. 3. Compound Keyed and Bolted Wooden Beams

solid beam of the same depth and of a breadth equal to the breadth of the beams. The DEFLECTION of the beam, however, will be about double that of solid beam of the same size, and on that account this type of beam is not recommended for supporting floors with plastered ceilings or for carrying plastered partitions.

**Keyed Beams.** Professor Kidwell tested, also, several types of KEYED beams, and found that a compound beam keyed and bolted together, as shown in Fig. 3, is the most efficient form that it is practical to build.

It was found that with oak keys it was possible to obtain an EFFICIENCY of spruce beams of 95%, while the DEFLECTION varied from 20 to 25% more than would be expected in a solid beam.

**Cast-Iron Keys.** By using CAST-IRON KEYS the deflection was found to be but little, if any, greater than for a solid beam.

**Shape of Keys.** The keys must be wedge-shaped, as shown in Fig. 4, so that they can be driven tightly against the end-wood.

**Efficiency of Keyed Beams.** Professor Kidwell recommends that for ordinary purposes an EFFICIENCY of 75% be allowed when oak keys are used, and of 80% when the keys are of cast iron. The width of an oak key should be twice its height. Numerous small keys closely spaced gave better results than fewer large keys. In his report, Professor Kidwell gives formulas, and tables, for the number and spacing of the keys.

**Keys, Bolts and Washers for Compound Beams.** As compound beams when used, are generally built up of 8, 10, 12 or 14-in timbers, Mr. Kidwell some years ago, prepared a table giving the sizes of keys, the number required on each side of the middle of the span, their minimum spacing and the sizes of the bolts and washers to be used for such beams of from 20 to 36-ft span. He noted that the MAXIMUM SAFE LOADS for such beams should be 75% of the loads computed by Formula (10), page 630, for a beam supported at both ends and loaded with a uniformly distributed load.

Table I. Keys, Bolts and Washers for Compound, Keyed Wooden Beams

Size of beams	Size of keys	Bolts	Washers	Number of keys each side of center line			
				White pine	Spruce	Douglas fir	Laburnum
16-in beams	1½ by 3 -in oak keys	¾-in	3 -in	7	8	11	
20-in beams	1½ by 3 -in oak keys	¾-in	3 -in	9	11	13	
24-in beams	2 by 4 -in oak keys	7⁄8-in	3½-in	8	9	12	
28-in beams	2¼ by 4½-in oak keys	7⁄8-in	3½-in	9	10	12	

Size of keys	Bolts	Washers	Minimum spacing of keys			
1½ by 3 -in oak keys.....	¾-in	3-in	11¼-in	11¼-in	9 -in	9
2 by 4 -in oak keys.....	7⁄8-in	3-in	15 -in	15 -in	11¼-in	11¼
2¼ by 4½-in oak keys.....	7⁄8-in	3-in	17 -in	17 -in	13 -in	13

The Breadth or Thickness of Compound Beams should be not less than two-fifths of the depth.

The Number of Keys required is not affected by the length or breadth of the beam, if the beam is figured for the full safe load.

In Spacing the Keys (Figs. 3 and 4) they should not be closer than the minimum spacing given in Table I. For beams loaded at the middle, the spacing of the keys should be uniform from X to Y, Fig. 3, Y being one-eighth of the span from the center line. If the distance between the keys, center to



works out less than the minimum spacing, the safe load should be correspondingly reduced or the thickness of the beam increased.

**For Beams Uniformly Loaded**, the first four or five keys from the end should be spaced for minimum spacing, and the spacing of the remaining keys increased toward the point *Y*. When the ratio of depth to span is greater than  $\frac{1}{16}$ , the inner key may be a little more than one-eighth the span from the center line, for distributed loads. Fig. 3 shows the proper spacing for a 20-in. beam of 28-ft span and for a long-leaf yellow pine beam of 30-ft span; the tabulation below gives the proper spacing of keys for spruce beams of




Fig. 4. Details of Keyed and Bolted Wooden Beam

spans, figured from the end of the beam in each case. For other woods spans the spacing should be made as near like these as the fixed conditions will permit. Four examples of spacing are given below. The sizes of keys and washers to be used are given in Table I. If the beam is not over 12 in. wide, the bolts may be arranged as for the spruce beam (Fig. 3); if 12 in. or over, the bolts should be staggered as shown for the hard-pine beam. For very wide beam the bolts might be spaced as in detail *B*, Fig. 4. Spacing of keys in inches for spruce beams, commencing at end, for uniformly loaded loads:

For a spruce beam, 32-ft span, 10, 12, 12, 16, 19, 24, 32  
 For a spruce beam, 32-ft span, 10, 11½, 11½, 11½, 12, 12, 12, 13, 15, 18, 24  
 For a spruce beam, 36-ft span, 13, 15, 15, 15, 15, 16, 18, 20, 30  
 For a spruce beam, 36-ft span, 15, 17, 17, 17, 17, 17, 17, 17, 17

## 2. Flitched Beams or Flitch-Plate Girders

**Flitch-Plate Beams** (Fig. 5) were at one time much used, but with the high prices of steel it is cheaper and better to use steel beams.

The following explanation and formulas are given, however, for the benefit of one who might have occasion to use a beam of this kind. It has been in practice that the thickness of the wood should be sixteen times the thickness of the steel. As the steel is so much stiffer than the wood, we must

proportion the load on the wood so that the latter will bend as much as the steel plate bends: otherwise the whole load might be thrown on the steel plate. The MODULUS OF ELASTICITY of steel is about twenty times that of long yellow pine; so that a beam of this wood, 1 in wide, will bend twenty

STEEL PLATE




Fig. 5. Flitch-plate Girder

as much as a plate of steel of the same size and under the same load. If we want this beam to bend just as much as the steel plate, we must only one-twentieth the load on the wooden beam is sixteen times

thick as the steel plate, we should put sixteen-twentieths of its safe load on it, or, what amounts to the same thing, use a constant only four-fifths of the strength of the wood.

**Formulas for Flitch-Plate Girders.** On this basis the following formulas have been derived for the strength of FLITCH-PLATE GIRDERS, in which the modulus of the wood is sixteen times the breadth of the steel, approximately:

$$\begin{aligned} \text{Let } d &= \text{depth of beam in inches} \\ b &= \text{total thickness of wood in inches} \\ l &= \text{clear span in feet} \\ t &= \text{thickness of steel plate in inches} \\ A' &= \begin{cases} 53.6 \text{ for long-leaf yellow pine} \\ 45 \text{ for Douglas fir} \\ 31 \text{ for spruce} \end{cases} \\ P &= \text{total load at middle in pounds} \\ W &= \text{distributed load in pounds} \end{aligned}$$

Then, for beams supported at both ends,

$$\text{Safe load at middle in pounds} = \frac{d^2}{l} (A'b + 889 t)$$

$$\text{Safe distributed load in pounds} = \frac{2 d^2}{l} (A'b + 889 t)$$

$$\text{For distributed load, } d = \sqrt{\frac{Wl}{2 A'b + 1778 t}}$$

$$\text{For load at middle, } d = \sqrt{\frac{Pl}{A'b + 889 t}}$$

The bolts should be  $\frac{3}{4}$  in in diameter, and spaced 2 ft on centers. Each end should have two bolts, as in Fig. 5.

**Example.** What is the safe load, uniformly distributed, for a girder composed of three 4 by 14-in Douglas-fir timbers and two  $\frac{3}{8}$  by 14-in flitch-plates, with a span of 25 ft?

**Solution.** By Formula (2),

$$\text{Safe load} = \frac{2 \times 196}{25} (45 \times 12 + 889 \times \frac{3}{4}) = 18,922 \text{ lb}$$

### 3. Trussed Beams and Girders

**Use of Trussed Beams and Girders.** Whenever we wish to support a floor upon girders having a span of more than 30 ft, we must use a TRUSSED GIRDER, a riveted STEEL-PLATE GIRDER, or two or more STEEL BEAMS.

\* For commercially seasoned timber and for ideal conditions these values may be about 30%.

under the circumstances and in some parts of the country it may be cheaper or more convenient to use a large wooden girder, and truss it, as in Figs. 6, 7, 8 or 9.

**Depth of Trussed Girder.** For all these forms it is desirable to give the girder as much depth as the conditions allow; as, the deeper the girder, the smaller the stresses in the pieces.

**In the Single-Strut Trussed Girder,** we either have two beams, and one rod which runs up between them at the ends, or three beams, and two rods running up between the beams in the same way. The beams should be in one continuous length for the whole span, if they can be obtained in that length. The requisite dimensions of the tie-rod, struts and beams, in any given case, may be determined by first finding the stresses developed in these pieces, and then the areas of cross-sections required to resist these stresses.

**For a Single-Strut Truss (Fig. 6),** the stresses in the pieces may be determined by the following formulas:

**For a Distributed Load  $W$  Over the Whole Girder (Fig. 6)**




Fig. 6. Trussed Wooden Girder. One Vertical Strut

$$\text{Tension in } T = \frac{W}{2} \times \frac{\text{length of } T}{\text{length of } C} \quad (5)$$

$$\text{Compression in } C = \frac{1}{2} W. \quad (\text{See Note.}) \quad (6)$$

$$\text{Compression in } B = \frac{W}{2} \times \frac{\text{length of } B}{\text{length of } C} \quad (7)$$

**Note.** When the beam  $B$  is in one piece, the full length of span. If  $B$  is split over the strut then compression in  $C$  or tension in  $R = \frac{1}{2} W$ .

**For a Concentrated Load  $P$  Over  $C$  (Fig. 6)**

$$\text{Tension in } T = \frac{P}{2} \times \frac{\text{length of } T}{\text{length of } C} \quad (8)$$

$$\text{Compression in } C = P$$

$$\text{Compression in } B = \frac{P}{2} \times \frac{\text{length of } B}{\text{length of } C} \quad (9)$$

**For a Girder Trussed as in (Fig. 7), Under a Distributed Load  $W$  Over the Whole Girder**

$$\text{Compression in } S = \frac{W}{2} \times \frac{\text{length of } S}{\text{length of } R} \quad (10)$$

$$\text{Tension in } R = \frac{1}{2} W. \quad (\text{See Note.})$$

$$\text{Tension in } B = \frac{W}{2} \times \frac{\text{length of } B}{\text{length of } R} \quad (11)$$

**Note.** When the beam  $B$  is in one piece, the full length of span. If  $B$  is split over the strut then compression in  $C$  or tension in  $R = \frac{1}{2} W$ .

For a Concentrated Load,  $P$  at the Middle (Fig. 7) ,




Fig. 7. Trussed Wooden Girder. One Vertical Tie

$$\text{Compression in } S = \frac{P}{2} \times \frac{\text{length of } S}{\text{length of } R}$$

$$\text{Tension in } R = P$$

$$\text{Tension in } B = \frac{P}{2} \times \frac{\text{length of } B}{\text{length of } R}$$

For a Double-Strut Trussed Beam (Fig. 8) with a Distributed Load  $W$  the Whole Girder (Beam  $B$  Divided into Three Equal Spans)




Fig. 8. Trussed Wooden Girder. Two Vertical Struts

$$\text{Tension in } T = \frac{W}{3} \times \frac{\text{length of } T}{\text{length of } C}$$

$$\text{Compression in } C = \frac{W}{3}$$

$$\text{Compression in } B \text{ or tension in } D = \frac{W}{3} \times \frac{\text{length of } B}{\text{length of } C}$$

For a Concentrated Load  $P$  Over Each of the Struts  $C$  (Fig. 8)

$$\text{Tension in } T = P \times \frac{\text{length of } T}{\text{length of } C}$$

$$\text{Compression in } C = P$$

$$\text{Compression in } B \text{ or tension in } D = P \times \frac{\text{length of } B}{\text{length of } C}$$

For a Girder Trussed as in Fig. 9, and Under a Distributed Load  $W$  the Whole Girder (Beam  $B$  Divided into Three Equal Spans)

$$\text{Compression in } S = \frac{W}{3} \times \frac{\text{length of } S}{\text{length of } R}$$

$$\text{Tension in } R = \frac{W}{3}$$

$$\text{Tension in } B \text{ or compression in } D = \frac{W}{3} \times \frac{\text{length of } B}{\text{length of } R}$$

Concentrated Loads  $P$  Applied at Joints 2 and 3 (Fig. 9)




Fig. 9. Trussed Wooden Girder. Two Vertical Ties

$$\text{Compression in } S = P \times \frac{\text{length of } S}{\text{length of } R} \quad (20)$$

$$\text{Tension in } R = P$$

$$\text{Tension in } B \text{ or compression in } D = P \times \frac{\text{length of } B}{\text{length of } R} \quad (21)$$

Trusses constructed as shown in Figs. 8 and 9 should be divided so that the ties  $R$ , or the struts  $C$ , will divide the lengths of the girder into three equal or nearly equal parts. The lengths of the pieces  $T$ ,  $C$ ,  $B$ ,  $R$ ,  $S$ , etc. should be measured ON THE AXIAL LINES of the pieces. Thus, the length of  $R$  should be measured from the CENTER LINE OR AXIS of the tie-beam  $B$  to the CENTER LINE OR AXIS of the strut  $D$ ; and the length of  $C$  should be measured from the AXIS of the rod to the AXIS of the strut-beam  $B$ .

After determining the stresses in the pieces by these formulas, we may compute the areas of the cross-sections by the following rules:

$$\text{Area of cross-section of a short strut} = \frac{\text{compression in strut}}{S_c} \quad (22)$$

which  $S_c$  for cast iron may be taken at from 13 000 or 14 000 lb per sq in, and for wood as given in Table XVI, page 647.

The size of the long strut  $D$  (Fig. 9) should be determined by means of Tables 451 and 452 for wooden columns, Chapter XIV.

The diameters of the tie-rods may be obtained from Table II, page 388.

For the beam  $B$  (Figs. 8 and 9) when the load is distributed, we must compute the necessary area of cross-section as a STRUT (Fig. 8) or a TIE (Fig. 9), and also the area of its cross-section, as a BEAM, required to support its load, and use a beam with a section equal to the sum of the two sections thus obtained.

$$\text{Area of cross-section of } B \text{ to resist } \left\{ \begin{array}{l} \text{tension or compression} \end{array} \right. = \frac{\text{tension}}{S_t} \text{ or } \frac{\text{compression}}{S_c} \quad (23)$$

the trusses shown in Figs. 6 and 7, with distributed loads,

$$\text{Breadth of } B \text{ (as a beam)} = \frac{W \times l}{4 \times d^2 \times A} \quad (24)$$

the trusses shown in Figs. 8 and 9, with distributed loads,

$$\text{Breadth of } B \text{ (as a beam)} = \frac{W \times l}{6 \times d^2 \times A} \quad (25)$$

(Compare Equation (24) and (25) with Equation (11), page 630.)

$W$  denotes the total distributed load in pounds on the girder, and  $l$  the length of one section of the beam. When the loads are concentrated over the struts  $C$  (Fig. 8) or at the joints  $R$  (Fig. 9) then there will be no TRANSVERSE

STRESS on the beams  $B$ , and they need be proportioned for the COMPRESSIVE OR TENSILE STRESS, only, as the case may be.

In Formulas (23), (24) and (25), for  $S_c$  and  $S_t$ , substitute the values of safe unit stresses for compression, Table XVI, page 647, and for tension, Table II, page 388, and for  $A$  substitute the values recommended in Tables II and XVI, pages 628 and 647.

**Illustrative Examples.** To illustrate the method of computing the dimensions of the different parts of girders of this kind, two examples are given.

**Example 1.** It is required to design a trussed girder of the form shown in Fig. 6, for a span of 30 ft. The girders are to be 12 ft on centers, and are to carry a floor loaded with 100 lb per sq ft. The girder consists of three beams  $B$ , side by side, and two rods. We can allow the rod  $T$  to come two feet below the beams  $B$ , and we will assume that the depth of the beams  $B$  is to be 12 in; then the length of  $C$ , measured from the center line of the beam, is to be 30 in. The length of  $B$  is 15 ft, and by computation, or by scaling, we will assume the length of  $T$  to be 15 ft 2½ in.

**Solution.** The total load on the girder equals 100 lb multiplied by the area of the floor, or multiplied by the distance of the girders on centers, or,  $100 \times 30 \times 12 = 36\ 000$  lb. From Formula (5),

$$\text{Tension in } T = \frac{36\ 000}{2} \times \frac{182\frac{1}{2} \text{ in}}{30 \text{ in}} = 109\ 500 \text{ lb}$$

or 54 750 lb on each of the two rods. For such a large stress it is best to use steel rods at the ends of the rods, and allowing 16 000 lb per sq in for steel rods, we find from Table II, Chapter XI, that we must use two 2½-in steel rods.

The strut-beam we will make of long-leaf yellow pine. From Formula (7) we find the compressive stress in  $B = (36\ 000/2) \times (180/30) = 108\ 000$  lb. As we are to use three beams side by side, there will be 36 000 lb compression in each beam.

To resist the compression there is required an area of  $36\ 000/1\ 000$  or 36 sq in, which is equal to 3 by 12 in.

From Formula (24) we find the total breadth required to resist the transverse stress =  $\frac{36\ 000 \times 15}{4 \times 144 \times 67} = 14$  in; or each beam must be 4¾ by 12 in in cross-section.

3 by 12 in to resist the transverse stress, and 3 by 12 in to resist the compressive stress. Consequently each beam must be 7¾ by 12 in in cross-section.

As this would make the girder very wide, 27¼ in, we will use beams 6 by 14 in deep, increasing the depth of the girder 1 in, so that the height on centers will still be 30 in.

The area required to resist the compressive stress will be the same as before, 36 in, but as the beam is 14 in deep the breadth will be only 2.57 in.

The total breadth to resist the transverse stress will be  $\frac{36\ 000 \times 15}{4 \times 196 \times 67} = 10.4$

or 3.43 in for each beam. The total breadth for each beam will therefore be 6 in. A beam with a cross-section of 6 by 14 in will meet the requirements. The total width of the girder will then be 22¼ in. The load on  $C = 54\ 750$  lb, or 11 250 lb over each rod. The theoretical sectional area in sq inches necessary to resist this load =  $11\ 250/13\ 000$  for cast iron and  $11\ 250/10\ 000$  for oak. As the struts must be the full width of the girder, however, it will be necessary to make the sectional area much greater than the theoretical requirements. If made of cast iron the strut should be of the shape shown in Fig. 10, and if of oak, of the shape shown in Fig. 11. The cast-iron strut will be the best, but an oak strut will answer.

**Example 2.** It is required to support a floor over a lecture-room 40 ft wide, means of trussed girders; and as the room above is to be used for electrical purposes, it is desired to have a truss with very little iron in it. It is decided, therefore, to use a truss such as is shown in Fig. 9.

**Solution.** Where the girders rest on the wall, there will be brick pilasters giving a projection of 6 in, which will make the span of the truss 39 ft, and rods *RR* will be placed so as to divide the tie-beam into three equal spans of 13 ft each. The tie-




Fig. 10. Cast-iron Strut for Two Tie-rods

beam *B* will consist of two long-leaf yellow pine beams, with the struts *S* coming between them. There are two rods, instead of one, at *RR*, coming down on each side of the struts *S*, and passing through iron castings below the beams *B*, and forming supports for them. The height of the truss from center to center of timbers must be limited to 18 in. The trusses are 8 ft on centers.




Fig. 11. Wooden Strut for Two Tie-rods

The total floor-area supported by one girder is 8 by 39 ft, or 312 sq ft. The heaviest load to which the floor will be subjected is the weight of the people in the room, for which 75 lb per sq ft is an ample allowance; and the weight of the floor itself is about 100 lb per sq ft. This makes the total weight liable to come on one girder 31 200 lb.

$$\text{Compression in } S, \text{ from Formula (18)} = \frac{W}{3} \times \frac{157 \text{ in}}{18 \text{ in}} = 90\,700 \text{ lb}$$

$$\text{Tension in one pair of rods} = \frac{W}{3} = 10\,400 \text{ lb}$$

$$\text{Tension in } B \text{ or compression in } D = \frac{W}{3} \times \frac{156 \text{ in}}{18 \text{ in}} = 90\,130 \text{ lb}$$

As the unsupported length of *D* is greater than that of *S*, a beam that will resist the compression in *D* will be ample for *S*. We find from Table II, Chap. XIV, that it will require a post 10 by 12 in in cross-section to resist the compression in *D*, which is 13 ft in length. The tension in each rod is only 5 200 lb; and as the rods must support a larger washer at the bottom, they are made 1 in in diameter, not upset. The tension in each of the beams *B* is 45 065 lb. Divided by 1 200, the safe unit tensional stress for long-leaf yellow pine is 37.5 sq in, or about 2¾ by 14 in.

The total breadth of the tie-beam to resist the transverse load is found from Formula (25). Assuming 14 in for the depth of *B*

$$\text{Breadth of } B = \frac{31\,200 \times 13}{6 \times 196 \times 67} = 5.15 \text{ in, or about } 2\frac{1}{2} \text{ in for each beam}$$

The breadth of each tie-beam must therefore be 2¾ in + 2½ in = 5¼ in. Hence the tie-beams must be 5 by 14 in in section. The girder, therefore, must be built with 10 by 14-in strut-beams and two 5 by 14-in tie-beams, each 42 ft long. The 1-in rods may be cut ½ in into the strut-beams, and ½ in into the tie-

beams, so that the latter will come close against the struts  $S$ . The thrust of the strut  $S$  is equal to its compressive stress, and a connection between the beams and the struts must be designed that will resist this thrust, which in this case is 90 700 lb. As the inclination of the strut is very slight, there is ample room for bolts. It is best to use bolts which are at least  $1\frac{1}{2}$  in in diameter. As they are in double shear, the resistance to shearing of one bolt is 35 340 (See Table IX, page 431.) Steel bolts are used.

The bearing area of a  $1\frac{1}{2}$ -in bolt in a timber 10 in wide is 15 in. For the bearing resistance of long-leaf yellow pine, we may allow 1400 lb per sq in (Table XVI, page 647), which will give 21 000 lb as the bearing resistance of one  $1\frac{1}{2}$ -in steel bolt. As the force to be resisted is 90 700 lb, it will require five  $1\frac{1}{2}$ -in steel bolts to sustain this bearing pressure, the resistance to shearing being greater than this stress.

The number of bolts required to resist the bending moment must now be determined. The total bending moment to be resisted (see page 434, Chapter XII) = 90 700 times the distance, in inches, between the centers of the beams divided by 12, or  $90\,700 \times 1\frac{1}{2} = 113\,375$  in-lb.

From Table IX, page 431, we find that the maximum bending moment at a fiber-stress of 20 000 lb per sq in, for a  $1\frac{1}{2}$ -in steel bolt is 6 630 in-lb. Hence it will require seventeen  $1\frac{1}{2}$ -in bolts to resist the thrust in  $S$  without bending the bolts. As it is impracticable to put in so many bolts, larger bolts must be used. For a  $2\frac{1}{4}$ -in steel bolt, the maximum bending moment is 30 700 in-lb (Table IX, page 431), and four times this is 122 800 in-lb, hence four  $2\frac{1}{4}$ -in steel bolts will be sufficient to resist the bending stress, also the shearing and bearing-stresses. It will be seen from this example that it is much more difficult and expensive to make satisfactory end-joints in girders trussed as in Figs. 7 and 9 than it is for the single and double-bolted trusses like those shown in Figs. 6 and 8. The latter forms are to be preferred when the conditions will admit of their use.

These four cases of TRUSSED GIRDERS are but special examples of trussed girders. The stresses in them may also be determined by the methods explained in Chapter XXVII; and where the divisions of the girder cannot be made in the form, the stresses should be computed by the general methods there explained.



## CHAPTER XVIII

## STIFFNESS AND DEFLECTION OF BEAMS

By

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. General Principles of the Deflection of Beams\*

**Strength and Stiffness.** In many structures it is necessary that beams and girders shall be not only **STRONG** enough but **STIFF** enough; that is, not only **RUPTURE** be prevented, but the beams must not **BEND** so much as to appear unsightly, or to crack the ceiling. Therefore, in many cases, **DEFLECTION**, rather than absolute **STRENGTH**, may become the governing consideration in determining the size of a beam. Unfortunately, there is no method at present of combining the two calculations for **STRENGTH** and for **STIFFNESS** in one. A beam properly proportioned for **STRENGTH** will not bend enough to stress the fibers beyond the **ELASTIC LIMIT**, but it may in some cases bend more than a regard for appearances will justify. The distance that a beam bends under a given load is called its **DEFLECTION**, and its resistance to deflection is called its **STIFFNESS**.

A General Formula for the Maximum Deflection of any beam under a concentrated or uniformly distributed load not stressed beyond the **ELASTIC LIMIT** is:

$$\text{Deflection in inches} = \frac{\text{load in pounds} \times \text{cube of span in inches} \times c}{\text{modulus of elasticity} \times \text{moment of inertia}} \quad (1)$$

The values of  $c$  are as follows:

For beam supported at both ends, loaded at the middle.....	0.021
For beam supported at both ends, uniformly loaded.....	0.013
For cantilever beam, loaded at free end.....	0.333
For cantilever beam, uniformly loaded.....	0.125

**Deflection of Beam with Rectangular Section.** By making the proper substitutions in Formula (1), the following formula for a **RECTANGULAR** beam **SUPPORTED AT BOTH ENDS** and **LOADED AT THE MIDDLE** may be derived:

$$\text{Deflection in inches} = \frac{\text{load in pounds} \times \text{cube of span in feet} \times 1728}{4 \times \text{breadth} \times \text{cube of depth} \times E} \quad (2)$$

**Modulus of Elasticity.** From this formula the value of the **MODULUS OF ELASTICITY**,  $E$ , for different materials, has been calculated by accurately measuring the actual deflection of known beams under given loads applied at the middle and then substituting these known quantities in Formula (2).

**Simple Formula for Deflection.** Formula (2) may be simplified somewhat by representing  $1728/4E$  by  $1/F$ , which gives the formula

$$\text{Deflection in inches} = \frac{W \times l^3}{b \times d^3 \times F} \quad (3)$$

For a **DISTRIBUTED LOAD** the deflection will be five-eighths of this.

\* See also, in Chapter XVI, formula on page 636 and Table XVI, page 647.

† The constant  $F$  corresponds to Hatfield's  $F$ , in his treatise on "Transverse Strains."

To Find the Load at the Middle that will cause a GIVEN DEFLECTION transpose Formula (2) so that the load becomes the left-hand member of equation. Thus:

Load at middle in pounds =  $\frac{4 \times \text{breadth} \times \text{cube of depth} \times \text{deflection in in} \times E}{\text{cube of span} \times 1728}$

**Limit of Deflection.** In order that this formula may be of use in determining the maximum load which may be placed upon a beam, the LIMIT OF DEFLECTION must in some way be fixed. This is generally done by making certain proportion of the span.

**Allowable Deflection of Floor-Beams.** Tredgold and other authorities state that if a floor-beam deflects more than ONE-FORTIETH OF AN INCH EVERY FOOT OF SPAN, it is liable to crack the ceiling on the under side; and hence this is the limit which is often set for the deflection of beams in first-class buildings.

**Formulas for Deflection of Floor-Beams.** If the length in feet divided by 40 is substituted for the deflection in inches, Formula (4) becomes

Load at the middle =  $\frac{\text{breadth} \times \text{cube of depth} \times e}{\text{square of span in feet}}$

in which  $e = \frac{E}{17280}$

Most engineers and architects, however, think that ONE-THIRTIETH OF AN INCH PER FOOT OF SPAN, that is,  $\frac{1}{360}$  of the span, is not too much to allow the deflection of floor-beams, as a floor is seldom subjected to its full estimated load, and then only for a short time.

Table I. Values of Constants for Stiffness or Deflection on Beams\*

Material	$E \dagger$	$F = \frac{E}{432}$	$e = \frac{E}{17280}$	$e_1 = \frac{E}{12960}$
Cast iron.....	15 000 000	34 722	862	1 157
Wrought iron.....	26 000 000	60 000	1 500	2 000
Steel.....	29 000 000	67 130	1 678	2 238
Ash.....	1 482 000	3 430	87	114
California redwood.....	700 000	1 620	40	54
Cedar.....	700 000	1 620	40	54
Chestnut.....	900 000	2 080	52	69
Cypress.....	900 000	2 080	52	69
Douglas fir.....	1 500 000	3 472	87	116
Hemlock.....	900 000	2 080	52	69
Long-leaf yellow pine.....	1 500 000	3 472	87	116
Maple.....	1 902 000	4 400	110	146
Norway pine.....	1 100 000	2 546	64	85
Short-leaf yellow pine.....	1 200 000	2 777	69	92
Spruce.....	1 200 000	2 777	69	92
White oak.....	1 500 000	3 472	87	116
White pine.....	1 000 000	2 315	58	77

$E$  = modulus of elasticity, pounds per square inch; seasoned timber;  
 $F$  = constant for deflection of beam, supported at both ends, loaded at middle;  
 $e$  = constant, allowing a deflection of one-fortieth of an inch per foot of span;  
 $e_1$  = constant, allowing a deflection of one-thirtieth of an inch per foot of span;  
\* See, also, in Chapter XVI formula on page 636, and Table XVI, page 647.  
† See Notes, page 637, regarding reductions in value for  $E$ , for unseasoned timber.

If this ratio is adopted, the CONSTANT FOR DEFLECTION becomes

$$e_1 = \frac{E}{12\,960}$$

**Constants for Stiffness or Deflection of Beams.** In either of the above it is evident that the values used for  $E$ ,  $F$ ,  $e$ , or  $e_1$ , should be derived from tests on timbers of the same size and quality as those to be used. The values in the various woods given in the preceding table have been adopted by the editors after careful comparison with the results of numerous tests on large timbers and with values given by different authorities. The editors believe that they are perfectly reliable for first-class, seasoned, merchantable timber.

## 2. Formulas for Loads, Based Upon the Stiffness of Beams

**Safe Loads for Limited Deflections for Rectangular Beams.** Knowing the deflection caused by a load concentrated at the middle of a beam, and the **MOD OF OTHER DEFLECTIONS**, caused by different modes of loading and supporting, formulas for Cases I to VIII, Figs. 1 to 8, considered under the strength of **RECTANGULAR BEAMS** (Chapter XVI), can be easily deduced. These cases, arranged in a different order, are:

### For Beams Supported at Both Ends\*

**Load at the middle**

$$\text{Safe load} = \frac{\text{breadth} \times \text{cube of depth} \times e_1}{\text{square of span}} \quad (6)$$

$$\text{Breadth} = \frac{\text{load} \times \text{square of span}}{\text{cube of depth} \times e_1} \quad (7)$$

**Load at a point other than at the middle,  $m$  and  $n$  being the segments into which the beam is divided**

$$\text{Safe load} = \frac{\text{breadth} \times \text{cube of depth} \times \text{square of span} \times e_1}{16 \times m^2 \times n^2} \quad (8)$$

$$\text{Breadth} = \frac{\text{load} \times m^2 \times n^2 \times 16}{\text{cube of depth} \times \text{square of span} \times e_1} \quad (9)$$

**Load uniformly distributed**

$$\text{Safe load} = \frac{8 \times \text{breadth} \times \text{cube of depth} \times e_1}{5 \times \text{square of span}} \quad (10) \dagger$$

$$\text{Breadth} = \frac{5 \times \text{load} \times \text{square of span}}{8 \times \text{cube of depth} \times e_1} \quad (11)$$

**Inclined beam, loaded at the middle‡**

$$\text{Safe load} = \frac{\text{breadth} \times \text{cube of depth} \times e_1}{\text{span} \times \text{horizontal distance between supports}} \quad (12)$$

$$\text{Breadth} = \frac{\text{load} \times \text{span} \times \text{horizontal distance between supports}}{\text{cube of depth} \times e_1} \quad (13)$$

\* In Formulas (6) to (17) the breadth and depth are to be taken in inches, and the length or span in feet. The load is always in pounds.

† The values given in either of the last two columns of Table I may be used for  $e$  or  $e_1$ , according to the degree of stiffness desired, but the values  $e_1$  in the last column are ample under ordinary conditions.

‡ See, also, formula in Chapter XVI, page 636.

§ Tredgold's Elements of Carpentry, page 65.

### For Beams Fixed at One End, or Cantilever Beams

Load at the free end

$$\text{Safe load} = \frac{\text{breadth} \times \text{cube of depth} \times e_1}{16 \times \text{square of span}}$$

or,

$$\text{Breadth} = \frac{16 \times \text{load} \times \text{square of span}}{\text{cube of depth} \times e_1}$$

Load uniformly distributed

$$\text{Safe load} = \frac{\text{breadth} \times \text{cube of depth} \times e_1}{6 \times \text{square of span}}$$

or,

$$\text{Breadth} = \frac{6 \times \text{load} \times \text{square of span}}{\text{cube of depth} \times e_1}$$

**Note.** When the span in feet is less than the depth in inches, the beam should not be calculated by the formulas for STIFFNESS, but by those for HORIZONTAL SHEAR. (See Chapter XVI, page 635.)

### 3. Relative Stiffness of Beams

Beam supported at both ends and loaded at the middle.....	1
Beam supported at both ends and uniformly loaded.....	9
Beam fixed or restrained at both ends and loaded at the middle...	4
Beam fixed or restrained at both ends and uniformly loaded.....	8
Cantilever beam loaded at the free end.....	3/4
Cantilever beam uniformly loaded.....	3/16

**The Stiffest Rectangular Beam** containing a given amount of material that in which the ratio of depth to breadth is as 10 is to 6; hence, in designing beams, the depth and breadth should be made to approach as near this ratio as is practicable.

**Example 1.** What is the greatest distributed load that an 8 by 10 in white pine girder, 20 ft in span, will support, without deflecting at the center more than one-thirtieth of an inch per foot of span?

**Solution.** This girder comes under the case of a beam supported at both ends and loaded with a uniformly distributed load, and hence should be calculated by Formula (10). Substituting the given dimensions in Formula (10),

$$\text{Safe load} = \frac{8 \times 8 \times 1000 \times 77}{5 \times 400} = 2464 \text{ lb}$$

**Example 2.** What should be the dimensions of a long-leaf yellow-pine beam 10 ft in span, to support a concentrated load of 4250 lb at the middle without deflecting more than one-third of an inch at the center?

**Solution.** A deflection of one-third of an inch in a span of 10 ft is in the proportion of one-thirtieth of an inch per foot of span; and as the load is concentrated at the middle, Formula (7) should be used, with  $e_1$ , the value given in fourth column opposite long-leaf yellow pine.

Formula (7) gives the dimensions of the breadth, but in order to obtain a value for the depth must first be assumed. For such a short span, 10 in would seem to be a proper depth.

Substituting in Formula (7)

$$\text{Breadth} = \frac{4250 \times 100}{1000 \times 116} = 3.6 \text{ in}$$

Hence it will be necessary to use a 4 by 10-in beam. As the span of this beam in feet is the same as its depth in inches, it should be tested to see if it meets the requirements for strength also. From Table XII, page 643, it is found that the safe distributed load for a 1 by 10-in beam, 10 ft in span, is 1 333 lb, and for a 4 by 10-in beam the safe load would be four times as much, or 5 332 lb. The load in this example, however, is applied at the middle; hence the safe distributed load must be divided by 2, which gives 2 666 lb for the safe load at the middle. As this is much less than the load to be carried, the size of the beam should be increased to 4 by 16 in. In general it is not safe to use the FORMULAS FOR STIFFNESS when the span in feet does not exceed the depth in inches.

**Example 3.** What is the largest load that an inclined spruce beam 8 by 12 in in cross-section and 16 ft in length between the supports will carry at the middle, consistent with stiffness, the horizontal distance between the supports being 14 ft?

**Solution.** Formula (12) is the one to be used in this case. Assuming the limit of deflection at one-thirtieth of an inch per foot of span, the value of  $e$  is found opposite spruce in the last column of Table I. Making the proper substitutions,

$$\text{Safe load} = \frac{8 \times 1\,728 \times 92}{16 \times 14} = 5\,678 \text{ lb}$$

#### 4. Cylindrical Beams

**Formulas.** The formulas for beams with SQUARE CROSS-SECTIONS may be used for beams with CIRCULAR CROSS-SECTIONS, if  $1.7 \times e$  is substituted for  $e$ . That is, other conditions being equal, a CYLINDRICAL BEAM bends or deflects 1.7 times as much as a beam the cross-section of which is the square circumscribing the circular cross-section of the cylindrical beam.

#### 5. Safe Loads for Wooden Beams for a Given Deflection

**Use of Tables and Formulas.** Tables VII to XV, inclusive, pages 638 to 646, giving the SAFE LOADS FOR BEAMS, give, also, the maximum loads for beams, 1 in thick, that will cause a DEFLECTION not exceeding  $\frac{1}{360}$  of the span, that is,  $\frac{1}{360}$  in per foot of span. Where two loads are given for any span or depth the upper load is calculated for STRENGTH and the lower load for DEFLECTION. Where one load is given the calculation is for strength, as the calculation for deflection in those particular beams would give an excessive load (Example 2). To find the corresponding load for any thickness, multiply the load given in the table by the breadth of the beam in inches. Suppose, for example, that it is required to find the greatest distributed load that an 8 by 10-in white-pine girder, 20 ft in span, will support, without deflecting at the center more than one-thirtieth of an inch per foot of span. Referring to Table VIII, page 639, giving the safe loads in pounds for white-pine beams, two values are found opposite the 20-ft span, 389 and 308, the latter being the safe load for deflection. The safe load, therefore, for an 8 by 10-in girder will be eight times, or  $308 \times 8 = 2\,464$  lb, which agrees with the safe load for the same girder calculated for deflection by Formula 10, Example 1.

#### 6. Nominal and Standard Sizes of Wooden Beams

**Conversion Factors for Wooden Beams of Standard Size.** Table II may be used for beams that measure less than the NOMINAL DIMENSIONS. DRESSED BEAMS, and in many localities floor-joists carried in stock, are more

or less SCANT of the nominal dimensions, and for such joists a reduction in the safe load must be made to correspond to the reduction in size. The DRESS SIZES are generally ¼ in scant up to 4 in in breadth, above which they are ½ in scant; while in depth they are all generally ½ in less than the NOMINAL SIZE. The safe loads may be obtained by multiplying the safe loads as given in Tables VII to XV, pages 638 to 646, by the FACTORS given in the following table:

Table II. Conversion Factors for Beams of Commercial or Standard Sizes

Cross-sections of beams in inches	Factors	Cross-sections of beams in inches	Factors
1¾×5½	1.47	1¾×11½	1.61
2¾×5½	2.31	2¾×11½	2.53
1¾×6½	1.51	1¾×13½	1.63
2¾×6½	2.51	2¾×13½	2.56
1¾×7½	1.54	1¾×15½	1.65
2¾×7½	2.42	2¾×15½	2.58
1¾×9½	1.58	1¾×17½	1.65
2¾×9½	2.48	2¾×17½	2.60

**Example 4.** What is the safe load for a 2¾ by 13½-in spruce beam, 18 ft span?

**Solution.** From Table VIII, page 639, the safe load for a 1 by 14-in beam is 847 lb. Multiplying this by 2.56 the product is 2 168 lb, the safe distributed load for a beam 2¾ by 13½ in in cross-section. For a full, “nominal” size 3 by 14-in, the safe load would be 2 541 lb.

7. Deflection of Steel Beams

**General Formula.** The DEFLECTION of any steel beam may be found by means of Formula (1), page 663.

**Example 5.** It is required to determine the deflection of a 12-in 31.8 lb beam, 20 ft in span, under its maximum uniformly distributed load of 9.59 tons.

**Solution.** The load in pounds = 9.59 tons × 2 000 = 19 180 lb; the span in inches = 20 ft × 12 = 240 in; *c*, for a beam supported at both ends and uniformly loaded, from the values given under Formula (1), is 0.013; *E*, for steel is 29 000 000 lb per sq in (Table I, page 664); and the moment of inertia, from the properties of steel I beams, page 355, is 215.8. Substituting these values in Formula (1), page 663,

Deflection in inches =  $\frac{19\,180 \times 240^3 \times 0.013}{29\,000\,000 \times 215.8} = 0.551$  in

The allowable deflection is ⅓₀ of an inch per foot of span, or 2⁹⁄₃₀ = 0.666 in.

**Coefficients of Deflection.** In order to save the time required to use the DEFLECTION-FORMULA, COEFFICIENTS OF DEFLECTION have been worked out for different spans and are given in Table III.

Table III. Coefficients of Deflection for Uniformly Distributed Loads \*

Span in feet	Fiber-stress, pounds per square inch			Span in feet	Fiber-stress, pounds per square inch		
	16 000	14 000	12 500		16 000	14 000	12 500
1	0.017	0.014	0.013	26	11.189	9.790	8.741
2	0.066	0.058	0.052	27	12.066	10.558	9.427
3	0.149	0.130	0.116	28	12.977	11.354	10.138
4	0.265	0.232	0.207	29	13.920	12.180	10.875
5	0.414	0.362	0.323	30	14.897	13.034	11.638
6	0.596	0.521	0.466	31	15.906	13.918	12.427
7	0.811	0.710	0.634	32	16.949	14.830	13.241
8	1.059	0.927	0.828	33	18.025	15.772	14.082
9	1.341	1.173	1.047	34	19.134	16.742	14.948
10	1.655	1.448	1.293	35	20.276	17.741	15.841
11	2.003	1.752	1.565	36	21.451	18.770	16.759
12	2.383	2.086	1.862	37	22.659	19.827	17.703
13	2.797	2.448	2.185	38	23.901	20.913	18.672
14	3.244	2.839	2.534	39	25.175	22.028	19.668
15	3.724	3.259	2.909	40	26.483	23.172	20.690
16	4.237	3.708	3.310	41	27.823	24.346	21.737
17	4.783	4.186	3.737	42	29.197	25.548	22.810
18	5.363	4.692	4.190	43	30.604	26.779	23.909
19	5.975	5.228	4.668	44	31.954	28.039	25.034
20	6.621	5.793	5.172	45	33.517	29.328	26.185
21	7.299	6.387	5.703	46	35.023	30.646	27.362
22	8.011	7.010	6.259	47	36.562	31.992	28.565
23	8.756	7.661	6.841	48	38.135	33.368	29.793
24	9.534	8.342	7.448	49	39.741	34.773	31.047
25	10.345	9.052	8.082	50	41.379	36.207	32.328

\* Taken by permission from Pocket Companion, Carnegie Steel Company.

To find the deflection in inches of a section SYMMETRICAL ABOUT THE NEUTRAL AXIS, such as the section of an I beam, channel, zee, etc., divide the coefficient in the table corresponding to the given span and fiber-stress by the depth of the section in inches. To find the deflection in inches of a section NOT SYMMETRICAL ABOUT THE NEUTRAL AXIS, such as the section of an angle, tee, etc., divide the coefficient corresponding to the given span and fiber-stress by twice the distance of the extreme fiber from the neutral axis, obtained from the tables of Chapter X. To find the deflection in inches of a section FOR ANY OTHER FIBER-STRESS than the fiber-stresses given, multiply this fiber-stress by any of the coefficients in Table III, for the given span, and divide by the fiber-stress corresponding to the coefficient used.

**Example 6.** Required the deflection of a 10-in 25-lb beam of 10-ft span, under a maximum distributed load of 13 tons, the fiber-stress being taken at 16 000 lb per sq in. Table III gives 1.655 as the deflection-coefficient, and dividing this by 10, the depth of the beam in inches, the result is  $1.655/10 = 0.1655$ , for the deflection at the middle. By Formula (1), page 663, the deflection for the same beam, span, and load =  $\frac{26\ 000 \times 1\ 728\ 000 \times 0.013}{29\ 000\ 000 \times 122.1} = 0.1649$  in, the

two results being nearly identical. For the same beam, a span of 18 ft and load of 7.2 tons, the deflection by the table is 0.5363 in; and by Formula (1) 0.5328 in, practically the same result.

**Safe Loads and Deflection.** In the tables of Chapter XV, giving the safe loads for I beams, channels and rolled beams of other cross-sections, the loads given are for the **SAFE LIMIT OF DEFLECTION**; and the safe loads, also, are given which will cause deflections of more than  $\frac{1}{400}$  of the span-length in inches.

**Lateral Deflection of Beams.** When the unbraced length exceeds 10 times the width, the tabular safe loads should be reduced in accordance with the ratios given in the following table in order to insure that the stresses in the compression-flanges should not exceed the allowed safe unit stress:

Length of span	Allowable safe load	Length of span	Allowable safe load
5 X flange-width	Full tabular load	25 X flange-width	71.9% tabular load
10 X flange-width	Full tabular load	30 X flange-width	62.5% tabular load
15 X flange-width	90.6% tabular load	35 X flange-width	53.1% tabular load
20 X flange-width	81.2% tabular load	40 X flange-width	43.8% tabular load

"In addition to this lateral deflection which is induced within the beam by the action of pure bending-stresses, lateral deflection may be induced by the thrust of floor-arches or other loading acting on an axis perpendicular to the line of principal bending-stress. The thrust of these arches should either be neutralized by tie-rods, or the safe carrying capacity of the beam should be computed in accordance with the general formulas of flexure to provide for the combined stresses due to the action of both vertical and horizontal forces. That is to say, the safe loads should be figured around both the axes 1-1 and 2-2, and the unit stress computed so as not to exceed 16 000 lb per sq in."

### 8. Graphical Determination of Deflection of Beams

The Deflection of a Beam with parallel flanges and constant moment of inertia may be DETERMINED GRAPHICALLY. The deflected form is identical




Fig. 1. Moment and Deflection-diagrams of Beam Loaded at the Middle

with the bending-moment curve for a beam with a load distributed in a form similar to that of the bending-moment diagram. Fig. 1 is a beam of length  $L$ .

The moment-curve due to load  $P$  is the triangle  $ABC$ . The deflection-curve due to concentrated load  $P$  is the parabola  $MNO$ . The deflection-curve is obtained graphically by dividing area  $ABC$  into thin vertical strips and constructing force and equilibrium polygons (page 296). If a pole-distance be chosen bearing a convenient ratio to  $EI$  ( $E$  is the Modulus of Elasticity of the material and  $I$  the Moment of Inertia of the cross-section of the beam), the deflection at any point of the beam will have the same ratio to the area

ordinate at that point of the equilibrium-polygon.



## CHAPTER XIX

## STRENGTH AND STIFFNESS OF CONTINUOUS GIRDERS

BY

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. General Considerations

**Continuous Versus Single-Span Girders.** A CONTINUOUS GIRDER is one resting upon three or more supports, as distinguished from a SIMPLE GIRDER which rests upon two supports. Continuous girders, except in reinforced-concrete construction, and in some types of grillage-foundations, are of rare occurrence in building-construction. While in almost every building of importance it is necessary to employ girders resting upon piers or columns, placed from 15 to 20 ft apart, and while in many cases steel girders could conveniently be obtained which would span two and even three of the bays between the supports, they are practically limited to one-story buildings, because in tall buildings it is better construction to have the vertical rather than the horizontal supports continuous. Many different opinions are held as to the RELATIVE STRENGTH and STIFFNESS of continuous and non-continuous girders, and different formulas have been proposed from time to time; but in this chapter the mathematical discussions will not be given.\*

**Continuous Girders and Overhanging Girders.** In all CONTINUOUS GIRDERS, the end-spans (Fig. 2) are somewhat in the condition of a SIMPLE GIRDER with ONE OVERHANGING END, while the other spans are somewhat in the condition of a SIMPLE GIRDER with TWO OVERHANGING ENDS. At each intermediate support there is a NEGATIVE BENDING MOMENT, the effect of which is to reduce the bending moments between the supports.

## 2. Supporting Forces or Reactions of Continuous Girders

**Continuous Girder of Two Equal Spans. Concentrated Load at the Middle of Each Span.** If a girder of two spans, each equal to  $l$  (Fig. 1), be loaded at the middle of the left span with  $P$  lb, and at the middle of the right span with  $P_1$  lb, the reaction at the support  $R_1$  is determined by the formula

$$R_1 = \frac{13 P - 3 P_1}{32} \quad (1)$$

the reaction at the support  $R_2$  by

$$R_2 = 11\frac{1}{16} (P + P_1) \quad (2)$$

the reaction at the support  $R_3$  by the formula

$$R_3 = \frac{13 P_1 - 3 P}{32} \quad (3)$$

\* For the derivation of the following formulas, see an article by F. E. Kidder on this subject, in Van Nostrand's Engineering Magazine, July, 1881.

If  $P = P_1$ , then each of the end-supports must support  $\frac{1}{4}P$  and the middle support  $\frac{3}{4}P$ . If the girder is cut so as to make two girders of one span each, then the end-supports will carry  $\frac{1}{2}P$  or  $\frac{1}{4}P$ , and the middle support  $\frac{1}{4}P$ . Hence, it is seen that by making the continuous girder of three spans the reactions of the end-supports are diminished, while the reaction at the middle support is increased.




Fig. 1. Continuous Girder of Two Spans

Continuous Girder of Two Spans. Uniformly Distributed Load Over Each Span (Fig. 1). Load over each span equals  $w$  lb per unit of length. Let  $l$  be the length of the left span and  $l_1$  the length of the right span. Reaction at left support

$$R_1 = \frac{w}{2} \left[ l - \frac{l^3 + l_1^3}{4l(l + l_1)} \right]$$

Reaction of middle support,

$$R_2 = w(l + l_1) - R_1 - R_3$$

Reaction of right support

$$R_3 = \frac{w}{2} \left[ l_1 - \frac{l_1^3 + l^3}{4l_1(l + l_1)} \right]$$

When both spans are equal to  $l$ , the reaction of each end-support is  $\frac{3}{8}wl$ , of the middle support  $\frac{5}{8}wl$ ; hence the girder, by being continuous, reduces reactions of the end-supports, and increases that of the middle support 25%.

Continuous Girder of Three Equal Spans. Concentrated Load of  $P$  Pounds at the Middle of Each Span (Fig. 2).

Reaction of either abutment

$$R_1 = R_4 = \frac{3}{10}P$$

Reaction of either middle support

$$R_2 = R_3 = \frac{7}{10}P$$

or the reactions of the two end-supports are  $\frac{3}{10}$  less, and those of the two middle supports  $\frac{7}{10}$  greater than they would have been had three separate girders of the same cross-section been used, instead of one continuous girder.




Fig. 2. Continuous Girder of Three Spans

Continuous Girder of Three Equal Spans. Uniformly Distributed Load Over Each Span (Fig. 2). The load per unit of length is  $w$  lb.

Reaction of either end-support

$$R_1 = R_4 = \frac{3}{8}wl$$

Reaction of either middle support

$$R_2 = R_3 = \frac{7}{8}wl$$

Hence the reactions of the end-supports are  $\frac{1}{8}$  less, and of the middle supports  $\frac{1}{8}$  more, than if the girder were not continuous.

### 3. Bending Moments of Continuous Girders

**Strength of Continuous Girders.** The **STRENGTH** of a girder depends upon its material and the shape of its cross-section, and also upon the disposition of the external loads imposed upon it. The latter give rise to the **BENDING MOMENTS**, which are measures of the tendencies of the external forces, such as the loads and the supporting forces, to bend or to break the girder. It is the difference in the numerical values of these **BENDING MOMENTS** which causes the difference in the **FLEXURAL STRENGTH** of continuous and non-continuous girders of the same cross-section.

**Continuous Girders of Two Spans.** When a beam is at the point of breaking in flexure, the **FLEXURE-FORMULA**,  $M = SI/c$ , is frequently used to calculate a **MAXIMUM UNIT STRESS** developed in the beam; and when the beam has a regular cross-section the formula takes the form (see page 635)

$$\text{Maximum bending moment} = \frac{\text{Modulus of rupture} \times \text{breadth} \times \text{square of depth}}{6} \quad (11)$$

In order that the beam may carry its load with perfect safety, the breaking-load must be divided by a proper **FACTOR OF SAFETY**. Hence, if the **MAXIMUM BENDING MOMENT** of a beam can be found under any conditions, the required dimensions of the beam can easily be determined from Formula (11). (See Table I, page 557, for the safe values of the **FIBER-STRESSES**.) The greatest bending moment for a continuous girder of two spans is almost always over the middle support, and is a **MINUS BENDING MOMENT**, if the plus sign is given to the maximum bending moments between the supports. It is the **NUMERICAL VALUE** only, however, that is considered.

**Continuous Girder of Two Spans. Distributed Load over Each Span.** The greatest bending moment in a continuous girder of two spans,  $l$  and  $l_1$  (Fig. 1), loaded with a uniformly distributed load of  $w$  lb per unit of length is over the middle support and is

$$\text{Maximum bending moment} = \frac{wl^3 + wl_1^3}{8(l + l_1)} \quad (12)$$

When  $l = l_1$ , or both spans are equal,

$$\text{Maximum bending moment} = wl^3/8 \quad (12a)$$

which is the same as the maximum bending moment of a beam supported at its ends and uniformly loaded over its whole length. Hence a continuous girder of two spans uniformly loaded is no stronger as far as flexure is concerned as if non-continuous.

**Continuous Girder of Two Equal Spans. Concentrated Load at the Middle of Each Span.** The greatest bending moment in a continuous girder of two equal spans, each of length  $l$ , loaded with  $P$  lb at the middle of one span, and  $P_1$  lb at the middle of the other, is

$$\text{Maximum bending moment} = \frac{3}{32} l (P + P_1) \quad (13)$$

The modulus of rupture is equal to the ultimate flexural unit stress developed in a beam when the bending moment is great enough to cause failure, and is expressed in pounds per square inch. It usually lies between the ultimate unit compressive strength and the ultimate unit tensile strength of the material. (See, also, Chapter XV, page 60) It is to be noted, that the flexure-formula  $M = SI/c$  is not really applicable to materials for which the stresses are not proportional to the deformation, nor to non-homogeneous beams, nor to beams under stresses greater than the elastic limit of the material.

When  $P = P_1$ , or the two loads are equal, this becomes

$$\text{Maximum bending moment} = \frac{3}{16} Pl \quad (1)$$

or  $\frac{1}{4}$  less than its value when the beam is cut at the middle support.\*

**Continuous Girder of Three Spans. Uniformly Distributed Load Over Each Span.** The greatest bending moment in a continuous girder of three spans loaded with a uniformly distributed load of  $w$  lb per unit of length, the length of each end-span being  $l_1$  and of the middle span  $l$ , is at either of the middle supports, and is determined by the formula

$$\text{Maximum bending moment} = \frac{wl^2 + wl_1^2}{4(3l + 2l_1)}$$

When the three spans are equal, this becomes

$$\text{Maximum bending moment} = wl^2/10 \quad (2)$$

or  $\frac{1}{6}$  less than what it would be were the beam not continuous.

**Continuous Girder of Three Equal Spans. Concentrated Load of  $P$  Pounds at the Middle of Each Span.** The greatest bending moment in a continuous girder of three equal spans, each of a length  $l$ , and each loaded at the middle with  $P$  pounds, is

$$\text{Maximum bending moment} = \frac{3}{40} Pl$$

or  $\frac{3}{8}$  less than that of a non-continuous girder.

#### 4. Deflection of Continuous Girders

**Continuous Girder of Two Equal Spans. Uniformly Distributed Load Over Each Span.** The greatest deflection of a continuous girder of two equal spans loaded with a uniformly distributed load of  $w$  lb per unit of length is

$$\text{Maximum deflection} = 0.005416 wl^4/EI$$

in which  $E$  is the MODULUS OF ELASTICITY and  $I$  the MOMENT OF INERTIA of the cross-section of the beam. The greatest deflection of a similar beam supported at both ends and uniformly loaded is

$$\text{Maximum deflection} = 0.013020 wl^4/EI$$

Hence the deflection of the continuous girder is only about  $\frac{2}{3}$  that of a continuous girder. The greatest deflection of a continuous girder of two equal spans is not at the middle of either span, but between the middle point of a span and one of the abutments. The greatest deflection of a continuous girder of two equal spans, loaded at the middle of one span with a load of  $P$  lb, and at the middle of the other with  $P_1$  lb, is, for the span with the load,  $P$

$$\text{Maximum deflection} = \frac{(23P - 9P_1)P^2}{1536EI}$$

for the span with load  $P_1$

$$\text{Maximum deflection} = \frac{(23P_1 - 9P)P^2}{1536EI}$$

When both spans have the same load

$$\text{Maximum deflection} = \frac{7}{648} PP^2/EI$$

\* In this continuous beam the maximum bending moment is the minus bending moment over the middle support and in each of the two simple beams the maximum bending moment is a plus bending moment and is between two supports.

The greatest deflection of a simple beam supported at both ends and loaded at the middle with  $P$  lb is

$$\text{Maximum deflection} = \frac{P l^3}{48 EI}$$

the deflection of the continuous girder is only  $\frac{1}{4}$  that of a non-continuous one.

**Continuous Girder of Three Equal Spans. Uniformly Distributed Load Over Each Span.**

The load per unit of length is  $w$  lb.

$$\text{Greatest deflection at the middle of middle span} = 0.00052 \frac{w l^4}{EI} \quad (18)$$

$$\text{Greatest deflection in the end-spans} = 0.006884 \frac{w l^4}{EI} \quad (19)$$

hence the maximum deflection of the continuous girder is only about  $\frac{1}{4}$  that of a non-continuous girder.

**Continuous Girder of Three Equal Spans. Concentrated Load  $P$  at the Middle of Each Span.**

$$\text{Greatest deflection at the middle span} = \frac{1}{480} \frac{P l^3}{EI} \quad (20)$$

$$\text{Greatest deflection at the middle of end-spans} = \frac{1}{660} \frac{P l^3}{EI} \quad (21)$$

hence the maximum deflection of the continuous girder is only  $\frac{1}{4}$  of that of a non-continuous girder.

## Notes on Reactions, Strength and Stiffness of Continuous Girders

**Supports and Reactions of Continuous and Non-Continuous Girders.** From the foregoing, some conclusions can be drawn which will be of use in deciding whether it is best in any case to use a CONTINUOUS or a NON-CONTINUOUS GIRDER. From the formulas given for the reactions of the supporting forces in the different cases of continuous girders it is seen that the end-supports do not bear as much of the load as they do when the girders are non-continuous. The difference is added to the reactions of the other supports. This might be an advantage in a building in which the girders run across the building, and their outside ends supported by the side walls and their inside ends by piers or columns. In this case, by using continuous girders, part of the load could be taken from the walls and transferred to the piers or columns. But in cases of this kind, the vibration may have to be considered. If the building is a mill or factory in which the girders support machines, any vibration in the middle span of the girder is carried to the side walls if the girder is continuous; but if non-continuous girders are used, with their ends an inch or so apart, no or no vibration is carried to the side walls from the middle span. In all cases of important construction the supporting forces should be carefully considered.

**Relative Strength of Continuous and Non-Continuous Girders.** As the RELATIVE STRENGTH of continuous and non-continuous girders of the same cross-section, material and spans, and loaded in the same way, is proportional to their maximum BENDING MOMENTS, the strength of a continuous girder can be calculated, from the formula for its MAXIMUM BENDING MOMENT. From the formulas given for these bending moments for the various cases considered, it is seen that the parts of the girder most stressed are those which come over the middle supports. It is seen, also, that, except in the single case of a girder of two spans uniformly loaded, the strength of a continuous girder is greater than that of a non-continuous girder. But the gain in strength in some instances is not very great, although it is generally enough to pay for making the girder continuous.

**Relative Stiffness of Continuous and Non-Continuous Girders.** The STIFFNESS of a girder varies inversely as its DEFLECTION; that is, the less the deflection under a given load the stiffer the girder. From the values given for MAXIMUM DEFLECTION of continuous girders, it is evident that the STIFFNESS of a girder is increased by making it continuous; and this is usually the principal advantage in the use of continuous girders. It sometimes happens in building construction that it is necessary to use beams and girders of much greater strength than is required to carry the superimposed load, because the deflections of smaller beams or girders would be too great. But if continuous girders are used they may be made of just the size required for strength, because the deflections are less. Where great stiffness is required, therefore, continuous beams or girders should be used if possible, as in the case of grillage-girders (See Example 3, page 679.)

## 6. Formulas for the Strength and Stiffness of Continuous Girders

**Girders of Rectangular Cross-Section.** For convenience, the proper formulas for calculating the strength and stiffness of continuous girders of rectangular cross-section are given. The formulas for strength are deduced from the flexure formula  $M = SI/c$ , modified for the rectangular section of breadth  $b$  and depth  $d$ .

$$\text{Bending moment} = \frac{b \times d^2 \times S}{6}$$

in which  $S$  is the safe unit fiber-stress. This is eighteen times the coefficient  $A^*$  of Table II, page 628.

**STRENGTH. Continuous Girder of Two Equal Spans. Uniformly Distributed Load Over Each Span.**

$$\text{Breaking-load } \dagger = \frac{2 \times b \times d^2 \times A^*}{l}$$

where  $b$  denotes the breadth and  $d$  the depth of the girder in inches, and  $l$  the length of one span, in feet. The values of the constant  $A$  are three times the values given in Table II, page 628. For long-leaf yellow pine, 201; for Douglas fir, 168; chestnut, 132; and for spruce and white pine, 117 lb per sq in, are recommended for the values of  $A$  in these formulas.

**Continuous Girder of Two Equal Spans. Concentrated Load at the Middle of Each Span.**

$$\text{Breaking-load} = \frac{2}{3} \times \frac{b \times d^2 \times A}{l}$$

**Continuous Girder of Three Equal Spans. Uniformly Distributed Load Over Each Span.**

$$\text{Breaking-load} = \frac{5}{8} \times \frac{b \times d^2 \times A}{l}$$

**Continuous Girder of Three Equal Spans. Concentrated Load at the Middle of Each Span.**

$$\text{Breaking-load} = \frac{5}{8} \times \frac{b \times d^2 \times A}{l}$$

\* See, also, Table I, page 557, and Table XVI, page 647, for safe fiber-stresses.

† Breaking-load in pounds in all cases.

**STIFFNESS. Continuous Girder of Two Equal Spans. Uniformly Distributed Load Over Each Span.**

The following formulas give the loads which the beams will support without deflecting more than one-thirtieth of an inch per foot of span.

$$\text{Load on one span} = \frac{b \times d^3 \times e_1}{0.26 \times l^3} \quad (27)$$

**Continuous Girder of Two Equal Spans. Concentrated Load at the Middle of Each Span.**

$$\text{Load on one span} = 1\frac{1}{4} \times \frac{b \times d^3 \times e_1}{l^3} \quad (28)$$

**Continuous Girder of Three Equal Spans. Uniformly Distributed Load Over Each Span.**

$$\text{Load on one span} = \frac{b \times d^3 \times e_1}{0.33 \times l^3} \quad (29)$$

**Continuous Girder of Three Equal Spans. Concentrated Load at the Middle of Each Span.**

$$\text{Load on one span} = 2\frac{1}{11} \times \frac{b \times d^3 \times e_1}{l^3} \quad (30)$$

The value of the constant  $e_1$  is obtained by dividing the MODULUS OF ELASTICITY by 12 960; and, for the three woods most commonly used as beams, the following values may be taken:

Long-leaf yellow pine, 116; white pine, 77; spruce, 92; Douglas fir, 116. For other woods, see Table I, page 664.)

For Continuous Steel Beams the requisite size may be found by first computing the MAXIMUM BENDING MOMENT, by means of Formulas (12) to (15), and then selecting a beam that has a

$$\text{SECTION-MODULUS} = \frac{3 \times \text{maximum bending moment in ft-lb}}{4\ 000} \quad (31)$$

Values for the SECTION-MODULI for the different shapes of rolled steel used as beams are given in the tables in Chapter X.

**Example 1.** What steel beam should be used to support two loads of 16 000 lb each, concentrated at the middle of two spans of 10 ft each, the beam being continuous?

**Solution.** Formula (13a) gives the maximum bending moment as  $\frac{3}{16} Pl$ , or 30 000 ft-lb. Therefore, from Equation (31), a beam having a section-modulus equal to  $3 \times 30\ 000 / 4\ 000$  or 22.5 should be used. From the Table IV, page 664, it is found that a 9-in 30-lb beam has a section-modulus of 22.5, and a 10-in 35-lb beam a section-modulus of 24.4. Either of these beams will therefore answer, the 10-in beam being the cheaper, however, and also the stiffer.

**Example 2.** A steel beam continuous over three spans is required to support a uniformly distributed load of 1 000 lb per lin ft. The two end-spans are 12 ft each, and the middle span 10 ft. What should be the size and the weight of the beam used?

**Solution.** The maximum bending moment is found by Formula (14), and is

$$\frac{1\ 000 \times 1\ 000 + 1\ 000 \times 1\ 728}{4 (30 + 24)} = 12\ 630$$

The section-modulus, by Equation (32), must equal  $3 \times 12\ 630/4\ 000 = 9.47$  which requires a 7-in 15.3-lb beam (Table IV, page 355).

If the beam were not continuous an 8-in 18.4-lb beam would be required for the 12-ft spans, and a 7-in 15.3-lb beam for the 10-ft span.

For a beam of two equal spans, loaded uniformly, the strength is the same as though it were not continuous.

The formulas given for the reactions at the supports, and for the deflection of continuous girders with concentrated loads, were verified by Mr. Kidd means of careful experiments on small steel bars. The remaining formulas were verified by comparing them with the formulas of other authorities where it was possible to do so. In regard to some of the cases given the author never seen any discussion of them in any work on the subject.

## 7. Continuous Girders in Grillage-Foundations

**Grillage-Beams Considered as Inverted Continuous Girders.** As stated at the beginning of this chapter, CONTINUOUS GIRDERS, as such, are seldom used in building-construction, although their employment in grillage-beam footings is



Fig. 3. Continuous Girder in Grillage-foundation




Fig. 4. Shear-diagram and Bending-moment Diagram

requent. Fig. 3 represents a footing consisting of two layers of beams, which tribute the load of the three columns above, uniformly over the foundation. By inverting the footing the three columns become the supports or reactions. The upper layer of beams, a continuous girder, loaded with a uniformly distributed load which is the pressure of the lower layer. As in practice the col



loads are never equal, and the distance between the columns seldom equal, it is necessary to project the continuous girder beyond the most heavily loaded column in order to insure a uniform pressure upon the lower layer. Because of these limitations none of the formulas previously deduced can be applied, although the principles upon which they are based hold good.

**Maximum Bending Moment.** Since the REACTIONS in this case are the given column-loads it is required first to find the MAXIMUM BENDING MOMENT. From what has already been said about continuous girders, it is evident that the point of maximum bending moment may be under columns 1 or 2, or between the columns. Since the maximum bending moments are the POINTS OF NO SHEAR, construct the SHEAR-DIAGRAM, find where the shear passes through zero, and calculate the bending moments at these points. The maximum bending moment is determined, as in examples 1 and 2, in order to determine the SECTION-MODULUS of the girder.

**Example 3.** The continuous girder under columns 1, 2 and 3 (Fig. 3) is 33 ft long; the overhang, to the left of column 1, 6.25 ft; the distance between columns 1 and 2, 13.12 ft; between columns 2 and 3, 12.88 ft; and from column 3 to the right edge of the girder, .75 ft. The column-loads are as follows: on column 1, 565 tons; on column 2, 600 tons; and on column 3, 255 tons.

The column-loads may be considered uniformly distributed over parts of the girder by the bases, which are 3 ft wide under columns 1 and 2 and 18 in wide under column 3. The UNIT PRESSURE under column 1, therefore, is  $565/3 = 188.3$  tons; under column 2,  $600/3 = 200$  tons; and under column 3,  $255/1.5 = 170$  tons. The unit pressure under the continuous girder is

$$(565 + 600 + 255)/33 = 43 \text{ tons}$$

The first step in the calculation of the girder is the determination of the POINTS OF NO SHEAR and the plotting of the SHEAR-DIAGRAM in Fig. 4. It is obvious from the shear-diagram that there are four points of no shear and consequently four points of POSSIBLE MAXIMUM BENDING MOMENT. The first of these is under column 1, the second between columns 1 and 2, the third under column 3 and the fourth between columns 2 and 3. The bending-moment diagram is shown by the solid curved line in Fig. 4. The points of contraflexure or no bending moment are the intersections of this line with the horizontal line of reference.

The SHEAR-DIAGRAM,\* shown by the broken line in Fig. 4, may be constructed as follows:

$$V_1 \uparrow = +43 \text{ tons per ft} \times (6.25 - 1.5 = 4.75 \text{ ft}) = +204.25 \text{ tons}$$

$$V_2 = (+43 \text{ tons per ft} \times 6.25 \text{ ft}) - 565/2 \text{ tons} = +268.75 - 282.5 \\ = -13.75 \text{ tons}$$

This shows that  $x_1$ , the point of no shear, lies between points 1 and 2. To find this point let  $y$  be its distance beyond or to the right of point 1. Then, the EQUATION FOR NO SHEAR is  $43 \text{ tons} \times (4.75 \text{ ft} + y \text{ ft}) = 188.3 \times y$ , or  $204.25 + 43y = 188.3y$ , from which  $145.3y = 204.25$  and  $y = 1.4$  ft: hence  $x_1$ , the FIRST POINT OF NO SHEAR, is  $4.75 \text{ ft} + 1.4 \text{ ft}$ , or  $6.1 \text{ ft}$  from the left end.†

The SECOND POINT OF NO SHEAR,  $x_2$ , is such a distance from the left end that the DOWNWARD SHEARING-FORCE of 565 tons from column 1 is neutralized by

\* The upward forces are here called plus or positive and the downward forces minus or negative.

†  $V_1$  is taken at point 1, the left edge of base of Column 1,  $V_2$  at point 2, at the axis of column 2, etc.

‡ The following computations are carried out to one decimal-place, only, the nearest approximate values being used.

an equal UPWARD SHEARING-FORCE of 43 tons per ft. on  $x_2$  ft. Hence  $x_2 = 565/43 = 13.1$  ft.

$$V_6 = +43 \text{ tons per ft} \times [(6.25 + 13.12 - 1.5) = 17.9 \text{ ft}] - 565 \text{ tons} \\ = 769.7 - 565 = +204.7 \text{ tons}$$

$$V_7 = +43 \text{ tons per ft} \times (6.25 + 13.12 = 19.4 \text{ ft}) - (565 + 600/2 \text{ tons}) \\ = +834.2 - 865 \text{ tons} = -30.8 \text{ tons}$$

This shows that the THIRD POINT OF NO SHEAR,  $x_3$ , lies between 6 and 7. Let  $y$  be its distance to the right of point 6. The equation for no shear at the point is  $43 \text{ tons} \times (17.9 \text{ ft} + y \text{ ft}) = 565 \text{ tons} + (200 \text{ tons} \times y \text{ ft})$ , or  $769.7 + 43y = 565 + 200y$ , from which  $157y = 204.7$  and  $y = 1.3$  ft. Hence  $x_3$ , the THIRD POINT OF NO SHEAR, is  $17.9 \text{ ft} + 1.3 \text{ ft} = 19.2 \text{ ft}$  from the left end.

The FOURTH POINT OF NO SHEAR,  $x_4$ , is such distance from the left end that the DOWNWARD SHEARING-FORCE of columns 1 and 2, amounting to  $565 + 600$  or 1165 tons, is neutralized by an equal UPWARD SHEARING-FORCE of 43 tons per ft on  $x_4$  ft. Hence  $x_4 = 1165/43 = 27.1$  ft.

Having found the points of no shear, the BENDING MOMENT at these points may now be determined.

$$M \text{ at } x_1 = 43 \text{ tons} \times 6.1 \text{ ft} \times 6.1/2 \text{ ft} - 188.3 \text{ tons} \times 1.4 \text{ ft} \times 1.4/2 \text{ ft} \\ = +615.5 \text{ ft-tons}$$

$$M \text{ at } x_2 = 43 \text{ tons} \times 13.1 \text{ ft} \times 13.1/2 \text{ ft} - 565 \text{ tons} \times 6.8 \text{ ft} = -152.4 \text{ ft-tons}$$

$$M \text{ at } x_3 = 43 \text{ tons} \times 19.2 \text{ ft} \times 19.2/2 \text{ ft} - 565 \text{ tons} \times 12.9 \text{ ft} - 200 \text{ T} \times 1.3 \\ \times 1.3/2 = +467 \text{ ft-tons}$$

$$M \text{ at } x_4 = 43 \text{ tons} \times 27.1 \text{ ft} \times 27.1/2 \text{ ft} - 565 \text{ tons} \times 20.8 \text{ ft} - 600 \text{ tons} \\ \times 7.7 \text{ ft} = -582.2 \text{ ft-tons}$$

The MAXIMUM BENDING MOMENT therefore is at  $x_1$  and equals 615.5 ft-tons\* or 1 231 000 ft-lb. Substituting in Formula (31), the SECTION-MODULUS is found to be  $\frac{3 \times 1\,231\,000}{4\,000} = 923.2$ . The following beams could be used, as far as

flexure is concerned. For investigations of the resistance of the girders to web buckling or crippling, see Chapter II, pages 182 to 184, and Chapter XI, pages 567 to 569.

Four standard 24-in 110-lb I beams, section-modulus of each, 239.1 (page 357)  
Three Bethlehem 30-in 120-lb I beams, section-modulus of each, 349.3 (page 357)

Three Bethlehem 24-in 140-lb girder-beams, section-modulus of each, 350 (page 358)

Two Bethlehem 28-in 180-lb girder-beams, section-modulus of each, 518 (page 358)

The 28-in and 30-in beams are stiffer than the 24-in beams, have a small total amount of steel and cost less than the others for the number of beams required.

\* The bending moments at  $x_1$  and  $x_4$  have very nearly the same numerical values, and in the computations the retaining or dropping of figures in the second decimal-place may change the result and make the value at  $x_4$  slightly greater than at  $x_1$ .

## CHAPTER XX

## RIVETED STEEL PLATE AND BOX GIRDERS

By

CHARLES P. WARREN

LATE ASSISTANT PROFESSOR OF ARCHITECTURE, COLUMBIA UNIVERSITY

## 1. General Notes on Plate and Box Girders

**Types of Riveted Girders.** Girders built up of plates and angles, as shown in section in Figs. 1 to 4, are extensively used. This is undoubtedly owing to the simplicity of their construction, to the comparatively low cost of the shapes of which they are fabricated and to their adaptability to any arrangement of loads or to any span for which girders are usually required. Riveted girders, however, are seldom made for spans greater than 60 ft and are seldom more than 6 ft in depth. The most common forms of these girders are shown in Figs. 2 and 4.



Fig. 1




Fig. 2




Fig. 3




Fig. 4

Types of Riveted Girders

The girders with a single vertical plate called the **WEB** are usually called **PLATE GIRDERS**, and those with double or triple webs, **BOX GIRDERS**. Plate girders are more economical than box girders, and more accessible for painting and inspection; but box girders are stiffer laterally and should always be used where great length of span requires wide flanges. In general, it may be said that plate girders should be used to support floor-beams and floor-arches and walls not over 12 in thick, and that box girders should be used where a flange-width greater than 12 in is required. The girder shown in section in Fig. 1 has no flange-plates and should be used only for comparatively light loads and short spans, and never to support masonry.

**Flange and Web.** The term **FLANGE**, as applied to riveted girders, includes all the metal in the top or bottom parts of the girder, exclusive of the web-plates.\* The **DEPTH** of a riveted girder is the distance between the centers of gravity of the flanges; but in practice this is usually taken as the **DEPTH OF THE WEB-PLATE**, and the word will be so used in this chapter. The top and bottom of the flange-angles extend  $\frac{1}{4}$  in beyond the top and bottom of the web-plate. (See the figure in Table IV, page 706.) **STIFFENERS** are short pieces of angles

\* This may be modified, however, as some engineers include one-sixth of the web-area in the effective flange-area. See, also, Flange-Area in the examples of this chapter.

riveted to the web at intervals, to keep it from BUCKLING. They should be placed closely against the horizontal legs of the flange-angles, and should always be used at the supports and under concentrated loads.

**Economic Depths of Girders.** The depth of a riveted girder may vary from one-tenth to one-fifteenth or, in exceptional cases, one-sixteenth the span. The greatest economy of material is said to be obtained when the depth is one-twelfth the span. Thus for a 36-ft span a 3-ft girder should be used if the conditions will permit; but the least depth should be  $\frac{1}{12}$  of 36, or about 3 ft 0 in or, in exceptional cases,  $\frac{1}{16}$  of 36, or 2 ft 3 in. A girder is said to have **ECONOMIC DEPTH** when the amount of material in the flanges is equal to that in the web, and there are no cover-plates. The rule holds approximately when there are cover-plates.

**The Width of the Top Flange** should not be less than one-twentieth the distance between lateral supports; or if there are no lateral supports, then not less than one-twentieth the span.

**Arches Between Girders**, or floor-beams riveted to the sides of girders, may be considered as **LATERAL SUPPORTS**.

## 2. Details of Construction of Plate and Box Girders\*

**General Requirements for Plate and Box Girders.** The following requirements are those which must be generally satisfied in the design of riveted girders.

(1) All the connections and details of the several parts shall be of such strength that, upon testing, rupture shall occur in the body of the members rather than in any of their details or connections.

(2) In members subject to tensile stress full allowance shall be made for the reduction of the section by the rivet-holes.

(3) The webs of plate girders, when they cannot be obtained in one length, must be spliced at all joints by a plate on each side of the web.

(4) Tees must not be used for splices.

(5) Stiffeners shall be used at the ends of all girders, wherever there are concentrated loads, and elsewhere when the shearing-stress is greater than the resistance to buckling.

(6) The **PITCH**, that is, the distance between centers of rivets, shall not exceed 6 in, nor 16 times the thickness of the thinnest outside plate, and it shall not be less than  $2\frac{1}{4}$  in for  $\frac{3}{4}$ -in rivets, or  $2\frac{3}{8}$  in for  $\frac{7}{8}$ -in rivets, in a straight line.

(7) The rivets used should be  $\frac{3}{4}$  in in diameter for plates from  $\frac{3}{8}$  to  $\frac{1}{2}$  in thick, and  $\frac{7}{8}$  in in diameter for plates of greater thickness.

(8) The distance between the edge of any piece and the center of a rivet hole must never be less than  $1\frac{1}{4}$  in.

(9) In **PUNCHING** plates or other members, the diameter of the die shall in no case exceed the diameter of the punch by more than  $\frac{1}{16}$  in.

(10) All **RIVET-HOLES** must be so accurately punched that when the several parts forming one member are assembled, a rivet,  $\frac{1}{16}$  in less in diameter than the hole, can be inserted, hot, into any hole without **REAMING** or stressing the metal by the use of drift-pins.

(11) The rivets when driven must completely fill the holes.

(12) The **RIVET-HEADS** must be hemispherical, except where flush surfaces are required, and of uniform size throughout for rivets of the same size. They must be full and neatly made, and be concentric with the rivet-holes.

\* These requirements are taken largely from Birkmire's "Compound Riveted Girders".

- (13) Whenever possible, all rivets must be MACHINE-DRIVEN.
- (14) The several pieces forming one built member must fit closely together, and, when riveted, must be free from twists, bends or open joints.
- (15) Girders 60 ft and less in length seldom require SPLICING, as the plates and angles can readily be obtained in such lengths. In splicing the top flange, even of two or more thicknesses, no additional COVER-PLATE will be required at the joint, but the ends should be planed true and butt closely. The rivets should be spaced closer near the joint.
- (16) The plate covering the bottom flange must be of the same area as the flanges joined, and of sufficient length to take a number of rivets equal to the length of the cover-plate.

### 3. Design of Plate and Box Girders

**The Principal Steps in the Design of Riveted Girders.** In designing a riveted girder to sustain safely a given load, the following steps are necessary:

- (1) The determination of the required flange-area.
- (2) The determination of the thickness of the web to resist
  - (a) Shearing.
  - (b) Buckling. This step also determines if stiffeners are necessary.
- (3) The determination of the number and pitch of the rivets.
- (4) The approximate weight of the girder.
- (5) The determination of the length of the flange-plates when more than one is required for each flange.

(1) **The Flange-Area.** In determining the FLANGE-AREA of riveted girders, it is customary to assume that the bending moments are entirely resisted by the upper and lower flanges, the web being assumed to resist the shear only. Just what should be included in the flange-area is a question on which engineers differ. Some include the flange-plates and angles and one-sixth of the web-area, others include the flange-plates and angles only, while others include the flange-plates and only the horizontal legs of the angles, the vertical legs being considered as belonging to the web. In compression-flanges, usually the upper ones, the gross section-area may be taken, provided the rivets are machine-driven and fill completely the holes; but in tension-flanges, usually the lower ones, the net area is taken, that is, the gross area minus the area of the greatest number of rivet-holes in any cross-section, since the stresses of tension are not transmitted through the rivets as are those of compression.

A general FORMULA\* FOR DETERMINING THE FLANGE-AREA, which applies to all conditions of loading is

$$\text{Area of one flange in square inches} = \frac{\text{maximum bending moment in foot-tons}}{\text{depth of web in feet} \times \text{safe unit fiber-stress in tons}}$$

$$A = M_{\max}/dS \quad (1)$$

\* This may be derived from what is sometimes called the PLATE-GIRDER FORMULA,  $M = SAd$ , in which  $S$  is the safe unit bending-stress in the flange at the section of maximum bending moment,  $A$  is the area of the cross-section of either flange and  $d$  is approximately the depth of the girder. Of course the units must be the same in both members of the equation. If the center of moments is taken at the center of gravity of the cross-section of either flange-area and if the area of metal resisting bending is considered as concentrated in the flanges, the depth of each being very small compared to that of the girder-depth, then  $SA$  is the total horizontal stress in either flange,  $d$  its lever-arm and  $SAd$  the resisting moment of the cross-section, equal to  $M_{\max}$ . Hence  $A = M_{\max}/dS$ . Another method uses the section-modulus,  $I/c = M/S$ , in determining the flange-areas and proportioning the girder. (See pages 706 to 716.)

Rules for finding the **MAXIMUM BENDING MOMENT** for different conditions loading are given in Chapter IX.

$S$ , the **SAFE UNIT FIBER-STRESS FOR FLANGE-BENDING**, was formerly taken from 13 000 to 16 000 lb per sq in, the tables in the manufacturers' handbooks giving the safe loads, etc., for riveted girders, varying in regard to this stress.\*

If it is required to compute the **SAFE UNIFORMLY DISTRIBUTED LOAD** for girder already constructed or designed, the following formula † may be used. The safe load in pounds, uniformly distributed is

$$W = \frac{8 \times \text{net area of bottom flange} \times \text{depth in ft} \times S}{\text{span in feet}}$$

or

$$W = 8 AdS/l$$

From the result the weight of the girder itself should be subtracted.

For the **SAFE CONCENTRATED LOAD AT THE MIDDLE OF THE SPAN** take one-half the result obtained by formula (2) and subtract the weight of girder. (Case IV, page 326.)

(2) **The Thickness of the Web.** The thickness of the web is determined by its resistance to **VERTICAL SHEARING**. Whether or not stiffeners shall be used is determined by the resistance of the web to **BUCKLING**.

(a) **Shearing.** To resist the vertical shear the **NET SECTIONAL AREA OF WEB** in square inches must be

$$A = \frac{\text{the maximum vertical shear}}{S}$$

or

$$A = V_{\max}/S$$

$V$  and  $S$  being both in tons,  $S$  is taken at 10 000 ‡ lb or 5 tons per sq in. Table II, page 703.)

The **MAXIMUM VERTICAL SHEAR** in any beam or girder is at the greater reaction and is equal to it.

For a girder supported at both ends and uniformly loaded with a load  $W$ , the **MAXIMUM VERTICAL SHEAR** is

$$V_{\max} = W/2$$

For a girder supported at both ends and loaded at the middle with a load  $P$ ,

$$V_{\max} = P/2$$

For a girder supported at both ends and loaded as in Fig. 7,

$$V_{\max} = Pm/l = R_1$$

For a girder supported at both ends and loaded with two equal concentrated loads  $P, P$ , equally distant from the middle, as in Fig. 8,

$$V_{\max} = P = R_1 = R_2$$






For combinations of loads the maximum vertical shear will equal the greater reaction. The method of determining the **REACTIONS** at the supports of a beam or girder is given in Chapter IX, Subdivision 1. The **VERTICAL SHEAR**

\* See Chapter XV, paragraphs relating to riveted single and double-beam girders, foot-note with same, pages 603 and 604; also page 704. The value in most cities is now 16 000 lb per sq in.

† From Formula (1) just explained, and from Case V, page 326,  $M_{\max} = SAd$  and  $M_{\max} = Wl/8$ . Hence  $Wl/8 = SAd$  and  $W = 8 AdS/l$ .

‡ This is a conservative value. The Carnegie Pocket Companion and the building laws of most cities permit 10 000 lb per sq in for steel.

At any given vertical section of a beam or girder between the supports is the algebraic sum of all the vertical external forces acting on the beam to the



Figs. 5 to 9. Diagrams for Vertical Shears for Different Loadings

of that section, forces acting upwards being considered as plus, and those acting downwards being considered as minus.

Thus, in the case of the beam shown in Fig. 9, the REACTION  $R_1$  will be found by the method explained in Example 2, page 323, and by Formulas (2)

and (3), page 323, to be 150 lb, and that at  $R_2$  to be 140 lb. The shear at various sections may be found by applying the foregoing definition of VERTICAL SHEAR, thus:

Shear at  $X = +150 - 50 = +100$  lb

Shear at  $Y = +150 - 50 - 80 = +20$  lb

Shear at  $Z = +150 - 50 - 80 - 100 = -80$  lb

Shear at  $O = +150 - 50 - 80 - 100 - 60 = -140$  lb

The manner in which the VERTICAL SHEAR varies between the supports, in different dispositions of the loads, is shown graphically by the hatched areas Figs. 5 to 9; in the first three cases  $W$  and  $P$  are assumed to have the same value.

When the load is UNIFORMLY DISTRIBUTED the VERTICAL SHEAR can be found graphically by laying off vertically  $R_1$  and  $R_2$  to a scale of pounds, and drawing the line  $ab$ , Fig. 5. The shear at  $X$  will then be represented by the ordinate  $X_1$  and the shear at  $Y$  by  $Y_1$ , and they can readily be scaled.

(b) Buckling.\* The safe resistance of the web to BUCKLING, in pounds per square inch, may be determined by the formula

$$S_b = \frac{10\,000}{1 + \frac{d^2}{3\,000\,t^2}}$$

in which  $S_b$  is the safe buckling value in pounds per square inch,  $d$  is the depth of the web in the clear between flange-plates in inches and  $t$  is the thickness of the web in inches. When this resistance is less than the UNIT STRESS VERTICAL SHEAR at any section, stiffeners must be used.

**Stiffeners.** These should be made of ANGLES, not less than  $3\frac{1}{2}$  by  $3\frac{1}{2}$  inches in size. They should always be tightly fitted between the flange-angle

as to support the horizontal flanges. In order to bring the stiffeners in contact with the web and the vertical leg of the angle, FILLERS, of the same thickness as the flange-angles, are generally used, as shown in Fig. 10. Where there are several girders exactly alike, something may be saved by omitting the fillers and BENDING THE STIFFENERS, as shown in Fig. 11. This bending, however, can be done properly, by the use of special dies, and costs less than the fillers unless there are many stiffeners. The SPACING OF STIFFENERS is more a matter of judgment and experience than of exact calculation. SHEAR-DIAGRAMS

Fig. 10. Stiffeners with Fillers

Fig. 11. Bent Stiffeners

shown in Figs. 5 to 9, are of great assistance in visualizing shearing-stress. The general rule is to place the stiffeners not farther apart than the depth of the full web-plate on girders over 3 ft in depth, with a maximum spacing of 3 ft. On girders under 3 ft in depth they are placed 3 ft apart. Girders 2 ft and under in depth require no stiffeners. On girders supporting distributed loads the stiffeners are generally placed nearer together at the ends than towards the middle.

\* See Table III, page 705, and also in Chapter XV, the paragraphs and footnotes on pages 567 to 569, relating to the web-buckling of beams and girders. The formula used for web-buckling in Table III, page 705, is the formula that was used in the American Steel Company's Manual, and as the values computed by it vary but little from those deduced by the Cambria formula (see page 568), Table III is retained as it is.



Stiffeners should always be placed at the ends of girders and directly over the edge of each support, as shown in Fig. 18, and wherever there are concentrated loads. On plate girders the stiffeners are always placed on each side of the web; on box girders on the outside only.

**The Bearing of Girders.** This depends somewhat upon the character of the loading, but a safe general rule is to make the BEARING of the girder beyond the edge of the support equal to ONE-HALF THE DEPTH OF THE GIRDER.

**(8) The Number and Pitch of the Rivets.** (a) **Rivets in Web-Legs of Angles.** It will readily be seen that when a plate or a box girder is loaded, the tendency of the bending moments is to cause the flange-plates and angles to SLIDE HORIZONTALLY past the web; this tendency is resisted by the rivets which connect the angles with the web. The TOTAL AMOUNT OF THIS TENDENCY TO SLIDE, called the HORIZONTAL FLANGE-STRESS, between any section of the flange and the nearer end of the girder, is equal to the BENDING MOMENT at that point DIVIDED BY THE DEPTH OF THE WEB.\* The TOTAL NUMBER OF RIVETS between that section and the nearer end must be such that their combined resistance to SHEARING or BEARING, whichever has the lower value, shall equal this horizontal flange-stress at the section; or

$$\text{number of rivets} = \frac{\text{horizontal flange-stress}}{\text{bearing or shearing of one rivet}} \quad (5)$$

and the total number of rivets in the web-angle from end to end is twice this, or

$$\text{total number of rivets} = \frac{2 \times \text{maximum bending moment}^\dagger \text{ in foot-pounds}}{\text{depth of web in feet} \times \text{least resistance of one rivet}} \quad (6)$$

If the NUMBER OF RIVETS determined by formula (6) is such that they would be more than 6 in apart, then the number must be increased, as in no case should they have a greater PITCH than 6 in.

(b) **Rivets in Flange-Legs of Angles.** WITH A SINGLE COVER-PLATE. For girders with a single cover-plate, it is customary to put the same number of rivets in the flange-leg as in the web-leg for a distance of 3 ft from the ends of the girder, STAGGERING the rivets as in Fig. 15. Beyond that point to the middle of the girder one-half the number of rivets will be sufficient, provided this will not give them a greater pitch than 6 in.

WITH TWO OR MORE COVER-PLATES. When two or more cover-plates are used, each plate must have sufficient rivets between the end of the plate and the point where its resistance is required, that is, for example, between  $a$  and  $b$ , Fig. 13, to transfer to the angle and flange-plates between, an amount EQUAL TO THE SAFE STRENGTH OF THE PLATE. From this point to the middle point of the girder, the rivets can be spaced according to the rule for the greatest pitch.

(c) **Rivets in Stiffeners.** The spacing of rivets in the stiffeners is generally determined by the rules given for the pitch of rivets. Further explanation of the method of determining the spacing of rivets will be found in the following examples.

**(4) The Approximate Weight of the Girder.** In determining the size of riveted girder to support a given load, it is desirable to be able to add to the

\* See Formula (1), page 683, and foot-note relating to it.  $M = SAd$ , and hence  $A = M/d$ ,  $SA$  being the total amount, in pounds, of the tendency to slide, and  $S$  being the horizontal unit, flange, fiber-stress in pounds per square in, due to flexure.  $A$  is the area in square inches of the cross-section of the flange and  $d$  is the approximate depth of the girder.

† Because the maximum horizontal flange-stress is equal to the maximum bending moment divided by the girder-depth, or  $S_{\max}A = M_{\max}/d$ .

superimposed load the WEIGHT OF THE GIRDER itself, as this often forms a considerable part of the load to be supported. The following empirical rule often used to determine the approximate weight of a plate or box girder:

$$\text{Weight of girder between supports, in tons} = Wl/700$$

in which  $W$  equals the load to be supported, in tons, and  $l$  equals the span in feet. The constant 700 was determined for girders of from 35 to 50 ft long, may be used without much excess for girders of shorter spans.

(5) **The Determination of the Lengths of the Flange-Plates.** For methods used to determine these, see the following examples.

#### 4. Explanation of Tables

The Calculations for the Design of Riveted Girders may be greatly facilitated by the use of Tables I, II, III and IV at the end of this chapter.

Table I gives the sectional area that should be deducted for rivet-holes in plates of different thicknesses. In computing this table  $\frac{1}{8}$  in was added to the diameter of the rivet to allow for the injury to the metal caused by punching and also to allow for the expansion of the heated rivet.

Table II gives the safe shearing value for web-plates for various depths and thicknesses, and the deduction to be made for each  $\frac{3}{4}$ -in or  $\frac{7}{8}$ -in rivet.

Table III gives the safe resistance to buckling per square inch of net section and also the total safe resistance in pounds for the more common sizes of plates, with two rivet-holes deducted. It is very seldom that any vertical stiffener between the stiffeners contains more than two rivet-holes. Tables giving the dimensions and properties of angles will be found in Tables XI and XII, pages 362 to 367, and the shearing value and bearing values of rivets are given in Tables II and III, pages 418 and 419.

Table IV gives the elements of riveted plate girders of various depths, which it is possible to select economical sections for almost any ordinary condition of loading.

#### 5. Examples of Plate and Box Girders

**Example 1.** It is required to support the floor over a room 50 by 60 ft by means of riveted steel plate girders, placed across the room, 16 ft on center. The room above is to be used for general assembly purposes. The floor is of wood and there is a plaster ceiling on the under side of them. The weight of the girder is required.

**First Step. The Load.** The first step is to determine the load to be supported by each girder. The floor-area supported by each girder is 50 by 16 ft, or 800 sq ft. The weight of the floor-construction between the girders will not exceed 25 lb per sq ft, and an allowance of 100 lb per sq ft for the live load is ample. The unit load,  $125 \text{ lb} \times 800 = 100\,000 \text{ lb}$ , or 50 tons, the load carried by the girder. To this should be added the weight of the girder. Substituting in Formula (7),

the approximate weight of the girder =  $\frac{50 \times 50}{700} = 3.57 \text{ tons}$ , or about 7 tons, and the total load, in round numbers, is 107 000 lb. This, of course, is uniformly distributed.

\* From "Compound Riveted Girders," by W. H. Birkmire.

**Second Step. The Flange-Area.** The next step is to determine the flange-area. Before this can be done, however, the width and depth of the girder must be decided. As it is desirable to keep the girder as shallow as possible, consistent with good engineering, the case will be considered an exceptional one and the depth of the web-plate will be made 36 in. which is about one-twentieth the span and a little less than the usual limit.

As the girders are braced sidewise by the floor-joists, it will not be necessary to make the width of the flange-plates one-twentieth the span of the girder, and it may be made 12 in width. The flange-area may be determined by formula (1), page 683, and is

$$A = M_{\max}/dS$$

$$\text{flange-area (sq in)} = \frac{\text{maximum bending moment (ft-tons)}}{\text{depth of web (ft)} \times S \text{ (tons per sq in)}}$$

The maximum bending moment for a uniformly distributed load on a simple span is  $M_{\max} = Wl/8$  (Case V, page 326), or in this particular case,  $53.57 \times 50 \text{ ft}/8 = 334.8 \text{ ft-tons}$ .

The value of  $S^*$  has varied in the handbooks from 6 to 8 tons, depending on varying conditions and upon the judgment of engineers. A value of  $S$  of 8 tons or 16 000 lb per sq in is the requirement of the new New York Building Code, and of the codes of most cities. In this example 14 000 lb per sq in is assumed for  $S$ .

Substituting this value in the formula gives for the net area of either flange,  $334.8/(3 \times 7) = 16 \text{ sq in}$ .

The upper flange may now be designed. For a girder of this size and loaded in this way, it will be advisable to try two 5 by  $3\frac{1}{2}$  by  $\frac{7}{16}$ -in angles, with the legs horizontal.† The sectional area of these angles (Table XI, page 363) is 10.6 sq in which leaves 9 sq in for the area of the flange-plates. Dividing this by 12-in, the width of the flange, gives  $\frac{3}{4}$  in for the total thickness of the plates, which may be made up of two  $\frac{3}{8}$ -in thick plates. Of course, any other combination of plates and angles having an area of cross-section of 16 sq in will fulfill the conditions of the problem, the selection in all cases depending upon the judgment and experience of the designer. Note, also, that no part of the web has been included in the flange-area although it would be safe to include one-third of it. This also is a matter of individual opinion.

Since the lower flange is in tension, the rivet-holes should be deducted in order to obtain the net area. Assuming that  $\frac{3}{4}$ -in diameter rivets are used, it will be noted that the greatest loss of section is by two rivet-holes opposite each other connecting the angles with the plates of the bottom flange. From Table I, page 102, the area of two  $\frac{3}{4}$ -in rivets in a  $\frac{3}{4}$ -in plate is 1.31 sq in, and in a  $\frac{1}{2}$ -in plate, the same thickness as that of the angles, it is 0.76 sq in. The sum of these thicknesses is 2.07 sq in, which must be added to the net area of the flange-plates, 16 sq in, making 18.07 sq in for the gross area of the lower

flange. See, in Chapter XV, paragraphs and foot-notes, page 603, relating to fiber-stresses in riveted beam girders, etc.

For the flange-angles of plate girders the 5 by  $3\frac{1}{2}$ -in size is most commonly used, and the flange-plate is 12 in wide, and 6 by 4-in angles when the flange-plate is over 12 in wide. For box girders 5 by 4, 5 by  $3\frac{1}{2}$ , 4 by  $3\frac{1}{2}$  and  $3\frac{1}{2}$  by  $3\frac{1}{2}$ -in are common sizes; and for very heavily loaded girders, requiring two rows of rivets in the web-leg, 6 by 4-in angles are often used. For most riveted girders, in which only one row of rivets is used, the short leg is riveted to the web, so as to bring most of the material as far from the neutral axis of the girder as possible. The minimum thickness of flange-angles is  $\frac{3}{8}$  in, and the maximum thickness for ordinary loads is  $\frac{3}{4}$  in.

flange-plates. This additional area may be obtained by increasing the thickness of the plates to  $\frac{1}{4}$  in.

The flanges will then be made up as follows:

Upper flange: Two angles 5 by $3\frac{1}{2}$ by $\frac{3}{16}$ -in	= 7.06 sq in. gross area
Two plates 12 by $\frac{1}{4}$ -in	= 9.00 sq in. gross area
Total	16.06 sq in. gross area
Lower flange: Two angles, 5 by $3\frac{1}{2}$ by $\frac{3}{16}$ -in	= 7.06 sq in. gross area
Two plates, 12 by $\frac{1}{4}$ -in	= 12.00 sq in. gross area
Total	19.06 sq in. gross area

**Third Step. The Length of the Flange-Plates.** To determine this it is necessary to plot the bending-moment diagram shown in Fig. 12. The bending




Fig. 12. Diagrams for Bending Moments and Vertical Shears. Example 2

moment diagram for a girder under a uniformly distributed load is bounded by a parabola having a height over the middle of the girder equal to the maximum bending moment. From the middle point  $C$ , of a horizontal line  $AB$ , at a convenient scale, lay off a vertical line  $CD$ , equal to the maximum bending moment, 334.8 ft.-tons. Construct the parabola  $ADB$  (see page 79); then the bending moment at any other point, as  $E$ , is equal to the ordinate  $EF$  at that point, measured to the same scale.

To find the theoretical length of the flange-plates of the lower flange, inclose the bending-moment diagram in a rectangle and from any convenient point, such as *C*, lay off any line *CG*, equal to the total flange-area, 19 units in length, and at such an angle that the upper end *G* will lie on a horizontal line drawn through *D*. Divide the line *CG* into three parts, *CH* representing the sectional area of the angles, equal to 7 units, and *HI* and *IG* representing the sectional area of the two plates, equal to 6 units each. Draw horizontal lines through *H* and *I*; then the line *JJ* will represent the theoretical required length of the second or upper flange-plate and the line *KK* the length of the first or lower flange-plate. In practice, however, the plates are usually extended beyond the points *J* and *K* on each side as an additional factor of safety, a distance sufficient to take enough rivets to transmit at least one-third the resistance of the plate. It is also customary to make the first or lower flange-plate the full length of the girder as it greatly stiffens the angles and adds but a small amount to the cost. Theoretically the length of the flange-plates of the top flange would be less than the length of the plates of the lower flange, because the flange-area of the top flange is less than that of the lower flange; but they are usually made the same length.

**Fourth Step. The Web.** Webs are proportioned to resist the shear. The maximum shearing-stress in a girder uniformly loaded is equal to either reaction, which in this case is one-half the total load, or 53 500 lb. As the girder is 3 ft deep, this small shear would require a very thin section, thinner than the minimum thickness for webs, which is  $\frac{3}{4}$  in. From Table II, page 703, it is seen that the shearing resistance of a  $\frac{3}{4}$  by 36-in web-plate is 135 000 lb, which is greatly in excess of the actual shear.

**Fifth Step. The Stiffeners.** As before explained, stiffeners will be required whenever the vertical shear exceeds the safe resistance of the web to buckling. The vertical shear is 53 500 lb and the resistance to buckling may be found from Table III, page 705. This, for a  $\frac{3}{4}$  by 36-in web with two  $\frac{3}{4}$ -in rivets is found to be 31 560 lb; hence stiffeners will have to be used. As stated under Buckling of Web, page 686, the spacing of stiffeners is more a matter of judgment and experience than of exact calculation, and for this a shear-diagram, also shown in Fig. 12, is of great assistance. It may be constructed as follows: On a horizontal line *LM*, lay off to any convenient scale vertical lines *LN* and *MP*, each representing 53 500 lb. Connect the points *N* and *P*; then the vertical shear at any point is equal to the ordinate at that point, measured to the same scale. Thus, at *X*<sub>1</sub>, 3 ft from the left end, the shear is 47 500 lb, at *X*<sub>2</sub>, 6 ft from *L*, it is 40 500 lb, at *X*<sub>3</sub>, 9 ft from *L*, it is 34 000 lb and at *X*<sub>4</sub>, 12 ft from *L*, it is 27 500 lb. As the vertical shear at *X*<sub>3</sub> is greater than the safe resistance to buckling and at *X*<sub>4</sub> less, it might be safe to stop the stiffeners at *X*<sub>4</sub>; but as the floor-joists are framed flush, or nearly so, with the top of the girder, and rest upon angles riveted to its web, it will be advisable to put about 3 stiffeners between *X*<sub>4</sub> and the corresponding point on the right-hand half of the girder. Additional stiffeners should be placed directly over each support, making 15 stiffeners on each side of the girder. These will be made of 4 by 4  $\frac{3}{4}$ -in angles.

**Sixth Step. The Number and Pitch of the Rivets.** First, the number of rivets in the web will be considered. As a rivet is required at the end of each stiffener, it will be necessary to determine the number and spacing of the rivets between each pair of adjacent stiffeners. In the web, the rivets are in double row. In Tables II and III, pages 418 and 419, values are given based upon shearing values of 7 500 and 10 000 and bearing values of 15 000 and 20 000 lb per sq in. (See foot-notes with these tables.) The shearing resistance

of a  $\frac{3}{4}$ -in rivet at 10 000\* lb per sq in is  $4\,420 \times 2 = 8\,840$  lb for double shear and the bearing value of the same rivet in a  $\frac{3}{4}$ -in plate, at 20 000\* lb per sq in is 5 630 lb. As the bearing value is the smaller, it will determine the number of rivets required.

The number of rivets from either end of the girder to any point depends upon the horizontal flange-stress at that point, and it has been shown that the flange stress is equal to the bending moment divided by the depth of the web. (Foot-notes with Equations (5) and (6).) Scaling off the bending moment at the point  $X_1$  gives 75 ft-tons; hence the horizontal flange-stress is equal to  $75/3 = 25$  tons = 50 000 lb. The number of rivets required between this point and left reaction is, from Formula (5), equal to  $50\,000/5\,630 = 10$  rivets, which are to be spaced in a distance of 36 in, making the spacing 3.6 in. Above  $X_2$  the bending moment scales 141.24 ft-tons, the flange-stress is  $141.24/3 = 47.08$  tons or 94 160 lb, and the number of rivets required between  $X_2$  and  $A$  is  $94\,160/5\,630 = 17$ ; but 10 of these are required between  $X_1$  and  $A$ , leaving 7 to be placed between  $X_1$  and  $X_2$  in a distance of 36 in making the spacing 5.1 in. At  $X_3$  the bending moment scales 197.4 ft-tons, and the flange-stress is  $197.4/3 = 65.8$  tons or 130 600 lb. The number of rivets required is  $130\,600/5\,630 = 24$ , but 17 of these are required between  $X_2$  and  $A$ , leaving 7 to be placed between  $X_2$  and  $X_3$ , making the spacing the same as in the second panel. At  $X_4$  the bending moment scales 243.96 ft-tons, and the flange-stress is  $243.96/3 = 81.32$  tons or 162 640 lb. The number of rivets required is  $162\,640/5\,630 = 30$ , but 24 of these are required between  $X_3$  and  $A$ , leaving 6 to be placed between  $X_3$  and  $X_4$  in a distance of 36 in, making the spacing 6 in. As this is the maximum spacing allowed, it will be used from  $X_4$  to the corresponding point on the opposite right-hand half of the girder. The same number of rivets will be used in the flange-legs of the angles as in the web-legs, but they will be spaced so that they will come between those in the web.

The outer flange-plate scales 28 ft 6 in in length in the bending-moment diagram, but this length, as before stated, should be increased sufficiently to allow enough rivets to transmit at least one-third of the resistance. The area of the plate is  $\frac{1}{2}$  in  $\times$  12 in = 6 sq in, minus the area of two  $\frac{3}{4}$ -in rivet-holes, 0.8 sq in (Table I, page 702), leaving a net area of 5.13 sq in. The resistance of the plate is therefore equal to 5.13 sq in  $\times$  14 000 lb per sq in = 71 820 lb. One-third of this, or 23 940 lb, must be transferred by rivets placed beyond points  $JJ$ . As the rivets in the flange are in single shear, the shearing value of one rivet in single shear, 4 420 lb, will govern. The number of rivets required, then, is  $23\,940/4\,420 = 6$ , or 3 in each angle. The spacing of the rivets in this panel is 6 in. The plates will therefore be extended 18 in on either side of  $JJ$ .

\* The shearing value of rivets is taken at from 7 000 to 12 000 lb per sq in and the bearing value at from 12 000 to 24 000 lb per sq in. The usual values are 10 000 lb for shear and 20 000 or 24 000 lb for bearing. Values of 12 000 lb for shear and 24 000 lb for bearing are the requirements of the New York Building Code. A bearing value other than those of Tables II and III, pages 418 and 419 is purposely used in this example as it is frequently necessary to use different unit stresses than those from which a particular table has been computed. If no other table is at hand for the values based on some particular rivet bearing-stress, Tables II and III, pages 418 and 419, may be used and the new value found by proportion; or the bearing-stress may be found by multiplying the product of the diameter of the rivet and the thickness of the web by the new unit stress. In this example, Table III, page 419, gives, for 18 000 unit stress, 5 060 lb for bearing;  $\frac{106}{180}$  of this gives 5 630 lb for a 20 000 unit stress. Also,  $\frac{3}{8}$  in  $\times$   $\frac{3}{4}$  in  $\times$  20 000 lb per sq in = 5 630 lb.

**Splices.** As the total length of the girder is but 53 ft, it will not be necessary to splice the webs or the flanges, because the extreme length of a  $\frac{3}{8}$  by 36-in plate is 110 ft and of a 12 by  $\frac{1}{2}$ -in plate, 90 ft.\* It is never necessary to splice angles as they are rolled in lengths up to 90 ft. In very long, deep girders, however, it is sometimes necessary to splice the web, and the joint is sometimes made at the middle, as theoretically there is no vertical shearing-stress in the web

Fig. 13. Splicing of Inner Plate of Bottom Flange of Plate Girder. Example 1

at that point when the load is uniformly distributed. Generally, however, the web is spliced in two places, equidistant from the middle of the girder. The splice is calculated for vertical shear only, the rule being to divide the shear at the splice by the safe shearing value or bearing value of one rivet. This gives the number of rivets required on each side of the splice-plate, unless the minimum pitch is exceeded, when more are added.




Fig. 14. Plan of Splice-plate. Example 1

Whenever a splice is required in a flange-plate, it should be, if possible, at a point just beyond the end of the plate above it. The joint must be made by setting to the spliced plate, a plate of the same thickness and of sufficient length to receive a number of rivets on each side of the joint equal to the strength of the plate that is spliced. When the flange is made up of two plates of the same thickness, the simplest method of splicing the inner plate is as shown in Fig. 13.

Let  $x$  denote the theoretical position of the end of the outer plate, as determined from the bending-moment diagram, and  $a$  the point to which the plate must be extended to receive rivets of a resistance equal to one-third the strength of the flange. Then let the joint in the inner plate be just over  $a$  and extend the inner plate to  $b$ , or such a distance that it can receive a number of rivets equal in resistance to the strength of one plate.

\* Tables of extreme lengths are published in the various handbooks. The above dimensions, for example, are taken from the table on page 111 of Carnegie's Pocket Companion.

Fig. 15 shows one end of the girder, drawn according to the foregoing calculations.

**The Bill of Quantities for the Girder.** The following is a bill of quantities for the construction of this girder.

Load: 100 000 lb, uniformly distributed. Span 50 ft  
Depth 3 ft

Upper flange:

Two angles, 5 by 3½ by ¾ in, 53 ft long

One plate, 12 by ¾ in, 5 ft 0 in long

One plate, 12 by ¾ in, 3 ft 6 in long

Lower flange:

Two angles, 5 by 3½ by ¾ in, 53 ft long

One plate, 12 by ¾ in, 5 ft 0 in long

One plate, 12 by ¾ in, 3 ft 6 in long

Web:

One plate, 36 by ¾ in, 5 ft 0 in long

30 stiffeners, 4 by 4 by ¾-in angles, 2 ft 11 in long

30 filler-plates, 4 by ¾ in 29 in long

92 ft 8 in of 4 by 4 by ¾-in angles for supporting floor-joists

Rivets:

¾ in in diameter

**Example 2.** The wall shown in Fig. 16 is to be supported by a riveted-steel box girder at the height indicated. It is required to design the girder.

Fig. 16. Box Girder Supporting Brick Wall.  
Example 2

**First Step. The Load.** The first step towards designing the girder is the determination of the load. The space under the lower windows is too small to distribute the weight from the piers uniformly over the girder, so that the only assumption is that the weight of the wall between the lines *A* and *B* is concentrated at *P*<sub>1</sub>, the weight of wall between lines *B* and *C* at *P*<sub>2</sub>, and so on. The floor-joists run across the building, so that only the weight of the wall will be supported by the girder. Allowing 200 lb per square foot of face for the 21-wall, and 165 lb for the 17-in wall, both walls being plastered on the inside:

Load at *P*<sub>1</sub>

$$= \left\{ \begin{array}{l} [5' 3'' \times 10' - 7' \times 2' 3''] \times 200 = \dots\dots\dots 7\,350 \\ [5' 3'' \times 40' - (2' 3'' \times 14' + 3' 2'' \times 7')] \times 165 = \dots\dots 25\,795 \end{array} \right\} = 33\,145$$



and at  $P_2$

$$\left\{ \begin{aligned} [7' 4'' \times 10' - 4' 6'' \times 7' 0''] \times 200 &= \dots\dots\dots 8\,366 \\ [7' 4'' \times 40' - (4' 6'' \times 14' + 4' 9'' \times 7')] \times 165 &= \dots\dots\dots 32\,354 \end{aligned} \right\} = 40\,720 \text{ lb}$$

and at  $P_3$  = that at  $P_2$  =  $\dots\dots\dots 40\,720 \text{ lb}$

and at  $P_4$

$$\left\{ \begin{aligned} [4' 11'' \times 10' - 2' 3'' \times 7'] \times 200 &= \dots\dots\dots 6\,683 \\ [4' 11'' \times 40' - (2' 3'' \times 14' + 3' 2'' \times 7')] \times 165 &= \dots\dots\dots 23\,595 \end{aligned} \right\} = 30\,278 \text{ lb}$$

Total load on girder =  $\dots\dots\dots 144\,863 \text{ lb}$

72.4 tons

Equation (7)

$$\text{Approximate weight of girder} = \frac{W \times l}{700} = \frac{72.4 \times 2456}{700} = 2.5 \text{ tons, or } 5\,000 \text{ lb}$$

but one-third of this, or say 1 600 lb, should be added to  $P_2$  and  $P_3$ , and 900 lb to  $P_1$  and  $P_4$ . This will give, approximately, the following loads, applied as in Fig. 17:

$$\begin{aligned} P_1 &= 34\,000 \text{ lb} & P_2 &= 42\,300 \text{ lb} \\ P_3 &= 42\,300 \text{ lb} & P_4 &= 31\,200 \text{ lb} \end{aligned}$$




Fig. 17. Diagram for Bending Moments. Example 2

**Second Step. The Determination of the Maximum Bending Moment.** By use of the formula under Case VI, page 327, the maximum bending moment in foot-pounds for the loads are found to be as follows:

$$\text{For } P_1, M_{\max} = \frac{34\,000 \times 1' 6'' \times 23' 4''}{24' 10''} = 47\,980 \text{ ft-lb}$$

$$\text{For } P_2, M_{\max} = \frac{42\,300 \times 8' 11'' \times 15' 11''}{24' 10''} = 242\,000 \text{ ft-lb}$$

$$\text{For } P_3, M_{\max} = \frac{42\,300 \times 16' 3'' \times 8' 7''}{24' 10''} = 237\,900 \text{ ft-lb}$$

$$\text{For } P_4, M_{\max} = \frac{31\,200 \times 1' 4'' \times 23' 6''}{24' 10''} = 39\,420 \text{ ft-lb}$$

By bringing these moments to a scale, as explained for Fig. 15, page 329, the bending-moment diagram shown in Fig. 17\* is obtained. The maximum bend-

The bending moments in this diagram are drawn to a scale of about 400 000 ft-lb in.

ing moment is at  $P_1$ , over the longest ordinate  $bb$  and where the vertical shear is zero, and is equal to the length of the ordinate  $bb$ , which scales 418 000 lb or 209 ft-tons.

**Third Step. The Determination of the Flange-Area and the Length of Cover-Plates.** Before these can be determined, the depth of the web-plate must be decided. As there is nothing to limit the depth of the girder, it may be made about one-tenth of the span, or 30 in. Then by Formula (1), page 683,  $A = M_{\max}/dS$ , and using 14 000 lb or 7 tons per sq in for  $S$ ,

$$\text{the gross area of upper flange} = 209/2.5 \times 7 = 12 \text{ sq in}$$

As the thickness of the wall to be supported is 21 in, the flange-plate must be at least 20 in wide and not less than  $\frac{3}{8}$  in thick. The sectional area of a 20-in plate is  $7\frac{1}{2}$  sq in, leaving  $4\frac{1}{2}$  sq in to be made up by the angles. The sectional area of two 5 by  $3\frac{1}{2}$  by  $\frac{7}{16}$ -in angles is 7.06 sq in (Table I, page 363), which leaves a small excess for the lower flange. For rivets  $\frac{3}{4}$  in diameter, the loss in area due to two rivet-holes in a  $\frac{3}{8}$ -in plate is (Table I, page 702) 0.65 sq in and in a  $\frac{7}{16}$ -in plate, the thickness of each angle, 0.76 sq in, making 1.41 sq in in all, for which the excess in the angles is more than sufficient. The width of the flange being more than one-twentieth the span no lateral support unnecessary.

**Fourth Step. The Webs and Stiffeners.** The maximum shear is equal to the maximum reaction which in this case is obviously equal to the left reaction. Taking the center of moments at the right reaction, the equation of moments

$$R_1 \times 24.83' = (17 \text{ tons} \times 23.33') + (21.15 \text{ tons} \times 15.91') + (21.15 \text{ tons} \times 8.5) + (15.6 \text{ tons} \times 1.33')$$


whence  $24.83 \times R_1 = 935.3215$  ft-tons and  $R_1 = 37.669$  tons, or 75 338 lb. Note that the loads have been changed from pounds to tons, for convenience in making the calculations. As this box girder has two webs, the maximum shear on each web will be 37 669 lb. The thinnest web permissible is  $\frac{3}{8}$  in thick. From Table II, page 703, the resistance of a  $\frac{3}{8}$  by 30-in web-plate to shearing is 112 500 lb, so that the webs are amply safe in resisting vertical shear. From Table III, page 705, the safe resistance to buckling, deducting for two rivets, is 33 830 lb. As this is less than the maximum shear, stiffeners must be used, placed 2 ft 4 in from each support, with five between them, making the spacing about 3 ft 4 in on centers. Two others will be placed over each support. 4 by 4 by  $\frac{3}{8}$ -in angles will be sufficient for the stiffeners.

**Note.** If the loads were really concentrated at the points  $P_1$ ,  $P_2$ , etc., coming from columns or girders, it would be necessary to place stiffeners at each of these points and two in each of the intermediate spaces, but as the loads are partly distributed it will be better to space them as first planned.

**Fifth Step. The Number and Pitch of the Rivets.** The rivets in the flange-legs and flange-legs of the angles are in single shear. From Table III, page 419, the shearing value of a  $\frac{3}{4}$ -in rivet in single shear at 10 000 lb per sq in is 4 420 lb, and the bearing value in a  $\frac{3}{8}$ -in plate at 18 000 lb per sq in is 5 625 lb. Hence the shearing value will govern. The number of rivets required depends upon the flange-stress, which is equal to the maximum bending moment divided by the depth of the girder. (See Formula (1), page 683.) The bending moment at  $P_1$ , found by moments or graphically by scaling off the ordinates  $aa$ , Fig 17, is 56.5 ft-tons.\* This, divided by the depth 2.5 ft, gives 22.6

\* This may be found, also, by taking  $P_1$  as the center of moments and multiplying  $R_1 = 37.669$  tons by the lever-arm  $1\frac{1}{2}$  ft. The result is 56.5 ft-tons. The bending moments at the other loads may be determined by taking, in each case, the algebraic sum of the moments of the external vertical forces on either side of each point coming

22 600 lb, for the flange-stress, or 22 600 lb for each web. The number of rivets, therefore (Formula (5), page 687) is  $22\,600/4\,420 = 6$ . The distance from  $P_1$  to the left reaction is 18 in, which makes the spacing 3 in. The flange-stress at  $P_2$  is  $209.88 \text{ ft-tons}/2.5 \text{ ft} = 83.95 \text{ tons}$ , or 167 900 lb, and one-half of this is 83 950 lb. The number of rivets therefore is  $83\,950/4\,420 = 19$ . 6 of these are required between  $P_1$  and the left reaction, leaving 13 to go between  $P_1$  and  $P_2$ , a distance of 89 in, making the pitch about 6.9 in. As this exceeds the maximum allowable pitch, the rivets will be spaced 6 in on each side between  $P_1$  and  $P_2$ , and between  $P_2$  and  $P_3$ . The spacing on the right-hand end of the girder will be made the same as that on the left. Some details of the girder are shown in Fig. 18.



Girder. Example 2

**Details and Bill of Quantities for the Girder.** The loads, dimensions, size, number of pieces, etc., for the girder are given in the following summary:

Loads: 34 000 lb, 1 ft 6 in from left support. Span: 24 ft 10 in  
 42 300 lb, 8 ft 11 in from left support Depth: 30 in  
 42 300 lb, 8 ft 7 in from right support  
 31 200 lb, 1 ft 4 in from right support  
 Both flanges: Four angles, 5 by  $3\frac{1}{4}$  by  $\frac{3}{16}$  in, 27 ft 6 in long  
 One plate, 20 by  $\frac{3}{4}$  in, 27 ft 6 in long  
 Two webs:  $\frac{3}{4}$  by 30 in, 27 ft 6 in long  
 Twenty-two stiffeners: 4 by 4 by  $\frac{3}{8}$  in, 29 $\frac{1}{4}$  in long  
 Twenty-two filler-plates: 4 by  $\frac{3}{16}$  in, 23 in long  
 Rivets:  $\frac{3}{4}$  in in diameter

**Example 3.** What are the dimensions of a box girder, 40 ft in span, required to carry the following loads? 90 tons from a column, 8 ft from the left support; 75 tons from a column, 12 ft from the right support; and a masonry pier, 10 ft high, beginning 10 ft from the left support and weighing 4 tons per running ft. (See Fig. 19.)

**Solution.** **Step. The Determination of the Reactions, Shears and Bending Moments.** To find either reaction, the center of moments is taken at the other reaction. The equation of moments for the left reaction is, therefore, taking the sum of moments at the right reaction,

$$40 R_1 = (90 \text{ tons} \times 32 \text{ ft}) + (40 \text{ tons} \times 25 \text{ ft}^*) + (75 \text{ tons} \times 12 \text{ ft})$$

which

$$40 R_1 = 4\,780 \text{ ft-tons and } R_1 = 119.5 \text{ tons}$$

\*Considering the moments of forces, distributed loads are treated as if they were concentrated at their centers of gravity.

In like manner, the equation of moments for the right reaction is

$$40 R_2 = (75 \text{ tons} \times 28 \text{ ft}) + (40 \text{ tons} \times 15 \text{ ft}) + (90 \text{ tons} \times 8 \text{ ft})$$

from which

$$40 R_2 = 3420 \text{ ft-tons, and } R_2 = 85.5 \text{ tons}$$

The greatest vertical shear  $V_1$  is equal to the greater reaction, which is 119.5 tons. The shear-diagram (Fig. 19) may be constructed by laying off




Fig. 19. Elevation of Box Girder and Diagrams for Bending Moments and Shears. Example 3

any convenient scale an ordinate equal in length to 119.5 tons. From the right end of point 1, under the left column, the shear is equal to 119.5 - 29.5 tons. It is the same at point 2, the left end of the wall. At point 3, right end of the wall, the shear is 119.5 - 90 - 40 = -10.5 tons, showing that the shear passes through zero somewhere between 2 and 3, which is the point of maximum bending moment. This point, X, is found by scaling the shear diagram 17.4 ft from  $R_1$ . It is over the point of intersection of the slanting line

the shear-diagram, with the horizontal line of reference. This slanting line is drawn from the top of the shear-ordinate for point 2 to the bottom of the shear-ordinate for point 3. Just at the right of point 4, the shear is  $119.5 - 80 - 40 - 75 = -85.5$  tons, the same as the right reaction. The point  $X$ , of no shear and maximum bending moment, may be found, also, as follows: At the left of point 2 the shear is 29.5 tons. One foot to the right of 2 it is  $29.5 - 4 = 25.5$  tons. Two feet to the right of 2 it is  $29.5 - 8 = 21.5$  tons, etc. Therefore, since the shear decreases at the rate of 4 tons per foot, it will be zero at  $29.5/4$  or 7.4 ft at the right of 2, or 17.4 ft from  $R_1$ .

The maximum bending moment is at  $X$ , the point of no shear. The equation of moments, considering the forces to the left of  $X$ , is

$$M_{\max} = (119.5 \text{ tons} \times 17.4 \text{ ft}) - (90 \text{ tons} \times 9.4 \text{ ft}) - (4 \text{ tons} \times 7.4 \text{ ft} \times 7.4 \text{ ft}/2)$$

7.4 ft/2 is the distance from  $X$  to the center of gravity of the wall-load to the left of  $X$ , and is the lever-arm of that load, considered as a vertical downward force concentrated in a single line of action. Hence

$$M_{\max} = 2079.3 - 846 - 109.5 = 1123.8 \text{ ft-tons}$$

The bending-moment diagram may be constructed by laying off at  $X$ , at any convenient scale, an ordinate  $XC$  equal to 1123.8 ft-tons in length. It is necessary to find the bending moment at other points, since the bending-moment diagram cannot be plotted, as in the previous examples, because the uniform load is not distributed over the entire girder. The other critical points are 1, 3 and 4.

$$M_1 = (119.5 \text{ tons} \times 8 \text{ ft}) = 956 \text{ ft-tons}$$

$$M_3 = (119.5 \text{ tons} \times 10 \text{ ft}) - (90 \text{ tons} \times 2 \text{ ft}) = 1015 \text{ ft-tons}$$

$$M_4 = (119.5 \text{ tons} \times 20 \text{ ft}) - (90 \text{ tons} \times 12 \text{ ft}) - (40 \text{ tons} \times 5 \text{ ft}) = 1110 \text{ ft-tons}$$

$$M_4 = (119.5 \text{ tons} \times 28 \text{ ft}) - (90 \text{ tons} \times 20 \text{ ft}) - (40 \text{ tons} \times 13 \text{ ft}) = 1026 \text{ ft-tons}$$

By laying off ordinates at these points equal by scale to the respective bending moments; drawing straight lines from  $R$  to  $A$ , the extremity of the ordinate through 1, and from  $A$  to  $B$ ; drawing curved lines from  $B$  through the points through 3 and 4; and connecting  $D$  and  $E$  and  $E$  and  $R_2$  by straight lines; the bending-moment diagram  $R_1ABCDER_2$  may be constructed.

**Second Step. The Webs.** As stated on page 683, it is considered safe by many engineers to include one-sixth of the web-area in the flange-area, and this will be done in this example. The web, therefore, must be designed first. Since there is nothing to limit the depth of the girder, it will be made 3 ft. deep, or one-twelfth the span. The greatest vertical shear is equal to the greater left reaction, 119.5 tons. Since the girder carries a brick wall, it must be of box type, and hence the vertical shear on each web is 59.75 tons. A  $\frac{1}{2}$  by 3 web will be tried first. Its area is 18 sq in, from which must be deducted loss in area due to the rivet-holes for the rivets through the stiffeners. The rivets will be placed the maximum distance on centers, making six in each web. Because of the concentrated loads near the reactions more rivets will be required, and in order to avoid a close spacing,  $\frac{3}{8}$ -in rivets will be used. In Table I, page 702, the sectional area to be deducted for a  $\frac{3}{8}$ -in rivet in a  $\frac{1}{2}$ -in plate is 0.50 sq in; hence the net area of the web is  $18 - (6 \times 0.50) = 15$  sq in, and its shearing resistance, at 10 000 lb or 5 tons per sq in (Table II, page 703), is  $15 \times 5 \text{ tons} = 75 \text{ tons}$ , which is 15.25 tons in excess of the 59.75 tons required.

**Third Step. The Flange-Area.** From Formula (1), page 683,

$$\text{the flange area, } A = M_{\max}/dS = \frac{1123.8}{3 \times 7} = 53.5 \text{ sq in}$$

As the girder has no lateral support, the flange-width should be not less than twentieth the span, which will make it 2 ft.

The upper flange may be proportioned as follows:

One-sixth of net section-area of two webs = . . . . .	5.00 sq in
Two 5 by 5 by $\frac{9}{16}$ -in angles,* with section-area = . . . . .	10.62 sq in
Three $\frac{9}{16}$ by 24-in plates, with section-area of 13.50 sq in each = . . . . .	40.50 sq in
Total section-area of upper flange = . . . . .	56.12 sq in

To proportion the lower flange, allowance must be made for the loss in area due to two rivet-holes.

From Table I, page 702, the area of two $\frac{3}{8}$ -in rivet-holes in a $\frac{9}{16}$ -in plate (thickness of angles) = . . . . .	1.12 sq in
Area† of two rivet-holes in three $\frac{3}{8}$ -in flange-plates = . . . . .	3.75 sq in
Total rivet-area = . . . . .	4.87 sq in

Hence the gross section-area of the lower flange must be  $53.5 + 4.87 = 58$  sq in.

This may be made up of

One-sixth of net section-area of two webs = . . . . .	5.0 sq in
Two 5 by 5 by $\frac{9}{16}$ -in angles, with section-area = . . . . .	10.62 sq in
Three $\frac{5}{8}$ by 24-in plates, with section-area of 15 sq in each = . . . . .	45.00 sq in
Total section-area of lower flange‡ = . . . . .	60.62 sq in

The length of the flange-plates is determined from the bending-moment diagram. Draw a horizontal line through *C* (Fig. 19) and at any point, lay off to any convenient scale and angle, a line  $3H = 60.62$  units in length with its upper extremity on the horizontal line *FG* drawn through *C*. Divide this line into five parts:  $3I$ , containing 5 units for the web-area; *IJ*, 10.62 for the angles; and *JK*, *KL* and *LH* of 15 units each, for the three plates. Draw horizontal lines through the points *I*, *J*, *K* and *L* as shown. The horizontal intercepts of these horizontals in the bending-moment diagram will give the theoretical lengths of the flange-plates. For practical considerations, the plate is always carried the full length of the girder and the other plates are extended beyond the intersection-points on either side, a distance sufficient to take enough rivets to transmit at least one-third of the resistance of the plate. The resistance *AS*, of the outer plate is  $15 \text{ sq in} \times 14\,000 \text{ lb per sq in} = 210\,000$  lb. One-third of this, or 70 000 lb, must be resisted by rivets placed beyond points *AA*. From Table III, page 419, at 10 000 lb per sq in, the shear value of a  $\frac{3}{8}$ -in steel rivet in single shear is 6 010 lb and in a  $\frac{5}{8}$ -in plate its bearing value at 18 000 lb per sq in is 9 820 lb. Hence the number of rivets required is  $70\,000 / 6\,010 = 12$ , or 6 on each side. With a 2-in pitch this would lengthen the plate 12 in at each end. The outside plates in this particular girder were extended far enough to pass beyond the base of the column on the left side of the girder.

\* Angles with equal legs are selected because the same number of rivets will be required in both legs, as they are all in single shear, and large angles are selected because the rivets will have to be staggered, owing to the concentrated loads being placed at the ends of the girder.

† Since  $\frac{9}{16}$ -in plates are selected for the upper flange, it is reasonable to suppose that  $\frac{5}{8}$ -in plates will be necessary for the lower flange.

‡ Both flange-areas are made slightly in excess of the requirements, because in this example one-sixth of the web-area is included.

**Fourth Step. The Stiffeners.** From Table III, page 705, the safe buckling value of a  $\frac{1}{2}$  by 36-in plate with two  $\frac{7}{8}$ -in rivets is 62 320 lb, and as this is much less than the shearing value, stiffeners must be used. The stiffeners under the concentrated loads may be considered as short struts in direct compression. Assuming that 4 by 4 by  $\frac{1}{2}$ -in angles are used for the stiffeners, the safe load from Table XV, page 502, is over 20 tons. The greatest concentrated load is 90 tons, and hence four stiffeners will be placed under each column. Four more will be placed at each bearing, as shown in Fig. 19, four on each side, between the columns, about 4 ft on centers; and two on each side, between the columns and the bearings, making 15 on each side, or 30 in all.

**Fifth Step. The Number and Pitch of the Rivets.** In a box girder, the rivets are in single shear. The shearing value of a  $\frac{7}{8}$ -in rivet at 10 000 lb per sq in, from Table III, page 419, 6 010 lb, and its bearing value at 18 000 lb per sq in, in a  $\frac{1}{8}$ -in plate, the thinnest outside plate, is 6 880 lb; hence the shearing value will govern.

The number of rivets depends upon the horizontal flange-stress, which is equal to the maximum bending moment divided by the depth of the girder (Formula (1), page 683).  $M$  at 1 = 956 ft-tons, and the horizontal flange-stress  $= 956/3 = 319$  tons, or 638 000 lb. From Formula (5), page 687, the number of rivets required  $= 638\,000/6\,010 = 106$ , or 53 on each side. These are to be spaced in a distance of 8 ft, or 96 in, which makes the pitch about 1.8 in. As this is less than the minimum pitch,  $2\frac{1}{4}$  in, or three diameters, the rivets will have to be staggered. Hence the justification for selecting large angles with equal legs for this particular girder. At  $X$  the horizontal flange-stress  $= 123.8/3 = 374.6$  tons, or 749 200 lb, and the number of rivets is  $749\,200/6\,010 = 124$ , or 62 on each side; 53 of these, however, are required between  $R_1$  and 1, leaving 9 to be placed between 1 and  $X$ , a distance of about 9 ft. As the resulting pitch will exceed the maximum pitch, they will be placed 6 in on centers between 1 and  $X$ . At 4 the horizontal flange-stress  $= 1\,026/3 = 342$  tons, or 684 000 lb. The number of rivets is  $684\,000/6\,010 = 112$ , or 56 on each side, to be spaced in a distance of 12 ft, or 144 in, making the spacing 2.5 in. Between 4 and  $X$  the maximum pitch will be determined as before.

**Sixth Step. The Weight of the Girder.** So far, no account has been taken of the weight of the girder. The practice is to neglect this weight when the maximum bending moment due to it alone is less than 10% of the maximum bending moment due to the loads. From Formula (7), page 688, the weight of the girder  $= 205 \times 40/700 = 12$  tons. From Case V, page 326, the maximum bending moment due to it  $= 12 \times 40/3 = 60$  ft-tons. As this is much less than 10% of 123.8 ft-tons, the maximum bending moment due to the loads, it may be neglected. Had it been otherwise, the weight would have to be considered as an additional uniformly distributed load over the entire girder and a new bending-moment diagram drawn.

**Other Data on Riveted Girders.** By applying the principles illustrated in the preceding examples it is possible to compute the necessary dimensions and weights for riveted girders under any conditions of loading. If further examples are desired, the reader is referred to "Compound Riveted Girders," by William Kirkmire, in which different examples of loading are fully worked and explained, and also to other recent treatises on this subject.

**Detail Drawings and Stress-Diagrams** of one of the earlier heavy plate girders used in building-construction are published in the Engineering Record, Dec. 28, 1895. This girder is one of six plate girders used in the construction of Tremont Temple, Boston, Mass., Blackall & Newton, architects. The girder is 75 ft long between centers of columns, 6 ft 1 in deep, with flanges 28 in

wide, and is calculated to support distributed and concentrated loads aggregating 497.5 tons. The single web-plate is 64¾ in deep, and ¾ in thick at ends; the flanges are 4½ in thick at the middle of the girder; and the flange angles are 6 by 8 by 1 in. Since that time there have been erected for many the large buildings a number of riveted girders of very great size and strength and details of their construction may be found in the engineering and architectural periodicals.

6. Tables Used in the Design of Plate and Box Girders

Tables I, II, III and IV contain data usually required for the design of plate and box girders to satisfy all but the most unusual conditions.

Table I.\*† Sectional Area in Square Inches to be Deducted from Plates and Angles for Rivet-Holes

Taken ¼ inch in excess of diameter of rivet‡

Thickness of plate, in	Number of rivets, 1 in diameter				Number of rivets, ¾ in diameter			
	1	2	3	4	1	2	3	4
1	1.12	2.25	3.37	4.50	1.00	2.00	3.00	4.00
1½	1.05	2.10	3.16	4.21	0.94	1.87	2.81	3.75
¾	0.98	1.97	2.95	3.93	0.87	1.75	2.62	3.50
1¾	0.91	1.83	2.74	3.63	0.81	1.62	2.44	3.25
¾	0.84	1.69	2.53	3.37	0.75	1.50	2.25	3.00
1½	0.77	1.55	2.32	3.09	0.69	1.37	2.06	2.75
¾	0.70	1.41	2.11	2.81	0.62	1.25	1.87	2.50
9⁄16	0.63	1.26	1.90	2.53	0.56	1.12	1.69	2.25
½	0.56	1.11	1.69	2.25	0.50	1.00	1.50	2.00
7⁄16	0.49	0.98	1.47	1.97	0.44	0.87	1.31	1.75
¾	0.42	0.84	1.26	1.69	0.37	0.75	1.12	1.50
Thickness of plate, in	Number of rivets, ¾ in diameter				Number of rivets, 5⁄8 in diameter			
	1	2	3	4	1	2	3	4
1	0.87	1.75	2.62	3.50	0.75	1.50	2.25	3.00
1½	0.82	1.64	2.46	3.28	0.70	1.40	2.11	2.81
¾	0.77	1.53	2.30	3.06	0.65	1.31	1.96	2.62
1¾	0.71	1.42	2.13	2.84	0.61	1.22	1.83	2.44
¾	0.66	1.31	1.96	2.62	0.56	1.12	1.69	2.25
1½	0.60	1.20	1.80	2.40	0.51	1.03	1.54	2.06
¾	0.55	1.09	1.64	2.19	0.47	0.94	1.41	1.87
9⁄16	0.49	0.98	1.48	1.96	0.42	0.84	1.26	1.75
½	0.43	0.87	1.31	1.75	0.37	0.75	1.12	1.50
7⁄16	0.38	0.76	1.15	1.53	0.33	0.66	0.98	1.31
¾	0.32	0.65	0.98	1.31	0.28	0.56	0.84	1.12
5⁄16	0.27	0.55	0.82	1.09	0.23	0.47	0.70	0.94
¼	0.22	0.44	0.66	0.87	0.18	0.37	0.56	0.75

\* For explanation of tables, see Subdivision 4, page 688.  
† This table is taken from "Compound Riveted Girders," by W. H. Birkmire.  
‡ See paragraph, Punching Rivet-Holes, page 414, and Table XI, page 400.



**Table II.\* Safe Shearing Value of Web-Plates in Pounds**  
Mild steel. Gross area. Safe unit stress, 10 000 lb per sq in

Depth, in	Thickness in inches						
	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$
28	105 000	122 500	140 000	157 500	175 000	210 000	245 000
30	112 500	131 300	150 000	168 800	187 500	225 000	262 500
32	120 000	140 000	160 000	180 000	200 000	240 000	280 000
36	135 000	157 500	180 000	202 500	225 000	270 000	315 000
40	150 000	175 000	200 000	225 000	250 000	300 000	350 000
42	157 500	183 800	210 000	236 300	262 500	315 000	367 500
46	172 500	201 300	230 000	258 800	287 500	345 000	402 500
48	180 000	210 000	240 000	270 000	300 000	360 000	420 000
Deductions in pounds for one $\frac{3}{4}$ -in rivet†							
	3 200	3 800	4 300	4 900	5 500	6 600	7 700
Deductions in pounds for one $\frac{1}{2}$ -in rivet†							
	3 700	4 400	5 000	5 600	6 200	7 500	8 700

\* For explanation of tables, see Subdivision 4, page 688.

† The area of the hole is taken  $\frac{1}{8}$  in in excess of the diameter of the rivet to allow for loss of the metal sustained by punching.

**Example 4.** What is the safe shearing value of a 36 by  $\frac{3}{8}$ -in web-plate with seven  $\frac{3}{4}$ -in rivets in the stiffeners?

**Solution.** The gross shearing value = 135 000 lb

The deduction for seven rivets =  $7 \times 3\ 200 = 22\ 400$  lb

The safe shearing value = 112 600 lb

Use this table for any other unit stress, divide the shearing value by 10 000 and multiply by the given unit stress. For example, what is the safe shearing value of a 40 by  $\frac{5}{8}$ -in web-plate at 12 000 lb per sq in?  $(250\ 000/10) \times 12 = 300\ 000$  lb.

**Tables of Riveted Steel Plate Girders.†** It is not practicable to give TABLES OF SAFE LOADS for riveted steel plate girders because of the great variety of combinations of plates and angles that can be selected for any given condition of loading. Moreover, any variation in the loading would make the tables useless. In place of the safe loads, therefore, the PROPERTIES OR ELEMENTS OF RIVETED STEEL PLATE GIRDERS are given in Table IV, pages 706 to 716, which will aid in determining the size of the girder and the approximate thickness of plates and angles for any special case. To determine the dimensions and details of a girder suitable to carry any specified loading, determine the MAXIMUM END-REACTION in pounds and the MAXIMUM BENDING MOMENT in inch-pounds. Select from Table IV the different parts for a girder of the required TYPE, a THICKNESS OF WEB as determined by the maximum end-reaction and a suitable SECTION-MODULUS as determined by dividing the maximum bending

For tables of riveted single-beam girders and double-beam girders, see Tables XIV and XV, pages 605 to 611.

moment by the PERMISSIBLE UNIT STRESS FOR FLEXURE in pounds per sq inch. The SPACING OF THE RIVETS, the number and position of the STIFFENERS, the LENGTH OF THE FLANGE-PLATES, if more than one are needed, and the LOSS OF AREA IN FLANGE-AREA and WEB-AREA due to the punching of the RIVET-HOLES, must be determined in each case by the rules already given. The weights of rivets and stiffeners are not included.

As an illustration of the use of these elements or properties, in Example 1, the total load on the girder is 107 000 lb, making each end-reaction 53 500 lb. The maximum bending moment is 334.8 ft-tons, or 8 035 000 in-lb. The section modulus  $I/c = M/S = 8\,035\,000/14\,000 = 574$ . The depth of the girder is limited to 36 in. Looking up the properties of 36-in girders in Table IV, page 709, it is seen that a  $\frac{3}{8}$ -in web is more than sufficient to resist the reaction. The nearest section-modulus to 574 is 567.2, that of a girder composed of a 36 by  $\frac{7}{16}$ -in web, 5 by  $3\frac{1}{2}$  by  $\frac{1}{4}$ -in angles, and 12 by  $\frac{1}{4}$ -in flange-plates. In working out the problem in detail it was found that the girder required 5 by  $3\frac{1}{2}$  by  $\frac{7}{16}$ -in angles and two 12 by  $\frac{1}{4}$ -in flange-plates to compensate for the loss of area due to the punching of the rivet-holes. (See pages 719 and 710.)

Table IV is based upon an extreme fiber-stress for flexure of 16 000 lb per sq in, and gross sections are used in determining the values given. The attention of readers is called to the two methods of plate and box-girder design: (1) the one using the plate-girder formula (page 683), and (2) the one using the section modulus (pages 703 and 704, and 706 to 716). It is customary, also, to take into account the tendency of the compression-flange of the girder, if long between lateral bracings, to buckle or fail as a column; and the permissible reduced fiber stress is determined by column-formulas.

Table III.\* Safe Buckling Values of Web-Plates

SAFE UNIT BUCKLING VALUE IN POUNDS PER SQUARE INCH

$$\text{Calculated by formula } \dagger S_b = \frac{10\,000}{1 + \frac{d^2}{3\,000\,t^2}}$$

$S_b$  = safe buckling resistance in pounds per square inch;  $d$  = depth of web in the clear between flange-plates in inches;  $t$  = thickness of web in inches

Depth, in	Thickness in inches						
	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$
28	3 498	4 228	4 890	5 476	5 932	.....	.....
30	3 192	3 896	4 546	5 133	5 656	6 522	.....
32	2 889	3 624	4 228	4 787	5 339	6 226	6 920
36	2 456	3 069	3 666	4 229	4 748	5 656	6 392
40	2 087	2 696	3 191	3 724	4 228	5 133	5 882
42	1 930	2 455	2 983	3 498	3 992	4 889	5 649
48	1 548	1 994	2 543	2 918	3 371	4 228	4 992

TOTAL SAFE RESISTANCE IN POUNDS FOR PLATES WITH TWO  $\frac{3}{4}$ -IN RIVETS

Depth, in	Thickness in inches						
	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$
28	34 450	48 580	64 200	80 880	97 340	.....	.....
30	33 830	48 150	64 230	81 560	99 880	138 200	.....
36	31 560	46 000	62 800	81 500	101 750	145 300	191 570
42	29 140	43 230	60 040	79 190	100 440	147 600	198 960
48	26 860	40 360	58 820	75 920	97 450	146 670	202 000

TOTAL SAFE RESISTANCE IN POUNDS FOR PLATES WITH TWO  $\frac{7}{8}$ -IN RIVETS

Depth, in	Thickness in inches						
	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$
28	34 100	48 110	63 570	80 100	96 390	.....	.....
30	33 510	47 720	63 640	80 840	98 980	136 960	.....
36	31 310	45 660	62 320	80 900	100 690	144 230	190 170
42	28 950	42 960	59 660	78 700	99 800	146 690	197 710
48	26 700	40 140	58 490	75 520	96 910	145 860	200 930

For explanation of tables, see Subdivision 4, page 688.

See in Chapter XV the paragraphs and foot-notes, pages 568 and 569, relating to web-buckling of I-beams. The formula for the above table is the formula that was in the Passaic Steel Company's Manual, and as the values computed by it vary but slightly from those deduced by the Cambria formula, Table III is retained as it is.

See also, page 686, paragraph relating to Safe Resistance of Web to Buckling.

Table IV.\* Elements of Riveted Plate Girders

To determine the details of construction of a girder su  
able to carry any specified loading, determine the ma  
ximum end-reactions in pounds and the maximum bendi  
moment in inch-pounds

Select from the table a girder having the desired dept  
a thickness of web as determined by the maximum en  
reaction and a suitable section-modulus, determined  
dividing the maximum bending moment by the permis  
ble unit bending fiber-stress in pounds per square incl

For limiting conditions, see the pages 702 to 705 a  
the first three subdivisions of this chapter

Weights given do not include stiffeners, rivet-heads,  
other details

Section- modulus, axis, I-I, in <sup>3</sup>	Sizes			Weight per foot		Maxim end- reaction thousan of pound
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
242.0	24X3/8	5X3 1/2 X 5/8		97.8		60.8
270.9		5X3 1/2 X 3/8	12X3/8	72.2	30.6	60.8
306.1		5X3 1/2 X 3/8	12X1/2	72.2	40.8	60.8
343.6		5X3 1/2 X 1/2	12X1/2	85.0	40.8	60.8
378.5		5X3 1/2 X 1/2	12X5/8	85.0	51.0	60.8
414.1		5X3 1/2 X 5/8	12X5/8	97.8	51.0	60.8
151.5	26X5/16	4X3 X 3/8		61.6		56.
176.8		5X3 1/2 X 3/8		69.2		56.
186.6		4X3 X 1/2		72.0		56.
201.2		6X4 X 3/8		76.8		56.
219.6		5X3 1/2 X 1/2		82.0		56.
252.0		6X4 X 1/2		92.4		56.
260.7		5X3 1/2 X 5/8		94.8		56.
341.5	26X3/8	6X4 X 3/8	14X3/8	82.4	35.7	67.
354.4		6X4 X 3/4		127.6		67.
377.4		5X3 1/2 X 1/2	12X1/2	87.6	40.8	67.
386.1		6X4 X 3/8	14X1/2	82.4	47.6	67.
415.2		5X3 1/2 X 1/2	12X5/8	87.6	51.0	67.
435.1		6X4 X 1/2	14X1/2	98.0	47.6	67.
454.5		5X3 1/2 X 5/8	12X5/8	100.4	51.0	67.
479.3		6X4 X 1/2	14X5/8	98.0	59.5	67.
526.1		6X4 X 5/8	14X5/8	113.2	59.5	67.
569.9		6X4 X 5/8	14X3/4	113.2	71.4	67.
613.9		6X4 X 3/4	14X3/4	127.6	71.4	67.
200.4	26X7/16	4X3 X 1/2		83.1		78.
233.4		4X3 X 5/8		93.1		78.
233.5		5X3 1/2 X 1/2		93.1		78.
265.8		6X4 X 1/2		103.5		78.
274.5		5X3 1/2 X 5/8		105.9		78.
314.8		6X4 X 5/8		118.7		78.

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa. Some  
tional values are given in the Pocket Companion.

# Tables Used in the Design of Plate and Box Girde

**Table IV \*† (Continued). Elements of Riveted Plate Girde**

Section-modulus, and I-I, in <sup>3</sup>	Sizes			Weight per foot	
	Web-plate, in	Flange-angles, in	Flange-plates, in	Web-plate and flange-angles, lb	Flange-plates, lb
361.3	26× <sup>7</sup> / <sub>16</sub>	6×4 × <sup>3</sup> / <sub>4</sub>		133.1	
384.0		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>1</sup> / <sub>2</sub>	93.1	40.8
421.8		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>5</sup> / <sub>8</sub>	93.1	51.0
441.7		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>1</sup> / <sub>2</sub>	103.5	47.6
461.1		5×3 <sup>1</sup> / <sub>2</sub> × <sup>5</sup> / <sub>8</sub>	12× <sup>5</sup> / <sub>8</sub>	105.9	51.0
485.9		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>5</sup> / <sub>8</sub>	103.5	59.5
532.7		6×4 × <sup>5</sup> / <sub>8</sub>	14× <sup>5</sup> / <sub>8</sub>	118.7	59.5
576.5		6×4 × <sup>5</sup> / <sub>8</sub>	14× <sup>3</sup> / <sub>4</sub>	118.7	71.4
620.5		6×4 × <sup>3</sup> / <sub>4</sub>	14× <sup>3</sup> / <sub>4</sub>	133.1	71.4
135.6	27× <sup>5</sup> / <sub>16</sub>	5×3 <sup>1</sup> / <sub>2</sub> × <sup>3</sup> / <sub>8</sub>		70.3	
211.0		6×4 × <sup>3</sup> / <sub>8</sub>		77.9	
230.3		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>		83.1	
264.1		6×4 × <sup>1</sup> / <sub>2</sub>		93.5	
273.2		5×3 <sup>1</sup> / <sub>2</sub> × <sup>5</sup> / <sub>8</sub>		95.9	
304.5		5×3 <sup>1</sup> / <sub>2</sub> × <sup>3</sup> / <sub>8</sub>	12× <sup>3</sup> / <sub>8</sub>	70.3	30.6
315.3		6×4 × <sup>5</sup> / <sub>8</sub>		108.7	
344.2		5×3 <sup>1</sup> / <sub>2</sub> × <sup>3</sup> / <sub>8</sub>	12× <sup>1</sup> / <sub>2</sub>	70.3	40.8
337.7	28× <sup>3</sup> / <sub>8</sub>	6×4 × <sup>5</sup> / <sub>8</sub>		115.7	
366.7		5×3 <sup>1</sup> / <sub>2</sub> × <sup>3</sup> / <sub>8</sub>	12× <sup>1</sup> / <sub>2</sub>	77.3	40.8
372.8		6×4 × <sup>3</sup> / <sub>8</sub>	14× <sup>3</sup> / <sub>8</sub>	84.9	35.7
398.5		6×4 × <sup>3</sup> / <sub>4</sub>		130.1	
411.7		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>1</sup> / <sub>2</sub>	90.1	40.8
420.8		6×4 × <sup>3</sup> / <sub>8</sub>	14× <sup>1</sup> / <sub>2</sub>	84.9	47.6
437.0		6×4 × <sup>7</sup> / <sub>8</sub>		144.5	
452.5		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>5</sup> / <sub>8</sub>	90.1	51.0
474.3		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>1</sup> / <sub>2</sub>	100.5	47.6
495.3		5×3 <sup>1</sup> / <sub>2</sub> × <sup>5</sup> / <sub>8</sub>	12× <sup>5</sup> / <sub>8</sub>	102.9	51.0
521.9		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>5</sup> / <sub>8</sub>	100.5	59.5
573.1		6×4 × <sup>5</sup> / <sub>8</sub>	14× <sup>5</sup> / <sub>8</sub>	115.7	59.5
620.4		6×4 × <sup>5</sup> / <sub>8</sub>	14× <sup>3</sup> / <sub>4</sub>	115.7	71.4
668.6		6×4 × <sup>3</sup> / <sub>4</sub>	14× <sup>3</sup> / <sub>4</sub>	130.1	71.4
257.1	28× <sup>7</sup> / <sub>16</sub>	5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>		96.1	
292.4		6×4 × <sup>1</sup> / <sub>2</sub>		106.5	
301.8		5×3 <sup>1</sup> / <sub>2</sub> × <sup>5</sup> / <sub>8</sub>		108.9	
345.8		6×4 × <sup>5</sup> / <sub>8</sub>		121.7	
396.5		6×4 × <sup>3</sup> / <sub>4</sub>		136.1	
419.5		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>1</sup> / <sub>2</sub>	96.1	40.8
445.1		6×4 × <sup>7</sup> / <sub>8</sub>		150.5	
460.2		5×3 <sup>1</sup> / <sub>2</sub> × <sup>1</sup> / <sub>2</sub>	12× <sup>5</sup> / <sub>8</sub>	96.1	51.0
482.0		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>1</sup> / <sub>2</sub>	106.5	47.6
503.0		5×3 <sup>1</sup> / <sub>2</sub> × <sup>5</sup> / <sub>8</sub>	12× <sup>5</sup> / <sub>8</sub>	108.9	51.0
529.6		6×4 × <sup>1</sup> / <sub>2</sub>	14× <sup>5</sup> / <sub>8</sub>	106.5	59.5
580.8		6×4 × <sup>5</sup> / <sub>8</sub>	14× <sup>5</sup> / <sub>8</sub>	121.7	59.5

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, 1

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot		Maxim end- reaction thousand of pound
	Web- plate, in	Flange- angles, in	*Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
628.0	28× $\frac{7}{16}$	6×4 × $\frac{5}{8}$	14× $\frac{3}{4}$	121.7	71.4	78.8
676.2		6×4 × $\frac{3}{4}$	14× $\frac{3}{4}$	136.1	71.4	78.8
221.8	30× $\frac{3}{8}$	5×3 $\frac{1}{2}$ × $\frac{3}{8}$		79.9		74.3
250.5		6×4 × $\frac{3}{8}$		87.5		74.3
272.1		5×3 $\frac{1}{2}$ × $\frac{1}{2}$		92.7		74.3
310.3		6×4 × $\frac{1}{2}$		103.1		74.3
320.5		5×3 $\frac{1}{2}$ × $\frac{5}{8}$		105.5		74.3
353.8		5×3 $\frac{1}{2}$ × $\frac{3}{8}$	12× $\frac{3}{8}$	79.9	30.6	74.3
366.2		5×3 $\frac{1}{2}$ × $\frac{5}{4}$		117.5		74.3
368.1		6×4 × $\frac{5}{8}$		118.3		74.3
397.8		5×3 $\frac{1}{2}$ × $\frac{3}{8}$	12× $\frac{1}{2}$	79.9	40.8	74.3
404.7		6×4 × $\frac{3}{8}$	14× $\frac{3}{8}$	87.5	35.7	74.3
423.1		6×4 × $\frac{3}{4}$		132.7		74.3
446.6		5×3 $\frac{1}{2}$ × $\frac{1}{2}$	12× $\frac{1}{2}$	92.7	40.8	74.3
456.1		6×4 × $\frac{3}{8}$	14× $\frac{1}{2}$	87.5	47.6	74.3
475.8		6×4 × $\frac{7}{8}$		147.1		74.3
490.3		5×3 $\frac{1}{2}$ × $\frac{1}{2}$	12× $\frac{5}{8}$	92.7	51.0	74.3
514.0		6×4 × $\frac{1}{2}$	14× $\frac{1}{2}$	103.1	47.6	74.3
536.7		5×3 $\frac{1}{2}$ × $\frac{5}{8}$	12× $\frac{5}{8}$	105.5	51.0	74.3
565.1		6×4 × $\frac{1}{2}$	14× $\frac{5}{8}$	103.1	59.5	74.3
620.6		6×4 × $\frac{5}{8}$	14× $\frac{5}{8}$	118.3	59.5	74.3
671.3		6×4 × $\frac{3}{8}$	14× $\frac{3}{4}$	118.3	71.4	74.3
723.8		6×4 × $\frac{3}{4}$	14× $\frac{3}{4}$	132.7	71.4	74.3
281.4	30× $\frac{7}{16}$	5×3 $\frac{1}{2}$ × $\frac{1}{2}$		99.0		86.6
319.5		6×4 × $\frac{1}{2}$		109.4		86.6
329.7		5×3 $\frac{1}{2}$ × $\frac{5}{8}$		111.8		86.6
375.5		5×3 $\frac{1}{2}$ × $\frac{3}{4}$		123.8		86.6
377.3		6×4 × $\frac{5}{8}$		124.6		86.6
432.3		6×4 × $\frac{3}{4}$		139.0		86.6
455.5		5×3 $\frac{1}{2}$ × $\frac{1}{2}$	12× $\frac{1}{2}$	99.0	40.8	86.6
485.0		6×4 × $\frac{7}{8}$		153.4		86.6
499.2		5×3 $\frac{1}{2}$ × $\frac{1}{2}$	12× $\frac{5}{8}$	99.0	51.0	86.6
523.0		6×4 × $\frac{1}{2}$	14× $\frac{1}{2}$	109.4	47.6	86.6
545.6		5×3 $\frac{1}{2}$ × $\frac{5}{8}$	12× $\frac{5}{8}$	111.8	51.0	86.6
574.0		6×4 × $\frac{1}{2}$	14× $\frac{5}{8}$	109.4	59.5	86.6
629.5		6×4 × $\frac{5}{8}$	14× $\frac{5}{8}$	124.6	59.5	86.6
680.1		6×4 × $\frac{3}{8}$	14× $\frac{3}{4}$	124.6	71.4	86.6
732.6		6×4 × $\frac{3}{4}$	14× $\frac{3}{4}$	139.0	71.4	86.6
290.6	30× $\frac{1}{2}$	5×3 $\frac{1}{2}$ × $\frac{1}{2}$		105.4		99.0
328.8		6×4 × $\frac{1}{2}$		115.8		99.0
338.9		5×3 $\frac{1}{2}$ × $\frac{5}{8}$		118.2		99.0
384.7		5×3 $\frac{1}{2}$ × $\frac{3}{4}$		130.2		99.0
386.5		6×4 × $\frac{5}{8}$		131.0		99.0

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot		Maximum end- reaction in thousands of pounds
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
441.5	30×½	6×4	×¾	145.4		99.0
464.4		5×3½	×½	105.4	40.8	99.0
494.2		6×4	×¾	159.8		99.0
528.0		5×3½	×½	105.4	51.0	99.0
531.9		6×4	×½	115.8	47.6	99.0
554.5		5×3½	×¾	118.2	51.0	99.0
582.8		6×4	×½	115.8	59.5	99.0
635.3		6×4	×¾	131.0	59.5	99.0
688.9		6×4	×¾	131.0	71.4	99.0
741.3		6×4	×¾	145.4	71.4	99.0
251.7	33×¾	5×3½	×¾	83.7		81.0
283.7		6×4	×¾	91.3		81.0
307.7		5×3½	×½	96.5		81.0
328.4		6×6	×¾	101.7		121.5
352.3		6×4	×½	106.9		81.0
430.3	36×¾	6×6	×½	124.3		135.0
460.0		5×3½	×¾	125.1		87.8
462.4		6×4	×¾	125.9		87.8
503.3		6×4	×¾	14×¾	35.7	87.8
510.5		6×6	×¾	142.7		135.0
530.2		6×4	×¾	140.3		87.8
531.6		6×6	×¾	14×¾	35.7	135.0
554.3		5×3½	×½	12×½	40.8	87.8
565.1		6×4	×¾	14×½	47.6	87.8
593.2		6×6	×¾	14×½	47.6	135.0
595.3		6×4	×¾	154.7		87.8
606.8		5×3½	×½	12×¾	51.0	87.8
636.5		6×4	×½	14×½	47.6	87.8
654.9		6×6	×¾	14×¾	59.5	135.0
664.2		5×3½	×¾	12×¾	51.0	87.8
674.4		6×6	×½	14×½	47.6	135.0
695.0		6×4	×½	14×¾	59.5	87.8
735.5		6×6	×½	14×¾	59.5	135.0
766.6		6×4	×¾	125.9	59.5	87.8
796.8		6×6	×½	14×¾	71.4	135.0
813.1		6×6	×¾	142.7	59.5	135.0
827.6		6×4	×¾	125.9	71.4	87.8
873.8		6×6	×¾	142.7	71.4	135.0
892.8		6×4	×¾	140.3	71.4	87.8
357.7	36×¾	5×3½	×½	108.0		102.4
404.7		6×4	×½	118.4		102.4
417.0		5×3½	×¾	120.8		102.4
443.6		6×6	×½	132.0		157.5

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis I-I, in <sup>3</sup>	Sizes			Weight per foot		Maximum end- reaction thousand of pounds
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
473.3	36× <sup>7</sup> / <sub>16</sub>	5×3½×¾	●	132.8	40.8	102.4
475.7		6×4 ×¾		133.6		102.4
523.8		6×6 ×¾		150.4		157.5
543.5		6×4 ×¾		148.0		102.4
567.2		5×3½×½	12×½	108.0	51.0	102.4
608.6		6×4 ×¾		162.4		102.4
619.7		5×3½×½	12×¾	108.0		102.4
649.5		6×4 ×½	14×½	118.4		102.4
677.1		5×3½×¾	12×¾	120.8	47.6	102.4
687.3		6×6 ×½	14×½	132.0		157.5
710.8		6×4 ×½	14×¾	118.4		102.4
748.4		6×6 ×½	14×¾	132.0		157.5
779.5		6×4 ×¾	14×¾	133.6	59.5	102.4
809.5		6×6 ×½	14×¾	132.0		157.5
825.9		6×6 ×¾	14×¾	150.4		157.5
840.4		6×4 ×¾	14×¾	133.6		102.4
886.6		6×6 ×¾	14×¾	150.4	71.4	157.5
905.5		6×4 ×¾	14×¾	148.0		102.4
418.0	36×½	6×4 ×½		126.0	47.6	117.0
456.9		6×6 ×½		139.6		180.0
489.0		6×4 ×¾		141.2		117.0
537.1		6×6 ×¾		158.0		180.0
556.9		6×4 ×¾		155.6	59.5	117.0
614.5		6×6 ×¾		176.0		180.0
621.9		6×4 ×¾		170.0		117.0
662.5		6×4 ×½	14×½	126.0		117.0
689.2		6×6 ×¾		193.6	47.6	180.0
700.3		6×6 ×½	14×½	139.6		180.0
723.7		6×4 ×½	14×¾	126.0		117.0
761.3		6×6 ×½	14×¾	139.6		180.0
792.3		6×4 ×¾	14×¾	141.2	71.4	117.0
822.3		6×6 ×½	14×¾	139.6		180.0
838.8		6×6 ×¾	14×¾	158.0		180.0
853.2		6×4 ×¾	14×¾	141.2		117.0
899.4		6×6 ×¾	14×¾	158.0	71.4	180.0
918.3		6×4 ×¾	14×¾	155.6		117.0
973.7		6×6 ×¾	14×¾	176.0		180.0
I 939.4	36×¾	6×4 ×¾	14×1	155.6	95.2	117.0
I 994.1		6×6 ×¾	14×1	176.0		180.0
I 101.1		6×4 ×¾	14×1	170.0		117.0
I 164.9		6×6 ×¾	14×1	193.6		180.0
444.7		6×4 ×½		141.3		146.3
483.5		6×6 ×½		154.9		225.0

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.



Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot	
	Web-plate, in	Flange-angles, in	Flange-plates, in	Web-plate and flange-angles, lb	Flange-plates, lb
515.7	36× $\frac{3}{8}$	6×4× $\frac{3}{8}$		156.5	
563.7		6×6× $\frac{3}{8}$		173.3	
583.5		6×4× $\frac{3}{4}$		170.9	
641.2		6×6× $\frac{3}{4}$		191.3	
648.5		6×4× $\frac{7}{8}$		185.3	
688.4		6×4× $\frac{1}{2}$	14× $\frac{1}{2}$	141.3	47.6
715.8		6×6× $\frac{7}{8}$		208.9	
726.2		6×6× $\frac{1}{2}$	14× $\frac{1}{2}$	154.9	47.6
749.4		6×4× $\frac{1}{2}$	14× $\frac{3}{8}$	141.3	59.5
787.0		6×6× $\frac{1}{2}$	14× $\frac{3}{8}$	154.9	59.5
818.1		6×4× $\frac{3}{8}$	14× $\frac{3}{8}$	156.5	59.5
847.9		6×6× $\frac{1}{4}$	14× $\frac{3}{4}$	154.9	71.4
864.6		6×6× $\frac{5}{8}$	14× $\frac{5}{8}$	173.3	59.5
878.8		6×4× $\frac{5}{8}$	14× $\frac{3}{4}$	156.5	71.4
924.9		6×6× $\frac{5}{8}$	14× $\frac{3}{4}$	173.3	71.4
943.9		6×4× $\frac{3}{4}$	14× $\frac{3}{4}$	170.9	71.4
999.3		6×6× $\frac{3}{4}$	14× $\frac{3}{4}$	191.3	71.4
1 045.9		6×6× $\frac{5}{8}$	14×1	173.3	95.2
1 064.7		6×4× $\frac{3}{4}$	14×1	170.9	95.2
1 119.3		6×6× $\frac{3}{4}$	14×1	191.3	95.2
1 126.3		6×4× $\frac{7}{8}$	14×1	185.3	95.2
1 190.1		6×6× $\frac{7}{8}$	14×1	208.9	95.2
390.2	42× $\frac{3}{8}$	6×4× $\frac{3}{8}$		102.8	
427.5		6×6× $\frac{3}{8}$		113.2	
477.2		6×4× $\frac{1}{2}$		118.4	
527.2		6×6× $\frac{1}{2}$		132.6	
561.4		6×4× $\frac{5}{8}$		133.6	
606.6		6×4× $\frac{3}{4}$	14× $\frac{3}{8}$	102.8	35.7
623.5		6×6× $\frac{5}{8}$		150.4	
638.3		6×4× $\frac{3}{8}$	16× $\frac{3}{8}$	102.8	40.8
642.1		6×4× $\frac{3}{4}$		148.0	
643.2		6×6× $\frac{3}{8}$	14× $\frac{3}{8}$	113.2	35.7
675.1		6×6× $\frac{3}{8}$	16× $\frac{3}{8}$	113.2	40.8
678.6		6×4× $\frac{3}{8}$	14× $\frac{1}{2}$	102.8	47.6
715.2		6×6× $\frac{3}{8}$	14× $\frac{1}{2}$	113.2	47.6
716.5		6×6× $\frac{3}{4}$		168.4	
719.5		6×4× $\frac{7}{8}$		162.4	
757.7		6×6× $\frac{3}{8}$	16× $\frac{1}{2}$	113.2	54.4
763.7		6×4× $\frac{1}{2}$	14× $\frac{1}{2}$	118.4	47.6
787.2		6×6× $\frac{3}{8}$	14× $\frac{5}{8}$	113.2	59.5
806.2		6×4× $\frac{1}{2}$	16× $\frac{1}{2}$	118.4	54.4
806.4		6×6× $\frac{7}{8}$		186.0	
812.7		6×6× $\frac{1}{2}$	14× $\frac{1}{2}$	132.0	47.6

\* From Pocket Companion, Carnegie Steel Company Pittsburgh.

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Sizes			Weight per foot		Maximum end- reaction in thousand of pounds
Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
42×3½	6×4×½	14×⅝	118.4	59.5	101.3
	6×6×½	16×½	132.0	54.4	157.5
	6×6×½	14×⅝	132.0	59.5	157.5
	6×4×¾	14×¾	133.6	59.5	101.3
	6×6×¾	16×¾	132.0	68.0	157.5
	6×6×¾	14×¾	132.0	71.4	157.5
	6×4×¾	16×¾	133.6	68.0	101.3
	6×6×¾	14×¾	150.4	59.5	157.5
	6×4×¾	14×¾	133.6	71.4	101.3
	6×6×¾	16×¾	150.4	68.0	157.5
	6×6×¾	14×¾	150.4	71.4	157.5
	6×4×¾	14×¾	148.0	71.4	101.3
	6×6×¾	16×¾	150.4	81.6	157.5
	6×4×¾	16×¾	148.0	81.6	101.3
	6×6×¾	14×¾	168.4	71.4	157.5
	6×6×¾	16×¾	150.4	95.2	157.5
	6×6×¾	16×¾	168.4	81.6	157.5
	6×6×¾	16×¾	168.4	95.2	157.5
	6×4×¾	16×¾	162.4	95.2	101.3
	6×6×¾	16×¾	186.0	95.2	157.5
	6×4×½		127.3		118.1
	6×6×½		140.9		183.8
	6×4×⅝		142.5		118.1
	6×6×⅝		159.3		183.8
	6×4×¾		156.9		118.1
	6×6×¾		177.3		183.8
	6×4×¾		171.3		118.1
	6×4×½	14×½	127.3	47.6	118.1
	6×4×½	16×½	127.3	54.4	118.1
	6×6×¾		194.9		183.8
42×7/16	6×6×½	14×½	140.9	47.6	183.8
	6×4×½	14×⅝	127.3	59.5	118.1
	6×6×½	16×½	140.9	54.4	183.8
	6×6×½	14×⅝	140.9	59.5	183.8
	6×4×⅝	14×⅝	142.5	59.5	118.1
	6×6×½	16×⅝	140.9	68.0	183.8
	6×6×½	14×¾	140.9	71.4	183.8
	6×4×¾	16×¾	142.5	68.0	118.1
	6×6×¾	14×¾	159.3	59.5	183.8
	6×4×¾	14×¾	142.5	71.4	118.1
	6×6×¾	16×¾	159.3	68.0	183.8
	6×6×¾	14×¾	159.3	71.4	183.8
	6×4×¾	14×¾	156.9	71.4	118.1

From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.  
 \* Explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot		Maximum end- reaction in thousands of pounds
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
1 129.9	42× $\frac{7}{8}$	6×6× $\frac{3}{8}$	16× $\frac{3}{4}$	159.3	81.6	183.8
1 147.9		6×4× $\frac{3}{4}$	16× $\frac{3}{4}$	156.9	81.6	118.1
1 156.0		6×6× $\frac{3}{4}$	14× $\frac{3}{4}$	177.3	71.4	183.8
1 211.6		6×6× $\frac{5}{8}$	16× $\frac{7}{8}$	159.3	95.2	183.8
1 219.8		6×6× $\frac{3}{4}$	16× $\frac{3}{4}$	177.3	81.6	183.8
1 300.9		6×6× $\frac{3}{4}$	16× $\frac{7}{8}$	177.3	95.2	183.8
1 387.3		6×6× $\frac{7}{8}$	16× $\frac{7}{8}$	194.9	95.2	183.8
513.5	42× $\frac{1}{2}$	6×4× $\frac{1}{2}$		136.2		135.0
563.5		6×6× $\frac{1}{2}$		149.8		210.0
597.7		6×4× $\frac{5}{8}$		151.4		135.0
659.8		6×6× $\frac{5}{8}$		168.2		210.0
678.4		6×4× $\frac{3}{4}$		165.8		135.0
752.8		6×6× $\frac{3}{4}$		186.2		210.0
755.8		6×4× $\frac{7}{8}$		180.2		135.0
799.2		6×4× $\frac{1}{2}$	14× $\frac{1}{2}$	136.2	47.6	135.0
841.7		6×4× $\frac{1}{2}$	16× $\frac{1}{2}$	136.2	54.4	135.0
842.7		6×6× $\frac{7}{8}$		203.8		210.0
848.1		6×6× $\frac{1}{2}$	14× $\frac{1}{2}$	149.8	47.6	210.0
870.8		6×4× $\frac{1}{2}$	14× $\frac{5}{8}$	136.2	59.5	135.0
890.6		6×6× $\frac{1}{2}$	16× $\frac{1}{2}$	149.8	54.4	210.0
919.4		6×6× $\frac{1}{2}$	14× $\frac{5}{8}$	149.8	59.5	210.0
952.6		6×4× $\frac{5}{8}$	14× $\frac{5}{8}$	151.4	59.5	135.0
972.6		6×6× $\frac{1}{2}$	16× $\frac{5}{8}$	149.8	68.0	210.0
990.8		6×6× $\frac{1}{2}$	14× $\frac{3}{4}$	149.8	71.4	210.0
1 005.7		6×4× $\frac{5}{8}$	16× $\frac{5}{8}$	151.4	68.0	135.0
1 012.9		6×6× $\frac{5}{8}$	14× $\frac{5}{8}$	168.2	59.5	210.0
1 023.7		6×4× $\frac{5}{8}$	14× $\frac{3}{4}$	151.4	71.4	135.0
1 066.0		6×6× $\frac{5}{8}$	16× $\frac{5}{8}$	168.2	68.0	210.0
1 083.7		6×6× $\frac{5}{8}$	14× $\frac{3}{4}$	168.2	71.4	210.0
1 101.7		6×4× $\frac{3}{4}$	14× $\frac{3}{4}$	165.8	71.4	135.0
1 147.5		6×6× $\frac{5}{8}$	16× $\frac{3}{4}$	163.2	81.6	210.0
1 165.4		6×4× $\frac{3}{4}$	16× $\frac{3}{4}$	165.8	81.6	135.0
1 173.6		6×6× $\frac{3}{4}$	14× $\frac{3}{4}$	186.2	71.4	210.0
1 229.0		6×6× $\frac{5}{8}$	16× $\frac{7}{8}$	168.2	95.2	210.0
1 237.4		6×6× $\frac{3}{4}$	16× $\frac{3}{4}$	186.2	81.6	210.0
1 318.4		6×6× $\frac{3}{4}$	16× $\frac{7}{8}$	186.2	95.2	210.0
1 321.2		6×4× $\frac{7}{8}$	16× $\frac{7}{8}$	180.2	95.2	135.0
1 404.7		6×6× $\frac{7}{8}$	16× $\frac{7}{8}$	203.8	95.2	210.0
466.9	48× $\frac{3}{8}$	6×4× $\frac{3}{8}$		110.4		121.5
512.7		6×6× $\frac{3}{8}$		120.8		180.0
567.4		6×4× $\frac{1}{2}$		126.0		121.5
628.9		6×6× $\frac{1}{2}$		139.6		180.0
664.9		6×4× $\frac{5}{8}$		141.2		121.5

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot		Maximum end- reaction thousand of pounds
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
714.4	48×3½	6×4×¾	14×¾	110.4	35.7	121.5
741.3		6×6×¾		158.0		180.0
750.8		6×4×¾	16×¾	110.4	40.8	121.5
758.5		6×4×¾		155.6		121.5
759.5		6×6×¾	14×¾	120.8	35.7	180.0
795.9		6×6×¾	16×¾	120.8	40.8	180.0
797.0		6×4×¾	14×½	110.4	47.6	121.5
841.9		6×6×¾	14×½	120.8	47.6	180.0
848.3		6×4×7⁄8		170.0		121.5
850.1		6×6×¾		176.0		180.0
890.4		6×6×¾	16×½	120.8	54.4	180.0
895.5		6×4×½	14×½	126.0	47.6	121.5
924.3		6×6×¾	14×5⁄8	120.8	59.5	180.0
944.0		6×4×½	16×½	126.0	54.4	121.5
955.2		6×6×7⁄8		193.6		180.0
955.8		6×6×½	14×½	139.6	47.6	180.0
977.7		6×4×½	14×5⁄8	126.0	59.5	121.5
I 004.3		6×6×½	16×½	139.6	54.4	180.0
I 037.6		6×6×½	14×5⁄8	139.6	59.5	180.0
I 072.7		6×4×5⁄8	14×5⁄8	141.2	59.5	121.5
I 098.2		6×6×½	16×5⁄8	139.6	68.0	180.0
I 119.5		6×6×½	14×¾	139.6	71.4	180.0
I 133.3		6×4×¾	16×5⁄8	141.2	68.0	121.5
I 147.1		6×6×5⁄8	14×5⁄8	158.0	59.5	180.0
I 154.4		6×4×5⁄8	14×¾	141.2	71.4	121.5
I 207.8		6×6×5⁄8	16×5⁄8	158.0	68.0	180.0
I 228.4		6×6×5⁄8	14×¾	158.0	71.4	180.0
I 245.2		6×4×¾	14×¾	155.6	71.4	121.5
I 301.2		6×6×5⁄8	16×¾	158.0	81.6	180.0
I 317.9		6×4×¾	16×¾	155.6	81.6	121.5
I 334.0		6×6×¾	14×¾	176.0	71.4	180.0
I 394.7		6×6×5⁄8	16×7⁄8	158.0	95.2	180.0
I 406.7		6×6×¾	16×¾	176.0	81.6	180.0
I 498.1		6×4×7⁄8	16×7⁄8	170.0	95.2	121.5
I 499.7		6×6×¾	16×7⁄8	176.0	95.2	180.0
I 601.3		6×6×7⁄8	16×7⁄8	193.6	95.2	180.0
591.2	48×7⁄16	6×4×½		136.2		141.8
652.7		6×6×½		149.8		210.0
688.7		6×4×5⁄8		151.4		141.8
765.0		6×6×5⁄8		168.2		210.0
782.3		6×4×¾		165.8		141.8
872.1		6×4×7⁄8		180.2		141.8
873.8		6×6×¾		186.2		210.0

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.

Table IV\*† (Continued). Elements of Riveted Plate Girders

Section-modulus, axis 1-1, in <sup>3</sup>	Sizes			Weight per foot		Maximum end- reaction in thousands of pounds
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
918.8	48×7½	6×4×½	14×½	136.2	47.6	141.8
967.3		6×4×½	16×½	136.2	54.4	141.8
979.0		6×6×¾		203.8		210.0
979.0		6×6×½	14×½	149.8	47.6	210.0
1 000.8		6×4×½	14×¾	136.2	59.5	141.8
1 027.6		6×6×½	16×½	149.8	54.4	210.0
1 060.8		6×6×½	14×¾	149.8	59.5	210.0
1 095.8		6×4×¾	14×¾	151.4	59.5	141.8
1 121.4		6×6×½	16×¾	149.8	68.0	210.0
1 142.5		6×6×½	14×¾	149.8	71.4	210.0
1 196.5		6×4×¾	16×¾	151.4	68.0	141.8
1 170.3		6×6×¾	14×¾	168.2	59.5	210.0
1 177.4		6×4×¾	14×¾	151.4	71.4	141.8
1 230.9		6×6×¾	16×¾	168.2	68.0	210.0
1 251.5		6×6×¾	14×¾	168.2	71.4	210.0
1 268.2		6×4×¾	14×¾	165.8	71.4	141.8
1 324.3		6×6×¾	16×¾	168.2	81.6	210.0
1 341.0		6×4×¾	16×¾	165.8	81.6	141.8
1 357.0		6×6×¾	14×¾	186.2	71.4	210.0
1 417.7		6×6×¾	16×¾	168.2	95.2	210.0
1 429.8		6×6×¾	16×¾	186.2	81.6	210.0
1 521.0		6×4×¾	16×¾	180.2	95.2	141.8
1 522.7		6×6×¾	16×¾	186.2	95.2	210.0
1 624.2		6×6×¾	16×¾	203.8	95.2	210.0
615.0	48×½	6×4×½		146.4		162.0
676.4		6×6×½		160.0		240.0
712.4		6×4×¾		161.6		162.0
788.8		6×6×¾		178.4		240.0
806.0		6×4×¾		176.0		162.0
895.8		6×4×¾		190.4		162.0
897.6		6×6×¾		196.4		240.0
942.1		6×4×½	14×½	146.4	47.6	162.0
990.6		6×4×½	16×½	146.4	54.4	162.0
1 002.3		6×6×½	14×½	160.0	47.6	240.0
1 002.7		6×6×¾		214.0		240.0
1 024.0		6×4×½	14×¾	146.4	59.5	162.0
1 050.8		6×6×½	16×½	160.0	54.4	240.0
1 083.9		6×6×½	14×¾	160.0	59.5	240.0
1 119.0		6×4×¾	14×¾	161.6	59.5	162.0
1 144.5		6×6×½	16×¾	160.0	68.0	240.0
1 165.6		6×6×½	14×¾	160.0	71.4	240.0
1 179.6		6×4×¾	16×¾	161.6	68.0	162.0
1 193.4		6×6×¾	14×¾	178.4	59.5	240.0

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.

† For explanation of table, see page 706.

Table IV \* † (Continued). Elements of Riveted Plate Girders

Section-modulus, axis I-I, in <sup>3</sup>	Sizes			Weight per foot		Maxim <sup>u</sup> end- reaction thousar of pound
	Web- plate, in	Flange- angles, in	Flange- plates, in	Web- plate and flange- angles, lb	Flange- plates, lb	
I 200.5	48×½	6×4×¾	14×¾	161.6	71.4	162.1
I 254.1		6×6×¾	16×¾	178.4	68.0	240.1
I 274.5		6×6×¾	14×¾	178.4	71.4	240.1
I 291.2		6×4×¾	14×¾	176.0	71.4	162.1
I 347.3		6×6×¾	16×¾	178.4	81.6	240.1
I 364.0		6×4×¾	16×¾	176.0	81.6	162.1
I 380.0		6×6×¾	14×¾	196.4	71.4	240.1
I 440.6		6×6×¾	16×¾	178.4	95.2	240.1
I 452.8		6×6×¾	16×¾	196.4	81.6	240.1
I 543.9		6×4×¾	16×¾	190.4	95.2	162.1
I 545.6		6×6×¾	16×¾	196.4	95.2	240.1
I 647.1		6×6×¾	16×¾	214.0	95.2	240.1

\* From Pocket Companion, Carnegie Steel Company, Pittsburgh, Pa.  
† For explanation of table, see page 706.

## CHAPTER XXI

## STRENGTH AND STIFFNESS OF WOODEN FLOORS

By

THOMAS NOLAN

PROFESSOR OF ARCHITECTURAL CONSTRUCTION, UNIVERSITY OF PENNSYLVANIA

**The Problems Stated.** The problems which are presented in this part of floor-construction are, in general, (1) the designing of the joists and girders forming the framework of the floor to safely support the greatest load likely to be upon it, and (2) the determination of the maximum safe load for a floor ready built. The first of these problems is the one with which architects and builders more commonly have to deal, and is, therefore, considered first.

**Layout of the Floor-Framing.** Before any calculations can be made for the sizes of the timbers it is necessary to know the spans of the joists, and, if there are openings in the floor, or the floor-joists have to support longitudinal partitions, a framing-plan should be made, showing the floor-area that will be supported by each joist, and also the position of partitions or special loads. If the floor is to be supported by posts and girders the position of these should be accurately indicated on the framing-plan. Where the joists are supported entirely by walls or partitions, the spans of the joists will of course be determined by the plan of the building. When the distance between a wall and a partition is too great for a single span, there may be a question as to the best positions for the posts and girders. When planning a building in which wooden floors are to be used, it is important to keep in mind the general scheme of the floor-framing and particularly the spans. Whenever practicable the spans of floor joists should not exceed 24 ft. When the distance between the supporting walls exceeds 30 ft, girders should be placed so that the maximum span of the joists will not exceed 24 ft for light buildings nor from 16 to 18 ft for houses.

**School Buildings** it is desirable to have the rooms at least 27 ft wide, and in this class of buildings the joists usually have spans of from 27 to 30 ft. A span of 30 ft, however, 16-in joists should be used, and as these are expensive, and often difficult to obtain, it is much better and more economical to make the schoolrooms 27 by 32 or 34 ft, than to make them 30 ft square. A schoolroom 27 ft wide by from 32 to 34 ft long, with windows on the long side, is economical and satisfactory, as it permits of using 3 by 14-in joists, 32 ft long, and also results in the most satisfactory lighting.

**Continuous Joists.** When joists are supported by a girder placed so that a 24 or 26-ft joist extends over the two spans, it is always better to have the joist continuous over the girder, as by that construction they make a much stronger floor. (See Chapter XIX.)

**Special Loads.** Having decided on the arrangement of the joists, and drawn the framing-plan showing the span and the locations of all special timbers, the

next step involves the determination of the loads for which the joists and girds are to be proportioned. Floor-loads are made up of two parts, the weight of materials composing the floor itself, and the ceiling below, if there is one; and the load liable to be put on the floor. The first is called the **DEAD LOAD**, and the second the **LIVE LOAD**. When the **SAFE LOAD** for a floor is spoken of, the live load is generally meant.

**Weight of Wooden Floor-Construction.** Wooden floors usually consist (1) beams, commonly called **JOISTS**,\* or **FLOOR-JOISTS**, (2) one or two thicknesses of flooring-boards, and, in a finished building, (3) a ceiling underneath the joists. In figuring the weight of  $\frac{3}{4}$ -in flooring-boards it will be sufficient to estimate the weight of a single thickness at 3 lb per sq ft. Joists may also be figured at 3 lb per ft, board-measure, with the exception of hard-pine and oak joists, which should be figured at 4 lb per ft, board-measure. The weight of the joists must also be reduced to their equivalent weight per square foot of floor. Thus, the weight of a 2 by 12-in joist is about 6 lb per sq ft. If the joists are spaced 12 in on centers, this will be equal to 6 lb per sq ft, but if the joists are 16 in on centers there will be but one linear foot of joist to every  $1\frac{1}{2}$  sq ft, which will be equivalent to  $4\frac{2}{3}$  lb per sq ft; and if they are 20 in on centers, the weight will be equal to  $3\frac{1}{2}$  lb per sq ft; spaced 24 in on centers, the weight will be 3 lb per sq ft. The weight of a lath-and-plaster ceiling should be taken at 10 lb per sq ft, and of a  $\frac{3}{4}$ -in wooden ceiling at 2 lb per sq ft. A corrugated-iron ceiling weighs about 1 lb per sq ft. For stamped steel ceilings, 2 lb per sq ft will cover the weight of the metal and furring. The following table, giving the weight of joists, will be found convenient in figuring the weight of floors:

**Table I. Weight of Floor-Joists per Square Foot of Floor**

Sizes of joists	Spruce, hemlock, white pine		Hard pine or oak	
	Spacing in inches, center to center		Spacing in inches, center to center	
	12	16	12	16
in	lb	lb	lb	lb
2X 6.....	3	2 $\frac{1}{4}$	4	3
2X 8.....	4	3	5 $\frac{1}{2}$	4
3X 8.....	6	4 $\frac{1}{2}$	8	6
2X10.....	5	3 $\frac{3}{4}$	6 $\frac{3}{4}$	5
3X10.....	7 $\frac{1}{2}$	5 $\frac{1}{2}$	10	7 $\frac{1}{2}$
2X12.....	6	4 $\frac{1}{2}$	8	6
3X12.....	9	6 $\frac{3}{4}$	12	9
2X14.....	7	5 $\frac{1}{4}$	9 $\frac{1}{4}$	7
3X14.....	10 $\frac{1}{2}$	8 $\frac{1}{2}$	14	10 $\frac{1}{4}$

**Weight of Crowds.** L. J. Johnson reports† results of some tests to ascertain the weight of crowds of men, in which he obtained weights of 134.2, 1.

\* Some building laws use the term **FLOOR-BEAM** instead of the word **JOIST**.

† See Engineering News, April 14, 1904.



156.1 and 156.9 lb per sq ft. The last-mentioned weight was obtained by packing 67 men in a room about 6 by 11 ft in size. Professor Johnson also found that with 50 men in the room, making a load of 122 lb per sq ft, the crowd was compacted "so that a man could elbow his way through it only with perseverance and determined effort."

**Superimposed Loads.** There is much difference of opinion as to what allowance should be made for the live load. Table II shows the minimum allowance for live loads for different classes of buildings, as fixed by the building laws of the cities mentioned. (See, also, page 149.)

**Table II. Minimum Safe Superimposed Loads for Floors, Required by Various Building Laws**

Classes of buildings	Minimum live load per square foot of floor					
	Buffalo, 1905	Boston, 1915	Chi- cago, 1916	Phila- delphia, 1914	New York, 1917	St. Louis, 1910
Dwellings.....	40	50	40	70	40	60
Hotels, tenements and lodg- ing-houses.....	70	50	50	70	60	60
Office-buildings.....	70	80	50	100	60*	70*
Buildings for public assembly	100	100	100	120	100	100†
Stores, warehouses and mfg. bldgs.....	120†	125†	100†	120†	120†	150†

\* First floor, 150 lb.

† Also school-houses.

‡ And upwards.

It was the opinion of Mr. Kidder that the following allowances for floor-loads, when in connection with the values given for the safe strength of joists or beams, provide absolute safety with proper allowance for economy.

	Lb per sq ft
For dwellings, sleeping-rooms and lodging-rooms.....	40
For schoolrooms.....	50
For office-buildings, upper stories.....	60
For office-buildings, first story.....	80
For stables and carriage-houses.....	65
For banking-rooms, churches and theaters.....	80
For assembly-halls, dancing-halls and the corridors of all public buildings, including hotels.....	120
For drill-rooms.....	150

**Live Loads for Stores and Buildings for Light Manufacturing.** Floors for heavy stores, light manufacturing and light storage should be computed for less than 120 lb per sq ft, and for a concentrated load at any point of 20 lb.

**Live Loads for Dwellings, etc.** Floors of dwellings, tenements, lodging-houses and rooms in hotels, are seldom loaded with more than 20 lb per sq ft for the live area, and a minimum load of 40 lb per sq ft should provide for all possible contingencies.

**Live Loads for Office-Buildings.** The floors of offices are, as a rule, not more heavily loaded than the floors of dwellings, but the possibilities for increased loads from safes and heavy furniture, and possibly from a more compact crowd of people, are greater, so that the minimum floor-load for offices should be somewhat increased. Some years ago the firm of Blackall & Everett, in Boston, found that the average live load in 210 offices, in three prominent office-buildings in that city, was between 16 and 17 lb per sq ft, while the average load for the heaviest office-buildings was 33.3 lb per sq ft. As such loads, however, are as a rule unevenly distributed, some portions of the floor being generally much more heavily loaded than others, it would not appear to be safe to use the average to determine the strength of floor-beams and floor-arches, although it would probably answer for the columns. There seems to be a considerable difference of opinion among the leading architects and structural engineers as to just what allowance should be made for office-floors. Among some of the earliest fire-proof office-buildings, for example, may be mentioned the former M. B. Building in San Francisco in which the live loads were assumed at 40 lb per sq ft for all floors above the first. In the Venetian Building, Chicago, the second, third and fourth floors were calculated for 60, and the upper floors for 35 lb per sq ft of live load, while in the Old Colony and Fort Dearborn Buildings in Chicago, the live loads on the floor-beams were assumed at 70 lb per sq ft. At the present time (1915), 50, 60, 70, 75, 100 and 150 lb per sq ft are the minimum live loads for the design of floors of office-buildings required by the building laws of six different cities. C. C. Schneider recommends\* for the design of floors of office-buildings above the first floor, for the uniform load of the floor-area, 50; for concentrated loads applied at any point of the floor, 5 000; and for the uniform load for girders, 1 000; the 50 being in pounds per sq ft, the 5 000 in pounds and the 1 000 in pounds per linear foot.

**Live Loads for Churches, Theaters and School-Houses.** "An allowance of 120 lb per sq ft for the live load in churches, theaters and school-houses is much greater than the actual conditions require. The average size of a school-room is about 28 by 32 ft, and such a room usually contains seats for fifty-six scholars and the teacher. Assuming the average weight of each scholar at 120 lb, the average live load, including ten visiting adults and the desks and furniture, is 13 lb per sq ft. Even supposing that the scholars of two rooms were united for some special occasion, there would be only 22 lb per sq ft; and this is not a great load as it is possible to imagine in such a room, as the fixed desks prevent the crowding together of the scholars except at the sides of the room. From this reasoning, therefore, 50 lb per sq ft would appear ample for school-rooms. As a matter of fact, 3 by 14-in long-leaf yellow-pine joists, 16 in on center and with a 28-ft span, have been used for school-room floors for years; such beams, if calculated by the formula for stiffness, would support a load of only 43 lb per sq ft. (Table XII, page 643 and Table I, page 7) The minimum floor-space allotted to a single seat in theaters is 4 sq ft, while the average is about 5 sq ft. Assuming the weight of an opera-chair at 30 lb and of the average adult at 140 lb, a liberal allowance, there results an average of 44 lb per sq ft of floor. A minimum of 80 lb per sq ft would therefore seem to provide for any possible crowding during a panic, except in corridors. On the other hand, it has been shown (see Weight of Crowds, page 718) that a crowd of able-bodied men may result in a load of about 120 lb per sq ft, and this should be the minimum for assembly-halls without fixed desks and also for the corridors of all public buildings. For armories, the minimum load should be increased on account of the vibration."†

\* "General Specifications for Structural Work of Buildings," 1910, page 53.

† F. E. Kidder.

The Average Floor-Loads for Stores has also been greatly over-estimated. W. L. B. Jenney found that the average load on the floors of the wholesale warehouse of Marshall Field & Company, in Chicago, was but 50 lb per sq ft, and very few retail stores will average over 80 lb per sq ft. An allowance of 120 lb per sq ft is sufficient for ordinary retail stores, with the possible exception of hardware stores.

**Live Loads for Warehouses.** Warehouses, on the other hand, may be very heavily loaded, and the floors in buildings intended for the storage of merchandise should be proportioned to the especial class of goods which they are designed to support. Table III, originally compiled by C. J. H. Woodbury,\* and to which some additions have been made by the Insurance Engineering Experiment Station and by Mr. Kidder, will be found of assistance in deciding upon the live load to be assumed for warehouse-floors. The weights per square foot are for single packages. If the goods are piled two or more cases high, the weight per square foot of floor will of course be increased accordingly. In fact, the height to which the goods are liable to be piled is a very important consideration in fixing upon the floor-load. In Table III "the measurements were always taken to the outside of case or package, and gross weights of such packages are given."

**Methods of Determining the Sizes of Joists, Beams or Girders Required for Any Building.** As already explained, the first step is the making of a framing-plan of the floors or enough of it to show any special framing and also the span and floor-area supported by the different joists, beams or girders.

Table III. Weights of Merchandise †

Materials	Measurements		Weights in pounds		
	Floor-space, sq ft	Contents, cu ft	Total, lb	Per sq ft	Per cu ft
WOOL					
Wool, East India.....	3.0	12.0	340	113	28
Wool, Australia.....	5.8	26.0	385	66	15
Wool, South America.....	7.0	34.0	1 000	143	29
Wool, Oregon.....	6.9	33.0	482	70	15
Wool, California.....	7.5	33.0	550	73	17
Bag. wool.....	5.0	30.0	200	40	7
Stack of scoured wool.....	.....	.....	.....	.....	5
WOOLLEN GOODS					
Case, flannels.....	5.5	12.7	220	40	17
Case, flannels, heavy.....	7.1	15.2	330	46	22
Case, dress goods.....	5.5	22.0	460	84	21
Case, cashmeres.....	10.5	28.0	550	52	20
Case, underwear.....	7.3	21.0	350	48	16
Case, blankets.....	10.3	35.0	450	44	13
Case, horse-blankets.....	4.0	14.0	250	63	18

\* The Fire Protection of Mills, page 118. † See, also, pages 1501 to 1508.

Table III (Continued). Weights of Merchandise

Materials	Measurements		Weights in pounds		
	Floor-space, sq ft	Con-tents, cu ft	Total, lb	Per sq ft	Per cu ft

COTTON, ETC

Bale.....	8.1	44.2	515	64	12
Bale, compressed.....	4.1	21.6	550	134	25
Bale, American Cotton Co.....	4.0	11.0	263	66	24
Bale, Planters' Compressed Co.....	2.3	7.2	254	110	35
Bale, jute.....	2.4	9.9	300	125	30
Bale, jute lashings.....	2.6	10.5	450	172	43
Bale, manila.....	3.2	10.9	280	88	26
Bale, hemp.....	8.7	34.7	700	81	20
Bale, sisal.....	5.3	17.0	400	75	24

COTTON GOODS

Bale, unbleached jeans.....	4.0	12.5	300	72	24
Piece duck.....	1.1	2.3	75	68	33
Bale, brown sheetings.....	3.6	10.1	235	65	23
Case, bleached sheetings.....	4.8	11.4	330	69	30
Case, quilts.....	7.2	19.0	295	41	16
Bale, print cloth.....	4.0	9.3	175	44	19
Case, prints.....	4.5	13.4	420	93	31
Bale, tickings.....	3.3	8.8	325	99	37
Skeins, cotton yarn.....	.....	.....	.....	.....	11
Burlaps.....	.....	.....	130	.....	30
Jute bagging.....	1.4	5.3	100	70	24

RAGS IN BALES

White linen.....	8.5	39.5	910	107	23
White cotton.....	9.2	40.0	715	78	18
Brown cotton.....	7.6	30.0	442	59	15
Paper shavings.....	7.5	34.0	507	68	15
Sacking.....	16.0	65.0	450	28	7
Woollen.....	7.5	30.0	600	80	20
Jute butts.....	2.8	11.1	400	143	36

PAPER

Calendered book.....	.....	.....	.....	.....	30
Supercalendered book.....	.....	.....	.....	.....	64
Newspaper.....	.....	.....	.....	.....	34
Strawboard.....	.....	.....	.....	.....	23
Leather-board.....	.....	.....	.....	.....	59
Writing.....	.....	.....	.....	.....	64
Wrapping.....	.....	.....	.....	.....	14
Manila.....	.....	.....	.....	.....	11

Table III (Continued). Weights of Merchandise

Materials	Measurements		Weights in pounds		
	Floor-space, sq ft	Contents, cu ft	Total, lb	Per sq ft	Per cu ft
GRAIN *					
Wheat, in bags.....	4.2	4.2	165	40	40
Wheat, in bulk, mean.....	.....	.....	.....	.....	48
Barrels, flour, on side.....	4.1	5.4	218	53	40
Barrels, flour, on end.....	3.1	7.1	218	70	31
Corn, in bags.....	3.6	3.6	112	31	31
Cornmeal, in barrels.....	3.7	5.9	218	59	37
Oats, in bags.....	3.3	3.6	96	29	27
Bale of hay.....	5.0	20.0	284	57	14
Hay, Dederick, compressed.....	1.75	5.25	125	72	24
Straw, Dederick, compressed.....	1.75	5.25	100	57	19
Tow, Dederick, compressed.....	1.75	5.25	150	86	29
Excelsior, Dederick, compressed.....	1.75	5.25	100	57	19
Hay, loose.....	.....	.....	.....	.....	4
DYE STUFFS, ETC					
Hogshead, bleaching powder.....	11.8	39.2	1 200	102	31
Hogshead, soda-ash.....	10.8	29.2	1 800	167	62
Box, indigo.....	3.0	9.0	385	128	43
Box, cutch.....	4.0	3.3	150	38	45
Box, sarnac.....	1.6	4.1	160	100	39
Caustic soda in iron drum.....	4.3	6.8	600	140	88
Barrel, starch.....	3.0	10.5	250	83	24
Barrel, pearl-alum.....	3.0	10.5	350	117	33
Box, extract logwood.....	1.06	0.8	55	52	70
Barrel, lime.....	3.6	4.5	225	63	50
Barrel, cement, American.....	3.8	5.5	325	86	59
Barrel, cement, English.....	3.8	5.5	400	105	73
Barrel, plaster.....	3.7	6.1	325	88	53
Barrel, rosin.....	3.0	9.0	430	143	48
Barrel, lard-oil.....	4.3	12.3	422	98	34
Rope.....	.....	.....	.....	.....	42
MISCELLANEOUS					
Box, tin.....	2.7	0.5	139	99	278
Box, glass.....	.....	.....	.....	.....	60
Crate, crockery.....	9.9	39.6	1 600	162	40
Cask, crockery.....	13.4	42.5	600	52	14
Bale, leather.....	7.3	12.2	190	26	16
Bale, goatskins.....	11.2	16.7	300	27	18
Bale, raw hides.....	6.0	30.0	400	67	13
Bale, raw hides, compressed.....	6.0	30.0	700	117	23
Bale, sole-leather.....	12.6	8.9	200	22	16
Flt, sole-leather.....	.....	.....	.....	.....	17
Barrel, granulated sugar.....	3.0	7.5	317	106	42
Barrel, brown sugar.....	3.0	7.5	340	113	45
Cheese.....	.....	.....	.....	.....	30

\* For pressure of grain in deep bins, see Engineering News, March 10, 1904, pages 2 and 356, and Dec. 15., 1904.

The second step is to determine approximately the weight of the floor and ceiling, and decide what superimposed load per square foot the floor is to be designed to carry. Having done this, the next step is the computing of the required dimensions of the common floor-joists. For most buildings the size of floor-joists required can be readily determined by reference to Tables XIII to XXV, inclusive, and XXII to XXVI, inclusive, of this chapter. For other floor-loads the sizes of the common joists may be determined by computing the load to be supported by a single joist and then, by the formulas or tables in Chapter XVI or the formulas in Chapter XVIII, determining the dimensions of the joist to support that load. (See Example 1.) For the floors of all buildings except stores and warehouses it is recommended that the sizes of the common joists be determined by the formulas for stiffness in Chapter XVIII or the stiffness values in the tables in Chapter XVI, unless one value, only, is given in tables for safe loads, in which case that value may be used. For stores and warehouses the sizes of the joists may be proportioned by the formulas or strength values of the tables in Chapter XVI.

The Dimensions of Special Beams, such as headers, trimmers and beams supporting partitions, and also of the girders, should be determined in the same



Fig. 1. Plan of Floor-joists

way, that is, by computing the maximum load the beam may have to support, and then the dimensions of a beam that will support that load with safety. The manner of making these computations is explained in the following examples.

**Example 1.** The simplest type of floor-framing is that shown in Fig. 1, in which all of the joists are of the same

span and support equal floor-areas. In such a floor, the FLOOR-AREA supported by each joist is equal to the span,  $L$ , multiplied by the spacing,  $S$ , in feet. The LOAD on each joist is equal to the FLOOR-AREA multiplied by the sum of the dead-loads and superimposed or live loads. To show the application of the above-mentioned formulas and tables we will assume that Fig. 1 represents the framing of a floor in a dwelling-house or lodging-house, that  $L = 18$  ft,  $S = 16$  in or  $1\frac{1}{3}$  ft, and that the timber is common white pine. The joists are to support a plastered ceiling and a double floor of  $\frac{3}{4}$ -in boards. What should be the size of the joists; average quality, conditions not ideal?

**Solution.** The FLOOR-AREA supported by each joist is  $1\frac{1}{3}$  by 18, or 24 sq ft. From Table XIII or XXII, pages 737 and 742, for a span of 18 ft, the joists will probably have to be at least 2 by 12 in, and their weight will be about 4 lb per sq ft (see Table I, page 718). The plastered ceiling weighs about 10 lb per sq ft, the flooring 6 lb per sq ft, making the total weight of the floor  $20\frac{1}{3}$  lb per sq ft. For the superimposed load we should allow at least 40 lb per sq ft (see page 719). This might be greater, if exacted by any particular building law. The load on a single joist will, therefore, be, with these assumed unit loads,  $60\frac{1}{3}$  by 24 sq ft, or 1 452 lb.

From Table VIII, page 639, we find that the maximum load for a 1

2-in white-pine joist of 18 ft span is 623 lb; hence to support 1 452 lb will require a breadth equal to  $1452/623 = 2\frac{1}{2}$  in. Therefore, to comply with the requirements for both strength and stiffness, the joists should be  $2\frac{1}{2}$  by 12 in.

This is not a stock size. Joists 2 by 12 in, 12 in on centers, may next be tried. Each joist must support 1 116 lb, requiring, by Table VIII, page 639, a 1.8 by 12-in joist, determined by the quotient  $1\ 116/623$ . So that, in this example, white-pine joists of a nominal size of 2 by 12 in and spaced 12 in on centers might be used, although they are slightly under the required depth, as the dressed size is about  $1\frac{3}{4}$  by  $11\frac{1}{2}$  in. From Table VI, page 637, the conversion-factor is 1.61, and  $623\text{ lb} \times 1.61 = 1\ 003\text{ lb}$  which is less than 1 116 lb, the load to be supported. From Tables XIII and XXII, pages 737 and 742, the maximum spans for 2 by 12 in white-pine joists, 12 in on centers, are 19 ft and 18 ft 8 in respectively, according to the assumed value of the modulus of elasticity for white pine. For 3 by 12-in joists, 16 in on centers, the load is 1 506 lb, and  $1\ 506/623 = 2\frac{3}{8}$  in. The dressed size is almost  $2\frac{3}{4}$  by  $11\frac{1}{2}$  in, the conversion-factor, 2.53, and  $623 \times 2.53 = 1\ 576\text{ lb}$ , an amount greater than 1 506 lb. Tables XIII

and XXII, again, give 19 ft 8 in and 19 ft 4 in for the maximum spans. Joists 3 by 12, 16 in on centers, are stronger than necessary. If, in this example, the span is made 10 ft, by Table VIII, page 639, for 12-in joists two values for the safe loads are found, and the smaller, stiffness-value, should be used, unless the deflection need not be considered.

**Example 2.** Fig. 2 shows a partial section of a dwelling, in which the second-floor joists support a plastered partition which also supports the attic joists. That should be the case of the second-floor joists to meet the requirements of STRENGTH, the timber being fair-quality Eastern spruce with a fiber-stress assumed to be 700 lb per sq in for flexure? As the effect of a concentrated load, compared with a distributed load, in producing deflection, is at least as great as the comparative effect in producing rupture, whenever a beam has a considerable CONCENTRATED load it may be calculated by the formula or rules FOR STRENGTH ONLY. The timber is assumed to be poorly seasoned.

**Solution.** The first step will be to determine the load on a single floor-joist. We will assume, as a trial, that the joists are to be 2 by 10 in, 12 in on centers, and that both the first-story and second-story ceilings are to be plastered, and that




Fig. 2. Section Through Floors and Partitions

only single flooring will be used in the second story and attic. We will assume that the attic-joists are to be 2 by 8 in, 16 in on centers, and that the width of floor supported by the partition is 10 ft.

The second-floor area supported by a single joist is 12 in by 15 ft, or 15 sq ft. The weight of the floor-joists per sq ft is 5 lb, of the plastered ceiling 10 lb and of the flooring 3 lb, making the dead load per sq ft 18 lb. For the live or superimposed load we should allow 40 lb and hence the load per square foot on each second-floor joist due to the second floor and its load is 58 lb. As the floor area for a single joist is 15 sq ft the load from the second floor is 15 sq ft  $\times$  58 lb per sq ft or 870 lb on each joist. We must now find what will be the load from the partition and attic-floor. The attic-floor and ceiling weigh about 16 lb per sq ft, and 24 lb is a sufficient allowance for the live load. The weight per linear foot on the partition will therefore be 40 lb. A partition of 2 by 4-in studs, lathed and plastered on both sides, weighs about 20 lb per sq ft face; hence the partition itself weighs 180 lb per lin ft. The partition and attic-floor, therefore, bring a load of 580 lb on each second-floor joist, concentrated at a point ONE-FOURTH of the span from the inner end of the joist. To combine this concentrated load with the load from the second floor, we must multiply the concentrated load by 1.5 (Table IV, page 632), which gives an equivalent distributed load of 870 lb. Adding this to the second-floor load we have 1740 lb as the total load for which each joist should be proportioned. From Table VIII, page 639, we find that the safe load for a 1 by 10-in spruce joist of 15-ft span is 518 lb; hence the breadth of each joist should be equal to  $1740/518 = 3.36$  or about  $3\frac{1}{2}$  in. Deeper joists, therefore, must be used. If we try 2 by 12-in joists, 12 in on centers, the safe load for a 1 by 12-in spruce joist of 15-ft span is 747 lb. Hence the breadth is  $1755/747 = 2.35$  or about  $2\frac{1}{2}$  in, indicating  $2\frac{1}{2}$  by 12-in joists, 12 in on centers. If the fiber-stress is assumed at 800 lb per sq in, the values of Table X, page 641, may be used. This will give, for 2 by 12-in joists, 12 in on centers and 15-ft span, 854 lb as the safe load for a 1 by 12-in joist; and  $1755/854 =$  about 2 in. The load per sq ft on each of these joists is  $1755/15 = 117$  lb; and Tables XVI and XXII, pages 739 and 744, give 16 ft 6 in and 16 ft 1 in for the maximum spans.

**Example 3.** It is required to determine the sizes of the girders and joists for the floor shown in Fig. 3, all of the timbers being of long-leaf yellow pine, and the floor above being supported by posts and girders in the same way. The building is intended for lodging purposes, and the height of the story is 10 ft. There is to be a double floor and the ceilings and partitions are to be plastered. The floor-joists are to be spaced 16 in on centers. Average timber, poorly seasoned.


**Solution.** We will first determine the size of the common joists at A, call the span 24 ft. The floor-area supported by a single joist is 24 by  $1\frac{1}{2}$  ft, 32 sq ft.

From Table XIII or XXII, pages 737 and 742, for a 24-ft span,  $2\frac{1}{2}$  by 14-in joists are probably required. We will allow  $8\frac{3}{4}$  lb per sq ft for the weight of joists and bridging (Table I, page 718), 10 for the ceiling and 6 for the flooring, making  $24\frac{3}{4}$  lb per sq ft for the dead load. For the live load we will allow 40 lb per sq ft. The load for which the joists should be proportioned is, therefore, 32 by  $64\frac{3}{4}$  or 2072 lb. We may use Table XII, page 643, to find the maximum load for a 1 by 14-in joist of 24-ft span. The deflection-load given in the table is 882 lb; hence the thickness of the joists must equal  $2072/882 = 2.35$  or about  $2\frac{1}{2}$  in. Therefore  $2\frac{1}{2}$  by 14-in long-leaf yellow-pine joists, 16 in on centers, may be used, but they should run full  $2\frac{1}{2}$  in thick. The joists at B (Fig. 3) have to support a partition, but as the span is much less, and



partition is quite near the end of the joints, it will be safe to make them of the same size as at A.

The joists at C (Fig. 3) have the same floor-load to support as at A, and in addition the weight of the partition, which is concentrated at one-third of the span from one support. As the partition is 10 ft high,  $13\frac{1}{2}$  sq ft of partition will be supported by each joist, the joists being 16 in on centers. Assuming 20 lb



**Fig. 3. Plan of Floor-framing Showing Partitions Above**

sq ft of face as the weight of the partition, we have 267 lb as the weight on the partition to be borne by each joist. To reduce this to an equivalent distributed load, we should multiply by 1.78 (Table IV, page 632), which gives 475 lb. The joists at C, therefore, should be proportioned to a uniformly distributed load of  $2072 + 475 = 2547$  lb, which requires 14-in joists, 2.88 in  $\tau$ , say, 3 by 14-in joists.

**The Header.** We will next determine the required breadth for the head  $H$  (Fig. 3), the depth being necessarily 14 in, the same as for the joists.

The header is 14 ft long and must support the floor half-way to the wall, a floor-area of 14 by 9 ft, or 126 sq ft. Multiplying this area by 64¾ lb, 1 weight per square foot, we have 8 159 lb, the total floor-load to be supported to which must be added a certain percentage of the partition. The portion the partition supported by the header is (14 ft - 1 ft 4 in) = 12 ft 8 in long a 10 ft high, and will weigh about 20 lb per sq ft of face, or a total of 2 532. As the partition is one-ninth of the span from the header, eight-ninths of weight will be supported by the header and one-ninth by the wall. Eight-ninths of 2 532 is 2 251 lb, which, added to the floor-load, makes a total load on the header of 10 410 lb. From Table XII, page 643, we find that the load for a 1 by 14-in beam of long-leaf yellow pine, 14-ft span, is 1 867 lb; hence it will require a breadth of  $10\,410/1\,867 = 5.58$  in. If the tail-beams are framed into the header, it should be thicker to allow for the weakening effects of the framing; so that, in this case, the header should be at least 6 by 14 in in actual cross-section, before any framing is done.

**The Trimmers.** We will next consider the trimmer,  $T$  (Fig. 3). This beam has four loads: (1) a distributed floor-load; (2) a distributed load from the partition above; (3) one-half the load on the header  $H$ ; (4) and a small direct load from the longitudinal partition.

(1) The strip of floor supported by the trimmer will be about 12 in wide a 24 ft long, and will weigh  $64\frac{3}{4}$  lb per sq ft  $\times$  24 sq ft = 1 554 lb.

(2) The partition above will weigh  $10 \times 24$  ft  $\times$  20 lb per sq ft = 4 800 lb.

(3) One-half of the load on  $H$  is  $10\,410/2 = 5\,205$  lb. As this is concentrated at one-fourth the span from the support, we must multiply it by 1.5 (Table, page 632) to obtain the equivalent distributed load, which then becomes  $5\,205 \times 1.5 = 7\,808$  lb.

(4) About 8 in of the longitudinal partition must be supported by the trimmer and this will weigh  $10 \times \frac{2}{3}$  ft  $\times$  20 lb per sq ft = 133 lb. As it is concentrated at one-third the span from the support, we must multiply by 1.78 (Table, page 632) to obtain the equivalent distributed load, which then becomes  $133 \times 1.78 = 237$  lb.

The total load for which the trimmer must be computed will be, therefore

(1) From the floor.....	1 554 lb
(2) From the partition above.....	4 800 lb
(3) From the header.....	7 808 lb
(4) From the longitudinal partition.....	237 lb
Total.....	14 399 lb

The trimmer should be of the same depth as the joists, 14 in. From Table XII, page 643, we find that a 1 by 14-in long-leaf yellow-pine beam of 24 ft span will safely support 882 lb and not cause a deflection of more than  $\frac{1}{400}$  the span. Hence, the breadth of the trimmer would be  $14\,399/882 = 16.34$  in, which is greater than the depth. This would suggest the substitution of a steel I beam of proper size or the use of a deeper wooden beam, such as an 11 by 14 in or a 12 by 16-in beam. If the deflection of the wooden beam is not taken into account, the strength-value, 1 090 lb of Table XII, page 643, may be used, giving  $14\,399/1\,090 = 13.21$  in as the width of the beam. This would agree with the former New York Code for strength. If the flexure fiber-stress is taken at 1 300 lb per sq in, permitted by the Chicago code, Table XIII, page 644, may be used, giving  $14\,399/1\,179 = 12.21$  in for the width of the trimmer.

800 lb per sq in is taken for  $S$ , Table XV, page 646, is used, giving  $14\,399/163 = 8.81$  in for the width. Hence, the architect will be governed by laws of safety, or by engineering judgment or experience elsewhere, and this applies to the joists as well as to the girders. If wooden trimmers are used, they should hang in beam-hangers (see last part of this chapter). The load on the trimmer,  $R$ , will be the same as on the trimmer,  $T$ , except for the cross-partition. Subtracting the weight of this partition, we have  $14\,399 - 4\,800 = 9\,599$  lb for the equivalent distributed load on  $R$ , which, from Table XII, page 643, gives, for the required breadth 10.88 in or 8.8 in, depending upon whether the deflection is or is not considered. Other variations in the required width of a 14-in wooden girder will result from the use of other fiber-stresses.

**The Girders.** The floor-area supported by the girder,  $G$  (Fig. 3), is equal to 12 by 24 ft, or 288 sq ft. As a general rule, it will be safe in estimating the live load on girders to take only 85% of the load assumed for the floor-beams, because there will always be some portion of the floor supported by the girder that is not loaded, and probably other portions that will not be loaded up to the assumed load. Hence, the live load would be 85% of 40 lb, or 34 lb. The dead load of the floor and ceiling will be about 25 lb, and the girder itself will weigh between 1 and 2 lb per sq ft, say 2 lb per sq ft of floor, more, so that we use 61 lb per sq ft for the total floor-load on this girder. As girder  $G$  supports 288 sq ft, this will be equivalent to 17 568 lb. The girder supports, also, the partition, 9 ft high, above, which will weigh  $12 \times 9 \times 20 = 2\,160$  lb. The total load for which the girder should be proportioned is, therefore, 19 728 lb. Assuming 14 in for the depth of the girder, we find from Table XII, page 643, that the safe load for a 1 by 14-in long-leaf yellow-pine beam of 12-ft span is 1 867 lb; hence the breadth of girder,  $G$ , should be  $19\,728/1\,867 = 10.56$  in and a 11 by 14-in girder could be used.

The girder,  $G'$  (Fig. 3), supports a floor-area at the left of  $12 \times 12 = 144$  sq ft, which represents a distributed load of 8 784 lb. On the right side of the girder there is a strip of floor 40 in wide by 12 ft long (8 in of the floor being included in the load on  $T$ ) which will weigh 2 440 lb. This may be considered as a concentrated load applied 20 in, or one-seventh the span, from the end of the girder, in which case the effect of the load is practically the same as if the load were distributed. The load coming upon girder  $G'$  from  $T$  will equal one-half the actual distributed load on  $T$ , plus three-eighths ( $\frac{1}{2}$  of  $\frac{3}{4}$ ) of the load on  $H$ . The load on  $H$  we found to be 10 410 lb, and three-eighths of this is about 3 900 lb. The actual distributed load on  $T$  we found to be  $1\,554 + 4\,800 = 6\,354$  lb, and one-half of this is 3 177 lb. Hence the trimmer,  $T$ , transmits a load of  $3\,900 + 3\,177 = 7\,077$  lb to the girder, which must be considered as a concentrated load applied at one-third the span from the support, and hence we must multiply it by 1.78 (Table IV, page 632) to obtain the equivalent distributed load, which gives 12 597 lb.

The load for which the girder,  $G'$  (Fig. 3), should be computed will be

From the floor at the left.....	8 784 lb
From the floor at the right.....	2 440 lb
From the trimmer, $T$ .....	12 597 lb
From the partition above.....	2 160 lb
Total.....	25 981 lb

From Table XII, page 643, we find that this load will require a (13.9 by 14) 14 by 14-in girder. For this floor, therefore, the requirements, if long-leaf yellow pine is used, and if the maximum flexure fiber-stress,  $S$ , is

taken at 1200 lb per sq in (a conservative value for non-ideal conditions, for example) and the modulus of elasticity,  $E$ , at 1500000 lb per sq in, are as follows: an 11 by 14-in girder at  $G$ ; a 14 by 14-in girder at  $G'$ ; an 11 by 16, or by 16-in wooden beam or a steel I beam for the trimmer,  $T$ ; an 11 by 14 beam for the trimmer,  $R$ ; a 6 by 14-in beam for the header,  $H$ ; 2½ by 14 joists at  $A$  and  $B$ ; and 3 by 14-in joists at  $C$ . For these stress-requirements the architect might decide to use steel I beams for girders  $G$ ,  $G'$ , etc., and for the trimmers,  $T$  and  $R$ . For  $S$ , 1300, Table XIII, page 644, may be used for long-leaf yellow pine; for  $S$ , 1500 lb per sq in, Table XIV, page 645; for a fiber stress,  $S$ , of 1800 lb per sq in, Table XV, page 646; and for  $S$  equal to 1600 lb per sq in, Table XII, page 643, with the strength-values increased one-third. Of course, the sizes of the timbers are diminished as the assumed safe fiber stresses are increased.

This example illustrates nearly all of the computations that are required to determine the sizes of the joists and special beams or girders in any ordinary floor-construction. The method of computation is the same for any floor load, the only difference being that the greater the live load assumed the greater will be the loads for which the beams must be proportioned. As will be seen, the most laborious computations are those for beams which receive loads from different sources, and it will generally be found that the weakest portions of any particular floor are the headers, trimmers and girders, and the beams which support partitions.

**The Strength of Mill-Floors.** The beams and girders for mill-floors should be computed by the same general method illustrated in the foregoing examples, involving, (1) the determination of the loads on the beams and girders and, (2) the sizes of the beams and girders required to support such loads.

**Required Thickness of Plank Flooring.** The thickness of the plank flooring in mill construction may be determined by formulas (1) and (2):

$$\left. \begin{array}{l} \text{Thickness of plank in in} \\ \text{required for strength} \end{array} \right\} = \sqrt{\frac{\text{weight per sq ft} \times l^2}{24 \times A}}$$

$$\left. \begin{array}{l} \text{Thickness of plank in in} \\ \text{required for stiffness} \end{array} \right\} = \sqrt[3]{\frac{\text{weight per sq ft} \times l^3}{19.2 \times e_1}}$$

In these formulas,  $l$  is the span in feet, from center to center of beams,  $A$  the constants for strength (page 628), and  $e_1$  the constant for stiffness (page 664).

When the planks are connected by ¾-in splines, and extend over two spans, Formula (1) may be used. If the planks are in single lengths from beam to beam or are not splined, then Formula (2) should be used.

Tables IV to XI,\* inclusive, show the safe loads for plank flooring of different woods, thicknesses and spans, derived from the formulas for strength and stiffness, the values in the first horizontal line in the case of each thickness of plank.

\* Tables VIII to XI, inclusive, were calculated by Mr. F. E. Kidder and are retained from the preceding edition of the Pocket-Book. Tables IV to VII, inclusive, are altered to conform to the most conservative fiber-stresses of the building codes and of the chapters of the new edition. In the judgment of many constructors the higher values of Tables VIII to XI are safe when more favorable conditions of quality and dryness of materials prevail. In using any of the tables, care must be taken to notice whether or not the safe loads given include the weight of the flooring itself. In the revision of this chapter the author is indebted to Professor F. H. Safford, of the University of Pennsylvania, for the computations required for the new Tables IV to VII and for the check of Tables VII to XI.

Listing the loads given by the formula for strength and the figures in the second line those given by the formula for stiffness. The span is supposed to be measured from center to center of beams. The values given by the formula for strength should be considered safe only for splined floors and where the planks are continuous over at least two spans. If the thickness of the planks falls at  $\frac{1}{4}$  or even  $\frac{1}{8}$  in from the dimensions given, the safe loads must be materially reduced.

In Table IV, the modulus of elasticity,  $E$ , on which  $e_1$  in the stiffness-formula depends, is 1 500 000 lb per sq in, and the safe fiber-stress,  $S$ , on which the constant for strength,  $A$ , depends, is 1 200 lb per sq in,  $A$  being 67. The safe loads given are within the requirements of all cities for strength and stiffness for short-leaf yellow pine, and of all cities for Douglas fir.

In Table V,  $E$  is 1 200 000 lb per sq in,  $S$ , 1 000 lb per sq in, and  $A$  is 56. The loads given satisfy the requirements of Chicago and of most other cities for strength for short-leaf yellow pine. The values given for stiffness, also, are recommended for this wood.

In Table VI,  $E$  is 1 200 000 lb per sq in,  $S$ , 800 lb per sq in, and  $A$  is 44. The loads given satisfy the requirements of all cities for strength, for spruce, Norway pine and white pine, and the values given for stiffness, also, are recommended for spruce. For Norway pine,  $E = 1\ 100\ 000$  lb per sq in may be used.

In Table VII,  $E$  is 1 000 000 lb per sq in,  $S$ , 700 lb per sq in, and  $A$  is 39. The loads given for strength can be used for any woods of that safe fiber-stress, and the loads for stiffness are recommended for white pine.

In Tables VIII, IX, X and XI, the safe loads are calculated from still other values of  $S$ ,  $A$ ,  $E$  and  $e_1$ , indicated with each table, and may be used by those who wish to assume larger safe values for the strength and stiffness-factors where there are no restrictions from building laws. For any other values of  $S$  or  $e_1$  required, such values must be inserted in Formula (1) or (2) and the thicknesses of the planks determined or the safe load determined for any given thickness of planks.

Note. It is to be noted that for ideal conditions and commercially dry lumber, protected from moisture, and when there is no impact, the given fiber-stresses in flexure may be increased from 30 to 40%. (See, also, important notes on pages 628, 637 and 647 regarding stresses in and loads on wooden beams.)

**Table IV. Safe Live Loads\* in Pounds per Square Foot for Plank Floors**

See explanation on pages 730-1. The loads are based on the following values.  
 Strength:  $S = 1\ 200$  lb per sq in,  $A = 67$ ; stiffness:  $E = 1\ 500\ 000$  lb per sq in,  $e_1 =$   
 LONG-LEAF YELLOW PINE AND DOUGLAS FIR †

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	
1 7/8	353	226	157	115	88	70	.....	.....	..
	229	117	68	43	29	20	.....	.....	..
2 3/8	567	363	252	185	142	112	91	75	
	466	239	138	87	58	41	30	22	
2 3/4	760	486	338	248	190	150	122	100	
	724	371	214	135	90	64	46	35	
3 1/2	.....	788	547	402	308	243	197	163	1
	.....	764	442	278	187	131	95	72	
4	.....	.....	715	525	402	318	257	213	1
	.....	.....	660	416	278	196	143	107	
5	.....	.....	.....	820	628	496	402	332	2
	.....	.....	.....	812	544	382	278	209	1
6	.....	.....	.....	.....	904	715	579	478	4
	.....	.....	.....	.....	940	660	481	361	2

\* Weight of ceiling, if any, and also of the flooring itself is to be deducted from these values.  
 † If  $S$  for Douglas fir is taken at 1000 lb per sq in, use Table V.

**Table V. Safe Live Loads\* in Pounds per Square Foot for Plank Floors**

See explanation on pages 730-1. The loads are based on the following values.  
 Strength:  $S = 1\ 000$  lb per sq in,  $A = 56$ ; stiffness:  $E = 1\ 200\ 000$  lb per sq in,  $e_1 =$   
 SHORT-LEAF YELLOW PINE

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	
1 7/8	295	189	131	96	74	.....	.....	.....	.
	182	93	54	34	23	.....	.....	.....	.
2 3/8	474	303	211	155	118	94	76	.....	.
	370	189	110	69	46	32	24	.....	.
2 3/4	635	406	282	207	159	125	102	84	
	574	294	170	107	72	50	37	28	
3 1/2	1 029	659	457	336	257	203	165	136	
	.....	606	351	221	148	104	76	57	
4	.....	860	597	439	336	265	215	178	
	.....	.....	523	330	221	155	113	85	
5	.....	.....	933	686	525	415	336	278	
	.....	.....	.....	644	431	303	221	166	
6	.....	.....	.....	987	756	597	484	400	
	.....	.....	.....	.....	745	523	382	287	

\* Weight of ceiling, if any, and also of the flooring itself is to be deducted from these values.

**Table VI. Safe Live Loads\* in Pounds per Square Foot for Plank Flooring**

See explanation on pages 730-1. The loads are based on the following values.

Strength:  $S = 800$  lb per sq in,  $A = 44$ ; stiffness:  $E = 1\,200\,000$  lb per sq in,  $e_1 = 92$ 

SPRUCE, NORWAY PINE AND WHITE PINE

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1 $\frac{3}{4}$	232	148	103	76	58	.....	.....	.....	.....
	182	93	54	34	23	.....	.....	.....	.....
2 $\frac{3}{4}$	372	238	165	122	93	74	60	.....	.....
	370	189	110	69	46	32	24	.....	.....
2 $\frac{1}{4}$	499	319	222	163	125	99	80	66	.....
	.....	294	170	107	72	50	37	28	.....
3 $\frac{1}{4}$	809	517	359	264	202	160	129	107	89
	.....	.....	351	221	148	104	76	57	44
4	.....	676	469	345	264	209	169	140	117
	.....	.....	.....	330	221	155	113	85	65
5	.....	.....	733	539	412	326	264	218	183
	.....	.....	.....	.....	.....	303	221	166	128
6	.....	.....	.....	776	594	469	380	314	264
	.....	.....	.....	.....	.....	.....	.....	287	221

Weight of ceiling, if any, and also of the flooring itself is to be deducted from these loads.

**Table VII. Safe Live Loads\* in Pounds per Square Foot for Plank Flooring**

See explanation on pages 730-1. The loads are based on the following values.

Strength:  $S = 700$  lb per sq in,  $A = 39$ ; stiffness:  $E = 1\,000\,000$  lb per sq in,  $e_1 = 77$ 

FOR HEMLOCK AND WOODS OF SIMILAR STRENGTH AND STIFFNESS

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1 $\frac{3}{4}$	206	132	91	67	.....	.....	.....	.....	.....
	152	78	45	28	.....	.....	.....	.....	.....
2 $\frac{3}{4}$	330	212	147	108	82	65	.....	.....	.....
	309	158	92	58	39	27	.....	.....	.....
2 $\frac{1}{4}$	442	283	197	146	111	87	71	.....	.....
	480	246	142	90	60	42	31	.....	.....
3 $\frac{1}{4}$	717	459	319	234	179	142	115	95	80
	.....	.....	293	185	124	87	63	48	37
4	936	599	416	306	234	185	150	124	104
	.....	.....	.....	276	185	130	95	71	55
5	.....	936	650	478	366	289	234	193	163
	.....	.....	.....	.....	361	253	185	139	107
6	.....	.....	936	688	526	416	337	278	234
	.....	.....	.....	.....	.....	.....	319	240	185

Weight of ceiling, if any, and also of the flooring itself is to be deducted from these loads.

**Table VIII. Safe Live Loads\* in Pounds per Square Foot for Plank Floors**

See explanation on pages 730-1. The loads are based on the following values.

Strength:  $S = 1\ 800$  lb per sq in,  $A = 100$ ; stiffness:  $E = 1\ 780\ 000$  lb per sq in,  $c_1 =$ 

Recommended by Mr. Kidder for

LONG-LEAF YELLOW PINE

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1½	515 258	325 126	222 68	160 38	120 21	92 11	72 5	..... .....	.... ....
2½	831 536	527 268	362 149	262 88	197 54	153 34	121 24	97 12	8 1
2¾	1 118 838	710 421	488 237	354 144	267 91	208 59	165 38	134 25	118 1
3½	..... .....	1 158 884	798 504	580 310	442 202	345 136	276 94	225 67	188 4
4	..... .....	..... .....	1 046 759	763 470	580 308	454 210	364 148	296 106	248 7
5	..... .....	..... .....	..... .....	1 200 934	913 618	716 427	576 304	471 223	388 16
6	..... .....	..... .....	..... .....	..... .....	1 322 1 081	1 038 751	836 540	686 398	576 3

\* Weight of ceiling, if any, to be deducted. The weight of the flooring has been deducted from values derived from formulas. Deduction about 72 lb per cu ft floor-material.

**Table IX. Safe Live Loads\* in Pounds per Square Foot for Plank Flooring**

See explanation on pages 730-1. The loads are based on the following values.

Strength:  $S = 1\ 620$  lb per sq in,  $A = 90$ ; stiffness:  $E = 1\ 425\ 000$  lb per sq in,  $c_1 =$ 

Recommended by Mr. Kidder for

DOUGLAS FIR AND SHORT-LEAF YELLOW PINE

Thickness of planks, in	Distance center to center of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1½	462 205	291 99	199 52	143 28	106 15	81 7	64 .....	..... .....	.. ..
2½	747 428	473 212	324 117	234 68	176 41	136 25	107 14	..... .....	.. ..
2¾	1 005 670	637 335	438 187	317 112	239 69	185 44	147 28	119 17	.. ..
3½	..... .....	1 040 706	717 401	522 246	395 199	308 106	246 72	200 50	.. ..
4	..... .....	1 362 1 061	940 606	685 374	520 244	406 165	325 115	265 81	.. ..
5	..... .....	..... .....	1 476 1 198	1 078 745	819 491	642 338	516 240	422 174	.. ..
6	..... .....	..... .....	..... .....	1 560 1 302	1 187 863	932 597	749 428	614 314	.. ..

\* Weight of ceiling, if any, to be deducted. The weight of the flooring has been deducted from values derived from formulas. Deduction about 72 lb per cu ft floor-material.



**Table X. Safe Live Loads \* in Pounds per Square Foot for Plank Flooring**

See explanation on pages 730-1. The loads are based on the following values.

Length:  $S = 1\ 260$  lb per sq in,  $A = 70$ ; stiffness:  $E = 1\ 294\ 000$  lb per sq in,  $e_1 = 100$ 

Recommended by Mr. Kidder for

## SPRUCE

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1 $\frac{3}{4}$	360	227	155	111	83	64	50	.....	.....
	188	92	49	28	15	8	.....	.....	.....
2 $\frac{3}{4}$	581	368	252	182	137	105	83	67	54
	391	194	108	64	39	24	15	.....	.....
2 $\frac{1}{4}$	782	496	341	247	186	144	115	93	76
	612	307	173	104	66	42	28	18	.....
3 $\frac{1}{2}$	1 228	781	548	391	296	231	184	150	124
	1 274	644	367	225	146	98	68	47	33
4	.....	1 060	731	533	405	317	253	207	171
	.....	968	554	343	225	153	108	77	56
5	.....	.....	1 148	839	638	500	402	329	273
	.....	.....	1 093	682	450	311	212	162	120
6	.....	.....	.....	1 213	924	725	583	478	400
	.....	.....	.....	1 188	789	548	394	290	220

\* Weight of ceiling, if any, to be deducted. The weight of the flooring has been deducted in values derived from formulas. Deduction about 72 lb per cu ft floor-material.

**Table XI. Safe Live Loads \* in Pounds per Square Foot for Plank Flooring**

See explanation on pages 730-1. The loads are based on the following values.

Length:  $S = 1\ 080$  lb per sq in,  $A = 60$ ; stiffness:  $E = 1\ 073\ 000$  lb per sq in,  $e_1 = 8$ 

Recommended by Mr. Kidder for

## WHITE PINE

Thickness of planks, in	Distance between centers of floor-beams, in feet								
	4	5	6	7	8	9	10	11	12
1 $\frac{3}{4}$	307	193	131	94	70	53	41	.....	.....
	153	74	39	21	11	5	.....	.....	.....
2 $\frac{3}{4}$	496	314	214	154	116	89	70	56	.....
	318	157	86	50	40	18	10	.....	.....
2 $\frac{1}{4}$	668	424	290	210	158	122	97	78	63
	499	249	139	83	52	33	20	12	.....
3 $\frac{1}{4}$	1 088	691	476	346	261	203	162	131	108
	1 041	526	298	183	119	78	53	36	25
4	.....	906	625	455	345	269	215	175	145
	.....	791	451	278	181	123	85	60	43
5	.....	.....	982	716	544	426	342	281	232
	.....	.....	893	555	366	251	178	129	95
6	.....	.....	1 419	1 037	789	619	497	407	339
	.....	.....	1 553	970	643	445	319	234	175

\* Weight of ceiling, if any, to be deducted. The weight of the flooring has been deducted in values derived from formulas. Deduction about 72 lb per cu ft floor-material.

**Tables for the Maximum Span of Floor-Joists.** As the timbers commonly used for floor-joists are sawed to regular sizes and are usually spaced either 16 in on centers, it is practicable to show by means of tables the sizes of joists required to support given loads with given spans and spacings. Tables giving the MAXIMUM SAFE SPANS are the most convenient for general use, and the following tables have accordingly been prepared. They show at a glance the maximum spans for which different sizes of floor-joists and ceiling-joists should be used for different loads and spacings, and it is believed that they will be found applicable to most buildings in which wooden floor-joists are used. By knowing the size of a room and the purpose for which it is to be used, the sizes of floor-joists required can be determined at a glance. Incidentally the tables also show, also, the kind of wood most economical to use. If, owing to the joists being irregular in shape, the joists must be of different lengths, the spacing and thickness of the joists may be varied, so that the same depth may be maintained throughout.

**Precautions Required in Using Tables.** The precautions necessary in using these tables are in regard to the superimposed loads and the ACTUAL SIZES of the timbers. The TOTAL LOADS for which the maximum spans have been computed are given at the head of each table. The actual weight of the joists, flooring, plastering and deafening, if any) subtracted from the total will give the SUPERIMPOSED LOAD, that is, the load which the floor is expected to carry. If the ACTUAL SIZES of the joists are less than the NOMINAL DIMENSIONS, the spans or spacings must be reduced from those given in the tables, as the STOCK SIZES of joists generally run from  $\frac{1}{4}$  in to  $\frac{3}{8}$  in scant of the NOMINAL DIMENSIONS, this fact should always be taken into account when determining upon the sizes of joists. In this connection it will be convenient to remember that 2-in joists, spaced 16 in on centers, have the same strength as 1½-in joists spaced 12 in on centers. A reduction should also be made for any CUTTING OF JOISTS that may be required. No allowance has been made for PARTITIONS when they are to be supported by the floor-joists, additional joists should be used or the span reduced according to the relative direction or position of partitions and joists.

**Tables XII to XX.** Tables XII to XVI, inclusive, were computed by the FORMULA FOR STIFFNESS (Chapter XVI, page 636 and Chapter XVIII, page 640) on the assumption that the deflection should not exceed  $\frac{1}{160}$  in per foot of span. They are based on the values of  $E$  (the modulus of elasticity) recommended by F. E. Kidder. Tables XVII to XX, inclusive, were computed by the FORMULA FOR STRENGTH (Chapter XVI, page 635), and values for  $S$  (the safe fiber-stress) recommended by Mr. Kidder. The spans given in Tables XII to XX, inclusive, come within the requirements of the Buffalo and Denver building codes, and Tables XII, XIV, XV, XVI and XVII comply with the Chicago law, and very nearly with the New York law; but to comply with the Boston law a reduction of about one-sixth must be made from the spans given (1914).\*

**Tables XXI to XXIX** † inclusive, were computed for reduced values of  $E$  (the modulus of elasticity,)  $S$  (the fiber-stress for flexure) and  $A$  (the constant for flexural strength) in the formulas used, these values agreeing generally with the stresses throughout the revised handbook. Of these new tables, also, Tables XXI to XXV, inclusive, were computed by the FORMULA FOR STIFFNESS and Tables XXVI to XXIX, inclusive, by the FORMULA FOR STRENGTH.

\* Building Codes are frequently revised and must be consulted.

† In the revision of this chapter the author is indebted to Mr. A. T. North, M. A. S. C. E., for valuable assistance in the computations required for the new Tables XXI to XXIX.

**Table XII. Maximum Span for Ceiling-Joists**

See explanatory notes on page 736

Total load, 20 pounds per square foot

Size of joists in	Distance on centers in	Hemlock, * $E =$ 1 045 000		White pine, $E = 1\ 073\ 000$		Norway pine or spruce, $E = 1\ 294\ 000$		Douglas fir or Texas pine, $E = 1\ 425\ 000$		Long-leaf yellow pine, $E = 1\ 780\ 000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X4	12	9	3	9	5	10	1	10	5	11	2
2X4	16	8	5	8	6	9	1	9	5	10	1
2X6	12	14	0	14	1	15	1	15	7	16	8
2X6	16	12	8	12	10	13	8	14	2	15	2
2X8	12	18	8	18	10	20	1	20	9	22	4
2X8	16	17	0	17	2	18	4	18	11	20	5
2X8	20	15	9	15	10	17	0	17	6	18	10

Total load, 24 pounds per square foot

2X10	12	22	0	22	2	23	8	24	5	26	4
2X10	16	20	0	20	2	21	7	22	3	23	10
2X10	20	18	6	18	8	20	0	20	7	22	2
2X12	12	26	5	26	8	28	5	29	4	31	7
2X12	16	24	0	24	2	25	10	26	8	28	8
2X12	20	22	3	22	5	24	0	24	8	26	8

\*  $E$  is the modulus of elasticity and is in pounds per square inch.**Table XIII. Maximum Span for Floor-Joists for Dwellings, Tenements and Grammar-School Rooms with Fixed Desks**

See explanatory notes on page 736

Total load, 60 pounds per square foot

Size of joists in	Distance on centers in	Hemlock, * $E =$ 1 045 000		White pine, $E = 1\ 073\ 000$		Norway pine or spruce, $E = 1\ 294\ 000$		Douglas fir or Texas pine, $E = 1\ 425\ 000$		Long-leaf yellow pine, $E = 1\ 780\ 000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X6	12	9	9	9	10	10	5	10	10	11	7
2X6	16	8	9	8	10	9	6	9	10	10	6
2X6	12	11	1	11	2	12	0	12	5	13	4
2X6	16	10	1	10	2	10	10	11	2	12	1
2X8	12	12	11	13	1	13	11	14	5	15	6
2X8	16	11	9	11	10	12	8	13	1	14	1
2X8	12	14	9	14	11	16	0	16	6	17	8
2X8	16	13	6	13	7	14	6	15	0	16	2
2X10	12	16	2	16	4	17	5	18	0	19	4
2X10	16	14	9	14	10	15	9	16	4	17	7

Total load, 66 pounds per square foot

X10	12	18	0	18	1	19	3	20	0	21	6
X10	16	16	3	16	5	17	7	18	2	19	6
X12	12	18	10	19	0	20	3	20	10	22	6
X12	16	17	2	17	3	18	4	19	0	20	6
X12	12	21	6	21	8	23	2	24	0	25	9
X12	16	19	7	19	8	21	1	21	9	23	5
X14	12	22	0	22	2	23	8	24	4	26	3
X14	16	20	0	20	1	21	6	22	2	23	10
2X14	12	23	8	23	10	25	6	26	3	28	3
2X14	16	21	6	21	8	23	2	23	10	25	8
X14	12	25	4	25	4	27	1	28	0	30	1
X14	16	23	0	23	0	24	7	25	4	27	4

\*  $E$  is the modulus of elasticity and is in pounds per square inch.

Table XIV. Maximum Span for Floor-Joists for Office-Buildings

See explanatory notes on page 736

Total load, 93 pounds per square foot									
Sizes of joists in	Distance on centers in	White pine, $E=1\ 073\ 000$		Norway pine or spruce, $E=1\ 294\ 000$		Douglas fir or Texas pine, $E=1\ 425\ 000$		Long-leaf yellow pine, $E=1\ 780\ 000$	
		ft	in	ft	in	ft	in	ft	in
3×8	12	12	10	13	9	14	2	15	4
3×8	16	11	8	12	6	12	10	13	10
2×10	12	14	1	15	1	15	6	16	9
2×10	16	12	9	13	8	14	1	15	2
3×10	12	16	1	17	3	17	9	19	2
3×10	16	14	8	15	8	16	2	17	3
2×12	12	16	10	18	1	18	8	20	1
2×12	16	15	4	16	5	17	0	18	3
Total load, 96 pounds per square foot									
3 ×12	12	19	2	20	6	21	2	22	5
3 ×12	16	17	5	18	7	19	3	20	8
2 ×14	12	19	6	20	10	21	7	23	1
2 ×14	16	17	9	19	0	19	7	21	2
2½×14	12	21	1	22	6	23	2	25	0
2½×14	16	19	2	20	4	21	2	22	1
3 ×14	12	22	4	23	10	24	8	27	1
3 ×14	16	20	4	21	8	22	5	24	1

\*  $E$  is the modulus of elasticity and is in pounds per square inch.

Table XV. Maximum Span for Floor-Joists for Churches and Theaters with Fixed Seats

See explanatory notes on page 736

Total load, 102 pounds per square foot									
Sizes of joists in	Distance on centers in	White pine, $E=1\ 073\ 000$		Norway pine or spruce, $E=1\ 294\ 000$		Douglas fir or Texas pine, $E=1\ 425\ 000$		Long-leaf yellow pine, $E=1\ 780\ 000$	
		ft	in	ft	in	ft	in	ft	in
3×8	12	12	6	13	4	13	9	14	1
3×8	16	11	4	12	2	12	6	13	
2×10	12	13	7	14	7	15	1	16	
2×10	16	12	4	13	3	13	8	14	
3×10	12	15	8	16	9	17	3	18	
3×10	16	14	2	15	2	15	8	16	1
2×12	12	16	5	17	7	18	1	19	
2×12	16	14	10	15	11	16	5	17	
Total load, 105 pounds per square foot									
3 ×12	12	18	7	19	11	20	6	22	
3 ×12	16	16	10	18	1	18	7	20	
2 ×14	12	19	0	20	3	20	10	22	
2 ×14	16	17	3	18	5	19	0	20	
2½×14	12	20	4	21	9	22	6	24	
2½×14	16	18	7	19	10	20	6	22	
3 ×14	12	21	8	23	2	23	10	25	
3 ×14	16	19	8	21	1	21	9	23	

\*  $E$  is the modulus of elasticity and is in pounds per square inch.

**Table XVI. Maximum Span for Floor-Joists for Assembly-Halls and Corridors**

See explanatory notes on page 736

Total load, 123 pounds per square foot

Sizes of joists in	Distance on centers in	White pine, * $E=1\ 073\ 000$		Norway pine or spruce, $E=1\ 294\ 000$		Douglas fir or Texas pine, $E=1\ 425\ 000$		Long-leaf yellow pine, $E=1\ 780\ 000$	
		ft	in	ft	in	ft	in	ft	in
3X8	12	11	7	12	7	13	0	14	0
3X8	16	10	8	11	4	11	9	12	8
2X10	12	12	10	13	9	14	2	15	2
2X10	16	11	7	12	6	12	10	13	10
3X10	12	14	8	15	8	16	2	17	5
3X10	16	13	4	14	3	14	9	15	10
2X12	12	15	4	16	6	17	0	18	3
2X12	16	14	0	15	0	15	5	16	7

Total load, 126 pounds per square foot

3 X12	12	17	6	18	8	19	3	20	9
3 X12	16	15	10	17	0	17	7	18	11
2 X14	12	17	10	19	1	19	8	21	2
2 X14	16	16	2	17	4	17	11	19	3
2½X14	12	19	3	20	6	21	2	22	9
2½X14	16	17	6	18	8	19	3	20	9
3 X14	12	20	5	21	9	22	6	24	3
3 X14	16	18	7	19	10	20	6	22	1

\*  $E$  is the modulus of elasticity and is in pounds per square inch.**Table XVII. Maximum Span for Floor-Joists for Retail Stores**

See explanatory notes on page 736

Total load, 174 pounds per square foot

Sizes of joists in	Distance on centers in	White pine, $S=1\ 080$ lb per sq in * $A=60$		Norway pine or spruce, $S=1\ 260$ lb per sq in $A=70$		Douglas fir or Texas pine, $S=1\ 620$ lb per sq in $A=90$		Long-leaf yellow pine, $S=1\ 800$ lb per sq in $A=100$	
		ft	in	ft	in	ft	in	ft	in
3X8	12	11	6	12	5	14	1	14	9
3X8	16	9	11	10	2	12	2	12	9
2X10	12	11	8	12	8	14	5	15	1
2X10	16	10	2	10	11	12	5	13	1
3X10	12	14	4	15	6	17	7	18	7
3X10	16	12	5	13	5	15	2	16	0
2X12	12	14	1	15	2	17	2	18	2
2X12	16	12	2	13	1	14	11	15	8

Total load, 177 pounds per square foot

3 X12	12	17	2	18	5	20	11	22	1
3 X12	16	14	10	16	0	18	2	19	1
2 X14	12	16	3	17	7	19	11	21	1
2 X14	16	14	2	15	2	17	3	18	2
2½X14	12	18	2	19	7	22	3	23	6
2½X14	16	15	9	17	0	19	3	20	4
3 X14	12	19	11	21	6	24	5	25	8
3 X14	16	17	3	18	7	21	2	22	3

\*  $A$  in the tables is the coefficient in formulas for beams and is one-eighteenth of the assumed flexural fiber-stress,  $S$ .

**Table XVIII.\* Maximum Span for Rafters. Shingled Roofs not Plastered**

See explanatory notes on page 736

Total load, 48 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, S=990 lb per sq in † A=55		White pine, S=1 080 lb per sq in A=60		Norway pine or spruce, S=1 260 lb per sq in A=70		Douglas fir or Texas pine, S=1 620 lb per sq in A=90		Long-leaf yellow pine, S=1 800 lb per sq in A=100	
in	in	ft	in	ft	in	ft	in	ft	in	ft	in
2X4	16	7	4	7	9	8	4	9	6	10	10
2X4	20	6	7	6	10	7	6	8	6	8	10
2X6	16	11	1	11	7	12	6	14	2	15	6
2X6	20	9	11	10	4	11	2	12	8	13	4
3X6	16	13	7	14	2	15	3	17	5	18	3
3X6	20	12	2	12	8	13	8	15	7	16	4
2X8	16	14	9	15	6	16	8	18	11	20	6
2X8	20	13	3	13	10	14	11	16	11	17	10
2X8	24	12	1	12	7	13	7	15	6	16	3
2X10	16	18	6	19	3	20	10	23	8	25	6
2X10	20	16	7	17	3	18	8	21	2	22	3
2X10	24	15	1	15	9	17	0	19	3	20	4

**Table XIX.\* Maximum Span for Rafters. Slate Roofs not Plastered, or Shingle Roofs Plastered**

See explanatory notes on page 736

Total load, 57 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, S=990 lb per sq in † A=55		White pine, S=1 080 lb per sq in A=60		Norway pine or spruce, S=1 260 lb per sq in A=70		Douglas fir or Texas pine, S=1 620 lb per sq in A=90		Long-leaf yellow pine, S=1 800 lb per sq in A=100	
in	in	ft	in	ft	in	ft	in	ft	in	ft	in
2X4	16	6	9	7	1	7	7	8	8	9	3
2X4	20	6	0	6	4	6	9	7	9	8	3
2X6	16	10	2	10	7	11	6	13	0	13	8
2X6	20	9	1	9	6	10	2	11	7	12	3
3X6	16	12	6	13	0	14	1	15	11	16	6
3X6	20	11	1	11	8	12	7	14	3	15	6
2X8	16	13	7	14	2	15	3	17	4	18	3
2X8	20	12	2	12	8	13	8	15	6	16	3
2X8	24	11	1	11	7	12	6	14	2	14	10
3X8	16	16	7	17	4	18	9	21	3	22	3
3X8	20	14	10	15	6	16	9	19	0	20	3
3X8	24	13	7	14	2	15	3	17	4	18	3
2X10	16	17	0	17	8	19	2	21	7	22	10
2X10	20	15	2	15	10	17	1	19	4	20	3
2X10	24	13	10	14	6	15	7	17	8	18	3

\* Tables XVIII, XIX and XX are intended for climates where a 2-ft snow-fall may be expected. In the Southern States, where there is very little snow, the spans in Table XVIII will be safe for slate or gravel roofs if the joists are sawed to the full dimensions. Variations in "Safe spans" in different tables, for the same kind of wood, depend upon the assumed safe flexural fiber-stress or modulus of elasticity or both.

† A in the tables is the coefficient in formulas for beams and is one-eighteenth of assumed flexural fiber-stress, S.

**Table XX.\* Maximum Span for Rafters. Slate Roofs Plastered, or Gravel Roofs not Plastered**

See explanatory notes on page 736

Total load, 66 pounds per square foot

Sizes of joists	Distance on centers	Hemlock, S=990 lb per sq in † A=55		White pine, S=1 080 lb per sq in A=60		Norway pine or spruce, S=1 260 lb per sq in A=70		Douglas fir or Texas pine, S=1 620 lb per sq in A=90		Long-leaf yellow pine, S=1 800 lb per sq in A=100	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X6	16	9	5	9	10	10	8	12	1	12	9
2X6	20	8	6	8	10	9	6	10	9	11	5
3X6	16	11	7	12	1	13	1	14	10	15	7
3X6	20	10	4	10	10	11	8	13	3	14	0
2X8	16	12	7	13	2	14	2	16	2	17	0
2X8	20	11	3	11	9	12	9	14	5	15	2
2X8	24	10	3	10	9	11	7	13	2	13	10
3X8	16	15	5	16	1	17	5	19	9	20	10
3X8	20	13	9	14	5	15	3	17	8	18	8
3X8	24	12	7	13	2	14	2	16	2	17	0
2X10	16	15	9	16	6	17	9	20	2	21	3
2X10	20	14	1	14	8	15	11	18	0	19	0
2X10	24	12	10	13	5	14	6	16	6	17	5
2X12	16	18	10	19	9	21	4	24	2	25	6
2X12	20	16	10	17	8	19	1	21	8	22	10
2X12	24	15	5	16	1	17	5	19	9	20	10

\*Tables XVIII, XIX and XX are intended for climates where a 2-ft snow-fall may be expected. In the Southern States, where there is very little snow, the spans in Table VIII will be safe for slate or gravel roofs if the joists are sawed to the full dimensions. Variations in "Safe spans" in different tables, for the same kind of wood, depend upon the assumed safe flexural fiber-stress or modulus of elasticity or both.

†A in the tables is the coefficient in formulas for beams and is one-eighteenth of the assumed flexural fiber-stress, S.

Table XXI. Maximum Span for Ceiling-Joists

See explanatory notes on page 736

Total load, 20 pounds per square foot											
Sizes of joists  in	Distance on centers  in	Hemlock, * $E=900\ 000$		White pine, $E=1\ 000\ 000$		Norway pine, $E=1\ 100\ 000$		Short-leaf yellow pine, spruce, $E=1\ 200\ 000$		Long-leaf yellow pine, Douglas fir, $E=1\ 500\ 000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
2×4	12	8	11	9	3	9	6	9	10	10	7
2×4	16	8	1	8	5	8	8	8	11	9	7
2×6	12	13	5	13	10	14	4	14	9	15	10
2×6	16	12	2	12	7	13	0	13	5	14	5
2×8	12	17	10	18	6	19	1	19	8	21	2
2×8	16	16	3	16	10	17	4	17	10	19	3
2×8	20	15	1	15	7	16	1	16	7	17	10
Total load, 24 pounds per square foot											
2×10	12	21	0	21	9	22	5	23	1	24	11
2×10	16	19	1	19	8	20	5	21	0	22	2
2×10	20	17	8	18	4	18	11	19	6	21	0
2×12	12	25	2	26	0	26	11	27	9	29	11
2×12	16	22	11	23	9	24	6	25	2	27	2
2×12	20	21	3	22	0	22	9	23	5	25	2

\*  $E$  is the modulus of elasticity and is in pounds per square inch.

Table XXII. Maximum Span for Floor-Joists for Dwellings, Tenements and Grammar-School Rooms with Fixed Desks

See explanatory notes on page 736

Total load, 60 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, * $E=900\ 000$		White pine, $E=1\ 000\ 000$		Norway pine, $E=1\ 100\ 000$		Short-leaf yellow pine, spruce, $E=1\ 200\ 000$		Long-leaf yellow pine, Douglas fir $E=1\ 500\ 000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X 6	12	9	3	9	7	9	11	10	3	11	0
2X 6	16	8	5	8	9	9	0	9	3	10	0
3X 6	12	10	8	11	0	11	4	11	8	12	7
3X 6	16	9	8	10	0	10	4	10	8	11	5
2X 8	12	12	4	12	10	12	3	13	8	14	8
2X 8	16	11	3	11	8	12	0	12	4	13	4
3X 8	12	14	2	14	8	15	2	15	7	16	10
3X 8	16	12	11	13	4	13	9	14	2	15	3
2X 10	12	15	6	16	0	16	7	17	0	18	2
2X 10	16	14	1	14	7	15	0	15	6	16	8
Total load, 66 pounds per square foot											
3 X 10	12	17	2	17	9	18	4	18	11	20	4
3 X 10	16	15	7	16	2	16	8	17	2	18	0
2 X 12	12	18	0	18	8	19	3	19	8	21	4
2 X 12	16	16	4	16	11	17	8	18	0	19	5
3 X 12	12	20	7	21	4	22	0	22	8	24	10
3 X 12	16	18	8	19	4	20	0	20	7	22	2
2 X 14	12	21	0	21	11	22	5	23	1	24	10
2 X 14	16	19	1	19	9	20	5	21	0	22	2
2½X 14	12	22	7	23	5	24	2	24	11	26	10
2½X 14	16	20	6	21	3	21	11	22	7	24	10
3 X 14	12	24	0	24	10	25	8	26	5	28	10
3 X 14	16	21	10	22	7	23	4	24	0	25	10

\*  $E$  is the modulus of elasticity and is in pounds per square inch.



**Table XXIII. Maximum Span for Floor-Joists for Office-Buildings**

See explanatory notes on page 736

Total load, 93 pounds per square foot

Size of joists in	Distance on centers in	Hemlock, * $E=900\,000$		White pine, $E=1\,000\,000$		Norway pine, $E=1\,100\,000$		Short-leaf yellow pine, spruce, $E=1\,200\,000$		Long-leaf yellow pine Douglas fir $E=1\,500\,000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
3X 8	12	12	3	12	8	13	1	13	6	14	6
3X 8	16	11	1	11	6	11	11	12	3	13	2
2X10	12	13	4	13	10	14	3	14	8	15	10
2X10	16	12	2	12	7	13	0	13	4	14	5
3X10	12	15	4	15	10	16	4	16	10	18	2
3X10	16	13	11	14	5	14	10	15	4	16	7
2X12	12	16	0	16	7	17	2	17	8	19	0
2X12	16	14	7	15	1	15	7	16	0	17	3

Total load, 96 pounds per square foot

3 X12	12	18	2	18	10	19	5	20	0	21	6
3 X12	16	16	6	17	1	17	8	18	2	19	7
2 X14	12	18	6	19	2	19	10	20	5	21	11
2 X14	16	16	10	17	5	18	0	18	6	19	11
2½X14	12	19	11	20	8	21	4	22	0	23	8
2½X14	16	18	2	18	9	19	5	19	11	21	6
3 X14	12	21	2	21	11	22	8	23	4	25	2
3 X14	16	19	3	19	11	20	7	21	2	22	10

\*  $E$  is the modulus of elasticity and is in pounds per square inch.**Table XXIV. Maximum Span for Floor-Joists for Churches and Theaters with Fixed Seats**

See explanatory notes on page 736

Total load, 102 pounds per square foot

Size of joists in	Distance on centers in	Hemlock, * $E=900\,000$		White pine, $E=1\,000\,000$		Norway pine, $E=1\,100\,000$		Short-leaf yellow pine, spruce, $E=1\,200\,000$		Long-leaf yellow pine Douglas fir $E=1\,500\,000$	
		ft	in	ft	in	ft	in	ft	in	ft	in
3X 8	12	11	10	12	3	12	8	13	1	14	1
3X 8	16	10	9	11	2	11	6	11	11	12	9
2X10	12	12	11	13	5	13	10	14	3	15	4
2X10	16	11	9	12	2	12	7	13	0	13	11
3X10	12	14	10	15	4	15	10	16	4	17	7
3X10	16	13	6	13	11	14	5	14	10	16	0
2X12	12	15	7	16	1	16	8	17	1	18	5
2X12	16	14	2	14	8	15	1	15	7	16	9

Total load, 105 pounds per square foot

3 X12	12	17	8	18	3	18	10	19	5	20	11
3 X12	16	16	0	16	7	17	1	17	8	19	0
2 X14	12	18	0	18	7	19	3	19	8	21	4
2 X14	16	16	4	16	11	17	5	18	0	19	4
2½X14	12	19	4	20	1	20	8	21	4	23	0
2½X14	16	17	7	18	3	18	10	19	4	20	11
3 X14	12	20	7	21	4	22	0	22	8	24	5
3 X14	16	18	8	19	4	20	0	20	7	22	2

\*  $E$  is the modulus of elasticity and is in pounds per square inch.

**Table XXV. Maximum Span for Floor-Joists for Assembly-Halls and Corridors**

See explanatory notes on page 736

Total load, 123 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, * $E=900\ 000$		White pine, $E=1\ 000\ 000$		Norway pine, $E=1\ 100\ 000$		Short-leaf yellow pine, spruce, $E=1\ 200\ 000$		Long-leaf yellow pine, Douglas fir, $E=1\ 500\ 000$	
in	in	ft	in	ft	in	ft	in	ft	in	ft	in
3X 8	12	11	2	11	7	11	11	12	3	13	
3X 8	16	11	0	10	6	10	10	11	2	12	
2X10	12	12	2	12	7	13	0	13	5	14	
2X10	16	11	1	11	5	11	10	12	2	13	
3X10	12	13	11	14	5	14	11	15	4	16	
3X10	16	12	8	13	1	13	7	13	11	15	
2X12	12	14	7	15	2	15	8	16	1	17	
2X12	16	13	3	13	9	14	2	14	8	15	
Total load, 126 pounds per square foot											
3 X12	12	16	7	17	2	17	9	18	3	19	
3 X12	16	15	1	15	7	16	1	16	7	17	
2 X14	12	16	11	17	6	18	1	18	7	20	
2 X14	16	15	4	15	11	16	5	16	11	18	
2½X14	12	18	2	18	10	19	6	20	1	21	
2½X14	16	16	8	17	3	17	10	18	4	19	
3 X14	12	19	4	20	1	20	8	21	4	22	
3 X14	16	17	7	18	3	18	10	19	4	20	

\*  $E$  is the modulus of elasticity and is in pounds per square inch.**Table XXVI. Maximum Span for Floor-Joists for Retail Stores**

See explanatory notes on page 736

Total load, 174 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, S=600 lb per sq in * A=33½		White pine, spruce, S=700 lb per sq in A=38.88		Norway pine, S=800 lb per sq in A=44.44		Douglas fir, short-leaf yellow pine, S=1 000 lb per sq in A=55.55		Southern long-leaf yellow pine, S=1 200 lb per sq in A=66⅔	
in	in	ft	in	ft	in	ft	in	ft	in	ft	in
3× 8	12	8	7	9	3	9	11	11	1	12	
3× 8	16	7	5	8	0	8	7	9	7	10	
2×10	12	8	9	9	5	10	1	11	4	12	
2×10	16	7	7	8	2	8	9	9	10	10	
3×10	12	10	9	11	7	12	5	13	10	15	
3×10	16	9	3	10	0	10	9	12	0	13	
2×12	12	10	6	11	4	12	2	13	7	14	1
2×12	16	9	1	9	10	10	6	11	9	12	1
Total load, 177 pounds per square foot											
3 ×12	12	12	6	13	6	14	6	16	2	17	
3 ×12	16	10	10	11	9	12	6	14	0	15	
2 ×14	12	12	2	13	1	14	0	15	8	17	
2 ×14	16	10	6	11	4	12	2	13	7	14	1
2½×14	12	13	7	14	8	15	8	17	6	19	
2½×14	16	11	9	12	8	13	7	15	2	16	
3 ×14	12	16	8	18	0	19	3	21	6	23	
3 ×14	16	14	5	15	7	16	8	18	8	20	

\*  $A$  in the tables is the coefficient in formulas for beams and is one-eighteenth of allowable flexural fiber-stress,  $S$ . For values of  $A$  for other woods, see Table II, 628.

**Table XXVII.\* Maximum Span for Rafters. Shingled Roofs, not Plastered**

See explanatory notes on page 736

Total load, 48 pounds per square foot

Size of joists	Distance on centers	Hemlock, S=600 lb per sq in † A=33½		White pine, spruce, S=700 lb per sq in A=38.88		Norway pine, S=800 lb per sq in A=44.44		Douglas fir, short-leaf yellow pine, S=1 000 lb per sq in A=55.55		Southern long-leaf yellow pine, S=1 200 lb per sq in A=66½	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X 4	16	5	9	6	3	6	8	7	5	8	2
2X 4	20	5	2	5	7	5	11	6	8	7	4
2X 6	16	8	8	9	4	10	0	11	2	12	3
2X 6	20	7	9	8	4	8	11	10	0	10	11
2X 6	16	10	7	11	5	12	3	13	8	15	0
2X 6	20	9	6	10	3	10	11	12	3	13	5
2X 8	16	11	6	12	6	13	4	14	11	16	4
2X 8	20	10	4	11	2	11	11	13	4	14	7
2X 8	24	9	5	10	2	10	11	12	2	13	4
2X 10	16	14	5	15	7	16	8	18	8	20	5
2X 10	20	12	11	13	11	14	11	16	8	18	3
2X 10	24	11	9	12	9	13	7	15	2	16	8

**Table XXVIII.\* Maximum Span for Rafters. Slate Roofs, not Plastered, or Shingled Roofs, Plastered**

See explanatory notes on page 736

Total load, 57 pounds per square foot

Size of joists	Distance on centers	Hemlock, S=600 lb per sq in † A=33½		White pine, spruce, S=700 lb per sq in A=38.88		Norway pine, S=800 lb per sq in A=44.44		Douglas fir, short leaf yellow pine, S=1 000 lb per sq in A=55.55		Southern long-leaf yellow pine, S=1 200 lb per sq in A=66½	
		ft	in	ft	in	ft	in	ft	in	ft	in
2X 4	16	5	3	5	9	6	1	6	10	7	6
2X 4	20	4	9	5	1	5	6	6	1	6	8
2X 6	16	7	11	8	7	9	2	10	3	11	3
2X 6	20	7	1	7	8	8	2	9	2	10	1
2X 6	16	9	9	10	6	11	3	12	7	13	9
2X 6	20	8	8	9	5	10	1	11	3	12	4
2X 8	16	10	7	11	5	12	3	13	8	15	0
2X 8	20	9	6	10	3	10	11	12	3	13	5
2X 8	24	8	8	9	4	10	0	11	2	12	3
2X 8	16	13	0	14	0	15	0	16	9	18	4
2X 8	20	11	7	12	6	13	5	15	0	16	4
2X 8	24	10	7	11	5	12	3	13	8	15	0
2X 10	16	13	3	14	4	15	3	17	1	18	9
2X 10	20	11	10	12	9	13	8	15	3	16	9
2X 10	24	10	10	11	8	12	6	13	11	15	3

\* Tables XXVII, XXVIII and XXIX are intended for climates where a 2-ft snow-fall may be expected. In the Southern States, where there is very little snow, the spans in Table XXVII will be safe for slate or gravel roofs if the joists are sawed to the full dimension. Variations in "Safe spans" in different tables, for the same kind of wood, depend on the assumed safe flexural fiber-stress or modulus of elasticity or both.

† See foot-note with Table XXVI.

**Table XXIX.\* Maximum Span for Rafters. Slate Roofs, Plastered, and Gravel Roofs, not Plastered**

See explanatory notes on page 736

Total load, 66 pounds per square foot											
Sizes of joists	Distance on centers	Hemlock, S=600 lb per sq in † A=33½		White pine, spruce, S=700 lb per sq in A=38.88		Norway pine, S=800 lb per sq in A=44.44		Douglas fir, short-leaf yellow pine, S=1 000 lb per sq in A=55.55		Southern long-leaf yellow pine, S=1 200 per sq in A=66½	
		ft	in	ft	in	ft	in	ft	in	ft	in
2× 6	16	7	5	8	0	8	6	9	6	10	4
2× 6	20	6	7	7	2	7	7	8	6	9	4
3× 6	16	9	0	9	9	10	5	11	8	12	10
3× 6	20	8	1	8	9	9	4	10	5	11	3
2× 8	16	9	10	10	8	11	4	12	8	13	11
2× 8	20	8	10	9	6	10	2	11	4	12	5
2× 8	24	8	0	8	8	9	3	10	5	11	4
3× 8	16	12	1	13	0	13	11	15	7	17	1
3× 8	20	10	9	11	8	12	5	13	11	15	3
3× 8	24	9	10	10	8	11	4	12	8	13	11
2×10	16	12	4	13	3	14	2	15	11	17	5
2×10	20	11	0	11	11	12	9	14	2	15	7
2×10	24	10	1	10	10	11	10	13	0	14	3
2×12	16	14	9	15	11	17	1	19	1	20	11
2×12	20	13	2	14	3	15	3	17	1	18	8
2×12	24	12	1	13	0	13	11	15	7	17	1

\* Tables XXVII, XXVIII and XXIX are intended for climates where a 2-ft snow-may be expected. In the Southern States, where there is very little snow, the spans Table XXVII will be safe for slate or gravel roofs if the joists are sawed to the full dimensions. Variations in "Safe spans" in different tables, for the same kind of wood, depend upon the assumed safe flexural fiber-stress or modulus of elasticity or both.  
† See foot-note with Table XXVI.

**To Determine the Strength of an Existing Floor.** When a building is leased for mercantile or manufacturing purposes the tenant will generally desire to know the greatest load which it will be safe to put upon the floor and some building laws require that the safe load for the floors in certain classes of buildings shall be computed and posted in a conspicuous place in each story. It is therefore important that every architect should know how to compute the safe strength of any existing floor. The problem is practically the reverse of that of proportioning a floor to a given load. In speaking of the strength of a floor a distinction should be made between the safe strength and the safe load. The **SAFE STRENGTH** should mean the maximum safe load for the beams, including the weight of the construction, flooring and ceiling, while the **SAFE LOAD** refers to the maximum load which may safely be placed upon the floor. The safe load is found by first computing the safe strength and then subtracting the weight of the materials forming the floor, including the ceiling below, if there is one. The most convenient measurement for either the **SAFE STRENGTH** or the **SAFE LOAD** of a floor is in pounds per square foot. The following example will serve to show the method of determining the safe load for an ordinary warehouse-floor.

**Example 4.** It is required to determine the safe load per square foot for a floor framed as shown in Fig. 4, the building being in a city the laws of which

allow 1 200 lb per sq in for the safe flexure fiber-stress for the wood of which the joists and girders are made. The joists are covered with two thicknesses of  $\frac{3}{4}$ -in flooring and the ceiling below is corrugated iron.

**Solution.** The first step will be to find the **SAFE STRENGTH** of the 22-ft joists. As this is a warehouse-floor we will use the tables for strength throughout. From Table XII, page 643, for  $S = 1\ 200$  lb per sq in, we find the safe strength of a 1 by 14-in joist of 22-ft span to be 1 188 lb; hence the strength of a  $2\frac{1}{2}$  by 14-in joist will be  $1\ 188 \times 2\frac{1}{2} = 2\ 970$  lb. As the joists are 16 in on centers, each joist supports a floor-area of  $1\frac{1}{2} \times 22$  ft =  $29\frac{1}{2}$  sq ft. The **SAFE STRENGTH PER SQUARE FOOT** of this portion of the floor will therefore




Fig. 4. Plan of a Warehouse-floor

$2\ 970 / 29.3 = 101$  lb. Suppose the estimated weight of the floor per square foot is 8 lb for the joists, 6 lb for the flooring and 1 lb for the corrugated-iron ceiling, or, say, 15 lb in all. Then the **SAFE LOAD PER SQUARE FOOT** for the 22-ft joists will be  $101 - 15 = 86$  lb.

**The Headers.** We will next find the safe load for the 4 by 14-in headers at each side of the stair-well. As the tail-beams are framed into the headers, we should deduct one inch from the thickness of each header for the loss of length in framing, leaving 3 by 14 in for the effective dimension of each. From Table XII, page 643, we find the safe strength of a 1 by 14-in beam of 17-ft span to be 1 867 lb. Hence the strength of the 3 by 14 will be  $1\ 867 \times 3 = 5\ 601$  lb. The floor-area supported by each header is  $4\frac{1}{2} \times 12$  ft = 54 sq ft; hence the **SAFE STRENGTH** of the header per square foot of floor is  $5\ 601 / 54 = 104$  lb. Deducting the weight of the floor per square foot, we have  $104 - 15 = 89$  lb for the **SAFE LOAD**.

**Trimmer A.** Trimmer A (Fig. 4) supports about the same amount of flooring as one of the common joists, and supports, also, the ends of the headers. Subtracting  $2\frac{1}{2}$  in, the thickness of the common joists, we have a 5 by 14-in beam

left to support the headers. As the headers are supported in iron stirrups, beam-hangers, no deduction in strength need be made for framing. To find the safe strength of a beam loaded with two concentrated loads, equidistant from the supports, we must use Formula (14), Fig. 11, page 631. In this case  $m = 8\text{ ft } 10\text{ in.}$ , or  $8\frac{5}{6}\text{ ft}$  and  $A = 1\,200/18 = 66.7$  (Table XII, page 643).

Applying the formula, the safe load at each joint  $= 5 \times 14 \times 14 \times 66.7/4 \times 8\frac{5}{6} = 1\,848\text{ lb.}$

The floor-area supported by one stirrup is equal to one-half of the area supported by the header, or  $27\text{ sq ft}$ ; hence the safe strength per square foot for the 5 by 14-in header is  $1\,848/27 = 68\text{ lb}$ , and deducting  $15\text{ lb per sq ft}$  for the weight of the floor, we have  $53\text{ lb per sq ft}$  as the safe load that the trimmer will support on the floor at each side of the stairs. Considering, as found above, that the safe load for the  $2\frac{1}{2}\text{ in.}$ , which we deducted to take the place of a common joist, is  $86\text{ lb per sq ft}$ , we might consider the safe load for the trimmer as the average of 86 and 53, or about  $70\text{ lb per sq ft}$ .

**Trimmer B.** This 10 by 14-in timber (Fig. 4) has to support the same floor loads as trimmer A, and also the lower end of a flight of stairs for which an allowance of at least  $1\,800\text{ lb}$  should be made. This stair-load being practically concentrated at the middle of the trimmer is equivalent to a distributed load of  $3\,600\text{ lb}$ . As the safe load for a 1 by 14-in joist of 22-ft span is  $1\,188\text{ lb}$  (Table XII, page 643), it will require a thickness of  $3\,600/1\,188 = 3\text{ in}$  to support the stairs, leaving  $7\text{ in}$  to support the floor-loads. As this is  $\frac{1}{2}\text{ in}$  less than the thickness of trimmer A, it is evident that the strength of the floor at B will be a little less than at A; but as it is improbable that the entire floor-space will be loaded at any given time, it would be safe to rate the strength of the floor each side of the stairway at  $70\text{ lb per sq ft}$ , LIVE LOAD, and beyond the stairway at  $86\text{ lb}$ .

**Partitions.** When the floor supports partitions, the weight of the latter as any load resting upon them must be taken into account in determining the safe load for the floor. If a partition runs the same way as the joists, then only the joist directly under the partition, and the joists at each side will be affected, but if a partition runs across the joists, then it affects the safe load of the entire floor.

**Example 5.** Suppose that the 22-ft joists in the floor shown in Fig. 4 have to support a plastered partition 12 ft high, running across the joists half-way between the walls. What will be the safe load for the floor?

**Solution.** A plastered partition with 2 by 4 or 2 by 6-in studs, set 16 in centers, weighs about  $20\text{ lb per sq ft}$  of partition-face; hence a partition 12 ft high will weigh  $240\text{ lb per lin ft}$  of partition. As the joists are 16 in on centers, each joist supports  $1\frac{1}{2}\text{ lin ft}$  of partition, weighing  $320\text{ lb}$ . As this load is concentrated at the middle span of the joists it is equivalent to a distributed load of  $640\text{ lb}$ . In Example 4, we found the safe distributed load for the  $2\frac{1}{2}\text{ in.}$  14-in joists of 22-ft span to be  $2\,970\text{ lb}$ . Subtracting  $640\text{ lb}$  from this we have  $2\,330\text{ lb}$ , which may be used for the floor. As the floor-area supported by each joist is  $29\frac{1}{2}\text{ sq ft}$ , the safe strength of the floor per square foot is  $2\,330/29\frac{1}{2} = 79\text{ lb}$ , and the safe load is  $79 - 15 = 64\text{ lb per sq ft}$ . Hence the partition decreases the safe load by  $86 - 64 = 22\text{ lb per sq ft}$ . Whenever the upper-floor joists are supported by a partition carried by a floor below, the effect of the partition and its load upon the strength of the lower floor should be very carefully computed.

**Bridging of Floor-Joists.** By BRIDGING is meant a system of bracing floor-joists, either by means of small struts, as in Fig. 5, or by means of similar

boards set at right-angles to the joists and fitting in between them. The effect of this bracing is of decided advantage in sustaining any CONCENTRATED LOAD upon a floor; but it does not materially strengthen a floor to resist UNIFORMLY DISTRIBUTED LOAD. The bridging also stiffens the joists, and prevents them from turning sidewise. It is customary to insert rows of cross-bridging in 5 to 8 ft apart; and to be effective the rows of bridging should be in straight lines along the floor, so that each bridging-joint may abut directly opposite those adjacent to it. The method of bridging shown in Fig. 5, and known as CROSS-BRIDGING, is considered to be by far the best, as it allows the thrust to act parallel to the axis of the strut, and not across the grain, as must be the case where single pieces of boards are used. The bridging should be of 1½ by 3-in stock, for 2 by 10-in and smaller joists, and of 2 by 3-in stock for 12- and 14-in joists.

#### Framing of Wooden Floor-Beams.

In dwellings, tenements and lodgings-

where it is frequently necessary to frame the timbers so that they are flush with one another. The old methods of framing the tail-beams and headers or trimmers by mortise-and-tenon joints are now generally superseded by nailing the timbers in stirrups or malleable-iron joist-hangers. In this construction the entire strength

Fig. 5. Floor-joists with Bridging

of the timbers is retained, while the cost of the hangers is often less than the labor-cost in preparing the mortise-and-tenon joints. All headers 6 ft or more in length should be carried in joist-hangers or stirrups and this is usually required in the building codes of the large cities. In warehouses and all first-class buildings the framing should be done by means of joist-hangers. For light floors, with moderate spans, it is generally safe to frame the tail-beams into a header, provided the latter is strong enough to carry the load and allow 1 in in thickness for the mortising. Headers,




Fig. 6. Framing of Joists into Header

carrying not more than two tail-beams are often framed into the trimmers. Where the old methods of framing are used instead of the superior methods of joist-hangers, the best shape and proportions for the tenons and ends of tail-beams or headers are those shown in Fig. 6. This form of framing

probably offers as large a proportion of the strength of the timbers as it is possible to utilize, although for tail-beams it was the opinion of Mr. Kidd that a single tenon like that shown in Fig. 7 is fully as strong, especially when the header is built up of 2-in planks spiked together. In either case, if the floor




Fig. 7. Alternate Method of Framing Joists into Header




Fig. 8. Framed Joist Split by Load

is loaded to its full strength, the tail-beam will split at the bottom of the tenon, as shown in Fig. 8, which illustrates the weakening effect of mortise-and-tenon framing.

**Stirrups and Joist-Hangers.** The first device used for framing headers and trimmers without mortising was the wrought-iron stirrup shown in Fig. 9. These are made either single or double, depending upon whether one or two beams are to be supported. To prevent the floor from spreading and thus p




Fig. 9. Framing with Wrought-iron Stirrups

mitting the header to slip out of the stirrup, a joint-bolt may be inserted, as shown in the two right-hand illustrations of Fig. 9. To determine the strength of a stirrup, multiply the sectional area of the iron, in square inches, by 12 lb per sq in. (Table 1, page 376.)

The following sizes of iron should, in general, be used for the different sizes of joists to be supported:



Size of joists or timbers to be supported, in inches	Sections of stirrup-iron in inches
2 by 8 to 3 by 10.....	$\frac{3}{4}$ by $2\frac{1}{4}$
4 by 10 to 4 by 12.....	$\frac{3}{4}$ by $2\frac{1}{4}$
6 by 12 to 3 by 14.....	$\frac{3}{4}$ by 3
8 by 12 to 4 by 14.....	$\frac{3}{4}$ by $3\frac{1}{4}$
6 by 14.....	$\frac{3}{4}$ by 4
8 by 14 to 10 by 14.....	$\frac{3}{4}$ by 4

**Joist-Hangers.** Aside from the matter of strength there are objections to the use of stirrups. If the timber on which they rest is not perfectly dry, the stirrups will settle by an amount equal to the shrinkage of the beam on which they rest, and let down the header with them, and the projection of the iron above the top of the timbers will necessitate cutting out the flooring. If the stirrups are exposed in this way their appearance is objectionable. While they may be designed to resist any tensional stress the resistance of steel to bending is comparatively small, and the resulting crushing of the timber where they pass over the edge is the chief objection to the use of stirrups of this type on heavily loaded floors. The small bearing of a timber on a stirrup is




Fig. 10. Failure of Steel Stirrup Wall-hanger

sufficient to distribute the load on the wood over the required area. This reduces the bearing per square inch, allows the hanger to crush into the edge of the timber, and tends to straighten out the stirrup as shown in Fig. 29, page 757. The most serious objection applies to the use of steel stirrup-hangers in brick walls carrying beams free of the walls. As previously explained, all the load is brought to the extreme edge, causing a much greater load per square inch on the masonry than is allowable. Fig. 10\* shows the effect of crushing, in a house-building in Minneapolis, Minn. Wall-hangers made of steel stirrups should not be used. Patented steel hangers riveted to bearing-plates are likewise very undesirable as the crushing effect is greatest at the outer edge, due to the straightening-out tendency of the hanger at this point.

Figs. 11 and 12 illustrate the Duplex and Goetz joist-hangers, which are patented and are claimed to be superior to the old-style stirrups. The Duplex hanger is used not only for ordinary building-construction, but for the most heavily loaded mill-construction in factories and warehouses. As these hangers are made of malleable iron they will not straighten out when heated, in case of fire, and drop the beams. That is what happens to wrought-steel stirrups

\*Taken from a paper on "Joist and Wall-Hangers," read by Mr. F. E. Kidder at a meeting of the Colorado Chapter of the American Institute of Architects, February 27,

when the twist becomes heated. This hanger has proven perfectly satisfactory and is extensively used. Both are made in sizes to fit all regular sizes of joist or girders, and have ample strength for the purpose for which they are intended.

Fig. 11. Duplex Joist-hanger

Fig. 12. Goetz Joist-hanger

As shown by the illustrations, they are made to be inserted in round holes in the side of the carrying timbers, at or a little above the center line. With these hangers the effect of shrinkage is reduced one-half, and the other two




Fig. 13. Duplex I-beam Hangers



Fig. 14. Duplex I-beam Shelf-hanger. Joists Raised Less than Four Inches

sections to the stirrup, previously mentioned, are overcome. The Duplex hanger has ridges on the inside of the side brackets to hold the beam.

For timbers of larger size and for the heaviest construction, the Duplex hanger

own in Fig. 32, page 789, are used and are bolted to the beams. By this construction the entire building is tied together laterally.

Fig. 13 shows the Duplex I-beam hanger, for framing floor-joists to I beams. This hanger is made to exactly fit into the flange of the I beam. It has a rib




Fig. 13. Duplex I-beam Box Hanger. Joists Raised More than Four Inches




Fig. 16. Duplex Wall-hanger for Joists

at the bottom,  $\frac{3}{4}$  in high, which serves as a tie when the joist is placed in the hanger, and it provides a bearing of at least  $4\frac{1}{2}$  in for the joist. It is made to carry any joist of regular size, and offers one of the best devices for framing wooden joists to I beams of the same depth.

The hangers are bolted to the web of the I beam. Fig. 14 shows the Duplex I-beam shelf-hanger which is used when the construction requires the joists be raised above the lower flange of the beam less than 4 in. Fig. 15 illustrates the Duplex I-beam box-hanger and is recommended where the joists are raised more than 4 in above the lower flange of the I beam. In both these constructions the hangers are bolted singly or in pairs, as required, on the I beam and the loads are carried on the lower flanges of the beams.




Fig. 17. Duplex Steel Wall-hanger for Large Beams

Fig. 16 shows a similar hanger made to support the wall-end of a floor-joist. This form of construction is considered much superior to the method of building the



Fig. 18. Duplex Extra-heavy Wall-hanger for Mill-construction

it into a wall, as it absolutely prevents dry-rot, and permits the joists to remain in case of fire, without throwing the wall. It also gives the load a good bearing on the wall. Fig. 17 illustrates the Duplex steel wall-hanger for larger beams, and Fig. 18 shows the Duplex extra-heavy wall-hanger for the heaviest

masonry-construction. These hangers bear the label of approval of the National Board of Fire Underwriters and are generally considered the best-designed wall-hangers now on the market. This hanger gives an extra bearing on the masonry and is so constructed that it reacts as a unit and distributes the load equally over the entire surface of the masonry. There is no tendency for a hanger of this




Fig. 19. Duplex Wall-hanger for Concrete Blocks

Fig. 20. "Ideal" Wrought-steel Beam-hanger

type to crush in at the edge of the masonry and straighten out, as is the case with some other types of wall-hangers. Fig. 19 shows the Duplex wall-hanger used in connection with walls constructed of concrete blocks. These hangers are often used in repair-work in party walls, as they avoid the cutting of large holes in the walls, and also provide an easy and simple method of carrying the joists clear of the walls. The Ideal hanger illustrated in Fig. 20 is made of wrought




Fig. 21. "Ideal" Wrought-steel Beam-hanger




Fig. 22. "Ideal" Wrought-steel Wall-hanger

steel and corrugated at the points where it is bent over. This reinforcement tends to prevent bending at these points. Fig. 21 illustrates another form of the Ideal hanger with holes for spiking to a timber. This hanger, also, is corrugated. In these hangers the full strength of the steel is retained as the fibers of the metal are not cut in forming them. They are made of wrought steel bars folded to the required shape. Fig. 22 shows the Ideal hanger riv-

a steel plate and in position to be built into a brick wall. Other illustrations of wall-hangers are given in Chapter XXII. The Van Dorn hanger, illustrated Fig. 23, is essentially a stirrup forged from high-grade steel. The few tests that have been made would seem to indicate that it develops a greater resistance to bending than the ordinary stirrup, while it gives a wider bearing



Fig. 22. Van Dorn Beam-hanger

Fig. 24. Van Dorn Wall-hanger

the joist and presents a much neater appearance. Fig. 24 shows the same hanger riveted to a bent iron plate, to build into brick walls. When the hanger is to be used over a steel beam the upper ends are bent to fit over the flange of the beam, as in Fig. 25. "Although I know of no test of the strength of a Van Dorn I-beam hanger, it would seem as though it must be much stronger than




Fig. 25. Van Dorn I-beam Hanger

Fig. 26. National Joist or Beam-hanger

pattern made for wooden beams, on account of the clinch over the flange of the beam. The Van Dorn hangers have been used in many important build-

ings. Figs. 26 and 27 show the general form of two other patented joist-hangers, which are forged from plate steel. Both of these hangers, also, are made to be

built into brick walls and to go over steel beams. The National hanger (Fig. 26) has a flange on top, which helps materially in distributing the load over the top of the beam as shown in figure. The larger hangers of this style have hole




Fig. 27. Lane Joist or Beam-hanger

trimmer which supports a load over a considerable floor-area that the stress

need be considered at all. From tests made on girder-hangers, it would appear that hangers usually develop great strength. A 14-in girder, sustained a load of 39 550 lb, when one side broke off short under the nipple projecting into the timber, the condition of the hanger after failure being shown in Fig. 28. A common stirrup made from  $\frac{5}{8}$  by  $2\frac{1}{2}$ -in wrought iron failed under a load of 13 750 lb by bending and pulling over the header, as shown in Fig. 29. A 6 by 12-in steel hanger "began to straighten out under a load of 13 300 lb, and failed to hold under a load of 18 750 lb."\* SINGLE hangers of the stirrup-type DO NOT BREAK, but fail by the bending up of the parts which lie over the top of the header

as shown in Fig. 29. They also appear to crush the wood under them particularly at the edges, to a very much greater extent than does the space between the Duplex hanger. With a DOUBLE stirrup the ultimate strength is measured by the strength of the iron. Thus, a double stirrup, made of  $\frac{5}{8}$  by  $2\frac{1}{2}$ -in wrought iron, was loaded up to 57 650 lb (28 825 lb on each side), when it broke at the lower corners. A single stirrup would of course be just as strong if it could be kept from bending. In actual construction the flooring over the beam to some extent prevents the top of a stirrup from springing up. The tests

Fig. 28. Result of Test of a Two-piece Beam-hanger

\* From data compiled by Mr. Kidder from a series of tests on beam-hangers and joist-hangers.

been made of two-part hangers show conclusively that where only a single hanger is used the holes which are bored in the header do not seriously affect its strength when the load is within the safe limit, and a test made at Baltimore, Md., August 24, 1904, with 12-in joists, spaced 12 in on center and suspended by these hangers let into a header formed of three 3 by 12-in joists, spiked together, would seem to prove that even when the holes are 12 in apart they do not seriously weaken the header. The only record of the failure of any form of hanger when in actual use in a building, of which I am aware, is that of a failure in Minneapolis, where a collapse of six floors of a warehouse, on Nov. 7, 1902, through failure of a wall-hanger made of a 4 by 2 by  $\frac{1}{4}$ -in structural-steel angle, which was sheared and bent, and riveted to an 8 by 16 by  $\frac{1}{4}$ -in gusset-plate. The failure was due to the crushing of the outer edge of the angle under the hanger, and the consequent bending up of the top portion. The actual load on the hanger was about 15 000 lb.\*




Fig. 20. Result of Test of Wrought-iron Stirrup-hanger

\*F. E. Kidder. See, also, *Engineering News*, Nov. 20, 1902.

## CHAPTER XXII

## WOODEN MILL AND WAREHOUSE-CONSTRUCTION

By

A. P. STRADLING

SUPERINTENDENT OF SURVEYS, PHILADELPHIA FIRE UNDERWRITERS'  
ASSOCIATION

## 1. Mill-Construction

**Definition.** The term **MILL-CONSTRUCTION** is commonly used to designate a method of construction brought about largely through the influence of the Boston Manufacturers' Mutual Fire Insurance Company of Boston, Mass., especially through the efforts of Mr. Wm. B. Whiting, whose judgment in mechanical matters, and experience and skill as a manufacturer were for many years devoted to the interests of insurance companies, and to the improvement of factories of all kinds. The extended use of this system and the improvements that have been made in it during recent years are probably due more to the influence of Mr. Edward Atkinson, President of the Boston Manufacturers' Mutual Insurance Company and Director of the Insurance Engineering Experiment Station at Boston, than to that of any other individual.

**Cost.** The purpose of mill-construction is to reduce the fire-risk to its lowest point without going to the expense of fire-proof construction. The increased cost of heavy timber, however, and in fact of all lumber, together with the lessened cost of the erection of the so-called **FIRE-PROOF TYPES**, constructed entirely of reinforced concrete, or built with protected steel frames and incombustible floors, and the recognition, also, of the obvious advantages of **FIRE-RESISTING CONSTRUCTION**, especially in the congested sections of cities, bringing these types into more general use. The cost of these latter types of construction is, in many instances, no more than the cost of various types of mill-construction.

**The Slow-burning or Mill-Construction Type.** The experience of years has entirely justified the use of this type. It renders possible a somewhat less costly, and at the same time, what is of great importance, a more effective system of fire-protection than can be installed in buildings of light construction, with the so-called **JOISTED FLOORS** and with the roofs made of boards supported by 2-in, 3-in, or 4-in joists. The entire subject of **SLOW-BURNING OR MILL-CONSTRUCTION** as applied to factories is most admirably described and illustrated in Report No. 5 of the Insurance Engineering Station of the Boston Manufacturers' Insurance Company, No. 31 Milk Street, Boston, Mass., from which the author has, by permission, taken and adapted many of the following illustrations and descriptions.

## 2. What Mill-Construction Is\*

(1) **Heavy Timbers.** **MILL-CONSTRUCTION** consists in so disposing of timbers and planks in heavy, solid masses as to expose the least number of corners or ignitable projections to fire; and to the end, also, that when fire occurs it may be most readily reached by water from sprinklers or hose.

\* From Report No. 5 of the Insurance Engineering Station of the Boston Manufacturers' Insurance Company, No. 31 Milk Street, Boston, Mass.



(2) **Fire-Stops.** It consists in separating every floor from every other floor by incombustible stops, by installing automatically closing hatchways and by encasing stairways either in brick or other incombustible partitions, so that a fire will be retarded in passing from floor to floor to the utmost consistent with the use of wood or any material not absolutely fire-proof.

(3) **Fire-Retardants.** It consists in guarding the ceilings over all specially hazardous stock or processes with FIRE-RETARDANT MATERIALS, such as plastering laid over wire lath or expanded metal, or over wooden dovetailed lath, following the lines of the ceilings and of the timbers and leaving no interspaces between the plastering and the wood; or else in protecting the ceilings over hazardous places with asbestos, air-cell boards, sheet metal, Sackett Plaster Board, or other fire-retardant.

(4) **Fire-Safeguards.** It consists not only in so constructing the mill, workshop, or warehouse that fire will pass as slowly as possible from one part of the building to another, but also in providing all suitable SAFEGUARDS AGAINST FIRE.

### 3. What Mill-Construction Is Not

(1) **Concealed Spaces.** Mill-construction does not consist in so disposing a great quantity of materials that the whole interior of a building becomes a SERIES OF WOODEN CELLS, or concealed spaces, connected with each other directly or by cracks through which fire may freely pass where it cannot be reached by water.

(2) **Size of Timbers, Fire-Stops, etc.** It does not consist of an open-timber construction of floors and roofs which resembles mill-construction, but which is built with light timber of insufficient size and with thin planks, without fire-stops or fire-guards from floor to floor.

(3) **Stairways.** It does not consist in connecting floor with floor by COMBUSTIBLE WOODEN STAIRWAYS encased in wood less than two inches thick.

(4) **Partitions.** It does not consist in putting in very numerous LIGHT, WOODEN DIVISIONS or partitions.

(5) **Sheathing and Furring.** It does not consist in SHEATHING brick walls with wood, especially when the wood is set off from the walls by FURRING, and even if there are stops behind the furring.

(6) **Varnish.** It does not consist in permitting the use of VARNISH on wood-work over which a fire will pass rapidly.

(7) **Glass, Fire-Shutters and Wire-Glass.** It does not consist in leaving windows exposed to adjacent buildings and unguarded by FIRE-SHUTTERS or WIRE-GLASS.

(8) **Painting and Dry-Rot.** It does not consist in painting, varnishing, oiling or encasing heavy timbers and thick planks, as they are customarily delivered, and thus making possible what is called DRY-ROT, caused by a lack of ventilation or opportunity to season.

(9) **Sprinklers, Pumps, Pipes, Hydrants, etc.** It does not consist in having even the best-constructed building in which dangerous occupations are followed without AUTOMATIC SPRINKLERS, and without a complete and adequate equipment of PUMPS, PIPES and HYDRANTS.

(10) **Finishing in Wood and Other Materials.** It does not consist in using more WOOD IN FINISHING a building after the floors and roof are laid than is absolutely necessary, since there are now many safe methods available at low cost for finishing walls and constructing partitions with slow-burning or in-

combustible materials. Accordingly if plaster is to be put on a ceiling and to follow the line of the underside of the flooring and the flooring-timbers, should be **PLAIN LIME-MORTAR PLASTER**, which is sufficiently porous to permit seasoning. The addition of a skim-coat of lime-putty is hazardous, especially if the overflooring is laid over rosin-sized or asphalt paper. This rule applies to almost all timber as now delivered. Examples of all of the faulty methods of construction above mentioned have been found in various buildings purporting to be of mill-construction, and they all form parts of what has sometimes been called **COMBUSTIBLE CONSTRUCTION**.

#### 4. Standard Mill-Construction

**Example of Standard Mill-Construction.** Fig. 1 shows a cross-section through a mill of the customary or **STANDARD TYPE** recommended by the **Bos Manufacturers' Mutual Insurance Company**, the details of construction being revised to May, 1908.

**Walls.** If additional stories are required, the walls may be increased in thickness according to the number of stories added, after a computation has been made of the loads which a **STANDARD FACTORY** may be called upon to sustain. Walls should be of brick and at least 13 in thick in the upper story, and their thickness should be increased in the lower stories to support additional loads. Plastered walls are often to be preferred to unplastered walls. Wind arches and door-arches should be of brick, and window-sills, outside door-sills and under-pinning of granite or concrete.

**Roofs and Floors.** The roofs should be of 3-in pine planks spiked directly to the heavy roof-timbers, and covered with five-ply tar-and-gravel roof. Roofs should incline from  $\frac{1}{2}$  to  $\frac{3}{4}$  in per ft, and incombustible cornices are recommended when there is exposure from neighboring buildings. Floor should be of spruce planks, 4 in or more in thickness according to the floor loads, spiked directly to the floor-timbers, and kept at least  $\frac{1}{2}$  in away from the face of the brick walls. In order to obviate the danger of cracking the walls, which sometimes results from the swelling of planks laid close against them, these spaces left between walls and floor-planks must be covered by strips of battens both above and below. In floors and roofs, the bays should be from 8 to 10½ ft wide, and all planks two bays in length should be laid to break joints every 4 ft, and grooved for hard-wood splines. Usually an overfloor of birch or maple is laid at right-angles to the planking, but the best mills have a double overfloor, a lower one of soft wood, laid diagonally upon the planks, and an upper one laid lengthwise. This latter method allows boards in alleyways and passageways to be easily replaced when worn, while the diagonal boards in the floors, reduce the vibration, and distribute the floor-loads more uniformly than the former method. Between the planking and the overfloor should be two or three layers of heavy, hard paper, laid to break joints, and each mopped with hot tar or similar material to make a reasonably water-tight as well as dust-tight floor. The usually rapid decay of the basement or lower floor in mills makes it desirable, whenever wood is not absolutely necessary, to make such floors of cement. If wooden floors are required, crushed stone, cinders or furnace slag should be spread evenly over the surface, and covered with a thick layer of hot-tar concrete. On this tarred felt is often laid, well mopped with hot-tar asphalt, and over it a flooring of 2-in seasoned planks, well pressed down and nailed on edge without perforating the water-proofing under it. The hard-wood boards of the overfloor are then nailed across the planks. Cement concretes promote decay of wood in contact with them. If extra supports are required for heavy machinery, independent foundations of masonry should

Fig. 1. Modern Mill-building of the Standard Type

provided. In view of the difficulties frequently met with in preserving basement floors of the ordinary timber construction, because of the lack of suitable ventilation underneath, and also in view of the rapid decay of timber and plank floors in bleacheries, dye-works, print-works, and the like, in which the floors quickly become saturated with moisture, artificial-stone floors are being used in many of the modern plants.

**Sizes and Kinds of Timbers.** All woodwork, not STANDARD CONSTRUCTION, in order to be SLOW-BURNING, must be in LARGE MASSES which present the least surface possible to a fire. No pieces less than 6 in in width should be used for the lightest roofs, and for substantial roofs and floors much wider ones are needed. Timbers should be of sound, long-leaf, yellow pine, and for sizes to 14 by 16 in, single pieces are preferred, or, timbers 7 to 8 by 16 in, are often used in pairs bolted together, without air-spaces between. They should be painted, varnished or filled for three years because of the danger of dry rot, and for the same reason, an air-space should be left in the masonry around the ends.

**Beam-Boxes, Column-Caps, etc.** Timbers should rest on CAST-IRON PLATES or BEAM-BOXES in the walls and on cast-iron caps on the columns. BEAM-BOXES are of value as they strengthen the walls when the floor loads are heavy and the distance between windows small; they facilitate the laying of bricks and the handling of the beams; and there is less danger of breaking bricks in putting the beams in place. They also insure proper air-spaces around

1

Fig. 2. Floor-timber on Wall-plate

Fig. 3. Roof-timber on Wall-plate

the ends of the beams. Fig 2 shows a floor-timber resting on a CAST-IRON WALL-PLATE with a lug for anchoring the timber to the wall. Fig. 3 shows a roof-timber resting on a CAST-IRON WALL-PLATE, an overhanging, open, wood cornice and a wrought-iron joist-anchor. Fig. 4 shows a CAST-IRON CAP and FINTLE for columns, and dogs for holding the floor-timbers together. Fig. 5 shows a roof-timber resting on a COLUMN-CAP cast to fit the slope of the roof; the timbers are held together by 1-in wrought-iron dogs. These diagrams are intended only as general illustrations of SLOW-BURNING or MILL-CONSTRUCTION. The details should always be adapted to the special conditions of the site and to the purposes for which the buildings are used.

Columns of yellow pine should be bored through the axis, making a 1½-in diameter hole, and should have ½-in lateral vent-holes near the top and bottom. The ends should be carefully squared. To prevent dry-rot, WOODEN COLUMNS

should not be painted until they are thoroughly seasoned. They should be set in **PINTLES** which may be cast in one piece with the cap, or separately. **CAST-IRON COLUMNS** are preferred by some engineers, and when a building is equipped with automatic sprinklers, such columns have proved satisfactory; but they

Be

Fig. 4. Post-cap and Pintle for Floor-timber and Columns

Fig. 5. Roof-timbers on Column-cap

are not as fire-resisting as wooden columns. **WROUGHT-IRON** or **STEEL COLUMNS** should not be used unless encased with at least 3 in. of fireproofing.

**Windows** should be placed as high and made as wide as possible to obtain the greatest amount of light, and the use of **RIBBED GLASS** is recommended for the upper sashes.

**Weight, Deflection and Vibration.** In computing the size of the timbers in ratio to the working-load, consideration must be given not only to the weights which are to be carried, but also to the **CHARACTER OF THE MACHINERY** which is to be operated on the floors. Beams of sufficient strength to support the weights may vibrate or deflect under the weight and action of the machinery; and there are, therefore, three factors, **WEIGHT, DEFLECTION AND VIBRATION**, which must be considered in determining the width and depth of the beams that are to be used in the structure.

**Objectionable Types of Construction.** "We do not approve what has been sometimes mis-called **MILL-CONSTRUCTION**, that is, longitudinal girders resting upon posts and supporting floor-beams spaced 4 ft. more or less, on centers. This mode of construction not only adds to the quantity of wood used, but the disposal of the timbers obstructs the action of the sprinklers, prevents the sweeping of a hose-stream from one side of the mill to the other, and the girders also obstruct the most important light, that from the top of the windows."

**Timber, Ventilation, Painting, etc.** Timbers, unless known to be thoroughly seasoned, should not be encased in any kind of air-proof plastering nor coated with oil-paints; white-wash, calcimine and water-paints may be used, but they are porous. As a rule, timbers should be **LEFT UNPROTECTED**, since a fire which will seriously impair and destroy heavy timbers will already have done its work upon other parts of the structure.

**Single and Compound Beams.** While, in general, **SINGLE BEAMS** should be used, in some instances it may be desirable to substitute **COMPOUND BEAMS**, made by fastening two or more beams or thick planks side by side. It is often easier to obtain well-seasoned lumber in small dimensions. Such **COMPOUND BEAMS** should be tightly bolted together without air-spaces, and owing to the danger of dry-rot, should not be painted or varnished for three years.

**Steam-Pipes.** If a mill is to be heated by conveying steam through pipes such pipes should be hung overhead.

**Cornices.** Wherever buildings are exposed or are liable to be exposed fire in the near future, the cornices should be of non-combustible construction preferably, the walls should extend above the roof-timbers.

**Glass, Frames and Shutters.** All openings in walls should be protected either by approved wire-glass in approved, metal frames or by standard fire shutters.

### 5. Belts, Stairways and Elevator-Towers

**Continuous Floors.** One of the most important features of **SLOW-BURN CONSTRUCTION** is to make each and every floor **CONTINUOUS** from wall to w




Fig. 4. Section through Tower for Elevator, Stairs and Belts

avoiding, as far as possible, holes for belt fire may be confined to the story in which owner, engineer or builder will, therefore main belts, in **BRICK TOWERS** or in sections

**Incombustible walls.** All openings in these walls should be protected by **STANDARD FIRE-DOORS**, preferably self-closing. In modern practice all belts and ropes which may be used for the transmission of power to the various rooms, are placed in **INCOMBUSTIBLE VERTICAL BELT-CHAMBERS**, from which the power is transmitted by shafts through the walls into the several rooms of the factory. There should be no unprotected openings in the inner walls of this **BELT-CHAMBER**.

**Shafts above Roof. Skylights.** All **SHAFTS** for **STAIRS**, **ELEVATORS**, **HOISTS**, etc., should extend at least 36 in above the roof, and all such shafts should be, if possible, on the outside of the building. Elevator and belt-shafts should be covered with thin glass skylights in metal frames, protected underneath with wire netting. Figs. 6 and 7 illustrate a section and plan of a **COTTON-FACTORY**, showing elevator, stair and belt-shafts arranged on the above principle. **HOISTS** should be in a separate tower rather than in manufacturing rooms.

The **Boiler-Plant** should be in a separate building cut off from the engine-room by a brick wall, and the openings in this wall should be protected by **AUTOMATIC, SLIDING, STANDARD FIRE-DOORS**.

### 6. Standard Storehouse-Construction

**Example of Storehouse-Construction.** Fig. 8 shows a cross-section through a fire-tower and Fig. 9 the first-story plan, including the elevator and stair-tower of a four-story storehouse.

**Area.** Buildings for this purpose should not, in general, exceed 5 000 sq ft in area. When used, however, for storage of non-hazardous goods, the area may be increased to 10 000 sq ft.

**Height of Stories.** Fig. 8. Four-story Storehouse. Section through Fire-tower. For storehouses, the height of stories should be made low enough (Fig. 10) to prevent overloading, and when used for case-goods, the **HEIGHT OF STORIES** should be sufficient to take two tiers of cases, with a 12-in. clear space under the beams to allow for the distribution of water from the sprinklers.

**Fire-Walls.** For convenience, as well as to separate the different hazards of raw materials and finished goods, the building should be divided into sections by **FIRE-WALLS** extending at least 36 in above the roof.

**One-Story Storehouses.** A **ONE-STORY STOREHOUSE** is recommended in place of the design just described, whenever there is a sufficient quantity of land at disposal for this purpose. The one-story building is cheaper, more convenient, and, when separated into small divisions by fire-walls, represents the safest method of storehouse-construction.

**Floors and Framing.** The **FLOOR-TIMBERS** and **ROOF-TIMBERS** should be of clear yellow pine, in single pieces, if possible. If necessary to use double timbers they should be bolted together without air-spaces between them. Tim-

bers should rest on cast-iron plates or beam-boxes in the walls, and on cast-iron caps on the columns. At least  $\frac{1}{2}$ -in air-spaces should be left around all beams built into the masonry, allowing free ventilation and preventing dry rot. Ce




Fig. 9. Four-story Storehouse. First-story Plan

views of yellow pine should have their end-surfaces cut square with the column axis.

**Floors.** The floors of such buildings should be continuous, without openings, and of the standard slow-burning construction, described under **STANDARD**



ISOMETRIC VIEW

Fig. 10. Four-story Storehouse. Isometric View

**MILL-CONSTRUCTION.** The flooring should be constructed as called for in **STANDARD MILL-CONSTRUCTION**. In order that the floors may be as near water-proof as possible, tarred paper, mopped with tar, should be applied as previously suggested. The floors in each story of the tower should be at least 1 in lower than the floor in the adjoining compartment, and the sills of the door openings to the tower should be inclined to make up the difference in level. The sill, also, of the outside door of the tower should be lower than the tower floor.



**Scuppers.** Water on the floors of the tower will ordinarily flow down the super-stairs, and the arrangement of the floor-levels indicated above will ordinarily prevent water from an upper story from flowing into one of the lower compartments, if it is escaping through the tower. Cast-iron SCUPPERS are used, and they should be set in the brickwork at frequent intervals, and so designed that they will carry away rapidly a maximum quantity of water from the floors of each compartment. To further the drainage of water, the floors should be inclined from the middle of the compartments to the scuppers. Fig. 11 shows the WIND-SHIELD SCUPPER\* which embodies the latest improvements.




Fig. 11. Detail of Wind-shield Scupper

In the old-style scupper only one flap is provided on the outside of the building. During winter and windy weather, this flap blows open and sometimes freezes open. This results in a continuous draft through the scupper and over the working floor of the factory or warehouse and necessitates an increase in the amount of heat furnished. The scupper shown in Fig. 11 corrects this condition by providing the light wind-shield on the floor-level of the scupper. When the outer flap blows open the wind-shield shuts off the draft from the outside. This scupper, in addition, acts as a fire-retardant when an adjoining building is burning, and when there is a tendency for the flames to communicate through an open scupper and ignite merchandise on the floor. The wind-shield, by shutting off the drafts and fire, acts as a retardant or shield to keep out the flames.

\* Manufactured by the Wind-Shield Scupper Company, 1 Madison Avenue, New York City.

**Tower for Stairways, Elevators, etc.** Access to the various stories obtained by means of a BRICK TOWER outside the main building, extending 36 above the roof, and containing STAIRWAYS, ELEVATORS, ETC., access to which




Fig. 12. Stairway-tower and Galleries at Side of Storehouse

obtained by open galleries at each floor-level. (See Fig. 12.) A door from the upper story of the tower affords a ready means of reaching the roof. AUTOMATIC HATCHES are not necessary for the elevator, as GUARD-GATES serve every purpose. If it is necessary to construct the tower for the elevator stairs inside of the building, access to it should be as shown in Fig. 13.




Fig. 13. Stairway-tower Inside of Storehouse

construction serves, also, as a FIRE-TOWER, part of the outside wall being omitted.

**Roof Walls and Parapets.** The WALLS should extend 36 in above the roof and the PARAPET should be laid in cement, because the moisture readily sorbed by the bricks would otherwise pass downward and make the walls of the top story damp. In some instances a course of bricks dipped in coal-tar is laid above the roof-level.

**Sprinklers, Standpipes and Hose.** Mills and storehouses should be protected throughout by AUTOMATIC SPRINKLERS and by inside STANDPIPE HOSE-EQUIPMENTS. Dry-pipe sprinklers should never be used unless it is practicable to heat the building. These systems should be planned and revised by a thoroughly reliable fire-protection engineer. (See, also, Chap. XXIII, pages 903 to 905.)

## 7. Example of One-Story Work-Shop

**Economy.** For work-shops on cheap, level land, and especially for buildings in which the stock is heavy, ONE-STORY BUILDINGS have proved to be more economical than higher buildings, in cost of floor-area, supervision, moving stock in process of manufacture and repairs to machinery, much of which can be run at greater speeds than when it is in high buildings.

**Warming and Ventilating. Window-Area.** Such buildings are readily warmed and ventilated, and heavy-plank roofs are free from condensation in cold weather. Window-areas should be as large as practicable, as a large window-area reduces the hours of artificial illumination. If the building is exposed to view from another building or buildings of hazardous occupancy, the windows should be of the Fenestra, Lupton or other equally good, steel construction, glazed with wire-glass. The forced circulation of heated air is a very desirable method of heating mills, and should be used in connection with overhead steam-heaters.

**Floors.** As wooden floors are subject to rot, the general floor-construction, if possible, should be of concrete or earth or some other non-combustible material. But as the dust rising from floors of such materials injures machinery, and as the dripping of oils weakens such floors and seems to make a WOODEN Wearing-Surface necessary, the following construction is recommended. Broken slag or stone, several inches in thickness and thoroughly rolled, is first laid down, and over this a 4-in layer of tar-concrete. On this is laid a 1-in thickness of asphalt, evenly rolled. Over this, 2 or 3-in hemlock planks, bedded on hot pitch, are laid and over them a  $\frac{7}{8}$  or  $1\frac{1}{8}$ -in maple floor, at right-angles to the planks.

**Column and Beam-Construction.** Figs. 14 and 15 show clearly the mode of COLUMN AND BEAM-CONSTRUCTION. No beams or other structural timbers should be painted or varnished until thoroughly seasoned.

**The Roofs** should be as called for under STANDARD MILL-CONSTRUCTION. TRUSSES in roofs are ordinarily from 8 to 20 ft on centers, the 3-in planks spanning the distance between the trusses as shown in Fig. 14, or resting on PURLINS less than 8 ft on centers, and running longitudinally, as in Fig. 15.

**Cornices and Gutters.** In Fig. 14, the overhanging OPEN CORNICE is shown, with a drip to the outside and without gutters. Roofs sloping back to side gutters, as shown in Fig. 15, are preferable. Projecting BRICK CORNICES, which protect the woodwork from outside fires, are shown in Fig. 15. If the building is exposed to other buildings of hazardous construction and occupancy, PAINTED BRICK WALLS and cornices are needed.

**Roof-Construction.** The roof-planks should be at least two bays in length, making joints every 3 ft; or, if purlins are used, the planks should cover at least two spaces between the purlins, and break joints as above. Roof-timbers should be well anchored to walls in a safe and suitable manner. While the GABLE form of roof may be used with this type of building, it may not be always necessary or advisable; and the types shown in Figs. 14 and 15 are types common for machine-shops, foundries, and similar buildings, in which increased head-room is required for traveling cranes. The middle section over the crane is often provided with SAW-TOOTH SKYLIGHTS with excellent results, and the side bays and others are made higher for galleries.

**Steel Structural Members.** In ordinary one-story machine-shops, or in buildings of similar nature, where wide spans or trusses are necessary, the use of STEEL STRUCTURAL MEMBERS is not objectionable.

**Fig. 14. One-story Work-shop. Roof-boards on Trusses**

with thoroughly mopped tarred felt under plank  
**Fig. 16. One-story Work-shop. Roof-boards on Purlins**

### 8. Saw-Tooth Roof-Construction \*

**The Great Advantages** and the increasing use of SAW-TOOTH roof-construction, and the lack of familiarity with it at many factories, make it desirable to outline important features.

**Two Typical Designs** are illustrated, Fig. 16, a TEXTILE WEAVE-SHED and Fig. 17, a design for a light MACHINE-SHOP or FOUNDRY. Other designs using light wooden trusses or reinforced-concrete walls, are applicable.

**Roof-Types.** It may be well to state here that while light roofs with 2- and 3-in joists and with light boards should never be used, and while the principles of SLOW-BURNING or MILL-CONSTRUCTION, with its heavy timbers, preferred, the increasing difficulty of promptly obtaining yellow-pine lumber of good dimensions, and its increasing cost, often necessitate the use of trusses and rather light timbers; but in no case should these timbers be less than 6 in in width nor of insufficient depth to carry the load. This, also, is in order that they may be SLOW-BURNING. The roofs in all cases should be constructed of planks and have wide bays.

**Steel Roof-Trusses.** The adaptability of the light forms of STEEL FRAMING TRUSSES, especially when wide spans are needed, often compels their use; and in plants having a safe occupancy, such as that of metal-workers, steel trusses are not objectionable, providing adequate sprinkler-protection with good water-supply is available to prevent quick failure of the steel work, or to heat from the combustion of the contents of the building or from the burning of the roof. Similar protection is, of course, needed in shops with wooden TRUSSES, if disastrous fires are to be prevented; but experience has shown that the STEEL-TRUSSED ROOF will fail much more rapidly than one of wood under similar conditions.

**Wooden versus Steel Columns.** WOODEN POSTS are nearly always preferable and should be given preference; but if light STEEL COLUMNS are necessary they should be well protected by insulating materials if they are in rooms containing combustibles, as the column is the vital part of the roof-support.

**Advantages of Saw-Tooth Roofs** may be outlined as follows:

(1) **Uniform Diffusion of Light** throughout the room, thus making the space in it available. With all interior surfaces painted white and with rich glass in the sashes, the DIFFUSION OF LIGHT is almost perfect.

(2) **Better and Cheaper Lighting.** Greater adaptability for lighting large floor-areas in wide buildings with low head-room when compared with what is necessary in wide buildings with the ordinary form of monitor-sky-light. Saw-tooth roofs furnish the true solution of the problem of excluding the direct rays of the sun and obtaining the very desirable north light. They result in greater ECONOMY IN LIGHTING, as they lower the fixed charges due to the small number of hours per day during which artificial light is necessary.

(3) **Better Working-Conditions**, especially in textile-mills, thereby increasing production and encouraging permanency of employees.

(4) **Special Adaptability to many Industries.** The SAW-TOOTH form is especially adapted to weaving and similar processes in textile-factories, to machine-shops, foundries doing light work, and similar processes, such as as

\* Taken and adapted by permission from the Boston Manufacturers' Mutual Insurance Company's specifications for the construction of saw-tooth roofs.

**Fig. 16. Saw-tooth Roof for Textile Weave-shed**



Fig. 17. Saw-tooth Roof for Machine-shop



ing and drafting, and to some dye-houses where careful matching of colors is necessary.

**Disadvantages of Saw-Tooth Roofs.** While the testimony of those who have had experience with SAW-TOOTH ROOFS is almost uniformly favorable, some difficulties have been experienced, practically all of which may be summed up as due to either faulty design or poor workmanship. The difficulties in general are caused by

- (1) Leaks, due to severe conditions during winter in our northern climates.
- (2) Poor Ventilation.
- (3) Excessive Heat when roofs are thin.
- (4) Excessive Condensation on the underside of roof and glass when the temperature outside is low and there is considerable moisture in the rooms.

**Approved Methods of Construction.** The following suggestions show how the difficulties mentioned may be obviated if the APPROVED METHODS are applied to special cases by competent engineers or architects. What is good ENGINEERING from the view-point of the manufacturer can also be good FIRE-PROTECTION ENGINEERING, and any design should be adapted to both if the best interests of the manufacturer are to be served:

(1) **Diffused Indirect Sunlight.** As it is desirable to avoid direct sunlight and at the same time obtain an abundance of light, perfectly diffused, the SAW-TEETH should face approximately north and the glass should be inclined to the vertical to take advantage of the brighter light in the upper sky and to prevent cutting off the light by the saw-tooth immediately in front; and, above all, to assure the DIFFUSION OF THE LIGHT over the floor rather than on the under side of the roof-planking.

(2) **Angle of Glass.** For the glass an angle of from  $20^{\circ}$  to  $25^{\circ}$  from the vertical and an angle of approximately  $90^{\circ}$  at the top of the SAW-TOOTH will be about right, the variations depending upon the amount of light required and the latitude. A sharper angle at the top is not needed, as it increases the cost, and makes more roof to be covered and larger spans; more glass, also, is required in proportion, and the light is not as good, as more light from the sky is lost and too much light is thrown on the under side of the roof.

(3) **Glazing-Details.** DOUBLE GLAZING with a space left between the lights of glass is preferred on account of its conducting qualities; but it is not always necessary, except in the more northerly countries. The inside glazing should be done with factory-ribbed glass, set with the ribs vertical and facing in. Shadows cast by trusses are then almost unnoticeable.

(4) **Gutters and Conductors.** CONDENSATION-GUTTERS are needed inside, at the bottom of the sashes, and they should be drained through INSIDE CONDUCTORS and not to the outside under the bottom of the sashes, as these latter admit cold air and are liable to freeze.

(5) **Valleys between the SAW-TEETH** should be flat, from 14 in to 2 ft in width and pitched  $\frac{1}{2}$  in per ft towards the conductors, which should be of ample size, and not much over 30 ft apart, and preferably less. The necessary PITCH may be obtained by cross-pieces of varying heights set on top of the trusses, and thus providing hollow spaces.

(6) **Prevention of Leaks.** LEAKS, which are common faults, may ordinarily be prevented by a careful design of the gutters, valleys and sashes, and by insisting on good workmanship and materials. The roof-covering of asphalt pitch should be continuous through the valleys and extend up to the glass.

One form of construction understood to have been very satisfactory is shown in Fig. 18 and in connection with it, reference should be made to the papers on discussion on SAW-TOOTH ROOFS in Trans. Am. Soc. M. E., 1907, vol. 28, which contain much of value.

(7) **Warming and Ventilation.** Experience has demonstrated the advantage of a combination of DIRECT RADIATION with a FAN sufficient only for VENTILATION and TEMPERING the heat of the room. Heating-pipes should usually be placed overhead and directly under the front of the SAW-TEETH, and run the

entire length, and this position assist preventing condensation. Where there is no moving shafting some forced circulation is necessary, and it is best obtained by a fan, which draws the air from either the dry basement or from outside as may be required, and discharges it over the heating-coils to the space above. In weaving and similar rooms this is especially necessary and advantageous in promoting the health and comfort of the employees and in making the working-efficiency

63

Fig. 18. Detail of Valley of Saw-tooth Roof

greater. Ventilation and cooling of these large areas with comparatively few stories must not be neglected. Ample vents are needed at the top in the form of large metal ventilators with double walls and tight dampers. They are recommended in place of pivoted or swinging sash, which are apt to break in driving storms, and when open, allow dirt to blow in from the street. Good windows are advised in side walls and experience has shown their value

(8) **Details of Framing and Construction.** The FRAMING of the SAW-TEETH may be of timber, steel or reinforced concrete. The design should be such as will obstruct the light as little as possible, strong enough to hold snow without sagging, and stiff enough to carry shafting motors, etc., when they are to be overhead. When wood or steel is used the roof-plank should be 3 in or more in thickness spanning bays from 8 to 10 ft in width. HOLLOW SPACES in roofs should not be permitted. They are very undesirable from a fire-standpoint, and any condensation which may take place in them during cold weather soon rots both planks and sheathing. SHEATHING even without spaces behind it, is a more or less objectionable feature, as it is readily combustible; but if it is used it should be applied directly to the underside of the roof-planks, with only a layer of some insulating material between them so that there will be no concealed spaces. If 3-in planks are sufficient for a flat roof, they should be, also, for a SAW-TOOTH roof; and with a good circulation of air there should be no trouble, except in wet rooms. In such rooms the

bound to be condensation, whether they are under a roof or under the floor of a room above, unless large quantities of dry air are discharged into them.

(9) **Cost.** SAW-TOOTH ROOFS necessarily cost more than FLAT ROOFS, as there is practically the same amount of roofing as in flat roofs and, in addition, the cost of windows, glazing, flashing, conductors, condensation-gutters for skylights, and a somewhat larger cost for heating. The additional cost of these items does not, however, fairly represent the comparative cost, as there should be considered the total cost of the building compared with that of an ordinary one with sufficiently high stories and with a width narrow enough to give the required light. When this is done the slight additional cost is far outweighed by the advantages gained for work requiring very good light.

## 9. Mill-Construction as Applied to Warehouses

**Cost.** Owing to the increasing cost of heavy timbers for wooden construction, to the lower cost of the so-called FIRE-PROOF CONSTRUCTION, and also to the better FIRE-RESISTING qualities of the latter, owners, architects and builders should carefully compare the cost of construction, and also the cost of insurance of the two types, before deciding on the one to be used. The difference in the cost of construction between these two types is so small, that in many localities the lower cost will be in favor of the REINFORCED CONCRETE or other type of FIRE-PROOF CONSTRUCTION. The cost of construction is also in favor of the FIRE-PROOF TYPE, where both long spans and strength are required.

**Timber-Spacing for Sprinklers.** Warehouses of MILL-CONSTRUCTION should be built so as to allow the best possible distribution of water from AUTOMATIC SPRINKLERS, with the least possible obstructions, and floor-timbers, therefore, should be as few as the floor-loads will allow. There should be no concealed spaces of any kind in the building. To insure the greatest efficiency of sprinkler-systems, it is better to adapt the timber-spacing to suit the sprinklers, rather than to arrange the sprinklers to suit the timber-spacing.


**Mill-Construction Adapted to Warehouses.** The features of bad construction mentioned under WHAT MILL-CONSTRUCTION IS NOT are as objectionable in warehouses as in factories, while the construction advocated for mills may be used with almost equal advantage in the erection of warehouses. But as the latter are usually erected in the more thickly settled portions of a city, they are more subject to the dangers of a conflagration; and it should be understood that even the best SLOW-BURNING CONSTRUCTION will stand but a short time after a fire has obtained a good headway, the main object of MILL-CONSTRUCTION being to retard the spreading of fire by the use of heavy timbers and the absence of concealed spaces. In applying the principles of MILL-CONSTRUCTION to warehouses, therefore, the general principle of using large timbers placed as far apart as the loads will permit, and of avoiding all concealed spaces, should be constantly kept in mind.

**Warehouse-Floors,** however, are generally required to sustain heavier loads than are found in woolen and cotton-mills, and hence require heavier construction. While WAREHOUSE-FLOORS are quite often built with transverse girders, 8 or 10 ft apart, the spaces being spanned by flooring from 4 to 6 in thick, the more common method of construction is to use one or more lines of longitudinal girders supporting floor-beams spaced as far apart as possible, preferably at less than 8 ft on centers.

**Area and Height.** The AREA of buildings of this type should be, preferably, over 7 500 sq ft, and in no case should it exceed 15 000 sq ft between fire-walls. If buildings of LARGE AREA are required, it is advisable to divide them into

separate sections by fire-walls, thus reducing the liability to one fire, and affording an opportunity of storing hazardous goods in one or more sections, and non-hazardous or less hazardous goods in the remaining sections. When ground is available, it is better to have a building of **LARGE AREA AND LOW HEIGHT** divided into fire-sections, than to have a building of **LESSER AREA AND GREATER HEIGHT**, as the former construction affords a more economical handling of goods, and less concentration of values. Buildings of this type should be limited to 65 ft in height, and to six stories, thus discouraging the overloading of floors. Piled goods should be kept at least 18 in away from beams, thus allowing for the distribution of water from the sprinklers.

**Walls** should be of brick, and not less than 13 in thick in the upper stories and they should be increased in thickness on the lower floors to take care of additional loads. **PARTY WALLS** should be increased at least 4 in in thickness and all walls should be laid in cement mortar, should extend above the roof at least 36 in and be coped with stone, salt-glazed terra-cotta, or similar non-combustible materials. **OPENINGS IN DIVISION WALLS** should be limited to few as possible, not over three in each story, they should not exceed 80 sq ft each in area, and should be protected by double, automatic, sliding fire-doors as specified elsewhere. (See Chapter XXIII, page 907.)



Note: Walls of brick or other approved material, built solidly from foundations to at least 36 inches above roof.  
Stair-treads, etc., of fire-proof material.

Fig. 19. Tower Fire-escape. Outside-balcony Entrance

**Openings in Walls.** As a protection against fires from surrounding properties, **OPENINGS IN OUTER WALLS** should be small, limited to as few as possible and protected by standard fire-shutters and doors, or standard wire-glass windows. If the surrounding buildings are of hazardous occupancy or inferior construction, and the distance between the warehouse and the latter but a few feet, shutters are preferable, as wire-glass windows are recommended elsewhere where the exposures are moderate. Even though the building is not exposed

fire from other buildings, the protection of WINDOW-OPENINGS may prevent the spread of fire from story to story through the windows.

Girders and Beams which support the floors and roof should be SINGLE MEMBERS, not less than 6 in in least dimension, and with a sectional area of not less than 72 sq in; while columns should be not less than 8 by 8 in in cross-section in the upper story, and should be increased in size in the other stories to take care of any additional loads. The beams and girders should be SELF-RELEASING (Fig. 2), and the floors should be built as outlined under STANDARD MILL-CONSTRUCTION, page 760, inclined at least 1 in in 20 ft, made as nearly water-proof as possible, and scuppered to the outside of the building. These cuppers should be set in brick-work at frequent intervals, of sufficient size to carry off the maximum amount of water from each floor, and so constructed that they will prevent the admission of cold air to the building. (See Fig. 11.)

Towers. The floors should be continuous from wall to wall, avoiding holes for belts, stairways, elevators, etc. All such openings should be enclosed in a BRICK TOWER or in TOWERS extending not less than 36 in above the roof, coped at the top, and accessible from each story by means of an outside balcony (Fig. 19).




Fig. 20. Tower Fire-escape for Adjoining Buildings

where it is impossible, owing to the location or otherwise, to have these openings on the outside, they should be placed in BRICK TOWERS constructed inside the building and connecting with an entrance to a fire-proof vestibule, open to the weather. There should be openings from each story to the vestibule, each protected by standard fire-doors (Fig. 20).

Gravity-Tanks for Automatic Sprinklers are usually placed on extensions of such towers, and they should be built to carry the additional load imposed. Access to the roof of the building may be had from a window or windows located in the tower, and such opening or openings should be protected by fire-shutters, especially where the tower is elevated a sufficient distance to allow a tank to be placed inside of the tower, thus preventing flames from gaining access to the tower and destroying the tank and tank-supports.

Boilers should be, preferably, in a separate building, cut off by stand fire-doors from the warehouse; or, if in the main building, should be located in a room of FIRE-PROOF CONSTRUCTION, access to which should be from outside the building only.

Structural Steel Members should never be used in this type of construction as they will not resist even a moderate fire. If used, they should be protected with fire-proof material. The lintels should be brick arches and not solid sections.

## 10. Steel and Iron Structural Members in Warehouse-Construction

**Metal versus Wooden Standard Members.** Owing to the fact that a beam or column of STEEL or WROUGHT IRON when heated will fail by buckling or bending very much sooner than an equivalent beam or post of WOOD, it is important that such members be of WOOD, provided that the WOODEN BEAMS have a sectional area of at least 72 sq in, and are not less than 6 in in least dimension, and that WOODEN COLUMNS have a sectional area of not less than 8 by 8. CAST-IRON COLUMNS, also, will generally fail in fire and water sooner than wooden columns.

**Fireproofing Steel Beams and Girders.** When STEEL BEAMS and COLUMNS are used, fireproofing is necessary to make them as FIRE-RESISTING



or

the floors. Such beams and girders may be fireproofed as shown in Fig. 21. Metal-wire mesh should be placed over the concrete shown, and tied to the beams and girders by metal clips; and insure rigidity during pouring of the concrete and to keep the mesh in alignment, forms should be used. The concrete should be poured before the floors are laid, after the wooden beams are in position. At

Fig. 21. Fireproofing of Steel Beam with Concrete and Plaster

completion, the insulation should be at least 1 in at the edges of flanges, 2 in under the lower flange of the beam and 3 in under the lower flange of the girder. The webs should be filled solid. Where there is little stock of a combustible nature in the building, the beams may be protected as shown in Fig. 22. (See, also, pages 863 to 866.)

**Fireproofing Metal Columns.** COLUMNS, either STEEL, WROUGHT-IRON or CAST-IRON, should be protected even to a greater extent than girders and beams and should have at least 3 in of concrete at the flanges, at least 1½ in at all edges, and be filled solidly against the webs. Fig. 23 shows two columns protected by concrete held by wire mesh on ½-in rods, and all securely held to the columns by metal clips. Forms should be used and the concrete should be poured while the girders and beams are protected. Steel beams, girders and columns are difficult to protect, especially at the intersections of steel and wood, and insulating material can best be applied before the floors are laid. The fireproofing of these members will be of little avail, unless the materials are of

plied to the metal members, and applied by workmen who understand such

At least  
one side of  
each corner  
flattened

At least  
outside of

Between  
wrap layer  
of metal is  
thickness



well  
wet,

dry  
to  
dry.

used

or  
id up  
a place,

Fig. 22. Fireproofing of Steel Beam with Metal-lath and Plaster



Fig. 23. Fireproofing of Steel Columns with Concrete and Plaster

24 illustrates the PROTECTION OF A ROUND COLUMN by reinforced concrete, the concrete is held in position by wire mesh on metal furring, held in position by metal clips or ties. The fireproofing should be at least 4 in. thick, and forms should be used in casting the columns. In addition to the above reinforcements for these columns, lateral reinforcement should be provided by means of iron rods wound spirally around mesh, and placed 12 in. apart. After the forms are removed, and the wooden floors are laid, the columns and girders should be covered with a 1-in. thickness of hard plaster, filling all interstices between the woodwork and the insulation. Tile,

Fig. 24. Fireproofing of Cast-iron Column with Concrete and Plaster

owing to the difficulty of properly bonding it, is not as effective as concrete but if securely bonded by means of metal, it is quite satisfactory. Fig. 26 illustrates the PROTECTION OF A GIRDER AND A COLUMN by means of tile. There are other equally efficient methods of beam and column-protection, described in Chapter XXIII. In buildings of warehouse-construction, heavy goods are




Fig. 26. Fireproofing of Steel Columns and Beam with Tile

handled, and it may be advisable to protect the base of each column with she metal to a height of 36 in above the floor, to prevent any weakening of the fireproofing. (See, also, pages 822 to 827, Figs. 1 to 13.)

Pipes for Gas, Water, etc., should not be enclosed in column or girder insulation. (See, also, page 827.)


### 11. Structural Details of Mill-Construction as Applied to Factories and Warehouses

**Column, Girder and Joist-Framing.** Fig. 26 illustrates the method of carrying the girders from the walls, posts, etc., the bottom post resting on a steel POST-BASE. The first floor above the basement is shown with longitudinal girders only, and heavy mill-flooring set on them. The girders are framed to the post in a steel POST-CAP, and are hung clear of the wall in an approved steel WALL-HANGER. The next floor above shows the construction in which joists are framed into the girders by means of JOIST-HANGERS. The framing at the post, also, is done by means of a DUPLEX FOUR-WAY POST-CAP, while the girder is built into the wall in a DUPLEX WALL-BOX. The JOIST-HANGERS are used singly or opposite each other as required and are bolted to the girders thus tying the building laterally. The upper floor shows the joists resting on the girder. This construction, however, does not conform to strict mill CONSTRUCTION, as it exposes a larger amount of timber-surface. The girder is shown built into the wall and resting on a WALL-PLATE. This distributes the load over the masonry but is not as effective in preventing dry-rot as the WALL-BOX OR WALL-HANGER.

**Steel and Malleable-Iron Post-Caps and Bases.** Fig. 27 illustrates several details of construction which may be used. The bottom post rests on a steel POST-BASE. The POST-CAP shown on the bottom post is a DUPLEX FOUR-WAY



POST-CAP, while the POST-CAP above it is one of the malleable-iron type, approved by the National Board of Fire Underwriters. The POST-CAP shown below, also, is of malleable iron and intended for lighter construction or for girders which run across the post as shown. The girders in every case are secured to the wall by means of approved WALL-HANGERS and the beams are supported by the girders in malleable-iron JOIST-HANGERS.



Mill-construction. Column, Girder and Joist-framing

**Post-Caps and Bases.** Fig. 28 illustrates other details of construction. The lowest post rests on a heavy, cast-iron, ribbed POST-BASE. The girders are carried at the post by means of heavy, cast-iron caps built into the wall in cast-iron WALL-BOXES. When cast-iron POST-CAPS it is essential that it be made extra-heavy, as cast iron shrinks on account of the uneven shrinkage when cooling, which creates stresses and weakens the caps. Flaws, also, may develop

during the manufacture which weaken the caps and greatly impair the safety of the building. An objection to cast iron is its tendency to crack and break during a fire when cold water is thrown on it. The POST-CAPS shown in Fig. are of cast iron for the first and second floors, Duplex steel for the third floor and malleable iron on the top post.

Fig. 27. Mill-construction. Malleable-iron Post-caps and Bases

**Duplex, Combination Post-Cap.** Fig. 29 illustrates the use of the DUPLEX COMBINATION POST-CAP on the bottom post. This cap is made with a malleable iron lower part and a steel upper part. The POST-CAP shown on the second post is called the IDEAL POST-CAP and consists of a steel upper part with angles riveted underneath to fit the post. The cap shown on the top post

Fig. 28. Mill-construction. Cast-iron Post-caps and Bases

**Steel Post-Caps.** Fig. 30 illustrates various forms of steel POST-CAPS. The LOZAL POST-CAP is shown on the bottom post and the VAN DORN POST-CAP on the post next above. On the top post the STAR POST-CAP is shown. This has a base for which the top of the post must be slotted to receive it. Steel joist-

HANGERS are shown for the two lower floors. The IDEAL JOIST-HANGER illustrated in the lower floor. It is spiked to the sides and top of the girder. The VAN DORN JOIST-HANGER is shown in the second floor, while the old-style STIRRUP is shown in the top floor. The WALL-HANGERS illustrated are of the approved type.

Fig. 29. Mill-construction. Combination Post-caps, etc.

**Framing Steel Beams and Girders.** Fig. 31 illustrates the use of I-BEAMS in place of WOODEN GIRDERS and their connections with wooden beams. In this kind of construction it is necessary to fireproof the steel beams, as they are more readily affected by heat in case of fire than large wooden timbers. Intense heat often causes them to collapse and ruin a building. The HANGERS

shown in the first floor is used where the I beams and wooden beams are of the same height. This HANGER provides an extra bearing for the timber and has proved very satisfactory. The HANGER shown in the second floor is used when it is necessary to raise the wooden beam above the lower flange of the steel beam. This HANGER brings all the load on the lower flange of the I beam and

Fig. 30. Mill-construction. Steel Post-caps, etc.

provides an anchorage for the wooden beam. It is used singly or in pairs on the I beam as required, and is bolted through the web of the I beam. This has been found to be a very economical and efficient construction. In the third floor the wooden beam is shown framed to the I beam by means of a SHELF-PLATE. With this form of construction it is necessary to rivet the SHELF-

Fig. 21. Mill-construction. Framing Steel Beams and Girders

ANGLE to the web of the I beam. The upper detail shows the old-fashioned STIRRUP passing over the top flange of the I beam and carrying the wood beam. The POST-CAPS shown are the DUPLEX STEEL POST-CAPS which are approved by the National Board of Fire Underwriters.

## 12. Connections of Floor-Beams and Girders

**Girder-Hangers and Joist-Hangers.** To render the construction, and particularly the girders, **SLOW-BURNING**, it is important to have no hollow spaces between the top of the girders and the flooring, that is, to have the top surface

of the floor-beams flush with that of the girders. This, of course, necessitates framing the floor-beams into the girders. For **HEAVY CONSTRUCTION** the only kind of framing that is permissible is one in




Fig. 32. Duplex Hanger for Heavy Floor-beams

Fig. 33. Framing I Beam and Wooden Beam of Same Depth

which some kind of **JOIST-HANGER** is used. The various kinds of **JOIST-HANGERS** now in the market have been illustrated and commented on in the last part of Chapter XXI. When the floor-beams are 6 by 12 in or larger in cross-section, and the girders are of wood, the author would give the preference to the **DUPLEX HANGER** shown in Fig. 32. (See, also, pages 752 and 753.)

If **STEEL-BEAM GIRDER**s are used in place of **WOODEN GIRDER**s, there are several methods in use for framing the wooden beams.

Fig. 33 shows a steel I beam, and a wooden beam of the same depth framed into it resting on its lower flange.

In most cases, however, this does not afford a sufficient bearing for the wooden beam.

Fig. 34 shows a **SHELF-ANGLE** bolted to the web of the I beam. Whenever this method of supporting the beams is used, enough bolts or rivets should be used to support the beam carried by the **SHELF-ANGLE**. Each  $\frac{3}{4}$ -in bolt may be considered to support 3 000 lb on each side of the girder, each  $\frac{3}{8}$ -in bolt, 4 000 lb.

The methods shown in Figs. 35 and 36 are sometimes used, but are open to objection on account of the weakening of the wooden beams when loaded.

Fig. 37 shows a **STIRRUP-TYPE** of hanger. This construction permits the




Fig. 34. Wooden Beam Framed to I Beam with Shelf-angle




Fig. 35. Wooden Beam Framed to I Beam with Wooden Cleat

Fig. 36. Wooden Beam Framed to I B with Shelf-angle




Fig. 37. Wooden Beam Framed to I Beam with Stirrup-hanger




Fig. 38. Wooden Beam Framed to I B with Duplex Hanger




Fig. 40. Wooden Beam Framed to I Beam with Duplex Box-hanger





Fig. 39. Wooden Beam Framed to I B with Duplex Shelf-hanger





ing of the wooden beam at any desired height, and has proved satisfactory. These hangers can be used with any depth of beam or girder, and are furnished by all manufacturers of steel JOIST-HANGERS of the various types, as well as by blacksmiths who can make WROUGHT-IRON STIRRUPS. Fig. 38 shows the DUPLEX-TYPE OF HANGER for framing a wooden beam flush with the lower flange of the I beam. This hanger is attached by means of bolts. Fig. 39 shows




Fig. 41. Floor-framing with Van Dorn Hangers and Post-caps

the same design of HANGER, with the SHELF-CONSTRUCTION used to carry the wooden beams up to 4 in above the lower flange of the I beam. Fig. 40 shows a HANGER for carrying the wooden beams 4 in or more above the lower flange of the I beam.

The HANGERS described in Figs. 38, 39 and 40 are all of the DUPLEX TYPE, and are so constructed that all the load is carried on the lower flange of the

Fig. 42. Floor-framing with Duplex Hangers and Post-caps

beam, which is a very satisfactory and ideal construction whenever it is necessary to frame wooden beams into and not rest them on the I beams. The Duplex is a very economical one for framing wooden beams to I beams, as the holes for attaching these HANGERS can be punched while the steel is being fabri-

cated, and the HANGERS are attached to the steel beams by means of bolts and the wooden beams are put in place. These HANGERS are provided with one or lag-screws for anchoring the wooden beams securely to the steel girders. Fig. 41 shows a floor-framing with the VAN DORN STEEL HANGERS. Fig. 42 shows the floor framed with the DUPLEX TYPE OF HANGER AND POST-CAP. The same principle of construction is applicable to larger wooden beams spaced farther apart.

### 13. Wall-Supports and Anchors for Joists and Girders

**Box Anchors, Wall-Hangers, etc. Anchoring.** In a warehouse intended to be constructed on the SLOW-BURNING PRINCIPLE, the floor-beams and girders should be anchored and supported by walls in such a way that in case the beams are burned through, the floor may fall without injuring the walls, and where large timbers are used, provision should be made against the possibility of dry rot.

**Box Anchors.** The method of supporting beams in MILL-CONSTRUCTION as originally developed in the New England mills is shown in Fig. 43. This fulfills the requirements alluded to above, but it weakened the walls to some extent. The GOETZ CAST-IRON

Fig. 43. Early Form of Beam-support in Mill-construction. This method of supporting beams in mill-construction as originally developed in the New England mills is shown in Fig. 43. This fulfills the requirements alluded to above, but it weakened the walls to some extent. The GOETZ CAST-IRON



Fig. 44. Goetz Box Anchor for Wooden Beams

Fig. 45. Goetz Box Anchor for Wooden Beams

BOX ANCHORS shown in Figs. 44, 45 and 46 and the DUPLEX WALL-BOX shown in Fig. 47 are decided improvements on the anchor shown in Fig. 43, as

and all the advantages of the latter without weakening the walls, unless the beams are very wide. The WALL-BOX as shown in Fig. 47 is made of a malleable-iron bottom plate and a steel box above. It has a rib on the plate at the back, which extends up and down, and acts as a secure anchorage in the brickwork. These WALL-BOXES are made wedge-shape, so it is therefore possible to pull them out of the wall. The more weight there is on the beam, the stronger will be the bond that holds the beam to the box and the box to the wall.

In case of fire or accident, the joists can burn through or break and in falling they can free themselves from the anchorage and leave the wall standing.

Fig. 46. Goets Box Anchor for Wooden Girders

The wall is not even weakened by the space left in it, because the box remains, and the crushing strength of this CAST-IRON BOX is much greater than that of the wall. No break or breach is made in the wall, and the box that remains, securely held, forms a space for the easy replacement of the wooden beam. The box provides a perfect and secure foundation for each beam.

Even from a defective flue cannot ignite a beam-end, because it is protected by a ventilated, CAST-IRON BOX. The WALL-BOXES have air-spaces, also, in the sides,  $\frac{1}{2}$  in wide, which permit a circulation of air around the ends of the beams, effectually preventing dry rot. If timber is wet or unseasoned these wall-boxes allow it to dry out after it is put in the building. The average weight of a box like that shown in Fig. 45, for 2 by 12-in joists, is 10 lb.




Fig. 47. Duplex Wall-box with Ribbed Plate

**Wall-Hangers.** Another device for obtaining the same results in a different way is the WALL-HANGER.

Figs. 48 and 49 show DUPLEX WALL-

HANGERS for large timbers. The hanger shown in Fig. 49 is made of open-hearth steel and is extra-heavy. Each of these hangers is provided with a plate which has 6-in bearing on the wall, and the bearing of the timbers on the hanger is also 6 in. For beams not exceeding 10 in in breadth there is probably little choice between the BOX ANCHOR, Fig. 46, and the WALL-HANGERS, Figs. 48 and 49, except perhaps in the price and appearance. When the WALL-HANGER is used, no hole is left in the wall, and a saving of 6 in in the length of the beams is effected, which in some cases would be a consideration. For girders 12 by 14 in upwards in cross-section, the author believes that the hanger shown in

Fig. 49 is preferable to the BOX ANCHOR. WALL-HANGERS made from STIRRUPS should not be used for heavy beams. The use of any one of the hangers




Fig. 48. Duplex Wall-hanger for Large Wooden Girder




Fig. 49. Duplex Extra-heavy Wall-hanger for Large Wooden Girders

boxes is obviously greatly superior to the ordinary method of anchoring beams or girders to walls, and the use of such hangers will undoubtedly save much trouble which would be caused by the falling of the walls. These are almost invariable




Fig. 50. Application of Wall-hanger to Brick Wall

pulled down by the ORDINARY IRON ANCHORS when the beams fall. Fig. 50 shows the application of a WALL-HANGER.

#### 14. Weakness of Wrought-Iron Stirrups when Exposed to Fire

**Stirrups and Fire-Tests.** Referring to this subject, Professor J. B. Johnson of Washington University, said: "The recent fire-tests of STEEL STIRRUPS in brick walls which were made under my supervision in this city (St. Louis) show very conclusively that unprotected stirrups are extremely dangerous. These stirrups become red-hot in a few minutes and then rapidly char and burn away the ends of the beams; and they also bend down, so that in from twenty to thirty minutes after the fire reaches the stirrups, the beam is dropped right out of the twisted steel by the straightening out of this bend or twist."

The Duplex Hangers possess an advantage over STEEL STIRRUPS because, being of malleable iron, they are not as quickly affected by heat, there are no twists or bends to straighten, and the bearing in the trimmer or header is to a great degree protected by the form of construction. During the severe fire at Paterson, N. J., February 9, 1902, some DUPLEX WALL-HANGERS were subjected to a most severe test without apparent injury. It is undoubtedly desirable that all structural iron should be protected from fire, but it is almost impracticable to effectively protect the STIRRUPS used in connection with wooden beams without going to a greater expense than the character of the construction warrants.

### 15. Post and Girder-Connections

**Iron Cap-Plates, Wooden Bolsters, etc.** Whenever a building is constructed with wooden posts extending through several stories, each upper post should rest on an **IRON CAP-PLATE**, fitted over the post below, and never on a girder or even on a **WOODEN BOLSTER**. A **BOLSTER** would not be objectionable except for the fact that the pressure under the post is generally sufficient to crush the fibers of any kind of wood. Then, too, there is always some settlement due from shrinkage. As posts are used expressly for the support of beams and girders, the **IRON CAPS** must, of course, extend sufficiently beyond the upper post to afford ample bearing for the end of the girder. This bearing in square inches should be equal to at least one-half the load on the girder divided by the resistance of the wood to crushing across the grain, as given in Table IV, p. 454.

**Example.** A 12 by 14-in yellow pine girder is designated to support a possible load of 38 000 lb. What bearing should it have at the ends?

**Solution.** The safe resistance given for long-leaf yellow pine to crushing across the grain is 350 lb per sq. in. One-half the load on the girder is 19 000 lb, and hence the bearing area should be 19 000 divided by 350 or about 54 sq in. If the breadth of the beam is 12 in this would require a bearing lengthwise of the girder of  $4\frac{1}{2}$  in. In no case should the bearing be less than that required by the above rule.

### 16. Form and Material of Post-Caps

**Cast-Iron versus Steel Post-Caps.** Formerly **CAST-IRON POST-CAPS** were used for the framing of the girders at the columns and posts. But the uncertainty attached to the use of cast iron, and the necessity of extremely heavy caps to assure safe construction have led most engineers to specify **STEEL POST-CAPS**, as they are unquestionably the strongest form of construction for framing posts and girders. The use of **STEEL POST-CAPS** is to be recommended, there being no uncertainty regarding the strength of steel as there is concerning the strength of cast iron used for post-cap construction. Internal stresses due to uneven cooling may seriously affect the strength of a **CAST-IRON CAP**, while a dry-combed casting may be used, undetected, and affect the safe carrying capacity; so that failure of the cap may occur even from the vibration due to machinery in the building.

**Cast-Iron Post-Caps** are still used in some localities and a few of the common forms as well as those of **STEEL POST-CAPS** are shown. Fig. 51 shows a cap which is frequently used for light construction. Fig. 52 shows a similar cap for a cylindrical post. These caps permit the use of girders wider than the post. When the girders and floor-beams are in place, and especially when the building is occupied, there is no danger of the girders or posts slipping on the cap; in fact it would require a greater force to move them. The girders should be tied together longitudinally by **IRON STRAPS** spiked to their sides. By persons, however, consider it important in a building of **SLOW-BURNING CONSTRUCTION**, to have the posts tied together in vertical lines, and the girders secured in such a way that they will be self-releasing without pulling down the posts. Figs. 53 and 54 show two **POST-CAPS** which fulfill these requirements. In these caps the ends of the girders are not fastened by bolts or spikes, but are held in place and tied longitudinally by means of the **LUG L** on the **GOETZ** cap and by **PINS** on the **DUVINAGE CAP**; so that in case the girder is burned to its breaking point, it can fall without pulling on the post. Provision is also made for bolting the cap to the upper post. The author doubts very much,




Fig. 51. Cast-iron Post-cap for Square-section Wooden Post




Fig. 52. Cast-iron Post-cap for Cylindrical Wood Post




Fig. 53. Cast-iron Duvinage Post-cap with Beam-plate




Fig. 54. Cast-iron Goetz Post-cap with Beam-lugs




Fig. 55. Cast-iron Post-cap High Sides

er, if posts bolted together in this way will stand after the girders have as the planking will be likely to pull the posts over, even if they do not as quickly as the beams. Fig. 55 shows another form of CAST CAP with idea, allowing lag-screws to be driven in the holes to tie the girders.





Fig. 56. Steel Post-cap with Side-plates and Brackets



Steel Post-caps for Posts Varying in Section. Second Figure Shows Four-way Beam-construction

**Post-Cap**, which is approved by the National Board of Fire Underwriters and bears their label, is shown in Fig. 56. This POST-CAP is made up of plates and heavy steel brackets, all held rigidly together by means of heavy bolts. The posts and girders are fastened to the cap by means of



Fig. 58. Steel Post-cap. One-way Beam-construction

Fig. 59. Malleable-iron Post-caps




Fig. 60. Steel Post-cap for Continuous Post

Fig. 61. Malleable-iron Post-cap Steel Top-plate




Fig. 62. Steel Post-cap for Cylindrical Wooden Post. Perspective



screws, permitting the girders to release themselves in case of fire. By this method the entire construction is tied together vertically and longitudinally. This cap, on account of its simple design, lends itself readily to every form of construction desired.

**Various Types of Post-Caps.** Fig. 57 illustrates one POST-CAP in which the width of the girder is less than that of the post below, and also another POST-




Fig. 58. Steel Post-cap for Cylindrical Wooden Post. Elevations and Plan

in which the width of the girder is greater than that of the post below. In the latter FOUR-WAY BRACKETS are riveted to the side-plates to provide for the FOUR-WAY CONSTRUCTION. Fig. 58 shows a ONE-WAY CONSTRUCTION. Fig. 60 shows a POST-CAP which is used when it is required to run a post through two girders. This is what is known as a CONDUIT POST-CAP. The bracket instead of being made clear across the cap is made not on both sides and fitted into holders notched into the post, so as to make a more rigid construction. Fig. 59 shows two POST-CAPS made of malleable iron which are preferable to cast-iron caps as they will not break off in case of a fire when cold water comes in contact with them. This danger is present when CAST-IRON POST-CAPS are used. The cap shown is made in two parts so that it will fit girders and girders of different sizes. This cap is also approved by the Board of Fire Underwriters. Fig. 61 shows a COMBINATION POST-CAP, the upper part of which is made of steel plate, and the lower part of malleable iron. Figs. 62 and 63 show STEEL POST-CAPS FOR PIPE COLUMNS. They are also frequently used for pipe-columns and concrete-columns. (See, also, Steel-Pipe Columns, page 469 and Lally Columns, pages 474 and 477.) Fig. 64 shows a STEEL POST-CAP intended for lighter

Fig. 64. Steel Post-cap for Light Construction

construction. Fig. 65 shows VAN DORN POST-CAPS. Fig. 66 illustrates STAR POST-CAP which is made of a bent steel plate with a fin projecting into a slot in the post. Both are approved by the Underwriters. It is ne




Fig. 65. Van Dorn Steel Post-caps

to slot out the post in order to insert this fin. POST-CAPS which encircle the top of the post in a socket, to a great measure tend to prevent the twisting effect of the post, which is so noticeable when th

are of wood. There is an d to the use of the FOUR-WAY P when the girders are of wood, the floor-beams that are hung girder drop a distance equal shrinkage in the girder, if th are hung in stirrups, or by this amount if they are 1 DUPLEX HANGERS. The best ported on the POST-CAP cam at all, and consequently the be higher over the beam by the posts, than over mediate beams. In one where deep beams were unevenness in the floor and nearly an inch and was v able. Wherever wooden

Fig. 66. Star Steel Post-cap with Fin

used it is, therefore, a much better construction to support all of beams from the girders, in which case the shrinkage will be uniform. In steel girders there is no shrinkage, and a beam may be placed on posts with advantage.

## 17. Roofing-Materials

**Warehouse-Roofs** are almost always flat and, like floors, should be continuous from wall to wall, without openings. The occupancy of such calls for little light, and hence skylights and other roof-structures are required.

**Dampness and Leaks.** Stored goods may be very easily damaged by dampness and roofs, therefore, should be of such construction that they will prevent dampness, either through leakage or condensation. While roofs are usually flat as possible, the incline should be sufficient to drain readily, and

should be of sufficient capacity to quickly drain the roof of a maximum amount of water.

Slag or Tin are almost exclusively used on buildings of this type, although asphalt or other mastics are sometimes used with good results.

Slag Roofs should be constructed generally as described on pages 1595-1599 and should be not less than 5-ply, with the maximum amount of coating. The flashings and counterflashings should be of copper or heavily-coated best metal plates.

Tin Roofs should be laid with the best open-hearth, palm-oil-process terne-plates, laid on felt or other suitable material which will avoid condensation and is a fire-retardant.

Canvas Roofing will stand hard usage, as is shown by its continued use on the sides of vessels and steamers; but it is not adapted to large buildings.

**Provisions for Flooding Roofs.** When warehouses are located in congested districts, surrounded by higher buildings, or by buildings of light construction and hazardous occupancy, their roofs should be so constructed that they may be protected during severe fires in such surrounding buildings. This can be accomplished by using good roofing-materials, making high flashings, waterproofing walls above the roof-line, and providing roof-outlets of types that will allow the removal of stoppers at the scuppers. (See Fig. 11.)

### 18. Partitions

**Non-bearing Partitions.** This refers only to those light walls or enclosures which separate rooms, etc., and not to those walls which divide the building into sections. PARTITIONS, as here defined, bear no floor-loads. Buildings of the NON-BURNING TYPE, for occupancies described above, need but few partitions, these should be built of non-inflammable materials, preferably metal lath plaster on light, metal studding. All cupboards, closets, lockers, etc., in buildings of this type should be of metal, or other equally non-inflammable material.

### 19. Doors and Shutters

**Underwriters' Specifications.** Doors and shutters should be built as specified in the Rules and Requirements of the National Board of Fire Underwriters for the construction and installation of fire-doors and fire-shutters, as these specifications are accepted by architects and builders as the standard.

Openings should be limited to 80 sq ft, or less, each, and all communications between buildings or sections of a building protected with double, auto-closing doors.

### 20. Fire-Protection

**Automatic Sprinklers,** supplied with an ample quantity of water at a good pressure, are needed in mills, storehouses, factories, warehouses, etc., where valuable goods are made or stored, or where large values are at stake. They should be installed in buildings of any type of construction and occupancy, and are most effective in buildings of FIRE-PROOF or MILL-CONSTRUCTION.

**Standpipes,** with outlets in each story, in the basement and on the roof, should be installed at points readily accessible in case of fire, and should have a sufficient quantity of good hose attached at each outlet.

**Nozzles.** If a building is badly exposed to other buildings of inferior construction or hazardous occupancy, a Monitor-nozzle of large size, located near the building, is advisable.

**Public Water-Supplies.** If these are not available, a private fire-service may be advisable.

**Competent Supervision.** All of the above FIRE-PROTECTION EQUIPMENT should be installed by men familiar with their operation, and supervised by competent FIRE-PROTECTION ENGINEERS, under plans approved by underwriters having jurisdiction.

## 21. Cost\* of Mills and Factories Built on the Slow-Burning Principle

**Difficulty of Estimating Costs from Tables.** The cost of a building of this type of construction depends upon the cost of material plus the cost of labor, and as the cost of either varies greatly in different localities the cost of similarly constructed buildings must also vary. Even if the cost of labor and materials does not vary, the cost of buildings of the same area will depend upon the height, floor-loads, distance between bearing-points, design, etc.; it is difficult to deduce a table accurate enough for use in computing even an approximate cost of buildings per square foot of floor-areas. One firm of architects† states: "Experience has taught us that estimating the cost of a building either by the SQUARE-FOOT METHOD or the CUBIC-FOOT METHOD has proved dangerous and misleading, and it was abandoned by us many years ago except to obtain a general idea of the cost of a building. We have found that the only reliable way to approximate the cost of a building is to block it out and to figure the approximate quantities, which at the market prices prevailing at the time the building is to be erected, will give the approximate cost of said building." Owing to the high cost of lumber, a FIRE-PROOF building will cost but little, if any, more than a building of MILL-CONSTRUCTION and owing to this fact it is always advisable to determine the cost of buildings of both types before deciding upon the type to be used. Buildings of MILL-CONSTRUCTION are becoming obsolete in some localities, and owing to the high rate of insurance on buildings of FIRE-PROOF CONSTRUCTION, those of the MILL type are much preferred, as in the end they cost less. It is not always safe to compare the TOTAL COST OF LABOR with the cost of the LABOR PER DIEM; for the cheaper labor is often the more expensive in the end, this depending upon the locality and the conditions imposed. Tables showing the approximate cost of buildings of the MILL-CONSTRUCTION type are computed from the cost of mill-buildings of light construction (cotton-mills with lateral beams) and are not adapted to computing the cost of heavy warehouses or similar factory-construction. The figuring of the cost of such buildings from the COST PER SQUARE FOOT gives, at the very best, only approximate results; and a discrepancy of but 1 ct per sq ft will sometimes amount to thousands of dollars; the method is hardly accurate enough to estimate even the approximate cost.

**The Cost of Buildings of Mill-Construction in New England.** The following eight buildings were designed by Lockwood, Greene and Company of Boston, Mass., who submit data and descriptions of buildings of MILL-CONSTRUCTION with their COST PER SQUARE FOOT. These buildings are, with a few exceptions, situated within a limited area where cost of labor and materials vary but little. The floor-loads vary from 75 to 150 lb per sq ft, and the cost runs from \$0.715 to \$1.56 per sq ft. Considering the textile-mills only, the average cost is \$1.038 per sq ft, while the average cost of all these buildings is \$1.113 per sq ft.

\* These are pre-war prices, but the data are retained for purposes of comparison of relative costs of different types of buildings, or of buildings in different sections of the country. For the cost of reinforced-concrete mills, warehouses, etc., see pages 1613 and 1618.

† Farrot & Livaudais, Ltd., New Orleans, La.

**A Cotton Spinning-Mill.** This mill has an attached picker-house, office and dye-house wings, and was built in Rhode Island in 1911. The following are the details of construction: main mill, four stories; size, 263.17 by 131.67 ft; one-story picker-house, 42.67 by 131.67 ft; one-story dye-house 55 by 85.67 ft; brick stair-tank, and other towers; walls of hard bricks; plank and wearings on transverse I-beam framing, supported by cast-iron columns, except five bays, where both transverse and longitudinal framing is used; slag roof-plank on wooden transverse rafters; floors built for a live-load of 75 lb per sq ft. The cost of the buildings was \$0.965 per sq ft.

**A Four-Story Cotton-Mill.** This mill is without basement. It was built, together with the fan-room and repair-shop additions in Georgia, in 1910. The following are the details of construction: mill, four stories; size, 272 by 128 ft; fan and repair-shop, one story in height and 122.67 by 36 ft in plan; regular brick construction, that is, brick walls, hard-pine transverse floor-framing, wooden beams and plank floors, except for six bays of the fourth floor which have steel I-beam longitudinals in addition to the hard-pine transverse timbers, and sixteen bays of the roof-framing which have both longitudinal and transverse hard-pine timbers, these having been found necessary in both cases because of omission of the alternate columns. These buildings have extensive monitors, saw-tooth skylights, stair-towers, etc. The floors are designed to carry a live load of 75 lb per sq ft. The cost of the building was \$0.715 per sq ft.

**A Cotton-Mill of Irregular Shape.** This mill is considerably wider at one end than at the other and has a basement at one end. It was built in Massachusetts in 1911. The following are the details of its construction: mill, five stories; length, 311.67 ft and average width, 75.42 ft; five-story wing, 66 by 40.01 ft, with extensive pent-houses; stair and elevator-towers and lights; brick walls, transverse wooden floor-framing, supported by cast-iron columns and brick walls; conditions at site demanded extensive foundations; windows in fourth and fifth stories of one wall protected by wire-glass in metal frames; and floors built for a live load of 75 lb per sq ft. The cost of the buildings was \$1.172 per sq ft.

**One-Story Machine-Shop.** This was built near Boston, Mass., in 1910. The main building is 200 by 136.375 ft with a connecting wing, 50 by 39.33 ft. It has brick walls; longitudinal, steel, I-beam framing; transverse, steel, saw-tooth skylight framing; plank roof covered with tar and gravel; 20-ft longitudinal and 16-ft transverse bays; steel I-beam columns; 4½-in cement floors except for three bays which have a 1-in maple overflooring, a 1-in North Carolina pine, intermediate layer, a 3-in kyanized spruce-plank layer, and 4½ in of concrete; and extensive saw-tooth skylights. The cost of the buildings was \$1.288 per sq ft.

**Building for Manufacturing Automobiles.** This building has forge-extensions and was built in Connecticut in 1910. The main building is four stories and a basement and is 54 by 151 ft in plan with a one-story extension, 50 by 149 ft, with extensive pent-houses and monitors. The factory has brick walls, transverse yellow-pine framing on heavy wooden columns and on walls, floors of 1-in maple overflooring over 4-in yellow-pine planks, and of 3-in yellow-pine planks covered with tar and gravel, and a 4½-in concrete basement-floor. The extension has brick walls; a brick-on-edge floor on a 4-in course of cement concrete on earth; steel roof-trusses, of 47-ft span placed 10 ft on centers; tar-and-gravel roof; and extensive monitors. Floors are built to carry a live-load of 125 lb per sq ft. The cost of the building was \$1.075 per sq ft.

**A Two-Story Wooden Box-Factory.** This factory has no basement. It was built near Boston, Mass., in 1909. In plan it is 155 by 305 ft and its average height is 32.5 ft. It has brick shafts; transverse wooden framing for the first floor; transverse beams supported by longitudinals for the second floor and roof; wooden columns and plank floors; and wooden monitors. The floors are designed to carry a live load of 150 lb per sq ft. The cost of this building was \$0.84 per sq ft.

**A One-Story-and-Basement Weave-Shed.** This was built near Boston, Mass., in 1909. It is 213 by 244.17 ft in plan, with extensive entrances, transoms and saw-tooth skylights. It has brick walls; longitudinal I-beam girders supporting transverse I-beam girders in the first story, resting on brick piers; transverse hard-pine girders supporting longitudinal girders for the saw-tooth skylight-framing; heavy, wooden floors and roof; wooden columns; an elevated basement-floor; and foundations on concrete piles. The floors are designed to carry a live load of 100 lb per sq ft. The cost of the buildings, on the story basis, was \$1.56 per sq ft.

**A Two-and-One-half Story Picker-House.** There is, also, a two-story house and a one-story connecting passage between the two buildings mentioned above for the cotton mill of irregular shape, which were built in Massachusetts in 1911. The picker-house is 64 by 95 ft in plan; the waste-house 21 by 40 ft; the covered bridge 10 by 40 ft; and the average height of the building 42.5 ft. The walls are of brick. The picker-house has transverse wooden framing supported by wooden columns and has plank floors. The waste-house wing has transverse, steel I-beam framing and no columns, and concrete-slab floors. The floors are designed to carry a live load of 75 lb per sq ft. The cost of the building, including plumbing, was \$1.29 per sq ft.

**The Cost of Buildings of Mill-Construction in Philadelphia, Pa., and Vicinity.** The following five buildings were designed by Stearns & Company, Philadelphia, Pa., who submit data and descriptions, with the COST PER SQ FT OF FLOOR. These buildings are within a very limited area, being in or within a few miles of Philadelphia, and are of somewhat heavier construction than those described above, the floor-loads varying from 120 to 150 lb per sq ft and the cost ranging from \$0.85 to \$1.23 per sq ft. The average floor-load is 132 lb and the average cost \$1.02 per sq ft. The two spinning-mills mentioned are designed for average floor-loads of 120 lb and their average cost was \$0.85 per sq ft.

**A Chocolate-Factory.** This was built in Philadelphia, Pa., on open ground. It has an ornamental exterior; walls of Sayer and Fisher bricks with terra-cotta trimmings, and a main building, 83 by 303 ft in plan and two stories in height. One section of the building, 60 ft in length, is three stories high. The clear heights are 14 ft from top to top of floors. The floors are designed to carry a live load of 150 lb per sq ft. It has foundations of concrete; heavy floors on heavy timber-framing; a slag roof; all stairways and elevators in brick towers; and openings in division walls equipped with fire-doors. The cost of the building, excluding plumbing, heating, electric work, elevators, fire protection and mechanical equipment, was \$0.85.

**A Four-Story-and-Basement Chocolate-Factory.** This building was erected in Philadelphia, Pa. It is 44 by 130 ft in plan, with average clear heights of 13 ft. It was built in a congested part of the city, between other buildings. The cost of underpinning and shoring the adjacent buildings is included in the cost given. It has plain brick walls; slow-burning floor-construction of heavy, wooden timbers, with finished flooring of maple; stairways and elevators

brick enclosures; and a slag roof. The floors are designed to carry a live load of 150 lb per sq ft. The cost of the buildings including plumbing, but excluding heating, electric work, elevators, fire-protection and mechanical equipment, was \$1.23 per sq ft.

**Spinning-Mill.** This building was erected in Philadelphia, Pa., on ground level and easy of access. Its exterior is of brick, without ornamentation. It is 14 by 268 ft in plan, three stories in height, the stories throughout being 15 ft high from top to top of floors. The floors throughout are calculated to carry a live load of 120 lb per sq ft. It has walls of brick; a slow-burning floor-construction with finished flooring of maple; a slag roof; and stairways and elevators in brick enclosures. The cost of the building, excluding plumbing, heating, electric work, elevators, fire-protection and mechanical equipment, was \$0.93 per sq ft.

**Spinning-Mill.** This building was erected in Philadelphia, Pa., on ground level and easy of access. Its exterior is a plain brick design. It is 69 by 269 ft in plan and three stories in height, the story-heights throughout being 15 ft high from top to top of floors. The floors throughout are calculated for a live load of 120 lb per sq ft. It has brick walls with concrete foundations; a slow-burning floor-construction with a finished flooring of maple; a slag roof; all stairways and elevators in brick enclosures; and all openings in division walls protected with fire-doors. The cost of the building excluding the plumbing, heating, electrical work, elevators, fire-protection and mechanical equipment, was \$1.07; and the cost of the building including the plumbing, heating, electrical work, elevators and fire-protection, but excluding the mechanical equipment, was \$1.34.

**Clothing-Factory.** This building was erected in Woodbine, N. J., on level ground open and easy of access. Its exterior is of brick, without ornamentation. It is 45 by 179 ft in plan and three stories in height. The basement is 10 ft in height, and the other stories 12 ft in height from top to top of floors. The floors are calculated throughout for a live load of 120 lb per sq ft. It has walls of brick; slow-burning floors with yellow-pine finished flooring; a slag roof; and stairways and elevators in brick towers. The cost of the building, excluding heating, electrical work, fire-protection and mechanical equipment, but including freight-elevators and plumbing, was \$1.01 per sq ft.

**The Cost of Buildings of Mill-Construction in the Middle West.** The following six buildings were designed by F. G. Mueller, Hamilton, Ohio, and submit data and descriptions with the costs of buildings of heavier construction. The floor-loads vary from 200 to 300 lb and the cost from \$0.62 to \$0.96 per sq ft. The paper-mill at Taylorsville, Ill., is partly of concrete construction, and was built at a cost of \$1.30 per sq ft. Exclusive of the last-mentioned building, the average floor-load is 230 lb and the average cost \$0.805 per sq ft.

**Addition to a Paper-Mill.** This was built in Dayton, Ohio. It is a two-story brick building, 116 by 79 ft in plan. The first story is used for paper-making and the second story as a finishing-room. The first floor is of cement and cinder fill; and the second floor of 2¼-in yellow-pine planks with an over-laying of ¾-in maple, supported by 8 by 14-in beams, 14 by 16-in girders and 10-in wooden posts. The floors are figured for a live load of 200 lb per sq ft. The roof is supported by six steel trusses and 4 by 10-in wooden purlins, covered with 1¾-in sheathing and composition roofing. The foundations are of concrete. The cost of the building, exclusive of the plumbing and heating, was \$0.75 per sq ft.

**An Addition to a Foundry.** This one-story, brick, foundry-building erected in Hamilton, Ohio, is 432 by 63 ft in plan, and has a one-story wing 86 by 46 ft in plan, and a one-story cupola-house, 28½ by 26½ ft in plan. It has a wooden floor in the wing only and dirt floors elsewhere. It has concrete foundations; a composition roof on 2¼-in sheathing, supported by 12 by 14 girders, 6 by 12-in beams and 6-in cast-iron columns; an elevator in the cupola-house; and all doors of tin-clad construction. The cost of the building was \$0.836 per sq ft.

**A Paper-Mill.** This was built in Monroe, Mich., and is a one-story-and-basement brick building, 185 by 87 ft in plan, with an end-wing 234 by 35 ft. It has heavy beam and girder floor-construction, designed to carry a live load of 300 lb per sq ft; concrete foundations and a basement-part, 130 by 87 ft. It is designed for one paper-making machine and four beaters, has a composition roofing and one skylight over the boiler-room. The cost was \$0.88 per sq ft.

**A Paper-Mill.** This is an irregular-shaped brick building erected in Kennerly, La., and is 356 by 168 ft in plan. About one-third of it is two stories and the remainder one story in height. It has a heavy wooden, beam, girder and post-construction; a stone foundation on cypress-grillage footings; floors designed to carry heavy paper-making machinery with a live load of 250 lb per sq ft. The cost of the building was \$0.96 per sq ft.

**A Warehouse.** This is a one-story-and-basement brick building, erected in Hamilton, Ohio, and is 38 by 50 ft and designed for a live load of 200 lb per sq ft. It has a cement floor in the basement; 10 by 14-in girders, 8 by 12-in beams and 10 by 10-in posts supporting 3½-in flooring; 10 by 14-in girders and 10-in round, wooden posts carrying 2¼-in sheathing and composition roofing. The cost of the building was \$0.62 per sq ft.

**A Paper-Mill.** This was built in Taylorsville, Ill., and has a main building two stories in height and 49 by 130 ft in plan; a one-story part, 138 by 8 ft in plan; and a one-story wing, 42 by 144 ft in plan. There is a basement under almost the entire building. The foundations are of concrete and there are cement floors in the basement. The first floor is of reinforced-beam, girder and slab-construction, designed for a live load of 250 lb per sq ft; the second floor of mill-construction, supported by cast-iron columns, 14 by 18-in wooden girders and 12 by 16-in wooden beams; and most of the roof is supported by steel trusses and wooden purlins. The second floor was designed for a live load of 150 lb per sq ft. There are extensive skylights, pent-houses, etc. The cost of the building was \$1.30 per sq ft.

**The Cost of Buildings of Mill-Construction in Toronto, Canada.** The building described in the following paragraph was designed by Sproost Rolph, of Toronto, Canada, who submit data of a warehouse-building with floor-openings and windows and other outer wall-openings protected in approved manner, and erected at a cost of \$1.12 per sq ft.

**A Five-Story-and-Basement Seed-Warehouse.** This was built in Toronto, Canada, and is 111 by 140 ft 3½ in in plan. The floor-heights are 11 ft 1 in, and the total height is 66 ft. The floors are built of 2 by 6-in piece pine on edge and the bays measure 12 ft 5 in by 13 ft. The beams are of long-yellow pine, 14 by 18 in in section; the posts of similar material, varying from 8 by 8 in to 16 by 16 in; the walls are of hard, red bricks with gray stone sills; and the sashes and frames are of steel throughout. The building has two elevators in a brick-enclosed shaft and one staircase in a separate brick building. The floors are designed to carry a live load of 250 lb per sq ft. The cost of the building, exclusive of the heating and lighting, was \$1.12 per sq ft.



**The Cost of Buildings of Mill-Construction in Northwestern Canada.** The following four buildings were designed by J. H. G. Russell, Winnipeg, Canada, and are warehouses of very superior, heavy construction, widely separated in location, yet varying little in cost. The floor-loads used vary from 300 to 350 lb, live load, per sq ft and the cost varied from \$1.41 to \$1.54 per sq ft. The average cost was \$1.46 per sq ft.

**A Seven-Story-and-Basement Warehouse.** This was built in Winnipeg, Canada, and is 50 ft 6 in by 119 ft 9 in in plan. The floors are of 6-in spruce with 1-in maple overflooring. All floors are on heavy girders and columns; the stairs and elevators are in brick shafts; and the walls are of brick, except the first story front wall, which is of cut stone. The floors are designed to carry 300 lb per sq ft, live load. The cost of the building, exclusive of the heating, elevators, etc., was \$1.46 per sq ft.

**A Three-Story-and-Basement Warehouse.** This was built in Winnipeg, Canada, and is 62 ft 6 in by 86 ft 6 in in plan. Heavy fir timbers were used for framing. It has a 6-in fir-plank solid floor with 3/8-in maple overflooring; stairs and elevators in brick towers; brick walls with the openings in the rear and sides of the building protected. The floors were designed to carry a live load of 350 lb per sq ft, and the cost of the building, excluding the heating, etc., was \$1.41 per sq ft.

**A Six-Story-and-Basement Warehouse.** This is a six-story-and-basement building, erected in Saskatchewan, Canada, and is 50 by 112 ft in plan. The floors are of 6-in fir, with 3/8-in maple overflooring, and are supported by heavy fir timbers. The building has brick walls with a front of pressed bricks and cut-stone trimmings; some of the openings are protected by wire-glass windows; and the stairs and elevators are in brick shafts. The floors were built to carry 350 lb per sq ft, live load, and the building cost, exclusive of the heating, elevators, etc., \$1.44 per sq ft.

**A Five-Story-and-Basement Warehouse.** This was built in Edmonton, Canada, and is 50 by 137 ft in plan. The floors are of 6-in fir with 3/8-in maple overflooring. The building has brick walls and the front and one side wall faced with pressed bricks with stone trimmings. It has the openings in the rear wall protected and the stairs and elevators are in brick shafts. The floors are strong enough for two additional stories and the floors are designed to carry 350 lb, live load, per sq ft. The cost of the building, exclusive of heating, elevators, etc., was \$1.54 per sq ft.

**The Cost of Buildings of Mill-Construction in Vancouver, Canada.** The building described in the following paragraph was designed by Dalton & High, Vancouver, Canada, who give data of a warehouse with floors designed to carry an average load of 500 lb per sq ft and costing \$1.09 per sq ft. Although the heaviest timbers and the heaviest wall-hangers and beam-hangers were used, and the floors built of the maximum thickness, the cost was extremely low.

This no doubt was partly due to the proximity of the timber and the facilities for transporting it by water.

**Warehouse for the Storage of Heavy Hardware.** This was erected in Vancouver, Canada. The main building has four stories and a basement, and is 85 ft 6 in by 115 ft 6 in in plan. The office-wing has four stories and a basement and is 60 by 40 ft. There is, also, a four-story and half-length-base building, 38 by 120 ft, connecting with the two upper stories of the main building by means of a steel bridge 40 ft long. The walls above the basement are of hard-burned brick and the concrete basement walls and floors are treated with hydrolite. The main girders are set 23 ft on centers and vary in section from 12 by 16 in to 18 by 24 in and are all one-piece sticks. The posts, set 11 ft

10 in on centers, vary from 12 by 12 in in one piece, to 20 by 38 in, in the pieces. The joists, set 4 ft on centers, vary from 8 by 16 in to 16 by 24 in in one piece. The floors are made of 4 by 6-in and 4 by 4-in pieces, laid solid, with top flooring made of 2 by 6-in, edge-grain, tongued and grooved pieces, with two layers of asbestos between, weighing  $10\frac{1}{2}$  ounces per sq ft. All the timbers are of fir. There are three brick-enclosed elevators with fire-doors, one elevator in a wooden shaft, built "solid" of 3-in. thick pieces. The front is of pressed bricks and has plate glass, marble steps and copper trim. The windows are glazed with wire-glass in metal frames, and there are doors on the outer door-openings. The roof is made of a 6-ply composition with a gravel coating. The live load used for the floors varied from 1 000 lb per sq ft on the ground floor to 250 lb on the top floor, the average live load being 500 lb per sq ft. The walls and posts were designed to carry two additional stories, with a live load of 225 lb per sq ft. The cost of the building, exclusive of the heating and office and warehouse-fixtures, was \$1.09 per sq ft.

## 22. Cost\* of Brick Mill-Buildings of Slow-Burning Construction

**Approximate Cost of Brick Mill-Buildings.** Mr. C. T. Main† has made a series of diagrams showing the cost in New England, in 1910, PER SQUARE FOOT OF FLOOR SPACE, of BRICK MILL-BUILDINGS of different sizes, from one to four stories in height, and of the type known as SLOW-BURNING. The calculations are made for total floor-loads of about 75 lb per sq ft. The figures taken from the diagrams are given on the following page. The costs include ordinary foundations and plumbing, but no heating, sprinklers or lighting.

**Modifications of the Costs given in Table I:** (1) If the soil is poor or the conditions of the site are such as to require more than ordinary foundations, the cost will be increased.

(2) If the building is to be used for ordinary storage-purposes with low stories and no overflooring, the cost will be decreased from about 10% for large, low buildings to 25% for small, high ones, about 20% being usually a fair allowance.

(3) If the building is to be used for manufacturing and is substantially built of wood, the cost will be decreased from about 6% for large, one-story buildings to 33% for small, high buildings; 15% would usually be a fair allowance.

(4) If the building is to be used for storage and built with low stories and substantially of wood, the cost will be decreased from 13% for large, one-story buildings to 50% for small, high buildings; 30% would usually be a fair allowance.

(5) If the total floor-loads are more than 75 lb per sq ft the cost will be increased.

(6) For office-buildings, the cost must be increased to cover the extra architectural treatment and the interior finish.

(7) Reinforced-concrete buildings, designed to carry floor-loads of 100 lb per sq ft will cost about 25% more than those of the slow-burning type of mill-construction.

\* These are pre-war prices, but the data are retained for purposes of comparison of relative costs in the analysis made. For the cost of reinforced-concrete mills, warehouses, etc., see pages 1613 and 1618.

† Engineering News, January 27, 1910.

**Table I. Cost of Brick Mill-Buildings per Square Foot of Floor-Area**

Length in ft	50	100	150	200	250	300	350	400	500
Width in ft	One story								
25	\$1.90	\$1.66	\$1.58	\$1.54	\$1.51	\$1.49	\$1.48	\$1.47	\$1.46
50	1.52	1.29	1.21	1.18	1.16	1.15	1.14	1.13	1.13
75	1.41	1.21	1.12	1.08	1.06	1.04	1.03	1.02	1.02
125	1.32	1.09	1.02	0.98	0.96	0.94	0.94	0.93	0.92
Two stories									
25	2.00	1.62	1.52	1.47	1.44	1.41	1.39	1.38	1.36
50	1.50	1.21	1.13	1.09	1.06	1.05	1.04	1.03	1.02
75	1.34	1.08	1.01	0.97	0.94	0.92	0.92	0.91	0.90
125	1.22	0.97	0.90	0.86	0.84	0.82	0.81	0.80	0.86
Three stories									
25	1.98	1.57	1.47	1.42	1.39	1.38	1.36	1.35	1.34
50	1.47	1.17	1.07	1.03	1.01	1.00	0.98	0.98	0.98
75	1.30	1.05	0.98	0.94	0.91	0.89	0.88	0.87	0.86
125	1.18	0.93	0.86	0.82	0.80	0.78	0.77	0.76	0.76
Four stories									
25	2.00	1.61	1.50	1.45	1.42	1.40	1.38	1.37	1.36
50	1.38	1.17	1.10	1.05	1.02	1.00	1.00	0.99	0.98
75	1.32	1.08	0.97	0.93	0.90	0.88	0.88	0.87	0.87
125	1.20	0.93	0.85	0.81	0.78	0.77	0.76	0.75	0.74
Six stories									
25	2.10	1.72	1.57	1.51	1.48	1.46	1.44	1.43	1.42
50	1.53	1.21	1.12	1.08	1.05	1.04	1.03	1.02	1.02
75	1.35	1.08	0.98	0.94	0.92	0.90	0.89	0.88	0.86
125	1.22	0.96	0.86	0.82	0.79	0.78	0.77	0.76	0.76

THE COST PER SQUARE FOOT of a building 100 ft wide is about midway between that of a building 75 ft wide and one 125 ft wide; and the cost of a five-story building about midway between the costs of a four-story and a six-story building.

**Additional Data** for estimating costs of foundation-walls and other wall surfaces are given in the following table:

**II. Cost of Walls in Brick Mill-Buildings of Slow-Burning Construction**

Number of stories	1	2	3	4	5	6
<b>Foundations, including excavations</b>						
<b>Cost per lin ft:</b>						
Outside walls.....	\$2.00	\$2.90	\$3.80	\$4.70	\$5.60	\$6.50
Inside walls.....	1.75	2.25	2.80	3.40	3.90	4.50
<b>Brick walls</b>						
<b>Cost per sq ft of surface:</b>						
Outside walls.....	0.40	0.44	0.47	0.50	0.53	0.57
Inside walls.....	0.40	0.40	0.40	0.43	0.45	0.47

**Columns**, including piers and castings, cost about \$15 each.

**Assumed Height of Stories:** From ground to first floor, 3 ft. Buildings 25 ft wide, stories 13 ft high; 50 ft wide, 14 ft high; 75 ft wide, 15 ft high; 100 ft and 125 ft wide, 16 ft high.

**Cost of Floors:** 32 cts per sq ft of gross floor-space, not including columns; 38 cts, including columns.

**Cost of Roof:** 25 cts per sq ft, not including columns; 30 cts, including columns. Roof to project 18 in on all sides of buildings.

**Stairways**, including partitions, \$100 each flight. Include two stairways and one elevator-tower for buildings up to 150 ft long; two stairways and two elevator-towers for buildings up to 300 ft long. In buildings over two stories height, three stairways and three elevator-towers for buildings over 300 ft long.

**Plumbing Fixtures.** In buildings of more than two stories figure \$75 each fixture, including the piping and partitions. Allow for two fixtures each floor up to 5 000 sq ft of floor-space, and one fixture for each additional 5 000 sq ft, or fraction thereof, of floor-space.

## CHAPTER XXIII

## FIREPROOFING OF BUILDINGS

By

RUDOLPH P. MILLER

SUPERINTENDENT OF BUILDINGS, NEW YORK CITY

## 1. Definitions, Areas, Heights, and Costs

**Definitions.** The term FIRE-PROOF, while now quite well understood by architects, is still used in a very broad sense by the public. To be strictly fire-proof, a building must be constructed and finished entirely with incombustible materials, and any of these materials, such as steel or iron, which are seriously affected by heat or streams of water must be efficiently protected by other materials which are not so affected. This precludes the use of wood, whether exposed or not exposed, also all exposed steel or iron, common glass, and most building stones. It is safe to say that there are very few buildings in this country that are absolutely FIRE-PROOF. There are many, however, that could not be destroyed by fire, and in which the salvage would probably amount to from 60 to 80%; and it is the latter class which is generally meant when the term FIRE-PROOF is used. Incombustible buildings, and buildings of wooden construction protected to a greater or less degree from the flames, are sometimes advertised as FIRE-PROOF; but such buildings should be considered merely as SLOW-BURNING. It is undoubtedly the duty of every architect to be well informed concerning the fire-proof qualities of all materials that enter into the construction and finishing of buildings, and to know how to use these materials to the best advantage. His choice and use of materials is then limited by the character of the building and the interests of his clients. It is intended to furnish this information in a concise manner in this chapter. The National Fire Protection Association recommends the discontinuance of the term FIRE-PROOF, and the use of the term FIRE-RESISTIVE in its stead. The latter term is the one used in the building laws of all the larger cities.

**Municipal Definitions.** Municipal definitions as to what constitutes FIRE-PROOF CONSTRUCTION have a great bearing on the construction of buildings within their jurisdiction. None is entirely comprehensive and the detailed requirements must be consulted in each case. The Chicago definition is typical of most of them.

**Chicago Definition.\*** "The term FIRE-PROOF CONSTRUCTION shall apply to buildings in which all parts that carry weights or resist strains,† and also all exterior walls and all interior walls and all interior partitions and all stairways and all elevator enclosures are made entirely of incombustible materials, and in which all metallic structural members are protected against the effects of fire by coverings of a material which shall be entirely incombustible, and a slow heat conductor, and hereinafter termed FIRE-PROOF MATERIAL. Reinforced concrete

Quoted matter is left in its original form. The editor-in-chief is not responsible for syntax, punctuation, etc.

Stresses are meant.

as defined in this ordinance shall be considered fire-proof construction, when built as required by Section 550."

**When Fire-proof Construction Should be Employed.** A building should be designed, built, and finished to conform to the purpose for which it is to be used. A building containing but little inflammable material, and that not of great value, need not be as thoroughly fire-proof as one designed for the storage of valuable goods, or for the protection of life in case of fire. The height of a building is an important factor in determining whether it should be fire-proof or not. The rate of increase in the difficulty of coping with fire in a building is greater than that of the increase in the height. The area covered by a building, also, is important, although in most instances interior division walls may be provided which practically cut up a building into a series of small buildings. Some of the limitations placed upon non-fire-proof buildings by various municipal laws will be found in the following classification and in Table on page 813.

#### Limiting Areas for Non-Fire-proof Buildings.

New York City,	7 500 sq ft on an interior lot. 12 000 sq ft on a corner. 15 000 sq ft when facing three streets.
Chicago, Ill.,	9 000 sq ft if of ordinary joisted construction. 12 000 sq ft if of slow-burning construction.
St. Louis, Mo.,	7 500 sq ft.
Boston, Mass.,	10 000 sq ft.
Cleveland, Ohio,	Mill-Construction: 20 000 sq ft when facing streets on four sides. 15 000 sq ft when facing streets on three sides. 12 000 sq ft when facing streets on two sides. 9 000 sq ft when facing streets on one side. 5 000 sq ft on any lot when of hazardous occupancy.
Cleveland, Ohio,	Ordinary Construction: 12 500 sq ft when facing streets on four sides. 10 000 sq ft when facing streets on three sides. 7 500 sq ft when facing streets on two sides. 5 000 sq ft when facing streets on one side. 2 000 sq ft on any lot when of hazardous occupancy.

**Cost of Fire-proof Construction.** F. W. Fitzpatrick, found, previous to 1903, that fire-proof construction for office-buildings, hotels, etc., adds from 9 to 13% to the cost of ordinary construction with wooden joists. For stores and warehouses the difference will often be less than 5%.\* Walter F. Ballinger stated (1909) that reinforced-concrete construction cost from 10 to 15% more per square foot of floor-surface than mill-construction and about 25% less than steel-frame and terra-cotta fire-proof construction.† Figures given by J. P. Perry (1911) indicated that reinforced-concrete construction added from 2 to 3% to the cost of mill-construction for commercial buildings, with an average of 6.7% for various localities and all classes of buildings in the United States. The increase in cost of structural-steel fire-proof construction over reinforced-concrete construction averaged 6.4% for fourteen buildings of all classes at various localities.‡ More recent comparisons are not available, but it can be safely asserted that the increased cost of fire-proof construction over

\* Fireproof, for March, June, and July, 1903.

† Proc. Nat. Fire Prot. Asso., 1909.

‡ Proc. Nat. Asso. Cement Users, 1911.

# Heights for Non-Fire-proof Buildings

TABLE I. Limiting Heights for Non-Fire-proof Buildings.

Factories	All buildings	Hotels	Schools	Hospitals and asylums	Residence- buildings
Four stories	75 ft	40 ft	40 ft	20 ft	75 ft
90 ft	90 ft	{ Five stories and basement }	{ Three stories and basement }	Two stories	{ Five stories and basement }
.....	{ Six stories }	Four stories	Four stories	Two stories	Four stories
.....	85 ft	{ Four stories above basement }	Two stories above basement	Two stories above basement	Four stories above basement
.....	90 ft	Five stories	.....	.....	Five stories
.....	75 ft	.....	.....	.....	.....
.....	60 ft	Ordinary construction	.....	.....	.....
.....	80 ft	Mill-construction	.....	.....	.....
.....	100 ft	Semifire-proof construction	.....	.....	.....
.....	85 ft	45 ft	45 ft	45 ft	70 ft
.....	90 ft	.....	{ One story More than 600 persons }	One story	.....
90 ft	90 ft	90 ft	.....	90 ft	90 ft
.....	.....	.....	.....	.....	.....
.....	72 ft	.....	.....	.....	.....
.....	55 ft	Ordinary construction	.....	.....	.....
.....	84 ft	Mill-construction	.....	.....	.....
.....	65 ft	50 ft	40 ft	40 ft	.....
.....	60 ft	55 ft	.....	55 ft	35 ft
.....	.....	Four stories	Three stories	Three stories	Four stories
.....	.....	.....	.....	Three stories	.....
.....	80 to 90 ft	Three stories	Three stories	Two stories	Four stories
.....	Four stories	Three stories	.....	.....	59 ft
.....	59 ft	.....	.....	.....	.....

construction and ordinary joisted construction is less than indicated by the figures.

**Divisions of the Subject.** In constructing fire-proof buildings it is necessary to consider:

- (1) Materials to be used.
- (2) Form of construction.
- (3) Protecting devices.
- (4) Extinguishing appliances.

This general order is followed in the discussion of the subject in this chapter.

## 2. Fire-Resistance of Materials

**Effect of Heat on Building Materials.** All materials of construction are more or less injuriously affected by high temperatures. Furthermore, an **INCOMBUSTIBLE** material is not necessarily **FIRE-RESISTING**, as, for instance, **STONE**. The value of various materials in fire-proof construction is indicated in the following paragraphs.

**Brickwork.** Common brickwork, when of a good quality, will stand exposure to severe fire for a considerable length of time. Experience has shown that thick walls are less affected by heat than thin walls, and that hard-burned bricks stand better than soft or underburned bricks. In the Baltimore and San Francisco fires, it was demonstrated that for outside walls brick is superior as a fire-proof material to any other material used in wall-construction.

**Stone in General.** Very few stones successfully stand the action of severe heat, and consequently stone in general should be used very sparingly in fire-proof buildings, and certain kinds of stone not at all.

**Granite** will explode and fly to pieces or disintegrate into sand when exposed to flames.

**Limestone and Marble** are usually ruined if not totally destroyed by ordinary fire. They are the least desirable of all stones for use in a fire-proof building, and the granites come next.

**Sandstone** when fine-grained and compact sometimes stands fire with but serious injury, but in the case of a severe conflagration it is generally so badly affected that it has to be replaced.

**Terra-Cotta** is made from clay by mixing it with water into a plastic mass, shaping the same into the form desired and baking it at a high temperature in kilns. For the usual structural form the shaping is generally done by forcing the plastic mass through a special die by means of machinery. Ornamental terra-cotta must generally be shaped by hand.

**Ornamental Terra-Cotta.** This material, and especially that which has a glazed surface, is well adapted for the trimmings of a building that is intended to be fire-proof. It should, however, be made heavy enough to carry both its own weight and its share of the wall-load.\*

**Structural Terra-Cotta.** Terra-cotta, as used for floor-arches, column and girder-protection, and for building light, hollow walls, is made of three different compositions, the material being known as **DENSE**, **POROUS**, and **SEMI-POROUS**, according to the method of manufacture.

**Dense Tiling** is made from a variety of clays. Some manufacturers use

\* Fire Prevention and Fire Protection, J. K. Freitag.



use or less fire-clay, and combine it with potter's clay, plastic clays, or tough brick-clay. It is very dense and possesses high crushing strength. In outer walls exposed to the weather and required to be light, it is very desirable. Some manufacturers furnish it with a semiglazed surface for the outer walls of buildings. For such use it has great durability, and effectually stops moisture. In using dense tilling for fire-proof filling, care should be taken that the tiles are free from cracks, sound, and hard-burned.

**Porous and Semiporous Terra-Cotta** is made by mixing sawdust with the clay, the sawdust being destroyed by the action of the heat, leaving the material light and porous. A small proportion of fire-clay mixed with the plastic clay is desirable but not essential. The proportion of sawdust should be from 10 to 35%, according to the toughness of the clay used. Care is required in the process of manufacture to have the work of mixing, drying, and burning thoroughly done. The burning should be done in down-draught kilns, by a quick process. The product should be compact, tough, and hard, and should ring when struck with metal. Poorly-mixed, pressed, or burned tiles, or tiles made from short or sandy clays, present a ragged, soft, and crumbly appearance, and are not desirable. When properly made, porous terra-cotta will not crack or break from unequal heating, or from being suddenly cooled with water when in heated condition. It can be cut with a saw or edge-tools, and nails or screws can be easily driven into it to secure interior finish, slates, tiles, etc. As a successful heat-resistant and non-conductor for the protection of other materials, it must be ranked very high.

**Semiporous Tiling.** This material was introduced by those factories which use pure fire-clay in the manufacture of tile, to enable them to compete with the standard porous material. During the process of grinding the clay, about 5% of ground coal is mixed with it. This coal aids in the burning of the material and also makes it lighter and more or less porous. Tiling made by this process is admitted to be a much better fire-resistant than the solid or dense material. E. V. Johnson says: "personally, I believe that good semiporous fire-clay tile is fully as efficient as a fire-resisting material as the standard tiles of porous terra-cotta."

**Strength of Terra-Cotta.** (See, also, page 276.) In tests made at Columbia University for the building authorities of New York City on terra-cotta blocks taken from material delivered in the open market, the following CRUSHING STRENGTH was developed:

Table II. Crushing Strength of Terra-Cotta

Description of material	Position of cells in test	Compressive strength, lb per sq in	
		Gross area	Net area
Dense tile.....	Vertical	1 864	4 721
	Horizontal	585	2 613
Semiporous tile.....	Vertical	1 027	2 168
	Horizontal	257	1 008

The inequality in strength of the two materials can be overcome by using thicker webs and shells for the semiporous or porous material. In the matter

of WEIGHT, porous and semiporous terra-cotta have the advantage over dense tile. Dense tiling, when heated and cooled by water, is liable to crack from the sudden contraction; "blocks with two or more air-spaces are very liable to have the outer webs destroyed under this action. Even if not cooled with water, other fires have shown that hard-burned terra-cotta will crack and shatter to pieces under severe heat alone." \* The experience of the recent conflagrations in Baltimore and San Francisco fully bears out this statement. The collapse of the floors of one of the buildings in Baltimore was largely due to the weakening of the terra-cotta arches by reason of the breaking off of the outer shells. Porous terra-cotta is non-heat-conducting in itself, and the blocks of good quality will usually resist fire and water successfully; but if the product is not burned at a sufficiently high temperature to consume all of the sawdust, the throwing of cold water upon the heated surfaces will cause an expansion and disintegration due to the absorption of the water and its conversion into steam. Porous terra-cotta absorbs water freely, and if allowed to freeze when wet will be more or less injured. If the process is permitted to continue, the blocks become so weakened that they are unsafe for use.

**Concrete Blocks and Concrete Tiles.**† Numerous forms of building blocks and tiles are manufactured of Portland-cement mortar or concrete for use as substitutes for brick, stone, and terra-cotta. Concrete blocks are made by the DRY PROCESS by tamping a dry-concrete mix into shape in forms, or by the WET PROCESS which consists of pouring a semiliquid or SLUSH-MIX into molds and curing the product by air or steam. A third method, known as the PRESSURE-PROCESS, is similar to the first, mechanical or hydraulic pressure being substituted for the tamping. Concrete hollow tile is being made for the same uses as terra-cotta tiling, for partitions and floors in general, and for enclosure-walls as well as for partitions in residences. For wall-bearing purposes, the tiles are usually filled solid for a layer or two where the beams rest upon them. In hollow-block construction, distinction should always be made between the strength of the blocks when laid with the core-holes vertical and when laid with the core-holes horizontal, as the strength, in the latter position, approximates only one half of what it is in the former. The specifications of the American Concrete Institute, 1917, are generally accepted as the best practice in the manufacture of concrete blocks. (See, also, Chapter I, page 233.)

**Concrete Tile.** Concrete building tiles have been used for residences in Chicago, Ill., Rochester, N. Y., and the suburbs of New York City. The shape and size of the blocks vary with the make of the product. In size and shape they resemble terra-cotta tile, though the walls and webs are thicker. A WET-PROCESS tile was tested by the Bureau of Buildings, New York City, in 1911, and showed a COMPRESSIVE STRENGTH in pounds per square inch as shown in Table III, page 817.

The Trout Concrete Tile Corporation of Flushing, N. Y., has developed a new method of making hollow tile whereby lightness is combined with strength. The Trout tile is made in a hydraulic machine, with a pressure of 1200 lb per sq in of net area of the tile. While this pressure is being applied, the particles of concrete are automatically moved about until the voids are filled and the result is a dense, hard product of even quality. This process permits the making of tile with thin walls, thereby reducing the weight to a minimum. A tile 8 in high, 8 in wide, and 15¼ in long, with two cells, and with walls

\* Fire Prevention and Fire Protection, J. K. Freitag.

† The subject is fully treated in Concrete Engineers' Handbook, by Hool and Johnson.

Table III. Compressive Strength of Concrete Tile

Dimensions and use			Cells vertical		Cells horizontal	
Height, in	Kind of tile	Number of cells	Gross area, lb per sq in	Net area, lb per sq in	Gross area, lb per sq in	Net area, lb per sq in
8	Wall-tile	2	.....	.....	320	746
10	Wall-tile	2	528	1 510	351	1 228
10	Corner-tile	2	633	1 580	.....	.....
12	Wall-tile	4	510	1 050	360	1 066
8	Wall-tile (Trout*)	2	1 016	2 588	.....	.....

\* Trout Tile tested by Bureau of Buildings, New York, in 1914.

nd webs 1 in thick, weighed 91.7 lb. Its compressive strength is given in the last line of Table III.

**Concrete.** Stone concrete, under the action of heat, is affected much the same way as brickwork. The heated surface expands, and as the concrete is a very poor conductor, the other surface remains cool and either cracks or warps. The heat also affects the strength and texture of the concrete, causing a disintegration of the concrete to a depth of about 1 in. Often the surface spalls off with a report. If water is applied after the heat, the surface is washed away to the depth of the affected part. These effects vary somewhat with the stone used in the aggregate. Siliceous gravel has been found by tests and in actual fires to be very destructive to concrete. Granite, on account of the difference between its coefficient of expansion and that of the concrete, is liable to spall. Limestone calcines under the action of heat and is liable to destruction for some depth by the water. Trap-rock is a satisfactory material to use, from the standpoint of fire-resistance as well as that of strength. If there is no application of water after the fire and the surface is allowed to cool gradually, the concrete may set again and become hard. It is not well, however, to rely on this. (See, also, Chapter III, page 245, for the effect of heat on concrete fireproofing.)

**Slag Concrete.** Blast-furnace slag has been used as the aggregate in concrete, with satisfactory results as to both fire-resistance and strength.\* Care must be exercised in the selection of the slag. R. L. Humphrey says that only acid slag should be used and that it must be "dense, tough, and free from sulphur." Sanford Thompson states that the slag must be "air-cooled, washed, screened from dust, and free from foreign material," and that "exceptional care must be used in proportioning, mixing, and placing." †

**Cinder Concrete.** Cinder concrete, because of its porous character and the nature of its aggregate, makes an excellent fireproofing material. Tests and experience of conflagrations would indicate that it is the best. Care must, however, be taken in the selection of the cinders. They must be clean furnace-cinders, free from unburnt coal. When properly selected and proportioned,

For a series of tests and description of materials, see pamphlet issued by the Carnegie Steel Company, 1911, *Furnace Slags in Concrete*. See, also, Proc. Am. Soc. for Test. Mat., 1914. A full discussion of slag concrete is published in the *Iron and Coal Trade Review* (London), for Nov. 22 and 29, 1918. *Engineering Record*, March, 1917.

cinders produce good concrete, but generally a very non-homogeneous material is obtained, so that its strength is variable and doubtful. If ground machinery before mixing, a better and more reliable concrete is produced. In using cinder concrete in floor-construction the working loads are generally determined from load-tests and a high FACTOR OF SAFETY is used. The former practice in New York City was to take one tenth of the BREAKING-LOAD as the WORKING LOAD. The building code now prescribes a formula for computing the strength of cinder-concrete floors, within certain limitations.

**Corrosive Action of Cinders.** When cinder concrete is used to encase steel, either as a protective covering or as a part of a concrete construction, the corrosive effect of cinders must be guarded against. A discussion of this subject will be found in Chapter XXIV, pages 960 and 961.

**Mortars, Plasters, and Plaster of Paris.** Mortar and plaster must necessarily enter into the composition of all masonry buildings, whether built of brick, stone, or terra-cotta. That ordinary lime mortar, when well made, will endure for unlimited periods of time, in dry situations, has been proved by actual use. Hydraulic-cement mortars are equally durable in wet or damp places. For laying brickwork or tilework in first-class buildings, cement-and-sand mortar is preferable to any other; and cement mixed with lime mortar gives greater strength than lime and sand alone. Regarding the fire-resisting qualities of mortars and plaster compositions there has been much controversy; the truth of the matter seems to be that all such compositions will withstand the action of heat up to a certain degree, when they are affected in one way or another, depending not only upon the composition but in large measure upon their body, and upon the way in which they are used. Lime mortar for walling was formerly considered as the most satisfactory, so far as fire-resistance was concerned; but since the improvements in cement-manufacture, cement mortar is generally preferred. Lime plaster, applied on wire lath, will withstand a high degree of heat without injury, but is liable to be washed away in places by streams of water. Gypsum plasters, usually termed hard wall-plasters, or patent plasters, when applied to brickwork or metal lath, are superior in heat-resistance to common lime, and the patent plasters will stand the combined effects of fire and water longer than the common mortars.

**Plaster of Paris.** Compositions of plaster of Paris (gypsum) and broken bricks, wood chips, or sawdust are non-conductors of heat and possess fire-resisting properties of considerable importance; and on account of their lightness and cheapness, are often used in fire-proof or semi-fire-proof buildings. In France such compositions have been used for generations to form ceilings between beams, and their durability and fireproofing qualities are unquestioned in that country. Plaster of Paris compositions when subjected to severe heat are softened on the surface, and when water is thrown upon them they wash away to some extent.

**Asbestic Plaster.** A plaster made by mixing Asbestic with freshly slacked lime-putty has been used to some extent in New York City. Asbestic is made from a serpentine rock, mined near Montreal, Canada, and contains a large proportion of asbestos. "Claims of great fire-resisting properties are made for this material, as well as resistance to the effects of water during fire; cracking and discoloration due to the percolation of water or acids are also claimed to be avoided. The plaster is tough and elastic, and it will receive nails without chipping or cracking. The weight is said to be about half that of ordinary cement mortar." Asbestic was subjected to a severe fire-and-water test in the presence of the officials of the Supervising Architect's office at Washington, D. C., "and the plaster did not crack or drop, but remained intact. All of

walls, ceilings, and columns of the appraiser's warehouse in New York City were covered with a coat of Asbestic, from  $\frac{1}{2}$  to  $\frac{3}{4}$  in thick, applied on concrete or terra-cotta surfaces. The great objection to the use of this material lies in its slow drying, the time required for a thorough drying out being usually very long."\*

**Asbestos-Products.** Asbestos fiber combined with cement is manufactured in the form of steam-packings, corrugated sheathings, roof-coatings and shingles, mill-boards and building-lumber, insulating sheathing and blocks, asbestos water-curtains, various forms of preservative and fire-resisting compounds, and substitutes for wall-plaster and stucco. The value of these products lies in their low heat-conductivity and incombustibility.

**Asbestos Building Lumber** is made in standard sheets, 42 by 48, and 42 by 96 in in size, and varying in thickness from  $\frac{1}{4}$  in (about  $1\frac{1}{4}$  lb per sq ft in weight) to 1 in (about  $10\frac{3}{4}$  lb per sq ft in weight). When seasoned it is harder than ordinary wood, takes nails and screws, and it can be manipulated with heavy tools and machinery such as are used for working iron. It is too hard for ordinary wood-working tools. It is sufficiently elastic to withstand ordinary vibration, expansion, and contraction of surrounding parts, wind-pressure, and blows; and in large pieces, it can be bent around slight curves without splitting.

**Asbestos Corrugated Sheathing** is corrugated asbestos building-lumber, reinforced with sheet steel of from No. 24 to No. 27 United States gauge, or with open-wire netting. It is applied in the same way that corrugated iron is applied, either nailed to wooden strips bolted to the purlins, or clipped directly to the purlins by clips of hoop-iron or wire. It comes in standard sheets, 27 $\frac{1}{2}$  in wide and in lengths of 4, 5, 6, 7, 8, and 10 ft.

**Asbestos Roofing-Shingles**, suitable for wooden-roof construction, possess fire-resisting qualities far superior to wooden shingles. The advantages claimed for their fire-proof qualities, toughness, elasticity, and lightness in weight; ease of manipulation, cutting, sawing, and shaping to fit dormer windows, chimneys, etc.; and their immunity from the corrosive action of salt air. The principal companies manufacturing asbestos building-products are the Johns-Manville Company, New York City; the Keasbey & Mattison Company, Ambler, Pa.; and the Asbestos Manufacturing Company, Lachine, Canada.

**Robertson Process Metal** consists of steel sheets of from No. 26 to No. 20 United States gauge, enveloped in successive layers of an asphaltic compound containing heavy natural oils, an asphalt-impregnated asbestos-felt, put together under great pressure, and a patented water-proof coating. The sheets are made corrugated, or beaded. It forms an incombustible roofing, siding, sheathing, and interior-finish material. The manufacture of this product is controlled by H. H. Robertson Company, of Pittsburgh, Pa.

**Steel and Wrought Iron.** Wrought iron and steel will expand, bend, and melt under a moderate degree of heat. Inasmuch as a temperature of  $1700^{\circ}$  F. is not unusual in fires, these materials should not be used in fire-proof construction without proper protection. Fire tests at the Continental Iron Works in 1896 showed that unprotected steel columns under load began to fail when temperature reached about  $1100^{\circ}$  F.† In the Baltimore and San Francisco fires there were many instances of failure in steel columns due to lack of or to inefficient protection.

**Cast Iron.** "As the result of tests and actual experience in conflagrations it may be stated that unprotected cast iron can stand practically unharmed up

\* Freitag.

† See Engineering News, Aug. 6, 1896.

to temperatures of 1300 or 1500° F. while carrying very heavy loads, even with frequent applications of cold water while the metal is at a red heat."\* In tests at the Continental Iron Works, referred to in the preceding paragraph, a temperature of nearly 1300° F. was reached before the cast-iron columns began to fail. The contents of most mercantile buildings, when burning freely, would probably generate a heat exceeding at times 2000° F. Consequently, cast-iron columns, when unprotected, are almost sure to fail in such a fire either by bending or breaking. No building in which unprotected iron or steel columns are used can be considered fire-proof; but in many classes of buildings unprotected cast-iron columns might safely withstand any heat to which they would probably be exposed. From a fire-resisting point of view, when there is no protection covering, cast-iron columns are unquestionably preferable to steel columns.

**Fire-proof Wood.** To meet the requirements of certain provisions of the New York City Building Code, an attempt has been made to produce fire-proof wood. The processes for rendering wood fire-proof, in general, consist in impregnating its fibers with certain chemicals. After the fireproofing process the lumber should be thoroughly kiln-dried before it is used. The softwoods are more easily thoroughly treated than the hardwoods, the resinous woods being particularly difficult to handle.

"The treatment of the wood to render it fire-proof slightly raises the ignition point of the wood. The treated wood is harder to light than the untreated wood, taking two to three times as long to ignite. The amount of wood destroyed when exposed to the action of a flame is from 5 to 12 per cent greater in the case of an untreated wood than in the case of a treated wood. The untreated wood furnished more flame than the treated wood. The untreated wood sustained flame longer than the treated wood after the source of heat had been removed. From this it can be seen that the fire-proofed wood is less likely to ignite and less likely to cause the spread of fire than the untreated wood."†

Among the disadvantages of fire-proof wood should be mentioned an increased difficulty in working the wood, and a tendency to dull woodworking-tools more rapidly than with untreated wood. Hence an increased cost in the use of fire-proof wood. The salts used in the process of fireproofing being hygroscopic tend to keep the woodwork damp. Hardware or other metalwork in contact with fire-proofed wood is liable to corrode. The strength of the wood is also affected, and in some cases the wood becomes quite brittle. These two last mentioned faults can be largely overcome by neutralizing the fireproofing solution by a proper mixture of acid and alkaline salts.

The test, known as the timber-test, applied to fire-proof wood in New York City, consists in placing a stick of the treated wood,  $\frac{3}{4}$  by  $1\frac{1}{2}$  in in cross-section and 8 in in length, for two minutes over a crucible gas-furnace in which a constant temperature of 1700° F. is maintained; then removing the test-piece, noting the time it continues to flame and glow; and then scraping away the charred wood and determining the percentage of unburned wood. The conditions of acceptance are that, "the flame and glow should disappear within ten to twenty seconds after the removal of the test-piece from the furnace, the unburned and uncharred section at the center of the specimen should be not less than 50 to 70 per cent of the original cross-section, depending on the variety of wood under test." If the wood has been thoroughly treated, a splinter of it after having been exposed to flame and withdrawn, will

\* Freitag.

† See Insurance Engineering, Vol. IV, page 551; also Professor Norton's Report No. 1 to the Boston Manufacturers' Mutual Fire Insurance Company.

glow or flame. Other tests have been suggested and used but need not be described here.

**Fire-Glass.** The introduction of this material has made it possible to have fire-protection in many cases, without the necessity of disfigurement due to fire-shutters. Wire-glass is either RIBBED, ROUGH, MAZE, COBWEB, or POLISHED PLATE, with wire embedded in its center during the process of manufacture. The temperature at which the wire is embedded in the glass insures adhesion between the metallic netting and the glass, and the two materials become inseparable, so that if the glass is broken by shock, by intense heat, or by other cause, it remains intact." It is this property of remaining intact which gives it its fire-retarding qualities. Although fire and water may cause cracks to spread throughout the glass, the wire holds the pieces so firmly that flames cannot pass through it. Many severe tests during actual fires have amply demonstrated the truth of the above claim. For warehouses and factories the RIBBED OR MAZE glass is generally preferable; but for offices, or wherever clear transparent glass is desired, the POLISHED PLATE is nearly if not quite as acceptable as the same glass without the wire, the effect being the same as that obtained by looking through a window with a screen on the outside.

Where FIRE-RESISTANCE is the desired feature, the following requirements should be satisfied. The thickness of the plate at the thinnest part should be not less than  $\frac{1}{4}$  in, and the plane of the wire mesh should be midway between the two surfaces of the glass. No wire should be smaller than No. 24 Brown wire gauge. The unsupported surface of the glass should not exceed 4 ft in any case and should be contained in a metal frame not larger than 9 ft between supports. The chief manufacturers of wire-glass in this country are the Pennsylvania Wire Glass Company, Philadelphia, Pa; the Mississippi Wire Glass Company, New York; the Western Glass Company, Streator, Ill, and the Highland Glass Company, Washington, Pa. As now manufactured by the continuous process, it is rolled in lengths up to about 10 ft and in thicknesses up to  $\frac{1}{2}$  in.

**Prism Glass.** Prisms installed for the purposes of increased light are usually not contained in frames which are designed to withstand severe heat. The dimensions of the unsupported electro-glazed panel should not exceed 4 ft in either direction. The polished plate in prism-glass units should not be less than  $\frac{1}{4}$  in in either direction, with a minimum thickness of  $\frac{3}{16}$  in. In Report No. 1 of the Insurance Engineering Experiment Station, C. L. Norton describes the results of comparative fire-tests on electro-glazed Luxfer prisms, 0.35 in thick and 4 in square; electro-glazed plate,  $\frac{1}{4}$  in thick and 4 in square; and  $\frac{1}{4}$ -in wire-glass.

The results of these tests indicate that the three materials, in sheets up to 30 in, are of equal value in FIRE-RESISTANT PROPERTIES and remain in effective operation up to the time when the temperature of melting glass is reached. (See, also, page 1578.)

**Fire-proof Paint.** Numerous so-called FIRE-PROOF PAINTS have been introduced in recent years. When applied to woodwork they provide a more or less effective protection against fire and may, for this reason, prevent the spread of fire. The following regulations regarding fire-proof paint were given in the annual report of the Manhattan Bureau of Buildings, New York, 1914.

The term FIRE-PROOF PAINT shall be understood to mean any preparation used to cover the surfaces of wood or other materials for the purpose of protecting the same against ignition.

No fire-proof paint will be considered satisfactory unless it so protects wood or other material to which it is applied that the same will not flame

or glow after having been subjected to the flame of a gasoline torch for 10 minutes.

“(3) Before applying fire-proof paint to any material the surfaces must be cleaned.

“(4) Application of fire-proof paint must be repeated whenever it is found that the material to which it is applied is no longer protected to fulfill Specification No. 2.”

3. Column-Protection

**Girder and Column-Protection.** As the columns and girders of a building form the BACK-BONE of the structure, it is of vital importance that they be thoroughly protected from heat. As a rule, the manner of protecting these structural elements depends quite largely upon the floor-system adopted. Where concrete is used for the floor-construction it is generally also employed for incasing the columns and girders; where hollow tile is used in the floors, the same material is almost invariably employed for protecting the steel frame. The methods used for protecting girders are described in Subdivision 4 of this chapter. (See, also, pages 780 to 782.)

**Necessity for Column-Protection.** It is now generally recognized that iron and steel columns should be incased with some material that will thoroughly protect the metal against fire. In 1896 a committee of the American Society of Mechanical Engineers, in conjunction with representatives from other organizations, made a series of fire-tests on full-sized unprotected cast-iron columns and steel columns, loaded to their figured safe capacities. These tests showed that the steel columns failed at an average temperature of 1150° F., and the cast-iron columns at an average temperature of 1300° F., the failure setting in after an exposure to the fire of from 23 minutes to 1 hour and 20 minutes, or an average duration of about 50 minutes. In order to determine the relative value of several materials as satisfactory protective coverings, the Bureau of Building

Table IV. Tests of Protective Coverings

Materials under test	Temp. on face of pro- tective material, degrees Fahr.	Temperature of plate at back of protective material, degrees Fahr.		
		Before heating	After heating for 2 hr	Heat trans- mission
Terra-cotta: dense, hollow, 2 in thick..	1700	75	223	148
Terra-cotta: semiporous, solid, 2 in thick.....	1700	73	244	171
Plaster of Paris and shavings, 2 in thick.....	1700	69	159	90
Plaster of Paris and asbestos, 2 in thick.	1700	70	163	93
Plaster of Paris, wood fibers, and in- fusorial earth, 2 in thick.....	1700	72	167	95
Concrete of ground cinders, 1½ in thick.....	1700	73	363	290
Cinder concrete, on metal lath, 2 in thick.....	1700	66	248	182
Metal lath and patent plaster, about ½ in thick over 1 in air-space.....	1700	76	296	218



New York City made a series of tests on the HEAT-CONDUCTIVITY of these tiles. A cast-iron plate covered with the material under test was subjected to a temperature of 1700° F. for two hours over a crucible furnace, and the plate was noted at regular intervals of time. The results of the tests are in Table IV on page 822.



Fig. 2. Hollow-tile Protection.  
Cylindrical Column




Fig. 3. Ribbed-tile Protection.  
Cylindrical Column

set in cement mortar, occasionally, iron, bound with copper wire at intervals.

Fig. 4. Hollow-tile Protection. Plate-and-angle Column

**Cast-iron Column-Protection.** Fig. 1 shows the manner in which built-up columns are protected in the best class of fire-proof buildings when tile fire-proofing is used. Figs. 2, 3, and 4 show common methods of protecting cylindrical columns, and Figs. 5 and 6 columns of rectangular cross-section. The method shown in Fig. 1, is often employed in mercantile and manufacturing buildings and put on to a height of 4 or 5 ft above the floor. The efficiency of this protection is greatly increased by wrapping the columns with wire lath and plastering, although it is not a common practice. To insure the protection of the metal under the most trying conditions, it is imperative that the



Fig. 5. Solid-tile Protection.  
Cylindrical Column




Fig. 6. Hollow-tile Protection.  
Built-up Box Column



Fig. 7. Hollow-tile Protection.  
Square Column-section

protective covering shall not be detached by the streams from the fire hose, and thus expose the steel. This can be positively guarded against by using two layers of tiling or concrete and wrapping the inner layer with metal lathing. Fig. 7 shows a column protected in this way, the construction being essentially that adopted in the Fair Building in Chicago, Ill.

inner layer of tiles is wrapped with wire lath embedded in the mortar, and spaces between the tiles and metal are filled solid with cement and tar.

**Concrete Column Protection.** When concrete is to be used for column-protection the way to obtain the most efficient construction is undoubtedly to surround the metal member with concrete, poured inside of a plank form set around the column, a coat of liquid cement being first applied with a brush to the metal. The plank form should be set at least 2 in.

side of the metal. It is generally conceded that this forms one of the most efficient fire-casings for columns, and, in addition, lends added stiffness to the members embedded in it. It is advisable to reinforce the concrete or anchor it

Fig. 7. Double-tilt and Metal-lath Column-protection

#10 Galv. Steel Wire Loops




Fig. 8. Concrete Column-protection and Wooden Form

Fig. 9. Concrete Column-protection and Wooden Form

use of metal lath to the steel column. There are two general methods in applying the concrete. Fig. 8 illustrates a column which is first wrapped with No. 10 gauge galvanized wire, 12 in on centers, to afford a key to the concrete. The wood forms are placed the full length of the column, the concrete poured from a hole in the ceiling above. A slush-mixture of 2 cinder or stone concrete of 1 : 2 : 5 mix may be used. Fig. 9 shows a form of boards, made in sections from 4 to 6 ft in length and provided with pins at each end. The concrete may be thoroughly tamped about the column in each section is placed and filled. Fig. 10 shows a method of furring the column with stiffened wire lath, which serves as a substitute for the wooden forms and at the same time anchors the concrete to the steel. A similar

### Furring

10

Concrete Column-protection. Fig. 11. Metal-lath and Plaster Column-protection  
Wire-lath Furring

It may be employed to obtain an air-space by placing immediately about the column an envelope of metal lath with a 2-in layer of concrete. In buildings with reinforced concrete floors, the columns are protected by plaster on metal lath. When only a single covering is provided, protection cannot properly be considered fire-proof; but when two coverings are provided, as in Fig. 11, they are probably all that is necessary for cast columns. The greatest defect in lath and plaster for fireproofing is that plaster is liable to be dislodged by the force of the water from the firemen's hose. When there are two coverings, however, this danger is reduced to a minimum. (See, also, Chapter XXII, Figs. 23, 24, and 25.)

**Plaster Column-Covering.** Plaster-blocks have been used in buildings as column-covering, but their use is not to be recommended. While it is true that plaster has a low **NON-CONDUCTIVITY** is in their favor, it is difficult to secure them. They are easily washed away by hose-streams and subject to greater deterioration than other materials. In unimportant work their cheapness may, at times, justify their use.

**Protection of Connections between Columns and Girders.** The most vulnerable parts of the coverings of columns, whatever the materials used, are those about the connections with the beams and girders. Concrete is better adapted for covering these parts of the column than any other material, because, being elastic, it can be made to fit into any space and any form of connection.

**The Cement-Gun.** During recent years, a new method of protecting structural steel by means of the CEMENT-GUN has been introduced. This consists essentially of two superimposed tanks, forming two compartments from the bottom of which a dry mixture of sand and cement is ejected by compressed air through a hose-line with a nozzle at the end. To this nozzle a second hose delivers a supply of water under pressure, which is applied to the dry constituents just before they emerge from the nozzle. The mortar issuing in form of a spray shoots out from the nozzle with considerable force and impinges on the surface of the steelwork. The columns of the fifty-five-story Woolworth Building in New York City are provided with a  $1\frac{1}{2}$ -in coating of cement mortar applied in this way, and coated on the outside with a thickness of terra-cotta. The steelwork, also, of the new Grand Central Terminal Buildings in New York City are protected with a 2-in coat of cement mortar or Gunnite. By this means, inaccessible corners are readily protected without the use of forms. Tests have shown that Gunnite is superior in tensile and compressive strength, permeability, absorption, porosity, and adhesion to good hand-made products of the same kind.\*

**Recesses for Pipes.** "As a matter of economy, both in original cost and in the matter of space, it has been the common practice to run water-pipes, waste-pipes, and vent-pipes immediately alongside the steel columns and in the fire-resisting covering."† This is undoubtedly bad construction, as Fre

FIG. 12. Tile Column-protection with Pipe-space

FIG. 13. Concrete Column-protection with Pipe-space

illustrates by explaining its disastrous results in recent conflagrations; as the better types of fire-proof buildings, the pipe-space is now separated from the columns by the fireproofing. Fig. 12 shows a method of running the pipes in some fire-proof buildings, and it is probably as satisfactory as any arrangement in which the pipes are to be run beside the columns. Fig. 13 shows somewhat similar method in which concrete, metal lath, and plaster are employed for the fireproofing.

#### 4. Fire-proof Floor-Construction

**Fire-proof Floors.** In the study of fireproofing-materials by far the greatest attention has been given to FLOOR-CONSTRUCTION; and of the very number of types which have been developed, the characteristic and best ones are here considered.

\* Engineering News, 1912, Vol. 67, page 26; and Vol. 68, page 2086.

† Fire Prevention and Fire Protection. J. K. Freitag, page 374.

**Requirements for a Fire-proof Floor.** It goes without saying that a fire-proof floor must be made of incombustible materials. It seems unnecessary, to mention that it must resist as much as possible the transmission of heat, so as to afford thorough protection to the metal incased by it or forming an essential part of it. The materials used should not disintegrate or otherwise be damaged when exposed to heat or flame. They should also resist the action of water which may be used to extinguish a fire. The floor-construction should be essentially water-tight, so as to prevent damage by water in stories below. It should be designed to safely carry its load at all times. The New York City Building Code describes certain acceptable forms of fire-proof floors, but also provides for the acceptance of other forms which successfully meet the prescribed fire and strength tests. Fully eighty tests have been made under the auspices of the New York City authorities and these, together with a few made by the authorities of other cities, comprise practically all that have been made in this country. The British Fire-Prevention Committee of London has also made a number of such tests.

**Tests for Floors.** The STANDARD FIRE TEST of the American Society for Testing Materials† is essentially the same as that required by the New York City Building Code and as the one used by the British Fire Prevention Committee. Briefly, the New York test consists in subjecting the floor in question to a load of 150 lb per sq ft, to a fire maintained at 1700° F. for four hours; and then in applying a stream of water, at 60-lb nozzle-pressure, for ten minutes, the floor being considered satisfactory if there has been no appreciable deterioration due to the test and if it has resisted the passage of flames during the test.

**Classes of Floor-Constructions.** In considering the several systems of floor-construction, they are for convenience divided into the following types or classes:

- (1) Brick arches,
- (2) Terra-cotta or tile floors:
  - a. Segmental,
  - b. Flat side-construction,
  - c. Flat end-construction,
  - d. Reinforced-tile arches,
  - e. Guastavino,
- (3) Concrete floors:
  - a. Segmental,
  - b. Flat reinforced floors,
  - c. Sectional systems,
- (4) Gypsum floors,
- (5) Metal-lumber-construction.

**Floor-Arches.** The first attempt at fire-proof floor-construction using wrought-iron beams was made by using BRICK ARCHES sprung between the beams and resting on the bottom flanges, as illustrated by Fig. 14. When this method of construction is used the bricks should be hard, well-burned bricks, of good shape, laid to a line on centers without mortar, with the vertical edges touching; and all the joints should be filled in with cement. The bricks of one line should break joints with those of the next adjoining, and if there is more than one row, the joints of one row should also break joints with those of the next row.

† List of these tests made in the United States and in London, see Proc. Am. Soc. Test. Mats., Vol. VI, page 128.  
 See also Year Book, Am. Soc. Test. Mats.

joints with those of the row above or below. The arches need not be over 4 in. thick for spans between 6 and 8 ft, provided the haunches are filled with a good cement and gravel concrete, put in rather wet. The rise of the arch should be about one-eighth the span, or  $1\frac{1}{8}$  in to the foot; and the most desirable span

FIG. 14. Brick Floor-arch

is between 4 and 6 ft. The building laws of many cities provide that when spans exceed 5 ft the arches must be increased in thickness, generally to 8 in. The HAUNCHES should be filled with concrete, level with the top of the arch. In first-class fire-proof construction the bottom flanges of the beams should be protected by terra-cotta SKEWRACKS, as in Fig. 15 which shows the construction

FIG. 15. Brick Floor-arch. Government Printing Office, Washington, D. C.

used for the floors of the principal stories of the Government Printing Office, Washington, D. C.\* A 4 in brick arch of 6-ft span, well grouted and leveled with Portland-cement concrete, should safely carry 300 or 400 lb to the sq foot. Experiments have shown that brick arches will stand very severe pounding and a great amount of DEFLECTION without failure. The WEIGHT of a floor such as is shown in Fig. 14, is about 40 lb per sq ft, without the concrete finish. TIE-RODS, as described on page 865, should always be provided. A brick arch is the strongest type of arch for the span it occupies, with the exception, perhaps, of the stone-concrete arch. It is perhaps, also, the most expensive. Its weight necessitates a heavier framework than is required for other types, and, on account of its appearance, it is adapted only to buildings of the warehouse type.

**Terra-Cotta or Tile Floor-Arches.** TERRA-COTTA or TILE as a fire-proofing material, and the relative merit of dense, porous, and semiporous tile have been discussed on page 815. For floor-construction the semiporous tile is probably the best as it is a compromise between the advantages and disadvantages of dense and porous tile, particularly as to strength and fire-resistance. As

\* A description of the structural features of this building may be found in the *Engineering Record* for Dec. 6, 1902.

On page 827, five different types of terra-cotta floor-construction, including a great number of systems, will be discussed. For these a great variety of shapes and sizes of blocks, of the dense, porous, and semiporous material, are manufactured in this country. The largest company devoted to the manufacture and erection of hollow-tile fireproofing-material is the National Fireproofing Company, New York and Chicago. Another large company is Henry Mercer & Son, New York. Any one of the large companies can make any size of blocks desired, except such as are covered by letters-patent, and, as a rule, they can make them in dense, porous, and semiporous material.

**Advantages of Tile Floor-Arches.** Many architects prefer the use of TERRA-COTTA ARCHES in buildings because the setting of them causes less disturbance to the mechanics of other branches of the construction. During the setting of CONCRETE ARCHES the continual-dripping of water and bits of concrete interferes seriously with other work. The work of installing tile arches is generally more rapid than for other types and it is not necessary to wait for the mortar to dry out. The quality of terra-cotta can be readily judged from its appearance, not only before it is put in place but also after it is set. Thus it does not require the constant supervision necessary for materials that are mixed and then put in place.

**Disadvantages of Tile Floor-Arches.** The principal DISADVANTAGE OF TERRA-COTTA ARCHES for floor-construction is the difficulty of adapting any system to the fitting of irregular-shaped spaces. The arches must be set between I beams or girders, and to get the best effect the supporting beams must be parallel or perpendicular to the arches. Tile arches, especially of the END-CONSTRUCTIONS, are weakened by holes for pipes than are the monolithic floors. As there is no bond between the rows of tiles in the END-CONSTRUCTION arch, if a single tile in a row is out or omitted, there is nothing to hold up the remaining tiles in the row except the adhesion of the mortar in the side joints. In this respect SIDE-CONSTRUCTION arches have an advantage over the END-CONSTRUCTION. Where it is necessary to use considerable concrete filling over the arch the weight of the construction will usually greatly exceed that of the concrete systems, and the additional weight means, also, additional expense. The floor-blocks are subject to breakage and chipped blocks in the floor are not unusual.

**Inspection of Floor-Arches.** Flat arches of hollow tile require close INSPECTION during erection to see that broken or imperfect tiles are not used; that the tiles in END-CONSTRUCTION abut opposite each other; that all joints are properly mortared and that all of the steelwork is properly protected. Much care and workmanship has been allowed to pass in order to avoid delay, and also because it cannot be discovered until the centering is removed. A tile arch always looks better on the top surface than it does on the bottom.\*

**Setting of Tile Floor-Arches.** Tile arches are always SET on wooden centers suspended by bolts hooked over the tops of the I beams. For all spans and over, the centers should be slightly CAMBERED. Before any floor-arches are set, all girders projecting below floor-beams should be completely covered on the bottom and sides, independently of the floor-construction. To protect the steel from rust it should have a good coat of Portland-cement mortar before the tiles are applied. After the centers are in place the beam-tiles should be laid under the bottom of the beams and mortar slushed on the sides. The ends of the SKEWBLOCKS which rest against the floor-beams should then be covered with just enough mortar to give them a perfect bearing, and shoved

careless workmanship possible in the setting of tile arches was clearly set forth in *Engineering News*, April 14, 1898.

up against the beams. After this, the **INTERMEDIATE BLOCKS**, with their ends on one end and one side covered with a full bed of mortar, should be shoved into place. The **KEYS** should have mortar on both sides and one end, if **SMALL METHOD KEYS** are used, and they should fit snugly, but not tight. "Under no conditions should a key be rammed in place. It is better to use a smaller key and fill out the space left with either a solid slab of tile, or, if the opening is too small, with a piece of slate."\* "In setting tile arches it is very common to build the arches in **STRING-COURSES**, first fitting all the skewers, then all the intermediate blocks and finally all the keys. This is bad practice, as it loads the center, both plan and stringers, to excess, causing too great a deflection. In the **END-CONSTRUCTION** the arches should be built one by one, each being complete before the next is started. In **SIDE-CONSTRUCTION**, where joints are broken longitudinally, the arches should be keyed up or completed at the first point where the intermediates meet the lines of the key, thus completing the successive arches as rapidly as possible."† All joints in the arches should be filled with mortar, especially at the top.

**Wetting the Floor-Tiles.** In warm weather all hollow tiles, whether dense or porous, should be well wet or water-soaked before laying. In freezing weather they must be kept dry.

**Mortar for Setting Floor-Tiles.** "Mortar for setting porous hollow tiles should never be made of cement and sand alone, as such mortar is too strong and rolls off the tile, and does not insure a full joint."\* A good mortar is made by mixing the cement and sand in the proportion of 1 : 3, and adding either lime putty or hydrated lime to the extent of 10% of the cement-content. The mortar should be thoroughly worked. Hot lime mortar should never be used. In dry weather the centers can be removed in 36 hours after the tiles are in place, but it is much better to allow 48 hours and even longer in cold or wet weather.

**Filling above Tile Floor-Arches.** The strength of all tile arches is greatly increased by wetting their top surface and covering it with a rich cinder concrete, mixed with Portland cement, well tamped and brought level with the tops of the steel beams. If the floors are to be finished in wood, **NAILING-STRIPS** are required to secure the flooring. These nailing-strips are usually dovetail shape in cross-section, about 2½ in wide at the top, 3½ in at the bottom and from 1¾ to 2 in thick. It is preferable to lay them at right-angles to the steel beams, so that they may be secured to the top flanges by metal clips, as in Fig.




Fig. 16. Segmental Tile Floor-arch

Before the nailing-strips are laid, all piping and wiring which must go through the tile arches should be put in place. After the nailing-strips are in place the tops of the steel beams should be covered with a thin coat of

\* E. A. Hoeppner.

† Freitag.



1-cement-and-sand grout, applied with a brush. The spaces between the ing-strips should be filled with a 1 : 8 or 1 : 10 cinder concrete, finished at  $\frac{1}{4}$  in below the tops of the strips. Some architects claim better results with strips of rectangular section, with nails driven horizontally into the vertical sides to form the grip in the concrete. This method avoids the loosening of the strips and flooring from any shrinkage of the strips.

**Filling-Blocks.** In cases where the tops of the tile arches are 2 in or more below the tops of the steel beams, hollow tile blocks are sometimes used filling to the top of the beams, as in Fig. 23. These blocks are lighter than concrete, but they do not strengthen the arches.

**Cement Floors.** If the floors are to be finished with cement, the cement and sand should be at least  $2\frac{1}{2}$  in and preferably 3 in thick above the steel beams, and should be blocked out in sections of not over 6 ft square, with joints extending through the concrete. When practicable the joints in one direction should be over the beams.

**Weather-Protection.** Terra-cotta arches should always be protected against snow, especially in freezing weather, as both the blocks and the mortar joints are injured by freezing. Porous terra-cotta, especially, may be ruined by freezing when soaked with water.

**Protection of Ceilings from Stains.** "If plastered ceilings are to be used, terra-cotta work should be protected against the smoke or soot from the gas-engines. Stains are also quite liable to occur from the effects of iron scale, or from the cinders in the concrete over the arches, if the floor is allowed to become wet." \* To prevent these stains several kinds of hydraulic cement have been used, some of which have proved very effective.

**Segmental Tile Floor-Arches.** "This form of arch is the strongest and most durable. It is particularly adapted to warehouses, lofts, factories, sidewalks, wherever great strength is required and a flat ceiling is not necessary. When a very strong arch is required in deep beams and a flat ceiling is also demanded, a flat ceiling can be obtained by using a metal-lath ceiling suspended below the arch." † These arches are usually formed by either 6 or 8-in hollow tiles, and are constructed on the SIDE-CONSTRUCTION principle and bonded endwise like a brick vault.




Fig. 17. Segmental Tile Floor-arch. Deep Skew

can be used for spans up to 20 ft, but it is better to limit the span to 10 ft. "END-CONSTRUCTION blocks may be used, but they are unsatisfactory unless the arches are of uniform span and rise throughout. The rise of the END-CONSTRUCTION arch can be varied by increasing the thickness of the lower part of the mortar joint, but this cannot be done with the END-CONSTRUCTION method." †

\* Freitag.

† Bevier, National Fire Proofing Company, New York City.

Figs. 17 and 18 show typical forms of SEGMENTAL ARCHES. The weight of the arch-tiles will run about 26 lb per sq ft for 6-in tile and 32 lb for




Fig. 18. Segmental Tile Floor-arch. Deep Beam. Dropped Skew

tile. To these weights should be added the weight of concrete filling, floor plaster, etc.

**Thickness of Webs.** "For general use the WEBS of segment-tile should be  $\frac{1}{2}$  in thick for semiporous tile and  $\frac{3}{4}$  in for porous tile. The SKEWBACK should be at least  $\frac{3}{4}$  in thick for the first-named material and 1 in for the second. In printing-establishments or any other building where a large amount of vibration occurs the webs of all tiles must be designed in proportionate thickness to the load they are required to carry."\* These thicknesses apply to Chicago practice more particularly, where a stronger tile is produced than in the East. In New York City webs are generally  $\frac{1}{2}$  in thick for semiporous and 1 in for porous tiles.

**Rise of Segmental Floor-Arches.** The RISE of the soffit of the arch at the springing-line should be from one tenth to one eighth the span. The greater the rise the less will be the THRUST of the arch. No single-cell tiles should ever be used in any form of terra-cotta arch-construction.

**Filling the Haunches.** The HAUNCHES of SEGMENTAL ARCHES should be filled with good cement concrete-leveled up to a point not less than 1 in below the CROWN of the arch. For short spans cinder-concrete filling may be used, but for wide spans it is better to use gravel concrete, as the concrete contributes to the strength of the arch at the haunches.

**Tie-Rods.** The THRUST of segmental arches is very considerable, so it is important to provide TIE-RODS between the beams. A formula for determining the STRESS in the tie-rods and their diameter is given on page 865. For the most effective the tie-rods should be placed at the center of the skew. Placing the tie-rods in this manner, however, may cause them to project below the SOFFIT of the arch, giving an unsightly appearance to the ceiling. It is more difficult to protect them when in this position.

**Strength of the Segmental Semiporous-Tile Floor-Arches.** The LOADS per square foot on 6 and 8-in segmental arches, with side-construction semiporous tile, a rise of one-eighth the span, webs and shells  $\frac{5}{8}$  in thick with a factor of safety of 7, as obtained from the tables of the National Fireproofing Company are given in Table V.

**Side-Construction Tile Floor-Arches.** By this term is understood flat-tile arches in which the voids in the blocks run parallel with the beams, as shown in Fig. 19. One advantage of this arch over the end-construction

\* E. A. Hoepfner.

Table V. Safe Loads for Segmental Semiporous-Tile Floor-Arches

Span, ft	6-inch arch, lb	8-inch arch, lb	Span, ft	6-inch arch, lb	8-inch arch, lb
4	1 103	1 318	11	402	480
5	878	1 049	12	370	442
6	735	883	13	340	407
7	630	735	14	317	379
8	554	662	15	296	353
9	490	585	16	278	331
10	443	529	.....	.....	.....

e loads include the weight of construction; so that to get the safe live load, all load of arch-blocks, concrete fill, plastering, flooring, etc., must be deducted.

**MAKING OF JOINTS** that is effected in the setting of the blocks, by means which the failure of a single block does not impair the strength of the arch in that block. The **WEBS** should not be less than  $\frac{1}{4}$  in thick. "RADIAL" are sometimes specified but should be avoided, as they incur needless expense in manufacture and endless confusion and delay in setting, without any




Fig. 19. Flat Tile Floor-arch. Side-construction

sating advantage."\* In the **SKEWBLOCKS** a web should always be projected across the block at the lower flange of the beam, as at this point comes the greatest pressure in this block. Arches have collapsed because of failure of this web. The **DEPTH** of the arch must be proportioned to the span, the beams and to the load to be carried. For ordinary loads, a safe rule is to make the depth of the block  $1\frac{1}{4}$  in for each foot of span, plus the depth necessary for protection below the beams. **SAFE LOADS** for semiporous-tile, side-construction, with webs  $\frac{1}{4}$  in thick and a factor of safety of 7, as given by the National Fire Proofing Company, are shown in Table VI.

**Construction Flat Floor-Arches.** In this construction the sides and the individual blocks run at right-angles to the beams, so that the pressure on the blocks is endwise of the tile. It has been conclusively demonstrated that flat tiles are much stronger in **END-COMPRESSION** than transversely. The objection urged against this construction is that it is wasteful of mortar in the joints. It is difficult to get the edges of the blocks properly bedded. They do require more mortar, but the second objection is not serious, for, if the blocks are set on a proper bevel, the tighter they are set the stronger the arch.\* The blocks in the **END-CONSTRUCTION** are commonly made rectangular, advancing by 1 in from 6 to 15 in in depth. The length and width of the blocks may be varied, but the standard size is 12 in for both dimensions. The number of partitions or webs in the blocks varies with the size of

\* Bevier, National Fire Proofing Company, New York City.

Table VI. Safe Loads for Semiporous, Side-Construction, Tile Floor-Arch

Depth of arch	6 in	7 in	8 in	9 in	10 in	12 in
Weight of arch per sq ft	24 lb	26 lb	27 lb	29 lb	34 lb	37 lb
Span of arch, ft in	Strength of arch in pounds per square foot					
4 0	197	230	263	296	438	521
4 6	156	182	208	233	346	411
5 0	.....	148	168	189	281	333
5 6	.....	.....	139	156	232	277
6 0	.....	.....	.....	131	195	233
6 6	.....	.....	.....	.....	166	199
7 0	.....	.....	.....	.....	.....	177

These loads represent the GROSS LOADS; so that for the SAFE LIVE LOADS the weight of the construction, including the arch-blocks, fill, flooring, plastering, etc., must be deducted. For blocks with thicker webs the loads may be increased proportionally. Where no loads are given in the table, the spans are considered excessive for the depth of block specified. The weights of arch given in the table are for the lightest blocks. If thicker webs are used, the weight of block must be taken proportionally greater.

the blocks and also with the strength desired. The 6-in, 7-in, and 8-in blocks usually have two vertical partitions and one horizontal partition, or one vertical and one horizontal, for blocks 8 in wide. The 10-in and 12-in arches may have either one or two horizontal partitions. Arch-blocks over 12 in deep should always have at least two horizontal partitions. In the strongest block arches the voids are about 3 in square. "The arch-blocks must be set end to end in straight courses from beam to beam, and cannot be set with breaking joints, as in the side-construction method."\*

**Thickness of Web.** This should be at least 3/4 in for porous and 1/2 in for semiporous tiling. The thicker the webs the greater will be the strength and fire-resistance of the arch. The end-joints are always beveled, as in Fig. 19, the ends being parallel; thus all the intermediate blocks are made with the same die.

**Form of Skewback.** An end-construction arch may have a skewback formed of the same blocks, with notches in the ends of the blocks to fit over the





FIG. 20. Flat Tile Floor-arch. End-construction

bottom flanges of the beams, as in Fig. 20. It is generally considered that the end-construction skewback is much stronger than the side-construction

\* Bevier.

but on account of the large amount of mortar lost in the voids and the difficulty of obtaining an even bearing with end-construction skewbacks, also, because of the greater facility with which the side-construction skewbacks can be used, contractors generally prefer to use the latter; and this has given rise to the form of arch shown in Fig. 21. But a more important reason for using side-construction skewbacks with end-construction arches is the better protection against fire that they afford to the beam or girder. To develop the necessary strength, side-construction skewbacks should have a large sectional area and a sufficient number of partitions, following, approximately, the lines of the arch. With any form of skewback the recess for the beam-flange should be of sufficient width, so that when the tiles are set the protecting flanges on the skewbacks will not touch the bottom of the beams, but will be at least  $\frac{1}{4}$  in. below. Many varieties of side-construction skewbacks are made to meet all possible conditions.

20. Both end-construction and side-construction KEYS are used with end-construction arches, the choice of the key depending principally upon its



21. Flat Tile Floor-arch. Combination End-construction and Side-construction

22. If the span of the arch is such that the standard intermediate blocks require a key 6 in. or more in width, the END-METHOD KEY is used, as in Fig. 20; if the space for the key is small, a SIDE-METHOD KEY, such as shown in Fig. 21, is used. As the key is almost entirely in compression, a side-construction key much less in width will usually give all the strength required, provided that the vertical webs are in the same line with those in the intermediate blocks. E. V. Brown, western manager of the National Fire Proofing Company, says: "We recommend the use of an end-construction key in all cases where possible. Our customers use side-construction keys for spaces of 6 in. and under, and end-construction keys for larger spaces. When using the latter keys we insert a fire-clay slab between the ends of the tile."

**Raised Skewbacks.** Where flat arches are sprung between 18-in., 20-in., or 24-in. beams it is necessary either to use a RAISED SKEWBACK or else to have a large space above the top of the tile arches which must be filled in some way. Raised skewbacks are preferable to a hollow space above the tiles and cheaper than the filling. They are often used for roof-arches, because for that purpose it is seldom necessary to make the arches as deep as the beams, while the top must be about on a level with the beams. Raised skewbacks are almost always made on the side-construction principle. Fig. 22 shows a typical formed skewback for end-construction arches.

**Flat Versus Paneled Ceilings.** In connection with the raising of the floor above the bottom of the beams or girders, J. K. Freitag calls attention to the advantages of FLAT CEILINGS, as follows: "Flat, unbroken ceilings are to be preferred to any type of terra-cotta arch which may require a decorative effect due to the projection of the girders or beams below the main

ceiling-line." A perfectly flat ceiling reflects more light, makes a better-light room, and deflects the heat. Paneling forms pockets for the retention of I and flame and greatly increases the exposed area.

Fig. 22. Raised Skews for End-construction Arches

**Floor-Arches and Beams of the Same Depth.** A deep block makes a stronger floor than a shallower one, and for the same depth of beams a lighter and cheaper floor. A 12-in arch weighs less per square foot than a 10-in arch with 2 in of concrete filling; and it costs less.

**Depth, Span, and Weight.** The MAXIMUM SPANS for different depths and the AVERAGE WEIGHTS per square foot of this type of arch, set in place, are as follows:

Table VII. Maximum Spans for Flat Tile Floor-Arches of Different Depths and Weights

Depth of arch, in	Maximum span, ft in	Weight per sq ft, lb
6	4 6	29
8	5 6	31
9	6 0	32
10	6 6	33
12	8 0	39
13	9 0	46
16	10 0	50

The weights per square foot, as given by different manufacturers vary greatly, no doubt, to the character of the material used and to the thickness of the webs.

The DEPTH OF ARCH most frequently used is 10 in, the girders being spaced to use 10-in I beams for joists spaced from 5 to 6 ft apart. As a rule the depth of the arch should be about equal to the depth of the beam, as it is just about as cheap and much better construction to use deeper tiles and less concrete filling.

**Safe Loads for End-Construction Tile Floor-Arches.** The strength of flat arches of hollow tile depends upon the CRUSHING RESISTANCE of the material, the sectional area per linear foot of arch, the depth, and the span. For these reasons it is impossible to give a table for strength which applies to all arches. The values given in Table VIII for END-CONSTRUCTION arches are based on arch-blocks of the cross-sectional areas, per foot, given in the second horizon


of the table, and are intended to have a FACTOR OF SAFETY of 7, with the weight of the tile only, deducted. Mr. Hinton says: "The SAFE LOADS as they are given in the table afford a safe general statement of SAFE LOADS FOR ALL SECTIONS; and they represent specifically a light section in the case of each arch."

**Table VIII. Safe Loads for End-Construction Tile Floor-Arches \***  
The loads are in pounds per square foot of floor

Depth of arch in inches	6	7	8	9	10	12	15
Areas, sq in	310	340	370	400	430	490	580
Spans, ft in	1b	1b	1b	1b	1b	1b	1b
4 6	196	254	319	391	470	648	968
5 0	155	202	254	312	376	519	777
5 6	.....	163	206	254	306	424	636
6 0	.....	.....	170	209	253	352	529
6 6	.....	.....	141	175	212	295	446
7 0	.....	.....	.....	147	179	251	380
7 6	.....	.....	.....	.....	153	215	326
8 0	.....	.....	.....	.....	.....	185	282

\* This table is condensed from two tables prepared by H. L. Hinton.

**Patented End-Construction Tile Floor-Arches.** Figs. 23 and 24 show variations of a type of arch invented and patented by E. V. Johnson when



**FIG. 23. Excelsior End-construction Tile Floor-arch. Side-skew**

of the Pioneer Company, Chicago, Ill. The right to manufacture and use this arch, in certain territory, has been granted to the National Fire Proofing Company, and to Henry Maurer & Son, New York City. The original shape of the tile is illustrated in Fig. 24. Henry Maurer & Son have modified the shape of the arch shown in Fig. 23, as they consider that this shape gives a stronger and heavier arch than one of the original shape. The advantages of this arch are the reduction in weight for an equal strength, and the clear space of 5 inches between the tiles, which avoids the cutting of the blocks for the tie-rods. The arch can be adapted to any span up to 10 ft by using blocks of suitable depth.

FIG. 24. Johnson End-construction Tile Floor-arch. Original Form

The LIMIT OF SPAN, WEIGHT PER SQUARE FOOT, and SAFE LOAD of the Excelsior arch (Fig. 23) is given by Maurer & Son as follows:

Table IX. Maximum Spans for Excelsior Tile Floor-Arches

Depth of arch, in	Limit of span, ft	Weight per sq ft, lb	Safe load per sq ft, lb
8	5 to 6	27	300
9	6 to 7	29	350
10	7 to 8	33	300
12	8 to 9	38	350

The National Fire Proofing Company has made arch-blocks as deep as 21 in and as heavy as 56 lb per sq ft. This company and Henry Maurer & Son use semiporous material for the arch-blocks. It should be noticed that the arch made by the former has an END-CONSTRUCTION SKEWBACK, while the latter uses SIDE-CONSTRUCTION SKEWBACK. The National Fire Proofing Company formerly used the side-construction skewback, but found that when arches of this type were tested to destruction the skewbacks were almost invariably the part which failed, hence their adoption of the end-construction skewback. Henry Maurer & Son, however, have tested, without failure, Excelsior arches of 8 ft to 10-ft spans, and with skewbacks as shown by them, with loads of over 1,000 lb per sq ft. These arches have been extensively used in both eastern and western cities.

**Reinforced-Tile Floor-Arches.** In order to obtain a wide-span flat arch and to obtain a reduced depth of arch-block for the shorter spans, the manufacturers of terra-cotta have applied to their floor-construction the principle of REINFORCEMENT WITH METAL, which is the basis of reinforced-concrete construction. Compared with reinforced concrete, even when cinders are used for the aggregate, the greater depth and hollow construction of these REINFORCED-TILE ARCHES secure for them greater strength per square foot for the same weight of construction. On the other hand, however, they are undoubtedly more expensive than cinder-concrete floor construction, because of the material used and the increased height of the building due to thicker floors.

**The Herculean Arch.\*** These floor-arches are built of semiporous terra-cotta blocks, 12 by 12 in on top and varying from 6 to 12 in in depth, according to span.

\* Patented and manufactured by Henry Maurer & Son, 1898 and 1900.



span and load. In the sides of the blocks are grooves to receive  $1\frac{1}{4}$  by  $7\frac{1}{2}$ -in T bars. The blocks are laid end to end the entire length of the span with a bearing of from 4 to 6 in on the walls or girders, presenting two longitudinal grooves, which are filled with cement mortar, and into which the T bars are then inserted. The T bars must, of course, extend the full length of the span. The grooves in the next course are then filled with cement mortar and the blocks pushed into place, thus thoroughly covering the steel with mortar. The joints between the blocks are filled with cement mortar and the blocks are laid in break joint endwise, as in Fig. 25. This floor has been used for spans

Fig. 25. Herculean Reinforced, Tile Floor-arch

from 19 to 23 ft. The weight per square foot given for the terra-cotta blocks and steel T bars is 26 lb for blocks 6 in deep, 33 lb for 8-in blocks, 41 lb for 10-in blocks and 51 lb for 12-in blocks. The manufacturers estimate the loads for this construction as follows:

For a 12-in arch with a 20-ft span, 400 lb per sq ft.

For a 10-in arch with a 16-ft span, 400 lb per sq ft.

For a 8-in arch with a 12-ft span, 150 lb per sq ft.

**Chief Advantage** of this construction is said to be its low cost as compared with the cost of systems equally fire-proof and requiring steel beams or 8 ft. It is particularly well adapted to buildings with masonry walls and partitions, as in such buildings little or no structural steel is required. The construction affords, also, an unusually smooth undersurface, thereby saving the cost of plastering. No tie-rods are required for this floor.

**Johnson Long-Span Flat Floor-Construction.** This reinforced-concrete floor was invented by E. V. Johnson, and is now controlled and erected by the National Fire Proofing Company. Its general construction is as follows: Heavy flat centering is first erected, and over this is spread a layer of rich sand-cement mortar about  $\frac{3}{4}$  in thick. On top of this mortar is laid a fabric containing steel rods varying from  $\frac{1}{4}$  to  $\frac{3}{4}$  in in diameter, spaced to the span, and spaced from 2 to 8 in, center to center. Another layer of the same mortar is then spread on top and hollow tiles, from 3 to 12 in in diameter according to the span, are then set in the mortar and laid so as to break

joint and to form continuous rows from one support to the other. A lay of concrete, also, about 2 in thick, is usually spread on top of the tiles. Fig. 2

Fig. 26. Johnson Reinforced, Tile Floor-arch

shows the general method of construction of this system, but without the rod which are inserted in place as the fabric is used. For short spans the fabric can be used without the rods. This system differs from the flat concrete system only in the substitution of hollow tiles for the concrete in the upper portion of the slabs, the strength of the floor depending upon the REINFORCEMENT and the ADHESION of the cement mortar to the steel and tiles. As the tiles are covered both on the bottom and top with concrete, the FIREPROOFING PROPERTY, also, is measured by the resistance of the concrete and not by that of the tiles. Tests have shown that the ADHESION of the mortar is perfect and that it will stand a high temperature without injury. This construction can be used for any span up to 25 ft, the most ADVANTAGEOUS SPAN being about 16 ft. The WEIGHT per square foot, including the fabric and the cement on the bottom and in the joints, but not on top of the tile, is as follows:

Depth of tile, inches.....	12	10	9	8	7	6	5	4
Weight per square foot, in pounds	60	55	45	42	37	34	26	24

The concrete above the tile should be figured at 12 lb per sq ft for each in thickness. The STRENGTH of the floor, with 1 in of 1 : 3 Portland-cement mortar on top of the tiles, is given in Table X.

**The New York Reinforced-Tile Floor-Arch.** This arch (Fig. 27) was designed by P. H. Bevier, of the New York City branch of the National Fireproofing Company, for use "when a light and cheap but strong floor construction with a flat ceiling is required, and is particularly adapted to wide spans in shallow beams. When light floor-construction with deep beams is necessary it can be secured by setting the blocks level with the tops of the beams and using a flat metal lath ceiling, or by omitting the ceiling a panel effect is obtained. When shallow beams are used the blocks are set level and 1 in below the bottom of the beams. Light cinder concrete or dry cinders are used to level up to the top of the beams. A WIRE-TRUSS REINFORCEMENT, similar to that shown in Fig. 28, used in this system, is shipped to the building in reels, and is cut to prop

Table X. Ultimate Strength of the Johnson Floor-Construction

Thickness of tiles in inches								
12	10	9	8	7	6	5	4	3
Ultimate strength in pounds per square foot								
3 375	2 580	2 140	1 850	1 525	1 265	1 000	775	560
2 800	2 310	1 780	1 536	1 264	1 052	832	640	464
2 350	1 800	1 480	1 280	1 064	880	700	540	390
2 000	1 540	1 265	1 100	910	752	595	460	334
1 730	1 325	1 100	950	780	650	510	400	290
1 500	1 160	950	830	680	590	450	348	250
1 320	1 010	840	720	600	500	395	305	220
1 180	900	740	640	578	440	350	270	194
1 020	795	664	570	473	392	310	242	174
844	645	535	462	381	314	250	194	.....
700	536	445	384	316	263	208	.....	.....
587	450	370	320	266	220	.....	.....	.....

he job as required. It is embedded in Portland-cement mortar blocks, so that it is protected both against rust and fire. The open-




FIG. 27. New York Reinforced, Tile Floor-arch

action of the WIRE TRUSS enables the mortar to flow freely all about it and can be thoroughly filled between the blocks, and the wire perfectly




FIG. 28. Wire Reinforcement for New York Floor-arch

The floor has successfully passed the fire and load tests of the buildings, of New York, and as a result has been used in a number of cases in New York. Load tests were made to determine the ULTIMATE strength of the 6-in arch on a 6-ft span, and it was found to be 1 600 lb per sq ft." **Stavino Tile-Arch System.** This is a method, devised by R. Stavino of New York and Boston, of constructing floors, partitions, stair-

cases, etc., by means of **THIN TILES**, 1 in thick, about 6 in wide, and from 12 to 24 in long, all bonded together in Portland-cement mortar so as to make one solid mass. The floors are built by spanning the spaces between the girders with single arches, vaults, or domes, constructed of two, three, or more thicknesses of 1-in tiles, the number of thicknesses depending upon the dimensions of the arches or vaults. In its best application, steel is used in tension only in tie-members; and in place of steel girders, tile girders are constructed of the same material. Wherever steel is used it is embedded in the masonry construction. One of the earliest notable buildings in which this system was used is the Boston Public Library Building, completed in 1895. Some of the later important constructions are the Cathedral of St. John the Divine, New York City; the Minnesota State Capitol Building, St. Paul, Minn.; the Girard Trust Company Building, Philadelphia; the Chicago and Northwestern Railway terminal station, Chicago; the Pennsylvania and the New York Central Railroad terminal stations, New York City; and the Hall of Fame, University of New York, New York City.

An illustration of the wide spans that can be safely used with this system of construction is seen in the Cathedral of St. John the Divine in New York City. The floor above the crypt, measuring 56 by 60 ft, with no interior support and designed to carry a safe load of 400 lb per sq ft, was constructed on this principle. Wherever a **VAULTED CEILING** is desired this form of construction seems to be well adapted for use. Floors built in this way have been tested under the supervision of the New York City Building Department up to 3 700 lb per sq ft, on spans of 10 ft. When used between I beams the only steel beams required are those spanning from column to column. Architects contemplating the use of this system of construction are advised to consult the R. Guastavino Company before letting any contracts. Wherever vaulted ceilings are required this construction should be at least as cheap as any other form of equally fire-proof construction, and it is often cheaper. One particular advantage of this system is that frequently the soffit-course of tile is of **PRESSED OR GLAZED MATERIAL**, making a most effective and permanent finish, as in the case of the City Hall station of the New York City subway. This station was constructed for very heavy loads and without the use of steel.

Incidentally, attention may be called to the **RUMFORD TILE** developed in connection with this construction, to be used as the first course of tile, that is, on exposed surfaces on the interior of auditoriums, on account of its sound-absorbing character. Professor Sabine of Harvard University concluded from his investigations that this tile "has over sixfold the absorbing power of any existing masonry construction, and one third the absorbing power of the best-known felt."\*

**Concrete Floors.** Concrete used in fire-proof floors may be either **PLAIN** or **REINFORCED**. Without reinforcement its use is generally practicable for very short spans only, on account of its weight. In this chapter it is considered only as a **FLOOR-FILLING** between steel beams. Chapter XXIV is devoted to a discussion of the principles governing the design and use of reinforced concrete.

**Advantages of Reinforced Concrete for Floor-Construction.** Although many **ADVANTAGES** are claimed for reinforced concrete over the tile system, the principal advantage is that of economy, taking into account the cost of both the steel framework and the filling between. The other important advantages are less weight per square foot of floor (usually but not always the case), adaptability to irregular framing, and rapidity of construction. Except in the immediate locality of the tile-factories, fire-proof floors of concrete are

\* The Brickbuilder, January, 1914.

ally be placed at less expense than is incurred in setting floors of hollow tile; when the spans permit the use of cinder concrete, the concrete floors are lighter than those of the tile, when both floors have the same strength. Some of the long-span tile-systems, on the other hand, are much lighter than many of the concrete floors that are now being built. The materials entering into the construction of reinforced-concrete floors are readily obtained in almost any locality, no specially prepared material is required, except perhaps in a few special forms of reinforcement, and the work can be done almost entirely by skilled labor. Less capital is required for concrete work than for the tile-constructions, and no material need be carried in stock during an idle period, except tools, mixing-machines, old centering, etc. That the above advantages of concrete are sufficiently proved by the immense amount of reinforced concrete now under construction throughout the world. Wherever a floor is to have a finished, cement surface, reinforced-concrete constructions are considerably cheaper than any tile system, because in the former, the entire concrete is used for its strength, while with the flat-tile arches it merely increases the dead weight.

**Disadvantages of Reinforced Concrete for Floor-Construction.** One of the principal DISADVANTAGE connected with concrete floor-construction is the interference in a large measure with the progress of other parts of the work. During installation, there is a constant dripping from the floor, making it sometimes impossible to continue other lines of work. After the completion of the floor a long time is required, depending upon the weather, for the drying out, before the interior finishing can proceed.

**Composition of the Concrete.** The materials used for concrete are discussed on pages 240 to 241 and on page 817. Portland cement, only, should be used in any floor-construction. For most reinforced-concrete floors, having a span between the steel beams of 8 ft or less, CINDER CONCRETE is generally used for the reason that concrete mixed with cinders is much lighter than that mixed with broken stone or gravel. The usual PROPORTIONS OF CINDER CONCRETE are one of cement, to two of sand, and five or six of cinders. For a first-class concrete the cinders must be screened through a mesh not larger than No. 10, and only hard-coal cinders should be used. Good cinders may sometimes be obtained from power-plants using soft coal, but they must be well cleaned and free from ash. Concrete mixed with common ashes, a mixture occasionally used, has little strength and is totally unreliable. For all spans exceeding 8 ft, either GRAVEL OR BROKEN ROCK should be used, and these should be mixed with one part cement, to two of clean sharp sand, and four of stone or gravel. The WEIGHT OF CINDER CONCRETE will vary from 80 to 110 lb per cu ft, depending upon the coarseness of the material, the quantity of sand, and the amount of tamping. For ordinary purposes a 1 : 2 : 5 cinder concrete should be used, weighing 96 lb per cu ft, or 8 lb per sq ft per inch of thickness.

**Forms of Reinforcement.** While steel in small sections is used almost exclusively for the reinforcement, there is a great variety in the shape and character of the metal employed. Different FORMS OF REINFORCEMENT are described and discussed in Chapter XXIV. All of them may be used, and most of them are now being used in floor-construction. In addition to those forms discussed there, others that are not readily adapted to beam-construction are used in slab-construction. Such are the METAL FABRICS described farther on under different types of construction. The proper position for the reinforcement in floor-construction is that in which it will take the TENSIONAL STRESSES, that is, in floor-slabs, near the lower surface. The most logical form is that of ROD OR BAR. A greater number of small rods or bars is preferable to a smaller number of larger ones, because the proportion of the AREA OF ADHESION between

steel and concrete to the SECTIONAL AREA OF STEEL is greater in the former. This result is apparently attained in systems in which wire fabrics are used. But the disadvantage in the use of the smaller reinforcement is the greater susceptibility of CORROSION and consequent failure of the construction. There is a further disadvantage in the use of wire fabrics; they are easily displaced in the process of placing of concrete, either getting too low and becoming exposed to fire or corrosion, or getting too high with a corresponding weakening of floor. Another detail that must be remembered when using metal fabric is that the mesh must be large enough to allow a good BOND to be formed between the concrete above and below it. Reinforcements in the form of bars set mechanically in the concrete have a tendency to SHEAR through slabs which are subjected to heavy loads. The best and most LOGICAL REINFORCEMENT for fire-proof floors consists of from  $\frac{1}{2}$  to  $\frac{3}{4}$ -in round or square rods, either plain or deformed, spaced at varying distances to suit the spans and loads.

**Necessity for Cross-Bars.** Where wire strands or bars are used for reinforcement it is essential to have CROSS-BARS as well as TRANSVERSE TENSILE BARS, because, when the loads are heavy and concentrated, or when a heavy body falls upon a slab the concrete will crack between the carrying bars. This can be readily demonstrated by testing with a drop-test a floor-slab that has no cross-bars. When the load is UNIFORMLY DISTRIBUTED the cross-bars are brought into play; floor-loads, however, are more often CONCENTRATED THAN UNIFORMLY DISTRIBUTED.

**Segmental Concrete Floor-Arches.** For heavy warehouse-floors ARCH SYSTEMS are preferable to the FLAT SYSTEMS, because in the former the concrete is used in its strongest form, and less reinforcement is required. In warehouses, also, a ceiling formed of a series of arches is not objectionable. For spans between floor-beams of 5 ft or less, a 1 : 6 gravel-concrete arch, 12 in thick at crown and without any reinforcement, should sustain, without cracking, a distributed load of 1 500 lb per sq ft. For spans exceeding 5 ft, the unbraced Austrian experiments (1891-1892) seem to show that the reinforcement of concrete with small I beams adds greatly to the strength of the arch; but small rods or netting are not of sufficient advantage to warrant the additional expense.\* Tests made on arches of 8-ft span gave the following results:

A concrete arch, 3 $\frac{3}{4}$  in thick, 9 $\frac{1}{4}$  in rise, broke at 1 130 lb per sq ft. A Melan arch (wire netting), 11 $\frac{5}{16}$  in thick, 10 $\frac{1}{4}$  in rise, or about one half the thickness of the concrete arch, failed at 1 217 lb per sq ft. A brick arch, 5 $\frac{1}{4}$  in thick, 9.85 in rise, failed at 885 lb per sq ft. A hollow-brick arch, 31 $\frac{5}{16}$  in thick, 11.4 in rise, failed at 401 lb per sq ft. A concrete arch, 13-ft span, 31 $\frac{5}{16}$  in thick, 11.4 in rise, failed at 812 lb per sq ft. A Melan arch, 3 $\frac{3}{4}$  in thick, 11.4 in rise, failed at 3 360 lb per sq ft. The Melan arch had I beams 3 $\frac{3}{4}$  in deep, spaced 12 in apart. The structure was one year old when tested.

The concrete arch, considered as a monolithic construction, if built of plain concrete, is superior to the brick arch. The cinder-concrete arch is inferior only in point of strength. Such an arch should be at least 4 in deep at crown, and the rise should be not less than one eighth the span. Cinder concrete should not be used for spans exceeding 8 ft. The strength of such an arch for ordinary cinder concrete is about the same as that of a 6-in segmental arch of the same span, as given in Table V. All arch systems, whether of concrete or tile, require tie-rods between the beams to take up the thrust of the arch. (See page 865.)

**Weight of Segmental Concrete Arches.** The weight of solid segmental

\* See Architecture and Building, Jan. 4, 1896.

may be found by the following formula which gives results approximately correct when the rise of the arch is not more than one sixth of the span:

$$W = (w/12)(c + 4S/p)$$

which

- $W$  = weight of arch, in pounds per square foot;
- $w$  = weight of material, in pounds per cubic foot;
- $c$  = thickness of arch at crown, in inches;
- $S$  = span of arch, in feet;
- $p$  = ratio of span to rise of arch.

Table XI gives the weight per square foot of arches having a thickness of 4 in at the crown and constructed of stone or gravel concrete, taken at 144 pounds per cubic foot, for various spans and ratios of span to rise. For greater thicknesses at the crown these weights should be increased by 12 lb for each inch of additional thickness. For other materials the weights are directly proportional to the weights of the materials. Thus, if cinder concrete weighing 102 lb per cu ft is used, the weight of the arch for any particular span and ratio of span to rise is  $102/144$ , or  $17/24$ , of the weight given in the table for the same span, ratio, and thickness at the crown. Cinder concrete of good quality weighs, according to density, from 96 to 108 lb per cu ft.

**Table XI. Weight per Square Foot of Segmental Concrete Arches**  
Concrete taken at 144 lb per cu ft

Ratio of span to rise	Thickness of arch at crown, in	Span in feet					
		5	6	7	8	9	10
6	4	88	96	104	112	120	128
6½	4	85	93	100	107	114	122
7	4	82	89	96	102	109	116
7½	4	80	86	93	99	106	112
8	4	78	84	90	96	102	108

**Flat Reinforced Floors.** These floors consist of slabs of concrete, varying in thickness according to the span and load, constructed between the steel beams and reinforced near the lower surface with steel in one of the shapes shown on page 843, and further described under their respective names. For ordinary loads the thickness of the slab should be at least  $\frac{5}{8}$  in for each foot of span, with a minimum thickness of  $3\frac{1}{2}$  in. Thinner slabs have been used, but their thickness should be carefully considered for each particular case. The floors are not usually of the same depth as the beams supporting them. The position of the slabs, therefore, determines the character of the ceiling. When the bottom of the slabs is placed at or below the lower flanges, a flat ceiling results, and the space over the slabs must be filled to the underside of the flooring with noncombustible material, thus often increasing the weight. When the slabs are set at the top flanges, there is a paneled ceiling, unless a hung ceiling is provided.

**Strength of Flat Floor-Construction.** The following empirical formula, representing the practise established by the New York Building Code, is based on investigation of cinder concrete floor-construction made by Harold Perrine

and George E. Streban,\* under the joint auspices of Columbia University the Bureau of Buildings, Manhattan, New York.

$$w = Kda/S^2$$

in which

- $w$  = safe load, in pounds per square foot, including the weight of slab;
- $d$  = distance, in inches, from top of slab to center of reinforcement;
- $a$  = cross-sectional area, in square inches, of the reinforcement, for foot of width of slab;
- $S$  = span, in feet, of slab;
- $K$  = a coefficient with values as follows: when cinder concrete is 26 000 if the reinforcement consists of steel fabric continuous supports; 18 000 if the reinforcement consists of steel rods or shapes securely hooked over or attached to the supports; and 17 000 if the reinforcement is not continuous over the supports; and if stone or gravel concrete is used, 30 000, 20 000, and 16 000, respectively, for the corresponding conditions.

The material contemplated by this formula is a concrete consisting of one part of Portland cement, and not more than two parts of sand, and five parts of gravel, or cinders. The reinforcement consists either of steel rods or suitable shapes, or steel fabric. In case cold-drawn steel fabric is used, the reinforcement should not be less than  $1\frac{3}{4}\%$ , and in case other forms of reinforcement are used, not less than  $2\frac{3}{4}\%$ , the percentage being based on the cross-sectional area of the slab above the center of the reinforcement. For protection against fire and corrosion the center of the reinforcement should be at least 1 in. above the bottom of the slab, but there should always be at least 1 in. of concrete outside of any part of the reinforcement. The formula should not be applied to spans exceeding 8 ft. Cinder-concrete floors should be limited to that span in any case.

**Expanded Metal.** This material is now so well known that it requires only a brief description. The diamond mesh shown in Fig. 29 is used in floors.




FIG. 29. Expanded Metal, Diamond Mesh

construction. For this purpose the 3-in mesh is used, the size of the mesh being designated by the width of the diamond-shaped spaces. It comes in lengths of 8, 10, 12, and 16 ft long, and from 3 to 8 ft wide, according to the width of the mesh. It is made from a soft, tough steel of fine texture, varying in thickness from No. 13 to No. 1, Stubbs gauge. The standard sizes offered by the

\* Trans. Am. Soc. C. E., Vol. LXXIX. 1915, page 523.



United Expanded Metal Companies and the Northwestern Expanded Metal Company are in accordance with a decimal variation in cross-section, thus: 0.30, 0.35, 0.40, etc., sq in per ft of width. The designations of the sizes indicate the cross-sectional areas per foot of width, thus: 3-9-20 denotes a 3-in sheet, No. 9-gauge plate, and a cross-sectional area of 0.20 sq in per ft of width. The Sharon Steel Hoop Company and also the General Fire Proofing Company offer from eight to ten sizes of expanded metal with a range sufficient to take care of the needs of concrete-floor designs.

**Concrete and Expanded-Metal Floor-Construction.** Of the numerous types of floor-construction possible with expanded-metal reinforcement, the one shown in Fig. 30 is generally used and recommended. At the right hand




FIG. 30. Concrete Floor-construction. Expanded-metal Reinforcement


The figure is shown the construction when there are steel beams, and at the left hand when there are reinforced-concrete beams. The advantages claimed for expanded metal as a reinforcement are: a better arrangement in the concrete than is possible with an equal amount of material in any other form; great efficiency in the carrying of concentrated loads, due to the obliquity of the ribs; a uniform distribution of small sections at frequent intervals, preferable to larger sections at greater intervals; an increased ultimate strength and high elastic limit, due to the method of manufacture, thus combining the advantages of a low-carbon steel with a high ultimate strength; and a mechanical bond with the surrounding concrete. When used between I beams, without other reinforcement, the spans usually vary from 6 to 8 ft, although spans 12 ft wide between beams have been constructed. In placing expanded metal in the concrete, it is necessary to lap the sheets on the ends up to and including 3-9-20, one diamond (8 in); from 3-9-25 to 3-6-60, one and a half diamonds (12 in); and heavier than 3-6-60, two diamonds (16 in).

Table XII. Properties of Rib-Metal

Size-number	Width of sheet, in	Area of metal per foot of width, sq in
2	12	0.540
3	24	0.360
4	32	0.270
5	40	0.216
6	48	0.180
7	56	0.154
8	64	0.135

**Rib-Metal.** The Truscon Steel Company's factory, at Youngstown, O., is manufacturing a steel reinforcement for concrete floors consisting of a series of straight ribs or main tension-members rigidly connected by light cross-ties expanded from the same sheet of metal in the form of a mesh (Fig. 31). It is manufactured from medium open-hearth steel in seven sizes of mesh, 2, 3, 4,

5, 6, 7, and 8 in, and in lengths up to 18 ft. It is supplied in either flat or curved sheets, and longer lengths and special sizes of mesh can be provided. The width



Area of rib 0.09 sq in  
Ribs spaced 2, 3, 4, 5, 6, 7, and 8 in

FIG. 31. Rib-metal Reinforcement for Concrete Floors




FIG. 32. Welded-metal Fabric. Clinton Wire Cloth

of sheet is governed by the size of mesh, there being nine bars or ribs in each sheet.

**Welded-Metal Fabric.** The Wickes Spencer Steel Corp. manufactures a welded fabric or mesh which has been extensively used in the United States as a reinforcement for concrete construction of all kinds. Fig. 32 shows the general style of the fabric, the meshes and wires of which can be varied indefinitely, upwards from a 1-in mesh. The advantage claimed for this fabric as reinforcement for slab-construction is that the carrying wires may be varied, both in size and spacing, to give the necessary strength for any given weight and span, and the distributing or cross-wires, also, may be varied in the same way. The direction of the wires coincides with the LINE OF STRESS, so that there is no tendency to distort the rectangle of the mesh. The cross-wires, being welded to the carrying wires, are rigidly held in place and prevent the fabric from slipping in the concrete. The design is made that the elongation that takes place in the carrying wire under the stress of heavy loading, is divided along the carrying wires as often as the cross-wires occur, instead of being concentrated at one point as is the case with loose rods or wires. In the mesh

usually used the carrying wires vary from No. 10 to No. 3 in size (Washburn Moen gauge), and are spaced from 1 to 4 in on centers; while the distributing wires vary from No. 11 to No. 6 in size, and are spaced from 3 to 12 in on centers. Welded metal is manufactured in long rolls, and by its use all joints and laps are avoided. A floor can be made with a continuous metallic bond from end to wall, that is, when the mesh is laid over the tops of the steel beams. The width of the rolls varies from 48 to 86 in.

**Lock-woven Steel Fabric.** This fabric\* is made up in a rectangular mesh, the usual spacing of the longitudinal wires being 3 in on centers and that of the transverse wires 12 in on centers. These spacings can be easily varied to meet




FIG. 33. Lock-woven Fabric

special conditions. The fabric is usually made 54 in wide and comes in rolls containing from 150 to 600 lin ft, the 150-ft length being commonly used. While the usual width of the fabric is 54 in, it can be varied in multiples of  $1\frac{1}{2}$  in from 54 in up to a maximum of 86 in. The longitudinals or carrying wires of the fabric are held in place by the transverse wires as shown in Fig. 33. The longi-




FIG. 34. Concrete Ceiling-slab Reinforced with Lock-woven Fabric

gitudinal wires can be furnished in sizes varying from No. 14 to No. 7 gauge, the sectional area of the fabric ranging from 0.0201 sq in to 0.1968 sq in per ft of width. Heavier fabric can be furnished to meet special conditions. The transverse wires are usually No. 14 or No. 12. The longitudinal wires are made by a special process which gives them an **ULTIMATE TENSILE STRENGTH** of from 150 000 to 200 000 lb per sq in, with a correspondingly high **ELASTIC LIMIT**. The fabric can be furnished either black or galvanized. This fabric has the general advantages common to any continuous, rectangular-mesh material, as it provides a **CONTINUOUS BOND** from end to end of a structure, and the wires are so placed that they lie parallel to the **LINES OF STRESSES** which they are called upon to carry. The standard type of construction for floor-slabs and roof-slabs is similar to that shown in Fig. 30 for expanded metal. Where a flat ceiling is desired the type of construction shown in Fig. 34 is very useful. Both of these types have been used by the Bureau of Buildings of the City of New York on spans up to and

\* Controlled by W. N. Wight & Company, New York City.

including 6 ft, for live loads running from 130 to 330 lb per sq ft; and on spans 7 ft, approvals have been given up to 175 lb per sq ft, and on spans of 8 ft, up to 150 lb per sq ft. The arches were constructed of cinder concrete and the fig given are based on a factor of safety of 10. In addition to its use for the construction of floor-slabs and roof-slabs, the fabric is suitable for use in panel-sewers, penstocks, and tanks, and in all other places where a sheet-reinforcement can be used to advantage.

**Triangle-Mesh Wire-Fabric Reinforcement.** Under this name the American Steel and Wire Company is manufacturing a wire fabric of cold-drawn wire for the reinforcement of fire-proof floors. A detail of the standard mesh is shown in Fig. 35. The triangular mesh is built up of either single or strand longitudinals with the cross-wires or bond-wires running diagonally across width of the fabric. It is claimed that the triangular mesh affords an even distribution of the steel, reinforcing in every possible direction, and that

FIG. 35. Wire-fabric Reinforcement, Triangular Mesh

strength is increased by reason of the truss-construction. For floor-reinforcement, this fabric is used the same way that any of the other fabrics previously described are used, and as indicated in Figs. 26, 30, and 34. The longitudinal wires in Triangle Mesh are invariably spaced 4 in on centers, but the diagonal wires may be spaced either 4 or 8 in apart. The manufacturers can furnish different styles, giving variations in the cross-sectional area from about 0.09 in to about 0.395 sq in per ft in width of the fabric, or a variation in weight square foot of from 0.2 to 1.6 lb. The material is furnished either galvanized or plain. The longitudinal wires are made of either a single wire or of two three wires stranded. The cross-wires or bond-wires are of either No. 1 or No. 1 1/4 gauge. Special sizes of additional area can be furnished upon application to the company. This fabric is said to have an ultimate strength of not less than 85 000 lb per sq in.

**Dovetailed Corrugated Sheets.** *Ferroinclave.* Sheets of thin steel corrugated so as to form dovetailed grooves have been used as a reinforcement and tying for concrete-steel, the dovetailing serving to unite the sheets to the concrete. The Brown Hoisting Machinery Company of Cleveland, Ohio,

ented, under the name Ferroinclave, a tapered corrugation which is small enough to hold hard mortar, and hence can be plastered on the under side. Fig. 36 shows a partial section of the Ferroinclave corrugated sheets, the depth of the corrugations being  $\frac{1}{2}$  in, the distance from center to center of corrugations 2 in, and the corrugations, with the opening between the edges,  $\frac{3}{4}$  in. The tapering of the corrugations is of especial advantage for roofs, as it allows the sheets to be lapped at the end-joints, making a roof absolutely tight, even if water should penetrate the cement coating. The principal advantage in the use of corrugated sheets for floor-construction is that they sustain the concrete, when the spans are of moderate width, before it has set, thus saving the cost of centering and the time required to put it in place. This advantage, however, appears to be offset by the high cost of the sheets when they have to be shipped. For roofs, however, this construction is light and relatively cheap, as the total thickness need not exceed  $1\frac{1}{4}$  in for spans of 4 ft 10 in. To make the roof water-tight some water-proof covering is required. With a good coat of hard plaster or grouted mortar on the under-side, the iron will not be affected by heat in case of fire until a considerable time has elapsed; and even if the mortar on the under-side should be more or less dislodged by the streams of water, it can be replaced,




FIG. 36. Ferroinclave Reinforcement for Concrete Floors

at a very slight expense. Another advantage in the use of Ferroinclave for roofs is that a building can be covered and made water-tight in the most severe winter weather and the cement applied during the following spring.

Ferroinclave is made in sheets 20 in wide and up to 10 ft long, and it is usually of No. 24 gauge. For roofs it is attached to purlins in the same way that iron roofing is attached, the most economical spacing of the purlins being 4 ft  $10\frac{1}{2}$  in center to center, which accommodates sheets 10 ft long and leaves an end-lap of 3 in. For the cement top coat on roofs, a mixture of one part Portland cement to two parts sand, applied to a thickness of  $\frac{3}{4}$  in above the top of the sheets, is sufficient. For floors a rich gravel or crushed-stone concrete should be used, the thickness being governed by the span and the loads to be supported.

The following table shows the ultimate strength of No. 24 Ferroinclave with different thicknesses of concrete, as determined by actual tests with sheets 20 in wide over a 4-ft  $10\frac{1}{2}$ -in span:

Thickness in inches of 1 : 2 mortar above the metal.....	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	$3\frac{1}{2}$	4
Ultimate strength in lb per sq ft for a span 4 ft $10\frac{1}{2}$ in.....	615	915	1220	1560	1860	2120

A factor of safety of 6 should be ample for ordinary loads.

Ferroinclave is especially adapted for the roofs and floors of large manufacturing plants, and may be used to advantage for partitions, stair-treads, vats, water-closet partitions, and fire-proof doors.

**Berger's Multiplex Steel Plate.** Fig. 37 shows a section of a corrugated steel plate manufactured by the Berger Manufacturing Company, Can Ohio, for floor and roof-construction, the plate being an invention of G. Fugner. As shown in the illustration, it consists of a series of vertical corrugations in sheet steel, painted or galvanized, ending at the top and bottom in three half-circle arches, separating the vertical sides of the corrugations from each other and giving stiffness to the top and bottom of the plate. The plate is made in depths,  $D$ , of 2,  $2\frac{1}{2}$ , 3,  $3\frac{1}{2}$ , and 4 in, and in corresponding widths of  $13\frac{1}{2}$ ,  $14\frac{1}{2}$ , and 15 in. The maximum length of plate is 10 ft. It can be made of gauge of steel, from No. 24 to No. 16, but No. 18 is as heavy a weight as is generally required. For floors and roofs, the corrugated plate is laid on top of the beams and the top portion filled with concrete and leveled off about 1 in. above the plate. For wooden floors the nailing-strips may be embedded in the concrete and the bottom of the strips raised only about  $\frac{1}{2}$  in. above the top of the plate. The construction is very light and strong and requires no centering. It cannot be plastered, however, on the under side; and when




FIG. 37. Berger's Multiplex Steel Plate

plaster ceiling is required it must be constructed independently of the plate by means of furring-strips and metal lath. The weight of the 4-in plate, with 1 : 2 : 5 furnace-slag concrete leveled 1 in. above the top of the plate, is about 40 lb per sq ft, and the safe load for a 10-ft span is given at 270 lb per sq ft. While this floor has several practical advantages, it cannot be considered thoroughly fire-proof, because the metal is exposed on the bottom. But if a plastered ceiling on the under side, the iron would probably not be affected by any ordinary fire before the latter could be controlled.

**Permanent Centering.** Numerous forms of sheet-metal fabrics have been developed in recent years for use as floor-reinforcements. They consist, generally, of steel plates pressed into series of solid ribs, variously spaced, between which the metal is stamped or perforated, or deployed into an open mesh-work. The characteristic form is shown in Fig. 38. The mesh is kept small enough to prevent ordinary concrete from passing through. For use as a reinforcement the sheets are furnished either in flat or segmental form. A 1 :  $2\frac{1}{2}$  : 5 stone or cinder concrete may be used, the thickness depending upon the span and the load to be provided for. For spans exceeding from 3 to 5 ft, according to the gauge of metal, the sheets must be temporarily supported until the concrete has set. The difficulty of providing efficient fire-protection on the underside of reinforcements of this type, and around the lower flanges of the supporting steel beams, is a serious disadvantage. Besides, the bond between the metal and the concrete is on one side of the sheet only. Some of the forms now on the market

their special characteristics, are briefly described in the following paragraphs.

**Rib-Truss.** These plates, manufactured by the Berger Manufacturing Company, Canton, Ohio, are designed with five longitudinal ribs, 6 in on centers, and  $\frac{1}{4}$ ,  $\frac{3}{8}$ , 1, and  $1\frac{1}{4}$  in high. The metal between the ribs is slit into truss-plates which are further reinforced with beads at right-angles to the main ribs. The standard sheets are 24 in in width and are carried in stock in lengths up to 12 ft, and made of No. 24, 26, 27, and 28-gauge metal.

**Self-Sentering.** In this form, manufactured by the General Fireproofing Company, Youngstown, Ohio, the ribs are  $1\frac{1}{4}$  in in height,  $3\frac{1}{2}$  in on centers, and connected by expanded metal. The sheets are 29 in in width and come in lengths from 4 to 12 ft, varying by units of 1 ft. Self-Sentering is made of Nos. 24, 26, and 28-gauge metal. (See, also, page 885.)

**Hy-Rib.** Hy-rib metal, now controlled by the Truscon Steel Company, Youngstown, O., is made in sheets measuring  $10\frac{1}{2}$  in from center to center of side ribs and having four ribs  $1\frac{1}{2}$  in in height; and also in sheets 14 in in width having three ribs. There is also a type known as the Deep Rib. The lengths are 6, 8, 10, and 12 ft. The sheets are of No. 24, 26, or 28 United States gauge, and are furnished either flat or in various types of curves. (See, also, page 886.)

**Corr-Mesh.** Corr-Mesh is manufactured by the Corrugated Bar Company, Buffalo, N. Y., which supplies, also, special clips for splicing and fastening the mesh to the supporting members. It is made in two types. One has ribs  $\frac{1}{2}$  in high, spaced  $3\frac{1}{4}$  in on centers; the other type has ribs  $\frac{3}{8}$  in high, spaced 3 in on centers. For the  $\frac{1}{2}$ -in-rib Corr-Mesh the sheets are 13 in wide, and for  $\frac{3}{8}$ -in-rib Corr-Mesh they are 18 in wide. The mesh is furnished in United States standard gauges, Nos. 24, 26, and 28. Standard sheets are 6, 8, 10, and 12 ft in length. No allowance need be made for side laps, but at least 2 in should be allowed for end laps.

**Duplex Self-Centering.** The Sharon Steel Hoop Company, of Youngstown, Ohio, manufactures the Duplex Self-Centering. It is 23 in in width, is furnished in lengths of from 4 to 12 ft, and in Nos. 24, 26, and 28 metal, United States gauge. It weighs 1.37 lb per sq ft for the No. 24 gauge, 1.03 lb for the 26 gauge, and 0.86 lb for the No. 28 gauge; and it has a corresponding sectional area per foot of width, of 0.411, 0.308, and 0.257 sq in.

**Sectional Systems.** During recent years, the UNIT SYSTEM OR SEPARATELY REINFORCED SYSTEM, consisting of shop-made reinforced-concrete members, such as

girders, lintels, floor-slabs, and wall-panels, made at a factory and shipped to sites of building operations, has been receiving considerable attention in this country. This system is more completely discussed in Chapter XXIV, p. 958, under the title Separately Molded Construction. Separately molded members have been used between the steel beams of fire-proof floor-construction as a substitute floor-filling for the usual terra-cotta or concrete floor-ard. The advantages of such systems, where they are practicable, are obvious. Such members are usually made as large as can be conveniently handled and of a comparatively long span.

**Disadvantages of Sectional Systems.** The reason that the SECTIONAL SYSTEMS have not found favor is because they necessitate a fairly uniform spacing of beams throughout a structure, and this is generally impracticable. The casting of the parts has hitherto not been commercially successful, as the forms, although used repeatedly, have been more expensive than the usual centering at the building; and it is also generally necessary to use a concrete that is rich and more carefully prepared in order that it may stand the additional handling. Even with all possible care, the breakages in transportation are considerable. As the methods of manufacture of factory-made members are constantly being perfected, chiefly in mechanical contrivances for cheapening the forms and reducing the handling during the process of manufacture, the economy of this system is being substantiated, and particularly when it is used in combination with a light structural-steel fire-proofed frame.

**Walte's Concrete Beam.** In Fig. 39 is shown a type of SECTIONAL FLOOR CONSTRUCTION that has been used in a number of buildings by the Standard

FIG. 39. Walte's Concrete I Beams

Concrete Steel Company of New York City. The floor-construction consists of a series of concrete I beams 10 or 12 in in depth, supported on the lower flanges of the steel beams, which are spaced from 5 to 7 ft apart. The concrete beams are set about 18 in apart and the spaces between the lower flanges are filled in with a cinder concrete of the same composition as the I beams. On the tops of the concrete beams is placed a metal fabric of small mesh on which a lean-concrete slab is laid. This makes a comparatively light floor-construction, because of the large spaces between the concrete beams. The concrete I beams are cast at the shop and allowed to harden before they are sent to the building. When the lower flange is inserted, as shown, a steel reinforcement, of small circular or other cross-section, to furnish the necessary tensile strength. The beams are cast with the proper lengths, in accordance with the drawings; and any slight variations at the building are made up by filling the spaces between the ends of the concrete beams and the webs of the steel beams, and covering the webs of the latter with concrete. A similar construction, consisting of a set



beams, with lower flanges  $1\frac{1}{2}$  in thick and 12 in wide and stems 2 in thick 12 in deep, of 1 : 4 cinder concrete, reinforced with  $\frac{3}{16}$ -in rods near the top, and without floor-finish of any kind, successfully withstood the fire, load, and load tests of the New York City Bureau of Buildings after having been constructed 28 days. This system has proved to be practical in cases in which a flat or level ceiling is required and the steel floor-beams are 10 in or 12 in depth. The cost of construction compares favorably with that of flush-ceiling types.

**The Siegwart Floor System.** This system (Fig. 40), designed by Hans Siegwart, of Lucerne, Switzerland, is in extensive use in that country. The




FIG. 40. Siegwart Reinforced-concrete Floor-construction

floor units are usually made 10 in in width, the height and reinforcement varying with the span and load. In a test on a beam of this type, designed to carry a live load of 150 lb per superficial ft over a 16-ft span, the construction withstood a satisfactory four-hour fire test with a load of 150 lb per sq ft, followed after the fire by a test with a load of 600 lb per sq ft. It is claimed for this system, that using the same working units for the strength of the material, the weight of the construction is only one half that of a monolithic reinforced-concrete floor designed to carry the same load with the same percentage of reinforcement. "The Siegwart Company claim their method to be much cheaper than monolithic floors. From quotations furnished by their Canadian company, the price in Montreal is quite a little less than the author's experience for monolithic floors in the same city, ranging from 17 to 26 cts per sq ft, based for various spans and loads."\* A modification of the Siegwart system has been developed by Grosvenor Atterbury, and has been employed in two-story and three-story residence-buildings for the Sage Foundation Homes Company at Forest Hills (Long Island), N. Y.




FIG. 41. Climax Reinforced-concrete Floor-construction

**The Climax Floor System.** This system (Fig. 41) was designed by S. M. Joseph. The design is similar to that of the Siegwart floor system.

See D. Watson, Concrete Construction with Separately Moulded Members and . Proc. Nat. Asso. Cement Users, Vol. VI, 1910.

**The Vaughan Floor System.** The Vaughan Company of Detroit, Mi is manufacturing a shop-made unit which is employed considerably through the Middle West. The general form of this unit is like that of Waite's composite beam, shown in Fig. 39.

**The Watson Floor System.** Two types of sectional floor systems for proof floor-fillings between steel beams are shown in Figs. 42 and 43. For




FIG. 42. Watson Reinforced-concrete Floor-construction. Without Slabs

spans and heavy loads, the T sections are used, laid side by side; and for spans less than 20 ft and loads of 200 lb per sq ft or less, the beams are spaced on centers with flat slabs between. This system is controlled and installed by the Unit Construction Company of St. Louis, Mo. Beams and girders




FIG. 43. Watson Reinforced-concrete Floor-construction. With Slabs

cast with unit frames in horizontal molds, and slabs are made on edge in forms. In the American School Board Journal for August, 1912, Theodore Skinner describes the construction and erection of a story-and-basement school house with a structural-steel frame and shop-made reinforced-concrete joists with unit-ribbed reinforced-concrete slabs.

**Gypsum Floors.** Gypsum has been extensively used for floors and roofs in fire-proof buildings. It furnishes a light construction which, with the addition

advantage of the rapidity with which it can be put in place, is economical not only with respect to the floor itself but also on account of a saving in the amount of structural steel supporting it. Another favorable feature is the great insulating property of gypsum, resulting in absence of condensation and a reduction in the cost of heating the building.

**The Metropolitan System.** This construction consists of a series of steel cables suspended from the supporting steel beams and encased in a slab of pure fine-grained gypsum containing about 15% of wooden chips. The cables are generally composed of two No. 12 galvanized-steel wires, twisted. They are made continuous over the supports, being securely fastened over the flanges of the end-beams in channels by heavy S hooks or other suitable means. The cables are spaced from 18 to 24 in apart, depending on the carrying capacity desired. They are held taut by a 1/2-in round steel rod, laid at the middle of the span at right-angles to their direction. The mixture of gypsum and chips is sent to the work in bags and spread on wooden centers, as in the case of concrete floors, wet, and allowed to set. The sides and flanges of the supporting steel beams are encased in the same material, all as shown in Fig. 44. The minimum thickness of floor-slabs is 4 in;

FIG. 44. Metropolitan Fire-proof Floor

usual thicknesses for roofs are 3 and 3 1/2 in. The finished slabs weigh about 10 lb per sq ft per in in thickness. Spans of from 6 ft 6 in to 7 ft are said to make the most economical arrangement, all things considered. Spans should not exceed 10 ft. The safe gross strength of the construction may be determined by the formula,

$$w = \frac{24Td}{bL\sqrt{9L^2 + d^2}}$$

in which

- $w$  = the safe gross load per sq ft of floor or roof-surface, in pounds;
- $T$  = the safe tensile strength of the twisted cables, in pounds, which for the ordinary case of two No. 12 cold-drawn steel wires, may be taken at 365 lb;
- $d$  = the deflection of the cable, in inches, and equals the slab-thickness less the sum of the protection of the cables at the center of the slab and over the supports, that is, ordinarily, the slab-thickness less 1 in;
- $b$  = the spacing of the cables, in inches;
- $L$  = the span, or distance, between centers of supports of the slab, in feet.

tie-rods are necessary in this floor-construction; but in the end-bays, when the lateral stiffness of the beams together with the compressive strength of the slab is not sufficient, struts must be provided of such size and spacing as may be necessary to resist the pull of the cables. This floor-construction is conceived and installed by the Keystone Gypsum Fireproofing Corporation, New

**Metal Lumber.** A system of pressed-steel I joists, channel-joists, cor joists, wall-ribbons, etc., has been developed as a substitute for ordinary wood framing in the construction of walls, floors, roofs, and partitions. In the floor construction, the I joists and channel-joists, of from No. 16 to 12 United States gauge sheet metal, are braced by metal bridging, to give additional rigidity. A typical floor-construction is shown in Fig. 45. The steel floor-joists are covered above with a concrete slab reinforced with expanded-metal lath, and the I flanges are protected by a ceiling of metal lath and cement plaster attached to the joists by means of the prongs. The metal-lumber joists frame into ordinary steel girders, resting on a shelf-angle as shown in the drawing. The joists are cut to length at the factory, properly marked and tagged and, with the erecting diagrams, are shipped to the site. All joints and splices are riveted in the field. The steel girders should be properly incased in some fire-proof covering.

FIG. 45. Berger's Metal Lumber and Concrete Floor-construction

The materials for this floor-construction are manufactured by the Berger Manufacturing Company, Canton, Ohio; the General Fireproofing Company, Youngstown, Ohio; the Truscon Steel Company, Youngstown, Ohio; and the National Pressed Steel Company, Massillon, Ohio. They publish safe-load tables for metal-lumber I joists and channel-studs for spans of from 4 to 20 ft. This system, contemplating the use of steel joists and girders, not thoroughly incased with fire-proof materials, cannot ordinarily be considered thoroughly fire-resistant, although a specially constructed floor with all the steel covered and protected with fire-proofing-material has passed the fire test prescribed by the New York Building Code. (See page 827.) It has been extensively used to replace combustible building-construction, especially in residence-buildings.

**Protection of Girders and Beams.** No form of floor-construction can be considered thoroughly fire-proof unless it includes a protection of the I flanges of all steel beams and girders, or provides for the protection of all steel used in its construction or support. The material used for the protective incasing is generally the same as that used in the floor-construction itself.

Principal materials are tile, either dense, porous, or semiporous; gypsum; and concrete, either of cinders, stone, or slag. Beam-protection, where the floor-construction incases the side of the beams, as in Figs. 17, 19, or 34, should never be less than 1 in thick. Where paneled ceilings are used, that is, where the lower part of the beams is below the lower side of the floor-construction, as in Figs. 18 or 30, the protection should be increased to at least  $1\frac{1}{2}$  in at all joints.

**Tile Beam-Protection.** When tile is used, there are two types of protection. In one case the blocks incasing the bottom flanges of the steel beams meet




FIG. 46. Tile Protection for Box Girder

at the middle of the lower side of the flanges; in the other, they simply turn over the edges of the bottom flanges and hold flat tiles with beveled edges

FIG. 47. Tile Protection for Single-beam Girder

at the lower side of those flanges. The latter is considered the better method, although in this method the danger of breakage of the part extending

under the flange is supplemented by the possibility of an omission of the protection-tiles. The blocks incasing the lower flanges may be the skewbacks of the arch, or they may be separate blocks. Different forms and conditions are illustrated in Figs. 15 to 24. Fig. 26 shows the entire beam protected by blocks on both sides. Girders, which often project below the ceiling-line, are more exposed to the effects of fire and water than the floor-beams, and should have, therefore, the most efficient protection. As a rule, such girders should be provided with not less than 4 in of terra-cotta protection at the top and  $1\frac{1}{2}$  in of solid tile on the lower side, with a space of  $\frac{1}{4}$  in between the terra-cotta tiles and the girder. Fig. 46 is a typical method of protecting girders by means of hollow tiles. The bottoms of the skewbacks are prevented from spreading by wire ties placed in the end-joints between the soffit-tiles and hooked into the round holes in the skewbacks. Single-beam girders are usually protected as shown in Figs. 22 and 47, the latter figure showing more particularly the protection of a beam at the side of an opening in the floor.

**Concrete Beam-Protection.** A more thorough incasing of the webs and lower flanges of beams and girders can be accomplished by the use of concrete. The superior fire-proof character of cinder concrete makes it the best material for this purpose. If of sufficient thickness and properly applied, it will protect securely, without reinforcement, around the flanges of beams and girders. But where it is less than 2 in thick, wire or metal lath, wrapped around the flanges, should be embedded in it. A common form of concrete-protection is shown on right hand side of Fig. 30. Sometimes the soffit of the beam is protected by a concrete slab with an insulating air-space. This method is one which may be advantageously used for the protection of girders. A fire test of this form of girder-protection made in the Butterick Building, New York, has thoroughly established its efficiency. Hung ceilings are sometimes used as a protection for the steel beams. This is very bad practice, as these ceilings are more than likely to collapse in a severe fire. The experience in the Chicago fire confirms this belief. (See, also, pages 780 to 782.)

**The Fireproofing of Trusses.** When steel trusses are used to support a roof or several stories of a building it is very important that they be protected not only from heat sufficient to warp them, but also from expansion sufficient to affect the vertical position of the columns on which they are supported. The following description of the covering of the trusses in the Tremont Temple, Boston, Mass., furnishes a good illustration of the way in which this should be accomplished: "The steel girders were first placed in terra-cotta blocks on top and sides and below, these blocks being then strapped with iron all around the girders, and upon this was stretched expanded-metal lathing, covered with a heavy coating of Windsor cement; over this comes iron furring, which receives a second layer of expanded-metal lath, the latter, in turn, receiving the final coat of plaster. There is, consequently, in this arrangement for fire-protection, a dead-air space, then a layer of terra-cotta, a Windsor cement covering, another dead-air space, and finally, the external Windsor cement." Numerous sizes of terra-cotta tiles are made for incasing the structural shapes commonly used in steel trusses. Some of these are shown in Fig. 48. The tiles should always be secured in place by metal clamps passing entirely around the envelope; better still, by wrapping with wire lath. The tiling should then be plastered with hard wall-plaster. Trusses, also, may be fire-proofed by complete incasing the several members in cinder concrete, either with or without reinforcement. The method of incasing steel columns by means of the cement gun (page 826) is also applicable to the protection of steel trusses, and if of sufficient thickness would probably serve as a suitable fire-protection; but

the data on this latter point are as yet available. When trusses are to be roofed, the additional weight must be provided for in the strength of the trusses themselves.

SECTION OF STRUT

SECTION OF BRACING

FIG. 48. The Protection for Members of Steel Trusses

**Steel Framing for Fire-proof Floors.** Before the framing-plans of a building can be made, it is necessary to decide, in a general way, upon the **SYSTEM FLOOR-CONSTRUCTION** or fireproofing that will be employed. Thus, if any one of the **LONG-SPAN SYSTEMS**, such as the Herculean, Johnson, and many of the concrete systems, is to be adopted, the girders should be spaced so that the floor-construction will span between them, without floor-beams, as shown Fig. 49, while if an **ORDINARY FLAT-TILE ARCH** is to be used, floor-beams will




FIG. 49. Steel Floor-framing for Long-span Construction

be required, spaced from  $5\frac{1}{2}$  to 9 ft apart, and these beams must be supported by girders, as indicated in Fig. 50. When there are no floor-beams, a STEEL BEAM should be riveted between the columns, as in Fig. 49, to hold the floor in place during erection and to stiffen the building. It should be remembered that with floor-beams spaced not more than 7 ft on centers, almost any system




Fig. 50. Steel Floor-framing for Short-span Construction

of floor-construction may be employed; while if the floor-beams are omitted there are few systems to select from. With any form of filling between beams or girders, less steel is required for moderate than for excessive spans of beams or girders.

**Computations for the Steel Framing.** The computations for the beams and girders of a fire-proof floor are very much the same as for a wooden floor. The load or loads which any given beam is required to support are estimated and then the beam of the necessary size to support the load is selected. The DEAD LOAD for any fire-proof floor may be estimated with sufficient accuracy by means of the data given in this chapter in connection with the different systems of floor-construction. The dead load should include the weight of beams, the fireproofing, including all concrete filling, the plastering, furring, lathing, nailing-strips, and flooring. The LIVE LOADS may be estimated by means of the data given in Chapter XXI, pages 718 to 721.

**Example.** The best arrangement for the columns in a retail store is to space them 18 ft on centers in one direction and 19 ft 6 in in the other. It is desirable to run the girders as shown by Fig. 50, and to put a beam opposite each column.



and two beams between the columns. It is required to determine the proper sizes of the beams and girders, using an ordinary end-arch construction between the beams.

**Solution.** From Table VII, page 836, we find that the least depth of arch which it is advisable to use is 10 in, but as we will probably have to use 12-in beams it will be better to figure on a 12-in arch, as this will give less filling on top. The weight of the 12-in arch will be about 39 lb per sq ft. We shall probably require 2 in of concrete filling on top, which will weigh 16 lb, and  $\frac{1}{2}$  in of light filling between nailing-strips, weighing, say, 9 lb per sq ft. The flooring and nailing-strips will weigh about 4 lb, the plastering on the ceiling 1 lb, and we must allow at least 6 lb per sq ft for the weight of the beams themselves. These make a total dead weight of 79 lb per sq ft. The live load for retail store should be taken at 150 lb per sq ft, making a total load per square foot on the beams of 229 lb. The total load that each beam must be capable of supporting will be  $6\frac{1}{2}$  ft by 18 ft by 229 lb, or 26 793 lb, or 13.4 tons, which is assumed to be uniformly distributed. From Table IV, page 580, we find that this load, with a span of 18 ft, will require either a 12-in, 45-lb beam, or a 15-in, 79.9-lb beam. The latter will be both stronger and cheaper, but will increase the thickness of the floor by 3 in and require additional filling.

The girder must support two concentrated loads of 26 793 lb or 13.4 tons each. On page 566 it is stated that when a beam supports two equal loads applied at points one-third the length of the span from each end, the equivalent uniformly distributed load may be found by multiplying one load by  $2\frac{3}{4}$ . Multiplying 26 793 lb by  $2\frac{3}{4}$  we have 71 448 lb as the equivalent distributed load on the girder, to which should be added the weight of the girder. This requires a standard 24-in 79.9-lb beam (Table IV, page 577).

If instead of using tile arches between beams  $6\frac{1}{2}$  ft apart, we conclude to use the Herculean or Johnson construction spanning from girder to girder, we could frame our floor as in Fig. 49. For this span we should require 10-in tiles, weighing 55 lb per sq ft. Allowing 8 lb for 1 in of concrete, 9 lb for filling, 4 lb for flooring and strips, and 5 lb for plastering, we have 81 lb as the dead load per square foot. We have added nothing for the weight of the girder, as this will be fully offset by the portions of the floor not loaded. The live load per square foot will be 150 lb as before, and the total load to be supported by the girder, 19 ft 6 in by 231 lb, or 81 081 lb, or 40.54 tons, which will require a 24-in 79.9-lb beam (Table IV, page 577). Hence by this arrangement we save the weight of the floor-beams; but a 6-in strut-beam should be placed between columns, as in Fig. 49. The calculations for any other floor-construction similar to the calculations for this example, the only variations being in figuring of the dead weights of the construction.

**Tables for Floor-Beams.** It is a difficult matter to prepare tables that may be generally used, showing the size of steel beams required for fire-proof floors, since such beams are often irregularly spaced, and there is a wide variation in the dead loads. The following tables, however, may be used in making approximate estimates and in checking the computations for any particular floor. The sizes of I beams given may be safely used where the total live and dead loads do not exceed the values given in the headings. The total loads should include a sufficient allowance for the weights of any partitions that the floor-beams may be called upon to support.

Table XIII gives the sizes and weights of I beams for floors of offices, stores, and apartment houses; Table XIV, for floors of retail stores and assembly-rooms; and Table XV, for floors of warehouses. The total loads used in the computations are, respectively, 120, 200, and 270 lb per sq ft.

Table XIII. Sizes and Weights of I Beams for Floors of Offices, Hotels and Apartment-Houses

Total load, 120 pounds per square foot

Span of beams in feet	Distance between centers of beams in feet				
	4½	5	5½	6	7
	in lb	in lb	in lb	in lb	in lb
10	6 12¼	6 12¼	6 12¼	6 12¼	7 15
11	6 12¼	6 12¼	7 15	7 15	7 15
12	6 12¼	7 15	7 15	7 15	8 18
13	7 15	7 15	7 15	8 18	8 18
14	7 15	8 18	8 18	8 18	9 21
15	8 18	8 18	8 18	9 21	9 21
16	8 18	9 21	9 21	9 21	10 25
17	9 21	9 21	9 21	10 25	10 25
18	9 21	9 21	10 25	10 25	12 31½
19	9 21	10 25	10 25	10 25	12 31½
20	10 25	10 25	12 31½	12 31½	12 31½
21	10 25	12 31½	12 31½	12 31½	12 31½
22	10 25	12 31½	12 31½	12 31½	15 42
23	12 31½	12 31½	12 31½	12 31½	15 42
24	12 31½	12 31½	12 31½	15 42	15 42
25	12 31½	12 31½	15 42	15 42	15 42

Table XIV. Sizes and Weights of I Beams for Floors of Retail Stores and Assembly-Rooms

Total load, 200 pounds per square foot

Span of beams in feet	Distance between centers of beams in feet				
	4½	5	5½	6	7
	in lb	in lb	in lb	in lb	in lb
10	7 15	7 15	7 15	8 18	8 18
11	7 15	8 18	8 18	8 18	9 21
12	8 18	8 18	9 21	9 21	9 21
13	8 18	9 21	9 21	10 25	10 25
14	9 21	9 21	10 25	10 25	12 31½
15	9 21	10 25	10 25	12 31½	12 31½
16	10 25	10 25	12 31½	12 31½	12 31½
17	10 25	12 31½	12 31½	12 31½	12 31½
18	12 31½	12 31½	12 31½	12 40	12 40
19	12 31½	12 31½	12 40	12 40	15 42
20	12 31½	12 40	12 40	15 42	15 42

Table XV. Sizes and Weights of I Beams for Floors of Warehouses

Total load, 270 pounds per square foot

Span of beams in feet	Distance between centers of beams in feet				
	4½	5	5½	6	6½
	in lb	in lb	in lb	in lb	in lb
10	8 18	8 18	8 18	9 21	9 21
11	8 18	9 21	9 21	9 21	10 25
12	9 21	9 21	10 25	10 25	10 25
13	10 25	10 25	10 25	12 31½	12 31½
14	10 25	12 31½	12 31½	12 31½	12 31½
15	12 31½	12 31½	12 31½	12 31½	12 40
16	12 31½	12 31½	12 31½	12 40	12 40
17	12 31½	12 40	12 40	12 40	15 42
18	12 40	12 40	15 42	15 42	15 42
19	12 40	15 42	15 42	15 42	15 42
20	15 42	15 42	15 42	15 45	15 55

**Tie-Rods.** In all segmental arches and other types in which a thrust is exerted against the beams, TIE-RODS must be provided to prevent the beams from being pushed apart, and especially to prevent the outer bays from spreading. They should run from beam to beam from one end of the floor to the other. If the outer arches spring from an angle, as in Fig. 14, the tie-rods in the outer bay should be anchored into the walls with large plate-washers. The rods should be located in the LINES OF THRUST of the arches, which are usually below the half-depth of the beams, and in some cases near the bottom flanges. If their appearance is objectionable, they should be hidden by a hung ceiling. For constructional purposes they are desirable in all types of floor-arch construction, even though the floors do not exert a thrust on the beams. The tie-rods are proportioned and spaced according to some RULE OF THUMB rather than by actual calculations of the thrust. For the interior arches this practice is probably safe enough, but for outside spans, and particularly for segmental arches, the thrusts of the arches should be computed and the tie-rods proportioned accordingly. The spacing of the rods is generally eight times the depth of the supporting beams, but never more than 8 ft. For interior flat arches, the following rule can usually be safely followed: for spans of 6 ft or less, use ¾-in rods spaced about 5 ft apart; for 7-ft spans, 7/8-in rods, 6 ft apart; and for 9-ft spans, 1-in rods, 4 ft apart.

HORIZONTAL THRUST of an arch may be found by the following formula:

$$T = \frac{3 w L^2}{2 R}$$

$T$  = pressure or thrust in pounds per linear foot of arch;  
 $w$  = load on arch in pounds per square foot, uniformly distributed;  
 $L$  = span of arch, in feet;  
 $R$  = rise of segmental arch, or effective rise of flat arch, in inches.

The **RISE** of a segmental arch is measured from the springing-line to the soffit of the arch at the middle. For flat hollow-tile arches, the effective rise may be figured from the top of the beam-flange to the top of the tiles. As the tiles usually project from  $1\frac{1}{4}$  to 2 in below the bottom of the beams, the effective rise will be from 2 to  $2\frac{1}{2}$  in less than the thickness of the arch. For the interior arches of a floor,  $w$  may be taken for the live load only, but for the exterior arches,  $w$  should include both the full dead and live loads. Having found the thrust of the arch, the **SPACING OF THE RODS** of any particular size may be readily determined by dividing the safe load given for that size of rod in the table on page 388, allowing 16 000 lb UNIT STRESS, by the thrust. The result will be the spacing in feet.

**Example.** What size of tie-rods and what spacing should be used for the floor-construction described on page 863, in the preceding example?

**Solution.** The depth of a tile arch is 12 in, the dead load 79 lb and assumed live load 150 lb. The span between the beams is  $6\frac{1}{2}$  ft. Then, for the interior arches,  $w = 150$  lb,  $R = 12 - 2\frac{1}{2} = 9\frac{1}{2}$  in,  $L = 6\frac{1}{2}$  ft and  $T = (3 \times 150 \times 42.25) / (2 \times 9\frac{1}{2}) = 1\,000$  lb. The tensile strength of a  $\frac{3}{4}$ -in rod, upset, at 16 000 lb per sq in, is, from Table II, page 388, 4 832 lb. Dividing this by 1 000 we have a little less than 4 ft 10 in as the spacing. The tensile strength of a  $\frac{7}{8}$ -in rod is given as 6 720 lb, which would admit of a spacing of a little more than 6 ft 8 in. For the outer spans,  $w$  should be taken  $150 + 79 = 229$  lb. Then  $T = (3 \times 229 \times 42.25) / (2 \times 9\frac{1}{2}) = 1\,526$  lb. For this thrust we should use  $\frac{7}{8}$ -in rods spaced about 4 ft 5 in apart.

**Load-Tests.** It may be desirable at times to test fire-proof floors after they have been installed. The same precautions should be taken as for tests on reinforced-concrete construction, described on page 967. If it is desired to determine from such tests the **ULTIMATE STRENGTH**, a section of the floor of a width equal to the span should be cut loose from the rest and loaded to destruction, supporting steel beams being shored up during the test. The **SAFE WORKING LOAD** is found by dividing the **BREAKING-LOAD** by the proper **FACTOR OF SAFETY**.

## 5. Fire-proof Roof-Construction

**Flat Roofs.** Flat roofs are constructed in the same way as the floors, except that the beams and girders are set so as to give a slight pitch to the roof to drain the water. As the **ROOF-LOADS** are usually less than the **FLOOR-LOADS**, as there are no partitions to be supported, the arches or roof-panels are usually considerably lighter than the floor-panels, but the general construction is practically the same for both. When the roof is formed of reinforced concrete the beams may be set so that the concrete will give the desired inclination to the roof and will have a nearly uniform thickness, as this reduces the amount of concrete required, and also the weight. In cases where level ceilings are desired, however, it would be cheaper to set the roof-beams level and to fill the roof with dry cinders, as the cost of the hung ceiling would more than offset the cost of the extra construction necessary to take the added weight of cinder fill. If the roof is to be covered with tin or copper, nailing-strips should be bedded in the concrete, as for wooden floors, and the entire roof sheathed. It is claimed that tin or copper laid over terra-cotta or concrete will rust out in a few years.\* Gravel or tile roofs may be built without woodwork of any kind. Whether terra-cotta, gypsum tile, or concrete is used for the roof-panels, the sides and bottoms of the steel beams and girders should be efficiently protected.

\* Freitag.

as well as all columns and all other structural metal in the roof-space. In an ordinary building, in which there are stair-wells or elevator-wells, the roof and upper ceiling are likely to be more severely tested by heat, in case of fire, than any of the floors below, and experience has shown that this part of the building often has the poorest protection.

**Pitched Roofs.** Pitched roofs may be constructed in various ways, according to the material that is to be used and the kind of roofing that is to be employed. When terra-cotta or gypsum tile is to be used for the fireproofing, the most common method of construction is that which involves the framing of the roof with I-beam rafters and T-iron purlins, set horizontally and spaced rather apart than the lengths of the tile. Between the tees, book tiles, or roofing-tiles are placed as in Fig. 51, and the roofing is applied directly to the surface of

FIG. 51. Tile Fireproofing for Roof-construction

the tiles. If the roofing is to be of slate or of clay tiles, solid, porous terra-cotta tiles should be used between the tees, as nails are held better by solid blocks than by hollow tiles; gypsum roof tile is also suitable for this purpose. The same construction may be used for flat roofs; but on account of the expense of the tees it will usually be more expensive than the construction above described, and not as strong or desirable. With the construction shown in Fig. 51, it is possible, by any economical method, to efficiently protect the bottom of the iron from the effects of heat. Reinforced-cinder concrete, or reinforced porous terra-cotta tile, Johnson System, affords an excellent and also an economical construction for fire-proof pitched roofs. Either of these constructions may be filled between or on top of the rafters without the use of purlins, except about once in from 6 to 10 ft, to prevent sliding and to stiffen the roof. Three-inch plates of concrete, with expanded metal embedded, have been successfully used in spans of from 6 to 7 ft and in some cases even in 8-ft spans. The concrete is deposited on wooden centerings, as in the floor-construction, and the upper side is smoothed off during the setting and floated smooth and bright to receive the roof-covering."\* The roof-covering, usually slate, or

\* Freitag.

clay tiles, may be nailed directly to the concrete, as nails are held nearly well by cinder concrete as by wood. This applies only to cinder concrete, as is quite impossible to nail into rock concrete or gravel concrete. In concrete roofs the rafters, also, should be surrounded with concrete held in place




FIG. 52. Hollow Book Tile and Solid Tile for Roofs

metal lath. With terra-cotta roofs, the beams should be incased with terra-cotta blocks. Fig. 52 shows the standard shapes of book tiles and solid roof tiles. These are made 2, 2½, and 3 in thick, and from 16 to 24 in long. The 2-in book tiles weigh about 13 lb per sq ft, and 2½-in solid tiles about 16




FIG. 53. Bonanza Reinforced-cement Tiles for Pitched Roofs

per sq ft. Tiles of both of these shapes are also used for ceilings and where light, fire-proof filling is required.

**Reinforced-Cement Tiles.** Cement tiles of interlocking types, made in factory and reinforced with metal fabric or mesh, may be laid without sheath directly on steel purlins. This type of construction, however, is suitable only as a semifire-resisting roof-covering, as it is usually made with plates of insufficient thickness and does not contemplate the thorough incasing of the understructure with concrete or other fire-resisting materials. Bonanza Cement Tile roofing is a type of this shop-made tile and is manufactured and controlled by the American Cement Tile Manufacturing Company, Pittsburgh. Two types of tiles are made, one for pitched-roof and the other for flat-roof construction (Figs. 53 and 54). The properties of the tiles are given in the following tabulation:

## Standard, Pitched-Roof Tiles

Thickness of tiles.....	about 1 in
Over-all dimensions of tiles.....	26 by 52 in
Tile-surface exposed to weather.....	24 by 48 in
Number of tiles per 100 sq ft of roof.....	12½
Weight of tiles per 100 sq ft of roof.....	1450 lb

## Standard, Flat-Roof Tiles

Width of tiles.....	24 in
Length of tiles.....	60 in or less
Thickness of tiles.....	1½ in
Weight of tile-construction.....	16 lb per sq ft






FIG. 54. Bonanza Reinforced-cement Tiles for Flat Roofs

The flat-roof tiles are designed for and have been used in connection with buildings for manufacturing-plants on spans of 5 ft between purlins. On these spans they have been tested up to an ultimate live load of 250 lb per sq ft. The top surfaces of these tiles are finished in a weather-proof and water-proof material of a dark, terra-cotta-red color.



THROUGH TYPE



"T" TYPE

"H" TYPE

FIG. 55. Structolite Roof-tile

**Structolite Roof-Tile.** Shop-made roof-tiles made of a dense quick-setting gypsum cement, called **STRUCTOLITE** by the manufacturers, are put on the market by the United States Gypsum Company of Chicago, Ill. The material used is said to have an average ultimate crushing strength of 2000 lb per sq in. As the material weighs only 77 lb per cu ft, a very light roof-construction results. The tiles are reinforced with steel in much the same manner as reinforced concrete and their strengths are figured by the same formulas, using working stress appropriate to the materials. For spans from 4 to 6 ft, a trough-like tile is used as shown in Fig. 55. For greater spans, up to 10 ft, the **T TYPE** and **H TYPE** tile are used, the latter when a continuous flat ceiling is desired. The tiles are placed directly on channel or I-beam purlins, but when the flanges of the purlins are less than 2½ in wide, bearing-plates should be inserted between the tiles and purlins. The weights of the roof-tiles in lb per sq ft are as follows, the tiles themselves being generally designed for safe superimposed loads of 50 lb per sq ft.

Span, ft	Depth, in	Trough type, lb	T type, lb	H type, lb
4	5	14	.....	.....
5	5	14	.....	.....
6	5	15	13½	18½
7	6	.....	14½	21
8	6	.....	14½	21
9	7	.....	16	22
10	7	.....	16	22

**Robertson Process.** Under the name of **ROBERTSON PROCESS FLOOR** the H. H. Robertson Company, Pittsburgh, Pa., make and install gypsum floor construction of the same general character and design as the Metropolitan Floor (page 857). They also manufacture pre-cast roof-tiles designed on the same suspension-principle. The cables protrude about 2 in at the ends of the slab near the top surface. When set in place on the roof-purlins with their ends abutting, the projecting ends of the cables of adjoining slabs are tied together by a device that draws them taut, thus effecting continuity. The tiles are rabbetted at the ends where the cables emerge, and these rabbets are filled with gypsum, covering over and protecting the cable-connections. The following are the standard sizes of roof-tiles:

- 3 in thick, 24 in wide, varying in length by 3 in, from 4 ft 0 in to 6 ft 0 in
- 3 in thick, 21 in wide, varying in length by 3 in, from 6 ft 0 in to 6 ft 9 in
- 3 in thick, 18 in wide, varying in length by 3 in, from 6 ft 9 in to 7 ft 0 in
- 3½ in thick, 15 in wide, varying in length by 3 in, from 7 ft 0 in to 8 ft 0 in
- 3½ in thick, 12 in wide, varying in length by 3 in, from 8 ft 0 in to 8 ft 6 in

The weight per sq ft is 14 lb for the 3-in tiles and 16 lb for the 3½-in tiles.

**Mansard Roofs** are usually framed with rafters, riveted or bolted to wall plates. The space between the rafters may be filled with cinder concrete, hollow partition-tiles, or blocks extending from rafter to rafter, as in Fig. 56. Slates or tiles may be nailed directly to cinder concrete or to porous terra-cotta. Probably the best way to attach slates or tiles is to nail 1¼ by 2-in wooden strips to the outer face of the concrete or terra-cotta, set them at the proper distance apart to receive the slates or tiles, and then plaster between the strips with



ment mortar. This gives a better nailing for the roofing, and the wooden joists are not affected by fire until the slate is practically destroyed.

**Roof-Coverings.** The materials ordinarily used for the roof-covering of fire-proof buildings are: (1) tar and gravel; (2) asphalt and gravel or sand; (3) vitrified bricks, or slate tiles over tarred felt, gravel and gravel, or asphalt felting and gravel or sand, offer the cheapest roof suitable for a fire-proof building; and (4) a good quality of felt and distilled asphalt or the best grades of asphalt are also, make a very satisfactory covering. Flat roofs, however, require to be renewed about every ten years. The roofing is put on in the same manner as over wooden construction, the felt being laid directly on concrete. Probably the best flat roof that can be put on a building is one of vitrified or slate tiles, laid over five plies of tarred felt. The felt is laid and mopped for a gravel roof, and the tiles are




FIG. 56. Tiles for Mansard Roof

laid on the felt in cement mortar. Vitrified tiles, about 8 in square and  $\frac{1}{2}$  in thick, are made for this purpose, and slate tiles, 12 in square by 1 in thick have been used. Flat, vitrified-brick tiles, also, are used. Gravel roofing should not be used on roofs which have an inclination exceeding  $\frac{3}{4}$  in in 1 ft. For pitched or inclined roofs, slates, clay tiles, or metal tiles may be used. Vitrified tiles are superior to slate when exposed to fire and are generally to be preferred to slate; this is especially true of some of the patent interlocking tiles. See, also, pages 1582 to 1587, and 1595 to 1599.)

**Suspended Ceilings.** Office-buildings, apartment-houses, etc., having flat roofs, require ceilings below the roofs in order to make a proper finish in the




FIG. 57. Suspended-ceiling Construction

is, and also for heat-insulation. In office-buildings the ceilings of the top floor are often framed and constructed like the floors, but with a lighter construction. More often the ceilings are suspended from the roof, as this requires less steel and is consequently much cheaper. It answers the purpose as well, that is, if the roof-beams are efficiently protected. Fig. 57 shows

a common construction for such ceilings. Wrought-iron hangers, about 1 1/2 in or 1 by 1/4 in, split at one end to hook over the lower flanges of roof-beams, are used to support 3/16 by 3/4-in flat steel bars, spaced about 4 ft centers; and to the under-side of these are laced 3/4-in, 7/8-in, or 1 1/4-in cham




FIG. 58. Suspended Ceiling. Details of Two-bar System

12 or 16 in on centers receive the metal lath. The bottom of each hanger is bent at right-angle to form a seat for the bar and the bar is laced to the hangers. No bolting or riveting is required, all connections being made by lacing wire, or by bending the iron. Where stiffened wire lath is used, the channels may be spaced 12 in on centers; but if the ordinary expanded laths

are used, it is better to space the channels 12 in on centers. If ordinary lime mortar is used for plastering 12-in spacing is really necessary. Another system is one which uses one set of horizontal bars, which are spaced close enough to receive

lathing, and which are supported by hangers. With stiffened wire lathing, roof-beams spaced not over 5 ft apart, and short hangers, this may be the cheaper system; but without the stiffened lathing, there is no stiffness to the ceiling at right-angles to the bars. Where the hangers are 3, 4, or 5 ft long, and the spans between the beams




FIG. 59. Suspended Ceiling. Details of Two-bar System

wider than 5 ft, the two-bar system, shown in Fig. 57, requires less steel, the reason that the channels, having spans of only 4 ft, may be made lighter, and only one third or one fourth the number of hangers are required. In place of the small channels, small T bars or flat bars may be used, but when bars are held by lacing, channels are preferable.

Figs. 58\* and 59\* show very satisfactory details for the construction of a two-bar system. Instead of the hook shown in Fig. 58, the hanger may be split at the top, one half bending around one side of the beam-flange and the other half around the other side. Where the ceiling is suspended below the cotta arches, toggle-bolts are used for the support of the hangers. The small bars supporting the lathing are usually spliced by means of small iron clamps, about 6 in long, wrapped closely around the bars and hammered tight. For suspended ceilings under segmental or paneled floor-construction the same methods are employed, except that the hangers are replaced by bolts holding the ceiling-bars close to the soffits of the beams.

\* From Fire Prevention and Fire Protection, J. K. Freitag, pages 687 and 688.

## 6. Partitions and Wall-Coverings

**Requirement of Fire-proof Partitions.** As a rule the partitions in fire-proof buildings are not required to support any weight, but merely to serve the purpose of dividing the spaces into rooms, and to confine a fire to the compartment in which it originates. No greater strength, therefore, is required in a partition than is necessary to carry its own weight. Rigidity, however, is required, and a rigidity in proportion to its height and unsupported length. When partitions separate apartments or sections of a story, that is, when they are practically without window-openings or door-openings, they should be rigid enough to prevent the passage of water from a hose-stream as well as the passage of flame. In other cases this may be unnecessary; in fact, at times it may be desirable to construct partitions which can be easily removed to get at fire spreading through doors or windows. The materials of partitions should be incombustible. They should be poor conductors of heat. It is desirable, also, to have them unaffected by water. Lightness is a good property, as any increase in the dead weight of the construction adds to the cost of the structure. Partitions should be as sound-proof as possible. Window-openings should be avoided, when possible, in fire-proof partitions, and even door-openings should be reduced in number to a minimum. In many buildings, however, in which there are no openings into streets or courts, such windows are necessary for lighting the halls. When this is the case the frames should be made fire-proof, fire-glass should be used, and, if possible, the sash made stationary.

**Fire Tests on Partitions.** In New York City no materials or types of construction are permitted for interior permanent partitions in fire-proof buildings that have not met the required fire tests. The standard test of the American Society for Testing Materials is based on the New York test.\* Briefly, these tests require that the partition shall resist for one hour the destructive action of a hot fire, the heat of which has been gradually increased to 1700° F. during the first half-hour and maintained at that temperature for the balance of the hour; and that it shall resist, also, for two and a half minutes at the conclusion of the fire test, the application of a hose-stream at 30 lb pressure.

**Types of Partitions.** Fire-proof partitions that are in common use may be grouped, according to the materials or the method of construction used, as follows:

- (1) Brick;
- (2) Hollow tile or terra-cotta;
- (3) Concrete (stone or cinder);
- (4) Gypsum block;
- (5) Plaster or concrete, with metal.

The choice of the materials and the type of construction are largely influenced by the character of the building and the purposes for which it is used.

**Partition-Walls.** For bearing-partitions, that is, those which support floors, there are probably no materials more satisfactory than brick and concrete. The latter may be used either in the form of blocks, or may be poured in forms. Dense tile, also, is being used with satisfactory results for bearing-partitions. Tests show a crushing strength, on net sections, equal to that of brick.

**Hollow-Tile or Terra-Cotta Partitions.** These are usually built of blocks, either square or brick-shaped, according to the particular product used. The square blocks are usually 12 by 12 in on the face, and the brick-shaped blocks are usually 12 in long but vary in height. Both shapes are made in thick-

\* See latest Year Book, Am. Soc. for Test. Mats.

nesses varying from 2 to 12 in. The 3-in, 4-in, and 6-in blocks are commonly used, the 4-in blocks being the most popular for ordinary work. For more important partitions, such as stair and elevator-enclosures, not narrower than the 6-in blocks with the double row of cells should be used. The blocks are commonly set with the voids vertical. Fig. 60 shows typ




FIG. 60. Hollow-tile or Terra-cotta Partition-blocks

shapes of both the square and brick shaped blocks. Fig 61 shows rounded cornered and angle-cornered partition-blocks, which must be set vertically. "Terra-cotta partitions of a 2-in thickness have been placed on the market but have not been extensively used. A 2-in terra-cotta partition of any strength or efficiency is quite impracticable, and where floor-area is so valuable more space cannot be occupied, terra-cotta is not the material to be employed

\* Freitag.

ugh the addition, however, of band-iron laid between the courses and  
sted under the name Phoenix,\* the strength of a 2-in tile partition is greatly  
ased. The New York partition, Bevier Patent, consists of 2-in tiles, rein-  
d with truss-metal, such as is used in the New York floor-arch. (See Fig. 28.)




FIG. 61. Hollow-tile Round-corner and Angle Partition-blocks

**ous Versus Dense Materials.** For inside partitions the **POROUS** mate-  
are preferable to the **DENSE**, while for outside walls the dense materials  
d be used. With **DENSE TILING** it is necessary to insert either wooden  
g-strips, which are very objectionable, or blocks of porous tile to take  
place. It is becoming daily more difficult to get the sawdust necessary to  
the porous material.

**star.** Tile partition-blocks should be set in mortar made of one part  
utty, two parts cement, and from two to three parts sand. The blocks  
l be well wet before setting and the partition wet down before the plaster-  
applied.

**ights and Lengths of Terra-Cotta Partitions.** "The safe **HEIGHT**  
ra-cotta partitions in inches may be approximated by multiplying the  
ess in inches by 40. Common practice allows a safe height of 12 ft for  
16 ft for 4-in, and 20 ft for 6-in partitions. For partitions without side-  
rts the **LENGTH** should not materially exceed the safe height. Doors and  
indows may be considered as side supports, provided the studs run from  
o ceiling."†

**ights.** The **WEIGHTS** of either **POROUS** or **DENSE** terra-cotta partitions  
not be taken at less than the following, adopted by the Hollow Building  
sociation, as proper average weights:

- 2-in partition, 14 lb per sq ft;
- 3-in partition, 16 lb per sq ft;
- 4-in partition, 18 lb per sq ft;
- 5-in partition, 20 lb per sq ft;

\* Made by Henry Maurer & Son, New York.

† Freitag.

6-in partition, 22 lb per sq ft for one-cell blocks;  
 6-in partition, 24 lb per sq ft for two-cell blocks;  
 8-in partition, 30 lb per sq ft;

not including plastering, which adds about 10 lb per sq ft for both sides.

**Concrete Partitions.** Partitions of stone concrete are seldom used because of the forms necessary for their erection, which make them comparatively expensive. Unless reinforced they take up too much room. Furthermore they are the heaviest of all partitions. Even in buildings that are entirely reinforced concrete they are not always used. Cinder-concrete partitions are somewhat lighter and considerably cheaper than those of stone concrete. Even these are too heavy and too troublesome to construct to be satisfactory. Among the partitions tested and approved by the New York City Building Bureau is one that consists of cinder-concrete blocks,  $2\frac{1}{2}$  and 3 in thick, thicker ones being hollow, 12 in high, and 18 in long. They have their ends cast with tongues and grooves that furnish more or less of a bond between blocks when they are set. Hollow, concrete building-blocks make fairly good partitions, but are objectionable on account of their thickness and weight.

**Gypsum-Blocks.** The term GYPSUM-BLOCKS is now more generally employed than the term PLASTER-BLOCKS, as it is more accurately descriptive.




FIG. 62. Plaster-blocks. Doweled Construction.

principal makes on the market are the ACME, made by Acme Cement Plaster Company, St. Louis, Mo.; the ANCHOR, made by the American Gypsum Company, Clinton, O.; the PYROS, made by the United States Gypsum Company, Chicago, Ill.; the BELL, made by Rock Plaster Manufacturing Company; the blocks of Niagara Gypsum Company and the M. A. Reeb Corporation, both of Buffalo, N. Y., and the blocks of the Plymouth Gypsum Company, Dodge, Iowa. The usual size of these blocks is 12 in by 12 in, although some are 12 in by 16 in.

The thickness is generally 2, 3, 4, 5, 6, and 8 in, for the hollow blocks, and 2 and 3 in for the solid blocks.

**Gypsum-Block Partitions.** Blocks made of gypsum (plaster of Paris) combined with various substances, such as cinders, wood chips, coconut husk, asbestos, etc., have been largely used for partitions in fire-proof buildings. The principal advantages claimed for these partitions are their great lightness and reduced cost compared with other forms of partitions. Gypsum blocks can be readily cut with a saw, and have a considerable holding power for nails. In fire tests, made for the Bureau of Buildings, New York City, they have generally shown considerable resistance to the flame and have transmitted less heat than partitions of any other form. They did not, however, always stand the water test, some of them being easily pierced, and all of them being more or less washed away by the water. An objectionable characteristic of these blocks

tendency to absorb moisture while being stored and to draw water from the string when it is applied. This moisture works down to the bottom of the partition where it is likely to injure the wooden base. These partitions are made in THICKNESSES varying from 2 to 4 in, those less than 3 in thickness generally being solid; and their height should not exceed from 50 to 100 times the thickness of the blocks, unplastered. Hollow blocks should always be set with the cells horizontal. The edges of the blocks are generally bed or otherwise arranged so that the mortar joint forms a key between them. In some forms of these partitions the blocks are BONDED together by means of metal dowels,\* running across the horizontal and vertical joints from block into the adjoining one, as shown in Fig. 62. The cut illustrates the use of the block in the construction of dumb-waiter shafts and shows how the blocks are anchored at the corners by iron dowel-angles. Gypsum plaster is used in laying plaster-blocks, and occasionally fibered-gypsum plaster, tempered sand, may be employed. All of the partitions in the newer portions of the Wadlock Block, Chicago, and in many other prominent buildings of Chicago and New York City, are of Gypsum blocks. Gypsum blocks make the lightest partition known. The weight of these partitions per square foot may be taken as follows;

Thickness of block, inches. . .	2	3	4	5	6	8
Weight in lb per sq ft . . .	10	12½	14½	17½	19	26

about 8 lb per sq ft should be added to obtain the weight of the partition when plastered on both sides.

**Mackolite.** A plaster-block extensively used is the Mackolite Hollow Block, made by the A. B. Fireproofing Company, Chicago, Ill. Mackolite partition tiles are generally made in the form shown in Fig. 63. The 3-in, 3½-in, and 4-in tiles are made 48 and the 5 in 30 in long, all the tiles being 8 in high. The blocks are laid in three courses, breaking joint as in stone work. Lime mortar is used for setting. In fitting around openings or at angles the tiles are cut with a saw, and this is a material saving in time and material. It is claimed that Mackolite blocks make very strong partitions. The composition of the material is plaster of Paris mixed with certain chemicals, reeds, and fiber.

FIG. 63. Mackolite Partition-blocks

Reeds of the same length as the blocks are placed in the molds and the plaster of Paris and fiber are then mixed with water, to which the chemical has been added, and poured around the reeds so that they are nowhere exposed. The reeds give longitudinal strength to the blocks while the fiber makes them tough and elastic. The material sets in about half an hour, after which the blocks are kiln-dried for four days.

**Gypsum Partitions.** The main feature of these partitions is the GYPSUM STUD which is handled and erected in the same manner as a wooden stud in the construction of non-fire-proof partitions. The stud is composed of wooden nailing-strips completely protected and embedded in a plaster-composition known as GYPSUM PLASTER, made by the Sanitary Fireproofing and Contracting Co., New York City.

**GYPSINITE CONCRETE.** The studs are carefully made and are plumb and true. Metal lath or plaster-boards are secured to the studs and plastered, completing the partition, which is about  $4\frac{1}{4}$  in thick. (Fig. 64.) This partition is slightly heavier than the ordinary partition of wooden construction. It is as stiff and as strong as a good tile or other partition, and the nailing-stud feature of the studding facilitates the application of a wooden trim. It is said to be particularly sound-proof, and the spaces between the studs afford an opportunity to conceal pipes, wires, etc. Gypsinite studs are 3 in by 12 in, and weigh 3 lb to the foot. They can be made any size required.

FIG. 64. Gypsinite Studs, Metal Lath, and Plaster

In the partitions the studs are usually placed 16 in on centers and bridged where necessary may be required. They are fastened to the floor or ceiling by the use of spikes and plates of the same material, or by light channel-irons, which are spiked to the fireproofing. The manufacturers believe that in large quantities these studs can be furnished as cheaply as wooden studs and that the partitions can be erected as cheaply as ordinary lath-and-plaster partitions. Gypsinite studs are manufactured by the United States Gypsum Company, Chicago, Ill.

**Solid, Plaster-and-Metal Partitions.** Thin partitions of plaster applied to metal lath and metal studs, made solid, and finished about 2 in thick, have been extensively used in fire-proof buildings. They are remarkably stiff, owing to the adhesion of the plaster to the steel, and they are lighter and occupy less space than any other practical fire-proof partition of equal strength. In fire tests these partitions act very much like the plaster-block partitions, resisting thoroughly the passage of the flames. But the plaster always washes off when the hose is applied and the lath becomes exposed. The rigidity of



metal fabric on the metal studding has been considered by firemen a disadvantage, as it is very difficult to cut through it when necessary to get at a fire. The construction of these partitions is practically the same for the different laths used, which are described on pages 846 to 850. This lath or fabric appears to be subject to the CORROSIVE EFFECTS of the plaster. In the demolition of the Pabst Building, New York City, the metal lath used throughout in the partitions was found to be considerably corroded, after about four years, even though the lath had been painted. On the other hand other cases are cited by




FIG. 66. Two-inch Solid Plaster Partition. Elevation

manufacturers, such as the Chess residence at Pittsburgh, Pa., the Sturtevant house at Springfield, Mass., and the West End Trust Building at Philadelphia, in which after twenty years no corrosion of the metal lath in plaster partitions was observed. The investigations of the United States Bureau of Standards of various forms of stucco-construction seem to bear out the manufacturers' contention. The lath should in all cases be protected against initial rampant corrosion by painting or galvanizing before being embedded in the corrosive material.

**Weights of Plaster-and-Metal Partitions.** The weight of a 2-in solid partition, when dry, is about 20 lb per sq ft. The weight of partitions of greater

thickness may be estimated on a basis of 120 lb per cu ft for plaster, and for cinder concrete, slightly tamped.

**Construction of Solid Two-Inch Partitions.** Figs. 65 and 66 show usual method of constructing 2-in partitions. The studs, usually  $\frac{1}{8}$ -in or




FIG. 66. Two-inch Solid Plaster Partition. Horizontal Section

channels, are bent and punched at the ends, and at the bottom are nail wooden strips, which are first secured to the floor-panels, or to the top of steel beams where the partitions come over them. These wooden strips have been found necessary as a sort of cushion to allow the studding to expand in case of fire. At the top, the studs are nailed to the underside of the floor-panels, or, if there is a suspended ceiling, they are wired to the bars supporting the ceiling. At the openings, 1 by 1 by  $\frac{3}{16}$ -in angles are used, and these are spaced every 16 in for No. 12 screws, used in attaching the rough wooden frame to the angles. After the studding is in position, the metal lathing is laced to one side of it with No. 18 galvanized wire. After the lathing is in place the plasterer should attach wooden grounds to secure the base, and pegs or spot-grounds for chair-rail, picture-molding, etc. These grounds are secured by staples and when the partition is plastered, become very rigid. In plastering partitions, five coats of plaster are required to make a good job; a scratch coat on one side, a brown coat on each side, and the usual white coat on each side for finishing. It is essential for all thin partitions that a HARD-SETTING mortar be used, such as Acme Cement, King's Windsor Cement, Adamant, or Rock Plaster.\* The partitions acquire their STIFFNESS largely from the solidity of the plastering, hence the firmer and harder the plastering the more substantial the walls.

**Double Partitions.** Electric wires and  $\frac{1}{2}$ -in gas-pipes can be run in the SOLID PARTITIONS; but if it is desired to run larger pipes, DOUBLE PARTITIONS




FIG. 67. Four-inch Solid Plaster and Concrete Partition. Horizontal Section

that is, partitions with lathing on each side of the studding, must be used. For these partitions, 2-in, 3-in, or 4-in channels, or flat bars set edgewise, may be used. Sheet-steel channels being probably the most economical. When the space between the studs is not filled with mortar or concrete, the DOUBLE PARTITION

\* Made respectively by the Acme Cement Plaster Company, St. Louis; T. B. King & Company, New York; the United States Gypsum Company, Chicago; and the Rock Plaster Manufacturing Company, New York.

stand fire and water as well as the SOLID PARTITION, while it is much more live.

**Construction of Solid Four-Inch Partitions.** Fig. 67 shows a partial section through a SOLID PARTITION finishing 4 in thick when plastered. It has great strength and resistance to fire and water, and affords convenient spaces for pipes and thicker jambs for frames. These partitions have cores of cinder concrete, with metal lath on both sides, and are plastered in the usual way. As the concrete will receive no wooden furring is required to fasten the baseboards, chair-rails, and picture-moldings in place.

**Berger's Economy Studding and Furring.** Fig. 68 illustrates a patent stud manufactured by the Berger Manufacturing Company, Canton, Ohio. It is made of No. 18 or No. 20 sheet steel, and in five sizes varying from  $\frac{3}{4}$  to  $1\frac{1}{4}$  in. The peculiar advantage of this stud is the provision for attaching the lath. For this purpose prongs are punched from the sides of the flange, which are left standing at angles to the face of the flange. The lath is pressed against the stud, the prongs pressed through the lath and then turned up over the lath with a screwdriver. This fastens the lath more firmly and more easily than by any other method. The ends of the studs are secured by sockets which are fastened to the floor and ceiling, a clear space being left above the top of the studs for expansion. Where partitions meet at angles, angle-irons with sockets are used in place of the T irons. By using Berger studs and expanded-metal lathing, a saving in cost can be effected over the construction shown in Fig. 66. These T's are used, also, for supporting suspended ceilings under I beams, the T's being bolted to the flanges of the beams by specially designed clips. Furring-strips and channels, also, are made on the same principle.

**Spacing of Studs in Two-Inch Solid Partitions.** In solid partitions with  $\frac{3}{4}$ -in rolled channels or Economy Studs, the studs should be placed 12 in on centers when the height of the story exceeds 10 ft. When the height of story is less than 10 ft, a spacing of 16 in will answer. For hollow partitions with 2-in studs, the studs can be spaced 16 in on centers for story-heights of 6 ft or less. For greater heights they should be placed 12 in on centers.

**Stud.** In Fig. 69 is shown the Rib Stud made by the Truscon Steel Company, Youngstown, Ohio. It is made in widths of  $2\frac{1}{4}$ ,  $3\frac{1}{4}$ ,  $4\frac{1}{4}$ ,  $6\frac{1}{4}$ , and in lengths up to 18 ft. The studs are made of OPEN-HEARTH STEEL, the two-rib studs weighing 0.55 lb per ft and the three-rib studs, 0.85 lb per ft. In SOLID PARTITIONS with  $\frac{3}{4}$  or 1-in channels or studs, the studs should be spaced from 12 to 16 in on centers, depending upon the stiffness and rigidity of the lath. A 12-in spacing should never be exceeded when the height of story is more than 12 ft. For HOLLOW PARTITIONS with 2-in studs, the studs can be spaced 16 in on centers for story-heights of 16 ft or less, when No. 24 (United States gauge) expanded metal or No. 18 (United States gauge) wire lath,  $2\frac{1}{2}$  by





FIG. 68. Berger Studding or Furring and Stud-sockets


$2\frac{1}{4}$  mesh, are employed. For greater heights the spacing should never exceed 12 in. No. 22 (United States gauge) expanded metal, weighing at least 4 lb per yard, and No. 20-gauge V-stiffened wire lath or wire lath with rods or runners spaced  $7\frac{1}{4}$  to 8 in on centers, give satisfactory rigidity for both parti



$2\frac{1}{4}$  Inches and  $3\frac{1}{4}$  Inches Wide.



$4\frac{1}{4}$  Inches Wide.



$6\frac{1}{4}$  Inches and  $8\frac{1}{4}$  Inches Wide.

FIG. 69. Rib Stud for Plaster Partitions

and ceilings when the studs or furring-strips are set 16 in on centers. It should be wired to the metal studding with No. 18-gauge annealed galvan wire.

**Metal Lath.** Numerous styles of METAL LATH have been put on the market in recent years to provide for a cheap, light, and thin partition-construction.




FIG. 70. Expanded-metal Lath with Diamond-shaped Mesh

For fire-proof buildings METAL LATH should always be used. Metal lath is supplied either plain, painted, or galvanized. It is recommended that metal lath be always at least painted, to prevent incipient corrosion until the lath can be covered by the mortar. Galvanizing is necessary where there is danger of moisture reaching the lath while it is without a protective coating of lime or cement. Where a particular type of lath is

mentioned in a specification, it should be generally described as follows: "Painted or galvanized No. 24-gauge expanded-metal lath, weighing not less than  $3\frac{1}{4}$  lb per sq yd, or painted or galvanized woven-wire cloth, No

2½ meshes to the inch, with stiffeners placed 8 in on centers and weigh not less than 3½ lb per sq yd." Metal lath should be so made that it will plaster freely, key it thoroughly, and wholly embed itself in it. These are characteristics of expanded-metal and woven-wire laths which make them superior to sheet lath. Sheet laths are economical in the use of mortar, which only covers one side of the lath and latches through the perforations without thoroughly embedding the metal. The difficulty of stretching plain wire lath is enough to make a firm foundation for plaster and the resulting necessity of close spacing of the studs to secure the required bearing, has led to the production of stiffened wire cloth and ribbed or corrugated expanded metal lath to obtain the necessary rigidity. To overcome the necessity for separate lathing-studs, expanded-metal and sheet-metal laths are manufactured also in a piece steel lath-and-stud.

EXPANDED METALS differ in the process of manufacture. One type is made simply slitting the sheet and deploying it into the diamond shape; the other is made from thin

of soft, tough metal by a mechanical process which pushes and expands the metal into the mesh at the same time as it sets the direction of the edge, so that the surface of the cut metal is nearly at right angles to the original surface of the metal. It is claimed that the COLD WORK-




FIG. 71. Expanded-metal Lath with Rectangular Mesh

of this low-carbon steel increases the ELASTIC LIMIT and ULTIMATE STRENGTH. In specifying expanded metal, it is necessary to give the weight of finished product per square yard as well as the gauge of metal, as the strands may be of various widths. EXPANDED METAL is made either with diamond-shaped (Fig. 70) or rectangular (Fig. 71) meshes. When laid with the long strands perpendicular to the studs, the lath with the rectangular mesh is the stronger of the two. Rigidity is also obtained by corrugating and expanding the metal in various ways, which make the so-called ribbed, corrugated, and integral laths. WIRE LATH is stiffened by clipping corrugated-steel furring-strips to the lath or by welding rods or V-shaped stiffeners at regular intervals.

**Types of Metal Lath.** Metal lath may be classified as follows:

Expanded-metal lath;

- (a) Diamond and rectangular mesh,
- (b) Ribbed or corrugated,
- (c) Integral, combining functions of both lath and studding,

Sheet lath;

- (a) Flat perforated,
- (b) Integral, combining functions of both lath and studding,

Woven-wire lath;

- (a) Plain,
- (b) Stiffened.

The characteristics of the laths and their characteristics are given in the following paragraphs.

## (1) Expanded-Metal Lath

**Rotary Diamond-Mesh Lath.** This lath is made by the Berger Manufacturing Company, Canton, Ohio. It is furnished in sheets 18 by 96 in Nos. 27, 26, 25, and 24 gauge, weighing respectively  $2\frac{1}{2}$  lb,  $2\frac{1}{2}$  lb, 3 lb, and lb per sq yd. It is made of Toncan Metal, for which greater HOMOGENEITY is claimed than for charcoal-iron and steel, and less liability to CORROSION PITTING.

**Bostwick Lath.** Bostwick lath is made by the Bostwick Steel Lath Company, Niles, Ohio. It is furnished in sheets 14 by 96 in, approximately 1 sq and also 24 by 26, and is made in Nos. 24 and 27 gauge.

**Steelcrete Lath.** This material is manufactured by the Consolidated Expanded Metal Companies, Braddock, Pa., and is furnished in two styles known as STEELCRETE A lath and STEELCRETE B lath, for exterior stucco-work and in the standard-form DIAMOND LATH, extensively used for exterior and interior plastering-work. STEELCRETE DIAMOND LATH is divided into three divisions, P LATH, F LATH, and H LATH. The P LATH meets the specifications of the United States Post Office Department, weighs 4.37 lb per sq yd, and is manufactured from 22-gauge material in sheets 24 by 97 in. The F LATH is manufactured in sheets 24 by 97 in from the gauges 24, 25, 26, and 27, respectively weighing 3.40, 3.00, 2.55, and 2.33 lb per sq yd. The H LATH has a size of 28 by 97 in and is manufactured from the gauges 24 and 26, weighing respectively 2.90 and 2.20 lb per sq yd. STEELCRETE LATH can be obtained manufactured from open-hearth black sheets or galvanized sheets, or in copper-bearing sheets (acid-resisting).

**A Diamond-Mesh Lath** is made by the Penn Metal Company, Boston, Mass., in sheets 24 by 96 in in size and of the following gauges: No. 22, weighing 4 lb per sq yd; No. 24, weighing 3.4 and 3 lb per sq yd; No. 26, weighing 2.5 lb per sq yd; and No. 27, weighing 2.3 lb per sq yd. For such extraordinary conditions as are found in gas-plants, dye-works or places where excessive moisture or salt-air action exists, Hampton Rust-Resisting Lath is made.

**Key Expanded-Metal Lath**, made by the General Fireproofing Company, Youngstown, Ohio, is furnished in sheets 24 by 96 in, in Nos. 27, 26, 25, and 24 gauge, weighing respectively 2.34, 2.50, 3.00, and 3.40 lb per sq yd.

**Kno-Burn Lath**, made by the North Western Expanded Metal Company, Chicago, Ill., is furnished in sheets 18 by 96 in, in Nos. 27, 26, 25, and 24 gauge, weighing respectively  $2\frac{1}{2}$ ,  $2\frac{1}{2}$ , 3, and 3.4 lb per sq yd. When made from special ACID-RESISTING sheet steel, this lath is sold under the name XX Cent Expanded Metal Lath.

**Herringbone Expanded Metal Lath** (Fig. 72), made by The General Fireproofing Company, Youngstown, Ohio, is furnished in three styles, A, AAA, and BB. STYLE A is made in sheets  $13\frac{1}{2}$  by 96 in (1 sq yd), of No. 28-gauge metal weighing 3 lb per sq yd. STYLE AAA is made in sheets 18 by 96 in, and from 26, and 24-gauge metal, weighing 2.53, 2.81, and 3.79 lb per yd, respectively. STYLE BB is made in sheets  $20\frac{1}{4}$  by 96 in ( $1\frac{1}{2}$  sq yd), of Nos. 27, 26, and 24-gauge metal, weighing respectively  $2\frac{1}{4}$ ,  $2\frac{1}{2}$ , and  $3\frac{3}{4}$  lb per sq yd. It is made of American ingot-iron, or galvanized sheets. Ribs are set across studs and run down towards them.

**Sykes Expanded Cup-Lath**, made by the Sykes Metal Lath and Roofing Company, Niles, Ohio, is furnished in sheets 18 by 96 in, with an anti-rust coating, or painted black, or galvanized. It is made of Nos. 27, 26, and 24 gauge metal, weighing respectively 2.8, 3, and 3.7 lb per sq yd.

**Standard Rib Lath**, made by the Truscon Steel Company, Detroit, Mich., furnished in sheets 20½ by 96 in, in grades 1, 2, and 3, weighing respectively 3.42, and 4.10 lb per sq yd. This company makes also the **BEADED PLATE**




FIG. 72. Expanded-metal Lath, Herringbone Mesh

**LATH**, which is about 35% heavier and more rigid, permitting wider spacing of studs.

**Mesh Diamond Expanded-Metal Lath** is manufactured by the Milwaukee Corrugating Company, Milwaukee, Wis. This lath is furnished in 24 by 96; in 27, 26, 25, and 24 gauges, painted; and in 26 and 24 gauges hot-galvanized after cutting. This Company, also, makes **CORRUGATED UP-FURRING LATH**, in sheets 21½ by 96 in, same gauges, except No. 25, as **DIAMOND MESH**.

**Up-Fur Lath**, made by the North Western Expanded Metal Company, Chicago, Ill., is furnished in sheets 22 by 96 in, of Nos. 24, 25, 26, and 27-gauge, weighing respectively 3.80, 3.36, 2.82, and 2.62 lb per sq yd. This lath has running obliquely across the sheets at the same angle as the strands of mesh. This corrugation is said to give the lath greater **RIGIDITY** so that it can be used on 32-in centers for walls and on 24-in centers for ceilings. The corrugations act as furring-strips. It is made from a special **ACID-RESISTING** metal and is always supplied painted.

**Truss Metal Expanded-Metal Lath**. Truss-metal lath, Fig. 73, made by the American Rolling Mill Company, Middletown, Ohio, is furnished in sheets




FIG. 73. Truss Metal Lath

20 in, of Nos. 26 and 28-gauge metal, weighing respectively 80 and 66.7 lb per sq ft. A partition constructed of this lath in one of the test-structures at Columbia University, New York City, passed through and withstood, without sign of distress, the fire and hose-streams of five successive tests.

**Fire-Sentering**, made by the General Fireproofing Company, Youngstown, Pa., is furnished in sheets 29 in wide and in lengths varying by 1 ft, from 4 to

12 ft, of Nos. 28, 26, and 24-gauge metal, weighing respectively 0.58, 0.70, 0.93 lb per sq ft. The width of 29 in is the covering capacity, as laps are vided for by outside ribs. (See, also, page 853.)

Hy-Rib, made by the Truscon Steel Company, Detroit, Mich., is furnish three types known as 4-Rib, 3-Rib, and Deep Rib. The first is in sheets in wide, and the others in sheets 14 in wide. (See, also, page 853.) All style furnished in Nos. 24, 26, and 28-gauge metal. The standard lengths are 6, 8 and 12 ft. Other lengths below 12 ft are cut, but the waste is at the cost o purchaser. Hy-Rib sheets interlock at the sides and ends. In ordering allowance need be made for side laps, but for end-laps 2 in should be allowe laps over supports, or 8 in between supports.

Trussit is manufactured by The General Fireproofing Company, You town, Ohio, in sheets 19 in in width, and in lengths of 8, 10, and 12 ft, from 26, and 24 gauge, weighing 0.57, 0.62, and 0.83 lb per sq ft, respectively.

(2) Sheet Lath

Clinched Lath, made by the American Rolling Mill Company, Mic town, Ohio, is furnished in sheets 13½ by 96 in (1 sq yd), of No. 30-gauge m weighing 4¼ lb per sq yd.

Truss-Loop Lath, Fig. 74, made by the Bostwick Steel Lath Comp Niles, Ohio, is furnished in sheets 13½ by 96, 16¼ by 80, 24 by 96, and 2 96 in, weighing 4½ lb per sq This lath is furnished painted u otherwise specified.




FIG. 74. Bostwick Truss-loop Lath

Genfire Sheet-Steel L made by the General Fireproo Company, Youngstown, Ohio, furnished in sheets 24 by 96 weighing 4.6 lb per sq yd, pai unless otherwise specified.

Sykes Trough Sheet L made by the Sykes Metal I and Roofing Company, Niles, O is furnished in sheets 13½ by 9

(1 sq yd), 15½ by 96, 18½ by 96, and 23½ by 96 in, weighing 5 lb per sq and made with an antirust coating, or painted or galvanized.

Integral Sheet Lath. Rib-Truss, made by the Berger Manufactu Company, Canton, Ohio, is furnished in widths of 24 in, and in stock length 4, 5, 6, 8, 10, and 12 ft, as follows:

Gauge	Weight per square yard in pounds		
	1½-in rib	¾-in rib	1-in rib
27.....	73	78	83
28.....	81	86	92
26.....	88	94	100
24.....	117	125	133



## (3) Woven-Wire Lath

**Woven-Wire Lath** is furnished with or without **STIFFENERS**, which are either **H** or **V-SHAPED RIBS** running through the wire mesh to reinforce and stiffen it. It is supplied painted or unpainted, or it is galvanized after weaving. It can be ordered to order in any required width up to 10 ft. In widths less than 18 in., there is a small charge for **STRIPPING**. Before ordering, it is very important to ascertain the proper width, especially of stiffened lath, as it is desirable to have the edges of the lath lap at the supports where it is laced to iron furring. When lath is not of the proper width the results are not so good and there is liable to be a waste of material. The standard width of **PLAIN** and of **V-RIB STIFFENED** is 36 in. When beams or studs are spaced 16 in from center to center, the lath should be 32 or 48 in wide.

The **Clinton Stiffened Lath** has corrugated-steel **FURRING-STRIPS** attached by 8 in, crosswise of the fabric, by means of **METAL CLIPS**. These strips constitute the **FURRING**, and the lath is applied directly to the underside of the floors, or to planking, furring, brick walls, etc. This lath is made in 36-in widths, with  $2\frac{1}{2}$  meshes to the inch, and comes in 100-ft rolls. The manufacturers of lath make, also, a lath **STIFFENED WITH ROUND RODS**,  $\frac{1}{4}$  to 1 in in diameter, spaced from 8 to 12 in apart. It can be had either galvanized or japanned, and thicknesses from 18 to 21 gauge. **Clinton plain WIRE LATH** is furnished in rolls 10 ft long.

The **Roebbling Standard Wire Lath** (controlled by the New Jersey Wire Lath Company, New York), is made of plain **WIRE CLOTH**, in which, at intervals  $\frac{1}{4}$  in, **STIFFENING RIBS** are woven. These have a **V-shaped** section and are made of 24 sheet steel,  $\frac{1}{2}$  and 1 in in depth. The  $\frac{1}{2}$ -in rib is the standard size for lathing on masonry work. This lathing requires no furring, and is applied directly to woodwork or to masonry with steel nails driven through the bottom of the **V**, as shown in Fig. 75. The No. 1  $\frac{1}{2}$ -rib stiffened lathing affords a satisfactory surface for plastering, when attached to studs or beams spaced 16 in apart. The 1-in rib lathing is used for furring exterior walls. It provides an air-space between the lath and plaster. Where this lath is to be applied to light iron furring, a  $\frac{3}{16}$ - or  $\frac{1}{4}$ -in steel rod is substituted for the **V-rib**, and the lathing is attached to light iron furring with lacing wire. This lath is distinguished from the others by the term **V-Rib Stiffened Wire Lath**. The Roebbling lath, whether plain or stiffened, is made with 2 by 2,  $2\frac{1}{4}$  by  $2\frac{1}{4}$ , and  $2\frac{1}{2}$  by 4-in mesh, the last named being known as **CLOSE WARP**. The  $2\frac{1}{4}$  by  $2\frac{1}{4}$  mesh is adapted to all plasters containing the usual proportion of hair or fiber. The  $2\frac{1}{2}$  by 4-in mesh should be used for heavy plasters and thin partitions. The lath can be furnished in widths up to 10 ft and in rolls averaging 50 yd in length.

FIG. 75. Roebbling V-rib Stiffened Wire Lath

**Wall-Boards.** There are various forms of **WALL-BOARDS** of an incombustible material, most of them made of gypsum in combination with felts. They can be used as substitutes for laths. They are very light and require but little plaster material. When this saving is taken into account, wall boards cost less than lath and but little more than wooden lath with three coats of plaster. The

boards are generally 32 by 36 in in size, and  $\frac{1}{4}$ ,  $\frac{5}{16}$ ,  $\frac{3}{8}$ , or  $\frac{1}{2}$  in in thickness. The thinnest boards ( $\frac{1}{4}$  in) weigh  $1\frac{1}{2}$  lb per sq ft, and the thickest ( $\frac{1}{2}$  in)  $2\frac{1}{2}$  lb. Wall-boards of asbestos are described on page 819. The best known is **TRANS** made by the H. W. Johns-Manville Company, New York.

**Sackett's Wall-Board.** This is a composite board of three layers of gypsum and four thin layers of wool-felt. The boards can be nailed to wood studding or set flat against solid beams or planks, and can be cut with a saw. For plastering, the best results are obtained by applying first a brown coat of hard wall-plaster,  $\frac{1}{4}$  to  $\frac{3}{8}$  in thick, and when this is thoroughly set, finishing with a thin coat of regular hard finish of lime-putty and plaster. Tests and investigations at the Underwriters' Laboratories "have shown Sackett Board Perfection Brand, to be suitable as a base for fibered-gypsum plasters; and when attached to walls, ceilings, and partitions and coated with  $\frac{1}{2}$  in of plaster, possesses fire-retarding properties considerably higher than those of wooden lath and gypsum or lime-and-cement plaster." The Perfection Brand, Sackett's Wall Board, is  $\frac{3}{8}$  in thick, and is attached with No. 10  $\frac{1}{4}$ ,  $\frac{1}{2}$ -in, flat-headed,  $\frac{3}{8}$ -barbed wire nails,  $1\frac{1}{4}$  in long, and spaced not more than 6 in at each support. **SACKETT BOARD** is made by the United States Gypsum Company, Chicago, Ill., and Grand Rapids Plaster Company, Grand Rapids, Mich. Other makers of gypsum wall-boards are the J. B. King Company, New York (Diamond Brand), Southern Gypsum Company, North Holston, Va. (Economy Brand), and American Gypsum Company, Port Clinton, Ohio (Monarch Brand).

**Metal-Rib Plaster-Board** is composed of alternate layers of strong absorbent paper reinforced with fine annealed wire about 2 in on centers, and stiffened transversely with  $\frac{1}{2}$ -in iron bands, No. 32 gauge, placed 8 in on centers. The material is made up to a total thickness of about  $\frac{3}{16}$  in, impregnated with a coal-tar product, and provided every 2 in with  $\frac{3}{16}$ -in circular holes to key the plaster. This is added to the adhesive effect of the absorbent paper. It is furnished in rolls 85 ft long and 34 in wide, nailed directly to the studs or beams set 12 or 16 in on centers, and lapped 2 in at all joints. This board is recommended for use with hard-plaster mortars only, and forms a satisfactory base for three-coat work, in which the lap-joint obviates the cracking frequently associated with ordinary plaster-board construction.

**Bestwall.** **BESTWALL** is primarily intended for use as an interior finish on side walls and ceilings in buildings of all classes. It may be used in all situations where finishes of lath and plaster may be used, and in many situations where the latter finish is not adaptable. It consists of a single layer of fiber calcined gypsum, surfaced on each side with specially prepared water-proofed paper, securely bonded to the surface. Bestwall is  $\frac{3}{8}$  in in thickness, and is furnished in stock sizes 47  $\frac{1}{4}$  in wide, and in lengths of 5, 6, 7, 8, 9, and 10 ft. The finished product presents a smooth, true surface, which is light cream in color on the face-side and gray on the reverse side. The edges are slightly beveled to provide for the filling of the joints, and are doubly reinforced. Its weight is approximately 1850 lb per 1,000 sq ft. Interior finish composed of Bestwall is applied by nailing the Bestwall directly to the joists, studs, and furring, and filling the joints between the pieces of Bestwall with a specially prepared filling of the same composition as the core of the board. For the nailing, three-penny fine wire nails, spaced from 2 to 3 in at the edges and from 8 to 12 in at the intermediate supports, are used. The filling consists of two operations; first, **ROUN** IN and then, **TROWELING OUT**, to a smooth, true finish, flush with the surface. Bestwall is cut and fitted either with a saw or by scoring and breaking over a straight-edge. The completed finish presents a smooth, true, continuous surface.

about showing joints or nail-heads, and ready to receive, if desired, a decoration of paint, paper, tint, etc.

**Shaft-Construction.** The most important partitions in a building are those inclosing interior shafts. Vertical openings through buildings form flues and are up-drafts. In all buildings, fire-proof as well as non-fire-proof, therefore, they should be inclosed for two reasons: first, to prevent a fire that would find a natural outlet in such openings from spreading to other floors; and secondly, to prevent, as far as possible, a fire from getting into these openings where the fire would greatly increase its fury. To be thoroughly effective the inclosed shafts should be constructed of the same materials as the outside walls of the buildings, namely, brick, stone, or concrete. While they need not be of the same thickness as the outside walls, 12 in is recommended as a minimum thickness. In less important structures terra-cotta partitions are sometimes used for such inclosing walls. In the walls inclosing elevator-shafts no openings except those necessary for entrance-doors should be permitted. The doors should be of fire-proof construction, pages 901-2, and made solid. Glass lights are sometimes provided in such doors, although this is not good practice; if they are used, wire-glass, only, should be used, in accordance with the limitations noted on pages 902-3. Open grille-work for passenger-elevator enclosures is being rapidly superseded by construction which is more fire-resisting. The architectural features of open grilles may still be retained for the fronts and doors of such elevators by using them in conjunction with approved wire-glass construction. In interior light-shafts and vent-shafts, openings must necessarily be provided, but here again the construction of the window-frames, sashes, and glazing should be as far as possible as described on pages 901 to 903. When the occupancy of a building admits, the stairs, also, should be inclosed in masonry walls, with fire-proof doors at the openings. Unless so inclosed the stairways form flues for the flames, and the stairs themselves, consequently, are exposed to intense heat. In such situations, even absolutely fire-proof stairs should not be used during a fire, and possibly it is for this reason that greater precautions have not been taken to make them fire-proof. Shaft-walls should in all cases be carried 3 ft or more above the roof.

**Deadening Properties of Partitions.** The resistance to the passage of sound through fire-proof partitions is an important consideration in buildings used for living-apartments; and where the rooms are to be used as music-studios, it becomes a matter of still greater importance. In January, 1895, some tests were made to determine the RELATIVE DEADENING PROPERTIES of the different partitions shown in Fig. 76, the object being to decide upon the construction that should be used in Steinway Hall, Chicago, Ill. The rank of the different partitions tested, IN SOUND-PROOF EFFICIENCY, is shown by the numbers at the bottom of the partition-diagrams. The 4-in porous partition was used, but was not a success. In the Fine Arts Building, in the same city, double partitions, similar to No. 1, were used, and it is said that they were a great success. It is interesting to note that in the tests above mentioned, the 2-in-solid-plaster partition, No. 3, plastered with common mortar, ranked higher in SOUND-DEADENING PROPERTIES than those with double studs. In 1892 C. L. Norton tested the SOUND-DEADENING PROPERTIES of partitions of several forms, for the purpose of determining a construction which was the most FIRE-RESISTING and SOUND-PROOF for the dormitories of the New England Conservatory of Music, in which practically every room is a music-studio.\* The various partitions were rated by Professor Norton as shown in the following table:

The results of these tests, with a description of the partitions, were published in *Engineering* for August, 1902.




Fig. 76. Relative Deadening Properties of Partitions

Table XVI. Sound-Deadening Properties of Partitions

Room	Side	Scale	Composition
E	Left	100	Cabot's quilt, 3 thick and metal lath
E	Right	95	Cabot's quilt, 2 thick and metal lath
E	Rear	95	Cabot's quilt, 2 thick and metal lath
C	Rear	85	Sackett board, 2 felt on channels
C	Left	85	Sackett board, 2 felt on channels
C	Right	80	Sackett board, 2 felt
D	Rear	75	Metal lath and paper
D	Right	75	Metal lath, paper, and felt
B	Right	60	Two 2-in Keystone blocks with 2-in air-space
A	Rear	50	4-in National terra-cotta blocks
B	Rear	50	3-in Keystone blocks
A	Right	45	3-in National terra-cotta blocks
B	Left	40	2-in Keystone blocks
A	Left	40	2-in National terra-cotta blocks
D	Left	30	2-in metal lath, solid plaster

thing more is to be inferred from the numerical efficiencies, under 'scale' that the first partition is about three times as good as the last, and that the equal interval between any two partitions on the list merely indicates the magnitude of the difference between the partitions." Professor recommended a partition of Sackett Board and plaster with two thick of Cabot's quilt between the plaster-boards, and this construction was used. The studding was put up the same as for the 2-in solid partition, the plaster-board wired on to the studs, and the plaster-board wired on to the studs through the quilt. This makes as light a partition, also, as it is possible to get. The investigations by Professor F. R. Watson of the University of Chicago showed that 2-in solid, metal-lath partitions are more sound-deadening than hollow, gypsum-block partitions. Gypsum tile has been found to be less satisfactory than terra-cotta tile of the same thickness.

**Furring for Outside Walls.** The outside walls of fire-proof buildings are usually finished on the inside by plastering applied directly to the masonry. If the walls are of brick, it is often desirable to furr them so that there will be an air-space between the plaster and the masonry to prevent the passage of heat. This furring should be either of terra-cotta or metal, and never of wood. For this purpose furring-bricks may be used. They are made of brick of the same size as common bricks; but they are hollow. They are laid with the rest of the wall, on the inside face, and bonded into the wall by the usual header-courses. Split furring-tiles, also, are often used on the inner face of brick walls, as shown in Fig. 77. The tiles are either  $1\frac{1}{2}$  or 2 in thick by 12 in on the face. The face is grooved to give proper bond for the plaster. At recesses in the walls partition-blocks are substituted across the wall, making a continuous wall-surface. When using furring-tiles, the builder should be careful not to drop mortar into the hollow spaces. When walls are built or lined with tile, solid porous terra-cotta blocks should be built in at the base. Nailings are required for bases, picture-moldings, etc. Wire lathing, made of 1-in V ribs woven in every  $7\frac{1}{2}$  in, makes a good furring for brick walls. It is easily applied and leaves air-spaces between the wall and plaster. These devices also protect the walls from being warped by heat during summer and prevent the passage of heat through the walls in summer and winter.

**Metal Furring.** To produce architectural forms in the interior decoration of fire-proof buildings, METAL FURRING and METAL LATH are now almost universally used. The furring is always of a sham nature, and never employs




FIG. 77. Hollow-Tile Wall-furring

to carry loads of any magnitude; so that the only requirement is that it shall be incombustible and furnish a satisfactory ground for attaching the metal lath. For coves, cornices, false beams, etc., the furring-members are made of light bars, angles, tees, or channels, attached to the walls by means of nails, staples or toggle-bolts, and to the steel beams by means of bolts, hangers, clips, etc. The furring-pieces are bent or shaped to the approximate outlines of the finish plaster-work, so that when the lathing is applied it will require not more than  $1\frac{1}{2}$  or 2 in of plaster to give the desired outline. For plane surfaces, the furring should be brought to within  $\frac{3}{4}$  in of the plaster-line. Deep beams, etc., should be braced by diagonal rods, to prevent distortion. All structural-steel members should always be fire-proofed back of the furring. The lathing is secured to the furring by means of No. 18 galvanized lacing-wire. The spacing of the furring should be either 12 or 16 in, according to the kind of lath that is to be used. When chases in walls are covered over, the covering should be done with metal furring and lath. The casings for vertical pipe-lines, also, should be of this construction and the space about the pipes at the floor-level should be filled solidly with fire-proof material, to cut off all connection between stories.

## 7. Fire-proof Flooring

**Fire-proof Flooring.** The floor-surfaces of most fire-proof buildings consist of hard-wood flooring secured in the usual manner to nailing-strips embedded in the concrete or in the filling above it. It is sometimes advisable to use incombustible flooring. The New York City Building Code requires that in buildings over 150 ft in height, the floor-surfaces shall be of stone, cement tiling, or similar incombustible material, or of wood treated by some process which renders it fire-proof. For warehouses and factories, floors finished with Portland-cement mortar are about as satisfactory as floors with any other floor finish; and cement floors have been much used for the guest-rooms

la. In the latter rooms, the floors are covered with carpets, which are set into wooden strips embedded in the cement around the borders of the floor. This makes a very sanitary floor, and one as easy for the feet as a carpeted wooden floor. For public corridors, banks, lobbies, toilet-rooms, etc., the mosaic, vitreous, ceramic, or marble tilings are generally used. In France and many large quantities of cement tiles are used. Cement tiles have been introduced into this country, also, but have not yet been able to compete with encaustic tiles. In most buildings, however, the use of stone, cement, or tile flooring is inadvisable. These materials are cold and trying to the feet. As a cement floor-surfaces do not wear well. Asphaltic flooring is sometimes used, but it is not pleasing in appearance. This material and different floorings are discussed on pages 1604 to 1609. The characteristics of fire-proofed flooring and its availability for this purpose are considered in the discussion of that material on page 820.

**Composition Flooring.** Several attempts have been made to obtain a flooring-material which could be spread, without joints, over an entire floor, at the same time be elastic, wear well, withstand water, acids, etc., and not be expensive. Various mixtures of magnesite, asbestos, fine sand, sawdust mixed with linseed-oil, and some binder like chloride of magnesium, have been in the market under different names, all more or less meeting the requirements above stated and being, also, fire-proof. These materials are shipped in the form of a dry powder to the place where they are to be used, and are there mixed with a specially prepared liquid. The resultant is a plastic material which is laid upon the surface to be covered in much the same way that ordinary cement or plaster is put on. The materials harden in from 12 to 24 hours in a moderately dry weather, when the floor is ready for use. When properly finished the floor presents a smooth, fine-grained, and continuous surface, resembling linoleum. These materials are made in various colors, such as red, white, brown, gray, black, blue, and green, and can be laid on wood, stone, concrete, asphalt, cement, or metals. Another advantage is that they can be applied up on the walls so as to form a covered base, without cracks or joints. Among the manufacturers furnishing such floorings may be mentioned: General Portland Cement Company, Long Island City, N. Y.; Marbleoid Company, New York; Franklyn R. Muller & Company, Waukegan, Ill.; and Ronald Taylor & Company, New York City.

**Asphalt Mastic Flooring.** This flooring is in the nature of an ASPHALTIC MASTIC consisting of natural asphalt and a well-graded mineral aggregate of gravel, and crushed stone, ranging in size from that which passes a 200-mesh screen to  $\frac{1}{4}$  in. The material is sent to the building-site in blocks and is broken up, reheated, and mixed with the coarser aggregate, the softened mixture being laid down in one or two courses, depending upon the thickness required, and smoothed down by rubbing with wooden floats. It is laid without expansion-joints, the usual thickness being  $1\frac{1}{2}$  in, weighing 18 lb per sq ft. Asphalt flooring is tough, ductile, water-proof, resistant to acids, alkali and fire-proof, noiseless, and easy on the feet. It is especially suitable for streets and warehouses. It is manufactured by the H. W. Johns-Manville Company, New York.

### 8. Interior Finish and Fittings

**Interior Finish.** In buildings in New York City in which the flooring must be of non-combustible material, the interior finish, also, including the doors, door-cases, window-frames, sashes, bases, and trims, must be made of incombustible



materials. The same materials that are accepted for flooring can be used for this interior finish also. Several of the largest buildings in New York City including the Fuller Building, have all the trim constructed of FIRE-PROOF WOOD. In the Hotel Gotham, all the doors and interior finish are made of Alignum.

**Metal Doors, Sashes, Frames, and Trim.\*** The effort to make the interior of buildings fire-proof has resulted in METAL-COVERED wood, and in doors, sashes, frames, trim, and moldings of HOLLOW steel or other metal. Many very large buildings have in recent years been equipped wholly or in part with these products, and the products themselves have reached a stage of great perfection of workmanship and efficiency. Several cities in the United States compel the use of these products for certain parts of buildings which are over a certain height; and it is probably only a question of time when other cities will pass ordinances compelling their use. At the present time cost enters largely into the question of substituting them for wood. Among the first attempts in the United States to fire-proof the interior trim of buildings were those made in New York City, about the year 1880, in the form of metal-covered woodwork by the firm of Campbell & Bantossell of that city. About this time, also, there were introduced along with various processes of fire-proofing woodwork FIRE-PROOF PAINTS. Later, FIRE-PROOF WOOD was introduced, that is, wood from which has the resin and other inflammable components extracted from it, and the fiber left. In the course of a few years the METAL-COVERED-WOOD industry developed to such a stage that it was possible to trim with its products the interior of a building and keep a good appearance. Notable examples are the Manhattan Life Insurance Company's Building and the Barclay Building, and of more recent date, the Metropolitan Tower,† the Fifth Avenue Office-Building, the Germania Life Insurance Company's Building, and the Vanderbilt Hotel, all in New York City; the Hoge Building, Seattle, Wash.; the Hall of Records, Los Angeles, Cal.; the Rockefeller Annex, Cleveland, Ohio, etc. The rough unfinished appearance of the STANDARD TIN-CLAD DOOR set men to seeking a product for use in interior finish which would lend itself to more decorative effects. The KALAMEIN IRON and other METAL-COVERED work resulted. In the meantime improvements were constantly being made in HOLLOW SHEET-METAL doors and trim, and from about the year 1903 HOLLOW STEEL construction for this work came into use. Owing to its generally superior workmanship and to the splendid enamel surfaces which can be given it by various baking-processes, this type of interior finish has found favor in the eyes of the architects and owners of modern offices, and mercantile and public buildings.

**Kalamein Iron.‡** KALAMEIN IRON is the trade name given to one of the open-hearth sheet-steel products which is covered with a thin alloy of tin and lead in much the same way that galvanized iron by galvanic immersion is coated with zinc. "The name CALAMINE (with Galmei of the Germans) is commonly supposed to be a corruption of Cadmia. Agricola says it is from

\* For a brief outline of this subject, illustrated with numerous detail drawings, see article on Metal Doors, Sashes, Frames, and Trim, by Professor Thomas Nolan, in Kidder's Building Construction and Superintendence, Part II, Carpenters' Work.

† The Metropolitan Tower has a metal-covered trim which is a special bronze-plated construction over a wooden core. This was developed by The John W. Rapp Company, afterwards consolidated with The J. F. Blanchard Company into the United States Metal Products Company, New York City.

‡ Among the better known manufacturers of metal-covered work, whose doors and trim are inspected and labeled by the Underwriters' Laboratories, Inc., are the United States Metal Products Company, New York City and the Thorp Fireproof Door Company, Minneapolis, Minn.



is, a reed, in allusion to the slender forms (stalactic) common in the formation."\* The term KALAMEIN is often used incorrectly, by architects and others, for any form of METAL-COVERED woodwork, whether the metal copper, or bronze, to distinguish metal-covered from HOLLOW METAL construction; but the term is obviously misleading and causes much confusion. In instances architects have specified KALAMEIN material expecting BRONZE to be used in the covering, whereas the manufacturer's interpretation of the specification was that KALAMEIN IRON was intended.

**Metal-Covered Doors, Frames, and Trim.** The cores of METAL-COVERED doors and frames are built up of oak or white-pine strips dovetailed together edge to the grain. In gluing up the strips into stiles and rails the grain of each strip is reversed in order to resist the tendency of the core to twist. The stiles and rails are mortised, tenoned, and box-wedged, and the cores are covered with asbestos paper or board and enclosed with sheet metal, either steel or iron may be painted to match a wooden trim, or electroplated with copper, or bronze), or solid sheet copper, brass, or bronze. For doors up to 3 ft in width and 8 ft in height, both sides are often made of continuous sheets of metal which have the panels pressed into them by hydraulic pressure and are joined at the seam or joint. The metal sheets of the two sides, in one make of door, are made to overlap in a depression on the edges of the door and are secured by screws which pass through both face-sheets. The standard thickness of sheet metal is  $2\frac{1}{8}$  in. When these doors are more than 3 ft 4 in in width, each door is usually made of two sheets which meet over a middle stile and lock with a flush double-lock joint. This makes a double row of vertical

**Metal-Covered Window-Frames and Sashes.** Window-frames and sashes, like door-frames and doors, are made of METAL-COVERED WOOD. Bronze is usually recommended and preferred although Kalamein iron may be substituted when a much cheaper construction is necessary. This cheaper metal may be painted and will give fair service but it is not recommended. Steel and iron and copper, also, are used. "Window-frames and sashes of sheet metal or of sheet-metal over wooden cores are principally used for skylights where the only danger of fire-contact is through the glass panes. They are NON-COMBUSTIBLE rather than FIRE-RESISTING. The glass panes are usually of plate glass, especially if KALAMINE trim is used to comply with the law in those cities where non-combustible windows, etc., are required in buildings of a certain class or of a height and limits. Previous mention has been made of their efficiency as demonstrated in the burning of the Kohl building in San Francisco, and their use as a substandard protection, has been pointed out; but for efficient fire protection, KALAMINE windows, especially, are an unknown quantity, as the service offered by the lighter members, such as sash-rails, is questionable. The examples of the work present pleasing workmanship and finish. If sheet metal could be used for the body instead of wood, without producing any action harmful to the metal, a superior type of KALAMINE work would be of great value."†

**Metal Finish in General.**§ The transition from METAL-COVERED

Dictionary of Mineralogy.

hardness seamless door, made by the Thorp Fireproof Door Company, Minneapolis.

Convention and Fire Protection, by J. K. Freitag.

the better-known manufacturers of hollow, sheet-metal doors, trim, etc., are the Armstrong Metallic Door Company, Jamestown, N. Y.; the National Metallic

wood to **HOLLOW SHEET METAL** for doors, sashes, frames, trim, moldings, etc. was naturally and easily made and to-day the latter type of construction, when expertly carried out, results in details for interior work which are very effective to resist fire and handsome in appearance. It would be difficult to devise structural details which would be more satisfactory and at the same time present greater possibilities in the way of elaborate design and high finish and it is on account of all these advantages that this type of construction is found in the interior equipment of many of the best examples of fire-resisting buildings, especially for the doors, frames, sashes, and trim of corridors, hallways, stair and elevator-enclosures, and even for entire office-partitions. Because of the non-absorbent character of the baked-enamel finish this material is particularly sanitary; and hollow metal doors are more easily cleaned than any other, especially if all moldings are omitted and panels made simply as smooth designs. The thickness of standard hollow metal doors approved by underwriters, varies from  $1\frac{1}{2}$  to  $2\frac{1}{8}$  in.

**Hollow Metal Doors.** The Dahlstrom patent **SHEET-METAL DOOR** is made from two No. 20-gauge-steel plates, one stile and one panel-face being formed from each of the sheets, which are connected by interlocking seams on opposite sides of the panels and make practically a double door. In constructing the panels they are first lined with a sheet of asbestos next to the stile on each side, and the space between is filled with a layer of hair-felt paper, which makes a resilient filling that is a non-conductor of heat. The stiles are hollow, but strips of cork are laid perpendicularly across the center of each to deaden the metallic ring. The panels are then attached to each other to form the door by planting on and welding in place properly formed cross-rails at the top and bottom, and wherever else they may be desired; the molding is coped over the molded stiles at the sides. The top and bottom edges of the door are then reinforced with channels and bars, and the doors made perfectly straight and rigid. The fire-resistance of this construction is increased by letting no rivets or screws pass through from one side of the door to the other in the exposed parts. The transmission of heat is thus avoided. While the door is being put together, provision is made for attaching the hardware. After the doors have been put together, they are sent to the finishing department where the steel is thoroughly cleaned from all rust, grease, or other impurities. They are then given six or eight coatings of enamel, being baked after the application of each coat in large ovens which are heated to  $300^{\circ}$  F. After the final coat of varnish is put on, they are usually rubbed to an egg-gloss-finish, equal in quality to any hardwood-finish, and more durable because baked on. The surfaces can be grained to imitate with wonderful exactness any wood, such as quartered oak, mahogany, Circassian walnut, etc. If the doors are to receive glass panels they are provided with detachable moldings to hold the glass in place. Doors of the Dahlstrom, **HOLLOW METAL** type are installed in the corridors and partitions of the Singer Building and tower of the United States Express Building, New York City; the Bell Telephone Exchange Building, Philadelphia, Pa.; the Seventh Regiment Armory, Chicago, Ill.; the Pontchartrain Hotel, Detroit, Mich.; the Bank of Commerce Building, St. Louis, Mo.; the First National Bank Building, Denver, Col.; and the Royal Insurance Building, San Francisco, Cal. In some of the buildings

Sash Company, Chicago, Ill.; the Solar Metal Products Company, Columbus, Ohio; and the Central Metallic Door Company, Gary, Ind.

\* Made by the Dahlstrom Metallic Door Company, Jamestown, N. Y.

† A severe fire in the twenty-sixth story of this tower was effectually confined to the room in which it originated by the doors of this type of construction.

In the preceding articles, **HOLLOW METAL** doors, trim, and moldings are lined by bronze or other **METAL-COVERED WOOD** window-frames, etc.

**Metal Door-Frames, Trim, and Moldings.** After the **HOLLOW** door reached an advanced stage of construction the manufacturers turned their attention to the problems involved in making metal frames and moldings. It was found that moldings made by the ordinary **HOT-ROLLED** metal were too rough and heavy and required too much labor to smooth down their surfaces; and that those pressed from light-gauge steel by the ordinary methods were not clear-cut and definite in their outlines, and were of no length and in variety of shapes. Accordingly, what is known as the **COLD-DRAWN METHOD** of making frames, trim, and moldings, was developed and perfected, and moldings made by this process are now used for many kinds of work. The cold metal is drawn through special dies to give it the shape and the bright finish is retained. The corners and angles come square and true and the pieces possess much greater strength and rigidity than **HOT-ROLLED** and several times thicker. There are dies for over a hundred different shapes. Moldings can now be made in lengths up to 40 or even 50 feet. Extra-freight rates and other drawbacks make it inadvisable to ship it in pieces of over 20 ft. Besides the **COLD-ROLLED** special high-grade steel, aluminum, bronze, and copper are used in their manufacture. The rolled shapes include angles, channels, and Z bars; moldings for bases, cornices, wire-conduits, sash-bars, panels, and glass; picture-frames, door and window frames and trims of all kinds; wainscoting and chair-rails; and numerous miscellaneous shapes. **WROUGHT-IRON** welded one-piece door-frames are made for use in partitions. These frames are constructed scientifically of specially selected **WROUGHT IRON** in several different shapes. The mitered corners are welded together making the frame one solid piece. They are made for any type of door or partition, require no bracing, and can be fitted with hinges if required.

**Metal Window-Frames and Sashes.** (See, also, Sheet-Metal for Window-Frames and Sashes, page 902). **HOLLOW METAL** window-frames and sashes, as well as those which are made of **METAL-COVERED WOOD** or iron, wrought iron, drawn bronze, cast bronze, etc., and glazed with prism glass, electroplated glass, etc., are used in those parts of buildings in which the exposure to fire is not great enough to require the use of hinged shutters, or where a more pleasing appearance is demanded than that obtainable from the use of hinged or rolling fire-shutters. Owing to many improvements made in recent years, both in design and details of manufacture, **SHEET-METAL** window-frames and sashes are now ranked among the best of those of moderate cost for general use. The National Fire Protection Association, by its recommendations and standardizations, and the labeling systems of the underwriters' laboratories, have been largely instrumental in bringing about these improvements and results. About the chief advantage connected with the use of **SHEET-METAL** windows is a relatively small deterioration when neglected. The materials used for making **HOLLOW METAL** window-frames and sashes are galvanized iron or steel; copper; sheet metal, galvanized; and sheet metal, bronze-plated. The sashes are glazed with **SAFETY** wire-glass where good appearance is an essential requirement, or **PLAIN** OR **ROUGH** wire-glass where a translucent material only is desired. **Clear glass**, unwired, may be used when additional fire-resistance is not required.

The National Board of Fire Underwriters fix, within certain limits, the constructional details, the maximum permissible sizes of openings for

glass, etc. The principal regulations have been very conveniently condensed by Mr. J. K. Freitag.\*

**Solid Steel Windows.** Where large window-surfaces giving maximum are desired, as in factories, the so-called **SOLID STEEL WINDOWS** are frequently used. They have been given this name because the frames and muntins are made of solid, rolled-steel sections, jointed at their junctions or intersections by special methods, in some cases oxy-acetylene welded, so as to make strong, stiff frames. The manufacturers generally carry stock sizes varying in approximate widths from 3 to 6 ft, and approximate lengths from 3 to 9 ft. The panes are about 12 by 18 in. The movable sections, or **VENTILATORS**, are pivoted on horizontal axes, though a **COUNTERBALANCE TYPE**, also, is made for use in hospitals and public buildings. Ventilators should not exceed 5 ft in height, nor more than 18 sq ft in area. Among the principal makers are the Detroit Steel Products Company (Fenestra), Detroit, Mich.; David L. Sons Company, Philadelphia, Pa.; American Steel Window Company, Chicago, Ill.; and Truscon Steel Company, Youngstown, Ohio.

**Electroplated Trim.** This product is made by a process which consists of electrically depositing a layer of copper on the outer surface of wooden moldings or doors. The metallic deposit preserves the markings of the grain of the wood and makes a very presentable door. A good sample of this work has been installed in the United Engineering Building, New York City, by the New Central Metal Company of the same city. Some very fine work of this kind has been done by the Hecla Iron Works of New York City, by electroplating fire-proof material known as Lignolith.

**Cement Trim.** Keene's cement has been used for many years for rubber-base-moldings, door and window-trim, etc., and in many European buildings practically all of the interior finish is made of this material. Any molding can be cast in it with good sharp angles, and it is sufficiently hard to stand ordinary wear. Fig. 78 shows a door-opening with a trim of Keene's cement. This detail can be further improved by covering the window frame and door with thin metal. The metal and cement can be painted and colored.

**Molded Hollow Tiles for Interior Finish.** These are also being substituted for the ordinary wooden finish.

**FIG. 78. Door-jamb with Cement Trim.** The Amelia Apartments, erected by the Camp at Akron, Ohio, in 1901,† is almost entirely of hollow tile. "The bases, the picture-moldings, and the architraves around the doors were made of specially formed tiles, as shown in Fig. 79. These tiles were afterward painted to harmonize with the scheme of color-decoration. All of the floors throughout the building are covered with a cement composition composed of Sandusky cement and ground wood, trodden down smooth and level."

**Metallic Furniture and Fittings.** In offices, banks, libraries, and public buildings, the furniture and fixtures are about the only articles on which

\* For the principal regulations, conveniently condensed, see *Fire Prevention and Fire Protection*, by J. K. Freitag.

† Described in the journal, *Fireproof*, July, 1903.

ted, if the building itself is fire-proof, and if these are made of incombustible materials there is no chance for a fire to gain headway or to do much




FIG. 79. Hollow-tile Door-trim, Picture-molding and Base

Almost anything in the way of furniture and fittings, including even desks and highly ornamental cabinets, may now be obtained in metal; libraries, banks, and court-houses have been fitted up and furnished with incombustible cabinet-work. Catalogues can be obtained from the following companies engaged in the manufacture of METAL FURNITURE:—such for example as the Metropolitan Construction Company, New York, N. Y., the Berger Manufacturing Company Canton, Mass., the Van Dorn Iron Works, Cincinnati, Ohio, and the Library of Congress, New York City and Boston.

In a majority of fire-buildings the architects have satisfied themselves with putting on INCOMBUSTIBLE STAIRS of iron, or have slate or marble treads.

FIG. 80. Hollow-tile Steps for Staircase

As pointed out in the first pages of this book unprotected iron cannot be considered fire-proof, but it is difficult to make the ironwork of a stairway, as it is usually built, and at the same time give it an ornamental effect. If exposed metal construction is to be used, cast iron is to be preferred to steel, as the cast metal will retain its shape under heat far better than thin facings or frameworks of steel. Slate and marble treads and platforms, unless supported underneath, should never be used in fire construction. When subjected to heat, marble and slate crack and fall, rendering the stairs impassable. A fire-department captain in New York lost his life through the collapse of a marble platform. If these materials are used, therefore, there should be a sub-tread of iron or concrete beneath. A really FIRE-PROOF STAIRCASE should be constructed with as little

ironwork as possible, and what ironwork there is, incased in FIRE-RESISTANT materials. It is possible and practicable to build stairs of clay tiles, brick reinforced concrete, that are absolutely fire-proof. The stairs in the Peirce Building at Washington, D. C., are built of brick, with the exception of

treads, which are of stone. In many of the earlier government buildings the stairs are of stone. Suitable for a fire, however, are not as resistant as cast iron to heat. Part of the Building Construction and Superintendence contains description and illustration of brick stairs. The Tavino Company built several cases according to a system of construction using flat clay tiles bedded in cement, iron-work whatever used in this construction; hence, eminently fire-proof.

Fig. 81

FIG. 81. Reinforced-concrete Stairs, Government Printing Office, Washington, D. C.

Fig. 80 shows a partial section of a tile staircase such as was used in the Amelia Apartment Building, Akron, Ohio. The blocks were of hard-burned material, 2 ft. and 4 ft. long. They were supported upon the partition-walls and were used by the mechanics for carrying up material during the erection of the building.

FIG. 82. Ferrocement Foundation for Stair-treads and Risers

ing. Reinforced concrete, with slate or marble treads, is a good material for the construction of stairs, and permits of very elaborate and complicated construction. Fig. 81† shows the construction of the stairs in the Government Printing Office.

\* By Frank E. Kidder, rewritten by Thomas Nolan.

† From the Engineering Record, of Dec. 6, 1902.

at Washington, D. C. These stairs have steel girders and strings enclosed solid concrete, which is molded to form the steps and risers, as shown in the

The steel strings, however, are hardly necessary, as the reinforcing-bars sufficient strength. Some excellent details for ornamental iron stairs were published in *Fireproof*, March, 1903, in an article by J. K. Freitag. The cold sheet metal, known as Ferroinclave (page 851), offers a very convenient foundation for cement stairs. When built between walls or partitions with an open string, Fig. 82 shows one way in which the material has been used, the stairs being finished with about 2 in of cement over the metal and finished underneath. The Ferroinclave is bolted to lugs or brackets screwed fast on the strings. Slate or marble treads and risers may be embedded in mortar if desired. (See, also, pages 947 and 983.)

## 9. Protection from Outside Hazard

**Window-Protection.** To be thoroughly protected against the outside, buildings must have the openings in the outside walls provided with some means of effectively closing those openings against flame. The same provision may be made for openings in the partition-walls of large buildings. Four principal types of devices are in use for this purpose: (1) tin-covered wooden shutters; (2) steel shutters or doors; (3) metal frames and sash, glazed with glass; and (4) water-curtains.

**Comparison of Window-Protection Compared.** When properly constructed, a TIN-COVERED WOODEN SHUTTER is still the most effective window-protection. In a very severe fire in Lynn, Mass., in which the heat was intense enough to melt most of the tin from the outside of the tinned plates covering the shutters, it was found afterward that the wood was charred to a depth of only about 1/2 in. The shutters were warped slightly, but afforded sufficient protection to enable the heat to allow men to remain behind them to put out such fire as occasionally crept through. This would not have been possible behind iron shutters under similar conditions.\* STEEL SHUTTERS, under the action of fire, warp very readily and transmit considerable heat. They belong to the second type of window-protection. "There is one objection to the use of shutters on window-openings, and that is that they depend on fallible human action to be effective. They must necessarily be open while the building is burning."

When the need for them comes they are apt to be overlooked and are not always closed.

Certain it is that on many buildings they are not closed at night.† METAL-FRAME-AND-WIRE-GLASS WINDOWS are not as unsightly as shutters, but at any kind are apt to be. They are more likely to be closed at night and are readily closed when necessary. They do not hide a fire and are easily opened when it is necessary to reach a fire. The one serious objection to them is the intense radiation of heat from the wire-glass.†

**Tin-Covered Wooden Fire-Shutters and Doors.** The effectiveness of this device depends on its construction. "Only well-seasoned non-resinous wood, dressed, tongued and grooved in narrow boards, should be used. Wood containing moisture or resin may generate, under heat, sufficient steam or gas to blow off the tin covering and expose the wood to the flame. The body of the shutter should consist of two or three layers of such boards laid at right-angles to each other and fastened together by clinch-nails. The best grade of tin should be used. No solder must be used, and the tin plates should be lock-

\* Insurance Engineering, Dec., 1902.

† For a consideration of water-curtains, see page 903.

jointed, with the nails in the seams. The nails must be long enough, at least  $1\frac{1}{2}$  in, to secure a good hold beyond the depth to which the wood is likely to char, which is about  $\frac{3}{4}$  in. Under intense heat the wood is certain to char, but if the nails are long enough to hold the tin up against the wood, and the shutter is properly put on so as to keep the air out to prevent burning, the shutter will stand under severe strains."\* The hinges, fastenings, or hangers must be bolted to the door, not nailed or screwed, as nails or screws would pull out during a fire. If hung on hinges, the hinge-hook should be built into the wall. This door was designed for use in mills, but it has worked so satisfactorily that it is generally adopted wherever a fire-proof door is wanted and its appearance is not objectionable. Fire-proof shutters, also, are made in this way. The National Board of Fire Underwriters issues complete specifications for this type of door and shutter, and these specifications should be closely followed for satisfactory results. Doors of this type, provided for the opening in interior partition-walls, are often, and wherever possible should be, hung on inclined tracks so that they will close automatically. Where it is desirable to keep them open most of the time, an automatic release operated by a fusible link is provided. (See, also, page 778.)

**Metal-covered Wooden Doors as Fire-Doors.** Wooden doors covered by the KALAMEIN or other process (page 894) are sometimes used as fire-doors where appearance is a consideration. They are not considered equal, however, to the STANDARD TIN-COVERED WOODEN DOORS.

**Steel Fire-Doors and Shutters.** For a satisfactory STEEL FIRE-DOOR a  $\frac{1}{2}$ -in sheet of steel should be used, and it should be reinforced on the back with a frame of angle-irons, not less than  $1\frac{1}{2}$  by  $1\frac{1}{2}$  by  $\frac{1}{4}$  in, and increasing in size with the door or shutter. These doors or shutters may operate in one of three ways: (1) swing on hinges, (2) slide on tracks, or (3) roll vertically. The SWINGING DOORS or shutters are the most reliable as there are no complicated parts to get out of order. They should be hung on eyes built into masonry walls. SLIDING DOORS OR SHUTTERS must have the rails on which they operate protected by metal shields to prevent obstruction. For larger openings the ROLLING SHUTTERS are generally preferred. They are made in horizontal or vertical sectional strips, which wind up on a roller placed in a pocket above the opening, the ends moving in metal grooves to hold them in place. They generally operate VERTICALLY, although some are made to operate HORIZONTALLY, the rollers being set vertically in pockets at the sides of the openings. The latter are more apt to get out of order. The VERTICALLY operated doors and shutters are balanced by springs or weights to make them move easily up and down. Where they are intended to be closed in case of necessity only, they are slightly weighed and held open by means of fusible links, so that in case of fire they will close automatically.

**Sheet-Metal for Fire-resisting Window-Frames and Sashes.†** They are now made weather-tight and perfectly practicable in all respects, and should be used wherever fire-resisting windows are desired. The sashes are made especially for holding wire-glass. These SHEET-METAL WINDOWS are made in a great variety of forms to meet all purposes and the sashes may be stationary or pivoted either horizontally or vertically, hinged, or double-hung with weights like ordinary windows. For factories, warehouses, stairways, and elevators, shafts, a stationary lower and a pivoted upper sash are commonly used, as this is the cheapest type of window. The double-hung windows are now made

\* Insurance Engineering, Dec., 1902.

† To be had for the asking.

‡ See, also, Hollow Metal Window-Frames and Sashes, page 897.



work as smoothly as wooden sashes in ordinary box frames. For offices, etc., a window having two sashes, glazed with wire-glass, and closing locking automatically in case of fire, and a third inner sash glazed with glass, has all of the advantages of an ordinary window with the additional advantages of fire-protection and better diffusion of light. Metal fly-screens, can be used with these windows. All movable sashes, glazed with wire-glass, should be provided with a device by which the sashes will close and lock automatically in case of fire. Two thicknesses of wire-glass are sometimes used with a ventilated air-space of at least 1 in between the lights.

## 10. Extinguishing Devices and Precautionary Measures

**Water-Curtains.** "The vulnerable portion of buildings generally is the front, where great window-openings are desired for purposes of light, and where it is considered objectionable on account of appearance to have shutters or wire-glass windows. These large window-openings afford great opportunities for the spread of fire across streets. The danger of damage is much increased where the fronts, as is very common, are made of unprotected metal. A notable example, illustrating such danger, was the building of the Manhattan Savings Institution, New York City, which was severely damaged and almost destroyed by a fire in a six-story non-fire-proof building across the street. Such conditions might be overcome to some extent perhaps, by the introduction of some system such as the WATER-CURTAINS that were placed on the Chicago Public Library. This is practically a SPRINKLER SYSTEM set along the edge of the cornice of the building, and so arranged as to furnish a thin sheet of water in front of the building. Such a sheet will, however, not extend far before it is turned into spray and thus becomes practically useless. A similar arrangement placed at each window-opening might be more useful, though it is doubtful whether it would be of much value in any severe conflagration."\* The rules of the National Board of Fire Underwriters for OPEN SPRINKLER Water-curtains determine the sizes of piping and feed-mains, and the general arrangement of the system.

**Precautionary Measures in General.**† No matter how thoroughly a building is fireproofed, if it is filled with combustible goods, as a warehouse, store, or factory, there is always the possibility of a fire, which, if unchecked when first discovered, must necessarily entail a great loss and more or less damage to the building. If a fire is discovered and checked in its incipient stage this loss is reduced. There are now many valuable devices for DETECTING and CHECKING fires which should be installed in every warehouse, and which often may be used with advantage in buildings used for other purposes. The more important of these are automatic alarms, automatic sprinklers, and standpipes.

**Automatic Alarms.** The prompt discovery of fire generally brings about prompt extinguishment, but as it is not practicable to have someone on duty in front of a property at all times, fires may gain serious headway before being checked, unless some system of automatic notification is used. Next to automatic sprinklers, approved automatic fire-alarm systems, THERMOSTATS, are perhaps the most important of the fire-protection devices. There are two general types of thermostats: one which operates at a FIXED OR PREDETERMINED TEMPERATURE, and the COMPENSATING-TYPE. The latter requires a certain rise in temperature within a given time. This latter type is common in Europe, while in this country the fixed-temperature-type has been preferred. The compen-

\* Insurance Engineering, Dec., 1902.

† See, also, Chapter XXII, page 768.

sating-types seem to have been used with some success in certain sections, but have not proved altogether satisfactory. For general use it would appear that the **SOLDER-TYPE OF THERMOSTAT** has many advantages when used in connection with a simple **CLOSED-CIRCUIT SYSTEM**. The most common type of thermostat system is the **ELECTRIC SYSTEM**, in which the thermostats are designed to open or close the electric circuit and cause bells to be rung at designated points. These thermostats, or circuit-closers, may be of the fixed-temperature type or adjustable to operate at any desired temperature. The former are chiefly of the **SOLDER-TYPE**, while the most common variety of the latter type consists of a **SPRING OF TWO DISSIMILAR METALS**, which expand unequally.

**The Aero System.** The best-known system of the compensating-type is the **AERO SYSTEM** installed by the Aero Fire Alarm Company, New York City. This consists of a small copper tube attached to the ceiling. A quick rise in temperature, as in the case of fire, expands the air in the tube and acts on a sensitive diaphragm, which latter makes an electrical connection, causing a transmitter to operate and send in an alarm.

**The Reichel System** is installed by the Pacific Fire Extinguisher Company, San Francisco, Cal. This system is of the **COMPENSATING-TYPE**, the **REICHEL THERMOSTATS\*** consisting of a **THERMOPYLE** of special design which is connected in series with an electric circuit. Any rapid increase in heat generates sufficient current to actuate a transmitter. Slow changes in temperature do not operate the system.

**The Derby Automatic Fire-Alarm System** is installed by the American Fire Prevention Bureau, New York City. This system consists of a **TWO-WIRE CLOSED CIRCUIT**, and uses the **DERBY FIRE-SENTINELS,\*** in multiple, across the line. Any derangement of the circuit gives a local or central station trouble alarm. Upon the operation of a **SENTINEL THERMOSTAT**, resistance is automatically cut out of the circuit, thereby causing the operation of fire-gongs and transmitters. The Derby Fire Sentinel can be used on wiring systems utilizing primary, storage, or public-service energy up to 110 volts. The Sentinels are made for attaching to open wiring and also for use in connection with concealed work.

**The Watkins Thermostat** is installed by the Automatic Fire Alarm Company, New York City. It consists of a perforated metal case, enclosing a **SPRING OF TWO DISSIMILAR METALS**. The spring is fastened at one end, and the heat causes a movement, due to the **UNEQUAL EXPANSION OF THE TWO METALS**. **WATKINS THERMOSTATS** are wired in multiple, the wiring system being part open and part closed. The thermostats are adjusted by hand. They are likely to be affected by corrosive influences, moisture, and rough handling. This system, however, has been more largely installed than any other, being the principal type of thermostat used in Boston, New York, and Philadelphia, where, with good supervision, its record has been satisfactory.

**Automatic Sprinklers.** "An **AUTOMATIC SPRINKLER** is a device for distributing water by means of a valve which is arranged to open under the action of heat, as from a fire which it is intended to extinguish. The distribution of water which results from properly located sprinklers occurs in the form of a rain of jets or drops, and is sufficient to drench almost any inflammable structure beyond the point of ignition. The distribution is also economical, as the water is more evenly applied than from a nozzle attached to a fire-hose, and the source is directly above the fire. Whenever combustible merchandise constitutes the contents of a building, **AUTOMATIC SPRINKLERS** are of great value, and in

\* Approved by the Underwriters' Laboratories.

ings of a height so great as to make the upper stories difficult of access, fully if containing large areas and very combustible contents, sprinklers are the best protection obtainable."\* SPRINKLER-SYSTEMS may be divided into two general types: (1) the WET-PIPE SYSTEM, or automatic sprinklers, just described; (2) the DRY-PIPE SYSTEM. Where the water cannot be kept from flowing in the ordinary wet-pipe system, recourse is had to the dry-pipe system. Sprinkler-pipes are filled with air under pressure, which is automatically released by the opening of a HEAD-VALVE under heat. This release of pressure opens the DRY VALVE in the main supply-pipe, allowing water to flow through sprinkler-pipes and the open heads. Automatic sprinkler-heads are made to open at various temperatures: ordinary, 155° to 165°; intermediate, 200°; hard, 286°; and extra hard, 360° F. The higher-temperature sprinklers are used in locations where the heat is above normal, such as boiler-rooms and engine-rooms. Various types, made by the following manufacturers, have been approved by the National Board of Fire Underwriters:† International Sprinkler Company, New York City; General Fire Extinguisher Company, Providence, R. I.; Automatic Sprinkler Company of America, New York City; F. W. Fisher Brothers, St. Louis, Mo.; Esty Sprinkler Company (H. G. Vogel Company, New York, sole agents); Globe Automatic Sprinkler Company, Philadelphia, Pa.; Independent Aetna Sprinkler Co., Philadelphia, Pa.; Ohio Automatic Sprinkler Company, Youngstown, Ohio; and Rockwood Sprinkler Company, Worcester, Mass.

**Sprinkler Supervisory Devices.** These devices consist of apparatus for TRANSMITTING SIGNALS when gate-valves are closed or open; when water in tanks falls below or is restored to a predetermined level; when pressure in tanks falls below or is restored to a predetermined amount; when water temperature falls below or rises above predetermined temperatures; also to transmit flow signals and to withhold signals from water-surges or variable pressure. They are used in connection with CENTRAL-STATION SIGNALLING SYSTEMS for supervising the operation and maintenance of sprinkler-equipment. The devices of the American District Telegraph Company of New York City, are approved by the National Board of Fire Underwriters.†

**Stand-Pipes and Hose-Reels.** In office-buildings, hotels, and apartment-houses, where sprinkler-systems are hardly suitable, STAND-PIPES with HOSE-REELS in each story and on the roof, ready for instant use, constitute the best means of quickly controlling a fire. All buildings over certain heights should be so equipped, the height being fixed by the ability of the local fire department to reach effectively the upper parts of the building with its hose-streams. The stand-pipe should be from 2½ to 6 in in diameter, according to the size and height of the building, and should be connected with the water-supply of the city and provided with Siamese connections at the street-level for the fire department. Check-valves should be provided, so that when the fire-department engines are attached, their force will be added to the force due to the head of water from the fire-tanks, or to the fire-pumps, or to the force of the city water system. Stand-pipes should be placed within the stair-enclosures. In cities where the practise is to attach them to the outside fire-escapes of the building. The number and location of stand-pipes should be such that all parts of the building can be reached by at least one stream supplied by hose not longer than 100 ft in length.

\* J. K. Freitag.

† List of Fire Appliances, National Board of Fire Underwriters.

## CHAPTER XXIV

# REINFORCED-CONCRETE CONSTRUCTION \*

By

RUDOLPH P. MILLER

SUPERINTENDENT OF BUILDINGS, BOROUGH OF MANHATTAN, NEW YORK CITY

### 1. Introductory Notes

**Definition.** The term **REINFORCED CONCRETE** is defined in the proposed standard regulations of the American Concrete Institute as "an approved mixture of Portland cement, with water and aggregates in which metal (generally steel) has been embedded in proportionately small sections, in such a manner that the metal and the concrete assist each other in taking stress."†

**Historical Notes.** The great value of concrete as a structural material when subjected to compression only has been recognized for centuries. The use of reinforced concrete, however, as a practicable and commercial form of construction is comparatively recent. It is true that as far back as 1869, François Coignet of Paris took out letters patent on a combination of iron and concrete and that even before this, in 1867, the principle of reinforcing concrete with iron had been applied by P. A. J. Monier, a gardener of Paris, to the making of large flower-pots; still, the general application to building-construction did not occur till about the middle of the last decade of the nineteenth century. In its development it was first applied to bridge-construction. The discussion of the subject in this chapter is confined to its use in the construction of buildings. The earliest example of a building of reinforced concrete in this country, and probably in the world, is that erected in 1875 by W. E. Ward, near Port Chester, N. Y. in which "not only all the external and internal walls, cornices, and towers were constructed of concrete, but all of the beams and roofs were exclusively made of concrete reinforced by light iron beams and rods."‡

**The Erection of Reinforced-Concrete Work.** In general outline, a building operation in reinforced concrete consists in the usual preparations of the site by excavation or otherwise, the provision of suitable foundations for walls, columns, or other supports, the erection of a series of wooden molds or forms, the placing of the necessary steel reinforcement, the pouring of the concrete, and the removal of the forms after the concrete has set sufficiently to sustain itself and the load that may come on it during construction. From the beginning of the erection of the forms the successive steps are progressive, that is, the placing of the steel and pouring of the concrete are going on in the lower sections or stories while the forms are being erected for the upper sections or stories. So that in a large operation the carpenters, the steel-setters, and the concreters may all be working at the same time, one set slightly in advance of the others, without interference one with the others. These several steps in the operation

\* For Concrete in general and Mass-Concrete, see Chapter III, pages 240 to 251; for Strength of Concrete without Reinforcement, Chapter V, pages 283 to 287; and for Reinforced-Concrete Factory-Construction, Chapter XXV. See, also, Chapter XXIII, pages 817 and 842.

† Proc. Am. Concrete Inst., Vol. XV, 1919.

‡ For a further and more extended history the reader is referred to the larger treatises on this subject and to Edwin Thacher's article in Engineering News, March 26, 1903.

considered in greater detail in Chapter-Subdivision 7, page 962, Erection of Reinforced-Concrete Construction.

## 2. Materials Used in Reinforced-Concrete Construction

Materials used in reinforced concrete are CONCRETE and STEEL. The concrete forms the mass of the construction. Its proper use is to resist compression. While it has some tensile strength the amount is so small and so variable that it should always be neglected. STEEL is used for the reinforcing material as it furnishes the greatest amount of strength at the least expense. CAST IRON could be used, but it is practically unobtainable under present conditions, and, as already intimated, its use is not economical.

**Concrete.** The CONCRETE consists of a mixture of cement and some aggregate in definite proportions, with the necessary water to cause the setting of the concrete.

**Portland Cement.** PORTLAND CEMENT should always be used in reinforced concrete, and should always be tested before being used. Even in small jobs it is important to know that the cement is strong and sound. In purchasing the cement, a certificate of some reliable testing-laboratory should be made one of the conditions of acceptance. Under all circumstances, it is always best to have testing done at some well-established and properly equipped cement-testing laboratory. The results of tests in temporary laboratories are often abnormal and may lead to unnecessary controversies with the manufacturers. To be reliable, a cement should meet the following requirements as called for in the following specifications.\*

**Specific Gravity.** The specific gravity of the cement should be not less than 3.10.

**Residue.** It should leave by weight a residue of not more than 22% on a No. 20 sieve.

**Time of Setting.** It should develop initial set in not less than 45 or 60 minutes according as the Vicat or Gillmore needle is used, but must develop final set in 10 hours.

**Tensile Strength.** The minimum requirements for tensile strength for cylinders of 1-in-square section should be as follows, and should show no retrogression in strength within the periods specified:

### NEAT CEMENT

Tests (1 day in moist air, 27 days in water)..... 600 lb per sq in

### ONE PART CEMENT, THREE PARTS STANDARD OTTAWA SAND

Tests (1 day in moist air, 5 days in water)..... 200 lb per sq in

Tests (1 day in moist air, 27 days in water)..... 300 lb per sq in

**Swelling and Shrinkage.** Pats of neat cement about 3 in in diameter, 1/2 in thick in the center, and tapering to a thin edge, should be kept in moist air for a minimum of 24 hours. The pat is then exposed in an atmosphere of steam, 1 in above the water, in a loosely closed vessel, for 5 hours.

The pats, to satisfactorily pass the requirements, should remain firm and show no signs of distortion, checking, cracking, or disintegration.

For the complete standard specifications see the latest Year Book of the Am. Soc. of Test. Mats. See, also, Chapter III, page 237, for the principal clauses of the last Specifications for Portland Cement, adopted in 1916, and effective January 1, 1917, by the Am. Soc. for Test. Mats. The tensile strengths for neat cement are given in the following table.

**SULPHURIC ACID AND MAGNESIA.** The cement should not contain more than 2% of anhydrous sulphuric acid ( $\text{SO}_3$ ) nor more than 5% of magnesia ( $\text{MgO}$ ). The test for **CONSTANCY OF VOLUME OR SOUNDNESS** is of particular importance for reinforced-concrete work. When used in large masses an occasional batch of concrete made with unsound cement may not seriously affect the final result, but in reinforced-concrete building operations, where the different members of the structures are comparatively small, the safety of the entire building may be jeopardized by the use of a small amount of unsound cement in some important part, such as a column.

**Aggregate.\*** By the term **AGGREGATE** is understood the materials, including the sand, mixed with the cement to make the concrete. In practically all cases the sand is a necessary element.

**Sand.** "The **SAND** should be clean. One may obtain some idea of its cleanliness by placing it in the palm of one hand and rubbing it with the fingers of the other. If the sand is dirty, it will discolor the palm. Unless from a bank of known quality, a sand should be tested for tensile strength of mortar, before using. Preference should be given to sand containing a mixture of coarse and fine grains. Extremely fine sand even if clean makes a weak mortar and should never be used unless with a large excess of cement."† Mortars composed of one part Portland cement and three parts fine aggregate or sand, by weight, should show a tensile strength of at least 70% of the strength of 1 : 3 mortar of the same consistency and of the same cement mixed with standard Ottawa sand. New York Regulations specify that fine aggregate shall consist of sand, crushed stone, or gravel screenings, passing when dry, a screen having  $\frac{3}{4}$ -in. diam. holes, and passing not more than 6% through a sieve having 100 meshes per linear inch. The Chicago Regulations specify that not less than 45% shall be retained on a screen of 400 meshes to the square inch. (See, also, page 241.)

**Coarse Aggregate.** For the **COARSER MATERIAL OF THE AGGREGATE** many materials are used and many others have been suggested. Its selection is generally dependent upon local conditions. If possible, gravel or crushed stone should be used. Whatever is used should be a clean, hard substance that will secure to the concrete the necessary strength; that is, the crushing strength of this material should be equal to or greater than that of the mortar used, at least at the age of 28 days. In any case, where no reliable information is to be had on the strength of a concrete made from a given aggregate, careful investigation should be made before such material is used. (See, also, page 241.)

**Gravel.** **GRAVEL**, like sand, should be clean. If dirty it should be washed before being used. To get the most satisfactory or uniform results, gravel should be screened and graded and then mixed in definite proportions, as **RUN OF THE BANK** will generally not give uniform results. (See, also, page 241.)

**Stone.** The most satisfactory stone that can be used is **TRAP-ROCK** (under which term are included most of the rocks of igneous origin), because of its toughness and great compressive strength. The **GRANITES**, as they are commercially known, are considered by some equal in quality to trap-rock for the making of concrete. The presence of mica in considerable proportion in some of the so-called granites would seem to make them unsuitable. **LIMESTONE**

\* See, also, Chapter III, pages 240 to 251. The data there on Aggregates, Proportioning Materials, etc., relate more particularly to mass-concrete, while the data in Chapter XXIV is intended to cover, more in detail, reinforced concrete.

† Treatise on Concrete, Plain and Reinforced, Taylor and Thompson, third edition, 1916, page 12.

soft varieties are excepted, make excellent concrete as far as strength is concerned. They would, however, seem to affect the fire-proof character of concrete. (See Tables on page 956.) The harder and more compact stones, also, may be used successfully, but great care must be exercised in selection. CONGLOMERATE, which is in reality a hard, coarse sandstone, give very satisfactory results. On account of their low crushing strength, or SHALE should not be used in concrete. Besides the stones thus far mentioned, broken BRICK, TERRA-COTTA, FURNACE-CLINKER and FURNACE-SLAG have been suggested. In the selection of broken brick or terra-cotta, care must be taken to get hard-burned material. The crushing strength of such material well selected, is a little more than that of acceptable concrete, 28 days. But ordinarily, commercial brick or terra-cotta will not meet the requirements for a good aggregate, and these materials should be used only as a last resort and then only after careful investigation. (See, also, page 241.)

**Cinders.** FURNACE-CLINKERS should be clean and entirely free from concretion matter. CINDERS are often used where fireproofing is the primary consideration, and no doubt good constructions may be obtained, with extreme economy by the use of clinker or cinder concrete, especially if the material is ground, washed and graded as suggested for gravel. But in general practice the concrete is not uniform in quality and is unreliable in strength. It is therefore not recommended in this chapter. In Chapter XXIII, Fireproofing of Buildings, its use is discussed on pages 817 and 818. (See, also, page 242.)

**Size of Aggregate.** The SIZE OF THE AGGREGATE may vary from  $\frac{1}{4}$  to  $2\frac{1}{2}$  inches in largest diametrical dimension, depending on the particular purpose for which it is to be used. Where the mass of concrete is comparatively large the size may run as high as 3 inches in size. This may sometimes be the case in foundations and in large piers and thick walls. In columns, girders, beams and slabs, very unsatisfactory results would be obtained if so large a stone were used. For such work no stone or other aggregate should be used larger than will pass a 1-in screen. In important girders and columns, especially when the concrete of viscous consistency is produced "which will pass readily around and easily surround the reinforcement and fill all parts of the forms." \* **MAXIMUM SIZES** allowed for the aggregate in reinforced concrete in the different cities are as follows: St. Louis and Buffalo, stone that will pass a  $\frac{3}{4}$ -in ring, "three-quarter-inch stone"; New York, Cleveland and Philadelphia, stone that will pass a 1-in ring; Chicago, stone passing 1-in-square mesh; San Francisco, for floors and fireproofing, 1-in stone, for foundations, 2-in stone. (See, also, page 241.)

**Water.** "The WATER used in mixing concrete should be free from oil, acid, or organic matter." \*

**Proportions of the Materials.** The proper PROPORTION OF THE MATERIALS to be used in concrete is dependent upon the size and character of the material. In cities in which there are regulations governing reinforced-concrete construction, the mixture to be used is generally specified. In the absence of other regulations the most satisfactory and reliable mixture is, one part of Portland cement, two parts of sand and four parts of stone or gravel. It is the mixture that has been used in most of the experimental work on reinforced concrete, and is therefore much trustworthy information to be had concerning it. In the case of large or important operations, however, great economy can often

be effected by a preliminary study of the materials to be used and of the proper proportions. In general, for given materials, the most economical mixture is also the strongest. The old method of determining the proportions of concrete by measuring the voids in the coarser particles by means of water poured into a box containing 1 cu ft of the material and then providing the quantity of finer material, assuming the cement the same as sand, is not to be recommended. It does not give accurate or satisfactory results. A better method is to take the materials to be used and make trial-mixtures by varying the proportions, always using, however, the same amount of cement and water. These trial-mixtures are placed successively in a measuring vessel of fixed capacity and tamped, and the height to which the vessel is filled for each mixture is noted. The proportions that give the lowest height, or result in the smallest volume, will give the most satisfactory concrete. (See, also, page 242 and following pages.)

The best and most scientific method, however, is that known as the MECHANICAL ANALYSIS, devised by W. B. Fuller. In this method the available materials, including the cement, are separated into the various sizes by means of a series of sieves; curves are plotted which indicate the percentages of the whole mixture which pass the several sieves; and from a study of these curves the proportions of the different aggregates are determined. For a detailed description of this method the reader is referred to the chapter on Proportioning Concrete in the 1912 edition of the Treatise on Concrete, Plain and Reinforced, by Taylor and Thompson. As an example of the saving possible, the following case, given in the work just referred to, will be of interest.

"The ordinary mixture for water-tight concrete is about 1 : 2 : 4, which requires 1.57 barrels of cement per cubic yard of concrete. By carefully grading the materials by methods of mechanical analysis the writer has obtained water-tight work with a mixture of about 1 : 3 : 7, thus using only 1.01 barrel of cement per cubic yard of concrete. This saving of 0.56 barrel is equivalent with Portland cement at \$1.60 per barrel, to \$0.89 per cu yd of concrete. The added cost of labor for proportioning and mixing the concrete, because of the use of five grades of aggregate instead of two, was about \$0.15 per cu yd, thus effecting a net saving \$0.74 per cu yd. On a piece of work involving, say, 20 000 cu yd of concrete, such a saving would amount to \$14 800, an amount well worth considerable study and effort on the part of those in responsible charge."

In the ordinances or regulations governing reinforced concrete of various cities the proportions to be used are generally prescribed. In New York, "concrete for reinforced-concrete structures shall consist of a wet mixture of one part of Portland cement to not more than six parts of aggregate, fine and coarse, either in the proportion of one part of cement, two parts of fine aggregate and four parts of coarse aggregate, or in such proportion that the resistance of the concrete to crushing shall not be less than 2 000 lb per sq in after hardening 28 days." In Chicago, various grades of concrete are specified with the ultimate compressive resistance, to be developed, from a mixture of 1 : 1 : 2 to an ultimate strength of 2 900 lb per sq in, to a 1 : 3 : 7 mixture with a strength of 1 500 lb per sq in. In Buffalo and San Francisco the proportion is given as one of cement to six of aggregate; in Boston it is one of cement to five of aggregate.

**Compressive Strength of Reinforced Concrete.** For reinforced-concrete work no mixture should be used that does not develop a COMPRESSIVE STRENGTH of at least 2 000 lb per sq in at the age of 28 days. The compressive strength of various concretes is shown in the following table:



Table I. Compressive Strength of Portland-Cement Concrete of Different Proportions

Proportions			Age, months	Compressive strength per sq in	Authority
Portl.	Sand	Stone			
1	0	0	4	4 370	James E. Howard, Tests, Watertown Arsenal
2	0	0	4	2 506	
3	0	0	4	1 812	
4	0	0	4	830	
5	0	0	4	532	
6	0	0	4	169	
7	0	0	4	118	
2	4	0	4	2 178	
3	6	0	4	1 815	
4	8	0	4	1 135	
5	10	0	4	707	
6	12	0	4	738	
2	2	4	4	1 768	
2	3	4	4	1 911	
2	4	4	4	2 147	
2	5	4	4	2 452	
2	6	4	4	2 124	
2	7	4	4	1 650	
2	8	4	4	1 295	
2	4	1	1	2 399	G. A. Kimball, Tests of Metals, U. S. A. Taylor and Thompson, Tests, Watertown Arsenal Watertown Arsenal, Tests of Metals, U. S. A.
2½	5	1	1	3 255	
3	5	1	1	2 042	

**Working Stresses for Reinforced Concrete.** Some formulas for the design of reinforced-concrete construction provide for the use of the **ULTIMATE STRESS** of the concrete and the application of a **FACTOR OF SAFETY**. This is not to be recommended as it necessitates either the test of the concrete or the assumption of an ultimate strength. While it is undoubtedly desirable that the concrete should be tested, this is generally impracticable when the building is being designed. It should be done during construction and is the best work, to make sure that the concrete is up to the requirements. Various factors of safety from two and one half to ten have been proposed. Different factors of safety are used for different members of a structure under different conditions. This is another reason why it would be better to use **WORKING STRESSES** than **ULTIMATE STRESSES**. The following **WORKING STRESSES** are recommended for reinforced concrete that will develop a **CRUSHING STRENGTH** of **3 000 lb per sq in** in 28 days:

Concrete fiber-stress in compression.....	650 lb per sq in
Concrete shear-stress.....	40 lb per sq in
Concrete shearing-stress when all diagonal tension is resisted by the steel, and the steel-resistance to both positive and negative moments is fully developed....	150 lb per sq in
Concrete compression between concrete and plain reinforcing-bars.....	500 lb per sq in
Concrete compression between concrete and suitable deformed bars.....	80 lb per sq in
Concrete compression between concrete and suitable deformed bars.....	100 lb per sq in

These give the stresses allowed by various building ordinances.

Table II. Working-Stresses for Reinforced-Concrete Construction

Authority	Extreme fiber-stress, concrete in compression, lb per sq in	Direct compression in concrete, lb per sq in	Shearing- stress in concrete, lb per sq in	Shearing- stress in concrete when all diagonal tension is resisted by steel, lb per sq in	Adhesion of steel to concrete, lb per sq in	Tensile stress in steel, lb per sq in	Tensile stress in steel to resist diagonal tension, lb per sq in	Ratio of modulus of elasticity of steel to that of concrete
New York, 1915...	650	500	40	150	80	16 000	16 000	$\left\{ \begin{array}{l} 15 \text{ (girders)}^a \\ 12 \text{ (columns)}^a \end{array} \right.$
Chicago, 1917.....	35% ult.*	$\frac{1}{2}$ ult.*	.....	$\frac{1}{2}$ ult.*	70 to 100	$\left\{ \begin{array}{l} \frac{1}{2} \text{ E. L.}^\dagger \\ \text{\< 18 000} \end{array} \right.$	$\left\{ \begin{array}{l} \text{shearing-} \\ \text{stress} \\ 12 000 \end{array} \right.$	10 to 20 c
Philadelphia, 1918.	650	500	40	120	80 and 100	16 000	.....	12 b
Boston, 1916.....	500	$\left\{ \begin{array}{l} 416^a \\ 347 \text{ min.}^d \end{array} \right.$	60	.....	60	16 000	.....	$\left\{ \begin{array}{l} 15 \text{ (girders)} \\ 10 \text{ (columns)} \end{array} \right.$
Cleveland, 1918....	700	500	40	125	50 to 100	16 000	10 000	15
Baltimore, 1908....	500	400	50	.....	.....	15 000	.....	15
Detroit.....	650	450	40	.....	80 to 100	$\left\{ \begin{array}{l} 45\% \text{ E. L.}^\dagger \\ \text{\< 16 000} \end{array} \right.$	.....	$\left\{ \begin{array}{l} 15^a \\ 12^b \end{array} \right.$
Buffalo.....	650	500	40	120	80 to 100	16 000	.....	$\left\{ \begin{array}{l} 15^a \\ 12^b \end{array} \right.$
San Francisco, 1912	$\left\{ \begin{array}{l} \text{\< 500} \\ \frac{1}{4} \text{ ult.}^* \end{array} \right.$	$\left\{ \begin{array}{l} \text{\< 500} \\ \frac{1}{2} \text{ ult.}^* \end{array} \right.$	75	.....	60 to 100	$\left\{ \begin{array}{l} 20 000 \\ \frac{1}{2} \text{ E. L.} \end{array} \right.$	.....	15

\* Ultimate strength. † Elastic limit. The symbol < indicates "equal to or less than."

a. 1 : 2 : 4 mixture; b. 1 : 1  $\frac{1}{2}$  : 3 mixture; c. according to mixture; d. in piers and columns.

**el Reinforcement.** The function of the steel reinforcement is to take up longitudinal and diagonal tensile stresses and in some cases, as in columns and beams reinforced at the top, to give additional compressive strength.

**d or High Steel.** Two grades of steel are used for the reinforcement, **MILD STEEL** and **HIGH-CARBON STEEL**. **MILD OR MEDIUM STEEL** is used for all usual shapes and is the ordinary **MERCHANT-STEEL**. It has an ultimate strength of from 60 000 to 70 000 lb per sq in, and its elastic limit is about half the ultimate strength. **HIGH-CARBON STEEL** has a greater percentage of carbon and is therefore more brittle. Its ultimate strength is about 105 000 lb per sq in and its elastic limit about 55 000 lb per sq in. The use of **HIGH-CARBON STEEL** permits greater stresses in the reinforcement, and consequently a less quantity of steel and a greater economy in construction. On account of its greater brittleness, however, it is liable to sudden failures under stress. It is also often found to be cracked or broken when sent to the work, and unless it is very carefully inspected there is great liability of defective material getting into the work. Furthermore, much of the so-called **HIGH-CARBON STEEL** has been found in practice, after testing, to fall far short of the specifications. Its use is therefore to be avoided, unless special care is taken to secure an absolutely reliable article and to have it inspected and tested. For large, important work inspection would be desirable. Ordinarily, however, mild steel should be used, as commonly it is manufactured and sold under such standard conditions that it is reliable. As the modulus of elasticity of high-carbon steel is practically the same as that of medium steel, the deformation under any given loading is the same. There is no special advantage in the use of one over the other. Steel meeting the specifications of the American Society for testing materials\* for reinforcing is recommended. See Table III. The phosphorus in the steel should not exceed 0.10% for Bessemer steel nor 0.05% for open-hearth steel. For slab and beam-reinforcement where wire or small rods are suitable, steel manufactured from Bessemer billets may be used with a **TENSILE STRENGTH** of 105 000, **YIELD-POINT** of not less than 52 500 lb per sq in.

**Working Stresses for Steel.** The generally accepted **WORKING STRESS** for mild steel is 16 000 lb per sq in in tension. Tests have shown that in cases of the failure of reinforced-concrete beams is due to the failure of the reinforcement, the stress in the metal had not more than reached the **YIELD-POINT**. The **YIELD-POINT** is somewhat lower than the **ELASTIC LIMIT**. The working stress in steel, therefore, should be a fixed proportion of the yield-point or the elastic limit. It is held by some that this ratio should not be as high as one to two, but is nearly one to three, reducing the working stress in mild steel as given to 10 000 or 12 000 lb per sq in. In using high-carbon steel they would use a similar ratio of the elastic limit, whatever that may be, according to which ordinarily 20 000 lb per sq in is taken as the working stress for high-carbon steel. Allowable **WORKING STRESSES** in steel reinforcement in various cities are given in Table II, page 912.

**Reinforcement Members.** Reinforcement is used in a variety of shapes and combinations, nearly all of them patented and some of them forming the basis for **REINFORCEMENT SYSTEMS**. Where the reinforcement is employed to take up tension, as in a beam or girder, the **BOND** between the concrete and the steel is relied upon to support the **TENSIONAL STRESSES** in the steel. The plain bars depend entirely upon the **ADHESION** of the steel and the concrete for the action of the two materials in combination, or the full tensile strength of the rod is developed by anchoring the rods into the concrete at the ends, in which case the beam becomes more

\* American Society for Testing Materials Standards, 1918.

Manufacture	Billet-steel, Bessemer or open-hearth, rolled from new billets only										Rail-steel, rolled from standard tee rails	
Kind of bar	Plain			Deformed			Cold-twisted	Plain	Deformed and hot-twisted			
	Structural	Inter-mediate	Hard	Structural	Inter-mediate	Hard						
Grade	55 000 to 70 000	70 000 to 85 000	80 000 or more	55 000 to 70 000	70 000 to 85 000	80 000 or more	.....	80 000	80 000			
	33 000	40 000	50 000	33 000	40 000	50 000	55 000	50 000	50 000			
Tensile strength, pounds per square inch.....	1 400 000 tens. str.	1 300 000 tens. str.	1 200 000 tens. str.	1 250 000 tens. str.	1 125 000 tens. str.	1 000 000 tens. str.	5	1 200 000 tens. str.	1 000 000 tens. str.			
Yield-point, minimum, pounds per square inch.	180° d = l	180° d = 2l	180° d = 3l	180° d = l	180° d = 3l	180° d = 4l	180° d = 2l	180° d = 3l	180° d = 4l			
Elongation, minimum, in 8 in, per cent.....	180° d = l	90° d = 2l	90° d = 3l	180° d = 2l	90° d = 3l	90° d = 4l	180° d = 3l	90° d = 3l	90° d = 4l			
Cold-bending test around a pin, without fracture, under 1/4 in.....	180° d = l	180° d = 2l	180° d = 3l	180° d = 2l	90° d = 3l	90° d = 4l	180° d = 3l	90° d = 3l	90° d = 4l			
1/4 in and over.....	180° d = l	180° d = 2l	180° d = 3l	180° d = 2l	90° d = 3l	90° d = 4l	180° d = 3l	90° d = 3l	90° d = 4l			

NOTE.  $d$  is the diameter of the pin;  $l$  is the thickness or diameter of the bar.

ious to a trussed beam with the rod as the tension-member. In cross-a, plain bars are usually round or square, though sometimes flat bars, , tees, or other shapes are used. In regard to the use of square bars and other shapes, it is contended that the edges start initial cracks in the con- as it shrinks in setting. Twisted flat bars, when placed too near the sur- the concrete, cause a spelling or breaking out of the concrete from between revolutions, when the steel is under stress.

mercial Sizes. As a result of the shortage of steel during and since the war, the larger producers of reinforcing-bars have agreed to eliminate of the commercial sizes of bars formerly in use and are now limiting their of bars to the following sizes:

Area	Equivalent to	Area	Equivalent to
0.110 sq in	3⁄8-in round	0.601 sq in	7⁄8-in round
0.196 sq in	1⁄2-in round	0.785 sq in	1-in round
0.250 sq in	3⁄4-in square	1.000 sq in	1-in square
0.307 sq in	5⁄8-in round	1.266 sq in	1 1⁄8-in square
0.442 sq in	3⁄4-in round	1.563 sq in	1 1⁄4-in square

ty in obtaining reinforcement will be avoided to a great extent by the these sizes in designing reinforced concrete.

rmmed Bars. With the DEFORMED BARS the adhesion of the concrete to el is supplemented by a MECHANICAL BOND due to the shape of the bar. lowing deformed bars have been and are at present widely used.

Ransome Bar. The Ransome Twisted Bars (Fig. 1) are made of square Bars should be "twisted cold with one complete twist in a length of not



Fig. 1. The Ransome Twisted Bar

five times the thickness of the bar."\* The work on the bars in the twist- ess increases the elastic limit and the tensile strength; but the amount crease is not fixed, as variations in the grade of rolled steel may result, isting, in still wider variations. The users of this bar generally assume a stress of 20 000 lb per sq in. The patent on this bar has expired and it e be used by anyone. Strictly speaking, this is not a deformed bar. rs can be obtained in all sizes, varying by 1⁄8 in from 3⁄8 to 1 1⁄4 in. Larger o, can be obtained on special order.




Fig. 2. The Buffalo Deformed Bar

uffalo Deformed Bar. The Buffalo Steel Company of Tonawanda, akes a square bar with rounded edges, thus eliminating the sharp cor- an Society for Testing Materials Standards, 1918, pages 149 and 152.

ners. The deformations consist of raised stars along the sides of the bar, as shown in Fig. 2. It is made in sizes of from  $\frac{3}{8}$  to  $1\frac{1}{4}$ -in diameter, and the cross-sectional areas are equal to the areas of equivalent squares. The bars are

rolled from old railroad rail and comply with the Standard Specifications of the American Society for Testing Material for reinforcing-steel of this kind. The steel is a high carbon steel with a tensile strength of 80 000 lb per sq in.

**Corrugated Bars.** Corrugated bars (Fig. 3), both square and round in cross section, are made by the Corrugated Bar Company, Inc.,

Buffalo, N. Y., of both medium and high-elastic-limit steel with a yield-point of about 50 000 lb per sq in. Corr-Bars are furnished either straight and cut to length, or bent ready for the forms. The standard sizes are as follows:

CORRUGATED ROUNDS

Size in inches	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	$1\frac{1}{8}$	$1\frac{1}{4}$
Net area in square inches.....	0.11	0.19	0.25	0.30	0.44	0.60	0.78	0.99
Weight per foot in pounds.....	0.38	0.66	0.86	1.05	1.52	2.06	2.69	3.41

CORRUGATED SQUARES

Size in inches	$\frac{1}{4}$	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	$1\frac{1}{8}$	$1\frac{1}{4}$
Net area in square inches.....	0.06	0.14	0.25	0.39	0.56	0.76	1.00	1.26	1.53
Weight per foot in pounds.....	0.22	0.49	0.86	1.35	1.94	2.64	3.43	4.34	5.30




Fig. 4. The Havermeier Bar, Square and Round

**e Havermeyer Bar.** The Havermeyer Bar (Fig. 4), controlled by the  
rte Steel Company, New York City, consists of square and round bars  
with a series of gradual projections and depressions on all sides, the defor-  
ns being so designed that there is a constant cross-sectional area. They  
mished in the following sizes and weights:

in inches	Square bars		Round bars	
	Area in square inches	Weight per foot in pounds	Area in square inches	Weight per foot in pounds
¼	0.0625	0.212	0.0491	0.167
⅜	0.1406	0.478	0.1104	0.375
½	0.2500	0.850	0.1963	0.667
⅝	0.3906	1.328	0.3068	1.043
¾	0.5625	1.913	0.4418	1.502
7⁄8	0.7656	2.603	0.6013	2.044
1	1.0000	3.400	0.7854	2.670
1 ¼	1.2656	4.303	0.9940	3.379
1 ½	1.5625	5.312	1.2272	4.173
1 ¾	1.8906	6.428	.....	.....
1 ½	2.2500	7.650	.....	.....

ation of 5% under and 2½% over the above weights is required for rolling.

company also rolls a flat bar with similar deformations on the wide faces.  
m is recommended where bars must be bent in curves, as in silos, sewers,  
a running them through a tire-machine to bend them, the edges of the  
event the lugs from being damaged.

**Diamond Bar.** The Diamond Bar (Fig. 5), put on the market by the  
e Steel Engineering Company, New York, is a bar of absolutely uniform




Fig. 5. The Diamond Bar

There is consequently no waste of metal due to the deformations.  
is practically a round bar, and as sudden transitions from one section to




Fig. 6. The Rib-bar

are avoided, all tendency to cause initial cracks in the concrete is over-  
he weights and areas of Diamond bars are equal to those of plain square  
like denominations. Bars from ¼ to 1 ¼ in in diameter may be ob-

**The Rib-Bar.** The Rib-Bar (Fig. 6) manufactured by the Truscon Steel Company, Youngstown, Ohio, is a rolled bar with a series of cross-ribs. These bars are made with rectangular or round section and are furnished in sizes from  $\frac{3}{8}$  to  $1\frac{1}{4}$  in, the areas of the cross-sections being equivalent to squares of equal denominations; but the weights are slightly greater, and are as follows:

Size, in	Square bars		Round bars	
	Area, sq in	Weight per linear foot, lb	Area, sq in	Weight per linear foot, lb
$\frac{3}{8}$	0.1406	0.48	0.1104	0.379
$\frac{1}{2}$	0.2500	0.86	0.1963	0.674
$\frac{5}{8}$	0.3906	1.35	0.3068	1.054
$\frac{3}{4}$	0.5625	1.95	0.4418	1.517
$\frac{7}{8}$	0.7656	2.65	0.6013	2.065
1	1.0000	3.46	0.7854	2.697
$1\frac{1}{8}$	1.2656	4.38	0.9940	3.414
$1\frac{1}{4}$	1.5625	5.41	.....	.....

**Kalman Grip-Bars.** These bars are similar in general design to the Rib Bars, differing from them by having the ribs running entirely around the bar instead of half-way. They are kept in stock in both round and square sections of standard sizes and weights, by the Paul J. Kalman Company, of Chicago, Ill.




Fig. 7. The Ovoid Bar

**The Ovoid Bar.** The Gabriel Reinforcement Company, located at Detroit, Mich., furnishes the Ovoid Bar (Fig. 7), in sizes and areas as follows:

Size in inches	$\frac{3}{8}$	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	$1\frac{1}{8}$
Area in square inches...	0.1406	0.250	0.3906	0.5625	0.7656	1.000	1.265
Weight in pounds.....	0.4940	0.873	1.3560	1.9470	2.6430	3.446	4.354

**The Monotype Bar.** These bars are cruciform in section, and have, at intervals, ribs connecting the stems. (Fig. 8.) The cross-sectional areas are




Fig. 8. The Monotype Bar

equivalent to those of standard round and square bars. They can be secured from the Edward A. Tucker Company, Boston, Mass.



**Grip-Bars.** These bars are rolled in sections equivalent to standard bars. The cross-section is especially designed so that shear-members




Fig. 9. The Rivet Grip-bar

ridly attached, as shown in Fig. 9, thus securing such advantages as are r them. They are handled by the Concrete Reinforcing and Engineer- any, Cleveland, Ohio.

Rivet grip- bars, size	Area, sq in	Perimeter, in	Weight, per foot, lb
$\frac{3}{8}$ in	0.1406	1.63	0.478
$\frac{1}{2}$ in	0.3906	4.00	1.328
$\frac{5}{8}$ in	0.5625	4.25	1.913
$\frac{3}{4}$ in	0.7656	4.75	2.603
1 in	1.0000	5.19	3.400
1 $\frac{1}{8}$ in	1.2656	5.75	4.303
1 $\frac{1}{4}$ in	1.5625	6.50	5.313

**Mesh and Expanded Metal.** Other types of tension-reinforcement, RE-MESH FABRIC and EXPANDED METAL in various forms, have been n Chapter XXIII, Fireproofing of Buildings. Wire fabric has come general use as a slab-reinforcement, as it resists temperature-cracks icking of the concrete from impact or shock. It is made in various h heavy longitudinal or carrying wires and lighter transverse dis- r tie-wires. Expanded metal is similar to wire mesh in providing nt in both directions, rigidly spaced and attached or fastened to- is additional advantage is claimed for it; it provides reinforcement ions, thus taking care of concentrated loads.

ag. Different methods have been used for ANCHORING the tension- forced concrete. In the Hennebique system of construction (Fig. 10) bars are used, the ends of the rods are split and flared out. In other s the ends of the bars are simply turned at right-angles in such is most suitable. In some instances nuts and washers have been he ends of reinforcing-rods. Where reinforced-concrete floors are ection with steel columns the rods are run through the web-plates angle-brackets and secured with nuts.

L. The strengths of the BOND between concrete and steel for various rs and differing conditions are shown in Table IV. After the bond he reinforcement still acts in conjunction with the concrete, due to OF FRICTIONAL RESISTANCE. Numerous tests have shown this fric-

tional resistance to be about two thirds of the initial bond-strength. **BOND-STRENGTH** for ordinary round or square-section bars may be taken at

Fig. 10. The Hennebique System

to 300 lb per sq in., depending upon the character of the concrete and the degree of roughness of the steel. **MECHANICAL BOND** depends upon the shape of bar and the compressive and shearing strength of the concrete.

Table IV. Results of Tests on Adhesion Between Concrete and Steel

Kind of bar	Size tested in fraction of inch	Concrete	Age	Ultimate stress developed in per sq in of surface in contact
Round .....	$\frac{1}{2}$	1:2:4	60 days	412 (a)
Square .....	$\frac{3}{4}$	1:3:6	30 days	274 (b)
Square (rusted) .....	$\frac{3}{4}$	.....	30 days	437 (c)
Square (rusted) .....	$\frac{3}{4}$	.....	90 days	642 (c)
Square .....	$\frac{3}{4}$	.....	90 days	431 (c)
Square .....	$\frac{3}{4}$	.....	30 days	294 (c)
Twisted (Ransome) .....	$\frac{5}{8}$	1:2:4	31 days	648 (d)
Twisted .....	$\frac{3}{4}$	.....	25 days	500 (c)
Twisted .....	$\frac{3}{4}$	Neat cement	7 mos.	1 290 (e)
Twisted .....	$\frac{3}{4}$	1:1	7 mos.	1 318 (e)
Twisted .....	$\frac{3}{4}$	1:2	7 mos.	1 199 (e)
Twisted .....	$\frac{3}{4}$	1:3	7 mos.	701 (e)
Twisted .....	$\frac{3}{4}$	1:4	7 mos.	796 (e)
Corrugated .....	$\frac{3}{4}$	Neat cement	7 mos.	962 (e)
Corrugated .....	$\frac{3}{4}$	1:1	7 mos.	977 (e)
Corrugated .....	$\frac{3}{4}$	1:2	7 mos.	934 (e)
Corrugated .....	$\frac{3}{4}$	1:3	7 mos.	735 (e)
Corrugated .....	$\frac{3}{4}$	1:4	7 mos.	564 (e)
Corrugated .....	$\frac{3}{4}$	1:2:4	31 days	640 (d)
Thatcher (f) .....	$\frac{3}{4}$	.....	30 days	646 (c)

The following are the authorities for the above tests:

- (a) A. N. Talbot. (b) C. M. Spofford. (c) New York City Rapid Transit.  
 (d) T. L. Condon. (e) Tests of Metals, Watertown Arsenal, 1904.  
 (f) No longer manufactured.

**Members.** In many of the tests on full-sized concrete beams, failure is due to the development of diagonal breaks near the supports. The first crack in a beam, with nothing but horizontal tension-steel at the ends, is apt to occur when the maximum VERTICAL SHEAR is from 100 to 200 lb. Since the vertical shear is accompanied by a HORIZONTAL SHEAR of equal intensity in all parts of the beam, it was formerly thought that this diagonal failure was due to these shearing-forces at the end of the beam and vertical or bent-up rods were provided to resist the horizontal shear. More tests have shown that the SHEARING STRENGTH of concrete is from 60 to 80 per cent of the compressive strength, and that these cracks are diagonal and in the direction which could be expected from the THEORY OF DIAGONAL TENSION, and attributes them to a combination of the shearing-stress with the horizontal tensile stress. The inclined cracks which first appear are due to a rupture of the concrete in tension. The most effective way to prevent this rupture is by a reinforcement in the direction of the stress that is inclined upwards near the supports, as nearly as possible normal to the line of the diagonal cracks. Vertical reinforcement could be used, but it would not act until deflection or downward displacement of the concrete occurred on the side of the beam away from the support. If vertical stirrups are used for this reinforcement, they must be spaced a less distance apart than the effective depth of the beam, and they must be looped around, though not necessarily attached to, the longitudinal bars. When inclined reinforcement is used, it must be rigidly attached to the longitudinal members and spaced a less distance apart than the effective depth of the beam. The reason for this is that the magnitude and inclination of the diagonal tension increases from the middle toward the end of the beam, being inclined  $45^\circ$  where the horizontal tension becomes zero.

**Kahn Bar.** In the Kahn Trussed Bar (Fig. 11) the attachment of the bar to the tension-member is positively secured. The bars are square or



Fig. 11. The Kahn Bar

in cross-section with webs rolled on them at two diagonally opposite corners. The stirrups are formed by shearing these webs through a part of their length and turning up parts, as shown in the cut. These stirrups may be placed on up in pairs or so as to alternate on opposite sides of the bar, making the spacing of the stirrups closer than when turned up in pairs. Another advantage to the use of this bar is that the greater effective cross-section in the middle, the point of greatest bending moment with the usual reinforcement. Two disadvantages, however, are the separation of the concrete by the bar above and below the bar, and the limitation as to the effective stirrup spacing in deep beams. This bar is controlled by the Truscon Steel Company, Cincinnati, Ohio.

A Trussed Bar can be obtained in the sizes shown in table on page

**Compression.** The steel reinforcement in reinforced concrete is mainly in tension cases to assist in developing COMPRESSIVE STRENGTH when the concrete is not sufficient for the purpose, as in the case of beams and girders with

Size, in	Weight per linear foot, lb	Area, sq in	Standard length of diagonal in
$\frac{1}{2} \times 1\frac{1}{2}$	1.4	0.41	13
$\frac{3}{4} \times 2\frac{1}{4}$	2.7	0.79	13-24
$1\frac{1}{2} \times 2\frac{3}{4}$	4.8	1.41	13-24-36
$1\frac{3}{4} \times 3\frac{1}{4}$	6.8	2.00	36
$2 \times 3\frac{1}{2}$	10.2	3.00	36

rods placed above the neutral axis, and columns with rods placed vertically. The use of the steel reinforcement in resisting COMPRESSION will be treated at length in Subdivision 3 of this chapter, in the paragraph Compression in Beams and Girders, page 941. On account of the uncertainty, however, the steel and concrete each receiving its proportionate share of the load, of steel in compression should be avoided as much as possible.

**The Position of the Reinforcement.** The importance of the EXACT POSITION OF THE REINFORCEMENT in the concrete will become more apparent in discussion of the design of beams. A slight displacement of the steel will materially affect the strength. If the steel shifts upward the beam is weaker; if it shifts downward the protection of the steel against rust or fire is reduced. In the so-called UNIT SYSTEMS the reinforcements, including the tension-rod stirrups, are so tied and framed together that after being placed in the concrete the possibility of shifting their positions with respect to the other surfaces of the beam or to one another is practically entirely removed.

**The Unit System.** The particular advantages in the use of a UNIT SYSTEM of reinforcement is, as already indicated, the assurance that each and every

Fig. 12. The Unit System

of the reinforcement is in its exact relative position, and maintains that position during the placing of the concrete. The reinforcement for each beam or column is as carefully laid out as the location of cover-plates, stiffeners, connection-plates and rivets in a built-up steel girder. It can consequently be thoroughly inspected and checked before being placed in position. Being marked, its location is easily determined by the foreman on the job, from the construction plan. After it is put in place a quick inspection will show at once whether it is correctly placed or not, as it must fit and extend the full length of the member. Being fabricated OFF THE JOB there is less interference between workmen.

on can proceed while the molds are being made, and consequently speed in erection is possible. The frames are readily transported and do not get mixed with loose rods sent to the job.

**Unit System** (Fig. 12) is the pioneer of this type of construction and was introduced by the American System of Reinforcing, Chicago, Ill. Its particular features are the bending up of some of the longitudinal reinforcements at the supports and the use of round U-shaped stirrups, wound around the bars and allowed to shrink into place.

**Cummings System** (Fig. 13) is manufactured by the Electric Welding Company, Pittsburgh, Pa. The particular feature of this system is the forming




Fig. 13. The Cummings System

layer of small rods into rectangular frames which, after being fastened to the main reinforcement at suitable points, permit the bending up of the ends to act as stirrups, thus utilizing for shear the steel that is not required for bending moments.

**Luten Truss.** The Luten Truss (Fig. 14) consists of longitudinal rods and diagonal members bent diagonally upwards across the beam and connected at the ends by a clamp and wedge.



Fig. 14. The Luten Truss

connecting the upper surface to the end of the beam. Diagonal members are provided through all the region of diagonal tension in both ends of the beam. The system is provided with a clamp and wedge that locks the members together. It was developed by the National Concrete Company, Indianapolis, Ind.

**Corr-Bar Unit.** The Corr-Bar Unit, Fig. 15, made by the Corrugated Bar Company, Inc., Buffalo, N. Y., is provided with a continuous stirrup of both




Fig. 15. The Corr-bar Unit

inclined web-members with a rigid anchorage at both top and bottom. Tests conducted by Professor Talbot on this type of reinforced beam, considerably stronger than ordinary were obtained in vertical shear.

### 3. Design of Reinforced-Concrete Construction

**Girders, Beams, and Slabs.** Different formulas for the design of reinforced concrete girders, beams, slabs, etc., based on various theoretical considerations have been devised by different investigators. The formulas here given have been widely accepted and are offered because they are simple in form and give satisfactory results. If anything, they err on the side of safety; and furthermore, they have been found to give results closely in accord with actual tests. They are by the New York City Building Bureau, and are accepted by other authorities.

**Assumptions in the Formulas.** The formulas are based on the following assumptions:

(1) The **BOND** between the concrete and steel is sufficient to make the two materials act together.

(2) A **PLANE CROSS-SECTION** of a beam before bending remains a plane section after bending, and the stress and strain\* in any fiber of either material is directly proportional to the distance of that fiber from the neutral axis of the cross-section.

(3) The **MODULUS OF ELASTICITY** of the concrete in compression remains constant within the assumed working stresses.

(4) The **TENSIONAL STRESS** is taken entirely by the steel; that is, the tensile strength of the concrete is not considered.

Fig. 16 represents a longitudinal section and a cross-section of a reinforced concrete beam in a state of flexure or bending under a load. The fibers




Fig. 16. Sections of Reinforced-concrete Beam

the **NEUTRAL SURFACE** of the beam or above the **NEUTRAL AXIS** of the cross-section are in compression and according to the assumptions the stresses vary in direct proportion to their distances from the neutral surface or axis, so that the total area of compression in the concrete, representing the **TOTAL COMPRESSIONAL STRESS**, may be graphically indicated by the shaded triangle. The **TOTAL TENSIONAL STRESS** may be assumed to be concentrated at the center of gravity of the cross-section of the steel reinforcement. One of the conditions of **STATIC EQUILIBRIUM** for the beam is that the algebraic sum of all the horizontal stresses in the cross-section shall be zero; that is, that the sum of all the compressive stresses, or the resultant compressive stress in the concrete, must equal the or resultant tensional stress in the steel.

**Formulas for Reinforced-Concrete Beams.** From these assumptions based upon **THEORETIC** and **EXPERIMENTAL LAWS**, the following formulas have been derived, in which

$S_t$  = the allowable unit tension or working stress in the steel in pounds per square inch;

\* Deformation.

the allowable unit compression or working stress in the extreme fibers of the concrete in pounds per square inch;  
 the ratio of the modulus of elasticity of the steel to the modulus of elasticity of the concrete;  
 the effective depth of the beam, in inches; the distance from center of gravity of steel reinforcement to extreme fibers in compression;  
 the ratio of the depth of the neutral axis from the extreme fibers in compression, to the effective depth of the beam, so that  
 the distance of the neutral axis, in inches, from the extreme fibers in compression;  
 the width of the beam in inches;  
 the ratio of the cross-section of the steel to the cross-section of the beam, considering the beam all of that part of the concrete above the center of gravity of the steel;  
 the maximum bending moment at the dangerous section of the beam in inch-pounds;  
 the moment of resistance, in inch-pounds, at the dangerous section of the beam, and must of course be equal to or potentially greater than the maximum bending moment;\*  
 a factor used for simplification of the formulas. This factor is constant for any given steel and concrete;  
 the sectional area of the steel in square inches.  
 for beams of rectangular cross-section

$$M = M_r = Kbd^2 \quad (1)$$

where  $K$  being determined by the formula

$$K = S_t \left( \frac{1}{2 \left( \frac{S_t}{S_c} \right) \left( 1 + \frac{S_t}{S_c} \right)} \right) \left( 1 - \frac{1}{3 \left( 1 + \frac{S_t}{S_c} \right)} \right) \quad (2)$$

This formula can be deduced from the LAWS OF FLEXURE of beams and the conditions noted above.

In using this formula for the value of  $K$  it must be remembered that the value of  $S_c$  for any given ratio of steel to concrete,  $p$ , is a constant, so that constant values of  $S_t$  and  $S_c$  must be used. This ratio,  $p$ , often spoken of as PERCENTAGE OF REINFORCEMENT, is the expression in the first parenthesis of the first member of Formula (2)

$$p = \frac{1}{2 \left( \frac{S_t}{S_c} \right) \left( 1 + \frac{S_t}{S_c} \right)} \quad (3)$$

The "moment of resistance" or the "resisting moment" referred to any cross-section in any horizontal position and in a state of flexure under a load or loads is the sum of the moments of the internal horizontal stresses with reference to a point on the neutral axis and the "bending moment" for that section is the algebraic sum of the moments of the external vertical forces on either side of the section with reference to the same point (the forces on the left side being usually taken). The resisting moment is equal to the bending moment and in the flexure formula,  $M = SI/c$  (see Formula X), they are made equal to each other,  $M$  being the bending moment and  $M_r$  the resisting moment. In the following formulas,  $M$  and the expression "bending moment" generally, denote the maximum bending moment.  $M_{\max}$  is often used for the latter.

The value of  $x$  is derived from the expression

$$x = rp \left( \sqrt{1 + \frac{2}{rp}} - 1 \right)$$

Values for  $K$  and  $x$  for corresponding values of  $p$ , for different conditions fixed by the building authorities of different cities, are given in Tables V, VII and VIII.

Table V. Values for Formulas for Reinforced Concrete  
 $r = 12$

$p$	$x$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$
0.0045	0.279	.....	...	.....	....	...	.....	65.4	516	164
0.0050	0.291	.....	...	.....	....	...	.....	72.2	550	"
0.0055	0.303	.....	...	.....	69.3	507	14 000	79.2	580	"
0.0058	0.310	.....	...	.....	73.0	525	"	83.4	600	"
0.0060	0.314	.....	...	.....	75.2	535	"	86.0	612	"
0.0065	0.325	.....	...	.....	81.2	560	"	92.8	640	"
0.0070	0.334	74.7	503	12 000	87.2	587	"	96.5	650	15
0.0075	0.344	79.5	523	"	93.0	610	"	99.0	"	14
0.0080	0.353	84.7	544	"	98.8	635	"	101.2	"	14
0.0085	0.361	89.9	565	"	103.3	650	13 800	103.3	"	13
0.0090	0.369	94.7	584	"	105.1	"	13 350	105.1	"	13
0.0095	0.377	99.6	605	"	107.0	"	12 900	107.0	"	12
0.0100	0.384	104.5	625	"	108.8	"	12 300	108.8	"	12
0.0105	0.392	109.5	643	"	110.9	"	12 130	110.9	"	12
0.0110	0.399	112.4	650	11 790	112.4	"	11 790	112.4	"	11
0.0115	0.405	114.0	"	11 450	114.0	"	11 450	114.0	"	11
0.0120	0.412	115.7	"	11 160	115.7	"	11 160	115.7	"	11
0.0125	0.418	117.2	"	10 900	117.2	"	10 900	117.2	"	10
0.0130	0.424	118.2	"	10 600	118.2	"	10 600	118.2	"	10
0.0135	0.430	119.8	"	10 350	119.8	"	10 350	119.8	"	10
0.0140	0.436	121.2	"	10 120	121.2	"	10 100	121.2	"	10
0.0145	0.441	122.2	"	9 890	122.2	"	9 870	122.2	"	9
0.0150	0.446	123.2	"	9 660	123.2	"	9 660	123.2	"	9
0.0155	0.452	124.8	"	9 460	124.8	"	9 460	124.8	"	9
0.0160	0.457	126.0	"	9 270	126.0	"	9 270	126.0	"	9
0.0165	0.462	127.0	"	9 100	127.0	"	9 100	127.0	"	9
0.0170	0.467	128.0	"	8 930	128.0	"	8 930	128.0	"	8
0.0175	0.471	129.1	"	8 740	129.1	"	8 740	129.1	"	8
0.0180	0.475	130.1	"	8 580	130.1	"	8 580	130.1	"	8
0.0185	0.480	131.0	"	8 440	131.0	"	8 440	131.0	"	8
0.0190	0.485	132.1	"	8 300	132.1	"	8 300	132.1	"	8
0.0195	0.489	133.0	"	8 150	133.0	"	8 150	133.0	"	8
0.0200	0.493	134.0	"	8 010	134.0	"	8 010	134.0	"	8



Table VI. Values for Formulas for Reinforced Concrete

 $r = 12$ 

	$x$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$
5	0.217	.....	....	.....	.....	....	.....	51.0	506	22 000
0	0.235	.....	....	.....	55.3	511	20 000	60.8	562	"
5	0.251	57.7	503	18 000	64.2	558	"	70.6	614	"
0	0.266	65.7	542	"	72.9	602	"	78.7	650	21 610
5	0.279	73.5	581	"	81.6	645	"	82.3	"	20 150
0	0.291	81.3	618	"	85.4	650	18 910	85.4	"	18 910
5	0.303	88.5	650	17 900	88.5	"	17 900	88.5	"	17 900
0	0.314	91.5	"	17 000	91.5	"	17 000	91.5	"	17 000
	0.325	94.2	"	16 250	94.2	"	16 250	94.2	"	16 250
	0.334	96.5	"	15 510	96.5	"	15 510	96.5	"	15 510
	0.344	99.0	"	14 900	99.0	"	14 900	99.0	"	14 900
	0.353	101.2	"	14 350	101.2	"	14 350	101.2	"	14 350
	0.361	103.3	"	13 800	103.3	"	13 800	103.3	"	13 800
	0.369	105.1	"	13 325	105.1	"	13 325	105.1	"	13 325
	0.377	107.0	"	12 900	107.0	"	12 900	107.0	"	12 900
	0.384	108.8	"	12 480	108.8	"	12 480	108.8	"	12 480
	0.392	110.9	"	12 130	110.9	"	12 130	110.9	"	12 130
	0.399	112.4	"	11 790	112.4	"	11 790	112.4	"	11 790
	0.405	113.9	"	11 450	113.9	"	11 450	113.9	"	11 450
	0.412	115.6	"	11 160	115.6	"	11 160	115.6	"	11 160
	0.418	117.2	"	10 900	117.2	"	10 900	117.2	"	10 900
	0.424	118.4	"	10 600	118.4	"	10 600	118.4	"	10 600
	0.430	120.0	"	10 350	120.0	"	10 350	120.0	"	10 350
	0.436	121.2	"	10 100	121.2	"	10 100	121.2	"	10 100
	0.441	122.2	"	9 870	122.2	"	9 870	122.2	"	9 870
	0.446	123.2	"	9 660	123.2	"	9 660	123.2	"	9 660
	0.452	124.8	"	9 460	124.8	"	9 460	124.8	"	9 460
	0.457	126.0	"	9 270	126.0	"	9 270	126.0	"	9 270
	0.462	127.0	"	9 100	127.0	"	9 100	127.0	"	9 100
	0.467	128.0	"	8 930	128.0	"	8 930	128.0	"	8 930
	0.471	129.1	"	8 740	129.1	"	8 740	129.1	"	8 740
	0.475	130.1	"	8 580	130.1	"	8 580	130.1	"	8 580
	0.480	131.0	"	8 440	131.0	"	8 440	131.0	"	8 440
	0.485	132.1	"	8 300	132.1	"	8 300	132.1	"	8 300
	0.489	133.0	"	8 150	133.0	"	8 150	133.0	"	8 150
	0.493	134.0	"	8 010	134.0	"	8 010	134.0	"	8 010

Table VII. Values for Formulas for Reinforced Concrete

 $r = 15$ 

$p$	$z$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$
0.0050	0.320	.....	...	.....	.....	...	.....	71.6	500	16 000
0.0055	0.332	.....	...	.....	.....	...	.....	78.3	530	"
0.0060	0.344	.....	...	.....	.....	...	.....	85.1	558	"
0.0065	0.355	.....	...	.....	80.2	513	14 000	91.6	586	"
0.0070	0.365	.....	...	.....	86.1	537	"	98.3	614	"
0.0075	0.375	.....	...	.....	92.0	560	"	105.1	640	"
0.0080	0.384	83.6	500	12 000	97.6	583	"	108.9	650	15 600
0.0085	0.393	88.6	519	"	103.3	606	"	111.0	"	15 000
0.0090	0.402	93.5	537	"	109.0	627	"	113.2	"	14 500
0.0095	0.410	98.4	556	"	114.8	648	"	115.1	"	14 000
0.0100	0.418	103.3	573	"	117.1	650	13 600	117.1	"	13 600
0.0105	0.425	108.2	593	"	118.6	"	13 150	118.6	"	13 150
0.0110	0.433	113.1	611	"	120.5	"	12 760	120.5	"	12 760
0.0115	0.440	117.9	627	"	122.0	"	12 420	122.0	"	12 420
0.0120	0.446	122.7	647	"	123.4	"	12 080	123.4	"	12 080
0.0125	0.453	125.0	650	11 780	125.0	"	11 780	125.0	"	11 780
0.0130	0.459	126.8	"	11 480	126.8	"	11 480	126.8	"	11 480
0.0135	0.465	127.7	"	11 200	127.7	"	11 200	127.7	"	11 200
0.0140	0.471	128.9	"	10 920	128.9	"	10 920	128.9	"	10 920
0.0145	0.477	130.4	"	10 690	130.4	"	10 690	130.4	"	10 690
0.0150	0.483	131.7	"	10 465	131.7	"	10 465	131.7	"	10 465
0.0155	0.488	133.0	"	10 240	133.0	"	10 240	133.0	"	10 240
0.0160	0.493	133.9	"	10 010	133.9	"	10 010	133.9	"	10 010
0.0165	0.498	135.2	"	9 810	135.2	"	9 810	135.2	"	9 810
0.0170	0.503	136.0	"	9 620	136.0	"	9 620	136.0	"	9 620
0.0175	0.508	137.2	"	9 435	137.2	"	9 435	137.2	"	9 435
0.0180	0.513	138.2	"	9 260	138.2	"	9 260	138.2	"	9 260
0.0185	0.518	139.4	"	9 100	139.4	"	9 100	139.4	"	9 100
0.0190	0.522	140.3	"	8 940	140.3	"	8 940	140.3	"	8 940
0.0195	0.527	141.1	"	8 790	141.1	"	8 790	141.1	"	8 790
0.0200	0.531	142.0	"	8 630	142.0	"	8 630	142.0	"	8 630

Table VIII. Values for Formulas for Reinforced Concrete

 $r = 15$ 

$x$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$	$K$	$S_c$	$S_t$
0.258	.....	...	.....	.....	...	.....	60.3	512	22 000
0.276	.....	...	.....	63.5	507	20 000	69.9	557	"
0.292	.....	...	.....	72.3	548	"	79.5	604	"
0.306	72.7	528	18 000	80.7	587	"	88.8	646	"
0.320	80.5	563	"	89.4	626	"	92.9	650	20 800
0.332	88.1	596	"	96.0	650	19 610	96.0	"	19 610
0.344	95.6	628	"	99.1	"	18 620	99.1	"	18 620
0.355	101.8	650	17 760	101.8	"	17 760	101.8	"	17 760
0.365	104.1	"	16 950	104.1	"	16 950	104.1	"	16 950
0.375	106.7	"	16 250	106.7	"	16 250	106.7	"	16 250
0.384	108.9	"	15 600	108.9	"	15 600	108.9	"	15 600
0.393	111.0	"	15 040	111.0	"	15 040	111.0	"	15 040
0.402	113.2	"	14 520	113.2	"	14 520	113.2	"	14 520
0.410	115.1	"	14 020	115.1	"	14 020	115.1	"	14 020
0.418	117.1	"	13 600	117.1	"	13 600	117.1	"	13 600
0.425	118.6	"	13 150	118.6	"	13 150	118.6	"	13 150
0.433	120.5	"	12 760	120.5	"	12 760	120.5	"	12 760
0.440	122.0	"	12 420	122.0	"	12 420	122.0	"	12 420
0.446	123.4	"	12 080	123.4	"	12 080	123.4	"	12 080
0.453	125.0	"	11 780	125.0	"	11 780	125.0	"	11 780
0.459	126.4	"	11 480	126.4	"	11 480	126.4	"	11 480
0.465	127.7	"	11 200	127.7	"	11 200	127.7	"	11 200
0.471	128.9	"	10 920	128.9	"	10 920	128.9	"	10 920
0.477	130.4	"	10 690	130.4	"	10 690	130.4	"	10 690
0.483	131.7	"	10 465	131.7	"	10 465	131.7	"	10 465
0.489	133.0	"	10 240	133.0	"	10 240	133.0	"	10 240
0.495	133.9	"	10 010	133.9	"	10 010	133.9	"	10 010
0.501	135.0	"	9 810	135.0	"	9 810	135.0	"	9 810
0.507	136.0	"	9 620	136.0	"	9 620	136.0	"	9 620
0.513	137.2	"	9 435	137.2	"	9 435	137.2	"	9 435
0.519	138.2	"	9 260	138.2	"	9 260	138.2	"	9 260
0.525	139.4	"	9 100	139.4	"	9 100	139.4	"	9 100
0.531	140.1	"	8 940	140.1	"	8 940	140.1	"	8 940
0.537	141.1	"	8 790	141.1	"	8 790	141.1	"	8 790
0.543	142.0	"	8 630	142.0	"	8 630	142.0	"	8 630

**Cinder Concrete.** Values of  $K$  for cinder concrete are given in Tables D and X, which are, however, recommended to be used only for slabs. Cinder concrete, though an excellent fireproofing material, lacks strength and should be used as a structural material for the slabs, only, between the beams.

Table IX. Values for Formulas for Reinforced Cinder Concrete

$$r = 35$$

$p$	$x$	$K$	$S_o$	$S_t$	$K$	$S_o$	$S_t$
0.0005	0.170	7.5	94	16 000	7.5	94	16 000
0.0010	0.232	14.8	138	"	14.8	138	16 000
0.0015	0.276	21.8	174	"	18.8	150	13 800
0.0020	0.311	28.7	206	"	20.9	"	11 633
0.0025	0.340	33.9	225	15 300	22.6	"	10 200
0.0030	0.365	36.1	"	13 688	24.0	"	9 125
0.0035	0.387	37.9	"	12 439	25.3	"	8 293
0.0040	0.407	39.6	"	11 447	26.4	"	7 631
0.0045	0.425	41.0	"	10 625	27.4	"	7 083
0.0050	0.442	42.4	"	9 945	28.3	"	6 630
0.0055	0.457	43.6	"	9 348	29.1	"	6 232
0.0060	0.471	44.7	"	8 831	29.8	"	5 888
0.0065	0.484	45.7	"	8 377	30.4	"	5 585
0.0070	0.497	46.7	"	7 988	31.1	"	5 325
0.0075	0.508	47.5	"	7 620	31.6	"	5 080
0.0080	0.519	48.3	"	7 298	32.2	"	4 866
0.0085	0.529	49.0	"	7 001	32.7	"	4 668
0.0090	0.539	49.7	"	6 738	33.2	"	4 492
0.0095	0.548	50.4	"	6 489	33.6	"	4 326
0.0100	0.557	51.0	"	6 266	34.0	"	4 178
0.0105	0.565	51.6	"	6 054	34.4	"	4 036
0.0110	0.573	52.1	"	5 860	34.8	"	3 907
0.0115	0.581	52.7	"	5 684	35.1	"	3 789
0.0120	0.588	53.2	"	5 513	35.5	"	3 675
0.0125	0.595	53.7	"	5 355	35.8	"	3 570
0.0130	0.602	54.1	"	5 210	36.1	"	3 473
0.0135	0.608	54.5	"	5 067	36.4	"	3 378
0.0140	0.615	55.0	"	4 942	36.7	"	3 295
0.0145	0.621	55.4	"	4 818	36.9	"	3 212
0.0150	0.626	55.7	"	4 695	37.1	"	3 130
0.0155	0.632	56.1	"	4 587	37.4	"	3 058
0.0160	0.637	56.4	"	4 479	37.6	"	2 986
0.0165	0.643	56.8	"	4 384	37.9	"	2 923
0.0170	0.648	57.2	"	4 288	38.1	"	2 859
0.0175	0.652	57.4	"	4 191	38.3	"	2 794
0.0180	0.657	57.7	"	4 106	38.5	"	2 738
0.0185	0.662	58.1	"	4 026	38.7	"	2 684
0.0190	0.666	58.3	"	3 943	38.9	"	2 629
0.0195	0.671	58.6	"	3 871	39.1	"	2 581
0.0200	0.675	58.9	"	3 797	39.2	"	2 531

# Design of Reinforced-Concrete Construction

Table X. Values for Formulas for Reinforced Cinder Concrete

$r = 30$

$x$	$K$	$S_c$	$S$	$K$	$S_c$	$S$	$K$	$S_c$
0.159	7.6	100.6	16 000	7.6	100.6	16 000	6.62	88
0.216	14.9	148	"	14.9	148	"	13.0	129.1
0.259	22.0	185	"	22.0	185	"	19.2	162
0.292	28.8	219	"	28.8	219	"	25.2	192
0.319	35.8	251	"	35.6	250	15 950	28.5	200
0.344	42.6	279	"	38.1	"	14 300	30.4	"
0.365	48.1	300	15 620	40.1	"	13 030	32.0	"
0.386	50.4	"	14 480	42.1	"	12 060	33.6	"
0.402	52.2	"	13 400	43.4	"	11 170	34.8	"
0.418	54.0	"	12 540	45.0	"	10 450	36.0	"
0.433	55.6	"	11 810	46.3	"	9 860	37.0	"
0.447	57.0	"	11 180	47.5	"	9 320	38.0	"
0.460	58.5	"	10 620	48.7	"	8 850	38.9	"
0.472	59.7	"	10 120	49.7	"	8 440	39.8	"
0.483	60.7	"	9 660	50.6	"	8 050	40.5	"
0.494	61.9	"	9 270	51.6	"	7 730	41.3	"
0.504	63.0	"	8 900	52.5	"	7 420	42.0	"
0.514	63.9	"	8 560	53.3	"	7 130	42.6	"
0.523	64.9	"	8 250	54.1	"	6 870	43.2	"
0.532	65.7	"	7 980	54.7	"	6 650	43.7	"
0.540	66.4	"	7 710	55.4	"	6 420	44.3	"
0.547	67.2	"	7 460	55.9	"	6 220	44.7	"
0.555	67.8	"	7 240	56.5	"	6 040	45.2	"
0.562	68.5	"	7 020	57.1	"	5 850	45.7	"
0.569	69.3	"	6 830	57.7	"	5 680	46.2	"
0.576	69.8	"	6 650	58.2	"	5 540	46.5	"
0.582	70.4	"	6 460	58.6	"	5 380	46.8	"
0.588	71.0	"	6 310	59.2	"	5 260	47.3	"
0.594	71.5	"	6 140	59.5	"	5 120	47.6	"
0.599	72.0	"	6 000	60.0	"	5 000	48.0	"
0.604	72.6	"	5 860	60.5	"	4 880	48.4	"
0.609	73.1	"	5 730	60.9	"	4 780	48.7	"
0.614	73.6	"	5 610	61.3	"	4 670	49.0	"
0.619	74.0	"	5 480	61.7	"	4 570	49.4	"
0.624	74.5	"	5 370	62.0	"	4 470	49.6	"
0.629	74.9	"	5 270	62.4	"	4 390	49.9	"
0.634	75.3	"	5 160	62.7	"	4 300	50.2	"
0.639	75.7	"	5 060	63.1	"	4 220	50.4	"
0.644	76.0	"	4 960	63.3	"	4 130	50.7	"
0.649	76.4	"	4 870	63.6	"	4 060	50.8	"

**Concrete Beams of Rectangular Cross-Section.** In the BEAM required for any given case,  $r$  and the limiting  $K$  are generally given, and  $K$  can be determined for any ratio,  $j$ . The value of  $M$ , the MAXIMUM BENDING MOMENT, that can be applied at the DANGEROUS SECTION of the beam, is determined by the loading, the span and the spacing; and the width  $b$  is to be found. Formula (1) may then be put in the form

$$d = \sqrt{\frac{M}{Kb}}$$

A value for  $b$  is assumed and the equation solved for  $d$ . Architectural or structural reasons will often limit the width or depth and several trials may have to be made.

**Reinforced-Concrete Slabs.** For the STRENGTH OF SLABS the same formulas apply. A slab may be treated (1) as a rectangular beam of unusual width (2) as a series of beams set one alongside the other, the width of each beam being equal to the spacing of the reinforcing-rods, and one rod being used for each beam; or (3) as a series of beams of unit width, the area of steel for each beam being the area of reinforcement per unit of width.

**Check-Formulas.** It may sometimes happen that it is advisable to check a given or existing beam-construction as to strength or compliance with specifications for working stresses. In that case the following formulas will be convenient (see, also, page 992):

$$M = p S_t b d^2 \left( 1 - \frac{x}{3} \right)$$

$$M = \frac{S_c x b d^2}{2} \left( 1 - \frac{x}{3} \right)$$

If the strength of the beam for the assumed working stresses is to be determined, these values of  $S_t$  and  $S_c$  are inserted in Formulas (6) and (7), and the least value of  $M$  is used. If the values of  $M$  resulting from these equations are not equal, the full benefit of one of the materials is not being obtained. If the stresses in the steel or concrete due to a given loading are to be determined the formulas are put in the following forms:

$$S_t = \frac{M}{p b d^2 \left( 1 - \frac{x}{3} \right)}$$

$$S_c = \frac{2 M}{x b d^2 \left( 1 - \frac{x}{3} \right)}$$

These formulas apply to rectangular beams only.  $M$  in Formulas (8) and (9) is the maximum moment due to the external forces, or the maximum bending moment. The value of  $x$  can be determined from Tables V to X. In Formula (8) it will be noted that the denominator of the fraction is an expression for the area of the steel multiplied by the lever-arm of the resisting moment that is, the distance from the center of gravity of the steel to the center of compression in the concrete. Similarly, in Formula (9), the denominator of the fraction is an expression for the area of the concrete in compression multiplied by the lever-arm,  $x$  again being determined by Formula (4) and  $M$  being the maximum bending moment due to the external forces.

**Reinforced-Concrete T Beams.** Where beams or girders are used in reinforced-concrete building-construction there are usually accompanying floor-slabs. If these slabs are cast with the beams or girders they add very much to the strength of the latter, and when adequate bond and shearing-resistance are provided between the slab and the stem or beam, economical design requires that the slab shall be considered in determining the strength of the beam. The width of slab that may be taken as part of the beam should not exceed one sixth the span-length of the beam, and the overhanging part on either side of the web or stem should not exceed six times the thickness of the slab. In any case

ge must not be considered wider than the distance between the beams. In any floor-construction the spacing of beams, girders, and columns is generally a matter of architectural or commercial consideration. Generally, the simplest procedure, therefore, is to first determine the thickness of slab required for the given load, and this determines the thickness of the flange of the T beam. In the calculation of the girder, it is not objectionable to use the same slab, or a portion of it as may be permissible, that has been used in the consideration of the slab framing into that girder, as the compression-stresses, in the two cases, are at right-angles to, and practically assist, one another. When, however, the slab-reinforcement is parallel to the girder, in the case of a combined slab and girder-construction, the slab-action produces compression in the direction of the girder-compression with a resulting overstress in the concrete. In this case, transverse reinforcement should be provided at right-angles to the girder and extending well into the slab.

**Notation for Reinforced-Concrete T Beams.** Fig. 17 shows a cross-section of a T beam resulting from the use of the slab as part of the beam, and




Fig. 17. Cross-section of Reinforced-concrete T Beam

will give, also, the notation used in the formulas. In a construction of this kind, two cases may be considered:

The neutral axis may fall below the flange, in which case

$$M = S_t A_s \left( d - \frac{t}{2} \right) \quad (10)$$

$$M = \frac{S_c}{2} b' t \left( d - \frac{t}{2} \right) \quad (11)$$

In the first formula the small area of concrete in compression below the flange is neglected, and the center of compression is assumed to be at the center of the flange.

This is done to simplify the formulas. The result is not materially in error on the side of safety. The position of the neutral axis is given by the following formula (12)

$$x = \frac{2r d A_s + b' t^2}{2d(r A_s + b' t)} \quad (12)$$

To find the most economical percentage of steel by Formula (13)

$$p = \frac{S_c b' t}{2 S_t b d} \quad (13)$$

**Case 2.** The neutral axis may coincide with the under side of the flange, in which case

$$M = S_s A_s \left( d - \frac{t}{3} \right) \quad (14)$$

and

$$M = \frac{S_c b' t}{2} \left( d - \frac{t}{3} \right) \quad (15)$$

The economical value of  $p$  in this case is the same as in Case 1, Formula (13).

**Case 3.** The neutral axis may fall above the lower edge of the flange. This case is the same as Case 2, since for purposes of calculation all the concrete in the flange below the neutral axis is neglected and  $t$  becomes  $x'd$  in this case as in the last.

**Alternate Solution for Cases 2 and 3.** In Cases 2 and 3 the section may also be considered as rectangular, with a depth  $d$  and a width  $b'$ , and the formulas for rectangular beams, (1) to (9), may be used. Tables V, VI, VII, and VIII are also applicable in these two cases.

When the slab is considered an integral part of the beam, adequate bond and shearing resistance between the slab and the web of the beam must be provided. The concrete is ordinarily adequate to take the vertical shear through the flanges next to the stem, and is further strengthened by placing horizontal steel reinforcements across the top of the beam or girder, as described above. Whether or not the resistance to shear is adequate can be determined by the formula

$$S_s = \frac{S_h b (b' - b)}{2 b' t} \quad (16)$$

in which  $S_s$  is the unit vertical shear at  $AB$ , and  $S_h$  is the unit horizontal shear at  $BC$  (Fig. 17). This should not exceed the safe unit shear for concrete unless steel reinforcement is provided. The value of  $S_h$  in the formula is

$$S_h = \frac{V}{b (d - \frac{1}{2} t)} \quad (17)$$

which, it will be noted, is the total vertical shear divided by the effective area of the stem.

**Moduli of Elasticity.** In the derivation of all these formulas and in the determination of the values of  $K$ , the ratio of the MODULUS OF ELASTICITY of the steel to that of the concrete plays an important part. It is necessary then to know what values to use. The generally accepted modulus of elasticity of steel is 30 000 000 lb per sq in. The modulus of elasticity of concrete varies with many conditions. Even in the same mixture, the character of the materials as well as the manner of mixing and placing, affect it. The modulus increases with the age of the concrete. It also increases with the richness of the mixture. It seems to decrease with an increase in the load on the concrete. It should also be noted that the modulus of elasticity as determined from a beam in flexure is greater than that determined from compression-cylinders. Moreover the modulus of elasticity as determined from compression varies with the point selected on the stress-strain curve. The different values for the RATIO OF THE MODULUS OF ELASTICITY of the steel to the modulus of elasticity of the concrete to be used in the design of reinforced-concrete construction, as fixed by the building regulations of various cities and by other authorities, is given in Table II, page 912. Values for the modulus of elasticity of concrete under different



for different mixtures determined by actual tests at the Watertown given in Table XI.


### Elastic Properties of Broken-Stone Concrete Twelve-Inch Cubes

position and	Broken stone	Age	Modulus of elasticity in pounds per square inch between loads of			Tests made by
			100 and 600 lb per sq in	600 and 1 000 lb per sq in	1 000 and 2 000 lb per sq in	
2	4	7 days	2 593 000	2 054 000	1 351 000	* Geo. A. Kimball.
2	4	1 mo	2 662 000	2 445 000	1 462 000	" " "
2	4	3 mos	3 671 000	3 170 000	2 158 000	" " "
2	4	6 mos	3 646 000	3 567 000	2 582 000	" " "
3	6	7 days	1 869 000	1 530 000	.....	" " "
3	6	1 mo	2 438 000	2 135 000	1 219 000	" " "
3	6	3 mos	2 976 000	2 656 000	1 805 000	" " "
3	6	6 mos	3 608 000	3 503 000	1 868 000	" " "
6	12	1 mo	1 376 000	.....	.....	" " "
6	12	3 mos	1 642 000	1 364 000	.....	" " "
6	12	6 mos	1 820 000	1 522 000	.....	" " "


\* Tests of metals, U. S. A., 1899, page 741.

**g Stresses.** The WORKING STRESSES for concrete and steel allowances are given in Table II on page 912. In the determination of  $S_c$ ,  $S_s$ , and  $r$  as taken from Table II are substituted in Formula (5). The value of  $K$  may be taken directly from Tables V to VIII, pages 91 to 94, and substituted in Formula (5). For  $M$  in that formula, the MAXIMUM MOMENT due to the external forces is used.

**g Moments in Beams.** Beams and girders are usually considered as BEAMS, that is, as beams supported at both ends, but not built



Reinforcement for Uniformly Distributed or Symmetrically Placed Load



9. Reinforcement for Unsymmetrically Placed Concentrated Load

r continuous, although in many instances they are actually carried over the supports. If continued over a support, the

is a **NEGATIVE BENDING MOMENT** at that support, and this negative bending moment should be taken care of by reinforcements in the upper part of the beam. This bending moment is one half that at the middle of a simple supported beam loaded at the middle, and two thirds that at the middle of a simple supported beam, uniformly loaded. In the case of simple supported beams loaded either at the middle or with a uniformly distributed load, the bending moments increase toward the supports. For these reasons it is advisable in arranging the steel to be used for the tensional reinforcement, to select the bars or rods in pairs, so that, as the supports are approached, a part of the reinforcement may be turned up toward the top and carried across the supports near the top as indicated in Figs. 18 and 19. For continuous beams and slabs with uniformly distributed loads, the following are recommended for **MAXIMUM POSITIVE** and **MAXIMUM NEGATIVE BENDING MOMENTS**:

"For beams, the bending moment at middle and at support for interior spans, should be taken equal to  $wl^2/12$ , and for end spans it should be taken equal to  $wl^2/10$  for middle and interior support, for both dead and live loads.

"In the case of beams and slabs continuous for two spans only, with their ends restrained, the bending moment both at the middle support and over the middle of the span should be taken equal to  $wl^2/10$ ."\*

Beams simply supported at the ends must be considered as **SIMPLE BEAMS** with maximum positive bending moments equal to  $wl^2/8$ . In all the above values,  $w$  is the load per linear unit and  $l$  the span in the same unit.

**Bending Moments in Slabs.** As floor-slabs are usually carried continuous across the supports, the maximum bending moment due to a uniformly distributed load is assumed to be less than in beams simply supported at the ends. The New York City Regulations provide that "the bending moments at the center and at intermediate supports of floor-slabs continuous over two or more supports shall be taken as  $Wl/12$ ." The same regulations provide that "the bending moments of slabs that are reinforced in both directions and supported on four sides and fully reinforced over the supports (the reinforcement passing in the adjoining slabs) may be taken as  $Wl/F$  for loads in each direction, in which  $F=8$  when the slab is not continuous or when continuous over one support and  $F=12$  at both center and supports when the slab is continuous over both supports." In these expressions  $W$  is the total distributed load and  $l$  the span. In square slabs with two-way reinforcement it is usually assumed that the load is uniformly distributed and that half the load is carried by each system. In rectangular slabs the amount of load carried by each system of reinforcement is given by the formula

$$r = \frac{1}{2} \frac{W}{\pi} \quad (1)$$

in which  $r$  is the proportion of load carried by the transverse reinforcement,  $W$  the total load on the slab, and  $\pi$  the ratio of its longer to its shorter side. Using this proportion of load, each set of reinforcements is calculated as a slab with supports on two sides only, and the total number of rods required is determined on the assumption of equal spacing. The rods may then be spaced uniformly at the usual spacing for the central half of the slab and gradually reduced in number per foot of width to the edge of the slab, using one half as many rods for the remaining two quarters. In this way, the amount of reinforcement is reduced 25%. When the length of the slab exceeds the breadth by 50% the stresses in the longitudinal steel become so low that the construction

\* Trans. Am. Soc. C. E., 1917, page 1227.

onomical. The slab should then be treated as one with a one-way reinforce-

**Shrinkage-Stresses and Temperature-Stresses.** In slabs resting on or over two supports some reinforcement should be provided at right-angles to the tension-rods to provide against SHRINKAGE-STRESSES and TEMPERATURE-STRESSES. Incidentally, this reinforcement may also serve to keep tension-rods properly spaced. In general it should not be less than one per cent of one per cent in amount and well distributed. It is common practice to use from  $\frac{1}{4}$  to  $\frac{3}{8}$ -in rods, spaced about 2 ft apart. Deformed bars with irregular surfaces and reinforcements of small diameters, placed as close as practicable to the surface, are most effective.

**The Disposition of the Steel.** In designing the reinforcement for any span of loading, the full sectional area required must be provided at the point of MAXIMUM BENDING MOMENT. As the supports are approached, part of the reinforcement, as already indicated, is turned up, but care must be taken to keep it so distributed that at any point there is still sufficient reinforcement below the neutral axis to furnish the necessary tensional resistance. The arrangement of reinforcement for a uniformly distributed or symmetrically disposed load is shown in Fig. 18, and for an unsymmetrically placed concentrated load, in Fig. 19. In the first instance the maximum bending moment is at the middle of the span, the reinforcement is symmetrical about that point, and as much as one-half the amount of reinforcement may be turned up. In the second instance the maximum bending moment is at some other point than the middle, the reinforcement must be so disposed that the full amount required will be under the load or at the point of maximum bending moment, and the turning up must be done between that point and the support. Other conditions might require more than half the reinforcement to be turned up. There is another reason for turning up the reinforcements toward the ends. In addition to the resistance to the NEGATIVE BENDING MOMENT, there is a resistance to the SHEAR offered by the metal running through the concrete at the points where the DIAGONAL CRACKS OCCUR.

**The Percentage of Reinforcement.** The AMOUNT OF THE REINFORCEMENT in any case is determined by Formulas (3) and (13) for rectangular and T beams respectively. The values obtained by these formulas give the most economical amount. This may vary from  $\frac{1}{4}\%$  to  $1\frac{1}{4}\%$  of the cross-section area of concrete, but will usually run about  $\frac{3}{10}\%$ . The nearest stock size of rods giving this amount or a slightly greater amount can be selected from the table given on page 1514, or from the catalogues of the manufacturers of the various reinforced bars.\* The NUMBER OF RODS used to make up the necessary sectional area must be determined by considerations mentioned in the following paragraphs.

**The Number of Reinforcing-Rods.** As already suggested, an even number adapts itself better to a symmetrical or balanced arrangement both in cross-section and horizontal section. One rod does not permit of the turning up toward the support. Two rods may be made either to continue along the lower edge of the beam, or one may start at one support, run along the lower part and turn up beyond the middle as it approaches the second support; and the second rod run similarly along the bottom from the second support and turn up after passing the middle as it approaches the first support. Three rods may be arranged so that two continue along the bottom and the third, the middle one, turns up as it approaches the supports. The arrangement for 4, 5, or 6 rods will naturally suggest

\* See, also, paragraph on Commercial Sizes, page 915.

itself from what has been already said. Too large a number of rods is not desirable, as a large number of them together acts more or less as a screen for coarser particles of the concrete and prevents a close contact between it and steel. This matter of complicated reinforcement is one of considerable practical importance. If, however, the steel is satisfactorily incased with concrete, a larger number of small rods is preferable to a small number of larger ones. The AREA OF CONTACT of a rod of smaller size is proportionately greater than that of a rod of larger size, as the perimeter varies directly as the diameter, and the sectional area as the square of diameter of the cross-section. In order that a rod may not slip, the ADHESION of the steel to the concrete must be equal or greater than the tension in the steel.

**The Adhesion Required.** The tension in a reinforcing-rod at any point having been determined from the given formulas, it must next be determined if, in either direction from that point, the AREA OF CONTACT of the steel is large enough to make the total ADHESION equal to or greater than the TENSION. If there is a deficiency in this respect it must be made up either by a mechanical bond or by anchoring the reinforcements at the ends. Safe VALUES of ADHESION of concrete and steel are given in Table II, page 912. A safe rule to apply, without calculation, to the case of beams with a maximum bending moment at the middle, is to make the diameter of the rods not more than one two-hundredth of the span. Under ordinary conditions, generally speaking, the length of rod on either side of the point of maximum bending moment should be at least eighty diameters for plain rods, and not less than fifty diameters for deformed bars. Under unusual conditions the adhesion should be carefully studied. The apparent discrepancy between the first and second statements in this paragraph is explained by an allowance made and based upon the fact that the tension in the steel does not decrease uniformly with the decrease in distance from the supports. The allowance is purely arbitrary but is considered safe. For cases of unsymmetrically loaded beams it is best to examine carefully into the conditions.

**The Separation of the Rods.** It has not been unusual in tests on beams to have the concrete split off from the under side along the line of the reinforcement. This is due in part, if not entirely, to an insufficiency of concrete between and around the reinforcement. To avoid this the SPACING or SEPARATION of the reinforcing-rods in the cross-sections of the beams must be such that the resistance of the concrete to SHEAR at the level of the rods is at least equal to the ADHESION of the concrete to the steel. As a general rule the rods should be spaced not less than two-and-one-half diameters on centers and about two diameters from the sides of beams. The clear distance between rods and the space between rods and edges of beams should in no case be less than  $1\frac{1}{2}$  in. For deformed bars, if stressed to their full tensional value, should be spaced farther apart than plain bars. At the middle of a beam, the BOND-STRESS is low, but at the top of a continuous beam, over the supports, where the negative moment increases rapidly, the bond-stress is apt to be excessive and frequently limits the diameter of the reinforcement.

**Provisions against Shear or Diagonal Tension.** Numerous tests of beams reinforced with horizontal rods without stirrups or inclined reinforcement have shown that DIAGONAL CRACKS occur when the maximum shear over the cross-section is from 100 to 200 lb per sq in. Tests conducted on concrete with the purpose of eliminating all other stresses but direct shear have given a SHEAR STRENGTH of concrete of from 800 to 1 600 lb per sq in. The ordinary concrete beam has, therefore, a cross-section of sufficient area to withstand a SHEAR STRESS of 200 lb per sq in. The cracks always occur at points where a large

**SHEAR-STRESS** exists in combination with **MOMENT-STRESSES**. Under loads, **DIAGONAL-TENSION** failure occurs under the conditions of a simple beam under a uniformly distributed load, the conditions of supports. The inclination of the diagonal tension in the concrete is the result of two forces, changes, therefore, with the variations of

beams with horizontal rods only, that is, beams in which the web is reinforced by the concrete, the **SAFE SHEARING VALUES** to be used under the regulations are given in Table II, page 912. The **SHEARING-STRESS** is determined by dividing the total **VERTICAL SHEAR** by the effective depth, that is, the distance from the center of compression to the steel, by the width of the beam. The **MAXIMUM SHEARING-STRESS** in this case, not exceed 2% of the **COMPRESSIVE STRENGTH** of the concrete.

When the resistance of the concrete to shear is not sufficient, reinforcement must be provided by one of the following methods or combinations of them:

- 1. Providing vertical members;
- 2. Providing horizontal members;
- 3. Securely attaching inclined rods to the horizontals in such a manner as to prevent slipping;
- 4. Bending of a part of the longitudinal reinforcement at certain angles to provide against the diagonal tension and allowing sufficient amount of horizontal steel to remain to resist the direct tension.

It is customary to use the calculated **VERTICAL SHEARING-STRESS** and **DIAGONAL TENSILE OR WEB-STRESSES**. In all cases, the concrete must be able to carry its safe load, and it is ordinarily assumed that the total **VERTICAL SHEAR** is resisted by the web-reinforcement. When provided with web-members, the total **VERTICAL EXTERNAL SHEAR** should not exceed 6% of the **COMPRESSIVE STRENGTH** of the concrete. The Building Code of New York City specifies that the **SHEARING-STRESS**, when all the **DIAGONAL TENSION** is resisted by steel, shall not exceed 5 sq in. For beams in which part of the longitudinal reinforcement is provided by bent-up rods, the **MAXIMUM VERTICAL SHEARING-STRESS** shall not exceed 3% of the **COMPRESSIVE STRENGTH** of the concrete. The **SAFE SHEARING VALUES** in web-reinforcements may be determined by the following formulas:

$$P = V_s / l$$

for inclined 45°, not bent-up bars,

$$P = 0.7 V_s / l$$

where  $s$  is the horizontal spacing of the web-members,  $V$  the total vertical shear,  $l$  the effective depth from center of compression to center of tension in a single reinforcing-member. Fixing the **ALLOWABLE SHEARING-STRESS** at 5 000 lb per sq in, the spacing of web-members is expressed by the following formulas, when  $A$  is the cross-section of a web-member:

$$s = 16\,000\, A / V$$

$$s = 16\,000\, A / 0.7\, V$$

In determining the length of horizontals necessary to properly develop the bars, the same method may be employed as for plate girders.

remainder of the bar being carried up as an inclined member and carried over the top of the supports in continuous beams. The rods remaining at any point at the bottom or top must be of sufficient sectional area to carry the direct tension beyond this point. There must also be a sufficient length beyond this point to prevent slipping. Web-members must be so spaced that there will be a reinforcement intersecting every  $45^\circ$  line of rupture below the neutral axis. The New York City Code prescribes that the spacing of the web-members should not exceed three fourths of the depth of the beam in that portion where the web stresses exceed the allowable value for shear in concrete. Sufficient **BOND-STRENGTH** of web-reinforcement should always be provided in the **COMPRESSION-SIDE** of the beam. In **SIMPLE BEAMS**, that is, beams resting on two supports, the ends of the bars should preferably be bent into hooks. Where bent up through large angles, web-members should extend horizontally along the upper part of the beam for some distance.

**Attached Shear-Members.** Stirrups need not be firmly attached to the tensional reinforcement; but the allowable **BOND-STRESSES** and **SHEARING-STRESSES** in the concrete must not be exceeded in transmitting the stresses between stirrups and longitudinal rods. The stirrups and inclined members must also develop sufficient **BOND-STRESSES** to transmit the entire stresses for which they are designed, and they must sometimes be supplemented with anchorages in the compression-side of the beam. It is, perhaps, better to have them attached, as they will certainly assist in anchoring the tensional reinforcement. Different forms of stirrups and methods of attachment are used. In the Kahn system (Fig. 11) the stirrups form a part of the tensional reinforcement. The U form, either upright or inverted, is a very common form of stirrup, and may be made of either round or square cross-section, or a flat strap as shown in Figs. 10 and 11. The Hennebique system employs both inclined rods and vertical stirrups. In some cases, when the slabs and beams are constructed together, the slab-reinforcement is carried through the upper ends of the stirrups.

**The Bond between Steel and Concrete.** The **BOND** between the steel and concrete must not exceed the safe working value. If the bond is not sufficient, the rod will slip. Tension-rods must, therefore, never be too large to develop sufficient **BOND-STRENGTH** to transmit the stresses. Where bent-up bars are employed, the **BOND-STRESSES** in places, in both the straight and bent bars, will be higher than if all bars are straight. In cantilever beams the ends of the bars at the supports are fully stressed and the bars must be carried into the supports and anchored to develop this stress. In anchored bars, an additional length must always be provided above that required, on the assumption of **UNIFORM BOND-STRESSES**. Wherever possible, adequate bond strength should be provided throughout the length of the bar in preference to end-anchorage. Between plain bars and concrete the **BOND-STRENGTH** may be assumed to be 4% of the **COMPRESSIVE STRENGTH** of the concrete.

**The Breadth of a Reinforced-Concrete Beam of Rectangular Cross-Section.** The breadth of a rectangular beam, and of the stem of a T beam, as already indicated, is generally dependent upon the amount of reinforcement necessary, and it is equal to the sum of the diameters of the tension-rods, the required spaces between them, and the amount of concrete outside of the rods needed to resist the shearing-stresses and to protect the steel. When no stirrups are used in a beam it is necessary, also, to make the width of the concrete sufficient to resist the horizontal shearing-stresses. This width should be at least equal to the sum of the perimeters of the tensional reinforcing-rods. The amount of concrete to be provided below the steel is fixed by the requirements for proper protection of the steel against fire and corrosion. (Pages 955-960)

**Compression-Rods in Beams and Girders.** Steel reinforcement in the form of rods is sometimes provided ABOVE THE NEUTRAL AXIS in beams and girders for the purpose of providing additional COMPRESSIVE STRENGTH where there is not sufficient concrete above the neutral axis to resist the total compression. If steel reinforcement is to be used for this purpose, the steel should be placed as high as possible, and the allowable unit compression in the steel limited to the actual compression in the concrete at that point multiplied by the ratio of the modulus of elasticity of the steel to that of the concrete, as in the case of columns with vertical reinforcement. The use of STEEL IN COMPRESSION in beams and girders, however, is not recommended, since at best it is very uneconomical and the steel has a tendency to buckle and disrupt the concrete.

**Reinforced-Concrete Columns.** Reinforced-concrete columns are of three general types: (1) concrete with VERTICAL REINFORCEMENT near the outer surfaces; (2) concrete wrapped with SPIRALLY-WOUND WIRE or with metal bands; (3) concrete with a METAL CORE.

**Lengths of Columns.** The lengths of reinforced-concrete columns are variably limited by different authorities as follows, the figures being in each case the RATIO OF THE LENGTH to the LEAST LATERAL DIMENSION:

New York.....	15
Chicago.....	12
Philadelphia.....	15
St. Louis.....	15
Cleveland.....	15
Baltimore.....	16
San Francisco.....	15
Buffalo.....	15
Detroit.....	15

New York limits, also, the least side or diameter to 12 in, and San Francisco to 10 in.

**Vertically-Reinforced Columns.** In determining the strength of columns with VERTICAL REINFORCEMENT, the steel is assumed to carry a load per square inch equal to the working load per square inch on the concrete times the ratio of the moduli of elasticity of the steel and concrete. The allowable stresses, ratio of moduli, etc., are given in Table II, page 912. For example, in New York a load of 500 lb per sq in is allowed on the concrete, and 15 times 500, or 7500 lb per sq in on the steel, 15 being the ratio of the moduli, as fixed by the regulations, 1:2:4 concrete and steel. Not less than  $\frac{1}{2}\%$  nor more than 4% of vertical reinforcement should be used in reinforced-concrete columns. The reinforcing-rods should be tied together horizontally at intervals of not more than the least side or diameter of the column. This prevents, to a great extent, the buckling of the reinforcement under load and the consequent splitting of the concrete. The VERTICAL REINFORCEMENT, in order to serve its purpose of taking up the bending in the column, should be placed as near the outer surfaces of the column as possible, consistent with proper protection of the steel. (See page 958.) If bending is possible in the longitudinal steel, due to bending, the bars must be fixed to resist the stress. In the DISPOSITION OF THE STEEL the same precautions are necessary as in the case of beams, in order to avoid a too close spacing of the reinforcing-pieces or an excess of reinforcing-material. (See page 937.) As the concrete in columns is generally poured into the molds at the extreme top, it is particularly important to keep the interior free from overlapping steel across the column. In columns in which the steel is assumed

to furnish part of the COMPRESSIVE STRENGTH, it should be made continuous from the columns of one story into those of the stories below. The rods extending from one column may be connected with those above or below by means of pipe-sleeves.

**Laterally-Reinforced Columns.** Tests made on HOOPED CONCRETE COLUMNS at the University of Illinois in 1907, at the Watertown Arsenal in 1906, and at the University of Wisconsin in 1906 and 1907, show that the ultimate compressive strength of such columns is increased from 500 to 1 000 lb per sq in for each percentage of hooping employed. The increase of strength is due to the LATERAL COMPRESSIVE STRESSES developed by the restraining action of the hoops or bands at right-angles to the direct compressive stresses. Below the limit of elasticity, however, very little stress is developed in the lateral steel, and the tests show that at an early stage, the deformation or shortening of the column is equal to that of plain concrete. With further loading, the laterals begin to work and prevent failure, thus increasing the so-called TOUGHNESS of the column and the ultimate compressive or breaking strength. This effect has been variously allowed for by considering the hooping-metal equivalent to and replaced by imaginary longitudinals. Considère and other investigators have shown that the hooping is equivalent to 2.4 times as much longitudinal steel. It is generally conceded that hooping permits of a somewhat higher unit stress in the concrete. The New York City Building Code permits an axial compression in such columns, having not less than  $\frac{1}{2}\%$  nor more than 2% of hoops or spirals spaced not farther apart than one sixth the diameter of the enclosed column nor more than 3 in, and having not less than 1% nor more than 4% of vertical reinforcement, not to exceed 500 lb per sq in on the concrete within the hoops or spirals nor 7 500 lb per sq in on the vertical reinforcement, plus a load per square inch on the effective area of the concrete equal to twice the percentage of lateral reinforcement multiplied by the permissible tensile stress in the lateral reinforcement. St. Louis and Cleveland permit 2.4 times the volume of hooping to be considered as longitudinal reinforcement; Chicago 2.5 times; and Cincinnati 2.5 times.

**New York Requirements Expressed by Formulas.** The safe load for reinforced-concrete columns according to the requirements of the New York Building Code may be determined by the following formulas, in which

$W$  = total safe load, in pounds;

$A_c$  = the effective cross-sectional area of concrete, in square inches, which in the case of columns with longitudinal reinforcement only, may be taken as the entire area, and in the case of hooped columns is limited to the area within the hoops;

$A_s$  = the cross-sectional area of the longitudinal steel, in square inches;

$p$  = percentage of lateral reinforcement (hooping), that is, the volume of hooping divided by the volume of the concrete enclosed within the hooping, for each unit length of column;

$S_c$  = allowable compressive stress in the concrete, in pounds per square inch, which is taken at 500 for 1 : 2 : 4 concrete, and at 600 for 1 : 1½ : 3 concrete;

$S_s$  = allowable compressive stress in the steel, in pounds per square inch, which is taken at 7 500 when 1 : 2 : 4 concrete is used, and at 8 000 when 1 : 1½ : 3 concrete is used;

$S_h$  = allowable tensile stress in the hooping steel, in pounds per square inch, which may be taken at 35% of the elastic limit, but not more than 20 000.



longitudinal reinforcement only,

$$W = A_c S_c + A_s S_s$$

steel must not be less than  $1\frac{1}{2}\%$ , nor more than 4% of the and the reinforcement must be secured against displacement spaced not farther apart than 15 diameters of the vertical 12 in.

is the safe carrying capacity of a 12-in square column of enforced in each corner with  $\frac{1}{8}$ -in square bars?

area of the concrete may be taken at  $12 \times 12 = 144$  sq in. has a sectional area of 0.7656 sq in. The area of the steel 1 sq in, a little over 2% reinforcement. The allowable and steel are 500 and 7500 lb per sq in, respectively. Hence

$$14 \times 500 + 3.06 \times 7500 = 94950 \text{ lb} = 47\frac{1}{2} \text{ tons}$$

ns,

$$W = A_c S_c + A_s S_s + 2 p A_c S_h$$

inforcement not less than 1%, nor more than 4%, and n  $\frac{1}{2}\%$ , nor more than 2%, the hooping being spaced not one sixth of the diameter of the enclosed column, and at

ine the maximum load that should be placed on a 24-in  $1\frac{1}{2} : 3$  concrete, with spiral hooping of  $\frac{5}{16}$ -in cold-drawn pitch, and reinforced longitudinally with six 1-in round just inside the hooping, and fastened to it, the concrete ide the hooping.

ective sectional area of the concrete has a diameter of re  $20 \times 20 \times 0.7854 = 314.16$  sq in. For an inch in height, the concrete is 314.16 cu in. The area of a 1-in round

The area of longitudinal steel is  $6 \times 0.7854 = 4.71$  sq in, cross-sectional area of  $\frac{5}{16}$ -in wire is 0.0767 sq in. The wire is 62.75 in, and as the turn is made in a height of its for an inch of height of the column is  $\frac{1}{4} \times 62.75 \times 0.0767$   $\frac{1}{2}\%$ . The working stress per square inch for the con- longitudinal steel 7200 lb, and for the hooping 20000 lb.

$$600) + (4.71 \times 7200) + (2 \times 0.005 \times 314.16 \times 20000) \\ = 285240 \text{ lb, or } 142.5 \text{ tons}$$

**Reinforcement.** At the top or base of the columns in ping should be made to continue through the floor-con- tain conditions, when the floor-construction is practically mns, thus affording good lateral support, equal to the better to omit the wrapping and avoid the possible com- orcement from column, girder, and floor-construction and ng of the bond of the concrete. The materials used for the teel wire or steel bands. When wire is used it is spirally s through the full length of the column. The ends of the he column and turned down to such an extent that when, poured and set, there will be sufficient anchorage to resist

the tension in the wrapping due to the outward pressure of the concrete. When metal bands are used, as in the Cummings system, care must be taken to make the riveted joints in the bands as strong as the bands themselves. A form wrapping that has the merits of rapidity and ease of erection is shown in columns used in the Bush Terminal Warehouse, Borough of Brooklyn, New York City, described on page 958.

Fig. 20. Concrete Column with Steel Core

**Metal-Core Columns.** The object of this type of column is to provide construction for tall or heavily loaded buildings that will have the necessary strength and yet not encroach too seriously on the floor-space. For this type of column some engineers advocate placing a steel core through the axis of concrete, the steel taking the bulk of, if not all of, the load.\* "A rational method of design is to determine the strength of the steel column by the use of the ordinary formula for the proper  $l/r$  of the column and to consider the concrete of the

\* Trans. Am. Soc. C. E., Vol. XIV, Part E, page 556.

have a stress-value proportional to the strength of plain con-

n H. Burr designed a column (Fig. 20) for the McGraw Building, New York. The steel core has sufficient strength as a column, independent of concrete, to carry the entire dead load coming upon it, the stresses in the concrete in no case greater than those allowed on steel columns under the

Building Code, considering the ratio of length to radius of gyration. Therefore, those stresses were not allowed to exceed 9 000 lb per sq in in any case. Live loads were provided for by placing enough concrete within the column-work to prevent the stress on the concrete from exceeding 750 lb

This is one twelfth of the maximum allowable load on the steel. The concrete outside of the steel was considered only as a protection against fire and corrosion. Columns of this type should be designed with caution. They should not be relied upon to tie the steel units together or to transmit load from one unit to another. The units should be tied together by tie-plates or lattice-bars in conformity with the standard practice for structural

For high percentages of steel, the concrete will develop low unit stresses and caution should, therefore, be used in placing dependence upon the

**Mixtures of Concrete.** Increasing the proportion of cement in a concrete increases the ultimate strength of the concrete proportionally and is desirable in designing columns with smaller cross-sectional area. The increased strength is also accompanied by a higher modulus of elasticity. Therefore, the employment of a rich mixture also permits of higher proportions of steel and consequently a more economical design. The stresses in a monolithic member, however, may be considerably reduced by the excessive shrinkage of rich mixtures, which have a tendency to crack. The New York Building Code provides that "in concrete columns the load on the concrete may be increased twenty per cent when the fine and coarse aggregates are carefully selected and the proportion of cement to total aggregate increased to one part of cement to not more than four and one-half parts of fine aggregate, and three parts of coarse aggregate, in proportion as will secure the maximum density. In such cases, however, the compressive stress in the vertical steel shall not exceed seven thousand pounds per square inch."

**Lateral Reinforcement.** Robert A. Cummings of Pittsburgh, Pa. (The Welding Company), following a European practice, has applied a method of reinforcing compression-members by placing horizontal wire spirals at right-angles to the main compressive stresses. This practice is based upon the theory that the failure of a concrete prism will take place along lines in the direction of the applied load. The method has been very successful in the construction of the heads of precast concrete piles, driven by hammer.

**Columns.** When a building for any reason need not be treated as a rigid structure, space and time may be saved by using CAST-IRON or STEEL COLUMNS. In such cases the column-connections must be designed with care for the concrete construction and so that there will be a continuous construction; for the great advantage in reinforced-concrete columns lies in its MONOLITHIC character. When cast-iron columns are used, the ends of the columns may be cast with openings through which the

\* University of Illinois Bulletin, No. 56, 1912.

† Proc. Am. Soc. C. E., Feb., 1913, page 153.

reinforcement may pass from one side to the other. Fig. 21 shows how this has been done in a building at Gay and Christopher Streets, New York City without impairing the strength of the columns at the connections.

Flanges F to have a combined Area equal to the Area of the Column they have to support. to be cast on at top of Supporting Column.



Fig. 21. Connections for Cast-iron Columns and Reinforced-concrete Construction

**Steel Columns.** In STEEL COLUMNS it is simpler to provide connection between the reinforcing-rods and the steel shapes of the columns. When reinforcement does not go through the columns, some rods should be placed outside of them to tie as much as possible the concrete on one side to the other.

**Eccentric Loads.** Bending stresses due to LATERAL and ECCENTRIC loads must be computed so that the combined direct and bending stress does not exceed the allowable maximum stress for axial compression. Formulas for eccentric loading on columns are given in Chapter XIV, pages 453 and 484.

**Concrete Walls.** If not reinforced, concrete walls are generally required to be of the same thickness, for given conditions, as brick walls. Under such circumstances they are not as economical as brick walls. If reinforced and used as bearing-walls, they can be reduced to about two thirds the thickness of brick walls, provided, however, that the load on the concrete does not exceed the load per square inch permitted on reinforced columns. The ratio of unsupported height to thickness should not exceed that fixed for columns. For span walls, supported entirely on girders, the minimum thickness should be 12 in. Such walls should be reinforced with not less than  $\frac{1}{4}$  lb of steel per square foot of wall, in the form of rods placed vertically and, less frequently, horizontally.

**Reinforced-Concrete Footings.** (See, also, pages 186, 225, and 226.) The principles underlying the design and construction of reinforced-concrete footings are the same as those applied to other types of footings. In wall, pier, or column footings, the overhang or off-set must be considered as an INVERTED CANTILEVER loaded uniformly with a load per square foot equal to the load per square foot imposed on the underlying soil. The reinforcing-rods will then necessarily be placed near the lower surface of the footing and the size and number determined as shown on pages 937, 938, and 979. A detail often overlooked in reinforced

ings is the tendency to **SHEAR** at the edge of the wall, pier, or column. When footings would otherwise become very **ECCENTRIC**, cantilevers resorted to, the same as for steel construction. (See pages 165 to 169, and 982.) The maximum bending moments are determined and the design as described on pages 925 to 932, and 978 to 982. Steel in footings should be protected by at least 3 in of concrete.

**Design of Reinforced-Concrete Footings.** Great economy over steel-footings of other types of footings may often be effected by the use of **REINFORCED-CONCRETE FOOTINGS**. The cost of the latter type will vary from 20 to 30 per cent of the cost of a corresponding **STEEL-GRILLAGE FOOTING**. This difference should be counted for. The amount of excavation for the reinforced footing is much less than for the steel grillage. A smaller amount of concrete is used in this concrete is considered in the calculations for strength; whereas in the steel grillage, the concrete is chiefly provided for incasing and protecting the steel. The amount of steel is much less, being used only to supply the tensile resistance of the construction, the compressive strength being supplied by the cheaper material, concrete. Incidentally, the protection of the reinforced footing is generally more certain than in the steel-grillage footing.

**Concrete Piles.** Concrete piles are discussed in Chapter II, pages 196 to 200. Some of the types are there described.

**Connections in Reinforced-Concrete Construction.** Much good judgment should be played and must be exercised in the design of the details in these connections. The great value of reinforced-concrete construction over other types is the possibility of securing great **RIGIDITY**. This can only be attained if the result is as nearly **MONOLITHIC** as possible. We then have mass to resist vibration and this advantage, in the case of workshops or factories in which heavy machinery is readily seen. The reinforced-concrete buildings which survived through the severe San Francisco earthquake in May, 1906, in good condition were those in which attention had been given to the details and connections. To secure a monolithic character requires **CONTINUITY** not only in the concrete but also in the reinforcement. This often means that there is a network of steel at the connections. If this is carried to excess, the **BOND** and **CONNECTION** of the concrete is apt to be broken, even when the spaces between the reinforcement are thoroughly filled. But when there is such a network of steel reinforcement like a sieve and the spaces are not readily filled. For this reason it is necessary to use a richer mixture at the columns and to keep the aggregate as small as possible.

The connections of floor system to columns are particularly troublesome in this respect, and partly for this reason and partly to insure rigidity, reinforcement should be provided under the girders at the columns, with metal reinforcement near the inclined surfaces of these brackets.

**Reinforced-Concrete Stairs.\*** Some of the most interesting work that has been done in reinforced concrete has been the construction of stairs. The reinforcement in the form of comparatively small, limber bars, can be adapted to any shape for which molds can be constructed, and when a wet, rich mixture and a small aggregate is used, little or no difficulty need be experienced. As an example of such work, the stairs in the residence of G. W. Brown in New York City, may be cited. When these stairs were five feet wide, a test of their strength was made, without distress, by dropping a barrel of six bags of cement, weighing about 380 lb, from the floor above to

\* See, also, pages 900 and 983.

the intermediate platform, a distance of 11 ft. No injurious effects were noticed.\*

#### 4. Types of Reinforced-Concrete Construction †

**Mill-Construction.** In localities where the cost of labor is high and where the conditions cause more or less congestion, it is probably more economical to use brick instead of concrete for the walls. In such cases the type of construction is similar to ordinary MILL-CONSTRUCTION. Provision must be made to anchor the beams and girders, and this can be done by bending the ends of reinforcing-rods so that they will extend horizontally into the walls on each side.

**Skeleton Construction.** The SKELETON TYPE of construction seems to be the form best adapted to reinforced concrete. A framework of columns, girders, beams, and flooring is built, as in steel construction, the wall-girders and columns of course, being designed to carry the weights of the outside walls as well as that part of the floor-loads and live loads which comes on them. The work in this type of construction, can generally progress more steadily than in the MILL-CONSTRUCTION since the concrete work need not be stopped at any time to allow for the brickwork to be carried up, if brick is used for the walls. In the SKELETON CONSTRUCTION any type of outside wall may be used; brick, concrete, etc. In some cases the panels are simply filled in with brickwork, 8 or 12 in. thick, leaving the concrete columns and girders showing between the brick panels. For walls situated on property-lines where adjoining buildings are to be erected, this is not objectionable. If the wall remains exposed and a good appearance is a consideration, the columns and girders can be treated architecturally to set off the brickwork; or the brickwork may be continued as a facing over the outside of the columns and girders. This was done in some of the Terminal Warehouses, Borough of Brooklyn, New York City.‡ To thoroughly secure this brick facing, galvanized anchors were placed in the concrete columns and girders as they were erected, projecting sufficiently to bond into the brick joints. In using concrete for the panels the sides of the columns are cast with pockets, grooves, or recesses to receive the panels, which, as in the case of brickwork, are most satisfactorily and most economically built after the removal of the molds from the skeleton frame. In the Marlborough-Blenheim Hotel, Atlantic City, N. J., the panels are filled in with hard-burned terra-cotta tiles and a stucco applied on the outside. This makes a comparatively light construction and affords good insulation. The particular advantage in the SKELETON TYPE of construction, especially for workshops and factories, is the possibility of large window-areas affording light and ventilation.

**System M.** A type of construction known as System M has been developed by the Standard Concrete Steel Company of New York City (Fig. 22). It consists of a light steel skeleton frame designed to carry the dead load of the entire structure, except that the columns are designed to carry the gross loads. The structure is incased in concrete, making ultimately a reinforced-concrete construction.§ Its advantage consists in its adaptation to the erection and inspection of the steel reinforcement before even the centers or molds are placed in position. Under congested conditions, such as prevail in large cities, it is a rapid form

\* For a detailed description, see *Cement*, Jan., 1904, and *Engineering Record*, Dec. 1903. For other examples of stair-construction, see *Engineering News*, June 30, 1903.

† See, also, Chapter XXV.

‡ For a description of this building, see *Engineering Record*, March 3, 1906.

§ For fuller description, see *Engineering News*, April 25, 1907, and *Engineering Record*, June 22, 1907.

on. The use of the steel in this type is, however, not economical. To get the necessary strength in the steel framework, shapes must be used which do not offer the amount of adhesion that should result from the

**Fig. 22. System M Type of Reinforced-concrete Construction**

metal used. Furthermore such shapes must necessarily be subjected to bending, which tends to break the bond between concrete and steel.

**Drop-panel Construction.\*** In this form of construction beams and girders are eliminated almost completely, if not entirely, and the slab is made to rest directly on the columns; the tops of the columns are enlarged into extended caps. This method of construction employs a shallower floor construction than is ordinarily used. The floor-centering, too, for purposes of erection, is somewhat simplified. In those forms of slabs in which the lower surface is all in one piece the slab may be of uniform thickness between the edges of the column-caps; a portion of it, symmetrical about the column, may be thickened to form a **COLUMN-DROP**, or the slab may be thickened to form a band or shallow cap between columns, with a paneled ceiling at the center of the panel.

In the method of reinforcing the slab and columns, a number of systems have been developed which may be divided into four general classes: (1) the **TWO-WAY SYSTEM**; (2) the **FOUR-WAY SYSTEM**; (3) the **THREE-WAY SYSTEM**; and (4) the **CIRCUMFERENTIAL SYSTEM**. In the **TWO-WAY SYSTEM**, the reinforcement is placed in two direct bands between the columns in both directions, with an interior band of reinforcement in two-way rectangular bands on the remaining panel-area at the center. In the **FOUR-WAY SYSTEM**, the reinforcement is placed in two direct bands in the four principal directions, and in two diagonal bands which cross the panel between columns. In the **THREE-WAY SYSTEM** the reinforcement is placed in three bands directly connecting the columns and passing over the column-caps. In the **CIRCUMFERENTIAL SYSTEM**, circumferential reinforcement is placed around the columns, with bars radiating from the column-centers. Concentric bands of reinforcement are also placed at the center of the sides joining the columns, which overlap the circumferential reinforcement at the columns. The center of the panel is reinforced in a similar manner. Some of the modifications developed are modifications of the above or a combination of two or more of the types described. The principles of design are based on empirical data determined by extensometer tests made on completed buildings.

**System M.** This is a **TWO-WAY SYSTEM** developed by the Condor Co., Chicago, Ill. It is constructed either with a slab of uniform thickness or with a drop-panel, or with a paneled ceiling. Each panel of the slab is

\* See, also, Girderless Floors, Chapter XXV, page 993.

divided into two sets of strips, called the **MAIN-SLAB STRIPS** and the **MID-STRIPS**, which are designed as flat, shallow beams.

**Corr-Plate System.** This type of construction has been developed and installed by the Corrugated Bar Company, Buffalo, N. Y. The construction is similar to other **TWO-WAY SYSTEMS** and is installed either with or without drops. The reinforcement is distributed across the entire slab, with varying spacings to resist the stresses determined experimentally.

**Mushroom System.** The **MUSHROOM SYSTEM**, invented by C. A. P. Turner, Minneapolis, Minn., is one of the earliest of the flat-slab constructions. A striking and essential feature which gives this system its name is the gradual spreading out of the column at the top to form a cap, the diameter of which is seven sixteenths of the sum of the distances between columns in the direction of the sides of the slab. The longitudinal column-reinforcement is bent to follow the curved outer surface of the cap, and the cap is reinforced both radially and circumferentially. The slab-reinforcement is placed at the top of the slab over the columns and allowed to sag to a catenary curve with the low point near the bottom of the slab at the middle of the span. The thickness of the slab varies from  $\frac{1}{3}$ s to  $\frac{1}{2}$ o of the shorter distance between the column-centering. This is essentially a **FOUR-WAY SYSTEM** with the added features described above.

**The Cantilever Flat Slab**, designed by the Concrete Products Company, Chicago, Ill., is another type of **FOUR-WAY SYSTEM**. It differs from the one described in the preceding paragraph mainly in the construction of the column-head. The column-bars are not bent to the shape of the cap but continue up straight. The horizontal cap-reinforcement is provided by a shop-made frame of radial bars, held together by a Diamond Bar which is intended to resist the circumferential stresses. The diameter of the cap is about  $\frac{1}{10}$  the span and the thickness of the slab about  $\frac{1}{3}$ s the span. Whenever necessary to provide for resisting shearing-stresses and bending-stresses around the column, the slab is increased in thickness at that point, forming, in appearance, an extended cap at the column-head. Later extensometer tests have proved the use of radial reinforcement with rings around the column-heads to be inefficient, and they therefore have been abandoned.

**Three-Way System.** This system was invented and patented by David Morrow, Cleveland, Ohio. The columns are located at the apexes of equilateral triangles, making equal the bands of steel between the columns. The reinforcement over the columns is placed in three instead of the four layers of the **FOUR-WAY SYSTEMS**. Flaring circular caps, with hexagonal or circular drops, are provided over the columns.

**S. M. I. System.** This system was invented and patented by Edward Smulski, and is controlled by the S. M. I. Engineering Company, Boston, Mass. Circumferential and radial reinforcement is placed in both the top and bottom of the slab, with trussed bars extending both rectangularly and diagonally between the columns (Fig. 23). The radial bars are provided with a semicircular hook to transfer the stresses into the concrete by bond, and to engage the ring reinforcement in the center of the panel. To prevent cracking on the top of the slab between columns, additional short, straight bars are sometimes used.

**Patents for Flat-Slab Construction.** In 1901 and 1902 patents were granted to O. W. Norcross, covering girderless floor-construction reinforced with bands of wire netting extending from column to column. Application for the original C. A. P. Turner patents was made in 1905. In 1915 the United States Courts held that the Norcross patents covering girderless floors were fundamental, and that bands of bars were, to all intents and purposes, the same






Fig. 23. S. M. I. Flat-slab System

e netting. It would seem, therefore, that any system of floor-con-  
 vention depending upon bands of bars running either diagonally or crosswise  
 to column constitutes an infringement of the Norcross patents.  
 promoters of flat-slab construction in the United States are now  
 or the Norcross patents; but several other United States patents  
 anted covering special methods of construction and reinforcement.  
**tion Hollow-Tile and Reinforced-Concrete Construction.** In  
 minimize the cost of centering, the floor-construction shown in Fig. 24  
 vided. It consists of a series of reinforced-concrete beams with  
 between them of the width of the hollow-tile blocks. In erection, a

flat centering is used, which, however, need not even be continuous. Planks few inches wider than the concrete beams, are placed under the spaces to be filled by the beams, and the tiles are laid in rows and supported along their edges by the planks, thus forming the sides of the molds for the beams. The reinforcement is placed and the concrete poured, with or without floor-plates, as the necessities of the case may require. Care must be taken in pouring the concrete

Fig. 24. The Combination Tile and Reinforced-concrete System

that the tiles are not displaced sidewise. The tiles should fit closely at the joints, otherwise the finer particles of the concrete are liable to flow into the joints, either making the concrete porous or requiring more cement and sand than necessary. This form of construction, besides being economical in centering, offers the advantages of a flat ceiling without the application of lath and, in reconstruction particularly, of freedom from condensation.

**The Floretyle Systems.** A floor-construction similar to the hollow-tile construction just described has been devised by the Truscon Steel Company, Youngstown, Ohio, in which forms of corrugated sheet steel, called FLORETTILES, replace the hollow tiles. The Floretyles are furnished in lengths of 28½ and 36 in., and in depths of 6, 8, 10, and 12 in. The width at the base is 20½ in., with the sides tapering at an angle of 7° 30'. They are furnished in two types, either with serrated edges for use with the company's fly-rib lath for ceilings, or with straight edges for use where paneled ceilings are required. Other makes of metal forms used in the construction of reinforced-concrete floors are the G F STEEL TILES of the General Fireproofing Company, Youngstown, Ohio, and the WISCOFORMS of the Witherow Steel Company, Pittsburgh, Pa. Besides a reduction in weight of finished floors, the additional advantages in the use of these steel tiles or forms over the terra-cotta fillers are: Greater economy in centering, larger covering capacity, less bulk in shipment because the forms can be nested, and less danger

	6 in	8 in	10 in	12 in	14 in
Average weight, in pounds per square foot . . .	40.100	46.000	53.500	61.000	72.600
Cubic feet of concrete per square foot of floor . . . . .	0.278	0.319	0.371	0.423	0.500
Core-area, percentage of section . . . . .	58.300	61.700	63.000	63.800	62.300

on of water from the concrete and of the flooring-out of the cement at

A concrete floor of **C & F STEEL TILES**, spaced so as to make 4-in centers, 24 in on centers, and having 2 in of concrete above the tiles, with is said to have the properties shown in the table on page 952, and the depth of tiles used.

**y Tile Systems.** Similar in general principle but using reinforcement in two directions, at right-angles with one another, is the **COMBINED HOLLOW-CONCRETE FLOOR**, controlled by the Burchartz Fireproofing Company, New York City, under the Burchartz patents (Fig. 25). This system uses terra-cotta blocks, channels, and soffits, providing uniform flat ceilings. plaster can be applied without the use of metal lath. In this case the floor is treated as a slab supported on four sides. (See page 936.) The concrete is prevented from running into the hollow spaces of the tile by the use of terra-cotta channels as shown.

**ies.** In the **FLOREDOME-CONSTRUCTION**, put on the market by the American Concrete Tile Company, Youngstown, Ohio, the tile spacing-blocks of the **TWO-WAY SYSTEM** are replaced by rectangular dome-shaped steel forms with the open top. Lightness in floor-weight, ease and rapidity of installation, and economy are the advantages claimed. The ceiling-treatment in this construction is similar to that in the Floretyle system. The base of the domes is 12 in square; the depth varies, being 6, 8, 10, or 12 in.

**of Combination Systems.** While the tiles may under favorable conditions add to the strength of the **COMBINED FLOOR-CONSTRUCTION**, the chances of faulty workmanship are too great to consider them in the calculations.

In the floors reinforced in one direction, the construction should consist of a series of either rectangular beams, or T beams, as the concrete is poured to or above the top face of the tiles. The **TWO-WAY REINFORCED FLOOR** should be treated as if it consisted of a slab supported on four sides by a series of intersecting rectangular beams, or T beams. If the concrete is to be treated as a series of T beams or as a slab, the concrete should be poured at least 2½ in above the top surface of the slab and the tiles or fillers should be 10% of the volume of the construction.

**Pre-molded Construction.** The **UNIT OR SEPARATELY-MOLDED CONSTRUCTION** consists of precast reinforced-concrete members, columns, girders, beams, and slabs, either molded at the site of the building, or made at the factory and transported to the site ready for use. The various members are swung into place in the same manner as steel is erected, and fitted together in the building by interlocking reinforcement and poured grouting. Great economy is obtained by this method of erection on account of the saving of forms. Maximum economy, however, cannot be obtained on a building operation of less than 10,000 sq ft, as economy is obtained by the greater use of the forms and the reduction of the erecting-crews with the particular type of building. But under certain conditions, economy can also be shown on an operation involving 10,000 sq ft. The advantages of this construction are said to be: a large number of uses possible of one set of forms, especially on a large operation; a small number of men required, due to the extensive use of locomotive engines, trucks, derricks, etc.; the ease with which the units may be moved and being poured and before entering the building; and the fact that all work takes place before the units enter the structure, thus eliminating delays in the building. The disadvantage of such a system, however, lies in the lack of sufficient rigidity in tall, separately-molded unit construction. All floor-members must be designed and cast as simple, **NON-COMBINED** members, with the reinforcement left projecting at both ends to serve for

**Fig. 26. Repetitive Two-way Tile-and-concrete System**

structure together. These junctures are made after the units are in place, and supported by a pouring of rich concrete. For tall structures more feasible to erect a light structural-steel frame and employ the units only. (See Chapter XXIII, page 854.) The saving in cost is particularly in low buildings, and more especially in one-story structures having been erected at a saving of from 10 to 20% over ordinary construction. Methods of interlocking the units and providing details are constantly being improved and a series of tests of the strength of such connections is being carried on by the Unit Construction Company, St. Louis, Mo. There are under construction, or already completed, buildings of this type installed by the above company, including five-story buildings at the National Lead Company, at St. Louis, Mo., Kansas City, Mo., Pittsburgh, Pa.; a three-story building for the Ohio Cultivator Company, Columbus, Ohio; five acres of car-barns at Philadelphia, Pa.; and approximately sixteen-and-a-half acres of cotton-warehouses at Memphis, Tenn. The Engineering Company of New York City has erected five-story buildings with its Unit system, in Boston, Mass.

## Fire-Resistance of Reinforced-Concrete Construction

**Non-Conductivity of Reinforced Concrete.** Concrete is a poor conductor of heat. In this fact lies whatever virtue it has as a fire-proof material.† A report made by Professor Woolson of Columbia University, New York, presented at the 1907 meeting of the American Society for Testing Materials, gave the following results:

"All concrete mixtures when heated throughout to a temperature of 500° F. will lose a large proportion of their strength and elasticity, and this fact must be well remembered in designing."

"All concretes have a very low thermal conductivity, and therein lies their known heat resisting properties."

"As a result of this low thermal conductivity, two to two and one-half inches of concrete covering will protect reinforcing metal from injurious effects during a period of any ordinary conflagration (provided, of course, that the metal is in place during the fire)."

"Reinforcing metal exposed to the fire will not convey by conduction a dangerous amount of heat to the embedded portion."

"The gravel concrete was not a reliable or safe fire-resisting aggregate."

**Strength of Reinforced Concrete.** If its NON-CONDUCTIVITY were taken into account in the fire-proof character of concrete, the minimum thickness for the protection of the steel could be easily determined. But the strength of the concrete is more or less affected when exposed to extreme heat. Effort has been made to determine this effect and a summary of the results is reported by Professor Woolson of Columbia University, New York, in Tables XII and XIII.

† *Engineering Record*, Vol. 60, page 643; *Engineering News*, Vol. 58, page 5; *Professional Association of Cement Users*, 1910, page 391.

Remembered that in this and succeeding paragraphs on the fire-resisting properties of concrete, only such material as is used in reinforced concrete, is considered. Under concrete as a fire-proof material is discussed in Chapter XXIII,

*Engineering News*, Aug. 15, 1907, page 168.

*Proc. for Test. Mats.*, Vol. IV, page 433.

**Fire Tests on Reinforced Concrete.** The EFFECT OF FIRE on reinforced concrete has been studied in a number of tests made by the building authorities of New York City and Philadelphia, and in some of the conflagrations in this country, notably at San Francisco. The tests to which the sample full-scale constructions have been subjected are similar to the test described in Chap. XXIII, page 827.\*

**Table XII. Tests of Concrete Blocks Heated on All Sides †**

Specimens, 6 by 6 by 14-in prisms; proportions 1 : 2 : 4  
Age 2 months; temperature 1500° F.

Treatment	Aggregate			
	Limestone	Trap-rock	Cinder	Gravel
Modulus of elasticity, At 200 lb per sq in:				
Unheated.....	6 000 000	3 430 000	1 090 000	8 000 000
Heated 3 hours.....	200 000	150 000	49 500	.....
Heated 5 hours.....	.....	129 000	571 000	.....
At 400 lb per sq in:				
Unheated.....	6 000 000	4 355 000	960 000	6 887 000
Heated 2 hours.....	285 000	222 000	.....	.....
Heated 5 hours.....	.....	188 000	.....	.....
At 800 lb per sq in:				
Unheated.....	5 647 000	4 355 000	915 000	6 000 000
Heated 3 hours.....	425 000	348 000	.....	.....
Breaking-load in lb per sq in:				
Unheated.....	2 740	3 140	1 400	2 780
Heated 3 hours.....	1 345	1 400	547	.....
Heated 5 hours.....	870	997	504	.....

**Table XIII. Concrete Blocks Heated on One Face Only ‡**

Specimens, 6 by 6 by 14-in prisms; proportions 1 : 2 : 4  
Age 2 Months; temperature 1 500° F.

Treatment	Aggregate	
	Limestone	Trap-rock
Modulus of elasticity. (Blocks heated 5 hrs.)		
At 200 lb per sq in.....	293 400	200 000
At 400 lb per sq in.....	521 700	268 000
At 800 lb per sq in.....	730 700	379 000
Breaking-load in lb per sq in.....	1 840	1 705

\* For a partial list of these tests, see Table in Proc. Am. Soc. for Test. Mats., Vol. V, page 128. Several tests have been made since that report was submitted.

† Proc. Am. Soc. for Test. Mats., Vol. VI, page 446.

‡ Proc. Am. Soc. for Test. Mats., Vol. VI, page 448.

lusion, from a study of the tests in detail,\* shows that to a depth about 1 in, the concrete is seriously impaired and easily washed off by a applied to the surface. Any stone containing an appreciable per-carbonate of lime will calcine and may cause failure. Where the con- poorly designed, allowing an excessive deflection, the fine cracks etc below the steel will open to such an extent as to permit the heat metal reinforcements. When the reinforcement is such as to pro- of weakness in the concrete there is liable to be a flaking off of the l a consequent exposure of the metal.

**Fire Tests of Reinforced Concrete.** The EARLIEST TEST of a re- crete building in an actual fire occurred in 1902, in the four-story re Pacific Coast Borax Company, at Bayonne, N. J. The roof of was of wood, and with the contents of the building, was destroyed The only damage suffered was a break in the top floor caused by heavy tank that had been supported by the roof. At the same mining building constructed with unprotected steel posts and beams into a tangled mass of metal.

**the Baltimore Fire.** In the Baltimore fire there was but one oncrete building of the three exposed to the fire, from which any fair an be drawn. In one of the buildings, the concrete construction destroyed, but this was probably due to the falling walls and the her non-fire-proof parts. In a second building, the heavy rein- ete floor of a banking-room came out practically unharmed; but it osed to severe fire. The third structure was, however, exposed to The contents of the building were destroyed and a large part of the : walls fell. The floors, five in number, were all of reinforced con- ted on concrete columns, having replaced an old wooden-joist con- A test made after the fire showed that the floors were still strong istain the loads for which they were designed, although the floor- racked. The girders were cracked longitudinally near the lines of ment, and the columns were spalled to such an extent as to expose reinforcement. It would have been difficult to restore the building ould resist another such attack.†

**the San Francisco Fire.** The EFFECTS OF THE FIRE ON concrete in the conflagration immediately following the San Francisco earth- 6 are summed up in the following paragraph from the report of a engineers that investigated the subject.

floors generally had hung ceilings, and, where thus protected, were Where exposed, the concrete is in most cases destroyed, for instance, Rialto, and the Aronson Buildings, and the Crocker Warehouse. is dry, and while in many cases hard, yet all the water has been nd it may be said to be destroyed, even if able to support weights. gs of wood invariably burned, adding to the destruction. Sleepers y burned. Surfaces of cement mortar fared much better, the lino- g remaining practically intact."‡

ng the report, Mr. A. L. A. Himmelwright, who made a personal the ruins, concludes that reinforced concrete is inferior as a fire- truction to any form of steel construction with concrete floors and ed reports are on file in the Bureau of Buildings, Borough of Manhattan,

ewell in his report on this building draws a different conclusion. See ews, March 24, 1904, page 276.

Soc. C. E., March, 1907, page 330.

concrete column and girder-protection, but superior to steel construction and terra-cotta floor and terra-cotta column and girder-protection. "Where this method was used, a very slight attack of fire was generally sufficient to cause rupture of the concrete underneath the reinforcing-metal, so that it fell away exposing the metal. There were comparatively few buildings, however, in which this method of construction was used."\*

**Thickness of Concrete Required.** From a study of the tests and fires referred to, the fair conclusions as to the AMOUNT OF PROTECTION against fire would seem to be as follows: (1) In all columns and in large and important girders, trusses, or other supports, at least 2 in of concrete outside of all reinforcements; (2) in girders and beams and in slabs of long spans, about 1½ in of concrete outside of all reinforcements; (3) in stair-work, floor-slabs of short spans, and walls and partitions, from ¾ to 1 in of concrete outside of all reinforcements. The provisions recommended in the Building Code of the National Board of Fire Underwriters are: "Steel reinforcement shall have a minimum protection of concrete on all sides as follows: In columns and girders, 2 in; in beams and walls, 1½ in; and in floor slabs, 1 inch. The steel in footings, walls and columns shall have a minimum protection of 4 inches of concrete."

"The minimum thickness of concrete surrounding and reinforcing members one-quarter inch or less in diameter shall be one inch; and for members heavier than one-quarter inch the minimum thickness of protecting concrete shall be four diameters taking that diameter, in the event of bars of other than circular cross-section, which lies in the direction in which the thickness of the concrete is measured; but no protecting concrete need be more than four inches thick for bars of any size; and provided, further, that all columns and girders of reinforced concrete shall have at least one inch of material on all exposed surfaces over and above that required for structural purposes; and all beams and floor slabs shall have at least three-quarters inch of such surplus material for fire-resisting purposes."

**Other Forms of Protection for Reinforced Concrete.** Because of the effects produced by fire on reinforced concrete, as above described, and the difficulty of restoring the construction where so affected, various suggestions have been made to protect the concrete construction with other materials. On account of its excellent fire-resisting qualities (see page 817), CINDER CONCRETE naturally suggests itself. This material is out of the question where strength is required. But its use may be combined with that of STONE CONCRETE, by placing a sufficient thickness for protective purposes on the outside of the reinforcements in columns, below the neutral axis in beams and girders,† and on the under surface of floor-slabs. Difficulties are likely to be encountered, however, in placing two kinds of concrete in the same mold, but these difficulties are not insurmountable. Careful inspection is required to see that the poorer material is not put in place of the stronger. One kind of concrete should follow the other immediately in order to secure a bond between the two. This suggestion, serving at the same time another purpose, was satisfactorily applied in the column-protection in the Bush Terminal Warehouses in the Borough of Brooklyn, New York. The steel-wire wrapping for the columns was prepared in sections 2 ft in height. Metal lath with about a ½-in mesh was placed outside the wrapping and secured to it. This was then placed in a cylindrical wooden mold 2 ft in height and with a diameter 4 in larger than the wrapping, thus forming an inner side of the mold. The space between the wrapping and the wooden mold was then filled with cinder concrete. When set and the m

\* Trans. Am. Soc. C. E., 1907, Vol. LIX, page 305.

† Trans. Am. Soc. C. E., Vol. LVI, page 284.



The result was a hollow cylinder of cinder concrete, 2 in thick and 2 ft in diameter, with the column-wrapping attached to the inside. These cylinders were placed one over the other in the building till the proper column-height was reached. Each vertical rod as were wanted were put in, and the interior filled with concrete. Thus was produced a fire-proof, wrapped column, without the inconvenience of any column-molds in the building.

A method of fire-protection, advocated by the National Fire Proofing Company, Philadelphia, Pa., is shown in Fig. 26. Here columns, beams, and girders are

Fig. 26. Tile Protection for Reinforced Concrete

encased with HOLLOW-TILE BLOCKS. Being either laid in the molds or built up around them, their rough and furrowed porous surfaces cause them to adhere to the concrete. They afford as efficient protection here as they do for walls, and if destroyed the blocks can be replaced.

**Aggregate on Fire-Resistance.** Fire tests on full-size reinforced-concrete columns, conducted by Walter A. Hull at the Pittsburgh laboratories of the American Standards, show that the nature of the aggregate plays an important part in the resistance to fire. Silicious gravels appear to make unsatisfactory concrete from the standpoint of fire-resistance. Limestone concretes are superior to others tested, including trap-rock and blast-furnace slags. Coatings of plaster, 1 in thick, and secured by a light, metal lath, protected the columns so effectively that the strength, after a four-hour fire test, was as much as that of the unplastered columns after the test, and about 90% of the strength of a column which had not been subjected to fire. Other forms of protection investigated and proved effective, were a roofing-material of asphalt, sand, and asbestos, and cylindrical forms of cast gypsum, 3 in thick, and applied in a manner similar to those of cinder concrete described

The ability of gravel concrete as fire-proof construction, was pointed out by Dr. C. E. Olson as early as 1907\* and appears to have been later confirmed

\* Proc. Am. Soc. for Test. Mats., 1907.

by an actual fire in a reinforced-concrete warehouse at Far Rockaway, N. Y., 1916. From this the conclusion was drawn that "all concrete specifications should contain a definite warning against the use of quartz gravel in concrete liable to be exposed to high heat."\*

## 6. Protection Against Corrosion in Reinforced-Concrete Construction

**Thickness of Reinforced Concrete.** The THICKNESS OF CONCRETE required for protection against fire has been found to be also ample for protection against CORROSION. It is well established that steel embedded in neat cement will not corrode. C. L. Norton of the Massachusetts Institute of Technology, Boston, Mass., draws the following conclusions from a series of experiments made in 1902 and 1903.†

- (1) Steel embedded in neat cement is secure against corrosion;
- (2) Steel embedded in a dense concrete mixture is safe against corrosion;
- (3) To assure a thorough coating of the steel the concrete should be mixed with fine sand;
- (4) Porous concrete allows the admission of moisture and will not protect the steel thoroughly;
- (5) A coating of rust is not a protection against further corrosion, as has been sometimes claimed.

In these experiments the steel was incased in concrete  $1\frac{1}{2}$  in thick on all sides. From this it would appear that

- (6) The steel of reinforced concrete is secure against corrosion, provided it is thoroughly embedded in concrete, and
- (7) A slight coating of rust on the steel, where embedded, does no harm, as the cement is strongly alkaline and will counteract the acidity of the iron oxide and prevent further corrosion.

"In practical design the most important question which arises is how far a concrete may be cracked (due to bending of beams) without exposing the steel to corrosive influences. In this respect it seems to the writer that the minor cracks which appear in the early stages of the tests can have very little influence."‡ This means that within the safe working limits, there is no danger from corrosion on account of the fine cracks due to tension in beams and girders.

**Corrosion of Steel in Cinder Concrete.** Cases are on record of serious CORROSION OF STEEL embedded in CINDER CONCRETE. In a report to the Structural Association of San Francisco, Cal.,§ the committee investigating the subject states that in cinder concrete "the extent of the corrosion is great enough to seriously endanger the safety of the floors, and it is not probable that the floors would have supported their loads more than one to three years longer. The committee recommended "that the Structural Association try to amend the present building law so as to exclude the use of cinder concrete in floor slabs or for fireproofing."

Mr. William H. Fox in his investigations || on this same subject finds that "after about forty days' treatment, the specimens were broken, and were then carefully examined for corrosion. With but one exception, one or more of the three steel pieces in each specimen showed unmistakable signs of corrosion."

\* Report to National Board of Fire Underwriters, on the fire in question.

† Reports Nos. 4 and 9, Insurance Experiment Station of the Boston Manufacturing Mutual Fire Insurance Company.

‡ Professor Turneaure in Trans. Am. Soc. for Test. Mats., Vol. IV, page 503.

§ Engineering News, Nov. 1, 1906, page 458.

|| Engineering News, May 23, 1907, page 569.

it made no difference how the concrete was mixed, wet or d  
ed, whether the steam or water treatment was used, the  
rust streaks and spots were found; the difference in the  
eing imperceptible." He concludes that "to secure a d  
nder concrete, a thorough tamping is necessary. A ric  
3 or one in which the proportion of cement to aggregat  
sed in all cases. The greatest of care should be taken in  
nd it may be necessary to resort to the seemingly impracti  
he reinforcement with grout before placing in the concret  
s of chemical and physical tests,\* made by George Bor  
ity of Nebraska, it was found that disintegration of cind  
by the oxidation of iron and sulphur producing inter  
ient cracking with occasional efflorescence of ferrous sulpl  
rom these tests, it was concluded that cinders with muc  
e sulphur are likely to give unsatisfactory results, especia  
e or porous material present; also that such material (ci  
l if allowed to weather with occasional washing, until  
lphur have been washed and leached out of the cinc  
l in these tests were from carefully screened steam coal  
s showed considerable ferrous iron and sulphur as sulphi

question of the CORROSION OF STEEL IN CINDER CONCRET  
cludes: "There is one limitation to the whole question,  
f getting the steel properly incased in concrete. Many  
thing to do with concrete because of the difficulty in getti  
is especially true of cinder concrete, where the porou  
has led to much dry concrete and many voids, and much  
nothing in this whole subject has been more misunder  
f cinder concrete. We usually hear that it contains mu  
es corrosion. Sulphur might, if present, were it not for t  
gly alkaline cement; but with that present the corrosi  
ur of cinders in a sound Portland concrete is the veriest  
f fact the ordinary cinders, classed as steam cinders, cor  
nount of sulphur. There can be no question that cind  
eat quantities of steel, but not because of its sulphur, l  
too dry, through the action of the cinders in absorbin  
ontained, therefore, voids; and secondly, because in a  
contain oxide of iron which, when not coated over with  
wet mixing, causes the rusting of any steel which it touch  
id only one, mix wet and mix well. With this precauti  
concrete quite as quickly as stone concrete in the ma

: Pabst Building in New York City, an eight-story ste  
was taken down after standing for about four years.  
n the steel I beams in this case consisted of cinder c  
uilt in segmental form.† The steelwork generally was l  
t, though it should be remembered that all the steel  
aking all things into consideration it is probably safe to

[Industrial and Engineering Chemistry, June, 1912.

9, Insurance Experiment Station, Boston Manufacturers l  
any.

stem, now obsolete.

Soc. C. E., Vol. L, page 297.

concrete, if care is taken to provide a proper mixture and careful and thorough workmanship.

## 7. Erection of Reinforced-Concrete Construction

**Forms for Reinforced Concrete.** For the erection of reinforced concrete it is generally necessary, first, to construct MOLDS or CENTERINGS for the columns, floors, etc. Wood is the material used for this purpose. Sheet-metal centering has been used with questionable success and economy. In the selection of the wood for the molds a clean grade of dressed pine should be used. It should be thick enough to resist warping and to resist deflection between supports. It must be coated on its surface with soap or some other satisfactory




Fig. 27. Wooden Form for Reinforced-concrete Column

substance to prevent it from sticking to the concrete. The forms or molds must be erected carefully, the exact size of the proposed parts, and must be true in position and direction. For floor-molds, sufficient supports must be provided not only to carry safely the heavy wet concrete, but also such materials as are liable to be placed on the floors up to the time when the concrete has set sufficiently to carry such loads. The supports must have sufficient rigidity to prevent deflection in the molds. The molds should be so constructed that they can be easily removed when the concrete has set. Sharp corners should be avoided as much as possible, as the wood is liable to stick in them. Where there are reentrant angles in the finished concrete-work, the molds should have beveled edges, and at salient edges of the finished concrete-work, triangular strips should be nailed in the corners of the molds to produce a beveled edge in the concrete.

the spreading of the sides of the molds, cleats must be provided at intervals. In the case of beams and girders, these are gen-  
ed by nailing. In the case of columns and piers and often in walls,  
are so notched at the ends that long bolts with washers may be  
l them in place, as shown in Fig. 27. In removing the form the bolts  
l and the cleats and the rest of the form are ready to use again. In  
particularly in the construction of walls, the cleats are held in place  
unning through the mold. These wires become embedded in the  
d in removing the molds they are cut and the portions in the con-  
owed to remain. The items of molds and centerings needed in the  
reinforced-concrete buildings form a considerable part of the cost of  
1. Economy in this respect can be affected in designing and planning  
he floor-panels throughout a building uniform in size and by repeat-  
s possible, such parts as piers, walls, etc. Successful attempts have  
o dispense with the erection of timber molds and centering by casting  
members of the construction on the ground and assembling and  
n in the same way that wood or steel columns, beams, and floors are  
nd erected. (See page 953.)

**Mixing.** In all reinforced-concrete work the concrete should be  
ANICALLY. Satisfactory HAND-MIXING can be obtained and might be  
n very small jobs, where it would be uneconomical to set up a  
ER. But a much more uniform product will result from machine-  
most types of mixers are mounted on wheels so as to be easily moved  
echanical mixers are either CONTINUOUS MIXERS or BATCH-MIXERS.  
ous mixers the materials are fed sometimes by hand and sometimes  
and the concrete issues continuously. The product, however, is  
he as uniform as that from the batch-mixer; for when the latter  
nder constant supervision, whereas when the continuous mixer is  
bine is relied upon. Of the batch-mixers the ROTARY TYPE is the  
most general satisfaction. Among the efficient examples of this  
mentioned the mixers made by the Ransome Concrete Machinery  
nellen, N. J., and the T. L. Smith Company, Chicago, Ill. They  
lifferent sizes and with capacities varying from about 10 to 60 cu yd

**Concrete-Mixers.** In CHARGING A CONCRETE-MIXER the materials  
carefully measured, are dumped into the mixer and the machinery  
r completing a definite number of revolutions, sufficient to thor-  
e ingredients, the concrete is discharged into wheelbarrows or  
nts for carrying it to the molds. Each batch should be completed  
is started. To obtain uniform results the number of revolutions  
on should be the same. It is not well to trust to the judgment of  
arge of the machine, as to when the mixing has been thorough.  
nstructed to count the revolutions each time. A good plan is to  
which rings when the fixed number of revolutions has been com-  
ode of the National Board of Fire Underwriters calls for "at  
ions," and the "speed of the mixer shall not exceed 20 revolutions

**etc Mixture.** The water is introduced during the process of  
amount, also measured, should be such as to produce what is  
MIXTURE, that is, a mixture that has the consistency of molasses  
adily flow around and thoroughly incase all steel to be embedded.  
ssary to vary the amount of water somewhat in placing a large  
te, as in walls, since the water generally works itself upward

through the successive layers. For TRANSPORTING THE CONCRETE from mixer to the mold, steel wheelbarrows, each holding about 2 cu ft, are generally employed. A larger vehicle, holding about 6 cu ft, is made by the Ransome Concrete Machinery Company, Dunellen, N. J., and is found very economical in larger work. When the conditions will permit, concrete may also be distributed by means of CHUTES, but care must be exercised to secure a consistency that will prevent the separation of the coarse aggregate from the mortar. Transporting through the chutes may be done either by gravity or by compressed air. Tests have shown that an excess of water tends to decrease the strength of concrete, so that care must be taken not to use more water than necessary to place the concrete properly.

**Pouring the Concrete.** Ideal conditions would obtain if the process of PLACING CONCRETE could be CONTINUOUS. This is not generally practical, so it is important that the point at which work is stopped each day shall be selected and predetermined that the strength of the construction shall suffer as little as possible. In smaller buildings, with floor-areas not exceeding about 3 000 sq ft, it should be possible to so arrange the progress of the work that each entire floor construction may be placed in one day. In larger work it is necessary to leave off a certain area to be completed within the time of concreting for the next day. Work should not leave off across important beams or girders, and the temporary stopping should be arranged for when the work is at the middle of a major or minor floor-beams. If any parts of floor-slabs are considered in the calculations for the strength of the beams or girders, such parts must be concreted at the same time and must be considered parts of such beams or girders. Joints in columns should be made perpendicular to the axes of the columns, and, as far as possible, at the lower side of girders. Columns should be allowed to set for at least two hours before girders are cast on them, in order to provide for settlement and shrinkage.

**Ramming the Concrete.** As soon as the concrete has been poured into molds, and during the process of pouring, it should be continually RAMMED to secure complete filling of the molds, density in the finished product, and thorough adhesion to the reinforcement. In wet concrete, such as is used for foundations, this ramming should be done with a flat steel spatula at the end of a handle long enough for comfortable manipulation. For column-work the handle should be lengthened out so as to reach to the bottom of the forms. Ordinary spades are sometimes employed, and where no special tools are provided, rammer sometimes made of 2 by 3-in scantlings, rounded off at the top end to form a handle. Where a smooth surface is desired the spatula rammer should be used, particularly at the sides of the molds. The honeycombed appearance that results from improper ramming is difficult to remedy afterward with the surface of patches. After having been placed, the concrete should be kept damp by sprinkling it with a hose until it has thoroughly hardened. The tapping of the forms with a hammer while the concrete is still plastic and before it has begun to set will cause it to flow more freely into place in intricate forms around reinforcing-bars, especially when a dryer concrete, recommended by recent investigators, is used. Tapping after it has started to set, however, tends to weaken the concrete.\*

**Removing the Forms from Reinforced Concrete.** No fixed rule can be given for the REMOVAL OF THE FORMS, as the time required for the setting of concrete varies with the CONSISTENCY of the mixture, and the climatic and

\* See "Effect of Vibrations, etc.," by Duff A. Abrams, Proc. Am. Concrete Inst., Vol. XV, 1919

Numerous failures of reinforced concrete have been attributed to the removal of forms. In warm weather concrete will set more quickly. The setting process may be somewhat accelerated after a day or two by moving the boards forming the sides of beams or girders and leaving them on the underside and the props supporting them. In cold weather it is possible to warm the building during the setting process by means of stoves.

**Finish of Concrete Surfaces.** The EXPOSED SURFACES of concrete are usually treated in attempts to produce a satisfactory appearance. A special provision is made, the marks of the lumber used in the forms are certain to show, and the lines of demarcation between successive layers are clearly defined. To eliminate these lines, grooves are sometimes formed, by tacking on the sides of the molds triangular or trapezoidal pieces to produce sunk joints in the wall, and give it an appearance resembling masonry. The successive layers of concrete are in such cases stopped at the joint so that the junction of the two layers is hidden. In some cases the surface is purposely left rough and scratched like the scratch-coat in plaster, and then stuccoed with a neat cement or a rich cement mortar. In this case there is always some danger that the stucco will flake off. The concrete when it comes from the mold, is sometimes hammer-dressed, or rather finished with a special hammer. This hammer has an edge at right-angles to the face and the edge is indented and made a series of points. A roughened surface is produced which in time shows a uniform texture. Another method is to strike the forms as soon as the concrete is sufficiently hard and to rub the surface with a plasterer's float or a block of carborundum, concrete, or stone, or to mix grout or fine sand with plenty of water between the float and the concrete.

Brushing, also, may be resorted to, consisting in scrubbing the surface while it is still green, with a wire brush, and a mixture of one part of hydrofluoric acid to six parts of water. A similar finish may be obtained by sand-blasting the concrete has thoroughly hardened.

**Finish of Reinforced-Concrete Floors.** If the FLOOR-SURFACES are covered with a wooden flooring, a satisfactory finish may be obtained by striking the surface, before the concrete has had time to set thoroughly, with a float from 1 to 1½ in thick, and troweling to make it smooth and level. If a finish is attempted after the concrete has set, the new and the old concrete probably will not bond; and there is always danger of flaking off unless the surface is of considerable thickness.

**Old and New Concrete.** Various fluids and special cementitious materials have been put on the market for the purpose of BONDING NEW AND OLD CONCRETE SURFACES. Whether or not these materials have any special merits, it is generally accepted that a good rich cement mortar will form sufficient bond between two concrete surfaces, providing the surfaces are clean. If the concrete is under COMPRESSION, the old surface of the concrete should be cleaned and the new surface may be roughened. Joints which are subject to TENSION should be filled with a 1 : 1½ or a 1 : 2 cement mortar before the new concrete is placed. In building walls which must be water-tight, the structure should be waterproofed. And if it cannot, all dirt and laitance should be removed, and a layer of very rich mortar placed.

**Inspection of Reinforced-Concrete Work.** In all reinforced-concrete work it is of great importance to have competent and thorough INSPECTION and SUPERVISION. The inspector should be familiar with the nature and qualities of the different materials entering into the construction. He should have

a knowledge of the underlying principles of the design of reinforced-concrete structures, so that he may realize the importance of carrying out all the details and particularly of placing the reinforcement exactly as planned. He must be sufficiently alert and active to see that the work of the contractor is progressing properly; so that, for instance, work shall not have to be rebuilt because of error in the forms. The MATERIALS used in the construction, particularly the cement, should be tested as the work progresses. Cubes of the concrete as used should be made up each day and at the end of seven days should be tested for compression, and if necessary again at the age of twenty eight days. This record will serve as a guide in the acceptance of the work, or in deciding on the necessity for a load test of the finished structure. Under no circumstances, however, should it replace or serve as an excuse to omit the testing of the cement upon delivery or before acceptance. In addition to the details discussed in this chapter, details which require the attention of the inspector on the work, and others may be especially mentioned here:

(1) In JOINING NEW WORK with that which is already in, and which has begun to set, the surface must be thoroughly cleaned and wet. In stopping off work, it is good practice where possible, to cast a groove in a surface that is to be joined with another, so that when the work is afterward continued, a tongue-and-groove junction is effected.

(2) All FORMS or MOLDS must be carefully cleaned out just before the concrete is poured. The bottoms of the column-molds must be especially watched for this, as shavings, sawdust, and even blocks of wood are liable to fall into them unobserved. It is well to leave off a small piece of one side of the column-mold at the bottom, for purposes of observation and cleaning, and to close it up just before pouring the concrete.

(3) Great care should be exercised in POURING and RAMMING concrete in deep molds, such as for columns, walls, etc., in order to get the molds thoroughly filled at the bottom. In careless work it is not unusual to find in such places very porous concrete, if not large pockets. This is particularly liable to occur when there is considerable reinforcing-steel in the construction.

(4) It should be remembered that concrete shrinks in setting. Hollow spaces at the tops of columns are sometimes found to be due to this cause. As they are not always observable from the outside after the forms are removed, great care should be exercised to guard against them. In pouring, therefore, the molds should be filled to overflowing to the top of deep molds.

(5) The exact position of the reinforcing-steel in the concrete is of such vital importance that particular mention is again made of it here. In loose-bar construction the greatest care must be exercised, in the first place, to have the reinforcement carefully placed, and then to avoid its being shifted out of position by the pouring and the ramming of the concrete.

(6) The REINFORCING-STEEL of those systems in which the advantage of detached stirrups is claimed, is often, for convenience in shipping, sent with the stirrups laid flat or close to the main bar. It is intended that in placing them on the job the stirrups shall be turned up to their proper positions. Unless carefully inspected, this is liable to be neglected.

(7) The use of a UNIT TYPE of construction (see page 922) practically obviates these two last-mentioned dangers, as the entire reinforcement comes framed together, so that the relative positions of reinforcing-rods or bars cannot be changed and a glance will show whether the FRAME is complete or has been damaged, and when placed in the molds, whether it fits or not. In this type of construction the parts are all assembled in the shop from details carefully drawn and checked in much the same way that steel beams, girders, columns, etc., are fabricated for



p drawings. The work of the inspector or superintendent on the job is simplified, and hence the liability of error reduced to a minimum.

**Tests on Reinforced-Concrete Construction.** Load tests on the structure should only be resorted to when, all reasonable care having been used to obtain good results, some doubt still exists as to the results. However, should not be accepted in place of a strict compliance with specifications. The architect should know beforehand that his building is designed and safe, and should employ, if necessary, an engineer. The architect should understand at the outset that the structure has been designed for definite purposes and loads, and that the materials and details of construction specified are not to be changed. If the contractor furnishes the test, sometimes does, a practice thoroughly condemned, the architect should require in his specifications that such design shall be checked and approved by an engineer appointed by him. A fair load to be applied in a test is the weight of the construction plus one-and-one-half times the working load. The stresses in the construction are then equal to one-and-one-half times the working stresses assumed in designing. Under these conditions there should be no evidences of distress, and the deflections should not exceed the limits specified. The material used for the load test should be so selected and applied when uniformly distributed, as required, it will not arch and assist in increasing the live strength of the beam or floor. Pig iron is a very good material for tests. If blocks are more generally available, but must often be piled very high to apply the required load, consuming much time and labor in making the test. If piles are used they should be set in vertical piles with spaces of 2 or 3 in. between them, thus avoiding all arching of the load.

## CHAPTER XXV

**REINFORCED-CONCRETE FACTORY AND MILL-CONSTRUCTION \***

By

EMILE G. PERROT

MEMBER OF AMERICAN SOCIETY OF CIVIL ENGINEERS

**General Principles.** The problem involved in the proper design of a reinforced-concrete factory or mill is a far more difficult one than might appear from a superficial examination of the finished structure. This applies to buildings constructed wholly or in part of reinforced concrete, and is due to the fact that maximum economy and efficiency in production can only be obtained when the building is thoroughly adapted to a given occupancy and use. Laymen and even some architects, look upon the factory as a mere workshop, consisting of four walls with floors and roof. To them it seems an easy matter to locate the structure with reference to the lot or site and then supply it with stairways, elevators and kindred features. This, however, is not the case. Each industrial process is peculiar to itself. The ease with which these processes can be employed renders the profit-making more or less successful; hence it is necessary to design the building to suit them. However, as the purpose here is to explain what constitutes proper design, as applied to the reinforced-concrete construction of a factory or mill-building, a typical case will serve to make clear the principles involved. This chapter, therefore, deals with such general types as would seem to meet the needs of the greatest number of persons.

**Walls, Floors and Roofs.** Reinforced-concrete construction may be used for walls and floors, or for floors and roofs only, in the latter case substituting for reinforced-concrete walls some masonry construction such as brick or stone. It is not always advisable to use reinforced concrete for walls. Circumstances very frequently arise in which it is more suitable and economical to use brick walls or piers.

**Types of Floor-Construction.** The floor-construction may be divided into two general types, the BEAM-AND-SLAB type and the GIRDERLESS type. The beam-and-slab type may in turn be divided into varieties. For example, it may consist of beams supported by columns, with slabs spanning from beam to beam. This arrangement corresponds to simple mill-construction in wood, where the heavy timbers run across the building every 8 or 10 ft. The timbers rest on the wall at one end and on a post at the other, with 3 or 4-in splined planks spanning from beam to beam. The earlier types of reinforced-concrete floors were patterned after this system. The next method was the introduction of girders running from column to column, and the placing of the columns farther apart, say twice the distance common to the former system. The beams were spaced as formerly. This may be called the BEAM-AND-GIRDER system. Still another variation of the beam-and-slab type is the SQUARE-PANEL system.

\* For Concrete in general and Mass-Concrete, see Chapter III, pages 240 to 247; for Strength of Concrete without Reinforcement, Chapter V, pages 283 to 287; for Reinforced-Concrete Construction in General, see Chapter XXIV, the paragraphs which, corresponding to the same details discussed here, should also be read. See, also, Chapter XXIII, pages 817 and 844.

beams are arranged along four sides of a square, a column being at each of the four corners. The simplest type of reinforced-concrete structure for factories is some form of the beam-and-slab type with walls and floors of reinforced concrete. The GIRDERLESS type consists of a heavy flat slab supported by columns without the use of beams or girders. The column-heads are made to form a large bearing-surface and the columns are spaced so as to give bays as near as possible. A typical example is worked out at the end of the chapter.

In general, as few columns as possible should be used to support the roof so that they may not interfere with the placing of machinery, and to make the most economical use of the floor-space. From the standpoint of




Fig. 1. Cross-section of Building

In construction, however, the use of one column to not more than 14 ft clear-space has been found to meet average requirements. This does not include construction of a special class. Adopting this, then, and bearing in mind the fact that the nearer a building comes to a square in plan the less is the total length of exterior wall required to enclose the area, it can be assumed that a four-story building 75 ft wide supported by four columns, making three spans across the building, is a suitable arrangement for most purposes. (See Fig. 1.)

The clear height of a Building of this width, with story-heights of 14 ft, will be ample for most purposes. There are always some parts of the building for which a strong light is not absolutely essential and which can be used for aisles and to the storing of material in process of manufacture. The end of the floor-space is generally used for this purpose, while the

machinery is placed nearer the windows where the light is best and where work is done. It is usually better, therefore, not to have a row of columns along the central axis of the building, unless it is definitely known that such arrangement will not interfere with the proper use of the floor-space. In building 75 ft wide, two rows of columns, with spans of 25 ft crosswise of structure, leave the central part of the floor-space free. Dividing 25 by 400 sq ft, the floor-space allowed for each column, gives 16 ft as the distance between columns, measuring lengthwise of the building.

**Bays.** The reason in this instance for making the bays rectangular instead of square is that there would be another row of columns if a square bay with a maximum of 20 ft in either direction were assumed. This would be likely




Fig. 2. Part Floor-plan of Building

interfere with the judicious placing of machinery and would result in a row of columns along the central axis of the building. This is not considered good practice and should be avoided, except when there is to be only one row of columns in the building.

**Example of a Typical Bay** The design of a typical bay of the size mentioned above, 25 by 16 ft, will now be considered. Referring to the illustrations (Figs. 1 and 2), it is seen that the windows occupy the major portion of the bay area, the sill being set much lower than is usual in brick buildings. This is done to avoid the necessity of the construction of an extra-high spandrel below the lintel over the windows below performs the double function of supporting the floor and forming a curtain wall. The head of the window is carried up to the under side of the floor-slab to simplify the construction of the bay.

and at the same time permit the window to extend to the ceiling, reducing the light at the highest possible point and allowing the rays into the room. The first beam should be set as far back as possible side wall and windows, so that the angle of the direct rays of light nearly horizontal as practicable. It will be found best to have the run across the building, bearing on the walls and interior columns. s may be made as deep as economy of design suggests, as they run the light-rays and do not interfere with the lighting-scheme. Again, is relatively very economical. It also acts as a stiffener across the dimension of the building, thus increasing the resistance to vibration owing machinery.

**Floor-System.** The various elements of the floor-system consist girders, beams and slabs. Each of these will be considered separately. A load of 120 lb per sq ft is ample for light manufacturing purposes. A load prescribed by the Building Regulations of the City of Phila-

1. The spacing of the beams should be governed both by economy construction and the maximum distance a slab will span while load safely. It is impractical to make a slab less than 3 in thick. Light, with concrete weighing 150 lb per cu ft, is  $37\frac{1}{2}$  lb per sq ft. A 1-in cement finishing-coat, weighing  $12\frac{1}{2}$  lb per sq ft, to be laid on the slab, the total live and dead load which the slab must carry, if it is 3 in thick, is  $120 \text{ lb} + 50 \text{ lb} = 170 \text{ lb per sq ft}$ . Referring to the diagram of the reinforced-concrete slabs (Fig. 18), calculated on a basis of the moment equaling  $WL/10$ , no curve is found in the 3-in diagram for a slab to carry a load of 170 lb per sq ft. Some other slab must be used, to carry the load.

**Reinforcement.** Referring to the diagram of the 4-in slab in Fig. 18, following the 6-ft line until it intersects the horizontal line opposite 170 lb per sq ft, it is found that a 4-in slab, reinforced with 0.195 sq in per lin of square bars per foot, will carry slightly more than is required for this load. The total load, if the slab is 4 instead of 3 in thick, is 182½ lb per sq ft, and as the 187½-lb line is the nearest to this load, the 4-in slab as above, is adopted. The reinforcing-rods are placed 1 in from the bottom of the slab and are of sufficient length to extend over two spans and one-half inch at each end; the joints are made over the beams and not in the space between them (Fig. 3).

2. The beams running from girder to girder are considered next. The span, center to center of girders, is 16 ft, and the distance apart between beams is 10 ft, giving an area of 100 sq ft carried by each beam. To the load per sq ft of 182½ lb must be added the weight of the beam itself, which is 15 lb per sq ft of floor-area, making a total of 197½ lb per sq ft of floor-area. This multiplied by the area, 100, equals 19 750 lb. The moment caused by this load on the beam, based on the formula  $M = WL^2/10$  for partially restrained beams is the one generally used, is 379 200 lb-ft. The stem or beam to form a T beam and hence is as the compression-flange of the girder; and as the slab is 4 in thick, the width of flange and the amount of reinforcement can readily be found by referring to Fig. 19, which is the diagram of the strength of T beams having a 4-in slab. In the diagram is the depth of the stem below the slab. On the opposite the center of the space between 350 000 and 400 000 lb-ft, on the left side, the depth of beam that best suits the conditions can be found. At the bottom of the diagram is given the total area of steel to

be used in the reinforcing-rods. As the depth of a beam from the standpoint of economical use of material should be about one-twelfth the span, a beam 16 in deep is found to comply with this rule. Below the space where the line representing the 14-in depth of beam intersects the line representing the bending moment, it is seen that the area of steel necessary is 1.8 sq in. Distributed

Fig. 3. Plan of One Bay, Showing Reinforcing

this over four bars, each bar should contain 0.45 sq in. The area of one  $1\frac{1}{2}$  square bar is 0.47 sq in, and hence a beam 14 in deep, reinforced with four  $1\frac{1}{2}$  square bars, is used. The width of the beam should be 6 in. A safe rule determines the width of the beam-stem is to allow  $1\frac{1}{2}$  in of concrete fireproofing on the sides of the bars and arrange the bars in two rows, if the beams have three or more bars. The distance in a horizontal direction, center to center bars, should be  $2\frac{1}{2}$  times the diameter, but in any case there should be a space between the bars horizontally, to permit the concrete to thoroughly imbed them.

**Arrangement of the Bars.** Assuming the bars to be twisted, the distance center to center, of the two bars is  $1\frac{1}{2}$  in. Adding to this the diameter of bars on their diagonal, which is about  $1\frac{1}{2}$  in, and 3 in for the fireproofing, sum is 6 in as the width of the beam required in this case (Fig. 8). It would be perfectly practicable to arrange the four bars in one row across the bottom of the beam; but the width would have to be  $9\frac{1}{2}$  in, which is wider than required. An additional objection to the latter arrangement is that it requires more concrete, thus adding to the dead weight of the construction. There should be 2 in of concrete under the bottom of the rods for fireproofing.

**Width of Beam.** Of course, the width of the beam must be sufficient to permit easy pouring of the concrete. Where wooden-box forms are used, it is not good practice to make beams narrower than 6 in. If the beam is very deep, say 36 in, 6 in would be too narrow a width in which to place the steel and clean out the beam-forms. Practical considerations very frequently govern the width of beams.

There should be in each beam and girder a sufficient number of bars of at least  $\frac{5}{16}$ -in round bars, bent U-shaped, run under the slab and extended up into the slab with an angle-bend 6 in long. If girder is short and excessively deep,  $\frac{3}{8}$ -in round or heavier stirrups are used. The function of stirrups is to unite mechanically the slab to the beam so that perfect T-beam action will result, and also to assist in the DIAGONAL TENSION or SHEAR as it is commonly called. The number of stirrups in a beam should be approximately one for each foot of the span, but the spacing should be as stated below. Thus, a 16-ft span should have not less than sixteen stirrups, that is, eight on each side of the centerline.

**Spacing for Distributed Loads.** For beams with distributed loads, stirrups are to be spaced so that the minimum distance between them

is not more than 36 in. The middle of the span should be divided into four parts. The first part should contain approximately one-half the stirrups allotted to the beam, or the total number divided in one-sixth the span, and the second part should contain one-twelfth the stirrups as shown in the distribution diagram, which comes out evenly. This should




Fig. 4. Section Showing Elevation of Beam

**Spacing for Concentrated Loads.** When there are concentrated loads, stirrups should be designed to suit the loading, but in any case, they should be spaced at least from 4 to 6 in on centers. A good rule to follow is to put in plenty of stirrups, if the determination of the number is in doubt, as there should be a sufficient number of them to resist the diagonal tension not safely resisted by the concrete.

**Development of the Bars in the Beam** is shown in Fig. 4. The bars are bent upwards near the supports to resist the negative bending moment which causes tension at the top of the beam near the supports. These bars extend into the next span at least 30 in to form a tie. As reinforcement is of a monolithic character, it is necessary to introduce metal ties to hold the concrete together when it is subjected to tensile stresses. While it is not possible to provide as much steel at the top of the beam over the supports as is provided in restrained beams gives, if 50% of the area in the beam is carried

to the top and over the supports, as shown in the illustration, the beam will be perfectly safe when calculated on a basis of  $M$  equaling  $Wl/10$ . In some cities beams must be calculated on the basis of  $M = Wl/8$ . Then it is only necessary to have about one-fourth the number of the bars bent up near the support. These bars, however, should extend at least 30 in beyond the center of the girder or column to tie the building together.

**For Simple Beams with Uniformly Distributed Loads**, all rods for 60% of the span should be straight and the truss-rods should bend up from the points so determined.

**For Beams or Girders with Concentrated Loads**, all bars are run straight as far as the concentrated loads extend. Beyond these loads, towards the supports, one-half the number of bars may be bent up as above.




Fig. 5. Elevation of Girder and Plans of Column-Footings

**The Girders.** The girders running across the building are calculated on the basis of carrying their own weight as a uniformly distributed load and concentrated loads at the points where the beams frame into them. Referring to the illustrations, Figs. 2 and 5, it will be noticed that there are three beams on each side supported by the girder, the fourth beam being carried by the column. Each concentrated load equals the total load on the beams, or 19 750 lb. The weight of the girder can be assumed as 20 lb per sq ft of area carried,  $20 \times 40 = 8000$  lb. This acts as a distributed load. One-half the span of 25 ft, or 12



the bending moment at the middle of the girder from the contributed loads is

$$\times 150) - (19\,750 \times 75) + \frac{8\,000 \times 300}{8} = 3\,262\,500 \text{ in-lb}$$

**8 and Width of Girder.** Referring again to Fig. 21, in case opposite 3 300 000 and 3 250 000, the line of a 26-in deep intersect the vertical line representing 8 sq in of steel. Hence bars arranged in two horizontal rows are used. The width of 12 in order to have the proper distance between the bars and give 1½ in of concrete fireproofing on the sides (Fig. 7).



section of Beam

Fig. 7. Cross-section of Girder

The Concrete Slab over the Girder is found by multiplying steel by the number on the line of the 26-in beam, which is 12. It is used for any area of steel when the beam is 26 in deep, the other beams are to be likewise used for their respective beams. For this girder, the width of the T beam is  $8.7 \times 8 = 69.6$  in, or 34.8 in at the middle of the girder. The portion of the slab used at the girder or beam should not exceed on each side of the beam 8-in thickness, nor one-third the span. In the case now being considered it is not exceeded. Similarly the width of the slab acting as a wing of the 14-in beam is  $1.8 \times 12 = 21.6$  in, twelve being the number of beams.

The next member to design is the lintel, or spandrel beam over the window (see Figs. 2, 5, and 8). This should be, for practical considerations, 6 in deep. The bottom of the lintel is flush with the bottom of the slab, the slab resting on the lintel over the top of the lintel-rods. In addition to the lintel-rods there should be bars of the same size as the stirrup-bars, 12 in apart and bent at right-angles, one leg extending up 12 in into the lintel and the other 18 in out into the slab; or else the slab-bars should extend into the lintel 12 in. These make a perfect tie between the lintel and the slab. The bottom of the lintel should be made with a rebate to fit into the window-frame. The load carried by the lintel is the weight of the window and the dead weight of the lintel. The weight of the floor-slab is  $13\frac{1}{2} \text{ ft (the clear span of the lintel)} \times 3 \text{ ft} = 40\frac{1}{2} \text{ sq ft}$  the load per square foot on the floor-slab, or a total load from the floor-slab of 371 lb. The total height of the lintel to the top of sill is 3 ft. This makes the weight per lin ft  $75 \times 3 = 225 \text{ lb}$ , the total weight of the lintel being  $225 \times 13\frac{1}{2} = 3\,038 \text{ lb}$ . For the window 10 lb per sq ft area being  $13\frac{1}{2} \times 11 \text{ ft, the height of the window, or in even}$

figures 149 sq ft, the weight is  $149 \times 10 \text{ lb} = 1490 \text{ lb}$ . The total load on lintel, then, is  $7371 + 3038 + 1490 = 11899 \text{ lb}$ .

**The Lintels Figured as Rectangular Beams.** By referring to the paragraph Explanation of Diagrams and Formulas, page 992, for the strength of rectangular beams, it is seen that when reinforced with 0.5% of steel the safe load carried the beam is  $W = wl = 48 \frac{bs^2}{l}$ . Hence, a 6 by (36 - 6)-in beam will carry  $48 \frac{6 \times 27^2}{13}$

$= 15552 \text{ lb}$ . The depth 27 is used, as it is taken to the center of action of the steel. This is more than the load upon the lintel and hence the lintel is safe. A reinforcement of 0.5% equals 0.005 of 162 sq in, the area of the concrete

or 0.81 sq in; and if two bars are used each must be of 0.4-sq-in sectional area. Two  $\frac{3}{8}$ -in square bars, each having area of 0.39 sq in, will be used. They should be located 2 in from the bottom and run straight. There should be 1  $\frac{3}{8}$ -in square bars near the top of lintel, running the full length, and four  $\frac{3}{16}$ -in stirrups, as shown in the illustration (Fig. 8). The top bars take place of bent bars and also prevent vertical cracks which are liable to occur from shrinkage near the middle of lintel.

**The Columns.** Having established the design of the floor-system, the dimensions of the wall piers, interior columns and footings are next determined. Fig. 8. Vertical Section, Showing Lintel schedule of the loads on the interior columns will now be made.

**The Load from the Roof.** Assuming a live roof load of 30 lb per sq and 10 lb additional for accidental load from overhead shafting, the total load is 40 lb per sq ft. The weight of the slab, if 3 in thick, which is as thick as is usually required, is  $37\frac{1}{2} \text{ lb per sq ft}$ . The beams and girders weigh another 30 lb per sq ft (12 plus 18), making a total dead load of 70 lb, including covering. Adding the live load of 40 lb to this gives 110 lb per sq ft as the total dead and live load.

**The Load on the Fourth-Story Column,** then, is 400 times 110 lb 44 000 lb, not counting the weight of the column itself. For practical reasons no column should be made less than 10 by 10 in in cross-section. Allow, therefore, 500 lb per sq in unit stress on the concrete for columns, which is 1 unit stress allowed by the Philadelphia Building Bureau in reinforced-concrete columns with vertical reinforcement, the carrying capacity of a 10 by 10 column is 100 times 500, or 50 000 lb, which is in excess of the load to be carried (See Table I)

**The Load on the Third-Story Column** is the load from the one above of 44 000 lb plus the load of one bay of the fourth floor, which is  $217 \text{ lb} \times 4 = 86800 \text{ lb}$ , being the total dead and live load; or  $86800 + 44000 = 130800 \text{ lb}$ , which must be added the weight of the column, which is assumed to be 300 lb per lin ft. As it is about 11 ft long in the clear, the weight of the column is 3300 lb, which, added to 130800 lb, equals 134100 lb. The area of the cross-section of a 16 by 16-in column is 256 sq in, which, at 500 lb per sq in, gives 128 000 lb

capacity. While this is 6 100 lb less than the load to be carried, of the required strength. It is customary to make a reduction to be carried on the columns in proportion to the amount of the reduction being greater as the floor-area increases. Use of the LIVE LOAD per floor, with a maximum not exceeding 100 lb per sq ft on columns for high buildings, is considered good practice.

**of Reinforced-Concrete Columns.** Length, Fifteen Diameters vertical bars. Safe working stress on concrete 500 lb per sq in, the weight of concrete being neglected in figuring the columns

Area	Total safe loads in lb	Size	Area	Total safe loads in lb
64	32 000	18×18	324	162 000
81	40 500	19×19	361	180 500
100	50 000	20×20	400	200 000
121	60 500	21×21	441	220 500
144	72 000	22×22	484	242 000
169	84 500	23×23	529	264 500
196	98 000	24×24	576	288 000
225	112 500	25×25	625	312 500
256	128 000	26×26	676	338 000
289	144 500	27×27	729	364 500

**The Second-Story Column** is 134 100 lb plus the load from the weight of the columns, all of which is assumed as being half-floor load and weight of column, or 90 100 lb, making the total 224 200 lb. A 21 by 21-in column will carry 441 times 500 lb per sq in,

**The First-Story Column** is 224 200 lb plus the second-floor load and the weight of the column, which, at 600 lb per lin ft, is 134 100 lb, making a total of 358 300 lb. A 25 by 25-in column will carry 625 times 500 lb, or 312 500 lb, which is almost the required strength. The column then becomes

For the first story 25 × 25 in in cross-section.

For the second story 21 × 21 in in cross-section.

For the third story 16 × 16 in in cross-section.

For the fourth story 10 × 10 in in cross-section.

**Reinforcement in the Columns** should consist of eight  $\frac{3}{4}$ -in round bars and four in the two upper stories, with ties of  $\frac{1}{4}$ -in round bars as shown in Fig. 9. It is the custom to use the same unit for concrete columns up to 15 diameters, and not to use columns larger than 15 diameters.

1. The schedule of all the wall piers is made by the same method as for the interior columns. The details of the calculations are not given, only the results being given. The size of the wall piers is determined by architectural effect desired and by practical considerations.

For the smallest face-dimension of the piers, this size should be the same for all height of the building (Fig. 10). The reveal of the piers should be 5 in, and the spandrels should line up flush with the inside of the piers. When doing this they are not made extremely thick. Reinforcement

concrete spandrels may be 6 in thick and give good results. It is not wise to make them thinner than this, on account of the difficulty of constructing them. It is to be noticed, also, that the lintels or spandrel beams act as ties from one wall pier to another. They should be of sufficient strength not only to carry the vertical loads coming upon them, but also to act as braces to take up any vibration

• Ties,  
12" apart  
1- $\frac{1}{2}$ " Rods



Fig. 9. Interior Column

Fig. 10. First-story Wall Pier

tion in the direction of the length of the building; just as the deep cross-girders resist the vibration in the direction of the width of the building. Very frequently the main girders are run lengthwise of the building, that is, spaced at the shortest distance, while the beams run across the building. Sometimes this will make the construction more economical; but the reduced height of the windows in the side walls due to the necessity of lowering the window-head to permit the beams to be carried by a lintel running over them, is objectionable as the light from the windows in this position is not as effective as when they are run up to the under side of the floor-slab or ceiling.

The wall-pier schedule, figured on the assumption above, becomes

For the first story 30 × 16 in in cross-section.  
For the second story 30 × 12 in in cross-section.  
For the third story 30 × 12 in in cross-section.  
For the fourth story 30 × 12 in in cross-section.

It will be noticed that the piers in the three upper stories are of the same dimensions. This is due to practical requirements, the reveal of the pier and the spandrel being 6 in and the minimum spandrel-thickness 6 in. The pier must be 12 in in order to be flush on the inside of the building.

**Spread Foundations.** The use of reinforced concrete for the footings of a building results in economical construction when it is necessary to project the base or footing more than is customary or permissible without reinforcement of some kind. In order to give sufficient information for the design of the foundations for the building under discussion in this chapter, as well as for other types of construction met with in practice, several examples are worked out in the following pages. The simplest form of reinforced concrete **SPREAD FOOTING** is shown in Fig. 5 and consists in considering the overhanging portions of the footings as **CANTILEVER BEAMS**. The footings of the interior columns are designed as explained in the following paragraphs.

**The Load on the Footing.** The load on the footing is assumed to be 317 000 lb and the safe bearing value of the soil 7 000 lb per sq ft. This requires a spread footing of 317 000 lb divided by 7 000, or 45 sq ft. The side of the square which comes the nearest to this area is 6 ft 9 in and its area is 45.5 sq ft.

**The Design of the Footing.** The footing is designed as follows: As each square foot of footing sustains an upward pressure of 7 000 lb, the overhanging portion is treated as a **CANTILEVER BEAM UNIFORMLY LOADED**. The load direct

column proper causes no bending, and this load is neglected in finding moment. The rods should be run as shown in Fig. 5, some diagonal at right-angles to the sides, the first layer located 3 in from the footing. The size of the rods on the diagonal is now to be determined, the others are to be made the same size. The longest length of diagonal cantilever is 4 ft, measured from the center of the column to the outer edge of the 1-ft-wide strip with the side of the square. The bending moment on this strip is equal to the load on an area, outside of the column, 1 ft wide, or  $(3 \times 7\,000 = 21\,000 \text{ lb}) \times 30 \text{ in} = 630\,000 \text{ in-lb}$ , 30 in distance from axis of the column to center of gravity of the area.

The footing to be 24 in thick over-all, the CENTER OF ACTION of the load is out 5 in up from the bottom, making an EFFECTIVE DEPTH of 19 in. The moment for the steel is nine-tenths \* of the depth when the stress in the steel is 16 000 lb per square inch, the resulting stress per square inch in the steel is  $16\,000 \times 0.9 = 14\,400$ . As the bending moment is 630 000 lb-in, the number of square inches of steel necessary per foot

$$\frac{630\,000}{14\,400 \times 19} = 2.34 \text{ sq in.}$$

This formula is for rectangular beams when the bending moment is given. (See Formula (1), page 992.) Spacing the reinforcement requires three rods per foot, each requiring a cross-section of 0.76 sq in. As a  $\frac{3}{4}$ -in square bar has a section-area of 0.76 sq in, this is the size of the bars. The bars in the layers at right-angles to the side are made the same size and spaced as above, so as to avoid complications in the construction.

It would be possible to space these farther apart, but this is unnecessary. (See Fig. 5.)

The load on a column is such as to require a footing more than 2 ft thick, so as to slope the top of the footing, thus saving in the quantity of concrete to provide a concrete PLINTH or BLOCK at the bottom of the footing so as to reduce the projection of the footing and make a more economical design. If steel column-cores or hooped vertical reinforcements are used, a metal base-plate is necessary and a footing of sufficient size to limit the direct stress on the footing to

**Designations for the Outside Walls** may be designed in either of two ways, as CONTINUOUS FOOTINGS such as are usual in ordinary construction, or as ISOLATED PIERS under the wall columns. In the first case the walls reinforce the footings and foundation-walls, as these act as beams loaded at each column, and must be made strong enough to transfer the loads from the columns uniformly over the entire length of the foundation-walls and footings can be treated as INVERTED CONCRETE BEAMS (Fig. 11), the upward reaction of the earth being considered as a distributed load on the beams, and the wall piers being considered as supports. Fig. 12 shows the arrangement of the reinforcing-rods. Their spacing is explained in the following paragraph.

The load per running foot of the foundation is equal to the load from a wall of the distance apart of the piers, omitting the weight of the spandrel or windows, this load per running foot =  $191\,140 \text{ lb}$ , the load on a 6 ft wide pier =  $11\,946 \text{ lb}$ . As great refinements in calculations are not necessary in the design of this kind, because of the advisability of large factors of safety, the part of the building and the small reduction in cost due to any increase in the strength of this continuous beam is calculated by the formula

(3), page 683; (4), 926; (6), 932; (1), 992; and Fig. 5, page 974.

$M = Wl/8$ , assuming  $l$  to be the clear distance between the piers, or, in this case, 13 ft 6 in (Fig. 12). Therefore,  $W = 13\frac{1}{2} \times 11\ 946 = 161\ 271$  lb and the bending moment  $M = (161\ 271 \times 162)/8 = 3\ 265\ 737$  in lb. As the size of the beam is determined by the thickness of the wall and its depth, all that is necessary is




Fig. 11. Foundation-wall an Inverted Continuous Beam

find the AREA OF THE STEEL by referring to Formula (1), page 992, which gives

$A = \frac{M}{14\ 400\ d}$ , or  $A = \frac{3\ 265\ 737}{14\ 400 \times 52} = 4.3$  sq in, distributed in eight  $\frac{3}{4}$ -in square bars with a total area of cross-section of 4.48 in. These are in two layers, four running straight and four bent as shown in Fig. 12. The top layer is placed




Fig. 12. Arrangement of Rods in Foundation-wall

from the top of the concrete. The footing is made wider than the wall to keep the load on the soil within the safe limit of 7 000 lb per sq ft. The width is determined as follows. As the column-spacing is 16 ft, center to center,  $7\ 000 \times 16 = 112\ 000$  lb, the load the foundation 1 ft wide and 16 ft long will carry; but to carry 212 120 lb (the load from the pier, plus 20 980 lb, the weight of spandrel and footing), 212 120 is divided by 112 000, giving 1.9 ft for the width of the footing, or 1 ft 11 in, nearly.

**Isolated Piers.** In the second case, a SPREAD FOOTING is provided under each wall column in the same manner as under the interior columns, but designed for the lighter load. The foundation or spandrel wall is not made as heavy as in the first case, as it carries no load except its own weight and the wall or window above it. (See Fig. 5.) WHERE THE SOIL IS BAD and of low carrying capacity the PIER-METHOD is found to make an economical foundation, especially where it is necessary to use piling under the building, as the piles can be grouped under the piers and columns, and capped with reinforced concrete. The foundation spandrel walls, properly reinforced, can be carried from pile-cap to pile-cap so they do not depend on the soil directly under them to sustain the load.

**Combined Column-Footings.** It very frequently happens that a building is to be built adjacent to and abutting on a property-line, and as foundations must not encroach upon the adjacent property the columns must

the footings. In order to secure uniform soil-pressure it is combine an interior with an exterior column-footing so as to uniformly from the two columns to the soil below. Sometimes to combine the footings of more than two columns. Fig. 13 is an actual construction and may be regarded as typical. The loads in this case are almost identical, one being 700 000 lb

Fig. 13. Combined Column-footing

lb, so that the shape of the combined footing in plan can be such that the center of gravity of the two loads is practically at the center of the footing. When one column is more heavily loaded than the other, the center of gravity of the loads is no longer at the middle of the span, but since it is necessary to make the combined footing TRAPEZOIDAL, the center of gravity of the trapezoid will coincide with the resultant of the loads from the columns.

Assumptions for the design of this footing are the actual ones. A good example of the necessity of assuming certain sizes at the beginning of calculations may change. The WIDTH OF THE FOUNDATION is determined by the LOAD-LIMIT on the soil, which in this case is not to exceed 6 650 lb per sq ft, and the size of the column-base being known, we may determine the BENDING MOMENT in the footing. We assume an area of 224 sq ft, giving a soil-pressure of  $1\,490\,000\text{ lb} \div 224\text{ sq ft} = 6\,650\text{ lb per sq ft}$ . The point of maximum shear is where the vertical shear is zero and is determined by the equation  $0 = 15\text{ ft} - 1.05\text{ ft} = 13.95\text{ ft}$ . Hence

$$0 \times 13.95 = 9\,765\,000\text{ ft lb} - [(46\,550 \times 15 \times 7\frac{1}{2}) + 5\text{ ft lb}] = (4\,528\,125 \times 12) = 54\,337\,500\text{ in lb}$$

The 1.05 ft is one-half the column-width, 2 ft 1 in.

We may determine the DEPTH OF THE FOUNDATION by assuming a sectional area of the reinforcing-steel and solving in Formula (1), page 990, for the depth. For practical considerations square bars larger than 1¼ in sq should not be used; hence by trial we find that thirty 1¼-in square bars with a section-area of 46.8 sq in, placed in two rows in the top part of the foundation will space out just right for a width of beam of 64 in, which is 6 in wider than the 58-in dimension of Column No. 1. The depth then by this formula is

$$d = \frac{M}{14\,400 A}, \text{ or } d = \frac{54\,337\,500}{14\,400 \times 46.8} = 80 \text{ in,}$$

the depth from the center of the steel to the bottom of the concrete. Therefore  $80 + 4 = 84$  in, the total depth of the foundation.

The WIDTH OF THE FOOTING AT THE BASE must be increased to keep the




Fig. 14. Section through Flight of Reinforced-concrete Stairs

stress on the concrete in compression within the allowable stress, 600 lb per sq in. As the total horizontal compression in the beam must equal the total tension, in order to satisfy the requirements for equilibrium, we have total tension = 800 lb per sq in  $\times$  46.8 sq in = 748 800 lb. From Table V, page 930, Chapter X, the depth of the AREA OF THE CONCRETE IN COMPRESSION is equal to 0.34  $\times$  80 = 24.8 in. The width is found by dividing 748 800 by  $(300 \times 24.8 = 7440)$ , giving the resistance of the concrete per inch in width of the beam, which gives 89 in the width of the concrete at the bottom of the footing, 300 lb being the allowable unit stress on the area of the concrete in compression, since the stress acts



500 lb on the outside upper surface of the concrete to zero at the

8. The ease with which stairs can be built of reinforced concrete has led to their general adoption for this purpose in reinforced-concrete buildings. As stairs are usually enclosed in stair-towers or shafts, their construction usually is of the double run or half-pace type (Fig. 14). This reduces the span of the run so that the construction does not become too heavy. Each run is considered as an inclined beam and is so figured, being supported at the bottom on the stair-landing header-beam. The rods are placed on top of the slab and run continuously from top to bottom. The span of the beam is considered to be equal to the distance from the soffit of the corner formed by the tread and rise, as shown by the letter *D* in Fig. 14. The landings are figured the same as floor-slabs. Their supporting beams are calculated to carry the load coming upon them from the landing and from the stair-run, which starts from the landing-beam. The lower stair-run under the landing-beam, acts as an inclined strut and supports the landing-beam. Hence the span of the landing-beam is equal to the distance between the side edge of the stair-tower or shaft and the side edge of the stair-run, and is a little more than the width of the stair-tower. This makes the design of reinforced-concrete stairs very economical. (See pages 900 and 947.)

**Stair-Design.** It is customary to make each of the runs 4 ft wide. The maximum live load is taken as 100 lb per sq ft come upon the stairs from one person, weighing 150 lb, with a 1-ft step, or 75 lb per sq ft step. With steps 4 in high, the load is 300 lb per sq ft. Hence the load on the run is 10 times 300 lb, or 3000 lb per run for the live load. Fig. 15. Detail of Reinforced-concrete Steps

The span of the run is approximately 400 in. This makes a total load on the inclined beam of 3000 lb. The span in calculating inclined beams is taken at the horizontal distance between supports; hence in our example the span is 8 ft 9 in. The bending moment, therefore, is  $\frac{7000 \times 105}{10} = 73500$  in-lb, figuring

the beam as simply supported. Assuming the thickness of the slab to be 5 in, the depth of the beam is 4 in, and the area of steel for a 4-ft width for this depth and load as above is  $\frac{73500}{4 \times 14400} = 1.3$  sq in, or 0.32 sq in for a 1-ft

width. This requires  $\frac{3}{8}$ -in round bars, 4 in on centers, or  $\frac{1}{2}$ -in round bars 7 in on centers. (See page 1514.) It is customary, also, to run cross-rod, spaced 2 ft on centers, at right-angles to the main rods, as shown in Fig. 15. It is also customary to run the rods which reinforce the run in the wall-edge of platform at the top to the wall-edge at the bottom of the landing, to make them come in the bottom of the landing-slab and their reinforcement. The treads should be finished with a layer of cement and grits; and the risers can be brushed smooth




Fig. 16. Diagram for Strength of Reinforced-concrete Slabs

when their forms are removed. The riser-forms should be removed as as the concrete has set sufficiently to hold its shape, so that the top of each or tread can be incorporated into the concrete. Top-surfacing applied the concrete has set hard is very likely to become loose and break off. A good form of step is shown in the detail, Fig. 15. When the stair-runs

not be carried, at bottom and top where the steps start and ends, a reinforced-concrete beam, forming an outside string, and the stair-reinforcement run parallel with the risers from the

The beam forming the string can be made any convenient and reinforced to suit the load.

$$M = \frac{Wl^2}{8}$$

Diagram for Strength of Reinforced-concrete Slabs

**Diagrams and Formulas.** Figs. 16, 17, 18 and 19 are to reinforced-concrete slabs. These diagrams are plotted in accordance with the 1907 Regulations of the Philadelphia Building Inspection, which permit a unit compressive stress on the concrete and a tension of 16 000 lb per sq in in the steel, the moduli of elasticity of steel to concrete equal to 12.

resses give a factor of safety of 4, based on the ultimate strengths and have been found to give results in practice which are on safety and economical construction, the concrete being a 1 : 2 :




Fig. 12. Diagram for Strength of Reinforced-concrete Slabs

and the aggregate a good hard stone. The building laws of cities specify the allowable unit stresses to be used in designing reinforced structures, and when they differ from those used in the calcu

to be made in the results obtained when using the diagrams, has the option of choosing his own method of calculating, used with absolute safety.

Fig. 23 are diagrams of the strength of T beams. The diagrams are based on the same unit stresses as above; but

$$M = \frac{Wl^2}{16} \quad \text{for Slab}$$

Diagram for Strength of Reinforced-concrete Slabs

the beam is taken as the distance from the center of action of the concrete slab and not to a point one-third the way from the top. The beam-depths in the diagrams are the clear depth of the slab. The width of the slab in compression is the area of the steel by the constant given in the diagram for depth of beams.

Bending moments in inch-pounds.

Area,  $A$ , of steel, square inches.

Fig. 20. Diagram for Strength of T Beams

Area,  $A$ , of steel, square inches.

21. Diagram for Strength of T Beams

DIAGRAM OF STRENGTH OF T BEAMS

Bending moments in inch-pounds.

Area,  $A$ , of steel, square inches.  
Fig. 22. Diagram for Strength of T Beams



DIAGRAM OF STRENGTH OF T BEAMS

Area,  $A$ , of steel, square inches.  
 p. 23. Diagram for Strength of T Beams



Given a bending moment of 217 728 in-lb and a depth (over all) in, to find the sectional area of steel necessary to make the resisting  $M$  to the bending moment.

$$A = \frac{M}{14\,400\,d} \text{ or } A = \frac{217\,728}{14\,400 \times 13\frac{1}{2}} = 1.12 \text{ sq in.}$$

ound bars of  $\frac{3}{4}$ -in diameter we have 0.56 sq in  $\times 2$ , or 1.12 sq in. for fireproofing and  $\frac{1}{4}$  in to the center of the bars, the effective span is reduced to  $13\frac{1}{2}$  in. For the width of the beam we can use page 931, Chapter XXIV, substituting for  $K$  the value corresponding to stresses and the ratio of the moduli of elasticity for the concrete we have been using, namely, 600 and 16 000 lb per sq in for the steel and 12 for the ratio. This value of  $K$ , from Table V, page 926, is 83.4 and  $M = 83.4\,bd^2$ . Transposing, we have

$$\frac{M}{83.4\,d^2}, \text{ or } b = \frac{217\,728}{83.4 \times (13\frac{1}{2})^2} = \frac{217\,728}{83.4 \times 182.2} = 14.3 \text{ in}$$

Therefore will be  $14\frac{1}{2}$  in  $\times$  16 in in cross-section, reinforced with two bars placed so that there will be  $2\frac{1}{2}$  in from the bottom of the beam.

As the width of this beam is excessive for the number of rods economical. It would be better to design the beam with a T section with a depth to 6 in for the stem and making the top flange  $14\frac{1}{2}$  in wide  $\times$  4.18 in thick. The ratio of the distance of the neutral surface of the beam to the effective depth of the beam, for the values we have, is 0.31 (see Table V, page 926, Chapter XXIV), and in order to balance the concrete in compression at the top of the beam to balance the steel, the head or flange of the T must extend from the top of the neutral surface.

**Floors.\*** In order to familiarize the student with the design of floors, an example is worked out, in which the area of a panel or bay is 400 sq ft, the same as that of a typical bay in the factory-buildings considered in this chapter. The column-spacing is made the same as in the example, so that the panels are square, with a length of side of 20 ft. In applying the various methods of computing the strength of flat, reinforced concrete slabs, we will use one under consideration by the Bureau of Building Inspection of Philadelphia.† This is a conservative method. It has been worked out in all its details and applications and gives results in safety and economical design. The following paragraphs set forth the principles and equations of this method as published by the Philadelphia Bureau of Building Inspection. It is the DROP-CONSTRUCTION.

1. center to center of columns, of the longest of straight bands of reinforcement.

2. distance or width, edge to edge, between capital-heads in inches.

3. distance from the center of action of the concrete in compression to the center of the steel at the drop in inches.

4. distance from the center of action of the concrete in compression to the center of the steel at the center of the slab in inches.

Chapter XXIV, pages 949 to 951. Flat-Slab Construction.

Dr. J. H. R. Chief of the Bureau of Building Inspection, Philadelphia, Pa., is working out and perfecting the practical applications of this method.

If the drop-construction is not used,  $d = d_1$ .

Sufficient depth of slab is to be provided for shearing-stresses as well as bending-stresses.

Width of capital-head = not less than  $\frac{3}{10} L$ .

Width of drop =  $\frac{3}{10} L$ .

Width of bands =  $\frac{4}{10} L$ .

$x$  = the area of section of steel over the capital-head.

$x_1$  = the area of section of steel in center of bay.

$-M$  = the bending moment at the edge of the capital-head.

$+M$  = the bending moment at the center of the span.

The load carried by the straight band =  $\frac{\text{total bay} - \text{capital-head}}{2} \times w$

$$-M = \frac{\text{total bay} - \text{capital-head}}{2} \times \frac{wL_1}{12}$$

$$+M = \frac{\text{total bay} - \text{capital-head}}{2} \times \frac{wL_1}{24}$$

Width of concrete to resist compression at edge of capital-head = width of drop.

Width of concrete to resist compression when negative moment =

= width of band.

Width of concrete to resist compression at middle of span = width of band

$$x = - \frac{M}{d \times 16000}$$

Place 66% of  $x$  in straight bands } over capital-head.  
Place 43% of  $x$  in diagonal bands }

$$x_1 = + \frac{M}{d_1 \times 16000}$$


Place 66% of  $x_1$  in straight bands } at middle of span.  
Place 43% of  $x_1$  in diagonal bands }

Add 20% of steel of  $-M$  to provide for negative bending over straight band

The drop equals the abacus outside of the capital-head, or the increase in thickness of the concrete to obtain the necessary compression in the concrete. This is not generally necessary when the live load of the floor is light, say 120 lb per sq ft and the span is not excessive. To determine  $d$  and  $d_1$  deduct from total thickness of the slab 1 in to the center of the steel when the rods are 1 in or less in diameter; if over 1 in deduct 1 1/2 in; and multiply the result by 12. The result will be the distance from the center of the steel to the center of action of the compressive stresses in the concrete.

The depth  $h$  is the distance from the top of the slab to the center of the column-head and is used in finding the thickness of the slab. Applying the above formula to the example considered, using a floor-load of 120 lb per sq ft as in the previous example, and assuming an average slab-thickness of 8 in with a 1-in top finish coat of cement, the dead load is 100 lb + 13 lb = 113 lb, which added to the live load = 233 lb, total.

The arrangement of the bands is shown in plan, Fig. 24, the width being  $\frac{4}{10}$  or  $\frac{4}{10}$  the span of 20 ft, which is 9 ft. The diameter of the column-head is 3 ft or 4 ft. The width of the drop is  $\frac{3}{10} L$ , or 7 ft 7 in.



#### 4. Arrangement of Bands in Girderless Floor

One bay =  $20^2 = 400$  sq ft.

Drop-head =  $4^2 = 16$  sq ft. Then, by the formula, the load

$$\text{on bands} = \frac{400 - 16}{2} \times 233 = 44\,736 \text{ lb}$$

$$\frac{44\,736 \times L_1}{12} = \frac{44\,736 \times 16 \times 12}{12} = 715\,776 \text{ in-lb}$$

$$\frac{44\,736 \times L_1}{24} = \frac{44\,736 \times 16 \times 12}{24} = 357\,888 \text{ in-lb}$$

This diagram is shown in Fig. 25.

To find the thickness of the concrete at the drop. The depth of a beam when the bending moment, the width and allowable stresses are given, is as follows, in which  $h$  equals the depth from the center of the steel to the top of the concrete:

$$\frac{M}{bS_s} = \sqrt{\frac{2 \times 715\,776}{0.27 \times 91 \times 600}} = \sqrt{100} = 10 \text{ in}$$

the width of the drop and  $S_s = 600$  lb per sq in. The total, therefore, is  $10 + 1 = 11$  in (Fig. 26).

$$\text{Load on column at the drop} = x = -\frac{M}{d \times 16\,000} \text{ in which } d = 0.9h$$

$$\frac{715\,776}{9 \times 16\,000} = 4.9 \text{ in, or about 5 in}$$

The straight band will have 66% of 5 or 3.3 sq in of steel. A  $\frac{3}{8}$  round rod has a cross-sectional area of 0.11 sq in. Therefore, there will be  $\frac{3.3}{0.11} = 30$  bars over the capital-head in the straight band. As the bars from the adjoining span overlap the column-head, extending into the next span as far as the edge of the drop, each straight band over the column will have  $\frac{3}{2}$  or fifteen bars. The diagonal




Fig. 25. Bending-moment Diagram for Girderless Floor




Fig. 26. Capital-head and in Girderless Floor

bands will have 43% of 5 or 2.15 sq in, which will require twenty  $\frac{3}{8}$ -in rods over the column, or ten on each side, lapped as above. The thickness of the slab at the middle of the span is found by the formula given above, substituting the proper values for the letters. The formula becomes

$$h = \sqrt{\frac{2 \times 357\,888}{0.27 \times 108 \times 600}} = \sqrt{\frac{715\,776}{17\,496}} = \sqrt{41} = 6.4 \text{ in}$$

The total depth is 6.4 + 1 in = 7.4 in, or about 7.5 in.

The width of the band = 9 ft = 108 in.

For the steel at the center of the span

$$x_1 = + \frac{M}{d_1 \times 16\,000} \text{ in which } d_1 = 0.9h \text{ or } 0.9 \times 6.4 = 5.76 \text{ in}$$

$$x_1 = \frac{357\,888}{5.76 \times 16\,000} = 3.9 \text{ sq in}$$

The straight bands will have 66% of 3.9 or 2.57 sq in of steel which will require  $\frac{2.57}{0.11} =$  twenty-three  $\frac{3}{8}$ -in round bars or eight bars more for the middle of the span than for the band set over the column.

In practice the rods are made the full length of the span, from column to column, plus the width of the drop, or in this example 20 ft + 7 ft 7 in = 27 ft 7 in for the fifteen rods. Eight additional rods, 13 ft long or about the distance from the edge of one drop to the edge of the next one, must be used with the fifteen rods to make the twenty-three required for the middle of the span. The diagonal bands will have in the center 43% of 3.9 sq in = 1.68 sq in which require fifteen  $\frac{3}{8}$ -in round rods or five more than one set of rods over the column. These five, however, are to be added at the middle of the span between the drops. The rods are bent up over the column-head so as to be near the top of the slab to take care of the negative bending moment, the bars extending horizontally near the top of the slab the full width of the drop. It is necessary to provide bent reinforcement extending down into the column and outwards as far as the outer ring with

as reinforcements of the column-head. The size and number of with the span and load; but for the floor under consideration there ht 1-in radial rods as near the top of the slab as practicable, the ne outer one being equal to the width of the band and that of the g equal to the capital-head. It will be noticed in the above analysis y calculations could be made certain assumptions were necessary, ickness of the slab, which was assumed as 8 in, in order to obtain whereas in the finished design the thickness of the slab is 7.5 in and , which, however, does not affect the practical results materially. ason that the design of flat slabs should be intrusted only to those : experience in the design of reinforced concrete, as good judgment : making up of a successful design; and one who is inexperienced : a specialist in this particular system of construction, if a design to execution.

est methods of determining GIRDERLESS FLOORS is that embodied o RULINGS GOVERNING THE DESIGN AND CONSTRUCTION OF t SLABS, which went into effect March 1, 1918. The following ese rulings: The least dimensions of concrete columns shall be 1/2 the panel-length, nor less than 1/2 the clear height of the minimum total thickness of the slab, in inches, shall be deter- formula,  $t = \sqrt{W}/44$ , in which  $t$  is the total thickness of the and  $W$  the total live and dead load, in pounds, on the panel, r to center of columns; but in no case shall the thickness be ( $L$  is the panel length, center to center of columns) for floors, /40 for roofs, nor shall a less thickness than 6 in be used. The punching shear on the perimeter of the column-capital shall ltimate compressive strength of the concrete. The allowable he perimeter of the drop-panel shall be 3/100 of the ultimate ngth of the concrete.

pose of establishing the bending moments and the resisting quare panel, the panel shall be divided into strips known as p  $B$ . Strip  $A$  shall include the reinforcement and slab in a from the center line of the columns for a distance each side : equal to one-quarter of the panel-length. Strip  $B$  shall include t and slab in the half width remaining in the center of the angles to these strips, the panel shall be divided into similar having the same widths and relations to the center line of the ove strips. These strips shall be for designing purposes only, ded as the boundary lines of any bands of steel used."

ENT COEFFICIENTS for interior panels for two-way and four- ll panels and panels without drops or capitals, are given in e length of panel does not exceed the breadth by more than putations shall be based on a square panel whose side equals ength and breadth. In no rectangular panel shall the length th by more than one-third of the latter. Wall columns in :ion shall be designed to resist a bending-moment of  $WL/60$   $WL/30$  at the roof. Interior columns must be analyzed for on of unbalanced loading. The Point of Inflection; Tensile nd Compressive Stress in Concrete; Rectangular Panels, ; Rectangular Panels, Two-way System; Placing of Steel; ler their respective headings.

## CHAPTER XXVI

### TYPES OF ROOF-TRUSSES

By  
MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

#### 1. Definitions

**Use of Trusses.** Whenever the distance between the side walls of a building exceeds about thirty feet, and there are no intermediate walls or columns, is usually necessary to support the roof on trusses. The ceilings of large room assembly-halls, etc., also, require trusses for their support. In many cases the roof and a ceiling are carried by the same trusses.

**A Truss** is a framework, composed of straight, or sometimes curved, members or pieces so arranged that the structure as a whole acts as a beam. Since a triangle is the only figure which cannot be changed in shape without changing the length of one or more of its sides, it follows that the pieces forming a truss must be arranged so as to form triangles. The members of a truss are usually subjected to longitudinal stresses only, either compressive or tensile. Curved members and members which act as beams supporting loads are subjected to additional bending stresses. Each member of a truss is either a **TIE** or a **STRUT**.

**A Tie** is a member which has developed in it a longitudinal tensile stress.

**A Strut** is a member which has developed in it a longitudinal compressive stress. When vertical, struts are sometimes called **POSTS** or **COLUMNS**.

**The Top Chord** of a truss is composed of the upper outside members. In some forms of roof-trusses top chords are called **RAFTERS** (Fig. 2).

**The Bottom Chord** of a truss is composed of the lower outside members (Fig. 2). In roof-trusses the bottom chord is commonly called the **TIE-BEAM**.

**The Web-Members** are those connecting the **CHORDS** (Fig. 2).

**A Joint** is the point of intersection of two or more members of a truss (Fig. 2).

**A Panel** is the distance between two adjacent **JOINTS** in either the upper or lower chords (Fig. 2).

**Purlins.** Whenever possible all roof-loads and ceiling-loads should be transferred to trusses at the joints. This usually requires beams spanning the space between trusses at corresponding joints. These beams, when supporting the roof, are called **PURLINS** (Fig. 2).

#### 2. Types of Wooden Trusses

**The Simplest Truss** that can be built is that shown in Fig. 1. It consists of three members forming a triangle. As the unsupported length of a strut for economical reasons, should not exceed 12 feet, such a truss is not suitable for spans exceeding from 20 to 24 ft; and even for a span of 20 ft there should be a center rod, as shown by the dotted line *R*, to support the tie-beam. To utilize this truss for spans greater than 24 ft, it is necessary to brace the rafters from the foot of the center rod, as shown in Fig. 2. This gives us the **KING-POST TRUSS**, the modern type of the old-fashioned **KING-POST TRUSS** which is shown in Fig. 3.



which was built wholly of wood except for the iron straps at S

**Braces.** When the tie-beam supports a ceiling or attic-floor, rods inserted at *RR*, Figs. 2 and 4, to support the load on the tie-beam. the number of rods and braces, as in Figs. 4 and 5, this type of

used for spans up to even for greater on account of the length of the center rods it is not an improvement when the span

When there is no tie-beam the rods and 5, merely support the beam and are often




Fig. 1. Simplest Three-piece Truss. Spans up to Twenty-four Feet

**Howe Trusses.** shown in Figs. 4 and 5, sometimes called Howe

The character of the stresses in the web-members corresponds with stresses in the web in the standard form of Howe truss. They are ANGULAR HOWE TRUSSES to distinguish them from the STANDARD with parallel chords.




Fig. 2. King-rod Truss. Spans up to Thirty-six Feet

**Truss.** The RISE of the rafter in any of the trusses, Figs. 1 to 5, should be less than 6 in in 12 in or  $26\frac{1}{2}^\circ$ ; a  $\frac{1}{3}$  pitch, or a rise of 8 in 12 in is usually the most economical. When the span exceeds 36 ft, it is better to cut off the top of the truss as in Fig. 6, which shows the form of the ancient queen-post truss. This truss is frequently used for deck roofs, although it may also be used for a pitched roof. When the top chord is more than 12 ft long, the size of the top chord is considerably reduced by using a center rod and a pair of struts

7. The center rod will be especially needed if the bottom chord is subject to a bending stress. The center rod should never be used without the braces.

**Counters.** The truss shown in Fig. 6 differs from those shown in Figs. 4 to 5, in not being composed entirely of triangles and in having a rectangle in the middle. Assuming the joints to be pin-connected and without friction,




Fig. 8. Modern King-post Truss




Fig. 4. Six-panel Triangular Howe Truss. Spans from Thirty-six to Fifty Feet





Fig. 5. Eight-panel Triangular Howe Truss. Spans from Forty-eight to Sixty Feet


is evident that a very small inequality in the position or magnitude of the load will cause the failure of the truss since the rectangle will not retain its shape. This is easily verified by means of a cardboard model fastened at the joints.

eyelets. When the joints at the corners of the rectangle are not to turn they have a tendency to prevent distortion. When the



1. Queen-rod Truss. Spans from Thirty to Forty-five Feet

ly upon the left of the center the truss itself tends to assume a that shown in Fig. 8. The DISTORTION of the rectangle may be the introduction of a diagonal member as shown in Fig. 9. For



Queen-rod Truss. Spans from Forty to Fifty-two Feet

wn, the diagonal is in compression and is usually called a  
If the piece were in tension it would be called a COUNTERTIE.  
al Loads. Although roof-trusses of the type shown in Fig. 9,  
etrical loads, do not theoretically require COUNTERS, it is never-




Fig. 8. Distorted Queen-rod Truss

o brace the rectangle along both diagonals to insure stability  
unsymmetrical loading and to relieve the joints from any  
latter, which is usually caused by wind, snow and floor-loads.

**Reversal of Stresses.** In some trusses subjected to different loadings different times, the diagonal web-members near the center may be subjected tension for one loading and compression for another loading. In such case




Fig. 9. Counterbraced Queen-rood Truss

is advisable to introduce a member following the other diagonal of the queen-rood containing the member subjected to the two kinds of stress, to assist main member. This piece, also, is called a COUNTERBRACE or COUNTER-DIAGONAL according to the kind of stress it has to resist. If this is not done, the member




Fig. 10. Queen-post Truss. Massachusetts Charitable Mechanics' Association Building, Boston, Mass.

which is subjected to two kinds of stress must be designed for both tension and compression and the ends connected at the joints to meet the same condition.

**An Ornamental Queen-Post Truss,** supporting a portion of the roof of the Massachusetts Charitable Mechanics' Association building in Boston, Mass.,

Mr. William G. Preston, is shown in Fig. 10. The truss-members, long-leaf yellow pine, were worked from timbers of the dimensions as truss wooden members instead of rods are used for the vertical bolts and tenoned to the tie-beam and secured to the rafters by The curved ribs take the place of counterbraces.

#### 11. Queen-rod Truss. Museum of Fine Arts, St. Louis, Mo.

**Rod Truss** from the Museum of Fine Arts, St. Louis, Mo., Crosby & Stearns, is shown in Fig 11. It supports the floor as of three rods. The truss-rods have nuts and washers below the threads on the rods are long enough to receive turnbuckles the suspension-rods with the truss. This is generally the best pending a floor from a truss.

is a detail of joint A of the

mitted for Special Reasons.

truss, sometimes used when it up the middle part of an attic structions. In building this isable to construct the lower ers of two timbers, thoroughly , as shown. What has been to counterbraces in queen-rod also to this truss, although in

continuous rafter aids very existing distortion from wind-

not exceeding 40 ft it is safe to Fig. 11A. Detail of Joint A, Fig. 11.

**Supporting Common Rafters.** Before describing other types ay be well to consider the manner of supporting the common russes. Occasionally it is desirable to span the common rafters russ, but as a general rule it is better construction to support of large beams or PURLINS which themselves span from truss wn in Fig. 13.

se trusses can be designed so that the purlins need not be more t, and very often not more than 6 or 8 ft apart; so that the need not be more than 2 by 4 or 2 by 6 in in cross-section, while be spaced 12, 14, or 16 ft on centers. As a rule a spacing of

about 14 ft for the trusses and of 9 ft 6 in for the purlins is found to be the most economical arrangement. Another advantage in the use of purlins is that where they are placed at the truss-joints no bending stresses are developed in the truss-rafters or chords; and hence the latter may be made lighter than




Fig. 12. Queen-rood Truss with Middle Part Clear. Spans up to Forty-two Feet.

they supported the common rafters. For wooden trusses of 60 ft or greater span, purlins should always be used.

**Supports for Purlins.** Purlins may be placed with their sides either vertical or at right-angles to the plane of the roof, as shown in Figs. 2 and 13. The

ends of the purlins may be supported by means of beam-hangers, described in Chapter XII by double stirrups; 3-in planks bolted and spiked to the sides of the trusses, or they may rest on the chords themselves. The ceiling-joists or floor-joists are usually supported at the sides of the tie-beams, as at Fig 13, or simply rest on them, as at B. When they support an

at floor it is better to use the latter construction. In the case of scissors truss it is sometimes more economical to support the ceiling-joists by purlins; when the tie-beams are horizontal it is more economical to use them for the direct support of the ceiling-joists or floor-joists. All chords which support rafters, ceiling-joists or floor-joists must be designed for bending stresses as well as for longitudinal stresses.

**Trusses with Horizontal Chords.** For the support of flat roofs, with or without a ceiling below, and for conditions such that horizontal trusses

types shown in Figs. 14 to 17 are undoubtedly the most satisfactory construction, when the span does not exceed 80 ft; and where the cost of iron rods is relatively great, it is as economical as any other. In this work the name HOWE TRUSS is given to this type, as it is of the Howe bridge-truss to building-construction; and the L TRUSS is also sometimes used. Trusses of this type can be




Fig. 14. Five-panel Howe Truss




Fig. 15. Six-panel Howe Truss




Fig. 16. Ten-panel Howe Truss




Fig. 17. Six-panel Howe Truss with Top Chord Inclined

used for spans up to 150 ft; but when the span exceeds 100 ft it is better to use a steel truss of the PRATT TYPE in which the verticals are in compression and the diagonals in tension. When a Howe truss is used in the longitudinal direction of a flat roof, the top chord may be given the shape of the roof itself, so as to support the rafters without the blocking of the roof. For deck roofs the top chord may be inclined upwards from the deck-ridge, to conform to the shape of the roof, as shown in

Fig. 18. For deck roofs and mansard roofs the middle panels should have counterbraces, as shown in Fig. 18, to resist the wind-pressure against the sides of the roof and any unequal distribution of snow.

**Height of a Howe Truss.** The height of the truss, measured from center to center of the chords, should never be less than one-ninth the span for spans up to 36 ft, nor less than one-tenth the span for spans from 36 to 80 ft.




Fig. 18. Howe Truss for Deck Roofs

As a general rule a height of from one-seventh to one-sixth the span will be most economical. When the top chord is inclined, as in Fig. 17, the height  $X$ , that is, at the shortest rod, should not be less than the limit given above.

**Number of Panels in a Howe Truss.** In this type of truss a **PANEL** is the space between two adjacent rods or between an outer rod and the end joint (Fig. 14). As a rule, the number of panels should be such that the diagonals will have an inclination of from  $36^\circ$  to  $60^\circ$ , an inclination of about  $45^\circ$  being the most economical. It is not material whether there is an even or odd number of panels. If the position of one or more of the purlins is fixed by some special requirement, then the panels should be so arranged that the upper joints come under the purlins, and the inclination of none of the diagonals is less than  $36^\circ$ . Although it is generally better to have the truss symmetrical about the center, it is not absolutely necessary; nor is it necessary to make all panels of uniform width. When the truss is not symmetrically loaded, however, it may be necessary to reverse the brace in one of the center panels. This point is considered in Chapter XXVII, page 1102, under the subject of **UNSYMMETRICALLY LOADED TRUSSES**.

**Counterbraces in a Howe Truss.** If there is any chance of the truss being more heavily loaded on one side of the center than on the other, **COUNTERBRACES**, that is, braces inclined in the opposite direction from that of the regular braces, should be placed in the center panels, as shown by the dotted lines in Fig. 15. If the truss is deep and the diagonals long it is economical to counterbrace each panel as shown in Fig. 18. If the number of panels is odd, as shown in Fig. 14, no diagonals are required in the middle panel when the braces and loading are symmetrical; but it is good practice to cross-brace this panel to provide for any accidental unsymmetrical loading.

**Spacing of Trusses.** The most economical spacing, center to center, of trusses, all things considered, is usually from 12 to 16 ft for spans up to 60 ft and from 14 to 20 ft for greater spans.

**Spacing of Purlins.** Purlins should always be placed as near the truss joints as possible; they should also be spaced so as to effect the greatest economy in rafter-construction. Their spacing, therefore, determines, to a large extent, the number of panels. When the height of the truss is not more than one-ninth or one-tenth the span, it is often more economical to place a purlin over every other joint, as in Fig. 16.



## Dimensions for Six-Panel Howe Trusses, Symmetrically Loaded

r, Norway pine, Douglas fir, or eastern spruce. (See Fig. 15)

Total height		Top chord	Bottom chord	Braces			Rods not upset		
				A	B	C	D	E	F
ft	in	in	in	in	in	in	in	in	in
6	7	6×6	6×8	6×6	6×4	6×3	} 1½	¾	⅝
5	2	6×8	6×8	6×6	6×6	6×4			
6	8	6×8	6×8	6×6	6×4	6×3	} 1¼	⅞	⅝
5	2	8×8	8×8	8×6	6×6	6×4			
6	8	6×8	6×8	6×8	6×6	6×4	} 1¼	⅞	⅝
5	2	8×8	8×8	8×8	6×6	6×4			
7	7	8×6	8×8	8×6	8×4	6×4	} 1¼	⅞	⅝
5	11	8×8	8×8	8×6	8×5	8×4			
7	8	8×8	8×8	8×6	8×5	6×4	} 1⅝	⅞	¾
5	11	8×8	8×8	8×8	8×6	8×4			
7	8	8×8	8×8	8×8	8×6	8×4	} 1½	1	¾
6	1	8×10	8×10	8×8	8×6	8×4			
8	8	8×8	8×8	8×8	8×6	8×4	} 1⅝	⅞	¾
6	8	8×8	8×8	8×8	8×6	8×4			
8	8	8×8	8×8	8×8	8×6	8×4	} 1⅝	1	¾
6	10	8×10	8×10	8×8	8×6	8×4			
8	8	8×8	8×8	8×8	8×6	8×4	} 1½	1	¾
6	10	8×10	8×10	8×10	8×6	8×4			
9	8	8×8	8×8	8×8	8×6	8×4	} 1⅝	⅞	¾
7	6	8×8	8×10	8×8	8×6	8×4			
9	8	8×8	8×8	8×8	8×6	8×4	} 1½	1	¾
7	7	8×10	8×10	8×8	8×6	8×4			
9	10	8×10	8×10	8×10	8×8	8×6	} 1⅝	1½	¾
7	7	10×10	10×10	10×8	8×8	8×4			
9	9	8×8	8×10	8×8	8×6	6×6	} 1⅝	1	¾
8	4	8×10	8×10	8×10	8×6	8×4			
9	10	8×10	8×10	8×10	8×6	6×6	} 1½	1½	¾
8	4	10×10	10×10	10×8	10×6	8×4			
9	10	10×10	10×10	10×8	10×6	8×6	} 1¾	1½	¾
8	4	10×10	10×10	10×10	10×6	8×6			
9	6	8×10	8×10	8×10	8×6	6×6	} 1½	1	¾
7	7	10×10	10×10	10×8	10×6	8×6			
9	6	10×10	10×10	10×8	10×6	8×6	} 1¾	1½	¾
8	9	10×12	10×12	10×10	10×8	10×6			
9	6	10×10	10×10	10×10	10×6	8×6	} 1⅝	1¼	⅞
8	9	10×12	10×12	10×12	10×8	10×6			
10	2	10×10	10×10	10×10	10×6	8×6	} 1⅝	1½	¾
10	10	10×10	10×10	10×10	10×6	8×6			
10	2	10×10	10×10	10×10	10×8	8×6	} 1⅞	1¼	⅞
10	0	10×12	10×12	10×10	10×8	10×6			
10	4	10×12	10×12	10×12	10×8	8×6	} 2	1⅝	1
10	1	10×12	10×14	10×12	10×8	10×6			

**Bearing on Wall or Post.** The point where the axial lines of the end brace and of the tie-beam intersect should always come over the support, as far as possible over the axis of the supporting wall or post.

**Stresses in a Howe Truss.** The stresses in the chords are always greatest at the middle of a truss, diminishing towards the supports, while the stresses in the rods and diagonals are greatest at the ends of a truss.

**Table of Dimensions for a Howe Truss.** In SYMMETRICAL TRUSSES having panels of uniform width and uniformly loaded, the stresses in the different members are proportional to the span, number of panels, height of truss, spacing of trusses and load per square foot. It is therefore possible to prepare tables giving the proper dimensions of the members of such trusses. Table I gives the dimensions for six-panel trusses for heights of one-sixth and one-eighth the span and for three different spacings. These dimensions are for a flat roof covered with tin, sheet iron, or composition; a snow-load of 16 lb per sq ft equivalent to about 24 in of light, dry snow; also for a lath-and-plaster ceiling supported by the bottom chord. The chords and braces are of Norway pine and the rods of wrought iron. These dimensions apply only when the rafters




Fig. 19. Lattice Truss

are supported on purlins placed at the upper joints, as in Figs. 15 and 16. When the rafters rest on the top chord, as in Fig. 17, the dimensions of the latter must be increased and special calculations made for it. The dimensions given in the table may be used for trusses of greater height than those given, but not for trusses of less height, as the less the height the greater the stresses in the chords and braces. When the conditions of load, span, height and spacing are not exactly as given above and in the table, the stresses should be determined and the members of the truss proportioned accordingly; but even in such cases the table will serve somewhat as a check on the computations.

**Lattice Trusses.** In localities where timber is not expensive the LATTICE TRUSS (Fig. 19) is often found economical for supporting flat roofs. This type of truss was invented for bridges by Ithiel Towne in 1820 and a large number of

have been constructed with trusses of this type, some of which now (1915) in New England. The principal objections to the tendency to twist sidewise, like a thin board on edge, its flexibility and the difficulty of getting sufficient bearing material at As indicated in Fig. 19, the truss is composed of top and bottom parallel, connected by lattice bracing. The chords are com- lanks, two being on one side and two on the opposite side of the bottom chord the planks should be as long as can be obtained o that no two splices are near the same point. The available om chord to resist tension is the area of three planks less the area oints by the connecting pins or bolts. Each member of the web gle plank arranged as shown in Fig. 19. The braces are inclined about  $45^\circ$  and usually three sets are sufficient, as shown in the nnections are best made with American-locust pins, which give eas without much extra weight. Modern construction employs : expensive and add considerable weight. There should be at




Fig. 21. Lower Joint of Truss Shown in Fig. 19

each connection, if the planks are wide enough to permit, and at the chord-joints. Since about one-half the web planks resist the web projects beyond the chord at least 4 in to provide additional shearing area. The ends are reinforced by vertical timbers on the chords and each set of diagonals is thoroughly fastened.

In some cases it is necessary to add timbers on the outside and them down to the lower face of the bottom chords to relieve bearing-stresses where they rest on the supports. The methods of the stresses in this truss are considered in Chapter XXVII, 91. Figs. 20 and 21 show details of this lattice truss.

**Trusses with Raised Bottom Chords.** All of the trusses thus have horizontal bottom chords; and this construction is the most economical and should be used whenever conditions require a greater height of ceiling. In roofing churches, public buildings, etc., raised ceilings are often desirable as they increase the general height of the interior by increasing the height of its side walls.

Table II. Dimensions for Lattice Trusses, Uniformly Loaded  
Timber, Norway pine, Douglas fir, and yellow pine. (Fig. 19)

Span	Spacing of trusses	Height out to out of chords		No. of spaces	No. and size of pcs of bottom chord		No. and size of pcs of top chord		Size of braces	No. and diameter of treenails or bolts, joint 1-5, Fig. 19		
ft	ft	ft	in		in	in	in	in	in	in		
40	12	{	5	6	16	4	2×6	4	2×6	2×6	4	1
			7	2	12	4	2×6	4	2×6	2×6	4	1
	14	{	5	7	16	4	2×6	4	2×8	2×6	4	1
			7	3	12	4	2×6	4	2×8	2×6	4	1
	16	{	5	8	16	4	2×8	4	2×8	2×8	4	1½
			7	4	12	4	2×8	4	2×8	2×8	4	1½
50	12	{	6	8	16	4	2×8	4	2×8	2×10	4	1½
			8	8	12	4	2×8	4	2×8	2×10	4	1½
	14	{	6	8	16	4	2×8	4	2×8	2×10	4	1½
			8	8	12	4	2×8	4	2×8	2×10	4	1½
	16	{	6	9	16	4	2×8	4	2×10	2×10	4	1½
			8	8	12	4	2×8	4	2×8	2×10	4	1½
60	12	{	8	4	16	4	2×10	4	2×10	2×10	4	1¾
			10	10	12	4	2×10	4	2×10	2×10	4	1¾
	14	{	8	4	16	4	2×10	4	2×10	2×10	4	1¾
			10	10	12	4	2×10	4	2×10	2×10	4	1¾
	16	{	8	4	16	4	2×10	4	2×10	2×10	4	1¾
			10	10	12	4	2×10	4	2×10	2×10	4	1¾
70	14	{	9	5	16	4	2×10	4	2×12	2×10	4	1¾
			12	4	12	4	2×10	4	2×10	2×10	4	1¾
	16	{	9	5	16	4	2×10	4	2×12	2×10	4	1¾
			12	4	12	4	2×10	4	2×10	2×10	4	1¾
	18	{	9	6	16	4	2×12	4	2×12	2×10	4	2
			12	6	12	4	2×12	4	2×12	2×10	4	2
80	14	{	11	0	16	4	2×12	4	2×12	2×12	4	2
			14	0	12	4	2×12	4	2×12	2×12	4	2
	16	{	11	2	16	4	2×14	4	2×14	2×12	4	2
			14	0	12	4	2×12	4	2×12	2×12	4	2
	18	{	11	2	16	4	2×14	4	2×14	2×12	4	2
			14	1	12	4	2×12	4	2×14	2×12	4	2

**Note.** All joints should be thoroughly spiked and packing blocks used where necessary. When treenails are used each chord-joint should have in addition one ¾-bolt as shown in Fig. 21.

**Scissors Trusses.** For the roofs described in the preceding paragraph some form of the SCISSORS TRUSS, so named from its resemblance to a pair of scissors, is most often used. When correctly designed, with members of the proper size, and with joints carefully proportioned to the stresses, it is a very good truss for supporting roofs over halls and churches, up to a span of 48 ft; but for greater spans it should be used with caution, as the stresses become very great and the joints difficult to make. Figs. 22 to 27 show different forms of this truss and modifications of it adapted to different spans and roof-pitches. None of these trusses exerts a large horizontal thrust if the members are of ample size and the joints properly made. The members having a plus sign





Fig. 22. Simple Scissors Truss. Spans up to Thirty Feet

Fig. 23. Scissors Truss. Spans Exceeding Thirty Feet



Truss. For Steep Roofs. (See Chapter XXVIII, Figs. 18 and 19)

or close to them are in COMPRESSION, while those having a minus sign are TENSION. The determination of the actual HORIZONTAL THRUST is considered on pages 1085-1087. The members indicated by a single line should be rod

Fig. 25. Modified Scissors Truss. For Medium Pitch. (See, also, Chapter XXVI, Figs. 18 and 19)

except in the case of bottom chords. Fig. 22 shows the simplest form of the scissors truss, which is suitable for spans up to 30 ft. When the span exceeds 30 ft, it is more economical to use two purlins on each side to support the co





Fig. 26. Finished Cambered Truss. (See, also, Chapter XXVIII, Figs. 18 and 19)

mon rafters; and additional supports from the bottom chords are generally required, calling for additional rods and braces, as shown in Fig. 23. For steep roof the arrangement shown in Fig 24 is generally the best, and for

as shown in Fig 25, in which the scissors pieces do not cross nor  
 Fig. 26 shows a finished truss, built on somewhat the same lines  
 as in Fig. 25 but with only one purlin. This truss can hardly  
 be called a scissors truss but is shown here for convenience. It is really  
 as that of the truss shown in Fig. 33. The truss shown in Fig.  
 27 is that shown in Fig. 24, with the peak cut off, but for spans



Scissors Truss. Spans Exceeding Thirty-six Feet. (See, also, Chapter XXVIII, Figs. 18, 19 and 20)

is more economical. It can also be used where the roof is  
 in this form it is better to use ceiling-purlins to support the ceiling-  
 in the latter from truss to truss.

**Gothic Trusses.** Two of the principal characteristics of the Gothic  
 architecture are the relatively elaborate ornamentation of structural  
 members and the disposition to view of the construction of a building as a whole.  
 When arch and steep roof were developed the roof-truss became an  
 important part of the ornamentation as well as in the construction of Gothic  
 structures. The trusses of this period were built almost entirely of  
 heavy timbers, to give the appearance of great  
 massiveness. The most common types of these Gothic trusses, and also  
 the most important, was the HAMMER-BEAM truss, still often used in churches  
 in the Gothic style. Figs. 28 and 29 show early English forms of this  
 truss. Its name comes from the horizontal beam *H*, called the HAMMER-  
 BEAM, which supports the principal rafter. In the more ornamental trusses this  
 beam is usually carved to represent royal personages or angels.  
 In principle it differs from those thus far described, in having no  
 substitute for one. In fact the trusses shown in Figs.  
 28 and 29 are within the scope of the definition of a TRUSS given at the  
 beginning of this chapter. Although the rafters or principals are connected  
 at their lower ends by a short COLLAR-BEAM, this offers but little resistance  
 to the tendency of the rafters to spread at their lower ends; and hence the  
 truss depends upon the transverse strength of the rafters or upon the  
 walls to keep it intact and, generally, upon both. This form of  
 truss is that of an ARCH, as vertical loads produce inclined reactions at the  
 walls and churches of the Gothic period the walls were generally

very thick and usually reinforced on the outside by BUTTRESSES built against them and directly opposite the roof-trusses. In most cases such a wall possesses sufficient stability to withstand the THRUST of the truss, and hence the bottom chord may be dispensed with; but in a wooden building the walls, unless thick at the top, offer no resistance whatever to being thrust out and hence, in such buildings, no truss which exerts an outward thrust on the walls should be used.

Fig. 28. Hammer-beam Truss. Early English Form

It is therefore generally impracticable to use a hammer-beam truss in a wooden building. Where these trusses are used, the CEILING is generally formed of木板 sheathing, nailed to the under side of the JACK-RAFTERS between the purlins, thus allowing the latter to be seen. The purlins are generally decorated, and FALSE RIBS are often placed vertically between them, to divide the ceiling into PANELS. The main rafters should be made very large to prevent them from breaking at the point A, Figs. 28 and 29.



**First Church, Boston, Mass.** An excellent example of a truss adapted to modern conditions is shown in Fig. 30, which is half of one of the trusses designed by Ware & Van Brunt, for

#### 29. Hammer-beam Truss. Early English Form

**Boston, Mass.** The truss is finished in black walnut and has very strong and heavy. Fig. 31 shows the framing of the : the casing and FALSEWORK. It should be noticed that **lamin** in the upper part of the truss, Fig. 30, there is an iron



Fig. 30. Hammer-beam Truss. First Church, Boston, Mass.

which resists the tensile stress. In this form of truss the line of action of the arch enters the wall just above the CORBEL, *K*; and, as it is inclined only about  $30^\circ$  from the vertical, its tendency to overturn is not very great, and may be resisted, in this particular case,




Fig. 31. Framing of Truss Shown in Fig. 30

2 ft thick, thoroughly reinforced by a BUTTRESS of proper height on the outside. In trusses of this kind, the various members are fastened together wherever they cross or touch each other, so as to make a whole as rigid as possible. No dependence should be placed on casings and panel-work for any extra strength.

Truss for Emmanuel Church, Shelburne Falls, Mass. Fig. 32 shows another form of truss designed by Van Brunt & Howe, for Emmanuel Church, Shelburne Falls, Mass. It is probably a variation of the HAMMER-BEAM





Fig. 33. Wooden Truss with Iron Tie. Spans up to Thirty-six Feet

form and when securely bolted together at all the joints can be designed to exert very little thrust on the walls. The rafters and cross-tie are formed of two pieces of timber, separated but bolted together, the upright members passing between these pieces. The hammer-beams are

ngels. The action of the stresses in hammer-beam trusses is napter XXVII, pages 1087 to 1089.

usses with Iron Ties. Where there is no ceiling beneath the lesirable to make the trusses as light in appearance as possible,



Detail of Joint B,  
Fig. 33




Fig. 33a. Alternate Detail of Joint at  
Ridge, Fig. 33

steel rods may be used for the ties, and the wooden rafter-  
is retained. For moderate spans such trusses are cheaper than  
nd where the rafters and purlins are of wood they are about as  
and 84 show forms of trusses well adapted to many roofs. The  
n in Fig. 34 are for yellow-pine or Douglas-fir timber and wrought-




Fig. 34. Wooden Truss with Iron Ties

are ample for a slate roof, the trusses being spaced from 12 to  
1. Trusses of the form shown in Fig. 33 are sometimes made  
and D continuous. They should not be made in this way,  
the entire rod is proportioned for the stress in C, as this stress  
that in D. The best construction for the joint B is illustrated

in Fig. 33A, which shows a CAST-IRON SHOE fitted to the end of the strut to receive the pin. For the truss shown in Fig. 34, a shoe made as shown in the detail drawing makes a better connection for the rods, two of the latter being placed outside of the brackets and three between them. For a truss with single strut, a TURNBUCKLE on the rod *E* serves to tighten the rods. When there are three struts, there should be five turnbuckles, as shown in Fig. 34. A cast-iron shoe should be made to receive the foot of the rafter and the rod secured to a pin passed through shoe and rafter. At the apex also, of the truss shown in Fig. 34, there should be castings to receive the ends of the rafter and pins for the tie-bars. The apex-joint of the truss (Fig. 33) may be made either by crossing the rods through CAST WASHER, or as shown in Fig. 33a. The pins at the joints should be computed for shear, bearing and flexure. More modern construction replaces the cast iron shown with STEEL PLATES and PINS. When a hammer beam truss is to be supported on a clerestory-wall which is not very thick nor braced from the outside, a truss of the form shown in Fig. 35 may be used to advantage. It has the appearance of a hammer-beam truss and when placed over a high nave the effect of the rods is not objectionable. The tie-rods should extend through the hammer-beams to their outer ends.

Truss for Grace Chapel, New York City. The CURVED RIBS *a, a*, Fig. 35, have a tendency to bend at their smallest section and BRACES under the hammer-beams are necessary to prevent vertical deflection in the latter. A truss similar to this was used in Grace Chapel, New York City.




Fig. 35. Hammer-beam Truss for Grace Chapel, New York City




Fig. 36. Truss for Metropolitan Concert Hall, New York City

Truss for Metropolitan Concert-Hall, New York City. Fig. 36 shows a form of truss used to support the roof of the Metropolitan Concert-Hall, New York City, George B. Post, architect. The span is about 54 ft and the proportions are about as shown. The arch between rafters and raised rib is ornamented with sawed work and the truss has a very light and airy appearance. The tie-rod is kept from sagging by a vertical rod from the crown of the arch.

arched Ribs with Iron or Steel Ties. For roofing large halls the ORIENTAL TIMBER ARCH, with an iron or steel tie to take up the thrust, is about the cheapest construction, especially where there is no support. Figs. 37 and 38 are good examples of this form of

Fig. 37. Segmental Timber Arch

the ribs supporting all the load and the TIE-RODS preventing the ribs from the spreading which would result without them.

**L. C. M. A. Building, Boston, Mass.** This truss is shown in the framework shown above the arch is simply to support the purlins and carry the load directly to the arch. It does not assist the ribs in carrying the load.




Fig. 38. Segmental Timber Arch


**the Fifth Avenue Riding-School, New York City.** The trussing the roof of the Fifth Avenue Riding-School,\* New York is unusual and very ingenious; and as it is an excellent example of the arched form of truss, a brief description is added. The room, which is 106 ft 6 in long by 73 ft wide, is shown in Fig. 39. It is free from columns, the entire roof being supported by two large ones of which is shown in Fig. 38. The entire roofing is supported by the arch, resting on these two large ones, each of the latter, however,

was altered in 1905. The old trusses were used in the altered structure.






ying a roof-area, equal to about 2 930 sq ft, and a great amount work. The method employed to resist the thrust of these large the use of rods showing in the room is very ingenious. Opposite of the iron posts which receive the arched ribs are oak struts



ed Wooden Truss. City Armory, Cleveland, Ohio. Span 79 feet

iron tie-bars and heavy iron beams and together forming a t each end. These two trusses are prevented from being pushed -in iron tie-bars in each side wall, as shown in the plan (Fig. 39). the two iron posts are tied together by iron rods running under



Arched Wooden Truss, Sanger Hall, Philadelphia, Pa.

length of the room. Altogether this gives for the tie-rods by 1-in iron bars and one  $1\frac{1}{2}$ -in-diam iron rod, equivalent tie-bars. Enlarged sections of the ribs, uprights and braces 8. It should be noticed that the uprights have iron rods holding the two ribs together. Fig. 40 shows a detail, or

enlarged view, of the iron **SKEWBACK** and post at each end of the truss shown Fig. 38.

**Truss for City Armory, Cleveland, Ohio.\*** Fig. 41 shows the method adopted for supporting the roof and gallery, the arch being of wood.

**Truss for S nger Hall, Philadelphia.†** Fig. 42 shows one-half of **ARCHED WOODEN TRUSS** which, with seventeen others, was designed to support the roof over the central bay of S nger Hall, Philadelphia, Hazelhurst & Huck

... Line

Fig. 43. Three-centered Curved Wooden Truss. O. N. G. Armory, Cincinnati, O.

architects. This building was erected in 1897 for the use of the Eighteenth National S ngerfest, and was intended only for temporary use. With dimensions slightly increased, however, these trusses would be suitable for permanent use. They were spaced 20 ft center to center. A description of the building and trusses was published in the Engineering Record of January 1897.

**Truss for the O. N. G. Armory, Cincinnati, Ohio.** Fig. 43 shows a truss used in this building. The curve of the axial line of the arch-truss is a three-centered ellipse. Hannaford & Sons were the architects of the building. G. Bouscaren was the designer of the trusses. (See the Engineering and Building Record, December 7, 1889.)

\* The building has been remodeled and is now used for commercial purposes.

† This building was torn down immediately after the meeting.

## 2. Types of Steel Trusses

**Pitched Roofs.** For ordinary conditions and for spans under 48 ft. the types shown in Figs. 44 to 55 will generally meet the requirements of strength and economy. Trusses of these types are composed of steel beams and angles.

At the joints. This is a cheaper combination of members. It is made of rods with pin-joints. The dimensions of the members do not exceed 12 in. They can be riveted up in the shop. The judgment will be made of the parts which are riveted at the building; but entire trusses having spans even 48 ft. can be raised from the ground and put in place. Occasionally a structural magnitude that this is not feasible, in which case the trusses are made in parts and riveted afterwards. For a narrow shed or shop a





Fig. 44. Truss for a Narrow Shed or Shop

be riveted at the building; but entire trusses having spans even 48 ft. can be raised from the ground and put in place. Occasionally a structural magnitude that this is not feasible, in which case the trusses are made in parts and riveted afterwards. For a narrow shed or shop a



Simple Fink Truss. Spans from Twenty to Thirty-six Feet

The truss shown in Fig. 44 is the most economical, the truss proper to be enclosed within the points A, B, C. This truss is practically shown in Fig. 45. For spans of from 24 to 48 ft, and inclining 6 in to the foot, the types shown in Figs. 46 and 47 are the trusses of the types represented by these two figures are called




Fig. 46. Fan Truss. Spans from Thirty-six to Fifty Feet

The truss shown in Fig. 45 is known as a SIMPLE FINK TRUSS.

Fig. 47 is supported on columns, the KNEE-BRACES B and the truss is used only when the building is subjected to wind-pressure.

By the middle dotted line, Fig. 46, is generally inserted. The construction demands three purlins on each side of the truss,

one of the forms shown in Figs. 48, 49, 50, or 51 should be used. The **FRENCH** appears to be generally given to those trusses in which the tie-beam is raised or cambered in the middle. The truss shown in Fig. 51 may be called




Fig. 47. Fan Truss with Knee-braces. Spans from Forty to Sixty Feet

a **TRIANGULAR PRATT TRUSS** as the web is composed of verticals in compression and diagonals in tension. This truss is not as economical as the **FINK TRUSS** except when the inclination of the rafter is less than  $\frac{1}{4}$  pitch. This is on account of the great length of the web-members in compression. In design




Fig. 48. Fink Truss. Spans from Forty to Eighty Feet

steel trusses it is desirable to have as many members, and especially as many long members, in tension as possible, as a given weight of steel resists a much greater stress when in tension than when in compression. The great economy of **FINK TRUSSES** and **FAN TRUSSES** lies in the fact that most of the members




Fig. 49. French Truss. Spans from Forty to Eighty Feet

are in tension and the struts are short. By comparing Figs. 50 and 51, it is seen that the inner strut in Fig. 50 is only one-half as long as the strut in Fig. 51. If the roof is hipped it is desirable to have vertical members in the trusses to receive the short trusses or **TRUSSED PURLINS**.

## Types of Steel Trusses

**nk and Fan Trusses.** The **DEPTH** of these trusses is determined by the roofing-material. Thus slate should be used where the rise is not equal to one-third the span. If corrugated metal roofing is used, the rise should be not less than one-fourth and for corrugated metal roofing the span. Steel-roll roofing may be used where the span. There are many kinds of so-called **READ** which may vary in slope from 1 in 12 to 1 in 4.





Fig. 50. Fink Truss with Vertical Struts

For trusses, the most economical pitch for a roof is a quarter-pitch, or what is commonly called a **QUARTER-PITCH**, the rise for each 12 in of run, or  $26^{\circ} 34'$ . When the span is large, some other type of truss is generally used. The pitch of the roof is determined almost entirely by the rise, which is generally made from 6 to 7 in in 12 in.




Triangular Pratt Truss

**TRUSSES OR FAN TRUSSES** having inclined rafters not exceeding 1 in 12 is more economical than a horizontal chord truss whose bottom chord has a rise of 2 or 3 in 12. Fig. 49, presents

an example, rather than one with a horizontal chord. Raising the pitch of the roof actually increases the stresses in the truss-members.

For steep roofs, however, it is generally as economical to use a horizontal chord, because of the shortening of the members.

**TRUSSES.** The **NUMBER OF PANELS** that should be used is determined in great measure by the construction of the roof.



Fink Truss with Knee-braces. Span Sixty-eight Feet

When purlins are used the length of a panel may be as great as 12 ft. If rafters are used and the planking of the roof is nailed directly to the rafters, the planking should be placed not more than 8 ft apart; and if the roof is secured to the purlins, the purlins should be not more than 4 ft apart. Whenever the purlins are more than 4 ft apart the joints should be staggered to prevent large bending-stresses in the

The spacing of the purlins, therefore, generally determines the number of panels in each half of the truss. For this reason also, the same form of truss may be required for spans of 40 and 80 ft; but of course the members will not be so heavy in the 40-ft truss as in the one with greater span. Most of the trusses shown in Figs. 45 to 55 are drawn from executed designs and give a good idea of the most economical division for different spans.

**Truss over Car-Barn, Newark, N. J.** When stresses due to flexure are developed in the truss-rafters, that is, when they are loaded between the joints,




Fig. 53. Fink Truss. Span Fifty-one Feet Six Inches

the distance between the latter should not exceed 9 ft, and preferably 7 or 8 ft, depending somewhat upon the distance between the trusses themselves. The diagram shown in Fig. 55 represents one-half of one of the steel trusses used for roofing a car-barn for the North Jersey Railway Company, Newark, N. J. There are 13 of these trusses spaced 19 ft  $2\frac{1}{4}$  in on centers, each having a span of 98  $\frac{1}{4}$  ft between the centers of the supporting columns, to which they are riveted by splice-plates engaging the end connection-plates and the webs of the columns. The dimensions of the principal members of these trusses are indicated in columns




Fig. 54. Fink Truss with Vertical Struts, for Drill-hall. Span Eighty Feet

in connection with Fig. 55. There is a more complete description in the *Engineering Record* of June 22, 1901. These trusses were shipped in four sections, and were assembled on the ground in a horizontal plane and riveted up complete. The bottom chord was stiffened by rails lashed on each side of its ends, and a sling being attached to the apex of the top chord, the truss was lifted and set on top of the columns by a gin-pole, 50 ft in length. The roofing consists of corrugated iron supported by 5-in I-beam purlins, weighing 10 lb to the foot, spanning from truss to truss and bolted to the rafters.

ch end. The general spacing of the purlins is 4 ft 9¾ in. This is of an extremely light roof, the weight of each truss being about the entire weight of truss, purlins, bracing of lower chord and roofing being only 8 lb for each horizontal foot of surface cov-

List of Descriptions of Different Types of Roof-Trusses  
Engineering Record

Date	Type	Number of panels
Feb 19, 1892.....	Howe	8
Nov, 1901.....	Fink	8
May 4, 1902.....	Fan	12
May 22, 1902.....	Fink	8
Oct 12, 1905.....	Pratt	6
Nov 2, 1905.....	Fan	12
Nov 16, 1905.....	Fan	12
Nov 2, 1907.....	Fink	8
Nov 2, 1907.....	Truss	16
Nov 16, 1911.....	Truss	12
Mar 7, 1911.....	Fink	16

mill-hall. The truss shown in Fig. 54 was designed for the roof of a building having a span of 80 ft and a spacing between trusses of 20 ft. The truss is constructed with 2 by 8-in rafters supported by purlins at the




Fig. 54. Car-barn, Newark, N. J. Span Ninety-eight Feet, Three Inches.  
(See, also, Chapter XXVIII, Fig. 25)

*E* and *F*. Sashes were to be placed in the rise *CD*, to light the building. The joint at *X* was located with reference to the gallery-rod; but if there had been no gallery it would have been located to space the vertical struts uniformly, as in Fig. 50. In all cases the PLUS SIGN adjacent to a member denotes that the member is in COMPRESSION, while the MINUS SIGN denotes that it is in TENSION. The main rafter, as *CD*, *DE* and *EF*, in Fig. 54, and *a* and *b* are a part of the truss proper, but are merely a framework to

support the elevated roof, and in drawing the stress-diagram for the vertical loads they would be omitted.

In the issues of the Engineering Record given in Table III may be found descriptions and illustrations of several types of roof-trusses, including the forms described above.

**Fink Trusses with Pin-Joints.** The use of PIN-JOINTS in ordinary roof trusses has practically been abandoned, even for long-span heavy trusses. In the Engineering Record of March 12, 1892, there is a description of a Fink truss with pin-joints. The truss is heavy and is built entirely of rolled metal. The tension-members are 5, 6 and 7-in eye-bars. The span is about 105 ft.

**Trusses for Flat Roofs.** For supporting flat roofs or roofs having a pitch not exceeding 1 in to the foot, one of the types shown in Figs. 56 to 60 will give




Fig. 56. Warren Truss with Verticals. Span Fifty-six Feet

usually be found economical, the choice of the particular type depending somewhat on the span and on whether the truss is supported by columns or by brick or stone walls. For spans up to about 50 ft, either of the forms shown in Figs. 56 or 57 answer all practical requirements. The truss shown in Fig. 56 is intended to be used where the slope of the roof is at right-angles to the truss. It can be built, however, with the top chord inclined as in Fig. 57. The end-diagonals in Fig. 56 are in tension, while in Fig. 57 they are in compression. The portions of the lower chord between the end-joints and the walls (Fig. 56) have no stress




Fig. 57. Warren Truss with Verticals and Knee-braces. Spans from Thirty to Fifty Feet

from the roof-load, but are put in to add rigidity to the construction as a whole. In trusses supported by brick walls this type is preferable to that shown in Fig. 56, while the latter is more suitable when the roof is supported by columns. The vertical A, Fig. 57, is inserted to receive the tension or compression from the knee-brace B, and has no stress from the roof-loads.

**Double Warren Truss.** The truss shown in Fig. 58 is known as a DOUBLE WARREN TRUSS, and is desirable where it is important to make the truss as shallow as practicable. It can be built with light members, and is a very



especially suitable for roofs supported by steel columns. Fig. 58 is a truss in actual use. The member in the middle indicated by the *x* could never be omitted, although examples may be found where it is included. Fig. 59, also, represents a roof-truss which was constructed over a span of 57 ft and supported by steel columns. The entire load is transmitted to the columns at the intersection of the diagonals.




Fig. 58. Double Warren Truss

up chord. Fig. 60 shows a truss of 96-ft span over a pier-shed, where the trusses being spaced 20 ft apart. They are about 10 ft high and weigh about 1300 lb each. They were delivered from the shops completely riveted, and were raised and set in position by falls suspended from the top of the pier. The dimensions of these trusses are given in the Engineering Record, May 18, 1896.



Fig. 60. Pratt-truss Type. Span Fifty-seven Feet

**MINUS SIGNS** in these illustrations, as has been mentioned, indicate **COMPRESSION** and **TENSION**, respectively, under a uniformly distributed load. The **PLUS** and **MINUS SIGNS** used together indicate that a member may be subject to **EITHER TENSION OR COMPRESSION** according to the direction of the wind or to the manner of distribution of the snow. In trusses unsymmetrical loads may change the stresses in the




Fig. 61. Pratt-truss Type. Pier-shed, New York City. Span Ninety-six Feet

in the middle of the truss. This **CHANGING OF STRESSES** due to moving loads is considered on pages 1096 to 1104. The trusses shown in these illustrations are almost invariably built with riveted connections and with gusset plates for all members.

The **RAFTER**, shown in Figs. 61 and 62, is the form of **STEEL TRUSS** used to support floor-loads, the members indicated by double lines being in **COMPRESSION** and those indicated by single lines in **TENSION**. When

supporting floors are subject to moving loads, **COUNTERTIES** should be inserted where indicated by dotted lines. For trusses of this type **PIN-CONNECTIONS** are generally employed and are preferable to **RIVETED CONNECTIONS**.

**The Quadrangular Truss.** The truss shown in Fig. 63 is known as a **QUADRANGULAR TRUSS**, and has the proportions of the truss over the amphitheater




Fig. 61. Pratt Truss

of the Madison Square Garden, New York. Figs. 64 and 66, also, show variations of this type, differing, however, from the latter in having all the diagonals each half-truss inclined in the same direction. In the typical truss their direction is usually reversed at about the middle of each half-span in order to keep the members in tension. The **PLUS AND MINUS SIGNS** indicate the kind of stress produced




Fig. 62. Suspended Pratt Truss

a member by a uniformly distributed dead load. It should be noticed that the middle diagonals of trusses 64 and 66 are in compression. These trusses are well adapted to steel construction and to spans up to 180 ft. When the span exceeds 100 ft one end of the truss should be supported on **ROLLERS** to allow for the **EXPANSION OR CONTRACTION** in the steel. In these trusses the load is trans-




Fig. 63. Quadrangular Truss. Amphitheater, Madison Square Garden, New York City

mitted to the top of the column-support, the truss proper being included within the points *A*, *B*, *C*, *D* and *E*, Figs. 64 and 65. The continuation of the bottom chord to the columns is for the purpose of bracing the roof from the latter, there being no stresses in these end-chord members due to vertical loads. This member *B*, Fig. 63, and the corresponding member in Figs. 64 and 65 should be constructed to resist both tension and compression. For short spans the load






Fig. 64. Quadrangular Truss. Span Eighty Feet

Fig. 65. Quadrangular Truss




of Trusses in Auditorium, Kansas City, Mo. Plan of Two Trusses Showing Lateral Bracing

chord may be made in the shape of a semicircle or half-ellipse so as to give more of an arch-effect. There are numerous examples in this country of



**Fig. 67. Riveted Truss with Broken Top Chord. Power-house, Interborough Rapid Transit Company, New York City**



**Fig. 68. Pin-connected Truss Over Drill-hall, 71st Regiment Armory, New York C**

angular trusses having spans of from 100 to 180 ft. For the wider spans it is customary to build the trusses with PIN-CONNECTIONS, EYE-BARS being used for the ties. When this is done it is usually necessary to insert COUNTERBRACING

of each half of the truss as shown by the dotted lines, Fig. 63, symmetrical or wind-load the stresses in the diagonals are gener-

For spans less than 100 ft, the trusses may be built with RIVETED

In this case the diagonals are generally made of angles capable both tension and compression, the counterbraces, therefore, not

For this type of truss the stresses due to wind and snow should independently of the dead load and the members computed for stresses produced by every possible combination of loading.

the Auditorium, Kansas City, Mo. A description, with the truss shown in Fig. 66, which is a diagram of one of the trusses is City Auditorium, may be found in the Engineering Record for and in the Engineering News of November 2, 1899.

uss with Broken Top Chord. A description is given in the record of October 15, 1904. The span is 78 ft between centers ng columns (Fig. 67).

Drill-Hall, New York City. A pin-connected truss, over the : 71st Regiment Armory, New York City, has a span of 190 ft escriptions of it are given in the Engineering News of June 16, : Engineering Record of July 2, 1904 (Fig. 68).

#### 6. Arched Trusses

between an Arched Truss and a Trussed Arch. For sup- f of very large spaces such as drill-halls, riding-halls, railway ., trusses in the form of arches or arches composed of trussed en employed. The essential difference between an **ARCHED TRUSS** **ARCH** is that under vertical loads the supporting forces of an arched al, while for 1 they are

usses. Pre- r 1880 most iron trusses are built in bow, from **BOWSTRING**





Fig. 69. Bowstring Truss

trusses of this type were built with spans of from 88 to 211 e at the middle of from  $\frac{1}{8}$  to  $\frac{1}{4}$  the span. At that time this



70. Bowstring Truss

type was considered the most economical for spans exceed- ing 120 ft, but in recent years they have been com- paratively little used. Fig. 69 is the diagram of a bow- string truss with a span of 153 ft 6 in. The trusses in this particular case are spaced 21 ft 6 in apart.

chord consists of a wrought-iron deck-beam 9 in deep, with plate, riveted to its upper flange. Towards the springing gthened with 7 by  $\frac{7}{8}$ -in plates riveted on each side of the : struts are wrought-iron I beams 7 in deep. The bottom tional area of  $6\frac{1}{2}$  sq in and each diagonal tension-rod a

diameter of  $1\frac{1}{4}$  in. Each truss is fixed at one end and rests on ROLLERS at the other, allowing free expansion and contraction due to changes of temperature in the metal. Fig. 70 shows a similar truss having a span of 213 ft. It consists of BOWSTRING PRINCIPALS spaced 24 ft apart. The rise is one-fifth the span, the middle of the bottom chord rising 17 ft, and of the top chord 40 ft above the springing. The top chord is a 15-in wrought-iron I beam and the bottom chord a round rod in short lengths, 4 in in diameter and thickened at the joints. The ties of the bracing are of plate iron from 5 to 3 in in width,  $\frac{5}{8}$  in thick. The struts are formed of bars having the form of a cross. During the last ten or twelve years a number of roofs have been supported on trusses which can hardly be classed as SIMPLE TRUSSES; and yet it is questionable if they are TRUE ARCHES. Probably the frames act partially as simple trusses and partially as arches.

**Trusses for the Conservatory Building, Garfield Park, Chicago, Ill.** Engineering News, August 27, 1908. The roof is supported by POINTED TRUSSES spaced 12 ft 6 in on centers. The truss-span is 80 ft 6 in, center to center end-supports. The chords of the trusses are parallel and connected by WARREN BRACING. Both ends of the trusses are bolted to the supports and consequently there must be some horizontal thrust under certain conditions. The trusses are riveted at all joints and have no HINGES or PINS.

**Trusses for the Chicago and North Western Railway Station, Chicago, Ill.** Engineering Record, June 18, 1910. The roof over the main waiting-room is carried by trusses each having a span of 90 ft 4 in and a rise of 31 ft and bolted to columns about 27 ft 6 in apart. All connections are riveted. The clear height of the bottom chords at the middle is 84 ft.

**Trusses for the Peoria and Pekin Union Railway Trains-Shed, Peoria, Ill.** Engineering Record, December 8, 1900. The trusses are riveted to columns about 30 ft above the floor and spaced 20 ft apart. The truss-span is 109 ft 4 in, center to center of end-supports, with a clear rise of about 10 ft. The depth at the middle is 18 ft and at the end 6 ft. All connections are riveted.

**Trusses for the New Union Station, Washington, D. C.** Engineering Record, February 6, 1904. The concourse-roof is supported by CRESCENT TRUSSES, each having a span of 132 ft  $5\frac{1}{2}$  in and a clear rise of 22 ft  $5\frac{1}{2}$  in. They are spaced about 39 ft 4 in apart. One end of each truss rests upon masonry and the other is riveted to a heavy plate girder. All connections are riveted. The bottom chord at the middle is 45 ft above the floor. The trusses over the waiting-room of the same station have a span of 137 ft 8 in and a rise of 45 ft 5 in. The chords are parallel and the ends are anchored with bolts to the masonry.


**Trusses for the Riding-Hall, Armory for Squadron C, National Guard, Brooklyn, N. Y.** Engineering News, August 29, 1907. The main trusses have a span of 179 ft 2 in and a rise of about 66 ft in the clear. The total depth of the truss at the middle is 14 ft, while at the ends, where the chords approach each other and finally become vertical, it is 3 ft 3 in. One end is anchored to the masonry and the other is on rollers. The trusses are in pairs 10 ft  $11\frac{1}{2}$  in on centers and the pairs are spaced 38 ft  $8\frac{1}{2}$  in on centers. All connections are riveted.

**Trusses for the New Rock Island Terminal Station Train-Shed, Chicago, Ill.** Engineering Record, September 12, 1903. Engineering News, August 1903. The trusses over the tracks have a span of 221 ft 1 in center to center of the end-pins, a rise of 28 ft and a depth at the middle of 25 ft 6 in. They

columns and are spaced from 10 ft 3 in to 19 ft 6 in apart. All sections are made with pins.

**Trusses with Horizontal Ties.** CURVED OR ARCHED TRUSSES are treated with a horizontal member connecting the ends at the supports. The structure as a whole, including the horizontal member, usually a SUSPENSION-ROD, a SIMPLE TRUSS requiring only vertical supporting forces at the ends, provided one end is free to move, as it is when placed on rollers. If the trusses are supported by long columns it may be assumed to have freedom. A few examples are given, some of which are treated as TRUE ARCHES.

For the Sullivan Square Station, Elevated Railway, Boston, Engineering Record, June 15, 1901. Fig. 71. These ARCHES spring



Truss for Sullivan Square Station, Elevated Railway, Boston, Mass.

rests on two 4 1/4-in pins at each end, as indicated in the diagram, and is connected to them. The bracing below each pin is riveted to the arch itself is built of angles and plates with riveted connections. The diagram shows the joint at A where the tie-rods are connected and a SUSPENSION-ROD from the crown of the arch. This construction is on the same principle as that of the WOODEN ARCH shown by Fig. 42.

**Express Company's Receiving Station, New York City.** For the Express Company's Receiving Station, New York City, Engineering Record, October 22, 1904. The roof-trusses in this building are supported by brick walls at the level of the second-story floor and have been braced by I beams which form a part of the floor-framing of the building. Each truss has a span of 74 ft 4 in and a clear rise of 27 ft. They are spaced 24 ft 5 in apart and have all connections riveted. Since the

es are very heavy one might be led to classify these trusses with TRUE ARCHES fixed at the ends; but as the condition of FIXED ENDS rarely obtains in practice it is better to consider this type of structure as an ARCHED TRUSS with a tie-rope or possibly as similar to the type shown in Fig. 75.

Table IV. General Dimensions of a Few Three-Hinged Arches

Location	Span		Rise		Tie
	ft	in	ft	in	
Syracuse University.....	101	4	...	...	Floor-beams
Lawson Riding-Academy.....	106	0	56	2¼	No tie
Machinery Hall, Chicago Exp.....	121	10	96	3	† Two 1½ × 1½
22nd Reg. Armory, New York....	134	0	32	6	
Coliseum, Chicago (new).....	149	9	66	6	† 2½ × 2½
Newark, N. J., Armory.....	163	6	73	5¾	† Two 2¾ round rods
Government Bldg., St. Louis Exp..	172	0	69	9½	9-in I beam
Coliseum, St. Louis.....	178	6	80	0	No tie
Hartford, Conn., Armory.....	181	0	90	2½	No tie
Frankfort, Germany, Train-Shed...	184	0	94 (about)		No tie
69th Reg. Drill-Hall, New York...	189	8	103	4½	† Two 1¾-in round rod
5th Reg. Armory, Baltimore, Md...	190	4	88	0†	Two channels
47th Reg. Armory, Brooklyn, N. Y.	191	4	84	0	† Two 4 × ¾-in plates
Coliseum, Chicago (old).....	215	0	73	0	
74th Reg. Armory, Buffalo, N. Y..	227	0	94	0	
Coal-Shed, Wende, N. J.....	230	0	...	...	† 9 × ½-in plate
Jersey City Train-Shed.....	252	8	89	9¾	Two 12-in I beams
Philadelphia Train-Shed.....	259	0	88	3½	
Broad Street Station, Phila.....	300	8	100	4	
Manufactures and Liberal Arts Bldg., Chicago Exp.....	368	0	206	4	

Location	Distance, center to center*		Reference
Syracuse University.....	17 ft	11½ in	R. Aug. 22, 1908
Lawson Riding-Academy.....	32 ft	0 in	R. Dec. 31, 1904
Machinery Hall, Chicago Exp.....	50 ft	8 in	R. Dec. 24, 1892
22nd Reg. Armory, New York....	11 and 52 ft		N. May 5, 1910
Coliseum, Chicago (new).....	22½ to 25 ft		N. Sept. 14, 1899
Newark, N. J., Armory.....	31 and 26½ ft		R. May 26, 1900
Government Bldg., St. Louis Exp..	35 ft	0 in	N. Sept. 29, 1904
Coliseum, St. Louis.....	36 ft	8 in	N. Aug. 10, 1899
Hartford, Conn., Armory.....	6 and 52¾ ft		R. Sept. 12, 1908
Frankfort, Germany, Train-Shed...	33 ft	6 in	R. Mar. 5, 1892
69th Reg. Drill-Hall, New York...	6¾ and 38¾ ft		R. June 3, 1905
5th Reg. Armory, Baltimore, Md..	.....		R. May 14, 1904
47th Reg. Armory, Brooklyn, N. Y.	34 ft	4 in	R. Dec. 23, 1899
Coliseum, Chicago (old).....	46 ft	8 in	N. Nov. 12, 1896
74th Reg. Armory, Buffalo, N. Y..	.....		R. June 9, 1900
Coal-Shed, Wende, N. J.....	22 ft	10¼ in	R. Oct. 3, 1908
Jersey City Train-Shed.....	14½ and 43½ ft		N. Sept. 25, 1899
Philadelphia Train-Shed.....	.....		R. July 16, 1892
Broad Street Station, Phila.....	.....		R. June 10, 1893
Manufactures and Liberal Arts Bldg., Chicago Exp.....	.....		N. Sept. 1, 1892

\* Center to center of end-supports.

† Dimensions in inches.

‡ To lower chord.

N. Engineering News.

R. Engineering Record.



for Drill-Hall, 13th Regiment Armory, Scranton, Pa. Engineering Record, August 24, 1901. These roof-trusses are about 5 ft deep and about 12 ft on centers. The truss-span is 156 ft, over all, with a rise 16 ft clear. The ends rest on masonry and are connected by a tie consisting of two 1½-in round rods. Expansion motion is provided at one end by the holes for the anchor-

for Armory Drill-Hall, Scranton, Pa. R. I. Engineering Record, August 13, 1907. The type of truss in this building is commonly known as a THREE-HINGED ARCH, consisting of two curved members joined by a pin at each support and by a tie and one end-shoe at the crown; with rollers and hence the




Fig. 71A. Detail at A, Fig. 71.

A SIMPLE TRUSS composed of three members, two of which are curved members. The truss-span is 166 ft 8 in and the rise about 61 ft. The members are riveted and spaced about 26 ft 1 in on centers.

for the Pennsylvania Railway Train-Shed, Pittsburgh, Pa. Engineering Record, August 23, 1902. The trusses have three HINGES and a ROLLER-BEARING at one end. The truss-span is 255 ft ¾ in between supports, the rise 93 ft between pin-centers and the depth at the center 16 ft. The members are riveted and stand in pairs 9 ft on centers and the pairs 12 ft 6 in on centers.

A three-hinged Arch as employed for supporting the roofs over large halls, drill-halls, etc., is composed of two CURVED TRUSSES, usually of equal form and dimensions, resting upon PINS at the supports and connected by a tie over the middle of the span. The supports are assumed to be fixed and are often connected by a TIE to insure stability and take up the horizontal thrust of the arch. While a metal tie between masonry supports would make these supports FIXED in position under all or any conditions for all practical purposes they may be so considered; and these STRUCTURES which have ties, provided there is no arrangement for expansion and-movement due to roller-bearings, etc., may be classified with fixed supports must resist all horizontal as well as all vertical forces. The ties are usually placed below the floor-level so that the tie-rods, if they are to be concealed by the floor or even made a part of its framing. Under these conditions the arches can be so designed that the horizontal thrust is balanced and the supports designed without the use of the horizontal tie. The advantages of the THREE-HINGED ARCH for the class of buildings mentioned are economy and a maximum amount of clear space. Much of the economy results from the omission of support-columns. The base of the arch being very near the ground-level, it is also able to resist wind-pressure. Another advantage of this type is the freedom allowed under temperature-changes without causing additional members of the structure, the middle part rising or falling freely about the pivots. In the case of the buildings of the Paris Exposition, it was estimated that a range of 100° F. would produce a change in level of 2 7/8 in at the center. CURVED TRUSSES are usually built of plates, angles, or channels, with

riveted connections and frequently with a solid-plate web at the bottom. The determining of the stresses and detailing of the members and joints require the services of a competent structural engineer; but the illustrations given will enable the architect to decide on the general shape of the trusses for the purpose of making preliminary drawings and the computations and detail drawings can be made later.




Fig. 72. Half Truss. Three-hinged Arch. Manufactures and Liberal Arts Building Chicago Exposition


**Trusses for Railway Station, Frankfort-on-the-Main, Germany.** The first suggestion for HINGING THE RIBS AT THE CROWN was made by M. Manton, a French engineer. The writer believes that the first application of this principle to roof-trusses, at least on a large scale, was made in the train-sheds of the Union Railway Station completed in the year 1888 at Frankfort-on-the-Main, Germany. These trusses have a span of about 184 ft. *Engineering Record* of September 12, 1891, and March 5, 1892.

**Trusses for Machinery Hall, Paris Exposition.** The large roof of the Machinery Hall of the Paris Exposition of 1899 was supported by trusses of

span being 368 ft and exceeding anything hitherto attempted in  
Since then trusses of this kind have been frequently used for  
exhibition-halls, train-sheds, armories, and similar buildings.

**Manufactures and Liberal Arts Building, Chicago Exposition of 1892** shows the half-truss of one of the **THREE-HINGED ARCHES** supporting the roof of the Manufactures and Liberal Arts Building of the Chicago Engineering News, September 1, 1892.

**Drill-Hall, Brooklyn, N. Y.** Fig. 73, in a similar manner, half-truss of one of the **THREE-HINGED ARCHES** over the drill-hall of



**Half Truss, Three-hinged Arch, Drill-hall, Brooklyn, N. Y.**

**Armory, Brooklyn, N. Y.** Engineering Record, December 19, 1892. Description of the arch shown in Fig. 74 is given in the Engineering Record, December 19 and December 24, 1892. The horizontal thrust due to the arch is small.

**Arches.** When there are only two pins, usually at the supports, they become **TWO-HINGED ARCHES**. As in the case of three-hinged arches, there may be a tie or the supports may be entirely depended upon to resist the horizontal thrust.

**Live-Stock Pavilion, Chicago, Ill.** In the Engineering News, December 15, 1892, there is a description of the **TWO-HINGED ARCHES** supporting the roof of the Live-Stock Pavilion building. The arch span is 198 ft, the rise 54 ft and the truss depth 12 ft. Each truss has a tie consisting of one 2 1/16-in round rod.

**Railway Station, Cologne, Germany.** This station, owned by the Prussian Railways, has **TWO-HINGED ARCHES** supporting the roof of the main hall. The arch-span is 209 ft 6 in and the rise 79 ft. There is a brief description of the arch in the Engineering News, October 6, 1892. A number of roofs



by structures similar to that shown in Fig. 75. While such a frame is a TWO-HINGED ARCH, owing to the lack of freedom at the supports, nevertheless, for all practical purposes, be so considered.

#### List of Buildings with Trusses of the Two-Hinged-Arch Type

Name	Span	Spacing
	ft	ft
ory, Pawtucket, R. I. ....	82	24
ory, Portland, Me. ....	92	25
nix Hall, Brockton, Mass. ....	96	24
ory, Northampton, Mass. ....	100	24
se Rink, Hartford, Conn. ....	104	25
sition Hall, Providence, R. I. ....	118	24.5
ry, Cleveland, Ohio ....	120	23 to 25
ry, Boston, Mass. ....	122	30
ry, 22d Reg., New York City ....	176	24.5
ry, Brooklyn, N. Y. ....	196	35

ures are described in Building Construction and Superintendence, Partadder and are similar to the type shown in Fig. 75.

es, or arches without hinges, are seldom employed in buildings. Examples cited above the structures have the appearance of being ds, but a closer inspection indicates that they are not sufficiently urant their being classed as FIXED ARCHES.

### 5. Cantilever Trusses

**Principles.** A CANTILEVER BEAM OR CANTILEVER TRUSS is that ger beam or truss which extends beyond one of the supports, as 79 and A in Fig. 80. The overhanging portion B is called the M and the portion C the ANCHOR-SPAN. The cantilever-arm may nd another beam or truss. The term CANTILEVER was originally te a projecting beam which served as a bracket; in engineering ote a beam or girder fixed at one end, by being either built into ore commonly the case, extended a sufficient distance beyond rm an anchorage. Thus in Fig. 76, which shows a beam resting , B is the cantilever or cantilever-arm and C the anchor-span or s obvious that if this entire beam were uniformly loaded the l carry the greater part of the total load; and also, that an V, at the end of the cantilever, might cause a negative reaction t the support D, in which case the reaction at P would exceed beam, unless the negative reaction at D is considered as an

Although both conditions of loading occur in practice, the the truss usually requires an anchorage rather than a support . As applied to roof-construction some such arrangement as 77 is generally required to make this method of support prac- wide middle span, with shorter spans or aisles on each side of ver-arm is usually made from  $\frac{1}{4}$  to  $\frac{1}{2}$  the middle span and a RUSS, represented by S, supported by the arms of the canti-support the rest of the roof. In all such cases, therefore, can- st be used in pairs, one on each side of the building; and there passages outside of the principal span to permit the use of the

outer or anchor-spans. This arrangement is generally found in auditoriums, armories, exhibition-halls and similar buildings, and is sometimes conveniently adapted also to other classes of structures. Of course, in a large building a beam consisting of a single member such as is shown in Fig. 77 could not be used.




Fig. 76




Fig. 77




Fig. 78




Fig. 79




Fig. 80

Figs. 76 to 80. Cantilevers and Cantilever Trusses

but the principle of construction is the same whether the cantilever is a single member or a large truss. Fig. 78 is the diagram of a truss which takes the place of the beam *CB* in Fig. 77, the single lines representing the tension-members and the double lines the compression-members. Fig. 81 shows the complete arrangement of two of these trusses with the accompanying middle truss, for





Fig. 81. Suggestion for Wooden Cantilever Truss

entire roof. The truss-principle shown in these figures may be developed almost any extent. The lower chord may be curved, but the general form of the truss is best adapted to those roofs in which a wide middle part is to be supported by cantilevers. For bridge-trusses or floors the form shown in Fig. 79 may be used; while for shed and platform-roofs, open on one side, the

own in Fig. 80 are about the only ones practicable. In this latter portions of the arms are such that only a slight support is required consequent compressive stress developed in the lower portion of the

**Advantages and Disadvantages of the Cantilever Truss.** The cantilever has some special advantages. The clear height in the middle is greater obtained with any other type excepting the three-hinged arch; its light and graceful, and there is no horizontal thrust and consequently no necessity for tie-rods. The particular advantage of this truss for very long spans is that it can be erected without scaffolding under the middle part, for this work this is considered as its only advantage. It is claimed by some engineers that the CANTILEVER TYPE OF TRUSS is not an economical one as desirable for spans of 150 ft or more as the THREE-HINGED ARCH, not as readily lend itself to methods of allowing for expansion and contraction as the THREE-HINGED ARCH, the BOWSTRING TRUSS, or the QUADRIANGULAR TRUSS. For certain classes of buildings, however, and especially where the clear span does not exceed 150 ft, it can perhaps be used with better structural effect than is possible with other types, the cost remaining low. For roofing platforms, grand-stands, etc., where an outer gallery is desired, it is the only type available.

**Grand-Stand, Monmouth Park, N. J.** Fig. 82 is a diagram of CANTILEVER TRUSSES supporting the roof of the grand-stand at this



2. Cantilever Truss, Grand-stand, Monmouth Park, N. J.

details of which were published in *Architecture and Building*, 1900. This is an instance in which the cantilever was the only type that could be used and the form adopted is both simple and economical. As seen from the drawing, the main supporting column extends to the roof truss, as is usually the case with cantilever trusses, and the truss is attached to the side of it. The upper and lower chords are made of two angles.

The bracing consists of angle-bars used in pairs and varying in size from  $\frac{1}{2}$  in. to 3 by 3 by  $\frac{5}{16}$  in., the whole frame being connected by

**the Fore River Ship-building Shed, Quincy, Mass.** In *Engineering Record*, July 26, 1902, there is a description of the roof of this building in which the CANTILEVER TRUSSES have an overhang of 60 ft.

**Grand-Stand, Empire City Trotting Association.** These trusses have CANTILEVER-ARMS at each end, 25 ft 6 in. on one side and 5 ft 6 in. on the other. The intermediate truss has a span of 110 ft. A full description is given in the *Engineering Record*, February 10, 1903. Examples of CANTILEVER ROOFS are given in *Building Construction*, Part III, by F. E. Kidder.

CHAPTER XXVII

STRESSES IN ROOF-TRUSSES

By  
MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

1. Roof-Loads. Data, Weights, Materials, Methods

**Data for Roof-Trusses.** Before the stresses in a roof-truss can be determined it is necessary to decide upon the character of the roof-covering, the method of supporting it between the trusses, the geometrical shape and spacing of the trusses and the spacing of the trusses.

**Roofing Materials for Pitched Roofs.** The materials suitable for covering pitched roofs are slate, burnt-clay tiles, metal tiles or shingles, wooden shingles, corrugated iron, tin with standing seams, standing-seam steel roofing and various kinds of ready roofing. The least slope to which these materials may be laid without danger of leaks, the weight per square foot of roof and the comparative cost are indicated in Table I. The cost, however, can only be considered as approximate, as it varies for different materials, localities and the scale of wages.

Table I. Covering Materials for Pitched Roofs

Material	Least rise of rafter in 12 in	Comparative cost per square
Slates, black.....	8	\$7.00 to \$12.00
Slates, green.....	8	7.00 to 10.00
Slates, red.....	8	12.00 to 17.00
Burnt-clay tiles, interlocking pattern.....	7	15.00 to 25.00
Tin shingles, painted.....	6	8.00 to 10.00
Galvanized-iron tile, painted.....	6	13.00 to 15.00
Cedar shingles, stained or painted.....	6	3.80 to 7.00
Corrugated iron, painted.....	3	4.00 to 4.50
Standing-seam steel roofing, painted.....	2	4.00 to 4.50
Ready roofing.....	1	3.50 to 4.00

**Roofing Materials for Flat Roofs.** Flat roofs or roofs having a fall from  $\frac{1}{2}$  to  $\frac{3}{4}$  in to the foot are usually covered with tar and gravel, asphalt, ready roofing, or tin with lock-and-solder joints. A good tin roof costs about \$8.00 a square, not including the painting. The other kinds vary from \$3 to \$4.50 a square.

**Manner of Supporting the Roof from the Trusses.** Wooden roofs, supported by wooden trusses, require common or jack-rafters to support the shingles or slate, and generally purlins to support the rafters, although in some cases may be more economical to span the rafters from truss to truss (Fig. 17, Chap. XXVI). When slates or burnt-clay tiles are used on steel roofs, they are usually secured to steel angles, running parallel with the walls and spaced from 8 to 10½ in apart, as may be necessary to accommodate the size of the slates.



span is not more than 6 or 7 ft, the angles may be fastened to the walls. As a rule, however, when slates or tiles are to be used, it is cheaper to space the trusses from 16 to 20 ft apart, and to use purlins and jack-raftering to support the smaller angles. Quite often, wooden rafters and sheathing are used for the trusses. This is more economical, but of course increases the weight. Protected steel is little if any better than wood. If corrugated metal is used for roofing, the most economical construction for steel roofs is to space the trusses from 16 to 20 ft apart, and to use light I beams for purlins, 12 in. on centers, as in Fig. 52, Chapter XXVI, the corrugated metal being fastened to the purlins by straps. If warm air comes in contact with the underside of a corrugated roof, either the roofing should be laid on boards, or an anticondensation lining should be provided, as otherwise the air will condense and fall on the floor or objects below. Flat roofs require rafters and sheathing, or fire-proof filling between the

trusses. From the above it is seen that the economical spacing depends to a great extent upon the kind of roofing that is used, and upon the span. As a general rule, however, the most economical spacing is as follows:

TRUSSES under 80-ft span, from 12 to 16 ft on centers.

TRUSSES over 80-ft span, from 16 to 24 ft on centers.

PURLINS under 80-ft span, from 16 to 20 ft on centers.

PURLINS over 80-ft span, from 20 to 40 ft on centers.

If a number of steel trusses of wide span is given in Chapter XXVI, and the distance between the trusses exceeds 16 ft for wooden roofs, it is generally necessary to use trussed purlins. Upon the kind of truss to be used, the spacing of the trusses and purlins, a section-drawing of the roof should be made, showing the truss, the points at which the purlins are to be supported, supporting the ceiling, if there is one, and any other loads that are carried by the trusses. The section and truss-drawing, with the weights of roofing-materials, will furnish the necessary data for determining the loads at each joint. Until the stresses have been determined, the members computed, and the joints detailed, an exact drawing of the roof, of course, cannot be made; but in order to compute the loads and stresses, it is necessary to know the positions of the joints, and these can be determined with sufficient accuracy before the exact sizes of the members are determined. Chapter XXVI gives sufficient information regarding the various types of trusses to enable one to decide upon the height and the number and positions of the struts and ties; and the sizes of the members can be approximately determined from preliminary drawings.

**Area Contributory to Any Joint.** Calculations for the stresses are always based on the assumption that the loads are transferred to the joints, and that the members are free to move at the joints as if the actual joints may be made with riveted or other connections. The reactions at the joints are, of course, equal to the reactions of the purlins or principals, if these receive the ceiling-joists or rafters. If the roof or ceiling is uniformly distributed, as is usually the case, the method of computing the joint-loads is to determine the roof area contributory to the joint, and to multiply this area by the weight of the roof per unit area. The area contributory to any joint is equal to the product of the span of the truss, measured half-way to the next joint, on each side, by the distance between the joints, or half-way to the next truss or wall, on each side. Thus if Fig. 1

represents truss 1, of Fig. 2, the roof-area contributory to joint 2 is, in square feet  $\frac{8 + 14}{2} \times a$ . For truss 2, the area supported by the same joint is  $\frac{14 + 12}{2} \times$  or, if we let  $D$  represent the length in feet of roof or ceiling supported at a joint, the area in square feet supported by joint 2 is  $a \times D$ , and the area s




Fig. 1. King-rod Truss

ported by joint 3 is  $2b \times D$ . In the same way, the ceiling-area supported by joint 6 is  $c \times D$ , the arrow-heads being half-way between the joints. It makes no material difference in the joint-loads whether the common rafters are supported on purlins or whether they rest on the top chord of the truss, provided




Fig. 2. Plan of Wall and Trusses

the purlins come at or close to the joints and the load is uniformly distributed. Thus the width of the ceiling contributory to joint 7 (Fig. 3) is equal to just the same as in Fig. 1. The arrangement in Fig. 1 produces cross-bend stresses in the tie-beam, while that in Fig. 3 does not. When the trusses are spaced a uniform distance apart,  $D$ , 2, is, of course, equal to the distance between centers of trusses. When the trusses are not spaced uniformly,  $D$  is equal to one-half the distance from the center of the truss on the left to the center of the truss on the right. When the purlin is more than 12 in from a joint, the roof-area is not symmetrical, and often the case at hips and valleys, the joint-load is determined by the principle of the REACTION OF BEAMS, as explained

Chapter IX. Examples showing the computation of joint-loads are given a little farther on.

**Roof-Load per Square Foot.** By the term ROOF-LOAD is meant the weight of the materials composing the roof, trusses and purlins, an ample allowance

an allowance for wind-pressure. The weight of the materials  
**DEAD LOAD.** Snow is generally considered a **LIVE LOAD**, acting  
 re pressure due to the wind is always assumed to act normal to,  
 les to, the surface of the roof; but for trusses of less than 100-ft

mm. (See, also, Figs. 12, 53 and 54 and Chapter XXVIII, Fig. 1)

r combined with the **DEAD LOAD** and **SNOW-LOAD** and treated  
 ad. This does not apply to the Fink and fan types. (See

**Computing Dead Loads.** The **DEAD LOAD** of any roof may be  
 efficient accuracy from the following data:

## **II. Weights per Square Foot of Roof-Surface**

1,  $2\frac{1}{2}$  lb; 18 in., 3 lb  
 k,  $7\frac{1}{4}$  lb;  $\frac{1}{4}$  in thick, 9.6 lb (the common thickness is  $\frac{9}{16}$  in for  
 r 20 in)  
 shingles, 11 to 14 lb  
 style, two parts, 12 lb; new style, one part, 8 lb  
 style, two parts, 19 lb; new style, one part, 8 lb  
 l tiles, 11 lb  
 b  
 ortar add 10 lb per sq ft  
 ets,  $1\frac{1}{2}$  lb; tiles,  $1\frac{1}{2}$  lb  
 or shingles, including one thickness of felt, 1 lb  
 uted or galvanized, No. 26, 1 lb; No. 24, 1.3 lb; No. 22, 1.6 lb;  
 o. 18, 2.6 lb; and No. 16, 3.3 lb  
 d roofing, 1 lb  
 ravel roof, 6 lb  
 ravel roof,  $5\frac{1}{2}$  lb  
 ofing (elaterite, rubberoid, asphalt, etc.), from 0.6 to 1 lb  
 rnalised-iron frame,  $\frac{1}{4}$ -in glass,  $4\frac{1}{2}$  lb;  $\frac{9}{16}$ -in, 5 lb;  $\frac{1}{2}$ -in, 6 lb  
 k, 3 lb per sq ft for white pine, spruce, or hemlock; 4 lb for yel-

Table III. Weights of Rafters per Square Foot of Roof-Surface

Size of rafter in inches	Spruce, hemlock, white pine. Spacing in inches, center to center			Hard pine. Spacing in inches, center to center		
	16	20	24	16	20	24
	1b	1b	1b	1b	1b	1b
2X 4	1½	1.2	1	2	1.6	1½
2X 6	2¼	1.8	1½	3	2.4	2
2X 7	2½	2.1	1¾	3½	2.8	2½
2X 8	3	2.4	2	4	3.2	2¾
2X 10	3¾	3	2½	5	4	3½

Wooden purlins weigh about 2 lb per sq ft of roof-surface when the span is between 12 and 16 ft.

For steel roofs the sizes and weights of the purlins and rafters should be computed for each particular case.

**Weight of Truss.** To the weight of the roof-construction proper should be added an allowance for the weight of the truss. If trusses could be built in exact accordance with the theoretical requirements their weight would be directly proportional to the roof-load and span; but as there is always some extra material, it is impossible to determine the weight of the truss exactly until it is completely designed. Several tables for the weights of wooden trusses and formulas for steel trusses have been published, but hardly any two of them are alike. The following are some of the formulas in use:

For Wooden Trusses

$$W = 0.04 L + 0.000167 L^2$$
$$W = 0.50 + 0.075 L$$

{ N. C. Ricker, for trusses like Fig. 1 and 5, Chapter XXVI.

H. S. Jacoby.

For Steel Trusses

$$W = 0.75 + 0.075 L$$
$$W = 0.6 + 0.06 L, \text{ for heavy loads}$$
$$W = 0.4 + 0.04 L, \text{ for light loads}$$
$$W = \frac{P}{45} \left( 1 + \frac{L}{5\sqrt{A}} \right)$$
$$W = 0.05 L + 12/A$$

Mansfield Merriman and Jacoby.

C. E. Fowler, for Fink trusses.

M. S. Ketchum, for steel mill-building trusses.

H. G. Tyrrell.

In the above formulas,  $W$  = weight of truss in pounds per square foot of horizontal projection of the roof supported,  $L$  = span in feet,  $A$  = distance between trusses, and  $P$  = capacity of truss in pounds per square foot of horizontal section.

Tables IV and V, compiled from a comparison of other tables and from the weights of actual trusses, are sufficiently accurate for the purpose of determining stresses. The weights given are probably slightly in excess of the actual weights of average trusses, as it is preferable to have the error, if any, on the safe side. It should be noted that the weights are for each square foot of roof-surface, and not for the horizontal area. Table VI gives the weights of a number of large steel roofs.

Weights of Wooden Trusses per Square Foot of Roof-Surface\*

Span	½ pitch	⅓ pitch	¼ pitch	Flat
	1b	1b	1b	1b
.....	3	3½	3¾	4
.....	3¼	3¾	4	4½
.....	3½	4	4½	4¾
.....	3¾	4½	4¾	5¼
.....	4¼	5	5½	6
.....	5	6	6½	7
.....	5¾	6¾	7	8
.....	6½	7½	8	9
.....	7	8½	9	10

Weights of Steel Trusses per Square Foot of Roof-Surface

Span	½ pitch	⅓ pitch	¼ pitch	Flat
	1b	1b	1b	1b
.....	5.25	6.3	6.8	7.6
.....	5.75	6.6	7.2	8.0
.....	6.75	8.0	8.6	9.6
.....	7.25	8.5	9.2	10.2
.....	7.75	9.0	9.7	10.8
.....	8.5	10.0	10.8	12.0
.....	9.5	11.0	12.0	13.2
.....	10.0	11.6	12.6	14.0

Weights and Spacing of Some Steel Roofs of Wide Span, Including Purlins and Braces, but not Roof-Covering or Rafters

Building	Type of truss	Span ft	Spacing, center to center of trusses, ft	Weight per sq ft sloping surface, lb	Weight of one truss, tons
Market, R. I....	Fig. 75†	82	24	8.7	6.7
and, Me.....	"	92	25	9.7	9
Brockton, .....	"	96	24	8.6	10
Hampton, .....	"	100	24	8.0	8.5
Hartford, .....	"	104	25	11.8	11.5
and, R. I....	"	118	24½	9.5	12.5
Armory, .....	"	120	23-25	....	....
Mass.....	"	122	30	12.4	21
and, N. Y....	"	176	24½	....	....
and, N. Y....	"	196	35	....	....

\* For scissors trusses, increase one-third.  
† Chapter XXVI.

The data for the first seven buildings in Table VI were compiled by H. C. Tyrrell, who states that all of the seven roofs were proportioned for slate and plank roofing resting on wide rafters 2 ft apart, supported by steel purlins about 10 ft apart. The spans given are measured from center to center of supports. Stresses were computed for a dead load of 25 lb per sq ft, a snow-load of 10 lb per sq ft of sloping surface, and a horizontal wind-load of 40 lb per sq ft, or a 28-lb-per-sq-ft normal pressure. Data for computing the weights of floors and floor-loads supported by trusses, and for fire-proof construction, may be found in Chapters XXI and XXIII.

**Snow-Loads.** As a basis for making an allowance for snow, Table VII perhaps as good a guide as any that can be given. When snow-guards are placed on a roof, the same allowance is made for a half-pitch as for a one-third pitch.

Table VII. Allowance for Snow in Pounds per Square Foot of Roof-Surface

Location	Pitch of roof				
	1/2	1/3	1/4	1/5	1/6 or less
	* †	* †	* †		
Southern states and Pacific slope.....	0-0	0-5	0-5	5	5
Central states.....	0-5	7-10	15-20	22	30
Rocky Mountain states.....	0-10	10-15	20-25	27	35
New England states.....	0-10	10-15	20-25	35	40
Northwest states.....	0-12	12-18	25-30	37	45

Columns headed by an asterisk (\*) are for slate, tile, or metal; those headed by dagger (†) are for shingles.

**Wind-Pressure.\*** For roofs having a pitch of 5 in or more to the foot, an allowance must be made for wind-pressure. For trusses of the FINK, FAN, KING, or QUEEN TYPES, the usual practice is to include the wind-pressure with the vertical loads, and to make a single allowance for both wind and snow, as during a gale snow is not likely to stay on a steep roof. When the wind-pressure is added to the vertical loads, the allowance for wind and snow combined should not be less than indicated in Table VIII.

Table VIII. Allowance for Wind and Snow Combined in Pounds per Square Foot of Roof-Surface

Location	Pitch of roof					
	60°	45°	1/3	1/4	1/5	1/6
Northwest states.....	30	30	25	30	37	45
New England states.....	30	30	25	25	35	40
Rocky Mountain states.....	30	30	25	25	27	35
Central states.....	30	30	25	25	22	30
Southern and Pacific states..	30	30	25	25	22	20

No roof-truss should be proportioned for a total load of less than 40 lb per sq ft of roof-surface except flat roofs in warm climates. For trusses having spans exceeding 100 ft (except trusses for flat roofs) and for trusses in which a part

\* (See, also, Chapter XXX, page 1199, and pages 1394 and 1717.)

duce maximum stresses, or call for COUNTERBRACING, as is the case  
ERAL TRUSSES, and trusses with CURVED CHORDS, the stresses for all  
oadings should be found separately and each member of the truss  
for the maximum stress to which it may be subject under any  
ination of loads. For determining the stresses due to wind-pres-  
force of the wind is usually assumed to act in a direction normal,  
t-angles, to the slope of the roof. This force is commonly based on  
ind, producing a pressure of 30 lb against a vertical surface. This  
s a wind-velocity of nearly 100 miles per hour. According to  
ula,

$$P = 0.0032 V^2$$

pressure in lb per sq ft against a surface normal to the direction  
d  $V$  = the velocity in miles per hour. For  $P = 30$  lb,  $V = 96.3$   
ormal pressure per square foot of roof-surface corresponding to  
and 30 lb per sq ft against a vertical surface is given in Table IX.

Wind-Loads in Pounds per Square Foot of Roof-Surface\*

Inclination of roof	Normal pressure $P_n$ , pounds per square foot	
	$P=30$ lb	$P=20$ lb
.....	5.1	3.5
.....	10.1	6.8
.....	14.6	9.6
h.....	19.8	13.1
h.....	22.4	14.0
.....	24.0	16.0
h.....	25.5	17.0
.....	26.7	18.2
.....	28.3	18.9
.....	30.0	20.0

Table IX are based on Duchemin's formula,

$$P_n = P \frac{2 \sin \theta}{1 + \sin^2 \theta}$$

e pressure per square foot on a vertical surface,  $P_n$  the normal  
essure and  $\theta$  the angle of inclination of the roof with the hori-  
d not only produces a pressure upon the windward side of the  
n upon the leeward side; therefore all roof-covering should be  
l, all joints in the trusses so constructed that they will resist  
pression, and the trusses themselves securely anchored to the

**Loading for which Stresses should be Found.** To deter-  
am stresses under any possible condition of loading, stresses  
or the following cases:

- due to permanent DEAD LOADS,
- covering only one side of roof,
- covering entire roof,
- side of truss nearer the expansion-end,
- side of truss nearer the fixed end.

It is generally assumed that the maximum wind-pressure and the snow-load cannot act on the same half of the truss at the same time; hence the combinations for maximum stress will be either cases 1 and 3 or cases 1, 2, and 4 or 3 and 4. If the trusses are supported on iron columns instead of on walls the wind-force is transferred to the foundations through the columns, producing a bending moment in the columns. The stresses in the columns, trusses and knee-braces should therefore be determined for the wind-pressures against the side of the building and roof. These pressures are obtained by multiplying the area of the vertical surfaces by the full pressure per square foot and the area of the roof by the normal component, given in Table IX.

**Kansas City Auditorium.** For the trusses supporting the roof of the Kansas City Auditorium (Fig. 66, Chapter XXVI) stresses were computed for the following conditions: First, full dead and live load on both galleries and roof-garden, and wind-pressure due to a velocity of 45 miles an hour; second, full dead load, snow-load, and gallery live load, wind-pressure 10 lb and load on roof-garden floor; third, full dead load and 50 lb wind-pressure; fourth, full dead load and wind-pressure at 45 miles an hour, and full live loads on gallery and roof-garden on one side only. Snow-loads throughout were taken at one-third of the dead load. Examples showing manner of combining the stresses due to different conditions of loading are given on pages 1114 and 1123.

## 2. Examples of the Computation of Roof-Loads\*

**King-Rod Truss. Example 1.** The first example considers the roof truss shown in Fig. 1, page 1048, which it is assumed represents truss 2 of Fig. 1048. It is assumed that the timber is to be common white pine and that the roof is to be covered with  $\frac{3}{16}$ -in slate of medium size on  $\frac{7}{8}$ -in sheathing. The ceiling is to consist of lath and plaster. The dead load of roof and truss per square foot of roof-surface is made up as follows:

	lb per sq ft
For slate.....	7 $\frac{1}{4}$
For sheathing.....	3
For rafters.....	3
For purlins.....	2
For truss.....	3
Total.....	18 $\frac{1}{4}$

For wind and snow-load combined there should be allowed about 28 lb (pitch being about  $40^\circ$ ), which makes a total roof-load of  $46\frac{1}{4}$  lb. To avoid fractions, however, the load is assumed to be 48 lb per sq ft. As the distance to truss 1, Fig. 2, is 14 ft and to truss 3, 12 ft, the length of roof supported by the truss is 13 ft. The roof-area supported by the purlins at joint 2 is equal to the distance  $a$  multiplied by 13 ft; and  $a$  is one-half the distance from the wall plate to the ridge-purlin, or 22 ft 8 in divided by 2, or 11 ft 4 in, or  $11\frac{1}{3}$  ft. Hence the roof-area supported at joint 2 is  $11\frac{1}{3}$  by 13 ft, or  $147\frac{1}{3}$  sq ft. The roof-area supported by the purlins at joint 3 is  $2b$  by 13 ft, or  $12\frac{1}{3}$  by 13 ft, or  $160\frac{1}{3}$  sq ft. Multiplying the roof-areas by the load per square foot, 48 lb, the results are 7 072 lb for the load at joint 2; and 7 696 lb for the load at joint 3. The load at joint 4 is equal to that at 2, as the truss is symmetrical. The ceiling loads at joints 6 and 7 are computed next. The ceiling-area supported at joint 6 is  $c \times 13$  ft, or  $8\frac{1}{4}$  by 13 ft, or  $107\frac{1}{4}$  sq ft. The area supported at joint 7 is  $d \times 13$  ft, or  $11\frac{1}{2}$  by 13 ft, or  $149\frac{1}{2}$  sq ft. The actual weight of the ceiling per square foot

\* In the following five examples all loads are considered as acting vertically.



ists and 10 lb for the lath and plaster; but where there is a large ble to be used for storage it is well to make a small allowance, sq ft, for any extra attic-load. Therefore, 18 lb per sq ft is be weight of the ceiling, which makes the weight at joints 6 and by 18 lb per sq ft, or 1 930 lb; and the weight at joint 7, 1 145 $\frac{1}{2}$  sq r sq ft, or 2 067 lb. As soon as computed, the roof and ceiling- e marked on a truss-diagram, as in Fig. 10. The roof and ceiling- r are transmitted directly to the wall and need not be taken into ermining the stresses in the truss.

128. **Example 2.** It is required to compute the joint-loads for n in Fig. 3, page 1049. All timber is to be of spruce and the roof d with shingles on 1-in sheathing. The ceiling is to be of lath The dead load is:

	lb per sq ft
shingles.....	2 $\frac{1}{2}$
sheathing.....	3
rafters.....	2 $\frac{1}{4}$
purlins.....	2
truss.....	3
dead load per sq ft.....	12 $\frac{3}{4}$
for wind and snow.....	30
roof-load in pounds per square foot.....	42 $\frac{3}{4}$

of the ceiling it is well, for a truss of this kind, to allow at least

It will be assumed that the trusses are to be spaced uniformly . Then the roof-area supported at joint 2 is 9 $\frac{5}{8}$  by 15 ft, or the load at this joint is 6 306 lb. The purlin at joint 3 supports joint midway to joint 2, to the ridge, or  $b = 4$  ft 11 in + 8 ft 5 in, he roof-area supported at this joint is 13 $\frac{1}{2}$  by 15 ft, or 200 sq is 8 550 lb. The loads at joints 4 and 5 are equal respectively 2. For the ceiling-loads at joints 7 and 8 there is an area to be to 12 $\frac{1}{2}$  by 15 ft, or 182 $\frac{1}{2}$  sq ft, which, multiplied by 20, gives

129. **Example 3.** For this example the church-roof shown in is considered. In this roof the trusses take the place of the g-beams, the sheathing spanning from truss to truss and the g being nailed to 1 $\frac{1}{4}$  by 2 $\frac{1}{2}$ -in furring strips, spaced 12 or 16 in mming that the parts of the trusses have the dimensions indi- e, and that the wood is white pine, the actual weight of one 20 lb. The roof-area supported by one truss is 170 sq ft, and of the trusses is about 7 lb per sq ft of roof-surface. This an twice that given in Table IV, owing principally to the close sses and also to the small dimensions of their members. The thing and shingles is about 5 $\frac{1}{2}$  lb and 30 lb is allowed for wind- f is too steep for snow to lodge on it. This gives a total roof- : sq ft of sloping surface. For the weight of the ceiling 12 lb as no load other than its own weight is likely to come upon it. orted at joint 2 is 10 $\frac{5}{8}$  by 2 $\frac{1}{2}$  ft, or 27 sq ft. The area sup- and 5 is equal to 12 $\frac{1}{2}$  by 2 $\frac{1}{2}$  ft, or 31 sq ft for each. The ted at joint 3 is 14 $\frac{1}{3}$  by 2 $\frac{1}{2}$  ft, or 35 $\frac{1}{2}$  sq ft. Multiplying the corresponding loads per square foot, there results 1 148 lb

for the load at joint 2, 1 318 lb for each load at joints 4 and 5, and 426 lb the load at joint 3.

**Truss over Car-Barn. Example 4.** In this example the roof is of corrugated iron, supported by a steel truss of the shape shown in Fig. 55, Chap. XXVI. This truss supports nothing but the corrugated iron, the purlins, the pressure due to wind and snow, the use of the building not requiring suspending of any load from the trusses. In figuring the dead loads for a roof, the sizes of the purlins and the gauge of the iron should first be defini

Fig. 4. Scissors Truss. (See, also, Fig. 24 and Chapter XXVIII, Fig. 2)

fixed, so that the weight per square foot of roof may be accurately determined. In this instance the purlins are 5-in I beams spaced 4 ft 9 in on centers weighing 10 lb per linear foot. The weight of the purlins per square ft of roof is therefore equal to 10 lb divided by 4¾, or 2.1 lb. For a span of 40 ft the corrugated iron should be No. 18 gauge (see Corrugated Iron, Part III, 1601) weighing 2 lb per sq ft. For the weight of the truss and bracing the value taken is that given in Table V for a span of 100 ft and ¼-pitch, 10.8 lb.\* gives a total dead load of 14.9 lb per sq ft of sloping surface.

For wind and snow we should allow 22 lb per sq ft if the building is situated in the Central states, making the total roof-load 36.9 lb per sq ft. It is generally recommended, however, that no roof should be designed for less, all told, than 40 lb per sq ft; the joint-loads, therefore, should be computed on that basis. The only loaded joints in this truss are those under the purlins. The trusses are spaced 19 ft 2¼ in and the purlins 4 ft 9 in on centers, the area supported at each upper joint being 91 sq ft. The joint-loads, therefore, should be figured at 3 640 lb. Even for the locality in which it was built


\* The actual weight of this truss and bracing was 4 lb per sq ft of sloping surface, which is remarkably small.

: roof; and it would hardly be considered safe for states further

**Flat Roof. Example 5.** This truss is for a flat roof (Fig. 5). of spruce and there is a five-ply gravel roof and a plastered ceiling. had we have,

	lb per sq ft
roofing.....	6
sheathing.....	3
rafters.....	2 $\frac{1}{4}$
purlins.....	2
truss, about.....	4 $\frac{1}{4}$
	<hr/>
dead load in pounds per square foot .....	17 $\frac{1}{2}$

s required for wind-pressure, but the snow-load is a large percentage load in any of the Northern states, as indicated in Table VII.



**Fig. 5. Howe Truss**


The building is located in one of the Central states, 30 lb per sq ft for snow, making the total roof-load  $47\frac{1}{2}$  lb. The plaster ceiling-joists weigh about  $12\frac{1}{4}$  lb and as the roof-space is not for storage, 13 lb per sq ft is a sufficient allowance for the ceiling. That the trusses are to be uniformly spaced, 14 ft on centers, the area supported at joint 2 is  $9\frac{1}{2}$  by 14 ft, or 133 sq ft, and the area supported at joint 3 is  $9\frac{2}{3}$  by 14 ft, or  $135\frac{1}{2}$  sq ft. The ceiling-area supported at joint 4 is 9 by 14 ft, or 126 sq ft and at joint 5, 9 by 14 ft, or 126 sq ft. Multiplying these areas by the corresponding load per square foot, we have 1 638 lb at joint 2, 1 699 lb at joint 4, 1 638 lb at joint 3, and 1 638 lb at joint 5. In practice it is hardly worth while to compute the stresses closer than this, as the loads may as well be put down at an even 50 or 100 lb per sq ft, as obtained by computation. When the roof is supported by the lower joints of the truss which have no load. Thus for Fig. 16, Chapter XXVI, there are no loads on joints 2, 6 and 10, and the area supported at joint 4 (Fig. 16) is equal to one-half the distance between the trusses, or the distance halfway to the truss on each side. If the lower joints are supported by ceiling-joists, there is a load at each of the joints 3, 5, 7, 9, etc. In drawing the truss for any arrangement of loads, the important thing is to compute the loads exactly as they are placed on the truss. The above examples illustrate fairly well the method of computing the loads on the joints of trusses. Other special cases of loading should be computed in the same manner.

3. Determination of Stresses by Computation

**Stresses.** To determine the stresses, a DIAGRAM OF THE TRUSS, composed of single lines representing the central axial or median lines of the truss-members should first be carefully drawn to a scale and the loads at the different joints indicated by arrows and numbers as in Figs. 10 and 12. If the center lines of the members, as they are actually placed, do not intersect at common points they must be made to do so in the diagram, as the stresses can be COMPUTED on the assumption that the center lines of all members meeting at any joint intersect at a common point. In wooden trusses it is not always practicable to place the members so that their center lines meet in a common point at each joint; but this condition should obtain as nearly as practicable, and in steel trusses the joint-connections should be made so that the lines passing through the centers of gravity of the cross-sections of the members meeting at a joint intersect in the same point.

Table X. Coefficients for Determining the Stresses in Simple Fink and Fan Trusses

WHEN PANEL-LOADS ARE ALL EQUAL



To find the stress in any member, multiply its factor by the panel-load, *P*

SIMPLE FINK TRUSS					
Member	Kind of stress	$l/h=3$	$l/h=3.464$ $=30^\circ$	$l/h=4$	$l/h=5$
A.....	Compression	2.70	3.00	3.35	4.04
B.....	"	2.15	2.50	2.91	3.67
D.....	"	0.83	0.87	0.89	0.93
F.....	Tension	2.25	2.60	3.00	3.75
G.....	"	1.50	1.73	2.00	2.50
K.....	"	0.75	0.87	1.00	1.25


SIMPLE FAN TRUSS					
A.....	Compression	4.51	5.00	5.59	6.73
B.....	"	3.54	4.00	4.55	5.59
C.....	"	3.40	4.00	4.70	5.99
D.....	"	0.93	1.00	1.08	1.21
E.....	"	0.93	1.00	1.08	1.21
F.....	Tension	3.75	4.33	5.00	6.25
G.....	"	2.25	2.60	3.00	3.75
K.....	"	1.50	1.73	2.00	2.50

on of Stresses. As a general rule, the stresses in a roof-truss can much more readily by the GRAPHIC METHOD than by MATHEMATI-  
IONS and with as close a degree of accuracy as is necessary. There is of trusses, however, for which the stresses can be more easily  
COMPUTATION. Such trusses must be symmetrical in shape  
oads all alike, as is quite frequently the case with simple steel roofs  
ng-load.

XIII give constants by which the stresses in Fink and fan  
readily COMPUTED simply by multiplying the constant by the  
load. These tables apply, however, only when the rafter is  
struts into equal spaces, giving equal panel-loads. For any  
is the stresses should be determined by the GRAPHIC METHOD.

Coefficients for Determining the Stresses in an Eight-Panel  
Fink Truss

WHEN PANEL-LOADS ARE ALL EQUAL



3.5 P

Eight-panel Fink Truss

stress in any member, multiply its factor by the panel-load, P

Kind of stress	$l/h=3$	$l/h=3.464$ $=30^\circ$	$l/h=4$	$l/h=5$
Compression	6.31	7.00	7.83	9.42
"	5.76	6.50	7.38	9.05
"	5.20	6.00	6.93	8.68
"	4.65	5.50	6.48	8.31
"	0.83	0.87	0.89	0.93
"	1.66	1.73	1.79	1.86
"	0.83	0.87	0.89	0.93
Tension	0.75	0.87	1.00	1.25
"	0.75	0.87	1.00	1.25
"	1.50	1.73	2.00	2.50
"	2.25	2.60	3.00	3.75
"	5.25	6.06	7.00	8.75
"	4.50	5.19	6.00	7.50
"	3.00	3.46	4.00	5.00

Table XII. Coefficients for Determining the Stresses in Cambered Fink and Fan Trusses

WHEN PANEL-LOADS ARE ALL EQUAL AND THE CAMBER EQUALS ONE-SIXTH THE RISE

Fig. A

Fig. B

To find the stress in any member, multiply its factor by the panel-load,  $P$

TRUSS LIKE FIG. A

Member	Kind of stress	$l/h = 3$	$l/h = 3.464 = 30^\circ$	$l/h = 4$	$l/h = 5$
A.....	Compression	3.64	4.13	4.70	5.78
B.....	"	3.09	3.63	4.25	5.41
D.....	"	0.83	0.87	0.89	0.93
F.....	Tension	3.07	3.62	4.24	5.40
G.....	"	1.80	2.08	2.40	3.00
K.....	"	1.43	1.69	1.98	2.52

TRUSS LIKE FIG. B


A.....	Compression	6.09	6.88	7.83	9.64
B.....	"	4.89	5.63	6.48	8.10
C.....	"	4.96	5.88	6.93	8.89
D.....	"	1.04	1.15	1.26	1.49
E.....	"	1.04	1.15	1.26	1.49
F.....	Tension	5.12	6.03	7.07	9.01
G.....	"	2.70	3.12	3.60	4.50
K.....	"	2.66	3.13	3.67	4.69

Table XIV gives coefficients which are general for any span and depth eight-panel roof-trusses with the Howe and Pratt types of bracing. Tables and XVI give formulas for COMPUTING the stresses in symmetrical Howe Pratt trusses which are symmetrically loaded. The coefficients are given trusses having an odd number of panels. For the Howe truss with an even number of panels the coefficients for the center load on the top chord are also divided by two. For the center load on the bottom chord the coefficients are also divided by two, except that for the center vertical, which remains un-

truss with an even number of panels the coefficients are divided by center loads for all pieces, except that for the center vertical top chord, the coefficient remains unity. For the young architect these tables will be found useful in furnishing a check upon stresses GRAPHIC METHODS.

Coefficients for Determining the Stresses in an Eight-Panel Cambered Fink Truss

-LOADS ARE ALL EQUAL AND CAMBER EQUALS ONE-SIXTH THE TOTAL RISE



-----  $l$  = span

= 3.5  $P$


: stress in any member, multiply its factor by the panel-load.  $P$

Kind of stress	$l/h=3$	$l/h=3.464$ $=30^\circ$	$l/h=4$	$l/h=5$
Compression	8.49	9.63	10.96	13.49
"	7.94	9.13	10.51	13.11
"	7.39	8.63	10.06	12.74
"	6.83	8.13	9.61	12.37
"	0.83	0.87	0.89	0.93
"	1.66	1.73	1.79	1.86
"	0.83	0.87	0.89	0.93
Tension	1.02	1.21	1.41	1.80
"	1.02	1.21	1.41	1.80
"	2.87	3.37	3.96	5.04
"	3.89	4.58	5.37	6.85
"	7.17	8.44	9.90	12.61
"	6.15	7.23	8.48	10.81
"	3.60	4.16	4.80	6.00





Coefficients for Howe Trusses which are Symmetrical About the Center of the Span and Symmetrically Loaded



7 panels			5 panels		3 panels
$P_1$	$P_2$	$P_3$	$P_1$	$P_2$	$P_1$
$-h$	$a+h$	$a+h$	$a+h$	$a+h$	$a+h$
$h$	$(a+b)+h$	$(a+b)+h$	$a+h$	$(a+b)+h$	.....
$h$	$(a+b)+h$	$(a+b+c)+h$	.....	.....	.....
$h$	$(a+b)+h$	$(a+b+c)+h$	.....	.....	.....
$\frac{a^2+h^2}{2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$
o	$\sqrt{b^2+h^2}+h$	$\sqrt{b^2+h^2}+h$	o	$\sqrt{b^2+h^2}+h$	.....
o	o	$\sqrt{c^2+h^2}+h$	o	o	.....
o	o	o	.....	.....	.....
o	1.0	1.0	o	1.0	o
o	o	1.0	o	o	.....
o	o	o	.....	.....	.....
$p_1$	$p_2$	$p_3$	$p_1$	$p_2$	$p_1$
1.0	1.0	1.0	1.0	1.0	1.0
o	1.0	1.0	o	1.0	.....
o	o	1.0	.....	.....	.....

, etc., the coefficients for the chords and diagonals are the same as is  $P_1$ ,  $P_2$ , etc. The coefficients for the verticals for loads  $p_1$ ,  $p_2$ , etc., supplementary table below the general table. Tension is indicated in by light lines.

Table XVI. Coefficients for Pratt Trusses which are Symmetrical About the Center of the Span and Symmetrically Loaded

Member	7 panels			5 panels		3 panels
	$P_1$	$P_2$	$P_3$	$P_1$	$P_2$	$P_1$
$L_1$ and $L_2$	$a+h$	$a+h$	$a+h$	$a+h$	$a+h$	$a+h$
$L_2$ and $U_1$	$a+h$	$(a+b)+h$	$(a+b)+h$	$a+h$	$(a+b)+h$	.....
$L_3$ and $U_2$	$a+h$	$(a+b)+h$	$(a+b+c)+h$	.....	.....	.....
$U_4=L_4$ .....	.....	.....	.....	.....	.....	.....
$D_1$ .....	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$	$\sqrt{a^2+h^2}+h$
$D_2$ .....	o	$\sqrt{b^2+h^2}+h$	$\sqrt{b^2+h^2}+h$	o	$\sqrt{b^2+h^2}+h$	.....
$D_3$ .....	o	o	$\sqrt{c^2+h^2}+h$	o	o	.....
$D_4$ .....	o	o	o	.....	.....	.....
$V_1$ .....	o	o	o	o	o	o
$V_2$ .....	o	1.0	1.0	o	1.0	.....
$V_3$ .....	o	o	1.0	.....	.....	.....
	$p_1$	$p_2$	$p_3$	$p_1$	$p_2$	$p_1$
$V_1$ .....	1.0	o	o	1.0	o	1.0
$V_2$ .....	o	o	1.0	o	o	.....
$V_3$ .....	o	o	o	.....	.....	.....

For loads  $p_1, p_2$ , etc., the coefficients for the chords and diagonals are the same as given for the loads  $P_1, P_2$ , etc. The coefficients for the verticals for loads  $p_1, p_2$ , etc. are given in the supplementary table below the general table. Tension is indicated in the truss-diagram by light lines.

### Examples Showing Use of Tables in Stress-Computations

**an Truss. Example 1.** In this example a simple-fan truss of 3 is considered. The distance on centers of trusses is 12 ft. The ss is 9 ft, or  $l/h = 4$ . The total load per square foot of roof is 40 lb. of rafter is 20 ft, nearly. The panel-load,  $P = 20\frac{2}{3} \times 12 \times 40 =$  ten from Table X,

lower end of rafter  $A = 3\,200 \times 5.59 = 17\,888 \text{ lb}$

nds of main tie  $F = 3\,200 \times 5.00 = 16\,000 \text{ lb}$

center of main tie  $G = 3\,200 \times 3.00 = 9\,600 \text{ lb}$

traces  $D$  and  $E = 3\,200 \times 1.08 = 3\,456 \text{ lb}$

$$e K = 3\,200 \times 2 = 6\,400 \text{ lb}$$

**Howe Truss. Example 2.** (Table XV.) A five-panel Howe truss, for which  $h = 6$  ft,  $a = 9$  ft,  $b = 10$  ft and  $c = 12$  ft. Let the span be 60 ft on centers, the roof-load be 40 lb per sq ft and the ceiling-load be 10 lb per sq ft. The panel-loads become:

$$\begin{array}{lcl} 9 + 10) (10 \times 40) = 3\,800 \text{ lb} & \left. \begin{array}{l} \\ \\ \end{array} \right\} & = 5\,200 \text{ lb} \\ 9 + 10) (10 \times 15) = 1\,400 \text{ lb} & & \\ 0 + 12) (10 \times 40) = 4\,400 \text{ lb} & \left. \begin{array}{l} \\ \\ \end{array} \right\} & = 6\,100 \text{ lb} \\ 0 + 12) (10 \times 15) = 1\,700 \text{ lb} & & \end{array}$$

$$1 = \frac{2}{8} \times 5\,200 + \frac{2}{8} \times 6\,100 = 17\,000 \text{ lb}$$

$$1 = \frac{9}{8} \times 5\ 200 + \frac{19}{8} \times 6\ 100 = 27\ 100\ \text{lb}$$

$$2/6 (5\ 200 + 6\ 100) = 20\ 400\text{ lb}$$

$$5/6 \times 600 = 500 \text{ lb}$$

$$0 + 1\,400 + 1\,700 = 7\,500 \text{ lb}$$

1b

results all values between 50 and 100 have been considered 100.

## nation of Stresses in Roof-Trusses by Graphic Methods

**c Method** is the simplest and in most cases the quickest method of determining the stresses in a roof-truss; and it has, besides, the additional advantage of being applicable to any true truss-form or any arrangement of members. It is also less chance of making a mistake in the GRAPHIC METHOD than in the method of NUMERICAL COMPUTATION, as an error in the graphical method always becomes manifest. When the principles are understood, the DIAGRAMS can be very quickly drawn, without the aid of books. By knowing the forms of trusses in common use, the method of drawing the diagrams is quite simple; and a careful study of the following examples, together with a little practice in drawing the diagrams, should enable any draftsman, or builder to understand the principles involved in the ANALYSIS OF ROOF-TRUSSES.

**Upon Which the Graphic Method is Based.** To thoroughly understand this method, a knowledge of the COMPOSITION AND RESOLUTION OF FORCES, explained in Chapter VI, is essential; and before studying this chapter the student should read carefully pages 288 and 289. The theorems explained on these pages form the basis of GRAPHIC STATICS. In the GRAPHIC METHOD all forces, including the loads, are represented by straight lines, and the directions of the forces must be constantly kept in mind. It is of assistance to indicate the direction of a force by an arrow-headed line, as explained on page 289. The direction in which a force acts with reference to the member indicates, also, whether it is a PUSHING or a PULLING force, or the number on which the force or in which the stress acts is in COMPRESSION or TENSION. This is more fully explained in the following pages, and also illustrated with several of the stress-diagrams.

**Forces and Stresses which Act On and In a Truss.** Every stress-diagram represents three sets of forces, viz., the external LOADS, the supporting forces or REACTIONS, and the STRESSES in the truss-members.

**Supporting Forces or Reactions.** For a truss to remain in place, two the conditions for equilibrium are that the algebraic sums of the vertical and horizontal components of all the forces acting upon the truss must respectively equal zero. Then the horizontal and vertical components of the supporting forces or reactions, taken together, must respectively equal the horizontal and vertical components of the loads. The LOADS and REACTIONS are considered as the EXTERNAL FORCES acting on the truss and form part of the STRESS-DIAGRAM.

**Symmetrical Loads.** When the loads or vertical forces are symmetrical on each side of the middle of the span, the supporting forces are equal, and each equal to one-half the total load on the truss.

**Unsymmetrical Loads.** When the loads are not symmetrical about the middle, either in regard to point of application or to magnitude, the supporting forces are unequal and in most cases must be determined before the stress-diagram can be drawn. The supporting forces for unsymmetrically loaded truss may be computed by the method of the MOMENTS OF FORCES, explained on pages 322 to 324.

**Stress-Diagrams for Vertical Loads.** Before the stress-diagram for a truss can be drawn, it is necessary to make a skeleton drawing of the truss, representing the central or median lines of the members as explained on page 1058. This diagram, called the TRUSS-DIAGRAM, should be drawn on the same sheet of paper as the STRESS-DIAGRAM, for convenience in drawing the latter. The truss-diagram should also have all of the loads which come on the truss indicated by arrows and figures, as in the following examples.

**Supporting Forces.** The SUPPORTING FORCES, also, should be indicated on the TRUSS-DIAGRAM as in Fig. 10. These forces are determined as explained on pages 322 to 324.

**Lettering the Truss-Diagram.** After the truss-diagram is drawn, it is convenient to letter it according to the method known as Bow's NOTATION, which allows a ready comparison of the TRUSS-DIAGRAM and the STRESS-DIAGRAM and also enables the student to readily draw the stress-diagram and to immediately determine the CHARACTER as well as the MAGNITUDE of the stresses. The essential principle of this method is the LETTERING of each space on each side of every external force and of every member of the truss, so that on the truss-diagram a truss-member or external force is denoted by the letters on each side of it. When the stress-diagram is drawn, it will be found that the same letters come at the ends of the lines representing the external forces and the stresses in the truss-members.

**The Simple Triangular Frame** is much used in building construction, and most forms of roof-trusses are combinations of such triangles. It is, therefore, worth while to show how easily the above principles may be used to determine the stresses in such a frame. Diagram 1, Fig. 6, represents the TRUSS-DIAGRAM of a triangular frame properly lettered. A load of 100 lb is applied at the apex. The weight of the frame is disregarded. In diagram 2, a vertical line  $ab$  is drawn 1 in long (say to a scale of 100 lb to the inch), representing the force  $A$ . From  $b$ ,  $bd$  is drawn equal to  $R_2$  and from  $d$ ,  $da$  equal to  $R_1$ . These three lines represent the external forces acting on the truss, and the polygon  $abda$ , called the FORCE-POLYGON, is always a CLOSED FIGURE if the forces are in EQUILIBRIUM. Since the force  $AB$  is vertical and  $R_1$  and  $R_2$  are parallel to  $AB$ , the figure  $abda$  is a straight line,  $bd$  and  $da$  coinciding with  $ab$ . If the external forces form a closed

en laid off to scale, usually in order, the frame or truss upon which not be moved either vertically or horizontally by the forces. The ON should always be drawn and closed before any attempt is made the stresses in the members of the truss. The stresses in the be truss will now be found, beginning with those meeting at joint 1. d CD meet at this joint. The stresses in these two pieces and  $R_1$  are  $m$  and, consequently, if laid off in order will form a CLOSED FIGURE Chapter VI. In diagram 2,  $da$  represents  $R_1$  in MAGNITUDE and From  $a$  draw a line parallel to  $AC$  and from  $d$  a line parallel to  $CD$




Fig. 6. Triangular Frame

em until they intersect at  $c$ .  $ac$  is the stress in  $AC$ , and  $cd$  that and  $da$ , or  $R_1$ , are in EQUILIBRIUM since they form a CLOSED FIG- the forces in order,  $da$ , or  $R_1$ , is known to act towards the joint.  $ac$  is also towards the joint and hence the stress is of the same e force  $R_1$  and the piece  $AC$  is in COMPRESSION.  $AC$  pushes it as  $R_1$  does. Continuing around the stress-polygon  $dac$ , in the  $cd$  acts away from the joint and the stress in  $CD$  is opposite in e force  $R_1$ , or  $CD$  is in TENSION.  $CD$  pulls away from joint 1. stresses in the pieces  $BC$  and  $CA$  and the force  $AB$  are in EQUI- sides of the STRESS-POLYGON are  $ab$ ,  $bc$  and  $ca$  (diagram 2). The represents the load of 100 lb acts down and towards the joint, act towards this joint, showing that the stresses in  $BC$  and  $CA$  : character as the force  $AB$ , or that the pieces push against the each is in COMPRESSION. At joint 3, the two pieces meeting are The STRESS-POLYGON is  $bdc$ . Here  $bd$  acts towards the joint,  $dc$  joint, and  $cb$  towards the joint. As found before, the stress in and that in  $CB$ , COMPRESSION. Diagram 2 is made up of three s, one for each of the joints shown in diagram 1. Each of these sidered independently when determining the MAGNITUDE and he stresses or forces. This is important to remember when the s are combined as in diagram 2. In determining the CHARACTER 4C, for example, from the STRESS-POLYGON  $dac$  for joint 1, the vards joint 1, while from the STRESS-POLYGON  $abc$  for joint 2,  $ca$  at 2. In both cases the piece  $AC$  is pushing against the joints : in COMPRESSION. If arrow-heads are used in indicating the di- orces in the STRESS-POLYGONS, they should be erased as soon as f the stresses for the joint being considered have been found; polygons are combined as in diagram 2, each line will have two ating in opposite directions, leading to confusion. Arrow-heads on the TRUSS-DIAGRAM. Each piece will have two arrow-heads, referring to the joint at the end. When the arrow-heads point

away from each other the piece is in COMPRESSION, and when they pull towards each other the piece is in tension.

It is important to keep in mind the direction in which the forces and stresses are considered in order, in going around the truss or around a joint. In Figs. 6 and 8 the curved arrows show that a clockwise direction has been chosen. This makes the stress-lines of the stress-diagram come on the left of the load line. This direction has been taken for all the trusses in this chapter, except





Fig. 7. Indication of Character of Stress


for a few diagrams for wind-loads. The stress could have been determined just as well by taking a contra-clockwise direction.

If two men pull on the two ends of a rope, exerting PULLING FORCES of equal intensity, the TENSIONAL STRESS in every cross-section of the rope is equal to the FORCE with which one man pulls; and each end of the rope pulls away from


the man holding it, with a FORCE equal in magnitude to that which he exerts. Thus if each man exerts a FORCE of 100 lb the STRESS in the rope is 100 lb at each end of the rope pulls away with a FORCE of 100 lb. If the men push against the two ends of a piece of timber with a FORCE of 100 lb, the timber pushes against each man with a FORCE of 100 lb, although the entire COMPRESSIONAL STRESS in every cross-section of the timber is but 100 lb. Consequently STRESS-LINES are sometimes drawn with arrow-heads pointing towards each other, as at A, Fig. 7, denoting TENSION; or with arrow-heads pointing




1. Truss-diagram



2. Stress-diagram



3. Truss-diagram



4. Stress-diagram

Fig. 8. Trussed Beam

in opposite directions, as at B, denoting COMPRESSION. It is better, however, to omit arrow-heads on STRESS-LINES, putting them on lines representing EXTERNAL FORCES only. The STRESS in any member of a truss acts in opposite directions at the two ends of the piece. This is an important thing to remember in drawing STRESS-DIAGRAMS.

**The Trussed Beam.** Fig. 8 shows a load supported by a beam, post or rod and two ties instead of by two struts and a tie. The effect on the rod forms



drawing the **STRESS-DIAGRAM**. The supporting force at the left is  $SM$ , the load at joint 1 is  $MA$ , the bottom of the rafter is  $AE$ , the left portion of the tie-beam or bottom chord is  $ES$ , etc. The loads acting at joints 1, 2, 3, 4 and 5 are designated as  $MA$ ,  $AB$ ,  $BC$ ,  $CD$  and  $DN$  respectively, and those at joints 8, 5 and 6 as  $OP$ ,  $PQ$  and  $QS$  respectively. It makes no difference what letters are used, except that it is better to first letter the outside spaces consecutive and then the inside spaces.

**Force-Polygon.** The **FORCE-POLYGON** is now constructed by laying off to scale (Fig. 10A) the external forces in order, beginning with the force  $MA$ , and following with  $AB$ ,  $BC$ ,  $CD$ ,  $DN$  laid off downward,  $NO$  laid off upward,  $OP$ ,  $PQ$ ,  $QS$  laid off downward, and  $SM$  laid off upward. If the work is correct, the forces form a **CLOSED FIGURE**.




Fig. 10A. King-rod Truss. Stress-diagram

**Stress-Diagrams.** The **STRESS-DIAGRAM** is drawn by taking the forces acting on the joints in consecutive order, commencing at one of the supports. It is convenient to start with the support at the left, or at joint 1. In actual computations it is not necessary to number the joints, but in order to refer to them in the description it is necessary to number them in the illustrations. Commencing at joint 1, the first step in drawing the **STRESS-DIAGRAM** is to draw a vertical line to a scale of **POUNDS-TO-THE-INCH** to represent the supporting force  $SM$ . This line is the line  $sm$  already drawn in constructing the **FORCE-POLYGON** (Fig. 10

which might be drawn to the scale of 16 000 lb to the inch. It is best to use a scale as large as convenient in order to have a relatively small **STRESS-DIAGRAM**. An engineer's scale, one divided to 10ths, 20ths, 30ths, etc., of 1 inch, is found most convenient for these drawings. The small letter  $s$  is placed at the bottom of the line  $sm$ , and the letter  $m$  at the top. From  $m$  is laid off a line representing the load  $MA$ . A line is then drawn from  $a$ , parallel to the rafter  $AE$ , and a line from  $s$  parallel to the tie-beam  $ES$ . The two lines meet at  $e$  and  $ae$  represents the stress in  $AE$  and  $es$  the stress in  $ES$ . The supporting force represented by  $sm$ , acts upward, and the others follow in rotation, showing that  $ae$  acts towards joint 1 and that the member  $AE$  is in **COMPRESSION**, and showing that  $es$  acts from joint 1 and that the member  $ES$  is in **TENSION**. Consider next the stresses at joint 6. Commencing at the bottom of the joint and going around to the left, the first force that is known is the load  $QS$ , or 1 930 lb, which is measured to the scale used from  $q$  to  $s$ , downward, as the loads act downward. The point  $s$  was located in drawing the **STRESS-POLYGON** for joint 1, and  $q$  was located in constructing the **FORCE-POLYGON** for the external forces. The next stress that is known is the stress  $se$  which has just been determined. As this stress acts to the right from joint 1, it will act to the left from joint 6, as the stresses in the two ends of a strut or a tie act in opposite directions, as explained on page 1068. The stresses in  $EE'$  and  $E'Q$  are not known, so from  $e$  a line is drawn parallel to  $EE'$  and extended so that a line drawn from its extremity  $e'$  parallel to  $E'Q$  closes on  $q$ . The lines  $ee'$  and  $e'q$  are thus found, which represent the stresses in  $EE'$  and  $E'Q$  respectively. Starting with  $se$ , the stress





metrically loaded, each supporting force or reaction is equal to one-half the total load, or 18 500 lb. There are no purlins at joints 1 and 6 to carry rafters as ceiling-joists, which are supported by the walls of the building, so there are no external loads at these joints as in the previous example. The very small dead load due to the truss itself is neglected. To draw the force-polygon, first draw the vertical line  $qa$  (Fig. 12A) equal in length, to some scale, to the magnitude of the left supporting force; then in rotation and at the same scale lay off the distances  $ab$ ,  $bc$ ,  $cd$  and  $de$ , downward;  $go$ , equal to the right supporting force upward; and  $op$  and  $pq$  downward, closing the figure at  $q$ . To construct the combined stress-diagram using the force-polygon just drawn, as a foundation first consider joint 1. From  $a$  draw a line parallel to  $AE$  and from  $q$  a line parallel to  $EQ$ . The triangle  $qae$  represents the three forces in equilibrium, meeting in a point at acting at joint 1. As the supporting forces act upward, the arrow-head on  $qa$  points upward. Following the sides of the stress-polygon  $qae$  in rotation  $ae$  acts towards the joint and  $eq$  from the joint showing that  $ae$  is in compression and  $eq$  in tension. Next determine the stresses acting at joint 2. The stress in  $EA$  is now known and represented by the line  $ea$ , and as the stress at joint 2 acts in a direction opposite to that at joint 1, it now acts upward towards joint 2. The next force is the load, 6 300 lb, which acts downward. The point  $b$  has already been found by measuring from  $a$  a distance equal to 6 300 lb at the same scale as used in drawing  $qa$ .





Fig. 12A. Queen Truss.  
Stress-diagram

There now remain two stresses to be found for joint 2, those in  $BF$  and  $FE$ . Draw  $bf$  parallel to  $BF$ , and  $fe$  parallel to  $FE$ , the two lines intersecting at  $f$ . Then the sides of the polygon  $abfe$  represent respectively the magnitude of the four forces acting at joint 2; and the character of the stresses determined by the directions in which the stress-lines are drawn, in order in going around the joint. In this case they all act toward the joint and  $EA$ ,  $BF$  and  $FE$  are in compression. The stresses acting at joint 3 or may be determined next, as only two of them are unknown at either joint. Considering the external force and the three stresses acting at joint 3, the stress in  $FB$  has been determined and is represented by the line  $fb$ , which is drawn upward for this joint. The load or force  $BC$ , 8 550 lb, is known and is represented by  $bc$ .  $ch$  is drawn parallel to  $CH$ , and  $hf$  parallel to  $HF$ , closing the polygon. The length of  $ch$  determines the magnitude of the stress in  $CH$  and  $hf$  the stress in  $HF$ . The stresses in all the truss-members but  $HP$  are now determined. This stress is found by considering the force and stresses acting at joint 7. At this joint the force  $PQ$ , or 3 650 lb, and the stresses in  $QE$ ,  $EF$  and  $FH$ , represented respectively by  $pq$ ,  $qe$ ,  $ef$  and  $fh$ , have been determined. The line  $hp$ , representing the stress in  $HP$ , completes the polygon for joint 7. Hence  $hp$  determines the stress in  $HP$ , and as  $ho$  is drawn from left to right, from the joint,  $HP$  is in tension. With reference to joint 3, the line  $ch$  is drawn towards joint 3 and hence  $CH$  is in compression. Scaling the lines in the stress-diagram (Fig. 12A) the figures shown by the side of the lines are obtained. They indicate the magnitude of each stress in pounds, the + sign denoting compression, and the - sign tension. The two foregoing examples illustrate the method of drawing the stress-diagrams for simple symmetrical trusses, symmetrically loaded. The truss-diagrams should be drawn in accordance with the measurements given

le of not less than  $\frac{1}{8}$  in to the foot; and the stress-diagram should line by line, in accordance with the foregoing directions and the ined and compared with those given in the figures. A variation of lb for small stresses and less than 1% for large stresses may be ex- a greater variation indicates either that sufficient care has not been drawing the stress-lines exactly parallel to the corresponding lines diagram, or that an error has been made in drawing the truss-dia- scaling the lines of the stress-diagram. After these two examples orked, a number of the following examples, also, should be solved, ap- ciples are fully understood.

r Museum of Fine Arts, St. Louis, Mo. Example 3. Fig. 13  
e truss-diagram of the truss shown in Fig. 11, Chapter XXVI,



. 13. Truss-diagram. Museum of Fine Arts, St. Louis, Mo.

Fig. 13A. Stress-diagram

ated being approximately those due to the roof and suspended  
The loads being symmetrically disposed, each supporting force is  
all the total load, or 41 040 lb. The counterbraces CC, shown  
VI, are omitted from the truss because they have no stress when  
niformly loaded. To draw the stress-diagram (Fig. 13A), first  
he vertical line  $sa$ , equal to 41 040 lb, equal to  $R_1$ ; and then  $ab$   
respectively to  $AB$  and  $BS$  and representing the stresses acting  
joint 2, the line  $ba$  represents the stress in  $BA$ ;  $ac$ , equal to 7 200  
;  $cd$ , the stress in  $CD$ ; and  $db$  the stress in  $DB$ . The polygon  
s the forces in equilibrium acting at joint 2. At joint 3 there are  
forces; and as three unknown forces out of five in one polygon  
mined, joint 4, where  $dc$  and the load  $CF$  are known, is considered  
ing off the load  $cf$ , equal to 12 240 lb, the stresses in  $FE$  and  $ED$   
determined. These are found by drawing  $fe$  parallel to  $FE$ , and  
 $ED$ , the two lines intersecting at  $e$ . At joint 3,  $sb$ ,  $bd$ ,  $de$  and the  
own, and  $eg$  and  $gq$  are drawn to close the polygon  $sbdeg$ . At

joint 10 the force  $pg$ , equal to 12 000 lb, and  $gg$  are known; and  $gg'$  and  $g'p$  are drawn to close the polygon. At joint 5,  $g'g$ ,  $ge$  and  $ef$  are known and  $ih$  and  $hi$  are drawn to close the polygon. Since there is no load at joint 5,  $f$  and  $i$  fall at the same point in the stress-diagram. The stresses in pounds, in the various members of the truss, are given in numbers on the corresponding lines in the stress-diagram (Fig. 13A).

**Triangular Howe Truss. Example 4.** Consider the skeleton triangular Howe truss represented in Fig. 14 loaded as shown by the weight of the roof

F

above and a ceiling below. To draw the stress-diagram, first draw to scale the supporting force  $gj$ , equal to 46 620 lb. Then lay off  $jk$  equal to 10 320 lb,  $kl$  equal to 10 320 lb, etc. Then draw the lines  $ja$  and  $aq$ , and the three forces at the left support are known. At joint  $a$ ,  $pq$  and  $qa$  are known and  $ab$  and  $ba$  are drawn to close the polygon. At joint 1,  $ba$ ,  $aj$  and  $jk$  are known and  $bc$  and  $cb$  are drawn to close the polygon. At joint 2,  $sp$ ,  $pb$  and  $bc$  are known and  $cd$  and  $dc$  are drawn to close the polygon. At joint 3,  $dc$ ,  $ck$  and  $kl$  are known and  $le$  and  $el$  are drawn. At joint 4,  $no$ ,  $ol$  and  $de$  are known and  $ef$  and  $fn$  are

the polygon. At joint 5, *fe*, *el* and *lm* are known and *mg* and *gf* Joint 7 is considered next, for at joint 6 there are three unknown d by the graphic method three out of five forces, meeting in a point ibrium, must be known in order to determine the other two. At and *mm'* are known and *m'g'* and *g'g* are drawn to close the polygon. tes the determination of the stresses in all the pieces for one-half and of course the stresses for each half are the same as the loading al.

nel Howe Truss. Example 5. For the next example a HOWE isdered, whose center lines give the diagram shown in Fig. 15.




Fig. 15. Howe Truss. Truss-diagram

used for a span of 64 ft, and it supports, in addition to a flat roof, ng below the bottom chord and a gallery on each side. The loads at joints are about as indicated in Fig. 15. To draw the stress- 15A), first construct the force-polygon by laying off to scale in ternal forces, commencing with the left reaction 34 200 lb. Next, t joint a, the supporting force *sa* is known, the stress in the rafter stress in the tie *ps*, closing the polygon. At joint 1, *pa* and *ab*




Fig. 15A. Howe Truss. Stress-diagram

*bm* and *np* are drawn, closing the polygon. At joint 2, *gs*, *sp* and ad *nm* and *mg* are drawn. At joint 3, *mn*, *nb* and *bc* are known re drawn. The stresses at the remaining joints are found in the ose at 3 and 4. The stresses in pounds in the various members noted in figures in the stress-diagram (Fig. 15A).

**Loaded at Alternate Joints.** Example 6. (Fig. 16.) This **HOWE TRUSS** is selected to show how to proceed when there is no

load at one or more of the joints. Fig. 16 represents the center lines of a truss 50 ft in span and only 5 ft in height. In order to give the braces an inclination approximating  $45^\circ$ , the truss is divided into ten panels; but purlins are placed over every other joint, as in Fig. 16, Chapter XXVI. The loads from the purlins are about 5 000 lb. The stresses at joint 1 are found in the same manner as in the previous example, always starting with the supporting force. At joint 2 the stress-line  $da$  is already drawn; and as there is no load at this joint




Fig. 16. Howe Truss. Truss-diagram

a line is drawn from  $a$  parallel to  $AE$  ( $A$  covers the entire space from joint 1 to joint 4), and a line from  $d$  parallel to  $ED$ , the two lines intersecting at  $e$ .

The force-lines and stress-lines are as follows:

- At joint 3:  $od$ ,  $de$ ,  $ef$  and  $fo$ ;
- At joint 4:  $fe$ ,  $ea$ ,  $ab$ ,  $bg$  and  $gf$ ;
- At joint 5:  $of$ ,  $fg$ ,  $gh$  and  $ho$ ;
- At joint 6:  $hg$ ,  $gb$ ,  $bi$  and  $ih$ ;
- At joint 7:  $oh$ ,  $hi$ ,  $ij$  and  $jo$ ;
- At joint 8:  $ji$ ,  $ib$ ,  $bc$  and  $ck$ ;

the latter line extending to the point of beginning,  $j$ , showing that there is no stress in  $kj$ . At joint 9 the only stresses are  $oj$  and  $lo$ , for as there is no stress






Fig. 16A. Howe Truss. Stress-diagram

in  $JK$ , for equilibrium there can be none in  $KL$ . There is, also, no stress in the middle rod. Although these members have no stress, it is advisable to insert them in the truss in order to stiffen the top and bottom chords. They may be made very light, say  $\frac{1}{2}$  in in diameter for the rods and 3 by 6 in in cross section for the braces.

**Truss with Slanting Top Chord. Example 7.** In order to give a roof it is often desirable to incline the top chord of a HOWE TRUSS, Chapter XXVI. Fig. 17 shows the truss-diagram for such a truss, and the stress-diagram. The latter is drawn in the same way as the one in Example 5, but because the top chord is not level, the stress-diagram is not symmetrical. When the stress-diagram is not symmetrical it is necessary to complete the entire diagram, so as to show the stress in every member. The stress-lines for joint 9 are  $om$ ,  $mn$ ,  $nr$  and  $ro$ . This leaves



17. Howe Truss with Slanting Top Chord. Truss-diagram



18. Howe Truss with Slanting Top Chord. Stress-diagram

to complete the diagram; and if the diagram has been correctly drawn, the lines  $rf$  and  $fe$  will be exactly parallel to  $RF$ . There is no stress

**Inclined Ties. Example 8.** (Fig. 18.) This truss has the same shape as the truss shown in Fig. 14, but the diagonals incline in the opposite direction and are in tension, while the verticals, except the middle one, are in compression. This form of truss is sometimes used in wooden construction for the long middle braces shown in Fig. 14. Long ties are, as a

rule, more economical than long struts. The construction of the stress-diagram requires no additional explanation after that given for the stress-diagram Fig. 14A. The student should compare the magnitude of the stresses scaled and marked in Fig. 18A with those in Fig. 14A, and note the effect of the change in the direction of the braces. The truss represented by Fig. 14 requires a very much larger rod in the middle than is required for  $KL$  and  $K'L'$  in the truss Fig. 18. The middle rod for the truss shown in Fig. 18 may be made very light

FIG. 18. Pratt Truss. Inclined Ties. Truss-diagram




Fig. 18A. Pratt Truss. Inclined Ties. Stress-diagram.

This truss, however, requires, for good construction, special cast-iron wash for the rods.

**Simple Fan Truss. Example 9.** (Fig. 19.) This figure shows the skeleton of a simple FAN TRUSS with rafters inclined  $30^\circ$  and divided into three equal panels, making the loads  $AB$ ,  $BC$ ,  $CC'$ , etc., equal. The stress-diagram drawn according to the principle already explained and requires no special treatment. As the loads are equal, the stresses in this truss may be refigured by means of Table X, and the student should compare the stresses determined with those obtained by scaling the stress-diagram.



d Fink Truss. **Example 1c.** (Fig. 20.) The inclination of the ° and the distance between the trusses 20 ft. The loads are cal- a slate roof on boards or on angle-iron purlins. Commence the m by drawing a vertical line equal to the supporting force  $R_1$ , or d lettering the lower end of the line  $o$  and the upper end  $e$ , as these




Fig. 19. Fan Truss. Truss-diagram

on each side of the supporting force at joint  $o$ .  $en$  and  $no$  are to  $AN$  and  $NO$ . For joint 1,  $na$  is drawn upward;  $ab$  is laid off lb and  $bm$  and  $mn$  are drawn parallel to  $BM$  and  $MN$ . At joint 2 known, and  $ml$  is drawn parallel to  $ML$ , the sides of the stress- $on$ ,  $nm$ ,  $ml$  and  $lo$ . At joint 3 a new condition is met, which is ay of the preced-

and which is is form of truss, arently unknown a study of the however, it is and  $IK$  act as -RODS, taking up i the lower ends t joints 2 and 5; s at joints 1 and  $NM$  and  $IH$  are h, the stress in as the stress in already known. he number of at joint 3 to force known at the next  $mb$  and al to 16 100 lb.




Fig. 19A. Fan Truss. Stress-diagram


s drawn parallel to  $CI$  and from  $l$ , the initial point, a line Between these two lines there must be a line,  $ik$ , parallel to length to  $ml$ ; and this line is determined by means of the arallel ruler and straight-edge. If correctly drawn, the joint i ith  $nm$ . The sides of the stress-polygon for joint 3 are, then, and  $kl$ .

**At joint 4 the stress-lines are  $ol$ ,  $lk$ ,  $kg$  and  $go$ .**


At joint 5 the stress-lines are  $gk$ ,  $ki$ ,  $ih$  and  $hg$ .

At joint 6 the stress-lines are  $hi$ ,  $ic$ ,  $cd$  and  $dh$ .

If the stress-diagram is accurately drawn, a line from  $d$  parallel to the rail will pass through the point  $k$ . The vertical tie  $GG'$  (Fig. 20) has no strength and its only purpose is to prevent the horizontal tie from sagging.



**Fig. 20. Cambered Fink Truss. Truss-diagram**



**Fig. 20A. Cambered Fink Truss. Stress-diagram**

**Cambered Fink Truss. Example 11.** (Fig. 21.) This is the truss shown in Fig. 20, with two additional loads. Steel trusses of this shape are required to support loads from below. In Fig. 21 there are two loads of 4 tons each, supported at joints 5 and 9, in addition to the roof-loads. The stress diagram is drawn in exactly the same way as in Fig. 20A, except that at joint 1 the first-known force  $r_o$ , parallel to  $RO$ , 4 tons, is laid off, locating  $r$ . At joint 5, then,  $r_o$ ,  $ol$  and  $lk$  are known and  $kg$  and  $gr$  are drawn to close the polygon. It should be noticed that the stresses in  $NM$ ,  $IH$ ,  $ML$ ,  $KI$  and  $LE$  are not affected by the ceiling-load. This is evident by comparing Fig. 21A with Fig. 20A. All of the other stresses, however, are increased because of the increase in the supporting forces, the greatest increase being in  $KG$  and




Fig. 21. Cambered Fink Truss. Truss-diagram




Fig. 21A. Cambered Fink Truss. Stress-diagram




Fig. 22. Scissors Truss. Truss-diagram




Fig. 22A. Scissors Truss. Stress-diagram

**Simple Scissors Truss. Example 12.** (Fig. 22.) This is the truss diagram of the truss shown in Fig. 22, Chapter XXVI, which is the simplest form of the SCISSORS TRUSS. The truss-diagram is drawn by commencing with a line  $oa$  equal to the supporting force, 9 600 lb, and then in order the forces  $bb'$ ,  $b'a'$ ,  $a'r$  and  $ro$ , forming the polygon of the external forces. At joint 1,  $ra$  is known and  $ad$  and  $do$  are drawn, closing the polygon. At joint 2,  $da$  and  $be$  are known and  $be$  and  $ed$  are drawn, closing the polygon. At joint 3,  $eb$  and  $ec$  are known and  $b'e'$  and  $e'e$  are drawn. This determines the stresses in one-half of the truss. Those for the other half are, of course, of the same magnitude and character, but the stress-diagram should be continued for the second half of the truss as a check.

**Scissors Truss. Example 13.** Fig. 23 is the truss-diagram of the truss shown in Fig. 23, Chapter XXVI, with the loads figured about as they would




Fig. 23. Scissors Truss. Truss-diagram

Fig. 23a. Scissors Truss. Stress diagram

be for a slate roof and wooden ceiling and for a spacing of 12 ft on centers. The stress-diagram is begun by drawing the line  $oa$  equal to the supporting force at joint 1 (14 600 lb). The sides of the stress-polygons for the different joints are as follows.

- At joint 1:  $oa$ ,  $ae$  and  $eo$ ;
- At joint 2:  $ea$ ,  $ab$ ,  $bf$  and  $fe$ ;
- At joint 3:  $ae$ ,  $ef$ ,  $fh$  and  $ho$ ;
- At joint 4:  $hf$ ,  $fb$ ,  $bk$  and  $kh$ ;
- At joint 5:  $ro$  (1 100 lb),  $oh$ ,  $hk$ ,  $kl$  and  $lr$ ;
- At joint 6:  $lk$ ,  $kb$ ,  $bc$  (5 400 lb),  $cm$  and  $ml$ ;
- At joint 7:  $mc$ ,  $cc'$  (5 400 lb),  $c'm'$  and  $m'm$ .

The student should notice how much the stresses in the principal members of this truss exceed the supporting forces or loads, and particularly the great stress in the middle rod. For these reasons this is not an economical type of truss for spans exceeding 36 ft.






with the center line of the strut in Fig. 27, because the inner end of  
 dropped slightly on account of the detail of the joint; but in truss-  
 lines must go from joint to joint, otherwise the stress-diagram can  
 . There are no stresses in the middle diagonals under a symmetrical  
 hence they are shown by dotted lines in Fig. 25. As no complica-  
 drawing the stress-diagram of this truss, a detailed description is  
 The sides of the stress-polygons for the different joints are as

For joint 1:  $oa, ad, do$ ;  
 For joint 2:  $ro, od, de, er$ ;  
 For joint 3:  $ed, da, ab, bf, fe$ ;  
 For joint 4:  $fb, bc, ck, hf$ ;  
 For joint 5:  $sr, re, ef, fh, hs$ .

side, showing that the compression in  $CH$  is equal to the tension  
 plus and minus signs in Fig. 25, as in all the other diagrams,  
 tension and tension respectively.



Truss without Tie-beam. Truss-  
 diagram

Fig. 26A. Truss without Tie-  
 beam. Stress-diagram

**Truss without Tie-Beam. Example 16.** Fig. 26 shows a truss which is  
 AS TRUSS NOT A HAMMER-BEAM TRUSS, yet this form can be made  
 r to the HAMMER-BEAM TRUSS by inserting a curved brace below  
 lacing the pieces  $OH$  and  $OH'$  by curved members. There is no  
 wing the stress-diagram shown in Fig. 26A.

**Initial Thrust of Scissors Trusses.** In the examples just given  
 need that the reactions are vertical and consequently that there  
 L THRUST. This would be true if the materials composing the  
 olutely rigid. This is not the case, however, and all trusses  
 geometrical lines of their shape change in shape after the full

In the SCISSORS TRUSS this changes the length of the span,  
 r and permitting the rafters to sag. If the trusses are con-  
 amber in the rafters and the span made a little short, the THRUST  
 orts can be practically eliminated by fastening one end of the  
 ing for a movement at the other, so that when the full roof and  
 e been placed on the truss the span will have its correct length.  
 is we must know HOW MUCH THE SPAN WILL CHANGE IN LENGTH  
 d. This can be determined in the manner shown in the follow-

ing example and by referring to Fig. 26B. Let Diagram 1 represent a simple SCISSORS TRUSS loaded as shown with 1 000 pounds at each top-chord joint and let the left end be assumed to rest upon rollers. Then both reactions will be vertical and the stresses in each member can be found from the usual stress diagram shown in Diagram 2. Let  $S$  be the stress in any member as found from Diagram 2;  $u$ , the stress in any member produced by one pound acting horizontally at  $K$  and from  $L$  as found from Diagram 3;  $A$ , the area of a




Fig. 26B. Simple Scissors Truss and Stress-diagrams

member, in square inches;  $l$ , the length of any member, in inches;  $E$ , Young's modulus of elasticity of the material composing any member and  $D$ , the total CHANGE IN LENGTH OF SPAN when the truss is subjected to its full load. The

$$D = \sum \frac{Sul}{AE}$$

If  $H$  is the HORIZONTAL FORCE applied at  $K$ , which is necessary to make the value of  $D = 0$

$$H = D + \sum \frac{ul^2}{AE}$$

\* Theory and Practice of Modern Framed Structures, Johnson, Bryan and Turner (John Wiley & Sons); Roofs and Bridges, Merriman and Jacoby (John Wiley & Sons)



calculations for Fig. 26a are given in Table XVII, assuming that, excepting *FG*, are composed of 6 by 6-in white pine timbers with 1000 lb per sq in, and that *FG* is an upset round steel rod having 1.785 sq in with *E* equal to 30 000 000 \* lb per sq in for steel.

II. Computations for *D* and *H* for a Particular Scissors Truss

(2) <i>S</i> , Dia- gram 2	(3) <i>A</i>	(4) <i>S</i> + <i>A</i>	(5) <i>u</i> , Diagram 3	(6) <i>l</i>	(7) $\frac{Su l}{A E}$	(8) $\frac{u^2 l}{A E}$
+3160	36	87.8	+0.71	84.8	0.00528	0.00000118
+2100	36	58.3	+0.71	84.8	0.00351	0.00000118
+2100	36	58.3	+0.71	84.8	0.00351	0.00000118
+3160	36	87.8	+0.71	84.8	0.00528	0.00000118
-2360	36	65.5	-1.58	126.5	0.01316	0.00000875
-2360	36	65.5	-1.58	126.5	0.01316	0.00000875
+ 800	36	22.2	0	63.2	0.0	0.0
-1980	0.785	2522.0	-1.00	80.0	0.00672	0.00000340
+ 800	36	22.2	0	63.2	0.0	0.0
					0.05062	0.00002562

in and  $H = 0.05062 + 0.00002562 = 1975$ , or, approximately, as shows that the span would lengthen about  $\frac{1}{30}$  in, if allowed free at one end; or, if fixed, there would be a HORIZONTAL FORCE of 1975 lb tending to push the supports out. In column 4 it is seen that the stresses are only about one-tenth of those permissible. Assuming that the loads become 10 000 lb at each apex-joint, the HORIZONTAL DEFLECTION becomes about  $\frac{1}{2}$  in, and the HORIZONTAL THRUST becomes 20 000 lb. Conclusively that a large excess of material must be employed in the members, particularly in the members *EM* and *HM* which contribute over 50% of the value of *D* as shown in column 7, if the HORIZONTAL DEFLECTION is small that its effect may be neglected. As stated before, if the truss is permitted to deflect horizontally until fully loaded, the walls or supports must be able to resist a HORIZONTAL THRUST of 20 000 lb.

**Hammer-Beam Truss.** As usually constructed the HAMMER-BEAM truss is designed to exert more or less HORIZONTAL PRESSURE at the supports; this pressure is provided for by heavy walls and buttresses. The diagram of such a truss is shown in Fig. 27, in which the CURVED BRACES usually built in the truss are not shown, as they are considered to be purely ornamental. Under vertical loading have no stresses. The brace *OM* is drawn as a straight line; but a curved brace may be used instead, without alteration. The stress in the curved piece is that found from the stress in the straight piece by the bending stress due to its curvature. To determine the stresses in the members of this truss it is necessary to first find the HORIZONTAL THRUST of the truss against the wall. To do this all the truss-members from joint 4 to the supports are considered to form a FRAMED BRACE, or ASSEMBLAGE OF BRACES. The upper portion of the truss at joint 4, or a SINGLE BRACE, shown by the broken line *o4*, Fig. 27, is assumed to have the same effect on the lower portion as the pieces put together in the FRAMED STRUT; that is, the truss is considered as a single member.

100 000 lb per sq in is used for the value of *E* for steel the values of *D* and *H* are changed. See Table I, page 664.

considered to have the same HORIZONTAL THRUST as the truss shown in Fig. 26. The load at joint 4 is evidently: 12 000 lb, plus the load at joint 5, plus the load at joint 6, plus half the load at joint 2; making in all, 36 000 lb.




Fig. 27. Hammer-beam Truss. Truss-diagram

two lines will intersect at  $m$ , and  $mx$  is the MAGNITUDE OF THE HORIZONTAL THRUST exerted on the wall at the joint  $o$ . Having obtained this thrust, it is easy to determine the stresses in the pieces. At joint  $o$  the four forces




Fig. 27A. Hammer-beam Truss. Truss-diagram




Fig. 27B. Hammer-beam Truss. Stress-diagram

equilibrium are the resistance to the thrust,  $mx$ , the vertical supporting force  $my$  and the stresses  $oa$  and  $om$ , closing the polygon. At joint 1,  $oa$ ,  $af$  and  $fo$  are the stresses in  $OA$ ,  $AF$  and  $FO$ . At joint 3 the stresses are  $mo$ ,  $af$ ,  $fg$  and  $go$ ; at joint 2 they are  $fo$ ,  $ob$ ,  $bg$  and  $gf$ ; at joint 4 the stresses are  $mg$ ,  $gb$ ,  $bc$  and

polygon. It will be noticed that the POLYGON CLOSES without allow-  
 to be drawn parallel to  $IM$ ; hence there is no stress in  $IM$ , with  
 ing. When there are wind-loads there is some compression in  $IM$ ,  
 ber is a necessary part of the truss. At joint 5 there are the stresses  
 $ki$ , and at joint 6.  $kd, dd', d'k'$  and  $k'k$ , which complete the stresses for  
 truss, which are all that are needed. Comparing, now, the diagram




Fig. 28. Suspended Pratt Truss. Truss-diagram

Fig. 27B, with Fig. 26A, it is seen that, in general, the MAGNITUDES  
 ES in the truss, Fig. 27, are much less than those of the stresses  
 Fig. 26; while, on the other hand, the latter truss may be so con-  
 to exert the OUTWARD THRUST on the walls, exerted by the truss  
 27. If curved members are introduced between joints 3 and  
 12, they should be lightly secured at the ends or the stresses deter-  
 e manner  
 e SCISSORS

ed Pratt  
 ple 17.  
 be the  
 of a SUS-  
 T TRUSS,  
 ed at top  
 with 2 tons  
 t. The  
 is drawn  
 same way  
 E TRUSS,  
 diagonals  
 site direc-




Fig. 28A. Suspended Pratt Truss. Stress-diagram

sses should be drawn for the joints in the order in which they  
 In this truss the verticals are in compression and the diagonals

ss. Example 18. Fig. 29 is the truss-diagram of a light iron  
 of 32-ft span, intended to support a tar-and-gravel roof, the  
 right-angles to the line of the trusses. The stress-diagram is  
 previous examples, taking the joints in the order in which they

ren Truss, or Lattice Truss. Example 19. The truss-dia-  
 Fig. 30 is best analyzed by considering it as built up of two




Fig. 29. Warren Truss. Truss-diagram




Fig. 29A. Warren Truss. Stress-diagram




Fig. 30. Double Warren Truss. Truss-diagram






Fig. 31. Warren Truss. Truss-diagram

SSSES, laid one over the other, the full lines indicating a truss such as in Fig. 31, and the dotted lines a truss as shown in Fig. 32. Three loads would come on the first truss and four on the second. The stress found for each truss separately combined for the top and bottom is the stress in the top chord of Fig. 30, would be that in  $AD$ , 3 tons; from 3 to 5 it would be stress in  $AD$ , Fig. 31, plus that in  $3D$ , Fig. 32, or 9 tons; from 5 to 7 it is equal to the stress in  $BF$ , Fig. 31, plus the stress in  $BE$ , Fig. 32, or 13 tons, the stress in the bottom chord is found in the same way. The diagonal stresses act independently of each



**Fig. 31A. Warren Truss. Stress-diagram**


e stresses are those indicated on the stress-diagrams. The plus  
ompression and the minus signs tension. In Fig. 32 the sides  
olygon for joint 7 are  $fe$ ,  $eb$ ,  $bc$ , and  $gc$ , which closes without  
a line parallel to  $GF$ , showing that there is no stress in the two



**Fig. 32. Warren Truss. Truss-diagram**

except that due to the weight of the bottom chord. This truss is constructed of steel angles. When wood is employed, three or four pieces are combined forming the LATTICE TRUSS shown in Fig.

It is entirely unnecessary to use graphical methods in



**n Truss. Stress-dia-**  
**gram**

determining the stresses, as the chords and web-members are respectively uniform in size. For the chords the maximum bending moment divided by the distance, center to center, of the chords gives the designing-stress for the chords. The maximum vertical shear, usually the reaction, divided by the number of simple WARREN TRUSSES combined gives the vertical component for which the web-planks are designed. This, of course, leads to a waste of material as far as resisting stresses is concerned, but for stiffness and economy in labor, the extra

used. This truss can be extended indefinitely by giving it for the span. (See, also, pages 1008 and 1009.)

**Truss. Example 20.** Fig. 33 is the truss-diagram of a truss shown in Fig. 59, Chapter XXVI, the panel-loads being taken at the analysis being the same for any other loads. The stress-




Fig. 33. Quadrangular Truss. Truss-diagram




Fig. 33A. Quadrangular Truss. Stress-diagram




Fig. 34. Quadrangular Truss. Truss-diagram




Fig. 34A. Quadrangular Truss. Stress-diagram

drawn exactly as in the previous examples, commencing with the force  $oa$  and considering the joints in the order in which they are. In this truss the diagonal web-members are all in tension and the compression. It will be noticed that the inclination of the diagonals in the panels nearest the middle of the truss is opposite to that of the diagonals in the outer panels. This is due to the inclination of the top chord, which causes the stresses in the inner diagonals when they incline the other way. The force  $LM$ , however, is so small that a single steel angle resists either a com-




Fig. 35. Quadrangular Truss. Truss-diagram

pression. The truss shown in Fig. 34 is very similar to that shown in Fig. 35, the principal difference being that the slope of the top chord is less than in the latter. In Fig. 34, the diagonals in the two middle panels incline from the top of the middle vertical, and the stress in these diagonals is very small. With a still less inclination to the top chord, the stress in the middle diagonal becomes zero; and with a horizontal top chord the character of the stress in the middle diagonal is reversed. To keep it in tension, its direction should be changed, as in the truss, Fig. 28. Comparing the stresses in these two trusses, it is

found that the stresses in the top chord are less in Fig. 34A than in Fig. 35. The stresses in the chords at the ends are considerably greater. The less the height of a truss in proportion to the span, the greater are the stresses in the chords, especially in the middle of the truss.

#### Stress-Polygon. Example

The stress-polygon for the truss shown in Fig. 66, is drawn as in Fig. 66, I. The truss-diagram is drawn exactly as in the previous examples, but in this case, as the truss has different inclina-




Fig. 35A. Quadrangular Truss. Stress-diagram

tion in different panels, the stress-lines do not lie over each other, but are drawn as separate lines in the stress-diagram being parallel to the corresponding members in the truss-diagram. In this truss the character of the stresses in the members is reversed in the two panels nearest the middle. Thus the stress-polygon for joint 4 are  $lk$ ,  $kb$ ,  $bc$ ,  $cm$  and  $ml$ , the stress  $ml$  denotes tension. At joint 8 the sides of the stress-polygon are  $rp$ ,  $pd$ ,  $de$ ,  $es$  and  $sr$ , the latter line acting towards the joint, denoting compression. Under irregular loading, the character of the stresses would probably be reversed, so that the piece would be in ten-

sion instead of in compression. The stresses in members of trusses like Figs. 34 and 35 should, therefore, always be computed for snow on one-half of the truss only and also for wind-pressure.

**Quadrangular Truss. Example 22.** In Fig. 36 is shown the diagram of the truss illustrated in Fig. 65, Chapter XXVI. This truss is similar to the one shown in Fig. 34, except for the secondary bracing in the panels and for the




Fig. 36. Quadrangular Truss. Truss-diagram

curved bottom chord. The stress-diagram presents no difficulties. In drawing the lines from  $o$  parallel to the members of the bottom chord the latter should be considered as made up of straight lines connecting the joints. Thus one line is drawn parallel to an imaginary straight line connecting joints 8 and 4. As there is no load over the center of the two panels next to the middle of the truss, there are no stresses in the truss-members between  $X$  and  $I$  and  $I$  and  $II$ . When




Fig. 36A. Quadrangular Truss. Stress-diagram

the bottom chord is straight as in Fig. 34, there is no stress in  $YY'$ ; but when the bottom chord is curved, a tension stress develops, in  $YY'$ , the magnitude of this stress being indicated by  $yy'$  (Fig. 36). When the diagram is completed for the entire truss, it is symmetrical about a horizontal line drawn through the center.

**Bowstring Truss. Example 23.** The span of this truss is 90 ft; the distance between the trusses from centers, 20 ft; and the rise of the arch of the rafter or upper chord, 20 ft. The form of truss represented in Fig. 37 is one of the most

economical for very great spans. In trusses similar to the one explained in the example, the top chord is curved and is the only piece that is in compression. All the other members are in tension. Under a steady load only, such as the weight of the roof itself, the diagonals drawn with solid lines and placed as shown in Fig. 37 are all that are needed; but when there is a severe wind-pressure on one side of the roof only, it is necessary to have the additional set of diagonals shown by the dotted lines. These COUNTERBRACES, as they are



ed, forming the additional set, are not stressed when there is a vertical load by and they are omitted in drawing the stress-diagram. To draw the stress-gram, the loads are laid off on a vertical line, as in all the previous examples, e point  $o$  being half-way between  $e$  and  $e'$  (Fig. 37A).  $oa$  is the supporting re at joint 1. In drawing the stresses at the different joints, those at joint 1 e first drawn and then those at joints 2, 3, 4, 5, etc., in the order in which they e numbered (Fig. 37). In the stress diagram,  $oa$ , equal to the supporting




Fig. 37. Bowstring Truss. Truss-diagram




Fig. 37A. Bowstring Truss. Stress-diagram

at joint 1, is known and from  $a$  a line is drawn parallel to  $AG$ , and from line parallel to  $GO$ . These two lines intersect at  $g$ . The lines representing the stresses in the curved members of the truss are drawn parallel straight lines connecting the two ends of each curved piece. Thus  $ag$  is parallel to 1-3 and  $og$  parallel to 1-2. At joint 2,  $og$  is known,  $gh$  is drawn parallel to  $GH$  and  $ho$  parallel to  $HO$ . At joint 3,  $hg$  and  $ga$  have been drawn, and  $eb$  is known and  $bi$  and  $ih$  are drawn. At joint 4,  $oh$  and  $hi$  have been drawn, and  $ik$  and  $ko$  are next drawn to close the polygon. The stress-lines for joints 6 and 8 are drawn in a similar way, and those for 5, 7 and 9 similarly to those at joint 3. After drawing the stress-lines for joint 9, joint 10 is next connected; and after the stress-lines for that joint are determined the stresses in the members of the truss are known. The stresses in this particular example are given in pounds on the respective lines in the stress-diagram. It will be

noticed that the stresses are very great in the top and bottom chords, but small in the bracing. The latter stresses are, in fact, so small that it is just well to make all the diagonal braces the same size and of dimensions sufficient to resist the stress in  $IH$ , which has the greatest stress; or  $IH$  and  $KL$  may be made the same size and  $MN$  and  $PR$  a smaller size. The verticals or radiating pieces may all have a sectional area sufficiently large to safely resist the stress in  $NP$ . The great advantage of this truss lies in the fact that all its parts are in tension excepting the upper chord, which, of course, is in compression. The manner in which stresses act may be described in general by saying that the upper chord carries all the load, like an ARCH, and is prevented from spreading out at the ends by the lower tie; and that the object of the bracing and vertical pieces is only to keep the bottom chord in its curved position.

**Trusses Unsymmetrically Loaded.** Now that the principles have been explained according to which the stress-diagrams may be drawn for several




Fig. 38. Unsymmetrical Truss. Truss-diagram

Fig. 38A. Unsymmetrical Truss. Force-polygon

forms of trusses SYMMETRICALLY LOADED, it may be well to consider the subject in a more general manner. It will now be assumed that there are no restrictions as to SYMMETRY in the form of the truss and its loading; and, furthermore, will not be assumed that all of the loads act as VERTICAL FORCES as in the problem just solved. Fig. 38 shows an UNSYMMETRICAL TRUSS UNSYMMETRICALLY LOADED and with loads or forces which are not parallel. In the previous problem the supporting forces or REACTIONS have been equal and each equal to one-half the load. In this problem such is not the case. The first step, then, is the determination

THE REACTIONS. If the truss remains in position it follows that  
 acting upon the truss, such as the LOADS and REACTIONS, must be  
 UM; also since by definition a TRUSS must act as a BEAM, the truss  
 acted by a BEAM in considering the OUTSIDE FORCES. In Fig. 38,  
 lines representing the direction of the forces, as shown, until they  
 ST and assume ST to be a simple beam loaded with the forces AB,  
 beginning with AB, to some convenient scale lay off the forces in  
 own in Fig. 38A. The broken line VU represents the forces in magni-  
 tude. For equilibrium, forces equivalent to UV are required.  
 ent when we remember that the algebraic sum of the vertical and  
 components of all the forces acting must respectively equal zero.  
 at the supports at S and T, Fig. 38 are similar in every respect we  
 that the reactions  $R_1$  and  $R_2$  act in the same direction and that they  
 to UV. This does not determine the magnitudes of  $R_1$  and  $R_2$ . These  
 as follows: In Fig. 38A, assume any point W and draw the lines 1,  
 Fig. 38, starting at any point on  $R_1$  draw the line 1 parallel to the  
 38A, and extend it until it cuts the direction or line of action of the  
 shown; from this point draw a line parallel to 2 in Fig. 38A, and extend  
 the direction of BC as shown, and so continue until line 6 is drawn




Fig. 38b. Unsymmetrical Truss. Truss-diagram

Draw line 7 in Fig. 38 and then in Fig. 38A draw a line parallel to  
 until it cuts UV. This point divides UV into two parts, the upper  
 magnitude of  $R_1$  and the lower the magnitude of  $R_2$ . No trouble will  
 in applying the above method if the following rule is obeyed to  
 Fig. 38, the parallels to any three lines in Fig. 38A which form a  
 meet in a point. For example, in Fig. 38A lines 1, 2, and  $P_1$ ,  
 triangle, and in Fig. 38, their parallels meet in the point X. In  
 is not necessary that the forces AB, BC, etc., be used in order in  
 considering them in order, on a simple beam, makes the graphical  
 Fig. 38 less complex and avoids many chances of error. The  
 and above is general and can be used for forces acting in any direc-  
 forces are parallel then the load-line ab, bc, ce, etc., in Fig. 38A, and  
 will coincide; but the method of procedure remains unchanged.  
 the FORCES acting upon the truss have been determined, for con-  
 will be shown in character, in Fig. 38b, and the STRESSES in the  
 solving the truss will be found. First lay off the forces in exact  
 t they form a CLOSED FIGURE, which must be the case if they are  
 The lines with arrow-heads in Fig. 38c show this construction,

which checks the values of  $R_1$  and  $R_2$  obtained above. This figure remains the same regardless of the interior arrangement of the truss. The construction of the stress-diagram follows the methods given in the previous examples until point 3 is reached. Here there are three UNKNOWNs,  $CM$ ,  $ML$  and  $LK$ , and cannot be assumed that  $ML$  is the same as  $JK$ , as was done in examples 10 and 11. Let the truss be cut as shown in Fig. 38D, and the actual stresses in the cut pieces assumed to act against the cut ends, then the frame shown in Fig. 38E and the forces  $R_1$ ,  $AB$ ,  $BC$ ,  $CE$ ,  $EN$ ,  $NO$ ,  $OG$  and  $GH$  will be in equilibrium




Fig. 38c. Unsymmetrical Truss. Stress-diagram




Fig. 38d. Unsymmetrical Truss. Truss-diagrams

The frame may be of any form as long as it is rigid so the bracing may be changed as shown in Fig. 38D and the stress-diagram proceeded with as in Fig. 38C until the stresses in  $EN$ ,  $NO$  and  $OG$  have been found. This will locate point  $O$ . Returning to Fig. 38B, it is found that at joint 4 all the stresses  $KL$  and  $LO$  are known; hence these can be found in the usual manner. Joint 5 is next considered and so on until the diagram is complete. The line  $gf$  in Fig. 38C will pass through  $f$  if the work is correct. Although the method for determining the CHARACTER OF THE STRESSES has been explained, it will be repeated here in a more general manner. Take, for example, joint 8, in Fig. 38B, which




Fig. 38e. Unsymmetrical Truss. Forces at Joint 8

is in equilibrium under the action of the stresses  $go$ ,  $op$ ,  $pq$  and  $qg$ , as indicated in Fig. 38E. The stress-diagram for this joint is shown in Fig. 38F, separated from Fig. 38C. It is





Fig. 38f. Unsymmetrical Truss. Stress-polygon

assumed that the stress in  $GO$  is tension. Then in Fig. 38F, starting at  $g$  we cut off  $go$ ,  $op$ ,  $pq$  and  $qg$ , placing the arrow-heads as shown. Transferring the arrow-heads to the ends of the cut pieces in Fig. 38E indicates at once the KIND OF STRESS. The following examples illustrate the above methods.

**Unsymmetrically-loaded Truss. Example 24.** Fig. 39 represents the diagram of a truss similar to that shown in Fig. 1, but of a greater span and having a gallery supported from it at one side only. The approximate roof and ceiling loads are indicated by the figures near the arrows, and the weight coming from one truss from the gallery would be about 9 000 lb. The first step toward drawing the stress-diagram is to determine the reactions at the two ends of

will give the supporting forces. This is readily done in this example  
MOD OF MOMENTS explained on pages 322 to 324. Moments are first  
joint 1. As the loads at joints 2 and 3 have the same arm, they  
gether before multiplying by the arm. The loads at joints 4 and 5



39. King-rod Truss. Truss-diagram and Equilibrium-polygon




Fig. 39A. King-rod Truss. Stress-diagram

5 and 7 are treated the same way. The moments about joint 1 will

$$\begin{aligned} 50 + 4\,500 + 9\,000) &= 21\,500] \text{ lb} \times 12\frac{1}{2} \text{ ft} = 268\,750 \text{ ft-lb} \\ 50 + 4\,500) &= 12\,500] \text{ lb} \times 25 \text{ ft} = 312\,500 \text{ ft-lb} \\ 50 + 4\,500) &= 12\,500] \text{ lb} \times 37\frac{1}{2} \text{ ft} = 468\,750 \text{ ft-lb} \end{aligned}$$

$$\text{The sum of the moments} = 1\,050\,000 \text{ ft-lb}$$

These CLOCKWISE MOMENTS about joint 1 must be balanced by the  
CLOCKWISE MOMENT of R<sub>2</sub>, the LEVER-ARM of which, with reference to  
joint 1. Knowing the arm, 50 ft, the force R<sub>2</sub> is obtained by dividing  
the moments of the loads by the span. Dividing 1 050 000 ft-lb by

50 ft, the result is 21 000 lb, which is the reaction or supporting force at joint 1 and  $R_1$  must equal the difference between the sum of the loads and  $R_2$ . The sum of the loads is 46 500 lb and subtracting from this 21 000 lb, the remainder 25 500 lb, is the value of  $R_1$ . The stress-diagram (Fig. 39A) may now be drawn. First draw a vertical line  $oa$  equal to  $R_1$ , 25 500 lb. From  $a$  and  $o$  draw lines parallel respectively to  $AE$  and  $EO$ , locating the point  $e$ . For the stress-line at joint 2 measure up from  $o$  a distance equal to the load at that joint, 13 500 lb, which gives the point  $r$ , and from  $e$  and  $r$  draw lines parallel to  $EF$  and  $FE$  which intersect at  $f$ . At joint 3, the sides of the stress-polygon are  $fe$ ,  $eo$ ,  $ob$  and  $bf$ . Draw the stress-polygons for joints 4, 5, and 6 in the order in which




Fig. 40. Unsymmetrical Truss. Truss-diagram and Equilibrium-polygon

they are numbered. At joint 6 the sides of the stress-polygon are  $ik$ ,  $kc$ ,  $cd$ ,  $dl$  and  $ji$ . If the diagram has been correctly drawn, the line  $ij$  will be just equal to the load at joint 7. The sides of the stress-polygon for joint 7 are  $ts$  equal to 4 500 lb,  $si$ ,  $ij$  and  $jt$ , the only line to be drawn being  $jt$ , which must be parallel to  $JT$ . Consequently  $j$  must be exactly opposite  $t$ , or the polygon will not close. The distance  $dt$  should be equal to  $R_2$ .

**Unsymmetrically-loaded Truss. Example 25.** Fig. 40 is the diagram of a wooden roof-truss. The actual loads were about as given on the diagram. There were purlins at joints 3 and 5 only, and the ceiling below was suspended by rods from joints 4 and 7, joint 4 being fixed by the framing of the ceiling. The moments of the loads about joint 1 are:

$$\begin{aligned} 3\ 200\ \text{lb} \times 8\frac{1}{2}\ \text{ft} &= 27\ 200\ \text{ft-lb} \\ 5\ 500\ \text{lb} \times 15\frac{1}{2}\ \text{ft} &= 85\ 250\ \text{ft-lb} \\ 4\ 100\ \text{lb} \times 19\ \text{ft} &= 77\ 900\ \text{ft-lb} \\ 5\ 500\ \text{lb} \times 24\ \text{ft} &= 132\ 000\ \text{ft-lb} \end{aligned}$$

$$\text{Sum of moments} = 322\ 350\ \text{ft-lb}$$

the sum of the moments by the distance between the supporting forces, 59 768 lb as the value of  $R_2$ .

The loads is 18 500 lb. Sub-

68 lb, 8 532 remains as the  
To draw the stress-diagram,  
 $o''a$  equal to 8 532 lb equal  
raw  $ae$  and  $eo''$ . The sides of  
olygon for joint 2 are  $ea$ ,  $ab$ ,  $bf$ ,

At joint 3,  $fb$  is known and  
red down and made equal to  
and  $gf$  are then drawn. At

t by measuring upwards from  
locating point  $o'$  and draw  $gh$   
t joint 5,  $hg$  and  $gc$  are now

uals 5 500 lb and a line from  $d$   
allel to  $DH$ . This should pass through  $h$ , completing the diagram.

rod 2-7 is the load at joint 7.





Fig. 40A. Unsymmetrical Truss. Stress-diagram



. Unsymmetrical Truss. Truss-diagram and Equilibrium-polygon

rically-loaded Truss. Example 26. Fig. 41 is the truss-diagram  
ss in the same building in which the truss shown in Fig. 40 was  
moments about joint 1, there results, for the sum of the moments,

and  $200 \text{ ft.}$  and dividing this by  $11$  it gives  $18 \text{ ft.}$  as the value of  $R_2$ . The sum of the loads is  $24 \text{ tons}$  and which agrees with  $24 \text{ ft.}$  as the value of  $R_1$ . The stress-diagram Fig. 41a is drawn in the same manner as in Fig. 40. Starting with  $1$  as equal to  $R_1$ ,  $10$  is chosen equal to the load at joint  $2$ , and the actual stress in  $EF$  is  $5 \text{ tons}$  or the length of the line  $ef$ . If the stress-diagram correctly drawn, a line through  $e$  parallel to  $AD$  will pass through the point  $f$  previously determined. The character of the stresses is indicated by the




Fig. 41a. Unsymmetrical Truss. Stress-diagram

PLUS AND MINUS SIGNS in Fig. 41, indicating compression. If the stress-diagrams in the last three examples be compared with those for symmetrical loaded trusses of similar shape it is found that while the stress-diagrams, Figs. 39, 40a and 41a are unsymmetrical, they are of the same general character, and the stresses are all of the same kind when the supporting forces are equal. This condition holds true for most triangular trusses, but for trusses with horizontal or curved chords, unsymmetrical

loading usually causes a REVERSAL OF THE STRESS IN KIND in one or more of the diagonals or verticals; and if the truss contains any four-sided panels, an additional diagonal is generally required. This is particularly true of the HOWE TRUSS; and as this truss is very extensively used by architects and builders, will now be considered at some length with special reference to the effect UNSYMMETRICAL LOADING.

**Howe Trusses, Unsymmetrically Loaded.** When a HOWE TRUSS is loaded symmetrically on each side of the middle, all of the braces incline downward from the center, as in Figs. 14 to 17, Chapter XXVI; and if there is an **ODD NUMBER OF PANELS**, the middle panel needs no brace. When a load of any magnitude is placed on one side of a truss having an **ODD NUMBER OF PANELS** without a corresponding load on the other side, a brace is always required in the middle panel and the brace should incline downward from the side which is most heavily loaded.

**Howe Truss with Even Number of Panels.** When the truss has an **EVEN NUMBER OF PANELS**, an unsymmetrical load causes a greater stress in the braces on one side of the truss than on the other; and if there is a sufficient




Fig. 42. Howe Truss. Truss-diagram

difference in the loads on the two sides of the truss, it causes compressive stress in one or more of the rods and tensile stresses in one or more of the braces. In this truss is especially designed with the idea of having the **BRACES IN COMPRESSION** and the **VERTICALS IN TENSION**, whenever the loading causes tension in a brace, or compression in a rod, the direction of the brace should be reversed causing it to be in compression again. Consider, for example, the truss shown in Fig. 42, divided into 6 panels of equal width and loaded with 4 tons at each of the upper joints and 9 tons at the second lower joint from the left. Without the bottom load of 9 tons, the brace in the third panel should incline downward from the middle joint, as shown by dotted line at  $B$ ; but when the load 9 tons is added, it causes a tensile stress in  $B$  and a compressive stress in  $R$ .



the DIRECTION OF THE BRACE IS REVERSED, as shown by the full line: compression and the vertical  $R$  has no stress except that caused by load of 9 tons. There are the same results when the load of 9 tons is at the joint directly above, instead of at the lower joint, although in this case there is no stress at all in  $R$  except that due to the weight of the tie-beam. When the load of 9 tons is reduced to 6 tons, no brace is required in the third panel.

When the bottom load is 3 tons, a brace in the second panel is required, as shown in Fig. 43. (See page 1006.)

**Truss with Uneven Panels.** In the five-panel truss shown in Fig. 44, a load of 15 tons at  $A$  requires the same direction of braces shown in Fig. 42.

When the load at  $A$  is increased to more than 15 tons, the direction of the brace in the second panel needs to be reversed, as shown by the dotted line. The stress diagram shows in which direction any brace should be placed to be in tension, but this may be determined also by the following rule.

When the sum of the loads to the left of any section, taken between  $R_1$  and the middle, is less than the reaction  $R_1$ , the direction of the brace cut by that section must be in its normal direction. When the sum of the loads is greater than  $R_1$ , the brace should be in its reversed position. When the sum of the loads, to the left of a section, is just equal to  $R_1$ , no brace is required. For example,




Fig. 43. Howe Truss. Truss-diagram

Howe Truss. Truss-diagram

Consider a section at  $x$ , Fig. 44. Here the sum of the loads to the left is 10.5 tons, which sum is less than  $R_1$ ; hence the brace should be in its normal direction. If the section is at  $y$ , the sum of the loads to the left is 13.5 tons, which sum is greater than  $R_1$ ; hence a brace is required, slanting downward from the more heavily loaded side. When the section is at  $z$ , Fig. 42, the load to the left is 4 tons, an amount less than  $R_1$ ; hence the brace in that panel should be in its normal position. When the section is at  $w$ , the sum of the loads is greater than  $R_1$ ; hence the brace in that panel is reversed. When the section is at  $v$ , Fig. 43, the sum of the loads to the left is less than  $R_1$ ; hence the brace should be in its normal position. By this rule the proper direction of the brace in any panel is indicated, without the complication of the loading and of the width of the panels; but to apply the rule, it is first necessary to determine the supporting forces, which may be found either by the METHOD OF MOMENTS, as explained in Art. 10, or by the GRAPHICAL METHOD.

**Unsymmetrical Howe Truss. Example 27.** As an example of an unsymmetrical truss unsymmetrically loaded, the truss represented in Fig. 45 is taken.

This truss is supposed to support a flat roof and a wooden tower on the right. The position of the tower necessitates a division of the panels so that the truss is quite unsymmetrical. It is assumed that the roof, snow, and tower constitute the loads in pounds at the upper joints, as indicated by the figures. The graphical determination of the reactions is clearly shown in Figs. 45 and 45A. The only panels of this truss in which any question as to the direction of the braces are the third and

fourth. Taking a section at  $x$ , the sum of the loads to the left is greater than  $R_1$ ; hence the brace should be placed as drawn. A section taken through  $W$  makes the sum of the loads to the left less than  $R_1$ ; and hence the brace should be in its normal position. The stress-diagram of this truss is readily drawn starting with  $w$  equal to  $R_1$ , and going from joint to joint as in previous examples. The completed stress-diagram is shown in Fig. 45A.




Fig. 45. Howe Truss. Truss-diagram




Fig. 45A. Howe Truss. Stress-diagram

**Counterbraces.** These are EXTRA BRACES that are put in a truss when stresses are REVERSED IN CHARACTER by a load which may be applied for a time and then removed. For illustration, consider the truss represented in Figs. 4 and 43. Here it has already been shown that when the load at  $A$  is less than 6, the brace in the third panel should be in the position shown in Fig. 43; while when the load is greater than 6, the brace should be in the position shown by the full line, Fig. 42. Now, if the load at  $A$  represents the weight of a crowded gallery or a hoist raising a heavy load, or in fact if it represents any live load, it is evident that when this live load is absent the brace in the third panel should be in its normal position; and that when this maximum load is present a brace is needed in the opposite direction. As it is not practicable to move the brace to suit the changing conditions of the loading, it is necessary to put in two braces, only one of which, however, is in action at a time. The stress in a HOWE TRUSS, therefore, which is subject to a variable and unsymmetrical loading, should be computed for at least TWO CONDITIONS OF LOADING: first for the condition resulting from the APPLICATION OF THE MAXIMUM LOAD; and

or the condition resulting from the REMOVAL OF THE VARIABLE LOAD. should be designed to resist both conditions. SNOW is a VARIABLE which such trusses are often subjected; but as it is nearly uniformly over the roof, it does not change the CHARACTER OF THE STRESSES in the members. If a truss, therefore, is designed for a MAXIMUM SNOW-load more than strong enough when there is no snow. Moreover, the strength of the chords is usually sufficient to resist any slight inequality in loading. The principal VARIABLE VERTICAL LOADS, therefore, to which a truss may be subjected and which require counterbraces, are those due to the weight of people, merchandise, etc., these loads being either suspended from the truss by rods or brought upon the truss by a floor supported by the truss. The truss shown in Fig. 45, also, is an instance of such loading. The figures given by the figures indicate merely the combined dead loads and

During a high WIND the weight on the LEEWARD SIDE of the tower is increased and on the WINDWARD SIDE decreased, so that when the wind blows from the right, the load at 4 is greater and at 8 less than indicated; while when the wind blows from the left the load is increased at 8 and decreased at 4. Therefore, COUNTERBRACES in both the third and fourth panels. As counterbraces do no harm, even if never brought into action, it is always well to use them in the middle panels wherever the loads are at all variable.

**For Trusses.** These trusses may be considered as UNSYMMETRICALLY LOADED, for although the loads may be symmetrical in relation to the truss, they are usually unsymmetrical in relation to the supports. The method of finding the SUPPORTING FORCES and drawing the stress-diagrams is shown in the following examples:




Fig. 46. Cantilever Truss. Truss-diagram

**For Truss. Example 28.** Fig. 46 is the diagram of a CANTILEVER TRUSS which might be used to support the roof over a grand stand or railway platform and may be constructed either of wood or steel, steel being preferred. The first step towards determining the stresses is to find the supporting forces. For this purpose the panel-loads have been made 1000 lb each, and of equal width. These assumed loads simplify the problem and are as near as possible to the actual loads to explain the method of procedure. In CANTILEVER TRUSSES the loads at the ends of the trusses, as well as the intermediate loads, must be taken into account. These end-loads are each equal to one-half of the panel loads. To find the supporting forces moments are taken about the fixed support. The sum of the moments of the external vertical forces is 147 000 ft.-lb. This must be resisted by the moment of the force  $R_1$ , which acts in the opposite direction with reference to the same point and with a lever-arm of 24 ft. Hence  $147\,000 = R_1 \times 24$ , there results 6125 lb as the value of  $R_1$ .

and as the total load is 7 000 lb,  $R_2$  must be 875 lb. The stress-diagram may be commenced either with the forces at joint 1 or with those at joint 13; but as the external loads were laid off from left to right in the preceding examples, the same order is used here. Commencing the




Fig. 46A. Cantilever Truss. Stress-diagram

with joint 1, lay off on a vertical line the load  $oa$  equal to 500 lb, which acts down, and draw  $ai$  and  $io$  parallel respectively to  $AI$  and  $IO$ . The forces act from  $o$  to  $a$ , from  $a$  to  $i$  (from the joint) and from  $i$  to  $o$  (toward the joint), showing that  $AI$  is in tension and  $IO$  in compression, a REVERSAL OF THE CHARACTER OF THE STRESSES developed in the corresponding members of a truss supported at both ends. Next, at joint 2, the stress  $ia$  is now known, and  $ab$  equal to 1 000 lb is laid off; then  $bj$  and  $ji$  are drawn,  $BJ$  being in tension and  $JI$  in compression. The forces at joint 3 are next drawn and then those for the remaining joints, in the order in which they are numbered. At joint 6, the first force known is the supporting force  $R_1$ , represented by  $o'o$  laid off equal to 6 125 lb and acting upward. The sides of the polygon of forces for joint 6 are  $o'o$ ,  $om$ ,  $mn$ , and  $no'$ . The stress in  $MN$  is equal to the supporting force  $o'o$ , which is evident from the truss-diagram. In practice,  $R_1$  would probably be a COLUMN continued to the apex of the truss. At joint 12 the stresses already determined are  $vu$ ,  $uf$ , and  $fg$  equal to 1 000 lb.  $gv$  must close the polygon. It will be noticed that  $gv$  acts toward joint 12; hence the rafter in the end-panel is in compression. If a line drawn from  $v$  parallel to the rafter, passes through  $o$ , the stress-diagram is correct; if it does not pass through  $o$ , then either the stress-diagram has not been drawn with




Fig. 47. Cantilever Truss. Truss-diagram

sufficient accuracy or an error has been made in computing the supporting forces. In drawing the stress-diagram for CANTILEVER TRUSSES, it is important to keep in mind THE DIRECTION IN WHICH THE FORCES ACT, in order to determine which members are in compression and which in tension.

**Truss. Example 29.** Fig. 47 is the diagram of a truss similar to that shown in Fig. 46, but with the **DIAGONAL BRACES INCLINED** TO THE **SITE DIRECTION**, so as to cause them to be in compression and the other members in tension. The supporting forces are found by the same methods as in Example 28, and the stress diagram, also, is drawn by the same method used for Fig. 46A.

However, the stress in the post  $MN$  is constant and less than the reaction at the support, a large portion of the load being transmitted to joints  $LM$  and  $NR$ . The three sections of the right side are in compression and three sections of the bottom chord are in tension. This is because in the projection of the stress-lines the stress is less than it is in the original truss. The **STRESSES ARE ALL OF THE SAME KIND**. This truss is adapted to wooden construction with vertical rods for the bottom chord, as shown in Fig. 47.




Fig. 47A. Cantilever Truss. Stress-diagram

The character of the supporting forces and moments are taken about joint 7:

Moments of loads to the right of joint 7, the figures on the force-arrow diagram indicating thousands of pounds:

$$(8) + (5 \times 16) + (5 \times 24) + (12.5 \times 32) = 640 \text{ 000 ft-lb}$$

Moments of loads to the left of joint 7:

$$(2.5 \times 24) + (5 \times 16) + (5 \times 8) = 180 \text{ 000 ft-lb}$$

The moments act in opposite direction with reference to the center o. The smaller sum, is subtracted from the larger, leaving a resultant of  $640 \text{ 000 ft-lb} - 180 \text{ 000 ft-lb} = 460 \text{ 000 ft-lb}$ , tending to pull down on the right of  $R_2$  at joint 6 and to lift it up on the left. This must be resisted by the moment of the reaction  $R_1$ , which has an arm of 24 ft,  $19 \text{ 250 lb}$  results as the reaction requires a downward force of this magnitude to maintain the equilibrium. As the support at 6 must resist this downward pull as well as the pull  $R_1$ ,  $R_2$  will equal the sum of the loads plus the pull  $R_1$ , or  $45 \text{ 000 lb}$ .

+ 19 250 lb = 64 250 lb. Having obtained the value of the supporting force the stress-diagram is drawn by laying off on a vertical line  $oa$  downward, equal




Fig. 48. Cantilever Truss. Truss-diagram

to 19 250 lb equal to  $R_1$ . The next force is the load of 2 500 lb, which also acts down, and which locates the point  $b$ . From  $b$  a line parallel to  $BI$  is drawn and




Fig. 48A. Cantilever Truss. Stress-diagram

from  $o$  a line parallel to  $BI$  is drawn, locating the point  $i$ .  $bi$  is drawn from joint 1 and is toward  $o$ , showing that  $BI$  is in tension and  $IO$  in compression. The remainder of the stress diagram is drawn by the same methods employed for the stress diagrams of Figs. 46A and 47A. At joint 6 the force polygon is begun with the force  $R_2$  or  $o'o$ , which acts upward, and the upper end of which must be at  $o$ . Consequently  $o'$  is located by measuring downward from  $o$  64 250 lb. The sides of the stress-polygon for this joint are  $o'o$ ,  $om$ ,  $mn$  and  $no$ . After  $gh$ , the load at joint 14 is laid off, the remaining distance  $ho'$  should be just equal to the load at joint 14, 12 500 lb. If  $R_1$  and  $R_2$  have

been correctly computed and the stress-diagram accurately drawn, the points  $s$ ,  $u$  and  $w$  will fall in the line  $no'$ .

## 6. Determination of Wind-Load Stresses

**ads.** Thus far the stresses due to VERTICAL LOADS only have been the pressure of the WIND being combined with the DEAD LOAD and is acting vertically. For TRIANGULAR and FINK TRUSSES this is sufficiently accurate, as the wind-pressure never causes a maximum stress of that obtained by the method explained in connection with the examples. For TRUSSES WITH CURVED CHORDS and in fact for almost STEEL TRUSSES except those of the FINK and FAN TYPES, it is not under wind-pressure as acting vertically, because the wind acts generally at right-angles to the roof-surface, and upon but one side of the truss at any given time, thus loading the truss unsymmetrically and often causing stresses of an opposite kind from those produced by a vertical loading. For trusses which are inactive under a vertical load may therefore be necessary to consider the effect of the wind, or the total stress due to wind and vertical load may be greater than it would be if the wind-pressure were considered as a dead load. To design a roof-truss correctly, therefore, it is necessary to find the stresses due to VERTICAL LOADS and WIND-LOADS separately and combine them so as to get the GREATEST STRESS that may be produced under probable conditions. (See statement on page 1049.)

**Chords.** In the calculation of trusses with CURVED CHORDS it is the practice to find the stresses for the following different loadings and then to obtain the maximum stress: Stresses due to the wind on the truss nearer the expansion-end; stresses due to the wind on the truss nearer the fixed end; stresses due to the permanent dead loads; stresses due to snow covering the entire roof or only one-half of the roof; and, in addition, stresses due to snow covering only a small area of the roof on one side.


**Snow.** It is generally assumed that the maximum wind-pressure load can not act on the same half of the truss at the same time. For trusses with straight rafters it will generally be sufficient to find the stresses due to the permanent dead load, and to the wind from both directions, disregarding the effect of the wind when the pitch of the roof is  $45^\circ$  or greater. For the Northern Hemisphere, when the pitch is less than  $30^\circ$ , it is well to consider that a heavy sleet may be expected on both sides of the roof at the time of a heavy wind and to add about 10% of roof-surface to the dead load to allow for it. In localities where heavy snow may be expected, the stresses due to the full snow-load should be added as these combined with the permanent dead load may exceed the dead load, sleet and wind-pressure.

**Reactions.** These are affected by the manner in which the truss is supported. If both ends of the truss are fixed, the WIND-REACTIONS are parallel to the wind-load; if one end is free to move horizontally, that is, if the truss is supported on a ROCKER, the reaction at the roller-end is vertical and the reaction at the fixed end inclined. "If one end be fixed and the other merely supported on a smooth IRON PLATE, the reaction at the free end may have a horizontal component equal to the vertical component multiplied by the COEFFICIENT OF FRICTION, which is about one-third."

**Free Ends of Trusses.** Wooden trusses may be considered as having one end fixed and the other free to move; and when the span exceeds 40 feet they should be supported on ROLLERS to permit of expansion or contraction. For steel trusses supported by steel columns, as in steel mill-trusses, the trusses are RIGIDLY ATTACHED to the columns and no provision

is made for expansion. In such buildings the wind-pressure causes a BENDING STRESS in the columns, which must be provided for.

**Truss with Fixed Ends. Example 31.** Wind-pressure is usually assumed to be applied uniformly over one side of the roof and to act at right-angles to the surface of the roof. The joint-loads or panel-loads, therefore, are proportional to the roof-areas supported. When the joints divide the rafter into panels of equal length, the joint-loads are uniform, except for the joints at the edges of the truss. The actual wind-pressure is obtained by multiplying the roof-surface by the values given in Table IX, page 1053. For this example the triangular truss shown in outline by Fig. 49 is considered and it is assumed that the span and space of the truss are such as will give a load of 1 000 lb at joints 2 and 4. The loads at joints 1 and 5 are only one-half of those at 2 or 4. To find the support forces or reactions, draw a line representing the resultant of the loads, cutting the bottom chord at  $X$ . As the loads are symmetrical the resultant acts at the middle of the rafter and at right-angles to it. The reactions  $R_1$  and  $R_2$  are inversely proportional to the two segments into which a horizontal line joining the points of support is divided by the resultant, or in this case to  $X-7$  and  $1-7$ .



**Fig. 49. Triangular Truss. Truss-diagram**


**Fig. 49A. Triangular Truss**  
**Stress-diagram**

the greater reaction being at joint 1. The sum of the reactions are equal to sum of the loads. To find the reactions graphically, draw a line from joint at any angle, say from  $30^{\circ}$  to  $45^{\circ}$ , and measure off a distance equal to the load. In Fig. 49 the line 1-8 represents 3 000 lb. Join 7 and 8, and from draw a line parallel to 7-8, intersecting 1-8 at  $X'$ . Then 8- $X'$  is the reaction at joint 1 and  $X'$ -1 the reaction at joint 7. To draw the stress-diagram. Fig. 4 first draw the load-line  $ae$  equal to the sum of the loads, in this case 3 000 lb, perpendicular to the rafter 1-5, and divide it so that  $ao$  is equal to  $X'$ -8. Then at joint 1,  $oa$  is the supporting force,  $ab$  is 500 lb and  $bf$  and  $fo$  are drawn parallel respectively to  $BF$  and  $FO$ , intersecting at  $f$ . The external forces and stress act in the direction  $oa$ ,  $ab$ ,  $bf$  and  $fo$ , showing that  $BF$  is in compression and  $FO$  in tension. At joint 2 the stress-lines are  $fb$ ,  $bc$  equal to 1 000 lb,  $cg$  and  $gf$ . The stress-lines at joint 3 are  $of$ ,  $fg$ ,  $gh$  and  $ho$ ; at joint 4,  $hg$ ,  $gc$ ,  $cd$ ,  $di$  and  $ih$ ; at joint 5,  $id$ ,  $de$ ,  $ek$  and  $ki$ . If the load-line has been correctly divided at  $o$ , the stress-lines have been drawn exactly parallel to the lines of the truss, the lines  $bf$  and  $fo$  will fall vertically above the point  $i$ . At joint 6 the stress-lines are  $ok$ ,  $ki$ ,  $ih$  and  $ho$ . As the figure must close by a horizontal line through  $o$ , it is evident that



the truss-diagram cannot be represented, and therefore there can be this member when the wind is from the left. At joint 7 the reaction acting up, and  $ok$  and  $ks$  must close the figure, showing that the line  $s$  is the stress in the entire length of the right rafter, and that there is the bracing on that side of the truss when the wind is from the left. However, either the lower chord or the rafter is not straight, some of the struts at side come into action. By noting the character of the stresses it is seen that the different members of the truss have the same kind of stress as is produced by vertical loads. As the wind may blow from either side it is evident that both sides of the truss must be made alike. This illustrates the method of drawing the stress-diagram for any truss with fixed ends when both ends of the truss are fixed.

**Rollers.** Example 32. When one end of the truss is **FREE TO MOVE** at that end must always be practically vertical, and this causes a considerable variation of stress when the wind is on different sides of the roof; so that it is necessary to draw two wind-stress diagrams, one



Triangular Truss. Truss-diagram and Stress-diagram, Wind Left

THE LEFT, marked W.L., and one for WIND FROM THE RIGHT,

It is customary with authors when writing on this subject to have the **ROLLERS** are always under the right-hand support, and this is followed here. In practice the **ROLLERS** may be placed under either end of the truss are usually proportioned to the maximum stresses. We will take the same truss-diagram that was used in Fig. 49, again in Fig. 50, which is drawn to show WIND FROM THE LEFT. Draw a line 1-8 and divide it at  $X'$ , as in example 31. Draw a line  $ae$ , parallel to the rafter and equal to 1-8 in length, and divide it into two parts in the same proportions. Through  $x'$  on  $ae$  draw a horizontal line, and through  $e$  draw a vertical line, the two intersecting at  $o$ . Then  $eo$  represents the reaction at joint 7 and  $ao$  the reaction at joint 1. The stress-lines at joint 1:  $ab$  equal to 500 lb.,  $bf$  and  $fo$ . At joint 2:  $fb$ ,  $bc$ ,  $cg$  and  $gf$ . The stress-diagram W.L. is completed exactly as described for Fig. 49A, the line between the two being the location of point  $o$ , which gives the position in the bottom chord for the truss of Fig. 50. Fig. 51 represents the truss with WIND FROM THE RIGHT. To draw the stress-diagram W.R. draw a line perpendicular to the rafter and equal to the total load, 3000 lb., and divide it at  $x'$  into two segments of the same proportions as the segments

of the line 1-8, Fig. 50, the longer segment being at the top. To find the reactions draw a horizontal line through  $x'$  and a vertical line through  $t$ , the two lines intersecting at  $o$ . Then  $do$  is the reaction at joint 1, and  $ot$  the reaction at joint 10. For this diagram it is better to start with joint 10 and take the forces in the reverse order from that in which they were taken before. The stress-lines at joint 10 are  $ot$ ,  $ts$  equal to 500 lb,  $sn$  and  $no$ ; at joint 9,  $ns$ ,  $sr$ ,  $rm$  and  $ml$ ; at joint 8:  $on$ ,  $nm$ ,  $ml$  and  $lo$ ; at joint 7,  $lm$ ,  $mr$ ,  $re$ ,  $ek$  and  $kl$ ; and at joint




Fig. 51. Triangular Truss. Truss-diagram and Stress-diagram, Wind Right

$ke$ ,  $ed$ ,  $di$  and  $ik$ . If the diagrams have been correctly drawn the point  $i$  will fall vertically above the point  $k$ . On comparing the two diagrams for W. and W.R. it is seen that the stress-lines for the rafters and braces are of the same length and that the stresses are of the same character in both, but that the stress in the bottom chord is considerably less when the wind is from the right. This condition does not apply to all trusses, however, so that it is best to draw two stress-diagrams for wind from both directions.

**Queen Truss. Example 33.** Fig. 52 represents the outline of a QUEEN-TRUSS for a roof having a rise of  $14\frac{1}{2}$  in in 12 in. As the truss is of wood the supports are considered fixed. Joint 2 divides the rafter into two equal parts; consequently the wind-load at this joint is twice that at joint 1 or 4. For convenience it is assumed that the wind-load at joint 2 is 1 000 lb and at joints 1 and 4, 500 lb. The resultant is 2 000 lb acting through joint 2 and intersecting the tie-beam at  $X$ . To find the supporting forces, draw the line 1-8 equal to 2 000 lb and connect 7 and 8. From  $X$  draw a line parallel to 7-8 intersecting 1-8 at  $X'$ . Then 8- $X'$  is  $R_1$  or the supporting force at joint 1 and  $X'-1$  is the supporting force at joint 7. Begin the stress-diagram (Fig. 52A) by drawing the line  $ad$  at right-angles to the rafter 1-4, and equal in length to 1-8 or 2 000 lb. By means of dividers locate the point  $o$  so that  $oa$  equals 8- $X'$ . Then the stress-lines for joint 1 are  $oa$ ,  $ab$ ,  $bc$  and  $co$ ; at joint 2,  $eb$ ,  $bc$ ,  $cf$  and  $fe$ ; at joint 3,  $ef$ ,  $fh$  and  $ho$ ; and at joint 4,  $hf$ ,  $fc$ ,  $cd$ ,  $dk$  and  $kh$ . It is seen that the force-polygon at joint 4 will not close without the brace  $KH$ , because the initial point in drawing the polygon is at  $h$ , and a horizontal line through  $d$  does not

rough  $k$ . A QUEEN-ROD TRUSS, therefore, requires braces in the middle panel to resist the wind-stress. With the wind from the right, a brace is required from joint 3 to joint 6. At joint 5 the stress-lines are  $oh$ ,  $hk$ ,  $kl$  and  $lo$ . It should be noticed that  $lo$  acts towards the joint, showing that  $LO$  is in compression. At




Fig. 52. Queen Truss. Truss-diagram




Fig. 52A. Queen Truss. Stress-diagram, Wind Left

it would seem as though this could not be true, but if we glance at joint 7 we see that  $R_2$  is thrusting in on the joint, and that a strut is required to keep the joint in position. This condition is true only when the inclination of the rafter is greater than  $45^\circ$ . When the inclination of the rafter is exactly  $45^\circ$ ,





Fig. 53. Queen Truss. Truss-diagram. (See, also, Figs. 3, 12 and 54 and Chapter XXVIII, Fig. 1)


There is no stress in  $LO$ , and when the inclination is less than  $45^\circ$ ,  $LO$  is in tension. The stress-lines for joint 6 are  $lk$ ,  $kd$  and  $dl$ . If no errors are made, a line through  $d$  parallel to  $DL$  passes through the point  $l$ , previously obtained. A slight inaccuracy in locating the point  $X'$ , or in drawing the stress-diagram,

however, causes the line through  $d$  to pass to one side or the other of point  $l$  and if this happens, it shows that there has been some inaccuracy somewhere. In practice, a slight divergence does not materially affect the stress. At joint  $d$  the sides of the stress-polygon are  $ol$ ,  $ld$  and  $do = R_2$ , the lines being already drawn.

**Combination of Stresses. Example 34.** For the purpose of showing how the stresses due to wind and vertical loads are COMBINED, the truss-diagrams Figs. 53 and 54 are shown, being the same as in Fig. 12, and representing the



**Fig. 53A. Queen Truss. Stress-**  
**diagram**



**Fig. 54. Queen Truss. Truss-diagram. (See, Figs. 3, 12 and 53 and Chapter XXVIII, for details.)**

truss shown in Fig. 3. The stresses first determined are those due to the weight of the roof and ceiling and to an allowance of 10 lb per sq ft for sleet. On page 1055 the roof-area supported at joint 2 was found to be  $147\frac{1}{2}$  sq ft and at joint 3, 200 sq ft. On page 1055 the weight of the roof was estimated at 12 lb per sq ft, and allowing 10 lb for sleet, there results  $22\frac{3}{4}$  lb as the greatest load under a heavy wind. This gives 3 360 lb for the load at joint 2 and 4 500 lb for the load at joint 3. The ceiling-loads will, of course, be the same as in Fig. 53. Fig. 53 shows the loads due to weight of materials and sleet, as computed above, and the ceiling-loads. Fig. 53A is the stress-diagram for these loads, with stresses indicated by figures. This diagram is drawn exactly in the same manner as the stress-diagram in Fig. 12, page 1071.

**Wind-Stresses.** The inclination of the roof is very close to  $45^\circ$ , and from Table IX, page 1053, the normal wind-pressure for that angle is found to be 28 lb. Multiplying the roof-area at joints 2 and 3 by 28, the wind-loads indicated in Fig. 54 are obtained. The wind-load at joint 1, also, must be found. The roof is supported at this joint, allowing 17 in for eave-projection (Fig. 3) is  $6\frac{1}{2}$  by 10 or 95 sq ft, which makes the wind-load 2 660 lb. The next step is to find the point at which the resultant of these loads cuts the rafter. As the load is not symmetrical or uniform on the rafter, the point through which the resultant acts must be determined by means of moments about joint 1. The arms of the loads at joints 2 and 4 are figured on the truss-diagram (Fig. 54). The moments are

$$4140 \text{ lb} \times 9\frac{5}{8} \text{ ft} = 38985 \text{ ft-lb}$$

$$5\,600\text{ lb} \times 18\frac{1}{4}\text{ ft} = 102\,200\text{ ft-lb}$$

**The sum of the moments = 141 185 ft-lb**

ted and should be arranged as in the following table. In wind-stresses, it should be remembered that the wind may blow on either side of the truss, and the greatest stress liable to occur should be

	Dead weights and sleet (Fig. 53A)	Wind-stresses (Fig. 54)	Totals	Stresses (Fig. 12)
.	+16 150	+5 100	+21 250	+25 600
.	+13 800	+5 100	+18 900	+21 300
.	+ 9 600	+3 600	+13 200	+14 700
.	+ 2 350	+4 100	+ 6 450	+ 4 400
.	0	+5 100	+ 5 100	0
.	- 5 400	-3 700	- 9 100	- 6 900
.	-11 200	-5 950	-17 150	-17 600
.	- 9 600	-3 150	-12 750	-14 700

rs are lettered as in Fig. 54. Thus the stress in the rafter  $F'B'$  is the stress in the rafter on the other side, and this stress acts through the center of the rafter; hence the stress for  $AE$  and  $BF$  should be entered in the stress in  $F'B'$ . In the same way the stress in the rod  $H'F'$  is

greater than in  $FH$ ; hence the stress in  $H'F'$  should be tabulated. The stress in  $OE'$  slightly reduces the tension due to the dead load, but as the stress in  $E$  increases it, the stresses in  $EQ$  and  $HP$  should be tabulated. Both sides of the truss should of course be made alike, and two braces should be inserted in the middle panel. In the fifth column of the table are given the stresses due to the ceiling-load and a vertical load on the roof of  $42\frac{3}{4}$  lb per sq ft, as obtained from the stress-diagram, Fig. 12. Comparing the stresses in the fourth and fifth columns, it is seen that except for the brace  $EF$ , and for the two rods, the stresses obtained by combining snow and wind and adding to the dead weight are greater than the totals due to wind, dead weight and sleet. Vertical loads, of course, cause no stresses in the braces of the middle panel, and unless the wind-stresses are drawn, it is necessary to estimate the sizes of these braces. The stresses in these braces, however, are so small that large pieces of timber are not required. The stresses given in the fourth column are unquestionably nearer what the real stresses are likely to be than those in the fifth column. If the roof is erected in a warm climate where there is no sleet, these stresses may be further reduced by omitting the 10 lb per sq ft added for sleet. If, on the other hand, the inclination of the roof is less than  $30^\circ$ , the stresses produced by a heavy fall of snow without wind generally exceed the sum of those due to dead weight, sleet and wind; and for such roofs the stresses due to the maximum snow-load should always be computed.

**Reactions.** The reactions, or supporting forces of the truss shown in Fig. 1 are very much inclined from the vertical. As the dead load, however, is always acting on the truss, the inclination of the real reaction is never so great, but is more nearly vertical; and when there is no wind the reactions are exactly vertical. The theoretical reaction, due to both wind-load and dead load, is the diagonal of a parallelogram, the two adjacent sides of which are the reactions for the dead load and wind-load drawn to the same scale. Thus if  $a-7$ , Fig. 1 represents the reaction due to the wind and  $b-7$  the vertical reaction, due to the dead load and drawn to the same scale, then  $R'$  is the resultant reaction, modified somewhat, however, by friction. Examples 31, 32 and 33 serve to show the general method of drawing WIND STRESS-DIAGRAMS, and are sufficient to enable the student to draw those diagrams for most trusses with straight rafters. For trusses with curved rafters the diagrams become more complicated, and the reader is referred to Graphical Analysis of Roof Trusses, by Charles E. Greiner, and to other standard handbooks on the subject.

## 7. Trusses with Knee-Braces

**Knee-Braces** are generally used to give greater stability to the structure as a whole when roof-trusses are supported by COLUMNS. Under the action of vertical loads the stresses in these members are usually assumed as zero, which would be true if the materials composing the TRUSS, KNEE-BRACES and COLUMNS were rigid. This discussion will deal, however, with the effect of wind blowing against one side of the building and roof. The ACTUAL STRESSES in the knee-braces, columns and truss-members will probably never be known exactly, for there are so many VARIABLE FACTORS entering into the problem. In the usual construction, in which columns are bolted to masonry pedestals at the bottom, either riveted or bolted to the trusses at the top, and in which the knee-braces are riveted at both ends, the degree to which these connections may be considered FIXED is a question leading to many arguments and differences of opinion. This will not be discussed at all; but it will be shown how the stresses in all members of the framework can be found under given assumptions. Assume, for example, that the bottoms of the columns are sufficiently FIXED, so that a point of

midway between the bottom of the knee-brace and the masonry (equivalent to assuming a PIN at this point), and so that the top attachments of the knee-braces may be considered as PIN-CONNECTIONS. The truss and loading shown in Fig. 55, it is clear that the outside forces are in equilibrium, and, unless the points  $M$  and  $N$  are unlike in some




Fig. 55. Truss with Knee-braces. Truss-diagram

reactions at these points will be parallel to the direction of the wind-forces. Lay off to any convenient scale the wind-forces shown in Fig. 55A. Then  $XY$  is the direction and magnitude of the wind-pressure and also the direction of  $R_1$  and  $R_2$ . The magnitudes are found by means of the equilibrium polygon explained on page 1097.

Lay off  $SX$  and  $R_2$  to  $YS$ . These are correct in direction and magnitude. Some condition is imposed to

If there are no moments at these points are RESTRAINED vertically, the vertical components of  $R_1$  and  $R_2$  must remain constant, extreme case where  $M$  may be a PIN-CONNECTION and  $N$  as a ROLLER. Any assumption may be made for the magnitudes of the horizontal reactions at these points as long as the sum of the horizontal components of  $R_1$  and  $R_2$  equals the sum of the horizontal components of the wind forces. It is assumed these as equal. In




Fig. 55A. Truss with Knee-braces. Force-polygon

reactions at  $M$  and  $N$  are  $TX$  and  $YT$ , respectively. The next step is to find the effect of these reactions at the points  $O$ ,  $Q$ ,  $P$  and  $R$ . The vertical components  $V_1$  and  $V_2$  act as vertical forces at  $O$  and  $P$ . The horizontal components  $H_1$  and  $H_2$  act as horizontal forces at  $O$  and  $P$ , and, in effect, horizontal forces at  $R$ . Taking the left column, the 8100 lb acting towards the left column to the left if not prevented by the joints at  $O$  and  $Q$ .

If the member  $MQ$  is considered to act as a lever with a fulcrum at  $O$ , a horizontal force of 8 100 lb acting towards the left at  $M$  will produce a pressure, or force acting from left to right at  $Q$  which equals, by the method of moments, the center of moments being at  $O$ ,  $8\ 100\text{ lb} \times 7.5\text{ ft} + 5\text{ ft} = 12\ 150\text{ lb}$ . At  $O$ , in like manner, taking the center of moments at  $Q$ ,  $8\ 100\text{ lb} \times 12.5\text{ ft} + 5\text{ ft} = 20\ 250$ .




Fig. 56. Truss with Knee-braces. Truss-diagram




Fig. 57. Truss with Knee-braces. Stress-diagram

is produced, acting from right to left. These forces are shown in Fig. 56. When combined with those shown in Fig. 55 they give the forces acting at  $O$ ,  $Q$ , and  $P$  which are used in constructing the stress-diagram shown in Fig. 57.

## 8. Arched Trusses

**An Arched Truss** is one which has the FORM OF AN ARCH and which is supported at the ends that the reactions produced by vertical forces are vertical. This is usually accomplished by placing PIN-CONNECTIONS at the supports and providing ROLLERS at one end to permit horizontal movement.

**Stresses in an Arched Truss.** The determination of the stresses in members of an ARCHED TRUSS is readily accomplished by following the method given in the previous examples.

**Arched Truss with Roller-Support.** Example 35. In Fig. 58 is shown the left half of an ARCHED TRUSS and the ROLLER-SUPPORT. This truss has the shape and dimensions of a truss in the Live Stock Pavilion, Union Stock-Yard.



and Transit Company, Chicago, Ill. It is discussed in the Engineering News of June 28, 1906. The loading shown is symmetrical about the middle of the span and hence each reaction equals one-half the total load. Fig. 58A shows



$$R_1 = 196\ 000$$

Fig. 58. Live Stock Pavilion, Chicago, Ill. Truss-diagram




Fig. 58A. Live Stock Pavilion, Chicago, Ill. Stress-diagram for Truss

stress-diagram for one-half of the truss. The stresses upon the right of the truss are the same as those upon the left.

The HORIZONTAL DEFLECTION of this truss is measured by the movement of the roller-end. This movement is computed in the manner explained for the truss, pages 1085-7, by the formula  $D = \Sigma(Sml + AE)$ . Where  $D$  is the

**HORIZONTAL MOVEMENT.**  $S$  the stress in any member as given by the stress-diagram shown in Fig. 58A,  $u$  the stress in any member produced by the unit load applied at the roller end of the truss and acting in a horizontal direction (Fig. 58B),  $l$  the length of any member,  $A$  the area of any member,  $E$  Young's modulus of elasticity for the material composing any member and  $\Sigma$  the sign of summation and when limits are not designated, the formula indicates that  $\Sigma(Sul + AE)$  is to be taken for each member of the truss. For the loads and areas indicated

Fig. 58, the rollers will move about 10 in. when  $E$  is 30 000 000 lb per sq in. In order that a given span may obtain under a given load each tension-member must be constructed shorter than its geometrical length by an amount which it is lengthened by the stress which it resists, and each compression-member must be lengthened in a like manner. Any other loading will produce a change in the length of the span. To reduce the **HORIZONTAL DEFLECTION** without changing the lengths

Fig. 58B. Live Stock Pavilion, Chicago, Ill. Stress-diagram

of the members they would have to be made excessively heavy. A truss of the form shown in Fig. 58 is not economical as an **ARCHED TRUSS** on rollers but may be satisfactorily used by connecting the two end-pins by a **TIE-ROD**.

**Arched Truss with Tie-Rod.** When a **TIE-ROD** is employed the members become much lighter and can be built according to their geometrical lengths. The stress in the **TIE-ROD** may be found from the formula


$$S_t = \sum \frac{Sul}{AE} + \left\{ \sum \frac{u^2 l}{AE} + \frac{l'}{A'E'} \right\}$$

in which  $S_t$  is the stress in the tie-rod,  $A'$  the area of the tie-rod,  $l'$  the length of the tie-rod and  $E'$  Young's modulus of elasticity for the material composing the tie-rod. The other symbols have the significance given above for the expression for  $D$ . Since the stress and area of the tie-rod appear in the above equation it is necessary to assume an area and then compute the value of  $S_t$ . If this produces a unit stress in the tie-rod differing greatly from the allowable value, a new trial must be made. Having found the stress in the tie-rod, the resulting stresses in the truss-members can be found graphically from a stress diagram which will be of the form shown in Fig. 58B, which was constructed with a horizontal force of 1 000 lb. The stresses can be found, also, by multiplying the stresses produced by one pound by the value of  $S_t$ . The stresses produced by  $S_t$  combined algebraically with those obtained from Fig. 58A give the final stresses. These stresses differ but little from those which obtain for a **TWO-HINGED ARCH** of the form shown in Fig. 58, and such structures with the **TIE-ROD** are often classed as **TWO-HINGED ARCHES**.

**Assumption of Areas.** Since the **DEFLECTION** of the truss shown in Fig. 58 depends upon the **AREAS** of the members, it is evident that they must be either known or assumed before the formulas for  $D$  or  $S_t$  can be applied. For a given structure the **AREAS** are of course unknown and the problem of determining stresses becomes one which is sometimes classed as **CUT-AND-TRY**. For the first trial, the areas may be assumed as unity and the corresponding value of  $D$  found and then the combined stresses. The members may now be designed to area and a new trial made with these areas. Usually the second trial is sufficient, as a slight change in areas does not materially affect the value of  $S_t$ .

## 9. Trussed Arches

**Symmetrical Trussed Arches.** The THREE-HINGED ARCH is the simplest form of TRUSSED ARCH, and, as used in buildings, it is usually symmetrical in form, consisting of two trusses connected by a pin over the middle of the span and resting on a pin at each support. The stresses in the truss-members are found by the ordinary graphical methods after the reactions have been determined.



**Fig. 59. Three-hinged Arch. Truss-diagram**  
**Fig. 59A. Stress-diagram**

The SUPPORTING FORCES are inclined and may be resolved into two components, one vertical and the other horizontal. For symmetrical loading the two reactions are equal in magnitude. The vertical components are each equal to one-half the vertical loading. The horizontal components are equal in magnitude and opposite in character. The following examples illustrate the methods to be followed in the determination of the stresses.

**Trussed Three-hinged Arch. Example 36.** Fig. 59 shows one-half of **TRUSSED THREE-HINGED ARCH** with a vertical load of 1 000 lb per top-chord joint. Fig. 59A shows the stress-diagram for this loading; but before it can be drawn, the vertical and horizontal reactions at the left support must be determined. The vertical reaction is  $(7 \times 1\,000) + 500 = 7\,500$  lb or one-half the vertical load. The horizontal component or the **HORIZONTAL THRUST** of the arch may be found by moments. The center of moments will be taken at the middle

a

c

e

t

Fig. 60. Liberal Arts Building, Chicago, Ill. Truss-diagram

Fig. 60A. Stress-diagram

pin at the crown as at this point the moment is zero. The equation of moments is  $H_1 \times 72.5 + 1\,000 (5.25 + 16.25 + 27.25 + 38.25 + 49.25 + 60.25 + 71.25)$

$$+ 500 \times 82.25 - 7\,500 \times 78.75 = 0,$$

or


$$H_1 = 281\,750 \div 72.5 = 3\,886 \text{ lb}$$

Having determined  $V_1$  and  $H_1$ , the stress-diagram shown in Fig. 59A can readily be constructed. Since the arch is symmetrical, it is necessary to draw only one-half the stress-diagram. If the right half of the arch is removed and in place a horizontal force applied at the middle pin, the magnitude of this force

3. HORIZONTAL THRUST  $H_L$ , since, for equilibrium, the algebraic sum of horizontal forces is zero.

**Three-hinged Arch.** Example 37. Fig. 60 represents one-half of THREE-RINGED ARCH used in the Liberal Arts Building of the Columbian, Chicago, Ill., 1893. (See Engineering Record, July 9, 1892.) the stress-diagram for the loading shown in Fig. 60.

**tion of Stresses.** In Examples 35 and 36 only the effect of vertical  
 cen considered. Where THREE-HINGED ARCHES are employed they  
 signed to carry dead, snow and wind-loads. The dead and snow-



100% Fine

11

51. 5th Regiment Armory, Baltimore, Md. Truss-diagram  
Fig. 61A. Stress-diagram

of loads but the snow-load is not symmetrical in all cases. The usually considered as acting normal to the roof. In order to be maximum stresses are obtained, the stresses for the following configurations must be found and combined

**AD LOAD only.**

**DW-LOAD** covering left half of roof.

3W-LOAD covering right half of roof.

ND-LOAD acting normal to roof on left of center.

ND-LOAD acting normal to roof on right of center.

Fig. 61a. 5th Regiment Armory, Baltimore, Md. Stress-diagram

Fig. 61c. 5th Regiment Armory, Baltimore, Md. Stress-diagram




Fig. 61d. 5th Regiment Armory, Baltimore, Md. Truss-diagram

esses for the above conditions of loading are to be found for one-half h. In combining the stresses those which occur at the same time are d in determining maximums. Many engineers do not consider snow loads acting on the same portion of the roof simultaneously.

**d Three-hinged Arch. Example 38.** Fig. 61 shows one-half of a THREE-HINGED ARCH with the dead, snow and wind-loads indicated at the upper-chord joints. This form of truss supports the roof of the 5th Regiment Armory, Baltimore, Md., described in the Engineering Record, 1904. The stresses for the loadings specified above will be determined; it will be shown how these are to be combined.

**Reactions and Stresses.** The reactions are obtained by the method used in Example 5.  $V_1$  is 77 900 lb and  $H_1$  32 000 lb. Fig. 61A is the stress-diagram with the numbers shown in Fig. 61.

**Left Half of Span.** Assuming that the snow covers the portion of the span shown in Fig. 61 and taking the center of moments at the middle pin, by moments that  $V_1$  is equal to 26 700 lb and  $H_1$  is equal to 15 000 lb. At the support the stress-diagram shown in Fig. 61B is readily drawn.

**Right Half of Span.** With the snow on the right of the crown, the left half of the span shown in Fig. 61 is unloaded. The total snow-load is 12 000 lb and it has just been found that the vertical reaction at the support on the left under the loading is 26 700 lb; hence the vertical reaction at the other support is 12 000 less 26 700 lb or 14 500 lb or  $V_1$  for the case considered. Since the moment at the middle pin is zero,  $V_1$  (half the span) less  $H_1$  (rise of the arch) or  $14 500 \times 95.16 - H_1 \times 92.0 = 0$ ; and  $H_1 = (14 500 \times 95.16) \div 92 = 15 000$  lb which is the  $H_1$  found above. As before, beginning at the left support, the stress-diagram is constructed as shown in Fig. 61C.

**Stresses on Entire Span.** The algebraic sums of the stresses found from the two cases above for each member will give the stresses produced by a loading covering the entire span.

**Reaction on Left of Crown.** Here no two of the wind-loads are parallel. This condition increases the complexity of finding the reactions. These may be combined into one resultant, but a graphical method is more convenient. The direction and magnitude of the resultant of the wind-forces are first found. As shown in Fig. 61E, the wind-loads are laid off in order. Then 3-13 is the direction and magnitude of the resultant.

Next, from any point  $O$  draw the strings of the truss and construct the equilibrium polygon shown in Fig. 61D, beginning with string  $S_1$  from  $A$ , and so on until string  $S_{11}$  cuts the line  $BC$  through the middle pin and the pin at the right support. This is the line of action of the reaction at the right support. In Fig. 61E, from 13 draw a line parallel to 3-13 and from  $O$  a line parallel to  $S_0$  in Fig. 61D, and prolong them until they intersect. Then 1-3 is the reaction at  $A$  and 13-1 that at the right support. These reactions are then resolved into vertical and horizontal components,  $V_1$  equals 23 400 lb,  $H_1$  equals 18 600 lb,  $V_2$  equals 18 000 lb and  $H_2$  equals 18 600 lb. Fig. 61F shows the stress-diagram from the left support up to the crown.

**Reaction on Right of Crown.** Since the reaction at  $A$ , Fig. 61D, produced by the wind-loads must pass through the hinges, or pins  $A$  and  $C$ , the stress-diagram




Fig. 61E. 5th Regiment Armory, Baltimore, Md. Force polygon

will be exactly similar in shape to that shown in Fig. 61c; but the values of  $H_1$  and  $H_2$  will be 18 000 lb and 18 600 lb respectively. The stresses will bear direct proportion to the stresses found from Fig. 61c, and hence a new diagram is not necessary.

20 21

Fig. 61f. 5th Regiment Armory, Baltimore, Md. Stress-diagram

**Combination of Stresses.** The maximum stresses may now be determined. To illustrate the method, consider the lower chord 1-37.

	lb
(a) DEAD-LOAD stress,	+ 22 100
(b) SNOW on left of crown,	- 14 300
(c) SNOW on right of crown,	+ 37 800
(d) WIND-LOAD on left of crown,	- 31 600
(e) WIND-LOAD on right of crown,	+ 46 900
(f) SNOW over all,	+ 23 500
Total stress without wind,	+ 59 900
(a) + (c),	+ 69 000
(a) + (d),	- 9 500

The maximum stresses are 69 000 lb compression and 9 500 lb tension, assuming that the wind and snow-loads are not considered to act on the same side of the crown. If no such restriction is made, the maximum stresses are 106 800 lb compression and 23 800 lb tension. In a like manner the maximum stress in each member of the truss is determined. Tables XIX and XX give the MAXIMUM STRESS for the members shown in Fig. 61.

**Stress-Diagrams for Three-hinged Arches.** The STRESS-DIAGRAMS in the above cases are very difficult to construct owing to the great number of  $H$ 's and the difficulty in drawing them exactly parallel to the lines of the truss diagram. One or more members should be computed as a check on the graphical work.

**Three-hinged Arch with Tie-Rod.** The introduction of a TIE-ROD connecting the end-pins of a THREE-HINGED ARCH and placing ROLLERS under one end



changes the ARCH into a SIMPLE TRUSS composed of three members, rafters and a horizontal tie. Under vertical loading, the supports are vertical, but for wind-loads the supporting force at the end with is inclined. The stresses in the truss-members are the same as found in the THREE-HINGED ARCH. The stress in the tie-rod equals the horizontal thrust found above at the roller-end for the given loading. The support at the roller-end is designed for vertical forces only, while the support at the other end must resist the vertical reaction and the total horizontal component of the wind load on the structure, or for roofs the horizontal component of the wind load is very much smaller than the horizontal force which must be resisted in the structure is without a tie-rod or a true THREE-HINGED ARCH.

Table XIX. Three-hinged Arch. Chord-Stresses

Thousand pounds

Dead load, Fig. 61A	Snow on left of crown, Fig. 61B	Snow on right of crown, Fig. 61C	Snow over all the roof	Wind on left of crown, Fig. 61F	Wind on right of crown,* Fig. 61C	Max. stresses	
						Tension	Compression
25.2	+ 6.1	- 2.1	+ 4.0	+25.6	- 2.6	....	50.8
6.3	- 7.0	-14.0	- 21.0	+32.8	-17.4	30.7	26.5
18.7	-13.2	-21.4	- 34.6	+42.6	-26.5	58.4	23.9
19.0	-13.9	-22.8	- 36.7	+45.8	-28.3	61.2	26.8
22.4	-15.5	-28.0	- 43.5	+58.7	-34.7	72.6	36.3
26.8	-15.8	-35.1	- 50.9	+73.8	-43.5	86.1	47.0
26.6	-11.2	-41.0	- 42.2	+85.3	-50.8	88.6	58.7
22.0	- 3.9	-44.6	- 48.5	+90.7	-55.3	81.2	68.7
13.3	+ 7.8	-44.8	- 37.0	+89.6	-55.6	68.9	76.3
3.7	+20.2	-41.7	- 21.5	+81.9	-51.7	55.4	78.2
6.4	+30.0	-33.5	- 3.5	+67.2	-41.5	35.1	73.6
14.3	+30.0	-20.6	+ 9.4	+47.2	-25.5	11.2	61.5
18.7	+19.3	- 2.8	+ 16.5	+23.3	- 3.5	....	42.0
21.8	+22.6	- 3.3	+ 19.3	+27.8	- 4.1	....	49.6
18.8	- 5.4	+21.9	+ 16.5	- 6.7	+27.2	....	46.0
22.1	-14.3	+37.8	+ 23.5	-31.6	+46.9	9.5	69.0
33.3	-11.3	+51.9	+ 40.6	-53.2	+66.0	19.9	99.3
47.7	+ 2.1	+61.0	+ 63.1	-69.5	+75.6	21.8	125.4
63.0	+18.1	+64.8	+ 82.9	-78.3	+80.4	15.3	161.5
18.4	+31.5	+65.1	+ 96.6	-80.1	+80.7	61.7	130.6
90.3	+41.1	+61.8	+102.9	-75.0	+76.6	....	208.0
98.7	+45.7	+55.8	+101.5	-62.8	+69.2	....	213.6
02.6	+46.0	+48.5	+ 94.5	-46.3	+60.1	....	208.7
01.8	+42.9	+40.0	+ 82.9	-26.0	+49.6	....	194.3
02.3	+42.3	+37.9	+ 80.2	-20.3	+47.0	....	191.6
86.7	+34.8	+29.3	+ 67.7	- 9.6	+36.3	....	157.8
59.5	+22.4	+16.2	+ 38.6	+ 3.9	+20.1	....	102.0
77.4	+29.2	+21.0	+ 50.2	+ 5.2	+26.0	....	132.6

\* By proportion, 18 600 : 15 000.

**and no Rollers.** If the ROLLERS are omitted and a TIE-ROD is used, the tie-rod and the reactions are indeterminate. They depend upon rigidities of the tie-rod and the material composing the supports. The tie-rod is made very heavy so that its stretch will be very small when

stressed, the stresses in all members of the structure may be taken the same found for the condition where rollers are used, and the horizontal component the wind-load equally divided between the supports.

**Table XX. Three-hinged Arch. Web-Stresses**  
Thousand pounds

Member, Fig. 61	Dead load, Fig. 61a	Snow on left of crown, Fig. 61b	Snow on right of crown, Fig. 61c	Snow over all the roof	Wind on left of crown, Fig. 61f	Wind on right of crown,* Fig. 61c	Max. stresses	
							Ten- sion	Com- pressi- on
39-38	- 4.9	- 3.8	+ 2.1	- 1.7	-13.7	+ 2.6	16.5	....
36-37	+10.4	+ 0.3	+14.5	+14.8	-18.5	+18.0	8.1	28.7
34-35	+14.5	+ 8.3	+13.0	+21.3	-18.6	+16.1	4.1	38.9
32-33	+17.8	+12.7	+10.6	+23.3	-15.4	+13.1	....	43.6
30-31	+19.7	+13.8	+ 7.6	+21.4	-10.7	+ 9.4	....	42.9
28-29	+20.3	+12.3	+ 4.7	+17.0	- 4.9	+ 5.8	....	38.4
26-27	+18.7	+ 9.3	+ 1.2	+10.5	+ 3.4	+ 1.5	....	29.5
24-25	+15.3	+ 5.4	- 1.8	+ 3.6	+10.8	- 2.2	....	26.1
22-23	+10.2	+ 1.5	- 5.1	- 3.6	+19.0	- 6.3	....	29.2
20-21	+ 9.9	+ 3.5	+ 2.0	+ 5.5	+ 2.4	+ 2.5	....	15.9
18-19	- 0.7	- 9.3	- 2.7	-12.0	+ 6.6	- 3.3	13.3	5.9
16-17	-13.6	- 6.8	- 8.1	-14.9	+10.9	-10.0	30.4	....
14-15	-42.3	-15.9	-11.4	-27.3	+ 2.8	-14.1	72.3	....
37-38	- 7.1	+11.2	-22.0	-10.8	+29.8	-27.3	23.2	22.7
35-36	-12.9	- 3.5	-16.3	-19.8	+24.9	-20.2	36.6	12.0
33-34	-16.8	-15.8	-10.4	-26.2	+18.8	-12.9	45.5	2.0
31-32	-17.9	-19.2	- 4.2	-23.4	+10.0	- 5.2	42.3	....
29-30	-17.9	-17.0	+ 0.6	-16.4	+ 1.4	+ 0.7	34.9	....
27-28	-14.1	-11.6	+ 5.0	- 6.6	- 7.4	+ 6.2	25.7	....
25-26	- 9.4	- 5.3	+ 8.7	+ 3.4	-17.0	+10.8	26.4	1.4
23-24	- 4.7	+ 0.4	+11.0	+11.4	-23.3	+13.6	28.0	9.3
21-22	+ 3.0	+ 5.2	+13.1	+18.3	-29.5	+16.2	26.5	24.4
19-20	+ 0.8	+ 1.6	+ 3.1	+ 4.7	- 7.4	+ 3.8	6.6	6.2
17-18	+18.5	+ 9.2	+10.9	+20.1	-14.8	+13.5	....	41.2
15-16	+36.3	+16.8	+17.8	+34.6	-19.1	+22.1	....	75.2

\* By proportion, 18 600 : 15 000.

**Changes in Temperature** do not seriously affect the stresses in the members of a TRUE THREE-HINGED ARCH, or one with a tie-rod and rollers at one end, as the change in geometrical shape is quite small. For the arch with a tie-rod and no rollers, the effect of changes in temperature may affect the support forces if the tie-rod is not so protected that it will change but little from average temperature. In most structures this is the case as the tie-rod is in under the floor of the building.

**The Two-hinged Arch** differs essentially in construction from the THREE-HINGED ARCH in having only two pins or hinges which are placed at the supports. Fig. 62 shows the form of truss which will be used in explaining the method of finding the stresses in the members of the truss.

**Supporting Forces.** The SUPPORTING FORCES are inclined but can be resolved into vertical and horizontal components. The vertical components are readily found as they are the same as for a simple truss on two supports. The horizontal components depend upon the AREAS of the members and their MODULI OF ELASTICITY when the dimensions of the truss and the loading are known.

tal Thrust for Vertical Loads. This can be found from the formula

$$H_1 = \sum \frac{Sul}{AE} + \sum \frac{u^2 l}{AE}$$

symbols have the significance given on page 1086. But this contains an area  $A$  for each piece. For a preliminary trial the procedure is as the truss shown in Fig. 62, divide the span into twenty equal parts and at the centers of the divisions erect verticals. Through the points on these verticals midway between the chords of the truss, draw a smooth curve as shown. This will be designated the **AXIS OF THE ARCH**. Number the points design-




Fig. 62. Two-hinged Arch. Truss-diagram

as 1, 2, 3, etc., as shown in Fig. 62, and let  $x$  and  $y$  be their coördinates, taking the left support as the origin. Scale the length of the curve between the divisions so that  $y$  is practically the ordinate of the center of gravity of the curve, and call this length of the curve  $\delta s$ . On a radial line numbered 1, 2, 3, etc., scale the distances between the upper and lower chords, calling the distance  $h$  and compute  $\frac{1}{2} h^2 = I$ , which expresses, the **MOMENT OF INERTIA** of the section when the chord-areas and the web-members are neglected. Let  $M$  represent the **BENDING MOMENT** at a point having the abscissa  $x$ , of the loads, considering the truss as supported on two supports; or, for a single load  $P$ ,  $M = Rx - P(x - a)$ , where  $a$  is the distance of the load  $P$  from the left support. Then  $\delta s + EI$  is represented by  $\phi$  the **HORIZONTAL THRUST** can be found from the formula,

$$H_1 = \sum My\phi + \sum y^2\phi$$

For the vertical loading shown in Fig. 62, the value of  $H_1$  is 108 000 lb, and being one-half the total load, is 195 000 lb. The stresses in the members of the truss can now be found by the usual graphical method. The snow-load, if any, must be treated in a like manner. The computations are considerably short since  $\Sigma y^2\phi$  remains unchanged, regardless of the loading.

**Wind-Loads.** For WIND-LOADS the process is not changed very much. The value of  $M$  is the moment of the wind-loads, assuming the truss as HINGED at the right support and on ROLLERS at the left support. The value of  $V_1$ , which is vertical, is found by taking the sum of the moments of the wind-loads at the hinge at the right support and dividing this by the length of the span. The value of  $H_1$  is found from the formula given above, and then the stresses are found by the ordinary stress-diagram. The MAXIMUM STRESSES are now found and the proper AREAS of the members determined.

**The True Horizontal Thrust.** The method just given is a close approximation to determine the AREAS of the pieces so that the correct formula for the true horizontal thrust can be applied. This formula is

$$H_1 = \sum \frac{Sul}{AE} + \sum \frac{u^2 l}{AE}$$

where the symbols have the meaning already given. Applying this formula for the dead load shown in Fig. 62 and AREAS shown in Fig. 58, the value of  $H_1$  is 110 600 lb, which is but a little different from the value found by the approximate method.




Fig. 62A. Two-hinged Arch. Stress-diagram

**Dead-Load Stresses.** The stress-diagram for the DEAD LOAD is shown in Fig. 62A. Considerable care must be exercised in drawing the stress diagrams, and their correctness should be checked by computing the stresses in one or more pieces. Compare Fig. 62A with Fig. 58A.

### Changes in Temperature


Unlike the THREE-HINGED ARCH, the TWO-HINGED ARCH is affected by CHANGES IN TEMPERATURE and the stresses which are produced by such changes must be provided for.  $V_1 = 0$  and  $H_1$  is determined from the formula

$$H_1 = e t^\circ L + \sum \frac{u^2 l}{AE}$$

where  $e$  is the COEFFICIENT OF EXPANSION for the material composing the truss,  $t^\circ$  the number of degrees CHANGE IN TEMPERATURE and  $L$  the SPAN of the truss. The other symbols have the significance already given. The above formula assumes that the truss-members are of the same kind of material. After  $H_1$  has been found, the stresses can be determined by constructing the stress-diagram which will be of the shape shown in Fig. 58B.

**Tie-Rod.** If a TIE-ROD connects the two supports of a TWO-HINGED ARCH, the remarks made concerning such an arrangement for the THREE-HINGED ARCH apply here.

ted Arch has no hinges and is a type which is seldom employed by in the truss-form. The rigid analysis of a TRUSSED FIXED ARCH is and tedious, so a few formulas will be given, necessary for the solution WITH SOLID WEBS, such as PLATE-GIRDER ARCHES. These formulas plied to truss-forms, where the chords are approximately parallel, rious error. Midway between the top and bottom chords draw a ve, called the ARCH-AXIS, and designate the distance between its ends : SPAN OF THE AXIS. Divide the span into  $n$  equal parts and at the these divisions draw perpendiculars until they cut the arch-axis.



**Fig. 63. Fixed Arch. Truss-diagram**

points 1, 2, 3, etc., as shown by Fig. 63, which also indicates the  $\epsilon$  employed.

tion of  $H_1$ ,  $V_1$  and  $H_{1/4}$ . The equilibrium-polygon for a single is shown in Fig. 63, in its true position with reference to the arch indicates the point of application of  $H_1$ . The following formulas are approximations for arches having a rise greater than one-eighth the

$$H_1 = \Sigma m_{ij} A'' \div \Sigma j A''$$

$$A'' = K \left\{ y - \frac{\Sigma yK}{\Sigma K} \right\} \quad K = \frac{\delta s}{EI}$$

$$\left. \begin{matrix} H_1 y_1 \\ H_2 y_2 \end{matrix} \right\} = H_1 \frac{\Sigma y K}{\Sigma K} - \left\{ \frac{\Sigma m_{xy} K}{\Sigma K} \pm \frac{\Sigma m_{xy} K (z - n)}{n^2 \Sigma K - \Sigma z^2 K} n \right\}$$

$$V_1 = \frac{H_1 y_2 - H_2 y_1}{L} + r_1 \quad y_1 = \frac{H_1 y_1}{H_1}$$

down from  $A$  when  $H_1 y_1$  is negative.  $\Sigma$  is the sum of quantities for each point on the arch-axis numbered 1, 2, 3, . . .  $n$ . For

$$\Sigma K = \left( \frac{\delta s}{EI} \right) + \left( \frac{\delta s}{EI} \right) + \left( \frac{\delta s}{EI} \right) + \text{etc.}$$

$I$  is the moment of inertia of the chords about an axis midway between the sections of the chords are to be taken on radial lines passing through points 1, 2, 3, etc.  $x$  and  $y$  are the coördinates of the points 1, 2, 3, etc., in Fig. 63

$$x = z \frac{\delta x}{2} = z \frac{L}{2n}$$




Fig. 64. Fixed Arch. Reactions

$m_{xy}$  is the moment at the point on the arch-axis having the coördinates  $xy$  assuming that the given loading is supported by the axis hinged at the right end and rollers at the left end.  $r_1$  is the reaction at the left support under the condition specified for  $m_{xy}$ . In the above formula the only terms which depend upon the loading are those containing  $m_{xy}$  and the others being constant for any given arch. While but one load has been used any number may be used by considering  $m_{xy}$  and  $r_1$  as the sum of the respective quantities for each load.

**Stresses.** The STRESSES in the truss members can be found by the ordinary graphical methods when  $H_1$ ,  $V_1$  and  $H_2$  are known. For example, assume the numerical values shown in Fig. 64. The resultant of  $V_1$  and  $H_1$  is resolved into two components parallel and perpendicular to the bottom-chord member at the support. Then  $T$  must act at the

upper-chord joint as shown. The two reactions parallel to the bottom chord are found by moments. The stress-diagram can now be drawn beginning with these forces and proceeding until the right support is reached.

**Symmetrical Loading.** When the loading is symmetrical,  $H_1y_1 = H_2y_2$  and hence  $V_1 = r_1$ . Also

$$H_1y_1 = H_1 \frac{\sum yK}{\sum K} = \frac{\sum m_{xy}K}{\sum K}$$

**Changes of Temperature.** For temperature-changes,

$$H_t = \alpha t^\circ L + \sum yA''$$

$$H_1y_1 = H_2y_2 = H_t \frac{\sum yK}{\sum K}$$

$$y_1 = \frac{\sum yK}{\sum K} \quad V_1 = 0$$

## 10. Arches with Solid Ribs

**Arches with Solid Ribs.** While this chapter considers TRUSSES only, it may not be out of place to briefly consider ARCHES HAVING SOLID RIBS. The computations for  $V_1$ ,  $H_1$  and  $H_1y_1$  remain unchanged, excepting that  $I$  now is the moment of inertia of the radial section of the rib at points 1, 2, 3, etc.

esses. If  $x$  and  $y$  are the coördinates of any point on the gravity-rib, which should coincide with the arch-axis, the bending moment  $t$  is, for each load,

$$M_x = H_1 y_1 + V_1 x - H_1 y - P (x - a) - Q (y - b)$$

tive when  $y_1$  is measured below  $A$  in Fig. 64.

$$S = \frac{M_{rc} c}{I} + \frac{Nxy}{A}$$

he distance from the gravity-axis to the outermost fiber. For the **FREE-HINGED ARCEES**,  $H_1 y_1 = 0$ .

ear. Let  $H_x$  be the algebraic sum of all the horizontal components of the section,  $V_x$  the algebraic sum of all the vertical components of the section and  $\theta$  the angle which the radial section, upon which wanted, makes with the vertical. Then  $T_x = V_x \cos \theta - H_x \sin \theta$ .

**Parabolic Arch.** If the center line of the **SOLID RIB** is a **PARABOLIC** and  $EI \cos \theta$  is a constant, the following simple formulas give the reactions and  $H_1$ :

$$H_1 = P(1 - k) - Q \frac{4f}{L} k(1 - k)$$

$$V_1 = \frac{L}{f} P [k(1 - 2k^2 + k^3)] - Q \left\{ 1 - \frac{k}{2} [5(1 - k - 2k^2 + 4k^3) - 8k^4] \right\}$$

$$H_1 y_1 = EI_0 e \ell^0$$

$a + L$  (Fig. 63),  $f$  is the rise of the axis,  $P$  is the vertical load acting at the crown,  $Q$  is the horizontal load acting from left to right and  $I_0$  is the moment of inertia of the section of the rib at the crown.

**Parabolic Arch.** In like manner the following formulas apply for **ARCHES** with **OUT HINGES**:

$$H_1 = P(1 - k)^2(1 + 2k) - \frac{12f}{L} Q(k - k^2)^2$$

$$V_1 = \frac{15L}{4f} Pk^2(1 - k)^2 - Q \left\{ 1 + k^2(-15 + 50k - 60k^2 + 24k^3) \right\}$$

$$\frac{L}{2} Pk(1 - k)^2(5k - 2) - fQ \left\{ 2k(1 - k)^2(2 - 7k + 8k^2) \right\}$$

$$\frac{45}{4f} EI_0 e \ell^0 \quad H_1 y_1 = \frac{15}{2f} EI_0 e \ell^0$$

the factors containing  $k$  in the above formulas are given in tabular form in the treatise on Arches.\*

**ARCHES**, with solid ribs of constant cross-section and the center line of the arch a **CIRCLE**, may be considered by using formulas somewhat similar to those for **PARABOLIC ARCHES** but very much longer and more complex. Tables for their solution are given in the treatise on arches referred to.

## 11. Influence-Lines for Simple Beams and Trusses

**An Influence-Line** is a line showing the variation in any function at a section of a beam or for any member of a truss, caused by a single load moving across the span. For convenience the LOAD is usually considered as UNITY.




Fig. 65. Influence-lines. Reactions for Beams

**Reaction for a Single Load.** If the load  $P$ , Fig. 65, moves from  $A$  toward  $B$ , the left reaction, when  $P$  is distant  $x$  from  $B$ , is expressed algebraically  $R_1 = Px + L$ , which is an equation of a straight line. If  $x = 0$ ,  $R_1 = 0$ , if  $x = L$ ,  $R_1 = P$ . If we make  $ac = P$  and draw the two straight lines  $ab$  and the ordinate  $de$  immediately below  $P$  is the value of  $R_1$  for this position of  $P$ . If  $ac = \text{unity}$ , then  $R_1 = P (de)$ .




Fig. 66. Influence-lines. Reactions for Beams




Fig. 67. Influence-lines. Moments for Beams

**Reaction for More than One Load.** The reaction for any number of concentrated loads can be found as shown in Fig. 66.

$$R_1 = P_1a_1 + P_2a_2 + P_3a_3 + P_4a_4$$

**Bending Moment for a Single Load.** The moment at  $C$ , Fig. 67, when the load is on the right of  $C$ , is  $M = R_1a = \frac{Pxa}{L}$ . When the load is at  $C$ ,  $M = P \frac{a^2}{L}$ .



at  $B$ ,  $M = 0$ . For all positions of  $P$  upon the left of  $C$ ,  $M = R_1 b$ . When  $P$  is at  $A$ ,  $M = 0$ , and when at  $C$ ,  $M = P \frac{(L-b)b}{L}$ .

If in Fig. 67 the figure  $mng$  is drawn with  $fg = \frac{(a)(b)}{L}$ , then the moment at  $C$  for any load in any position is  $P (de)$ .

**Moment for Any Number of Concentrated Loads.** The moment at  $C$  for the loading shown in Fig. 68 is  $M = P_1 a_1 + P_2 a_2$




Fig. 68. Influence-lines. Moments for Beams

This gives the moment at  $C$  for a given position of the loads, not necessarily the GREATEST MOMENT which these loads may cause, or position may cause a greater moment. The greatest moment at  $C$  occurs when some concentration is at  $C$ . Let  $P$  be this concentration and




Fig. 69. Influence-lines. Moments for Trusses

be divided into two parts,  $nP$  and  $mP$  so that  $n + m = 1$ , and  $n$  is zero and less than 1. The maximum moment at  $C$  will occur when

$$\frac{P_1 + P_2 + P_3 + P_4}{L} = \frac{P_1 + nP_2}{a}$$

in the beam where any given moving load causes the GREATEST MOMENT is so situated that the middle of the span is half-way between the center of gravity of the load. Since a concentration will always be used, a few trials will determine the proper concentration to use. For equal concentrated loads should be placed on the beam so that

the middle of the span is at the quarter-point between the concentrations. **THE MAXIMUM MOMENT** falls under the concentration nearer the middle of the span.

### Chord-Member in Truss with One Set of Web-Members Vertical.

Fig. 69 the top chord member  $U_2U_3$  has its center of moments at  $L_2$  and the bottom chord member  $L_1L_2$  at  $U_2$ . The **INFLUENCE-DIAGRAM** for the moment at  $L_2$  and  $U_2$  is precisely the same as shown in Fig. 67. The moment produced by any load  $P$  is  $P(de)$ . As long as one set of web-members is vertical the **INFLUENCE-DIAGRAM** will be identical with that shown in Fig. 69, regardless of the inclination of the diagonals or the chord-members.

**Chord-Members in Truss with Inclined Web-Members.** The moments at points in the loaded chord, Fig. 70, have **INFLUENCE-DIAGRAMS** identical with




Fig. 70. Influence-lines. Moments for Trusses




Fig. 71. Influence-lines. Shear for Trusses

that shown by Fig. 69. For the unloaded chord a slight modification must be made. For example let  $U_2$  be a center of moments, then if the loads were on a beam,  $mgn$  would be the **INFLUENCE-DIAGRAM** (Fig. 70). For all loads on the left of  $L_1$  and on the right of  $L_2$  the diagram is correct and the moments at  $U_2$  are  $= P_1a_1$  and  $P_3a_3$ . For loads between  $L_1$  and  $L_2$  draw the line  $rs$ . The moment at  $U_2$  is  $P_2a_2$ .

**Web-Members of Trusses with Parallel Chords.** Fig. 71. The stress in  $U_3L_3$  equals the shear in the panel  $L_2L_3$  multiplied by the secant of  $\theta$ . **THE**

DIAGRAM will be drawn for the shear. For any load between  $L_3$  shear in this panel equals  $R_2$ ; hence, with  $ab$  as a reference-line,  $ba'$  INFLUENCE-LINE for  $R_2$  and the shear is  $P_1a_1$ ,  $P_2a_2$ , etc., until the point  $L_3$ . In like manner  $af$  is the INFLUENCE-LINE for  $R_1$  and the shear for left of  $L_2$  is  $P_1a_1$ . The shear for the loads  $P_2$  between  $L_2$  and  $L_3$  is amount of  $P_2$  which is transferred to  $L_2$ . The INFLUENCE-DIAGRAM for  $P_2$  on a span  $L_2L_3$  is  $ff'e$ . The shear in this panel due to  $P_2$  is  $P_2(d'c)$  or  $P_2a_2$ . A load at  $k$  produces no shear in the panel.

## 12. Secondary Stresses in Truss-Members \*

**Primary Stresses.** In the determination of stresses in a truss it is assumed that they act along the GRAVITY-AXIS of each member; that the axes of all members at any joint meet at a common point; that the joints are free to turn around this point, the joints being considered as hinges and that all loads, including the weights of the members, are applied at the joints only. The stresses determined with these assumptions are direct stresses, sometimes called PRIMARY STRESSES or MAIN STRESSES. The assumptions made are not realized in practice and other stresses, called SECONDARY STRESSES, are induced. An eccentricity causing BENDING MOMENTS is a common case of the rivet-line not coinciding with the gravity-axes of members about a joint do not intersect at the same point. Stresses are induced. The resistance of a joint to free angular movement of the truss deflects also induces bending moments. The weights of inclined members add slight BENDING-STRESSES to the direct stresses in these members. At the supports there will be a RESISTANCE TO HORIZONTAL SLIP from temperature-changes and the deflection of the truss. If this resistance depends upon the coefficient of friction between the support, the vertical loads and the length of span. Members and imperfect workmanship are other causes of secondary stresses. In the design and fabrication secondary stresses in ordinary roof-trusses these causes need not be considered seriously. The main causes, however, of secondary stresses are FAULTY DETAILS. The actual shearing-stresses found in details is much more than the direct shearing-stress, and ECCENTRICITY IN THE LINES OF STRESS-ACTION. Eccentric riveted joints may not be wholly avoided but they should be reduced to a minimum. The history of bridge and building-failures is mostly a story of faulty structure has seldom given way for lack of strength in the main members but if the strength of a structure is measured by the strength of its weakest part, it can be only as strong as the weakest detail. Because of conditions that induce large secondary stresses, insufficient lacing of members and careless grouping of rivets, have all invited disaster. The importance of the detailer's work is often underrated. What is usually the case in the DESIGNING of a structure may be comparatively easy while the detailing may be difficult. A well-designed structure may be spoiled by faulty detailing. The detailer should be a designer, that is, a designer of details, and at the same time the designer should be thoroughly familiar with detailing.

\* From Notes by Robins Fleming.

CHAPTER XXVIII  
DESIGN AND CONSTRUCTION OF ROOF-TRUSSES  
By  
MALVERD A. HOWE

PROFESSOR EMERITUS OF CIVIL ENGINEERING, ROSE POLYTECHNIC INSTITUTE

1. Design of Wooden Trusses

**Proportioning the Members.** In Chapter XXVII it has been shown how the STRESSES in the members of a truss, supporting known LOADS, may be found. The next step is to PROPORTION THE MEMBERS for the stresses which they have to resist. The methods employed and the ALLOWABLE UNIT STRESSES are given in detail in Chapters XI to XVI, inclusive. For example, tension-members are considered on pages 385 to 400; steel strut-beams and tie-beams on pages 549 and 572; and wooden strut-beams and tie-beams on page 633. As a matter of convenience the UNIT STRESSES used in this chapter are given in the following table in a condensed form. White pine is here used for the wooden trusses.

Table L. Allowable Unit Stresses Used in Truss-Design \*

Material	Kind of stress	Safe unit stress lb per sq in
White pine.....	Tension with the grain.....	700
".....	Tension across the grain.....	50
".....	Compression on end-fibers.....	1 100
".....	Compression across the grain.....	200
".....	Compression across the grain, round pins..	200
".....	Columns† under 15 diam long.....	1 100
".....	Shear with the grain.....	100
".....	Shear across the grain.....	500
".....	Transverse, fiber-stress.....	700 ‡
Wrought iron.....	Rods in tension.....	12 000
".....	Bolts in shear.....	7 500
".....	Bolts in bearing.....	15 000
".....	Bolts in bending, fiber-stress.....	15 000
Rolled steel.....	Rods in tension.....	16 000
".....	Bolts in shear.....	10 000
".....	Bolts in bearing.....	20 000
".....	Bolts in bending, fiber-stress.....	24 000
".....	Beams in bending, fiber-stress.....	16 000
".....	Beams in shear.....	10 000

\* See also, the tables on pages 376, 412, 449, 454, 557, 647 and 1200. These must be modified, when necessary, to comply with building laws. White pine is used for the examples in this chapter because of the difficulties in making the joints owing to the relative softness of the wood. If one can design a truss in white pine he will have no trouble with the design of trusses constructed with other kinds of wood.

† See, also, Table I, page 449, and Table XVI, page 647.

‡ The Borough of Manhattan, New York, Building Code (1917), gives 1 200 for this value. Other values are about the same as in the table.

**Inclined Surfaces of Wood.** The normal intensity of the stress on inclined surfaces may be found from the empirical formula

$$r = q + (p - q)(\theta/90)^2$$

quals the permissible normal unit stress on this inclined surface,  $q$  the fibers,  $p$  that on the end of the fibers and  $\theta$  the angle the inclined es with the direction of the grain. For white pine this gives

$$r = 200 + \theta^2/9$$

**Pins on End-Fibers.\*** For all practical purposes the permissible may be taken as the mean of  $p$  and  $q$ ; or, for white pine

$$\frac{1}{2} (p + q) = 650 \text{ lb per sq in}$$

**Columns over Fifteen Diameters Long.** The formula  $\dagger$  used in r and considered amply conservative by many engineers is the roved by the American Railway Engineering and Maintenance of ation in 1907. For white pine this formula is

$$S_1 = S (1 - l/60 d) = 1100 (1 - l/60 d)$$

the permissible unit stress,  $S$  = the permissible compression on the = the length of the column in inches and  $d$  the least dimension ot ation of the column in inches.

**Columns.** For the shapes used in roof-trusses, the formula advocated wler in his specifications for roof-trusses is used in this chapter:

$$S_1 = 12\,500 - 500 l/r$$

he permissible unit stress,  $l$  = the length of the column in feet, and radius of gyration of the cross-section of the column.

. The truss shown in Fig. 1, which is the queen truss shown in 53 and 54 in Chapter XXVII, is considered for this example. The n in the following table are used. The members  $RR$  are wrought-ods, not upset at the ends; and all other members are of white of the members in this truss is subject to transverse stress, so a and compression only, have to be considered:

. Stresses and Dimensions for the Truss Shown in Figure 1

Member	Stress in pounds	Dimensions
Top chord	+21 250	6 by 6-in white pine
Bottom chord	+18 900	6 by 6-in white pine
Verticals	+13 200	6 by 6-in white pine
Diagonals	+ 6 450	4 by 6-in white pine
End posts	+ 5 100	4 by 6-in white pine
Roof	-17 150	{ 6 by 8-in white pine or Three 2 by 8-in pieces with 3/4-in bolts, 2 ft on centers
Truss	-12 750	
Bottom chord	- 9 100	
End posts		One 1 1/4-in round rod

es, Fig. 1. The tension in each rod is 9 100 lb. If the permis- 2 000 lb, the section-area of each rod is  $9\,100 \div 12\,000 = 0.76$  sq in. f a 1 1/8-in rod is 0.694 sq in; and of a 1 1/4-in rod, 0.893 sq in. The ld answer but the 1 1/4-in rod is preferred.

same unit stresses are used for flat and curved surfaces, Tables VII and to 431, of Chapter XII may be used. Formulas and Tables based upon them, see Chapter XIV, pages 449 to 452.

**Rafters, Fig. 1.** The stress in the rafter at *A* is 21 250 lb and at *B* 18 900 lb but as it will be made of one piece, the size is governed by the greater stress. The unsupported length is about 9 ft, and assuming the least dimension of piece to be 6 in,  $S_1 = 1\ 100 \left( 1 - \frac{9 \times 12}{60 \times 6} \right) = 770$  lb per sq in.  $21\ 250 / 77 = 27.6$  sq in = the area of cross-section required, which is less than that of a 6 by 6 piece. A 6 by 6-in timber is actually  $5\frac{1}{2}$  by  $5\frac{1}{2}$ -in, with a cross-sectional area 30.25 sq in, a little in excess of the area required. In general the NOMINAL STANDARD sizes of timbers differ by about one-half an inch in each cross-dimension.

Fig. 1. Queen Truss. (See, also, Figs. 4A, 10, 13 and 16 and Chapter XXVII, Figs. 3, 12, 53 and 54)

**Member C, Fig. 1.** The stress in this member is 13 200 lb and its unsupported length, 12 ft. In this case  $l/d = 24$ , when  $d = 6$  in;  $S_1 = 660$  lb per sq in. The required section-area is  $13\ 200 / 660 = 20$  sq in, and hence a 6 by 6-in timber is used. The top-chord should have one dimension constant in order to facilitate the making of good connections at the joints.

**Braces, Fig. 1.** The stress in the brace *D* is 6 450 lb and its unsupported length about 9 ft. A 4 by 6-in timber is first tried. Here  $l/d = 27$  and  $S_1 = 440$  lb per sq in. The required area, therefore, is 10.7 sq in and a 4 by 4-in timber answers the purpose; but for additional stiffness and convenience in making connections, a 4 by 6-in piece is used. Each brace, *E*, has a stress of 5 100 lb and a total length of 17 ft. If the braces are bolted where they cross the unsupported length may be taken as  $8\frac{1}{2}$  ft. It is evident that a 4 by 6-in piece is ample for each brace.

**Bottom Chord, or Tie-Beam, Fig. 1.** The maximum tension in the bottom chord is 17 150 lb in *N*. The permissible unit stress is 700 lb per sq in; hence the net section-area required is  $17\ 150 / 700 = 24.5$  sq in. A 2 by 12-in plank is continuous from end to end of the truss and without holes and notches, will carry the stress alone but will not permit of proper connections. A 6 by 6 piece is selected, but it may be necessary to substitute for it a 6 by 8-in piece when the connections are made and it is spliced in the middle. If the member is built up of planks, three 2 by 8-in pieces are required; and they must

bolted together by a pair of bolts every 2 ft of their length. If 24-lengths are used, the joints of the strands will be about 10 ft apart.

1. For this example the truss illustrated in Fig. 2, which is the same as shown in Figs. 4 and 24, Chapter XXVII, is considered. The stresses for dead load, wind and snow were found in Chapter XXVII and are given in the following table. The rafters and the bottom chord support

#### Scissors Truss. (See, also, Chapter XXVII, Figs. 4 and 24)

the joints and consequently must resist CROSS-BENDING stresses and TRANSVERSE STRESSES. The load on each piece is given in the table under TRANSVERSE LOAD.

Stresses and Dimensions for the Truss Shown in Figure 2

Member	Stress, lb	Transverse load, lb	Dimensions, white pine
Top chord	+8 000	1 000	Two 2 by 8-in planks
Bottom chord	+6 600	1 320	Two 2 by 8-in planks
Left rafter	+1 890	.. .. .	One 2 by 10-in plank
Right rafter	+ 750	.. .. .	One 2 by 10-in plank
Left tie beam	-4 350	.. .. .	Two 1 by 8-in planks
Right tie beam	-2 530	.. .. .	Two 1 by 8-in planks
Left post	-1 875	470	One 2 by 10-in plank
Right post	-5 400	384	One 2 by 10-in plank
Left strut	-1 875	.. .. .	One 2 by 10-in plank

g. 2. The piece B rather than the piece A is considered, as it is longer. The total vertical load on the piece acting as a beam is 10 000 lb. The horizontal span is about 8 ft. The bending moment at the center

is  $\frac{1}{8} (1\ 320 \times 8 \times 12) = 15\ 840$  in-lb. If the depth of the piece is assumed to be 8 in, the proper thickness is found from the equation,  $15\ 840 = \frac{1}{8} S_b$ ,  $\frac{1}{8} (700 \times 8 \times 8 \times b)$ , or  $b = 2.12$  in. This neglects the component of the vertical load parallel to the rafter. Considering now the direct compression of 6 600 lb and remembering that the sheathing is nailed to the rafter, the least dimension  $d$  of the piece is its depth, which may be taken the same as that used for the piece resisting the TRANSVERSE STRESS. The unsupported length of the piece is about 12 ft. Then  $l/d = 18$ ,  $S_1 = 770$  lb per sq in and the required area of cross-section is  $6\ 600/770 = 8.6$  sq in. As the depth is 8 in, the thickness is about 1.1 in. Combining the two pieces, the total thickness is  $2.12 + 1.1 = 3.22$  in, and a piece having the nominal size of 4 by 8 in is required. Since the sheathing is nailed to the rafters, two 2 by 8-in planks may be used without increasing the stiffness of the member. While the above method of designing a piece subject to TWO KINDS OF STRESS is not correct for all conditions which occur in practice, the results are on the safe side, and the method has the advantage of being easily applied.

**Member S, Fig. 2.** Considering the transverse load first, the bending moment at the middle is found to be  $\frac{1}{8} (470 \times 15.5 \times 12) = 10\ 930$  in-lb. If the depth is assumed to be 10 in, the required thickness, found from the equation  $10\ 930 = \frac{1}{8} (700 \times 10 \times 10 \times b)$ , is 0.94 in; or, a board 1 by 10 in in cross-section will carry the transverse load if prevented from twisting sidewise, which it has a tendency to do in this case where the ceiling is attached directly to the member. The side-stiffness will be further increased when the additional material resisting the tension is in place. The net area for the direct tension of 1 875 lb is 2.68 sq in, which requires a board 10 in wide and only a trifle over  $\frac{1}{4}$  in thick. The total thickness becomes  $0.94 + 0.27 = 1.21$  in, and it will therefore be necessary to use a 2 by 10-in plank.

**Member E, Fig. 2.** This is in compression, but the stress is quite small, being only 750 lb. The possible extension of the 2 by 10-in piece used for S is next considered, to find if it can be extended and used here. The unsupported length is about 6 ft, and the least dimension 2 in; hence  $l/d = 36$ ,  $S_1 = 440$  lb per sq in and the required area of the cross-section becomes less than 2 sq in. The 2 by 10-in piece is therefore ample.

**Members T and T<sub>1</sub>, Fig. 2.** Inspection shows that a 2 by 10-in plank is quite sufficient for these pieces.

**Member D, Fig. 2.** The unsupported length is about 7 ft. Then, for  $d = 2$  in,  $l/d = 42$ ,  $S_1 = 330$  lb per sq in and the required section-area is  $1890/330 = 5.73$  sq in. A piece 2 by 10 in is more than sufficient; but as this size allows a simple prolongation of the pieces T and T<sub>1</sub>, a piece of this dimension is used.

**Members F and H, Fig. 2.** For the piece F a net area of  $4\ 350/700 = 6.21$  sq in is required; or a board 1 by 8 in in cross-section may be used. For convenience in construction, two 1 by 8-in boards are chosen. It is evident that the same arrangement can be made for the piece H.


**Caution.** Since this truss is a SCISSORS TRUSS, the horizontal deflection at the supports should be determined, and, if this is an appreciable quantity, the members as designed above, should be increased in size or their lengths changed in framing; this is so that the span, after the truss is loaded and the deflection has taken place, becomes the distance between the supports. This is discussed in Chapter XXVII, pages 1085 to 1087.

**Example 3.** For this example the HOWE TRUSS shown in Fig. 3 is considered. The vertical load is assumed to be  $46\frac{1}{2}$  lb per sq ft on the top-chord and 10 lb per sq ft on the bottom-chord. For trusses spaced about 15 ft 8 in on centers



... is 2½ by 2 by ¼ in; and while ¾-in rivets, which are the largest that are used in steel trusses, it is economical to use the same straight line, but

...ions of a truss  
...ght and con-



1 with Stresses

...ny of the members. For conven-  
...nbers and final sections are arranged

...or the Half-Truss Shown in Figure 5

Net area required, sq in		Make-up of member
72	1.06	{ Two 2½ by 2 by ¼-in angles Net area = 1.70 sq in
144	.....	
72	.....	
72	.....	
72	.....	{ Two 2½ by 2½ by ¼-in angles, and one 10 by ¼-in plate
144	.....	{ Two 2½ by 2 by ¼-in angles
72	.....	

This member has the maximum stress of the bottom-  
...e used up to the joint F and possibly for the entire length  
...t area required is 16 900/16 000 = 1.06 sq in, or the net  
...ngle is 0.53 sq in. One leg of the angle is riveted to the  
...in rivets which is assumed to cut out a section 7' in the

chord 10 by 12 in. A single piece of this size, nearly 50 ft long, is difficult to obtain; so at least one splice is necessary. If planks are substituted it requires six 2 by 12-in pieces to give an equivalent area.

**Inclined End-Post, Fig. 3.** The stress in this post is 33 450 lb and its supported length about 9.75 ft. An 8 by 10-in piece is tried first, the 10-in dimension being the same as one dimension of the chords. Then  $l/d = 19.5$ ,  $S_1 = 825$  lb per sq in and the required area of cross-section becomes  $33\,450/825 = 40.54$  sq in, which is about one-half the cross-sectional area of an 8 by 10-in piece. If  $d = 6$  in, there results  $l/d = 19.50$ ,  $S_1 = 740$  lb per sq in and the required area = 45.2 sq in, which is a much smaller cross-sectional area than that of a 6 by 10-in timber.

**Intermediate Diagonals, Fig. 3.** For the first diagonal a 6 by 6-in piece is tried. The required section-area is  $19\,630/740 = 26.5$  sq in, which is well within the section-area of a 6 by 6-in timber. A 4 by 4-in timber could be used for the next brace, but it is better to use either a 6 by 6-in timber or one 4 by 6 in.

**Purlins, Figs. 1 and 4A.** While the stresses given for the members of the truss shown in Fig. 1 are based upon a vertical loading covering the effect of




Fig. 4A. Purlin-design for Joint 2 of Truss Shown in Fig. 1

dead load, snow-load and wind-load, the wind load is separated from the others in order to illustrate the method to be followed in designing a purlin when the plane of the load is parallel to one of its sides. The trusses of the type illustrated in Fig. 1, are 15 ft on center. This distance, therefore, is the span of the purlin. The purlin at joint 2, Fig. 1, has a vertical loading of 4 500 lb and a wind-load acting normal to the roof, of 2 000 lb. The inclined loading, resolved parallel to  $b$  and  $d$ , Fig 4A, and combined with the vertical load gives for the total, parallel to  $d$ , 4 500 + 1 400 = 5 900 lb; and for that parallel to  $b$ , 1 400 lb. If then, loads are assumed to act through the center of gravity of the purlin-section,

produce both tension in the fiber at  $B$  and compression diagonally opposite. The bending moment at the middle of the purlin due to the vertical load  $(5\,900 \times 15 \times 12) = 1\,327\,500$  in-lb; and that due to the horizontal load  $(1\,400 \times 15 \times 12) = 315\,000$  in-lb. It is assumed that  $b = 8$  in and  $d = 10$  in. Then the fiber-stress at  $B$ , due to the first moment is

$$S' = 6 \times 1\,327\,500 / bd^2 = 996 \text{ lb per sq in}$$

The fiber-stress at  $B$ , produced by the second moment is


$$S'' = 6 \times 315\,000 / b^2d = 295 \text{ lb per sq in}$$

The total fiber-stress is  $996 + 295 = 1\,291$  lb per sq in. This is 91 lb in excess of the permissible fiber-stress in the most conservative practice and in some building laws for white oak. If a 10 by 10-in timber is used the fiber-stress is 986 lb per sq. in, and if the piece is 10 by 12-in, the fiber-stress becomes 812 lb per sq in.

## 2. Design of Steel Trusses

**General Considerations.** The members of the ordinary STEEL TRUSSES are composed of two rolled ANGLES placed back to back and at the joints each piece is connected to GUSSET-PLATES by RIVETS. The size of

**Example 4.** Fig. 5 shows a FAN TRUSS of the form and dimensions of a truss used for supporting the roof of a machine-shop. The loading is light and con-



**Fig. 5. Fan-truss Diagram with Stresses**

**Table IV. Stresses and Dimensions for the Half-Truss Shown in Figure 5**

Member	Stress, lb	Approximate length, in	Net area required, sq in	Make-up of member
D .....	-16 900	.....	1.06	} Two 2½ by 2 by ¼-in angles Net area=1.70 sq in
PF .....	-13 800	.....	.....	
M .....	- 9 200	.....	.....	
L .....	- 4 650	.....	.....	
K .....	- 7 700	.....	.....	
E and EL...	- 3 070	.....	.....	} Two 2½ by 2½ by ¼-in angles, and one 10 by ¼-in plate
B .....	+20 200	72	.....	
F .....	+ 5 000	144	.....	
D .....	+ 1 900	72	.....	

**Member AD, Fig. 5.** This member has the maximum stress of the bottom chord and its size will be used up to the joint *F* and possibly for the entire length of the chord. The net area required is  $16\,900/16\,000 = 1.06$  sq in, or the net area of one angle is 0.53 sq in. One leg of the angle is riveted to the end-plate with  $\frac{3}{4}$ -in rivets which is assumed to cut out a section  $\frac{7}{8}$  in by the

thickness of the angle. From Table XI, page 365, we find that a  $2\frac{1}{2}$  by  $2\frac{1}{2}$  by  $\frac{1}{4}$ -in angle has an area of 1.06 sq in. The area to be deducted on account of one rivet-hole is  $\frac{7}{8} \times \frac{1}{4} = \frac{7}{32} = 0.22$  sq in. This leaves for the net area of the angle  $1.06 - 0.22 = 0.84$  sq in, which is well above the required area. As this is the smallest angle which can be used and as all the other tension-members have less stress than  $AD$ , the tension-members will be made uniform throughout. With the exception of  $FK$ , many designers would use but one angle for the web-members. While the net area is ample for the stresses, yet it is poor practice, as one angle produces a ONE-SIDED PULL on the gusset-plates.

**Member  $AB$ , Fig. 5.** This piece has the maximum stress of the top-chord under a compression of 20 200 lb and a transverse load of 2 000 lb. The COMBINED EFFECT OF THE TWO LOADINGS in this case must be determined in a manner quite different from that followed for wooden construction. The maximum fiber-stress must not exceed that found from some column-formula as, for example,  $S_1 = 12\,500 - 500\,l/r$ . The maximum fiber-stress  $S$  may be found, approximately, from the expression  $S = P/A + Mc/I$ . In this equation,  $P$  is the direct compression, which is 20 200 lb in this case;  $A$  the area of the section of the piece,  $I$  the moment of inertia of this section,  $c$  the distance of the outermost fiber of the section which is in compression from its gravity-axis and  $M$  the maximum bending moment produced by the transverse load. The PRINCIPAL AXES of the section must lie in the plane of the transverse loading, if the above formula is used. For symmetrical sections, as two angles back to back, an I-beam, or a channel, the principal axes are AXES OF SYMMETRY, and the values of  $I$  and  $c$  are readily found from the properties of rolled shapes tabulated in Chapter X. The first trial-section is that shown in Fig. 6, consisting of two  $2\frac{1}{2}$  by  $2\frac{1}{2}$  by  $\frac{1}{4}$ -in angles and one 10 by  $\frac{1}{4}$ -in plate. To find the moment




Fig. 6. Section through Rafter-member of Truss Shown in Fig. 5. (Axis at  $d_1$  from  $AB$ , through c. g. of angles; axis at  $C_g$ , through c. g. of sections; axis at  $d_{11}$  from  $AB$ , through c. g. of plate.)

inertia,  $I$ , and the radius of gyration,  $r$ , the center of gravity of the section must be found first. The distance  $X$  of the center of gravity from  $AB$  (Fig. 6) is found from Equation (2), page 295,

$$X = \frac{\text{area of plate} \times d_{11} + \text{area of angles} \times d_1}{\text{area of entire section}}$$

From the properties of angles, Table XII, page 367, the distance from the back of the angle to the center of gravity of the angle is  $d = 0.72$  in.  $I = 0.7$  and the area of the two angles = 2.38 sq in. The plate does not usually extend to the back of the angles, a clearance of from  $\frac{1}{8}$  to  $\frac{1}{4}$  in being allowed. A clearance of  $\frac{1}{4}$  in is assumed.

Then,  $d_1 = 10.25 - 0.72 = 9.53$  in, and  $d_{11} = 5$  in,

Hence,  $X = \frac{2.5 \times 5 + 2.38 \times 9.53}{2.50 + 2.38} = 7.21$  in

The value of the moment of inertia  $I$ , about  $C_g$  as an axis, is found as follows (Chapter X):

For the plate (page 335),  $\frac{bh^3}{12} = \frac{0.25 \times 10^3}{12} = 20.80$

Eq. (3) (page 338),  $A(X - d_{11})^2 = 2.5(2.21)^2 = 12.21$

$$\begin{aligned} & \text{angles (page 367)} & 2 \times 0.70 &= 1.40 \\ & \text{ge 338), } A (d_1 - X)^2 &= 2.38 (2.32)^2 &= 12.81 \\ & \text{ire section,} & I &= 47.22 \end{aligned}$$

section,  $I = Ar^2$  or  $r = \sqrt{I/A}$ , hence for this section  $r = \sqrt{47.22/4.88}$  (See Equation (2), page 333.) The distance to the outermost fiber from the axis  $Cg$  is 3.04 in =  $c$ . There is now sufficient data to be actual fiber-stresses due to the loading and also the permissible bending moment produced by the transverse load is

$$\begin{aligned} M &= \frac{1}{8} (2\,000 \times 6.16 \times 12) = 18\,480 \text{ in lb} \\ S &= 20\,200/4.88 + (18\,480 \times 3.04)/47.22 = 5\,330 \text{ lb per sq in} \\ S_1 &= 12\,500 - 500 \times 6.16/3.11 = 11\,510 \text{ lb per sq in} \end{aligned}$$

that the actual fiber-stress is very much smaller than the allowance, but as we have used minimum-size angles and a minimum thick-plate, the only way to reduce this section is to use a smaller plate. Possible because of the requirements for making proper connections

The above analysis assumes that the member is prevented from rise by the roof-covering. If such is not the case,  $r$  will have to be for a vertical axis through the center of gravity of the section. the moment of inertia,

$$\begin{aligned} & I_1^2/12 = (10 \times 0.25^3)/12 = 0.013 \\ & 2 \times 0.70 &= 1.400 \\ & 2.38 (0.72 + 0.125)^2 &= 1.699 \\ & \text{section,} & I &= 3.112 \end{aligned}$$

$$\begin{aligned} r &= \sqrt{3.112/4.88} = 0.6377 \text{ in} \\ S_1 &= 12\,500 - 500 \times 6.16/0.6377 = 7\,670 \text{ lb per sq in} \end{aligned}$$

less than the value of  $S_1$ , and hence this sections fulfills all the considering the unsupported length vertically and sidewise as

Fig. 5. Taking two  $2\frac{1}{2}$  by 2 by  $\frac{1}{4}$ -in angles with the  $2\frac{1}{2}$ -in back, the least value of  $r = 0.78$  in (Table XVI, page 371).

$$\begin{aligned} S_1 &= 12\,500 - 500 \times 12/0.78 = 4\,810 \text{ lb per sq in} \\ 5\,000 + 4\,810 &= 1.04 \text{ sq in, required.} \end{aligned}$$

the two angles used is  $2 \times 1.06 = 2.12$  sq in (Table XVI, page 371).

Fig. 5. The stress in this member is very small and one angle will the requirements. For one angle,  $2\frac{1}{2}$  by 2 by  $\frac{1}{4}$  in, the least (Table XI, page 365) and  $S_1 = 5\,300$  lb per sq in, indicating that this is an excess of strength. As pointed out above, it is better to use

ratio. The best specifications limit the ratio of the least dimensioned length of a compression-member to 50, unless the allowance given by the column-formula is decreased. The member  $EF$  is about 144 in long, so that its length is 57.6 times its least dimension. There is a great excess of area, the actual unit stress is much less than that given by the formula.

The compression-members made up of two angles and designed as in the preceding paragraphs, have been considered as if acting as a single member. It is clear that the various parts must be so fastened together that they will not buckle. If  $l$  is the unsupported length of the member

as a whole,  $r$  the corresponding least radius of gyration,  $r'$  the least radius of gyration for any part and  $l'$  the unsupported length of the part, or the distance between stay-rivets, there is the following relation:

$$l'/r' = l/r \text{ or } l' = lr'/r$$

For the member  $EF$   $l' = 144 \times 0.42/0.78 = 78$  in.  
Practice reduces this to 2 or 3 ft.

**Tension-Members**, also, should be riveted together in a similar manner to make the parts pull together.

**Example 5.** The next truss considered is the FINK TRUSS shown in Fig. 7 in which two angles are used for all members and  $\frac{3}{4}$ -in rivets at the connections.

**Member AC, Fig. 7.** For a unit stress of 16 000 lb per sq in, the net area required is  $21\ 800/16\ 000 = 1.36$  sq in. Two  $2\frac{1}{2}$  by  $2\frac{1}{2}$  by  $\frac{3}{4}$ -in angles have a section-area of 2.38 sq in (Table XII, page 367). Deducting  $2(\frac{3}{8} \times \frac{1}{4}) = \frac{1}{8}$  sq in, the net section becomes 1.94 sq in, while the required area is 1.36




Fig. 7. Fink Truss. (See, also, Figs. 22, 22A, 22B, 22C, and 22D)

**Members CE and EH, Fig. 7,** are composed of angles of the same size.

**Members CD, DF, EF and FG, Fig. 7,** are made of two  $2\frac{1}{2}$  by 2 by  $\frac{3}{4}$ -in angles with a net area of 2.12 sq in. This greatly exceeds the required area.

**Members BC, BF and DE, Fig. 7.** From the preceding example it is seen that a pair of minimum-size angles will be quite sufficient. Two  $2\frac{1}{2}$  by  $\frac{3}{4}$ -in angles, having a section-area of 2.12 sq in, are used.

**Member AB, Fig. 7.** For this member in which there is a direct compression of 23 500 lb and a transverse stress due to a load of 2 500 lb, a preliminary trial is made with two 5 by  $3\frac{1}{2}$  by  $\frac{3}{4}$ -in angles, with the 5-in legs back to back separated by a  $\frac{1}{4}$ -in gusset-plate. The moment of inertia about an axis passing through the center of gravity of the two angles and parallel to the short legs is (Table XI, page 363) 7.78\* and the corresponding radius of gyration is 1.42 in. About a vertical axis the radius of gyration is (Table XVI, page 363) 1.42 in, which is the least radius to be used in the column-formula.

\* It will be noticed that some values given for the properties and the sizes of angles in this example differ slightly from those given in the tables referred to, as the section modulus  $I$ ,  $r$ ,  $x$ , etc. This changes the result very slightly and is due to variations in the figures of values in different editions of manufacturers' handbooks. Editor-in-Chief

duced by the 2 500-lb load at the center of the member is  $\frac{1}{2} \times 12 = 34\,500$  in-lb. The section-area of the two angles is (page 363).

$$= [23\,500/6.10] + [(34\,500 \times 1.61)/7.78] = 10\,990 \text{ lb per sq in}$$

$$= 12\,500 - (500 \times 9.2)/1.42 = 9\,260 \text{ lb per sq in}$$

less than  $S$ , it is seen that the angles selected are a little too light. Using angles of greater thickness it will be better to select a larger 6 by  $3\frac{1}{2}$  by  $\frac{7}{16}$ -in angles are used (page 363)

$$= [23\,500/6.86] + [34\,500 \times 2.04]/12.86 = 8\,890 \text{ lb per sq in}$$

$$= 12\,500 - [(500 \times 9.2)/1.34] = 9.070 \text{ lb per sq in}$$

that there is ample strength and stiffness and that the area is in 16 sq in. If two 5 by  $3\frac{1}{2}$  by  $\frac{7}{16}$ -in angles had been used, the area been increased 0.96 sq in (page 363). The least radius of gyration expression for  $S_1$  assumes that the angles will be separated by  $\frac{1}{4}$ -in

If thicker gusset-plates are used, the value of  $r$  will increase.

stalls. The use of UNIFORM SIZES for members in the same straight line adds rigidity to the truss. The angles can be furnished of 60 ft and over, thereby reducing the labor of cutting them and the number of rivets and the size of the gusset-plates. The portion  $EG$  shown by Fig. 7 would be completely riveted up in the shops, three joints to be riveted at the building. In general, any truss of outside dimension not exceeding 10 ft, can be shipped by rail. The location of the splices.

### 3. Joints of Wooden Trusses

of any truss should be proportioned with as much care as is used in the sizes of the members, so that the truss will be equally strong. The general principles and methods for designing joints are in Chapter XII and illustrated by examples. To further explain the methods of design of some of the joints for the trusses shown in the preceding chapter are added in this chapter.

1. This is the most important joint in the truss. There are many types of this joint, but only a few of them are illustrated. Fig. 8 shows a **JOINT**. The rafter rests in a notch in the bottom chord and is held by one or more rolled-steel bolts. These bolts are perpendicular to the rafter, and the stresses in them are found graphically by the method shown in Fig. 8) in which  $ac$  is perpendicular to the SCARF-CUT or SEAT of the rafter. The tension in the bolts is found to be 31 550 lb, and with a permissible stress of 16 000 lb per sq in, the net section-area required is 1.97 sq in, which is about one  $1\frac{1}{4}$ -in bolt (Table II, page 388). The WASHER, bearing on the grain of the rafter, will have an area of  $31\,550/200 = 158$  sq in. Since the top-chord is actually but  $5\frac{1}{2}$  in wide, the length of the plate is 8 in. Such a plate would look out of proportion with one bolt, so two bolts are substituted, having a net section-area of 2.10 sq in (Table II). Two bolts are placed near each end of the plate and one bolt in the middle. The bolts are spaced about  $9\frac{1}{2}$  in apart. The thickness of the plate may be taken as one-fifth the distance from the end of the plate to the center of the first pair of bolts. This distance is about 3.4 in; hence the thickness is 0.67 in. A  $\frac{3}{4}$ -in plate is used. The lower end of each pair of bolts is held with a PLATE-WASHER bearing upon the inclined surface of the bottom chord as shown. The ANGLE OF INCLINATION approximates  $45^\circ$

and hence the allowable pressure on the wood is  $500 + (1\ 400 - 500) \frac{1}{4} = 71$  per sq in. (See Table VI, page 454, Table XVI, page 647, and the equation page 1138.) The pair of bolts carry a tension of  $31\ 550 \times \frac{3}{4} = 23\ 620$  lb, this stress requires a plate having an area of  $23\ 620/715 = 33.0$  sq in, which will be provided by a plate  $5\frac{1}{4}$  by 4 by  $\frac{3}{4}$  in. For the single bolt, a 4 by CAST-IRON BEVELED WASHER is used, having a  $\frac{3}{4}$  in lug let into the bolt to take the horizontal component of the pull in the bolt. To prevent the bolt slipping on the bottom chord, two OAK KEYS are employed. (See Table page 454, and Table I, page 1138, for permissible unit stresses.) The horizontal component of the pull in the bolts is about 22 300 lb, and for one key, 11

Fig. 8. Detail of Joint 1, Fig. 1


lb, and taking the actual thickness of 6 in to be  $5\frac{1}{4}$  in, each inch in length the key will safely carry  $5\frac{1}{4} \times 200 = 1\ 100$  lb in longitudinal shear (Table page 412). The keys will, therefore, be 10 in long. The ends of the keys, against the notch in the white-pine chord, and for end-bearing each inch in depth of the notch carries  $5\frac{1}{4} \times 1\ 100 = 6\ 050$  lb. The depth of the notch, therefore, is 1.8 in in the chord. In the bolster each inch in depth of wood carries  $5\frac{1}{4} \times 1\ 400 = 7\ 700$  lb (Table XVI, page 647), and the depth of wood is 1.43 in. This makes the total thickness of the keys  $1.8 + 1.43 = 3.23$  in, say  $3\frac{1}{4}$  in. The size of the keys is  $3\frac{1}{4}$  by  $5\frac{1}{4}$  by 10 in. The SPACING OF KEYS is governed by the longitudinal shear of the white-pine chord. 1 inch in length carries  $5\frac{1}{4} \times 100 = 550$  lb (Table I, page 1138), and the distance between keys is  $11\ 150/550 = 20$  in. The various dimensions given above will probably appear large to many. The large dimensions are due to the timber used. If long-leaf yellow pine had been employed, many of the dimensions would have been materially smaller. The ANGLE-BLOCK shown in Fig. 9b, makes a much better connection in this case. The  $1\frac{1}{4}$  in becomes  $1\frac{1}{2}$  in and 15 in becomes 13 in. The net area of the bottom chord should now be determined to see if it is sufficient to take the tension.

**Wall-Plate.** As a rule it is a good idea to place the WALL-PLATE, which receives the common rafters, just above the bottom chord as shown. It affords an opportunity to get at the nuts on the bolts to tighten them as the wood shrinks. The BEARING OF THE TRUSS ON THE BRICKWORK should be



and a STONE or METAL PLATE provided to distribute the pressure. (See XIII.) In this case a 16 by 14 by  $1\frac{1}{4}$ -in CAST-IRON PLATE is used, reduces the pressure on the brickwork to  $82\frac{1}{2}$  lb per sq in.

Fig. 8. This joint might be made in the manner described above, type shown in Fig. 9 is used. The thickness of the plate is usually by the thickness required at Y to give the HOOK the proper strength.



Detail of Joint 1, Fig. 8




Fig. 9A. Alternate Detail of Joint 1, Fig. 8

practically takes one-half the horizontal component of the stress in which is the stress in the bottom chord in this case) as the bolts are rely to keep the parts in place. The metal bears against the end- each inch in depth of the notch, the fibers carry  $9\frac{1}{2} \times 1100 = 10450$  lb, the notch is  $\frac{1}{2}$  ( $27350/10450$ ) = 1.31 in deep, say  $1\frac{3}{4}$  in. Considering a WROUGHT-IRON CANTILEVER,  $1\frac{3}{4}$  in long and uniformly loaded

per sq in, the thick- l from the expression  $2 = \frac{1}{16}(12000 \times 1 \times l^2)$ , in. The nearest e is a thickness of length of the bot- necessary to take from the hook in shear is  $9\frac{1}{2} \times 100$  r in, or,  $13675/950$  all. The inclination at H with the ver- about  $36^\circ$ , and the sure on this surface  $-200)(\frac{3}{4})^2 = 344$

$350/(344 \times 9\frac{1}{2}) = 8.3$  in, which is the required depth of the cut. are confined by the plate, one-half this value, or  $4\frac{1}{4}$  in, approx- ed. The bolts, Z, are two  $\frac{3}{4}$ -in bolts. There should be two efully placed so that the hook bears against them. There is a y for the hook to straighten and hence 1-in bolts are used. n of the plate in tension is evidently greatly in excess of that




Fig. 9B. Alternate Detail of Joint 1, Fig. 8

. 8. A better detail at Y, Fig. 9, is shown in Fig. 9A. It is fore that one-half the tension is taken by the notch at Y. The




Fig. 9c. Detail of Joint 1, of Truss Similar to Fig. 1

depth of the notch is  $1\frac{3}{4}$  in and the size of the metal block,  $1\frac{3}{4}$  by 3 by  $9\frac{1}{4}$ . The bolts are assumed to have a close fit in the block and in the plate and be

carry the stress in single she. At 10 000 lb per sq the area of the bolts is  $(27\,350/10\,000) = 2.735$  sq requiring two 1-in steel bolts (Table III, page 419). The thickness of the steel plate necessary to give sufficient bearing against the bolts  $\frac{1}{4}(13\,675) + 20\,000 \times 1$ , or .34 in. A  $\frac{1}{2}$ -in plate is therefore ample.

Joint 1, Fig. 8. An ordinary CAST-IRON ANGLE-BLOCK may be used in this particular case as shown in Fig. 9a.

Other Details for Joint Fig. 3. Another design for this joint, but for another truss, is shown in Fig. 1. The rafter and bottom chord are of long-leaf yellow pine and the metal parts of steel. The stresses are transmitted through 3 by  $\frac{3}{4}$ -in plates bearing against the ends of the wood, and from the plates to the SIDE PLATE

through the bolts in bending. The side plates should be drawn up against the wood by LAG-SCREWS, as shown, to prevent buckling when in compression.

shows a good application of the CAST-IRON ANGLE-BLOCK used in the shop of a blacksmith-shop of the Boston & Maine Railroad Company. The tensile and shearing values are provided for principally by a tenon on the end of the brace which is driven into the bottom chord as indicated by the dotted lines.

Fig. 1. Where a brace abuts against a rafter, as in this joint, one cut of the brace should bisect the angle made between the brace and the rafter and the second cut should be at right angles to this, as shown in Fig. 10. The brace is then set in a notch or mortise to keep the brace in place and to transmit the stress to the rafter. The purlin may be supported by a 3-in plank, as

Fig. 10a. Purlin-connection.  
Purlin on Top of Truss-chord

Detail of Joint 2, Fig. 1, with Rod Added



Purlin-connection  
with Steel-

Fig. 10c. Purlin-connection with Wooden Bearing-block

with Beam-hanger

Fig. 10. Some form of METAL HANGER, of the DUPLEX TYPE is used. In the truss shown in Fig. 1, there is no vertical rod at this joint. Many trusses have a rod there, and one is therefore shown in Fig. 10. The top of the rafter must have sufficient area to transmit the stress to the purlin. Other forms of purlin-connections are shown in Figs. 11 and 12.

King-Rod Truss. Fig. 11 shows the joint at the top of a KING-ROD TRUSS with a DUPLEX HANGER to support the purlin. The wrought-iron hanger for large trusses should extend along the top of each rafter a sufficient distance to permit its being fastened by LAG-SCREWS or BOLTS. Fig. 12 shows the use of a ROLLED PLATE in place of the DUPLEX HANGER.

Joint 2, Fig. 1. This should be made as shown in Fig. 13. The inclined side must be made between the two 6 by 6-in. pieces. In place of the 6 by 6-in. WOODEN WARRING & WELMONT IRON or STEEL PLATE may be used.




Fig. 11. Detail of Apex of King-rod Truss




Fig. 12. Alternate Detail for Apex of King-rod Truss




Fig. 13. Detail of Joint 3, Fig. 1




Fig. 14. Detail of Joint 2, Fig. 3

Joint 2, Fig. 3. The method of making the connections at this joint is shown in Fig. 14. The end-cut of the main brace is made as shown, the distance




Fig. 15. Alternate Detail of Joint 2, Fig. 3

From the center of the vertical axis of the inclined cut in the top chord of the main brace, a line is drawn at right angles to the cut. Then as also it requires that the distance from the center of the cut to the end of the brace. This

staff can only be used for the end-brace by making two notches as the dotted lines. A much better method is shown in Fig. 15, where BLOCK is used. The angle-block is made of very hard wood so that 1/2 of the brace is provided for, and it is notched into the chord a sufficient to transfer the horizontal component of the stress in the brace to the chord. A notch 1 in deep carries  $1100 \times 9\frac{1}{4} = 10450$  lb (Table I, page 1138) for a horizontal component of 27350 lb (Fig. 4), the notch is 1 in deep. This clearly shows that braces should be inclined  $5^\circ$  with the horizontal, and no weak details are created. The vertical rod carries a stress of 13492 lb. The top of the chord transfers a bearing across the grain. The stress of 200 lb (Table I, page 1138) the area is 67.4 sq in, and 8 by 9 by 3/4-in.

Fig. 1. This is shown in Fig. 16, and the above discussions cover all design.

Since it is not economical and often impossible to procure timbers, or 30 ft in length, it is necessary to make one or more SPLICES. The top-chord of a HOWE TRUSS is spliced by placing the timber end to end, and by spiking or bolting on side planks to keep them in place. The bottom chord cannot be treated in this manner, as it is in tension.

Splice or Tabled Fish-Plate of Wood. It is assumed that the bottom chord of the truss shown in Fig. 3 is to be spliced at the middle of the span. Fig. 17A shows this splice. It is assumed that the side pieces are of white pine.




Fig. 17. Splice of Bottom Chord of Truss

The total depth of the notches is  $48560 + (1100 \times 11\frac{1}{2}) = d = 3.84$  in (Table I, page 1138). Each notch, then, is about 2 in deep. The length of the table is  $l = \frac{1}{4} [48560 + (100 \times 11\frac{1}{2})] = 21$  in. The net thickness of each side

piece is  $560 / (700 \times 11\frac{1}{2}) = 3$  in, without deducting anything for the two end-pieces have less than the required area because of the required; hence a 12 x 12-in timber is required if this form of splice is used.

The proper dimensions are shown in Fig. 17A.

Fig. 17 shows an old and very efficient form of splice, proposed by the author to replace the form shown in Fig. 17A.

**Built-up Chord.** The top chord, when BUILT UP of 2-in planks, is kept together by spiking with two 3/4-in bolts at the ends of each plank. The bottom chord, which is in tension, should be so arranged that the ends of one strand are well removed from the ends in other strands. The

middle strand of a BUILT-UP CHORD is completely cut away to permit the passage of the vertical rods. The strands should be thoroughly spiked, and bolted every 2 ft, care being taken to see that the bolts do not come nearer than 5 in from the end of any plank. While BUILT-UP MEMBERS are in favor with builders




Fig. 17A. Alternate Detail for Splice of Bottom Chord

ers because the materials are readily obtained, yet for important structures the writer believes it is worth while to use a little more effort and pay a little more to get SOLID STICKS for truss-members.

**Wall-Joint of Scissors Trusses.** In SCISSORS TRUSSES the joint over the wall formed by the rafter and tie-beam should always be carefully proportioned




Fig. 18. Wall-joints for Scissors Trusses, Figs. 24 to 27, Chapter XXVI

to the stresses; otherwise the joint is liable to open and the wall to be pushed out. Much greater strength is required in this joint than in the wall-joint of a KING-ROD TRUSS of the same span, because the stresses in a SCISSORS TRUSS are usually at least twice and sometimes three or four times as great as in a truss with a horizontal tie-beam. For a SCISSORS TRUSS built of planks, as in Fig.

t through the center of each joint, with as many spikes as can be  
 l ordinarily give sufficient strength. For trusses like those shown in  
 27 of Chapter XXVI, one of the best methods of making the wall-  
 is the roof is quite flat, is that shown in Fig. 18, which is the detail  
 d joint where the stress in the tie-beam was 25 000 lb. It should be  
 at the WROUGHT-IRON STRAP is secured to the tie by LAG-SCREWS in-  
 OLTS. It is practically impossible to bolt a strap to each side of a  
 to get a good bearing for all of the bolts, owing to the difficulty in  
 holes straight; and if the holes are bored a little large, some bolts  
 on the wood and some may not. With LAG-SCREWS each screw is  
 et a good bearing in the wood. The holes in the two sides of the  
 , of course, be staggered, so that they will not come opposite each  
 e net sectional area of the strap should at least be equal to the stress  
 eam divided by  $2 \times 12\,000$  (Table I, page 1138). The number of  
 s, for both sides, is found by dividing the stress in the tie-beam by  
 ce of one screw. For the safe resistance of LAG-SCREWS used in this  
 lues given in Table V are recommended. In the joint shown in Fig.  
 ss in the tie-beam is 25 000 lb, and the wood is Douglas fir. The  
 therefore, require a sectional area in the strap of  $\frac{1}{2} (25\,000) / 12\,000 =$   
 nd twenty-three  $\frac{3}{4}$ -in lag-screws. Only thirteen are shown in Fig. 18.

Safe Resistance of Mild-Steel Lag-Screws When Used as in Fig. 18

crew in es	Safe resistance in pounds				Minimum thickness of strap in inches
	Oak	White pine	Douglas fir	Long-leaf pine	
3½	288	255	267	288	¼
4	512	454	474	512	¼
4	800	709	741	800	⅜
4½	1 153	1 022	1 067	1 153	⅜
5	1 569	1 391	1 453	1 569	½

d upon experiments made (1915-1916) by Professor H. A. Thomas.

ickness of  $\frac{3}{8}$  in, the width of the strap necessary to give a sectiona  
 sq in is  $1.05 / .375$ , or about 3 in. To this should be added the diam-  
 ag-screw to obtain the working width. Thus  $3 + \frac{3}{4} = 3\frac{3}{4}$  in. The  
 4 by  $\frac{3}{8}$  in in cross-section, as some additional strength is obtained by  
 , which it is necessary to insert to hold the timbers together while  
 being raised into position, and also to bring them tightly together  
 the strap. Fig. 19 shows another method of making this joint  
 be used with advantage when the inclination of the rafter is less  
 ne advantage in using this truss is that if it is erected ONE PIECE  
 e tie-beams may be put up first, thus providing a SEAT to receive  
 The strap prevents the end of the rafter from springing up. The  
 he bolt should be proportioned to the horizontal component of the  
 rafter. Fig. 20 shows a good form of joint to use at joint 5 of Fig.  
 XXVI, when it is desired to substitute a wooden tie for the rods  
 27. The sectional area of the strap and the number of lag-screws  
 proportioned by the rules given for Fig. 18.

Where iron or steel rods are used in wooden trusses, washers are  
 der the heads and nuts to properly distribute the loads on the  
 dimensions of the washers are determined by the allowable bear-

ing pressure on the wood and the magnitudes of the loads. Table VI gives the allowable loads which can be transmitted by standard round cast washers and rectangular washers bearing across the wood fibers. Table VII gives the dimension of standard round cast washers. The bearing areas of these washers




Fig. 19. Alternate Detail for Fig. 18

are too small for use on the softer woods and, therefore, except when the rods are small, it is better to use rectangular washers of iron or steel plate. Very large washers should be cast, and should have the form shown in Fig. 20A. The use of the ribs gives the required strength and saves considerable material




Fig. 20. Detail of Joint 5, Fig. 27, Chapter XXVI




Fig. 20A. Cast-iron Washer with Brackets

**Thickness of Rectangular Steel-Plate Washers.** The thickness of rectangular steel-plate washers can be found from the following formulas in which  $l$  is the distance from the edge of the plate to the nut and  $t$  the thickness of the plate. When used

On white oak.....	$l = 3.4 t$
On white pine.....	$l = 5.2 t$
On long-leaf yellow pine.....	$l = 3.9 t$
On short-leaf yellow pine.....	$l = 4.6 t$



**Safe Bearing Resistance of Cast-Iron Washers, in Pounds**

Round washers				
Area, <sup>π</sup> sq in	White pine, lb	Short-leaf yellow pine, lb	Long-leaf yellow pine, lb	White oak, lb
5.16	1 030	1 290	1 810	2 580
6.69	1 340	1 670	2 340	3 350
7.78	1 560	1 950	2 720	3 890
10.4	2 080	2 600	3 640	5 200
11.7	2 340	2 930	4 100	5 850
16.6	3 320	4 150	5 810	8 300
26.9	5 380	6 730	9 420	13 500
28.6	5 720	7 150	10 000	14 300
38.5	7 700	9 630	13 500	19 300
49.9	9 980	12 500	17 500	25 000
62.8	12 600	15 700	22 000	31 400
77.1	15 400	19 300	27 000	38 600
92.9	18 600	23 200	32 500	46 500
110.2	22 000	27 600	38 600	55 100


Rectangular washers				
Area, <sup>π</sup> sq in	200	250	350	500
24	4 800	6 000	8 400	12 000
32	6 400	8 000	11 200	16 000
36	7 200	9 000	12 600	18 000
42	8 400	10 500	14 700	21 000
48	9 600	12 000	16 800	24 000
54	10 800	13 500	18 900	27 000
60	12 000	15 000	21 000	30 000
64	12 800	16 000	22 400	32 000
72	14 400	18 000	25 200	36 000
80	16 000	20 000	28 000	40 000
96	19 200	24 000	33 600	48 000
100	20 000	25 000	35 000	50 000
110	22 000	27 500	38 500	55 000
120	24 000	30 000	42 000	60 000
140	28 000	35 000	49 000	70 000
144	28 800	36 000	50 400	72 000
168	33 600	42 000	58 800	84 000
192	38 400	48 000	67 200	96 000
196	39 200	49 000	68 600	98 000
224	44 800	56 000	78 400	112 000

bearing on the wood are given for round washers. For rectangular washers, if the length is given, no allowance being made for holes.

other forms of connections are in use and their proper design is determined by the methods explained in Chapter XII and in this chapter. All details are not suitable for all cases and the designer must use common sense in the selection of the PARTICULAR TYPE to be used. Wood is very variable in its properties and consequently different grades of wood are used for certain kinds of stress and smaller factors.

for others. Heavy trusses, in which the sizes of the members are selected according to the magnitudes of the stresses, should be very carefully worked in every detail, while small trusses with large excess of material do not demand as much care.

Table VII. Proportions of Standard Cast-Iron Washers



Diam of bolt, <i>d</i> in	<i>D</i> in	<i>d''</i> in	<i>d'</i> in	<i>T</i> in	Weight, lb	Bearing area, sq in
1/2	2 5/8	1 3/4	9/16	5/8	1/2	5.16
5/8	3	1 7/8	1 1/16	3/4	3/4	6.69
3/4	3 1/4	2 1/8	1 3/16	7/8	1 1/4	7.78
7/8	3 3/4	2 1/2	1 5/16	7/8	1 1/2	10.40
1	4	2 3/4	1 7/16	1 1/8	2 1/2	11.70
1 1/8	4 3/4	2 3/4	1 3/16	1 1/8	3	16.60
1 1/4	6	3	1 5/16	1 3/8	5 3/4	26.90
1 1/2	6 1/4	3 1/4	1 5/8	1 1/2	6	28.60
1 3/4	7 1/4	3 3/4	1 7/8	1 3/4	9 1/2	38.50
2	8 1/4	4 1/4	2 1/8	2	17 1/4	49.90
2 1/4	9 1/4	4 3/4	2 3/8	2 1/4	20	62.80
2 1/2	10 1/4	5 1/4	2 5/8	2 1/2	27 1/4	77.10
2 3/4	11 1/4	5 3/4	2 7/8	2 3/4	36	92.90
3	12 1/4	6 1/4	3 1/8	3	46	110.20

For sizes not given,  $D = 4d + \frac{1}{4}''$   
 $d' = d + \frac{1}{8}$

$d'' = 2d + \frac{1}{4}$   
 $T = d$

4. Joints of Steel Trusses

**Trusses with Riveted Joints** are usually made with ANGLES for the web members and generally for the chords, although the latter are sometimes made of a pair of CHANNELS or of two ANGLES and a WEB-PLATE. The members are connected at the joints by means of GUSSET-PLATES, to which all of the members are RIVETED. Typical examples of riveted joints in roof-trusses are shown in Figs. 22 to 24E. When the rafter or chord has a WEB-PLATE, as in Fig. 23, the web-members are riveted to this plate and a GUSSET-PLATE is not required except at the end-joint and apex, as shown in Figs. 23A and 23E. In order that there shall be no twisting, it is necessary to make the principal members of the truss DOUBLE, so that the gusset-plates can be riveted between them. When single angles are used for web-members and two such members come at a joint they should be riveted to opposite sides of the gusset-plates. For equal strength the thickness of the gusset-plate should be such that the BEARING of the rivets equals the strength of the rivets in DOUBLE SHEAR, the thickness, however, not exceeding the combined thickness of the two angles. Practical considerations seldom make the gusset over 3/8 in thick for ordinary construction.

joints, which should be done to a scale of not less than 1 in members should be arranged, when practicable, so that the lines of centers of gravity will coincide with the lines of the truss-meet at a single point, as in Fig. 21. This is not always prac-

practicable. The

Fig. 21. Riveted Truss-joint with Truss-diagram Lines

remained according to the stress in that member, the resistance is considered for both SHEARING and BEARING. The method of determining the number of rivets in a joint is explained in Chapter XII, and clearly the application to truss-joints, the joints for the Fig. 7 will be designed.

considerations, Truss of Fig. 7. It is assumed that the truss is made of three parts, making all the joints SHOP-RIVETED except those at each end of the piece *EH*. All gusset-plates are to be all rivets  $\frac{3}{4}$ -in, except in the 2-in legs of angles, where  $\frac{1}{2}$ -in are used. Since the bearing of a  $\frac{3}{4}$ -in plate on a  $\frac{3}{4}$ -in rivet at 18 000 lb per sq in (Table I, page 1138) is 5 630 lb, or at 18 000 lb per sq in (Table II, page 419) is 5 060 lb, and the resistance of the rivet in double shear, 5 060 lb (Table III, page 419), the number of rivets in all the joints is determined by bearing value. Only one leg of the angles will be connected



Fig. 21. Riveted Truss-joint with Truss-diagram Lines




Fig. 22A. Detail of Joint D, Fink Truss, Fig. 7

ate as about 80% of the full strength of the angle is thereby not less than three rivets are used. The use of HITCH-ANGLES in the leg has but little influence in increasing the efficiency of the joint. Six rivets may be considered the minimum number in any case of the unimportance of the member.

9. The top-chord stress is 23 500 lb, and if one rivet carries the gusset-plate, five rivets will be required to carry this total

stress. In like manner four rivets are required for the bottom chord. The supporting force or the reaction is transferred to the gusset through the bottom chord prolonged. In this case the reaction is about 8 800 lb which requires 1 rivets. Fig. 22 shows the arrangement of this joint at the expansion-end.

**Joint D, Fig. 7.** The web-members each require less than one rivet, but two or three should be used. Since the top-chord angle is continuous, the number of rivets in it is determined by the difference between the two adjacent stresses and the load of the purlin if it rests on the chord. Here again the number of rivets required falls below the minimum number. Fig. 22A shows this joint.

**Joint E, Fig. 7.** The piece *CE* requires four rivets and the web-members the minimum number permissible. The piece *EH* requires, at 20 000 lb per sq




Fig. 22a. Detail of Joint E, Fink Truss, Fig. 7




Fig. 22c. Detail of Joint E and Splice in EH, Fink Truss, Fig. 7

bearing value,  $12\,500/5\,630 = 2.22$  rivets; but as this connection is one to be made IN THE FIELD, it is customary to increase the number 25%. This makes the required number three. Sometimes the outstanding legs are spliced to the member *CE* by a plate. Without doubt this increases the strength of the joint but it is doubtful if the increase in strength is enough to offset the extra cost. Fowler's specifications do not permit the piece *EH* to be connected to the gusset-plate. They specify that the connection shall be made upon the right of *E*. This arrangement allows the use of a smaller gusset-plate at *E* which may

be counterbalanced by the additional metal required for the splice beyond *E*. (Figs. 22a and 22c.)




Fig. 22d. Detail of Joint G, Fink Truss, Fig. 7

required for the FIELD-CONNECTION. In this case the top chord requires four rivets and the web-member three. Two rivets may be used in the sag-tie (Fig. 22d.)

**Field-Connections.** Bolts are often used instead of rivets for making FIELD CONNECTIONS. If the bolts fit the holes snugly, there is no serious objection to their use. In fact a good bolt is better than a poor rivet. For important work, however, bolts should not be used unless turned true to size and driven into the holes. Open holes or holes for FIELD-RIVETS are indicated by BLACK CIRCLES.

**Shop-Drawings.** It is not advisable for the architect to make complete drawings for the steelwork. He should make what are usually designated GENERAL DRAWINGS. These are made to scale and give the general dimensions

**Joint G, Fig. 7.** The pieces *BG* and *FG* are SHOP-RIVETED to the gusset on one side and FIELD-RIVETED on the other. In order to make the joint symmetrical, the number of SHOP-RIVETS is made the same as required for the FIELD-CONNECTION.




Fig. 22. Fink-truss Diagram. (See, also, Figs. 23A to 23E) ]




Fig. 23A. Detail of Joints A, B and C of Fig. 23




Fig. 23B. Detail of Joint D, Fig 23.




Fig. 23c. Detail of Joint E, Fig. 23

and sizes of the various members, and show each rivet approximately in its proper position. The manufacturer who fabricates the structure prefers to make his own SHOP-DRAWINGS to conform with his standards and methods.

**Examples from Practice.** Figs. 23 to 23E show the details of a modern shop-truss. These details were taken from the SHOP-DRAWINGS but with the rivet-spacing omitted. No metal under  $\frac{5}{16}$  in thickness, or rivets under  $\frac{3}{4}$  in




Fig. 23D. Detail of Joint F, Fig. 23




Fig. 23E. Detail of Joint G, Fig. 23

in diameter, are used. Another point may be mentioned in connection with this truss; very few BEVEL-CUTS are made. The contrary appears to be the case for the details of the very light truss shown in Figs. 24 to 24E, in which BEVEL-CUTS are made on the angles and more cuts than necessary on the gusset plates. These two trusses were designed by manufacturers widely separated





Fig. 24. Fink-truss Diagram. (See, also, Figs. 24A to 24F)

and are quite different in their details; and the variations emphasize the fact that the architect should not attempt to make SHOP-DRAWINGS.

**Trusses with Knee-Braces.** Fig. 25 represents joint 1 of Fig. 55, Chap. XXVI, and was engraved from the WORKING DRAWING made by the New Jersey Steel and Iron Company, Trenton, N. J. Another detail of a truss-connected to a column is shown in Fig. 26. This was used in the template-shop roof-truss at the Ambridge plant of the American Bridge Company, Ambridge, Pa. Fig.

4000

**Fig. 24A. Detail of Joint A, Fig. 24**



**Fig. 24a. Detail of Joint B, Fig. 24.**

•

Fig. 24c. Detail of Joint *D*, Fig. 24

.

/ D

•

Fig. 24d. Detail of Joint *F*, Fig. 24

•



Fig. 24x. Detail of Joint C, Fig. 24



p. 25. Detail of Joint 1, Fig. 55, Chapter XXVI

shows the wall-end of a small truss supported by brick walls. The intersection of the STRESS-LINES is approximately in a point above the center of the support.

•  
•  
•

Fig. 26. Connection of Steel Truss with Steel Columns




Fig. 27. Wall-end of Steel Truss. Support and Anchoring-details

This condition is seldom considered by architects. Usually it is possible without any extra expense to satisfy this requirement and thereby to a great extent prevent unknown bending-stresses.

### 5. Purlins and Purlin-Connections

Where the roofing is supported directly on the PURLINS, as is general in light steel roofs, the purlins and trusses are usually spaced so near that SIMPLE ROLLED SHAPES may be used for the purlins. For




Fig. 28. Purlin-connections. Steel Clips, Angles and Z Bars




Fig. 29. Purlin-connections. Steel Sections with Wooden Nailing-strips

In trusses of from 8 to 10 ft, ANGLES are commonly used, and for Z BARS, CHANNELS and I BEAMS. WOODEN PURLINS are often used in trusses. If STEEL PURLINS support wooden rafters or plank roofing, a STRIP of wood is bolted to the purlin, as shown in Fig. 29. When the distance between purlins is large, a line of  $\frac{3}{8}$ -in rods should run from end to end through the purlins, to prevent them from twisting out of the plane of the roof. The purlin at the ends should be designed to take the vertical compression stress in these rods.

**Connections.** Figs. 28, 29 and 30 show a few of the various methods of fastening the purlins to the trusses.

**Purlins.** Fig. 31 shows the cross-sections of RECTANGULAR WOODEN PURLIN and of ROLLED STEEL SHAPES employed for purlins. See page 1170, when using wooden purlins, for the stress in the outer fiber is true to the axis with reference to the PRINCIPAL AXES of the section. Then, if the axis does not lie in the plane of the loading, the loading must be resolved into two components, respectively parallel to the two principal axes. (See page 573 and 593.)




Fig. 30. Purlin-connection. Braced Channel

Let  $S'$  = the fiber-stress with reference to the principal axis,  $AA$ , for the rectangle, 1-1 for the I beam and channel, and 4-4 for the angle and Z bar.  $M'$  = the bending moment of the component of the load which lies in the plane perpendicular to the above axis.  $I'$  = the moment of inertia of the section with




Fig. 31. Sections of Wooden and Steel Purlins

reference to the above axis.  $c'$  = the distance of any selected fiber from the above axis. For the other principal axis use  $S''$ ,  $M''$ ,  $I''$  and  $C''$ ; then if  $S$  = the resultant fiber-stress,

$$S = S' + S'' = M'c'/I' + M''c''/I''$$

For the rectangle,

$$S = S' + S'' = 6M'/bd^2 + 6M''/b^2d$$

For the channel and I beam,

$$S = S' + S'' = M'd/2I_{1-1} + M''b/2I_{2-2}$$

For the angle and Z bar,

$$S = S' + S'' = M'c'/I_{4-4} + M''c''/I_{3-3}$$

The application of these formulas offers no difficulties except in the case of ANGLES and Z BARS. For the other forms, the values of  $I$  and  $c$  are given in the tables of properties of the sections (Chapter X). The locations of the principal axes for the Z bars and angles are also given in the tables, but the values of  $c$  are not given for any of the fibers. The easiest way to get the values in any particular case is to draw the section of the angle or Z bar full size, locate the principal axes and then measure the actual distances,  $c$ .

## CHAPTER XXIX

## WIND-BRACING OF TALL BUILDINGS

By

N. A. RICHARDS

OF

PURDY &amp; HENDERSON, INC., CIVIL ENGINEERS

## 1. Data for Wind-Pressure. Building Laws

**Buildings of Modern Construction**, that is, buildings with skeleton light curtain walls or filler walls, require that resistance to wind be considered with care. The proportions of a building and the arrangement of the walls determine to what extent special bracing must be provided. Building ordinances in the larger cities usually require consideration of wind-pressure. Where such ordinances do not definitely fix wind pressure, a unit force of 30 lb per sq ft of surface is generally proper and adequate. (See, also, page 150.)

**Laws.** The following are extracts \* from the building ordinances of New York City, Chicago, Philadelphia and Baltimore with reference to wind-

**New York (1917)**

**CONSIDERED.** All buildings over 150 ft in height and all buildings in which the height is more than four times the minimum width dimension, shall be designed to resist a horizontal wind pressure of 30 pounds per every square foot of exposed surface measured from the ground to the top of the structure, including roof, allowing for wind in any direction.

**REQUIREMENTS.** The overturning moment due to wind pressure shall not exceed 10 per cent of the moment of stability of the structure, unless the structure is anchored to the foundation. Anchors shall be of sufficient strength to carry the excess overturning moment, without exceeding the working stress of the anchors.

**ALLOWABLE STRESSES.** When the stress in any member due to wind does not exceed 50 per cent of the stress due to live and dead loads, it may be neglected. When such stress exceeds 50 per cent of the stress due to live and dead loads, the working stresses prescribed may be increased by 50 per cent in design of members to resist the combined stresses."

**Chicago (1915)**

**Buildings and structures** shall be designed to resist a horizontal wind pressure of 30 pounds per square foot for every square foot of exposed surface. In no case shall the overturning moment due to wind pressure exceed 10 per cent of the amount of stability of the structure due to the dead load.

**Stresses.** The stresses produced by wind forces combined with those from live and dead loads shall not be less than required if wind forces be neglected. The unit stress may be increased fifty per cent over those given above; but the stresses shall not be less than required if wind forces be neglected."

**Remarks.** Form in general not edited or changed. Some paragraph-captions have been added by the editor.

## Philadelphia (1915)

**WIND PRESSURE.** "In all buildings allowances shall be made for wind pressure, which shall not be figured at less than thirty pounds per square foot elevation where erected in open spaces or upon wharves. In high buildings erected in built-up districts, the wind pressure shall not be figured for less than twenty-five pounds at tenth story, two and one-half pounds less on each succeeding lower story, and two and one-half pounds additional on each succeeding upper story, to a maximum of thirty-five pounds at fourteenth story and above."

**WIND BRACING.** "Wind bracing may be provided by making the connection joint between girders and columns sufficient for the vertical load as well as bending due to side pressure; or brackets may be placed at this joint, proportioned for the side pressure; or diagonal bracing may be placed between columns proportioned to transfer the shear of the side pressure to the footings."

**BASE OF COLUMN MUST BE ANCHORED.** "Where buildings are narrow and tall, so that the overturning due to wind is more than the down pressure of unloaded building, the base of column must be anchored down to a sufficient foundation to counteract this upward strain." \*

## Baltimore (1914)

**WIND PRESSURE.** "All new buildings exposed to wind shall be made strong enough to resist a horizontal wind pressure in any direction of thirty pounds per square foot of exposed surface, measuring the entire height of the building."

**CALCULATION OF.** "The additional loads caused by the wind pressure on beams, girders, walls and columns must be determined by calculation and added to other loads for such members, as provided for in Section 19 of this Article."

**SPECIAL BRACING.** "Special bracing shall be employed wherever necessary to resist the distorting effect of the wind pressure."

**OVERTURNING MOMENT.** "In no case shall the overturning moment due to the wind pressure exceed fifty per cent of the moment of the stability of the structure."

**Magnitude of Unit Stresses Used for Wind-Pressure.** As the above extracts indicate, it is generally considered proper to use **HIGH UNIT STRESSES** when allowing for wind-pressure. The practice is based on the assumption that the **HIGHEST UNIT WIND-PRESSURE** will occur very infrequently and that the duration usually will be limited to a very few moments. It should be noted that the combined stresses due to wind-loads and dead and live loads shall not exceed ordinary stresses by more than 50%. If stresses developed by wind alone do not exceed 50% of those due to dead and live loads, they may be neglected.

## 2. Conditions Determining or Affecting Wind-Bracing

**Construction which Resists Wind-Pressure.** The dead weight of a building, the exterior walls, the interior partitions and the ordinary connections of beams to columns, all aid in resisting wind-pressure, but to a degree which is not determinable in any exact way; and these factors vary greatly, also, in different buildings. Any allowance for these factors must be largely a question of pure guesswork, or it may be judgment, based on the resistance which other buildings have offered when no special bracing was provided. It is therefore best to make special bracing take care of all, or very nearly all, of an assumed **MAXIMUM PRESSURE**, when the building under consideration is unusually light construction, or when its proportions are such as to make resistance to wind pressure a prime consideration.

\* Stress is meant.

† This refers to a section of the Baltimore building laws.

**Width as Affecting Wind-Pressure.** It is generally safe to assume in structural designs for buildings ten stories or less in

height, where the average width is not less than one-third the height. It is also usual to omit special provision for wind-bracing in higher buildings where the width is two-thirds the height, or more. The writer believes the above approximations represent conservative practice, so far as general rules are possible.

**Dead Load as Affecting Wind-Pressure.** A building should not be so proportioned that the OVERTURNING MOMENT of a wind-pressure of 30 lb per sq ft exceeds 75% of the available RESISTING MOMENT of the dead load. If necessary, the columns should be anchored to the foundations.

3. General Theory of Wind-Bracing

**Buildings Considered as Cantilevers.** Buildings are usually considered to resist wind as





Fig. 1. Section and Plan of Wind-braced Building

**RDERS** or trusses, planted in the earth. Assuming a building dimensions shown in section and plan in Fig. 1. with a wind-

pressure against side *A*, the walls *A* and *B*, together with the column beams, etc., in these walls, are the **FLANGES** of the girders. Walls *C* and *D* with their framing, together with other intermediate lines of vertical framing form the **WEB** of the cantilever and transmit the vertical shears. Steel bracing in horizontal planes is seldom necessary, as ordinary floor-construction are generally sufficient to transmit wind-loads to the vertical bracing. In some cases, however, it is necessary to add steel bracing in the floors. Such a case is found in the tower of the new Custom-House, in Boston, Mass. The elevators and stairs are next to the west wall throughout the typical stories. Under this arrangement there is no adequate provision in the ordinary floor-construction for a wind-pressure on the north or south face to reach the resisting bracing in the west face, as the various open wells cut off nearly all direct connection between the floors and this wall. Flat plates were therefore added on top of the floor-beams at each floor-level, running out from the wall girders behind the wells into the main floor-construction, and attached at each end with connections sufficient to transmit the horizontal increment of the wind-pressure on each floor to the bracing which resists it.

#### 4. Arrangement of Wind-Bracing

**Usual Position of the Bracing.** As wind-pressure is assumed to be uniformly distributed over the face of a building, it is best to arrange systems of bracing, as nearly as may be, symmetrically about the axis of each face. It is generally easier to conceal in the exterior walls the required knees, gussets, other braces, and bracing is usually placed there. When the lines of bracing have been selected, the areas of wall-surfaces which bring wind-pressure to the bracing are readily determined.

**Bracing of Buildings of Irregular Plan.** Some buildings are of such shape that it is impossible to provide bracing of equal stiffness in lines symmetric about the center of wind-pressure. This is notably true when the plan is **TRIANGULAR**, as in the so-called Flatiron Building or in the Times Building in New York City. The result is a tendency in such buildings to **TWIST ABOUT VERTICAL AXIS**. The analysis of the resistance offered by a building to a twist of this sort is unsatisfactory and complicated. The stresses produced in the usual case, however, are small, if not negligible. In the examples mentioned above, provision against twist is made by the use of deep spandrel girders around the building at each floor-level.


#### 5. Types of Wind-Bracing

**Ordinary Beam and Girder Column-Connections.** Wind-bracing should be so proportioned that the joints between horizontal and vertical members be sufficient to prevent the distortion of the frame, and the main horizontal and vertical members sufficient to resist any bending moments produced through the joints, as well as any direct loads coming on them. The **ORDINARY CONNECTIONS** of steel beams to steel columns (Fig. 2) provide considerable resistance to a distortion from side thrust. This is also true, of course, of connections between beams and columns made of cast iron or concrete; but as these types are not adapted to construction where wind-bracing is required, they will not be considered. A usual connection for beams or girders to columns consists of **CLIP ANGLES** above and below the beam, and perhaps a **STIFFENER** below, if the beam is large. Usually, in high buildings, four rivets are used to connect either clip to the clip-angles above and below, and four to connect each clip to the column. The value of four rivets, in single shear, multiplied by the depth of the beam



**RESISTING VALUE** of such a connection against a moment due to side wind on buildings it is usual to specify two rivets instead of four in the case of very high or narrow buildings, six rivets are some-

**of Beam and Girder-Connections to Wind-Pressure.** It is noted that the connections of all beams or girders (running in the



Heavy Girder and  
Column-connections

Fig. 3. Heavy Girder and  
Column-connection

as the wind) to columns act at their full value to resist the wind. It is not entirely wrong, because the many connections could probably not work at the same time, and also because building-frames are seldom made of such a result could be possible, under any rational assumption, as to the distribution of the vertical shears. **SIDE CLIPS** are sometimes used in column-connections to furnish additional stiffness. They are not, however, as on most beams they are not deep enough to help

**Connections in Wind-Resistance.** Column-connections made very heavy, as shown in Fig. 3. A connection of this kind is used to resist a large **TWIST**. The **RESISTING VALUE** is, of course, the resisting moment of the rivets connecting the beam to the clip-angle connection of the angles to the column. This type is used where no wind is provided for in a very large number of connections. In the column-connections, throughout the building. Such an

arrangement was used in the Hudson Terminal Buildings, New York City. There are several objections to this type of connection. Double beams or girders are required, and the resulting finish is awkward in appearance; the cost, also, of double, compared with single, beams and girders, is high. The additional fireproofing, also, increases the expense, and on the whole, it does not generally prove a satisfactory method of stiffening a building.

**The Gusset-Plate Type of Wind-Bracing.** In addition to ordinary beam and girder-connections, as described in the preceding paragraphs, there are several distinct types of special wind-bracing commonly employed. Perhaps the most common form is the GUSSET-PLATE, shown in Fig. 4. This is not usually an economical type, as it requires much field-riveting and results in large bending moments in the columns and girders. It accommodates itself well, however, to walls in which there are openings, and is generally easily concealed by architectural treatments.

**The Knee-Brace Type of Wind-Bracing** shown in Fig. 5 is also commonly used where wind-bracing is placed in exterior walls.

**The Sway-Rod Type of Wind-Bracing** shown in Fig. 6 is theoretically the most economical type of wind-bracing, but is now little used. It is difficult to arrange openings in walls or partitions in which the sway-rods are placed and they cut up the masonry considerably.

**The Latticed-Girder Type of Wind-Bracing** shown in Fig. 7 is sometimes used where deep bracing is desirable for stiffness, and where the stresses are light.

**The Portal Type of Wind-Bracing** shown in Fig. 8 is cumbersome and expensive, but is sometimes necessary where large openings are required between columns.

## 6. Computation of Wind-Stresses

The Shears to be Transmitted by Wind-Bracing of any Type are the same in any given case, but the bracing of each type transmits these shears in different manner, and thus each must be considered separately. It is as though a PLATE GIRDER with SOLID WEB were set on end in the ground, a side thrust exerted, and the WEB THEN CUT AWAY at successive levels corresponding to the stories in a building. The amount of the shears to be transmitted between the flanges would not vary as holes in the web were made, but the road by which the shears traveled would need to be determined by the character of the resulting construction after the holes were cut; and the exact character of the secondary stresses, also, set up in the remaining portions of the web, would depend entirely upon the number and size of holes and their position in the web. The investigation of the shears and moments taken care of by the individual members of a bracing-system may be likened to a study of the secondary stresses in the mutilated web in the imaginary plate girder described above. For a building it is generally convenient to determine the VERTICAL-SHEAR INCREMENTS at each level of bracing, and use these increments in the further analysis of the bending moments and shears in the individual members of the system.

## 7. Illustration of Method of Computing Wind-Stresses

**Thrusts, Vertical Shears and Moment-Increments.** If bracing is placed in the walls *C* and *D*, Fig. 1, it is assumed that one-half the length of the building contributes pressure to each line. Let it be further assumed, for the present, that these lines of bracing are the only features of the construction offering resistance to wind-bracing against side *A*. Then, assuming the wind to blow

re per sq ft, perpendicular to side *A*, there are **HORIZONTAL THRUSTS** on each line of bracing, of 50 by 12 by 30 lb, or 18 000 lb. Re-  
 e I, page 1178, there are found listed in the second column of the  
 izontal thrusts at each floor. It is assumed that no additional  
 reached the building below the fourth floor. In the third column  
 se horizontal thrusts,  $\Sigma H$ , are summarized from the top down to  
 giving the **TOTAL HORIZONTAL THRUSTS**. For example, 202 500 lb  
 izontal thrust down to and including the tenth floor. Each tier  
 t transmit a **VERTICAL SHEAR** equal to the difference in flange-  
 a point midway in the story above the tier in question, and a  
 the story below. This difference of flange-stress can, of course,  
 certaining the difference in bending moments between the two  
 ling by the effective depth of the system, as in a plate girder or  
 ow appear that the differences in moments applying to each tier  
 ound and tabulated. These will be called the **MOMENT-INCRE-**  
 ave been tabulated for the assumed case in the fifth column of  
 ourse, the sum of all the moment-increments must equal the  
 ING MOMENT of the wind. The simplest way to obtain the  
 it for any tier is to multiply the total horizontal thrust,  $\Sigma H$ ,  
 al in question by the distance between points midway in the  
 below the tier. Thus, for the tenth floor, 202 500 by 12 equals

**nts of Vertical Shear** are found by dividing the moment-  
 e effective depth of the cantilever, in this case, 47 ft. The  
 ENTS are listed in the sixth column of the table. It is  
 full depth between outside columns as the effective depth of  
 his is not strictly correct where there are four or more columns  
 bracing, but the assumption is made on the ground that the  
 nish flanges which are so many times more effective than the  
 uns that the latter may be neglected. If there are a number  
 lane of the bracing, say six or seven, this assumption becomes  
 te, and the effective depth should be reduced. The function  
 erebefore stated, is to carry between the flanges at each floor-  
 s of vertical shears thus found. The summation of all the  
 from the top down gives the **TOTAL VERTICAL LOAD** and UP-  
 on the corner-columns, or more correctly, on the outside

**Shear.** In this assumed case, the total uplift exceeds the  
 live loads on the corner-columns. This, however, is not  
 re are sufficient means furnished for transferring any excess  
 the walls *A* and *B*, which act as flanges to the wind-resisting  
 rule, the side walls of a city building are not much reduced  
 higher buildings there are usually spandrel beams in the  
 With such an arrangement a considerable amount of EXCESS  
 are of. In some cases special bracing may be necessary, at  
 s of walls *A* and *B*.

**al or Flange-Stress.** When considering any question  
 AL LOAD OR UPLIFT, such as the one described in the pre-  
 should be kept in mind that totals should be used without  
 . Vertical forces forming couples to resist the wind must  
 hey are transmitted through the masonry walls or through  
 Referring again to the illustration of the plate girder set  
 ertical shears are dependent only on the force of the wind

and the effective depth of the girder. The exact WEB-STRESS will vary with the form and arrangement of the web, but the TOTAL VERTICAL OR FLANGE-STRESS must remain the same in any case.

**Indeterminate Resistance-Factors.** An analysis which makes no allowance for the resistance of walls, ordinary connections, etc., to wind is fairly direct and simple, and the bracing can be proportioned with as much precision as any structural feature. When the wind-resistance of a building is a primary consideration, as in a tower, the analysis should be made thus, for only in this way can a result be obtained, where it is not required to rely on almost unsupported judgment for the value of INDETERMINATE FACTORS OF RESISTANCE. When, however, ordinary buildings of usual proportions are under consideration, it is customary and well to make allowance for the INDETERMINATE FACTORS, to the best of one's judgment. This is necessary for economy, and is perfectly proper so long as usual cases are to be dealt with.

Table I. Thrusts, Shears, Moment-Increments, etc., for the Building Shown in Fig. 1

I Floor	II Horizontal thrust at each floor, $H$	III Total horizontal thrusts from roof to each floor, $\Sigma H$	IV Arm, $A$	V Moment-increment, $M$	VI Vertical increment, $V$	VII Total vertical increments from roof down, $\Sigma V$	VIII Corrected vertical increment,
	lb	lb	ft	ft-lb	lb	lb	lb
Roof	4 500	4 500	6	27 000	550	550	.....
20	18 000	22 500	12	270 000	5 750	6 300	.....
19	18 000	40 500	12	486 000	10 350	16 650	.....
18	18 000	58 500	12	702 000	14 950	31 600	.....
17	18 000	76 500	12	918 000	19 500	51 100	.....
16	18 000	94 500	12	1 134 000	24 100	75 200	.....
15	18 000	112 500	12	1 350 000	28 700	103 900	.....
14	18 000	130 500	12	1 566 000	33 300	137 200	.....
13	18 000	148 500	12	1 782 000	37 900	175 100	4 600
12	18 000	166 500	12	1 998 000	42 600	217 700	9 300
11	18 000	184 500	12	2 214 000	47 200	264 900	13 900
10	18 000	202 500	12	2 430 000	51 800	316 700	18 500
9	18 000	220 500	12	2 646 000	56 400	373 100	23 100
8	18 000	238 500	12	2 862 000	61 000	434 100	27 700
7	18 000	256 500	12	3 078 000	65 600	499 700	32 300
6	18 000	274 500	12	3 294 000	70 200	569 900	36 900
5	18 000	292 500	12	3 510 000	74 700	644 600	41 400
4	18 000	310 500	12	3 726 000	79 300	723 900	46 000
3	.....	310 500	12	3 726 000	79 300	803 200	46 000
2	.....	310 500	15	4 657 500	99 200	902 400	65 900
1	.....	310 500	15	4 657 500	99 200	1 001 600	65 900

**Scheme for Developing Special Bracing.** The writer offers the following as a reasonable and consistent scheme for DEVELOPING SPECIAL BRACING when such allowances are considered. Unfortunately, it does not seem possible to recommend any method of determining the correct allowances, except such general guides as are mentioned in Subdivision 2, page 1172. In each instance some one familiar with construction and usual practice should decide how

at the top it will be safe to assume the building rigid and secure against any special bracing. In this case, let it be assumed that the building is safely resisting the wind, without the aid of special bracing, as far as the thirteenth floor. Then, assuming that the walls, beam-connections, are reasonably the same in the floors below, it is fair to say that the increment at the fourteenth floor can be deducted from the increment at each floor below.

**Corrected Vertical Increments.** The CORRECTED VERTICAL INCREMENTS in this manner should be used only in the proportioning of special bracing. The overturning moment of the wind, and the full vertical shears, should be considered, considering all other effects of the wind and the resistance of the building. It should also be borne in mind that this method of proportioning is, at best, largely dependent upon individual opinion, and in any case it is far better to err on the safe side, even to the extent of disregarding the uncertain factors of resistance. The CORRECTED VERTICAL INCREMENTS for the assumed case have been listed in the eighth column of Table I. Since the flanges of the building, acting as an upright cantilever, have been assumed concentrated in the outside walls *A* and *B* (Fig. 1), it follows that the VERTICAL-SHEAR INCREMENTS will be constant from outside to inside.

## Analysis of Stresses in Different Types of Wind-Bracing

**Horizontal Thrusts,** which must be carried by the bracing at each level, are small and can usually be neglected. The MAXIMUM THRUST at each level can be determined by the horizontal force of the wind on the one story, for example,

**Horizontal Thrust.** The horizontal thrust must carry the horizontal force of the wind on each story, which is usually small compared with the shearing force in the columns and can be neglected.

**Gusset-plate Type of Wind-bracing.** Fig. 4 represents the influence of the gusset-plates on the frame.

Fig. 4. Gusset-plate Type of Wind-bracing

Fig. 5. Knee-brace Type of Wind-bracing

There is a tendency to distort the frame, changing the angle between the vertical members; that is, the columns and girders. For this investigation, a level is considered, with gusset-plates at either end, as shown. These plates act to prevent the distortion, and since they both, at either end, re-

sist the same wind-action, the twisting moment in each has the same sign. But they twist in the same direction at opposite ends of the girder, there is somewhere along the girder and between the gussets a POINT OF INFLECTION OR A POINT OF BENDING. The position of this point varies with the relative strength of the gussets, but for simplicity it is usually assumed midway between them and they are then proportioned to take care of the resulting moments. Let the point of inflection in the example be thus taken. As there is no bending moment at this point, the bending moment at any other point on the girder may be found by multiplying  $V$ , the increment of vertical shear for the level in question, by the distance from the point of inflection. So, at the toe of the gusset-plate, the bending moment on the girder equals  $V$  multiplied by  $e$ , and this is the MAXIMUM BENDING MOMENT ON THE GIRDER. The flange-stress having been determined from this bending moment, it is possible to fix the number of rivets required to fasten the flanges to the gusset. The connection of the web to the gusset must provide for a shear equal to  $V$ .  $V$  multiplied by  $f$  gives the moment produced through the gusset at the face of the column. The rivets connecting the gusset to the column must be sufficient to resist this moment.

**Points of Inflection** occur in the columns midway between the gussets, just as in the girders. The bending moment in the column may be obtained approximately by assuming the moment exerted through the gusset-plates to be applied in the form of a couple acting at points two-thirds of the way out from the center of the gusset to the tips, as indicated. The MAXIMUM BENDING MOMENT IN A COLUMN will then be the horizontal force  $P$  multiplied by  $d$ .  $P$  is obtained by multiplying  $V$  by  $l$  and dividing by  $c$ ,  $l$  being the distance from the inflection point in the girder to the axis of the column, and  $c$  being the distance between the inflection-points in the column above and below the girder.

**Gusset-Plates on Both Sides of Column.** If there are GUSSET-PLATES ON TWO SIDES of a column, as is usual on interior columns, the maximum bending moment in the column will be the sum of the maximum moments due to each gusset. Gusset-plate connections are easily arranged with plate girders or with double channels, or even with I beams.

**Stresses in Knee-Braces.** Let Fig. 5 represent a typical panel of knee-bracing. As described in the preceding paragraphs on gusset-plates, there must be POINTS OF INFLECTION, and consequently POINTS OF NO BENDING, in the girders and also in the columns. These points are assumed midway between the ends of the knee-braces in both the columns and girders. Let  $V$  be the vertical increment for the level under investigation.

Then

$$P = Vl/c$$

and the reaction of the girder at the column,

$$R = Va/b$$

Since  $V$  and  $R$  act always in the same direction,  $S$  must be equal to their sum.

Hence

$$S = R + V$$

$$\text{Maximum bending moment on girder} = Va$$

or the equivalent

$$\text{Maximum bending moment on girder} = Rb$$

$$\text{Maximum bending moment on column} = Pd$$

$$\text{Stress in each knee-brace} = \frac{1}{2} S \operatorname{cosecant} \alpha.$$

It is evident that  $R$  is the shear anywhere between the intersection-point of the center line of the knee-braces and the columns, and that  $V$  is the shear

tween the braces at either end of the girder. All web-splices, and  
itch of flange-rivets, must be proportioned from these shears.

**Arrangement of Braces for No Bending Moment in Girder or Column.**  
rent from the above that the nearer  $a$  and  $d$  approach zero the less the  
moments in the girder and column become. If the intersections of the  
es of the braces can be arranged so that  $a$  and  $d$  become zero, there  
BENDING MOMENTS in the girders or columns.

**Braces on One Side, Only, of Girder.** It is often necessary to  
NEE-BRACES ON ONE SIDE, only, of the girder, either above or below.  
of this kind the girder itself serves as one arm of the brace, and

The stress in the single knee =  $S \operatorname{cosecant} \alpha$

$S$  are as determined above, but there must also be taken into account  
ntal stress in the girder, due to its action as one arm of the brace.

Horizontal stress in girder =  $Vl/(\frac{1}{2}c - d)$

nection between the column and the girder must provide for the com-  
on of  $R$  vertical and  $Vl/(\frac{1}{2}c - d)$  horizontal.

**Stresses in Sway-Rods.** For the correct analysis of SWAY-BRACING (Fig. 6),  
l increments should be found in a manner slightly different from that

in Subdivision

1176-9. The  
pressures are  
before, except  
otal pressures  
top down to  
clude, in each  
lditional pres-  
st areas of one-  
y below. The  
or each level  
e the story-  
w. (See sec-  
1 and fourth  
Table I.) The  
crements are  
s for the other  
pt for these  
ations; and,  
e vertical in-  
re constant  
each story.

IN ANY DI-  
als the verti-

nt in the story multiplied by the cosecant of the angle  $\alpha$  (Fig. 6).  
d that the diagonals are used for tension only and that, consequently,  
tem acts at a time. Each horizontal member must take compression  
vertical increment in the story below, multiplied by the cotangent  
e joints are arranged so that axial lines of members intersect, there  
ending either in the columns or the horizontal members.

**Stresses in Latticed Girders.** Let  $V$  in Fig. 7 equal the vertical increment  
y. As in the other types,  $V$  is constant between the columns, and  
any diagonal equals  $V$  multiplied by the cosecant of  $\alpha$ . As in the




Fig. 6. Sway-rod Type of Wind-bracing




Fig. 7. Latticed-girder Type of Wind-bracing

**GUSSET-TYPE and KNEE-BRACE TYPE**, there is no bending at the middle section of the girder-length, and consequently no stress in the middle section of the top chord. The maximum bending moment in the girder is at the column-face and this

$$\text{Maximum bending moment in the girder} = Vf$$

The maximum chord-stress is at this same point, and this

$$\text{Maximum chord-stress} = Vf/h$$

The connections of the chords to the columns must provide against this minimum stress.

$$P = Vl/c$$

and the

$$\text{Maximum bending moment in the column} = Pd$$

**Stresses in Portal Bracing.** It is not possible to analyze exactly the stresses in PORTAL BRACING (Fig. 8), when it is used in connection with columns of continuous section. The analysis, as given follows that of C. T. Purdy in "Modern Framed Structures." It is considerably on the safe side, and for ordinary cases it will be followed. In a large building, where much bracing of this type might be used, the exact form of the PORTALS should be determined, and greater allowance made for the effect of CONTINUOUS COLUMNS.

Let  $\Sigma H$  equal the accumulated force of horizontal shear from the wind at the floor next above floor  $M$ , applied half on each side and half on the other. Let  $H_1$  equal the force of the wind or the shear direct tributary to floor  $M$ . Then, taking moments about  $O$  (Fig. 8)

$$V \times 2l = (\Sigma H + H_1) c$$

or

$$V = (\Sigma H + H_1) c / 2l$$

and the

$$\text{Horizontal reaction} = \frac{1}{2} (\Sigma H + H_1)$$




Fig. 8. Portal Type of Wind-bracing

To determine the maximum stress in the curved flange  $t$ , assume a point  $p$  in

flange  $r$ , horizontally distant  $x$  from the line  $WW$ , and at the distance  $y$ , measured normal to a tangent to any point in the flange  $t$ ; then, taking the center of moments at the left extremity of the distance  $x$ , the stress in flange  $t$  multiplied by  $y$ , equals  $V$  multiplied by  $x$ , or  $Vx/y$  equals the stress in the flange  $t$ , at the section taken, and this is a maximum when  $x/y$  has its greatest value.


Each leg of the portal, including the column, may be considered as a CANTILEVER with two forces acting on it, the horizontal force  $\frac{1}{2} (\Sigma H + H_1)$  and the vertical force  $(\Sigma H + H_1) c / 2l$ , the flange  $t$  (of the right leg for example) being in COMPRESSION and the column itself acting as a TENSION-CHORD. Assuming a point on the axial line of the column, distant  $z$  from the bottom of the leg and at right-angles to, and distant  $y_1$ , measured normal to a tangent to any point in the flange  $t$ , and taking moments about this assumed point, the stress in flange  $t$  multiplied by  $y_1$  equals  $\frac{1}{2} (\Sigma H + H_1)$  multiplied by  $z$ , or the stress



uals  $\frac{1}{2} (\Sigma H + H_1)$  multiplied by  $\pi_1/\gamma_1$ , and this is a maximum its greatest value. There is approximation in this treatment, e side of safety. If the flange  $t$  has a section proportioned to stresses the requirements will be fulfilled. The stress in, and uired for, the flange  $r$  can be obtained in a similar manner. The e portal above this flange to the portal and column above must will safely resist the stress  $\frac{1}{2} \Sigma H$  at each leg.

## ination of Dead and Live Loads with Wind-Loads

inciples. It usually happens that the same girders that are used serve also to carry floors or walls. The dead and live loads dered with the wind, and the **RESULTANT COMBINED STRESSES**



### 9. Types of Columns Arranged for Wind-bracing.

ould be borne in mind that the maximum bending moment l is often at a point on the girder more or less removed from um bending moment for dead and live loads. When **RESULT-OMENTS** are considered, in which the forces are the wind-load ead loads, it is generally deemed proper to use unit stresses ose of common practice under usual loading. The columns ted for direct live, dead and wind-loads and for the bending **RESULTANT STRESS**, again, should not exceed 150% of the sed for live and dead loads only. It is often best to design icial view to proper connections for bracing. This aids in

both design and detail. In Fig. 9 are shown a few TYPICAL ARRANGEMENTS column-material illustrating this point.

### 19. Wind-Bracing of Water-Towers and Similar Structures

**The Principles Involved in Water-Tower Bracing.** In the case of TOWER WITHOUT MASONRY WALLS, a problem is presented much simpler than that of a building, as the INDETERMINATE FACTORS OF RESISTANCE are largely




Fig. 10. Whitehall Building. Plan and Lines of Bracing

eliminated. The bracing should be designed to resist the wind-pressure. It should be borne in mind that in water towers the condition of **MOIST STABILITY** obtains when the tank is empty. The most common form for tower-bracing is **SWAY-ROD**. The analysis of stresses is the same as described on page 1181. The application of the thrust is largely at the top where the tank stands, but it does not in any way alter the analysis. The legs of water-towers are frequently **SLOPED** to give greater spread at the bottom. In this case the stresses are more readily determined by **GRAPHIC METHODS** than by algebra or trigonometrical computation. (See Chapter XXVII.)

**The Assumed Unit Pressure** should be somewhat greater for towers than for buildings. Towers are small in comparison with buildings, and the probability of the full wind-pressure being developed over the entire surface is greater. Probably 40 lb per sq ft is assumed pressure against a **CYLINDRICAL BODY**, such as a tank, may be taken at about two-thirds of the full pressure against the projection on the diametrical plane. The stresses under this assumed pressure should be kept within usual bounds for ordinary dead or live loads. The anchorage

each post should exceed, by a safe margin, the full uplift due to the assumed pressure. The weight of water in the tank should not be considered as resisting the uplift.

A Good Example of a Steel Water-Tower is described and illustrated in the Engineering Record of June 20, 1903, the stress-diagrams and details of construction being given.

1

itchell Building. Wind-bracing on Line I, Fig. 10



## Recent Examples of Wind-Bracing in Tall Buildings \*

**Whitehall Building†** (Figs. 10 to 14 West Street, New York City) is a thirty-one story addition to the earlier Battery Place Building. The older twenty-story building is to the south. As the plan, Fig. 10, shows, the building is very long and narrow compared with its height and its type in which wind-bracing must be an essential feature. The six girders indicated on the plan (Fig. 10) were used so as to interfere as little with the requirements of the plan. They were used as far as practicable. In several instances it was necessary to use cross-bracing because of the limited space. It was assumed that the connections of girders to columns, when properly furnished, would furnish sufficient stiffness up to the twenty-fourth floor-level. Below the twenty-fourth floor the bracing was proportioned to the height of the building.

**States Realty Building‡** (Broadway, New York City) is a building in which wind-bracing is quite essential. It is a very high, and its width is very small compared with its length and its height. Wind-bracing was used, as indicated, in the plan. It was not feasible to put in cross-bracing to do all the work. Diagonal bracing was therefore added between the elevator-shafts and in the plan. No cross-bracing was used above the fifteenth


**Building§** (Fig. 19). 681 Broadway, New York City, is but twelve stories high. It is rather narrow. The building is on a narrow interior lot, and it was necessary to make the openings in the exterior walls as possible, in order to get light into the interior. This, of course, made the exterior walls of but little value.

Frederick C. Henderson acted as designing engineers for these buildings.

Frederick C. Russell, architects.


Frederick C. Kimball, architect.

Frederick C. Lead & White, architects.



## III

Fig. 13. Whitehall Building. Wind-bracing on Line III, Fig. 10



IV  
Fig. 14. Whitehall Building. Wind-bracing on Line IV, Fig. 10

**Fig. 13. Whitehall Building. Wire bracing on Line V and VI, Fig. 10**








Fig. 17. Whitehall Building. Wind-bracing Details





## 1 States Realty Building. Lines of Bracing



**Fig. 19. Morton Building. Plan and Lines of Bracing**




Fig. 20. Masonic Building. Plan and Lines of Bracing




Fig. 21. Everett Building. Plan

18. Small KNEE-BRACES and GUSSETS were introduced in each end—additional knee-braces next to the elevator-wells and stair-wells. The girder-connections to the columns, also, were made with six rivets in place, instead of with four as is usual. These special bracing-features were carried to the fifth floor-level.

**Masonic Hall\*** (Fig. 20), 24th Street Building, New York City, twenty-stories high, has virtually no special bracing. Light KNEE-BRACES were used in the two wings, but these were rather to insure the steelwork against sagging out of plumb in erection, than to assist in wind-resistance.

**Verrett Building†** (Fig. 21), 45 East 17th Street, New York City, is a very building, with no special bracing of any kind. It is large on the ground and the ordinary features of construction offer ample resistance to

**Metropolitan Tower‡** (Fig. 22), Madison Square, New York City, is a usual case that it is, perhaps, out of place to mention it as an example of the typical. It is 700 ft high, and about 75 by 85 ft in plan throughout the lower stories. The bracing in this case is a feature of the structural design, and has received much attention. It is subjected from top to bottom to a full pressure of 30 lb per sq ft, with no reduction for the walls, etc. The bracing is, in general, of PLATE GIRDER type, with the walls at each level, and KNEE-BRACES and GUSSETS at the corners. The columns are of steel, with especial view to the connection for the bracing. The weight of the tower is far in excess of the weight of the wind.

Examples, all drawn from New York City buildings, are typical of the most approved

practice in respect to wind-bracing as could be chosen. There is so much variety in the shape and size of buildings that no case is ever exactly like any previous example.




Fig. 22. Metropolitan Tower. Plan and Lines of Bracing

\* H. P. Knowles, architect.

† Goldwin Starrett & Van Vleck, architects.

‡ N. LeBrun & Sons, architects.

## CHAPTER XXX

SPECIFICATIONS \* FOR THE STRUCTURAL STEELWORK  
OF BUILDINGS. DATA ON STRUCTURAL STEEL

By

ROBINS FLEMING

OF THE AMERICAN BRIDGE COMPANY, NEW YORK, N. Y.

## 1. General

(1) **Drawings.** The drawings forming a part of these specifications [give number, maker, title, and date of each drawing].

(2) **Classification.** For the purpose of classification buildings are divided into two classes:

## I. MILL-BUILDINGS

## II. OFFICE-BUILDINGS

Under CLASS I are included manufacturing plants, machine-shops, power-houses, rolling-mills, foundries, forge-shops, pattern and template-shops, tin-sheds, pier-sheds, car-barns, roundhouses, electric-light stations, armories, buildings of a similar character.

Under CLASS II are included office-buildings, hotels, apartment-houses, dwellings, public buildings (hospitals, libraries, schools, court-houses, jails), places of public assembly (churches, theaters, halls), stores, warehouses, garages, buildings of a similar character.

(3) **Scope of Work.** It is intended that these specifications and drawings cover the structural steelwork complete for the building. Cast-iron bases are included with the structural steel. The steel-erector shall erect in place the steel framework on foundations furnished by others. Anchor-bolts, loose iron and material not connected with main frame of structure, are to be delivered to the site, but put in place by other contractors.

(4) **Materials to be Furnished for Buildings of Class I.** Unless specified otherwise in contract, the MATERIALS TO BE FURNISHED for buildings of CLASS I include steel trusses, columns, purlins, bracing, floor-framing, crane-girders, rails, trolley-beams, lintels, girts, framing around door and window-openings, beams supporting tanks, elevator-framing, stair-framing, floor-plates, bulkhead framing and steel lining, stairs and railings unless of an ornamental character, cast-iron bases, grillage-beams, and anchor-bolts.

The MATERIALS NOT FURNISHED include ornamental ironwork and steel masons' anchors, carpenters' anchors and irons, elevator sheave-beams, supports for trolley-beams, steel stacks, steel tanks, and steel reinforcement for concrete.

(5) **Materials to be Furnished for Buildings of Class II.** Unless specified otherwise in contract, the MATERIALS TO BE FURNISHED for buildings of CLASS II include steel columns, cast-iron bases, rolled and cast-steel slabs, grillage-beams, anchor-bolts, floor-framing, roof and ceiling-framing, purlins, cornice-supports for tanks, penthouse framing, bracing, and lintels.

The MATERIALS NOT FURNISHED include ornamental ironwork and steel masons' anchors, terra-cotta anchors, carpenters' anchors and irons, stair-

\* The various values used in these Specifications agree generally with those given throughout the book. Any slight variations in values are due to recognized and allowable differences in engineering judgment, differences in Building Codes, etc.

framing, elevator sheave-beams, steel stacks, steel tanks, light shapes and metal ceiling-lath, cast-iron sills and similar work, and steel reinforcement for concrete.

**RIVETS AND BOLTS** for fastening steel to steel (but not for connecting the other trades) shall be furnished by the steel-contractor. Fitting-up and erection are to be furnished by the contractor for erection as a part of the contract.

As soon as possible a **COLUMN-FOOTING PLAN** shall be sent to the purchaser showing the location, elevation, and dimensions of all column-bases, with location, elevation, size, and length of all anchor-bolts. The loads coming on column-footings from the columns shall also be given.

Clearance diagrams showing the **CLEARANCES** assumed for traveling cranes shall be furnished the purchaser at an early date.

**Substitution of Material.** If the contractor wishes to substitute **OTHER SIZES** for those called for on the drawings he may do so, subject to the approval of the engineer, provided the architectural features are maintained and the sections are sufficient to carry the required loads.

**Work of Other Trades.** **HOLES** conforming to the usual standards of the trade shall be punched in the steel for attaching the work of other trades, and their location is given while the working drawings are being made.

**Working Drawings.** **WORKING OR SHOP DRAWINGS** shall be made by the contractor, and when requested, prints in duplicate sent to the purchaser for his engineer for approval. The engineer's approval of drawings shall be for general design, strength and type of details. The engineer shall not be responsible for the fit of work at the site. If, to expedite delivery, or for any other reason, he waives the approval of drawings, the contractor will not be relieved of responsibility for errors or omissions due to neglect or oversight on the contractor's part.

All work shall conform to local or state **ORDINANCES AND REGULATIONS**.

## 2. Material \*

**Properties and Tests.** All parts of the metallic structure shall be of **STEEL**, except column-bases, bearing plates, or minor details, which may be of **IRON OR CAST STEEL**.

Structural steel may be made by either the **BESSEMER PROCESS** or the **OPEN-HEARTH PROCESS**; except that rivet-steel, and steel for plates or angles over 1/2 inch thickness which are to be punched, shall be made by the open-hearth process.

Structural steel, if made by the Bessemer process, shall contain not more than 0.05% of PHOSPHORUS; and if by the open-hearth process, not more than 0.06% of PHOSPHORUS. Rivet-steel shall not contain more than 0.06% of PHOSPHORUS nor 0.045% of SULPHUR.

Structural steel shall have an **ULTIMATE TENSILE STRENGTH** of from 55 000 to 65 000 lb per sq in of cross-section, and rivet-steel from 46 000 to 56 000 lb per sq in of cross-section. The **YIELD-POINT** as determined by the drop of the beam of the testing machine shall be one half of the ultimate tensile strength.

Requirements for material are taken, by permission, from the following Standard Specifications of the American Society for Testing Materials, Philadelphia, Pa.: Standard Specification for Structural Steel for Buildings (A9-16), Standard Specifications for Steel Castings (A48-05), and Standard Specifications for Steel Castings (A27-16).

(17) The MINIMUM PERCENTAGE OF ELONGATION in 8 in shall be 1 400 divided by the ultimate tensile strength. For structural steel over  $\frac{3}{4}$  in in thickness, a deduction of 1 from the above percentage of elongation in 8 in shall be made for each increase of  $\frac{1}{4}$  in in thickness above  $\frac{3}{4}$  in, to a minimum of 18%. For structural steel under  $\frac{5}{16}$  in in thickness, a deduction of 2.5 from the above percentage of elongation shall be made for each decrease of  $\frac{1}{16}$  in in thickness below  $\frac{5}{16}$  in.

(18) TEST-SPECIMENS for plates, shapes, and bars shall bend cold through 180° without cracking on the outside of the bent portion, as follows: For material  $\frac{3}{4}$  in or under in thickness, flat on itself; for material over  $\frac{3}{4}$  in, to and including  $1\frac{1}{4}$  in in thickness, around a pin the diameter of which is equal to the thickness of the specimen; and for material over  $1\frac{1}{4}$  in in thickness, around a pin the diameter of which is equal to twice the thickness of the specimen. The TEST-SPECIMEN for rivet-steel shall bend cold through 180°, flat on itself, without cracking on the outside of the bent portion.

(19) IRON CASTINGS shall be of tough gray iron, true to pattern, free from cracks, flaws, and excessive shrinkage. The SULPHUR-CONTENTS shall be not over 0.08% for light castings, 0.10% for medium castings, and 0.12% for heavy castings.

A TEST-BAR  $1\frac{1}{2}$  in in diameter and 15 in long, placed upon supports 12 in apart and tested under a centrally applied load, shall conform to the following requirements:

MINIMUM APPLIED LOAD, 2 500 lb for light, 2 900 lb for medium, and 3 300 lb for heavy castings;

MINIMUM DEFLECTION AT CENTER, 0.10 in.

Light castings shall be able to withstand an ultimate tension of 18 000, medium castings 21 000, and heavy castings 24 000 lb per sq in. Castings having a section less than  $\frac{1}{2}$  in thick shall be known as LIGHT CASTINGS. Castings in which no section is less than 2 in thick shall be known as HEAVY CASTINGS. MEDIUM CASTINGS are those not included in the above classification.

(20) STEEL CASTINGS for ordinary use, not annealed, shall contain not more than 0.30% of CARBON, nor more than 0.06% of PHOSPHORUS. They shall substantially conform to the sizes and shapes of the patterns, be made in a workmanlike manner, and be free from injurious defects.

### 3. Loads

(21) **Roof-Loads.** ROOF-TRUSSES AND COLUMNS shall be designed to carry a uniform load per square foot of exposed roof-surface, applied vertically. The load includes the weight of the structure, the snow, and the wind. For spans 10 ft to and including 90 ft, and in climates corresponding to that of New York, the total minimum uniform load in pounds per square foot of roof-surface for different kinds of covering shall be taken as follows:

Corrugated metal.....	15
Gravel or composition on wood sheathing.....	20
Slate on boards.....	25
Tile on steel purlins.....	30
Gravel or composition on cinder concrete.....	35
Gravel or composition on stone concrete.....	40
Slate or tile on cinder concrete.....	45
Slate or tile on stone concrete.....	50
Fire-proof buildings of CLASS II, where slope is less than 2 in per ft.....	55

For roof-spans over 90 ft, the above-cited loads shall be increased 1% for each 2-ft increase of span.

For roofs in climates where snow is excessive, from 5 to 10 lb per sq ft shall be added, and in climates where there is not liable to be snow, 10 lb per sq ft shall be deducted from the foregoing loads.

If a ceiling is carried by the roof-framing, the ceiling-load shall be assumed to be not less than 10 lb per sq ft.

If SHAFTING is carried by the bottom chord, the load at the shaft shall be not less than 2 000 lb for light shafting, 4 000 lb for ordinary shafting, and 6 000 lb for heavy shafting. Unless the shafting is definitely located these loads shall be considered as liable to be concentrated at any point of the bottom chord.

In designing PURLINS carrying roof-covering only, the loads in Paragraphs (21) and (23) may be decreased 5 lb and considered normal to the roof. If the pitch of the roof is more than from  $2\frac{1}{2}$  in to 1 ft, tie-rods shall be used between the purlins.

SPECIAL LOADINGS, such as tanks or elevator-supports above the roof, or trolleys on the bottom chord, shall be taken into consideration.

For ROOFS used as places of public assembly or for storage-purposes they shall be considered as floors.

**Floor Loads.** Floor loads consist of DEAD LOADS and LIVE LOADS. The dead load is composed of the weight of the floor-construction and of any permanent loads resting upon it. In designing floor-beams and girders for fire-proof construction the dead load shall be assumed at not less than 70 lb per sq ft. If of wooden studding or of hollow tile, not more than 4 in thick, may be considered as part of the live load.

Buildings governed by a local or state building code, buildings of CLASS I designed for MINIMUM LIVE LOADS, in pounds per square foot of floor-areas, shall be as follows:

	lb per sq ft
Pattern and template-shops.....	60
Factories, light machinery.....	120
Factories, heavy machinery.....	150 to 200
Warehouses.....	150 to 200
Charging-floor.....	300 to 800
Stairs.....	200

Buildings FOR SPECIAL INDUSTRIES shall be designed for the loadings specified for those industries.

Provision shall be made for the SUPPORT OF MACHINERY, engines, boilers, and other concentrated loads, when carried by the steel construction.

**Crane-Loads.** Loads due to electric TRAVELING CRANES shall be in addition to provide for the effects of impact. For hand-power cranes the loads shall be taken at 10%. For two cranes in action on the same girder, no additional load shall be added, provided the stress obtained is larger than the stress due to one crane with impact. In addition to the vertical loads the top flanges of girders shall be designed to resist a transverse horizontal thrust on each girder applied at the wheels, of 10% of the lifting capacity of the crane. The load due to stopping the crane shall be assumed at 20% of each wheel-load and shall be considered as distributing itself along the entire length of the girder.

(34) **Coal-Bunkers.** COAL-BUNKERS shall be assumed to be surcharged when it is possible for them to be so loaded. The weight of anthracite shall be taken at not less than 50 lb per cu ft, and the angle of repose assumed be  $30^{\circ}$ .

(35) Buildings of CLASS II shall be designed for minimum live loads, in pounds per square foot of floor-area as follows:

	lb, sq
Dwellings (private residences), first floor.....	
Dwellings (private residences), upper floors.....	
Apartment-houses, first floor.....	
Apartment-houses, upper floors.....	
Hotels, first floor.....	
Hotels, upper floors.....	
Office-buildings, first floor.....	
Office-buildings, upper floors.....	
School-buildings, class-rooms.....	
School-buildings, assembly-rooms.....	
Churches and theaters.....	
Places of public assembly, where floors are used for drilling or dancing.....	
Places of public assembly, where floors are not used for drilling or dancing....	
Retail stores, ordinary.....	
Warehouses.....	200 to 300
Private garages, pleasure vehicles only.....	
Public garages, pleasure vehicles only.....	
Garages, motor trucks, from 1 to 3 tons capacity.....	
Garages, motor trucks, from $3\frac{1}{2}$ to 5 tons capacity.....	

(36) **CONCENTRATED LOADS** shall be taken into consideration. Every steel beam in any floor used for business purposes shall be capable of sustaining a live load, concentrated at the middle, of not less than 3 000 lb. Every steel beam supporting the floor of a garage shall be capable of sustaining a concentrated live load of 2 000 lb, if a private garage storing pleasure vehicles only; of 3 000 lb, if a public garage storing pleasure vehicles only; of 8 000 lb, if motor trucks of from 1 to 3 tons capacity are stored; and of 12 000 lb, if motor trucks of from  $3\frac{1}{2}$  to 5 tons capacity are stored. Structural members carrying elevators and elevator machinery shall be proportioned to carry twice the actual moving dead and live loads.

(37) **Reduction of Live Load.** The full live FLOOR LOAD shall be used in proportioning all parts of buildings designed for warehouses, and such buildings are likely to be loaded on all floors at the same time. In other buildings the specified live load may be reduced 10% for girders carrying 200 sq ft or more of floor. For COLUMNS the load on the top floor may be assumed at 90% of the specified live load; the live load on the floor next below the top floor at 85% and on each succeeding lower floor at correspondingly decreasing percentages provided that on no floor shall less than 50% of the specified live load be used and that for the lower floor the full specified live load shall be used. No reduction shall be made for any ROOF LOAD.

(38) In calculating COLUMN LOADS no reduction of floor-area shall be made for stair-wells. Stairways shall be proportioned for not less than 75 lb per sq ft of horizontal projection.

(39) **Wind-Pressure.** Wind shall be assumed blowing horizontally in any direction. The surface exposed to WIND-PRESSURE shall be measured vertically from the ground to the top of the structure, including the roof.



When the OVERTURNING MOMENT due to wind-pressure exceeds 75% of the restoring moment the structure shall be securely anchored.

All steel buildings belonging to CLASS I shall be designed to carry wind-loads on the ground by steel framework. For buildings not more than 25 ft above the eave-line the wind-pressure shall be assumed at not less than 15 lb per sq ft for the corresponding normal pressure on the roof. For buildings more than 25 ft above the eave-line the wind-pressure shall be assumed at not less than 15 lb per sq ft for the lower 25 ft and 20 lb per sq ft for the side surface above 25 ft, and 15 lb per sq ft for the corresponding normal pressure on the roof.

The steel framework of fire-proof buildings belonging to CLASS II, in which the height is more than twice the minimum horizontal dimension, shall be designed to resist a wind-pressure of not less than 20 lb per sq ft on the sides, and 15 lb per sq ft for the corresponding normal pressure on the roof.

The normal pressure,  $P_n$ , in pounds per square foot, on a surface inclined  $\theta$  to the horizontal for a horizontal wind-pressure,  $P$ , of 20 lb per sq ft, is given by the DUCHEMIN FORMULA,\*

$$P_n = P \frac{2 \sin \theta}{1 + \sin^2 \theta}$$

is:

	$P_n$ lb per sq ft	Slope	$\theta$	$P_n$ lb per sq ft
	3.46	1 in to 1 ft	4° 45' 49"	3.30
	6.76	2 in to 1 ft	9° 27' 45"	6.39
	9.63	3 in to 1 ft	14° 2' 10"	9.14
	12.25	4 in to 1 ft	18° 26' 6"	11.50
	14.35	5 in to 1 ft	22° 37' 12"	13.42
	16.00	6 in to 1 ft	26° 33' 54"	14.88
	17.28	7 in to 1 ft	30° 15' 24"	16.06
	18.20	8 in to 1 ft	33° 41' 25"	16.95
10°	18.88	.....	.....	.....
	20.00	.....	.....	.....

For wind-pressure other than 20 lb per sq ft these values are to be changed proportionately.

In case of excess of the wind-stresses, determined by the data of this paragraph, and stresses according to Paragraph (21), need be considered. In this excess, the wind included in the total uniform roof-loads design diagram (21), shall be assumed at 5 lb per sq ft for slopes of 3 in per ft and 10 lb for slopes more than 3 in per ft.

CYLINDRICAL STEEL CHIMNEYS and TANKS shall be designed to resist a wind-load not less than 20 lb per sq ft on the projected area, that is, the diameter multiplied by the height.

SIGNS on tops of buildings shall be designed to withstand a wind-load not less than 30 lb per sq ft of surface.

#### 4. Stresses †

**Working Stresses.** In proportioning structural steel for stresses due to WIND, DEAD AND LIVE LOADS together with IMPACT, the working stresses shall be based on the following values:—

For variations from these values, see Table XVIII, page 618, and Table I, page 1053.

in pounds per square inch of sectional area shall be not more than the following:

	lb per sq in
Tension, net section, rolled steel.....	16 000
Direct compression, rolled steel and steel castings.....	16 000
Bending on extreme fibers of rolled shapes, built sections, girders, and steel castings, net section.....	16 000
Bending, on extreme fibers of pins.....	24 000
Shear, on shop-rivets and pins.....	12 000
Shear, on field-rivets.....	10 000
Shear, on bolts.....	9 000
Shear, average, on webs of plate girders and rolled beams, gross section.....	10 000
Bearing pressure, on shop-rivets and pins.....	24 000
Bearing, on field-rivets.....	20 000
Bearing, on bolts.....	18 000
Tension, in rivets.....	7 000
Tension, in field-bolts (not anchor-bolts).....	9 000
Axial compression, on gross section of columns and struts.....	16 000 - 7000/l
where $l$ is the effective length of the member, in inches, and $r$ is the least radius of gyration of section, in inches, with a maximum of.....	
	13 000

(47) For COMBINED STRESSES due to wind and other loads the unit stresses Paragraph (46) may be increased 50%, except for Paragraph (44), provided the section thus obtained is not less than that required if wind-forces are neglected.

(48) When the laterally unsupported length,  $l$ , of the compression-flange beams and girders exceeds 12 times its width,  $b$ , the UNIT STRESS IN THE COMPRESSION-FLANGE, shall not exceed  $19\,000 - 250l/b$ .

(49) COUNTERSUNK RIVETS in plates of thickness equal to or greater than one half the diameter of rivet shall be assumed to have three fourths the value of rivets with full heads. In plates of thickness less than one half the diameter of rivet their values shall be taken as three eighths that of full-headed rivets. RIVETS WITH FLATTENED HEADS of height not less than  $\frac{3}{8}$  in, or one half the diameter of the rivet for  $\frac{3}{8}$ -in rivets and less, may be assumed to have the value of corresponding rivets with full heads. Rivets with heads flattened to less than these heights shall have countersunk holes and be regarded as countersunk rivets.

(50) The allowable pressure of COLUMN-BASES and BEARING-PLATES on masonry shall not exceed, in pounds per square inch, the following. (See, also pages 265 to 267, and 441.)

	lb per sq in
On brickwork, cement mortar.....	4 000
On brickwork, lime mortar.....	3 000
On Portland-cement concrete, 1 : 2 : 4 mixture.....	5 000
On Portland-cement concrete, 1 : 3 : 5 mixture.....	3 000
On rubble masonry, cement mortar.....	2 000
On rubble masonry, lime mortar.....	1 500
On first-class dimension sandstone.....	4 000
On first-class limestone.....	3 000
On first-class granite.....	6 000

## 5. Design

**General Design-Requirements.** TRUSSES shall be riveted structures. TENSION-MEMBERS as well as COMPRESSION-MEMBERS shall be composed of rolled or built-up sections. Flat bars with riveted ends shall not be used.

In calculating TENSION-MEMBERS, net sections shall be used. The diameter of rivet-holes shall be assumed to be  $\frac{1}{8}$  in. larger than the nominal size of rivets.

In single angles connected by one leg, the net area of the connected leg shall be considered effective.

The NOMINAL SIZES OF RIVETS shall be used in calculations of their values.

In proportioning COLUMNS provision shall be made for eccentric loading.

COLUMNS AND STRUTS with direct loads of 40 000 lb or less, when they shall have the entire load transmitted through splice-plates.

COLUMN-SPLICES shall be designed to resist the bending-stresses, and to make columns practically continuous for their whole length.

Members subject to REVERSAL OF STRESS from moving loads shall be designed for the stress requiring the larger section, but their connections shall be proportioned for the larger stress plus one half the smaller.

The EFFECTIVE LENGTH OF MAIN COMPRESSION-MEMBERS shall not exceed their least radius of gyration, and for secondary members and lateral bracing shall be 50 times their least radius of gyration. Any portion of the cross-section of a compression-member may be neglected in computing the radius of gyration, provided that portion is neglected in the design of the member.

HEEL-LOADS OF CRANES shall be assumed to be distributed on the top flange of runway girders over a distance equal to the depth of the girder, with a minimum width of 30 in.

FLANGE GIRDERS shall be proportioned either by the moment of inertia of the section, or upon the assumption that the bending-stresses are resisted by the flanges concentrated at their centers of gravity, and that the shear is resisted by the web. When the second method is used one eighth of the gross area of the web, if properly spliced, may be used as flange-section.

WEB-PLATES OF GIRDERS shall have a thickness of not less than  $\frac{1}{160}$  of the clear distance between flange-angles.

FLANGE-PLATES OF GIRDERS shall be limited in width, so as to extend not more than 6 in. beyond the outer line of rivets connecting them to the angles.

WEB-STIFFENERS, in pairs, shall be placed over bearings, at points of concentrated loadings and at intermediate points, usually not farther apart than one-third of the depth of the girder, when the thickness of the web is less than  $\frac{1}{80}$  of the depth of the girder.

STIFFENERS under concentrated loads and over bearings shall be designed to resist the shear, with a length equal to one-half the depth of the girder, and shall be riveted to properly transmit the shear. When loads are transmitted to the bearing of stiffeners, the bearing value may be assumed at 24 000 lb per sq in. of section, excluding the area of the chamfered portion over fillets at the ends.

DEPTH OF GIRDERS AND ROLLED BEAMS in floors shall be not less than one-tenth of the span, and if used as roof-purlins shall be not less than  $\frac{1}{32}$  of the span. In floors subject to shocks and vibrations the depth shall be limited to one-tenth of the span.

ROOF PURLINS shall be single rolled shapes, plate girders or lattice

(67) Lateral, longitudinal, and transverse BRACING in all structures shall preferably be composed of rigid members, and shall be designed to withstand wind and other lateral forces when building is in process of erection as well after erection.

(68) WIND-BRACING shall be provided for tall buildings by making the connection-joint between girders and columns sufficient for the bending due to side pressure as well as for the vertical load; or diagonal bracing shall be placed between columns, proportioned to transfer the shear of the side pressure to the footings.

(69) No steel in any structural member subject to stress shall be less than  $\frac{1}{8}$  in thick, except the webs of rolled beams and channels. Steel subject to the action of harmful gases or severe atmospheric conditions shall be not less than  $\frac{3}{16}$  in thick.

## 6. Details

(70) General Detail Requirements. DETAILS throughout shall conform to first-class standard practice.

(71) No connection except lattice-bars shall have less than two rivets, preferably three, for better handling in fabrication.

(72) In cases where it is necessary to carry loads subject to shock by bolts in tension, CHECK-NUTS shall be used. When bolts go through beveled flanges, BEVELED WASHERS to match shall be used so that head and nut are parallel. In general, rivets and bolts in tension shall be avoided as far as practicable.

(73) ABUTTING JOINTS in compression-members faced for bearing shall be spliced sufficiently to hold the connecting members accurately in place.

(74) When two or more rolled beams are used to form a girder, they shall be connected by BOLTS AND SEPARATORS at intervals of not more than 6 ft. All beams having a depth of 12 in and more shall have at least two bolts to each separator.

(75) The MINIMUM DISTANCE BETWEEN CENTERS OF RIVET-HOLES shall be three diameters of the rivet, and the maximum distance in the line of stress eight diameters.

(76) The MINIMUM DISTANCE FROM THE CENTER OF ANY RIVET-HOLE TO SHEARED EDGE shall be  $1\frac{1}{2}$  in for  $\frac{1}{8}$ -in rivets,  $1\frac{1}{4}$  in for  $\frac{3}{8}$ -in rivets,  $1\frac{1}{2}$  in for  $\frac{1}{2}$ -in rivets, and 1 in for  $\frac{3}{4}$ -in rivets; and to a rolled edge,  $1\frac{1}{4}$ ,  $1\frac{1}{2}$ , 1, and  $\frac{3}{4}$  in respectively.

(77) The MAXIMUM DISTANCE FROM THE CENTER OF ANY RIVET-HOLE TO AN EDGE shall be eight times the thickness of the plate.

(78) The PITCH OF RIVETS AT THE ENDS OF BUILT COMPRESSION-MEMBERS shall not exceed four diameters of the rivets for a length equal to one-and-one-half times the maximum width of the member.

(79) The LATTICING OF COMPRESSION-MEMBERS shall be proportioned to resist a shearing-stress equal to 2% of the direct stress. TIE-PLATES shall be provided at each end and at intermediate points where latticing is interrupted. In members carrying calculated stresses, the end tie-plates shall have a length not less than the distance between the lines of rivets connecting them to the flanges and intermediate ones not less than half this distance. Their thickness shall be not less than  $\frac{1}{60}$  of the same distance.

## 7. Workmanship

(80) General Requirements. All WORKMANSHIP shall be first-class in every respect.

Material shall be thoroughly STRAIGHTENED before being worked, by that will not injure it.

BEARING shall be done accurately, and all portions of the work exposed neatly finished.

BUTTING SURFACES OF COMPRESSION-MEMBERS, except where joints are used, shall be planed to an even bearing so as to give close contact at.

UNCHING shall be done accurately, but occasional inaccuracies in matches may be corrected with a reamer. The diameter of the punch shall be more than  $\frac{1}{16}$  in larger, nor that of the die  $\frac{1}{8}$  in larger than the diameter of the rivet. Rivets shall be driven by pressure-tools wherever possible.

HOLES IN MATERIAL of same thickness as diameter of punch may be of full size.

WEB-STIFFENERS OF PLATE GIRDERS under concentrated loads shall have rounded ends.

### 8. Painting

General Painting Requirements. Cast iron need not be painted at the shop. Steelwork for foundations to be entirely embedded in concrete shall be painted, but must be free of dirt, grease, or other matter which would impair the bond of the concrete. Other steelwork shall be thoroughly cleaned and given two coats of paint before shipment. One coat shall be given to surfaces that are exposed after being riveted together.

Machine-finished surfaces shall be coated with white lead and tallow before shipment.

Before erection all structural metalwork shall be cleaned of dirt and rust and given one coat of paint of a color or shade different from that of the shop-coat. All painting at the shop and site shall be done by hand when the surface to be painted is perfectly dry. Painting shall not be done in freezing weather.

The paint shall be a good quality of red lead or graphite, ground in pure linseed oil or their equivalent.

### 9. Inspection

General Requirements. All inspection and tests shall be made at the expense of the purchaser.

When material is tested at the mills, the necessary number of test-pieces and a testing-machine shall be furnished free of charge by the steel-con-

tractor. The purchaser or his representative shall have free access at all times to the mills where material is rolled and to the shops where it is fabricated. In addition, for his needs he shall be given dates of mill and shop-operations and furnished with complete working drawings.

### 10. Erection

General Requirements. The structural steel and iron, except anchor-bolts, girders, and material not connected with the main frame of the structure, shall be erected by the steel-contractor on foundations furnished by the

owner. It shall be taken that all steelwork is level and plumb before bolting or

(97) Proper provision shall be made for resisting stresses due to erection operations.

(98) In general, field-connections shall be riveted, but connections of the following classes may be bolted:

- (a) Light subordinate framing, such as purlins, monitor and skylight-framing, girts, platforms, stair-framing, partitions, ceilings, and penthouses;
- (b) Ordinary framing of beams to beams, and beams to girders;
- (c) Connections not subject to direct shearing-stress.

All connections, however, affected by loads that cause undue vibration, shall be riveted. One-story buildings, not subjected to excessive wind-pressure, not supporting heavy concentrated loads, shafting, or moving loads, may be bolted throughout. The threaded part of a bolt shall not be so long that the bearing value of the unthreaded portion is reduced to less than the shearing value of the bolt. Washers shall be used under nuts wherever needed.

(99) Drift-pins shall be used only to bring parts together. Unfair holes shall be made to match by reaming.

(100) After finishing the work the erector shall remove his equipment and rubbish resulting from his operations.

## DATA ON STRUCTURAL STEEL \*

### Estimating the Cost of Structural Steel for Buildings

Structural steel for buildings is commonly made up of I beams, channels, angles, Z bars and plates, which may be used as single beams or braces, or built into riveted girders, columns, or trusses. The Z bars are now seldom used in columns or other structural work in buildings. The cost of the completed steel work is made up of the following items:

- (1) Cost of the plain steel at the mill, plus freight and dealers' profits.
- (2) Extras for cutting, punching, fitting and assembling into girders, columns or trusses.
- (3) Cost of the fittings, such as connection-angles, gusset-plates, etc.
- (4) Shop-painting.
- (5) Cost of erection at the building.
- (6) Painting after erection.

**Base-Price of Steel.** For orders of any considerable size, the cost of plain steel is based on the price at the mills plus the freight to the point of delivery.

The BASE-PRICE, free on board cars at Pittsburgh, Pa. (1920), is about \$2.45 per 100 lb for I beams and channels 15 in and less, and for angles and zees from 3 to 6 in.

I beams over 15 in, cost 10 cts per 100 lb extra, and tees over 3 in, 5 cts extra.

For angles, channels and zees under 3 in, the base is \$2.45 at Pittsburgh.

For angles, over 6 in, \$2.45 + \$0.10.†

For H beams, \$2.45 + \$0.10.

For deck beams and bulb angles, \$2.45 + \$0.30. ‡

For corrugated and checkered plates, \$2.65 + \$1.75.§

For plates, structural, the base is \$2.65.

\* Valuable data was contributed for this section by Associate Editor, Robins Fleming.

† \$2.45 + \$0.10 means a base-price of \$2.45 and an extra \$0.10.

‡ \$2.45 + \$0.30 means a base-price of \$2.45 and an extra of \$0.30.

§ \$2.65 + \$1.75 means a base-price of \$2.65 and an extra of \$1.75; the same with \$0.15, etc. Corrugated steel, painted, is usually quoted at a base-price plus an extra for painting. At present (1920) it is \$4.25 + \$0.25.

ates, flange, the base is \$2.65 + \$0.15.\*  
 corrugated steel, painted, No. 22, \$4.25 + \$0.25.\*  
 corrugated steel, galvanized, No. 22, \$5.30.  
 eel sheets, black, Nos. 10 and 11, \$4.00.  
 eel sheets, galvanized, Nos. 10 and 11, \$4.70.  
 eel sheets, black, No. 22, \$4.20.  
 eel sheets, galvanized, No. 22, \$5.25.  
 r-iron, the base is \$4.50.  
 ets, \$4.50.  
 eel bars, \$2.35.

at-Rates (March, 1920) in car-load lots are:

h to Albany, N. Y.....	27.0 cts
to Baltimore.....	23.0 cts
to Boston.....	29.5 cts
to Buffalo, N. Y.....	21.0 cts
to Chicago.....	27.0 cts
to Cincinnati.....	23.5 cts
to Cleveland.....	17.0 cts
to Columbus, O.....	20.0 cts
to Denver.....	99.0 cts
h to Louisville.....	26.5 cts
to New York.....	27.0 cts
to Norfolk, Va.....	31.5 cts
to Philadelphia.....	25.0 cts
to Richmond, Va.....	30.0 cts
to Rochester, N. Y.....	21.0 cts
to St. Louis.....	34.0 cts
to Washington, D. C.....	24.0 cts

unt of the expense of carrying beams in stock, local dealers usually  
 m  $\frac{1}{2}$  to  $1\frac{1}{2}$  ct a pound, extra, on orders supplied from stock.†

rd Classification of Extras. These lists are for STEEL BARS AND  
 APES, and the extras are added to the BASE-PRICES for each 100  
 This standard classification was adopted June 15, 1919, by the  
 eel Company.

### Specification and Inspection

ial, subject to United States Navy Department specifications  
 edium or soft steel.....\$0.10  
 e hull-steel (except rivet-rods) subject to United States Navy  
 tment specifications..... 1.00  
 for other than mill-inspection, such as Lloyd's or American Bureau  
 , for buyer's account.

### Quantity-Differentials

fications for less than 2 000 lb of a size will be subject to the fol-  
 as, the total weight of a size ordered to determine the extra, regard-  
 h and regardless of exact quantity actually shipped:

\$1.75 means a base-price of \$2.65 and an extra of \$1.75; the same with  
 , etc. Corrugated steel, painted, is usually quoted at a base-price plus  
 painting. At present (1920) it is \$4.25 + \$0.25.  
 t (1920) a war tax of 3% is to be added to the rates given.

Quantities less than 2 000 lb, but not less than 1 000 lb.....  
 Quantities less than 1 000 lb.....

### Straightening

Machine-straightening.....

### Machine-Cutting to Specified Lengths, Rounds and Squares, 1 ½ Inches and Larger

Machine-cutting to lengths over 48 in.....  
 Machine-cutting to lengths over 24 in to 48 in, inclusive.....  
 Machine-cutting to lengths over 12 in to 24 in, inclusive.....  
 Machine-cutting to lengths of 12 in and less, extra will be furnished on application, but will not be less than.....

The above extras apply only to .50 per cent carbon and under. Extras for machine-cutting over .50 per cent carbon will be furnished on application.

Extras for machine-cutting Rounds and Squares under 1 ½ in, Flats, etc., will be furnished on application.

### Cutting to Specified Lengths, Other than Machine-Cutting

Cutting to lengths of 60 in and over.....No charge  
 Cutting to lengths over 48 in to 59 in, inclusive.....  
 Cutting to lengths over 24 in to 48 in, inclusive.....  
 Cutting to lengths over 12 in to 24 in, inclusive.....  
 Cutting to lengths of 12 in and less, extra will be furnished on application, but will not be less than.....

**Cost of Erecting.** For erecting ordinary beams and columns in buildings having masonry walls the cost of erection should not exceed \$20 per ton when there are bolted connections, and it will sometimes be as low as \$13 per ton. In erecting the steelwork of skeleton buildings having riveted connections it is customary to allow \$18 per ton.

**Cost of Painting.** The usual charge for shop-painting is about \$3 per ton, but if done in accordance with the specification on page 1203 it would cost this amount. For painting one additional coat after erection, allow about \$2 per ton.

**Roof-Trusses.** In lots of at least six, the shop-cost of ordinary roof-trusses in which the ends of the members are cut off at right-angles is about as follows: Trusses weighing 1 000 lb each, from \$2.00 to \$3.50 per 100 lb; trusses weighing 1 500 lb each, from \$2.00 to \$2.50 per 100 lb; trusses weighing 2 500 lb each, from \$1.50 to \$2.50 per 100 lb; and trusses weighing from 3 500 to 7 500 lb each, from \$1.25 to \$2.00 per 100 lb. Pin-connected trusses cost from 10 to 30 cents per 100 lb more than riveted trusses.\*

**Steel Mill-Buildings.** The average shop-cost for the frames of steel mill buildings, including draughting, is about \$40 per ton, and the cost of erection from \$20 to \$35 per ton.\*

**Cost of Drafting.** Details for church and court-house roofs having valleys cost from \$10 to \$20 per ton; details for ordinary mill-buildings from \$6 to \$12 per ton. The cost of making shop-drawings varies greatly with the character of the construction of the buildings, and with the accuracy of

\* If there is little duplication or parts of if manual labor enters into the fabrication to any great extent the costs given will be increased.



's drawings. The average costs per ton of steel, for making shop- are about as follows:

tire skeleton construction, in which the loads are all carried to the foundations by the steel columns, \$4.00.

: interior parts which are supported on steel columns, when the outside lls carry the floor-loads and their own weight, \$3.50.

: interior parts which are supported on cast-iron columns, when the tside walls carry the floor-loads and their own weight, \$2.50.

struction without columns, and in which the floor-beams rest on masonry walls, \$2.50.

ldings in which roof-trusses supported by columns comprise the greater t of the construction, \$7.00.

ldings in which roof-trusses on masonry walls comprise the greater t of the construction, \$4.00.

l-buildings, average, \$9.00.

ufacturing or shop-buildings, with flat roofs, and one story in height, 10.

rations, additions, remodeling, which require measurements before ils and shop-drawings can be made, \$12.00.\*

**imate Estimates of the Weight of Steel in Buildings.** Accord- G. Tyrell,† the weight of steel in any proposed new building may be imated from the following data, which is a fair average for buildings even stories high, designed according to the Building Laws of the ston:

	Per sq ft of floor
ment-houses and hotels, with outside frame.....	14 lb
ment-houses, without outside frame.....	9 lb
uildings, with outside frame.....	23 lb
uildings, without outside frame.....	15 lb
uses, with outside frame .....	28 lb
uses, without outside frame.....	18 lb

ings higher than eleven stories, the weight of floors will increase in ortion to the number of stories, while the weight of columns will e rapidly.

roximate weight of roof-trusses, see Chapter XXVII, pages 1050

### **Weights of Steel in Buildings †**

**affecting the Weights of Steel Structures** are many and varied. er square foot of area or per cubic foot of volume of a structure should not be assumed as the weight of a proposed structure conditions which govern the one are found in the other. Munici- codes specify floor-loads and these vary greatly. The prescribed , working stresses and column-loads, affect the weight. The features to be followed also play an important part. In mill- weight is affected by the kind of roofing and siding used, capacity

f \$12.00 includes the cost of taking measurements. This generally has to contractor.

Structural Steel, in Architects & Builders' Magazine, Jan., 1903.

by Robins Fleming.

of cranes, spacing of trusses and columns, shafting, special loadings and allowable minimum thickness of metal.

Weights of Steel in a Number of Structures are given in the following table and notes. The caution regarding such weights being taken as precedents should be emphasized. The office-building heading the list is Equitable building, the largest office-building in the world.

	Average dimensions in feet			Tiers of beams	Weight in pounds per square foot of framed area	Weight in pounds per cubic foot of volume
	Width	Length	Height			
Office-buildings	159	308	542	41	37.00	2.55
	43	79	217	17	26.10	2.30
	90	90	258	22	28.92	2.42
	81	139	225	19	21.90	1.83
	43	104	149	13	33.40	2.90
	48	111	115	9	17.34	1.51
Hotels	97	119	244	20	26.02	1.92
	84	143	270	24	26.95	2.39
	96	101	232	18	25.40	2.00
	108	120	115	9	14.00	1.00
Department-stores	133	219	150	11	23.87	1.77
	62	211	130	8	29.44	1.83
	103	132	89	7	18.30	1.43
Warehouses	100	105	131	10	22.83	1.70
	88	121	121	9	20.60	1.80
	145	357	102	7	30.80	2.13
	58	72	52	3	31.35	1.87

Among prominent New York buildings the 55-story Woolworth Building with a ground-area of 31 000 sq ft weighs 3.0 lb per cu ft.; the 39-story Bank Trust Building with an area of 9 000 sq ft, 3.1 lb.; the 25-story Municipal Building with an area of 42 700 sq ft, 3.6 lb.; the 25-story Hotel McAlister with an area of 31 000 sq ft, 2.0 lb. The 10-story Curtis Building of Philadelphia with an area of 94 000 sq ft weighs 3.0 lb. The structural steel of four buildings of Pittsburgh, the Arrott, the Farmers' Bank, the Empire and the Oliver, is quoted as weighing respectively 2.8, 2.3, 2.1 and 1.8 lb per cu ft. For buildings of from 8 to 12 stories in which the exterior walls are carried by steel framing the weight per cubic foot of volume may be assumed at 1.5 for office-buildings and 1.5 for hotels.

**Armories.** The three-hinged arches with roof-framing of an armory in Brooklyn, 191 by 300 ft in area, weighs 15.5 lb per sq ft of ground area. The armory in Buffalo, 233 by 335 ft, weighs 18.3 lb. The steelwork of the Kingsbridge Armory, New York City, 289 by 590 ft, said to cover the largest hall in the world, weighs about 90 lb per sq ft, of which one half is roof and one half floor and miscellaneous framing.

**Boiler-Shops.** Sizes and weights per square foot of a few boiler-shops are as follows: 167 by 336 ft, three aisles, floor in center and cranes in outer aisles, concrete roof and sides, steel purlins and girts, 23.9 lb; 124 by 300 ft, 1

h 15, 25 and 50-ton cranes respectively, steel purlins and brick walls columns, 36 lb; 74 by 160 ft, 10-ton crane in center aisle, single beams aisles to carry roof, galvanized corrugated-steel covering and siding, 85 by 140 ft, two aisles, one with crane, 20.8 lb; 94 by 97 ft, two aisles, crane, 26.3 lb.

urns. The steel roof-trusses and bracing of a car-barn 100 by 154 ft, ins, brick walls, weighs 6.2 lb per sq ft. Another car-barn, 44 by 270 ft, l-steel roof, and sides on steel purlins and girts, 9.15 lb. Another, 4 ft, four aisles, concrete roof on steel purlins, 11.8 lb.

t-Plants. Four cement-plants with ground-areas of 58 000, 73 000, 1 128 000 sq ft respectively, weigh respectively, 23.6, 22.0, 23.5, and These weights are the averages of the buildings that usually form a nt. The individual buildings vary from 10 lb for an engine-room for a clinker-grinding room.

unkers. The weights of six coal-bunkers of the suspended type and ities of from 350 to 1 000 tons, range from 128 to 234 lb per ton of he average being 204 lb. A system of rectangular pockets to store (10 ft 6 in from ground to valves) weighs 158.3 lb per ton of capacity. the weights of supports but not of roofs are included. A 35 by 70-ft oported on plate girders with a capacity of 1 000 tons weighs 240 lb capacity, including the roof-trusses that carried the conveyor.

shops. The steel framing for the roof of a forge-shop 83 by 126 ft, umns and no cranes, covered with corrugated steel on steel purlins, lb per sq ft of ground-area. A forge-shop 220 by 240 ft, four aisles, rane-runways, composition roofing, concrete sides, steel purlins and s 24.6 lb. A forge-shop 110 by 425 ft for heavy work, 47 ft 6 in to rd, two aisles each with a 50-ton crane, tile roof, glass and brick s 40 lb.

s. A pipe-foundry, 50 by 150 ft, slate covering, wooden purlins, 15-ton crane, weighs 11.35 lb per sq ft. A similar one for the ny, 45 by 82 ft, with a 30-ton crane, weighs 17.23 lb. A foundry, , one center aisle, with light crane, lean-to each side, corrugated-d sides, weighs 14.8 lb. A foundry, 150 by 290 ft, for a pump- ur aisles with 20-ton crane in one aisle, wooden purlins, two charging-floors of concrete on steel beams, weighs 13.9 lb. A by 252 ft, equipped for heavy work, 60-ft center aisle, two side charging-floor, storage-platform, weighs 38.9 lb.

Shops. A machine-shop, 90 by 328 ft, for heavy work, one o ft wide with 25-ton crane, each side aisle 25 ft wide with gallery- on crane underneath, tile roof on steel purlins, brick and glass 43 lb per sq ft of ground-area. A two-story machine-shop, three aisles, light cranes in lower story, composition roof, steel ete sides, weighs 35.15 lb. A one-story building, 75 by 300 ft, om chord, shafting, corrugated-steel roofing and siding, weighs ther one-story building, 70 by 100 ft, 18 ft to bottom chord, rete roof on trusses 10 ft apart, no purlins, weighs 13.88 lb. In steel framing for the Hy-rib sides of this building weighs 3.44 lb ertical surface. A machine-shop, 116 by 252 ft, 60 ft center aisle, o-ton-crane runway and lower 25-ton-crane runway, two side le with traveling jib-cranes, weighs 33 lb.

lls. A rolling-mill, 93 by 186 ft, corrugated-steel roof and 7.6 lb per sq ft. Another, 170 by 384 ft, two aisles each with

5-ton cranes, saw-tooth roof-trusses on longitudinal girders, concrete slabs, steel purlins, brick walls between columns, weighs 17.5 lb. A similar building for shop-purposes weighs 18.62 lb.

**Paper-Mills.** The entire structural steel for three paper-mills weighs respectively 18.4, 20.6 and 21.4 lb per sq ft of area. All roof-trusses are of the flat type, spaced 8 ft apart in the first and third, and 16 ft in the second.

**Power-Houses.** A power-house, 44 by 186 ft, 49 ft to bottom chord, 5-ton crane, tile roof on steel purlins, brick walls between columns, weighs 39.1 lb per sq ft. Another, 53 by 270 ft, 33 ft to bottom chord, 20-ton crane, tile roof on steel purlins, brick walls and sash between columns, weighs 39.6 lb. Another, 120 by 96 ft, one aisle for boiler-room and one with 10-ton crane for engine-room, steel purlins for concrete roof-covering, brick walls between columns, weighs 17.8 lb.

**Train-Sheds.** The train-shed of the Pennsylvania Railroad in Philadelphia, 598 ft long and with arches 300 ft 8 in from center to center of arches, weighs 39.1 lb per sq ft of ground-area; the train-shed of the same railroad in Jersey City, 777 ft long and with arches 252 ft 8 in, weighs 27.9 lb; and the train-shed of the Philadelphia & Reading Railroad in Philadelphia, 506 ft 8 in long and with arches 259 ft 8 in, weighs 31.5 lb. The train-shed, 390 by 815 ft, of the Central Railroad of New Jersey in Jersey City, is a series of concrete and steel umbrellas, of the Bush-type. The structural steel weighs 17 lb per sq ft of area.

**Three Industrial Plants.** In one of the plants of a great industrial corporation a two-story shop, 51 by 380 ft, weighs 28 lb per sq ft of ground-area; a three-story shop, 80 by 420 ft, 37.9 lb; a three-story shop, 80 by 300 ft, 46.3 lb; a three-story shop, 80 by 630 ft, 67.5 lb; a four-story shop, 77 by 140 ft, 66.6 lb; a foundry, 121 by 150 ft, 40.5 lb. In another plant of the same corporation, a three-story machine-shop, 80 by 510 ft, weighs 84.3 lb; a five-story office-building, 49 by 243 ft, 70.3 lb; a power-house, 55 by 120 ft, 37.5 lb; a blacksmith-shop, 81 by 200 ft, 15.6 lb. In a plant of another corporation, a boiler-house, 50 by 94 ft, weighs 23.3 lb; a furnace-building, 60 by 160 ft, 25.1 lb; a rolling-mill, 80 by 80 ft, 24.4 ft; a rod-mill, 243 by 220 ft, 28.1 lb.

**Cost of Merchant Steel.** The cost of merchant iron and steel of all shapes is based on a certain size of each particular shape, which is taken as the base price and the price of all other sizes is figured at a certain extra rate above the base price according to a standard CARD OF MILL-EXTRAS. The BASE-PRICE may fluctuate and be changed without notice, but the extras remain constant, and are the same in all localities. The following tables include the standard classification of extras on iron and steel bars.

**Standard Classification\* of Extras on Iron and Steel Bars**  
Adopted July 15, 1919.

Rounds and squares			
Sizes	Extra per 100 lb	Sizes	Extra per 100 lb
6 in.....	Base	7 <sup>3</sup> / <sub>2</sub> in.....	\$1.00
6 in.....	\$0.05	8 in.....	1.25
7 in.....	0.10	3 <sup>1</sup> / <sub>8</sub> to 3 <sup>9</sup> / <sub>16</sub> in.....	0.075
8 in.....	0.20	3 <sup>5</sup> / <sub>8</sub> to 4 <sup>1</sup> / <sub>16</sub> in.....	0.125
9 in.....	0.25	4 <sup>1</sup> / <sub>8</sub> to 4 <sup>9</sup> / <sub>16</sub> in.....	0.15
10 in.....	0.30	4 <sup>5</sup> / <sub>8</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....	0.20
11 in.....	0.35	5 <sup>1</sup> / <sub>8</sub> to 5 <sup>9</sup> / <sub>16</sub> in.....	0.25
12 in.....	0.40	5 <sup>5</sup> / <sub>8</sub> to 6 <sup>1</sup> / <sub>16</sub> in.....	0.375
13 in.....	0.50	6 <sup>1</sup> / <sub>8</sub> to 6 <sup>1</sup> / <sub>16</sub> in.....	0.50
14 in.....	0.75	6 <sup>5</sup> / <sub>8</sub> to 7 <sup>1</sup> / <sub>4</sub> in.....	0.625

Flats		Extra per 100 lb
Sizes		
1 in X 1 <sup>3</sup> / <sub>8</sub> to 1 in.....		Base
1 in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		\$0.10
1 <sup>1</sup> / <sub>16</sub> in X 3 <sup>1</sup> / <sub>8</sub> to 3 <sup>1</sup> / <sub>4</sub> in.....		0.20
1 <sup>1</sup> / <sub>16</sub> in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		0.25
1 in X 3 <sup>1</sup> / <sub>8</sub> to 1 <sup>1</sup> / <sub>2</sub> in.....		0.25
1 in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		0.35
1 in X 3 <sup>1</sup> / <sub>8</sub> to 7 <sup>1</sup> / <sub>16</sub> in.....		0.50
1 in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		0.60
1 in X 3 <sup>1</sup> / <sub>8</sub> in.....		0.70
1 in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		0.80
1 in X 1 <sup>1</sup> / <sub>4</sub> to 5 <sup>1</sup> / <sub>16</sub> in.....		1.00
1 in X 1 <sup>1</sup> / <sub>16</sub> to 1 <sup>3</sup> / <sub>16</sub> in.....		0.05
1 in X 1 <sup>1</sup> / <sub>4</sub> to 1 <sup>1</sup> / <sub>2</sub> in.....		0.10
1 in X 1 <sup>5</sup> / <sub>8</sub> to 2 <sup>3</sup> / <sub>4</sub> in.....		0.15
1 in X 3 to 4 in.....		0.20

**Standard Classification † of Angles, Channels and Tees**

Angles		Extra per 100 lb
Sizes		
1 in and wider, but under 3 in X 3 <sup>1</sup> / <sub>16</sub> in and over.....		\$0.10
1 in and wider, but under 3 in X 1 <sup>1</sup> / <sub>8</sub> in.....		0.15
1 <sup>1</sup> / <sub>4</sub> X 1 <sup>1</sup> / <sub>4</sub> in X 3 <sup>1</sup> / <sub>16</sub> in and over.....		0.15
1 <sup>1</sup> / <sub>4</sub> X 1 <sup>1</sup> / <sub>4</sub> in X 1 <sup>1</sup> / <sub>8</sub> in.....		0.20
1 in X 3 <sup>1</sup> / <sub>16</sub> in.....		0.20
1 in X 1 <sup>1</sup> / <sub>8</sub> in.....		0.25
1 in X 3 <sup>1</sup> / <sub>16</sub> in.....		0.25
1 in X 1 <sup>1</sup> / <sub>8</sub> in.....		0.30
1 in X 1 <sup>1</sup> / <sub>8</sub> in.....		1.10
1 in X 3 <sup>3</sup> / <sub>32</sub> in.....		1.30
1 in X 1 <sup>1</sup> / <sub>8</sub> in.....		1.60
1 in X less than 1 <sup>1</sup> / <sub>8</sub> in.....		1.80
both legs X less than 1 <sup>1</sup> / <sub>4</sub> in.....		0.35

Angles are subject to special prices, which will be furnished on application

Small sizes take the next higher extra. It is not customary to enforce more than the "standard-card extras" for round and square bars.

Large sizes take the next higher extra.

## Standard Classification \* of Angles, Channels and Tees (Concluded)

Channels	
Sizes	Extra per 100 lb
1 1/2 in and wider, but under 3 in X 3/16 in and over.....	\$0.15
1 1/2 in and wider, but under 3 in X 1/8 in .....	0.25
1 to 1 1/4 in X 3/16 in and over.....	0.25
1 to 1 1/4 in X 1/8 in.....	0.35
1 to 1 1/4 in X 7/64 in.....	0.50
3/4 and 7/8 in X 3/16 in and over.....	0.30
3/4 and 7/8 in X 1/8 in.....	0.40
3/4 and 7/8 in X 7/64 in.....	0.55
5/8 in X 1/8 in and over.....	1.20
5/8 in X 3/32 in.....	1.40
1/2 in X 7/64 in and over. ....	1.80
1/2 in X 5/64 in. ....	2.00
Tees	
Sizes	Extra per 100 lb
1 1/2 X 1 1/2 in and wider, but under 3 in X 3/16 in and over.....	\$0.20
1 X 1 to 1 1/4 X 1 1/4 in X 3/16 in and over.....	0.40
1 X 1 to 1 1/4 X 1 1/4 in X 1/8 in.....	0.50
7/8 X 7/8 in X 3/16 in.....	0.50
7/8 X 7/8 in X 1/8 in.....	0.60
3/4 X 3/4 in X 3/16 in.....	0.60
3/4 X 3/4 in X 1/8 in.....	0.70
5/8 X 5/8 in X 1/8 in.....	1.30
1/2 X 1/2 in X 1/8 in.....	1.80
Unequal-leg tees are subject to special prices, which will be furnished on application.	

\* Intermediate sizes take the next higher extra.

The base for car-load lots for any city may be obtained by adding the freight rates given on page 1524 to the base prevailing at the mills.

## CHAPTER XXXI

## DOMICAL AND VAULTED STRUCTURES \*

By

EDWARD F. RIES

CONSULTING ENGINEER, SAN ANTONIO, TEXAS

## 1. Domes \*

**Definition:** Domical structures may be considered under two main divisions: (1) Smooth-shell domes, and (2) ribbed domes. The first division may be divided into (a) domes with shells of uniform thickness, and (b) domes with shells of uniformly varying thickness. The materials of construction of division (1) are brick, stone, concrete, and tile; and of division (2), iron, steel, and wood. A dome may be constructed with or without an oculus or eye; and in the case of ribbed domes may have either circular or polygonal bases.

## (1) Smooth-Shell Domes

**General Principles.** Under this heading are considered both (a) domes of uniform thickness, and (b) domes with shells of uniformly varying thickness, and also domes with or without lanterns and eyes. A dome that tapers toward the top is the more stable dome. It is evident that the upper part, or crown, tends to fall in and thereby push out the lower portion of the dome. The lighter the upper part is in relation to the lower part, the more stable the dome. The exact actions of the INTERNAL STRESSES in a dome are difficult to determine, but a very practical solution can, however, be developed by assuming that the stresses are parallel to a surface midway between the inner and outer surfaces of the dome.

**Analysis.** A dome may be imagined to consist of a number of concentric rings of decreasing diameter, each one laid on top of another. As the upper part tends to fall in and push out the lower part, there must be a tendency to contract each ring in the upper part and to expand each ring in the lower part. That is, there must be END-COMPRESSION on all stones (imaginary or concrete) of the upper part, and END-TENSION on all stones of the lower part. The dividing line or horizontal joint between these upper and lower parts of the dome is called the JOINT OF RUPTURE. The angle made by the line of rupture with the vertical (center of dome as apex of angle) is known as the CRITICAL ANGLE. It is evident, then, that the determination of the CRITICAL ANGLE and the CRITICAL TENSION determines also the points below which there is tension in the rings. By reinforcing the lower part with steel to resist this tension, the dome can be made secure. If the dome is a true dome, that is, one in which the angle the base makes with the vertical is the CRITICAL ANGLE, the tension-steel must be placed at the base to resist the outward push or thrust,

\* See, also, Chapters VII and VIII.





$$s = 2\pi \left[ (1 - \cos \theta) + \frac{cr}{a} (\sin \theta - \theta \cos \theta) \right]$$

$$(4) \quad P = 2\pi war^2 \left[ (n \operatorname{cosec} \theta + \operatorname{cosec} \theta - \cotan \theta) + \frac{cr}{a} (1 - \theta \cotan \theta) \right]$$

$$(5) \quad U = war \left[ \frac{n}{\sin^2 \theta} + \frac{\operatorname{cosec} \theta - \cotan \theta + \frac{cr}{a} (1 - \theta \cotan \theta)}{\sin \theta} \right]$$

$= war (S_1 + S)$ , in which

$$S_1 = \frac{n}{\sin^2 \theta} \quad \text{and}$$

$$S = \frac{\operatorname{cosec} \theta - \cotan \theta + \frac{cr}{a} (1 - \theta \cotan \theta)}{\sin \theta}$$

$$(6) \quad T = \frac{H}{2\pi} = war^2 \left[ n \cotan \theta + (1 - \cos \theta) \cotan \theta + \frac{cr}{a} (\sin \theta - \theta \cos \theta) \cotan \theta \right]$$

$= war^2 (Y_1 + Y)$ , in which

$$Y_1 = n \cotan \theta \quad \text{and}$$

$$Y = \left[ (1 - \cos \theta) \cotan \theta + \frac{cr}{a} (\sin \theta - \theta \cos \theta) \cotan \theta \right]$$

$$(7) \quad \frac{cr}{a} = \left[ n \operatorname{cosec}^2 \theta - \frac{\cos \theta - \sin^2 \theta}{1 + \cos \theta} \right] + \left[ \theta \cos \theta - \frac{1 - \theta \cotan \theta}{\sin \theta} \right]$$

**and Investigation of Smooth-Shell Circular Domes.** By the use of the foregoing equations any CIRCULAR DOME can be designed or investigated. Computations, however, connected with some of these equations are long and tedious, and are simplified by using curves plotted from the solutions giving different values to some of their elements or factors. (See Plates III, and IV.)

Equation (7) is represented by the curves in Plate I. By the use of these curves the position of the JOINT OF RUPTURE for any dome is found by inspection.

If the values of  $\frac{cr}{a}$  and  $n$  are known. The value of  $\theta$  is easily determined, as

shown by using Equation (1) after determining or assuming  $a$ , the thickness at the crown, and  $t$ , the thickness at the base; and the value of  $n$  is found

$$n = \frac{W_{1-0}}{2\pi war^2}.$$

Equation (5) is represented by the curves in Plate II. From these curves the value of  $U$  is determined.

Equation (6) is represented by the curves in Plate III. Knowing the values of  $T$  and  $H$ , the values of  $S_1$  and  $S$  are found by inspection, and hence  $U$  is easily




Plate I. Curves for Determination of Joint of Rupture of Domes. Based on Equation 5

Equation (6) is represented by the curves in Plate IV. Knowing the values  $m$  and  $\frac{\sigma}{\delta}$ , the values of  $Y_1$  and  $Y$  are found, and  $T$  computed for any ring. When  $m$  equals zero,  $Y_1$  equals zero, and the value of  $T$  depends upon  $Y$  as given in the lower curves. It will be noticed that  $Y$  increases as  $\theta$  increases until the critical angle for a dome without lantern, or eye ( $m = 0$ ), is reached; that is, as successive rings increase the outward thrust, and at the critical angle there is a maximum value of  $Y$ , and hence a maximum hoop-tension  $T$ . After the critical angle is passed the rings are in tension, and therefore  $T$  and  $Y$  are reduced by the tension required of the ring or masonry.

The curves also indicate that the stability of a dome with a shell of walls

Angle  $\theta$ 

### Values of $z$

Determination of Weight of Shell of Domes. Based on Equation (3)

no lantern is not affected by the thickness of the shell, therefore  $\frac{cr}{a} = 0$ , regardless of the value of  $a$ .

required to design a SMOOTH SHELL REINFORCED CONCRETE and with a lantern of 10-ft radius, weighing 50 000 lb. The lantern is to be removed, forming an eye. (Fig. 2.)

a crown-thickness,  $a$ , of 5 in, and a thickness,  $t$ , at the base

$$t = a + cr\theta, \text{ or } \frac{cr}{a} = \frac{t-a}{a\theta}$$

Angle  $\theta$ 

Plate III. Curves for Determination of Tangential Stress per Unit-length of Dome-ring. Based on Equation (5)

For the dome without wind-loads or snow-loads

$$\frac{cr}{a} = \frac{\frac{8}{12} - \frac{5}{12}}{\left(\frac{5}{12}\right) 1.396} = 0.165$$

The angle  $\alpha = \sin^{-1} \frac{10}{45} = 12^\circ 50'$ .

From Plate II the weight of the shell removed for the eye is

$$150 \left(\frac{5}{12}\right) (45)^2 (0.165) = 20\,883 \text{ lb}$$

Angle  $\theta$ 

Curves for Determination of Hoop-tension or Hoop-compression in Dome-ring. Based on Equation (6)

$$W_{1-\theta} = 50\,000 - 20\,883 = 29\,117 \text{ lb}$$

loads and snow-loads a simple and safe method of procedure is to form load over the surface of the dome, since this load can be transformed equivalent in inches of masonry and hence the same equations and

A wind-load, for example, of 25 lb per sq ft, is equivalent to 2 in weighing 150 lb per cu ft. Hence the new  $a$  and  $t$  equal 7 and 10 in, Hence from Equation (1)

$$\frac{\sigma}{s} = \frac{\frac{10}{12} - \frac{7}{12}}{\left(\frac{7}{12}\right) 0.1396} = 0.307$$

and

$$n = \frac{W_{l-o}}{2\pi r a^2} = \frac{29\ 117}{2\pi(150)\left(\frac{7}{12}\right)(45)^2} = 0.026^*$$




Fig. 2. Smooth-shell Concrete Dome with Lantern and Eye. See Example

The remaining required sectional area of steel,  $4.12 - 2.12 = 2$  sq in, must be spaced in the lower part of the dome over an angular distance of  $(80^\circ - 52^\circ) = 27^\circ 25' = 0.4785$  radian, or  $0.4785 \times 45 = 21.53$  ft up the surface of dome.

The assumed thickness of shell at the base was 8 in, and the thickness at lantern-ring will be, from Equation (1),

$$t = a + cr\theta = a + a \frac{cr}{a} \theta$$

or

$$5 + 5(0.43)(0.2239) = 5.48 \text{ in}$$

Allowing 0.2 per cent of steel cross-section, horizontally and meridionally, SECONDARY STRESSES caused by temperature-changes and possible uneven snow-loads and wind-loads, there should be  $8 \times 12 \times 0.002 = 0.19$  sq in of cross-section per running foot at the base, and  $5.48 \times 12 \times 0.002 = 0.13$  sq in per running foot at the lantern-ring. The spacing of the horizontal reinforcement

\* The snow-load on the top of the lantern is taken care of because snow-loads and wind-loads over the entire dome were included, and only the actual masonry of the eye subtracted.

From Plate I, with  $\frac{cr}{a} = 0.3$  and  $n = 0.026$ , the CRITICAL ANGLE is found to be  $52^\circ 35'$ .

From Plate IV, at the CRITICAL ANGLE for the dome with snow-load and wind-load

$$T = 150 \left( \frac{7}{12} \right) (45)^2 (0.020 + 0.3) = 65\ 914 \text{ lb tension}$$

This must be resisted by reinforcing rods. Allowing a tensile stress of 16 000 lb/sq in in the steel, a total  $\frac{65\ 914}{16\ 000} = 4.12$  sq in sectional area of steel is required. At the base ( $\theta = 80^\circ$ )

$$T = 150 \left( \frac{7}{12} \right) (45)^2 (0.005 + 0.3) = 33\ 843 \text{ lb}$$

The total cross-sectional area of steel in tension at the base  $\frac{33\ 843}{16\ 000} = 2.12$  sq in, given by

round rods, each  $\frac{3}{4}$  in in diameter

and as indicated in Fig. 3. Curve *A* gives the total amount of steel for SECONDARY STRESSES above any point in the cross-section of the dome. Curve *B* gives the necessary tensional resistance, using Curve *A* as a

#### Diagram for Determination of Amount of Horizontal Steel Reinforcing in Concrete Domes

for the ordinates. Various points on the curve are easily determined, for example, for  $\theta = 70^\circ$

$$t = 5 + 5(0.43)(1.2217) = 7.63 \text{ in}$$

Amount of temperature-steel per foot at  $70^\circ$  is

$$7.63 \times 12 \times 0.002 = 0.18 \text{ sq in}$$

Amount of temperature-steel above  $70^\circ$  is then

$$\frac{0.18 + 0.13}{2} \times (1.2217 - 0.2239)45 = 6.96 \text{ sq in}$$

Amount of tension-steel in cross-section (Plate IV) above  $70^\circ$  is

$$= \frac{(150)(7/12)(45)^2(0.298 + 0.009)}{16,000} = 0.72 \text{ sq in}$$

When determined in this manner the curves are developed.

Amount of horizontal steel in the entire cross-section of the

$$8.45 + 2.00 = 10.45 \text{ sq in}$$

Amount of tension-steel at the base. If  $\frac{3}{4}$ -in round rods

be  $\frac{10.45}{0.1963} = 54$ , required in the shell. By dividing the area

below the curve (Fig. 3) into 54 parts, the distance up from the base, where each rod should be placed, is determined. The meridional steel should be such that there will be 0.19 sq in of cross-section per foot of circumference at the base and 0.13 sq in per foot of circumference at the lantern-ring; that is, if  $\frac{1}{4}$ -in round rods are used, they should be spaced  $\frac{0.1963}{0.19} = 1.03$  ft at the base, and  $\frac{0.1963}{0.13} = 1.51$  ft at the lantern-ring. The punching-shear at the lantern-ring is equal to

$$\frac{50\,000}{(5.48)(2\pi 10 \times 12)} = 12.1 \text{ lb per sq in}$$

This is well within the limit of 40 lb per sq in.

## (2) Ribbed Domes

**General Principles.** The following discussion applies to domes of either circular or polygonal horizontal cross-sections. All steel domes are ribbed domes, and usually have from six to twenty-four ribs resting against a LANTERN RING or SPIDER at the top. The ribs may have solid webs, perforated webs, or latticed webs, with angle or channel-flanges. The latticed angle-ribs are preferable because of their lightness. The tension-rings and compression-rings may be built similar to the main ribs, and should brace the latter through rigid gusset-connections. The diagonals are usually rods with turnbuckles for adjustment. CONCRETE-RIBBED DOMES or WOODEN-RIBBED DOMES may be designed according to the same general principles followed for steel domes, but the diagonals are omitted and dependence for rigidity is placed on the slab-filling between the ribs.

**The Schwed or Method for the Design of Steel Domes.** W. Schwed has by simple resolution of the forces derived equations for domes, based on the forms of SURFACES OF REVOLUTION. These equations are easily checked with the forces acting through a RIB (the rib acting as a strut between the joints) and through a RING at a joint are considered. The following laws may be stated:

- (1) The ribs are in maximum stress when the whole dome is loaded;
- (2) A ring is in maximum tension when all of the dome above the ring is fully loaded, and in maximum compression when all of the dome below the ring and the ring itself is fully loaded;
- (3) The DIAGONALS are not stressed when the dome is symmetrically loaded. The diagonals in a panel are in maximum stress when the dome on one side of the meridional plane passed through the center of that panel is fully loaded and the other side unloaded.

In Fig. 4 let

- $\alpha_1, \alpha_2, \alpha_3$ , etc. = angles made by rib-sections with the horizontal;
- $\beta_1, \beta_2, \beta_3$ , etc. = angles made by diagonals with the ribs;
- $P_1, P_2, P_3$ , etc. = dead loads at ends of rib-sections;
- $L_1, L_2, L_3$ , etc. = live loads at ends of rib-sections;
- $D_1, D_2, D_3$ , etc. = stresses in rib-sections;
- $T_1, T_2, T_3$ , etc. = stresses in rings;
- $N_1, N_2, N_3$ , etc. = stresses in diagonals;
- $n$  = number of ribs.






Fig. 4. Schwedler Ribbed Dome

$$D_1 = \frac{P_1 + L_1}{\sin \alpha_1} \quad D_2 = \frac{(P_1 + L_1) + (P_2 + L_2)}{\sin \alpha_2}$$

$$D_3 = \frac{(P_1 + L_1) + (P_2 + L_2) + (P_3 + L_3)}{\sin \alpha_3}, \text{ etc.}$$

$$T_1 = - \frac{(P_1 + L_1) \cot \alpha_1}{2 \sin \frac{\pi}{n}} = - \frac{D_1 \cos \alpha_1}{2 \sin \frac{\pi}{n}}$$

ult is negative the stress is compressive).

$$\left\{ \begin{array}{l} \text{Maximum } T_2 = \frac{(P_1 + L_1) \cot \alpha_1 - (P_1 + L_1 + P_2) \cot \alpha_2}{2 \sin \frac{\pi}{n}} \end{array} \right.$$

$$\left\{ \begin{array}{l} \text{Minimum } T_2 = \frac{P_1 \cot \alpha_1 - (P_1 + P_2 + L_2) \cot \alpha_2}{2 \sin \frac{\pi}{n}} \end{array} \right.$$


$$\left\{ \begin{array}{l} \text{Maximum } T_3 = \frac{(P_1 + L_1 + P_2 + L_2) \cot \alpha_2 - (P_1 + L_1 + P_2 + L_2 + P_3) \cot \alpha_3}{2 \sin \frac{\pi}{n}} \end{array} \right.$$

$$\left\{ \begin{array}{l} \text{Minimum } T_3 = \frac{(P_1 + P_2) \cot \alpha_2 - (P_1 + P_2 + P_3 + L_3) \cot \alpha_3}{2 \sin \frac{\pi}{n}}, \text{ etc.} \end{array} \right.$$

$$N_1 = \frac{L_1}{2 \sin \alpha_1 \cos \beta_1}$$

$$N_2 = \frac{L_1 + L_2}{2 \sin \alpha_2 \cos \beta_2}$$

$$N_3 = \frac{L_1 + L_2 + L_3}{2 \sin \alpha_3 \cos \beta_3}, \text{ etc.}$$



For the stresses in the diagonals factor 2 is introduced because Mr Breslau found, by exact analysis, stresses only one half as large as those determined by the simple resolution of forces. The diagonals are stressed as if by a wind-load, and this is resisted by the ribs assuming a vertical live load equal from 20 to 30 lb per sq ft of HORIZONTAL PROJECTION.

A GRAPHICAL METHOD, developed by E. Schmidt, for determining the stresses  $D_1, D_2, D_3, T_1, T_2, T_3$ , etc., is shown in Fig. 4A.

**Weights of Steel Domes.** It was found by Scharowsky, from calculations made for a large number of Schwab & Co. FLAT DOMES varying in span from 6 to 180 ft, that the weight of the last and steel skeleton per sq ft of projected (covered) area is

$$w = 0.0156S + 4$$

where  $w$  = pounds per square foot of projected area, and  $S$  = the span, in feet. For preliminary calculations on HEMISPHERICAL DOMES, the weight found by this equation should be increased from two and a half to three times.

Fig. 4A. Graphical Determination of Stresses in Ribbed Domes

**Dome of the Horticulture Palace, San Francisco, Cal.\*** This is a **LER HEMISPHERICAL DOME** of 152-ft span, with twenty-four latticed ribs, carrying a **LANTERN-RING** or **SPIDER** at the top, and connected by eleven al rings. The lantern-ring is 6 ft in diameter, 36 in deep, with a solid 1 braced twice diametrically. The ribs are constructed of two 4 by 4 angles at the top, two 3 by 3 by  $5\frac{1}{8}$ -in angles at the bottom, and a  $2\frac{1}{2}$  by  $1\frac{1}{4}$ -in angle single-lattice web. The dome-steel weighs about 17 lb of projected area.

**ete Ribbed Domes.** In a **REINFORCED-CONCRETE RIBBED DOME** ber of ribs, varying from eight upward, is determined by the substructure the size of the dome. The different steps in designing a ribbed reinforced concrete dome are: (1) the determination of the number of ribs and rings; (2) determination of the loading, per rib, using the required shell-thickness assumed rib-sizes and ring-sizes for preliminary calculations; (3) the determination of the forces acting on the ribs by the use of Schwedler's formulas; (4) drawing of the **ELASTIC CURVE** for the ribs; (5) the determination of the required and necessary reinforcement in the ribs, rings, and slabs; (6) the adjustment of the sizes and loads, so as to be on the side of safety; and (7) the reworking of the preliminary computations for the final design. The **ELASTIC CURVE** should always remain in the **MIDDLE HALF** † OF THE RIB, and should never be far from the center of gravity of the rib-section that the maximum compression of 500 lb per sq in in the outer fiber of the rib is exceeded. The reinforcement in the RIBS should be sufficient to resist the flexural stresses due to the **EXCENTRICITY OF THE ELASTIC CURVE**. The reinforcement in the RINGS should be sufficient to resist the tensile stresses, and should be as straight as possible in order to avoid a sidewise stress or movement. The rings must be designed to resist their **FLEXURE**, as beams. The panel-slabs, if domical (see Bell Domes), should be reinforced for **SHRINKAGE-STRESSES** and **TEMPERATURE-STRESSES**, in addition to the reinforcement for tension below the slab. If the slabs are straight they should be designed as floor-slabs, by similar methods.

‡ It is required to build a dome (Fig. 5) with a span of 132 ft and a height of 6 in. This makes the radius 85 ft. The eye is to be 12 ft in diameter. The outer surface of the dome is to be a domical slab on ribs, carrying a plastered ceiling forming the inner surface.

§ To obviate the necessity of building a complete domical form, from the floor below, the decision is to build a **RIBBED DOME** as follows: First, build a central tower to temporarily carry the upper ends of the ribs; then cast these ribs, raise them into position, cast the ring of the eye, supporting forms from the ribs, pour the rings in place, and then fill in the panels on forms supported from the rings and ribs.


Since the **SPAN** of the dome is 132 ft, the **CIRCUMFERENCE** at the base is 414.7 ft. In the case of the suspension of the panel-forms, it is well to keep the **PANEL-FORMS**

See R. L. and T. F. Chase, Engineering Record, Oct. 24, 1914.

In practice has been to keep the resistance-line within the **MIDDLE THIRD** in the arch. In reinforced-concrete arches and domes it may depart a small distance from the middle third, but there should be sufficient steel to resist any tension. The ribs of domes differ from ordinary arches as they are rigidly braced and the slab-panels.

The design of this example is similar to the dome over the Hippodrome at Copenhagen, by Christiani and Nielsen. See the periodical, Concrete, for December,

In the construction of this example all calculations have been made with the slide-rule.



**Fig. 5. Segmental Concrete Ribbed Dome**

within about a 20-ft limit. Hence twenty ribs are necessary. With INTERMEDIATE RINGS, the lower panels are approximately square. The ribs are not to show below the ceiling, and hence a narrower spacing toward the top is unnecessary for appearance. For preliminary calculations, allowing 150 lb per lin ft for the eye-ring and the load due to a glass covering over the intermediate rings; and assuming a slab-thickness of  $3\frac{1}{2}$  in, a suspended ceiling  $\frac{3}{4}$  in thick, and 25 lb per sq ft of surface for snow-loads and wind-loads (an equivalent of a 2-in thickness of concrete), the loading on the ribs is shown in Diagram A of Fig. 5. To illustrate the METHOD OF DETERMINING LOADS, the calculations for the loading at the lower intermediate ring are given. The WEIGHT OF THE RIB is  $250 \times 17.39 = 4\,347$  lb. The WEIGHT OF THE GLASS IS  $150 \frac{2 \times \pi \times 85 \times \sin 39^\circ 14'}{20} = 2\,534$  lb. The WEIGHT OF THE CEILING between  $\theta = 33^\circ 21'$  and  $\theta = 45^\circ 5'$  is, from the curves in Fig. 4, with  $\frac{c'}{a} = 0$ ,

$$\frac{25 \left( \frac{3\frac{1}{2}}{12} + \frac{3}{4} \right) (85)^2 (1.84) - 150 \left( \frac{3\frac{1}{2}}{12} + \frac{3}{4} \right) (85)^2 (1.03)}{20} = 15\,570 \text{ lb}$$

The dead load is

$$4\,347 + 2\,534 + 15\,570 = 22\,451 \text{ lb}$$

The total live load is

$$\frac{15\,570 \times 2}{3\frac{1}{2} + \frac{3}{4}} = 7\,330 \text{ lb}$$

The stress  $D_4$  (see method in Fig. 4A), in the lower section of the rib is the same, and according to Schwedler's formulas, page 1223, is

$$\frac{6\,600 + 15\,301 + 22\,908 + 29\,781}{\sin 45^\circ 5'} = 105\,400 \text{ lb}$$

The ECCENTRICITY of the stress  $D_4$  is

$$85 - (85 \cos 5^\circ 51') = 0.445 \text{ ft}$$

The moment due to the ECCENTRICITY of  $D_4$  is

$$105\,400 \text{ lb} \times 0.445 \text{ ft} = 46\,903 \text{ ft-lb, or } 562\,836 \text{ in-lb}$$

At the COLUMN-LIKE COMPRESSION of  $D_4$  there is required a cross-section of rib of

$$\frac{105\,400}{500} = 211 \text{ sq in of concrete}$$

To resist the effect of the ECCENTRICITY of the stress  $D_4$ , it is necessary to use enough steel so that the total stress in it, multiplied by the distance between the top and bottom steel reinforcements, is equal to the moment, 562 836 in-lb, as just found.

The ECCENTRICITY of  $D_4$  is 0.445 ft, and the line of action of the thrust must be within the MIDDLE HALF OF THE RIB,\* the rib will be

$$4 \times 0.445 = 1.78 \text{ ft} = 21\frac{1}{2} \text{ in in depth}$$

\* See foot-note on page 1225.

Allowing  $1\frac{1}{2}$  in of concrete for steel-protection at the top and bottom of rib, the distance between the inner and outer reinforcements is

$$21\frac{1}{2} - 3 = 18\frac{1}{2} \text{ in}$$

Therefore a stress of

$$\frac{562\,836}{18\frac{1}{2}} = 30\,424 \text{ lb}$$

is to be resisted by the steel at the top and bottom. Since there is steel in both COMPRESSION and TENSION, the allowable UNIT STRESS in it is

$$\left( \frac{650 \times 18\frac{1}{2}}{21\frac{1}{2}} \right) (15 - 1) = 7\,830 \text{ lb per sq in}$$

This is because the allowable compressive unit stress in the outer fibers of concrete beams is 650 lb per sq in; the ratio of the MODULUS OF ELASTICITY of steel and of concrete, 15; and the distance between the inner and outer steel reinforcements, and the distance of the rib-depth,  $18\frac{1}{2}$  and  $21\frac{1}{2}$  in respectively. The 1 in the expression  $(15 - 1)$  is to take care of the stress carried by the concrete replaced by the steel.

The TOTAL CROSS-SECTION of steel necessary at both the top and bottom of the rib is, therefore,

$$\frac{30\,424}{7\,830} = 3.89 \text{ sq in}$$

furnished by four  $1\frac{1}{4}$ -in round rods. The best arrangement of the 211 sq in of concrete, and the steel, results in a cross-sectional shape shown in Diagram of Fig. 5. The STIRRUPS should be spaced not more than three fourths of the distance between lines of longitudinal steel, or  $\frac{3}{4} \times 18\frac{1}{2} = 12$  in (approximately) and they should be made from  $\frac{3}{8}$ -in round rods. Because of the TIES in the flanges, it is advisable to use small  $\frac{1}{4}$ -in rods as STIFFENERS at the intersections of the ties and stirrups. Projecting LOOPS should be left for fastening the panel-slabs. The actual weight per linear foot of the ribs is

$$\frac{211}{144} \times 150 = 220 \text{ lb}$$

for the concrete, plus

$$(4 + 3.38) + 11 = 25 \text{ lb}$$

for the steel, equal to a total of 245 lb, as against 250 lb per lin ft previously allowed in the calculations.

As the ribs are to be precast and raised into place, it is necessary to determine whether they are of sufficient strength for this, and whether they will stand, unsupported by the rings, without breaking under their own weight. By considering the ribs to be simple arches, and testing them by determining the line of thrust, it is found that they are amply safe. In order to resist the thrust stresses developed by raising the ribs into place, it is necessary to tie the ends together with bow-string rods.

The stresses in all of the rings, except the FOOTING-RING, are compressive. This is because they are all above the CRITICAL ANGLE. (See Smooth-Shear Domes.) Therefore, in determining the stresses by Schwedler's formulas, only the equations for the MINIMUM VALUES of  $T_1$ ,  $T_2$ ,  $T_3$ , and  $T_4$  need be used.

The stress in the EYE-RING is

$$\frac{(5\,750 + 850) \cot 9^\circ 55'}{2 \sin \frac{\pi}{20}} = -120\,600 \text{ lb}$$

stress in the FIRST INTERMEDIATE RING is

$$\frac{750 \cot 9^\circ 55' - (5\,750 + 12\,146 + 3\,155) \cot 21^\circ 38'}{2 \sin \frac{\pi}{20}} = -65\,000 \text{ lb}$$

stress in the SECOND INTERMEDIATE RING is

$$\frac{12\,146 \cot 21^\circ 38' - (5\,750 + 12\,146 + 17\,573 + 5\,335) \cot 33^\circ 21'}{2 \sin \frac{\pi}{20}} = -53\,900 \text{ lb}$$

stress in the THIRD INTERMEDIATE RING IS

$$\frac{12\,146 + 17\,573 \cot 33^\circ 21' - (5\,750 + 12\,146 + 17\,573 + 22\,451 + 7\,330) \cot 45^\circ 5'}{2 \sin \frac{\pi}{20}} = -35\,600 \text{ lb}$$

stress in the FOOTING-RING is tensile, and hence the equation for the MAXIMUM VALUE of  $T$ , gives

$$\frac{12\,146 + 17\,573 + 22\,451 + 7\,330 \cot 45^\circ 5' - (850 + 12\,146 + 3\,155 + 17\,573 + 5\,335 + 22\,451 + 7\,330) \cot 45^\circ 5'}{2 \sin \frac{\pi}{20}} = 238\,000 \text{ lb}$$

FOOTING-RING should have  $\frac{120\,600}{500} = 242$  sq in of concrete, but for appearance it should be as wide as or wider than the ribs; hence it is made  $21\frac{1}{2}$  in high and 16 in wide.

This size allows, also, a firm ANCHORAGE for the rib-reinforcing. With this anchorage it requires four  $1\frac{1}{8}$ -in round rods. (See Diagram C, Fig. 5.) The intermediate ring should be

$$\frac{65\,000}{500} = 130 \text{ sq in}$$

section, requiring a 7-in width and a  $18\frac{1}{2}$ -in height, to resist the load, as a

As the ring must also act as a BEAM, carrying its own weight, the weight of half the slab, and the live load (the forms taking the place of the live load during construction), steel must be added to resist the BENDING MOMENT

$$\frac{130}{144} \times 150 \left( \frac{2\pi 85 \sin 15^\circ 47'}{20} \right)^2 + \left( \frac{6\,710 + 3\,155}{2} \right) \left( \frac{2\pi 85 \sin 15^\circ 47'}{20} \right)$$

12

$$70 \text{ ft-lb} = 42\,840 \text{ in-lb}$$

steel, in TENSION and COMPRESSION, must be added to keep the stress in the concrete, due to this moment, down to 150 lb per sq in, since 650 lb per sq in is the MAXIMUM ALLOWABLE COMPRESSIVE STRESS in concrete of the beam. From Formula (1) page 925, or Formula (5) page

$$K = \frac{42\,840}{7 \times (17)^2} = 21.2$$

Formulas (2), (3) and (4), (pages 925-6), when  $K = 21.2$  and  $S_t = 16\,000$  in<sup>2</sup>;  $S_c = 245$  lb per sq in,  $p = 0.0014$ , and  $x = 0.185$ . Since  $S_c$  must

not exceed 150 lb per sq in, it is necessary to add COMPRESSION-STEEL to resist stress of

$$\left( \frac{245 - 150}{2} \right) (7)(0.185 \times 17) = 1\,040 \text{ lb}$$

The allowable stress in the COMPRESSION-STEEL (page 1228), less the stress already allowed for the concrete which is replaced by the steel, if placed  $1\frac{1}{2}$  in from the outside, is

$$\left( \frac{650}{0.185 \times 17} \right) \left( (0.185 \times 17) - 1.5 \right) (15 - 1) = 4\,770 \text{ lb per sq in}$$

The amount of COMPRESSION-STEEL is, therefore,

$$\frac{1\,040}{4\,770} = 0.22 \text{ sq in, cross-section}$$

The tensile-steel necessary is

$$0.0014 \times 7 \times 17 = 0.16 \text{ sq in}$$

but because of the NEGATIVE MOMENT at the ribs, the same cross-sectional area is used as for COMPRESSION, that is, 0.22 sq in, furnished by two  $\frac{3}{8}$ -in round rods. The UNIT-SHEAR is

$$\frac{\left( \frac{130}{144} \times 150 \right) \left( \frac{2\pi 85 \sin 15^\circ 47'}{20} \right) + \left( \frac{6\,710 + 3\,155}{2} \right)}{7 \times 17 \times \left( 1 - \frac{0.185}{3} \right) \times 2} = 18.6 \text{ lb per sq in}$$

No STIRRUPS are necessary to resist shear, but stirrups made from  $\frac{1}{4}$ -in round rods should be spaced about 18 in on centers, to tie the panel-slabs securely to the ring.

The SECOND INTERMEDIATE RING, if made the same size as the first, will have a stress of

$$\frac{53\,900}{7 \times 18\frac{1}{2}} = 416 \text{ lb per sq in}$$

The MOMENT will be

$$\frac{\left( \frac{130}{144} \times 150 \right) \left( \frac{2\pi 85 \sin 27^\circ 31'}{20} \right)^2 + \left( \frac{11\,375 + 5\,335}{2} \right) \left( \frac{2\pi 85 \sin 27^\circ 31'}{20} \right)}{12} = 10\,300 \text{ ft-lb} = 123\,600 \text{ in-lb}$$

From Formulas (1), (2), (3), and (4), (pages 925-6),  $K = 61.2$ ,  $S_c = 455 \text{ lb per sq in}$ ,  $p = 0.0043$ , and  $x = 0.3$ . Since  $S_c$  cannot exceed  $650 - 416 = 234 \text{ lb per sq in}$  the COMPRESSION-STEEL must resist

$$\left( \frac{455 - 284}{2} \right) (7)(0.3 \times 17) = 3\,930 \text{ lb}$$

The section-area of the COMPRESSION-STEEL is, therefore,

$$\frac{3\,930}{\left( \frac{650}{0.3 \times 17} \right) \left( (0.3 \times 17) - 1.5 \right) (15 - 1)} = 0.62 \text{ sq in}$$

furnished by two  $\frac{3}{4}$ -in round rods at top and bottom. The UNIT SHEAR is



$$\frac{\left( \frac{2\pi 85 \sin 27^\circ 31'}{20} \right)^2 + \left( \frac{11\,375 + 5\,335}{2} \right)}{7 \times 17 \times \left( 1 - \frac{0.3}{3} \right) \times 2} = 46.9 \text{ in per sq in}$$

efore necessary to resist  $46.9 - 40 = 6.9$  lb per sq in of shear, with that is, with two  $\frac{3}{4}$ -in round-rod stirrups, spaced 12 in apart at the the others 18 in apart through the remaining distances.

IRD INTERMEDIATE RING is 7 by  $18\frac{1}{2}$  in in section, with two  $\frac{1}{8}$ -in s at top and bottom, and with two  $\frac{3}{8}$ -in round-rod STIRRUPS, spaced at the ends, two more, spaced 12 in, and the rest spaced 18 in.

MENT due to the ECCENTRICITY of the COLUMN-LIKE THRUST, that is, rdinal horizontal compressive stress, in the rings is resisted by the slabs. act analysis may be made by considering only the NORMAL COMPONENTS ADS on the rings in determining these moments.

TING-RING must have enough tensile-steel to resist the outward PUSH of the ribs, that is  $\frac{238\,000}{16\,000} = 14.9$  sq in of steel cross-section. In

o this, if the ring acts as a BEAM, there must be sufficient steel to resist t due to the combined weights of the dome and the ring itself.

VEL-SLABS being domical and above the critical angle, are in com- and should be designed as illustrated in the discussion of Smooth- es.

## 2. Vaults \*

ation. Vaults may be conveniently considered under the following (1) Barrel vaults, (2) Groined vaults, and (3) Ribbed vaults (Masonry, amed).

Considerations. A knowledge of the ELASTIC THEORY OF ARCHES bility of buttresses is necessary in a rigid investigation of vaults, since involves the application of the principles of that theory. (See, also, II and VIII.) In any vault, lines of action of the stresses or thrusts through the material between certain limiting lines; otherwise the ail. These thrusts are brought to the grade-line, or to foundations, ften buttressed in the case of barrel vaults, and by piers and but- he case of groined and ribbed vaults. By building vaults of light uch as hollow bricks or hollow tiles, the magnitude of the thrusts are and lighter walls, piers, or buttresses can be used.




Fig. 1. Three Methods of Building Barrel Vaults

ults. Fig. 1, (a), (b), and (c), illustrates three methods of building VLTS. In (c) the longitudinal ribs are merely for appearance, as atment of this subject may be found in the *Handbuch der Architektur*, 's *Baukonstructions Lehre*.

they do not strengthen the vault. The diagrams (a) and (b), Fig. 2, illustrate methods of disengaging the masonry of barrel vaults from the walls. Dia-

(b) is the better method and improves the appearance of the vault on inside. Diagrams (c) and (d) illustrate the use of stone skewbacks for barrel vaults.

**Strength of Barrel Vaults.** Barrel vaults may be considered as a series of arches set next to each other; and hence if a section one unit long is found to be safe when investigated as an arch, the vault itself may be considered safe. By joining the wall and the vault together as a unit, the

(a) (c) (d) (b)  
Fig. 2. Methods of Joining Barrel Vaults to Walls

point on the arc  $60^\circ$  from the vertical or crown, that is, to a point on the intrados one third of the distance from the horizontal spring-line, the actual thickness is materially decreased. With the spring-line at  $60^\circ$ , the line of thrust in an unloaded arch or barrel vault of an equal thickness throughout, will remain within a strip whose radial thickness or width is about one forty-second of the radius. If the line of thrust is to remain within the middle third of the arch-ring or vault-ring,  $t$  should be  $(r/42) \times 3 = r/14$ . If it is to remain within the middle half,  $t$  should be  $(r/42) \times 2 = r/21$ . In the following example, the theory of the middle half will be followed, in which  $t = r/21$ . If it were assumed that  $t = r/14$ , the line of thrust being kept within the middle third, the span of the vault in the example would have to be changed from 21 to 14 ft.




Fig. 3. Analysis of Barrel Vault

If built, then, as described (Fig. 3), the minimum thickness of the vault-shell is about one twenty-first of the vault-radius, that is,

$$t = r/21$$

The VERTICAL COMPONENT  $P_v$  of the thrust  $P$  is equal to the weight of half free vault, that is, of the section ABCD. It can be shown that the

THE  $P_h$  of the thrust is 0.79 of the vertical component, and that the thrust is not at right-angles with the spring-line  $AB$ ; that is,

$$P_h = 0.79P$$

Ex. 1. It is required to construct a BARREL VAULT over a corridor 21 ft wide. The vault-radius is  $10\frac{1}{2}$  ft, and the minimum thickness of the shell is 6 in. If built of bricks it is cheaper to build a ribbed vault, as the dimensions of bricks are approximately 4 in, 8 in, 12 in, etc. Referring to Ex. 1, it is found that a 4-in vault with ribs 4 by 8 in every 3 ft 3 in, is equiva-

#### 1. Barrel Vaults, Ribbed and Non-ribbed. Equivalent Thicknesses

6-in vault, and hence would be used. The brick masonry weighs 125 lb per cu ft.

VERTICAL COMPONENT  $P_v$  of the thrust is

$$\frac{\frac{1}{2} \times \frac{1}{3}\pi \times 10.5 \times 125 + [4/12 \times 8/12 \times \frac{1}{3}\pi(10.5 + 0.33) \times 125]}{3\frac{1}{4}} = 557 \text{ lb per lin ft}$$

HORIZONTAL COMPONENT  $P_h$  of the thrust is  $0.79 \times 557 = 440$  lb per lin ft. The supporting wall must be thick enough, buttressed enough, or loaded sufficiently from above, to take care of this horizontal component of the thrust. See a graphical analysis of the stresses in this vault. It will be noticed that the line of pressure remains in the MIDDLE HALF of the vault-thickness. Reffler, after numerous tests of vaults, stated \* that if one fourth the

\* Theorie der Gewölbe.

vault-thickness is deducted at the extrados, and one fourth at the intrados, so that if the line of pressure found according to the elastic theory of arches

:

Fig. 5. Graphical Determination of Stresses in a Barrel Vault

confined to the remaining portion, that is, the MIDDLE HALF, then the vault may be considered safe. Fig. 6 shows the resistance-line passing slightly outside of the





Fig. 6. Line of Pressure through Vault-thickness

middle third.\* It illustrates the less conservative theory that the resistance line might in some cases pass near the outside of the middle half. The arch or vault in Diagram (b) of Fig. 6 would have a greater tendency to fail according to the middle-third theory, because the line of pressure or resistance-line passes outside of the middle third. Diagram (a) of Fig. 6 shows the same arch or vault with the shell cut so that the line of pressure passes down the exact center of the uncut portion. This results in a sort of theoretical or ideal arch-form

\* See foot-note relating to Concrete Ribbed Domes, page 1225.

se the thickness of part  $c$  must be sufficient to develop a safe compressive resistance in the material, and it is advisable to add sufficient steel to take any tension in the parts farthest from the resistance-line. Vaulted construction is often relatively protected and free from the live loads and moving loads which arches are generally subjected; and for such construction the conclusions are considered valid.

**Groined Vaults.** A GROINED VAULT is formed by the intersection of two vaults. (See (a), Fig. 7.) By using groined vaults it is possible to



ective, Showing Penetrations and Intersections

Intersecting Vaults of Different Widths

Fig. 7. Groined Vault

tops of windows and doors above the spring-lines of the vaults, and to be the pressures or thrusts on piers or columns.

The intersections of two vaults, called GROINS, are straight lines in projection, only when they are of the same curvature and height. If they are of different widths, it is best to make one semicircular, draw vertical projections of the groins as straight lines, and then determine the contour of the other vault. This is illustrated in Fig. 7 (b). Vault  $A$  is semicircular and has a span  $A$ . Vault  $B$  has a span  $B$ .  $CC$  are the GROINS, and  $D$  is the contour of the narrow vault. Any points,  $a, b, c$ , etc., are chosen at equal intervals along the span of the wide vault, and lines  $a-a_1, b-b_1, c-c_1$ , etc., and  $a-a_2, b-b_2, c-c_2$ , etc., drawn parallel to the respective vaults. The line  $a_1-a_2$  is laid off equal to  $a_1-a_2, b_1-b_2, c_1-c_2$ , etc. The smooth curve connecting  $a_1, b_1, c_1$ , etc., is the contour  $E$  of the wide vault. In like manner the contour  $F$  of the groins is found by similarly laying off  $a_3-a_4, b_3-b_4, c_3-c_4$ , etc., equal to  $a_1-a_2, b_1-b_2, c_1-c_2$ , etc.

**MITER-SHELLS**, at the intersections or groins, should never have what are called MITER-JOINTS. The vaults should be monolithic or there should be continuous ribs to carry the vault-shells and transmit the thrusts to the piers. If intersecting vaults are of stone, and of the same diameter, the groins may be constructed as shown in Fig. 8 (a) for small vaults, or as in Fig. 8 (b) for larger vaults. In Fig. 8 (a) the GROIN-STONES are L-shaped and are cut so as to carry the courses of one vault around to the other vault. The stone shown in (b) of Fig. 8 is shown in plan at  $b$ , with two views at  $c$  and  $d$ . A better method is shown in Fig. 8 (b). Here the groin-stones are cut so that the joints

are normal to the groins, thus forming concealed ribs. This bearing-surface is obtained as follows. Point  $a$ , the intersection of an extended vault-joint with the groin-edge, is projected down to  $a'$  and  $b'$ , the intersections of the projecti line and the assumed side and center lines of the rib. Point  $b'$  is projected up




Fig. 8. Groin-details for Stone Vaults of the Same Diameter

$b''$ , a point on the center line or edge of the rib. From  $b'$  a horizontal line intersects with a line projected up from  $a'$  to give  $c''$  a point on the joint, which is drawn normal to the groin. The intersection  $d''$  of this joint with the groin edge is projected down to  $d'$  on the center line of the rib. By connecti

## Vaults

$f$ , and  $d'$  and  $e'$  (the point opposite  $a'$  on the other side of the rib)  
line, the lower edge of the bearing-surface is determined.  
 $d'$  and  $e'$  projected up determine  $d$  and  $e$ , the same points in elev:

### Fig. 9. Groin-details for Stone Vaults of Different Diameters

on these curved lines can be found by choosing points between  
projecting them in the same way as in the method used to find  
of  $f$ . The procedure is as follows. The point  $f$  is projected

to the center line of the rib, locating  $g'$ . Then  $g'$  is projected up to  $g''$ , the intersection with the line representing the joining of the upper surfaces of the vaults. A horizontal line is projected over from  $g''$  to  $f''$ , the point of intersection with the normal joint. The point  $f''$  is projected down to  $f'$ , on the projecting line from  $g'$ . By connecting  $f'$  and  $h'$  ( $h'$  is opposite  $f'$  and equidistant from the center line of the rib) with a straight line, the upper edge of the bearing-surface is determined. The point  $h$  is found by projecting up from  $h'$ . By connecting  $a'$  and  $f'$ ,  $a'$  and  $h'$ ; also  $a$  and  $f$ , and  $e$  and  $h$ , the side edges of the bearing-joint are located. The lower bearing-surface of a stone, or the upper bearing-surface of the lower stone, is found in a similar manner.

If the vaults are not of the same diameter, either of two methods may be used. The number of stone courses in both vaults may be made the same, thus making the courses in the wide vault wider than those in the narrow vault, and the method of finding the shape of the groin-stones is similar to that shown in Fig. 8, or the stones may be the same width, thus making a greater number of courses in the wide vault than in the narrow vault. In the latter case the groin-stones are terminated as in Fig. 9. To take care of the different number of courses in the vaults, one course in the narrow vault is sometimes made to receive two courses in the wide vault, as shown by stone  $A$  in Fig. 9. Because the joint  $a$  is higher than the joint  $b$ , there results a peak toward the side of the groin-line. This is cut off at right-angles to the groin, thus making the bearing-surface  $c$ . The surface is determined as follows. The intersection of the joint-planes  $d$  and  $e$  is at  $f$ . The vertical projection  $f_1$  of  $f$ , is drawn through  $h_1$ , found by projecting up  $h$  and  $g$ , and a horizontal line from  $g_1$ . The intersection of  $f_1$  and a line through  $g_1$ , normal to the groin-curve gives  $i_1$ , which, projected to  $i$ , gives the intersection of the sides of the bearing-surface.

The point  $j$  is found by projecting up  $k$ , the intersection of  $a$  and the diagonal, to  $k_1$ ; then projecting  $k_1$  to  $j_1$ , the intersection with the normal line; and then projecting  $j_1$  to  $j$ . By connecting  $g$  and  $j$  with a curved line (of which points of which are determined by drawing lines parallel to  $a$  and proceeding by the method used in finding  $j$ ); and  $g$  and  $i$ , and  $j$  and  $i$ , with straight lines; the sides of  $c$  are determined.

If the vaults are built of brick, it is better to run the courses at right-angles to the groin, thus giving a chance for the bricks to overlap, as shown in Fig. 10. If the brick courses are to run parallel to the center line of the vault, it is necessary to use stone ribs to carry the shape.

**Determination of the Stresses in Groined Vaults.** The problem of a groined vault spanning a RECTANGULAR AREA which is not square is here considered, as a vault spanning a SQUARE AREA offers fewer difficulties and can

be worked out on the same principles. The problem is to span an area, whose half-length of the short diameter is  $a$ , and whose half-length of the long diameter is  $b$ , Fig. 11 (a). In order to obtain a more stable construction, the point of intersection of the crowns of the vault is raised a distance  $cd = c'd$ , thus giving the crown of the long-span vault a slope  $ce$  and the crown of the short-span vault a slope  $c'f$ . The vault is divided into strips  $A, B, C$ , etc., and  $A', B', C'$ , etc., from the rib  $R$ , as shown in the projected area in Fig. 11 (a). The rib  $R$




Fig. 10. Groins of Brick Vaults






Fig. 11. Determination of Stresses in Groined Vaults

given a width equal to the assumed width of the supporting diagonal concealed arch, and the widths  $A, B, C$ , etc., and  $A', B', C'$ , etc., are obtained by dividing the two vaults into the same number of equal parts. These strips are considered as adjacent arches resting on the rib  $R$ . For simplification the line of pressure or resistance-line of each strip is placed in the center of that strip as  $gk$  in  $A$  and  $g'k'$  in  $A'$ . The error in this is on the side of safety.

Even though the projected areas of the two intersecting vaults are the same, the actual surface-area of the smaller-span vault is slightly larger than that of the longer-span vault. Therefore, if the vaults are of the same thickness, the shorter-span vault is slightly heavier than the larger-span vault. In order to have the resultants of the horizontal components of the thrusts from strip  $A$  and strip  $A'$ , strip  $B$  and strip  $B'$ , etc., parallel to the direction of the rib  $R$ , the procedure is as follows.

The thrusts of the strips on the heavier side, that is of strips  $A, B, C, D$ , and  $F$ , are determined as shown in Fig. 11 (b) and (c). The curvature of the strips being the same, the work can be considerably lessened by dividing the arch into sections of unequal lengths for weight-determinations. The dividing line for the sections is found, by projecting up the point of intersection of the line of pressure of each strip and the side of the rib  $R$ , as  $g$  to  $g', h$  to  $h'$ , etc. The weights  $w_1, w_2, w_3$ , etc., of each section are then determined and the component load-line drawn as in Fig. 11 (c). The positions of  $W_A, W_B, W_C$ , etc., in Diagram (b) are determined by the usual STRESS-POLYGON.  $H$  is then drawn as to be at the upper limit, and the different thrusts so as to act near the lower limit of the middle half of the vault-thickness.\* Lines drawn in Fig. 11 (d) parallel to these thrusts, determine their values, and the values of the horizontal components  $H_A, H_B, H_C$ , etc. The weights  $w'_1, w'_2, w'_3$ , etc., in Diagram (d), are found in the same way, the load-line in Diagram (f) drawn, and the positions of  $W_{A'}, W_{B'}, W_{C'}$ , etc., found as before.  $H'$  in Fig. 11 (d) is drawn at the upper limit of the middle half in this demonstration.\*  $H_A', H_B', H_C'$ , etc., however, must have such values that the resultants of  $H_A$  and  $H_A', H_B$  and  $H_B'$ , etc., are parallel to  $R$ . The required values of  $H_A', H_B', H_C'$ , etc., are found as in Fig. 11 (e), by laying off  $H_A, H_B, H_C$ , etc., and drawing  $T_1, T_2, T_3$ , etc., parallel to  $R$ . The resulting values of  $H_A', H_B', H_C'$ , etc., are then laid off in Fig. 11 (f) and the thrusts drawn. When drawing the thrusts in Fig. 11 (d) through the intersection, of  $H'$  and  $W_{A'}$ ,  $H'$  and  $W_{B'}$ , etc., parallel to their directions in Fig. 11 (f), it is found that they act slightly above the lower edge of the middle half.


The rib  $R$  is then drawn as in Fig. 11 (h) and the points of application of the loads located. The LOAD-POLYGON is drawn as in Fig. 11 (g). The RESULTANT  $R_1, R_2$ , etc., are drawn in both Diagrams (h) and (g) of Fig. 11, the position of  $R_1$  in Diagram (h) found by the usual STRESS-POLYGON, and the THRUSTS  $Z$  and  $Z'$  determined. The point through which  $Z$ , Diagram (h), passes at the spring of the rib, should be so chosen that the LINE OF PRESSURE remains at least within the middle half of the rib; or the more usual and conservative limits of the middle third may be used. In the case of brick vaults the strips  $A, B, C$ , etc., are taken at right-angles to the groin, resulting in vertical loads, only, on the assumed rib.

**Ribbed Vaults.** In RIBBED VAULTS the ribs are designed to be built so as to be free-standing, and of sufficient strength to support the shell when placed over them. To simplify the construction, all the rib-arcs are ordinarily made with the same radius, thus making all the ribs disengage each other at

\* The theory of the middle third is the one usually followed, as it is the most conservative and results in a larger factor of safety. See, also, foot-note on page 1225.

light. This makes the narrower rib-arches pointed, and the diagonal ones semicircular, but they are all constructed of similar stones with cross-ribs of the same shape. To determine the points *A* and *B* (Fig. 12), at which the stresses become independent of each other and of the wall, the proceeding is as follows:

In plan the clustered ribs are shown just above the column-capitals, diagonal ribs extending into the wall a distance  $ab$ . To find the height  $w$  an arc through  $a$  with the same curvature as that of the diagonal rib, at right-angles to the ribs, in plan, a line from  $b$ , until it cuts this arc at right angles  $cb$  is the height at  $A$ . The height at  $B$ , equal to  $fe$ , is found in the same way. The WEBS, or parts of the vault-shell supported by the ribs, are



**Fig. 12. Vault-rib Construction**

flow arches in cross-section, and are SPHERICAL TRIANGLES, that is, SYMMETRICAL.

to use to the fullest advantage the finished lower portions of the vault for the upper courses as laid, the courses of the VAULT-SHELL, or WEB planes normal to the wall and the transverse ribs. This is shown in projection in Fig. 13 I. The web being arched in both directions, the in two directions, as in domes. From the study of the theory of found that the THICKNESS OF THE SHELL in a dome has NO EFFECT ON ry. The web in ribbed vaults being domical, can be made relatively or stone or brick vaults it should not be less than about 4 in thick p to 35 ft.

are designed as arches, loaded with the thrusts of the web supported. The thrusts are determined as illustrated in Fig. 13 II. The vaulting of the half-wall, or transverse rib *A*, and the half-diagonal rib *B*, is composed of any number of equal LUNES, or figures bounded by the two intersecting arcs, and radiating from the AXIS OF THE DOME of which that part of the dome is a SPHERICAL TRIANGLE. This axis is found by projecting, at right angles, the ribs *A* and *B*, lines starting at the center of curvature of the ribs

and intersecting at the point  $e$ , which is the projection of the axis of the dome. The RADIUS OF THE DOME is then  $R_1$  in Fig. 13 II, equal to the distance from




Fig. 13. Determination of Stresses in Vault-ribs

the spring of the diagonal rib  $B$ . The thrust of each LUNE on the ribs is found as shown for lune  $L$ .

**Example.** Let the radius  $R_1$ , Fig. 13 II, be 25 feet, and let the shell be 4 inches thick, constructed of stone, and weighing 125 lb per cu ft. The angle  $\theta$  (by measurement) is  $54^\circ 30'$ , and the angle  $\alpha$  is  $18^\circ 30'$ . These are found by projecting up from the point of intersection  $f$  of the center line of the lune  $L$  and the center line of the rib  $B$ , and the intersection  $g$  of the center line of the lune  $L$  and the center line of the vault, to  $f_1$  and  $g_1$ , respectively, on the vertical projection  $L_1$  of lune  $L$ .

Using the same notation, equations, and curves as were derived for **SMOOTH SHELL DOMES** (page 1214), it is found from Plate II, with  $\frac{cr}{d} = 0$  and  $\alpha = 18^\circ$ , that

$$W_{I-\theta} = -125 (4/12) (25)^2 (0.33) = -8594 \text{ lb}$$

and that

$$n = \frac{-8594}{2\pi(125)(4/12)(25)^2} = -0.0525$$

From Plate I it is found that the CRITICAL ANGLE, for values of  $\frac{cr}{d} = 0$ ,

0.0525, is  $55^{\circ} 30'$ , and the vaulting should be back-filled as high as this, 11 ft.

Plate III, with  $\frac{cr}{a} = 0$ . and  $n = -0.0525$ , it is found that at  $\theta = 54^{\circ} 30'$

$$U = (125 \times 4 / 12 \times 25)(-0.079 + 0.63) = 573 \text{ lb}$$

Measurement, the width of LUNE  $L$  at  $f$  is 2 ft; hence the total TANGENTIAL COMPONENT  $C$  (Fig. 13), is  $2 \times 573 = 1146$  lb. The HORIZONTAL COMPONENT  $D$  is 6655 lb, and the COMPONENT  $F$  (along the rib  $B$ ) of  $D$  is 5750 lb. The COMPONENT  $E$  of  $C$  is 9339 lb.

VALUE OF  $T$  is found from Plate IV to be  $125 \times 4 / 12 \times (25)^2 \times (-0.004) = 7570$  lb, and the COMPONENT  $H$  (along the rib  $B$ ) of  $T$  is 3630 lb.

THRUSTS acting on the rib  $B$  of the other LUNES above  $L$  are found in the same manner, and the portion of rib above the back fill investigated as an arch. That portion of the rib below the web is not indicated.

Results with semicircular diagonals of about 33-ft span, the ribs should be 10 in wide and from 10 to 14 in in total height, and the minimum thickness of the projecting portions of the ribs below the webs, for smaller spans, should be  $3\frac{1}{2}$  in width and 6 in in height.\*

Results. TILE VAULTS, as built by the R. Guastavino Company, are made of tiles, from 6 by 12 to 24 in in plan, and 1 in in thickness, and several layers so as to make a solid, thin shell that is both light and strong. Because of the overlapping of the tiles, the shell has considerable RESISTANCE, and the vaults are practically MONOLITHIC. It is due to the lightness of the construction that the thrusts and the weight of the structure are materially reduced. Ordinarily a finished ACOUSTIC TILE, or rough CONSTRUCTIONAL TILE, is used for the exposed surfaces.

Vaults. Vaulting in buildings of moderate cost is frequently accomplished by suspending from the roof-trusses STEEL OR WOODEN FRAMES with and plaster. The roof-trusses must in this case be designed to carry direct loads of the FRAMED VAULTING, which must be of the required cross-section and shape to carry and fit the plastered surfaces.

\* Handbuch der Architektur.



# PART III

---

## USEFUL INFORMATION

FOR

### ARCHITECTS, DRAUGHTSMEN, BUILDERS, AND SUPERINTENDENTS

AND ALL WHO HAVE TO DO WITH THE BUILDING TRADES

The editor has arranged the information in Part III in the following

1. Heating and Ventilation.

2. Elevators.

3. Sanitation, Plumbing and Drainage, Gas and Gas-Piping.

4. Lighting and Illumination of Buildings.

5. Acoustical Work for Buildings.

6. Natural Acoustics.

7. Weights, Measures, Quantities, and Miscellaneous Data on Building Materials.

8. Methods and Data Useful in the Preparation of Drawings and Specifications.

9. Miscellaneous Information for Architects and Builders.

10. Glossary of Architectural and Technical Terms.

11. Definitions of Architectural Terms.





## HEATING AND VENTILATION OF BUILDINGS \*

By

LOUIS A. HARDING

SENIOR PROFESSOR OF MECHANICAL ENGINEERING, PENNSYLVANIA STATE  
COLLEGE

## Physical Units and the Measurement of Heat

**System of Units.** In this country the system of units in general use by engineers is known as the FOOT-POUND-SECOND SYSTEM, and the following definitions and examples will show the significance of each.

**Definition of Units Employed.** The UNIT OF TIME is the second, which is  $\frac{1}{86,400}$  part of the mean solar day.  $t$  = time. Time is also expressed in minutes and hours.

**Length.** The UNIT OF LENGTH is the foot = 0.3048 meter.

**Weight.** The UNIT OF WEIGHT is the pound = 0.4532 kilogram.

**Area.** The UNIT OF AREA is the square foot. The unit often used is the square inch.

**Volume.** The UNIT OF VOLUME is the cubic foot. Volume = area  $\times$  length =  $A \times L$ .

Calculations involving the quantity of air required  $Q$  is often used for cubic feet.

**Example.** The volume displaced per stroke by the plunger of a pump, if the diameter is 6 in and the stroke is 12 in, is  $\frac{1}{4} \times \pi \times 6^2 \times 12 = 339.29$  cu in, or 0.244 ft.

If the plunger makes 30 WORKING strokes (not revolutions) per minute, then the DISPLACEMENT per minute is  $0.244 \times 30 = 7.32$  cu ft. One United States gallon = 231 cu in = 0.1336 cu ft. This pump will therefore theoretically deliver  $7.32/0.1336$ , or 54.8 gal per minute. The actual delivery of the pump will be 10 to 15% less, owing to the SLIP, which is the leakage back through the valves, around the plunger, and that due to imperfect filling of the cylinder on the suction-stroke.

**Weight.**  $D$  = density. The weight of a unit volume (1 cu ft) of a substance is called its DENSITY. The density of water at 70° F. is 62.3 lb per cubic foot. The density of air at 70° is .075 lb per cubic foot. The pump in the preceding example would, therefore, handle  $7.32 \times 62.3$  or 456 lb of water per minute.

The water-end of the pump is operated by a steam-cylinder having a displacement of 0.349 cu ft per stroke, and takes steam at the same pressure for the same work as in the DIRECT-ACTING type and if we assume that the steam pressure is 100-lb gauge, we find from the steam-table (Table I), that the weight of steam at this pressure is 0.2565 lb. The STEAM-CONSUMPTION of the pump, therefore, would be  $0.2565 \times 0.349 \times 30 \times 60 = 161.6$  lb per hour, or 2.69 lb per minute. A fan handling 10,000 cu ft per minute of air at 70° F, delivers  $10,000 \times 0.075 = 750$  lb per minute.

**Velocity.**  $v$  = velocity. The RATE OF MOTION of a body is measured by the distance moved over in a unit time. Velocity is expressed in feet per second.

The data of this section has been condensed from Vol. I of Mechanical Engineering, by Harding and Willard, published by John Wiley & Sons, Inc.

**Energy or Work.**  $U$  = ENERGY or WORK. The UNIT OF WORK is the foot-pound, and is the quantity of energy expended or the work performed by a force of 1 lb moving through a distance of 1 ft in the line of action of the force.

**Power** is the RATE OF DOING WORK. Note that POWER involves the factor TIME and is equal to the amount of work done divided by the time required to do this work.

**Horse-Power.** h.p. = HORSE-POWER. The UNIT OF POWER is the horse-power and is the performance of work at the rate of 550 ft-lb per second or 33 000 ft-lb per minute.

**Example.** Required the theoretical work and horse-power developed by the water-end of the pump in the preceding example, assuming that the head or height pumped against is 200 ft, and that no frictional resistance is to be overcome.

The work  $Um$  performed per minute is the lifting of the weight of water, 366 lb per min, through a height of 200 ft and is  $Um = 366 \times 200 = 73\,200$  ft-lb per min. The h.p. =  $Um/33\,000 = 73\,200/33\,000 = 2.22$ .

The actual power required will be somewhat greater, as the force required to overcome frictional resistance, etc., has been neglected.

#### Equivalent Values of Electrical and Mechanical Units

1 horse-power..	746 watts	1 kilowatt	1 000 watts
	0.746 kilowatt		1.34 h.p.
	33 000 ft-lb per min		2 654 200 ft-lb per hr
	550 ft-lb per sec		44 240 ft-lb per min
	2 546 Btu per hr		737.6 ft-lb per sec
			3 414.5 Btu per hr

**Measurement of Pressure.** It is customary to measure PRESSURE by means of GAUGES which, in reality, only indicate the difference between the pressure being measured and the pressure of the atmosphere, BAROMETRIC PRESSURE, at the same time and place. These gauges may indicate either a higher or lower pressure than that of the atmosphere; in the former case they are known as PRESSURE-GAUGES and in the latter as VACUUM-GAUGES or DRAFT-GAUGES.

**Pressure-Gauges and Vacuum-Gauges.** The most common type of pressure-gauge (Fig. 1) is provided with a flexible hollow brass tube of oval cross-section known as BOURDON TUBE. When subjected to pressure, this tube tends to straighten out; and this causes a sector of a gear to rotate with a small pinion, which is on the same shaft with the indicating hand or pointer, and rotates the latter a corresponding amount. The pointer is placed just in front of a graduated dial, as shown in the figure, from which the pressure may be read in suitable pressure-units, such as pounds per square inch. These gauges may also be used for indicating vacuum, or a pressure lower than that of the atmosphere.

Fig. 1. Single-spring Pressure-gauge. Interior View

**Draft-Gauges.** The measurement of pressure, but slightly above or below the atmospheric pressure, barometric pressure, is usually accomplished by the use of a DRAFT GAUGE. This is essentially a U tube, containing either water, kerosene, alcohol, or mercury, mounted upon a graduated scale, and reading either in inches of fluid or in pounds or ounces per square inch. Since the pressure indicated

ferential one, due to the left-hand leg being open to the air, the reading is obtained by adding the depression in the left-hand leg to the elevation of the right-hand leg, using zero as the reference-point in both cases.

**Barometers.** The PRESSURE OF THE ATMOSPHERE is usually measured by a **Simple Barometer** (Fig. 2), which, in its simplest form, consists of a glass tube about 3 ft long, closed at one end. After being filled with mercury it is inverted in a shallow dish of mercury.

The pressure of the atmosphere at the level of the mercury in the dish maintains the mercury-column in the tube about 30 in above the level in the bath or cistern. The barometric height or length of this column of mercury varies with the altitude above sea-level. When the mercury in the tube rises in the cistern, the level in the tube falls, and vice versa, so that there is an ever-reversing relation between the level of the mercury in the tube and the mercury in the cistern, which is necessary for the accuracy of the readings. It is, therefore, necessary, before reading the height of the column on the stem of the barometer by means of a movable vernier, to adjust the level of the mercury in the cistern. All standard or observatory barometers of the mercurial type have this adjustment. Barometers of other types, such as the **Aneroid Barometer**, must be frequently compared with a standard mercurial barometer in order to check the accuracy of their readings.




Fig. 2. Simple Barometer

**Barometric Pressure.** By **BAROMETRIC HEIGHT** is meant the height of a column of pure mercury at  $32^{\circ}$  F. which just balances the pressure of the atmosphere at the time and place of the observation. The **STANDARD OR NORMAL BAROMETRIC PRESSURE** is defined as the pressure of a column of pure mercury (29.92 in) high at  $32^{\circ}$  F. This is the normal barometric pressure at  $59^{\circ}$  and at sea-level. Since the weight of 1 cu in of mercury under these conditions is 0.491 lb, the normal barometric pressure = height of column  $\times$  weight per cubic inch =  $29.92 \times 0.491$ , or 14.7 lb per sq in. This pressure of 14.7 lb per sq in is known as the **ABSOLUTE PRESSURE** of the atmosphere at latitude  $45^{\circ}$  and at sea-level. Now, since the ordinary gauge measures only pressures above or below that of the atmosphere, it is necessary to **ADD THE BAROMETRIC PRESSURE** at the place in question to the **GAGE-READING** to obtain the **TOTAL ABSOLUTE PRESSURE** corresponding to the pressure indicated by the gauge. That is, absolute pressure = barometric pressure + gauge-pressure.

## Heat

**Definition of Heat.** **HEAT** IS A FORM OF ENERGY. It is, in fact, the kinetic energy of the molecules of which all substances, whether solid, liquid, or gaseous, are composed. Whenever the vibratory motion of the molecules composing a body of given mass is increased from any cause the **THERMAL ENERGY** is increased. The temperature of the body rises, its **SENSIBLE HEAT** increases, and the body feels warmer.

**Measurement of Temperature.** **Thermometry.** **INTENSITY OF HEAT** is measured by **THERMOMETERS** and **PYROMETERS**, the latter being used for high temperatures above from  $400^{\circ}$  to  $500^{\circ}$  F. In engineering work mercurial

thermometers are very largely employed. These depend upon the uniform expansion of mercury to indicate changes in temperature. The UNIT OF MEASUREMENT is called a DEGREE, and is capable of very exact determination, provided that two points, at which the heat-intensity is always constant, can be used as bases or references for calibration. The melting-point of ice and boiling-point of water at atmospheric pressure are usually selected as bases, and the uniform expansion of the mercury between these two points is indicated on a scale divided into 180, 100, or 80 divisions. (Fig. 3.) Each of these divisions

known as a DEGREE and the scales used are known respectively as FAHRENHEIT, CENTIGRADE or CELSIUS, and REAUMUR. The Fahrenheit is used almost exclusively in engineering in this country.

**Absolute Temperature.** In addition to the three temperature-scales already described, physicists employ what is known as the ABSOLUTE SCALE OF TEMPERATURES, based on the so-called ABSOLUTE ZERO OF TEMPERATURE, at which point no molecular vibration exists. This zero is conceived as  $491.6^{\circ}$  F. below the melting-point of ice ( $32^{\circ}$  F.), it having been discovered that an ideal perfect gas would change in volume by  $1/491.6$  of its volume at  $32^{\circ}$  F. for each  $1^{\circ}$  change in its temperature, at constant pressure. Thus, if 491.6 cu ft. of gas, measured at  $32^{\circ}$  F., is cooled  $20^{\circ}$  F. at constant pressure, the new volume will be 471.6 cu ft. It is only necessary to add  $491.6 - 32$ , or 459.6, to the actual thermometer-reading to get the absolute temperature. That is,  $T = t + 459.6$ , where  $T$  = absolute temperature, and  $t$  = actual thermometer-reading, on the Fahrenheit-scale. For engineering-work, 460 is used rather than 459.6. For the Centigrade scale the relation is  $T = t + 273.1$ .

**Measurement of Heat-Quantity.** Calorimetry. HEAT MAY BE MEASURED, since it is a form of energy, in any of the usual energy-units, as the JOULE, FOOT-POUND, or HORSE-POWER HOUR. It is the custom, however, to use for this purpose a special unit more readily applicable to heat-changes.

This unit in the English system is known as the BRITISH THERMAL UNIT (Btu), and is the amount of heat required to raise 1 lb. of water from  $63^{\circ}$  to  $64^{\circ}$  F. For all practical purposes in ordinary calculation the Btu is the amount of heat required to raise 1 lb. of water  $1^{\circ}$  F.

**Specific Heat.** It is a well-known fact that equal quantities of heat will raise equal weights of different substances a different number of degrees, depending on the nature of the substances. This property of matter is known as SPECIFIC HEAT, and for any substance can be expressed as the number of Btu required to raise or lower the temperature of 1 lb.  $1^{\circ}$  F., at some given temperature. It is also customary to make use of the mean or average value for a certain temperature-interval. Two specific heats are recognized, one known as the TRUE SPECIFIC HEAT, measured at the temperature stated, and the other as the MEAN SPECIFIC HEAT, which is the average value between the temperatures under consideration. The specific heat of air at constant pressure is 0.24.

**Relation between Units of Energy and Power.** Since the various forms of energy, heat, mechanical energy, electrical energy, etc., are mutually convertible, there must be definite numerical relations between the various units and




Fig. 3. Fahrenheit and Centigrade Thermometers

ess energy. As determined by various physicists the relation between  
1 and the ft-lb is

$$1 \text{ Btu} = 777.64 \text{ ft-lb}$$

umber 777.64 is called the **MECHANICAL EQUIVALENT OF HEAT** and is  
l by *J*. For ordinary use the value 778 may be taken. Another con-  
relation is,

$$1 \text{ h.p.} = 2564 \text{ Btu per hr}$$


### Steam

**Properties of Steam.** Steam is water-vapor, which exists in the vaporous  
n because sufficient heat has been added to the water, from which the  
as been formed, to supply the latent heat of evaporation, and to change  
id into a vapor. This change of state takes place at a definite and  
temperature, which is determined solely by the pressure of the steam.  
e in pressure will always be accompanied by a change in the tempera-  
which ebullition or boiling will occur, and there will be a corresponding  
n the latent heat. The properties of steam, together with other char-  
s, are tabulated in the steam-tables. (See Table I.) Steam in con-  
the water from which it has been generated is known as **SATURATED**  
nd may be known as **DRY SATURATED STEAM**, or as **WET SATURATED**  
The latter contains more or less actual water in the form of mist or  
as it is called. If dry, saturated steam be heated, and the pressure  
nd the same as when it was vaporized, its temperature will increase  
II become **SUPERHEATED**; that is, its temperature will be higher than  
aturated steam at the same pressure.

**Sensible and Latent Heat.** Whenever heat is added to a substance, without  
state, its temperature is raised, and the heat thus added is known as  
**HEAT**, as, for example, the heat added to water the temperature of  
etween 50° and 140° F. Sensible-heat changes, as already stated, are  
by the thermometer. Heat may be added to a body without any  
temperature provided a change of state from solid to liquid or from  
vapor takes place, and the heat thus added is known as **LATENT HEAT**.  
Change is from solid to liquid, as from ice to water, this heat is known  
**HEAT OF FUSION**. At atmospheric pressure ice melts at 32° F.,  
latent heat is 144 Btu per lb. When the change is from liquid to vapor,  
water to steam, the heat required to effect the change is known as the  
**HEAT OF EVAPORATION**. At atmospheric pressure water evaporates at  
nd the latent heat is 971.7 Btu per lb. A conception of the relation  
e properties or characteristics of steam, and the manner in which the  
state, temperature and pressure are brought about, is described in the  
paragraphs.

**Formation of Steam.** Consider a frictionless cylinder (Fig. 4), containing  
er at 32° F. Also consider the pressure of the atmosphere to be 14.7  
and to be replaced by that of the piston *B*. When heat is applied  
der the temperature of the water rises until the boiling-point, 212° F.,  
The heat necessary to raise the temperature from 32° F. to the  
it is known as the **HEAT OF THE LIQUID OR SENSIBLE HEAT**, and is de-  
ne symbol *Q*. This condition is denoted in Fig. 8 by the point *C*.  
e specific heat of water between 32° F. and 212° F. is 1; hence the  
**British thermal units (Btu)** necessary to raise the temperature of  
his amount is 212 - 32 or 180 Btu.  
re heat is added the water begins to evaporate and expand at con-

stant temperature until, as in Fig. 5, the water is entirely changed into steam. This condition is also shown in Fig. 8, by the point *D*. The heat thus added known as the **LATENT HEAT OF EVAPORATION** and is denoted by the symbol  $r$ . This heat  $r$  is subdivided into two parts. (See Fig. 7.) First the attractive between the molecules must be broken down. This is known as the **INTERNAL LATENT HEAT** and is denoted by the symbol  $\rho$ . Next the external resistance must be overcome, the weight  $P$  being raised against gravity. The heat thus added is known as **EXTERNAL LATENT HEAT** and is designated by the symbol  $APu$ , where  $u$  is the change in volume, in cu ft of 1 lb of water,  $A$  is  $1/778$ , and



Figs. 4 to 8. Diagrams Explaining the Generation of Steam

$P$  is the pressure of the atmosphere in pounds per square foot (barometric pressure). It is evident then that the latent heat

$$r = \rho + APu, \text{ or } \rho = r - APu$$

The term  $APu$  is the heat-equivalent of the work performed for the change in volume from water to steam.

The heat added from the starting point ( $32^\circ \text{F}$ ), is known as **TOTAL HEAT** ( $H$ ), or  $q + r = H$ . If more heat is added, the pressure remaining constant the temperature of the steam rises and the steam becomes what is known as **SUPERHEATED STEAM**. The heat added is equal to the **MEAN SPECIFIC HEAT** ( $C_p$ ) of the steam, times the change in temperature ( $t_3 - 212$ ). The specific heat of steam is the Btu, or heat, required to raise the temperature of 1 lb of steam  $1^\circ \text{F}$ . Since the specific heat of steam is less than that of water, the slope of this line becomes greater than that of the water-line. The point now located at  $t_3$  (Fig. 6), and the steam has increased in volume in the cylinder (Fig. 5), until the piston occupies the dotted position  $B'$ .

If instead of the above condition of pressure, additional pressure is added

Table I. Properties of Saturated Steam. \*

G. A. Goodenough

Pressure lb per sq in	Tem- pera- ture, deg. F.	Vol- ume, cu ft per lb	Weight, lb per cu ft	Heat-content in Btu		Latent heat in Btu	
				of liquid	of vapor	of vapor- ization	In- ternal
<i>p</i>	<i>t</i>	<i>v</i>	<i>d</i>	<i>q</i>	<i>H</i>	<i>r</i>	<i>ρ</i>
2	126.10	173.6	0.00576	94.02	1 116.2	1 022.2	957.9
4	152.99	90.6	0.01104	120.9	1 127.9	1 007.0	939.9
6	170.07	62.0	0.01614	137.9	1 135.0	997.1	928.2
8	182.87	47.35	0.02112	150.8	1 140.3	989.5	919.4
10	193.21	38.43	0.02602	161.1	1 144.4	983.3	912.2
12	201.96	32.41	0.03086	169.9	1 147.9	978.0	906.0
14.74	212.13	26.75	0.03739	180.1	1 151.8	971.7	898.8
16	216.3	24.76	0.04038	184.3	1 153.4	969.1	895.8
18	222.4	22.18	0.04508	190.5	1 155.7	965.2	891.4
20	228.0	20.10	0.04976	196.0	1 157.7	961.7	887.3
22	233.1	18.38	0.0544	201.2	1 159.6	958.4	883.6
24	237.8	16.95	0.0590	206.0	1 161.3	955.3	880.1
26	242.2	15.73	0.0636	210.4	1 162.8	952.4	876.8
28	246.4	14.67	0.0681	214.6	1 164.3	949.7	873.7
30	250.3	13.76	0.0727	218.6	1 165.7	947.1	870.7
32	254.0	12.95	0.0772	222.4	1 166.9	944.6	867.9
34	257.6	12.24	0.0818	225.9	1 168.1	942.2	865.2
36	260.9	11.60	0.0862	229.4	1 169.2	939.9	862.7
38	264.2	11.03	0.0907	232.6	1 170.3	937.7	860.2
40	267.2	10.51	0.0951	235.8	1 171.3	935.5	857.8
42	281.0	8.53	0.1173	249.8	1 175.6	925.9	847.1
44	285.9	7.93	0.1261	254.7	1 177.1	922.4	843.2
46	292.7	7.18	0.1392	261.7	1 179.1	917.4	837.8
48	296.9	6.76	0.1479	266.1	1 180.3	914.3	834.3
50	302.9	6.22	0.1609	272.2	1 182.0	909.8	829.5
52	306.7	5.90	0.1695	276.1	1 183.0	906.9	826.4
54	312.0	5.48	0.1824	281.6	1 184.4	902.8	821.9
56	315.4	5.23	0.1910	285.1	1 185.3	900.2	819.1
58	320.3	4.905	0.2039	290.1	1 186.5	896.4	815.0
60	323.3	4.709	0.2124	293.3	1 187.3	894.0	812.4
62	327.8	4.442	0.2251	297.9	1 188.4	890.5	808.6
64	330.7	4.279	0.2337	300.9	1 189.0	888.2	806.1
66	334.8	4.057	0.2465	305.1	1 190.0	884.8	802.6
68	337.4	3.921	0.2550	307.9	1 190.6	882.7	800.3
70	341.3	3.735	0.2678	311.9	1 191.4	879.5	796.9
72	343.7	3.620	0.2762	314.4	1 191.9	877.5	794.8
74	347.4	3.461	0.2889	318.2	1 192.6	874.4	791.6
76	349.7	3.363	0.2973	320.6	1 193.1	872.5	789.5
78	353.1	3.226	0.3100	324.2	1 193.7	869.6	786.4
80	355.3	3.140	0.3184	326.5	1 194.1	867.7	784.5
82	358.5	3.020	0.3311	329.8	1 194.7	864.9	781.6
84	360.5	2.945	0.3396	332.0	1 195.1	863.1	779.7
86	363.6	2.839	0.3522	335.2	1 195.7	860.5	776.9
88	365.6	2.773	0.3606	337.3	1 196.0	858.7	775.1
90	368.5	2.679	0.3733	340.3	1 196.5	856.2	772.4
92	370.4	2.620	0.3817	342.3	1 196.8	854.5	770.6
94	373.1	2.536	0.3943	345.2	1 197.2	852.0	768.0
96	377.6	2.408	0.4154	350.0	1 197.9	847.9	763.9
98	381.9	2.292	0.4364	354.5	1 198.5	844.0	759.1

from original tables published by John Wiley &amp; Sons, Inc.

as shown by the weight  $W$  in Fig. 6, the temperature of the boiling-point will be raised from the temperature of  $212^{\circ}$  F. to some other point, as  $t_1$  (Fig. 8). As may be seen by this figure, the sensible heat  $q$  has been increased to  $q_1$ . When more heat is added the water is evaporated at the temperature  $t_1$ , and if heat is again added the SATURATED STEAM will become SUPERHEATED STEAM.

**Quality of Steam.** The proportion of the DRY STEAM, per pound of steam delivered by the boiler, is known as the QUALITY OF THE STEAM and is represented by the symbol  $x$ , and the heat ( $H_x$ ) contained in the steam above  $32^{\circ}$  is  $q + xr$ ; the state-point is located at  $E$  (Fig. 8).

**Specific Volume and Density.** The volume of a pound of steam is known as the SPECIFIC VOLUME  $v$ , and as may be seen by comparing Figs. 5 and 6, it increases as the pressure increases. The reciprocal of this, or the weight of steam per cubic foot, is known as the DENSITY, and is denoted by  $d$  or  $1/v$ .

**Entropy.** Another quantity known as ENTROPY is made use of in calculations relating to steam-engines and turbines, and is defined as the ratio obtained by dividing the quantity of heat added to a substance by the absolute temperature at which it is added.

**The Total Heat,  $H$ ,** of a dry, saturated vapor for any pressure and temperature is the sum of the heats required to raise the temperature of one pound of the liquid from the freezing-point to the given temperature and corresponding pressure and ENTIRELY VAPORIZE IT at this pressure. For this case  $x = 1$  and consequently

$$H = (p + APu) + q = r + q$$

The total heat ( $H_x$ ) of wet vapor at any pressure and temperature is

$$H_x = xr + q$$

It is manifestly incorrect to say that this is the heat in the vapor, as the  $Ap$  is not the heat in the vapor, but the external work performed by the vapor while evaporating.

**Superheated Steam or Vapor.** Superheated steam is defined as water-vapor which has been heated out of contact with its liquid, until its temperature is higher than that of saturated vapor at the same pressure.

The heat-content of superheated steam or vapor may be expressed by the following equation

$$H_s = q + r + C_p(t_s - t) = H + C_p(t_s - t)$$

where  $t_s$  is the temperature of superheated vapor,  $t$  the temperature of saturated vapor at the corresponding pressure,  $q$  the heat of the liquid at  $t$ , and  $r$  the heat of vaporization at temperature  $t$ .  $C_p$  is the mean specific heat of superheated vapor (approximately 0.50),  $H$  the total heat of 1 lb of dry saturated steam, and  $H_s$  the total heat of 1 lb of superheated steam.

### Properties of Air

**Charles' Law.** Charles' Law refers to the relation between pressure, volume, and temperature of a gas, and may be stated as follows. The volume of a given weight of gas varies directly as the absolute temperature at constant pressure, and the pressure varies directly as the absolute temperature at constant volume. Hence, when heat is added at constant volume  $V_c$ , this equation results

$$\frac{P_2}{P_1} = \frac{T_2}{T_1}$$



temperature-range, at constant pressure  $P_c$ , the relation is

$$\frac{V_2}{V_1} = \frac{T_2}{T_1}$$

or any weight of gas  $M$ , since volume is proportional to weight at same and temperature,

$$PV = MRT$$

characteristic equation for a perfect gas. In this formula  
absolute pressure of the gas in pounds per square foot = 2116.8 (atmospheric pressure);  
volume of the weight  $M$  in cubic feet;  
weight in pounds of the gas taken;  
constant depending on the nature of the gas = 53.37 for air;  
absolute temperature in degrees Fahrenheit ( $t + 459.6$ ).

Table II. Properties of Dry Air

Barometric pressure, 29.921 in. Specific heat, 0.24

	Weight per cubic foot in pounds	Per cent of volume at 70° Fahrenheit	Btu absorbed by one cubic foot dry air per degree Fahrenheit	Cubic feet of dry air warmed one degree per Btu
	0.08636	0.8680	0.02080	48.08
	0.08453	0.8867	0.02039	49.08
	0.08276	0.9057	0.01998	50.05
	0.08107	0.9246	0.01957	51.10
	0.07945	0.9434	0.01919	52.11
	0.07788	0.9624	0.01881	53.17
	0.07640	0.9811	0.01846	54.18
	0.07495	1.0000	0.01812	55.19
	0.07356	1.0190	0.01779	56.21
	0.07222	1.0380	0.01747	57.25
	0.07093	1.0570	0.01716	58.28
	0.06968	1.0756	0.01687	59.28
	0.06848	1.0945	0.01659	60.28
	0.06732	1.1133	0.01631	61.32
	0.06620	1.1320	0.01605	62.31
	0.06510	1.1512	0.01578	63.37
	0.06406	1.1700	0.01554	64.35
	0.06304	1.1890	0.01530	65.36
	0.06205	1.2080	0.01506	66.40
	0.06110	1.2270	0.01484	67.40
	0.06018	1.2455	0.01462	68.41
	0.05673	1.3212	0.01380	72.46
	0.05225	1.4345	0.01274	78.50
	0.04903	1.5288	0.01197	83.55
	0.04618	1.6230	0.01130	88.50
	0.04364	1.7177	0.01070	93.46
	0.04138	1.8113	0.01018	98.24
	0.03934	1.9060	0.00967	103.42
	0.03746	2.0010	0.00923	108.35
	0.03423	2.1900	0.00847	118.07

A PERFECT GAS conforms exactly to the above equation, and while no gases PERFECT in this sense, they conform so nearly that the above equation applies to most engineering-computations. The volume of 1 lb of air, known as SPECIFIC VOLUME, at any temperature and pressure, can be found at once by the equation

$$V = (53.37 \times T)/P$$

Estimating Heating Requirements of Buildings

Heat Required and Supplied. The amount of heat, measured in Btu to be supplied by the heating-apparatus to a building to maintain the inside temperature above that of the outside, commonly termed HEAT-LOSSES, is:

(a) The heat required to offset the heat-transmission of the walls, ceiling, roof, and floor. This loss of heat depends upon the type and materials of construction used and the temperature-difference to be maintained between inside and the outside of the building.

(b) The heat required to warm the air entering the building from the outside either by infiltration or purposely introduced for ventilation.

(c) The heat supplied by persons, lights, machinery and motors, which may be deducted from the sum of items (a) and (b) to obtain the net amount of heat to be supplied by the heating-apparatus. (Item (c) is usually not considered.)

It is customary in all calculations connected with the design of heating installations to base the estimate on the amount of heat per hour to be supplied by the apparatus. The total heat to be supplied per hour is  $H = [(item\ a) + (item\ b) - (item\ c)]$  Btu. The method in use for the calculation of the various items above mentioned will now be taken up and discussed in the order given.

Temperatures. The inside temperature to be maintained and the air required for ventilation for various classes of work are discussed under Ventilation to which the reader is referred. The outside temperature for which the heating installation should be designed is fixed by the lowest outside temperature that is liable to continue for several days during the heating-season.

Usual Inside Temperature Specified

Kind of buildings	Degrees F.
Public buildings.....	68-72
Factories.....	65
Machine-shops.....	60-65
Poundries, boiler-shops, etc....	50-60
Residences.....	70
Bath-rooms.....	85
Schools.....	70
Hospitals.....	72-75
Paint-shops.....	80

In designing the heating-system a temperature of from 10° to 15° F. higher than the lowest recorded temperature is recommended to be used for the outside temperature.

Heat-Transmission of Walls, Ceilings, Roofs, Floors, etc. (a) The heat loss through building-construction is dependent upon the character of material, thickness and character of the surfaces, and the velocity of the air over the surfaces. Numerous tests have been conducted by various experimenters to determine accurately the heat-transmission of various types

Table III. Outside Temperatures







and Average Temperatures in the United States. All stated in Fahrenheit degrees and compiled from United States Weather Bureau Records

City	Lowest	Average.*	State	City	Lowest	Average*
Mobile.....	- 1	57.7	Neb..	North Platte..	-35	34.6
Montgomery..	5	56.1		Lincoln.....	-29	35.8
Flagstaff.....	-21	34.8	Nev..	Carson City...	-22	.....
Phoenix.....	22	58.9		Winnemucca..	-28	37.9
Fort Smith....	-15	49.5	N. H	Concord.....	-35	33.1
Little Rock...	-12	52.0	N. J..	Atlantic City..	- 7	41.6
San Diego....	32	57.2	N. Y.	Saranac Lake..	-38	34.1
Independence..	10	48.7		New York City	- 6	40.1
Denver.....	-29	38.4	N. M.	Roswell.....	-14	48.9
Grand Junction	-16	39.2		Santa Fé.....	-13	38.0
Southington...	-19	36.3	N. C.	Hatteras.....	8	53.3
Washington...	-15	42.9		Charlotte.....	- 5	49.8
Jupiter.....	24	69.8	N. D.	Devil's Lake..	-51	18.9
Jacksonville...	10	60.9		Bismarck.....	-44	23.5
Savannah.....	8	57.2	Ohio .	Toledo.....	-16	36.8
Atlanta.....	- 8	51.4		Columbus.....	-20	39.8
Boise.....	-28	39.6	Okla .	Oklahoma.....	-17	47.1
Lewiston.....	-18	42.5	Ore. .	Baker City....	-20	34.1
Chicago.....	-23	35.9		Portland.....	- 2	45.4
Springfield....	-22	39.0	Pa...	Pittsburgh....	-20	40.8
Indianapolis...	-25	40.4		Philadelphia...	- 6	41.8
Evansville....	-15	44.1	R. I. .	Providence....	- 9	37.5
Sioux City....	-31	32.1		Rock Island...	- 4	39.7
Leokuk.....	-26	37.6	S. C. .	Charleston....	7	56.9
Dodge City...	-26	....		Columbia.....	2	53.5
Vichita.....	-22	42.9	S. D..	Huron.....	-43	25.9
Louisville.....	-20	45.0		Yankton.....	-32	31.2
New Orleans..	7	60.5	Tenn.	Knoxville.....	-16	47.0
Breveport....	- 5	55.7		Memphis.....	- 9	50.7
Eastport.....	-21	31.1	Tex..	Corpus Christi.	11	62.7
Portland.....	-17	33.5		Fort Worth...	- 8	49.5
Baltimore.....	- 7	43.3	Utah.	Salt Lake City.	20	39.7
Boston.....	-13	37.2	Vt...	Northfield....	-32	27.8
San Pedro.....	-27	29.1	Va...	Cape Henry...	5	48.6
Detroit.....	-24	35.3		Lynchburg....	- 5	45.2
Duluth.....	-41	25.5	Wash.	Seattle.....	3	44.3
Minneapolis...	-33	28.4		Spokane.....	-30	37.0
Meridian.....	- 6	53.9	W.Va.	Parkersburg...	-27	41.9
Wicksburg.....	- 1	56.0		Elkins.....	-21	38.8
Springfield....	-29	43.0	Wis..	La Crosse....	-43	31.2
Annibal.....	-20	39.7		Milwaukee....	-25	32.4
Avre.....	-55	27.7	Wyo .	Cheyenne.....	-38	33.7
Alena.....	-42	30.9		Lander.....	-36	29.0

\* Average is taken from October 1 to May 1.

n. The following table represents the results of the experiment by Harding and Willard in this connection, based on an average wind-movement of approximately 15 miles per hour:

Table IV. Heat-Transmission of Building-Construction

Construction	Thick- ness, in	Btu transmitted per square foot per hour					
		Temperature-difference					
		1°	20°	40°	60°	70°	80°
 Plain brick wall	9	.363	7.3	14.5	21.8	25.4	29.0
	13	.281	5.6	11.2	16.9	19.7	23.5
	18	.220	4.4	8.8	13.2	15.4	17.6
	24	.174	3.5	7.0	10.4	12.2	13.9
 Brick wall and air-space, furrowed and plastered	9	.217	4.3	8.7	13.0	15.2	17.4
	13	.185	3.7	7.4	11.1	13.0	14.8
	18	.156	3.1	6.2	9.4	10.9	12.4
	24	.132	2.6	5.3	7.9	9.2	10.6
 Wood wall or floor ← Lath and plaster ← Clipboards, sheathing	1 1/2	.20	4.0	8.0	12.0	14.0	16.0
	Solid wood 7/8	.547	10.9	21.9	32.8	38.3	43.8
	1 1/4	.370	7.4	14.8	22.2	25.9	29.0
	2 1/4	.279	5.6	11.2	16.7	19.5	22.3
 Hollow tile	2	.409	8.2	16.4	24.5	28.6	32.7
	4	.325	6.5	13.0	19.5	22.8	26.0
	6	.281	5.6	11.2	16.9	19.7	22.9
 Concrete walls	2	.784	15.7	31.4	47.0	54.9	62.1
	3	.714	14.3	28.6	42.8	50.0	57.0
	4	.655	13.1	26.2	39.3	45.9	52.4
	6	.563	11.3	22.5	33.8	39.4	45.0
For 3-in concrete covered with slag roofing, de- duct approximately 10% from values stated.							
 Windows	Single	1.126	22.5	45.0	67.5	78.8	90.0
	Double	.450	9.0	18.0	27.0	31.5	36.0
	Triple	.281	5.6	11.2	16.9	19.7	22.9
One air-change per hr cu ft		.018	.360	.720	1.08	1.26	1.44
Btu loss per foot of sash perimeter per hour							
Wooden sash.....		2.05	41.0	82.0	123	144	165
Wooden sash, metal strip.....		0.43	8.6	17.2	26	30	34
Hollow metal sash.....		4.5	90	180	270	315	360
Hollow metal sash, stripped.....		1.6	32	64	96	112	128

\* For lath-and-plaster ceiling with no floor above, double the values given for wood floor with plaster ceiling.

data on the heat-transmission of various types of roofs were  
st-results of C. L. Norton:

Table V. Heat-Transmission through Roofs

Construction	Btu per sq ft per hour per 1° difference in temperature of still air inside and outside
asphalt roof 4 in thick with 5-ply tar and felts...	0.134
asphalt roof 3 ½ in thick with 5-ply tar and felts...	0.149
asphalt roof 3 in thick with 5-ply tar and felts...	0.170
asphalt 3 in thick with 5-ply tar and felts.....	0.192
asphalt 3 in thick with 5-ply tar and felts.....	0.282
asphalt tile 3 in thick with 5-ply tar and felts...	0.348
asphalt 3 in thick with 5-ply tar and felts.....	0.488
asphalt 4 in thick with 5-ply tar and felts.....	0.508
asphalt 4 in thick with 5-ply tar and felts.....	0.575
asphalt 4 in thick with 5-ply tar and felts.....	0.633

mission of stone walls is approximately 50% greater than that  
thickness. The Btu-loss per foot of sash-perimeter is based on  
minations by Voorhees and Meyer, Trans. Am. Soc. H. and

ssion of Roofs and Floors. The temperature of the air in  
under side of a ceiling or roof is found to be higher than the  
tained at the breathing-line, at which point the temperature  
ed; and this is due to the natural tendency of the warmer or  
ise. It is recommended that an increase of approximately  
the specified inside temperature for the temperature at the  
or wall-heights not exceeding 15 ft, and 30% for ceiling-heights  
n estimating the heat-loss of roofs. Thus, if 65° F. is the spe-  
perature to be maintained in a room the height of which is  
ature of the air in contact with the under side of the roof may  
65° + 30%, or 85° F. The loss of heat through the ceiling  
which a large air-space exists, through partitions between a  
room, or through the first floor to the cellar, may be estimated  
n that the warmed rooms give off sufficient heat to maintain  
of these colder spaces according to the following schedule:

- Losses under metal or slate roofs..... 14° F.
- Losses under tile, cement, tar, or gravel roofs..... 23° F.
- Losses in rooms kept closed..... 35° F.

mission of floors that are laid directly upon the ground may be  
assumption that the ground in contact with the under side of  
pproximate temperature of 50° F. Thus the estimated heat-  
in concrete floor laid directly upon the ground, assuming an  
e of 65° F., is

53 (65 - 50) or 8.4 Btu per square foot per hour

Infiltration. (b) The heat required to warm the outside air

which may enter by LEAKAGE through the cracks or clearances around window and doors is that required to raise the temperature of the weight of incoming air per hour from the outside to the inside temperature.

- Let
- $b$  = Btu required per hour to heat the incoming air;

$t$  = inside room-temperature in degrees Fahrenheit;

$t_0$  = outside temperature;

$C_p$  = specific heat of air at constant pressure = 0.24;

$d$  = density of the air at temperature  $t$ ;

$\phantom{d}$  = 0.075 for 70° inside temperature;

$\phantom{d}$  = 0.076 for 60° inside temperature;

$Q$  = cubic feet of air per hour entering building by infiltration, measured at temperature  $t$ ;

$W$  = weight of air per hour entering building by infiltration =  $d \times Q$ ;
- Then
- $b = C_p (t - t_0) Q \times d = 0.24 \times W \times (t - t_0)$ ;

$\phantom{b} = 1.26 Q$  for 70° inside temperature;

$\phantom{b} = 1.08 Q$  for 60° inside temperature.

There are two assumptions made by engineers in practice for obtaining the value of  $Q$ . The common method in vogue is to assume a certain number of air-changes  $n$ , per hour in the cubical contents  $C$ , of the room in accordance with the following table:

Table VI. Number of Air-Changes per Hour

Halls.....	$n = 3$
Rooms on 1st floor.....	$n = 2$
Rooms on 2nd floor.....	$n = 1$
Offices and stores, 1st floor.....	$n = 2$ to 3
Offices and stores, 2nd floor.....	$n = 1\frac{1}{2}$ to 2
Churches and public assembly-rooms.....	$n = \frac{3}{4}$ to 2
Large rooms with small exposure.....	$n = \frac{1}{2}$ to 1
Factory-buildings.....	$n = \frac{1}{2}$ to 1

**Example.** Required the heat-loss, by infiltration, from a room containing 20 000 cu ft, the temperature of which is maintained at 70° F. in zero weather the estimated number of air-changes  $n$ , being two per hour.

**Solution.**  $Q = 2 \times 20\,000 = 40\,000$  cu ft of air entering per hour measured at 70° F.

$b = 0.018 \times 40\,000 \times (70 - 0) = 50\,400$  Btu per hour.

The other method is to use the estimated amount of air-leaking in the building through the cracks around the sash-perimeter and meeting-rail. The following data may be used in this connection and is based on a wind-movement of approximately 20 miles per hour (Voorhees and Meyer Tests).

Plain wooden sash.....	114	cu ft air per hour per foot perimeter
Plain wooden sash, weather-stripped.....	24	cu ft air per hour per foot perimeter
Hollow metal sash.....	216 to 268	cu ft air per hour per foot perimeter
Hollow metal sash, weather-stripped.....	72 to 150	cu ft air per hour per foot perimeter
Copper-covered sash.....	132	cu ft air per hour per foot perimeter

For a room with more than one outside wall use only the sum of the perimeters of the windows, in the side having the greater number.

office 14 by 16 by 10-ft-high ceiling, has two 3 by 7-ft wooden-  
The maintained inside temperature is 70°, and the outside  
F. Required the heat-loss by infiltration.

the first method, assuming two air-changes per hour, the loss

$$= 1.26 \times 2 \times (14 \times 16 \times 10) = 5\,645 \text{ Btu per hr}$$

method this loss is:

$$2 (3 + 3 + 3 + 7 + 7 \text{ perimeter}) \times 114 = 6\,607 \text{ Btu per hr}$$

**Heat-Losses for Tall Buildings.** It is advisable to increase the  
losses above the tenth floor by approximately 15% for walls  
to the prevailing winds.

**Losses by Persons, Lights, Motors, Machinery, etc.** (c) The  
heat emitted by persons is ordinarily not of sufficient importance  
to account, except in cases of assembly-halls and theaters. The  
losses may be made when required:

rest.....	400 Btu per hour
work.....	500 Btu per hour

Heat produced by lights is as follows:

Losses:

$$\text{Btu per hour equals watts per lamp} \times \text{number of lamps} \times 3.415$$

producer gas.....	150 Btu
illuminating gas.....	700 Btu
natural gas.....	1 000 Btu

Each burner averages 3 cu ft of gas per hour and a fish-tail burner

Motors and the machinery which they drive, if both are located  
convert all of the electrical energy supplied into heat, which is  
the same as the product being manufactured is not removed until its  
temperature is the same as the room-temperature.

If power is transmitted to the machinery from the outside,  
the equivalent of the brake horse-power, d.h.p., supplied is used.  
the

$$\text{Btu supplied per hour} = \frac{\text{motor horse-power}}{\text{efficiency of motor}} \times 2\,546$$

in each

$$\text{Btu per hour} = \text{d.h.p.} \times 2\,546$$

the Btu equivalent of 1 horse-power hour. In high-powered  
the chief source of heating and is sometimes sufficient to overheat  
in zero weather, thus requiring cooling by ventilation the year

**How to Estimate the Heat-Loss of Buildings.** There is  
a **RULE-OF-THUMB METHODS** for estimating the heat-loss *H*  
the heating-surface required when direct radiation is to be

used. These so-called practical rules are intended to be based on *even* building-construction and on the ratio of wall and glass-surface to the cubic contents as found in buildings of the class to which they refer. These rules when modified for unusual conditions and applied by engineers of long experience in the proportioning and design of heating systems produce satisfactory results. They are, however, rapidly being discarded except as rough checks on the more refined methods of calculation.

**Carpenter's Rule.** The following formula, or rule, which has been widely used for many years in this country, was proposed by R. C. Carpenter. It




Fig. 9. Floor-plans and Section of Building Explained in Table VII. (See, also, Fig. 1)

not intended to be applied to buildings covered with corrugated sheet steel, metal lath and plaster walls, unless the wall-constant is changed to suit the condition.

By reference to Table IV, it will be noted that a fair average value for the heat-transmission of the usual well-constructed building-wall is approximately



Table VII. Tabulation of Heat-Losses for Building Shown in Fig. 9.

Room-designation	Net volume, cu ft	Net wall-area, sq ft	Floor or ceiling, sq ft	Glass-area, sq ft
1	2	3	4	5
<b>First floor:</b>				
Sample-room.	10 080	852	864	180
Hall . . . . .	2 595	99	216	45
Laboratory..	4 320	378	360	90
Office . . . . .	2 520	288	210	60
Toilet . . . . .	900	90	75	30
<b>Second floor:</b>				
Mgr's office. .	4 320	393	360	75
Hall . . . . .	2 595	119	216	25
Gen'l office..	10 080	852	864	150
Sup't's office..	4 320	393	360	75
<b>Totals . . . .</b>	<b>41 730</b>	<b>3 464</b>	<b>.....</b>	<b>730</b>

Room-designation	Transmission-loss, Btu per hour			Infiltration loss, Btu per hour		Total heat-loss, Btu per hour
	Wall-loss 19.7 × col. 3	Floor or ceiling-loss, 13. × col. 4 18.8 × col. 4	Glass-loss, 78.8 × col. 5	Assumed no. air-changes per hour	Infiltration-loss, 1.26 × col. 2 × col. 9	
1	6	7	8	9	10	11
<b>First floor:</b>						
Sample-room.	16 784	11 232	14 184	1	12 700	54 900
Hall . . . . .	1 950	2 808	3 556	3	10 809	19 123
Laboratory..	7 446	4 680	7 112	2	10 886	27 358
Office . . . . .	5 674	2 730	4 728	2	6 350	19 482
Toilet . . . . .	1 773	975	2 364	2	2 268	7 380
<b>Second floor:</b>						
Mgr's office. .	7 742	6 768	5 910	2	10 886	31 306
Hall . . . . .	2 344	4 061	1 970	3	10 809	19 224
Genl. office..	16 784	16 243	11 820	2	25 400	70 247
Sup't's office..	7 742	6 768	5 910	2	10 886	31 306
<b>Totals . . . .</b>	<b>.....</b>	<b>.....</b>	<b>.....</b>	<b>.....</b>	<b>100 994</b>	<b>280 326</b>

25 Btu and for glass 1.0 Btu per degree difference between the inside and outside temperature per hour.

Professor Carpenter states that usually we may, with sufficient accuracy, neglect all inside walls, floors and ceilings and consider only the outside walls.

The estimated number of air-changes per hour, by infiltration, has already been given in Table VI.

Let  $C$  = cubical contents of room in cubic feet;

$n$  = number of air-changes per hour (see Table VI);

0.02 = Btu to raise 1 cu ft of entering air  $1^{\circ}$  F.;

$W'$  = net wall-surface in square feet;

$G$  = glass-surface in square feet;

$(t - t_0)$  = temperature-difference between inside and outside;

$H$  = total heat to be supplied per hour in Btu;

$H = (0.02nC + G + \frac{1}{4}W')(t - t_0)$ .

**Calculating the Heat-Loss of a Building.** The following example (Table VII) will serve to illustrate the method employed in calculating and tabulating the heat-loss of a typical building, the floor-plans and section being shown in Fig. 9. (See, also, Fig. 34.) The heating requirements are for a temperature of  $70^{\circ}$  in zero weather. The heat-transmission for the outside walls per square foot is taken from Table IV for a temperature-difference of  $70^{\circ}$ . The heat-loss through the first floor is based on a temperature-difference of  $70 - 35$  or  $35^{\circ}$ . The heat-transmission per square foot per  $1^{\circ}$  difference in temperature per hour for  $1\frac{3}{4}$ -in wood is 0.37; hence for  $35^{\circ}$  it is  $0.37 \times 35 = 13$  Btu per hour. The heat-loss through the ceiling of the second floor is based on a temperature difference of  $70 - 23 = 47^{\circ}$ ,  $23^{\circ}$  being the assumed temperature of the air in zero weather. The heat-transmission per square foot per hour is therefore  $47 \times 0.40 = 18.8$  Btu. The infiltration-loss is, in this example, based on an estimated number of air-changes per hour as indicated in Table VII.

By Carpenter's rule the heat-loss of this building based on two air-changes per hour, is

$$[0.02 \times 2 \times 41\,730 + (3\,464/4) + 730] \times 70 = 228\,564 \text{ Btu per hour}$$

### Radiation

**Direct Radiation.** Steam or hot-water radiators placed in the room to be heated are termed DIRECT RADIATORS or DIRECT RADIATION. Common types of direct radiators are shown in Figs. 10, 11, 12 and 13.

**Indirect Radiation.** Radiators used to warm the air passed over them, the heating of the building being accomplished by hot air, are termed INDIRECT RADIATORS or INDIRECT RADIATION. (See Figs. 45 and 46.) This type of radiation is frequently used for installations in which provision must be made for ventilation as well as heating, as in the case of schools, public buildings, etc. Indirect radiation is also used to some extent in high-grade residence-heating where direct radiation may be thought unsightly, particularly for the first floor. Direct radiation is ordinarily employed for the floors above the first floor. The principal use of indirect radiators is in connection with the HOT-BLAST SYSTEM of heating, described later, in which a fan is used to circulate the air over the radiator and through the duct system.

**Direct-Indirect Radiation.** DIRECT-INDIRECT RADIATORS (Fig. 14) are radiators placed in the rooms to be heated and furnished with a cold-air connection through the outside wall. It serves the purpose of providing tempered-air ventilation.

**Materials and Connections of Radiators.** Radiators are constructed of cast iron, pressed steel or pipe-coils. The sections for one-pipe steam systems are connected only at the bottom. The sections for hot-water radiators and two-pipe steam systems are connected at both top and bottom. The latter is known to the trade as HOT-WATER RADIATION.

**radiation.** Cast-iron radiators should not be operated above 125 lb. pressure. Standard pipe-coil direct radiation, up to 125 lb. pressure. Radiators are rated according to the square-foot heating-surface. Cast-iron and pressed-steel direct radiators are rated in sections. The amount of heating-surface per section of cast-iron radiators of various standard heights manufactured is given in Table VIII.

**Three-column Radiator**      Fig. 11. Peerless Three-column Radiator

**Direct Cast-Iron Radiator.** The American Radiator Company has placed on the market a new type of direct cast-iron radiator which gives approximately 30% more heating-surface for a given floor-area than is obtainable with other types of direct radiation. The length of section is 48 in. and the width 8 in. for all heights.

The heating-surface per section is as follows:

38-in., 4½ sq ft	34½-in., 4 sq ft	31-in., 3½ sq ft
23-in., 2½ sq ft	19½-in., 2 sq ft	

Fig. 12) is largely used in bath-rooms, and also for factory-rooms. The narrow width of column-type radiation is objectionable. (See Fig. 12 and dimensions.)

**Radiators.\*** These radiators have been developed in recent years and are ingeniously fabricated of No. 20 United States standard sheet metal made into shapes, widths and heights which correspond to the cast-iron column-radiators. Each section is made up of two sheets joined by a double-lapped seam and the separate sections are joined by single-lapped seams. The pipe-connection is made into a cast-iron ring secured to the end-section by rolling the sheet metal over the ring. Manufactured by the Pressed Metal Radiator Company, Pittsburgh, Pa.

**Table VIII. American Direct Radiators**  
 Heights, widths, lengths and heating-surfaces

Height in inches	45	38	32	26	23	22	20	1
Peerless, single-column, steam and water....	3	2 1/2	2	1 3/4	...	1 1/4	...	...
Rococo, single-column, steam and water....	3	2 1/2	2	1 3/4	...	1 1/4	...	...
Peerless, two-column, steam and water. ....	5	4	3 1/2	2 3/4	2 1/4	...	2	...
Rococo, two column, steam and water.....	5	4	3 1/2	2 3/4	2 1/4	...	2	...
Verona, steam and water.....	4	3 1/2	2 3/4	...	...	...	2	...
Peerless, three-column, steam and water....	6	5	4 1/2	3 1/4	...	3	...	2
Rococo, three-column, steam and water.....	6	5	4 1/2	3 1/4	...	3	...	2
Peerless, four-column, steam or water.....	10	8	6 1/2	5	...	4	...	3
Rococo, four-column, steam or water.....	10	8	6 1/2	5	...	4	...	3
Aetna flue, steam or water.....	...	...	...	...	...	...	6	5
Italian flue, steam or water.....	7	5 3/4	4 1/2	...	...	...	3 1/2	...
Rococo window, steam or water.....	...	...	...	...	...	...	5	...

	16	15	14	13	Length per section in inches	Width of section in inches
Peerless, single-column, steam and water....	...	...	...	...	2 1/2	4 1/2
Rococo, single-column, steam and water....	...	...	...	...	2 1/2	4 1/2
Peerless, two-column, steam and water.....	...	1 1/2*	...	...	2 1/2	7 1/2
Rococo, two-column, steam and water.....	...	...	...	...	2 1/2	7 1/2
Verona, steam and water.....	...	...	...	...	2 1/2	8
Peerless, three-column, steam and water....	...	...	...	...	2 1/2	9
Rococo, three-column, steam and water.....	...	...	...	...	2 1/2	9
Peerless, four-column, steam or water.....	...	...	...	...	3	10 1/2
Rococo, four-column, steam or water.....	...	...	...	...	3	10 1/2
Aetna flue, steam or water.....	4 3/4	...	4	3 3/4	3	12 1/2
Italian flue, steam or water.....	...	...	...	...	3	8 1/2
Rococo window, steam or water.....	3 3/4	...	...	3	3	12 1/2

\* Peerless 15-in in steam only.

The location of the figures in the above columns in line with the names of parts of radiators indicates the heights in which the various patterns are made. The figures themselves represent the amount of heating-surface contained in each section.

To obtain the total length of the radiator, multiply the length per section by the number of sections.

**Table IX. American Rococo Wall-Radiators**  
 Ratings and measurements of sections

Section-numbers	Length, in	Width, in	Thickness, in	Thickness (with bracket), in	Heating surface, sq ft
5-A.....	16 1/2	13 5/16	2 1/2	3 3/4	5
7-A and 7-B....	21 3/8	13 5/16	2 3/4	3 3/4	7
9-A and 9-B....	29 1/16	13 5/16	2 1/2	3 3/4	9

er a suitable flange on the inner face of the ring. Air-valve made in a similar manner. See Fig. 13 and Table X. These

---

#### d Installation of Rocco Wall-radiators in Single Tier on Adjustable Brackets

it in weight and therefore easy to handle and install, and cost and shipping charges. For the same height, width and area of

### 13. Presto Single-column Pressed Metal Radiator

these radiators are shorter than cast-iron radiators, being d of  $2\frac{1}{4}$  in, center to center of sections.

oil Radiation is largely used in manufacturing establishments made up of  $1\frac{1}{4}$  or  $1\frac{1}{2}$ -in pipe screwed into cast-iron manifolds 15.

n of Direct Radiation. The unit heat-transmission  $K$ , or the by one square foot of direct radiation per hour per degree dif-

**Table X. Presto Single-Column Floor or Wall-Radiators for Steam or Water**Each section is  $4\frac{1}{4}$  in wide. Legs spread  $5\frac{1}{4}$  in

Number of sections	Length * 1 $\frac{1}{2}$ in per section	Heating-surface in square feet					
		32 in high	26 in high	23 in high	20 in high	17 in high	14 in high
		2 sq ft per section	1.5 sq ft per section	1.3 sq ft per section	1.1 sq ft per section	0.9 sq ft per section	0.7 sq ft per section
4	6	8	6.0	5.2	4.4	3.6	2.8
5	7 $\frac{1}{2}$	10	7.5	6.5	5.5	4.5	3.5
6	9	12	9.0	7.8	6.6	5.4	4.2
7	10 $\frac{1}{2}$	14	10.5	9.1	7.7	6.3	4.9
8	12	16	12.0	10.4	8.8	7.2	5.6
9	13 $\frac{1}{2}$	18	13.5	11.7	9.9	8.1	6.3
10	15	20	15.0	13.0	11.0	9.0	7.0

\* Length of radiator over all, including malleable-iron hubs. Add  $\frac{3}{4}$  in for each bush.

Legs are detachable and can be applied to any section.

These radiators are tapped  $1\frac{1}{2}$  in and bushed as specified.



ference between the heating-medium and the temperature of the air in the room varies somewhat with the type of radiator, height, temperature, etc.

**Fig. 14. Direct-indirect Radiator-Installation**

**Coefficients of Transmission for Direct Steam-Radiators.** Table 1 is based on the average performance of direct steam-radiators standing exposed in still air at  $70^{\circ}$  F. with steam at  $220^{\circ}$  F., or 2-lb pressure, with a standard

ence of  $150^{\circ}$ . In order to apply the coefficients given in conditions other than standard, it is only necessary to know the

### Pipe-Coil Radiators and Connections



TABLE

1" Branch-Tees 2 1/4" c-c	1 1/4" Branch-Tees, 3" c-c	1 1/2" Branch-Tees, 3 1/2" c-c	2" Branch-Tees, 4 1/2" c-c
Runs	Runs	Runs	Runs
1"-1 1/4" 1 1/2" 2"	1 1/4"-1 1/2" 2" 2 1/2"	1 1/2"-2" 2 1/4" 3"	2" 2 1/4"-3" 3 1/2"
No. of Branches	No. of Branches	No. of Branches	No. of Branches
2 to 9	2 to 16	2 to 16	2 to 16
Inside Diam.	Inside Diam.	Inside Diam.	Inside Diam.
1 1/4" 2 1/4" 2 1/2"	2 1/4" 2 1/2" 2 1/2"	2 1/4" 2 1/2" 2 1/2" 3 1/2"	3 1/2" 3 1/2"

NOTE. All openings in Branch-Tees for circulation are tapped right hand.

Branch-Tees for Box Coils are always tapped left hand in branches and right hand in back inlet.

The run and back openings of Branch-Tees are tapped the same size as branches, unless otherwise ordered.

Fig. 15. Pipe-coil Radiation-data

given increase or decrease in the temperature-range above standard range. An examination of test-data so far avail-

able seems to indicate, that this variation is nearly 0.2% per degree above or below the standard range of 150°. Thus, if a three-column, 38-in high, direct radiator is to be used in a room kept at 60° F., with steam at 230°, we would have a temperature-range of 170° or 20° above standard, and the value of  $K$  would become

$$K = (1.55 + 0.002 \times 20 \times 1.55) = 1.61$$

and each square foot of radiation would give off  $1.61 \times 170 = 274$  Btu per hr

Table XI. Values of  $K$  for Direct Radiators

Type of radiator	Height of radiator			
	20 and 22 in	26 in	32 in	38 in
One column.....	1.95	1.90	1.85	1.80
Two columns.....	1.80	1.75	1.70	1.65
Three columns.....	1.70	1.65	1.60	1.55
Four columns.....	1.60	1.55	1.50	1.45
Flue, 42 sq ft.....	.....	.....	.....	1.57*
Window.....	1.85	.....	.....	.....
Wall (horizontal).....	1.95	.....	.....	.....
Wall (vertical).....	1.90	.....	.....	.....
Pipe-coils.....	2.00	.....	.....	.....

\* Air entering flues at 70° F. and leaving same at 152° F. Allen.

$K$  increases (1) as height of radiator is reduced and (2) as number of columns or width of radiator decreases.

**Coefficients of Transmission for Direct Hot-Water Radiators.** Table XI may be used for values of  $K$  for hot-water radiators of the same type as those listed, but allowance should be made for the lower temperature-range in hot-water heating. Thus, with a room usually at 70° F., and water at 180° entering and at 160° leaving the radiator, the temperature-range is only 100°, or 50% below the standard range. Then for a two-column 26-in high direct radiator the value of  $K$  becomes

$$K = (1.75 - 0.002 \times 50 \times 1.75) = 1.58$$

and each square foot of this radiation gives off,  $1.58 \times 100 = 158$  Btu per hr

**Concealed Radiators.** The effect of placing a grill in front of a direct radiator, with a cover over the top, reduces the heat-emission by approximately 20%. A clear space between the radiator, wall and enclosure should not be less than 2½ in. Concealed radiators are not looked upon with favor from a strictly sanitary point of view.

**The Usual Assumptions Made for the Heat-Transmission of Direct Radiation** is 250 Btu per sq ft per hr for low-pressure steam (2 lb) cast-iron radiators, and 150 Btu per sq ft per hr for cast-iron hot-water radiators with water at 180°. The square-foot rating of heating-boilers is based on the above figures. For more exact values use the data given in Table XI. According to these figures a hot-water installation requires 66⅔% more radiation than a low pressure steam system.

**Example.** It is required to determine the amount ( $R$ ) of direct cast-iron radiation, low-pressure steam and hot water, to supply a heat-loss of

$$H = 10\,000 \text{ Btu per hr}$$



tion. For the direct steam system

$R = H/250 = 40 \text{ sq ft}$

a direct hot-water system

$R = H/150 = 66\frac{2}{3} \text{ sq ft}$

ee-column cast-iron radiator, 38 in high, is to be used, the heating-surface h is 5 sq ft per section, it will require  $40/5 = 8$  sections for the steam-job, the length of radiator equal to  $8 \times 2\frac{1}{2} = 20$  in.

Fuels and Combustion

ification of Fuels. Fuels are generally classified as solid, liquid, and . SOLID FUELS are coal, wood, and wastes. LIQUID FUELS are petroleum products. GASEOUS FUELS are natural and artificial gas.

Fields in the United States. Most of the anthracite is found in beds han 500 sq miles in area located in eastern Pennsylvania. The prin- posit of semibituminous coal is about 300 miles long by 20 miles wide along the eastern edge of the Northern Appalachian field. The bitumi- ls extend from this deposit westward. A little graphitic coal is found e Island.

osition of Coal. The uncombined carbon in coal is known as FIXED Some of the carbon-constituent is combined with hydrogen, and this, with other gaseous substances driven off by the application of heat, t portion of the coal known as the VOLATILE MATTER. The fixed carbon volatile matter constitute the COMBUSTIBLE. The oxygen and nitrogen l in the volatile matter are not combustible, but custom has applied a to that portion of the coal which is dry and free from ash, thus includ- rygen and nitrogen in the combustible.

lication of Coals. Coals may be classified according to the percentages arbon and volatile matter contained in the combustible.

Table XII. Classification of Coals (Kent)

e of coal	Percentages of combustible		Btu per pound of combustible
	Fixed carbon	Volatile matter	
ite.....	97.0 to 92.5	3.0 to 7.5	14 600 to 14 800
hracite ....	92.5 to 87.5	7.5 to 12.5	14 700 to 15 500
minous ...	87.5 to 75.0	12.5 to 25.0	15 500 to 16 000
ous. East...	75.0 to 60.0	25.0 to 40.0	14 800 to 15 300
ous West...	65.0 to 50.0	35.0 to 50.0	13 500 to 14 800
.....	50.0 and under	50.0 and over	11 000 to 13 500

etric Determinations. The only accurate and reliable way to deter- heating-value of a fuel is to do so experimentally with a calorimeter. uels, the BOMB-CALORIMETER is the most practical. The various types rket include the Mahler, the Hempel, the Atwater and the Emerson. ist essentially of a tight vessel containing a weighed sample and oxygen sure. This receptacle is placed within another vessel containing a ght of water and surrounded by heat-insulating material to minimize

radiation. The sample is EXPLODED electrically, and the heat absorbed by surrounding water is determined by means of a very accurate thermometer reading hundredths of a degree. Correction has to be made for the heat absorbed by the instrument itself, and for radiation.

For a complete description of calorimeters and their use, see Carpenter & Diederichs' Experimental Engineering.

**Calorific Value by Formula.** The following expression, known as Du Long FORMULA for heating-value per pound of coal, can be used if the ultimate chemical analysis of the fuel is known:

$$F = 14\,600\,C + 62\,000\,(H - \frac{1}{8}O) + 4\,000\,S$$

where *C*, *H*, *O*, and *S* represent the proportionate parts of each element per lb of fuel, and *F* denotes the heat-value in Btu per pound due to combustion. This formula does not apply when the fuel contains carbon monoxide, CO, but can be made to apply by adding a term, 10 150 *C*, in which *C* is the proportionate part of carbon burned to the monoxide.

**Example.** The application of the formula to a coal of ultimate analysis here given follows:

Analysis (based on fuel as received)

C	74.79%
H	4.98
O	6.42
N	1.20
S	3.24
H <sub>2</sub> O	1.55
Ash	7.82
<hr/>	
	100.00%

Then by Du Long's formula, 14 600 × 0.7479 + 62 000 (0.0498 - 0.0642) + 4 000 × 0.0324 = 13 650 Btu per 1 lb of coal.

A bomb-calorimeter test showed 13 480 Btu for this coal. The formula fails to allow for evaporating and superheating the moisture present in the fuel.

**Combustion of Fuel.** Combustion, as used in steam-engineering, signifies rapid chemical combination between oxygen, and the carbon, hydrogen, and sulphur composing the various fuels. This combination takes place usually

Table XIII. Theoretical Amount of Air Required for Combustion

Fuel	Composition by weight			Lb of air per lb of fuel
	% C	% H	% O	
Wood-charcoal.....	93.0	.....	.....	11.16
Peat-charcoal.....	80.0	.....	.....	9.6
Coke.....	94.0	.....	.....	10.8
Anthracite coal.....	91.5	3.5	2.6	11.7
Bituminous coal, dry.....	87.0	5.0	4.0	11.6
Lignite.....	70.0	5.0	20.0	8.9
Peat, dry.....	58.0	6.0	31.0	7.68
Wood, dry.....	50.0	6.0	43.5	6.00
Mineral oil.....	85.0	13.0	1.0	14.30

temperature with the evolution of light and heat. The substance which combines with the oxygen is known as the COMBUSTIBLE, and if it is completely oxidized the combustion is PERFECT, that is, no more heat is evolved than is taken up by the products of the reaction. The combustion is incomplete when carbon burns to form carbon monoxide, CO, instead of carbon dioxide, CO<sub>2</sub>, since the former may be further burned to form carbon dioxide if necessary oxygen is supplied. It is necessary to provide for an excess of air in burning coal under either natural or forced draft, amounting to 25 to 100% of the net calculated amount, or about 18 to 25% excess. Less air results in IMPERFECT COMBUSTION and smoke, while too much air is wasteful and setting and carries away a large percentage of the heat.

**IV. Weight and Calorific Value of Various Gases at Standard Temperature and Atmospheric Pressure, with Theoretical Amount Required for Combustion**

Gas	Symbol	Cubic feet of gas per pound	Btu	
			Per pound	Per cubic foot
Hydrogen.....	H	178.0	62 000	348
Carbon monoxide...	CO	12.81	4 380	342
Methane.....	CH <sub>4</sub>	22.4	23 842	1 065
Ethane.....	C <sub>2</sub> H <sub>6</sub>	12.0	22 400	1 865
Propane.....	C <sub>3</sub> H <sub>8</sub>	12.8	21 430	1 675
Acetylene.....	C <sub>2</sub> H <sub>2</sub>	13.79	21 430	1 555

**Storage.** Space for fuel-storage must be based on fuel-consumption as estimated under Fuel-Consumption, page 1278, and in practice it is customary to proportion the storage-space on the basis of cubic feet per ton, the storage-space being made ample to handle the fuel supply.

Following volumes per ton of 2240 lb of coal are given for reference: bituminous coal, 41 to 45 cu ft, and may run as high as 50 cu ft; anthracite coal, 34 to 41 cu ft; charcoal, 123 cu ft; coke, 70.9 cu ft. These are based on fuel broken down ready for market. Also 1 ton = 2000 lb and 1 bushel soft coal = 76 lb.

**Steam-Heating Boilers and Hot-Water Heaters**

**Design, Operation, Attention, and Materials.** Heating-boilers usually operate at lower PRESSURE than do power-boilers, and in most cases require no special treatment. The steam-boilers are usually designed to operate on forced draft, and the WATER-BOILERS or hot-water heaters are designed to operate under hydrostatic head in excess of 100 FT when in operation. The operation of these boilers is of such an INTERMITTENT CHARACTER that the heating-load for comparatively long periods without interruption. The range from 6 to 10 hrs and in consequence the comparatively large grates and fire-pots are necessary. The materials for constructing heating-boilers are CAST IRON, especially for the lower parts, although boilers of nearly 100 equivalent steam rating (see Rating of Heating-Boilers) are made of this same material.

**STEEL OR WROUGHT IRON**, which are more generally used in the larger sizes. The government departments usually specify steel heating-boilers, and they are used extensively in office and loft-buildings as well.

**Boiler Heating-Surface.** The CAPACITY of any boiler or water-heater depends on the amount of, and the temperatures on the opposite sides of, the heat-transmitting surfaces in contact with the water in the boiler on one side, and the fire or hot gases on the other. It is most important that a rapid circulation of water and the hot gases shall take place over these surfaces, and preferably in opposite directions. Two kinds of surface are distinguished in boiler-practice and known as direct and indirect surface. **DIRECT SURFACE** is that on which the fire shines, and **INDIRECT** that in contact with the flue-gases only. All surface must have water on the opposite side. In some boilers the hot gases are allowed to come in contact with the boiler-surface above the water-level so that there is only steam in contact with this surface on the inner side. Such surface is known as **SUPERHEATING-SURFACE** in order to distinguish it from ordinary heating-surface. Direct surface is the more valuable of the two, per square foot, as it is usually subjected to a higher temperature, and furthermore because the intensity of radiation from an incandescent surface appears to vary as some power of the temperature of that surface, either the third or fourth.

**Equivalent Evaporation.** The equivalent evaporation of a boiler is the pounds of water the boiler would evaporate per pound of coal burned if it received the feed-water at  $212^{\circ}$ , and evaporated it into steam at this same temperature and pressure, so that the evaporation would take place FROM AND TO  $212^{\circ}$  F. In practice the feed-water is usually below this temperature and the evaporation actually takes place at some higher temperature. Hence to find the **EQUIVALENT EVAPORATION** it is always necessary to make use of the following relation:

$$E = \frac{(x_2 r_2 + q_2 - q_1)}{971.7} \times P$$

where the fractional part of the expression is known as the **FACTOR OF EQUIVALENT EVAPORATION**; so that

$$E = \text{factor of evaporation} \times P$$

$E$  = equivalent evaporation from and at  $212^{\circ}$  F., in pounds;

$x_2$  = quality of steam as actually evaporated;

$r_2$  = latent heat of steam as actually evaporated;

$q_2$  = heat of the liquid as actually evaporated;

$q_1$  = heat of the liquid as actually fed to boiler;

$P$  = actual evaporation in pounds per pound of fuel burned;

971.7 = latent heat of steam at  $212^{\circ}$  F.

**Boiler Horse-Power.** A boiler horse-power is the energy required to evaporate 34.5 lb of water at  $212^{\circ}$  F. into DRY STEAM of  $212^{\circ}$  F., or

$$971.7 \times 34.5 = 33\,524 \text{ Btu}$$

The **HORSE-POWER RATING** of a boiler is always measured in terms of the equivalent evaporation. Thus, if we divide the **EQUIVALENT EVAPORATION** of a boiler by 34.5 we get the boiler horse-power developed.

**Boiler-Efficiencies.** Heating-boilers, operated at their rated capacity, show an **EFFICIENCY** of from 55 to 65%. This efficiency is the ratio of the heat absorbed per pound of dry coal by the water and steam in the boiler to the actual heat-value of one pound of the coal, and is the **COMBINED EFFICIENCY** of the boiler and furnace.

**Tables of Combustion for Heating-Boilers.** Combustion-rates for varying grate-areas are given in Table XV:

**Table XV. Combustion-Rates**

Grate-areas	Coal per square foot per hour, in pounds	Remarks
4 sq ft or less (small),	5	A variation of 10% up or down from these rates is perfectly safe. The higher values are for full-sized chimneys with lined flues and the lower for unlined flues or long breeching-connections.
5-10 sq ft (medium),	5.7	
11 ft or larger (large),	6.6	
to 8 sq ft	4	(Am. Soc. H. and V. E. Com. 1909.) Rates of combustion reported for anthracite coal, as fired in internally fired heating-boilers. See Transactions for further details.
to 18 sq ft	6	
to 30 sq ft	10	

**Rating of Heating-Boilers. Standard Conditions.** It is the general custom of American manufacturers of heating-boilers to rate their boilers in terms of number of square feet of standard direct cast-iron radiating-surface which is capable of supplying under the following conditions:

Steam boilers; steam-pressure 2-lb gauge at boiler.

Hot-water boilers; water-temperatures: 180° F. leaving, and 160° F. boiler.

Fuel; anthracite coal of stove-size.

**RATING OF COMBUSTION**, or amount of coal necessary per hour for the boiler upon its rating has, until recently, seldom been given; and the method of making the rating has varied with different makers and is seldom stated. Therefore, it is possible for a boiler to be placed on the market and assigned a rating although such rating has never been actually checked by test. It therefore becomes most important to not only establish STANDARD CONDITIONS OF TESTING, but to require the manufacturer to be in a position to provide certified test-sheets of such tests for his line of boilers. The STANDARD CONDITIONS under which a boiler should be tested to develop its rating are generally understood by the manufacturers at the present time to be as follows: pressure, temperature and fuel as stated above.

Grate-capacity to be sufficient to carry the boiler from 6 to 8 hr on one charge and leave 20% reserve for igniting fresh charge.

Flue draft of sufficient intensity to burn the fuel at the required rate. A flue not less than 40 ft in height is recommended.

Each square foot of direct cast-iron radiation has a transmission-value of 150 Btu per hour for steam and water-radiators respectively.

Condensation from steam-radiators returns to the boiler at the same pressure as the steam, or without loss of heat, so that the boiler simply supplies latent heat of evaporation at 2 lb pressure, or 967 Btu per lb evaporated.

Water from hot-water radiators returns to the boiler at 160°, allowing for drop in the radiators, so that there is no loss in temperature allowed in the return main.

Reasonable heat-allowance must be made for all connecting piping and boiler fittings and such surface must be figured as radiating-surface or its equivalent.

A general rule is to add, for an ordinary installation, about 50% of the sq ft radiation installed, in calculating the total load on the boiler, with anthracite fuel and 65% with bituminous fuel, to allow for radiation-loss of piping and boiler and the additional tax on the boiler due to starting up with cold radiation.

**Equivalent Boiler Horse-Power Rating of Heating-Boilers.** The capacities of heating-boilers may be stated in boiler horse-power, and the equivalent of same in square feet of standard radiation may be easily determined as follows:

Since 1 boiler horse-power is equal to 34.5 lb of water evaporated per hour from and at 212° F., the boiler must deliver

$$34.5 \times 971.7 \text{ (latent heat at 212° F.)} = 33\,524 \text{ Btu per hr}$$

Now since 1 sq ft of standard cast-iron steam-radiation transmits 250 Btu per hour,

$$1 \text{ boiler horse-power} = 33\,524/250 = 134.1 \text{ sq ft of this radiation, or}$$

$$1 \text{ sq ft of direct cast-iron steam-radiation} = 0.00756 \text{ boiler horse-power}$$

It also follows that the equivalent boiler horse-power rating of a hot-water heater is

$$33\,524/150 = 223.5 \text{ sq ft of direct cast-iron hot-water radiation, or}$$

$$1 \text{ sq ft of direct cast-iron hot-water radiation} = 0.00447 \text{ boiler horse-power}$$

**Grate-Surface.** It is always advisable to check THE GRATE-AREA REQUIRED for heating-boilers, especially if the total heat-loss to be supplied by the boiler is known. This total heat-loss must include not only the calculated loss, due to transmission through walls and glass, for which the radiation is proportional, but also about 50% additional for heat-losses from the piping system, boiler, etc. So that, if  $H$  is the building-loss in Btu,  $1.5H$  = total Btu-loss.

Then

$$G = 1.5H/(C \times F \times E)$$

where  $C$  = rate of combustion in pounds of dry coal per square foot of grate area per hour,  $F$  = calorific value of fuel in Btu per pound of dry coal (12,000 is the usual assumption for anthracite coal), and  $E$  = the combined efficiency of boiler and grate (60% is the usual assumption).  $G$  is in sq ft and the boiler selected should have not less than this grate-area. Special attention is called to the distinction between GRATE-AREA and FIRE-BOX OR FUEL-POT AREA explained below under Depth of Fuel-Pot.

**Depth of Fuel-Pot.** The average of the fire-box area is usually somewhat larger than the grate-area in sectional boilers, while it may be less than the grate-area in certain types of round boilers. In any event the capacity of the fire-box or fuel-pot from grate to middle of fire-door should always be sufficient to hold all the coal required for an 8-hr firing-period, plus at least a reserve to be used for igniting a fresh charge.

The following method is used to determine the depth of pot or the firing-pot as the case may be. Let  $G$  = grate-area in sq ft,  $C$  = rate of combustion,  $A$  = average area of fire-pot,  $h$  = firing-period in hours,  $W$  = weight of fuel per sq ft (50 lb for anthracite and 40 lb for bituminous),  $D$  = depth of fuel-bed in ft. Then  $(GC h) + 20\%$  (allowance to ignite fresh charge) = total weight of fuel charge; also,  $AWD$  = total weight of one charge. Hence

$$D = 1.2GC h/AW, \text{ or } h = AWD/1.2GC$$

noted above  $D$  is measured from grate to center of fire-door, which varies  $3 \times 14$  in in small, to  $11 \times 19$  in in large boilers. This formula allows greater bulk of soft coal.

**Example.** Given a boiler with grate-area of 8 sq ft, average area fire-pot height to center of fire-door = 18 in, rate of combustion = 6 lb per sq ft for anthracite coal. Required the number of hours this boiler will load on one charging.

**Solution.**

$$h = (9 \times 50 \times 1.5) / (1.2 \times 8 \times 6) = 11.7 \text{ hours}$$

**Notes of Fuels on Ratings.** All ratings are based on ANTHRACITE COAL OF SIZE unless otherwise stated. In case bituminous coal is used and the size selected by catalogue-rating, a boiler with fire-pot having at least 25% capacity should be selected, for the same weight of coal occupies 25% space. With SOFT COAL additional heating-surface is also required as the liberation of soot from such coal renders the heating-surfaces less effective when hard coal is used. Boilers for PEA-COAL should also have a larger capacity than those for stove or furnace-coal. The SMALL SIZES OF ANTHRACITE produce far more ash than the larger sizes, and hence have a greater bulk for the heating effect; so that larger fuel-pots for the same capacity are required. PERIODS, differing from the one on which the boiler is rated, will also affect the heating capacity. For example, if it is required to operate a certain line of radiators designed for an 8-hr period on a 12-hr basis, at least 50% greater fuel-capacity will be necessary and a larger boiler must be selected, as shown by the formula already given for the depth of the fuel-pot.

**Equivalent Rating for Conditions Other than Standard.** It often happens that a load connected to a steam-or hot-water boiler may not be operated under standard conditions previously assumed as a basis of rating. In this case the standard ratings cannot be used until the EQUIVALENT VALUE of this load in square feet of standard cast-iron radiation has been determined.

The following relations show a method for finding such equivalent values:

1 sq ft standard cast-iron radiation = 250 Btu per sq ft for steam, and 150 Btu per sq ft for water. Also let

$r$  = actual sq ft of radiation to be supplied;

$K$  = coefficient of transmission for this radiation;

$t_w$  = temperature of steam or average temperature of hot water in the radiator;

$t_a$  = temperature of air surrounding radiator;

$(t_a)$  = radiation-factor or Btu given off per sq ft per hr;

$$R_s = r_1 \times K_1(t_s - t_a)/250, \text{ and } R_w = r_2 \times K_2(t_w - t_a)/150$$

**Example.** (Steam-heating.) Required the size of boiler (rating in sq ft of cast-iron radiation) to supply 1 000 sq ft of direct pipe-coil radiation. Pressure = 5-lb gauge. Air = 65° F.  $K$  (by test) = 2.42 Btu. From tables,  $t_s = 227.14$ ,  $R = 1\,000 \times 2.42(227.14 - 65)/250 = 1\,000 \times 52.14/250 = 1\,570$  sq ft. To this add 50% for pipe and boiler-radiation and the additional tax for starting up with cold radiation, or,  $1.5 \times 1\,570 = 2\,355$  sq ft, or practically a 2 400-sq-ft-capacity boiler will be required. This should be checked by calculation previously given to ascertain size.

$$G = 1.5H/(C \times F \times E)$$

**Example.** (Water-heating.) Let  $Q$  = total number of gal of water to be heated in  $h$  hours.

$$W = (8\frac{1}{2} \times Q)/h = \text{weight of water to be heated per hour}$$

$$t_1 = \text{initial temperature of water, } t_2 = \text{final temperature of water}$$

Then  $W(t_2 - t_1)$  = Btu to be supplied per hour. Hence  $W(t_2 - t_1)/150$  = hot-water-heater rating required.  $W(t_2 - t_1)/250$  = steam-boiler rating required.

**Example.** A swimming pool contains 50 000 gal of water, and this water heated by being passed through a hot-water heater in four hours. Entering temperature = 50° F. and final temperature = 75° F. Hot-water radiation reduced to equivalent standard value =  $[(50\,000 \times 8\frac{1}{2})/(4 \times 150)](75 - 50) = 17\,350$  sq ft = rating of hot-water heater, to which must be added 50% for losses from piping, etc.

**Fuel-Consumption.** The ESTIMATED FUEL-CONSUMPTION FOR HEATING BOILERS per heating-season may be based on grate-areas, square feet of radiation installed, or cubic contents of building to be heated. The United States Treasury Department allows 5 tons of coal per sq ft of grate-area per season of 240 days or 1 lb of coal per cu ft of contents of building for the same period. This applies to government buildings. The district steam-heating companies estimate 500 lb of steam per sq ft of direct steam-radiation per season, which is practically the same as 70 lb of coal of good quality. This is approximately equivalent assuming that one-third of the radiation installed is in operation continuously for 240 days. In other words, the coal required for a heating-season is about one-third the quantity that would be used if all the radiation were in constant operation every hour of the day and night. The amount of coal for maximum conditions is determined as follows:

Since each foot of direct steam-radiation or its equivalent will give off 2 Btu per hour under conditions of 2 lb (220°) pressure at boiler, and 70° air surrounding the direct radiators (the piping on the average job may be roughly taken as 25% of the direct radiation); and since for approximation we may assume 8 000 Btu per pound of anthracite coal burned; we can readily estimate the amount of coal per hour if  $R$  = amount of direct radiation in square feet

$$(1.25 \times R \times 2.50)/8\,000 = C = \text{coal per hour in pounds}$$

In a heating-season of 7 months or 210 days of 24 hours each, there would be burned under maximum conditions during the entire period

$$(1.25 \times R \times 2.50 \times 210 \times 24)/(8\,000 \times 2\,000) = 0.0984R \text{ tons of coal}$$

the actual consumption being about one-third of the maximum possible, 0.0328  $R$  tons of coal for the heating-season. For hot-water heating the fuel consumption for the entire season is approximately 0.0197  $R$  tons.

**Types of Heating-Boilers.** Cast-iron steam-heating boilers are designed to be operated at a maximum pressure of 15 lb per sq in, and the sections are tested by the manufacturer to about 100 lb per sq in, hydrostatic pressure. Cast-iron boilers are constructed of sections, which are connected by means of nipples, either the push or screw-type. The sections are held in place by means of 12 bolts. Round-type boilers have horizontal sections surrounding the fire-pipe, and in the sectional type the sections are placed vertically. (See Figs. 16, 17, and 18.) The maximum size of round-type boilers manufactured is rated at about 1400 ft. Sectional boilers are obtainable up to a 10 000 sq-ft-rating. See manufacturers' catalogues for capacities, dimensions, etc.)



**Upward or Down-Draft Cast-Iron Boilers.** Boilers having a water-grate now being made for use with free-burning soft coal, where local smoke-laws would not permit the use of such fuel on ordinary grates.

**Fig. 16. Sectional Type of Cast-Iron Boiler**

**Selection of Cast-Iron Boilers.** The selection of cast-iron boilers should not be influenced too largely by considerations of price, and the ease with which they may be carried into a building where structural conditions interfere with the introduction of a steel boiler.

In many cases the character of the service, the nature of the attendance, or both, especially in government and other public building work, may be such that steel equipment, which is capable of withstanding more abuse, should be used. This is particularly true when hot water returns are handled by a pump. If cast-iron boilers are to be installed, the gross area necessary should be carefully computed as already indicated, using an average rate of combustion, and a fuel-pot depth based on the firing-period required. The United States Treasury Department selects cast-iron boilers by proportioning them to carry 25% more radiation than actually installed if anthracite coal is used, and 35% more if bituminous coal is used. In addition to this, suitable allowance must be made for pipe mains and other piping, and in most cases two boilers are installed, each capable of supplying two-thirds of the radiation required in order to provide for units which can be operated with a high-load factor, and to act as a reserve for each other in case of breakdown.

Fig. 18. Section of Round-type Boiler

**Steel Heating-Boilers.** There are two general types of all-steel boilers used for heating work, the **FIRE-BOX TYPE** and the **RETURN TUBULAR TYPE**.

In the fire-box type the grate and combustion-chamber are surrounded by an extension of the steel shell which is water-jacketed. The products of combustion pass directly through the tubes to the smoke-flue located in the rear. In the return tubular type, the boiler consists of a shell with tubes set in brick setting, the grate and combustion-chamber being directly under the front portion of the shell. The products of combustion in this case pass under and around the shell to the rear of the boiler, and then through the tubes to the front into the smoke-box.

Fire-box type boilers may be obtained in capacities ranging from 500 to 134 sq ft of direct radiation. The most common of these boilers are the Durrill, Gorton, and Kewanee. Detailed information as to capacities, dimensions, etc., may be obtained from the makers' catalogues. As usually constructed, these boilers are designed for a working pressure of 60 lb per sq in and are so insured by the boiler-insurance companies. This type may be obtained with or without (portable type) brick-setting. The return tubular boiler is erected with brick setting and as ordinarily constructed, is designed for a working pressure of 100 lb per sq in, but may be obtained for a working pressure of 150 lb per sq in if desired. It is primarily a power-type boiler, but is commonly used in conjunction with large heating systems having 10 000 sq ft or more of direct radiation. These boilers are rated on a basis of 10 sq ft of boiler heating-surface per boiler horse-power. A special design of setting is required for smokeless combustion when bituminous coal is to be used as fuel. The so-called standard setting should not be used in this connection. (See Boilers and Rules for C

ion in Mechanical Equipment of Buildings, Vol. II, by Harding and d.)

mneys for Heating-Boilers. (See also, under Chimneys, page 1364.)  
er to produce an intensity of draft sufficient to properly operate low-  
e heating-boilers, hot-water boilers, and hot-air furnaces up to their  
apacity, the chimney should not be less than 40 ft in height, measured  
e grate. No flue should be less than 8 × 8 in. The failure of many  
-installations may be traced to insufficient draft to burn the fuel at the  
quired to run the boiler or furnace to rated capacity. The tempera-  
flue-gases leaving the boiler should range between 400° and 500° F. when  
aratus is worked at its rated capacity. The chimney should be so  
with reference to any higher buildings nearby that wind-currents will  
n eddies and force the air downward in the shaft, as shown in Fig. 19.

ie should run as nearly  
as possible from the base  
top outlet. The outlet  
ot be capped so that its  
less than the area of the  
he flue should have no  
into it other than the  
moke-pipe. Sharp bends  
ets in the flue often reduce  
and choke the draft, and

must be free of any  
which prevents the full  
the passage of smoke. If the flue is made of tile, the joints must be  
mented, or all space between the tile and brickwork filled in tightly.  
ust be no open crevices into the flue where the tile sections meet, other-  
draft will be checked. If the flue is made of brick, the stack should  
side walls at least 8 in thick to insure safety. The inside joints should  
struck, and each course should be well bedded and free from surplus  
t the joints. The exposed bricks at the top of a brick chimney should




Fig. 19.Relation of Height of Chimney to Draft

Table XVI. Fire-Clay Flue-Linings

Robinson Clay Product Co., Akron, Ohio

Rectangular			Round	
nominal size, in.	Actual size outside, in	Actual size inside, in	Inside diameter, in	Outside diameter, in
8 1/2	4 3/4 × 8 3/8	3 1/4 × 7	6	7 1/2
13	4 3/4 × 13 1/4	3 1/8 × 11 3/4	7	8 1/2
18	4 1/2 × 17	3 1/8 × 15 1/2	8	9
12	6 × 12	4 1/2 × 10 1/2	9	10 1/2
7	7 1/4 × 7 1/4	5 3/4 × 5 3/4	10	12
8 1/2	8 1/2 × 8 1/2	7 1/4 × 7 1/4	12	14
13	8 1/2 × 13	6 7/8 × 11 5/8	15	17 1/8
18	8 1/2 × 18	6 1/2 × 16	18	20 1/8
13	13 × 13	11 1/4 × 11 1/4	20	23
18	13 × 18	10 3/4 × 15 3/4	24	27
18	18 × 18	15 1/2 × 15 1/2	30	35

be laid in cement mortar to prevent the acid fumes and rain from cutting the joints. This will happen if lime mortar is used. The most desirable location for a chimney is near the center of the building, as all walls are then warm. If there is a soot-pocket in the flue below the smoke-pipe opening, clean-out door should always be tightly closed. If this soot-pocket has other openings into it from fireplaces or other connections, these openings check draft and prevent the best results. The smoke-pipe should not extend into the flue beyond the inside surface of the latter. If it does extend beyond, it cuts down the area of the flue. The joints, where the smoke-pipe fits the smoke-hood of the boiler, or where the pipe enters the chimney, should be made tight with boiler-putty or asbestos cement. Fire-clay flue-linings are used as the best practice for small and medium-sized flues. Rectangular flue-linings are rated by outside dimensions, and round linings by inside dimensions.

**Flues for Kitchen Ranges and Fireplaces.** (See also, under Chimneys, page 1364.) For a kitchen range an  $8\frac{1}{2}$  by  $8\frac{1}{2}$ -in tile flue is ordinarily sufficient, but an  $8\frac{1}{2}$  by 13-in is better. For fireplaces the sectional area of the flue burning wood or bituminous coal should be from  $\frac{1}{10}$  to  $\frac{1}{8}$  the area of the fireplace-opening for a rectangular flue, and  $\frac{1}{12}$  for a circular flue. For burning anthracite coal the areas may be reduced to  $\frac{1}{12}$  and  $\frac{1}{16}$  respectively.

**Selection of Chimney-Flues.** (See also, under Chimneys, page 1364.) The selection of chimney-flues for heating-boilers must depend upon the judgment of the heating-engineer, but it is believed that Table XVII, by R. C. Carpenter, will very much assist the engineer in selecting flues. It is necessary that AREA, HEIGHT, THICKNESS OF WALLS, GENERAL STRUCTURE, and the POSITION OF THE TOP OUTLET with reference to the building and other buildings near by should be carefully noted and observed in the selecting or building of a flue. The figures given under the varying heights of chimneys are diameter-measurements in inches, or, the side of a square, the theory being that the spirally ascending column of smoke and gases will make a 12 by 12-in flue no more effective in practical working-area than a twelve-inch round flue. Rectangular shapes may be used if the area is equal and the difference in width and breadth is not extreme. A maximum ratio of 2 : 1 for the internal dimensions should not be exceeded.

**Table XVII. Chimneys for Steam and Hot-Water Boilers**

Direct radiation		Height of chimney-flue				
Steam, sq ft	Water, sq ft	30 ft	40 ft	50 ft	60 ft	80 ft
250	375	7.0	6.7	6.4	6.2	6.0
500	750	9.2	8.8	8.2	8.0	7.6
750	1 150	10.8	10.2	9.6	9.3	8.8
1 000	1 500	12.0	11.4	10.8	10.5	10.0
1 500	2 250	14.4	13.4	12.8	12.4	11.5
2 000	3 000	16.3	15.2	14.5	14.0	13.3
3 000	4 500	18.5	18.2	17.2	16.6	15.8
4 000	6 000	22.2	20.8	19.6	19.0	17.8
5 000	7 500	24.6	23.0	21.6	21.0	19.4
6 000	9 000	26.8	25.0	23.4	22.8	21.2
7 000	10 500	28.8	27.0	25.5	24.4	23.0
8 000	12 000	30.6	28.6	26.8	26.0	24.2
9 000	13 500	32.4	30.4	28.4	27.4	25.6
10 000	15 000	34.0	32.0	30.0	28.6	27.0

**Grate-Areas and Stack-Dimensions.** For return tubular  
S. Thompson gives the following rules for grate-areas and

radiation in building; B. H. S. = heating-surface in boiler;  
(all in sq ft)

7 for steam;  $R + 11$  for water.  $G = B. H. S. + 25$  (anthracite);  $G = B. H. S. + 30$  to  $B. H. S. + 35$  (bituminous coal, B. H. S. + 45 (lower grate of down-draft furnace).

stack, ft.  $A$  = area of grate, sq ft.  $S$  = area of stack, sq ft. (anthracite coal, lump coal, oil, and gas).

$+ \sqrt{H}$  (bituminous and small anthracite).

pea, or rice coal, tube-area must be not less than  $\frac{1}{8}$  grate, and a stack.

In down-draft furnace, tube-area must be not less than  $\frac{1}{8}$  of always larger than stack.

Thickness of tube must not exceed 48 diameters.

Length of boilers, 54-in diameter and under, must not exceed 3 54-in,  $2\frac{1}{2}$  diameters.

Number of feet in length, are not used.

**Buildings** are special cases and may be designed by methods of chimneys for power-boilers. (See Power Plants and Harding and Willard. See also, List of Tall Brick Chimneys,

## Direct Steam Heating

**Direct Steam Heating in Use.** Systems for heating with direct are broadly divided into two general classes, known as: (1) **NATURAL CIRCULATING SYSTEMS**, and (2) **MECHANICAL CIRCULATING SYSTEMS**. The distinguishing characteristic is the manner in which the water of condensators is returned to the boiler. In the first type the condensate returns by gravity, due entirely to the **STATIC HEAD** existing in the system is a closed circuit. The steam-pressure existing in the mains and radiators is the same, except for friction-pressure losses due to the steam to the heating-surfaces. In the second type the condensate returns to a receiver or feed-water heater and is then forced into the boiler, or **RETURN-TRAPS**, or both. This is not a closed system, and the boiler may be much higher than that in the mains and radiators. The receiver is usually vented to the atmosphere, and in the case of the second type an additional pump is attached directly to the returns and discharges the condensation into the receiver or heater. Gravity circulating systems are further divided into the **ONE-PIPE SYSTEM** and the **TWO-PIPE SYSTEM**. In the one-pipe system the basement-mains supplying risers to the various floors above (Figs. 19, 20), or with overhead mains supplying drop-risers to the floors below. In the two-pipe system the steam and water of condensation in the risers flow in opposite directions, so that less friction is produced as countercurrents do not occur. In all cases smaller pipe-sizes may be used. The overhead system is very common, and is known as the **MILL'S SYSTEM**.

**Gravity Systems.** The **ONE-PIPE CIRCUIT SYSTEM** (Fig. 20) with its main is probably the simplest, and most common gravity system in use. The main rises close to the basement-ceiling, just above the boiler, and then descends uniformly from this high point with a fall of 1 or  $\frac{1}{4}$  in in 100 ft. The last radiator has been served the main drops below the boiler.

water-line and its size is reduced, as on the run back to the boiler it carries on condensation and is known as a WET RETURN. This return may be run above the boiler water-line if necessary, and is then called a DRY RETURN. Return-mains are graded 1 in in 30 ft in gravity work. In either case an automatic air-valve




Fig. 20. Low-pressure Gravity System. One-pipe Basement-main

must be installed on the end of the main at the drop, as shown, to vent the steam when air collects in the piping. The elevation of the end of the steam-main with respect to the boiler water-line must be carefully determined, in order that water may not back up from the boiler and flood the main, including the air-valve and




Fig. 21. One-pipe Relief Basement-main

branches. It is customary to maintain at least 18 in between the under side of the main at the drop and the normal water-line of the boiler to provide for contingencies. In operation it will be noted that steam and water flow in the same direction through the one-pipe steam-main, and in opposite directions through the basement-branches, risers, and radiator-branches. This necessitates larger piping and valves than in any other steam system, and especially is this true of the main, which must be run full size from boiler to drop, unless dripped as shown under piping-details.

**ONE-PIPE SYSTEM** (Fig. 21) is very similar to the one-pipe circuit, the risers are dripped individually into the return, and the no radiator-condensation, and is itself dripped at intervals in, which may run DRY or WET. This makes it possible (1) if main as radiation is taken off, (2) to use smaller branches, main much closer to the basement-ceiling, a very important basement-space is valuable. A COMBINATION OF THE ONE-PIPE TWO-PIPE SYSTEM is frequently used in large installations, used for the first and second floors, and the former for the buildings. In this way the amount of condensation flowing risers against the steam is much reduced and smaller risers application of the one-pipe system, with gravity-circulation to tall buildings, is not at all unusual, and if the piping is or the circulation of steam and the return of the water of be found satisfactory. In the case of long narrow buildings system it may be necessary to provide a deep boiler-pit so of water in the return-connections will not flood the far end

**y Systems.** The TWO-PIPE SYSTEM with basement-mains used in large buildings, and in ALL WORK WHERE INDIRECT

Fig. 22. Two-pipe Basement-main

**LEAD.** This system can be readily adapted to mechanical and is very extensively used in this connection. It will be t when applied to a gravity system the return from each ILY SEALED, either by dropping below the water-line to a using drip-loops, as shown at the left, before connecting to in one-pipe work all drips or reliefs are sealed as shown in action is not taken steam may enter a drip or return from use knocking in the system due to countercurrents of steam ation. Any drip, relief, return-riser, or connection from the side of the system MUST BE SEALED. This may be done by water-line, or else by using a running trap or a return-trap connecting line. Neglect of this precaution will cause an ion of the system.

**for Air-Valves for Gravity Systems.** The AUTOMATIC steam-radiators must be provided for if the highest efficiency-surfaces is to be realized in gravity circulating systems.

Manually controlled air-valves or cocks are usually neglected, and are seldom used for steam-radiators although their use is quite general for hot-water radiators. Fig. 23 shows a float-type of automatic air-valve. Thermostatic air-valves are finding favor in this field. The proper location of the air-valve on a steam-radiator is at the end of the radiator opposite the steam-inlet, and near the bottom of the radiator as possible, since air is heavier than steam at the same temperature. In practice, however, the manufacturer of radiators

VALVE CLOSED

VALVE OPEN

Fig. 23. Norwall Automatic Air-valve

usually places the air-valve tapping about two-thirds the height of the radiator from the floor in order to prevent possible flooding of the valve.

**Special Gravity Systems.** In addition to the low-pressure gravity system already described there are many special steam heating systems known as Air




Fig. 24. The Paul Air-Line System

LINE, VAPOR, and VACUUM SYSTEMS, also operating with gravity-return of water of condensation. The AIR-LINE SYSTEM may be attached to any one or two-pipe gravity system, and is applied by connecting the automatic air-valve of each radiator with small-size piping to an exhauster which maintains a slight vacuum in the air-piping and effectually removes the accumulation of air from the radiators. As this scheme is a positive means of air-removal its application to the ordinary one or two-pipe gravity system will improve its operation. The original air-line system is known as the PAUL SYSTEM (Fig. 24). The exhauster used for less than 2500 sq ft is a water-driven vacuum-pump, with a pump



at least 20 lb per sq in. Larger systems use a high-pressure steam-jet (bove), or if steam is not available, a motor-driven vacuum pump of about one-horse-power, in air-mains in basement, and a gate valve on each air-riser. The steam used varies from 1 to 5% of the total condensation. All air-connections are made as shown. The Bishop-Babcock-Becker Com-

Fig. 25. The Bishop-Babcock-Becker Air-line System

manufacture the following line of air-pumps that are used for exhausters in air-line systems (Fig. 25):

Table XVIII. Hydraulic Exhausters

Diam suction-cylinder, in	Length of stroke, in	Number of pump	City water-pressure, lb	Max. cap. direct rad., sq ft	Number of pump	City water-pressure, lb	Max. cap. direct rad., sq ft
2 3/4	4	101	20	700	104	40	4 000
2 1/2	4	101	40	800	106	20	6 600
4	8	102	20	900	106	40	9 600
5 1/2	10	102	40	1 100	2-106	20	14 000
.....	.....	104	20	2 500	2-106	40	20 000

**Mechanical Vacuum Systems.** The so-called mechanical VACUUM SYSTEMS are two-pipe type, and have a vacuum-pump attached directly to the

This pump may be steam or motor-driven, but must be capable of exhausting both air and water, as no air-valves can be used on the radiators in the system. The return-end of each radiator is equipped with a radiator-

Table XIX. Motor-Driven Exhausters

Number of pump	Max. capacity, direct radiation, sq ft	Cylinder-sizes		Size of connection		Strokes per minute	Horse-power
		Bore, in	Stroke, in	Disch'-pipe, in	Suction-pipe, in		
I 279	4 000	2 1/4	3	1	1	150	1 1/2
112	10 000	3	3 1/2	1	1	70	1 1/2
113	18 000	4	3 1/2	1 1/4	1 1/4	70	3/4
114	28 000	4	5	1 1/2	1 1/2	68	1
115	35 000	5	5	2	2	60	2

trap, usually of the thermostatic type and commonly termed a **VACUUM-VALVE** such as the Dunham (Table XX), Webster, Illinois, Monash, etc. A volatile liquid is employed in the thermostatic element or bellows. This liquid is vaporized immediately as steam is brought in contact with the bellows, and cause the latter to expand and thus close the valve. The temperature of the condensate from the radiator is slightly below the temperature of the steam but is not sufficiently high to vaporize the liquid. The valve therefore remains open and will pass the water of condensation and air until the steam starts to flow, when it immediately closes. These valves are very sensitive, and when properly adjusted and in order will not blow steam. One type of **THERMOSTATIC VALVE** is shown in Fig. 26. It is customary practice to connect a 1/4-in cold-water line to the main return at the pump, which serves to condense any steam that may leak by the vacuum-

Connected to


Connected to Return-Pipe

Fig. 26. Thermostatic Valve or Vacuum-trap

Overhead system

valves due to dirt getting under the seat and preventing the valve from closing tight. Figs. 27, 28 and 29 show clearly the application of vacuum-traps to the two-pipe system. It will be observed by inspection of Table XXVII that the return-connections for a vacuum system are much smaller than are used in the ordinary two-pipe system, Table XXVI. The vacuum

is largely employed in connection with exhaust steam-heating, where it is important to keep down the back-pressure on the steam-engines or turbines to approximately 5 lb per sq in. A steam trap with reducing-valve is used to connect the live-steam main to the heating system. This valve automatically opens and allows live steam at a reduced pressure (usually to 5 lb) to flow into the heating



Detail Showing Method of Dripping Rise in Steam-main

Fig. 29. Detail Showing Method of Connecting Rotary Vacuum-pump when Return-line is Below Vacuum-pump

whenever the demand is greater than the supply from the engines, or the engines are not in operation. (See Fig. 30.)

Reduction

Fig. 30. Exhaust Steam-heating Vacuum System

vacuum maintained by the pump on the main-return line is ordinarily in of mercury. This pump is placed under automatic control. The being operated by the pressure in the return-line

Table XX. Capacities of Dunham Vacuum-Traps

Number	Size. in	Capacity, direct radiation, sq ft	Pipe- connec- tion, in	Weight, lb	Diameter of port, in	Lift, in
1	$\frac{1}{2}$	100	$\frac{1}{2}$	$1\frac{1}{2}$	.....	.....
2	$\frac{1}{2}$	350	$\frac{1}{2}$	$2\frac{1}{2}$	$\frac{3}{8}$	$\frac{1}{2}$
3	.....	450	$\frac{3}{4}$	.....	.....	.....
B.T.	$\frac{3}{4}$	1 500	$\frac{3}{4}$	13	$\frac{3}{4}$	$\frac{1}{2}$
B.T.	1	3 000	1	21	1	.....

These traps are designed for steam-pressures not in excess of 10-lb gauge. For use and riser-drips, use no smaller trap than the No. 3, and install trap as per details.

Care must be exercised in selecting a trap or traps of the proper size for hot-blast heating-coils. The capacity-ratings for all traps are in terms of direct cast-iron radiation, on a condensation-basis of approximately 0.25 lb per sq ft per hr. Every unit blast-coil must be reduced to that basis before trap-sizes are chosen and specified. (See Hot-Blast Heating for further details in reference to rating of vacuum-traps for hot blast coils.)

**Size of Vacuum-Pump Required.** The following table by the Warr Webster Co. may be used in determining the size of steam-driven vacuum-pump necessary. To determine the size of pump required the following empiric formula is used:

Square feet of direct radiation + (number of units  $\times$  100) =  $F$ . Choose the nearest size corresponding to the value of  $F$  given in the table. The steam cylinders are proportioned on a basis of 80-lb pressure and for lower pressure the steam-cylinder must be proportioned accordingly.

**Example.** Required the size of pump for 5 000 sq ft of direct radiation in 15 radiators.  $5\text{ }000 + (150 \times 100) = 20\text{ }000$ . Use a 5  $\times$  6  $\times$  10-in pump.

Table XXI. Sizes and Capacities of Vacuum-Pumps

Size	Steam, in	Exhaust, in	Suction, in	Dis- charge, in	$F$	Floor- space
4 $\times$ 5.....	$\frac{3}{8}$	.....	.....	.....	6 830	.....
4 $\times$ 4 $\times$ 6..	$\frac{3}{8}$	$\frac{1}{2}$	$2\frac{1}{2}$	2	7 270	11 $\times$ 34
4 $\times$ 4 $\times$ 8..	$\frac{3}{8}$	$\frac{1}{2}$	$2\frac{1}{2}$	2	8 000	11 $\times$ 34
5 $\times$ 5.....	.....	.....	.....	.....	10 680	.....
4 $\times$ 5 $\times$ 6..	$\frac{3}{4}$	$\frac{1}{2}$	3	$2\frac{1}{2}$	11 353	13 $\times$ 36
4 $\times$ 5 $\times$ 8..	$\frac{3}{8}$	$\frac{1}{2}$	3	$2\frac{1}{2}$	12 500	13 $\times$ 38
4 $\frac{1}{2}$ $\times$ 5 $\frac{1}{2}$ $\times$ 8..	$\frac{1}{2}$	$\frac{3}{4}$	3	.....	15 125	13 $\times$ 38
6 $\times$ 5.....	.....	.....	.....	.....	15 990	.....
6 $\times$ 7.....	.....	.....	.....	.....	17 215	.....
4 $\frac{1}{2}$ $\times$ 6 $\times$ 8..	$\frac{1}{2}$	$\frac{3}{4}$	3	$2\frac{1}{2}$	18 000	13 $\times$ 38
5 $\times$ 6 $\times$ 10..	$\frac{3}{4}$	1	4	3	19 390	18 $\times$ 50
7 $\times$ 7 $\frac{1}{4}$ $\times$ 10..	1	$1\frac{1}{4}$	5	5	28 256	18 $\times$ 52
6 $\times$ 7 $\frac{1}{2}$ $\times$ 12..	$\frac{3}{4}$	1	5	4	30 605	19 $\times$ 54
7 $\times$ 8 $\times$ 16..	1	$\frac{1}{4}$	5	4	34 470	18 $\times$ 52
6 $\times$ 8 $\times$ 12..	$\frac{3}{4}$	1	5	4	36 620	19 $\times$ 54

This table may also be employed in determining the size of motor-driven reciprocating vacuum-pumps, the last two figures under Size being the diameter

roke, respectively, of the pump. A vacuum-pump should be specified to displacement of at least from 10 to 15 times the volume of the condenser when operating at its normal rated speed.

**Table XXII. Capacity and Size of Steam-Driven Vacuum-Pumps**

Water-cylinder diameter, in	Stroke, in	Steam-pipe, in	Exhaust-pipe, in	Suction-pipe, in	Discharge-pipe, in	Draining capacity direct radiation,* sq ft	Draining capacity condensed steam, lb	Floor-space, in
2½	4	¾	½	1¼	1¼	2 700	810	30 × 6
4	6	½	¾	2	1½	7 000	2 100	40 × 10
6	10	1	1¼	4	3	16 000	4 800	59 × 14
10	12	1¼	2	6	5	40 800	12 240	72 × 20
12	12	1¼	2	8	7	62 000	18 600	72 × 20
14	12	1¼	2	10	8	85 000	25 500	....
16	18	1½	2	12	10	92 000	27 600	....
18	18	1¼	2	12	10	128 000	38 400	....

condensation figured at 0.3 lb per sq ft radiating-surface per hour.

vacuum-pumps with belted electric motors are made by the Bishop-Babcock Co., with capacities of 2 000, 5 000, 10 000, 17 000 and 25 000 sq ft of direct radiation. This pump should be under the control of a reliable VACUUM-PUMP GOVERNOR so that when the required vacuum has been produced the pump will stop.

### Design of Low-Pressure Steam-Heating Systems

**Amount of Radiation Required.** The heat-loss,  $H$ , of the various rooms is determined as previously indicated, and  $H$  is divided by 250. The result is the amount of direct radiation in square feet required. The heat-emission of cast-iron radiators for pressures up to 5 lb per sq in may be assumed as 250 Btu for square feet of radiation for purposes of calculation.

**Amount of Boiler Required.** If anthracite coal is to be used for fuel add not less than 50% to the total amount of direct radiation to be installed and 65% if bituminous coal is to be used, to allow for radiation-loss of boiler, mains, etc. The steam-mains and risers should always be covered.

**Design of Mains, Branches and Return-Pipes.** Steam-mains in low-pressure systems should be so proportioned that the loss in pressure, due to pipe-friction, does not exceed approximately 1 oz or 0.062 lb per sq in, per 100 ft of main. The reason for thus limiting the pressure-loss is apparent from an inspection of Fig. 31. Owing to the fact that the steam is losing pressure as it flows along the main, it follows that the pressure at the last riser will be lower than at the boiler. The difference in pressure, or pressure-loss,  $P$ , causes the water in the return-main to stand higher than the water-line of the boiler. The height  $Z$  is equal to the height of a column of water which pressure  $P$  will support. Thus, if the boiler-pressure is 2 lb per sq in and the pressure at the end of the main is, say 1½ lb, with water weighing 61 lb per cu ft, or 0.035 lb per sq in, the water in the return will stand  $(2 - 1.50) \div 0.035$ , or  $Z = 14$  in above the water-line of the boiler for a ½-lb loss in pressure between the boiler and the end of main. It is apparent in this instance that unless the water-line

of the boiler is about 18 in or more below the last riser, or radiator-connection water is quite likely to flood the steam-main and to be accompanied by a hammering and a poor circulation in the radiators located at or near the end of the run. Steam-mains are graded in the direction of flow approximately 1 in in 100




Fig. 31. Location of Boiler and Arrangement of Pipes for Low-pressure Steam-heating Systems

Referring to Fig. 31, and assuming a 7 ft-6 in, or 90 in, clear height of basement, and a boiler having a 72-in water-line and a length of steam-main of 100 ft, it is evident that the boiler must be located in a pit, the depth,  $X$ , of which

$$6 + 10 + 18 + 72 - 90 = 16 \text{ in}$$

in order to maintain 18 in between the water-line in the boiler and the end of the steam-main. The distance in practice should not be made less than from 18 to 24 in. The extreme pressure-load stated,  $\frac{1}{2}$  lb, in this illustration, is never approached in normal operation, when the mains are designed for 1-oz drop per 100 ft, but may approach the value stated when the system is being started up with cold radiators, when the rate of condensation is very much higher. The pressure-loss in a pipe flowing full of steam may be approximated by Babcock's formula

$$W = 87.5 \sqrt{\frac{y p d^5}{L \times \left(1 + \frac{3.6}{d}\right)}}$$

in which  $W$  is the weight of steam flowing per minute in pounds,  $L$  the length of pipe in feet,  $d$  the diameter of pipe in inches,  $y$  the density of the steam and  $p$  the loss in pressure in pounds per square inch.

One square foot of direct radiation will condense, under normal conditions of operation, 0.25 lb per hr, and the density of steam,  $y$ , is 0.043 lb for a 2.3-lb pressure. The sizes of steam-mains given in the tables were calculated by the above formula, the pressure-loss,  $p$ , being limited to 1 oz, or 0.062 lb per sq in per 100 ft of straight pipe. To allow for the fittings approximately twice this or  $\frac{1}{4}$  lb per sq in per 100 ft of pipe may be assumed. The pipe-sizes for the one-pipe system are given in Table XXIII, corresponding to the amounts of direct radiation stated in the last column. Branches and risers may be taken from Table XXIV, and reliefs for risers from Table XXV. For the two-pipe and also the one-pipe relief system the steam-main may be reduced in size as rapidly as the radiation carried will permit. The steam-main should not, however, be of any smaller size than risers called for in Table XXIV.

For one-pipe circuit systems, unless the steam-main is frequently dripped

THE MAIN MUST BE RUN FULL SIZE to the end, at which point an automatic air-valve should be installed and the main dripped into the return. This system is generally used for the heating of residences not exceeding two stories in height. For buildings two stories or more in height the one-pipe relief system




Fig. 32. One-pipe Relief System

Table XXIII. Pipe-Sizes for One-Pipe Low-Pressure Gravity Heating Systems. Main-Table

Steam-main, in	Dry return,* in	Radiation, sq ft
1	1	40
1 1/4	1	75
1 1/2	1 1/4	126
2	1 1/2	286
2 1/2	2	535
3	2 1/2	890
3 1/2	2 1/2	1 360
4	3	1 950
5	3	3 600
6	4	5 900
8	4	12 700
10	5	22 900
12	6	37 000

\* For wet returns reduce one size, with 1 1/4 in as a minimum size.

may be employed, in which case the risers supplying the radiation for the second floor and above are dripped into the return as shown in Fig. 32. The minimum size for a wet return should not be less than 1 1/4 in, as a smaller pipe is likely become plugged with an accumulation of dirt and scale.

Table XXIV. Pipe-Sizes for One-Pipe Low-Pressure Gravity Heating Systems—Branch and Riser-Table

Radiation, sq ft	Radiator-tapping, in	Branch-riser, radiator-arm, in
0 to 20	1	1
21 to 24	1	1 1/4
25 to 40	1 1/4	1 1/4
41 to 60	1 1/4	1 1/2
61 to 80	1 1/2	1 1/2
81 to 100	1 1/2	2
101 to 200	2	2 1/2
201 to 300		3

For risers carrying more radiation than given by the table, use the table for steam-mains and increase one size.

Table XXV. Pipe-Sizes for One-Pipe Low-Pressure Gravity Heating Systems—Reliefs for Risers (One-Pipe Relief System)

Riser, in.....	1	1 1/4	1 1/2	2	2 1/2	3	3 1/2	4	4 1/2	5
Relief, in.....	1/4	1	1	1 1/4	1 1/2	2	2	2 1/2	3	3


Table XXVI. Pipe-Sizes for Two-Pipe Gravity Systems

Diameter of supply, in	Diameter of dry return,* in	Direct radiation-surface supplied, sq ft
3/4	3/4	20
1	3/4	36
1 1/4	1	72
1 1/2	1 1/4	120
2	1 1/2	280
2 1/2	2	530
3	2 1/2	900
3 1/2	2 1/2	1 320
4	3	1 920
4 1/2	3	2 760
5	3 1/2	3 720
6	3 1/2	6 000
8	4	12 800
9	4 1/2	17 800
10	5	23 200
12	6	31 000

\* For wet returns, reduce one pipe-size, with 1 1/4 in as a minimum.



### Two-Pipe Low-Pressure Gravity Heating Systems.



### r-diagram for Down-feed Mechanical Vacuum System

**Pipe-Sizes for Two-Pipe Mechanical Vacuum Systems.** The size of branch-supplies to radiators, risers, steam-mains, radiator-returns with the mostatic valves and main-returns may be taken from Table XXVII. (See Example, Fig. 33.)

**Table XXVII. Two-Pipe Mechanical Vacuum Systems**


Size of pipe,  in	Rating direct radiation		Radiator-connections		
	Steam-mains and risers,  sq ft	Return-mains and return-risers,  sq ft	Size of radiator,  sq ft	Size of steam-connection,  in	Size of return-connection and valve  in
1/2	5	40	30	3/4	1/2
3/4	20	160	50	1	1/2
			75	1 1/4	1/2
			100	1 1/4	.....
1	40	320	125	1 1/2	1/2
			150	1 1/2	.....
1 1/4	75	600	200	2	1/2
1 1/2	150	1 200	300	2	3/4
2	300	2 400	.....	.....	.....
2 1/2	500	4 000	.....	.....	.....
3	900	7 200	.....	.....	.....
3 1/2	1 500	12 000	.....	.....	.....
4	2 000	16 000	.....	.....	.....
4 1/2	2 800	22 400	.....	.....	.....
5	3 600	28 800	.....	.....	.....
6	6 000	48 000	.....	.....	.....
8	13 000	72 000	.....	.....	.....
9	18 000	.....	.....	.....	.....
10	23 000	.....	.....	.....	.....
12	37 000	.....	.....	.....	.....
14	55 000	.....	.....	.....	.....

**Table XXVIII. Direct Radiation Required for the Factory Office-Building Shown in Figs. 9 and 34.**

Room-designation	Btu-loss per hr	Direct rad'n required, column 2 + 250	Radiation to be installed			
			No. radiators	No. cols. and height	No. sect's each radiator	Total, sq ft
I	2	3	4	5	6	7
Sample rm.....	54 900	219	4	3-32"	12	216
Hall.....	19 123	77	1	3-38"	15	75
Laboratory.....	27 358	95	2	3-32"	11	99
Storage.....	19 482	77	1	3-32"	17	76
Toilet.....	7 380	29	1	3-32"	7	31
Mgr's office.....	31 306	125	2	3-32"	14	126
Hall.....	19 224	78	1	3-38"	16	80
Gen'l office.....	70 247	281	4	3-32"	16	288
Sup't's office.....	31 306	125	2	3-32"	14	126
Totals.....	.....	.....	.....	.....	.....	1 108

**For Indirect Gravity Radiation.** Multiply square feet of a by 2 and use Table XXVI.

**One-Pipe Low-Pressure Gravity Heating System.** Direct it be required to design a heating system of this type



**Single-pipe Low-pressure Steam-heating System for Factory Office-building.**  
(See, also, Fig. 9.)

tory office-building shown in Figs. 9 and 34, the heat-losses being as calculated and given by Table VII. The location of the radiators is indicated on the floor-plans, Fig. 9.

**Direct Radiation Required.** The total Btu-loss for each room is repeated in column 2 of Table XXVIII. The amounts of radiation required for these losses is given in column 3 and were obtained by dividing the Btu-loss in each case by 250, the average heat-emission of direct radiation (Btu) per square foot per hour for a room-temperature of 70° and 2 lb steam-pressure.

**Boiler-Capacity Required.** The boiler-capacity must be such that it will carry the radiation installed plus the extra heat-loss from the steam-main, return-mains and boiler. The steam-mains are to be covered and anthracite fuel is to be used. The fuel-capacity of the fire-pot is to be sufficient for an 8-hr firing-period. Adding 50% to the sq ft of radiation installed,  $1.5 \times 1,108 = 1,662$  sq ft, the boiler-rating required. The fuel-holding capacity of the fire-pot should be checked for the boiler proposed as previously stated under Boilers.

**Chimney-Size.** The size of chimney may be taken from Table XVII, and in this case, is 12 × 12-in inside dimensions, by a 40-ft height. The nearest size for flue-lining, Table XVI, is 13 × 18 in.

**Design of Piping System.** The layout of the basement-mains and risers for a ONE-PIPE CIRCUIT SYSTEM is given in Fig. 34. The risers are not dripped in this case. Steam-main A supplies 623 sq ft of radiation, and, according to Table XXIII must be 3 in in diameter. The diameter must be carried to the end where it is dipped into the return-main by a 1 1/2-in relief, as indicated in Table XXIII, for a dry return-pipe. In order to keep the steam-main as close to basement-ceiling as possible, where it passes beneath the floor-girder, a riser is made, and consequently a 1 1/4-in drip must be provided to take care of 13 sq ft of radiation. The main wet return takes care of 1,108 sq ft of radiation and is therefore made 2-in diameter. The risers and branches are proportioned by Table XXIV.

Gravity Indirect Heating

**General Description.** A satisfactory means of providing for the heat-loss in a room, and, at the same time, supplying air-ventilation, is accomplished by this system. The radiators properly encased with a sheet-metal casing, covered

**Table XXIX. Final Temperature of Air Passing Over Indirect Radiation. Extended-Surface Type. Initial Temperature of Air, 60° F. Heater, On Stack in Depth. Four-Inch Spacing of Sections**

Velocity of air through free area of heater, in ft per min, v*	Final temperature, t <sub>2</sub> , in degrees Fahrenheit	
	Steam at 2-lb pressure	Hot water, 180° F.
50	122	147
100	100	127
125	95	120
150	90	113
175	86	106
200	82	102

\* Measured at 70° F. For first-floor registers a velocity of 150 ft per min through free area and 150 ft per min for second-floor registers is the usual assumption.

on, are ordinarily hung from the basement-ceiling by means of strap-iron, as shown in Fig. 35. Each radiator is ordinarily

FIG. 35. INDIRECT RADIATOR WITH G.I. CASING AND DUCTS



35. Indirect Radiators, Casings, Connections, etc.

sh-air inlet and hot-air duct connecting the radiator with the recirculating duct may be provided, as indicated, in order to heating in ex-  
er if desired.

separate ver-

each register

nnected with

diator. At-

y more than

an indirect

ally success-

ed, unless a

ried to give

as with the

described

ducts for

best results,

pe as later

ice-heating.

is designed

num of heating-surface to the air passing over same.

standard types for gravity indirect heating may be men-

Pin Radiator (Fig. 36), Excelsior, Sterling and Vento.

e now rated according to the temperature-increment, or

Fig. 36. School Pin Indirect Radiator for Steam or Water

rise, which they are capable of giving to the air passing between and over the sections of the heater for various velocities of air, initial temperature, and temperature or pressure of the steam, or temperature of the hot water. The velocities stated are, for convenience in rating, based on air at 70°. The free or unobstructed area means the net area between heater-sections after deducting the area of the projecting surfaces from the gross area. Limitations of space prevent giving more than these data for one type of indirect radiator.



Fig. 37. Vento Thirty-inch Indirect Heater-section

Tables XXIX and XXX give the results of tests made on Vento, indirect radiation, American Radiator Company. (See Fig. 37.)

Table XXX. Dimensions, etc., Vento Indirect Radiation

Size	Heating-surface, s. sq ft	Height, in	Width, in	Free area between sections, (s) sq ft
30-in section . . . .	8.00	29 <sup>7</sup> / <sub>8</sub>	9 <sup>1</sup> / <sub>2</sub>	0.256
40-in section . . . .	10.75	41 <sup>1</sup> / <sub>8</sub>	9 <sup>1</sup> / <sub>2</sub>	0.35
50-in section . . . . .	13.50	50 <sup>3</sup> / <sub>8</sub>	9 <sup>1</sup> / <sub>2</sub>	0.423
60-in section . . . .	16.00	60 <sup>1</sup> / <sub>2</sub>	9 <sup>1</sup> / <sub>2</sub>	0.511

Spacing of sections, 4 in on centers for gravity air-circulation.

Weight of Air to be Circulated per Minute,  $W$ .  $t_1$  = temperature of air leaving register.  $t$  = temperature of room. 0.24 = sp heat of air.  $H$  = heat loss of room to be warmed in Btu per hour.  $V$  = volume of air in cubic ft per minute measured at 70°.

Then

$$W = H / [60 \times 0.24(t_1 - t)], \text{ lb of air per min}$$

$$V = W / (0.075 = \text{the density of the air at } 70^\circ)$$

**Example of Indirect Heating-Surface Required,  $S$ .**  $t_0$  = initial temperature of entering indirect heater.  $t_2$  = final temperature air leaving heater =  $t_1 + 5^\circ$  (estimated temperature-loss in hot-air duct).  $V$  = velocity through free area of duct in feet per minute, measured at a temperature of  $70^\circ$ .  $F$  = total fire-surface required in heater, in square feet.  $a$  = free area for one section of heater in square feet.  $n$  = number of sections required.

$$F = V/v = W/0.75v, n = F/a \text{ and } S = n \times s$$

**Example.** Required the amount of indirect low-pressure steam-surface of extended-surface type, the number and size of sections, and the over-all dimensions of an indirect radiator to supply the necessary heat to warm a poor room, the heat-loss of which is  $H = 20\,000$  Btu per hour. All the air is taken from the outside, the temperature of which is  $t_0 = 0^\circ$  F. The temperature to be maintained is  $t = 70^\circ$  F.

**Solution.** It is first necessary to assume a temperature,  $t_1$ , for the air entering room, in order to calculate the amount or weight,  $W$ , of air required to be heated to convey the heat required to make up the heat-loss  $H$ .

Assume  $t_1 = 95^\circ$  and  $t_2 = t_1 + 5$  (loss) =  $100^\circ$ ; and  $v = 100$  ft per min. (Table XXIX).

$$W = 20\,000/[60 \times 0.24(100 - 70)] = 46.3 \text{ lb per min}$$

$$V = 46.3/0.75 = 617 \text{ cu ft per min, measured at } 70^\circ \text{ F.}$$

Assume 40 in as the length of section desired in this installation,

$$a = 0.35 \text{ (Table XXX);}$$

$$F = 617/100 = 6.17, \text{ the total square feet of free area required;}$$

$$n = 6.17/0.35 = 18, \text{ the number of sections of 40 in.}$$

Thus is, therefore, required, giving a total heating-surface of

$$S = 10.75 \times 18 = 193.5 \text{ sq ft}$$

Dividing this equally between two indirect radiators the width of each heater is 10.75 in. Dividing by 3 (spacing-sections) = 36 in.

**Pressure Boiler-Rating Required for Gravity Indirect Radiation.** Amount of heat given up to the radiator is

$$h = 0.24W(t_2 - t_0) \times 60 \text{ Btu per hr}$$

The equivalent rating in square feet of direct radiation is therefore  $R = h/250$  plus 25% for radiation of mains, returns, etc.

**Example.** Required the equivalent low-pressure boiler-rating to supply the radiation in preceding example.

**Solution.**

$$h = 0.24 \times 46.3 (100 - 0) \times 60 = 66\,672 \text{ Btu per hr}$$

$$R = (66\,672/250) \times 1.5 = 399 \text{ sq ft}$$

In other words, 1 sq ft of low-pressure steam indirect radiator with gravity-circulation is practically equivalent to 2 sq ft of direct radiation; or the amount of indirect surface is approximately 0.4 of the amount of direct radiation.

**Hot-Air Ducts for Gravity-Circulation.** A velocity of approximately one third of the theoretical velocity attainable by natural draft, due to

the smaller density of the heated air, is assumed in practice in proportion to the area of the hot-air ducts.

**Table XXXI. Theoretical Velocity ( $V$ ) of Air, in Feet per Second, Due to Natural Draft**

Height of flue in feet, $E$	Excess of temperature in flue above external air							
	10°	15°	20°	25°	30°	50°	100°	150°
1	1.1	1.4	1.6	1.8	2.0	2.5	3.6	4.4
5	2.5	3.1	3.6	4.0	4.5	5.6	8.1	9.9
10	3.6	4.4	5.1	5.7	6.6	8.1	11.4	14.0
15	4.4	5.4	6.3	7.0	7.7	9.9	14.0	17.1
20	5.1	6.3	7.2	8.1	8.8	11.4	16.1	19.8
25	5.7	7.1	8.1	9.0	9.9	12.8	18.0	22.1
30	6.3	7.8	8.8	9.9	10.8	14.0	19.8	24.2
35	6.8	8.4	9.5	10.7	11.7	15.1	22.3	26.1
40	7.3	8.9	10.2	11.4	12.5	16.1	22.8	27.9

**Example.** Required the size of hot-air duct for each of the indirect radiators in the preceding examples for a first-floor installation, the effective height  $E$  being 5 ft.

**Solution.** The excess of temperature in the flue above the external air  $100 - 0 = 100^\circ$ . The theoretical velocity in the duct, from Table XXXI,  $8.1 \times 60 = 486$  ft per min. The actual velocity is approximately one third of this, or 162 ft per min. The weight of air per minute passing through the flue is 23 lb, or

$$23 / [0.071(\text{density at } 100^\circ)] = 324 \text{ cu ft}$$

The required area of the flue is therefore

$$324 / 162 = 2 \text{ sq ft} = 288 \text{ sq in}$$

The gross area of the register-face must be approximately 1.8 this amount, or 518 sq in, to obtain the same free area through the register-grill as exists in the flue or duct. Sizes of standard registers are given in the section on Furnace-Heating.

### Direct Hot-Water Heating

**Systems in Use.** Systems for heating with direct hot-water radiators, like the direct steam heating systems, may be divided into two general classes, the first of which includes all those systems OPERATING BY GRAVITY ONLY, depending on the difference in density of the water-columns in the flow and return-lines to cause circulation. The second class includes those systems in which a FORCED CIRCULATION is maintained by means of a pump placed on the return-line just before it enters the boiler or heater. These latter systems are employed usually only in large installations or in district-heating service.

**Gravity Hot-Water Heating Systems.** The gravity systems are divided into the UPFEED SYSTEMS, using basement-mains, and the DOWNFEED SYSTEMS using overhead or attic-mains. The upfeed systems may have either a one-pipe basement-main or two-pipe basement-mains, and the latter type may have either a DIRECT or a REVERSED return-main. (See Figs 38 and 39 for reversed



feed systems may have either SINGLE OR DOUBLE RISERS. They may be operated with an OPEN OR CLOSED EXPANSION-TANK, as shown in Figs. 43 to 46. In general, the downfeed or overhead systems are better than the use of smaller mains and risers, and provide for the escape of air from the radiators and piping. It is necessary, however, that some clear space in the attic should be at least 4 or 5 ft if the overhead mains and branches are to be properly installed. It is sometimes necessary to run overhead mains at the ceiling of the top floor, and in such cases the same restriction does not apply. Mains run in attics must be protected against freezing. The underfeed systems are used where

#### BASEMENT HEATING PLAN

##### Fig. 41. Hot-water Heating. Two-pipe Up-feed System

Underfeed systems are available, and of little or no value, and the radiation is not so effective on the upper floors; or where attic-space is so limited that it would be necessary to install all overhead mains and branches. Underfeed systems are not satisfactory in buildings less than two stories in height, as the radiation from radiators on the first floor only is so slight that faulty or no circulation is quite likely to result.

**Up-feed System.** The upfeed one-pipe system is in very common use. It is employed almost exclusively by the United States Army and Navy Departments whenever upfeed hot-water systems are to be installed. As shown in Figs. 43 and 45, the supply-main rises vertically from the boiler just above the boiler and grades down in the direction of the radiators at a grade of  $\frac{1}{4}$  in in 10 ft. Branches are taken from the supply-main and the return-branches are made into

the side or bottom. (Fig. 40.) Flow-connections should always be made from the top, or at an angle of 45° in the case of branches near the boiler, or for branch

HOT-WATER HEATING - EXPANSION TANKS  
(OPEN AND CLOSED SYSTEMS)




Table  
Expansion-Tanks

No.	Size in Inches	Capa- city Gal.	Sq. ft Bot- tom
0	10 x 20	8	20
1	12 x 20	10	30
2	12 x 30	15	40
3	14 x 30	20	50
4	16 x 30	25	60
5	16 x 36	32	70
6	16 x 48	42	80
7	18 x 60	66	100
8	20 x 60	82	120
9	22 x 60	100	140

Note.- Galvanized Steel, Tests  
at 100 lb. Tapped 1 1/2 inch Top and  
Bottom, and for Gauge-  
Glass






Fig. 43  
ONE-PIPE UNDERFEED  
SYSTEM, OPEN TANK  
For Piping-Sizes See  
Tables XXXII and XXXIII



Figs. 42, 43, 44, 45 and 46. Hot-water Heating. Expansion-tanks. One-pipe Underfeed System

supplying only upper-floor radiators. It will be seen that in the case of branch supplying radiators on all floors the upper-floor radiators may be made to re

culation of the first-floor radiators by taking the basement-riser from the side of the branch running to the latter radiator. This is usually run full size all the way to favor the lowest in Fig. 45. After having served all the radiator-branches and returns to the boiler, continuing the same size for the connections (Fig. 43) to radiators should be made at the TOP using a union elbow, and at the BOTTOM on the return-end, using hot-water radiator-valve with union connection. By only one valve is required to control the radiator. Since the water in the one-pipe main gradually drops, due to the return temperature from the radiators served in the course of the building, it is advisable to increase the last radiators on the 6 in area and to increase the size of branch and riser-connection the main by a one-pipe size. Pipe-sizes may be taken from XXXIII. In using the tables all mains must be measured and risers to any floor are proportioned to supply all the at floor as well as the radiator actually installed on that Figs. 43 and 45.

#### Water Heating. Piping-Sizes. Open-Tank (Upfeed with Basement-Mains)

Mains up to 100 ft

Pipe-size in inches	Direct radiation in square feet	Indirect radiation in square feet
1 ¼	135	100
1 ½	220	135
2	350	225
2 ½	460	320
3	675	500
3 ½	850	650
4	1 100	850
4 ½	1 350	1 050
5	1 700	1 350
6	3 600	2 900
7	4 800	3 900
8	6 200	5 000
9	7 700	6 300
10	9 800	7 900
12	14 000	11 400

compiled by J. J. Hogan, and is to be used for either one or two-

th of main must be measured back to boiler.

over 100 ft, reduce capacity in the ratio of  $\sqrt{\frac{100}{L}}$ .

**Pipe System.** The upfeed two-pipe system is also in if installed with a REVERSED RETURN, as shown in Figs. and results. If a DIRECT RETURN is used so that the water in the radiators nearest the boiler, and then through each return, the ends of mains will be slow in warming up, the last, and the system prove unsatisfactory. With the RE-

**Table XXXIII. Hot-Water Heating. Piping-Sizes. Open-Tank (Upfeed and Downfeed Systems). Basement-Mains)**  
Branches and Risers

Pipe-size in inches	Floor			
	First	Second	Third	Fourth
	Direct radiation in square feet			
$\frac{3}{4}$	30	45	55	70
1	60	75	85	95
$1\frac{1}{4}$	110	120	135	150
$1\frac{1}{2}$	180	195	210	230
2	290	320	350	370
$2\frac{1}{2}$	400	490	525	550
3	620	650	690	730
$3\frac{1}{2}$	820	870	920	970
4	1 050	1 120	1 185	1 250
$4\frac{1}{2}$	1 325	1 400	1 485	1 560

Table XXXIII was compiled by J. J. Hogan, and is to be used for either one or two pipe work.

**VERSED-RETURN SYSTEM** each group of radiators has exactly the same length of water-travel, and hence the resistance to be overcome is practically the same, irrespective of the distance of the radiator-group from the boiler. It will be noted that the return begins at the first radiator served and flows in the same DIRECTION as the flow-main, increasing in size while the latter decreases. The flow-main grades UP uniformly  $\frac{1}{4}$  in in 10 ft, and the return grades DOWN toward the boiler with the same pitch. Pipe-sizes may be taken from Tables XXXII and XXXIII as in one-pipe work, and the main-size reduced or increased rapidly as the change in radiation supplied will permit. It is also customary in government work to install a STARTING-PIPE (Fig. 38), between the main and return at the boiler, in underfeed systems. This pipe ranges from  $1\frac{1}{4}$  to  $2\frac{1}{2}$  in in size, depending upon the capacity of the boiler, and is intended to assist in the establishment of an initial circulation between flow and return-heads even before the water in the mains is moving.

**Equalization-Table.** In Federal-building work N. S. Thompson makes use of the following Equalization-Table in proportioning mains and risers serving more than one radiator in both upfeed and downfeed systems. The equalizing-numbers represent the relative capacities of the different sizes of pipes.

**Table XXXIV. Equalization-Table for Mains and Risers**

in	in	in	in	in
$\frac{1}{2}$ = 2	$\frac{3}{4}$ = 5	1 = 10	$1\frac{1}{4}$ = 20	$1\frac{1}{2}$ = 30
2 = 60	$2\frac{1}{2}$ = 110	3 = 175	$3\frac{1}{2}$ = 260	4 = 360
5 = 650	6 = 1 050	7 = 1 600	8 = 2 250	.....

**Example.** A  $1\frac{1}{4}$ -in,  $1\frac{1}{2}$ -in and 2-in pipe have a total value of 110 units, and are equivalent in carrying capacity to a  $2\frac{1}{2}$ -in main.

me friction-pressure loss per 100 ft of run, and are proportional to the  $5/2$  powers of the diameters. Thus the weight of water flowing varies as shown by relation,  $W = Kd^{5/2}$ , in which  $W$  = weight,  $K$  = a constant, and  $d$  = pipe diameter.

**Details of Piping Systems and Connections for Direct Hot-Water Heating.** The distinctive piping-details of each system of hot-water heating have been discussed under that system, as described in the preceding paragraphs. In general all main piping and branches must be UNIFORMLY GRADED, readily indicated, and ample provision made for EXPANSION and CONTRACTION, and ready REMOVAL OF AIR from all parts of the system. Air-traps or pockets in a hot-water system are fully as serious as water-pockets in a steam system. In a hot-water main grading down in the direction of flow cannot be relayed unless an air-outlet is provided at the top of the relay. If the main is reduced in size at any point an ECCENTRIC FITTING must be used to keep the TOP of the main and small main in the same plane and avoid an air-pocket. Not only must all the piping be designed to permit the removal of air, but FREE AND COMPLETION DRAINAGE of water must be provided for as well, so that when the drain-off cock is opened at the boiler the entire system can be emptied of water. Branch-mains are taken from a HEADER at the boiler they must all rise to the same ELEVATION so that the tops of all the branches will lie in the same plane and start away from the boiler. The fittings on all main piping and branches must be of the long-sweep pattern, and all pipe should be carefully reamed to remove burrs and sharp edges. Where the same riser supplies radiators on two floors the branches to the radiators on the intermediate floors may be made with special tees (Fig. 41) known as O. S. FITTINGS, with a deflector designed to divert the current of flow into the outlet of the tee, and thus favor radiators on the intermediate or lower floors. By using TOP-FLOW and RETURN CONNECTIONS at each radiator it is possible to positively control flow by a single valve, except for the slight circulation intended to prevent freezing which takes place through the  $1/8$ -in-diameter hole drilled in the valve-levee, when the valve is closed. If both connections are made at the top of the radiators, and only one valve is used, it is entirely possible that the radiator may still be supplied with hot water through the unvalved connection when the valve is closed.

**Removal of Air in Hot-Water Systems.** Suitable provision must be made for removal of air from all hot-water radiators, wherever an upfeed system is used.

Usually small air-cocks are attached to the highest point of each radiator and are periodically opened to relieve any accumulation of air. If these cocks are forgotten a radiator may become air-bound and fail to heat on account of faulty circulation; hence automatic air-valves are sometimes installed for this purpose. The automatic air-valve for hot-water radiators is not very generally used, due to its liability to pass water as well as air; but a standard design by the Monash-Younger Company, may be mentioned.

**Expansion-Tanks for Hot-Water Heating. Open-Tank Systems.** The open-tank system of hot-water heating is not a closed system, as provision is made for expansion and contraction of the water within the system. An expansion tank is provided at a suitable elevation, not less than 3 ft above the highest radiator, and connection made to the nearest return-riser; or preferably the expansion-line is run to the flow or return-main in the basement. The capacity of THE EXPANSION-TANK varies with the amount of water in the system, and with the range in temperature of same, and its capacity is determined

increase in volume of a given weight of water heated from  $32^{\circ}$  to  $212^{\circ}$  is

about  $\frac{1}{2}\%$ , or approximately 4.33%; so that for every 23 gal in the system  $32^\circ$ , an allowance of 1 gal must be made in the expansion-tank when the water in the system is raised to  $212^\circ$ . Cast-iron radiators have an internal volume  $1\frac{1}{2}$  pints per sq ft, while steel radiators and 1-in pipe hold about 1 pint per sq ft. Assuming the internal volume of the radiators to be about 50% of the entire system, we have for 3 000 sq ft of actual radiation,  $3000 \times 2 \times \frac{1}{2}$  gal = 3 000 gal of water. This water will increase  $\frac{1}{2}\% \times 750 = 33$  gal on being heated from  $32^\circ$  to  $212^\circ$ . Hence an expansion-tank of  $2 \times 33 = 66$ -gal capacity is necessary, the tank being made double the theoretical volume for practical considerations.

A list of expansion-tank capacities and dimensions is given in a table (included with Figs. 42 to 46), from which a commercial tank may be readily selected for systems under 6 000 sq ft. For larger systems the size of tank should be separately determined and the nearest commercial tank-size, as taken from the manufacturer's list, should be specified. These tanks should have 1-in or  $1\frac{1}{4}$ -in top and bottom tapplings with  $\frac{1}{2}$ -in water-gauge tapplings, for connecting a gauge-glass, at least 12-in long, on the side of the tank as shown in Fig. 43. The tank must be securely supported well above the highest radiator in the system, and in the larger installations special framing must often be designed to carry the weight of tank and water. Automatic expansion-tanks equipped with a ball-cock and overflow are sometimes installed, and the altitude-gauge on boiler, and the gauge-glass and fittings on tank omitted. These tanks may be covered with hardwood and varnished if it is necessary to place them in a finished room or apartment.

**Expansion-Tank Connections.** The most approved method of connecting an expansion-tank to a low-pressure one-pipe system is shown in Fig. 43, where an expansion-and-vent line is run from the top of the main, at the high point just above the boiler, and connected to a return-bend just beneath the tank. A return circulating-line is taken from the other side of this bend and connected with the return-main at the boiler. The circulation of water in this loop will prevent freezing at the tank. From the top of the tank a  $1\frac{1}{4}$ -in vent-line is taken through the roof, and a  $1\frac{1}{4}$ -in overflow is taken out of this vent-line at a tee just above the tank. This overflow should discharge into an open sink or drain near the boiler so that it will be immediately evident to a person in the boiler-room, filling the system, just when the water has risen to the overflow above the tank. The movable hand on the boiler altitude-gauge can then be set to correspond with the middle of the gauge-glass, and the water-level brought to this point with the system cold. No valves should ever be installed on either the expansion or the overflow-lines, and in case the system is valved at the boiler the expansion-line must be connected on the boiler-side of this valve; and when two boilers are installed this line must be carried to a point above the water-line in the expansion-tank to prevent siphoning the water out of the entire system in case it is necessary to drain only one boiler. Expansion or vent-tank connections must always be so made to main-piping in basement so that all air will be automatically removed from high points. Wherever possible riser-branches to risers may be used for relieving any accumulation of air in the main piping. In SMALL INSTALLATIONS the expansion-line may be connected to the return-riser of one of the highest radiators, and no overflow other than the tank need be provided for, as shown in Fig. 46. This is a cheap method, and should not be resorted to unless extreme economy must be practised. The tank should be in the same room with the radiator to prevent freezing, as no circulation is provided for; and the overflow is simply discharged out of doors and up through the roof. The usual result is that an unsightly appearance is soon created.

The United States Treasury Department employs a special vent and over-

) in cold climates, where there is liability of the vent-line freezing rough the roof, due to the condensation and freezing of vapor in this line. The vent-line is made only 2 ft high above the point within the building, and it is equipped with a check-valve to prevent the flow of water through the same in case the tank should suddenly close. The closing of the check-valve will compel the excess water to flow, and prevent the flooding of the building.

**Systems.** The PERMISSIBLE TEMPERATURES in any hot-water system are determined by the pressure on the system, which latter factor determines the temperature at which boiling will take place. The pressure at any elevation in an open system will vary directly with the distance below the level of the expansion-tank, and hence it will be possible theoretically to determine the temperature at the boiler at a temperature corresponding to the hydrostatic pressure before boiling would occur. The relation between hydrostatic pressure and boiling-point are given in the following table:

Relation between Hydrostatic Head, Pressure and Boiling-Point

0	12	24	37	49	61	74	87	100	113	125
0	5	10	15	20	25	30	35	40	45	50
212	227	239	250	259	268	274	281	287	292	298

It will be quite impossible to carry temperatures in excess of 212° in an open-tank system, as the high-temperature water would immediately open the tank and boil. In order to overcome the limitations of an open-tank system, in which water will always boil as soon as a temperature is reached, various means of increasing the pressure in these systems have been resorted to in the attempt to carry a higher water-temperature. In very cold weather than would be possible with an open-tank system, devices have usually been installed on the expansion-line, or else just below the expansion-tank and the static head is increased by putting a column of mercury in the path of the expanding water, thus forming the expansion-tank.

The apparatus, known as the HONEYWELL HEAT-GENERATOR No. 44, in which it is seen that water entering the generator forces the mercury up the inner tube A until a head of 20 in is reached, at which time the entrance to this tube will be uncovered and water or air may enter it and pass to the expansion-tank. The head above that required to just fill tube A is returned by tube B to the base. When the system cools off water can flow back to the boiler as the mercury-column drops in it, and the slight head of water at the outlet of this tube is easily overcome by the head of water in the expansion-tank above this point. This increase of 10 lb in static head is sufficient to carry a maximum water-temperature of 240°, which would be impossible in an open-tank system. While a static head of 24 ft, this could theoretically be carried AT THE BOILER in an open-tank system, just as soon as this water rose in the expansion-tank and escape from the expansion-tank, at the same time it would carry off water. In fact with the open-tank system the water at the boiler would be at a temperature of 212° F. The use of pressure-generated head makes it possible to use smaller radiators in the

heated rooms, as it is entirely possible to maintain steam-temperatures in radiators whenever desired. Since higher temperatures are used, the difference between flow and return-riser temperatures becomes greater than in the open-tank system, and hence a greater motive head exists and smaller mains and risers may be used with this system. The HONEYWELL COMPANY recommends the following schedule of radiator-tappings:

**Table XXXVI. Riser-Sizes for Honeywell System**

Pipe-size in inches	Capacity in square feet of hot-water radiation		
	1st floor	2nd floor	3rd floor
$\frac{1}{2}$	30	40	50
$\frac{3}{4}$	75	100	125
1	75 up	100 up	125 up

It should be remembered that since radiators and pipes are smaller in this system there is much less water than in the open-tank system, making it more sensitive in warming up and also in cooling off. The GENERATOR should not be placed close under the expansion-tank. Otherwise than this its location may be anywhere in the expansion-line, as the same hydrostatic head is always added in addition to the head of mercury-column.

### Furnace-Heating

**The Furnace and Its Location.** The method of warming or heating a building by what is generally known as a warm-air furnace is termed FURNACE HEATING. The furnace consists briefly of a cast-iron or steel heater, containing a COMBUSTION-CHAMBER, FIRE-POT and GRATE. The heater is usually set in a brick or concrete foundation and is encased by a double-wall galvanized sheet steel JACKET (Fig. 47), although brick is sometimes used instead of the steel jacket for this purpose. Furnaces burning soft coal are usually designed with a secondary air-supply or OVERDRAFT admitting heated air just at the surface of the fire in order to produce a more perfect combustion of the volatile combustible gases which are liberated from this fuel immediately after firing. This overdraft should be under positive control so that it may be checked or closed after the fuel has been coked. Soft coal may also be burned efficiently in the underfeed-type of furnace in which coal is fed from below by means of a plunger operating in a feed-chute discharging through the center of the grate. The furnace should be located in the basement in an approximately central position with reference to the rooms to be heated, preferably toward the side or sides from which the prevailing winds blow in winter-time. This arrangement not only favors the more exposed rooms on the upper floors above by shortening the leaders to these rooms, but also makes it possible to reduce the length of the cold-air duct, which should always be run from the exposed side of the building to the cold-air pit below the furnace. (Figs. 53 and 54.) In operation cold air is drawn from the outside through the cold-air duct, passed through the space between the heater and its jacket, and warms by coming in contact with the outside heated surface of the combustion-chamber and the radiator, which is usually just above the combustion-chamber.




discharged through flues connected at the top of the JACKET, FURNACE-CALAMINET to the rooms to be warmed.



Fig. 17. Warm-air Furnace with Galvanized Sheet Steel Jacket

lers and Stacks. These connecting flues are made up of two sections, nearly horizontal round pipes in the basement, known as LEADERS (Figs. 49), which connect to the COLLARS on the top or conical sides of the



Warm-air Furnace-leaders with Elbows




Fig. 49. Warm-air Furnace-leaders without Elbows

and (2) the vertical rectangular pipes called STACKS (Fig. 50), which rise from the outer end of the leader, with the double-walled REGISTER-GRILLE (Fig. 51) into which the REGISTER-GRILLE covering the opening into the room. The leaders should have an upward pitch toward the base of the

stack of at least 1 in per foot, and for the best results they should not be less than from 12 to 15 ft in length. The boots are made in a great variety of shapes to suit actual conditions, and are simply ADAPTERS for the purpose of changing

from round leaders to rectangular stacks. The stacks are usually run between the studding of interior wall partitions (Figs. 50 and 51) since if they are placed outside walls the cooling effect reduces their efficiency not only in temperature of the gas but also in velocity of flow. The METAL used for leaders and stacks is usually bright tin, although for leaders larger than 12 in, galvanized steel of No. 26 United States Standard gauge is more commonly employed. The covering of all leaders, boots and stacks as well as the furnace itself is most important, and either a heavy grade of asbestos paper is pasted on the outside, as in the case of leaders and the furnace itself, asbestos air-cell covering, about 1/2 in thick may be used and secured with brass bands or wire. Since the stacks must fit generally, in a 4-in studding space, with a net depth about 3 3/4 in, every effort must be made to keep them as deep as possible; and if lathing or expanded metal should be used in front of such stacks, which ordinarily

Fig. 50. Vertical Stack with Side-wall Register

have only a single layer of asbestos-paper covering. A more effective insulation may be provided by using a DOUBLE-WALL STACK, in which there is an air-space between the inside and outside pipes, and no asbestos covering is used. See Table XLII for this equipment, as made by the Excelsior Steel Furnace Company. Attention of the architect is here called to the fact that in the case of large second-floor rooms to be warmed by one register, 6-in stud partitions are generally required for the first floor.

### The Design of a Furnace Heating System.

**Heat-Loss and Air Required.** The determination of the size of the furnace and the connecting leaders, stacks, registers, ducts, etc., is based on: (1) the actual heat-loss from each room in the building, including wall and glass-transmission losses, as well as loss due to infiltration; and (2) the amount of air circulated per hour, which in turn is based on this heat-loss. A building

by hot air by introducing the air into the rooms at a higher temperature than that required to be maintained in the rooms at the breathing-point (usually 70° F.) The air in cooling gives up per pound, 0.24 Btu at constant pressure. For each degree of temperature difference necessary to maintain the room temperature, 0.24 Btu is necessary to maintain the room temperature. This is the heat loss due to the furnace-cap or bonnet. The air in cooling gives up per pound, 0.24 Btu at constant pressure. For each degree of temperature difference necessary to maintain the room temperature, 0.24 Btu is necessary to maintain the room temperature. This is the heat loss due to the furnace-cap or bonnet.

Fig. 51. Vertical Stack and Register-box

These are the conditions under which the air is heated. If the air is all drawn from the outside, and the outside temperature is 0°, then the air is heated from 0° to 190°, and the room, from 175° to 70°, or 105°. In other words, 0.24 Btu is apparently thrown away, for every pound of air circulated. The air brought in from the outside in order to supply a sufficient amount, then this is the price which must be paid for ventilation, the same, no matter what system of heating is employed, for ventilation. It is almost invariably the case, however, that a considerable amount of the air may, if desired, be recirculated, in which event, for example, the furnace system of heating requires no more expenditure of fuel burned than a direct steam or hot-water system, as economical to operate when correctly designed, installed and maintained. The head producing the flow or circulation is due to the difference in the ascending column of heated air and the weight of an equal column of the colder intake air. The system may be proportioned to meet the requirements of the air during the extreme cold weather.

**to be Circulated per Hour.** It is first necessary to determine the amount of air required per hour which must be supplied to each room.

- 1. Volume of air to be circulated per hour;
  - 2. Temperature to be maintained;
  - 3. Temperature of air leaving the registers (assumed 15° lower than the temperature leaving the furnace-cap or bonnet),
  - 4. Amount of air to be supplied to room per hour as determined by heat-loss calculations;
  - 5. Heat given up per pound of air circulated.
- $Q = V(t_2 - t_1)$ .  
 where  $t_2$  is 175° F., and  $t_1 = 70°$  F.

of air, entering at temperature 175° = 0.063;  
 weight of warm air entering room per hour  
 =  $H/1.58$ .

**Heat Required from Heater per Hour, Based on Recirculation.** The heat required per hour from the heater will depend on the temperature of the entering air and will be a maximum when all the air circulated is taken from the outside and a minimum when all of the air is recirculated.

Let  $h$  = Btu required from heater per hour;  
 $t_e$  = temperature of air entering heater =  $65^\circ$ ;  
 $t_h$  = temperature of air leaving heater =  $190^\circ$ .

Then  $h = 0.24 W(t_h - t_e)$ .

Substituting the values given above for  $W$ ,  $t_h$ , and  $t_e$ ,

$$h = 1.2 H.$$

**Size of Furnace.** The capacity of a furnace for heating air depends primarily upon the amount of coal that may be burned per hour, which is the product of the RATE OF COMBUSTION by the grate-area. With an assumed or fixed rate of combustion, the capacity of the furnace is dependent upon the grate-area. The grate-area is therefore used as a basis for the rating and comparison of warm-air furnaces. The average rate of combustion usual in furnace-heating ranges from 3 to 4 lb per sq ft of grate-surface per hour, but in zero weather this may run as high as 6 lb, and is readily obtainable with the ordinary height residence-chimney; that is, at least 35 ft. A properly designed furnace will have a combined furnace and grate-efficiency of from 55 to 60%. Higher efficiencies have been obtained in tests.

**Commercial Ratings of Furnaces.** Manufacturers rate their furnaces according to the amount of space, cubical contents, in the ordinary residence construction they will heat to  $70^\circ$  F. in zero weather. Maximum temperature of air leaving registers =  $175^\circ$  F. The detailed dimension and capacity data other than grate-area and space heated, of most furnaces are seldom published by the manufacturer, although there are a few notable exceptions. The actual size of the furnace naturally depends upon the heat-transmission of the walls, floors and roofs, plus the infiltration-losses, as already explained. The claim, however, is made that these "in turn bear a reasonably uniform relation to the cubical contents of the ordinary house," with the usual proportions and ratio of wall to glass-surface, and that therefore the rating, as given, is justifiable. Tables XXXVII and XXXVIII were taken from the Warm Air Furnace Handbook.

**Table XXXVII. Capacity of Warm-Air Furnaces of Ordinary Construction**  
Cubic Feet of Space Heated

Divided space in cubic feet			Fire-pot		Undivided space in cubic feet		
$+ 10^\circ$	$0^\circ$	$- 10^\circ$	Diameter, in	Area, sq ft	$+ 10^\circ$	$0^\circ$	$- 10^\circ$
12 000	10 000	8 000	18	1.8	17 000	14 000	12 000
14 000	12 000	10 000	20	2.2	22 000	17 000	14 000
17 000	14 000	12 000	22	2.6	26 000	22 000	17 000
22 000	18 000	14 000	24	3.1	30 000	26 000	22 000
26 000	22 000	18 000	26	3.7	35 000	30 000	26 000
30 000	26 000	22 000	28	4.3	40 000	35 000	30 000
35 000	30 000	26 000	30	4.9	50 000	40 000	35 000

**XXXVIII. Air-Heating Capacity of Warm-Air Furnaces**

Area, sq ft	Casing * Diameter, in	Total cross- sectional area of heat- pipes, $a$ , sq in	Number and size of heat- pipes that may be supplied
1.8	30-32	180	3-9" or 4-8"
2.2	34-36	280	{ 2-10 and 2-9" 2-9" and 2-8"
2.6	36-40	360	{ 3-10" and 2-9" 4-9" and 2-8"
3.1	40-44	470	{ 3-10" and 1-9" 2-10" and 5-8"
3.7	44-50	565	{ 5-10", 3-9" 3-10", 4-9" and 2-8"
4.3	48-56	650	{ 2-12", 3-10" and 3-9" 5-10", 3-9" and 2-8"
4.9	52-60	730	{ 3-12", 3-10" and 3-8" 5-10", 5-9" and 1-8"

$\frac{1}{2}$ -diameter should be such that the minimum cross-sectional area  $M$ , of the duct and radiator, will be at least 20% greater than the total cross-sectional area of the heat-pipes,  $a$ , or  $M = 1.2 \times a$  sq in.

recommended by the Federal Furnace League, an association of United States furnace manufacturers. This association is no longer in existence. If the basement or leader-pipes exceed 12 ft in length or have less than 1 ft of vertical rise, or if more than one sixth of the outside surface of the building is heated by the furnace should be increased one or more sizes. The size of the duct required can also be determined by the combined area of the cross-sections of the warm-air pipes.

**Rating Based on Efficiency and Rate of Combustion.** The rating of a furnace is capable of imparting to the air (not the room) heat is estimated from the grate-area by assuming that the average coal contains approximately 12 000 Btu per lb. A combined furnace-and-radiator efficiency of 55%, and a maximum combustion-rate of 6 lb per sq ft of grate-surface per hour for maximum conditions (coldest weather) are also usually assumed.

**Grate-Surface Required, Based on Recirculation.** The area of the grate-surface is readily calculated as soon as the heat to be supplied to the building per hour has been determined.

$H$  = Btu to be supplied building per hour;

$h$  = Btu required from furnace per hour for heating the air =  $.12 H$ ;

$C$  = heating value Btu of coal per lb;

$E$  = combined furnace-and-grate efficiency;

$R$  = rate of combustion, pounds of coal per square foot of grate-surface per hr;

$G$  = grate-area in square feet;

$h = G \times C \times E \times R = 1.2 H$ .

$h$  = area of grate in square feet  $\times 12\ 000 \times 0.55 \times 5.5$

=  $36\ 300 \times G$ , which is Btu transmitted to the air passing the furnace;

$G = (1.2 \times H)/36\ 300$ .

Table XXX. Dimensions and Capacities of the Keboey Warm-Air Generator

Size or number of generator	Cold-air supply, etc.			Dimensions			Measurements of galv. casings and tops, series A. B. C., in
	Inside diameter of brickwork if pit is used, in	Size of cold-air duct if air is taken from outside, in	Size of cold-air face if air is taken from inside, in	Diameter of base, in	Height of castings, in	Height of generator, cased complete, in	
1	34	12 X 24	18 X 24	38	49	61	35
2	38	12 X 30	20 X 26	42	53	63	40
3	42	12 X 36	21 X 29	46	56	68	43
4	49	14 X 40	24 X 32	53	59	69	50 1/4
5	53	14 X 48	24 X 32	56	59	69	52
6	56	14 X 56 or (2) 14 X 32	30 X 36 or (2) 21 X 29	60	62	72	56 1/4
7	60	14 X 60 to 72 or (2) 14 X 40	30 X 48 or (2) 24 X 32	64	66	76	59 1/4

Number of generator	Heating capacities			Church-heating		Size of coal recommended
	House-heating	Church-heating		Number of pipes	Estimated capacity, cu ft	
	Number of average-size pipes or rooms	Estimated capacity, cu ft	Total area of heating-pipe supplied by each generator, sq in			
14	3 to 4	4 000-6 000	280 to 350	1	3 000	Chestnut
16	4 to 6	6 000-10 000	350 to 450	1 to 2	10 000-14 000	Chestnut or stove
18	6 to 8	12 000-16 000	450 to 500	1 to 2	16 000-20 000	Stove
21	9 to 11	18 000-24 000	575 to 625	1 to 2	25 000-35 000	Stove or egg
24	10 to 13	24 000-32 000	675 to 750	1 to 3	35 000-45 000	Stove or egg
27	12 to 16	32 000-42 000	850 to 925	1 to 3	50 000-60 000	Egg

The usual assumptions, with ANTHRACITE FUEL are:

$C = 12\,000$  Btu per lb;

$R = 4$  lb ordinary rate and 5.5 lb for maximum conditions in coldest weather;

$E = 0.55$ ;

then  $G = h/(12\,000 \times 5.5 \times 0.55) = h/36\,300 = 1.2H/36\,300$ .

**Size of Leaders and Stacks.** The area of the air-pipes (leaders and stacks) required for a room depends upon the quantity of air to be introduced per minute and the velocity with which the air will flow with natural circulation.

$Q/60$  = cubic feet of warm air to be introduced into the room per minute;

$V$  = velocity of air in feet per minute attainable;

$H$  = heat-loss of room;

$A$  = area of pipe in square feet;

$Q/60 = AV$ , and substituting value of  $Q = H/1.58$ ;

$A = H/(95 \times V)$ .

The following velocities are approximately obtained in the leaders and stacks on the floors as stated:

First floor, 175 ft per min;

Second floor, 240 ft per min;

Third floor, 310 ft per min.

The above velocities have been observed in practice in well-designed systems. For various floors, substituting in the above equation, in square inches:

$A_1 = H/115$  for first-floor pipes, leaders and stacks;

$A_2 = H/160$  for second-floor pipes, leaders and stacks;

$A_3 = H/206$  for third-floor pipes, leaders and stacks.

Bulletin No. 112, Engineering Experiment Station, University of Illinois,

Equal leader and stack-sizes are based on the above areas, using the nearest inch for leader the diameter (Table XL), and keeping the stacks of such proportions that the cross-sectional dimensions are never in a greater ratio than 4 to 1. For example, a stack 4 by 20 in is seldom effective over its full area, as it is too narrow, and as its large rubbing-surface causes excessive friction. Actual velocities obtained, however, will depend upon the head or pressure driving the flow and the friction-head, and will seldom exceed 50% of the theoretical velocities. Table XL has been recommended by the Federal Furnace Bureau and gives the sizes of round pipe for leaders, the size of wall-pipe for registers, and free areas of registers to connect with same. Leaders over 12 ft in length should be increased 1 in in diameter for each 5 ft beyond 12 ft.

**Registers.** The FREE AREA through the ordinary register-grille is only approximately 55% of the gross area, and consequently a register must be selected so that its gross area is double the area of the pipe with which it connects, in order that the air-passage may not be contracted and the capacity reduced. Commercial register-sizes are based on the actual inside dimensions of the grilled register and are made either of pressed steel or cast iron, with a variety of fancy designs and grilles. The plain rectangular grille is to be preferred, finished to suit the decorative scheme, in black japan or electro-plated in brass, bronze or nickel finish. Warm-air registers may be placed in the floor, but preferably in the partitions, for first-floor rooms. By using the modern BASE-BOARD REGISTER, Fig. 52, it is usually possible to secure the required capacity without

Table XL. Capacities and Dimensions of Warm-Air Piping and Registers

Diameter of round cellar or riser-pipe, in *	Proper size of rectangular riser-pipe, in *	Area of riser-pipe, sq in	Required area of register-face, sq in *
6	3 X 9½	28	52
6½	3½ X 9½	33	62
7	3½ X 11	38	72
7½	3½ X 12½	44	84
8	3½ X 14	50	96
8½	4 X 14	57	108
9	4 X 16	64	120
9½	4 X 18	71	134
10	4 X 20	78	142
10½	6 X 14½	86	158
11	6 X 16	95	176
11½	6 X 17½	104	194
12	6 X 19	113	204
12½	6 X 20½	122	222
13	6 X 22	132	242
13½	8 X 18	143	254
14	8 X 19	154	276
14½	8 X 20½	165	298
15	8 X 22	176	320
16	8 X 25	201	358
17	10 X 22½	227	410
18	10 X 25½	254	450
19	12 X 23½	283	508
20	12 X 26	314	554
21	12 X 28½	346	618
22	14 X 27	380	686
23	14 X 29½	415	707
24	14 X 32	452	770

\* When the required size of pipe falls on the odd half-inch (as 7½, 8½, 9½, etc.) the size may be increased to the even inch (as 8 instead of 7½, 9 instead of 8½, etc.) for the first-floor rooms and bath-rooms; provided that the pipes for upper-floor rooms other than bath-rooms, be decreased by ½ in when the required sizes fall on the odd half-inch. It is better, however, to use pipes of the sizes given in the above table, with proper allowances for length of pipe, extra bends, etc., beyond straight runs 12 ft long.

resorting to floor-registers. These base-board registers can be connected to a flue from 3 to 4½ in deeper than the studding. This has been accomplished by making the special base-board register so that it projects 2 in into the room at the floor-line, necessitating the cutting out of the floor, and also utilizing the space of about 1 in occupied by the lath and plaster, or a total increase in depth of flue of about 3 in. For upper-floor rooms registers should be placed in inside partition walls, using CONVEX REGISTERS for shallow stacks. As a general rule warm-air registers should be so placed as to shorten leader and stack-connections as much as possible. The use of a floor-register may be permitted in an entrance hall for drying shoes and garments, but it is unsanitary and cannot fail to collect dirt and filth of all kinds. In case such registers are used, however, suitable REGISTER-BOXES must be provided, and they are preferably constructed with double walls.

**Example in Furnace-Heating.** A gravity furnace-heating system is to be designed for the two-story frame building shown in Fig. 55, with inside and outside



. Register  
at Floor  
supply  
line 7 in.  
n. Down-  
siding

Fig. 52. Modern Base-board Register




Fig. 53. Cold-air Ducts for Warm-air Furnaces

FRESH - AIR ROOM  
WITH DUST-COLLECTOR

Table XLI. Table of Sizes of Floor-Registers, Base-Board Registers and Register-Boxes

Size of round cellar-pipe, in	Size of round floor-register, in	Size of rectangular register-box to base-board	Size of register-box to base-board	Size of base-board register	Size of register-box to base-board register	Size of base-board register where there is no limit to depth of register-box, in
6	9	8 X 8	2½ X 10	7 X 10	2½ X 10	7 X 10
6½	9	8 X 8	3¼ X 10	7 X 10	3¼ X 10	7 X 10
7	10	8 X 10	3½ X 10	7 X 10	3½ X 10	7 X 10
7½	12	8 X 12	4¼ X 10	7 X 10	4¼ X 10	7 X 10
8	12	8 X 12	4¼ X 12	7 X 12	4¼ X 12	7 X 12
8½	12	9 X 12	4½ X 12	7 X 12	4½ X 12	7 X 12
9	14	10 X 12	5 X 13	8 X 13	5 X 13	8 X 13
9½	14	10 X 14	6 X 12	10 X 12	6 X 12	10 X 12
10	14	10 X 16	6½ X 12	10 X 12	6½ X 12	10 X 12
10½	16	10 X 16	6½ X 13	10 X 13	6½ X 13	10 X 13
11	16	12 X 13	6½ X 14	12 X 14	6½ X 14	12 X 14
11½	16	12 X 18	7 X 15	12 X 15	7½ X 14	12 X 14
12	18	12 X 20	6½ X 18	12 X 18	7½ X 15	12 X 15
12½	18	14 X 16	6½ X 18	12 X 18	6½ X 18	12 X 18
13	18	14 X 18	.....	.....	7½ X 18	12 X 18
13½	18	14 X 20	.....	.....	8 X 18	12 X 18

Table XLII. Dimensions of Excelsior Double Wall-Pipe  
Excelsior Steel Furnace Company

Number	Measurements			Area of stack, sq in
	Nominal, in	Inside, in	Outside, in	
4	3 X 10	2½ X 10	3 X 10½	24
6	3 X 12	2½ X 12	3 X 12½	28½
7	4 X 11	3 X 10	3½ X 10½	30
8	4 X 13	3 X 12	3½ X 12½	36
9	4 X 14	3 X 13	3½ X 13½	39
12	6 X 13	5 X 12	5½ X 12½	60
14	6½ X 14	5½ X 13	6½ X 13½	72

Number	Collar-diameter, in	Area of collar, sq in	Register-size, convex or wafer, sq in
4	7	39	6 X 8— 8 X 10
6	8 and 9	51 and 63	8 X 10— 9 X 12
7	8 and 9	61 and 53	8 X 10— 9 X 12
8	8, 9 and 10	51 and 78½	8 X 10— 10 X 14
9	9 and 10	63 and 78½	10 X 12— 10 X 14
12	9 and 10	63 and 78½	10 X 12— 10 X 14
14	10 and 12	78½	10 X 14— 12 X 14

of 70° and 0° F. respectively, and the air all recirculated in transmission and infiltration-losses are as computed in Table

Fig. 58. Furnace-heating Layout. (See data in Table XLVI)

ch also gives the size of heat-pipes, leaders and stacks, and register-

**Furnace and Grate.** The size of the furnace is calculated on the basis that all the air is taken from the outside. The total calculated heat-requirement per hour is 124 558 Btu, which, multiplied by 1.2, and divided

Table XLIII. Dimensions of Excelsior Single Furnace-Pipe

Excelsior Steel Furnace Company

Measurement in inches	Size of boot- collars, diameter, in	Capacity of collars, sq in	Capacity of pipe, sq in
3 X 10	8	51	30
3½ X 10	8	51	35
3 X 12	8 and 9	51 and 63	36
3½ X 12	9	63	42
3½ X 13	9 and 10	63 and 78	45
5½ X 12	10	78	66
5½ X 14	12	114	77
5½ X 16	12 and 14	114 and 154	88
7½ X 16	14	154	112

NOTE. Stacks 5½ in deep, made to order only. With frictionless boots, collars same can be made with a diameter equal to width of stack. Collars 11 in in diameter furnished when so ordered.

Table XLIV. Capacities and Dimensions of Fresh-Air Ducts, Rooms, Etc.

Size of horizontal portion of rectangular fresh-air duct,  in	Size of horizontal portion of round fresh- air duct,  in	Cross-section area of horizontal portion of fresh-air duct,  in	Size of fresh- air-room; length and width (height same as depth of cellar),  in	Size of fresh- air intake (area of woven-wire netting, not including frame),  in
8 X 18	1-14	144	18 X 48	12 X 16
8 X 21	1-15	168	21 X 48	14 X 16
8 X 24	1-16	192	24 X 48	16 X 16
10 X 21	1-16	210	21 X 60	14 X 20
10 X 24	1-18	240	24 X 60	16 X 20
10 X 27	2-13	270	27 X 60	18 X 20
10 X 30	2-14	300	30 X 60	20 X 20
12 X 27	2-14	324	27 X 72	18 X 24
12 X 30	2-15	360	30 X 72	20 X 24
12 X 33	2-16	396	33 X 72	22 X 24
12 X 36	2-17	432	36 X 72	24 X 24
12 X 39	2-17	468	39 X 72	24 X 26
14 X 36	2-18	504	36 X 84	24 X 28
14 X 39	2-19	546	39 X 84	26 X 28
14 X 42	2-19	588	42 X 84	28 X 28
14 X 45	2-20	630	45 X 84	28 X 30
14 X 48	2-21	672	48 X 84	28 X 32
14 X 51	2-21	714	51 X 84	28 X 34
16 X 48	2-22	768	48 X 96	32 X 32
16 X 51	2-23	816	51 X 96	32 X 34
16 X 54	2-24	864	54 X 96	32 X 36
16 X 57	2-24	912	57 X 96	32 X 38
16 X 60	2-25	960	60 X 96	32 X 40

No XLV. Sizes and Capacities of Wooden Register-Faces for Cold-Air Ducts

Size	Net area of air-space, sq in	Nearest size of round pipe of equivalent area, in	Size, in	Net area of air-space, sq in	Nearest size of round pipe of equivalent area, in
2 X 20	135	12	24 X 24	323	20
2 X 24	161	14	24 X 26	349	20
2 X 30	202	16	24 X 30	403	22
4 X 20	157	14	28 X 28	439	22
4 X 26	203	16	30 X 30	504	26
6 X 20	179	14	36 X 20	403	22
6 X 24	215	16	36 X 24	484	24
6 X 30	269	18	36 X 30	605	28
8 X 24	242	18	36 X 36	725	30
8 X 30	303	20	72 X 18	726	.....
10 X 20	224	16	72 X 20	806	.....
10 X 24	269	18	72 X 24	968	.....
10 X 26	291	18	72 X 30	1 210	.....
10 X 30	336	20	72 X 36	1 450	.....

Table XLVI. Furnace-Heating Example (See Fig. 55)

First floor	Parlor	Hall	Dining-room	Library	Kitchen	
Volume in cubic feet.....	2 280	2 170	2 400	2 280	3 600	Heat-loss of kitchen is based on kitchen-range supplying one-half the required amount.
Heat-loss, $H$ , in Btu per hour....	14 855	13 400	11 655	11 515	11 127	
Area of heat-pipe, $\frac{H}{15}$ sq in.....	127	116	101	100	96	
Diameter of leader in inches.....	13	12	11	11	11	
Length of register in inches.....	12 X 18	12 X 18	12 X 15	12 X 15	12 X 15	

Second floor	Chamber No. 1	Chamber No. 2	Chamber No. 3	Chamber No. 4	Chamber No. 5	Bath-room
Volume in cubic feet.....	2 052	1 458	1 746	1 206	1 242	576
Heat-loss in Btu per hour.....	14 370	12 000	10 413	9 070	10 883	5 400
Area of heat-pipe, $\frac{H}{15}$ sq in.....	89	75	65	56	68	34
Diameter of leader in inches.....	10½	10	9	9	9	8
Length of register in inches.....	5½ X 16	5½ X 14	5½ X 12	5½ X 12	5½ X 12	5½ X 10
Length of register in feet.....	12 X 14	10 X 13	10 X 12	9 X 12	10 X 12	10 X 12

net area of register-faces is assumed to be 55% of the gross area. The gross area is 1.8 times the area of the leader-pipe.

by 36 300, the heat available from 1 sq ft of grate when burning 5.5 lb of coal of 12 000 Btu heat-value per pound, at 55% efficiency, gives 4.1 sq ft as the grate-area. This will require a grate of 28-in diameter. This building has a net volume of 26 000 cu ft, and by reference to Table XXXVII it is seen that a 28-in grate is recommended for this amount of divided space. The furnace, in this problem, has been located practically in the center of the house, but on the north side of its east and west axis, giving a direct cold-air connection from the north wall and short direct runs for most of the leaders.

**Leader-Layout.** The leaders may be laid off, as shown in Fig. 55 and in Fig. 48, by dividing up the circumference of the bonnet into areas proportional to the amount of air to be distributed by each leader, and then connecting collars and leader radially to furnace-cap, making one or more elbows in the leader, if necessary to connect with stack. Another method is to run practically all leaders direct from furnace to foot of stack (Fig. 49) and cut the collars in on the angles at which they intersect the casing. The former method is recommended and requires less skill in installation. The basement heating-plan is shown on the first-floor plan, which also shows all stack-sizes to both floors. Floor registers have been shown on the first-floor plan in order to simplify the layout and make the plan clearer. In general, base-board registers are to be preferred. The sum of the areas of leader-pipes is 927 sq in.

### Hot-Blast Heating

**General Features.** The mechanical indirect method of heating, commonly known as the **BLOWER SYSTEM** or **HOT-BLAST SYSTEM**, particularly adapted to the warming and ventilating of large structures, is made up of three units: (1) A **HEATER** constructed of pipes, tubes, or cast-iron sections, through which steam, hot water or hot gas may be passed. (2) A **FAN OR BLOWER** to circulate air over the heater-surfaces, the air acting as a heat-carrier or medium of heat-transfer. (3) A **SYSTEM OF DUCTS OR PIPES** to convey the heated air from the heater to points where heat may be required. When the heater is located between the fan and main duct, the combination is termed **BLOW-THROUGH**, and when the fan is installed between the heater and the duct, the arrangement is known as **DRAW-THROUGH**. These two arrangements are shown in Fig. 57. The **DRAW-THROUGH** combination is more often used for shop and factory-installations where compactness is desirable, the **BLOW-THROUGH** combination being used principally for **HOT-AND-COLD** systems as installed in schools and public buildings.

**Advantages of the Blower or Hot-Blast System.** The advantages of the blower or hot-blast system over those of direct radiation, briefly summarized are:

(1) When ventilation is a requirement in order to maintain a healthful atmosphere, this method affords a positive means of accomplishing this particular desirable result, which is entirely independent of the changing climatic conditions.

(2) When a standard humidity of the air is to be maintained, a feature which is becoming to be more generally recognized as desirable in any heating-and-ventilating installation, and quite essential to the successful manufacture of some materials, the humidifying-apparatus may readily be made an integral part of the system.

(3) A much smaller amount of radiating-surface is required to perform an equal heating-duty, with a consequent reduction in the number of steam-tight joints, unions and valves to keep in repair.

(4) The air-leakage being mostly outward, the building will in general be in

m drafts and more uniformly heated. If the air is simply recirculated, no fresh air being taken into the heating system from the outside, the above statement does not apply. The pressure of the air in the building, even when all of the air is taken into the heating system from the outside, is comparatively feeble, and some air will enter by infiltration through the window and door-cracks on the windward side of the building, although the statement is often made that the leakage being all outward, prevents the infiltration of cold air from the outside.

) This system is more easily regulated, and readily responds to changing outside temperatures.

) The air entering for ventilation may be conveniently cooled in summer, either by the circulation through the heater of cold water or of brine previously cooled by mechanical refrigeration.

) Simply running the fan will in itself greatly relieve the oppressiveness in hot weather, and when cold water is circulated through the coils the difference is very noticeable.

**Typical Arrangements.** When ventilation is not a requirement, or when it is relatively unimportant, as is frequently the case in shop or factory-heating where the number of persons vitiating the air is small compared with the cubical content of the building, the air may be simply RECIRCULATED, sufficient fresh air for ventilation being supplied by infiltration. The amount of heat to be supplied by the heater in this case is the same as would be required for a direct-radiation system. When ventilation is a requirement to be met a COLD-AIR INTAKE must be provided. Since the amount of air necessary for heating is generally in excess of the amount required for ventilation considerable economy may be effected by recirculating a portion of the air. In this case only sufficient fresh air is drawn into the system from the outside to meet the ventilation requirement and the remainder of the air necessary for heating, is recirculated. This may be readily accomplished by an arrangement of ducts and dampers on the suction-side of the fan. The fresh air introduced is to be washed or conditioned in the washer or humidifier and a tempering-coil may be added between the inlet for the recirculated air and the fresh-air intake.

**Amount of Air to be Circulated for Heating.** The weight of air to be circulated per hour for heating a room or building is found by dividing the heat-loss ( $H$ ) by the amounts of heat given up by 1 lb of air in cooling from the temperature at the duct-outlets to the mean room-temperature.

$H$  = heat-loss of room, Btu per hr;

$M$  = weight of air to be introduced in room per hour;

$t$  = mean inside temperature;

$t_d$  = temperature of air leaving duct-outlets.

$$M = H/[0.24(t_d - t)]$$

temperature  $t_d$  depends upon the temperature of the air entering the duct, the velocity through the clear area, the amount of heating-surface and the temperature of the steam. This temperature in practice ordinarily ranges from 125° to 150° F. and may be readily determined for any specified condition from the data given later under Hot-Blast Heaters. The temperature of the air leaving the duct-outlets for ordinary installations, when the ducts are not run underground or in outside walls, may be assumed to be the same as the temperature of the air leaving the heater. Any loss in temperature in this case is toward heating the building and is therefore not a direct loss. If, however, the ducts are run underground or in outside walls, a considerable loss in

temperature may occur, which is a direct loss, and must be provided for by INCREASING THE TEMPERATURE OF THE AIR LEAVING THE HEATER by an amount equal to the estimated temperature-drop in the ducts.

### Temperature of Air Entering Heater.

Let  $t_1$  = temperature of air entering heater;

$t_0$  = outside temperature;

$t$  = mean inside temperature;

$t_2$  = temperature of air leaving heater;

(a) When the air is all recirculated,  $t_1 = t$ ;

(b) When fresh air only is circulated,  $t_1 = t_0$ ;

(c) When a portion of the air is recirculated the resulting temperature of the mixture of fresh and recirculated air may be found by the METHOD OF MIXTURE.

Let  $M_v$  = weight of fresh air, pounds required per hour for ventilation (cu ft per min per person);

=  $0.075 \times 1800 \times$  number of persons (usual requirements);

$M_r$  = weight of air that may be recirculated;

$M = M_v + M_r$

$H = 0.24 (M_v + M_r) (t_2 - t)$ .

Having assumed or fixed the value of  $t_2$ , the only unknown quantity is  $M_r$ .

$$M_r = H/[0.24(t_2 - t)] - M_v$$

The temperature  $t_1$  may then be found as follows:

$$M_v \times (t_0 + 460) = A$$

$$M_r \times (t + 460) = B$$

$$(M_v + M_r) (t_1 + 460) = A + B$$

or

$$t_1 = (A + B)/(M_v + M_r) - 460$$

**Example.** The heat-loss  $H$  for a certain factory-building is 70 600 Btu per hr. The number of men employed is 50. Mean inside temperature  $t = 65^\circ$ . Outside temperature  $t_0 = 0^\circ$  F. Ventilation is to be provided at the rate of 1800 cu ft of fresh air per hour per person. Assumed temperature of air leaving duct-outlets is  $135^\circ$  F.

**Solution.**  $M_v = 0.075 \times 1800 \times 50 = 6750$  lb per hr fresh air for ventilation. The weight of air that may be recirculated is

$$M_r = 706000/[0.24(135 - 65)] - 6750 = 35273 \text{ lb per hr}$$

The temperature of the air entering the heater will be:

$$6750 \times (0 + 460) = 3105000$$

$$35273 \times (65 + 460) = 18516750$$

$$t_1 = (21621750/42023) - 460 = 55^\circ \text{ F.}$$

If FRESH AIR ONLY is to be used, as in school-house and public-building heating, the weight of air to be circulated is determined directly by the ventilation requirement.

Then  $M = M_v = H/[0.24(t_2 - t)]$ , or  $t_2 = (H + 0.24 M t)/0.24 M$ .

**Temperature of Air at Duct-Outlets.** When heating, by the hot-water system, a building containing a number of rooms having different heat-loss and ventilation requirements, it is obviously impossible to maintain the desired



perature by controlling the temperature ( $t_h$ ) of the air leaving the heater at point. The temperature  $t_d$  of the air leaving the duct-outlets will ordinarily be different for each room in the building, as shown in the following example. The result is accomplished by the double plenum-chamber system described

example. Let it be required to determine the temperature of the entering air ( $t_d$ ) to offset the heat-loss and provide ventilation for the several rooms as shown in Table XLVII. Inside temperature ( $t$ ) to be maintained is  $70^\circ$ .

Table XLVII. Data for Example

Room-number	Number of occupants, $n$	Ventilation		Heat-loss, $H$	Temperature of entering air, $t_d$ (see formula)
		Cubic feet per hour at $70^\circ$ , $1\ 800 \times n$	Weight per hour, $M_o$		
Room-1	50	90 000	6 750	32 000	89.5
Room-2	53	95 400	7 125	21 000	82.2
Ball	.....	30 000	2 250	4 000	77.4

**Temperature of Air Leaving Heater.** If all of the air is first warmed by the RING-COIL to  $70^\circ$  F., and a mixture of approximately  $(1 - x)$  parts of tempered air and  $x$  parts of hot air is to be used, then the required temperature of air leaving the heater may be determined, for any particular case, by the METHOD OF MIXTURES previously given; or, assuming this temperature, the proportions of hot and tempered air may be determined.

Example. Required the temperature of the hot air ( $t_h$ ) leaving the heater for Room-2, (Table XLVII) if the mixture entering the room is made up of tempered air at  $70^\circ$  and one half hot air. The total weight of air entering the room is 7 125 lb per hr, or 3562.5 lb of tempered air and 3562.5 lb of hot air.

$$3\ 562.5 \times (70 + 460) + 3\ 562.5 \times (t_h + 160) = 7\ 125 \times (82.2 + 460).$$

$$t_h = 94.$$

Assuming a temperature of  $t_h = 120^\circ$ , it is required to determine the relative proportions, by weight, of the mixture required.

$x$  = parts of hot air in mixture. Then  $(1 - x)$  = parts of tempered air.

$$x(120 + 460) + (1 - x) \times (70 + 460) = (82.2 + 460)$$

$$x = 0.244 \text{ and } (1 - x) = 0.756$$

**Applied for Ventilating Purposes Only.** A combination of direct radiation to offset the heat-loss  $H$ , and a hot-blast system, to supply the fresh air for ventilation, is sometimes installed. In this case it is customary to have a heater of sufficient capacity to warm the air for ventilation to about  $80^\circ$ . The heater used for this purpose is made three sections deep and is often termed a G-COIL.

**Hot-and-Cold Systems.** In order to accomplish the results required in the example, the so-called HOT-AND-COLD SYSTEM or DOUBLE-PLENUM-SYSTEM is used. All of the air drawn into the system from the outside

is first passed through a TEMPERING-COIL, which is designed to heat the air to approximately  $70^{\circ}$ . A portion of the tempered air is then passed through a heater and raised to  $125^{\circ}$  to  $150^{\circ}$ . Then if varying proportions of the hot air




Fig. 56. Double-duct System




Fig. 57. Types of Heater-jackets




Fig. 58. Single-duct System

Fig. 59. Deflecting-damper for Branch-duct

Fig. 60. Thermoregulator-controlled Mixing-damper

Figs. 56 to 60. Details of Ducts for Hot-and-cold Heating Systems

tempered air are correctly mixed the resulting temperature ( $t_s$ ) is readily controlled without varying the quantity of air discharged, which evidently must remain constant on account of the ventilation requirement. There are two

Methods of distribution used, as shown in Figs. 56 and 58. Referring to Fig. 58, it is seen that the hot and tempered air meet at the end of the plenum-chamber at the entrance to the ducts, and the temperature of the mixture is controlled by the MIXING-DAMPERS, which may either be hand-operated or placed under automatic thermostatic control. It will be observed that the plenum-chamber is divided, and that each duct serving a room has its own independent set of mixing-dampers. This method of distribution is known as the SINGLE-DUCT SYSTEM and is frequently employed where the installation of the DOUBLE-DUCT SYSTEM, as described below, is not feasible or is undesirable. Fig. 56 shows a single set of ducts run from the plenum-chamber to the base of each vertical flue, one carrying the hot air and the other the tempered air, the mixing being done at the base of the flue as shown. The mixing-dampers (Fig. 60) may be controlled by hand by means of a chain carried up the flue and run into the room at a point several feet above the floor-line, or placed under automatic thermostatic control through the medium of a compressed-air-operated damper.

### Hot-Blast Heaters

**Coil Heaters.** The type of heater that has been a standard for a number of years, for hot-blast work, is made up of four or eight vertical rows,

Fig. 61. Pipe-coil Heater-base

depending on the manufacturer, of 1-in pipe screwed into a cast-iron base and spaced from  $2\frac{1}{4}$  to  $2\frac{3}{4}$  in on centers, the pipes in each row being cross-connected at the top by the use of nipples and ells. The arrangement of coils and the method of dividing the base by a vertical partition, running longitudinally, in order to separate the supply and return as used by the American Blower Company is shown in Fig. 61. A base with its accompanying pipes is termed a

**SECTION.** The heater is made up of a number of such sections enclosed by **SHEET-STEEL JACKET**, usually No. 22 gauge.

**Cast-Iron Indirect Heaters.** Special cast-iron sections for indirect heat are often used, and Fig. 62 shows a cast-iron heating-unit or section, **Vento**, manufactured by the American Radiator Company, which is quite widely used in this class of work. A stack made up of several sections has a small number of joints than a pipe-coil section of equal heating-surface. The deterioration of the cast-iron sectional type of heater is practically nothing except the right-hand and left-hand hexagonal nipples connecting the units which to make up a stack. There are three standard lengths of Vento heater-sections

Fig. 62. Plan of the Assembly of a Vento Heater

as indicated in Table XLVIII, which also includes other data required by the designer.

Table XLVIII. Vento Hot-Blast Heater-Data

Length of section in inches	Heating-surface, regular sections, in square feet	Free area in square feet, per section, inches on centers			Ratio, square feet heating-surface to free area for 5 in on centers
		4 <sup>5</sup> / <sub>8</sub>	5	5 <sup>7</sup> / <sub>8</sub>	
40	10.75	0.52	0.62	0.72	17.34
50	13.50	0.65	0.77	0.91	17.53
60	16.00	0.78	0.92	1.08	17.39

**Selection of Hot-Blast Heaters. General Conditions.** In selecting the size of a heater for any particular service the choice is based on the temperature desired and the **FREE AREA** required for a certain allowable velocity. That is, for any specified initial and final temperature desired, and a certain number of sections, a final temperature results when the velocity has been fixed in advance. Good practice limits the velocity to the values given by the following tables. High velocities are objectionable in public-building work.

ment of the resulting noise. The resistance through the heater increases proportion to the square of the velocity, which adds to the power required to move the air as the velocity is increased, as will be noted later.

**Rating of Hot-Blast Heaters.** The RATING of an assembled heater of sections (pipe-coil type) or stacks (Vento type) is based on the TEMPERATURE of the air passing over the heating-surface for certain velocities through the clear or unobstructed area of the heater-face. The VELOCITY is based on the volume of air at an assumed temperature of 70° for convenience in rating.

Let  $M$  = weight of air to be circulated through heater per hour;

$\rho = 0.075$  = density of air at 70°;

$A$  = free area of heater in square feet;

$V$  = velocity of air in feet per minute through free area based on 70° temperature.

then

$$A = M / (60 \times 0.075 \times V) = M / 4.5V \text{ sq ft.}$$

The following tables will serve as guides in selecting the VELOCITY  $V$  and the NUMBER OF SECTIONS OR STACKS for various purposes.

**Table XLIX. Allowable Velocities of Air through Vento Heaters**

Referred to a temperature of 70° F.

Number of stacks deep, regular 5 in on centers	Public-building work, velocity in feet per minute	Factory work, velocity in feet per minute
4	1 000 to 1 500	1 200 to 1 600
5	1 000 to 1 300	1 200 to 1 600
6	1 000 to 1 200	1 200 to 1 600
7	900 to 1 100	1 200 to 1 500
8	800 to 1 000	1 200 to 1 400

**L. Number of Heater-Sections for Pipe-Coil Heaters or Stacks of Vento Ordinarily Required**

Service	Number of sections or stacks	Number of rows of 1-in pipe
Public buildings, fresh air, exhaust-steam.....	5	20
Industrial buildings, fresh air, 4-lb gauge.....	6	24
Industrial buildings, fresh air, exhaust-steam.....	7	28
Industrial buildings, recirculation, 5-lb steam.....	5	20
Heating-coils, fresh air, exhaust-steam.....	3	12

**Temperature-Rise.** The TEMPERATURE-RISE of the air passing through hot-blast heaters of various types has been well established by experiment, the manufacturers having published the results in the form of bulletins and reports.

**Example.** It is required to determine the size of a Vento hot-blast heater to supply the necessary heat for a public building, the calculated heat-loss of which

is  $H = 1\,420\,000$  Btu per hr for  $70^{\circ}$  inside and  $0^{\circ}$  outside temperature. The temperature of the air entering the rooms,  $t_d$ , is to be approximately  $120^{\circ}$ . The steam-pressure is 5-lb gauge. The temperature of the air entering the heater is  $0^{\circ}$ .

**Solution.** First determine from Table LI the number of stacks deep require for F.T. at  $120^{\circ}$  and entering air at  $0^{\circ}$ , using a velocity of 1000 ft per min. This condition calls for a 5-stack-deep heater. Then determine the weight of the air to be circulated per hour.

$$M = H/[0.24(t_d - t)] = 1\,420\,000/[0.24(120 - 70)] = 118\,333 \text{ lb}$$

The free area required is

$$A = 118\,333/(4.5 \times 1\,000) = 25.1 \text{ sq ft}$$

Table LI. Final Temperatures and Condensations, Vento Heaters

Regular section, Standard spacing, 5-in center to center, of loops. Steam, 5-lb gauge. C is the condensation in pounds per hour per square foot of heating-surface. F. is the final temperature of air leaving heater.

Velocity through heater in feet per minute, measured at 70°									
Number of stacks deep	Temperature of entering air	1 000		1 200		1 400		1 600	
		F.T.	C.	F.T.	C.	F.T.	C.	F.T.	C.
1	20	51	1.99	49	2.23	47	2.42	45	2.56
	30	60	1.92	58	2.17	56	2.33	54	2.46
	40	68	1.80	66	2.00	64	2.16	62	2.26
	60	84	1.54	82	1.69	81	1.89	80	2.05
	70	92	1.41	90	1.54	89	1.71	88	1.85
2	20	76	1.80	72	2.00	69	2.20	66	2.36
	30	83	1.70	79	1.89	76	2.06	73	2.21
	40	90	1.60	86	1.77	83	1.93	81	2.10
	60	103	1.38	100	1.54	98	1.71	96	1.85
	70	110	1.28	107	1.42	105	1.57	103	1.69
3	20	97	1.65	92	1.85	88	2.06	85	2.22
	30	103	1.56	98	1.75	94	1.91	91	2.08
	40	109	1.47	104	1.64	100	1.79	97	1.95
	60	120	1.28	116	1.44	113	1.58	110	1.71
	70	126	1.20	122	1.34	119	1.46	116	1.57
4	20	115	1.52	110	1.73	105	1.91	101	2.08
	30	120	1.44	115	1.63	110	1.80	106	1.95
	40	124	1.35	119	1.52	115	1.68	111	1.82
	60	134	1.19	129	1.33	125	1.46	122	1.59
	70	138	1.09	134	1.23	131	1.37	128	1.49
5	20	130	1.41	124	1.60	119	1.78	114	1.93
	30	134	1.33	128	1.51	123	1.67	118	1.80
	40	138	1.26	132	1.42	127	1.56	123	1.70
	60	145	1.09	140	1.23	136	1.36	133	1.50
	70	149	1.01	144	1.14	141	1.27	138	1.40
6	20	142	1.30	136	1.49	130	1.65	126	1.81
	30	145	1.23	139	1.40	134	1.56	130	1.71
	40	148	1.15	143	1.32	138	1.47	134	1.60
	60	155	1.02	150	1.15	146	1.29	142	1.40
	70	...	....	...	....	...	....	...	....
7	20	152	1.21	146	1.39	141	1.55	136	1.70
	30	155	1.15	149	1.31	144	1.46	139	1.60
	40	158	1.08	153	1.24	148	1.39	143	1.51

Table LI (Continued). Final Temperatures and Condensations, Vento Heaters

Velocity through heater in feet per minute, measured at 70°									
Number of inches deep	Temperature of entering air	1 000		1 200		1 400		1 600	
		F.T.	C.	F.T.	C.	F.T.	C.	F.T.	C.
1	-20	...	....	...	....	...	....	...	....
	-10	...	....	...	....	...	....	...	....
	0	35	2.24	32	2.46	...	....	...	....
2	-20	49	2.22	44	2.46	40	2.69	37	2.92
	-10	56	2.12	51	2.35	47	2.56	44	2.77
	0	62	1.99	58	2.23	54	2.42	51	2.62
3	-20	75	2.03	69	2.28	64	2.51	59	2.70
	-10	80	1.92	75	2.18	70	2.39	66	2.60
	0	86	1.84	81	2.08	76	2.27	72	2.46
4	-20	96	1.86	90	2.12	84	2.34	78	2.51
	-10	101	1.78	95	2.02	89	2.22	84	2.41
	0	106	1.70	100	1.92	95	2.13	90	2.31
5	-20	114	1.72	107	1.95	100	2.15	94	2.34
	-10	118	1.64	111	1.86	105	2.06	99	2.24
	0	122	1.56	115	1.77	109	1.96	104	2.14
6	-20	129	1.59	121	1.81	115	2.02	110	2.22
	-10	132	1.52	125	1.73	119	1.93	114	2.12
	0	135	1.44	129	1.65	123	1.84	118	2.02
7	-20	141	1.47	134	1.69	128	1.90	122	2.08
	-10	144	1.41	137	1.62	131	1.81	126	1.99
	0	147	1.35	140	1.54	135	1.73	130	1.90
8	-20	151	1.37	144	1.58	138	1.77	133	1.96
	-10	153	1.31	147	1.51	141	1.69	136	1.87
	0	156	1.25	150	1.44	144	1.62	139	1.78

ing to Table XLVIII and choosing a 60-in length of units, 5 in on centers, and that the free area per section is 0.92 sq ft. The number of sections across the face of the heater is

$$A/0.92, \text{ or } 25.1/0.92 = 27$$

ating-surface per section is 16 sq ft. The total heating-surface is there-

$$S = 5 \times 27 \times 16 = 2\,160 \text{ sq ft}$$

: condensation per hour is

$$2\,160 \times 1.56 \text{ (Table LI)} = 3\,370 \text{ lb}$$

plied by the boiler, or by exhaust-steam, at 5-lb pressure.

### Design of Air-Ducts

**Pressure-Loss.** The frictional resistance of air flowing through smooth metal ducts, commonly termed PRESSURE-LOSS, measured in inches of air 70° and for a length of duct equal to 100 ft, is given by the following formula:

$$h = 0.000136 \times (R/A) \times v^3$$

$R$  is the perimeter of the duct in feet,  $A$  the area of duct in square feet,  $v$  the velocity of the air in feet per second, and  $h$  the pressure-loss

measured in inches of water-column. For round ducts the above form reduces to

$$h = 0.00055v^2/D$$

in which  $D$  is the diameter of the duct in feet.

The diagrams in Figs. 63 and 64 are based on this formula, from which:


Cubic Feet of Air per Minute,  $Q$

Friction in Inches of Water-Gauge per 100 Feet

10  
8  
6  
5  
4  
3  
2  
1  
1



METER OF A ROUND DUCT for various velocities, and the PRESSURE-LOSS or DISTANCE for various quantities of air flowing, may be found without solving above equation.



**Fig. 64. Diagram of Friction-pressure Loss**

prob. What should be the size of a round duct required to convey 1500 air per minute with a velocity of 1800 ft per min; and what is the pressure per 100 ft of duct.

**Solution.** Locate 1 500 on the upper side of the pipe-diagram in Fig. 64, and pass horizontally downward until the 1 800-ft-velocity diagonal line is intersected. The duct which comes nearest to the required size has a diameter 12 in. At this intersection pass to the right side to the base-line and read 0.4 in water-pressure loss.

**Allowable Velocity of Air in Ducts and Flues.** In order to limit the resistance or pressure-loss in the duct system the designer should, in general, keep the velocities within the limits stated in Table LII. In public-building work the air should be delivered to a room at a velocity that will insure its movement to the desired points in the room without objectionable draft or noise in passing through the register-grills.

Table LII. Allowable Velocities in Hot-Blast Systems

Types of buildings		Allowable velocity in feet per minute
Public buildings		
Through free area of wall-registers.....		400- 500
Through free area of floor-registers.....		200- 300
Vertical flues to registers.....		600- 750
Connections to base of flues.....		800-1 000
Main horizontal distributing ducts.....		1 500-2 500
Manufacturing plants		
In plants where the occupation is more or less sedentary and the employe sits all day feeding automatic machinery:		
Main ducts.....		1 200-1 500
Branches.....		600- 900
In plants where the employe stands all day, as in machine-shops, foundries, etc.:		
Main ducts.....		1 500-2 400
Branches.....		900-1 500

The velocity through the fan-outlet, under the ordinary conditions that obtain in heating work, varies from 1 500 to 2 500 ft per min.

Table LIII. Metal Gauges for Ducts  
American Blower Company

Heating and ventilating		Thickness and weight		Blowpiping and exhaust work	
Diameter in inches	United States standard gauge-number	Thickness in inches and weight in pounds per square foot		Diameter in inches	United States standard gauge-number
		in	lb per sq ft		
6-18	26	0.1087	0.91	3- 5	26
19-36	24	0.025	1.16	6- 8	24
38-48	22	0.0312	1.41	9-15	22
50-60	20	0.0375	1.66	16-24	20
63-72	18	0.05	2.16	26-30	18

**Pipes and Ducts.** The recommended gauge (United States gauge) for various sizes of galvanized sheet-steel pipes for heating work, blowpiping and exhaust work, is given in Table LIII.

**Loss of Rectangular Ducts.** The simplest method of determining the system for ROUND DUCTS throughout, and then transfer R SIZES giving equal pressure-losses (not equal areas) by means of

#### V. Round and Rectangular Ducts of Equal Pressure-Losses

4	6	8	10	12	14	15	16	18	20	22	24
Equivalent diameters in inches											
4.4	..	..	..	..	..	..	..	..	..	..	..
4.9	..	..	..	..	..	..	..	..	..	..	..
5.4	6.6	..	..	..	..	..	..	..	..	..	..
5.8	7.0	..	..	..	..	..	..	..	..	..	..
6.1	7.6	8.8	..	..	..	..	..	..	..	..	..
6.5	8.0	9.3	..	..	..	..	..	..	..	..	..
6.8	8.4	9.8	11.0	..	..	..	..	..	..	..	..
7.1	8.8	10.2	11.5	..	..	..	..	..	..	..	..
7.4	9.2	10.7	12.0	13.2	..	..	..	..	..	..	..
7.6	9.6	11.1	12.5	13.7	..	..	..	..	..	..	..
7.6	9.9	11.5	12.9	14.3	15.4	..	..	..	..	..	..
8.2	10.2	11.9	13.4	14.7	16.0	16.5	..	..	..	..	..
8.4	10.5	12.3	13.8	15.2	16.5	17.1	17.6	..	..	..	..
8.6	10.8	12.6	14.2	15.7	17.0	17.6	18.2	..	..	..	..
8.9	11.1	13.0	14.6	16.1	17.4	18.1	18.7	19.8	..	..	..
9.1	11.4	13.3	15.0	16.5	17.9	18.6	19.2	20.4	..	..	..
9.3	11.6	13.6	15.4	17.0	18.4	19.0	19.7	20.9	22.0	..	..
9.7	12.1	14.2	16.1	17.8	19.2	19.9	20.6	21.9	23.1	24.2	..
10.0	12.6	14.8	16.8	18.5	20.0	20.8	21.5	22.8	24.0	25.2	26.4
10.4	13.1	15.4	17.3	19.2	20.8	21.6	22.3	23.8	25.1	26.3	27.5
10.8	13.5	15.9	18.0	19.8	21.5	22.4	23.1	24.6	26.0	27.3	28.5
11.0	13.9	16.4	18.5	20.5	22.2	23.1	23.9	25.4	26.8	28.2	29.5
11.3	14.3	16.9	19.1	21.1	22.9	23.8	24.6	26.2	27.7	29.1	30.5
11.6	14.7	17.3	19.6	21.6	23.5	24.4	26.3	26.9	28.5	30.0	31.3
11.9	15.1	17.7	20.1	22.2	24.2	25.1	26.0	27.7	29.3	30.8	32.2
12.2	15.4	18.2	20.6	22.8	24.8	25.8	26.7	28.4	30.0	31.5	33.1
12.5	15.7	18.6	21.1	23.3	25.4	26.4	27.3	29.1	30.8	32.4	33.9
12.7	16.1	19.0	21.6	23.8	25.9	26.9	27.9	29.8	31.4	33.0	34.5
13.0	16.4	19.4	22.0	24.3	26.5	27.5	28.5	30.3	31.2	33.7	35.3
13.3	16.7	19.8	22.4	24.8	27.0	28.1	29.1	31.0	32.8	34.6	36.2
13.5	17.0	20.1	22.8	25.2	27.5	28.6	29.6	31.6	33.4	35.2	37.0
13.7	17.3	20.4	23.2	25.7	28.0	29.2	30.3	32.2	34.1	35.9	37.6
13.9	17.6	20.8	23.6	26.2	28.5	29.6	30.7	32.9	34.7	36.5	38.3
14.1	17.9	21.1	24.0	26.6	29.0	30.1	31.2	33.4	35.3	37.2	38.9
14.3	18.2	21.5	24.4	27.0	29.5	30.6	31.7	33.9	35.9	37.8	39.6
14.6	18.4	21.8	24.7	27.4	30.0	31.1	32.2	34.4	36.4	38.4	40.3
14.7	18.7	22.1	25.1	27.8	30.5	31.6	32.7	34.9	37.1	39.1	40.9
15.0	19.0	22.4	25.5	28.2	30.9	32.1	33.2	35.4	37.7	39.6	41.6
15.1	19.2	22.7	25.9	28.6	31.3	32.6	33.7	35.9	38.2	40.2	42.2
15.3	19.5	23.0	26.2	29.0	31.7	33.0	34.2	36.4	38.7	40.8	42.8
15.5	19.7	23.3	26.5	29.4	32.1	33.4	34.7	36.9	39.2	41.4	43.4

**Example.** What is the width of a rectangular duct 6 in high equivalent to the pressure-loss for a duct 12-in in diameter? **Solution.** 22 in.

Table LV. Friction Pressure-Loss of 90° Elbows

Radius of throat in diameters of pipe . . . . .	¼	½	¾	1	1 ¼	1 ½	2	3	4	5
Number of diameters of straight pipe of equivalent pressure-loss . . . . .	67	30	16	10	7.5	6	4.3	4.8	5.2	5.8

**Example.** A duct 12 in in diameter and 120 ft long contains two 90° elbows. The ratio of the radius of throat to pipe-diameter is 3. The amount of air flowing is 1 500 cu ft per min and the velocity 1 800 ft per min.  
**Solution.** The total equivalent length of duct is

120 + (2 × 4.8) = 129.6 ft

The pressure-loss, from the diagram of Fig. 64, is 0.48 in per 100 ft. The loss  
0.48 × (129.6/100) = 0.62 in of water

The pressure-loss through register-grills may be taken at 0.023 in for velocity of 400 ft per min through free area. The gross area of registers twice the free area. The pressure-loss in standard air-washers for a velocity of 400 ft per min through the free area may be assumed to be 0.15 in of water. In the case of humidifiers, in which the spray is directed against the flow of air, a pressure-loss of 0.55 in of water may be assumed for preliminary estimates. The values assumed for this loss vary with different manufacturers. The pressure-loss through hot-blast heaters may be taken from Table LVI.

Table LVI. Friction of Air through Vento Heaters

Friction-loss, in inches of water, due to air passing through Vento stacks. Regular section. Standard 5-in spacing of loops. Air-temperature 70° F.

Velocity in feet per minute	One stack	Two stacks	Three stacks	Four stacks	Five stacks	Six stacks	Seven stacks
800	0.037	0.070	0.103	0.135	0.167	0.200	0.232
900	0.047	0.088	0.129	0.170	0.211	0.252	0.293
1 000	0.059	0.109	0.160	0.211	0.262	0.313	0.364
1 100	0.071	0.132	0.193	0.255	0.316	0.377	0.438
1 200	0.084	0.157	0.230	0.303	0.376	0.449	0.522
1 300	0.099	0.185	0.271	0.356	0.442	0.528	0.614
1 400	0.115	0.214	0.314	0.414	0.513	0.612	0.712
1 500	0.132	0.246	0.360	0.474	0.588	0.702	0.816
1 600	0.150	0.280	0.410	0.540	0.670	0.800	0.930
1 700	0.169	0.316	0.463	0.609	0.756	0.903	1.049
1 800	0.190	0.354	0.518	0.683	0.848	1.012	1.177

**Effect of Temperature on Pressure-Losses.** The preceding data on pressure-losses in ducts, registers and heaters are based on an air-temperature of 70° F.

other temperatures, the pressure-losses are to be multiplied by the ratio, density of air at actual temperature to density at 70°. These ratios are given in Table LVII. For heaters use the average temperature of the air passing through the heater.

Table LVII. Ratios of Density of Air at Actual Temperature to Density at 70° F.

Temperature	Factor	Temperature	Factor
100	0.945	140	0.880
120	0.910	150	0.865
130	0.890	160	0.850

**Design of Duct Systems.** There are two schemes used in PROPORTIONING DUCTS: (1) the velocity method, and (2) the method of equal friction pressure-loss per foot of length. The first method involves the fixing of the velocity (see Table LII) in the various sections, and the gradual reduction of the velocity from the beginning of duct to the point of discharge. In this case the pressure-loss is computed separately for each section having a different velocity and the various pressure-losses added together to obtain the total loss in pressure. The second method is used principally in the design of duct systems for space-heating. The velocity in the outlet farthest from the fan is fixed and the area and diameter of this branch are determined by the volume of air to be delivered. The friction pressure-loss per 100 ft of a duct of this size is determined by the diagrams in Figs. 63 and 64. The remainder of the main duct is proportioned for this same pressure-loss per 100 ft.

**Example.** The first method is illustrated in Fig. 65, showing a single-duct system. The risers are figured for a velocity of 600 ft per min, or 10 ft per sec;




Fig. 65. Single-duct System

ft per min, or 6.6 ft per sec; through free area of register-grill. The velocity in the longest main, B, is 900 ft per min, the volume of air to be delivered is 2000 ft per min, and the temperature 120°.

**n.** The area of the riser required is

$2\,000/600 = 3\frac{1}{3}$  sq ft, or 480 sq in

A 27-in riser, giving 486 sq in area, is used. The area of main, B, is

$2\,000/900 = 2.22$  sq ft, or 320 sq in

The size of the duct is 12 by 27 in. The diameter of a round duct for the same friction-loss for the riser, from Table LIV, is 24 in, and for the main,  $B$ , 19.5

Referring to the diagram in Fig. 64, the pressure-loss for the riser is 0.032 per 100 ft. For the main the pressure-loss is 0.09 in per 100 ft. The main has one elbow and the riser one elbow, and the ratio of radius at throat to diameter

Fig. 66. Part of Basement-layout for a Single-duct System for a School-building

will be assumed to be 3, in both cases. The equivalent length of main,  $L$ , therefore

$$200 + (4.8 \times 20/12) = 208 \text{ ft}$$

and the pressure-loss is

$$0.09 \times (208/100) = 0.187 \text{ in}$$

The equivalent length of riser is

$$34 + (4.8 \times 24/12) = 44 \text{ ft}$$

and the pressure-loss is

$$0.032 \times (44/100) = 0.014 \text{ in}$$

The pressure-loss through the register-grill is 0.023 in. The total resistance of the duct system is therefore

$$0.0187 + 0.014 + 0.023 = 0.224 \text{ in}$$

assuming that a five-section Vento heater is employed, with a velocity (fig. 1 through free area) of 1 200 ft per min, the pressure-loss through the heater is 0.376 in (Table LVI). The total resistance against which the fan must operate is

$$0.224 \text{ in} + 0.376 \text{ in} = 0.60 \text{ in}$$

and on 70° air. Assuming the temperature of the air to be 120°, the resistance is

$$0.60 \times 0.91 \text{ (Table LVII)} = 0.55 \text{ in}$$

The second method of duct-design is illustrated by the example given under the heading of Hot-Blast Heating-Data, page 1342.

### Ventilating Fans

**Steel-Plate Fan.** The standard type of fan that has been used for a number of years in hot-blast work is known as the STEEL-PLATE FAN, the construction of the wheel being shown in Fig. 67. As the name implies, the wheel and casing of this fan are constructed of steel plate in eight structural sections, the segments having eight to twelve straight or slightly curved ribs on their periphery, and in a direction opposite to the rotation. Steel-plate fans are designated by a number, this number being the inside diameter height of the fan in inches.

**Bladed Fan.** A new type of fan, known as the SIROCCO or TURBINE-TYPE IMPELLER, fig. 68, has recently entered the service of heating and ventilation on account of its higher efficiency, quieter running, and its smaller size for the same capacity than the steel-plate fan, rapidly supplanting the latter.

Fig. 67. Standard Steel-plate Fan-wheel

Its higher efficiency is accounted for by the material reduction of the air resistance or pressure-head loss by friction through the fan, due to the shorter length of the ribs and the larger inlet, which is of practically the same diameter as the outlet itself. This fan deserves more than passing mention as it represents the greatest single improvement ever made in the design of a centrifugal fan.

**Selection of Fans.** The volume of air at 70° which a fan will deliver (cubic feet per minute) varies with the resistance against which it operates. In order to select a fan from Table LIX, the resistance (static pressure) must first be determined by the duct-design, and after the size of the heater has been chosen the resistance determined. The speed and brake horse-power required to

drive the fan are also stated in the tables. The temperature of the air handled by the fan with DRAW-THROUGH apparatus is higher than 70°, except for a fan which is connected ahead of a tempering-coil, usually a two-section-deep heat exchanger. The tabulated speed, volume and brake horse-power to maintain the pressure must be multiplied by the factors given in Table LVIII for temperatures other than 70°. The above factors in this table are the square roots of the ratios of the density of the air at 70° F. to its density at the temperature stated.

Table LVIII. Factors for Speed, Volume and Brake Horse-Power

Temperature in degrees Fahrenheit	Factors
0	0.933
100	1.028
120	1.046
130	1.055
140	1.064
150	1.073

Fig. 68. Sirocco Wheel or Turbine-type Impeller

### Application of Hot-Blast Heating-Data

**The Application of the Foregoing Data on hot-blast heating to a factory building follows (see Fig. 69). The calculated heat-loss is 1 423 920 Btu per hour.**

**Conditions.** Air recirculated and inside temperature maintained at 60°. Velocity of air through heater, from 1 000 to 1 200 ft per min. Velocity of air at last outlet in duct system, 1 275 ft per min. Temperature of air delivered by heater, 145°.

**Weight of Air to be Circulated per Minute.** This is

$$1\,423\,920 / [0.24(145 - 60)60] = 1\,163 \text{ lb}$$

**Size of Heater.** This condition, 60° initial and 145° final temperature requires a heater five stacks deep (Table LI), and a velocity of 1 000 ft per min. through free area at a temperature of 70°. The volume of air per minute measured at 70°, to be handled by the heater and fan is

$$1\,163 / 0.075 = 15\,506 \text{ cu ft}$$

**The FREE AREA required is:**

$$15\,506 / 1\,000 = 15.5 \text{ sq ft}$$

Assuming a 60-in length of section with loops 5 in on centers, the free area per section is 0.92 sq ft (Table XLVIII). The number of sections per stack is

$$15.5 / 0.92 = 17$$

**The total number of sections required is**

$$5 \times 17 = 85$$





Table I.II. Speeds, Capacities and Horse-Powers, American Sirocco Single-Inlet, Standard-Width Fans  
American Blower Company

Air-temperature, 70° F. Ratio of total to static pressure, 1.15. Ratio of velocity to static pressure, 0.15. Fifty-percent opening									
no- nbs	net er of feet in ches	Maintained resistance or static pressure in inches of water-gauge	$\frac{1}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2
4	24	C. F. M.*	425	3480	4260	4920	5500	6020	690
		R. P. M.	285	320	391	453	505	554	636
		B. H. P.	.344	.526	.97	1.485	2.08	2.725	4.
4½	27	C. F. M.	470	4410	5400	6205	6970	7620	884
		R. P. M.	200	284	348	402	449	492	561
		B. H. P.	.308	.664	1.215	1.86	2.62	3.44	5.
5	30	C. F. M.	790	5450	6650	7690	8600	9416	108
		R. P. M.	180	256	313	362	403	443	5
		B. H. P.	.378	.811	1.492	2.295	3.225	4.22	6.
6	36	C. F. M.	460	7835	9580	11060	12350	13540	156
		R. P. M.	150	214	260	302	336	369	4
		B. H. P.	.541	1.06	2.14	3.28	4.6	6.01	9.
7	42	C. F. M.	425	10670	13050	15070	16800	18425	212
		R. P. M.	129	183	223	259	288	316	3.
		B. H. P.	.731	1.57	2.9	4.44	6.22	8.15	12
8	48	C. F. M.	720	13920	17000	19700	22000	24100	278
		R. P. M.	112	160	196	226	252	277	3
		B. H. P.	.954	2.045	3.76	5.78	8.14	10.61	16.
9	54	C. F. M.	950	17615	21500	24860	27800	30440	351
		R. P. M.	100	142	174	201	224	246	21
		B. H. P.	.206	2.58	4.73	7.26	10.22	13.38	20
10	60	C. F. M.	150	11760	15000	17750	20300	22650	264
		R. P. M.	90	128	156	181	202	222	21
		B. H. P.	.423	3.17	5.81	8.95	12.55	16.48	25.

12	72	C. F. M. R. P. M. B. H. P.	21 800 75 2.11	31 350 107 4.54	38 300 130 8.35	44 240 151 12.81	49 400 168 18.0	54 130 185 23.55	59 45
13	78	C. F. M. R. P. M. B. H. P.	25 600 69 2.465	36 800 99 5.31	45 000 120 9.8	52 000 140 15.0	58 100 155 21.1	63 600 171 27.6	73 500 197 43.5
14	84	C. F. M. R. P. M. B. H. P.	29 650 64 2.87	42 650 92 6.15	52 100 113 11.33	60 200 130 17.4	67 300 144 24.45	73 700 158 32.0	85 000 183 49.2
15	90	C. F. M. R. P. M. B. H. P.	34 100 60 3.27	49 000 86 7.06	59 900 104 13.0	69 230 121 19.93	77 500 135 28.0	84 700 148 36.6	97 800 171 56.4
16	96	C. F. M. R. P. M. B. H. P.	38 800 56 3.73	55 900 80 8.0	68 100 98 14.6	78 750 112 22.65	88 400 126 31.8	96 500 139 41.6	111 800 160 65.1
17	102	C. F. M. R. P. M. B. H. P.	43 800 53 4.21	63 100 75 9.03	77 000 92 16.75	89 000 106 25.6	99 900 119 35.9	109 000 130 46.9	126 000 150 73.5
18	108	C. F. M. R. P. M. B. H. P.	49 200 50 4.72	70 750 71 10.15	86 400 87 18.8	99 900 100 28.65	12 000 112 40.3	122 000 123 52.6	141 500 142 82.5
19	114	C. F. M. R. P. M. B. H. P.	54 750 47 5.25	78 750 67 11.3	96 900 83 20.9	111 000 95 31.9	24 500 106 45.0	136 000 117 58.6	157 200 134 91.8
20	120	C. F. M. R. P. M. B. H. P.	60 600 45 5.88	87 300 64 12.5	106 800 78 23.7	123 000 91 35.4	138 000 101 49.7	150 800 111 65.0	174 500 138 101.8

Double-inlet fans have approximately double the capacities of single-inlet fans and require for their operation, under the same conditions, approximately twice the power. The "per-cent opening" refers to the opening used for the rating given from the test-data.

\* C. F. M. denotes cubic feet per minute, R. P. M., revolutions per minute and B. H. P., brake horse power.

The total heating-surface is

$$85 \times 16 = 1\,360 \text{ sq ft}$$

Weight of Steam or Condensation per Hour. This is

$$1\,360 \times 1.09 \text{ (Table LI)} = 1\,482 \text{ lb}$$

The equivalent amount of direct radiation is

$$1\,482/0.25 = 5\,929 \text{ sq ft}$$

**Design of Duct System.** The round ducts will be designed for equal-friction pressure-loss per foot of length. The final velocity at the last or most remote outlet from fan will be taken at 1275 ft per min. The friction pressure-loss for this velocity, as read from the diagram in Fig. 64, is 0.25 in of water per 100 ft of length. There are to be eighteen outlets. The total volume of air to be discharged, measured at 145° F., is

$$1\,163/0.065 = 18\,000 \text{ cu ft per min}$$

or

$$18\,000/18 = 1\,000 \text{ cu ft per min per outlet}$$

The cross-sectional area of the outlet or last section is 1 000/1 275 sq ft, corresponding to a circular section with a diameter of 12 in. The branch-outlets may all be made the same size and provided with dampers to adjust or equalize the flow. The friction pressure-loss in the duct system is therefore

$$(212/100) \times 0.25 = 0.53 \text{ in of water}$$

The size of each section of duct is determined by locating the quantity of air at the right of the diagram and passing horizontally to the intersection with the 0.25-in pressure-loss line.

Table LX. Data for Design of Ducts in Fig. 60

Section	Quantity of air in cubic feet per minute 145° F.	Duct-diameter in inches	Velocity in feet per minute	Measured length plus allowance for elbows, in feet
A	1 000	12	1 275	25 + [1 × (6 + 3)] = 34
B	2 000	16	.....	15
C	3 000	18 ½	.....	15
D	4 000	21	.....	15
E	5 000	23	.....	15
F	6 000	25	.....	15
G	7 000	26	.....	15
H	8 000	28	.....	15
I	9 000	29	.....	35 + [2.4 (6 + 10)] = 71
J	18 000	38	2 285	.....
				Total length = 212

**Selection of Fan for Draw-Through Arrangement.** The static pressure rating required, referred to a temperature of 70°, is:

Pressure-loss in heater (data from Table LVI) = 0.26 in

Pressure-loss in duct (data from chart, Fig. 64) = 0.53 in

Total = 0.79 in

The actual pressure-loss will be somewhat less, owing to the fact that the air-temperature is higher (145° F.) and the density less than for air at 70° F. The actual estimated pressure-loss is therefore assumed to be  $\frac{3}{8}$  in.

The volume of air the fan must handle in this example is 18 000 cu ft per min, measured at 145° F. As stated under Rating of Fans, to maintain a constant pressure the tabulated speed, volume and horse-power must be multiplied by the square root of the ratio of densities, or

$$\sqrt{0.075/0.066} = 1.07 \text{ (nearly) (Table II)}$$

We therefore select from Table LIX a fan having a capacity, measured at 70° F., equal to

$$18\,000/1.07 = 16\,822 \text{ cu ft per min (approximately 17\,000)}$$

and operating with a static pressure of  $\frac{3}{8}$  in. A No. 8 Sirocco fan fulfills this requirement. The tabulated speed and horse-power when multiplied by the factor 1.07 gives

$$196 \times 1.07 = 210 \text{ R.P.M.}$$

$$3.76 \times 1.07 = 4.02 \text{ brake horse-power}$$

**Selection of Fan for Blow-Through Arrangement.** In this case the fan may be called upon to handle air at a temperature of 0° F., or lower. Assuming the same weight of air, or 70 000 lb per hr, to be handled by the fan at a static pressure of  $\frac{3}{8}$  in, the volume at 0° is

$$70\,000/(0.086 \times 60) = 13\,566 \text{ cu ft per min}$$

According to Table LVIII, the ratio between the speed, volume and power necessary to produce the same pressure for air at 0° and air at 70°, is found to be 0.932. We therefore choose a fan with a capacity of

$$13\,566/0.932 = 14\,557 \text{ cu ft of air at 70°}$$

with a static pressure of  $\frac{3}{8}$  in.

**Steam-Engine.** When high-pressure steam is available an automatic high-pressure steam engine is frequently employed for fan-driving, and the exhaust from the engine is used in the first section of the heater.

**Selection of Motor for Fan-Driving.** It is considered good practice to add 10 to 15% to the brake horse-power, as determined from the fan-tables, to the rating of the motor, to allow for a possible overload due to the fact that the motor may not be operated under exactly the same conditions as to pressure and speed as those under which it was originally rated. For the preceding example (Blow-Through Arrangement) a 5-horse-power motor would be selected.

**Additional Heating Requirement.** It is frequently desirable to proportion the heating-apparatus large enough so that the fan may be shut down at night and started up about two hours before the shop or factory is opened in the morning. In this event it may be safely assumed that the temperature of the air in the building will not be below 30° F. when the fan is started, and that the air is all recirculated. The fan and heater must be of sufficient capacity to care of the heat-loss from the building, including the infiltration, and to warm up the contained air from 30° to 60° in two hours. Assuming the same data as given in the preceding example, the additional heat required will be, if the cubic contents of the building are 328 000 cu ft,

$$(328\,000 \times 0.08 \times 0.24 \times 30)/2 = 94\,464 \text{ Btu per hr}$$

This amounts to an increase of approximately 7% in the heating requirement as previously calculated, and is readily provided for by increasing the steam pressure carried in the heater to approximately 10-lb gauge. Catalogues, bulletins, etc., on the subject of hot-blast heating, air-washing and humidification may be obtained from the American Blower Company, the B. F. Sturtevant Company, the Buffalo Forge Company, and the Carrier Air Conditioning Company.


### Ventilation

**Natural and Mechanical Ventilation.** Ventilation, whether NATURAL or MECHANICAL, consists in the displacement of vitiated air from an apartment and

replacement by fresh air. To state that the air in an apartment is renewed any given number of times per hour is not strictly accurate, as a positive change does not actually occur; the incoming air mixes with and dilutes the foul air to a point suitable for healthful respiration. In NATURAL-VENTILATION systems the movement of the air in flues, ducts, etc., is induced solely by the thermal head produced by the difference between the density of the column of air in the ducts and that of the outside atmosphere; the higher the temperature in the ducts the more powerful the draft. The direction and velocity of the wind materially affect the natural ventilation, retarding or accelerating the movement of the air through ducts and flues, according to the exposure of the building and the position of inlets and outlets. In MECHANICAL VENTILATION the movement of air is maintained by means of various types of fans, driven by a steam-engine, electric motor, or other prime mover. With fans of known efficiencies the results can be accurately estimated. The principal advantages of the use of mechanical systems of heating and ventilation have already been stated under Hot-Blast Heating.

**Systems of Ventilation.** Ventilation systems are also broadly divided into two general classes known as the UPWARD SYSTEM and the DOWNWARD SYSTEM. The UPWARD SYSTEM (Fig. 70) is generally used for audience-rooms where there is a strong natural tendency for the heat given off by the large number of occupants to rise and take with it the vitiation-products due to respiration. The AIR IS SUPPLIED NEAR THE FLOOR-LINE through mushroom ventilators in the floor, or through the hollow pedestals of the chairs themselves, or through low registers. THE VITIATED-AIR OUTLETS ARE IN OR NEAR THE CEILING. This system makes it rather difficult to heat the room in advance of the arrival of the audience as the outlets allow the warmed air to escape almost as rapidly as it can be introduced. The DOWNWARD SYSTEM is very generally used in school-rooms, hospitals, institutions, etc. where the occupants are not as closely placed as in the former case, and a more even distribution of air and more uniform heating can be secured when the AIR IS SUPPLIED EIGHT FEET OR MORE ABOVE THE FLOOR, and the VITIATED AIR REMOVED AT OR NEAR THE FLOOR-LINE. On account of the elevation of the inlets above the heads of the occupants there is little liability of drafts, and if the outlets are on the same side wall as the inlets there is very little opportunity for short-circuiting between inlet and outlet, so that the incoming air must flow out across the room to the cold outside wall before it can cool and drop to the floor-level. It is, however, necessary in the downward system, to overcome the natural tendency of the warmed air from the bodies of the occupants to rise and oppose the uniform downward tendency of the incoming fresh air. The selection of either system depends entirely on the conditions to be met. These have been outlined in the above paragraphs.

**Distribution of the Air.** In general, it should be observed that whether upward or downward ventilation is employed there should always be a definite plan of vitiated-air removal, designed to provide for uniform distribution and



SIZES OF "ABC" MUSHROOM VENTILATOR.

Size.	Approximate Inside Diameter.	Approximate Weight
4	4 1/4	6 lb.
5	5 1/4	10 lb.
6	6 1/4	15 lb.

Fig. 71. Section through A B C Mushroom Ventilator

prevent short-circuiting between inlets and outlets. A practically complete diffusion can only be attained when inlet and outlet are placed in the same inside wall, with the former at least from 7 to 8 ft above the latter. **MULTIPLE**




Fig. 72. Heating and Ventilating Symbols

**INLETS** and **MUSHROOM VENTILATORS**, in order to secure a better mechanical distribution of the air, are being made use of in many systems of upward ventilation for audience-rooms with fixed seats. In this case a false floor or **PLENUM CHAMBER** must be constructed just below the main floor through which the air



to be supplied. Mushroom ventilator-heads (Fig. 71) are then located under every second or third seat and adjusted to give a uniform discharge of tempered air over the entire seating-area. These heads are either mounted on an ad-




Fig. 73. Heating-boiler Connections

stable spindle (Fig. 70), which is supported centrally in the cast-iron floor-plate or flange, or else they have a non-adjustable spindle similarly supported, and are equipped with a control-damper. In either case the adjustable head or

damper must be locked positively in the finally adjusted position. In the case of concrete floors it is very desirable to use a cast-iron sleeve and flange (Fig. 70) rather than a galvanized sleeve and cast-iron flange.

**The Effect of Vitiated Air.** The amount of CARBON DIOXIDE present in vitiated air has been, until recently, quite generally understood to be the element of danger that should be kept within safe limits. Dr. Ira Remsen has pointed out that the presence of carbon dioxide in itself is not dangerous to health except that it reduces the supply of oxygen by displacing it. Carbon dioxide is not poisonous, but the ORGANIC IMPURITIES that are exhaled at the same time with other gases that are given off may prove a menace to health. The ill effects of breathing air in a poorly ventilated room are due to the small quantities of decomposing organic matter and unhealthful gases. The carbon dioxide generated by the lungs and given off at the same time as the other impurities serve more or less as an indicator of the presence of the real danger. Any lowering of the oxygen-supply that is actually required for the proper and necessary transformation of the potential heat-value of the food into the physical and nervous energy required to keep the human machine running, and to readily supply the additional demand made upon that machine to perform external work, means that industrial workers who perform their duties in a vitiated atmosphere do so at the expense of a lowered vitality, and are naturally less productive. Satisfactory ventilation consists not only in constantly supplying the room with a pure condition, fresh air FREE FROM DUST AND OTHER IMPURITIES, at the proper temperature and WITH THE PROPER AMOUNT OF MOISTURE PRESENT, but also in efficiently removing the vitiated air. This cannot be positively accomplished during the heating-season by simply opening the doors and windows. Some mechanical means must be employed. Many physicians, however, do not believe in MECHANICAL VENTILATION for hospitals, and advocate ventilation by the OPEN-WINDOW METHOD; and many hospitals are now constructed without any provision for mechanical ventilation except for the toilets and operating rooms for which exhaust-fans are provided.

**Relation between Humidity and Temperature.** The proper and healthful RELATIVE HUMIDITY OF THE AIR in buildings has only in recent years been given the thought and attention it rightfully deserves. Heated or warmed air, whether purposely introduced into a building for warming, or naturally entering by infiltration, on being expanded by heat, has its percentage of moisture or relative humidity lowered, and consequently its CAPACITY FOR ABSORBING MOISTURE greatly increased. There is, therefore, experienced the sensation due to so-called DRY HEAT. This causes an excessive and unnatural evaporation of moisture from the skin and from the membranes of the respiratory organs. Evaporation takes place by the direct application of heat and is essentially a refrigerating and cooling process. The abstraction of heat from the body for this purpose, naturally tends to lower the surface-temperature, and one feels several degrees cooler than the temperature recorded by the thermometer in the room. Dr. H. M. Smith's many observations and experiments upon the sensations produced by DIFFERENT PERCENTAGES OF SATURATION, led him to make the following statement: "It may be accepted as a cardinal rule that if a room is at 68° and is not warm enough for any healthy person, it is because the RELATIVE HUMIDITY is too low." A STANDARD RELATIVE HUMIDITY may be obtained when mechanical ventilation is used by the addition of a HUMIDIFIER to the system. The subject of AIR-CONDITIONING is fully treated in Heating and Ventilating, Vol. I, by Harding and Willard.

**Requirements for Good Ventilation.** There is quite a diversity of opinion among various authorities as to what constitutes GOOD VENTILATION in any

stances. The following data by G. D. Small represent good practice in this  
pect:

**Types of Buildings. Air-Changes to be Allowed**

**OFFICE-BUILDINGS** { Portions above grade..... One change per hour.  
Basement, general..... Four changes per hour.  
Mechanical plant..... Ten changes per hour.

**FACTORY-BUILDINGS** which have no mechanical or natural ventilation, one  
change per hour. For factories in which large doors from the outside are  
frequently opened, about four air-changes per hour.

**RESIDENCES** which have loose windows, two changes per hour.

**CHURCHES.** Four changes per hour, except small rooms, which should have five  
or six changes per hour. These data for churches contemplate mechanical  
ventilation. The majority of public buildings and many of the factories  
require ventilation or the fan system of heating.

**The Usual Requirements for Air Supplied per Person are as Follows**

**HOSPITALS** { Ordinary..... from 35 to 40 cu ft per min  
Epidemic..... 80 cu ft per min

	Air-change
Detention-rooms .....	6 min
Toilet-rooms.....	6 min
Bath-rooms and duty-rooms.....	8 min
Kitchens.....	3 min
Serving-rooms.....	10 min
Fumigating-rooms.....	10 min
WORKSHOPS.....	25 cu ft per min
CLASS-ROOMS.....	30 cu ft per min
LABORATORIES.....	from 20 to 30 cu ft per min
READING-HALLS .....	20 cu ft per min
SCHOOL-ROOMS.....	30 cu ft per min per child and 40 cu ft per min per adult

**The Usual Time-Intervals for One Air-Change are as Follows**

**HOTELS**

Room	Air-change	Room	Air-change
Engine-room.....	6 min	Café .....	8 min
Kitchen.....	1½-5 min	Lobby under balcony..	8 min
Restaurant.....	6 min	Main lobby.....	20 min
Re-toilet.....	5 min	Banquet-hall.....	15 min
Staircase.....	10 min	Retiring-room.....	10 min
Barber-shop.....	8 min	Kitchens.....	8 min
Living-room.....	15 min	All others.....	15 min
Bed-room.....	12 min	Toilets.....	6 min
Refrigerator.....	8 min		

**LIBRARIES**

Aisles.....	15 min	Inside rooms.....	8 min
Reading-rooms.....	15 min	Corner rooms.....	7 min
Storage-rooms.....	12 min	Toilet-rooms.....	5 min

Laundries should have an air-change every 4 to 6 min.

2. Radiation on sides of buildings subjected to prevailing and cold winds should  
be increased 10% up to the 10th floor and 15% above that floor.

**Ventilation-Laws.** The number of VENTILATION-LAWS has increased rapidly in the last few years, not only as regards the number of states which have added such laws to their codes, but also as to the scope and effectiveness of these statutes. In many cases a special ventilation-officer or commission has been appointed to see to the enforcement and extension of the requirements for compulsory ventilation, so that it behooves the architect or engineer to become thoroughly familiar with the law of the state or states wherein he practices. A summary of the law recently enacted by the legislature of the state of Ohio is given in the following paragraphs as an example of the regulations with which architects and engineers must conform in preparing plans and specifications. This law as well as the law of Massachusetts, attempts to provide very definite regulations for heating and ventilating all classes of buildings. Future legislation in other states will undoubtedly take a more specific form, establishing complete and definite codes for the heating and ventilation not only of public buildings but of workshops, factories and mercantile establishments as well.

**Requirements of the Department of Inspection of the Industrial  
Commission of Ohio for the Heating and Ventilation  
of Public Buildings, Hospitals, Asylums and  
Homes**

**Temperature**

A heating system shall be installed which will uniformly heat the various parts of the building to the following temperatures in zero weather.

**THEATERS AND ASSEMBLY-HALLS.** All parts of the buildings, except storage-rooms, 65° F.

**CHURCHES.** Auditorium, social and assembly-rooms, 65° F. All other parts of the building, except storage-rooms, 70° F.

**SCHOOL-BUILDINGS.** Corridors, hallways, play-rooms, toilets, assembly-rooms, gymnasiums and manual-training rooms, 65° F. All other parts of the buildings, 70° F.

**HOSPITALS, ASYLUMS AND HOMES.** Operating-rooms, 85° F. All other parts of the buildings, except storage-rooms, 70° F.

**Change of Air**

The heating system shall be combined with a system of ventilation which at normal temperature will change the air the following number of times, or supply to each person the following number of cubic feet of air per hour.

**THEATERS.** Parlors, retiring, toilet and check-rooms, six changes per hour.

**AUDITORIUMS.** 1 200 cu ft of air per person per hour.

**ASSEMBLY-HALLS.** When used in connection with a school-building, lodge building, club-house, hospital or hotel, six changes per hour; and in all other assembly-halls, 1 200 cu ft of air per hour per person.

**CHURCHES.** Auditoriums, assembly-rooms and social rooms, six changes per hour.

**SCHOOL-BUILDINGS.** All parts of the buildings, except corridors, halls and storage-rooms, six changes per hour.

**ASYLUMS, HOSPITALS AND HOMES. (1) Rooms with fixed capacity:**

	Adults	Children	Babies
Hospitals, contagious and epidemic.....	6 000	4 000	3 000
Hospitals, surgical and medical.....	3 000	2 400	1 500
Mental institutions.....	1 800	1 800	...
All other buildings.....	1 800	1 500	...

**(2) Rooms with variable capacities:**

Hospitals, contagious and epidemic.....	12 times per hour
Hospitals, surgical and medical.....	12 times per hour
All other buildings.....	6 times per hour

Rooms accommodating four or less persons need not be provided with a system ventilation.

**Radiators**

No radiator shall be placed in any aisle, foyer or passageway of a new theater, assembly-hall or church, but such radiators may be placed in recesses in the walls.

**Registers**

Floor-registers shall be used in theaters, assembly-halls, or hospitals.

Floor-registers, except foot-warmers, shall be used in a school-building.

Floor-registers may be used in churches.

Otherwise all vent-registers shall be placed not more than 2 in above the floor-line, and warm-air registers not less than 8 ft above the floor-line (except when floor registers are used when a change of air is not prescribed).

**Systems to be Installed Where a Change of Air is Required**

The system to be installed when a change of air is required shall be either a gravity or mechanical furnace system, gravity indirect steam system, or hot-water system; mechanical indirect steam or hot-water system, or split steam or hot-water system; except in hospitals, where a direct-indirect system may be used in connection with an exhaust-fan. The fresh-air supply shall be taken from outside the building and no vitiated air shall be reheated. All vitiated air shall be conducted through flues or ducts and be discharged above the roof of the building.

**EXCEPTIONS.** Standard ventilating stoves may be used in the following buildings:

Assembly-halls seating less than 100 persons.

Churches seating less than 100 persons.

School-buildings, hospitals, asylums and homes.

**Furnaces**

Furnaces may be used in all classes of buildings.

**Gravity Indirect Hot-Water or Steam-Radiator Systems**

Indirect hot-water or steam-radiators shall be located in basement fresh-air ducts directly at the base of masonry hot-air flues, and shall be properly connected to same with galvanized-iron housing.

Indirect Radiating-Surface for Heating and Ventilating Purposes

One square foot of radiating-surface shall be provided to heat not more than the following number of cubic feet of air per hour:

Height	Steam	Hot water
First story.....	200	125
Second story.....	250	160
Third story.....	300	200
Fourth story.....	250	235

FOR HEATING WALL-SURFACES AND GLASS-SURFACES. The amount of radiating-surface for the heating of the glass-surface and wall-surface shall not be less than that obtained by adding together the glass-surface and one fourth the exposed wall-surface, both in square feet, and multiplying by the following factors:

Height	Steam	Hot water
First story.....	0.7	1.05
Second story.....	0.6	0.9
Third story.....	0.5	0.75
Fourth story.....	0.4	0.5

ACCELERATING OR ASPIRATING COILS FOR VENT-FLUES. Vent-flues used in connection with a gravity indirect steam or hot-water system shall be provided with accelerating coils placed 1 ft above the vent-openings.

Mechanical Fan Plenum System

This system shall be designed with furnaces, tempering coils or blast-coils so as to furnish heated air, and is to have cleaning-screens, fan plenum chamber, galvanized-iron or masonry horizontal ducts, masonry hot-air flues, electric motor, gas or gasoline engine, or a low-pressure steam-engine operating on a steam-pressure not to exceed 35-lb gauge to operate fan and such other device as is necessary to make this a complete working system. All parts and apparatus in connection with the installation are to be of ample size to make a perfectly free and easily working system, which must thoroughly heat all portions of the building without forcing.

Velocity of Air

The velocity of the air traveling through ducts, flues, etc., shall never exceed the following number of feet per minute:

Ducts, Flues, etc.	Feet per minute
Fresh-air screens, small mesh.....	600
Fresh-air ducts, gravity system.....	300
Fresh-air ducts, mechanical system.....	850
Tempering coils, gravity system.....	300
Tempering coils, mechanical system.....	1 000
Furnaces, gravity system.....	400
Furnaces, mechanical system.....	900
Trunk-ducts, mechanical system.....	1 000
Laterals, branches and single ducts, mechanical system.....	750
Vertical flues, mechanical system.....	500

Vertical warm-air flues, gravity system, first story.....	300
Vertical warm-air flues, gravity system, second story.....	350
Vertical warm-air flues, gravity system, third story.....	390
Vertical vent-flues less than 20 ft high.....	300
Vertical vent-flues from 20 to 33 ft high.....	350
Vertical vent-flues from 33 to 46 ft high.....	390
Vertical vent-flues from 46 to 60 feet high.....	440
Warm-air registers.....	300
Cold-air registers.....	300

### Maximum Speed of Fans

The maximum speed of fans used in connection with either an exhaust or warm-air system of heating or ventilating, under normal conditions, shall never exceed the following:

Diameter of fan in inches....	18	24	36	48	60	72	96	120	180
Revolutions per minute.....	700	550	400	300	225	175	150	125	75

### Location of Heater-Room

The heater-room shall be located under the auditorium, stage, lobby, passageway, stairway or exit of a theater; nor, under any exit, passageway, public hall or lobby of an assembly-hall, church, school-building, asylum, hospital or home. This applies to new buildings, and a changed location of a heater-room in an existing building. No cast-iron boiler carrying more than 10-lb pressure or a steam boiler carrying more than 30-lb pressure shall be located within the main body of any school-building.

### Standard Fire-Proof Heater-Room for New Buildings

All furnaces and boilers, including the breeching, fuel-rooms and firing-spaces, shall be enclosed by brick walls not less than 12 in thick, or by monolithic concrete walls not less than 8 in thick. The ceiling over the same shall not be less than the following: reinforced-concrete slab, 4 in thick; brick arches, 4 in thick, covered with 1 in of cement mortar and supported by fire-proof steel with the necessary tie-rods; or hollow-tile arches, 6 in thick, covered with 2 in of concrete, covered on the under side and supported by fire-proof steel with the necessary tie-rods.

### Specifications for Furnace-Work

The following form is given as a guide to architects in preparing the specifications for furnace-work:

SPECIFICATIONS FOR FURNACE-WORK IN RESIDENCE FOR MR.....TO BE  
 BY.....ARCHITECT

**Furnace.** Furnish and set up complete, where shown on basement-plan, one (same as shown on plan) furnace, or approved equal, portable-pattern, with double casings. Connect the furnace with the chimney with a No. 22 galvanized-iron smoke-pipe of same size as the collar on the furnace; all bends or turns to be made with piece elbows; the pipe to be strongly supported by wire, and to be kept below the ceiling.

**Pit.** Excavate for and build a cold-air chamber under the furnace not less than 18 in deep, with 8-in brick walls, laid and plastered with cement; also

cement the bottom of the chamber. Build the cold-air duct under cellar-floor, where shown on plan, — ft long, 14 in deep in the clear, and — in wide, with sides of hard brick in cement, and with the sides and bottom smoothly plastered with cement. Cover the duct with 3-in flagstones with tight joints, leaving opening of proper side for the wooden box to be built by the carpenter (wooden box should be included in carpenter's specifications).

**Hot-Air Pipes.** Furnish and properly connect with furnace and register-boxes leaders and stacks of the following sizes, all to be made of bright IX tin, and the stacks are to be double with an air-space. All turns in leaders to be made by three-piece or four-piece elbows, and the stacks to have boots or starters of approved pattern.

Sizes of Pipes and Registers

Hall.....	11"	leader,	no stack	12" X 14" register.
Parlor.....	11 1/2"	leader,	no stack	12" X 15" register
Dining-room.....	12"	leader,	no stack	12" X 15" register
Library.....	10 3/4"	leader,	no stack	12" X 14" register
Chamber No. 1.....	10"	leader,	4" X 15" stack, 10" X 14" register	
Chamber No. 2.....	9"	leader,	4" X 13" stack, 10" X 12" register	
Chamber No. 3.....	8 1/2"	leader:	4" X 13" stack, 10" X 12" register	

**Registers.** All registers are to be of sizes given in the foregoing list, of the (...name...) or approved equal manufacture; japanned, except those in the first story, which are to be electro-bronze-plated. All floor-registers are to be set in iron borders corresponding with the registers.

**Register-Boxes.** All register-boxes to be made double; for first-story boxes the JOISTS ARE TO BE LINED WITH TIN and provided with CEILING-PLATES the full size of the registers, with plaster-collars attached, so that pipes and boxes can be removed without disturbing the plastering or defacing the ceiling.

**Miscellaneous.** All horizontal pipes in the basement are to be round, and where they pass through partitions they are to be provided with collars, so that the pipes can be removed without disturbing the plastering. All leaders are to be provided with dampers and tin tags designating the different rooms they supply; and whenever pipes run near woodwork the same is to be properly covered with tin and protected from any danger from fire. The contractor is to remove all rubbish made by him, clean up all ironwork, leave the whole apparatus in complete working order, and furnish a poker of proper size.

**Guarantee.** The contractor is to guarantee, if he furnishes the heating drawings, that the furnace shall, under proper management, heat all rooms with registers connected with the furnace, to 70° F., when the temperature outside indicates 0°. In the event of the failure of the furnace to do this the contractor, at his own expense and without unnecessary delay, is either to make the furnace heat said rooms or substitute another furnace that will heat them.

Hot-Air-and-Water Combination-Furnaces

**Combination-Furnaces.** It is quite difficult, if not impossible, to heat dwellings covering throughout, more than 1 400 sq ft with warm air alone. On account of the much larger exposure and the increased length of leaders it becomes necessary to supplement the warm air with an auxiliary heat which



be carried to remote and exposed parts of the house, and which will not be affected by pressure of wind or long and crooked pipes. For supplying this dry heat, hot water has been found best adapted as a rule, and a variety of COMBINATION-FURNACES are now made which contain provisions for heating a room which may be carried by pipes to radiators located in those parts of the house most difficult to heat by warm air. Such combination-systems have been used with success. The construction of the parts for heating the water varies with different makes of furnaces. Some furnaces have a portion of the boiler hollow, and the water is heated there; others have a separate heater connected over the fire-pot. As a rule, the parts of the house which should be heated by the hot water are the halls, bath-rooms, and perhaps the rooms on the north or west sides of the house. The same rules govern the location of the radiators and piping and the manner of installing as in an entire hot-water plant.

### Specification for Hot-Water Heating-Apparatus in a Residence

This specification contemplates a complete upfeed two-pipe gravity hot-water heating system, to be installed in accordance with the drawings covering the

**Boiler.** Furnish and set up in cellar, where shown on plan, one (. . . name . . .) boiler, or approved equal, guaranteed free from all flaws and defects. Heater to be set on a substantial foundation of hard brick laid in cement mortar and put in by the heating-contractor. Furnish and deliver one set of tools, consisting of one poker, one slice-bar and one fine brush and handle.

**Smoke-Pipe.** Connect the boiler to the chimney by means of smoke-pipe of No. 22 galvanized iron, the diameter of the pipe to be equal to the diameter on the heater.

**Thermometer.** The boiler is to be provided with one thermometer registering 0° F. to 250° F., and one Standard altitude gauge.\*

**Water-Connections and Blow-off.** Feed-water with its supply-pipe will be set within 6 ft of the boiler by the plumber and left with one ¾-in cast-iron pipe for boiler-connection, which is to be made by this contractor, with suitable cock. Draw-off cock to be placed on lowest point of system and to be suitable for hose-attachment.

**Risers.** Furnish and run all necessary flow and return-mains of ample size, connecting them to radiators with risers of ample size to insure the free flow of water to and from the radiators. All connections from risers to radiators made below floors.

**Quality of Materials.** All materials used in the construction of this apparatus shall be the best of their respective kinds, all fittings to be heavily beaded and made of the best gray iron with clean-cut threads, and, when practicable, Y's and L's are to be used.

**Pipes.** The ends of all pipes used in the construction of this apparatus shall be reamed and all obstructions removed before pipes are placed in position. Flow and return-mains in the basement are to be supported by neat, strong, metal hangers, arranged to suit expansion and contraction, and properly braced to timbers overhead. At all points where pipes pass through ceilings,

altitude-gauge indicates the amount of water in the system and is a convenient point at which avoids the necessity of consulting the gauge-glass in the tank. It is to be opened with if desired.

floors, or partitions, tin thimbles are to be provided and the holes protected with floor or ceiling-plates.

**Expansion-Tank.** The expansion-tank is to be constructed of galvanized iron and is to be furnished with a proper gauge-glass with brass mountings complete. It is to be placed at least 3 ft above the highest radiator in a suitable place and supported on a proper shelf. From this tank an overflow-pipe will run to the basement or other suitable place with a vent-pipe through the roof properly flashed.

**Radiators.** Furnish, set up, and pipe the following radiators:

Rooms	Number of radiators	Radiating-surface, sq ft
Main hall.....	1 indirect radiator	108
Sitting-room.....	1 indirect radiator	120
Library.....	1 direct radiator	40
Dining-room.....	1 direct radiator	60
Sitting-room chamber.....	1 direct radiator	40
Library chamber.....	1 direct radiator	44
Dining-room chamber.....	1 direct radiator	36
Kitchen chamber.....	1 direct radiator	32
Bath-room.....	1 direct radiator	32
	9 radiators	512

In all there are to be 284 sq ft of direct surface and 228 sq ft of indirect; total surface, 512 sq ft. The direct radiators to be (...name...) hot-water pattern or approved equal, 38 in high.

**Air-Valves.** Each radiator is to be provided with a nickel-plated key-type air-valve.

**Radiator-Valves.** Each direct radiator is to be promptly connected to the system of piping with a quick-opening nickel-plated radiator-valve and union elbow.

**Indirect Radiation.** The indirect radiators are to consist of two stacks (...name...) hot-water radiation, or approved equal, connected together with tight joints and firmly suspended from the basement-ceiling by suitable wrought-iron hangers. The stacks are to be so piped and hung as to permit a noiseless and constant flow throughout of the heated water. Each stack is to be enclosed in a galvanized-iron chamber with proper fresh-air inlet-duct and a corresponding outlet-duct for warm air, connected to the register in the room which the stack is intended to heat. The registers are to be of (...name...) pattern, electro-bronze-plated, and of the following sizes: main hall, 12 by 19; sitting-room, 14 by 22 in. Registers are to have floor-borders and to be set in register-boxes. The duct connecting the stack and register is to be so arranged that all fresh air coming in will be properly heated and conveyed, with least loss, to its destination. In arranging indirect boxes, care is to be exercised in getting ample space for cold air under the stack, and corresponding space for warm air over the stack.

**Covering of Pipe.** All flow and return-pipes and fittings in cellar above floor are to be properly covered with 1-in hair-felt neatly sewed up in casing.

and painted one coat of good white lead, or covered with asbestos or magnesia sectional covering, with canvas cover, and secured by lacquered-brass bands.

**Boiler-Covering.** All exposed parts of the boiler, except the front, are to be covered with plastic asbestos,  $1\frac{1}{2}$  in thick, neatly applied and troweled, smooth.

**Workmanship.** All work is to be done in a neat, substantial and workmanlike manner, and the apparatus, when completed, is to be thoroughly tested and left in good working order.

**Guarantee.** The contractor is to guarantee, if he is to furnish the heating-drawings, that the apparatus he installs will be of ample capacity to evenly maintain a temperature of  $70^{\circ}$  F. in the rooms in which radiators are located, when the outside temperature is at zero, and that the apparatus throughout shall have a free circulation when in operation.

### Steam-Heating for Residences

**General Requirements.** For very large residences, the author would recommend steam-heat, all of the principal rooms to be heated by indirect radiation, and only the bath-room, halls, and perhaps the attic and one or two rooms on the north side, which generally includes the dining-room, by direct radiation. For dining-rooms a special direct radiator, containing a warming-pan, is made. The air-supply to the indirect stacks should be very large and provided with a damper, so that the supply may be regulated according to the weather. The boilers used in residence-heating are generally of the cast-iron sectional type described on page 1278. The single-pipe system is commonly used in dwellings, all indirect radiators, however, being two-pipe.

### Specification for a Low-Pressure Steam-Heating Apparatus for Heating by Direct Radiation

**Attention.** This specification is intended to cover everything necessary to finish and install in the above-mentioned building a complete steam-heat-system in strict accordance with the plans and this specification, as prepared by \_\_\_\_\_, architect.

**Plans.** The drawings herewith are intended to show only the location of the boiler, piping and radiators; the arrangement of the piping will be left largely to the contractor, subject to the approval of the architect.

**General Requirements.** This contractor is to provide all necessary tools and appliances for the erection and completion of the work, and when completed, to remove all apparatus, refuse and debris from the building and grounds, leaving the work in a clean, uninjured and perfect condition. No cutting or description tending to weaken the building structurally is to be undertaken without consulting the architect. This contractor is to be fully responsible for the safety and good condition of the work and material embraced in this contract at the completion and acceptance of the same. All work is to be of the best quality, and should at any time improper, imperfect, or unsound material or workmanship be observed, whether before or after same has been built into the structure, this contractor, upon notice from the architect, is to remove the same and substitute good and proper material and workmanship without delay or cost thereof, in default of which the architect is to effect same by other means as may be deemed best, and is to deduct the cost of such alterations from the money due the contractor under this contract.

**System.** The heating is to be effected by direct radiation distributed throughout as shown on the drawings, and the circulation of the steam is to be by one-pipe circuit system.

**Boiler.** This contractor is to build the foundation for the boiler, as shown, 12 in deep, of common hard brick laid in cement mortar. He is to leave an ash-pit for the boiler of proper size, 12 in deep, cemented, and made water-tight. He is to furnish and set up one (...name...) cast-iron sectional or approved equal, boiler, provided with 6-in low-pressure brass-cased steam gauge, water-gauge, and glass, gauge-cocks, combination-column, safety-valve and blow-off valves, and all other usual and necessary trimmings to complete the boiler,\* and a full set of fire-tools, consisting of one slicing-bar, one hammer, one poker, and a cleaning-brush. He is to cover the boiler with 1 1/4-in of asbestos cement, neatly troweled to a smooth finish.

**Water-Supply.** The plumber is to bring the water-supply to within 6 ft of boiler, but this contractor is to make connection with boiler with 3/4-in iron pipe, stop-cock and check-valve.

**Smoke-Pipe.** Contractor is to connect the boiler with the chimney with round smoke-pipe made of No. 22 galvanized iron with suitable balance-dampers. This connection to be of same size as left for this purpose by maker of boiler.

**Main Pipes and Risers.** The steam-main is to be run full size for the entire length and provided with an automatic air-vent at the end of the run. It is to be of ample size to carry all the risers and radiators attached to the system and is to be graded 1 in in 10 ft in the direction of the flow. From the top of this main the various branches are to be taken to radiators and risers, the connections for which are to be so made that no traps are formed. If a trap cannot be avoided, a drip connected with the return-main is to be installed. Radiators on first story are to be connected direct to steam-main. Radiators for the second and third floors may be taken off the same riser. The main after serving the last radiator, is to drop below the water-line of the boiler and its size reduced, and it is to run back to the boiler as a wet-return-main. The steam-main at the end of the run is to be 24 in or more above the water-line of the boiler. The boiler is to be installed in a pit if necessary to accomplish this.

**Pipes and Fittings.** All pipe used throughout is to be of the best quality wrought-iron or steel pipe of standard weight and thickness, with the ends reamed, free from imperfections, and true to shape. All threads are to be clean-cut, straight and true. All fittings are to be of the best heavy gray iron with taper-threads, and are to be heavily beaded. No inferior pipe or fittings will be allowed.

**Supports.** All piping is to be supported by approved expansion-hangers and rollers, not to exceed 10 ft apart. Neat cast-iron floor and ceiling-plates are to be used where pipes pass through floors, ceilings and partitions.

**Radiators.** Direct radiation is to be furnished to the amount enumerated on the drawings of the (...name...) make, or approved equal.

**Radiator-Valves.** The radiators are to be furnished with removable diamond type union valves, rough nickel-plated, and are to have hard-wood hand-wheels.

**Air-Valves.** Radiators throughout the entire building are to be furnished with (...name...) automatic air-valves, or approved equal.

\* For house-heating plants it is well to specify also "one automatic damper-regulator of approved pattern, with connection for operating draft-door and cold-air check."

**Pipe-Covering.** All pipes in the cellar above the floor are to be covered with 1-in asbestos (or magnesia) sectional covering with canvas cover and secured by lacquered-brass bands.

**Painting and Bronzing.** All radiators and exposed pipes in rooms or halls are to be neatly painted two coats of best radiator-enamel, or bronzed in desired color.

**Finally.** When completed, the apparatus is to be tested to 10-lb steam-pressure and made tight at that pressure, said test to be conducted under the supervision of the architect. Fuel for the test is to be furnished by the owner, when accepted, the apparatus is to be turned over to the owner in complete working order. All valves and stuffing-boxes are to be properly packed. The plant completed in all its parts, it being understood that this contractor shall furnish all miscellaneous material, tools, labor, etc., necessary to complete the work in a first-class and workmanlike manner.

**Guarantee.** This contractor is to guarantee that when the apparatus is completed it will be free from all mechanical defects and, if he is to furnish design and layout, that the installation shall be of ample capacity to heat rooms where radiation is placed to a temperature of 70° F. when the outside temperature is 0° F.

## CHIMNEYS\*

By

L. A. HARDING

FORMERLY PROFESSOR OF MECHANICAL ENGINEERING, PENNSYLVANIA STATE COLLEGE

**Draft.** To burn a fuel at a given rate (pounds per square foot of grate-surface per hour) requires a definite weight of air to be supplied for combustion. The air passes under the grate and through the fuel-bed and meets with considerable resistance in its flow, not only through the fuel-bed, but through or around the boiler-tubes and smoke-flue or breeching. The motive force causing the air-flow in a natural-draft plant is supplied by the chimney. The difference between the atmospheric pressure and the pressure existing at any point in the furnace or in the flue is termed the **DRAFT** at that particular point. This pressure is ordinarily measured by means of a U tube filled with water, the draft being recorded in inches of water, and is the difference in the heights of the water columns in the two legs of the U tube.

**Height.** The **INTENSITY OF DRAFT** that a chimney is capable of producing at the base is a function of its height, the temperature of the flue-gases, and the temperature of the outside air, which is generally assumed to be 60°. The temperature of the flue-gas is ordinarily assumed to be 550°. The intensity of draft produced, per foot height, measured in inches of water is

$$H = 0.0071 L$$

$L$  = height of chimney above grate, in feet. The flue-gas temperature is taken at 550° and the outside temperature at 60°. Ordinarily  $0.8H$  is taken as representing the **AVAILABLE DRAFT**, in order to allow for the cooling of the chimney gases. Then  $0.8H$  must be equal to or greater than the sum of the expected draft-losses as given in the following paragraphs.

**Draft-Losses.** The **DRAFT-LOSSES** through the fuel-bed depends upon the rate of combustion required and the kind of fuel. This loss may be approximated by using the data in Table I.

The **LOSS OF DRAFT** between the grate or furnace and a point just beyond the damper-box of a boiler is about as shown in Table II when the boilers are operated at normal rating; bituminous coal burned at the rate of from 25 to 50 lb per sq ft of grate-surface per hour.

The loss of draft through the boiler will depend largely upon the method of baffling employed, and increases with the per-cent rating at which the boiler is operated. The precipitating-figures should be increased by approximately 55% when the boiler is operated at 150% of its rated capacity, and by 75% when it is run at 200% rating.

**Velocity of Gases through Flue and Chimney.** In preliminary estimates 5 lb coal per boiler horse-power developed, and 24 lb air per lb of coal is usual.

\* See, also, Chimneys for Heating Boilers, page 1281; Flues for Kitchen Ranges and Fireplaces, page 1282, and Selection of Chimney Flues, page 1282.

Table I. Loss of Draft between Furnace and Ash-Pit to Burn Coal

Kind of coal	Combustion-rate, <i>R</i> , in pounds of dry coal per square foot of grate per hour						
	15	20	25	30	35	40	45
	Force of draft in inches of water						
Ind., Kan., bituminous . . . . .	.14	.20	.26	.33	.40	.48	.57
., Ky., Pa., Tenn.. bituminous . . . . .	.16	.23	.31	.40	.49	.60	.72
., Pa., Va., W. Va., semibitu- minous . . . . .	.18	.26	.35	.45	.57	.71	.87
thracite pea . . . . .	.30	.45	.64	.88	1.23	...	...
thracite buckwheat No. 1 . . . . .	.43	.68	1.00	1.50	...	...	...

Table II. Loss of Draft between Grate or Furnace and a Point Just beyond Damper-Box

Horizontal return tubular . .	.25 to .30 in of water
Babcock & Wilcox . . . . .	.20 to .35 in of water
Stirling . . . . .	.51 in of water
Vertical tubular . . . . .	.43 in of water

ed. The customary allowable VELOCITIES OF GASES in chimneys, when sign is based on 120 lb of the flue-gas per hour per rated boiler horse-power, from 17 ft per sec for a diameter of stack equal to 24 in, to 31 ft per sec 72-in or larger diameter. These figures correspond to a weight of 0.68 10 lb per sq ft of area. The formula that is supposed to give the most nical diameter for an unlined steel chimney or stack, and used by many ers in this country is  $d = 4.68 \sqrt[4]{(h.p.)^2}$ , in which *d* is the inside diameter es and *h.p.* is the rated capacity of the boilers served.

following figures are frequently used by engineers for approximating the draft in flues or breechings:

Horizontal flues, square or rectangular, from 0.13 to 0.15 in of water per Increase these values 50% for brick-lined flues. Loss of draft for easy angle bends, 0.05 in of water.

When economizers are to be installed the temperature of the flue-gas is d to from 250° to 325°, and the total head, *H*, should be calculated on a these temperatures.

The loss of draft through the economizers should not be figured less 3 in of water.

The turns which the flue makes in leaving the damper-box of the boiler, enters the main flue and at the stack, should be considered and allowed

t is customary to make the flue or breeching approximately from 10 to eater in area than the stack to which it connects. The cross-section is re- n proportion to the volume of gas to be handled as the flue passes the n succession. The width of the flue or breeching, where it enters the

chimney, should never exceed one third the outside diameter of the chimney at its base.

**Example.** The method of procedure in determining the dimensions of chimney and breeching is explained in the following example.

Three 150-h.p. return tubular boilers with a total of 1500 sq ft of heating surface are to be served. The total area of the grate-surface is 90 sq ft. The measured length of the breeching is 40 ft. The gas makes two right-angle turns, one at the entrance to the breeching, and one on entering the chimney. The fuel assumed is Pennsylvania bituminous coal. If 5 lb of coal per boiler horsepower per hour is assumed as the fuel-consumption, the rate of combustion is  $(3 \times 150 \times 5)/90 = 25$  lb per sq ft of grate-surface per hour.

The weight of flue-gas per second is

$$(3 \times 120 \times 150)/(60 \times 60) = 15 \text{ lb}$$

Assuming a temperature of  $550^{\circ}$ , the volume of the flue-gas per second is  $15/0.0393 = 382$  cu ft. Assuming an allowable velocity through the chimney of 25 ft per sec, the required area is,

$$382/25 = 15.3 \text{ sq ft}$$

corresponding to 54-in diam, approximately. The area of the flue is to be 15% greater, or

$$15.3 \times 1.15 = 17.6 \text{ sq ft}$$

at the last boiler next to the chimney. The chimney must produce sufficient draft to overcome the following resistance. The loss of draft through fuel based on a rate of combustion of 25 lb per sq ft per hr (Table I) is 0.31 in. The loss of draft through return tubular boilers (Table II) is 0.27 in. The loss of draft through the breeching is

$$0.15 \times 40/100 = 0.06 \text{ in}$$

The loss of draft occasioned by two turns is

$$2 \times 0.05 = 0.10 \text{ in}$$

The total loss is

$$0.31 + 0.27 + 0.06 + 0.10 = 0.74 \text{ in}$$

Then

$$H = 0.74/0.8 = 0.92 \text{ in}$$

or approximately 1 in.

Substituting this value of  $H$  in the equation

$$H = 0.0071L$$

the height,  $L$ , of the stack is

$$1/0.0071 = 140 \text{ ft}$$

measured above the grate.

**Kent's Chimney-Formulas.** The following chimney-formulas by Wm. Kent are largely used by engineers in this country: The formula is based on the assumption that the friction-head in the chimney is considered equivalent to a diminution of the area by an amount equal to a lining of inert gas, 2 in thickness.



# Size of Chimneys for Steam-Boilers

TABLE III. SIZE OF CHIMNEYS FOR STEAM-BOILERS.

## Kent's Formula

Diam-eter, in	Area, sq ft	Effective area, $E=A-\frac{1}{2}A$ $0.6\sqrt{A}$ sq ft	Height of chimney in feet												Equivalent square chimney. Side of square, $\sqrt{E+4}$ in		
			50	60	70	80	90	100	110	125	150	175	200	225		250	300
Commercial horse-power of boiler *																	
18	1.77	.97	23	25	27	29	...	...	...	...	...	...	...	...	...	...	16
21	2.41	1.47	35	38	41	44	...	...	...	...	...	...	...	...	...	...	19
24	3.14	2.08	49	54	58	62	66	...	...	...	...	...	...	...	...	...	22
27	3.98	2.78	65	72	78	83	88	...	...	...	...	...	...	...	...	...	24
30	4.91	3.58	84	92	100	107	113	119	...	...	...	...	...	...	...	...	27
33	5.94	4.48	...	115	125	133	141	149	156	...	...	...	...	...	...	...	30
36	7.07	5.47	...	141	152	163	173	182	191	204	...	...	...	...	...	...	32
39	8.30	6.57	...	...	183	196	208	219	229	245	...	...	...	...	...	...	35
42	9.62	7.76	...	...	216	231	245	258	271	289	316	...	...	...	...	...	38
48	12.57	10.44	...	...	...	311	330	348	365	389	426	486	...	...	...	...	43
54	15.90	13.51	...	...	...	...	427	449	472	503	551	595	...	...	...	...	48
60	19.64	16.98	...	...	...	...	536	565	593	632	692	748	...	...	...	...	54
66	23.76	20.83	...	...	...	...	...	694	728	776	849	918	981	...	...	...	59
72	28.27	25.08	...	...	...	...	...	835	876	934	1023	1105	1181	1253	...	...	64
78	33.18	29.73	...	...	...	...	...	...	1038	1107	1212	1310	1400	1485	1565	...	70
84	38.48	34.76	...	...	...	...	...	...	1214	1294	1418	1531	1637	1736	1803	2003	75
90	44.18	40.19	...	...	...	...	...	...	...	1496	1639	1770	1893	2008	2116	2318	80
96	50.27	46.01	...	...	...	...	...	...	...	1712	1876	2027	2167	2298	2423	2654	86
102	56.75	52.23	...	...	...	...	...	...	...	1944	2130	2300	2459	2609	2750	3012	91
108	63.62	58.83	...	...	...	...	...	...	...	2090	2399	2592	2771	2939	3098	3393	96
114	70.88	65.83	...	...	...	...	...	...	...	...	2685	2900	3100	3288	3466	3797	101
120	78.54	73.22	...	...	...	...	...	...	...	...	2986	3225	3448	3657	3855	4223	107
132	95.03	89.18	...	...	...	...	...	...	...	...	3637	3929	4200	4455	4696	5144	117
144	113.10	106.72	...	...	...	...	...	...	...	...	4352	4701	5026	5331	5618	6155	128

If  $A$  = the actual area in square feet;  
 $E$  = the effective area in square feet;  
 $D$  = the diameter in feet;

Then  $E = A - 0.60\sqrt{A}$ .

The draft-power of a chimney varies directly as the effective area,  $E$ , and as the square root of the height,  $L$ . The formula for the horse-power of a chimney will take the form,  $h.p. = CE\sqrt{L}$ , in which  $C$  is a constant. The value of  $C$  as obtained by Kent from an examination of a large number of chimneys is 3.33 when 5 lb of coal is burned per boiler horse-power per hour.

The formula for the horse-power rating of a chimney is, therefore,

$$h.p. = 3.33E\sqrt{L} = 3.33 (A - 0.6\sqrt{A})\sqrt{L}$$

or

$$E = 0.3 \text{ h.p.} / \sqrt{L}$$

The Babcock & Wilcox Company recommend that when the fuel used is low grade bituminous coal of the Middle or Western States, the sizes given in Table III be increased from 25 to 60%, depending upon the nature of the coal and the capacity desired. If the gas makes more than two turns it is advisable to increase the diameter given in the table by one size. The height must be increased at least 30% if economizers are used. Table III may be applied to heating-boilers the equivalent rating in square feet of direct radiation being approximately equal to the horse-power rating  $\times 100$ .

**Chimneys for Tall Office and Loft-Buildings.** The chimney or stack for a tall building is a special case in which the height is frequently fixed by the height of the structure itself or the height of the adjoining buildings. In this case the diameter is assumed and the method outlined in the preceding example applied.

### General Formulas for the Design of Brick Chimneys. See Fig. 1

Let  $P$  = horizontal wind-pressure in pounds per square foot, ordinarily assumed as 25 lb per sq ft for round chimneys

$xx$  = any section distant  $z$  from top of chimney

$z \left( \frac{d + d_1}{2} \right)$  = projected area above  $xx$

$R$  = horizontal wind-load in pounds

$$= Pz \left( \frac{d + d_1}{2} \right)$$

$y$  = distance from  $xx$  to center of gravity of portion above  $xx$

$M$  = wind-moment in foot-pounds

$$= Pz y \left( \frac{d + d_1}{2} \right)$$

### PROPERTIES OF SECTION

$d_1$  = outside diameter

$d_2$  = inside diameter

$c$  =  $d_1/2$

$I$  = moment of inertia of section

$A$  = area of section in square feet

$$= 0.7854 (d_1^2 - d_2^2)$$

$\frac{I}{c}$  = section-modulus

$$\frac{I}{c} = \frac{0.0982 (d_1^4 - d_2^4)}{d_1}$$

$W$  = weight of chimney above  $xx$ , in tons

$S_1$  = compressive stress at edge on leeward side due to  $W$ , in tons per square foot

$S_2$  = compressive stress at edge on leeward side due to  $M$ , in tons per square foot

$$S_1 = +\frac{W}{A} \quad S_2 = \pm \frac{Mc}{I}$$

$$\text{Windward side, } S_w = \frac{W}{A} - \left[ \frac{Mc}{I} \text{ (tension)} \right]$$

$$\text{Leeward side, } S_l = \frac{W}{A} + \left[ \frac{Mc}{I} \text{ (compression)} \right]$$

$S_w$  and  $S_l$  should not exceed the following values, in tons per square foot, for solid Brick Chimneys:

#### MAXIMUM TENSION

#### MAXIMUM COMPRESSION

Below 150 ft. . . . . 2 to 2½

200 ft and below . . . . . 19

From 150 to 200 ft. . . 1 to 1½

Above 200 ft. . . . . 21

Above 200 ft. . . . . 0

**FOUNDATIONS.** Calculate wind-moment,  $M_1$  for chimney above ground-line.

$$M_1 = Ph y_1 \left( \frac{d + d_1}{2} \right)$$

$l$  = length of side of square base in feet

$A_1 = l^2$  = area of base in square feet

$$\frac{I}{c} = \frac{l^3}{6} = \text{section-modulus of base}$$

$W_1$  = combined weight of chimney and foundation

**Example.** It is required to determine the maximum compression, in tons per sq ft at the base of the column, for the chimney shown in Fig. 2, and also the maximum soil-pressure in tons per sq ft. The assumed wind-pressure is 25 lb per sq ft. (See General Formulas for the Design of Brick Chimneys, and Fig. 1.)

The area of section at base,  $A = 0.7854 (16^2 - 12.3^2) = 80.9$  sq ft.

The section-modulus at base,  $I/c = [0.0982(16^4 - 12.3^4)]/16 = 257$ .

The total weight of brick column (Table V) is  $W = 495$  tons (interpolated).

The projected area of column is  $\frac{1}{2} \times (8.75 + 16) \times 180 = 2228$  sq ft.

The horizontal wind-load,  $R = 2228 \times 25 = 55700$  lb = 27.8 tons.

The moment-arm of  $R$  is  $y = \frac{1}{3} \times 180[(2 \times 8.75) + 16]/(8.75 + 16) = 81$  ft.

The wind-moment,  $M = 81 \times 27.8 = 2252$  ft tons.

$S_1 = 495/80.9 = 6.2$  tons per sq ft.

$S_2 = \pm 2252/257 = 8.7$  tons per sq ft.

The maximum compression on the leeward side,  $S_1 + S_2 = 6.2 + 8.7 = 14.9$

tons per sq ft. The maximum tension on the windward side,  $S_1 - S_2 = -2.2$

tons per sq ft. The following computations are for a square base:

**FOUNDATIONS.** The length of base,  $l = 25.5$  ft,  $A_1 = l^2 = 650$  sq ft,  $I/c = l^3/6 = 814$ . The weight of foundation, based on 1.9 tons per cu yd, is 266

tons. The weight of the 4½-in lining is  $36 \times 11 \times 0.063 = 25$  tons. The total weight of column, lining and foundation, is  $W_1 = 495 + 25 + 266 = 786$  tons.

The moment-arm for  $R$  may be assumed the same as before, or 81 ft. Therefore  $M = 2252$  ft-tons. The section-modulus of the base,  $I/c = l^3/6 = 814$ .

$S_1 = 786/650 = 1.2$  tons per sq ft.  $S_2 = 2252/814 = 2.8$  tons per sq ft.

The maximum soil-pressure,  $S_1 + S_2 = 1.2 + 2.8 = 4$  tons per sq ft.


 $+s_1$ 
 $+s_2 =$ 
 $+s_3 =$ 

Tons per square foot

 $S_1 = \frac{W_1}{I^2} = \text{compression per sq ft due to } W_1$ 
 $S_2 = \frac{6M_1}{I^2} = \text{compression per sq ft due to } M_1$ 

Fig. 1. Details of Construction of Tall Brick Chimney

# 21 Formulas for the Design of Brick Chimney




Fig. 2. Details of Tall Radial-brick Chimney

[illegible]

**Table V. Dead-Load of Radial-Brick Chimneys in Tons of 2 000 Pounds \***

Height in feet	Inside diameter at top, in feet							
	3	4	5	6	7	8	9	10
90	90	98	110	122	.....	.....	.....	.....
100	110	120	131	143	161	180	.....	.....
110	138	143	155	167	188	206	.....	.....
120	160	170	185	198	218	237	.....	.....
130	.....	202	218	231	252	273	295	318
140	.....	237	256	270	290	310	337	357
150	.....	277	296	311	330	353	375	400
160	.....	317	340	357	375	402	423	447
170	.....	362	388	410	425	454	475	500
180	.....	.....	.....	.....	480	510	537	555
190	.....	.....	.....	.....	535	570	592	617
200	.....	.....	.....	.....	600	632	657	685
210	.....	.....	.....	.....	.....	.....	727	760
220	.....	.....	.....	.....	.....	.....	804	843

These values are interpolated from curves by the M. W. Kellogg Company, and are for radial-brick chimneys exclusive of the weight of the foundation.

**Table VI. Width of Foundations at Base for Radial-Brick Chimneys \***

Height in feet	Inside diameter at top, in feet							
	3	4	5	6	7	8	9	10
	ft in	ft in	ft in	ft in	ft in	ft in	ft in	ft in
90	11 6	12 0	13 0	13 9	.....	.....	.....	.....
100	12 6	13 0	14 0	14 8	15 6	16 0	.....	.....
110	13 6	14 3	15 0	15 6	16 6	17 0	.....	.....
120	14 6	15 3	16 0	16 6	17 6	18 0	.....	.....
130	15 6	16 6	17 3	17 8	18 8	19 3	20 0	21 3
140	.....	17 9	18 6	18 10	19 9	20 3	21 0	22 3
150	.....	19 0	19 9	20 0	21 0	21 6	22 3	23 6
160	.....	20 6	21 0	21 6	22 6	23 0	23 6	24 9
170	.....	22 0	22 6	23 0	23 9	24 3	25 0	26 3
180	.....	.....	.....	.....	25 6	26 0	26 6	27 6
190	.....	.....	.....	.....	27 0	27 6	28 3	29 3
200	.....	.....	.....	.....	28 6	29 0	29 9	30 9
210	.....	.....	.....	.....	.....	.....	31 6	32 6
220	.....	.....	.....	.....	.....	.....	33 0	34 3
	.....	.....	.....	.....	.....	.....	.....	37 0

These values are interpolated from curves by the M. W. Kellogg Company. The maximum unit soil-pressure at the outer edge of the foundation, due to dead and wind loads, does not exceed 2 tons per square foot.

**Reinforced-Concrete Chimneys. Area of Steel Reinforcement Required.**  
The following formulas are used by one concern in the design of reinforced-concrete chimneys:

- wind-moment at section considered, in inch-pounds;
- weight of shell above section considered, in pounds;

- $D$  = outside diameter of shell, in feet;
- $d$  = inside diameter of shell, in feet;
- $R$  = radius of steel circle, in inches;
- $r$  = radius of neutral core =  $\frac{1}{8}D[1 + (d/D)^2]$  feet;
- $WR$  = moment of stability from weight of shell, in inch-pounds;
- $S$  = 16 000, the allowable fiber-stress in the steel in pounds per square in.
- $A$  = total cross-sectional area of steel rods required at section considered, square inches;
- $A = 2(M - Wr)/SR$  = number of bars  $\times$  cross-sectional area of one bar

The bars used are ordinarily  $\frac{3}{4}$ -in square, twisted bars, each with a cross-sectional area of 0.5625 sq in. The thickness of the shell, if made without taper, is ordinarily 6 in, and if constructed with a taper the shell is made 5 in thickness at the top and increased  $\frac{1}{4}$  in in thickness for each 5 ft in height. The maximum compression due to the wind-moment and dead load in the concrete, at the base, is ordinarily limited to 350 lb per sq in. The same formulas apply in this case as in the design of brick chimneys (Fig. 1).

**Example.** A reinforced-concrete chimney has the following dimensions: 150 ft high; no taper; 9 ft inside diameter; thickness of shell 6 in; outside diameter 10 ft; weight of shell 335 250 lb. It is required to determine the total cross-sectional area of reinforcement.

$M = 25 \times 10 \times 150 \times 150/2 = 2\,812\,500$  ft-lb = 33 750 000 in-lb;  
 $r = 10/8 \times [1 + (9/10)^2] = 2.3$  ft = 27.6 in;  
 $R = 58$  in;  
 $A = 2[33\,750\,000 - (335\,250 \times 27.6)]/16\,000 \times 58 = 53$  sq in;  
If  $\frac{3}{4}$ -in square bars are used, it requires  $53/0.5625 = 94$  bars.

Table VII. Reinforced-Concrete Chimneys. Dimensions. (Fig. 3)

Height above grade  ft	Inside diam- eter  ft	Depth below grade  ft	Height double shell  ft	Height single shell  ft	Ttotal height $A+B+C$  ft	Maxi- mum outside diam- eter ft in	Width of squan founda- tion ft
$H$	$C$	$A$	$B$	$C$	$D$	$E$	$F$
100	4	5	33	67	105	6 4	12
100	5	5	33	67	105	7 4	13
125	5	5	42	83	130	7 4	15
125	6	5	42	83	130	8 4	16
150	6	6	48	102	156	8 4	18
150	7	6	48	102	156	9 4	18
150	8	6	48	102	156	10 4	19
175	8	7	57	118	182	10 6	22
175	9	7	57	118	182	11 6	22
175	10	7	57	118	182	12 6	23
200	10	7	66	134	207	12 6	25
200	11	7	66	134	207	13 6	25
200	12	7	66	134	207	14 6	26
225	12	8	69	156	233	14 8	29
225	13	8	69	156	233	15 8	29
225	14	8	69	156	233	16 8	30
250	14	8	81	169	258	16 8	32
250	15	8	81	169	258	17 8	33
250	16	8	81	169	258	18 8	34






Fig. 3. Details of Tall Reinforced-concrete Chimney

Chimney Company, Chicago, Ill., designed and constructed, chimneys, the great reinforced-concrete chimney at Saganoseki, Oriental Compressor Company, for the copper smelter. It was erected, 1917, and ranks with the highest in the world, being 266 ft in height and 26 1/4 ft in internal diameter at the top.

**Self-Sustaining Steel Chimneys\*** are largely used, especially for tall chimneys of iron-works and power-houses from 150 to 300 ft. in height.

"The advantages claimed are: Greater strength and safety; smaller space required; smaller cost by 30 to 50% as compared with brick chimneys; avoidance of infiltration of air and consequent checking of the draught, common in brick chimneys. They are usually made cylindrical in shape, with a wide curved flare for 10 to 25 ft at the bottom. A heavy cast-iron base-plate is provided, to which the chimney is riveted, and the plate is secured to a massive foundation by holding-down bolts. No guys are used."†

The largest SELF-SUSTAINING STEEL CHIMNEY in the world (1919) is that built by the Chicago Bridge and Iron Works at the plant of the United Verde Copper Company, Clarkdale, Arizona. It is 30 ft 9½ in in diameter and 400 ft in height. The thickness of plates varies from ¼ in at the top to 1½ in for the bell-shaped portion at the bottom. The weight of steel is 800 000 lb. The stack is anchored to the foundation by thirty-six bolts, each 4 in in diameter, upset, and spaced equidistant in a bolt-circle of 25 ft 4½ in radius.

**Table VIII. Sizes of Foundations for Self-Sustaining Steel Chimneys, Half-Lined‡**

Diameter, clear, in feet. . .	3	4	5	6	7	9	11
	ft in	ft in	ft in	ft in	ft in	ft in	ft in
Height . . . . .	100	100	150	150	150	175	225
Least diam. of foundation	15 9	15 3	20 4	21 10	22 7	25 9	29 11
Least depth of foundation	6 6	7	9	8	9	10	13
Height . . . . .	....	125	200	200	250	275	300
Least diam. of foundation	....	17 6	23 8	25 0	29 8	33 6	36 0
Least depth of foundation	....	7 6	10	10	12	12	14

The governing feature in the design of a SELF-SUSTAINING STEEL CHIMNEY OR STACK is the force of the wind. The cylinder above any horizontal plane section may be assumed to act as a cantilever beam in which the bending moment, in foot-pounds, is

$$M = HD \times P \times \frac{1}{2}H = \frac{1}{2}H^2DP$$

in which *H* is the height in feet above the section considered, *D* the diameter in feet and *P* the assumed pressure of the wind in pounds per square foot on a vertical cross-section. The fiber-stress *S*, in pounds per square inch, according to the formula for flexure, is *S* = *Mc*/*I*. For hollow cylinders of large diameter and small thickness, the moment of inertia *I* = π*R*<sup>3</sup>*t*, in which *R* = mean radius in feet (equivalent to *c* in the flexure formula) and *t* = thickness of shell in inches. Hence

$$S = MR/12\pi R^3t = 0.106M/D^2t, \text{ and } t = 0.106M/SD^2.$$

The stress *S* is tensile on the windward side and compressive on the leeward side

\* Compiled from data furnished by Robins Fleming.  
† Mechanical Engineers' Pocket Book. Kent.  
‡ These dimensions were taken from a pamphlet published by the Philadelphia Engineering Works.

small compressive stress due to the weight of the stack. The be taken at 25 lb per sq ft and of  $S$  at 16 000 lb per sq in, as given tions for the Structural Steel Work for Buildings, Chapter XXX. built for durability as well as strength it is often advisable to oretical thickness of the shell. No plate should be used with a an  $\frac{1}{4}$  in. It is important that the stack be securely anchored n. Many methods have been proposed for determining stresses

As the problem depends for its solution on the physical con- base and bolts, no exact analysis is possible. (See editorial dis- icle, Anchor-Bolt Tension, in Engineering News, April 30, 1914.) : assumption is that the bolts are screwed up with a high initial nchor-bolt ring can then be considered in the same way as a ring

The maximum stress at any point of the bolt-circle is devel- wind is blowing parallel to the radius through that point. The circumferential inch is  $0.106M/(2R_1)^2$ ,  $2R_1$  being the diameter e. Let  $b$  be the circumferential distance in inches between -bolts,  $N$  the number of bolts equidistant on the bolt-circle and the stack. For the anchor-bolt on the windward side there is a , due to the wind,

$$S_w = 0.106bM/(2R_1)^2 ]$$

$$b = (2R_1 \times 12 \times \pi)/N$$

$$S_w = 2M/R_1N$$

weight of the portion of the stack between adjacent bolts, the : stress in any anchor-bolt may be expressed by the equation

$$S_w = (2M/R_1N) - W/N$$

**Chimneys.** These chimneys are built with special blocks e circular and radial lines of each section of the chimney so brickwork has joints of an even thickness throughout and a surface. The blocks being much larger than common bricks, om one third to one half as many joints. Radial-brick chim- ircular in plan above the base. The best form of base is octag- ion so as to permit the breeching to enter the chimney at a at the same time comply best with the rules of stability. cal-works, refineries, furnaces, etc., radial-brick chimneys are e shell, a lining only being provided in the immediate vicinity ce. All radial bricks are perforated vertically and this insures and allows the mortar to enter the perforations, thus forming ge.

for chimney-construction have been used extensively in y, France and Russia since 1870. They were not introduced , however, until 1898. About forty-five years ago (1869 or odidis, of Düsseldorf, Germany, originated a method of building erforated radial blocks, made from selected clays and burned mperature, and in 1898 an American company \* was formed f erecting chimneys by this method of construction. Since

that time the company through various agencies has built more than six thousand chimneys in all parts of the world. The tallest chimney in the world (1919), 585 feet high and 60 ft in internal diameter at the top, was built by this company in 1918 for the Anaconda Copper Company, at Anaconda, Mont.

Mr. H. R. Heinicke,\* of Chemnitz, Germany, builder of the 460-ft stack at Halsbrücke, Germany, has employed radial bricks-made especially for each chimney. This firm through long and costly research has done much to make chimney-building a science. The chimney at Halsbrücke is a very remarkable one on account of its proportions. In a height of 460 ft, the diameter at the top is only 8 ft, whereas the 585-ft stack at Anaconda, Mont., has a diameter of 60 ft at the top.

The Heine Chimney Company † has erected many important high chimneys. The essential difference in the methods of construction used by this company from those of the other chimney-constructors is that the Heine Chimney Company uses perforated, INTERLOCKING, radial bricks. It is claimed that this interlocking-feature has an advantage over the straight-sided bricks in acting as a preventive of deep weathering of the joints and of air-leaks. In addition to this it is claimed that the circumferential strength of the walls when built of this type of brick is considerably greater than when built with plain-sided or corrugated bricks. The perforations in these bricks are fewer but larger than those of some of the other constructors. The brickwork is laid on full-mortar beds with SHAVED joints. These large perforations allow the mortar to rise in them, thus forming PINS which give the walls great strength and enable them to withstand the stresses due to expansion caused by the high temperature of the flue-gases. In walls more than one brick thick, the bricks are laid up in English bond, that is, with alternate header and stretcher-courses. This company advocates this method of construction even in chimneys built with the ordinary straight-sided common building-bricks. Among the many important chimneys constructed by the Heine Chimney Company is the one erected at the St. Joseph Lead Company's plant, at Herculaneum, Mo. The height of this chimney is 350 ft and the inside diameter at the top 20 ft. (See page 1706.)

The M. W. Kellogg Company ‡ has designed and built many radial-brick chimneys for power-plants, chemical-works and other purposes. Several of the important chimneys put up by them are mentioned in the list of tall chimneys (page 1379). Some of the details of construction differ from those of the other companies mentioned. One of the points of difference is the detail relating to the corrugations on their bricks. These corrugations are  $\frac{3}{8}$  in wide and  $\frac{1}{4}$  in deep and are placed along the vertical sides of the bricks as they lie in the wall. The adhesion between the bricks and mortar is increased by this increased area. It is claimed that tests made show that this is the case. On account of the corrugations it is not considered necessary to embed any ironwork in the chimneys to prevent the development of cracks due to heat-expansion. Ironwork has sometimes been inserted when plain-sided bricks have been used. It is claimed that this design is somewhat heavier than that employed by some other constructors, this company holding that it is not safe to figure on wind pressure of less than 25 lb per sq ft of projected area. Among the most tall chimneys erected by this company may be mentioned especially the

\* H. R. Heinicke, Incorporated, New York City.

† The Heine Chimney Company, Chicago, Ill.

‡ The M. W. Kellogg Company, New York City.

glas, Ariz., erected for the Copper Queen Consolidated Mining

er reliable companies which design and construct tall chimneys.  
d here were the pioneers in this work.

### List of Tall Chimneys Over 300 Feet in Height

sted that this list is constantly added to from year to year.

	Height, ft	Diam. inside at top, ft
st., Anaconda Copper Co. (1918).....	585	60
, American Smelting & Refining Co. (1917)...	573	25
pan, Oriental Compressol Co. (1917).....	570	26 1/4
ont., Boston & Montana Consolidated Copper ining Co. (1907).....	506	50
y, Germany, Halsbrücke Foundry.....	460	8
Dundas, Scotland, F. Townsend.....	454	..
ollox, Scotland, Tenant & Co.....	436 1/2	..
United Verde Extension Mining Co. (1918).....	425	30
, Messrs. Musprath Chemical Works.....	406	..
, United Verde Copper Co.....	400	30 3/4
Consolidated Kansas City Smelting & Refining .....	400	30
American Smelting & Refining Co. (1911).....	400	25
ont., American Smelting & Refining Co. (1917)...	400	16
Clough Mill, Scotland, Messrs. Crossley's.....	381	..
K. Williams & Co. (1911).....	375	7
ton, England, Dobson & Barlow.....	367	..
, Eastman Kodak Co. (two) (1906, 1911).....	366, 9 and 13	
, N. J., Orford Copper Co. (two) (1900, 1910)...	365	10
Garfield Smelting Co. (1913).....	350	22
Mo., St. Joseph, Lead Co.....	350	20
Fall River Iron Co.....	350	11
Heller Merz Co (1904).....	350	8
. J., Clark Thread Co.....	335	..
, Germany, Wessenfield & Co.....	331	..
land, Gas-Works.....	329	..
nn., Tennessee Copper Co.....	325	20
d., Indianapolis Traction Co.....	320	13
ngland, Brook & Son, Fire-clay Works.....	315	..
land, Adams Soap-Works.....	312	..
., Rhode Island Suburban Railway Co.....	308	16
N. Y., New York Steam Co. (1904).....	308	15
d, P. Dickon & Son.....	300	..
nd, Mitchell Brothers.....	300	..

the Alphons Custodis Chimney Construction Company, New York

crete, The Weber Chimney Company, Chicago, Ill.

H. R. Heinicke, Incorporated, New York City.

steel chimney, the largest (of this type) in the world (1919).

The Heine Chimney Company, Chicago, Ill.

**Partial List of Tall Chimneys over 300 Feet in Height (Continued)**

	<b>Height ft</b>	<b>Diam. inside at top ft</b>
*Garfield, Utah, American Smelting and Refining Co. (1905)....	300	30
*Hayden, Ariz., American Smelting and Refining Co.....	300	25
† Douglas, Ariz. Copper Queen Consolidated Mining Co.....	300	22
‡ Tacoma, Wash., Tacoma Smelting Co.....	300	18
§ McGill, Nev., Steptoe Valley Traction Co.....	300	15
*Brooklyn, N. Y., Nichols Chemical Co. (1905).....	300	12
*Claymont, Del., General Chemical Co. (1912).....	300	8

\* Constructed by the Alphons Custodis Chimney Construction Company, New York City.

† Constructed by The M. W. Kellogg, Company, New York City.

‡ Reinforced concrete, The Weber Chimney Company, Chicago, Ill.

§ Constructed by H. R. Heinicke, Incorporated, New York City.

# PLUMBING, PLUMBING AND DRAINAGE, ILLUMI- NATING-GAS AND GAS-PIPING

By

J. J. COSGROVE

CONSULTING SANITARY ENGINEER

## (1) HYDRAULICS

atically an incompressible liquid, weighing, at the average temper-  
62.355 lb to the cu ft and 8.335 lb to the gallon. These figures  
with changes in temperature and atmospheric pressure, and a  
for the same temperature will be found in different works.

**Water.** The pressure of still water in pounds per square inch  
s of any pipe or vessel of any shape whatever is due alone to the  
: of the surface of the water above the point considered pressed  
ual to 0.433 lb per sq in for every foot of head at 62° F. The  
er square inch is equal in all directions. To find the total pres-  
ater against and perpendicular to any surface, whether vertical,  
inclined at any angle, whether it be flat or curved, multiply  
ea in square feet of the surface pressed, the vertical depth of its  
ty below the surface of the water, and the constant 62.4. The  
: the required pressure in pounds. This may be expressed by  
ws:

$$P = 62.4 AD$$

essure in pounds of quiescent water on the surface considered;  
ea pressed upon in square feet; and  
rtical depth in feet of center of gravity of surface considered.

Pressure in Pounds per Square Inch for Different Heads of  
Water in Feet

1	2	3	4	5	6	7	8	9
0.433	0.866	1.299	1.732	2.165	2.598	3.031	3.464	3.897
4.763	5.196	5.629	6.062	6.495	6.928	7.361	7.794	8.227
9.093	9.526	9.959	10.392	10.825	11.258	11.691	12.124	12.557
13.423	13.856	14.289	14.722	15.155	15.588	16.021	16.454	16.887
17.753	18.186	18.619	19.052	19.485	19.918	20.351	20.784	21.217
22.083	22.516	22.949	23.382	23.815	24.248	24.681	25.114	25.547
26.413	26.846	27.279	27.712	28.145	28.578	29.011	29.444	29.877
30.743	31.176	31.609	32.042	32.475	32.908	33.341	33.774	34.207
35.073	35.506	35.939	36.372	36.805	37.238	37.671	38.104	38.537
39.403	39.836	40.269	40.702	41.135	41.568	42.001	42.436	42.867

for greater heads can be readily found by multiplication or addi-  
pressure for a head of 110 ft is ten times that for 11 ft. The pres-  
s equal to the pressure for 110 ft plus that for 8 ft.

**Flow of Water in Pipes.** Owing to the many practical and variable conditions which affect the flow of water in pipes, such as the smoothness of the pipe, number and character of the joints, bends and valves in the pipe, to say nothing of the size and length of the pipe, all formulas for the velocity and discharge of water in and through pipes can only be considered as approximate. The following formulas and data are taken largely from the National Tube Company's Book of Standards, 1902 edition. They agree fairly well with similar tables by Kent and Trautwine, both of whom devote much space to this subject. The **QUANTITY OF WATER** passing through a given pipe is governed by the sectional area of the pipe or outlet and the mean **VELOCITY**. The velocity depends primarily upon the **PRESSURE** or **HEAD**, and is greatly affected by **FRICTION**, which again varies with the smoothness of the bore, the diameter and length of the pipe, and whatever obstructions there may be in the pipe. The **HEAD** is the vertical distance from the surface of the water in the reservoir to the center of gravity of the lower end of the pipe when the discharge is into the air, or to the level surface of the lower reservoir when the discharge is under water. When the pressure is produced by mechanical means, the head of water in feet may be readily determined by the following table:

**Table B.\*    For Converting Pressure in Pounds per Square Inch into Head of Water in Feet**

Pres- sure	0	1	2	3	4	5	6	7	8	9
0	.....	2.309	4.619	6.928	9.238	11.547	13.857	16.166	18.476	20.785
10	23.0947	25.404	27.714	30.023	32.333	34.642	36.952	39.261	41.570	43.880
20	46.1894	48.499	50.808	53.118	55.427	57.737	60.046	62.356	64.665	66.975
30	69.2841	71.594	73.903	76.213	78.522	80.831	83.141	85.450	87.760	90.069
40	92.3788	94.688	96.998	99.307	101.62	103.93	106.24	108.55	110.85	113.16
50	115.4735	117.78	120.09	122.40	124.71	126.02	129.33	131.64	133.95	136.26
60	138.5682	140.88	143.19	145.50	147.81	150.12	152.42	154.73	157.04	159.35
70	161.6629	163.97	166.28	168.59	170.90	173.21	175.52	177.83	180.14	182.45
80	184.7576	187.07	189.38	191.69	194.00	196.31	198.61	200.92	203.23	205.54
90	207.8523	210.16	212.47	214.78	217.09	219.40	221.71	224.02	226.33	228.64

\* Tables A and B are exact for water at 62° F. and for atmospheric pressure at 14.7 lb per sq in.

**To find the velocity of water discharged** from a pipe-line longer than four times its diameter, knowing the head, length and inside diameter, use the following formula:

$$v = m \sqrt{\frac{hd}{L + 54 d}}$$

in which

- v = approximate mean velocity in feet per second;
- m = coefficient from the table below;
- d = diameter of pipe in feet;
- h = total head in feet;
- L = total length of line in feet.

The following coefficients are averages deduced from a large number of experiments. In most cases of pipes carefully laid and in fair condition, they should give results varying not more than from 5 to 10%.



Values of Coefficient  $m$

Diameter of pipe in feet							
0.05	0.10	0.50	1	1.5	2	3	4
$m$	$m$	$m$	$m$	$m$	$m$	$m$	$m$
29	31	33	35	37	40	44	47
34	35	37	39	42	45	49	53
39	40	42	45	49	52	56	59
41	43	47	50	54	57	60	63
44	47	52	54	56	60	64	67
47	50	54	56	58	62	66	70
48	51	55	58	60	64	67	70

Given the head,  $h = 50$  ft; the length,  $L = 5\ 280$  ft and the diameter,  $d = 1$  ft; to find the velocity and quantity of discharge. Using these values in the foregoing formula, we get

$$\sqrt{\frac{d \times h}{L + 54 d}} = \sqrt{\frac{1 \times 50}{5\ 280 + 54}} = \sqrt{\frac{100}{5\ 334}} = 0.136$$

on headed  $\sqrt{\frac{hd}{L + 54 d}}$  find 0.10, which is the value nearest to 0.136, along this line until column headed 2 is reached; then read 62 as value of coefficient  $m$ .

$= 62 \times 0.136 = 8.432$  ft per sec, the velocity required.

To find the discharge in cubic feet per second, multiply this velocity by cross-section of pipe in square feet.

$3.1416 \times (1)^2 \times 8.432 = 26.49$  cu ft per sec.

There are 7.48 gal in a cubic foot, the discharge in gallons per second  $= 26.49 \times 7.48 = 198.2$ .

Above formula is only an approximation, since the flow is modified by joints, incrustations, etc.

To find the head in feet necessary to give a stated discharge in cubic feet, the formula

$$h = \frac{0.000704 Q^2 (L + 54 d)}{d^5}$$

h

= total head in feet;

= total length of line in feet;

= diameter of pipe in feet;

= quantity of water in cu ft per second.

Example. Given the diameter of pipe,  $d = 0.5$  ft; the length of pipe,  $L = 20 + 27 = 47$  ft and the quantity of water to be discharged,  $q = 3.07$  cu ft per sec; to find the necessary head.

Substituting these values in the above formula, we get

$$h = \frac{0.000704 \times 9.4 \times (20 + 27)}{(0.5)^5} = \frac{0.000704 \times 9.4 \times 47}{0.03125} = 9.95 \text{ ft, the required head.}$$

The following formula is simpler and can be used when  $d$  in relation to  $L$  is so small as to be negligible:

$$h = \frac{0.000704 Q^2 \times L}{d^5}$$

If the pipe instead of being straight has easy curves (say with radius not less than five diameters of the pipe) either horizontal or vertical, the discharge will not be materially diminished so long as the total heads and total actual lengths of pipe remain the same, but it is advisable to make the radius as much more than five diameters as can conveniently be done.

To find the diameter of a pipe of given length to deliver a given quantity of water under a given head use the following,

$$d = 0.234 \sqrt[5]{\frac{Q^2 L}{h}}$$

in which

- $d$  = diameter of pipe in feet;
- $Q$  = cubic feet per second delivered;
- $L$  = length of line in feet;
- $h$  = head in feet.

**Example.** Given the head,  $h = 700$  ft; the length of pipe,  $L = 3\,000$  ft; the quantity to be delivered,  $Q = 4$  cu ft per sec; required the diameter of pipe necessary.

Substituting these values in the foregoing formula, we get :

$$d = 0.234 \sqrt[5]{\frac{16 \times 3\,000}{700}} = 0.234 \sqrt[5]{68.57} = 0.545 \text{ ft} = 6.54 \text{ in}$$

To find the diameter of pipe required to deliver a given quantity of water with a given head.

**Rule.** (1) Reduce the head to feet per 100 ft; (2) from Table C, page 1385, find the discharge for the head thus obtained through a pipe 1 ft in diameter; (3) divide the required discharge by that obtained from Table C; look for the quotient in the column of Table D, page 1386, headed Ratio of Discharge, etc., and opposite it, in the adjoining columns of the table, will be found the required diameter.

**Note.** The use of Tables C and D gives results sufficiently correct for pipes less than 700 diameters in length.

**Example.** If the head of water from a reservoir to the point of delivery is 20 ft in a distance of 1 860 ft, what is the diameter of a pipe required to deliver 6 cu ft of water per second?

20 ft head in 1 860 ft = 20/18.60 ft in 100 ft, or 1.075 ft in 100

From Table C we find that the discharge per second with a head of 1.136 is 3.989 cu ft; for a head of 1.075 it would be about 3.8 cu ft. Dividing the required discharge 6, by 3.8 cu ft per sec, we have 1.58. From Table D the diameter of pipe having a ratio of discharge equal to 1.58 is found to be about 14½ in; therefore we must use a 15-in pipe to obtain the required discharge. If the required discharge is in gallons, divide by 7.5 to reduce to cubic feet. If in cubic feet per minute, divide by 60 to reduce to feet per second.

**ocities and Discharges Through a Straight, Smooth Pipe One Diameter and One Mile, or 5 280 Diameters, in Length**

	Head in feet per mile	Velocity in feet per sec	Discharge in cubic feet per sec	Discharge in cubic feet per 24 hours
	3	1.13	0.8914	76 982
	4	1.31	1.028	88 862
	5	1.47	1.150	99 403
	6	1.61	1.264	109 209
	7	1.74	1.366	118 022
	8	1.86	1.455	125 740
	9	1.96	1.539	132 969
	10	2.08	1.633	141 145
	12	2.27	1.782	153 964
	14	2.45	1.924	166 233
	16	2.62	2.057	177 724
	18	2.78	2.183	188 611
	20	2.93	2.301	198 806
	25	3.28	2.572	222 156
	30	3.59	2.819	243 604
	35	3.88	3.047	263 260
	40	4.15	3.267	282 288
	45	4.40	3.451	298 209
	50	4.64	3.638	314 352
	60	5.08	3.989	344 649
	70	5.49	4.311	372 470
	80	5.85	4.602	397 613
	90	6.23	4.900	423 435
	100	6.56	5.144	444 312
	110	6.87	5.395	466 128
	120	7.18	5.639	487 209
	130	7.47	5.866	506 822
	140	7.76	6.094	526 521
	150	8.05	6.322	546 048
	160	8.30	6.534	564 576
	170	8.55	6.715	580 176
	180	8.80	6.903	596 418
	190	9.04	7.100	613 440
	200	9.28	7.276	628 704
	225	9.84	7.696	664 848
	250	10.4	8.168	705 728
	275	10.8	8.482	732 844
	300	11.3	8.914	769 824
	350	12.3	9.621	831 168
	400	13.1	10.28	888 624
	450	13.9	10.91	943 056
	500	14.7	11.50	994 032
	550	15.4	12.09	1 044 576
	600	16.1	12.64	1 092 096
	650	16.7	13.11	1 132 704
	700	17.4	13.66	1 180 224
	750	18.0	14.13	1 220 832
	800	18.6	14.55	1 257 408
	850	19.1	15.00	1 296 000
	900	19.6	15.39	1 329 696
	950	20.3	15.94	1 377 216
	1 000	20.8	16.33	1 411 456
	1 200	22.7	17.82	1 539 648
	1 400	24.5	19.24	1 662 336
	1 600	26.2	20.57	1 777 248
	1 800	27.8	21.83	1 886 112
	2 000	29.3	23.01	1 988 064
	2 500	32.8	25.72	2 221 560
	3 000	35.9	28.19	2 436 040

Table D.    Diameters of Pipes and Ratio of Discharge

Diameter of pipe, in	Diameter of pipe, ft	Ratio of dis- charge to that through a 1-ft pipe with the same head per mile	Diameter of pipe, in	Diameter of pipe, ft	Ratio of dis- charge to that through a 1-ft pipe with the same head per mile
1	0.0833	0.0020	12½	1.042	1.106
1½	0.1250	0.0055	13	1.083	1.221
2	0.1667	0.0113	14	1.167	1.470
2½	0.2083	0.0198	15	1.250	1.746
3	0.2500	0.0310	16	1.333	2.053
3½	0.2917	0.0458	17	1.417	2.388
4	0.3333	0.0643	18	1.5	2.754
4½	0.3750	0.0857	19	1.583	3.153
5	0.4167	0.1119	20	1.667	3.585
5½	0.4583	0.1422	21	1.75	4.051
6	0.5	0.1767	22	1.833	4.551
6½	0.5417	0.2159	23	1.917	5.084
7	0.5833	0.2600	24	2	5.649
7½	0.6250	0.3090	24½	2.052	6.000
8	0.6667	0.3631	26	2.167	6.912
8½	0.7083	0.4220	28	2.333	8.319
9	0.75	0.4871	30	2.5	9.822
9½	0.7917	0.5575	30½	2.521	10.0
10	0.8333	0.6337	32	2.667	11.6
10½	0.8750	0.7157	34	2.833	13.5
11	0.9167	0.8044	36	3	15.5
11½	0.9583	0.8987	38	3.167	17.8
12	1	1	40	3.333	20.2

This table shows, also, the relative discharging capacities of long pipes. Thus, one 12-in pipe is equal to two 9-in pipes, to nearly six 6-in pipes, or to thirty-three 3-in pipes.

**Table E. Flow of Water in House Service-Pipes**

Thomson Meter Company

To find the discharge in gallons, multiply by 7.47

Condition of discharge	Pressure in main, lb per sq in	Discharge in cubic feet per minute from the pipe								
		Nominal diameters of iron or lead service-pipe in inches								
		$\frac{1}{2}$	$\frac{3}{8}$	$\frac{3}{4}$	1	$1\frac{1}{2}$	2	3	4	6
Through 35 ft of service-pipe; no back-pressure	30	1.10	1.92	3.01	6.13	16.58	33.34	88.16	173.85	444.63
	40	1.27	2.22	3.48	7.08	19.14	38.50	101.80	200.75	513.42
	50	1.42	2.48	3.89	7.92	21.40	43.04	113.82	224.44	574.02
	60	1.56	2.71	4.26	8.67	23.44	47.15	124.68	245.87	628.81
	75	1.74	3.03	4.77	9.70	26.21	52.71	139.39	274.89	703.03
	100	2.01	3.50	5.50	11.20	30.27	60.87	160.96	317.41	811.79
	130	2.29	3.99	6.28	12.77	34.51	69.40	183.52	361.91	925.58
Through 100 ft of service-pipe; no back-pressure	30	0.66	1.16	1.84	3.78	10.40	21.30	58.19	118.13	317.23
	40	0.77	1.34	2.12	4.36	12.01	24.59	67.19	136.41	366.30
	50	0.86	1.50	2.37	4.88	13.43	27.50	75.13	152.51	409.54
	60	0.94	1.65	2.60	5.34	14.71	30.12	82.30	167.06	448.63
	75	1.05	1.84	2.91	5.97	16.45	33.68	92.01	186.78	501.58
	100	1.22	2.13	3.36	6.90	18.99	38.89	106.24	215.68	579.18
	130	1.39	2.42	3.83	7.86	21.66	44.34	121.14	245.91	660.36
Through 100 ft of service-pipe and 15-ft vertical rise	30	0.55	0.96	1.52	3.11	8.57	17.55	47.90	97.17	260.56
	40	0.66	1.15	1.81	3.72	10.24	20.95	57.20	116.01	311.09
	50	0.75	1.31	2.06	4.24	11.67	23.87	65.18	132.20	354.49
	60	0.83	1.45	2.29	4.70	12.94	26.48	72.28	146.61	393.13
	75	0.94	1.64	2.59	5.32	14.64	29.96	81.79	165.90	444.85
	100	1.10	1.92	3.02	6.21	17.10	35.00	95.55	193.82	519.72
	130	1.26	2.20	3.48	7.14	19.66	40.23	109.82	222.75	597.31
Through 100 ft of service-pipe and 20-ft vertical rise	30	0.44	0.77	1.22	2.50	6.80	14.11	38.63	78.54	211.54
	40	0.55	0.97	1.53	3.15	8.68	17.79	48.68	98.98	266.59
	50	0.65	1.14	1.79	3.69	10.16	20.82	56.98	115.87	312.08
	60	0.73	1.28	2.02	4.15	11.45	23.47	64.22	130.59	351.73
	75	0.84	1.47	2.32	4.77	13.15	26.95	73.76	149.99	403.98
	100	1.00	1.74	2.75	5.65	15.58	31.93	87.38	177.67	478.55
	130	1.15	2.02	3.19	6.55	18.07	37.02	101.33	206.04	554.96

Table E may also be used when the pressure is in feet-head of water by reducing head in feet to pounds per square inch by Table A. Thus, if we wish the discharge per minute through a  $\frac{3}{4}$ -in pipe 100 ft long with a head of 70 ft, we find from Table A that a head of 70 ft corresponds to a pressure of 30 lb per sq in. From Table E we find the discharge through a  $\frac{3}{4}$ -in pipe 100 ft long with a pressure of 30 lb to be 1.84 cu ft per minute.

**Table F.   Friction of Water in Pipes Based on Ellis and Howland's Experiments**

The following table gives the friction-loss in pounds-pressure per square inch for EACH 100 ft of length in clean iron pipes of different sizes, discharging given quantities of water per minute.    This friction-loss is greatly increased by bends or irregularities in the pipe.

To find the friction-head in feet, multiply by 2.3

Gallons per minute	Sizes of pipes, inside diameter							
	¾ in	1 in	1¼ in	1½ in	2 in	2½ in	3 in	4 in
5	3.3	0.84	0.31	0.12	.....	.....	.....	.....
10	13.0	3.16	1.05	0.47	0.12	.....	.....	.....
15	28.7	6.98	2.38	0.97	0.26	.....	.....	.....
20	50.4	12.3	4.07	1.66	0.42	.....	.....	.....
25	78.8	19.0	6.40	2.62	0.64	0.21	0.10	0.27
30	.....	27.5	9.15	3.75	0.91	.....	.....	.....
35	.....	37.0	12.4	5.05	1.22	.....	.....	.....
40	.....	48.0	16.1	6.52	1.60	.....	0.20	.....
45	.....	.....	20.2	8.15	2.02	.....	.....	.....
50	.....	.....	24.9	10.0	2.44	0.81	0.35	0.09
75	.....	.....	56.1	22.4	5.32	1.80	0.74	0.23
100	.....	.....	.....	39.0	9.46	3.20	1.31	0.33
125	.....	.....	.....	.....	14.9	4.89	1.99	0.49
150	.....	.....	.....	.....	21.2	7.00	2.85	0.69
175	.....	.....	.....	.....	28.1	9.46	3.85	0.94
200	.....	.....	.....	.....	37.5	12.47	5.02	1.22
250	.....	.....	.....	.....	.....	19.66	7.76	1.89
300	.....	.....	.....	.....	.....	28.06	11.2	2.66
350	.....	.....	.....	.....	.....	.....	15.2	3.65
400	.....	.....	.....	.....	.....	.....	19.5	4.73
450	.....	.....	.....	.....	.....	.....	25.0	6.01
500	.....	.....	.....	.....	.....	.....	30.8	7.43
600	.....	.....	.....	.....	.....	.....	.....	9.54
700	.....	.....	.....	.....	.....	.....	.....	14.31

**Water-Pipe** is usually tested to 300 lb pressure per square inch before delivery, and a hammer-test should be made while the pipe is under pressure.    The usual length for each section of cast-iron water-pipe is from 12 ft 4 in to 12 ft 6 in, depending upon the depth of the socket, each length making approximately 12 ft of pipe when laid.    Pipes from 2 to 4 in diameter are sometimes made in 8 or 9-ft lengths.

# Safe Pressures and Equivalent Heads of Water for Cast-Iron Pipes of Different Sizes and Thicknesses

Calculated by F. H. Lewis from Fanning's Formula

Thick- ness, in	Size of pipe, in											
	4		6		8		10		12		14	
	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft
$\frac{3}{16}$	112	258	49	112	18	42	.....	.....	.....	.....	.....	.....
$\frac{1}{2}$	224	516	124	280	74	171	44	101	24	55	.....	.....
$\frac{9}{16}$	336	774	199	458	130	300	89	205	62	143	42	97
$\frac{5}{8}$	...	...	274	631	186	429	132	304	99	228	74	170
$1\frac{1}{16}$	...	...	...	...	...	...	177	408	137	316	106	244
$\frac{3}{4}$	...	...	...	...	...	...	224	516	174	401	138	316
$1\frac{3}{16}$	...	...	...	...	...	...	.....	.....	212	488	170	392
$\frac{7}{8}$	...	...	...	...	...	...	.....	.....	249	574	202	465
$1\frac{5}{16}$	...	...	...	...	...	...	.....	.....	.....	.....	234	538
I	...	...	...	...	.....	...	.....	.....	.....	.....	266	612

	16		18		20		24		30		36	
	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft	Pressure, lb	Head, ft
$\frac{5}{8}$	56	129	41	95	...	...	.....	.....	.....	.....	.....	.....
$1\frac{1}{16}$	84	194	66	152	51	118	30	69	.....	.....	.....	.....
$\frac{3}{4}$	112	258	91	210	74	170	49	113	24	55	.....	.....
$1\frac{3}{16}$	140	323	116	267	96	221	68	157	39	90	.....	.....
$\frac{7}{8}$	168	387	141	325	119	274	86	198	54	124	32	74
$1\frac{5}{16}$	196	452	166	382	141	325	105	242	69	159	44	101
I	224	516	191	440	164	378	124	286	84	194	57	131
$\frac{3}{8}$	...	...	216	497	209	481	161	371	114	263	82	189
$\frac{1}{2}$	...	...	...	...	256	589	199	458	144	332	107	247
$\frac{5}{8}$	...	...	...	...	...	...	237	546	174	401	132	304
$\frac{3}{4}$	...	...	...	...	...	...	.....	.....	204	470	157	362
$\frac{7}{8}$	...	...	...	...	...	...	.....	.....	234	538	182	419
$\frac{15}{16}$	...	...	...	...	...	...	.....	.....	.....	.....	207	477

## Weights of Lead and Gaskets for Pipe-Joints

Dennis Long & Company

Diameter of pipe, in	Lead, lb	Gasket, lb	Diameter of pipe, in	Lead, lb	Gasket, lb
2	2.5	0.125	12	15	0.250
3	3.5	0.170	14	18	0.375
4	4.5	0.170	16	22	0.500
6	6.5	0.200	18	26	0.500
8	9.0	0.200	20	33	0.625
10	13.0	0.250	.....	.....	.....

**Weights, per Foot, of Cast-Iron Pipes in General Use, Including Socket-Ends and Spigot-ends**

Dennis Long &amp; Company, Inc., Louisville, Ky.

Diam- eter, in	Thick- ness, in	Weight per ft., lb	Diam- eter, in	Thick- ness, in	Weight per ft., lb	Diam- eter, in	Thick- ness, in	Weight per ft., lb
3	$\frac{3}{8}$	12 $\frac{1}{2}$	16	$\frac{3}{4}$	129	30	2	668
	$\frac{7}{16}$	15		$\frac{7}{8}$	152		$\frac{7}{8}$	334
	$\frac{1}{2}$	18		1	175		1	382
	$\frac{9}{16}$	20 $\frac{1}{2}$		$\frac{5}{8}$	120		$1\frac{1}{8}$	432
	$\frac{5}{8}$	23		$\frac{3}{4}$	146		$1\frac{1}{4}$	482
4	$\frac{3}{8}$	17	18	$\frac{7}{8}$	171	36	$1\frac{3}{8}$	532
	$\frac{7}{16}$	20		1	197		$1\frac{1}{2}$	587
	$\frac{1}{2}$	23 $\frac{1}{2}$		$1\frac{1}{8}$	223		$1\frac{5}{8}$	632
	$\frac{9}{16}$	26 $\frac{3}{4}$		$1\frac{1}{4}$	249		$1\frac{3}{4}$	683
	$\frac{5}{8}$	30		$1\frac{3}{8}$	276		$1\frac{7}{8}$	734
6	$\frac{7}{16}+$	30	20	$1\frac{1}{2}$	305	42	2	786
	$\frac{1}{2}$	34		$\frac{3}{4}$	161		2	786
	$\frac{9}{16}$	38 $\frac{1}{4}$		$\frac{7}{8}$	190		1	445
	$\frac{5}{8}$	42 $\frac{1}{2}$		1	216		$1\frac{1}{8}$	471
	$\frac{3}{4}$	52		$1\frac{1}{8}$	247		$1\frac{1}{4}$	560
8	$\frac{7}{16}$	40	24	$1\frac{1}{4}$	276	48	$1\frac{3}{8}$	629
	$\frac{1}{2}$	43 $\frac{1}{2}$		$1\frac{3}{8}$	305		$1\frac{1}{2}$	675
	$\frac{9}{16}$	49 $\frac{3}{4}$		$1\frac{1}{2}$	334		$1\frac{5}{8}$	734
	$\frac{5}{8}$	56		$\frac{3}{4}$	191		$1\frac{3}{4}$	794
	$\frac{3}{4}$	68		$\frac{7}{8}$	225		$1\frac{7}{8}$	853
10	$\frac{7}{16}$	50	30	1	258	60	2	912
	$\frac{1}{2}$	54		$1\frac{1}{8}$	293		$1\frac{1}{8}$	572
	$\frac{9}{16}$	60		$1\frac{1}{4}$	327		$1\frac{1}{4}$	637
	$\frac{5}{8}$	68		$1\frac{3}{8}$	361		$1\frac{3}{8}$	701
	$\frac{3}{4}$	82		$1\frac{1}{2}$	395		$1\frac{1}{2}$	768
12	$\frac{1}{2}$	70	36	$1\frac{5}{8}$	430	72	$1\frac{5}{8}$	835
	$\frac{9}{16}$	76		$1\frac{3}{4}$	465		$1\frac{3}{4}$	901
	$\frac{5}{8}$	82		$1\frac{7}{8}$	500		$1\frac{7}{8}$	967
	$\frac{3}{4}$	99		2	532		2	1 034
	$\frac{7}{8}$	117		$1\frac{1}{8}$	319		$1\frac{1}{4}$	797
14	$\frac{9}{16}$	85	42	$1\frac{1}{4}$	360	84	$1\frac{3}{8}$	880
	$\frac{5}{8}$	94		$1\frac{3}{4}$	405		$1\frac{1}{2}$	964
	$\frac{3}{4}$	113		$1\frac{5}{8}$	448		$1\frac{5}{8}$	1 049
	$\frac{7}{8}$	137		$1\frac{1}{2}$	489		$1\frac{3}{4}$	1 133
	$\frac{9}{16}$	100		$1\frac{5}{8}$	532		$1\frac{7}{8}$	1 216
16	$\frac{5}{8}$	108	48	$1\frac{3}{4}$	575	96	2	1 300
				$1\frac{7}{8}$	619		$2\frac{1}{4}$	1 470

There is no standard weight of pipe for any given pressure.

**Private Water-Supply. Pumps**

**Private Water-Supplies.** The architect is frequently required to furnish a water-supply for isolated buildings, and even in cities it is becoming quite common for manufacturing establishments and large buildings to have their own water-supply; so that some knowledge of the various methods of supplying water is requisite. Power-pumps are of so many kinds and so intricate in construction that no attempt will be made to describe them.

**The Hydraulic Ram.** Where a small stream of water having a fall of a foot or more flows near the premises, an hydraulic ram may be used to great advantage.



water for domestic purposes, or even for irrigation. The ram uses the momentum of the water flowing through the drive-pipe and discharges it into an open tank. Water can be conveyed by a ram 13 000 ft high, provided there is sufficient fall. The drive-pipe supplying the ram is 30 or 40 ft long to give the necessary momentum. The use of the ram is the most economical method of pumping water, as there is no maintenance except for repairs, and the cost of installation, also, is small.

The capacities of the Rife Rams are given in the following table. The capacity can be determined from the table by multiplying the available supply of water by the factor at the intersection of the line giving the fall available, for the column showing the height the water is to be elevated. The capacity for a 10-ft and 50-ft discharge is 192, and this multiplied by the supply of water per minute will give the delivery per day. This is shown by the example worked out in the corner of the table. These capacities are based on efficiencies dependent on the ratio of fall to lift. A fall of 10 ft and a lift of .50 ft give a ratio of 1 to 5, and an efficiency of 66⅔%. The efficiencies of Rife rams based on various ratios, are also given in the table.

**Deep Wells and Plunger-Pumps.** The common method of obtaining a private water-supply is to drive a deep well until a sufficient supply of water is obtained. The depth to which a well must be driven will, of course, depend upon the locality, and can only be determined by drillings. As the well is driven, a large wrought-iron pipe is sunk to form the casing. Casings are seldom less than 6 or more than 10 in inside diameter, 8 in being the common size. When the water-pocket has been reached, the water will usually rise and stand in the pipe several hundred feet above its bottom, and the amount of water that can usually be pumped from such wells, without lowering the water, is practically unlimited. The cost of drilling deep wells, per foot

Fig. 2. Deep-well Working-head for Belt-attachment

THE CASING, differs, of course, with the strata, location and so on. As a rule, however, it will average about \$5 per foot for a rock and \$6 per foot for a well through sand. For raising water from an open tank a single-acting pump consisting of a working-plunger operates a cylinder placed in a smaller pipe lowered into the well, in which the water is raised, is commonly employed. The plunger can be placed below the water-line in the well, and is raised by the working-head by wooden sucker-rods. The working-



ad may be operated by hand, or by a crank-rod attached to a pumping-jack, mill or engine. With a single-acting pump the plunger is raised and lowered once with every revolution of the driving-wheel, the principle of operation being the same as in an ordinary hand suction-pump. Fig. 2 shows a simple arrangement for operating a working-head by belt-power. This is known as a deep-well power working-head. A DEEP-WELL PUMP (Fig. 2) differs from a SUCTION-PUMP in that it will raise water from any depth, whereas a suction-pump in practice will raise water only about 20 ft. A suction-pump may be placed at any point in relation to the well, and will draw the water any considerable horizontal distance. The deep-well pump, on the other hand, must be set directly over the well, but it will then deliver the water at any desired height. The amount of water pumped in a minute by any single-acting pump is determined by the diameter of the suction-cylinder, the length of stroke, and the number of strokes per minute. The table following gives the capacity per minute for cylinders of different diameters, and for strokes of different lengths. To find the capacity per minute, multiply the values given in the table by the revolutions per minute. The usual speed of single-acting working-heads and pumping-jacks is from 25 to 30 revolutions per minute. Cylinders over 2¾ in in diameter should have a substantial iron working-head.

Table Showing Capacity of Single-Acting Pumps of Given Diameter and Length of Stroke

m. n- in es	Length of stroke in inches								
	6	8	10	12	14	16	18	20	24
	Capacity per stroke in gallons								
1	0.0319	0.0425	0.0531	0.0637	0.0743	0.0848	0.0955	0.1062	0.1274
2	0.0385	0.0513	0.0642	0.0770	0.0890	0.1027	0.1156	0.1280	0.1541
3	0.0459	0.0612	0.0765	0.0918	0.1071	0.1224	0.1377	0.1530	0.1836
4	0.0625	0.0833	0.1041	0.1249	0.1457	0.1666	0.1874	0.2082	0.2499
5	0.0816	0.1088	0.1360	0.1632	0.1904	0.2176	0.2448	0.2720	0.3264
6	0.1033	0.1377	0.1721	0.2063	0.2410	0.2754	0.3096	0.3442	0.4128
7	0.1275	0.1700	0.2125	0.2550	0.2975	0.3400	0.3825	0.4250	0.5100
8	0.1543	0.2057	0.2571	0.3085	0.3598	0.4114	0.4626	0.5142	0.6170
9	0.1836	0.2448	0.3060	0.3672	0.4284	0.4896	0.5508	0.6120	0.7344
10	0.2154	0.2872	0.3594	0.4312	0.5030	0.5748	0.6466	0.7182	0.8624
11	0.2499	0.3332	0.4165	0.4998	0.5831	0.6664	0.7497	0.8330	0.9996
12	0.2868	0.3824	0.4780	0.5736	0.6692	0.7648	0.8605	0.9561	1.1470
13	0.3264	0.4352	0.5440	0.6528	0.7616	0.8704	0.9792	1.0880	1.3056
14	0.3684	0.4912	0.6141	0.7368	0.8596	0.9824	1.1050	1.2280	1.4730
15	0.4131	0.5508	0.6885	0.8262	0.9639	1.1016	1.2393	1.3770	1.6524
16	0.4602	0.6136	0.7671	0.9204	1.0730	1.2270	1.3800	1.5340	1.8400

**Air Engines.** These are very extensively used for pumping water for houses, as they are absolutely safe, require little attention, and have no valves, springs or gauges to get out of order. They are also adapted to any kind of fuel, such as coal, coke, wood, gas, or kerosene oil. They may be used for either a shallow or a deep well, but are best adapted to wells

in which the surface of the water is within 20 ft of the top of the well. The best known hot-air engines are the Rider-Ericsson, which have been in successful operation for many years. These engines have capacities ranging from 1 to 3 500 gal per hour and will deliver water from 50 to 350 ft above the surface of water in the well, although the higher the water is raised the less will be the quantity delivered. The cost of these engines, with pump attached, varies from \$110 for the smallest size, having a capacity of 150 gal per hour raised 50 ft, to \$540 for the largest size, having a capacity of 3 500 gal per hour raised 50 ft. The smaller size requires about 1 quart of kerosene or 3 lb of anthracite coal per hour. Hot-air engines should be placed close to the source of supply, and when the latter is a deep well the engine must be placed so that the pump-rod will be in a vertical line above the cylinder of the well, the operation of pumping being the same as that of the ordinary single-acting deep-well pump. It is not practicable to DRAW water more than from 20 to 25 ft, in height, with any form of suction-pump, because of the difficulty of keeping the pipe, valve and fittings absolutely air-tight. For further information, see the catalogue of the Rider-Ericsson Engine Company.

**Action of Wind and Capacities of Pumping Windmills**

Velocity per hour in miles	Pressure * per square foot in pounds	Description of wind	Action of wind and windmill
3	0.045	Just perceptible.....	Windmills will not run
5	0.125	Pleasant wind.....	Might start if lightly loaded
8	0.33	Fresh breeze.....	Will start pumping
10	0.5	Average wind.....	Pumps nicely if properly loaded
15	1.125	Good working wind...	Does excellent work
20	2	Strong wind.....	Gives best service
25	3.125	Very strong wind.....	Maximum results secured
30	4.5	Gale.....	Should be furled out of wind
40	8	Storm.....	{ Well-constructed mills and towers safe if properly erected
50	12.5	Severe storm.....	
60	18	Violent storm.....	{ Buildings, trees, etc., might be injured
80	32	Hurricane.....	{ Buildings, trees, etc., would be injured
100	50	Tornado .....	Ruin

From the above table it will be seen that the only available winds are those blowing with a velocity of from 8 to 25 miles per hour, and that a 15-mile wind can be utilized to the best advantage. It is therefore advisable to LOAD a windmill for a 15-mile wind. It then starts pumping in an 8-mile wind, does excellent work in a 15-mile wind and reaches the maximum results in a 25-mile wind.

\* The pressures per square foot in pounds will vary slightly from the values given according to the formula which is used to obtain such pressures. See, also, Chapter XXVII, pages 1052-3, Chapter XXX, page 1199, and page 1717.

**Windmills.** In the country and on large suburban estates, windmills are extensively used for pumping water. Aside from the noise of operation, the only objection to the windmill, where it can be used, is the irregularity of the water supply, but with a large storage-tank this is not a serious objection when the windmill is used for domestic purposes only. Professor Thurston says, regarding windmills, "In estimating the capacity, a working-day of eight hours is assumed, but

machine, when used for pumping, may actually do its work twenty-four hours a day for days, weeks, and even months together, whenever the wind is stiff enough to turn it. It costs for work done only one-half or one-third as much as steam, hot-air, or gas-engines of similar power." The action of wind of different velocities, the pressure per square foot of sail-surface and its relation to the pumping capacity of pumps can be found in the following table, compiled by Airbanks, Morse & Company.

The windmill operates the plunger in the well, the process of pumping being the same as that of the single-acting pumps described above. The following table of capacity was prepared by Alfred R. Wolff, and is sufficiently accurate for all practical purposes:

Capacity of the Windmill

Designation of mill wheel, ft	Velocity of wind in miles per hour	Revolutions of wheel per minute	Gallons of water raised per minute to an elevation of						Equivalent actual useful h.p. developed
			25 ft	50 ft	75 ft	100 ft	150 ft	200 ft	
8½	16	40 to 50	6.192	3.016	....	....	....	....	0.04
10	16	35 to 40	19.179	9.563	6.638	4.750	....	....	0.12
12	16	30 to 35	33.941	17.952	11.851	8.435	5.680	....	0.21
14	16	28 to 35	45.139	22.569	15.304	11.246	7.807	4.998	0.28
16	16	25 to 30	64.600	31.654	19.542	16.150	9.771	8.075	0.41
18	16	22 to 25	97.682	52.165	32.513	24.421	17.485	12.211	0.61
20	16	20 to 22	124.950	63.750	40.800	31.248	19.284	15.938	0.78
25	16	16 to 18	212.381	106.964	71.604	49.725	37.349	26.741	1.34

The horse-power of windmills of the best construction is proportional to the areas of their diameters and inversely as their velocities; for example, a 10-ft mill in a 16-mile breeze will develop 0.15 horse-power at 65 revolutions per minute; and with the same breeze:

- a 20-ft mill, at 40 revolutions per minute, 1 horse-power;
- a 25-ft mill, at 35 revolutions per minute, 1¾ horse-power;
- a 30-ft mill, at 28 revolutions per minute, 3½ horse-power.

The wheels of very few windmills are larger than 25 ft in diameter. There are no pumps which will enable the user of a windmill to utilize the increased power obtained from winds of high velocity, so that in practice the amount of water pumped by windmills in high winds is but little more than is pumped by the same mills in winds having velocities of from 12 to 18 miles per hour. For this reason it is customary to regulate windmills to govern at about 25 miles an hour. Theoretically the increase in power from increased velocity of wind is equal to the square of its proportional velocity; as, for example, the 25-ft mill rated for a 16-mile wind will, with a 32-mile wind, have its horse-power increased  $\times 1\frac{3}{4} = 7$  horse-power. A windmill "will run and produce work in an 8-mile breeze." Windmills have also been used for the generating and storage of electricity for small lighting-plants.\*

**Compressed-Air Lift Process.** Compressed air is now being used to an increasing extent for raising water from artesian wells. The process in general consists of submerging a discharge-pipe in a closed well, with a smaller pipe inside delivering

\* See Kent's Mechanical Engineers' Pocket-Book.

compressed air into it at the bottom. The compressed air by its inherent expansive force lifts a column of mingled air and water which is conveyed to an open tank, to permit of the escape of the air. If desired the water may then be conveyed by gravity into a series of closed tanks, and forced by air-pressure to different parts of a building, the only machinery required being an air-compressor and power for driving it. The slip of the bubble constitutes the chief loss of energy in the air-lift. The method of piping a well differs according to its general conditions and the quantity of water to be pumped. "No two wells are alike, and consequently the method of piping which might be applied to one would be unsuited to another." Information as to the best method of piping any particular well may be obtained from the Ingersoll-Sergeant Drill Company.

**Advantages of the Air-Lift Process.** From two to six times as much water may be obtained from a given diameter of well as with any other known system because there are no valves, cylinders, or rods to hinder the rapid discharge of water. One air-compressor operates any number of wells, which may be at any distance apart so as not to affect one another. There is nothing outside the engine-room to look after or wear out. Nothing but common pipe in the well. Sand or gravel does no harm. The cost of raising 1 000 gal of water by this method, including fuel, labor, oil, interest on cost of well, boiler, compressor, foundations, pipes, real estate, erection and taxes, including 15% for depreciation, runs from 2½ cts down to ¼ ct, according to the size of the plant, height of lift, and other local conditions. With the average outfit of medium or small size, it is usually under 1¼ cts.\* The air-lift process is now extensively used in ice-works, breweries, cold-storage houses, textile mills, dye-works, etc., and a great variety of industrial plants, and for the water-supply in quite a number of the smaller cities. In Newark, N. J., pumps of this type are at work having a total capacity of 1 000 000 gal daily, lifting water from three 8-in artesian wells.†

**Pneumatic Water-Supply Systems.** The pneumatic system of supplying water to buildings is used extensively in buildings and institutions remote from public water-supplies. With the pneumatic system, instead of an open elevated tank, a closed water-tight tank of iron or steel is used, and this tank may be located at any level, for the water is forced from it by means of compressed air confined in the top of the tank. This fact makes it possible to bury the tank in the ground below the frost-line, away from the heat of the sun, and where the water will have an almost uniform temperature the year round. The water is protected from possible contamination from insects, rats, birds, dust, or other agencies, while the tank takes up no valuable space above ground, imposes no weight upon the attic-floor of a building, and does not disfigure the landscape. The principle of operation is this: Air is compressible, while water is not. When, then, water is pumped into a closed tank at the bottom, it will trap the air within, and the more water pumped in, the greater the compression, of the air. The elasticity of the air, then, will force the water out again, whenever a faucet is opened, and the water will continue to flow as long as the air is under sufficient pressure in the tank. In practice the air would become absorbed by the water in the tank, and in a short time become exhausted, if it were not supplied as fast as used. This is accomplished by injecting a proportionate amount of air with each stroke of the pump, by means of a SNIFFER-VALVE air-compressor, or other device. All connections to the tank are taken from the bottom, to prevent the escape of air, which would occur if the connections were taken from the top of the tank.

\* Ingersoll-Rand Drill Company, St Louis, Mo.

† Kent.

Horse-Power Required to Raise Water to Different Heights

**General Principles.** The power required to raise a certain quantity of water to certain height varies directly with the quantity to be raised, and also with the height. For instance, it requires twice as much power to raise 200 gal per minute 20 ft high as it does to raise 100 gal to the same height and in the same time; and to raise 100 gal 20 ft high requires twice as much power as it does to raise 100 gal 10 ft high. To find the theoretical horse-power necessary to elevate water to a given height, multiply the number of gallons per minute by 8.335, the weight of 1 gal, and this result by the total number of feet the water is raised, that is, from the surface of the water to the highest point to which the water is raised, and the result gives the power in foot-pounds; divide by 33 000, and the quotient is the horse-power. To the theoretical power a liberal allowance must be made for the inefficiency of the pump. For a cylinder-pump add from 75 to 100%. To the actual height to which the water is to be raised add the friction-loss in ft, given in Table F, page 1388, when the discharge is to be piped any distance.

**Example.** Find the theoretical horse-power required to raise 100 gal per minute 120 ft high, through a 3-in pipe, 200 ft long.

**Solution.** From Table F, the friction-head for 100 gal per min in a 3-in pipe, 200 ft long, is  $1.31 \times 2.3$  or 3 ft. For 200 ft it will be 6 ft, which, added to 120, makes 126 ft for the height. Then theoretical horse-power =  $100 \times 8.35 \times 126 / 33000 = 3.2$  h.p. The actual horse-power required will probably vary from 4 to 6, according to the efficiency of the pump. The mistake of using too small a discharge-pipe can easily be seen from Table F. For instance, if it is attempted to force 100 gal per minute through 100 ft of 2-in pipe, the back-pressure would be equivalent to raising the water 22 ft high. The horse-power used would be correspondingly increased. Right-angle turns are to be provided, as the friction is very materially increased, being practically equal to the friction of 25 ft of straight pipe.

Table of Effective Fire-Streams

Using 100 ft of 2 1/4-in ordinary best-quality rubber-lined hose between nozzle and hydrant or pump

Smooth nozzle	3/4 in					7/8 in				
Pressure at hydrant, lb.....	32	54	65	75	86	34	57	69	80	91
Pressure at nozzle, lb.....	30	50	60	70	80	30	50	60	70	80
Theoretical height, ft.....	48	67	72	76	79	49	71	77	81	85
Horizontal distance, ft.....	37	50	54	68	62	42	55	61	66	70
Gal discharged per min.....	90	116	127	137	147	123	159	174	188	201

Smooth nozzle	1 in					1 1/8 in				
Pressure at hydrant, lb.....	37	62	75	87	100	42	70	84	98	112
Pressure at nozzle, lb.....	30	50	60	70	80	30	50	60	70	80
Theoretical height, ft.....	51	73	79	85	89	52	75	83	88	92
Horizontal distance, ft.....	47	61	67	72	76	50	66	72	77	81
Gal discharged per min.....	161	208	228	246	263	206	266	291	314	336

**Fire-Streams.** The following is an extract from a paper read by John Freeman at a meeting of the New England Waterworks Association, and Some Experiments and Practical Tables Relating to Fire-Streams,

"When unlined linen hose is used the friction or pressure-loss is from 8 to 60%, increasing with the pressure. This kind of hose is best for inside use in short lengths. Mill-hose is better than unlined linen hose for long lengths but ordinarily the best quality of smooth rubber-lined hose is superior to the mill-hose, having less frictional resistance. The ring-nozzle is inferior to the smooth nozzle and actually delivers less water than the smooth nozzle. For instance, the  $\frac{7}{8}$ -in ring-nozzle discharges the same quantity of water as a  $\frac{3}{4}$ -in smooth nozzle, and a 1-in ring-nozzle the same as a  $\frac{7}{8}$ -in smooth nozzle. Two hundred and fifty gallons per minute is a good standard fire-stream at 80-lb pressure at the hydrant; 100-lb pressure should not be exceeded except for very high buildings or lengths of hose exceeding 300 ft."

### **Notes on the Construction of Cylindrical Wooden Tanks\***

**Material** should be either cedar, cypress, juniper, fir, yellow pine, or white pine, free from imperfections and thoroughly air-dry. Clear Louisiana red Gulf cypress makes the most durable tanks.

**Staves and Bottom** of tanks of greater capacities than 15 000 gal should be made of  $2\frac{1}{2}$ -in, dressed to about  $2\frac{3}{4}$  in, stock for tanks 12 ft and not exceeding 16 ft diameter or 16 ft deep. For larger tanks 3-in, dressed to about  $2\frac{3}{4}$  in stock should be used. For smaller tanks 2-in stock may be used. Staves should be connected about one-third the distance from the top by a  $\frac{1}{2}$ -in dowel to hold them in position during erection. The bottom planks should be dressed on four sides, and the edges of each plank should be bored with holes not over 3 ft apart for  $\frac{3}{8}$ -in dowels.

**Taper.** The batter to each side should not be less than  $\frac{1}{4}$  in nor more than  $\frac{1}{2}$  in per ft.


**Hoops** should be of ROUND wrought iron or mild steel of good quality. Wrought iron is preferable because it does not rust as easily as steel. There should be no welds in any of the hoops. Where more than one length of iron is necessary, lugs should be used to make the joints; and when more than one piece is necessary the several pieces constituting one hoop should be tied together in preparing for shipment. Hoops for fire-tanks should be of such size and spacing that the stress in no hoop will exceed 12 500 lb per sq in when computed from the area at root of thread. For general purposes, a stress of 15 000 lb per sq in is permissible. On account of the swelling of the bottom planks, the hoops near the bottom may be subjected to a stress greater than that due to the water-pressure alone; additional hoops, therefore, should be provided. For tanks up to 20 ft in diameter, one hoop of the size used next above it should be placed around the bottom opposite the croze and not counted upon as withstanding any water-pressure. For tanks 20 ft or more in diameter, two hoops, as above, should be used. Hoops with UPSET ends must not be used. The top hoop should be placed within 2 in of the top of staves, so that the overflow-pipe may be inserted as high as possible. Hoops should be so placed that the lugs will not be in a vertical line. No hoop should be less than  $\frac{3}{4}$  in in diameter. All should be cleaned of mill-scale and rust and painted one coat of red lead, lampblack and boiled oil before erecting.

**Note.** The strength of a tank depends chiefly on its hoops. Round hoops are specified because they do not rust rapidly; a slight amount of rust does


\* These notes have been condensed from specifications published by the Inspection Department of the Factory Mutual Fire Insurance Company, 31 Milk Street, Boston; most excellent pamphlet.



**Spacing of Hoops.** The hoops should be spaced so that each one will have the same stress per square inch, and no space should be greater than 21 in. To meet this requirement the hoops must be spaced quite close together at the bottom, the space between them gradually increasing towards the top.



**Fig. 4. Lug for Tank-hoops**



**Fig. 5. Support for Bottom of Tank**

30,000 Gals. 18 ft. stove. 18 ft. dia.

$$\text{Spacing of hoops in inches} = \frac{\text{strength}}{2.6 \times \text{diameter in feet} \times H}$$

### 3. Diagram of Hoop-spacing of Tanks

$H$  is the distance from surface of the water to center of hoop in feet.

**Example.** How far apart should 1-in hoops be placed, at 15 ft 2 in from top of tank, on a tank 20 ft diameter?

**Solution.**       $\text{Spacing} = \frac{6\,875}{2.6 \times 20 \times 15} = 8\frac{3}{4} \text{ in}$

**Lugs** should be as strong as the hoops. A lug similar to Fig. 4 is simple and fulfils the requirement for strength. Malleable lugs are required.

**Support.** The weight of the tank should be supported entirely from its top; and in no event should any weight come on the bottom of the staves. The planks upon which the tank-bottom rests should cover at least one-fifth area of the bottom, should be not over 18 in apart, and of such thickness that the bottom of the staves will be at least 1 in from the floor (see Fig. 5).

**The Discharge-Pipe** should preferably leave the bottom of the tank at its center and extend up inside of the tank 4 in., to allow the sediment to collect at the bottom of the tank.

**The Overflow-Pipe** should be placed as near the top of the tank as possible, discharging either through side or bottom, as may be desired. An overflow is much to be preferred to a telltale, as the latter is liable to get out of order.

**Heating.** Tanks of moderate size need to be provided with some means to prevent freezing. When a tank is in an enclosed room, as in a mill-tower, the best method is to keep the room warm by a coil of steam-pipe with a return to the boiler-room. A covered tank out of doors may often be similarly heated by placing the steam-pipe in the bottom of the tank. With a tank located on a high trestle, or at a distance from the steam-supply, it is often impracticable to arrange a return-pipe. In this case steam may be blown directly into the water in the tank. A 1-in pipe is generally sufficient for this purpose. It should be carried to the top of the tank and there bend over and dip downwards, so that its outlet is about 1 ft below the high-water line. A check-

3 in. horizontal nailing strips

valve should be placed in this steam-pipe, near its point of discharge, to prevent water being drawn back by siphon-action when the steam is shut off. The water in fire-tanks must be kept from freezing by means of a water-heater which either heats a coil in the tank, or circulates a current of water through the tank.

#### **Frostproofing for Pipes.**

The discharge-pipe from a tank on a trestle, or from one elevated above a roof, must be protected from freezing. The common practice is to enclose the pipe in a double, triple, or quadruple box made of boards and tarred paper, as

3 Thick  
around each box except outside, grooved sheathing.


Fig. 6. Method of Frostproofing Pipes

shown in Fig. 6. If steam is supplied to the tank, the steam-pipe is carried inside the box. In New England, New York State and Canada the quadruple boxing is generally used, whereas in the milder regions to the south triple or double boxing is used. The boxing should always be carried down into the ground below the frost-line, and a good tight joint made at the underside of the tank.

**Covers.** For economy in heating and to prevent birds, leaves, etc., from getting into the water, all out-of-door tanks should be covered. A double cover is recommended consisting of a tight flat cover made of matched boards supported by joists which span the top of the tank, and above this a shingled, conical roof. To prevent the covering from being blown off, it should be firmly fastened to the top of the tank by straps of iron. In order to keep out the wind particular attention should be given to making a tight joint where the roof rests on the top of the staves.

Scuttles should be arranged in both the conical and flat covers to give access to the inside of the tank and a substantial, permanent ladder erected to give easy access to the top of the tank.

Dimensions of Tanks of Standard Sizes

Approximate net capacity, gal	Size. Outside dimensions		Thickness of lumber after being machined					Hoops	
	Average diameter, ft in	Length of stave, ft	Staves, in	Bottom, in	A, in	B, in	C, in	Number of	Size, in
10 000	13 4	12	2 1/4	2 1/4	3 1/2	5/8	2 1/8	11	3/4
15 000	14 6	14	2 1/4	2 1/4	3 1/2	5/8	2 1/8	14	3/4
20 000	15 6	16	2 1/4	2 1/4	3 1/2	5/8	2 1/8	{ 5 11	3/4 7/8
25 000	17 6	16	2 3/4	2 3/4	3 1/2	3/4	2 5/8		{ 4 12
30 000	18 0	18	2 3/4	2 3/4	3 1/2	3/4	2 5/8	{ 4 16	3/4 7/8
50 000	22 0	20	2 3/4	2 3/4	3 1/2	3/4	2 5/8		{ 4 19
75 000	24 6	24	2 3/4	2 3/4	3 1/2	3/4	2 5/8	{ 4 6 21	7/8 1 1 1/8
100 000	28 6	24	2 3/4	2 3/4	3 1/2	3/4	2 5/8		{ 5 29

**Pumps for Fire-Streams.** The dimensions of steam-pumps for fire-protection in buildings, approved by the Board of Underwriters, can be found in the following table.

Underwriter Steam Fire-Pumps

Rated capacity, gal per min	Size in inches			Boiler h.p. required, A.S.M.E. standard	Size in inches							Over-all dimen- sions of largest pump of given capacity						Proper capacity for priming-tank
	Diameter of steam-piston	Diameter of water-plunger	Length of stroke		Suction-pipe	Discharge- pipe	Steam supply-pipe	Steam exhaust-pipe	Relief-valve	Piston-rod	Valve-rod	Length	Width	Height				
	in	in	in		in	in	in	in	in	in	in	ft	in	ft	in	ft	in	
500	14	7	12	80	8	6	3	4	3	2	1	9	1/8	5	2	7	5	250
	14	7 1/4	12															
	16	8	10															
750	16	9	12	115	10	7	3 1/2	4	3 1/2	2 1/4	1 1/8	9	5	5	2	8	0	375
	16	9 1/4	12															
	18	10	12															
1000	18 1/2	10 1/2	10	150	12	8	4	5	4	2 3/8	1 1/8	10	8	5	7 1/2	8	10	500
	20	12	16															
1500	20	12	16	200	14	10	5	6	5	2 1/2	1 1/4	12	5	5	7	8	11	750

The capacities given in last column are desirable; but in case the suction-pipe is short and the lift low, a tank of not less than one-half the capacity stated may sometimes be used.

### Notes on Steel Tanks \*

**Steel Tanks** of sizes commonly used for fire-protection cost from 40 to 100% more than wooden tanks. The additional cost for large tanks is relatively less than for small tanks. A steel tank of about 40 000-gal capacity or over can be erected on a steel trestle at about the same cost as a wooden tank, since a saving can be made in the cost of supports by making a hemispherical or conical bottom to the steel tank and supporting the tank directly on the legs of the trestle, thus saving the expense of horizontal supporting beams. A steel tank is superior to a wooden tank for the following reasons: (1) It will last for an indefinite time if KEPT THOROUGHLY PAINTED inside and out, whereas a wooden tank will have to be replaced in from twelve to thirty years, usually in about fifteen years; (2) it will be absolutely tight when once well erected and properly cared for, whereas a wooden tank will shrink and leak if the water gets low; (3) it will not be at all likely to burst suddenly, if originally correctly designed, even if painting is neglected, for experience shows that a few spots will first rust through and thus show the weak condition by small leaks, whereas a wooden tank, if neglected, may burst its hoops suddenly and cause serious damage. The objections to steel tanks are that: (1) They require skilled boiler-makers to erect them, thus adding considerable to the cost when erected at a distance from a boiler-shop; (2) they are more difficult to protect against freezing; (3) they give more trouble by SWEATING when placed in a mill-tower; (4) they deteriorate rapidly if painting is neglected.

**Stresses in Cylindrical Tanks.**† The intensities of stresses in lb per sq in found in cylindrical tanks are as follows: A tensile stress due to hydrostatic pressure at any vertical joint or section of the shell of a tank filled with water,

$$S = 62.5 HD / (2 \times 12 t) = 2.6 HD / t$$

A compressive stress at any horizontal joint or section, due to the weight of the stack,

$$S = W / (\pi D \times 12 t) = 0.026 W / Dt$$

A stress at any horizontal joint or section, tensile on the windward side and compressive on the leeward side, due to the wind,  $S_s = 0.106 M / D^2 t$ . (See Self-Sustaining Steel Chimneys, page 1376.) In the above equation,  $H$  = height of tank in ft above section considered,  $D$  = diameter in ft,  $t$  = thickness of shell in in,  $W$  = weight of tank in lb, and  $M$  = bending moment in ft-lb. The conditions for overturning from wind are most severe when the tank is empty.

**Stand-Pipes** were much used for storage-reservoirs at one time. They usually varied from 12 to 30 ft in diameter and from 35 to 120 ft in height. A tank built in 1889 at Greenwich, Conn., was 80 ft in diameter and 30 ft in height. Its capacity was 1 300 000 gal. A stand-pipe built in 1876 at Winona Minn., was 4 ft in diameter by 210 ft in height. The steel cylinder was surrounded by a masonry tower. A long list of failures, mostly due to faulty design, are recorded against the stand-pipe. Because of this and the superior advantage of the elevated water-tower, few are now built. General Specifications for Elevated Steel Tanks on Towers, and for Stand-pipes (Trans. Am. Soc. C. E., Vol. 64, 1909, pages 548 to 566), and General Specifications for Steel, Water and Oil-Tanks (Proc. Am. Ry. Eng. Asso., vol. 13, 1912), are both reprinted in Ketchum's Structural Engineers' Handbook.

\* Inspection Department of the Factory Mutual Insurance Company, Boston.

† From Notes by Robins Fleming.

**in Cubic Feet and U. S. Gallons of Pipes and Cylinders of Various Diameters and One Foot in Length**

1 gallon = 231 cu in. 1 cu ft = 7.4805 gal

For 1 ft in length		Diameter in inches	For 1 ft in length		Diameter in inches	For 1 ft in length	
1 ft. area in sq ft	U. S. gal 231 cu in		Cu ft, also area in sq ft	U. S. gal, 231 cu in		Cu ft, also area in sq ft	U. S. gal, 231 cu in
.0003	0.0025	6¼	0.2485	1.859	19	1.969	14.73
.0005	0.0040	7	0.2673	1.999	19½	2.074	15.51
.0008	0.0057	7¼	0.2867	2.145	20	2.182	16.32
.0010	0.0078	7½	0.3068	2.295	20½	2.292	17.15
.0014	0.0102	7¾	0.3276	2.450	21	2.405	17.99
.0017	0.0129	8	0.3491	2.611	21½	2.521	18.86
.0021	0.0159	8¼	0.3712	2.777	22	2.640	19.75
.0026	0.0193	8½	0.3941	2.948	22½	2.761	20.66
.0031	0.0230	8¾	0.4176	3.125	23	2.885	21.58
.0036	0.0269	9	0.4418	3.305	23½	3.012	22.53
.0042	0.0312	9¼	0.4667	3.491	24	3.142	23.50
.0048	0.0359	9½	0.4922	3.682	25	3.409	25.50
.0055	0.0408	9¾	0.5185	3.879	26	3.687	27.58
.0065	0.0463	10	0.5454	4.080	27	3.976	29.74
.0073	0.0518	10¼	0.5730	4.286	28	4.276	31.99
.0087	0.0579	10½	0.6013	4.498	29	4.587	34.31
.0101	0.0632	10¾	0.6303	4.715	30	4.909	36.72
.0116	0.0666	11	0.6600	4.937	31	5.241	39.21
.0131	0.0730	11¼	0.6903	5.164	32	5.585	41.78
.0147	0.0785	11½	0.7213	5.396	33	5.940	44.43
.0163	0.0872	11¾	0.7530	5.633	34	6.305	47.16
.0180	0.0939	12	0.7854	5.875	35	6.681	49.98
.0197	0.0998	12½	0.8522	6.375	36	7.069	52.88
.0215	0.0738	13	0.9218	6.895	37	7.467	55.86
.0233	0.6528	13½	0.9940	7.436	38	7.876	58.92
.0251	0.7369	14	1.0690	7.997	39	8.296	62.06
.0270	0.8263	14½	1.1470	8.578	40	8.727	65.28
.0289	0.9206	15	1.2270	9.180	41	9.168	68.58
.0308	1.0200	15½	1.3100	9.801	42	9.621	71.97
.0327	1.1250	16	1.3960	10.440	43	10.085	75.44
.0346	1.2340	16½	1.4850	11.110	44	10.559	78.99
.0365	1.3490	17	1.5760	11.790	45	11.045	82.62
.0384	1.4690	17½	1.6700	12.490	46	11.541	86.33
.0403	1.5940	18	1.7680	13.220	47	12.048	90.13
.0422	1.7240	18½	1.8670	13.960	48	12.566	94.00

\* Actual.

and the capacity of pipes greater than those given, look in the table for a one-half the given size and multiply its capacity by 4, or one of one-size and multiply its capacity by 9, etc. To find the WEIGHT of water of the given sizes, multiply the capacity in cubic feet by the weight of a foot of water at the temperature of the water in the pipe.

and the capacity of a cylinder in U. S. gallons, multiply the length by the of the diameter and by 0.0034.

## Cylindrical Vessels, Tanks, Cisterns, Etc.

Diameter in feet and inches, area in square feet, and U. S. gallons capacity for 1 ft in depth

1 gallon = 231 cu in = 0.1337 cu ft

Diam. ft in	Area, sq ft*	Gal, 1-ft depth	Diam. ft in	Area, sq ft*	Gal, 1-ft depth	Diam. ft in	Area, sq ft*	Gal, 1-ft depth
1	0.785	5.87	5 8	25.22	188.66	19	283.53	2120 9
1 1	0.922	6.89	5 9	25.97	194.25	19 3	291.04	2177 1
1 2	1.069	8.00	5 10	26.73	199.92	19 6	298.65	2234 0
1 3	1.227	9.18	5 11	27.49	205.67	19 9	306.35	2291 7
1 4	1.396	10.44	6	28.27	211.51	20	314.16	2350 1
1 5	1.576	11.79	6 3	30.68	229.50	20 3	322.06	2409 2
1 6	1.767	13.22	6 6	33.18	248.23	20 6	330.06	2469 1
1 7	1.969	14.73	6 9	35.78	267.69	20 9	338.16	2529 6
1 8	2.182	16.32	7	38.48	287.88	21	346.36	2591 0
1 9	2.405	17.99	7 3	41.28	308.81	21 3	354.66	2653 0
1 10	2.640	19.75	7 6	44.18	330.48	21 6	363.05	2715 8
1 11	2.885	21.58	7 9	47.17	352.88	21 9	371.54	2779 3
2	3.142	23.50	8	50.27	376.01	22	380.13	2843 6
2 1	3.409	25.50	8 3	53.46	399.88	22 3	388.82	2908 6
2 2	3.687	27.58	8 6	56.75	424.48	22 6	397.61	2974 3
2 3	3.976	29.74	8 9	60.13	449.82	22 9	406.49	3040 8
2 4	4.276	31.99	9	63.62	475.89	23	415.48	3108 0
2 5	4.587	34.31	9 3	67.20	502.70	23 3	424.56	3175 9
2 6	4.909	36.72	9 6	70.88	530.24	23 6	433.74	3244 6
2 7	5.241	39.21	9 9	74.66	558.51	23 9	443.01	3314 0
2 8	5.585	41.78	10	78.54	587.52	24	452.39	3384 1
2 9	5.940	44.43	10 3	82.52	617.26	24 3	461.86	3455 0
2 10	6.305	47.16	10 6	86.59	647.74	24 6	471.44	3526 6
2 11	6.681	49.98	10 9	90.76	678.95	24 9	481.11	3598 9
3	7.069	52.88	11	95.03	710.90	25	490.87	3672 0
3 1	7.467	55.86	11 3	99.40	743.58	25 3	500.74	3745 8
3 2	7.876	58.92	11 6	103.87	776.99	25 6	510.71	3820 3
3 3	8.296	62.06	11 9	108.43	811.14	25 9	520.77	3895 6
3 4	8.727	65.28	12	113.10	846.03	26	530.93	3971 6
3 5	9.168	68.58	12 3	117.86	881.65	26 3	541.19	4048 4
3 6	9.621	71.97	12 6	122.72	918.00	26 6	551.55	4125 9
3 7	10.085	75.44	12 9	127.68	955.09	26 9	562.00	4204 1
3 8	10.559	78.99	13	132.73	992.01	27	572.56	4283 0
3 9	11.045	82.62	13 3	137.89	1031.5	27 3	583.21	4362.7
3 10	11.541	86.33	13 6	143.14	1070.8	27 6	593.96	4443.1
3 11	12.048	90.13	13 9	148.49	1110.8	27 9	604.81	4524 3
4	12.566	94.00	14	153.94	1151.5	28	615.75	4606 2
4 1	13.095	97.96	14 3	159.48	1193.0	28 3	626.80	4688 8
4 2	13.635	102.00	14 6	165.13	1235.3	28 6	637.94	4772 1
4 3	14.186	106.12	14 9	170.87	1278.2	28 9	649.18	4856 2
4 4	14.748	110.32	15	176.71	1321.9	29	660.52	4941 0
4 5	15.321	114.61	15 3	182.65	1366.4	29 3	671.96	5026 6
4 6	15.90	118.97	15 6	188.69	1411.5	29 6	683.49	5112 9
4 7	16.50	123.42	15 9	194.83	1457.4	29 9	695.13	5199 9
4 8	17.10	127.95	16	201.06	1504.1	30	706.86	5287.7
4 9	17.72	132.56	16 3	207.39	1551.4	30 3	718.69	5376 2
4 10	18.35	137.25	16 6	213.82	1599.5	30 6	730.62	5465 4
4 11	18.99	142.02	16 9	220.35	1648.4	30 9	742.64	5555 4
5	19.63	146.88	17	226.98	1697.9	31	754.77	5646.1
5 1	20.29	151.82	17 3	233.71	1748.2	31 3	766.99	5737 5
5 2	20.97	156.83	17 6	240.53	1799.3	31 6	779.31	5829 7
5 3	21.65	161.93	17 9	247.45	1851.1	31 9	791.73	5922 6
5 4	22.34	167.12	18	254.47	1903.6	32	804.25	6016.2
5 5	23.04	172.38	18 3	261.59	1956.8	32 3	816.86	6110.2
5 6	23.76	177.72	18 6	268.80	2010.8	32 6	829.58	6205.1
5 7	24.48	183.15	18 9	276.12	2065.5	32 9	842.39	6301.1

\* Also cubic feet for 1 ft in depth.

## Capacity of Cisterns and Tanks

Number of barrels (31 1/2 gal) in cisterns and tanks

Diameter, ft								
5	6	7	8	9	10	11	12	13
23.3	33.6	45.7	59.7	75.5	93.2	112.8	134.3	157.6
24.0	40.3	54.8	71.7	90.6	111.9	135.4	161.1	189.1
24.7	47.0	64.0	83.6	105.7	130.6	158.0	188.0	220.6
27.3	53.7	73.1	95.5	120.9	149.2	180.5	214.8	252.1
28.0	60.4	82.2	107.4	136.0	167.9	203.1	241.7	283.7
28.7	67.1	91.4	119.4	151.1	186.5	225.7	268.6	315.2
31.3	73.9	100.5	131.3	166.2	205.1	248.2	295.4	346.7
36.0	80.6	109.7	143.2	181.3	223.8	270.8	322.3	378.2
36.7	87.3	118.8	155.2	196.4	242.4	293.4	349.1	409.7
38.3	94.0	127.9	167.1	211.5	261.1	315.9	376.0	441.3
40.0	100.7	137.1	179.0	226.6	280.8	338.5	400.8	472.8
44.7	107.4	146.2	191.0	241.7	298.4	361.1	429.7	504.3
49.3	114.1	155.4	202.9	256.8	317.0	383.6	456.6	535.8
54.0	120.9	164.5	214.8	272.0	335.7	406.2	483.4	567.3
58.7	127.6	173.6	226.8	287.0	354.3	428.8	510.3	598.0
63.3	134.3	182.8	238.7	302.1	373.0	451.3	537.1	630.4

## Diameter, ft

2.8	209.8	238.7	269.5	302.1	336.6	373.0	411.2	451.3
9.3	251.8	286.5	323.4	362.6	404.0	447.6	493.5	541.6
5.9	293.7	334.2	377.3	423.0	471.3	522.2	575.7	631.9
2.4	335.7	382.0	431.2	483.4	538.6	596.8	658.0	722.1
9.0	377.7	429.7	485.1	543.8	605.9	671.4	740.2	812.4
5.5	419.6	477.4	539.0	604.3	673.3	746.0	822.5	902.7
2.1	461.6	525.2	592.9	667.7	740.6	820.6	904.7	992.9
3.6	503.5	572.9	646.8	725.1	807.9	895.2	987.0	1083.2
1.2	545.5	620.7	700.7	785.5	875.2	969.8	1069.2	1173.5
1.8	587.5	668.2	754.0	846.0	942.6	1044.4	1151.5	1263.7
1.3	629.4	716.2	808.5	906.4	1009.9	1119.0	1233.7	1354.0
1.9	671.4	773.9	862.4	966.8	1077.2	1193.6	1315.9	1444.3
4	713.4	811.6	916.3	1027.2	1144.6	1268.2	1398.2	1534.5
.0	755.3	859.4	970.2	1087.7	1211.9	1342.8	1480.4	1624.8
5	797.3	907.1	1024.1	1148.1	1279.2	1417.4	1562.7	1715.1
.1	839.3	954.9	1078.0	1208.5	1346.5	1492.0	1644.9	1805.3

## Diameter, ft

3	24	25	26	27	28	29	30
3.3	537.1	582.8	630.4	679.8	731.1	784.2	839.3
2.0	644.3	699.4	756.5	815.8	877.3	941.1	1007.1
2.6	752.0	815.9	882.5	951.7	1023.5	1097.9	1175.0
1.3	859.4	932.5	1008.6	1087.7	1169.7	1254.8	1342.8
1.9	966.8	1049.1	1134.7	1223.6	1316.0	1411.6	1510.7
1.6	1074.2	1165.6	1260.8	1359.6	1462.2	1568.2	1678.5
1.2	1181.7	1282.2	1386.8	1495.6	1608.7	1723.0	1846.4
1.9	1289.1	1398.7	1512.9	1631.5	1754.6	1882.2	2014.2
.6	1396.5	1515.3	1639.0	1767.5	1900.8	2039.0	2182.0
.2	1503.9	1631.9	1765.1	1903.4	2047.1	2195.9	2343.9
.9	1611.4	1748.4	1891.1	2039.4	2193.3	2352.7	2517.8
5	1718.8	1865.0	2017.2	2175.4	2339.5	2509.6	2685.6
.2	1826.2	1981.6	2143.3	2311.3	2485.7	2666.4	2853.5
.9	1933.6	2098.1	2269.4	2447.3	2631.9	2823.3	3021.3
.5	2041.1	2214.7	2395.4	2583.2	2778.1	2980.1	3189.2
.2	2148.5	2321.2	2521.5	2719.2	2924.4	3137.0	3357.0

tapering, measure the diameter four-twelfths from large end.

Number of U. S. Gallons in Rectangular Tanks  
For One Foot in Depth  
1 cu ft = 7.4805 gal

Width, ft	Length of tank, ft										
	2	2.5	3	3.5	4	4.5	5	5.5	6	6.5	7
2	29.92	37.40	44.88	52.36	59.84	67.32	74.81	82.29	89.77	97.25	104.73
2.5	....	46.75	56.10	65.45	74.80	84.16	93.51	102.80	112.21	121.56	130.91
3	....	....	67.32	78.54	89.77	100.99	112.21	123.43	134.65	145.87	157.09
3.5	....	....	....	91.64	104.73	117.82	130.91	144.00	157.09	170.18	183.27
4	....	....	....	....	119.69	134.65	149.61	164.57	179.53	194.49	209.45
4.5	....	....	....	....	....	151.48	168.31	185.14	201.97	218.80	235.63
5	....	....	....	....	....	....	187.01	205.71	224.41	243.11	261.82
5.5	....	....	....	....	....	....	....	226.28	246.86	267.43	288.00
6	....	....	....	....	....	....	....	....	269.30	291.74	314.18
6.5	....	....	....	....	....	....	....	....	....	316.05	340.36
7	....	....	....	....	....	....	....	....	....	....	366.54

Width, ft	Length of tank, ft									
	7.5	8	8.5	9	9.5	10	10.5	11	11.5	12
2	112.21	119.69	127.17	134.65	142.13	149.61	157.09	164.57	172.05	179.53
2.5	140.26	149.61	158.96	168.31	177.66	187.01	196.36	205.71	215.06	224.41
3	168.31	179.53	190.75	202.97	213.19	224.41	235.63	246.86	258.07	269.30
3.5	196.36	209.45	222.54	235.63	248.73	261.82	274.90	288.00	301.09	314.18
4	224.41	239.37	254.34	269.30	284.26	299.22	314.18	329.14	344.10	359.06
4.5	252.47	269.30	286.13	302.96	319.79	336.62	353.45	370.28	387.11	403.94
5	280.52	299.22	317.92	336.62	355.32	374.03	392.72	411.43	430.13	448.83
5.5	308.57	329.14	349.71	370.28	390.85	411.43	432.00	452.57	473.14	493.71
6	336.62	359.06	381.50	403.94	426.39	448.83	471.27	493.71	516.15	538.59
6.5	364.67	388.98	413.30	437.60	461.92	486.23	510.54	534.85	559.16	583.47
7	392.72	418.91	445.09	471.27	497.45	523.64	549.81	575.00	602.18	628.36
7.5	420.78	448.83	476.88	504.93	532.98	561.04	589.08	617.14	645.19	673.24
8	....	478.75	508.67	538.59	568.51	598.44	628.36	658.28	688.20	718.12
8.5	....	....	540.46	572.25	604.05	635.84	667.63	699.42	731.21	763.00
9	....	....	....	605.92	639.58	673.25	706.90	740.56	774.23	807.89
9.5	....	....	....	....	675.11	710.65	746.17	781.71	817.24	852.77
10	....	....	....	....	....	748.05	785.45	822.86	860.26	897.66
10.5	....	....	....	....	....	....	824.73	864.00	903.26	942.53
11	....	....	....	....	....	....	....	905.14	946.27	987.43
11.5	....	....	....	....	....	....	....	....	989.29	1032.3
12	....	....	....	....	....	....	....	....	....	1077.2

To find weight of water in pounds at 62° F., multiply the number of gallons by 8½.

**Example.** To find number of gallons in a rectangular tank that is 7.5 ft by 10 ft., the water being 4 ft deep. Look in the extreme left-hand column for 7.5 and opposite to this in the column headed 10 read 561.04, which being multiplied by 4, the depth of water in the tank, gives 2244.2, the number of gallons required.



**(a) PLUMBING AND DRAINAGE**

**Reliable Rules for Plumbing and Drainage.** The water-supply of buildings, including the apparatus for heating water, the system of drainage and sewage, and the various fixtures connected therewith, are installed by the plumber, usually in accordance with specifications prepared by the architect and subject to municipal regulations. An efficient and safe system of plumbing is a matter of vital importance. The following may be used as a reliable guide in any locality.

**EXTRACTS \* FROM THE RULES AND REGULATIONS OF THE DEPARTMENT OF BUILDINGS OF THE CITY OF NEW YORK; ADOPTED APRIL 23, 1913**

**Definitions of Terms**

(12)† The term **PRIVATE SEWER** is applied to main sewers that are not constructed by and under the supervision of the Department of Sewers.

(13) The term **HOUSE-SEWER** is applied to that part of the main drain or sewer extending from a point 2 ft outside of the outer wall of building-vault or area to its connection with public sewer, private sewer or cesspool.

(14) The term **HOUSE-DRAIN** is applied to that part of the main horizontal drain and its branches inside the walls of the building-vault or area and extending to and connecting with the house-sewer.

(15) The term **SOIL-PIPE** is applied to any vertical line of pipe extending through roof, receiving the discharge of one or more water-closets with or without other fixtures.

(16) The term **WASTE-PIPE** is applied to any pipe, extending through roof, receiving the discharge from any fixtures except water-closets.

(17) The term **VENT-PIPE** is applied to any special pipe provided to ventilate the system of piping and to prevent trap-siphonage and back-pressure.

**Materials and Workmanship**

**Soil-Pipe and Vent-Pipe.** (19) All cast-iron pipes and fittings must be coated, sound, cylindrical, and smooth, free from cracks, sand-holes and other defects, and of uniform thickness and of the grade known in commerce as **EXTRA HEAVY**.

(20) Pipe, including the hub, shall weigh not less than the following average weights per linear foot:

Diameters	Weights per linear foot, lb
2 in. ....	5½
3 in. ....	9½
4 in. ....	13
5 in. ....	17
6 in. ....	20
7 in. ....	27
8 in. ....	33½
9 in. ....	45
10 in. ....	54

These numbered paragraphs, from (12) to (174), extracts from Building Regulations, unedited, except in those details which affect typographical uniformity throughout book. Editor-in-chief.

Paragraph-numbers are the same as those in the Official Regulations. Missing numbers indicate paragraphs purposely omitted.

(22) All joints must be made with picked oakum and molten lead and be made gas-tight. Twelve (12) oz of fine, soft pig lead must be used at each joint for each inch in the diameter of the pipe.

(24) Wrought-iron and steel water-pipes, vent-pipes, waste-pipes and soil-pipes must be galvanized.

(29) All brass pipe for soil-pipes, waste-pipes, and vent-pipes and solder-nipples must be thoroughly annealed, seamless-drawn, brass tubing of standard iron-pipe gauge.

**Lead Waste-Pipes.** (37) The use of lead pipes is restricted to the short branches of the soil-pipes and waste-pipes, bends, traps, and roof-connections of inside leaders. **SHORT BRANCHES** of lead pipe shall be construed to mean not more than

- 8 ft of 1½-in pipe
- 5 ft of 2-in pipe
- 2 ft of 3-in pipe
- 2 ft of 4-in pipe

(38) All connections between lead pipes and between lead and brass or copper pipes must be made by means of **WIPED** solder joints.

(39) All lead waste, soil, vent, and flush-pipes must be of the best quality, known in commerce as *D*, and of not less than the following weights per linear foot:

Diameters	Weights per linear foot, lb
1¼ in (for flush-pipes only).....	2½
1½ in.....	3
2 in.....	4
3 in.....	6
4 and 4½ in.....	8

(40) All lead traps and bends must be of the same weights and thicknesses as their corresponding pipe-branches. Sheet lead for roof-flashings must be 6-lb lead and must extend not less than 6 in from the pipe, and the joint made water-tight.

(41) Copper tubing when used for inside leader roof-connections must be seamless-drawn tubing not less than 22 gauge, and when used for roof-flashings must be not less than 18 gauge.

**Yard, Area and Other Drains**

(54) All yards, areas, and courts exceeding 15 sq ft in area must be drained into the sewer. A shaft open at the top and not exceeding 25 sq ft in area, and which cannot be connected in back of a leader, yard, court, or area drain-trap, may be drained into a publicly placed, water-supplied, properly capped and vented slop-sink.

(59) These drains, when sewer-connected, must have connections not less than 3 in in diameter. They should be controlled by one trap, the leader-trap if possible.

**Leaders**

(60) Every building shall be kept provided with proper metallic gutters and rain-leaders for conducting water from all roofs in such manner as shall protect the walls and foundations of said buildings from injury. In no case shall the water from any rain-leader be allowed to flow upon the sidewalk or adjoining property, but the same shall be conducted by proper pipes to the sewer. If there be no sewer in the street upon which the buildings front, then the water

leaders shall be conducted by proper pipes below the surface of the street-gutter, or may be conducted by extra-heavy cast-iron leeching cesspool located at least 20 ft from any building. No plumb- shall discharge into a leeching cesspool.

de leaders must be made of cast iron, wrought iron, or steel, with tions made gas-tight and water-tight by means of a heavy lead or rn tubing wiped to a brass ferrule or nipple calked or screwed into

side leaders may be of sheet metal, but they must connect with the by means of a cast-iron pipe extending vertically 5 ft above the

lers must be trapped with cast-iron running traps so placed as to zing.

-water leaders must not be used as soil-pipes, waste-pipes or vent- all any such pipe be used as a leader.

### House-Sewer, House-Drain, House-Trap and Fresh-Air Inlet

house-drain must properly connect with the house-sewer at a point of the outer front vault or area-wall of the building. An arched or opening in the wall must be provided for the drain to prevent ettlement.

house-drain if above the cellar-floor, must be supported at inter- by 8-in brick piers or suspended from the floor-beams, or be other- supported by heavy iron-pipe hangers at intervals of not more

eam-exhaust, boiler blow-off, or drip-pipe shall be connected with in. Such pipes must first discharge into a proper condensing tank, a proper outlet to the house-sewer outside of the building must be low-pressure steam-systems the condensing tank may be omitted, -connection must be otherwise as above required.

ouse-drain and house-sewer must be run as direct as possible, at least  $\frac{1}{4}$  in per ft, all changes in direction made with proper ll connections made with Y branches and one-eighth and one-six-

use-Sewer. (74) The house-sewer and house-drain must be at liameter where water-closets discharge into them. Where rain- es into them, the house-sewer and house-drain up to the leader- ust be in accordance with the following table:

Diameter of pipe, in	For a fall of $\frac{1}{4}$ in per foot, sq ft of drainage-area	For a fall of $\frac{1}{2}$ in per foot, sq ft of drainage-area
3	1 200	1 500
4	2 500	3 200
5	4 500	6 000
6	8 000	10 000
7	12 400	15 600
8	18 000	22 500
9	25 000	31 500
10	41 000	59 000
12	69 000	98 000

(75) Full-size Y and T-branch fittings for hand-hole clean-outs must be provided where required on house-drain and its branches. No clean-out need be larger than 6 in in diameter.

(76) An iron running-trap must be placed on the house-drain near the wall of the house, and on the sewer-side of all connections, except a Y fitting used to receive the discharge from an automatic sewage-lift, oil-separator or a drip-pipe where one is used. If placed outside the house or below the cellar-floor it must be made accessible in a brick manhole, the walls of which must be 8 in thick, with an iron or flagstone cover. When outside the house it must never be less than 3 ft below the surface of the ground.

(79) A FRESH-AIR INLET must be connected with the house-drain just inside of the house-trap and extended to the outer air, terminating with a return-bend, with open end 1 ft above the grade at most available point, to be determined by the superintendent of buildings and shown on plans. The fresh-air inlet-pipe must be of the same diameter as the house-drain. An automatic device approved by the superintendent of buildings may be used when set in a manner satisfactory to him.

**Note.** The fresh-air inlet and running trap prescribed by Sections 76 and 79 are not required in many cities, and it is better to omit them where not required.

### **Soil-Pipes, Waste-Pipes and Vent-Pipes**

(81) All main, soil, waste or vent-pipes must be of iron, steel, or brass.

(90) The diameters of soil-pipes and waste-pipes must not be less than those given in the following table:

Main soil-pipes.....	4 in
Main soil-pipes for water-closets on five or more floors.....	5 in
Branch soil-pipes.....	4 in
Main waste-pipes.....	2 in
Main waste-pipes for kitchen-sinks on five or more floors.....	3 in
Branch waste-pipes for laundry-tubs.....	1 ½ in
When set in ranges of three or more.....	2 in
Branch waste for kitchen-sinks.....	2 in
Branch waste for urinals.....	2 in
Branch waste for other fixtures.....	1 ½ in

(97) The SIZES OF VENT-PIPES throughout must not be less than the following:

For main vents, 2 in in diameter; for water-closets on three or more floors, 3 in in diameter; for other fixtures on less than seven floors, 2 in in diameter; 3-in vent-pipe will be permitted for less than nine stories; for more than eight and less than sixteen stories, 4 in in diameter; for more than fifteen and less than twenty-two stories, 5 in in diameter; for more than twenty-one stories the size of vent-pipe shall be determined by the superintendent of buildings.

For fixtures other than water-closets and slop-sinks and for more than eight stories, vent-pipes may be 1 in smaller than above stated.

### **Traps**

(101) Every fixture must be separately trapped by a water-sealing trap placed as close to the fixture-outlet as possible and no trap shall be placed more than 2 ft from any fixture.

set of not more than three wash-trays may connect with a single trap, trap of an adjoining sink, provided both sink and tub waste-outlets same side of the waste-line and the sink is nearest the line. When so the waste-pipe from the wash-trays must be branched in below the

the discharge from any fixture must not pass through more than one reaching the house-drain.

earthenware traps must have approved heavy brass floor-plates cured to the ~~branch soil-pipe and bolted to the~~ trap-flange and the gas-tight. The use of rubber washers for floor-connections is pro-ll floor-flanges must be set in place and inspected before any water-thereon.

trap shall be placed at the foot of main soil- and waste-pipe lines. e sizes for traps must not be less than those given in the following

ater-closets.....	4 in in diam.
op-sinks.....	2 in in diam.
itchen-sinks.....	2 in in diam.
ash-trays.....	2 in in diam.
inals.....	2 in in diam.
ower-baths.....	2 in in diam.
her fixtures.....	1½ in in diam.

leaders, areas, floor and other drains must be at least 3 in in diam-

## Water-Closets

enement-houses, lodging-houses, factories, workshops, and all gs the entire water-closet apartment and side walls to a height ie floor, except at the door, must be made water-proof with asphalt, metal, or other water-proof material as approved by the superia-ldings.

general water-closet accommodation of any building cannot be cellar nor can any water-closet be placed outside of a building, ce an existing water-closet.

sewer-connected occupied buildings there must be at least one nd there must be additional closets so that there will never be en persons per closet.

gging-houses there must be one water-closet on each floor, and more than fifteen persons on a floor, there must be one additional r every fifteen additional persons or fraction thereof.

-closets and urinals must never be connected directly with or ie water-supply pipes, except when flushometer-valves are used, water-closet and urinal-cisterns and automatic water-closets erns are prohibited unless approved by the superintendent of

pper lining of water-closets and urinal-cisterns must not be lighter er.

closet flush-pipes must not be less than 1¼ in and urinal flush-umeter, and if of lead must not weigh less than 2½ lb and 2 lb h-couplings must be of full size of the pipe.

### **Sinks and Wash-Tubs**

(147) In all houses sinks must be entirely open, on iron legs or brackets, without any enclosing woodwork.

(148) Wooden wash-tubs are prohibited, except when used in hotels, restaurants or bottling establishments for washing dishes or bottles. Cement or artificial stone tubs will not be permitted unless approved by the superintendent of buildings.

### **Testing the Plumbing-System**

(171) The entire plumbing and draining-system within the building must be tested by the plumber, in the presence of a plumbing inspector, under a water-test. All pipes must remain uncovered in every part until they have successfully passed the test. The plumber must securely close all openings as directed by the inspector of plumbing. The use of wooden plugs for this purpose is prohibited.

(172) The water-test will be applied by closing the lower end of the main house-drain and filling the pipes to the highest opening above the roof with water. The water-test shall include at one time the house-drain and branches, all vertical and horizontal soil, waste and vent and leader-lines and all branches therefrom to point above the surface of the finished floor and beyond the finished face of walls and partitions. If the drain or any part of the system is to be tested separately, there must be a head of water at least 6 ft above all parts of the work so tested, and special provision must be made for including all joints and connections in at least one test.

(173) After the completion of the plumbing-work, in any new or altered building and before the building is occupied, a final smoke-test must be applied in the presence of the plumbing-inspector. Except that for a building not over six stories in height, a peppermint-test may be applied.

(174) The material and labor for the tests must be furnished by the plumber. Where the peppermint-test is used, 2 oz of oil of peppermint must be provided for each line up to five stories and cellar in height, and an additional ounce of oil of peppermint must be provided for each line when lines are more than five stories in height.

### **Traps**

A trap is a device which permits the free passage of liquids through it, and also of any solid matters that may be carried by the liquid, while at the same time preventing the passage of air or gas in either direction. Traps used for plumbing purposes are shaped so that an amount of water sufficient to close the passage and prevent the passage of air will stand in them at all times. The principle of the common trap is shown in Fig. 7. The pipe *T* receives the waste from a sink or wash-basin, while the lower end *B* connects with the sewer. Sewer-gas rises in pipe *B*, but is prevented from passing to the fixture by the water which stands in the trap. The depth of water through which gas must pass to effect a passage is termed the **WATER-SEAL**. The water-seal in the trap, Fig. 7, is the distance *S*. All plumbing-pipes which connect with a sewerage-system require to be trapped to prevent sewer-gas from passing through them to the fixture and into the room in which the fixture is located.

**Ventilation of Traps.** When a considerable body of water rushes down through a pipe it forms a suction, and if the pipe is made air-tight, this suction is often sufficient to prevent enough water remaining in the trap to form a seal, thus leaving an opening for the passage of sewer-gas, as in Fig. 8. By connecting the upper bend of a trap with the outside air by means of a pipe, as at *V*, Fig. 8

will be stopped, and the water in the pipe *T* will not fall below the outlet at *b*. Several non-siphoning traps have been patented for obviating the necessity of back-venting, but they are used to a very limited extent. There are also several varieties of back-pressure




Fig. 7. Water-seal of Trap




Fig. 8. Water-trap Unsealed

ed to prevent the sewage from flowing back into the house-drain. the nature of check-valves, and are used principally in seaport-tide-water might possibly force the sewage back. The more common of lead traps used in plumbing, with their trade names, are shown




Fig. 9. Types of Traps

The same shapes are also made of cast iron. The pipes marked *V* connections. The drum-trap shown in Fig. 10 has a deeper seal shown in Fig. 9, and is commonly used under kitchen-sinks, bath-tubs, &c. Drum-traps are not easily siphoned, even when not vented. Water-closets are commonly formed in the fixture.

**Grease-Traps.** The waste-water from kitchen-sinks always contains considerable grease, which if permitted to enter the soil-pipe system is liable to clog the pipes by adhering to the walls. In certain localities grease gives much more trouble than in others, due to the chemical composition of the water. In Colorado and many other places it is necessary to connect the waste from kitchen-

Fig. 10.    Drum-trap

Fig. 11.    Outdoor Grease-trap

sinks with a large grease-trap, which collects and holds the grease, but permits the water to pass into the sewer system. After a time the accumulated grease fills the trap and must be removed. On account of this it is desirable to use a large trap, and whenever possible it should be placed underground, just outside the house, and as near to the sink as practicable. Grease-traps to be placed

underground are commonly made of 24-in vitrified drain-tile or cement pipe, and should be about 4 ft deep. They may also be built of brick in cement mortar. Fig. 11 shows a section through such a grease-trap and the inlet and outlet-pipes. When the sink is in a basement or an upper story, or when the building occupies the entire lot, the grease-trap must be placed under the sink. When so placed, a round lead trap 12 or 14 in in diameter may be used, with a large trap-screw in the top for removing the grease. Fig. 12 shows a section through such a trap and the way in which the connections should be made. A better form

Fig. 12.    Lead Grease-trap

of grease-trap is made of cast iron. Some city ordinances require that inside grease-traps shall have a chilling-jacket for the purpose of more perfectly separating the grease and thus preventing any of it from entering the waste-pipes. To be effective, a grease-trap must have a capacity of at least twice the amount of greasy water that will be discharged into it at any one time.



es. These may be of lead, brass, galvanized iron, tin-lined lead, Lead pipe offers the least resistance to the flow of water, is easily any situation, and easy curves are readily made. It is generally ore durable underground than galvanized-iron pipe. The grade or STRONG, is the lightest that should ever be used, and when the n from city mains, in which there is a considerable pressure, AA, g pipe, should be used. Galvanized-iron pipe is probably more ed than any other material for water-supply pipes in buildings, nickel-plated pipe is required, in which case brass piping is com- Brass pipe used for water-supply should be what is known as IRON- brass piping is preferable to galvanized iron or lead for conveying d is largely used in the better class of buildings. Tin-lined iron s and pipes of block tin are usually considered as offering the ance to corrosion or chemical action, and should always be used ale, beer and other liquors. Tin-lined iron pipe is made by pouring o a wrought-iron pipe. While in a fluid state the tin is inseparably on, and the result is one solid pipe composed of two metals which ORN APART. It is essentially different from iron pipe merely and immeasurably superior to iron pipe lined with a separate will become detached. Its fittings are lined with tin to match. I not injure it, rats will not gnaw it, and thieves will not cut it ot or cold water may stand in block-tin pipes and yet be drawn re and free from poison or rust. Lead-lined pipe is made in the insures delivering the water to the house just as it comes from the ged by the chemical action which often results from contact with pipe.

**Drawn Benedict Nickel Tubing** is used to some extent for the bing-pipes in high-class residences, office and public buildings. uite metal throughout it cannot rub or wear BRASSY or become is made in all the regular iron-pipe sizes, and necessary fittings f the same metal.\*

les. Where the pressure in the street-mains is not great enough ficient volume of water for supplying the fixtures at all times, or rivate water-supply, a tank should be placed in the attic, or ele- 6 ft above the highest fixture to be supplied. In some cases the lower story are supplied direct from the street mains, while those ory are supplied from a tank. The advantage of a tank is that it ully from a very small stream, and thus form a reservoir from volume can be drawn in a shorter space of time than could be t from the service-pipes. Storage-tanks should always be pro- overflow-pipe of ample size and when supplied from the street- oly should be controlled by a ball-cock and float. Storage-tanks ze are preferably made of wood lined with planished or tinned lead, zinc or galvanized iron should not be used for lining tanks er for drinking or cooking purposes, and are not as durable as hen the effect on the water need not be considered.

**Tank Required** will depend largely upon the character of the s supplied from the street-main in which the pressure is fairly not have a capacity exceeding 160 gal. Where the water is e tank by a windmill or hot-air engine, the tank should have a ent for a three or four days' supply at least.

information consult the Benedict & Burnham Manufacturing Company, D.

**Amount of Water Required for Various Purposes.** The amount of water required for household purposes has been found to be about 25 gal for each person, large or small, but waste will triple that amount sometimes. A horse will drink about 7 gal per day and a cow from 5 to 6 gal per day. A carriage requires from 9 to 16 gal for washing.

**Size of Supply-Pipes.** The proper diameter of supply-pipes depends upon several considerations, such as the number and size of faucets that are likely to be discharging water at the same time, the urgency of the demand, the length of the pipes and number of angles, and upon the pressure. There is no objection to having a pipe larger than is really necessary, except from the standpoint of cost. Service-pipes should always be one size larger than the tap in the street-main. The following table affords a fair guide for proportioning the supply-branches to plumbing-fixtures. If the pressure is less than 20 lb per sq in the system may be rated as **LOW PRESSURE**, and if above 20 lb as **HIGH PRESSURE**.

Supply-branches	Low pressure, in	High pressure, in
To Bath-cocks.....	¾ to 1	¾ to ¾
Basin-cocks.....	½	½
Water-closet flush-tank.....	½	½
Water-closet flush-valve.....	1¼ to 1½	1¼ to 1½
Sitz or foot-bath.....	½ to ¾	½
Kitchen sinks.....	¾ to ¾	½ to ¾
Pantry sinks.....	½	½
Slop-sinks.....	¾ to ¾	½ to ¾
Urinals.....	¾ to ¾	½ to ¾

With high-pressure systems, dwellings of five or six rooms are sometimes, for economy, supplied entirely through ¾-in pipe.

**Minimum Diameter of Waste-Pipes.** The following are considered as the smallest diameters allowable for waste-pipes. The diameters required in New York City are given on page 1410.

- Bath and sink-wastes, 1½ in.
- Basin and urinal-wastes, 1¼ in.
- Wash-trays, 1½ in from each compartment, entered into 4-in drum-trap and 2-in outlet from trap.
- Water-closet trap, 2½ in.

Approximate Spacing for Tacks on Lead Pipes

Size of pipe, in	Vertical pipe		Horizontal pipe	
	Distance apart		Distance apart	
	Hot, in	Cold, in	Hot, in	Cold, in
½	19	25	14	17
¾	20	26	15	18
¾	21	27	16	19
1	22	28	17	20
1¼	23	29	18	21
1½	24	30	18	22

## Lead Pipe

on of Lead Pipe. The different thicknesses of lead pi  
gnated by letters as in Table H, page 1418, but are no  
signed as in Table G, following, which may be consid  
pted by dealers.

**Table G. Weights and Sizes of Lead Pipe**

liber	Weight per foot		Caliber	Wei
	lb	oz		
.....	.....	6	1½-in Aqueduct.....	3
ne.....	I	4	Extra light.....	3
act.....	.....	8	Light.....	4
ght.....	.....	9	Medium.....	5
.....	.....	12	Strong.....	6
l.....	I	.....	Extra strong.....	7
.....	I	8	Extra extra strong..	9
rong.....	2	.....	1¾-in Extra light.....	3
act.....	.....	10	Light.....	4
ght.....	.....	12	Medium.....	5
.....	I	.....	Strong.....	6
l.....	I	4	Extra strong.....	8
.....	I	12	2-in Waste.....	3
.....	2	.....	Extra light.....	4
rong.....	2	8	Light.....	5
tra strong...	3	.....	Medium.....	7
ct.....	.....	12	Strong.....	8
ght.....	I	4	Extra strong.....	9
.....	I	12	Extra extra strong..	10
.....	2	.....	2½-in Waste.....	4
.....	2	8	Light.....	6
rong.....	3	.....	Medium, ¾ thick.	8
tra strong...	3	8	Strong, ¼ thick....	11
ct.....	I	.....	Extra strong, ¾	
ght.....	I	8	thick.....	14
.....	2	.....	Extra extra strong,	
l.....	2	4	¾ thick.....	17
.....	3	.....	3-in Waste.....	4
rong.....	3	8	Light.....	6
tra strong..	4	.....	Medium, ¾ thick.	9
ct.....	I	8	Strong, ¼ thick....	12
ght.....	2	.....	Extra strong, ¾	
.....	2	8	thick.....	16
t.....	I	8	Extra extra strong,	
ht.....	2	.....	¾ thick.....	20
.....	2	8	3½-in Waste.....	5
.....	3	4	Strong, ¼ thick....	15
.....	4	.....	Extra strong, ¾	
rong.....	4	12	thick.....	18
tra strong..	5	8	4-in Waste.....	5
ct.....	2	.....	Medium.....	10
ht.....	2	8	Strong, ¼ thick....	16
.....	3	.....	Extra strong, ¾	
.....	3	12	thick.....	22
.....	4	12	Extra extra strong,	
ong.....	6	.....	¾ thick.....	25
ra strong..	6	12	5-in Waste.....	8

Coils of supply-pipe weigh about 200 lb; aqueduct about 90 lb; suction-pipe, 100 to 180 lb each.

Block-tin pipe is stronger for a given weight per foot than lead pipe or tin-lined lead pipe. As compared with lead pipe its strength is as 3½ to 1.

Tin-lined and lead-lined iron pipe is made with inside diameters of ¾, ¾, 1, 1¼, 1½ and 2 in, and in 10-ft lengths, threaded without couplings. Tin-lined and lead-lined fittings are also made (see page 1415).

Weights and Sizes of Sheet Lead

Thickness, in...	½	¾	1	1½	2	3	4	5	6	8	10	12	14	16	20	24
Lb per sq ft.....	2½	3	3½	4	5	6	8	10	12	14	16	20	24	28	36	48

Table H. Thickness and Strength of Lead Pipes

Caliber, in	Mark	Weight per foot, lb oz	Thickness, in	Mean bursting-pressure, lb	Safe working-pressure, lb	Caliber, in	Mark	Weight per foot, lb oz	Thickness, in	Mean bursting-pressure, lb	Safe working-pressure, lb
¾	AAA	1 12	0.18	1 968	492	1	A	4 0	0.21	857	214
¾	AA	1 5	0.15	1 627	406	1	B	3 4	0.17	745	186
¾	A	1 2	0.13	1 381	347	1	C	2 8	0.14	562	140
¾	B	1 0	0.125	1 342	335	1	D	2 4	0.125	518	129
¾	C	0 14	0.11	1 187	296	1	E	2 0	0.10	475	118
¾	....	0 10	0.087	1 085	271	1	....	1 8	0.09	325	81
7/16	....	0 9½	0.08	775	193	1¼	AAA	6 12	0.275	962	240
½	AAA	3 0	0.25	1 787	446	1¼	AA	5 12	0.25	823	205
½	....	2 8	0.225	1 655	413	1¼	A	4 11	0.21	685	171
½	AA	2 0	0.18	1 393	343	1¼	B	3 11	0.17	546	136
½	A	1 10	0.16	1 285	321	1¼	C	3 0	0.135	430	105
½	B	1 3	0.125	980	245	1¼	D	2 8	0.125	390	87
½	C	1 0	0.10	782	195	1¼	....	2 0	0.095	322	80
½	D	0 9	0.065	468	117	1½	AAA	8 0	0.29	742	185
½	....	0 10	0.07	556	139	1½	AA	7 0	0.25	700	175
½	....	0 12	0.09	625	156	1½	A	6 4	0.22	608	157
5/8	AAA	3 8	0.23	1 548	387	1½	B	5 0	0.18	506	126
5/8	AA	2 12	0.21	1 380	345	¾	C	4 4	0.15	430	107
5/8	A	2 8	0.18	1 152	288	¾	D	3 8	0.14	385	78
5/8	B	2 0	0.16	987	246	1½	....	3 0	0.12	245	61
5/8	C	1 7	0.117	795	198	1¾	B	5 0	....	....	116
5/8	D	1 4	0.10	708	177	1¾	C	4 0	....	....	93
¾	AAA	4 14	0.29	1 462	365	1¾	D	3 10	0.125	318	79
¾	AA	3 8	0.225	1 225	306	2	AAA	10 11	0.30	611	152
¾	A	3 0	0.19	1 072	268	2	AA	8 14	0.25	511	127
¾	B	2 3	0.15	865	216	2	A	7 0	0.21	405	101
¾	C	1 12	0.125	782	195	2	B	6 0	0.19	360	90
¾	D	1 3	0.09	505	126	2	C	5 0	0.16	260	65
1	AAA	6 0	0.30	1 230	307	2	D	4 0	0.09	200	50
1	AA	4 8	0.23	910	227	....	....	....	....	....	....

Weight and Sizes of Pure Block-Tin Pipe

	Weight per foot, oz	Size inside diameter in	Weight per foot, lb
	4	$\frac{3}{4}$	9, 12, 16
	4, 5, 6	1	12, 16
	4, 5, 6, 8	$1\frac{1}{4}$	20, 28
	4, 5, 6, 8	$1\frac{1}{2}$	24 and upwards
	5, 6, 8, 10	2	32 and upwards
	9, 12, 16	.....	.....

## Sewer-Pipe

three kinds of sewer-pipe or drain-pipe offered in the market, (1) VITRIFIED CLAY PIPE, (2) SLIP-GLAZED CLAY PIPE and (3) CEMENT PIPE. The name of the latter sufficiently indicates what it is without any description. The SLIP-GLAZED CLAY PIPE is made of what is known as FIRE-CLAY, or brick clay, which retains its porosity when subjected to the most intense heat.

It is glazed with another kind of clay, known as SLIP, which, when heated, melts, creating a very thin glazing, and which, being a FOREIGN GLAZE, is liable to wear or scale off. SALT-GLAZED CLAY PIPE is made of a clay, which, when subjected to an intense heat, becomes glass-like. It is glazed by the vapors of salt, the salt being thrown over the pipe, thereby creating a vapor which unites chemically with the clay, and forms a glass, which will not scale or wear off, and is impervious to the action of water, steam, or any other known substance. It unites with the clay to form PART OF THE BODY OF THE PIPE, and is therefore permanent.

Salt-glazed pipe can only be made from clay that will vitrify, and when subjected to an intense heat will become a hard, compact, non-porous substance.

It should be borne in mind that SLIP-GLAZING is only resorted to when the pipes are of such a nature that they will not vitrify.

The material of Drain-Pipes should be a hard, vitreous substance; not only so, but it should lead to the absorption of the impure contents of the drain, and its actual strength to resist pressure, would be more affected by the formation of crystals in connection with certain chemical substances, or would be more susceptible to the chemical action of the contents of the sewerage.

Pipes should be Salt-Glazed, as this requires them to be subjected to a more intense heat than is needed for SLIP-GLAZING, and thus secures a permanent glaze. Cement pipes made without metal reinforcement have not proved sufficiently strong and durable to be used with confidence in any important work.

When reinforced with metal, however, they have ample strength, and cement sewer-pipes of large diameter are used to a considerable extent.

In determining the diameter of house-sewers, the table on page 1409 will be a good guide. Storm-sewers should be proportioned to the area drained. The average rainfall, as shown by statistics, is about 1 in. per hour, except in heavy storms, equal to 27 225 gal per hour for each acre, or 453 gal per acre. Owing to various obstructions, not more than from 50 to 100 gal will reach the drain within the same hour, and allowance should be made for this fact in determining size of storm-sewer required.

**Carrying Capacity of Sewer-Pipe**  
Gallons per minute

Size of pipe, in	Fall per 100 ft							
	1 in	2 in	3 in	6 in	9 in	1 ft	2 ft	3 ft
3	13	19	23	32	40	46	64	79
4	27	38	47	66	81	93	131	163
6	75	105	129	183	224	258	364	450
8	153	216	265	375	460	527	750	923
9	205	290	355	503	617	712	1 006	1 240
10	267	378	463	755	803	926	1 310	1 613
12	422	596	730	1 033	1 273	1 468	2 076	2 554
15	740	1 021	1 282	1 818	2 224	2 464	3 617	4 467
18	1 168	1 651	2 022	2 860	3 508	4 045	5 704	7 047
24	2 396	3 387	4 155	5 874	7 202	8 303	11 744	14 466
27	4 407	6 211	7 674	10 883	13 257	15 344	21 771	26 622
30	5 906	8 352	10 223	14 298	17 714	20 204	28 129	35 513
36	9 707	13 769	16 816	23 763	29 284	33 722	47 523	58 406

**Quantities of Cement, Sand and of Cement Mortar for Sewer-Pipe Joints**

Prepared by J. N. Hazlehurst

For each 100 ft of sewer (with Portland cement, 375 lb net per bbl)

Size of pipe, in	Length, ft	Mortar, cu yd	Proportions: 1 Cement to					
			1 Sand			2 Sand		
			Cement, bbl	Sand, cu yd	Pipe per bbl cement, lin ft	Cement, bbl	Sand, cu yd	Pipe per bbl cement, lin ft
6	2½	0.003	0.01248	0.00201	803	0.00855	0.00252	1 168
8	2½	0.038	0.15808	0.02546	633	0.10830	0.03192	923
10	2½	0.058	0.24128	0.03886	410	0.16530	0.04872	605
12	2½	0.089	0.37024	0.05963	270	0.25365	0.07476	394
15	2½	0.123	0.51268	0.08241	195	0.35055	0.10332	285
18	2½	0.167	0.69472	0.11189	144	0.47595	0.14018	210
20	2½	0.237	0.98592	0.15879	101	0.67545	0.19908	148
24	2½	0.299	1.24384	0.20033	80	0.85215	0.25116	117
27	3	0.492	2.04672	0.32964	49	1.40220	0.41328	71
30	3	0.548	2.27968	0.36716	44	1.56180	0.46032	64
36	3	0.849	3.53184	0.56883	29	2.41965	0.71316	41

**Plumbing Specialties**

**The Kenney Flushometer.** This is a gravity valve designed for flushing all water-closets, urinals and slop-sinks in a building direct from one tank situated in the attic or where most desirable, thus dispensing with the individual overhead tank. The pipe from the main tank is run down to the different floors either exposed or concealed and branches taken off from there to the flushom-

operation of the flushometer is to pull the handle forward, which lifts the valve off its seat, making a direct connection from the flushometer tank. After the handle is released the valve closes slowly of its own weight against a high or low pressure. It is constructed without springs and closes by gravity, is built to stand the hardest service, is simple in construction and operation that the same valve is used for all pressures, the only differences in adjustment being those necessary for high or low pressure. The flushometer is extensively used for fountains in buildings in the Eastern States, including many large office buildings, schools, hospitals, and the better class of residences; also on boats and yachts.

There are few cities in which the public water-supply is not greatly improved in wholesomeness by being filtered, and in many places filtering is necessary. The filter should be large enough so that the velocity of water passing through it will be low and it should be so arranged that the flow can be reversed and the accumulated impurities washed into a sump. In the country a filter suitable for rain-water may be built under a cistern, the filtering process being accomplished by beds of sand and gravel. In cities, however, a portable filter located in the basement should be used. A simple sand filter, either pressure or gravity, will clarify water of most impurities, suitable for plunge-baths, and other general uses in the home. To provide a perfectly sterile water, however, the filter must be provided with a coagulating apparatus to automatically feed a proportionate dose of coagulant to the raw water. Those so-called filters which are made to screw on to the end of an ordinary faucet should be considered merely as strainers, for that purpose they soon become foul.

**Instantaneous Water-Heaters** are a great convenience for heating water for wash-basins in buildings in which a constant supply of hot water is required, and especially in residences where the cooking is done by gas. They are cylindrical in shape, made of nickel-plated copper, and are usually with a shelf attached to the wall close to the fixture to be supplied. A heater 18 in in diameter and 30 in high will heat 20 gal of water in eight minutes at a cost of 1 1/4 to 2 cts with gas at \$1 per 1 000 cu ft. A large line of heaters is made by the Instantaneous Water Heating Company, Kalamazoo, Mich., for both gas and gasoline, although gas is preferable when it is available. The cost of heaters varies from \$15 to \$45, according to size.

**Automatic Water-Heater** which maintains water at any desired temperature without attention, provided the building has a supply of live steam, is made by B. Clow & Sons, the supply of steam being automatically regulated by a float-valve. It will be found especially desirable in hospitals, hotels, schools, churches and public institutions. The heater is made in four sizes, of 1 500, 2 500, 4 000 and 6 500 gal per hour.

**Cellar-Drainer** \* is a simple device for raising water from 6 to 12 ft without attention or power, except a supply of steam or water. It is used for draining cellars, wheel-pits, furnace-pits, etc., when they are below the sewer. For such places a box or barrel is sunk so that the water will run into it, and the drainer is set in this receiver and the discharge pipe runs to a sink or open drain. The drainer performs its functions by means of steam under pressure through the drainer-point or jet, thus creating a vacuum which draws the water from the receiver in which it is placed. The discharge pipe, and both the jet-water and cellar-water are discharged into the sewer.

\* Manufactured by Jas. B. Clow & Sons.

together. As long as the city water or steam passes through the drainer-pipe this suction and discharge continues. The supply of water or steam is turned on or off automatically, so that there is no consumption of city water or steam except when the drainer is removing water. This drainer will operate with a pressure of 15 lb or more, the heavier the pressure the greater the amount of dead water discharged. When the drainage-water does not have to be raised more than 10 ft, this is the most economical apparatus that can be used, as the amount of city water consumed is very small. The Climax Drainer is made in six sizes, costing from \$25 to \$160.

**Sewage-Ejectment.** Mechanical ejectment of sewage is resorted to in case where the street-sewer is above the level of the area to be drained. This condition is found principally in the subbasement-floors of tall buildings, underground public-comfort stations and underground passenger-stations. A system of mechanical ejectment consists of a gravity drainage-system to a receiving tank or sump located in a water-tight pit at the lowest part of the drainage system, and a pump or compressed-air ejector to raise the sewage and discharge it into the street-sewer. There are three types of apparatus used to raise sewage to the street sewers, centrifugal pumps, piston-pumps, and compressed-air ejectors. The compressed-air ejectors, however, are commonly used owing to their numerous advantages. They are automatic and almost noiseless in operation, are perfectly odorless, and have but few working parts that can get out of order. Sewage-ejectment apparatus is generally installed in duplicate so that one set may be cut out of service for cleaning or repairs, without interrupting the drainage-service.

### **Plunge-Baths**

**AN EXAMPLE OF THE CONSTRUCTION AND DETAILS OF A SMALL PLUNGE BATH OR SWIMMING-BATH.** The following is a description, with illustrations of the bath in the house of the Racquet and Tennis Club on Forty-third Street New York City.\*

"The swimming-bath has inside dimensions of 15 by 22 ft and is about 9 ft in total depth. It was built in a pit about 19 by 26 ft and about 8 ft deep below the main excavation, which was blasted out of solid rock. A concrete invert 1 ft or more in thickness was laid over the bottom, serving as a footing on which the 12-in. walls of common red brick were laid in cement. They were built close to the rough vertical faces of the excavation, and the spaces behind them were filled with concrete or cement mortar or were flushed with grout. Then on the inner surface of the walls and on top of the concrete bottom lining a waterproofing of six layers of felt with lapped joints was mopped on with hot tar and flashed around the iron outlet-pipe, which also had a wide calked lead flange extending between the layers of felt. On the bottom of this waterproof coat an 8-in. inverted segmental flat floor-arch of common brick was laid, and on its skewbacks 4-in. vertical brick walls were built against the water-proofed side. The bottom was then lined with vitrified white tile and the sides were faced with English white enameled brick. The tops of the walls were coped with beveled and molded white-marble slabs which are about 2 ft above the floor-level and are surmounted at one side and one end by a low heavy rail with twisted ornamental posts, all of brass. A similar horizontal hand-rail is carried along the inside wall of the bath just above water-level and a curved brass hand-rail is fastened to the wall above the narrow brick-and-marble stairs at one end. The

\* The illustrations and accompanying descriptions are taken by permission from the Engineering Record of Nov. 3, 1900.



occupies one corner of the room and its elevated marble platform extends across it, forming a diving-platform which is reached by steps. All the water-supply is filtered and it can be warmed by inserting a coil into the delivery-pipe at the filter. The water enters through the end of a 2-in brass pipe projecting a foot or more through the top of the bath and delivering a solid jet unless it is reduced by valve or is formed into a fan-shaped cascade by means of a







Fig. 13. Plunge-bath

which can be screwed in the open end of the pipe. When the bath is used a small stream of water is constantly admitted and causes a circulation and corresponding overflow, and the entire bath is cleaned out and the bath cleaned every two or three days. There is, an open one about 8 ft above the bottom and a valved one

L. W. Eidlitz was the architect of the house and the water-work was done by the T. New Construction Company."

**Plumbing.** Figs. 14, 15 and 16 show the symbols suggested in the "Standard Specifications" for designating plumbing-work on plans

and details, and generally accepted for the purpose. It is just as necessary to have conventional symbols to indicate plumbing-work and fixtures, as it is to have symbols to show-windows, doors, steps, partitions and other structural details.



**Fig. 14. Symbols for Plumbing-pipes and Valves**

structural details on architectural drawings. Before these symbols became generally used there was no uniformity in the drawing of plumbing-plans, and this lack of standards often led to serious confusion. For instance, if plans from

were examined, the chances were that on no two of them would have been alike. Further, plans prepared in the same office at




Fig. 15. Miscellaneous Plumbing-symbols

one set of plans on which several different draughtsmen had shown as many different symbols for a water-closet or lavatory. That was rather con-

fusing to plumbers who had to take off quantities from the plans; for, often the symbols were so strange and bore so little resemblance to the fixtures or apparatus that some of them were liable to be overlooked. It is owing to this




Fig. 16. Symbols for Plumbing-fix

uncertainty wherever it exists from this cause, that prices in the bids submitted, and all of them are a amount of work to be done. To avoid confusion, an standard symbols should be used.

**of Soil and Waste-Stacks.** In tall buildings, provision should be made for the soil-stacks and connections to take care of the expansion, contractions, swaying and other movements of the building. This is no inconsiderable amount, in some localities the settlement alone is as much as 5 in when the foundations are not carried to bed-rock.

For instance, most of the sky-scrapers which were built on compression-beds are out of plumb and lean far out over the plumb-building in particular leaned so that the top was 30 in outside of the foundation. Most of the earlier heavy buildings there erected "on foundations" are carried on jacks, and periodically jacked up as occurs. When the building finally comes to rest, the jacks are removed and the walls filled in with masonry. The settlement which takes place in such buildings from 3 to 5 in. These various movements, expansion, contraction, settlement, racking out of plumb, also sway-buildings as they follow the sun in its course from East to West prove destructive to steam-pipes and plumbing-pipes if provision is not made to take care of them. Steam-pipes always have expansion-loops, but recently that the proper attention has been given to soil and waste-stacks and pipes; and

after as many as 100 joints in one building are made through faulty or rigid connections, the remedy is to put in flexible joints (Fig. 17) in soil and waste-stacks of




Fig. 17. Expansion-joints

soil and waste-stacks, and to connect all water-closets to the soil-pipes by means of collapsible connections which will stretch, collapse, or stretch on collapse on the other, according to the stress to which they are subjected. These flexible fittings should be placed as close to the closets as possible. They should be used also in connection with slop-sinks and inside rain-leaders. In inside rain-leaders the number of corrugations can be increased to the height of the building. Ordinary stock fittings have a range of about 2 in. That is, they will stretch about 1 in and collapse 1 in. In tall buildings, however, greater range than that is desirable. Flexible fittings would be sufficient for a rain-leader in an ordinary building 10 ft in height; then, for taller buildings, it is well to allow an extra joint for each additional 100 ft or fraction thereof. The flexibility of these fittings can be seen in the accompanying illustrations of Fig. 17.

**in Buildings.** Ninety-seven per cent of buildings erected have wood-frame construction, and the floor-joists, when they dry out, shrink. This causes the use of many thousands of closets being broken annually, and the failure of the seal at the closet-connection of those which are not broken, is due to the shrinkage of the floor-beams. The amount of shrinkage of floor-beams of different depths, can be found in the following table compiled from information furnished by the United States Government, Department of Agriculture, Division of Forestry, in Bulletin No. 10. Besides the shrinkage of the individual tiers of joists, there is the multiple shrinkage of the tiers when bearing-partitions, supporting the joists at the building, rest on sills at each floor which are laid on top of the joists instead of extending down through to the plate which supports the building.

When the framing is properly done, there is only the shrinkage of the floor-beams to take into consideration. When improperly framed,

there might be three or four shrinkages affecting the top floor of the building. Even though the timbers are dry and seasoned when put in, by the time the plasterers are through the joists are wet and swollen from the moisture in the plaster and from the rain which saturates the timbers before the building is closed. It is safe to assume, therefore, that a 12-in joist will shrink almost 1 in, and an 18-in joist about ¾ in.

**Table of Shrinkage of Timbers**

Depth of green or wet timber, in	Amount lost by shrinkage, 4% in	Depth of timber when dry, in
6	0.24	5.76
8	0.32	7.68
10	0.40	9.60
12	0.48	11.52
14	0.56	13.44
16	0.64	15.36
18	0.72	17.28
20	0.80	19.20

**Floor-Connections for Water-Closets.** No water-closet can be considered sanitary which depends upon a PUTTY-JOINT, slip-joint, rigid-gasket joint or rigid connection of any kind for a seal. Improved metal-to-metal floor-flange now cost no more than rigid-gasket joints formerly did, and they are flexible, water-tight, will remain permanently tight, and protect the closets from being broken by shrinkage or other movement of the building or piping. The only way to get a perfectly sanitary water-closet is to specify a flexible, metal-to-metal, closet floor-flange with it.

**Expansion of Hot-Water Pipes.** In all tall buildings expansion-loops ought to be placed in both the hot-water and the circulation-pipes, to permit the expansion and contraction of the lines without injury to the system. The loops are usually from 6 to 8 ft long, made up with elbows, and extend into the floor of the building. Generally the hot-water and circulation-pipes are supported midway between loops so that they can expand both up and down. The length that water-pipes will expand depends upon the degree to which they are heated, and the materials of which the pipes are made. The first of the following three tables gives the expansion of cast-iron pipes, the second the expansion of wrought-iron pipes, and the third the expansion of brass pipes.

**Expansion of Cast-Iron Pipes**

Temper- ature of air when pipe is fitted, degrees F.	Length of pipe when fitted, ft	Length of pipe when heated to			
		215° F. ft    in	265° F. ft    in	297° F. ft    in	338° F. ft    in
0	100	100' 1.59	100' 1.96	100' 2.20	100' 2.50
32	100	100' 1.36	100' 1.65	100' 1.96	100' 2.27
64	100	100' 1.12	100' 1.43	100' 1.73	100' 2.00

## Expansion of Wrought-Iron Pipe

Length of pipe when fitted, ft	Length of pipe when heated to			
	215° F. ft in	265° F. ft in	297° F. ft in	338° F. ft in
100	100 1.72	100 2.21	100 2.31	100 2.70
100	100 1.47	100 1.78	100 2.12	100 2.45
100	100 1.21	100 1.61	100 1.87	100 2.19

## Expansion of Brass Pipe

Length of pipe when fitted, ft	Length of pipe when heated to			
	215° F. ft in	265° F. ft in	297° F. ft in	338° F. ft in
100	100 2.58	100 3.18	100 3.56	100 4.05
100	100 2.19	100 2.79	100 3.18	100 3.67
100	100 1.81	100 2.41	100 2.79	100 3.28

**Hard Water for Domestic Use.** In many parts of the country TEMPORARILY HARD, PERMANENTLY HARD or both TEMPORARILY and PERMANENTLY HARD. This is due to the fact that in those regions the rock is limestone, and in percolating through the limestone the water which is originally soft, dissolves carbonates and sulphates of lime or magnesia from the rock. The solvent capacity of water for lime and magnesia is greater when the water is cold than when it is hot. Therefore, deep-well water in some regions is usually saturated with lime or magnesia, and when it is used in tanks or boilers the point of saturation is lowered and lime is liberated in the form of hard scale or incrustation. The effect of this is to shorten the life of the boiler and decrease the efficiency of the boiler in use. It is estimated that:

1/16-in lime-scale means a loss of 13% of fuel.

1/8-in lime-scale means a loss of 22% of fuel.

1/4-in lime-scale means a loss of 38% of fuel.

3/8-in lime-scale means a loss of 50% of fuel.

1/2-in lime-scale means a loss of 60% of fuel.

3/4-in lime-scale means a loss of 91% of fuel.

The above figures are probably a little high, but making due allowance, the table shows the loss due to the use of hard water. In the laundry the addition of soap to soften hard water is a further item of expense. It takes 1 lb of soap to soften 100 gal of moderately-hard water, and 1 lb more is required for washing after the water has been softened. Hence, hard water forms an insoluble curd when washing which is very annoying to hotel-guests; therefore, it is advisable to use soft water for large hotel-buildings, laundries and for many industries. Permanently hard waters contain sulphates of lime or magnesia, while temporarily hard waters contain carbonates of lime or magnesia.

Temporarily and permanently hard waters contain both carbonates and sulphates of lime or magnesia. Temporarily hard waters are softened by adding lime-water to the raw water to remove the carbonates of lime. This is known as the **CLARK PROCESS**. Permanently hard waters are softened by the **PORTER PROCESS**, which consists of adding soda-ash to the raw water. Stock types of apparatus are manufactured for this purpose, and may be had with capacities of any required amount.

**Heating Water with Steam-Coils.** The following constants will be found convenient for proportioning steam-coils for heating water:

$W$  = gallons of water to be heated.

$W + 10$  = sq ft of iron pipe-coil required for exhaust-steam.

$W + 15$  = sq ft of copper pipe-coil required for exhaust-steam.

$W \times 0.07$  = sq ft of iron pipe-coil for 5 lb pressure-steam.

$W \times 0.045$  = sq ft of copper pipe-coil for 5 lb pressure-steam.

$W \times 0.05$  = sq ft of iron pipe-coil for 25 lb steam-pressure.

$W \times 0.035$  = sq ft of copper pipe-coil for 25 lb steam-pressure.

$W \times 0.04$  = sq ft of iron pipe-coil for 50 lb steam-pressure.

$W \times 0.25$  = sq ft of copper pipe-coil required for 50 lb steam-pressure.

$W \times 0.03$  = sq ft of iron pipe-coil required for 75 lb steam-pressure.

$W \times 0.02$  = sq ft of copper pipe-coil required for 75 lb steam-pressure.

**Capacity of Water-Backs.** The average size of water-back having about 110 sq in, or about  $\frac{3}{4}$  sq ft of exposed surface, will heat to the ordinary temperature of domestic hot water,  $180^{\circ}$  F., about 21 gal of water an hour. It will heat about 17 gal of water to the boiling-point with an ordinary fire. With a fire such as is used for roasting, washing, or baking, a water-back of this same size will heat about 23 gal of water to the boiling-point, or 27 gal to a temperature of  $180^{\circ}$  F. Wrought-iron pipe heating-coils will heat from 30 to 40 gal of water under the same conditions, and copper pipes will heat from 45 to 60 gal per hour for each square foot of surface exposed to the fire. In calculating the heating capacity of water-backs or coils, the average temperature of the water is taken. Thus, if water at  $60^{\circ}$  is heated to  $200^{\circ}$  F., the average temperature of the water would be  $(60 + 200) \div 2 = 130^{\circ}$  F., and the range of temperature through which it is heated would be  $200 - 60 = 140^{\circ}$  F.

**Value of Pipe-Covering.** Hot-water pipes and hot-water tanks when uncovered lose by radiation from their surface about 13 heat-units per minute per square foot of surface. To prevent this loss of heat and consequent extra consumption of coal, hot-water pipes, circulation-pipes and hot-water tanks in large institutions are generally covered with some non-heat-conducting material. The value of pipe-covering is not proportional to its thickness. Sectional pipe coverings average about  $1\frac{3}{4}$  in in thickness and reduce the loss by radiation about 90%. Doubling the thickness of pipe-covering saves only about another 5% of heat-loss. In specifying covering for pipes and boilers, therefore, a thickness of  $1\frac{3}{4}$  in will be sufficient. Carbonate of magnesia is a very poor conductor of heat. Therefore, it is a good material for covering hot-water pipes. Carbonate of lime, on the other hand, is not a good covering material, although it often masquerades as carbonate of magnesia. When magnesia pipe-covering is specified, therefore, it is well to require a composition containing from 80 to 90% of magnesia, and require a test to be made at the expense of the contractor, by a chemist named by the architect. The following coverings are the best materials for hot-water pipes, in the order in which they are named. Nonpareil Cork, Magnesia, Asbestos Air-Cell and Imperial Asbestos.



**(3) ILLUMINATING-GAS AND GAS-PIPING\***

**1 of Gas.** Five varieties of gas are now commonly used for lighting, namely:

**Gas,** which is made by heating bituminous coal in air-tight retorts. most common variety of gas furnished for the lighting of cities and

**-Gas,** which is made usually from anthracite coal and steam, and nsively used in Eastern cities. Gas made by this process contains han good coal-gas, and consequently does not give as bright a light, urns perfectly in heating-burners. When used for lighting purposes d in carbon by vaporizing a quantity of petroleum by heat and in- to the hot gas before it leaves the generator. Pure water-gas is as less odor than coal-gas.

**d Gas** is obtained from holes or wells which are drilled in the ground. where it can be obtained it furnishes cheap light and fuel. The btained in the hard-coal regions develops more heat per cubic foot in any other kind of gas except acetylene. Natural gas is usually under ure in the street-mains and house-pipes than manufactured gas.

**me-Gas.** Used almost exclusively for the lighting of isolated for public buildings in towns or cities where there is no public gas- commonly generated on the premises. It is formed by bringing alcium carbide in contact. Calcium carbide is produced by the ion of coke and lime. It is now a commercial article produced in ies and sold at a moderate price. It is a very hard substance like has a very slight odor, will not burn or explode, and can be handled ity with perfect safety. The fact that carbide begins to disintegrate acetylene at the slightest touch of moisture makes it practicable to gas in small quantities for single buildings.

**Generating Acetylene-Gas.** The satisfactory production of acety- ires a generator which shall feed carbide of sufficient size and weight d a sufficient depth under the water in the generator-chamber to is and proper washing. The carbide-chamber must be so arranged l that no gas can return to it to be wasted when the chamber is permeate the house with its smell. It must feed carbide loosely small quantities, in order to provide for perfect coolness by free er to all of the carbide. It must work automatically and with ainty. Acetylene-gas to be pure must be thoroughly washed. lene, as with any other illuminating-gas, means a discoloration of nished illuminating power, clogging of pipes and burners with ther foreign matter, and smoky burners, causing blackening of arnished and soiled woodwork and upholstery. It is now gener- at the requirements above outlined can be attained only by a he plunger-type. Portable generators which may be set in the nent of any building are manufactured in great variety; it is esti- o 000 acetylene-gas generators are now in use in the United States. le in sizes of 5, 10, 15, 20 and up to 500-lights capacity. In all yping carbide into water there should be a connection open from olding receptacle to the safety-vent run out of doors from the t is claimed that for a given degree of illumination, acetylene is dollar gas. A large residence may be lighted for about \$2.50 a

See, also, *Lighting and Illumination of Buildings*, page 1437.

month. To develop the full illuminating power of the gas it is necessary to use a burner-tip having the thinnest slit obtainable, the illuminating power of the gas being about fifteen times that of coal-gas, for the same consumption. The light is a clear white, very nearly resembling sunlight in color and diffusiveness, with none of the red of the incandescent lamp, the orange of the ordinary gas-flame, or the green tone of the incandescent mantle; and it possesses the quality, unique among artificial illuminants, of reproducing even the most delicate shades of color as faithfully as sunlight. Even when used with mantle-burners, as it may be with great economy, acetylene-light presents a strong dissimilarity from ordinary gas under the same conditions. Acetylene corrodes silver and copper, but does not affect brass, iron, lead, tin, or zinc. A government specification for a complete apparatus for acetylene-gas was published in *Engineering News* of Feb. 4, 1904.

(5) **Gasoline-Gas** is a mixture of gasoline vapor with air. It is never piped but is generated close to the burner, and is seldom used for lighting except for street stands, and the like. It is much used for fuel, however.

Gasoline changes from the liquid to the gaseous form under ordinary atmospheric pressure, at temperatures above 40° F., the evaporation being very slow at 40°, quite rapid at 70°, and furious at 212°. If a tank containing liquid gasoline is left open to the air, the liquid will all pass away in the form of gas.

Although generally considered dangerous, it is only so when carelessly or ignorantly handled. To produce 1 000 cu ft of gas of good quality requires about 4½ gal of the best grade of gasoline. An ordinary burner consumes about 5 cu ft per hour.

### **Piping a House for Gas\*†**

**General Principles and Requirements.** Ordinary wrought-iron pipe, such as is used for steam or water, is suitable and proper for all kinds of gas. Galvanized malleable-iron fittings, in distinction from plain iron, are very superior. The coating of zinc inside and out effectually and permanently covers all blow-holes, makes the work solid and durable, and avoids the use of perishable cement. Before the pipe is placed in position it should be looked and blown through. It is not infrequently obstructed, and this precaution will save much damage and annoyance. What is known as gas-fitters' cement never should be used. It cracks off easily, in warm places it will melt and it can be dissolved by several different kinds of gas. Nothing but solid metals is admissible for confining gas of any kind. When pipes under floor run across floor-timbers, the latter should be cut into near their ends, or when supported on partitions, and not near the middle of spans. It is evident that a 10-in timber notched 2 in in the middle is no stronger than an 8-in timber. All branch outlet-pipes should be taken from the sides or tops of running lines. Bracket-pipes should run up from below, and not drop from above. Never drop center pipe from the bottom of a running line. Always take such outlet from the side of the pipe. The whole system of piping must be free from low places or traps, and decline toward the main rising pipe, which should run up in a partition as near the center of the building as is practicable. It is obvious that where gas is distributed from the center of a building, smaller running lines of pipe will be needed than when the main pipe runs up on one end. Hence, timbers will be

\* Circular issued by the Gilbert & Barker Manufacturing Company.

† See, also, *Lighting and Illumination of Buildings* pages 1437 to 1456.

deep cutting, and the flow of gas will be more regular and even. For reason in large buildings, more than one riser may be advisable. When has different heights of post, it is always better to have an increasing pipe for each height of post, than to drop a system of piping higher to a lower post, or to grade to a low point and establish. Drip-pipes in a building should always be avoided. The whole piping should be so arranged that any condensed gas will flow back the system and into the service-pipe in the ground. All outlet-pipes so securely and rigidly fastened in position that there will be no possibility of their moving when the gas-fixtures are attached. Center pipes should have solid support fastened to the floor-timbers near their tops. The pipe should be securely fastened to the support to prevent lateral movement. The pipe must be perfectly plumb, and pass through a guide fastened near the top of the timbers, which will keep them in position despite the assaults of masons and others. In the absence of express directions to the contrary, outlets for brackets should generally be 5 ft 6 in high from the floor, but it is usual to put them 6 ft high in halls and bath-rooms. The upright pipe should be plumb, so that the nipples that project through the walls will be plumb. The nipples should project not more than  $\frac{3}{4}$  in from the face of the wall. Laths and plaster together are usually  $\frac{3}{4}$  in thick; hence the nipples should project  $1\frac{1}{4}$  in from the face of the studding. Drop center pipes should project  $1\frac{1}{2}$  in below the furring, or timbers if there is no furring, where it is known that there will be no stucco or centerpieces used. Where centerpieces are to be used, or where there is a doubt whether they will be or not, the drop-pipes should be left about a foot below the furring. All pipes properly fastened, the drop-pipe can be safely taken out and cut to the length when gas-fixtures are put on. Gas-pipes should never be placed on the tops of floor-timbers that are to be lathed and plastered, because they are inaccessible in the contingency of leakage, or when alterations are desired, the gas-fixtures are insecure. The whole system of piping should be proved to be gas-tight under a pressure of air that will raise a column of mercury 12 in in a glass tube. The pipes are either tight or they leak. There is no middle ground. If they are tight the mercury will not fall a particle. A piece of paper should be pasted on the glass tube, even with the mercury, to mark its position while the pressure is on. The system of piping should remain under pressure at least a half-hour. It should be the duty of the person in charge of the construction of the building to thoroughly inspect the system of gas-fitting; as much so as to inspect any other part of the building. He should know by personal observation that the specifications are complied with. After being satisfied that the mercury does not fall he should cause caps on the outlets to be loosened in different parts of the building, first loosening one to let the air escape, at the same time observing if the mercury falls, then tightening and repeating the operation at other points. This plan will prove whether the pipes are free from obstruction or not. When he is satisfied that the whole system is properly and perfectly executed, he should give the gas-fitter a certificate of effect.

The following requirements from specifications published by the Denver Gas & Electric Company are worthy of attention. Always use fittings in making joints; do not bend pipe. Do not use unions in concealed work; use long screws in right-and-left couplings. Long runs of approximately horizontal pipe must be properly supported at short intervals to prevent sagging.

**Rules and Table for Proportioning Sizes of House-Pipes for Gas\***

**Rules Governing Sizes of Gas-Pipes.** The table on page 1435 is based on the well-known formula for the flow of gas through pipes. The friction, and therefore the pressure necessary to overcome the friction, increases with the quantity of gas that goes through, and as the aim of the table is to have the loss in pressure not exceed  $\frac{1}{10}$  in water-pressure in 30 ft. the size of the pipe increases in going from an extremity toward the meter, as each section has an increasing number of outlets to supply. The quantity of gas the piping may be called on to pass through is stated in terms of  $\frac{3}{8}$ -in outlets, instead of cubic feet, outlets being used as a unit instead of burners, because at the time of first inspection the number of burners may not be definitely determined. In making the table, each  $\frac{3}{8}$ -in outlet was assumed to require a supply of 10 cu ft per hour. In using the table observe the following rules:†

(1) No house-riser shall be less than  $\frac{3}{4}$  in. The house-riser is considered to extend from the cellar to the ceiling of the first story. Above the ceiling the pipe must be extended of the same size as the riser, until the first branch line is taken off.

(2) No house-pipe shall be less than  $\frac{3}{8}$  in. An extension to existing piping may be made of  $\frac{1}{4}$ -in pipe to supply not more than one outlet, provided said pipe is not over 6 ft long.

(3) No gas-range shall be connected with a smaller pipe than  $\frac{3}{4}$  in.

(4) In figuring out the size of pipe, always start at the extremities of the system, and work TOWARD the meter.

(5) In using the table, the lengths of pipe to be used in each case are the lengths measured from one branch or point of juncture to another, disregarding elbows or turns. Such lengths will be hereafter spoken of as SECTIONS. No change in size of pipe may be made except at branches or outlets, each section therefore being made of but one size of pipe.

(6) If any outlet is larger than  $\frac{3}{8}$  in it must be counted as more than one, in accordance with the schedule below:

Size of outlet, inches.....	$\frac{1}{2}$	$\frac{3}{4}$	1	$1\frac{1}{4}$	$1\frac{1}{2}$	2	$2\frac{1}{2}$	3	
Value in table.....	2	4	7	11	16	28	44	64	11

(7) If the exact number of outlets given cannot be found in the table, take the next larger number.

(8) If, for the number of outlets given, the exact length of the section which feeds these outlets cannot be found in the table, the next larger length, corresponding to the outlets given, must be taken to determine the size of pipe required. Thus, if there are eight outlets to be fed through 55 ft of pipe, the length next larger than 55 in the eight-outlet line in the table is 100, and as this is in the  $1\frac{1}{4}$ -in column, that size pipe would be required.

(9) For any given number of outlets, do not use a smaller size pipe than the smallest size that contains a figure in the table for that number of outlets. Thus, to feed 15 outlets, no smaller size pipe than 1 in may be used, no matter how short the section may be.

(10) In any piping-plan, in any continuous run from an extremity to the meter, there may not be used a longer length of any size pipe than found in the table for that size, as 50 ft for  $\frac{3}{4}$  in, 70 ft for 1 in, etc. If any one section would exceed the limit length, it must be made of larger pipe. Thus, 6 outlets could

\* The Denver Gas and Electric Company.

† See, also, Lighting and Illumination of Buildings, pages 1437 to 1456

‡ With the exception of typographical changes made to conform to the rest of the base, these rules are quoted literally. Editor-in-chief.

# Gas-Piping

## Showing the Correct Sizes of House-Pipes for Different Lengths of Pipes and Number of Outlets

Lengths of pipes in feet								
¾-in pipe	½-in pipe	¾-in pipe	1-in pipe	1¼-in pipe	1½-in pipe	2-in pipe	2½-in pipe	3-in pipe
20	30	50	70	100	150	200	300	400
.....	27	50	70	100	150	200	300	400
.....	12	50	70	100	150	200	300	400
.....	.....	50	70	100	150	200	300	400
.....	.....	33	70	100	150	200	300	400
.....	.....	24	70	100	150	200	300	400
.....	.....	18	70	100	150	200	300	400
.....	.....	13	50	100	150	200	300	400
.....	.....	.....	44	100	150	200	300	400
.....	.....	.....	35	100	150	200	300	400
.....	.....	.....	30	90	150	200	300	400
.....	.....	.....	25	75	150	200	300	400
.....	.....	.....	21	60	150	200	300	400
.....	.....	.....	18	53	130	200	300	400
.....	.....	.....	16	45	115	200	300	400
.....	.....	.....	14	41	100	200	300	400
.....	.....	.....	12	36	90	200	300	400
.....	.....	.....	.....	32	80	200	300	400
.....	.....	.....	.....	29	73	200	300	400
.....	.....	.....	.....	27	65	200	300	400
.....	.....	.....	.....	24	58	200	300	400
.....	.....	.....	.....	22	53	200	300	400
.....	.....	.....	.....	20	49	200	300	400
.....	.....	.....	.....	18	45	190	300	400
.....	.....	.....	.....	17	42	175	300	400
.....	.....	.....	.....	12	30	120	300	400
.....	.....	.....	.....	.....	22	90	270	400
.....	.....	.....	.....	.....	17	70	210	400
.....	.....	.....	.....	.....	13	55	165	400
.....	.....	.....	.....	.....	.....	45	135	330
.....	.....	.....	.....	.....	.....	27	80	200
.....	.....	.....	.....	.....	.....	20	60	150
.....	.....	.....	.....	.....	.....	.....	33	80
.....	.....	.....	.....	.....	.....	.....	22	50
.....	.....	.....	.....	.....	.....	.....	15	35
.....	.....	.....	.....	.....	.....	.....	.....	28
.....	.....	.....	.....	.....	.....	.....	.....	21
.....	.....	.....	.....	.....	.....	.....	.....	14

rough 75 ft of 1-in pipe, but 1¼ in would have to be used. Successive sections work out to the same size of pipe and if the total length exceeds the longest length in the table for that size pipe, use the meter of the next larger size. For example, if we have 10 outlets supplied through 45 ft of pipe and these 5 and 5 more, or 30 ft of pipe, we should find by the table that 10 outlets require 1-in pipe, and that 5 outlets through 45 ft would also require 1-in pipe, as the sum of the two sections, 30 plus 45 equals 75 ft, and 75 ft is the limit of 1 in that may be used in any continuous run, the one nearer the meter, must be made of 1¼-in pipe. The

tion of the limit in length of any one size in a continuous run may also be shown as follows: Eight outlets will allow of 13 ft of  $\frac{3}{4}$ -in pipe in the section between the eighth and ninth outlet (counting from the extremity of the system toward the meter), provided that this 13 ft added to the total length of  $\frac{3}{4}$ -in pipe that may have been used between the extremity of the run and the eighth outlet does not exceed 50 ft, which, according to the table, is the greatest length of  $\frac{3}{4}$  in allowable in any one branch of the system. Therefore, up to the eighth outlet, 37 ft of  $\frac{3}{4}$ -in pipe could have been used, and yet allow 13 ft of  $\frac{3}{4}$  in to be used in the section between the eighth and ninth outlet. If more than 37 ft had been used, then the entire 13 ft between the eighth and ninth outlets would have to be of 1-in pipe.




Fig. 18. Diagram of Gas-piping

(11) Never supply gas from a smaller size of pipe to a larger one. If we have 25 outlets to be supplied through 200 ft of pipe, and these 25 and 5 more, making 30 in all, through 100 ft of pipe we should find by the table that 25 outlets through 200 ft would require  $2\frac{1}{4}$ -in pipe, and 30 outlets through 100 ft would require 2-in piping, but as under this condition a 2-in pipe would be supplying a  $2\frac{1}{4}$ -in pipe, the 100-ft section must be made  $2\frac{1}{4}$  in. The sizes of pipes in Fig. 18 are in accordance with the foregoing rules and the table.

## LIGHTING AND ILLUMINATION OF BUILDINGS\*

By

W. H. TIMBIE

ASSOCIATE PROFESSOR OF ELECTRICAL ENGINEERING, MASSACHUSETTS INSTITUTE OF TECHNOLOGY

**General Principles.** Objects are illuminated for the sole purpose of making them visible to the eye. The eye, then, is the natural starting-point. When passing upon the merits of any scheme of ordinary illumination, that which should mark it as a success or failure should be the general effect of the scheme upon the eye. Success should be measured largely by the degree of clearness with which the objects are perceived by the eye, as to shape and color. If certain parts of a room or street are too brilliantly lighted, objects in the dimmer portions are not perceived by the eye. If a certain side of one object is too highly illuminated, the general shape of the object is lost, as the eye does not readily perceive its more dimly lighted parts. This is because the eye automatically adjusts itself to the most brilliantly lighted area within its view, and, accordingly, is out of adjustment for perceiving the rest. We should get rid of the idea, therefore, that a light of intense brilliancy is the thing to be sought. It is, in general, highly undesirable. A room may **APPEAR** brilliantly **LIGHTED** and yet objects looked at may not be sufficiently well **ILLUMINATED** for reading or for working purposes. The lights **APPEAR** brilliant to the eye, but because they throw their strongest rays in other directions than those in which they are needed for use, they do not give efficient illumination.

**Distinction between Light and Illumination.** There is not only a great difference between **LIGHT** and **ILLUMINATION**, but there is a great difference between a brilliantly lighted room and a well-illuminated one. When anybody is asked whether a room is well illuminated or not, the chances are ten to one that he at once looks at the light itself. If the light appears to him to be brilliant and dazzling, he will invariably say, "Why, of course, the room is well lighted." He would first look away from the light at the objects around the room or underneath the light. If these can be seen clearly and easily, then the room is well **ILLUMINATED**. Afterwards he should look at the lights themselves, and if they appear soft and pleasing to his eyesight the room is well **LIGHTED**. A room in which the lights appear soft to the eye and yet in which the eye can distinguish objects clearly is both well lighted and well illuminated. A room in which the objects appear clear to the eye while the lights remain dazzling is well illuminated but badly lighted. A room in which the lights appear soft to the eye and the objects are not clearly illuminated, is well lighted, but badly illuminated. A room in which the lights appear dazzling to the eye and the surrounding objects or those underneath appear not clear to the eyesight is both badly lighted and badly illuminated. Axiom in good artificial illumination is to keep the illumination of objects as long as is necessary, but the intensity or brilliancy of the lights as low as possible. By doing the first we enable the eye to see better; by doing the second we enable the eye to feel better and suffer less from temporary discomfort or permanent injury. It is not generally understood that a light which is dazzling and brilliant to the eyesight may not be giving as much illumination as another source of light which appears soft, or even dim, by comparison. Thus an open light is more dazzling than an enclosed light, but is less efficient in illumi-

\* See, also, *Illuminating-Gas and Gas-Piping*, pages 1431 to 1436.

nating a room. The problem, then, resolves itself into two parts. The first step should be to secure a kind of lamp which will cause objects to appear in their accustomed colors; that is, the colors in which they appear by sunlight. The second is to so distribute the lamps that the several illuminated surfaces receive their share of the light, and yet no bright light is thrown directly into the eyes

**Nature of Light.** All space is supposed to be filled with a medium infinitely lighter than air, called ETHER. The sensation of light is experienced when certain wave-motions in this ether are transmitted to the eye. These wave-motions are called LIGHT-WAVES. Light-waves differ from one another in length and violence. The DIFFERENCE IN LENGTH causes a difference in color. Thus short waves may be blue or violet, while longer waves may be red or orange. If we have a source of light which sends out long ether-waves, we may expect a predominance of red and orange light in it. The sunlight contains waves of practically all lengths and thus is composed of all colors. The DIFFERENCE IN VIOLENCE of the waves give rise to a difference in intensity of the light. When these light-waves strike an object, they are partly reflected and partly absorbed. Substances differ widely as to the percentage of light they absorb and the percentage they reflect. If two objects are illuminated by the same amount of light, the one which absorbs the less light and reflects the more will appear the brighter. Some objects reflect light-waves of a certain length only, and absorb all the rest. It is this property that gives color to objects. Suppose, for instance, that a piece of cloth were receiving light from the sun, all of which it absorbed except the waves of proper length to cause a sensation of green to the eye. The green waves only would then come from the cloth to the eye, all the rest being absorbed, and the cloth would appear green. If it absorbed waves of all lengths, it would appear black, because no light would be reflected from it to the eye. If now the piece of cloth, which absorbs all wave-lengths except that of green, were exposed to a source of light which was emitting all colors EXCEPT GREEN, there being no green waves to be reflected from it, the cloth in this light would appear black. Suppose a piece of cloth absorbed all colors but two, say violet and red. When light having all wave-lengths fell upon it, it would absorb all the waves except violet and red. These two, the cloth would reflect as a mixture and would appear purple. If, however, the source of light contained no violet waves, it could only reflect the red waves and appear red. This light, then, would not cause the cloth to show its normal color. So in choosing an artificial source of light, it is necessary to select one which will send out all wave-lengths, if we wish to have the different objects appear in their normal colors.

Table I. Colors of Light-Sources \*

Sun (at zenith).....	White (all colors)
Electric arc.....	Violet-white
Candle.....	Orange-yellow
Kerosene.....	Pale orange-yellow
Gas-flame.....	Pale orange-yellow
Welsbach (gas).....	{ Nearly white to amber, depending upon composition of mantle
Acetylene-flame.....	Almost white
Carbon, incandescent.....	Reddish white
Tungsten or Mazda.....	Yellowish white
Mercury-arc.....	Blue-green
Moore tube (carbon dioxide).....	White

\* Compiled by R. F. Pierce, Welsbach Company.



Experiment has shown that no artificial light except the CO<sub>2</sub> Moore tube is even a remote approximation to daylight. The Welsbach white mantle gives a much whiter light than the tungsten-lamp, although neither can be said to approximate daylight.

**Light-Intensity or Brilliancy. Candle-Power.** The brilliancy of a source of light is stated as its **CANDLE-POWER**; that is, the number of standard candles to which it is equivalent. Thus an ordinary open gas-flame, consuming 5 cu ft of gas per hour, is equivalent in brilliancy to about 18 candles, and is said to have an intensity of 18 candle-power. Welsbach lamps, consuming 3 cu ft per hour, average about 75 candle-power; that is, they are equivalent to 75 candles. Since no two sources of light have the same amount of luminous surface, it is customary to rate a lamp by the number of candle-power per square inch of its apparent (or projected) surface. Thus an ordinary candle-flame has about  $\frac{1}{4}$  sq in of area, and its intensity would be rated as 3 candle-power per square inch; that is, the candle-power it would have if its area consisted of exactly 1 sq in. This is often called the **INTRINSIC BRILLIANCY** of a light-source.\*

**Table II. Accepted Values of Intrinsic Brilliancy for Various Light-Sources now in Use \***

Light-Source	Candle-power per sq in
Moore tube.....	0.3-1.75
Frosted electric incandescent-lamp.....	2-5
Candle.....	3-4
Gas-flame.....	3-8
Oil-lamp.....	3-8
Cooper-Hewitt lamp.....	17
Welsbach gas-mantle.....	20-50
Acetylene-burner.....	75-100
Enclosed alternating-current arc-lamp.....	75-200
Enclosed direct-current arc-lamp.....	100-500
Incandescent lamps:	
Carbon, 3.5 watts per candle.....	375
Carbon, 3.1 watts per candle.....	480
Gem, 2.5 watts per candle.....	625
Tantalum, 2.0 watts per candle.....	750
Mazda or tungsten 1.25 watts per candle.....	875
Mazda or tungsten, 1.0 watt per candle .....	1 000
Nernst, 1.5 watts per candle.....	2 200
sun, on horizon.....	2 000
flaming arc-lamp.....	5 000
Mazda, nitrogen-filled.....	7 700
open arc-lamp.....	10 000-50 000
open arc-crater.....	200 000
sun, 30° above horizon.....	500 000
sun, at zenith.....	600 000

\* E. B. Rowe, Holophane Works.

**Intensity of Illumination. Foot-Candle.** The extent to which a surface is illuminated is measured in **FOOT-CANDLES**. A surface has 1 foot-candle illumi-

The total amount of light given out by a light-source is measured in **LUMENS**. For definition and use of this term see any standard book on illumination.

nation when it is placed, at right-angles to the light-rays, 1 ft away from a light of 1 candle-power intensity. Thus a paper placed 1 ft away from a 16-candle-power incandescent lamp would be illuminated to 16 foot-candles.

**Law of Inverse Squares.** The farther away from the light the above paper is held the less the illumination. But if it were held 2 ft away, that is, twice as far as stated above, it would not have one-half the illumination. The illumination which an object receives varies inversely as the square of the distance from the source. Thus, in this example the paper would receive one-fourth as much illumination, or 4 foot-candles. If it were held 3 ft away, it would be illuminated by one-ninth of 16, or 1.6 foot-candles.

**Rule.** To find the intensity of illumination on any surface, at right-angles to light-rays, divide the CANDLE-POWER of the lamp by the SQUARE of the distance in FEET. The result will be FOOT-CANDLE illumination. This is called the LAW OF INVERSE SQUARES. Accordingly, an unshaded 32-candle-power lamp will illuminate a surface facing it squarely and 1 ft away from it with an intensity of 32 foot-candles, but a surface 4 ft away, with only  $32/4^2$ , or 2 foot-candles.

**Candle-Power and Foot-Candle.** Careful distinction should be made between CANDLE-POWER and FOOT-CANDLE. CANDLE-POWER is the measure of the intensity of a source of light. The FOOT-CANDLE is the measure of the intensity of illumination of some surface upon which the light falls.

**Example 1.** What is the illumination on a surface 5 ft from a 32-candle-power lamp?

**Solution.**  $\frac{32}{5 \times 5} = 1.28 \text{ ft-candles.}$

**Example 2.** The illumination required on a printed page for easy reading is about 2 foot-candles. (1) How high above a reading-table should a 16-candle-power lamp be hung? (2) A 32-candle-power lamp?

**Solution.**  $\frac{16}{x^2} = 2 \quad x^2 = 8 \quad x = \sqrt{8} = 2.83 \text{ ft} \quad (1)$

$\frac{32}{x^2} = 2 \quad x^2 = 16 \quad x = 4 \text{ ft} \quad (2)$

**The Primary Function of a Lighting-Installation** is to supply sufficient illumination as required by the character of the work to which the lighted space is devoted. The following table can be used in computing the amount of electric power or of gas necessary to satisfactorily illuminate the various rooms included.

Since the lower efficiencies of the indirect and semiindirect systems are largely compensated by the lower intensities required as compared to direct lighting the same watts per square foot may be allowed in either case, provided the conditions are fairly favorable to the use of the indirect and semiindirect systems namely, light-cream or yellow ceilings. The following table is based upon rooms of average proportions with light-cream, or yellow ceilings and medium walls. High, narrow rooms may require about 10% more, and low, wide rooms about 10% less, energy. Similar allowances may be made for dark or light walls respectively.

**Three Systems of General Illumination.** To secure the proper illumination, as indicated in Table III, there are three general systems.

Table III. Amount of Gas or of Electric Power Required to Illuminate Rooms Used for Various Purposes

Class of service	* Cu ft of gas per sq ft per hour	* Watts per sq ft
Armory or drill-hall.....	0.02 - 0.025	0.5-0.6
Auditorium.....	0.04 - 0.05	1.0-1.3
Barber-shop.....	0.06 - 0.07	1.5-1.7
Church (see Auditorium).....	.....	.....
Drafting-room.....	0.10 - 0.112	2.5-2.8
Factory (general illumination).....	0.01 - 0.02	2.5-0.5
Hospital (corridor).....	0.016-0.02	0.4-0.5
Hospital (operating-room).....	0.14 - 0.15	3.5-3.9
Hotel (lobby).....	0.06 - 0.065	1.5-1.6
Hotel (ball-room).....	0.05 - 0.052	1.2-1.3
Hotel (dining-room).....	0.04 - 0.045	1.0-1.1
Hotel (restaurant).....	0.06 - 0.07	1.5-1.7
Hotel (kitchen).....	0.05 - 0.052	1.2-1.3
Hotel (writing-room, general illumination only).....	0.052-0.06	1.3-1.5
Hotel (billiard-room, general illumination only).....	0.06 - 0.065	1.5-1.6
Hotel (buffet).....	0.065-0.072	1.6-1.8
Library (reading-room).....	0.055-0.06	1.4-1.5
Library (stacks).....	0.012-0.024	0.3-0.6
Office (banking and accounting).....	0.06 - 0.065	1.5-1.6
Office (general).....	0.052-0.06	1.3-1.5
Office (private).....	0.05 - 0.52	1.2-1.3
Office (stenographic).....	0.06 - 0.07	1.5-1.7
Residence (bedroom).....	0.012	0.3
Residence (dining-room).....	0.036-0.04	0.9-1.0
Residence (hall).....	0.008	0.2
Residence (living-room).....	0.036-0.04	0.9-1.0
Residence (music-room).....	0.02 - 0.025	0.5-0.6
Residence (kitchen).....	0.05 - 0.052	1.2-1.3
School (assembly or class-room).....	0.04 - 0.045	1.0-1.1
School (class-room, business colleges).....	0.055-0.06	1.4-1.5
Stores (piano, furniture, haberdashery, dry-goods, automobile, clothing, cigar).....	0.06 - 0.07	1.5-1.7
Stores (book, shoe, hardware).....	0.055-0.06	1.4-1.5
Warehouses.....	0.012-0.036	0.3-0.9

\* These figures are based upon the use of Welsbach reflex lamps and Mazda electric nps. For Welsbach KINETIC lamps and nitrogen-filled tungsten-lamps (type C Mazda) about 0.6 the values in the first and second columns, respectively. Data on gas supplied by R. F. Pierce, Welsbach Company.

(1) **Direct Lighting.** A system is designated as DIRECT when more than one-half the light reaches the area to be illuminated by coming directly from the light-source, without being reflected from the ceiling or walls. This includes all systems using lamps with clear, frosted, translucent, or opalescent globes, or reflectors, in which the light is reflected downward. It is the most efficient system, was the first to be used, and is still the most common. The color of the walls or ceiling has less effect in this system than in the others.

(2) **Indirect Lighting.** A system is designated INDIRECT when all the light is thrown first on the ceiling and walls, and reflected from these to the surface to be illuminated. Any system which conceals the source of light by opaque reflection is thus INDIRECT. Light finish must always be used on the walls and ceiling

with this system. Even then, the efficiency is usually lower than that of a direct system, but the total absence of glare and shadows and the even distribution of light make this a popular scheme in restaurants, show-rooms, etc., where decorative lighting is desired.

(3) **Semiindirect Lighting.** This system throws most of the light to the walls and ceiling, but allows a small percentage to be diffused through the reflector straight to the area to be illuminated. This system is rapidly coming into favor because apparently we have become accustomed to looking for the source of light and miss it when it is concealed as in the indirect system. The totally indirect fixtures often show up rather unpleasantly as a dark spot against a light background.\* This is avoided in the semiindirect system. The slightly higher efficiency of this system is another advantage over the indirect. Any given room may usually be lighted by any one of the three systems although it is generally true that conditions are such as to make one of the three more desirable than either of the other two. The following paragraphs show in detail how each system may be worked out for a given room.

### General Considerations † in Direct Lighting

**Outlets and Lamps.** Outlets should be located in the centers of as nearly as possible square and equal areas into which the ceiling, for the purpose of calculation, may be subdivided. The greater the number of outlets the more uniform the illumination and the greater the freedom from annoying shadows. Unless great care is used in planning the directions in which the light is received by illuminated surfaces, a disagreeable glare from glazed paper is likely to be present. The greater the height of lamps above the illuminated area, the more uniform the illumination. Figures suggestive of good practice in selection of mounting-heights are given in Table IV, page 1444.

### General Considerations in Indirect and Semiindirect Lighting

**Outlets and Lamps.** The location of outlets should in general conform to the requirements for direct lighting, that is, at the centers of approximately square and equal areas. Since glare from glazed papers is minimized when most of the light is received from ceiling-reflection, larger and fewer units are permissible than in the case of direct lighting. The nearer to the ceiling the lamps are placed, the less uniform the illumination and, within reasonable limits, the higher the illuminating efficiency of the installation. Generally speaking, lamps should not be placed less than 2 ft from the ceiling. Aside from this, the position of a fixture should be determined by artistic considerations and reflectors selected which will direct most of the light upon the ceiling without concentrating it enough to illuminate the ceiling unevenly.

**A. The Interior Colorings and Finishes.†** (1) Ceilings especially should be of nearly white, cream, or light-buff colors to efficiently diffuse the light downward. Dark greens, reds, or blues are not advisable since the reduction in illumination caused by a green color, over a cream tint, may easily be from 30% to 60%. On the other hand, this system shows very plainly all dirt and discolorations on the ceiling, and no colors should be used that are so light as to easily show dirt, where there may not be careful cleaning.

\* This unpleasant effect can sometimes be avoided by illuminating the underside of the fixture.

† By R. F. Pierce, Welsbach Company and G. S. Forbes, Macbeth-Evans Company.

‡ By G. S. Forbes, Macbeth-Evans Company.

(2) Finishes preferably should be matt, or satin, rather than glazed or varnished. From the matt ceiling-surface the maximum light will always be downward, but the varnished ceiling will reflect specularly, directing light sidewise or showing lamp-images and glare.

(3) Tints and details of decoration should be considered together with the lighting-system, so that daylight-colors and reliefs will not be reversed or distorted by colored light from artificial illuminants and shadows.

**B. The Positions of Outlets and of Fixtures.** (1) Semiindirect units should, if possible, be placed above the places where maximum light is wanted.

(2) Fixtures should not be so close to side walls as to cause light-spots running down across picture-moldings, etc.

(3) Outlets should be placed logically with reference to the ceiling-panels, so that the more brightly illuminated ceiling-areas will be the ones that on account of their tints, shapes, or decorations, will naturally bear emphasis. If the panels are deep (deep beams), and one outlet is in each panel, it will ordinarily be located at the center. If several panels intervene between units, the fixtures should be on the beams rather than in the panels, to prevent dark ceiling-areas in the shadows of the beams.

(4) Spacing should be such as to have the illuminated ceiling-areas overlap if the ceiling-surface is uniform.

**C. The Proper Lamp and Bowl-Sizes.** (1) Ordinarily the symmetrical appearance of fixtures with respect to the other interior furnishings will largely determine their sizes, although the bowls should never be so small as not to completely conceal and nearly surround the lamp-bulb.

(2) The smaller the bowl and the brighter the lamp, the less effective the semiindirect system becomes, and the more the effect approaches direct lighting.

**D. Shapes and Styles of Bowls.** (1) Bowls used close together or hung far from the ceiling should be of the focusing (upward) distribution, while broadly distributing bowls are better when used singly, or when fairly wide apart and close to the ceiling.

(2) Bowls too flat in shape may waste considerable light sidewise to the upper walls and therefore be inefficient.

(3) Wide open-top bowls should not be used in halls, etc., where the bare lamps are visible to the observer from above, nor on or below the level of a balcony or mezzanine.

**E. Care of Fixtures.** (1) The average saving in light (expressed in terms of cost of current) that results from washing once and dusting once monthly, will be from four to ten times the cost of such cleaning. Bowls often collect films of dust which are not visible and which materially reduce the efficiency both of reflection and transmission.

(2) A bowl with a dust-cap, button-ornament, or small area of thick glass at the bottom, will allow dead insects or dirt to collect at that point without marring the appearance of the unit.

(3) Dilute ammonia is an excellent glass-cleanser.

(4) Fixtures should be arranged to be lowered, for cleaning, from above if on a very high ceiling in a church or similar structure.

(5) It should be possible to easily raise the lamp or lamps from within the bowl, to allow of dusting or wiping out.

Figures suggestive of good practice in the selection of mounting-heights and types of light-distribution are given in Table VI.

Table IV. Direct System

LAMP-SIZE, MOUNTING-HEIGHT AND SPACING\*
























Mount- ing- height	Commercial size of lamps in watts = <i>W</i> and cubic feet per hour		Watts per square foot = <i>w</i> and cubic feet per square foot		Ideal spacing = distance $\sqrt{\frac{W}{w}}$		Minimum spacing- distance		Maximum spacing- distance	
ft	Watts	cu ft	Watts	cu ft	ft	in	ft	in	ft	in
7 to 10	40	1.6	0.5	0.02	9	0	8	0	10	0
			1.5	0.06	5	2	4	6	6	0
			2.5	0.10	4	0	3	9	4	3
8 to 13	60	3.0	0.5	0.02	11	0	9	6	12	9
			1.5	0.06	6	4	5	6	7	3
			2.5	0.10	4	11	4	6	5	6
12 to 16	100	4.0	0.5	0.02	14	5	12	6	16	0
			1.5	0.06	8	2	7	0	9	6
			2.5	0.10	6	4	5	8	7	0
14 to 20	150	6.0	0.5	0.02	17	4	15	0	20	0
			1.5	0.06	10	0	9	0	11	0
			2.5	0.10	7	9	7	0	8	6
17 to 27	250	10.0	0.5	0.02	22	5	20	0	25	0
			1.5	0.06	12	11	11	9	14	3
			2.5	0.10	10	0	9	0	11	0
25 to 35	400	16.0	0.5	0.02	28	2	25	0	31	6
			1.5	0.06	16	4	15	0	17	9
			2.5	0.10	12	7	11	6	13	6
30 to 40	500	20.0	0.5	0.02	31	7	28	0	35	6
			1.5	0.06	18	6	16	6	20	9
			2.5	0.10	14	2	12	6	15	0

\* To determine the size of equivalent Welsbach lamps allow 1 cu ft per hour for each 25 watts. Adapted from the Electric Journal, by A. J. Airston.

The Designing of General Illumination by Each System Using Tungsten or Welsbach Lamps

- (1) From Table III should be determined the watts per square foot desirable for the given class of work, and the total number of watts necessary should then be computed.
- (2) From Table IV should be obtained the size of unit desirable for a given height of room and the number and spacing of fixtures then computed.
- (3) The ceiling should be laid off in squares the sides of which are as nearly as possible equal to the value of the ideal spacing. One fixture should be located at the center of each square.
- (4) Each lamp should be checked up on the plan to see that it is useful and clear of obstacles, and the layout incorporated into the building plans using the standard methods and symbols for electricity or gas as the case may be.

Table V. Standard Symbols for Gas-Piping Plans\*

	Ceiling-outlet; gas only. Numeral indicates the number of single-mantle gas-lamps.
	Single-lamp outlet (ceiling-units, pendants, etc.); gas only.
	Ceiling-outlet; combination. $\frac{4}{2}$ indicates 4 electric lamps and 2 single-mantle gas-lamps.
	Bracket-outlet; gas only. Numeral indicates the number of gas-lamps.
	Bracket-outlet; combination. $\frac{4}{2}$ indicates 4 electric lamps and 2 gas-lamps.
	Baseboard-outlet; gas only. Numeral indicates number of gas-lamps.
	Floor-outlet; gas only.
	Special outlet (for portable lamp, heater, etc.); gas only.
	Outlet for outdoor-standard or pedestal; gas only. $\frac{2}{5}$ indicates 2 gas-lamps, with 5 mantles per lamp.
	Outlet for outdoor standard or pedestal; combination. $\frac{6}{2}$ indicates 6 electric lamps, and 2 gas-lamps, with 5 mantles per lamp.
	Arc-lamp outlet; gas only. Numeral indicates the number of mantles.
	Pump or pneumatic lighting-system. Numeral indicates the number of lamps to be operated from one pump.
	Push-button for magnet-valve. The numeral indicates the number of lamps to be operated from one push-button switch.
	Meter-outlet.
	Main or supply-pipe concealed under floor.
	Main or supply-pipe concealed under floor above.
	Main or supply-pipe exposed.
	Branch pipe concealed under floor.
	Branch pipe concealed under floor above.
	Branch pipe exposed.
	Street gas-main.
	Battery-outlet.
	Riser.

\* Illuminating Engineering Laboratories, Welsbach Company.

Distance from Floor to Center of Wall-Outlets\*

	ft	in
Living-room.....	5	6
Chambers.....	5	0
Offices.....	6	0
Corridors.....	6	3
Push-button switches or pneumatic pumps.....	4	0

\* Illuminating Engineering Laboratories, Welsbach Company.

Examples of Design of Lighting-System for accounting-office, 63 by 25 ft with 13-ft ceiling (Fig. 1). Walls and ceiling-light in color.




Fig. 1. Plan of Ceiling-lights

Direct System

- Watts per sq ft
- Total watts
- Unit, size of
- Number of units
- Spacing (average) desired
- Number of rows
- Number of outlets per row
- Spacing between rows
- Spacing in rows
- Spacing-average
- = 1.5 (Table III)
- = 1.5 × 63 × 25 = 2 400 (nearly)
- = 60 watt electric (Table IV)
- = 3 cu ft per hour, ordinary inclosed gas, or } about!
- = 2 cu ft per hour, Welsbach KINETIC
- = 2 400/60 = forty
- = 6 ft 4 in (Table IV)
- = 25/6¼ = four
- = 40/4 = ten
- = 25/4 = 6¼ ft
- = 63/10 = 6½ ft
- = 6 ft 4 in.




Fig. 1A. Modification of Plan Shown in Fig. 1

Fig. 1A is a modification of the plan shown in Fig. 1, and is a great improvement. It will not produce such even illumination but will result in a much more



artistic effect, especially if fixtures are chosen which harmonize with the furnishings of the room. The lamps are placed in groups of four on ten fixtures and these are equally spaced throughout the room. Here again it is always possible to use lamps of higher wattage at any point where the illumination is not sufficient. The importance of a proper choice of reflector is shown from a study of Figs. 2 to 5.\* It will be noted in Fig. 2 how a bare tungsten-lamp throws the greater part of its light to the walls. The distribution of any light can be controlled to a remarkable extent by the use



Fig. 2. Distribution of Candle-power about a Bare Tungsten Lamp




Fig. 3. Holophane Reflector. Extensive Distribution of Light

Fig. 4. Holophane Reflector. Intensive Distribution of Light

the proper reflector. Figs. 3 to 5 show how the several types of Holophane reflectors distribute the light.

\* Furnished by E. B. Rowe, of the Holophane Works.




Fig. 5. Holophane Reflector. Focusing Effect on Light

Fig. 6. Example of Type of Fixture Used in Semiindirect System. Macbeth-Evans Company

#### Indirect or Semiindirect Systems, for Electricity

Watts per sq ft	= 1.5 (Table III)
Total watts	= 2 400, nearly
Average spacing	= 14 to 24 ft (Table VI)*
Select 25/2	= 14 ft for lamps in two rows
Number of units in row	= $63/12.5$ = five
Spacing in row	= $63/5$ = 12 ft 7 in, about
Type of reflector	= Concentrating (Table VI)
Distance from reflector to ceiling	= 30 in (Table VI)
Number of units	= two rows of five each = ten
Watts per unit	= $2\,400/10$ = 240
Lamps per unit	= one, 250 watts four, 60 watts six, 40 watts

#### Calculations for this Example for Gas-Lighting

Welsbach kinetic burner used.

Cu ft per hour per sq ft	= $0.06 \times 0.6$ = 0.036 (Table III)
Total hourly consumption	= $63 \times 25 \times 0.036$ = 57 cu ft per hour.
Average spacing (see above)	= 12½ ft
Number of units	= ten
Consumption per unit	= $57/10$ = 6
Reflector and mounting-height as in preceding problem	
Lamps per unit	= one, 6 cu ft
Lamps per unit	= two, 3 cu ft, etc.

\* See How to Use Table VI, immediately following the Table.

### Ceiling-Outlets and Reflectors

**Table VI. For Determining Number of Ceiling-Outlets, Type of Reflex and the Distance from Top of Reflector to Ceiling for Indirect and Semirect Lighting \***

Height of ceiling in feet	One side of the limiting square in feet that can be uniformly illuminated from one center outlet												Distributing	Concentrating			
	10	12	14	16	18	20	22	24	26	28	30	32			34	36	38
20																	Distributing Concentrating
19																	Distributing Concentrating
18																	Distributing Concentrating
17																	Distributing Concentrating
16																	Distributing Concentrating
15																	Distributing Concentrating
14																	Distributing Concentrating
13																	Distributing Concentrating
12																	Distributing Concentrating
11½																	Distributing Concentrating
11																	Distributing Concentrating
10½																	Distributing Concentrating
10																	Distributing Concentrating
9½																	Distributing Concentrating
9																	Distributing Concentrating
8½																	Distributing Concentrating
8																	Distributing Concentrating

Table VI gives the distance in inches (except as noted) from the top of the reflector to the ceiling to obtain the desired distribution of light from one ceiling-outlet.

Where values are not given to the left, it is advisable to submit data to Human engineers and for greater ceiling-heights than 20 ft.

\* H. B. Wheeler, X-Ray Eye-Comfort Company.

An idea of the appearance of some of the typical modern fixtures using gas or electricity in these systems of lighting may be obtained from Figs. 6, 7 and 8.



Fig. 7. Type of Fixture in Indirect Illumination. National X-Ray Reflector Company

Fig. 8. Fixture Used for Gas by Either Indirect or Semindirect System

**How to Use Table VI.** In the first column of Table VI is located the height of ceiling, in this case, 13 ft. The last square to the right of this figure, which has a number in it, is noted. In this case the last square to the right of 13 ft, which has a number in it, contains the number 48. By following this column containing the number 48 down to the figures printed in heavy type at the bottom of the table, the heavy-faced number in this case is found to be 24. This 24 is the length of the side of the largest square which a single fixture can properly illuminate when the ceiling is 13 ft high. The 48 which is opposite the 13 is merely the number of inches the fixture must be hung from the ceiling. Thus the largest squares into which we can possibly divide the ceiling have 24-ft sides. But a room 25 ft wide cannot be divided into 24-ft squares. We are compelled, therefore, to divide it into squares of a smaller size, since the fixtures will not illuminate any larger square. The greatest length into which we can divide 25 ft is 12½ ft. We may, then, decide to use fixtures which will illuminate 14-ft squares. Locate the number 14 in heavy type at bottom of table, and trace up the column in which it is found until the square is reached which is opposite the ceiling-height of 13 ft. Here the number 30 is found. This means we must hang the fixture so that the top of it is 30 in from the ceiling in order to get the desired results. Looking along the squares to the right of the one in which we find the 30, we find the word **CONCENTRATING** which signifies the type of reflector advised for this installation.

**School-Room Lighting.\*** The following illumination-constants have been worked out by experiments and experience covering a wide range of conditions. In each of the following cases light tinted walls and ceilings are taken as a standard.

**Auditoriums and Lecture-Halls.** Since no continuous reading is required here, 0.75 watt per sq ft, direct system, is all that is needed, if it is properly diffused to a pleasant softness.

**Class-Rooms and Laboratories.** These must be lighted for the purpose of writing notes and taking accurate readings of instruments. Thus  $1\frac{1}{4}$  watts per sq ft, direct system, are required.

**Wood-Working Shops.** The surfaces here are generally high and offer good reflecting properties, so that  $1\frac{1}{4}$  watts per sq ft, direct system, are sufficient.

**Machine-Shops.** Because the belts, machines and dingy floors offer great absorbing surfaces at least 2 watts per sq ft, direct system, are necessary.

**Foundries.** The dark molding-sand and the dust and smoke in the air make 3 watts per sq ft, direct system, necessary.

**Drafting-Rooms.** The semiindirect system with  $2\frac{1}{4}$  watts per sq ft (about the equivalent of  $1\frac{1}{4}$  watts per sq ft, direct system) has proved highly satisfactory.

**Illumination by Gas.†** Recent progress in incandescent gas-lighting has resulted in the development of appliances in which practically all of the shortcomings of previous types are overcome, and except for inaccessible locations, or where lamps are very infrequently lighted, there is little to choose between the two illuminants, gas and electricity, upon the score of convenience or of artistic possibilities, while the greater economy of gas-lighting (often in the ratio of about  $2\frac{1}{2}$  to 1) coupled with the freedom from interruption which characterizes gas-service makes it desirable to pipe all buildings, particularly residences, for gas throughout, preferably installing combination-fixtures and providing wall-outlets and baseboard-outlets for the connection of the various gas-operated conveniences which are being developed in rapidly increasing numbers.

**Welsbach Kinetic-Burner Lamps With Nearest Equivalent Sizes in Electric Incandescent Lamps**

Lamps	Mazda watts	Nitrogen-filled Mazda (Type C) watts
1 mantle 2.5 cu ft per hour.....	two, 40	.....
2 mantles 5.0 cu ft per hour.....	150	.....
3 mantles 7.5 cu ft per hour.....	250	.....
4 mantles 10.0 cu ft per hour.....	six, 40	.....
5 mantles 12.5 cu ft per hour.....	400	.....
6 mantles 15.0 cu ft per hour.....	500	.....
8 mantles 20.0 cu ft per hour.....	.....	500
10 mantles 25.0 cu ft per hour.....	.....	750

**Gas-Lamps** are available in a variety of types and sizes. The most recent development is the KINETIC burner of the Welsbach Company in which the efficiency is increased by from 50% to 100% over the previous types. With this burner no enclosing glassware or housings are required, and the lamp is said

\* A. L. Williston.

† R. F. Pierce, Welsbach Company.

to require no attention beyond the renewal of mantles every 2 000 burning-hours. There is practically no depreciation in candle-power during this interval. Ignition is accomplished either by a pilot-flame burning about  $\frac{1}{10}$  cu ft per hour, or by electrical means, and several types of distant control are available. The following table gives the sizes in which these lamps may be obtained and the nearest equivalent sizes in electric incandescent lamps.

### Selection of Illuminants

(1) Factors favorable to the use of electricity:

Units less than 60 candle-power required.

Lamps in inaccessible positions.

Lamps lighted at infrequent intervals.

Lamps placed very close to ceiling (12 in or less).

Poor gas service as regards:

Pressure-regulation (more than 50% variation from minimum).

Non-uniformity of gas-quality.

Imperfect purification.

Good electric service as regards:

Voltage-regulation.

Freedom from liability to derangement by accident.

Non-rigid fixtures.

(2) Factors favorable to the use of gas:

Units of 60 candle-power or more.

Accessible locations.

Frequent use of lamps.

Lamps placed 15 in or more from ceiling.

Good gas service as regards:

Pressure-regulation (not more than 50% variation from minimum).

Uniformity of gas-quality (chemical composition).

Proper purification.

Poor electric service as regards:

Voltage-regulation (more than 5% variation from maximum) most likely on alternating-current circuits.

Liability to derangement by accident (overhead circuits).

Rigid fixtures.

**Hygiene.\*** From the hygienic point of view there is little to choose between the two illuminants. The investigations of Dr. Rideal have shown that: (1) Gas-light positively improves the air for breathing purposes under the actual conditions of use. The causes of this improvement are the acceleration of ventilation, the destruction of disease-germs and the addition of necessary moisture. Gas-burners give rise to stronger air-currents and invariably produce a more active ventilation and diffusion of air than electric lights; hence, along with the products of the gas-burner, the exhalations of persons present are more rapidly removed; (2) The ascending currents of air from the gas-lights on reaching the ceilings rapidly part with their heat, which is conducted away by the rafters and joists; (3) The electric lamps produce more heat than is commonly accredited to them, and this is the explanation of the unexpected result that the average temperature of the room is practically the same under either illuminant, and that the electric light does not show the superiority in coolness usually claimed. When excessive temperatures are encountered in gas-lighted

\* See Relative Hygienic Values of Gas and Electric Lighting, by Samuel Rideal, Transactions Royal Sanitary Institute, March, 1908.

rooms, it will be found due to the radiant heat from low-hung lamps of excessive size. On account of the economy of gas-lighting, it is a common practice to provide from four to six times as much illumination as is required. Dr. Rideal's tests also emphasized, what is a matter of common experience, that under direct lighting, the lower brilliancy of the gas-mantle reduced the glare from glazed papers to such an extent as to be noticeable in the results: "The sensitiveness of the eye to light as measured in the perception-test diminished very markedly after exposure to the electric light, while no corresponding effect is noticeable after the eye has been subjected to gaslight. All the results point strongly in the same direction, namely, that gaslight, as used in these experiments, is less fatiguing to the eye than electric light." Under semi-indirect or indirect lighting, of course, no such disparity in effect is found.

**The Foregoing Rules Indicate the General Practice** in planning the illumination of a room. It must be said, however, that this set of rules must not be followed too slavishly. In illumination no rules can take the place of judgment and intelligence. Each project must be considered more or less as a problem by itself, for which previous experience and former installations should be made to furnish data and to suggest methods. It is well, therefore, when planning the illumination of a room, to visit as many similar rooms as possible, note the effect of the systems in use and obtain data as to their efficiency, cost, etc. The most successful scheme may then be used as the basis for planning the desired installation.

### **The Diffusion of Light through Windows \***

**Tests on the Diffusion of Light by Glass.** Abstracts from report of Charles L. Norton, on an elaborate series of tests made at the Massachusetts Institute of Technology:† The results of the tests on a score or more of different glasses may be stated briefly. We may increase the light in a room 30 ft or more deep to from three to fifteen times its present effect by using **FACTORY-RIBBED GLASS** instead of **PLANE GLASS** in the upper sashes. By using prisms we may, under certain conditions, increase the effective light to fifty times its present strength. The gain in effective light on substituting ribbed glass or prisms for plane glass is much greater when the sky-angle is small, as in the case of windows opening upon light-shafts or narrow alleys. The increase in the strength of the light directly opposite a window in which ribbed glass or prisms have been substituted for plane glass is at times such as to light a desk or table 50 ft from the window better than one 20 ft from the window had previously been lighted.

**The Kinds of Glass Tested** were as follows:

- (1) Ground glass of different degrees of fineness.
- (2) Rough plate or hammered glass.
- (3) Ribbed or corrugated glass, with five, and eleven and twenty-one ribs to the inch, the corrugations being sinusoidal in outline, as in *A*, Fig. 9, and the back of the plate smooth.
- (4) Glass known as **MAZE**, **FLORENTINE** or **FIGURED**, in which a raised pattern is worked upon one side, practically roughening the whole surface.
- (5) Wash-board glass, corrugated, with twenty-one ribs to the inch on one side and five ribs to the inch on the other side, the ribs being parallel.
- (6) Skylight-glass, which has five ribs to the inch on each side, the groove on one side being opposite the rib on the other, giving a sinuous section *B*, Fig. 9.

\* See, also, the subjects **Pressed Prism-Plate Glass** and **Prism Glass**, Part III, pages 1577 to 1579.

† From Report No. III, Insurance Engineering Experiment Station, September, 1902.

(7) Ripple-glass, with rippled surfaces on both sides; of very beautiful appearance and a clear white color.

(8) Glass ribbed on one side and figured on the other.

(9) Ribbed glass with a wire net pressed into it, to increase its resistance to fire.

Of these several specimens, one or two may be dismissed with brief mention. Ground glass is of little value, except as a softening medium for bright sunlight.




Fig. 9. Types of Ribbed or Prism-glass

Its rapidly increasing opaqueness with moisture and dust makes it undesirable as a window-glass. The common rough plate has very little action as a diffusing-medium, giving no perceptible change in the effective light. Ripple-glass has great value as a diffusing-medium in small rooms with nearly open horizon. Of the ribbed glasses, the fine Factory-Ribbed, with twenty-one ribs to the inch, is distinctly the best, not in all probability because of the fineness, but because of the greater sharpness of the corrugations.

The Ribbed wire-glass is about 20% less effective than the ordinary Factory-Ribbed glass. The addition of a second corrugation upon the back of the plate giving the Skylight and Wash-Board glass is of no apparent value. The raised pattern imprinted upon one surface of the glass, as in the case of the Maze glass, gives the widest diffusion, especially in bright sunlight. A raised figure, when worked upon the back of the Ribbed glass, renders it less offensive to the eye in bright sunlight, but less effective in deep rooms. The only glasses of this group which it is worth while, then, to discuss further are the Factory-Ribbed and the Maze glass.

The second group comprises the following glasses:

- (1) The Luxfer prisms.
- (2) The Solar prisms.
- (3) The Daylight-prisms.
- (4) The glass of prismatic section made by the Mississippi Glass Company.
- (5) Three-way prisms.
- (6) Maltby prisms.

The Luxfer prism consists of a plate smooth on one side and deeply notched on the other as in C, Fig. 9, the teeth or prisms being of very flat, smooth faces of brilliant appearance. The glass is clear white, and the prisms used in canopies and in the major part of the vertical glazing are made in tiles or plates about 4 in square. Tiles are built up in large sheets in frames of copper or brass, so made as to give to the sheets of tiles a strength and durability far in excess of a single sheet of the same size. The Luxfer prisms are made for factory-use in large sheets, as well as in the small tiles. The Solar prisms are made in small tiles, which are held together in a metal frame to make large sheets. The main difference between the Solar and Luxfer prisms is that the under face of the former prism is curved instead of plane, as in D, Fig. 9. The Daylight-prisms tested were made in large sheets and of approximately the same cross-section and general appearance as the Luxfer prisms for factory-use. No tiles of Daylight-prisms were tested, as none came to hand in time for the test. The Mississippi prism glass is much like the other prisms in cross-section, but the ridges or



ms do not run across the plate in a straight line, but in a wavy or sinuous line. advantage arising from this over the straight-edge prism was detected.

inclusions. (1) The conditions in a room less than 15 ft deep are such , except with a skylight of less than  $45^\circ$ , it is not advisable to alter the general se of the light by using a prismatic or ribbed glass. A nearly hemispherical sion, such as is given by the e or Ripple-glass, is ordi- y preferable.


) When a room is from 20 : ft deep, or even more, and : skylight of  $60^\circ$  or less, the :d and prismatic glass results :very great gain in effective . The gain in brilliancy is :as to make a basement with :canopies as light as a :d story with plane glass.

oms with windows opening

light-shafts and narrow : with very limited openings :e sky, where the available

is now small, may have the light 20 ft back from the window increased ten :enty times by using prisms; and, by using canopies of prisms, it is some- :possible to strengthen the light fifty to one hundred times. With sky- :s of  $30^\circ$ , or less, and in deep rooms, the relative efficiency of the prism :increases greatly. The refraction of the incident ray in a case of the ribbed

Fig. 10. Refraction of Light in Ribbed and Prism-glass



1. Basement and First Story Lighted from Court

diffusing glass as well, a further increase of about 25% may be :ed.

nsidering both expense and efficiency, the following general suggestions are

Use Maze or Ripple-glass in small rooms or offices not more than 15 or 20 ft :use Factory-Ribbed glass in rooms from 30 to 50 ft deep, with sky-angles of :more; use prisms or Factory-Ribbed glass, in sheets, in all vertical win-

glass and prism is shown in Fig. 10. Ribbed and maze glass are of very great value in softening the light, especially in the case of such windows as are exposed to the direct sun, aside from their effectiveness in strengthening the light at distant points. With the Maze glass, the artist may have, in all weather and in all directions, what is in effect a much-desired NORTH LIGHT. The photographer may have in this way as well diffused a light as he now has with cloth screens or shades, and with a much greater intensity. To be efficient in rooms 20 ft deep or more, ribbed glass should be set with its ribs horizontal, and where the sunlight falls upon it, it should be provided with thin white shades. All inferences drawn from the test are made :upon the assumption that the windows are to be glazed with diffusing glass only in the upper half, which is the common practice. If the lower sash is to be glazed

dows in rooms more than from 50 to 60 ft deep, with sky-angle of less than  $45^\circ$ . With a sky-angle of less than  $30^\circ$  use prisms in canopies. Fig. 11 shows an effective method of lighting the basement and first story where the light must come from a court.

### Reference Books on Illumination

- Practical Illumination, 1907. Cravath and Lansingh.  
Art of Illumination, 1902. Louis Bell.  
Electrical Illuminating Engineering, 1908. Barrows.  
Light, Visible and Invisible. Sylvanus Thompson.  
American Practice of Gas-Lighting. W. P. Gerhard.  
Color Values. C. R. Clifford.  
Radiation, Light and Illumination, 1909. C. P. Steinmetz.  
Illumination and Photometry, 1910. Wickenden.  
Electric-Lamps, 1908. Maurice Solomon.  
Illumination, its Distribution and Measurement, 1910. Alex. Pelhan Trotter.  
Photometric Measurements, 1904. W. M. Stine.  
Proceedings and Transactions of Illuminating Engineering Society.  
Proceedings and Transactions of American Institute of Electrical Engineers.  
Proceedings and Transactions of National Electric Light Association.  
Proceedings and Transactions of American Gas Institute.  
The Illuminating Engineer (New York).  
The Illuminating Engineer (London) with which is combined the Transactions of the London Illuminating Engineering Society.  
Foster's Engineers' Pocket-Book, 1908.  
Standard Handbook for Electrical Engineers, 1908.  
Engineering Section, Holophane No. 2 Data Book.  
Bulletins of the Engineering Department, National Electric Lamp Association.  
Bulletins of the General Electric Company.  
Tungsten Illumination, 1910. Westinghouse Company.  
The Electrical Solicitor's Handbook, 1910. National Electric Light Association.  
Gas Solicitor's Handbook, 1910. Welsbach Company.  
Factory Lighting, C. E. Clewell.  
American Electricians' Handbook, Terrell Croft.

# ELECTRIC WORK FOR BUILDINGS

By

W. H. TIMBIE

ASSOCIATE PROFESSOR OF ELECTRICAL ENGINEERING, MASSACHUSETTS INSTITUTE OF TECHNOLOGY

**General Considerations and Definitions.** Electrical energy is now in common use, furnishing power, heat and light, operating bells and buzzers, and transmitting messages by telephone and telegraph. In order to accomplish these results, a current of electricity must flow around an electric circuit. The nature of electricity is not known, but the flow of it through an electric circuit is analogous to the flow of water through a system of pipes.

**Current. Amperes.** The flow of water is measured in GALLONS PER SECOND. The flow of electricity is measured in AMPERES. An ampere-flow of electricity is analogous to a gallon-per-second flow of water. The amperes thus indicate the quantity of electricity flowing through an electrical appliance in one second. About  $\frac{1}{2}$  ampere is flowing through an ordinary carbon-filament incandescent lamp when it is glowing at 16 candle-power. The same current of  $\frac{1}{2}$  ampere causes a modern tungsten lamp to produce over 40 candle-power. An arc-lamp usually requires a flow of from 5 to 10 amperes.

**Pressure. Volts.** When a current of water flows from one point to another in a pipe-system, it is always because there is a hydraulic pressure present causing it to flow. This pressure is usually measured in pounds per square inch. Similarly, when a current of electricity flows from one point to another in an electric circuit, it is because there is an electric pressure present which causes it to flow. This electric pressure is measured in VOLTS. An electric pressure of 1 VOLT is analogous to a hydraulic pressure of 1 lb per sq in. The pressure which causes the  $\frac{1}{2}$ -ampere current to flow through an incandescent lamp is usually 110 volts. The electric company installs at least two wires in a residence and then maintains an electric pressure of 110 volts between them just as the water company maintains a pressure in the water-pipes. This electric pressure is at all times tending to force electricity from one wire to the other wire across the space between the two wires, just as the water-pressure tends to force the water out from the pipe. The rubber insulation is put on to prevent this flow, very much as the strength and compactness of the iron prevents the flow of water through the walls of the pipe. But when one terminal of a lamp is connected to one wire and the other terminal to the other wire, the electric pressure tending to send a current from one wire to the other, sends a current through the lamp and causes it to glow. We mark the wire bringing the




Fig. 1. Current Always Flows from (+) to (-)

causes it to flow. This electric pressure is measured in VOLTS. An electric pressure of 1 VOLT is analogous to a hydraulic pressure of 1 lb per sq in. The pressure which causes the  $\frac{1}{2}$ -ampere current to flow through an incandescent lamp is usually 110 volts. The electric company installs at least two wires in a residence and then maintains an electric pressure of 110 volts between them just as the water company maintains a pressure in the water-pipes. This electric pressure is at all times tending to force electricity from one wire to the other wire across the space between the two wires, just as the water-pressure tends to force the water out from the pipe. The rubber insulation is put on to prevent this flow, very much as the strength and compactness of the iron prevents the flow of water through the walls of the pipe. But when one terminal of a lamp is connected to one wire and the other terminal to the other wire, the electric pressure tending to send a current from one wire to the other, sends a current through the lamp and causes it to glow. We mark the wire bringing the

current to the lamp (+). The wire taking the current away, we mark (-). Thus in Fig. 1, if the current comes in on the wire marked (x), this wire is (+) and the wire (y) is (-). A pressure of 110 volts is maintained which tends to cause a current to flow across from the wire (x) to the wire (y). No current can flow, however, unless some path is afforded between the two wires. For instance, no current is flowing through lamp  $L_1$ , because the open switch  $A$  makes a gap across which the current cannot pass. Switch  $B$ , however, is closed, thus allowing the pressure to force a current from the wire (x) through the lamp  $L_2$  to the wire (y) and back into the street-mains. Of course the electric company maintains the 110-volt pressure between the wires (x) and (y) whether any current is drawn from the wires or not, just as a water company maintains the pressure in the water-mains whether any water is drawn from the pipes or not.

**Resistance. Ohms.** The fact that a current of only  $\frac{1}{2}$  ampere flows through an incandescent lamp when a pressure of 110 volts is applied to it, is due to the RESISTANCE of the fine filament. This resistance of the filament is analogous to the resistance which a pipe of small bore offers to the flow of water. The resistance of an electrical appliance is merely the ratio of the pressure to the current which that pressure can force through it. As an equation, it is expressed

$$\text{Resistance} = \frac{\text{pressure}}{\text{current}}$$

When the pressure is measured in volts and the current in amperes, the resistance is then in ohms. Thus

$$\text{Ohms} = \frac{\text{volts}}{\text{amperes}}$$

Thus, since a pressure of 110 volts forces  $\frac{1}{2}$  ampere through an ordinary incandescent lamp, the resistance of the lamp is  $110/\frac{1}{2} = 220$  ohms.

**Ohm's Law.** This relation between pressure, current and resistance is called OHM'S LAW. It is written in symbols in the three forms

$$R = E/I$$

$$E = IR$$

$$I = E/R$$

where

$R$  = resistance in ohms;

$E$  = pressure in volts;

$I$  = current in amperes.

**Example.** An electric flat-iron has a resistance of 35 ohms. What current will flow through it when it is put across a 110-volt circuit?

$$I = E/R = 110/35 = 3.14 \text{ amperes}$$

**Example.** An electric toaster takes  $1\frac{1}{2}$  amperes when on a 115-volt circuit. What resistance does it have?

$$R = E/I = 115/1.5 = 76.6 \text{ ohms}$$

**Insulators and Conductors.** In order that practically no current may leak from one wire to the other, the wires are covered with rubber. This rubber covering offers such high resistance to the flow of an electric current that, although two wires may lie very close to one another with only this rubber between them, practically no current leaks through the rubber from one wire to the other. Materials such as rubber, glass, porcelain, dry wood, etc., have this resisting property and are said to be INSULATORS. Metals, on the other hand, offer very little resistance to the flow of an electric current and are called con-

**DUCTORS.** A copper wire  $\frac{1}{16}$  in in diameter has a resistance of only  $\frac{1}{1000}$  of an ohm per foot. Accordingly, because of their low resistance, copper wires are generally used to carry electric currents, and because of its high resistance, rubber is generally used as a covering of the copper wires to prevent leakage from one wire to another. Wire, approved by the National Board of Fire Underwriters and installed according to their rules, will have the proper insulating covering for each installation.

**Power. Watts.** The flow of an electric current has been likened to the flow of water through a pipe. A current of water is measured by the number of gallons, or pounds, flowing per minute; a current of electricity is measured by the number of amperes. The power required to keep a current of water flowing is the product of the current in POUNDS PER MINUTE by the head, or pressure, in FEET. This gives the power in FOOT-POUNDS PER MINUTE. To reduce to horse-power, it is necessary merely to divide by 33 000. Thus

$$\frac{(\text{pounds per minute}) \times (\text{feet})}{33\,000} = \text{horse-power}$$

In exactly the same way, the POWER required to keep a current of electricity flowing is the product of the current in AMPERES by the pressure in VOLTS. This gives the power in WATTS.

$$\text{Watts} = \text{amperes} \times \text{volts}$$

The term WATT is merely a unit of power, and denotes the power used when one volt causes one ampere of current to flow. The watts consumed when any given current flows under any pressure can always be found by multiplying the current in amperes by the pressure in volts. Thus, if an incandescent lamp takes 0.5 ampere when burning on a 110-volt line, the power consumed equals

$$0.5 \times 110 = 55 \text{ watts}$$

That is,

$$\text{Power} = \text{current} \times \text{pressure}$$

or

$$\text{Watts} = \text{amperes} \times \text{volts}$$

**Example.** What power is consumed by a motor which runs on a 220-volt circuit, if it takes 4 amperes?

$$\text{Watts} = \text{amperes} \times \text{volts} = 4 \times 220$$

$$\text{Power} = 880 \text{ watts}$$

Incandescent lamps are rated as to the voltage of the line on which they can run, and also as to the amount of electric power it takes to keep them glowing. Thus, a carbon-filament lamp may be rated as a 110-volt, 50-watt lamp. A tungsten-lamp may be rated as a 110-volt, 25-watt lamp. This means that both lamps are intended to run on a 110-volt circuit, but that it takes twice as much power to keep the carbon-filament lamp glowing as it does to keep the tungsten-lamp glowing.

**The Power-Equation.** The above relation between volts, amperes and watts is usually expressed in the form of an equation:

$$P = IE$$

$$I = P/E$$

$$E = P/I$$

where

$P$  = power in watts;

$I$  = current in amperes;

$E$  = pressure in volts.

**Example.** What current does a 40-watt tungsten-lamp take when running on a 115-volt circuit?

$$I = P/E = 40/115 = 0.348 \text{ ampere}$$

**Power. Kilowatt and Horse-Power.** Because the watt is so small a unit of power, being only 0.74 ft-lb per second, a larger unit, the kilowatt, is generally used in connection with machines, etc.

$$1 \text{ kilowatt} = 1\,000 \text{ watts} = 1\frac{1}{2} \text{ horse-power}$$

Thus a motor drawing 10 amperes from a 220-volt line would take  $10 \times 220 = 2\,200$  watts  $= 2\,200/1\,000 = 2.2$  kilowatts.

At 80% efficiency this motor would give out 80% of 2.2 = 1.76 kilowatts  $= 1.76 \times 1\frac{1}{2} = 2\frac{1}{2}$  horse-power.

**Horse-Power-Hour. Kilowatt-Hour.** When a man buys mechanical power to run machinery, he has to pay not only according to the horse-power he uses but also according to the number of hours he uses the power. For instance, he may use 40 horse-power for 1 hour and pay \$1.20 for it, that is, at the rate of 3 cts for each horse-power-hour. If he uses 40 horse-power for 2 hours he would have to pay twice as much, because he has used the same power twice as long. Another way of stating the same fact is to say that he used twice as many horse-power-hours. For in the first instance he used  $40 \times 1$ , or 40 horse-power-hours, and in the second  $40 \times 2$ , or 80 horse-power-hours. In other words, he did twice as much work in the second case as he did in the first, or received twice as much energy. The unit of work or energy, then, is the HORSE-POWER-HOUR, and is the work done in 1 hour by a 1-horse-power machine.

**Example.** How much work is done by a machine delivering 15 h.p. when it is run for 8 hours?

$$\begin{aligned} 1 \text{ h.p. in } 1 \text{ hr does } & 1 \text{ h.p.-hr} \\ 15 \text{ h.p. in } 1 \text{ hr does } & 15 \text{ h.p.-hr} \\ 15 \text{ h.p. in } 8 \text{ hr does } & 8 \times 15, \text{ or } 120 \text{ h.p.-hr} \end{aligned}$$

That is

$$\text{Work} = \text{horse-power} \times \text{hours}$$

or

$$15 \times 8 = 120 \text{ h.p.-hr}$$

Similarly, electric power is sold by the KILOWATT-HOUR. This unit is the work or energy delivered in one hour by a 1-kilowatt machine.

For lighting purposes electrical energy is usually sold for from 10 to 15 cts per kilowatt-hour. Thus at 12 cts per kw-hr the monthly bill for burning a 40-watt lamp on an average of 5 hours per day would be computed as follows:

For 1 month of 30 days the lamp is burning

$$30 \times 5 = 150 \text{ hours}$$

To use a 40-watt lamp 150 hours consumes

$$40 \times 150 = 6\,000 \text{ watt-hours} = 6\,000/1\,000 = 6 \text{ kilowatt-hours}$$

At 12 cts per kw-hr, 6 kw-hr cost

$$6 \times 12 = \$0.72$$

An instrument called a KILOWATT-HOUR METER is placed in each house to measure the number of kilowatt-hours which each customer consumes. See *M* in Fig. 13 for location of Kilowatt-hour meter, and Fig. 18 for method of connection in typical installation.

**Heating-Effect of Current.** An electric current always heats the material through which it passes. Examples of this are the incandescent lamp, in which

the current heats the fine tungsten wire until it glows; the electric heaters for warming-dishes, toasters, etc. Even the wires carrying the current to and from the lamps are heated by the passage of the current through them. But since the heating effect for a given current is directly proportional to the resistance of the conductor, and the conductors always have very little resistance, the heating here is very slight indeed. If conductors of smaller size, and therefore of higher resistance, were used, the heating would be very pronounced; in fact, it would soften the rubber insulation and might even produce a temperature high enough to set fire to the building. For this reason The National Board of Fire Underwriters issues a table specifying the size of wire which must be used for each amount of current. If smaller wire is used, the resistance of it might be great enough to raise the temperature to a dangerous degree. On the other hand, if a greater current than allowed by this table is sent over the wire, the temperature will also rise, because the heating of a current is also directly proportional to the SQUARE OF THE CURRENT. Thus, doubling the current which a certain wire is carrying will quadruple the amount of heat which the wire must dissipate. For this Tables III and IV, see pages 1473 and 1474.

**Fuses and Circuit-Breakers.** Use is made of the heating effect of a current to protect a circuit against too much current, very much as a boiler is protected by a safety-valve against too much pressure. A small piece of fusible metal, generally a mixture of lead and bismuth, is inserted in the circuit in such a way that all the current which passes through the circuit must also pass through




Fig. 2. Enclosed Fuse

piece of metal. This device is called a FUSE. Any current which would be dangerous to the circuit melts this fuse, opens the circuit at this point, and thus protects the rest of the circuit from the effects of the current. The cause of large current may be then removed and a new fuse inserted in place of the one. CIRCUIT-BREAKERS are also used to protect a circuit against too much current. They are AUTOMATIC SWITCHES controlled by an electro-magnet and made in a variety of styles. They operate upon the principle that when electric current passes through a coil of wire it makes a magnet of the coil. The coil is so adjusted that when a current of a certain number of amperes passes through it, it attracts to itself a small piece of iron. The motion of this piece of iron opens the circuit. Fuses and circuit-breakers are thus AUTOMATIC SAFETY-DEVICES required for the protection of all constant-potential systems whatever the voltage. Both are for the purpose of protecting the wires from damage due to the presence of too much current from any cause whatever. An ordinary fuse consists of a porcelain base that has suitable terminals for inserting a fuse between the ends of a wire. It must be constructed so that the pulling out of a fuse can do no damage, that is, set anything on fire, and placed so that it can easily be reached to replace the fuse. Formerly a piece of fuse-wire, called a LINK-FUSE, was used in cut-outs, but the underwriters now require enclosed fuses (Fig. 2) or fusible plugs which screw into a receptacle. Fuse-

plugs may be used for currents up to 30 amperes; above that enclosed fuses must be used. Fuse-plugs and enclosed fuses are somewhat more expensive than the link-fuse, but are considered safer. A FUSE CUT-OUT or CIRCUIT-BREAKER is required at or near the place where the wires enter a building, and every circuit of twelve 16-c.p. carbon-lights or of sixteen 40-watt tungsten-lights must be protected by a cut-out. Circuit-breakers are more expensive than fusible cut-outs, and are generally used only on SWITCHBOARDS for large installations and where it is desirable to open the circuit instantly on certain loads, which a fuse cannot be depended on to do with any degree of accuracy, owing to both time and surrounding temperature-factors. Circuit-breakers are also used largely on installations where the variation in load is large and frequent and the repeated burning out of fuse would become expensive not only for renewals but also on account of the time required to replace them.

**Lamps.** Two kinds of lamps are used for electric lighting, INCANDESCENT LAMPS and ARC-LAMPS. The former are used principally for interior illumination, although sometimes used for street-lighting, especially where the streets are thickly shaded by trees. Arc-lamps are especially adapted for street-lighting and for large interiors where they can be kept concealed or above the range of the eye, as in railway-stations, stores, etc. An incandescent lamp as commonly made consists of a glass bulb containing a simple carbon or a tungsten conductor the ends of which are connected to the source of the electric current. When the current flows through the filament it heats it to such a degree that it becomes incandescent; hence the name of the lamp. The lamps with the filament of finely-drawn tungsten represent the latest type and are superior in every way to those having a carbon filament. Tungsten-lamps require about one-third as much power to produce the same candle-power as carbon-lamps, and have a much longer life.

**Voltages.** In order that the current shall cause the lamp to give its rated CANDLE-POWER, it must be designed for the voltage at which the system is run. If the voltage of the current is much greater than that for which the lamp is designed it will quickly burn out the filament, while if the voltage of the current is below that of the lamp, it will not give its rated candle-power, a voltage 10% lower reducing the candle-power about one-half. The voltage commonly used for tungsten-lamps is from 100 to 130. Tungsten-lamps are also made for voltages of from 20 to 260. Two to four candle-power lamps, for illuminating signs or decorative purposes, are made for from 10 to 13 volts by  $\frac{1}{4}$ -volt steps, these lamps being commonly used in series, ten lamps on a 100 to 130-volt circuit. Two 5-watt lamps, 50 volts, are also often used in series on a 100-volt circuit.

**Candle-Power.** Incandescent lamps of from 100 to 130 volts are commonly made 15, 20, 25, 40, 60, 100, 150, 250, 400 and 500 watts. These lamps average 1 candle-power for every 1.1 watts. For the method of computing the number, size and distribution of tungsten-lamps for illuminating a given room see pages 1476 to 1478.

**Arc-Lamps.** These are of two kinds, OPEN ARC-LAMPS and ENCLOSED ARC-LAMPS, the latter being generally used for interior illumination. The light from the enclosed arc is much softer and steadier than that from the old-style open arc; there are no sparks, and the life of the carbon is from twelve to fifteen times as great as in the open arc.

"Direct-Current Open Arcs usually require about 10 amperes at 45 volts, or 450 watts. The range of voltage is from 42 to 52 for ordinary constant-current arcs. The most satisfactory light is given by from 45 to 47 volts.



arc-lights used for stereopticon-lanterns may use as high as 25 amperes and provision should always be made in the wiring-plans for such a light for sufficiently large wires to be installed to carry one and one-half times this current.

“**Direct-Current Enclosed Arcs** consume about 5 amperes at 80 volts, or 400 watts.” Arc-lamps generally require a resistance in series with the arc in order to regulate properly. This resistance is usually placed within the structure of the lamp, and may be so adjusted that a single lamp can be made to run well on any circuit from 100 to 130 volts.

**Dynamo-Electric Machines.** There are three classes of dynamo-electric machines:

- (1) **GENERATORS** for generating an electric current.
- (2) **MOTORS** for converting electrical into mechanical energy.
- (3) **TRANSFORMERS** and **ROTARY CONVERTERS**.
  - (a) Transformers for converting one voltage into a higher or lower voltage. Converters and transformers belong to the same class.
  - (b) Rotary converters for changing alternating currents to direct currents or vice versa.

A **DYNAMO** is either a motor or a generator. A **MOTOR** is the same machine as a generator, but with the nature of its operation reversed. **GENERATORS** are of two general classes, namely, continuous-current and alternating-current machines; the latter are commonly called **ALTERNATORS**. Generators and motors of all kinds vary in voltage, current and speed, according to the purpose for which they are designed. A **TRANSFORMER** consists essentially of two coils of wire, one coarse and one fine, wound upon an iron core. Its function is to convert electrical energy from one voltage to another. If it reduces the voltage it is known as a **STEP-DOWN** transformer, and if it raises it, it is known as a **STEP-UP** transformer. A transformer has no moving parts and requires no attendant.

**Kinds of Currents Produced.** There are two kinds of electrical currents commonly used for light and power in buildings, (1) **DIRECT CURRENTS**, and (2) **ALTERNATING CURRENTS**.

A direct current is uniform in strength and direction, while an alternating current rapidly rises from zero to a maximum, falls to zero, reverses its direction, attains a maximum in the new direction and again returns to zero. A complete series of these changes is called a **CYCLE**. The number of times the current goes through these changes during each second is called the **FREQUENCY** of the current. The frequency commonly used for incandescent lighting is 60 cycles per second; that is, the current goes through the above changes in value 60 times per second. A frequency of 25 cycles is also in common use, especially for running motors, although it is not so satisfactory for use with incandescent lights.

A direct current is likened to the steady flow of water through a pipe-system, while alternating current may be likened to the rapid surging back and forth of water in a pipe-system. More difficulty was experienced in utilizing these rapid changes of electricity than in developing direct-current apparatus. Consequently the use of the alternating current was retarded but is now becoming general. The advantages of alternating over direct currents are: (1) Greater simplicity in dynamos and motors, no commutators being required in some types; (2) the facility of obtaining high voltages by means of transformers for cheapening the cost of transmission; (3) the facility of transforming from one voltage to another, either higher or lower, for different purposes.” \*

Table I. Average Current Taken by Direct-Current Motors

Horse-power	Amperes on 110-volt line	Amperes on 220-volt line	Horse-power	Amperes on 110-volt line	Amperes on 220-volt line
$\frac{1}{4}$	3	1.5	25	186	93
$\frac{1}{2}$	5.4	2.7	30	222	111
1	9	4.5	35	260	130
2	17	8.5	40	296	148
3	25	12.5	50	.....	185
5	40	20	60	.....	220
$7\frac{1}{2}$	58	29	75	.....	275
10	76	38	85	.....	312
15	114	57	100	.....	366
20	150	75	.....	.....	.....

The current taken by single-phase alternating-current motors can be found by noting the current taken by a direct-current motor of the same size and voltage, and dividing this current by the power-factor of the alternating-current motor. To find the current taken by each terminal of a three-wire, three-phase alternating-current motor, divide the current taken by a single-phase alternating-current motor of the same size and voltage by 1.73.

**Example.** What current is taken by a 5-horse-power, alternating-current, 220-volt, induction-motor of 80% power-factor?

**Solution.** A 5-horse-power, direct-current, 220-volt motor takes 20 amperes. A single-phase, 5-horse-power, 220-volt motor of 80% power-factor takes  $20 / .80 = 25$  amperes.

Electric-Lighting Systems Commonly Used for Supplying the Electrical Energy to Lamps

**Direct-Current, Constant-Potential Systems.** The systems most used in America are:

(1) **TWO-WIRE SYSTEM** largely used for incandescent lighting from small plants, as for a large office-building or factory. It is usually operated at 110 volts.

(2) **THREE-WIRE SYSTEM** used in small towns for the lighting of buildings from the public mains, usually operated at 220 volts. Also in large cities with underground conduit-system. See pages 1466 to 1468.

**FIVE-WIRE and SEVEN-WIRE SYSTEMS** with high voltage have been used in Europe, but very little in America.

**Alternating-Current, Constant-Potential Systems.** There are two systems:

(1) **SINGLE-PHASE SYSTEM.** Current transmitted to building at from 1 000 to 2 000 volts and reduced to from 50 to 110 volts by a transformer. The term **PHASE** is used in connection with alternating-current systems only in the sense of **CIRCUIT**. Thus a single-phase system means an alternating-current system sending out power from one circuit only of the generator. A three-phase system has three circuits.

(2) **THREE-PHASE SYSTEM.** Three or four wires are used. This system is most used for lighting from public plants, principally because it enables both lights and motors to be operated from the public dynamo and is the most economical in wire. (See Table II.) Both of these systems are used for incandescent lighting and for power from central stations. For a comparison of a three-wire direct current with a three-phase, three-wire alternating current, see pages

668-9. An alternating current may be changed to a direct current at a substation by a rotary converter or by a mercury-arc rectifier. The latter is very generally used in garages in order to convert an alternating current into a direct current for charging storage-batteries.

### Methods of Connecting Lamps.

There are three ways of connecting lamps to the distribution-wires: (1) in series; (2) in parallel; and (3) in parallel series.

#### (1) Lamps in Series.

Lamps are said to be connected in series when they are arranged one after the other, so that the same current flows through all the lamps. The most common




Fig. 3. Five Lamps in Series on a 550-Volt Line. Each Lamp has a Voltage of 110 Volts Across It

example of this system is the lighting of electric cars and the stations on an electric-railway line. The voltage of such lines is usually 550 volts. Since an ordinary incandescent lamp requires but 110 volts, five of these are placed in series as in Fig. 3. Each lamp now has a pressure of 110 volts across it, and the set of five lamps requires 550 volts across it, and so can be placed across the railway supply-wires. When lamps are arranged in series the total resistance of the circuit is the sum of the resistances of the several parts, and the voltage required to force the current through a number of lamps in series is the sum of the voltages required for the separate lamps. Thus the voltage required to supply the proper current for four 52-volt lamps is  $4 \times 52 = 208$  volts. Arc-lamps for street-lighting are often connected in series, but incandescent lamps are very seldom connected in series except as described above or for decorative purposes or electric signs. Where lamps of low voltage, as in signs, etc., are used on 110-volt systems it is necessary to connect them in series. The underwriters do not approve connecting incandescent lamps in series. The series system requires that the same current flow through each lamp, and if one lamp burns out the circuit is broken and all of the lamps will go out, unless some provision is made for maintaining the circuit around the dead lamps.




Fig. 4. Four Lamps in Parallel. Each Lamp Has the Full-Pressure of 110 Volts Across It

(2) Lamps in Parallel. This is the common method of connecting incandescent lamps. It is illustrated in Fig. 4. With this system the pressure in each lamp is the same as in the distributing lines, and any lamp may be turned on or off without affecting the other lamps. For this system the **PRESSURE** or voltage must be kept constant, while the current or quantity of electricity flowing

in the lines will depend upon the number of lamps that are burning. With twelve 16-candle-power lamps of 110 voltage on a parallel circuit, each lamp requiring 0.51 ampere when all the lamps are burning, a current of 6.12 amperes, or 673.2\* watts, will be required. With but one lamp burning,

\* Watts being equal to amperes times voltage.

a current of only 0.51 ampere will flow. The voltage, however, must be the same for one lamp as for the twelve. For lamps in parallel, therefore, a **CONSTANT-POTENTIAL** system is required. The current for lamps in parallel may be turned on or off at the lamp, or a switch-loop may be run any distance and the contact made by a switch (S) as for the lower lamp (Fig. 4).

(3) **Lamps in Parallel Series.** This method is a combination of the other two. Parallel lines are run as in the parallel system, but two or more lamps




Fig. 5. Lamps in Parallel Series




Fig. 6. Lamps in Parallel Series

are connected in series between them as in Figs. 5 and 6. This method of connecting lamps is used principally in places where it is desired to operate lamps on a power system. Fig. 5 shows a series of five lamps operated on a 500-volt system and Fig. 6 a series of two lamps on a 220-volt system using 110-volt lamps. Any number of series may be connected across the mains, each series




Fig. 7. The Three-wire Edison System. 220 Volts Between Outside Wires; Only 110 Volts Between Either Outside Wire and Neutral Wire

being independent of the others. But in each series if one light burns out, the others in the same series will be useless, and one lamp alone cannot be used. The sum of the voltages of the lamps in series must be approximately equal to the voltage between

the mains. There are a number of special cases in which this method of connection may be used.

**The Edison Three-Wire System.** Figs. 4, 5 and 6 are examples of the two-wire system of distribution, which is the system recommended for average-sized office-buildings, apartment-houses, theaters and stores. Where power for motors is to be taken from the same plant as the lighting current, and where the power is not too great a portion of the capacity of the installation, this two-wire system may also be used. Separate mains, however, should under all circumstances be run for the motors, as the variation in load and, consequently, the current-demand on the mains would cause a very appreciable fluctuation in

middle-power of the lamps, if on the same mains with the motors. Where comparatively long lines are required and the amount of current to be supplied is




Fig. 8. Example of Three-wire System of Wiring

the THREE-WIRE SYSTEM is used. By this system two voltages or pressures can be supplied, 110 and 220 volts being those generally adopted, the 110-volt

circuit supplying the arc and incandescent lights and the 220-volt circuit the motors.

Fig. 7 shows how the wires run and connections are made.

The pressure between two outside wires is the voltage transmitted from generator, usually 220 volts for interior wiring.

The current in these two wires flows in opposite directions.

The middle wire, called the NEUTRAL WIRE, is one side of two circuits, the current from one side it tending to flow in one direction and that from the other circuit in the opposite direction; consequently the currents of the same strength, in amperes, are equal in both circuits they balance each other in the neutral wire and there will be no current flowing in this

With a current of 10 amperes flowing in one circuit and one of 6 amperes in the other circuit, the current flowing in the neutral wire will be 4 amperes.



Fig. 9. The Wiring of a Cabinet. Showing How to Divide a Three-wire System into Six Two-wire Circuits, Three Circuits to Each Leg

amperes. To obtain the greatest benefit from this system, it should always be installed so that there will be nearly the same load or number of lamps on each

side of the neutral wire. Even then there will be times when more lamps will be burning on one side than on the other, so that it is necessary to give some size to the neutral wire. The neutral wire is seldom made less than one-half the cross-section of the outer wires. For distributing mains in buildings carrying lamps only, the neutral wire should be of the SAME SIZE as the outer wires. From Table II it will be seen that the three-wire system effects a considerable saving in copper, amounting to fully 60% of the ordinary two-wire 110-volt system. As a rule, in supplying current for light and power from one plant, the main wires only are arranged on the three-wire system and the distributing wires are run




Fig. 10. Three-phase, Three-wire System, Alternating Current. Compare with Fig. 11

on the two-wire system as in Fig. 8. When using the three-wire system for lighting only, the three wires are usually run no farther within the building than to the centers of distribution, and from these centers two wires are run for each circuit, the circuits being divided as equally as possible on the two sides of the three-wire system as shown by Fig. 9. Three-wire mains are now very commonly used where the current exceeds 100 amperes. When motors are operated from the three-wire system they are usually connected only to the outside wires. Motors used on three-wire incandescent-lighting systems should be wound for 220 volts.

**Comparison of the Three-Phase and Three-Wire Edison Systems.** The wiring for the Edison three-wire direct-current system is the same as that for the three-wire, three-phase alternating-current system, the only difference being that the voltage BETWEEN ANY TWO WIRES of

a three-phase system is the same. Thus in Fig. 10 which represents a three-wire, three-phase system the voltage between the wires A and B (phase No. 1)



To Street Mains

Fig. 11. Three-wire System, Direct Current. Compare with Fig. 10

110 volts; between *B* and *C* (phase No. 2) is 110 volts; and between *A* and *C* (phase No. 3) is 110 volts. But in Fig. 11, which represents a three-phase direct-current system, in which the voltage across *A* and *B*, and *B* and *C* is 110 volts, the voltage across *A* and *C* is 220 volts or twice that across either leg.

**Table II. Relative Weight of Copper Required in Different Systems for Equal Effective Voltage**

Direct-current, ordinary two-wire system.....	1.000
Direct-current, three-wire system, all wires of same size.....	0.375
Direct-current, three-wire system, neutral, one-half size.....	0.313
Alternating-current, single-phase two-wire system.....	1.000
Three-phase three-wire.....	0.750
Three-phase four-wire.....	0.333

### Wire-Calculations

**Wire-Gauges.\*** As the diameter of wires is ordinarily designated by the number of a wire-gauge, and as there are a number of wire-gauges in common use, the knowledge of those used for copper wire is necessary. The Brown & Sharpe, B. & S., gauge (see page 1474) is almost exclusively used in America in connection with electrical work, except where the size of the wire is designated in circular mils. The sizes of wire given by this gauge range from No. 0000 (0.46 in) to No. 40 (0.0031 in), but No. 14 is the smallest size permitted for interior wiring. No. 10 wire has a diameter of about  $\frac{1}{16}$  in and its resistance per 1 000 ft is very nearly 1 ohm. For any given number of this gauge a wire three numbers lower has very nearly half the cross-section, and one three numbers lower has one-fourth the cross-section; thus a No. 13 wire has very nearly one-half the cross-section of a No. 10 wire, and a No. 7 has twice the cross-section of a No. 10, or four times that of a No. 13.

**The Circular-Mil Wire-Gauge.** This gauge was designed by the engineering department of the Edison Company especially for the designation of copper wire for electrical work, and is now in general use in this country. In practice the B. & S. gauge is commonly used for designating wires up to No. 0 or No. 00, and all wires above that size are designated by circular mils (c.m.). The size of wire required is often determined in circular mils and designated by the corresponding B. & S. gauge-number, which is readily done by means of Table III, page 1473. Copper wire is sold by the pound if bare or of the numerous weather-proof varieties, but rubber-covered wire is sold by the 1 000 ft.

The basis of the circular-mil gauge is the area of a wire  $\frac{1}{1000}$  in in diameter (1 mil = 0.001 in); consequently, 1 c.m. = 0.0000007854 sq in. As the areas of wires vary as the squares of their diameters, it follows that the sectional area of a wire 2 mils in diameter = 4 c.m., of a wire 10 mils in diameter 100 c.m., and of a wire 1 in in diameter 1 000 000 c.m.

When wires are designated by circular mils, the SECTIONAL AREA and not the diameter is generally given, c.m. always referring to sectional area. The diameter of a wire in MILS OR IN THOUSANDTHS OF AN INCH = square root of its area in CIRCULAR MILS.

Thus the diameter of a wire of 3 600 c.m. = 60 mils, or 0.060 in.

The diameter of a wire 14 400 c.m. = 120 mils = 0.12 in.

The area of a wire 0.162 in in diameter, or 162 mils, =  $162^2 = 26\,244$  c.m.

For other gauges, see pages 401, 402, 403, 1473, 1509, 1510, 1512 and 1600.

To reduce circular mils to square inches. Multiply by 7 854 and point off ten places of decimals. Thus, 5 000 c.m. =  $7\ 854 \times 5\ 000 = 0.0039270000$  sq in.

To obtain the sectional area of a square or rectangular bar in circular mils. Multiply together its dimensions in mils and the product by 1.273.

**Example.** What is the sectional area in circular mils of a bar  $\frac{1}{8}$  in  $\times$   $\frac{1}{4}$  in?

**Solution.**  $\frac{1}{8}$  in = 0.125 in = 125 mils,  $\frac{1}{4}$  in = 0.250 in = 250 mils;  $125 \times 250 \times 1.273 = 39781.25$  c.m.

The weight of bare copper wire per 1 000 ft = c.m.  $\times$  0.003027 lb. Thus the weight of 1 000 ft of copper wire having a sectional area of 2 000 c.m. =  $0.003027 \times 2\ 000 = 6.054$  lb. Table IV, page 1474, gives the dimensions and weights of bare copper wire from No. 18 to No. 0000 B. & S.

**Carrying Capacity of Copper Wire.** The safe carrying capacity of copper wire for interior wiring is practically fixed by the underwriters, and if the capacity-limits given in the table published by them are exceeded it would tend to destroy the right to recover insurance in case of fire. The safe carrying capacity of rubber-covered and weather-proof wires given by the National Board of Fire Underwriters is shown by Table III, page 1473. The lower ampere-capacity assigned to rubber-covered wires is due to the fact that the rubber insulation would deteriorate in quality under a temperature as high as that allowed for weather-proof wire; that is, the rubber covering makes necessary a lower rate of heat-development than is required for safety from fire. No wire smaller than No. 14 may be used under insurance-rules, except that No. 16 may be used for flexible cord and No. 18 for fixture-wiring. Nos. 13, 11, 9 and 7 are not usually carried in stock and can only be purchased on special order. Rubber-covered wire must be used for service-wires, for molding-work and in damp places; it is more expensive than weather-proof wire. The latter wire may be used in open or exposed places and for outside line-wires.

**Drop of Potential.** When an electric current flows through a wire of any appreciable length the pressure becomes reduced by the resistance of the wire, so that if the current enters the wire at, say, 110 volts, at the extreme end of the circuit it will be somewhat less, depending upon the length and sectional area of the wire. This loss in voltage is called **DROP OF POTENTIAL**. Drop of potential corresponds to **LOSS OF HEAD** in hydraulics. As a drop of voltage materially below that for which the lamps are designed means diminished candle-power, it is very important that the wires be proportioned so that the drop shall not be sufficient to affect the illumination. The table for safe carrying capacity for wires has nothing to do with the drop of potential which these currents will cause in the wires. Accordingly, mains and distributing wires may be capable of carrying the number of amperes in accordance with Table III, page 1473, and yet cause a drop of potential of such magnitude that the most distant lamps will burn only at a dull red. It is therefore necessary, in computing the size of these mains and distributing wires, to consider two things:

(1) That the wire is large enough, according to the underwriters' table, to carry the current safely.

(2) That the potential drop from the generator to the farthest lamp shall not be excessive. An excessive drop in voltage also means increased cost for light and not enough copper in the wires.

Where the current is supplied from the public mains it is usual to specify a 2% drop, but where the current is produced cheaply, as by a dynamo on the premises, a 3% or 5% drop may be allowed. Not more than a 5% drop on short distances should be permitted, even where very cheap work is desired. The



drop in volts (not in percentage) = current in line  $\times$  resistance of line, or drop in volts = amperes  $\times$  ohms.

**Example.** What will be the drop in a circuit of No. 14 copper wire 280 ft long, supplying nine lamps, requiring 4.5 amperes?

**Solution.** From Table IV, page 1474, it is found that the resistance of No. 14 wire is 2.527 ohms per 1 000 ft; hence for 280 ft it will be  $2.527 \times 0.280 = .7075$  ohm, and drop in volts =  $4.5 \times 0.7075 = 3.1837$  volts. The voltage for this current (0.5 ampere per lamp) will be about 110; consequently the percentage of drop =  $3.1837/110 = 2.91\%$ , nearly. A 2% drop on a pressure of 10 volts is 2.2 volts.

**Load-Center.** The meaning of this term may best be illustrated by an example. Let Fig. 12 represent a circuit carrying six lamps, the first lamp being




Fig. 12. The Point D is the Load-center

ft from the cut-out, or source of supply. The whole of the current must be transmitted through this 40 ft, but from that point it will gradually fall off, and average current will only extend to the point CD, halfway between the remote lamps. Or, in other words, the load-center is analogous to the center of gravity of the lamps on the circuit. The load-center determines the length of line in the rules for finding the necessary size of wire.

**Distributing Centers** are the points in a building where the cut-out cabinets are located and the branch circuits taken off.

**Calculations for Size of Wire for Incandescent Lighting.** The sizes of wire for interior lighting are or should be always determined on a basis of a fixed drop of potential, usually 2 volts on the distributing circuit and from 2 to 3 volts on the feeders or mains.\* The size of wire may be determined either in terms of its sectional area in circular mils or in terms of its resistance in ohms per 1 000 ft. Knowing the sectional area in circular mils, one may find the corresponding gauge-number from Table III, page 1473, or if the resistance in ohms per 1 000 ft is known, the corresponding gauge-number may be found in Table IV, page 1474.

Many municipal lighting companies require that there shall be no more than 1% drop in the wiring for interior lighting.

The formula for circular mils is as follows:

$$\text{Circular mils} = \frac{10.4 \times 2 d \times N \times c}{v} \quad (1)$$

The formula for resistance per 1 000 ft of wire is

$$\text{Resistance} = \frac{1\ 000\ v}{N \times c \times 2 d} \quad (2)$$

In both these formulas  $d$  = distance in feet, one way, from cut-out to load-center (see page 1471) for distributing wires, or from entrance cut-out or source of current to distributing center for main lines or feeders.  $c$  = current in amperes PER LAMP.  $N$  = number of lamps supplied.  $v$  = drop in volts. Both formulas apply to any voltage and to any two-wire system. To use these formulas for the ordinary three-wire system, let  $N$  = maximum number of lamps on ONE SIDE of the neutral wire and DOUBLE THE DROP IN VOLTS. The neutral or middle wire should be of the same size as the outside wires.

**Example.** The distance from the cut-out to load-center of a circuit carrying sixteen 40-watt, 110-volt lamps is 50 ft. What size of wire should be used for a drop of 2 volts?

**Solution.**  $d = 50$ ;  $N = 16$ ;  $c = 40/110 = 0.364$ ; and  $v = 2$ .

By Formula (1),

$$\text{Circular mils} = \frac{10.4 \times 100 \times 16 \times 0.364}{2} = 3\ 030$$

Table III, page 1473, shows that the next larger size of wire is 4 107 c.m., equivalent to a No. 14 wire.

By Formula (2),

$$\text{Resistance per 1 000 ft} = \frac{1\ 000 \times 2}{12 \times 0.364 \times 100} = 4.59$$

which we see from Table IV, page 1474, is about the resistance of a No. 16 wire; but as No. 14 is the smallest wire permitted that size must be used.

**Example.** The distance from the entrance cut-out, where the wires enter the building, to the main distributing center of a building is 100 ft. The total number of 16-candle-power, 110-volt carbon-lamps supplied is ninety. What is the size of the mains that should be used on the two-wire system with a drop of 2 volts? (A 16-candle-power 110-volt carbon lamp takes approximately 0.51 ampere.)

**Solution.**  $d = 100$ ;  $N = 90$ ;  $c = 0.51$ ;  $v = 2$

By Formula (1),

$$\text{Circular mils} = \frac{10.4 \times 200 \times 90 \times 0.51}{2} = 47\ 800$$

In Table III it is seen that No. 3 wire must be used. If a drop of 3 volts is allowed the sectional area required will be 33 048 c.m., which requires a No. 3 wire. The weight per 1 000 ft of No. 3 weather-proof wire (Table IV) is 200 lb and of No. 5 wire 125 lb; consequently, the SAVING IN WEIGHT OF WIRE by using a drop of 3 volts instead of 2 is 75 lb, or 37½% of 200, and as wire is sold by the pound, the SAVING IN COST with a 3% drop ranges from 30 to 40% of a 2% drop.

**Example.** With the same conditions as given in the preceding example what is the size of the wire that will be required for the ordinary three-wire system with 2% drop?

Table III. Carrying Capacity of Wires and Cables  
FOR INTERIOR CONDUCTORS, ALL VOLTAGES  
From the National Electrical Code

No. of wire, B. & S. gauge *	Circular mils	Capacity in amperes	
		Rubber- covered	Weather- proof
18	1 624	3	5
16	2 583	6	10
14	4 107	15	20
12	6 530	20	25
10	10 380	25	30
8	16 510	35	50
6	26 250	50	70
5	33 100	55	80
4	41 740	70	90
3	52 630	80	100
2	66 370	90	125
1	83 690	100	150
0	105 500	125	200
00	133 100	150	225
000	167 800	175	275
0000	211 600	225	325
Cables	200 000	200	300
"	300 000	275	400
"	400 000	325	500
"	500 000	400	600
"	600 000	450	680
"	700 000	500	760
"	800 000	550	840
"	900 000	600	920
"	1 000 000	650	1 000
"	1 100 000	690	1 080
"	1 200 000	730	1 150
"	1 300 000	770	1 220
"	1 400 000	810	1 290
"	1 500 000	850	1 360
"	1 600 000	890	1 430
"	1 700 000	930	1 490
"	1 800 000	970	1 550
"	1 900 000	1 010	1 610
"	2 000 000	1 050	1 670

A current of one ampere will supply two 16-candle-power carbon lamps.

**Solution.** In this case we use one-half of  $N$ , or 45, and  $2v$  instead of  $v$ ; then

Circular mils =  $\frac{10.4 \times 200 \times 45 \times 0.51}{4} = 11\,920$

just ONE-FOURTH the section required for the two-wire system. The size wire required is No. 8; a No. 9 would answer if it could be had. Comparing weight of wire required with the two-wire system gives two No. 3 wires weighing 400 lb per 1 000 ft, and with the three-wire system three No. 8 wires weighing 207 lb; hence, the saving in cost is nearly 50% and if No. 9 wire were obtainable the saving would be 55%. With a drop of 3% (3.3 volts) the cir-

r mils required for the three-wire system =  $\frac{10.4 \times 200 \times 45 \times 0.51}{6.6} = 7\,230$ ,

\* For other gauges, see pages 401, 402, 403, 1469, 1509, 1510, 1512, and 1600.

requiring No. 10 wires. The current in amperes in the two-wire system =  $N \times c = 45.9$ , and in the three-wire system  $\frac{1}{2} N \times c = 22.95$ . Referring to Table III it is seen that the smallest size of weather-proof wire permitted for 45.9 amperes is No. 8; consequently, No. 8 wire could be used with the two-wire system and comply with the underwriters' rules, but the drop in potential would be  $45.9 \times 0.2 \times 0.6285$  (amperes  $\times$  resistance of line) = 5.77 volts; or over 5%.

For the three-wire system, the current being 23 amperes, the smallest weather-proof wire permitted by Table III is No. 12, which would give a drop of 7.4 volts, or 3.8 volts on each side, or about 3½% of the lamp-voltage. Except on very short lines a 2% drop will always demand larger wires than required by the underwriters, and this is also usually true of a 3% drop.

Table IV. Dimensions, Weights and Resistances of Copper Wire

Gauge-number, B. & S.	Diameter in mils	Area in cir. mils	Area in sq in	Weight in lb per 1 000 ft		
				Bare wire	Weather-proof* wire	Ohms per 1 000 ft at 20° C. or 68° F.
0000	460	211 600	0.166190	640.73	800	0.04893
000	410	167 800	0.131790	508.12	666	0.06170
00	365	133 100	0.104520	402.97	500	0.07780
0	325	105 500	0.082887	319.74	363	0.09811
1	289	83 690	0.065732	253.43	313	0.1237
2	258	66 370	0.052128	200.98	250	0.1560
3	229	52 630	0.041339	159.38	200	0.1967
4	204	41 740	0.032784	126.40	144	0.2480
5	182	33 100	0.025999	100.23	125	0.3128
6	162	26 250	0.020618	79.49	105	0.3944
7	144	20 820	0.016351	63.03	87	0.4973
8	128	16 510	0.012967	49.99	69	0.6271
9	114	13 090	0.010283	39.65	.....	0.7908
10	102	10 380	0.008155	31.44	50	0.9972
11	91	8 234	0.006466	24.93	.....	1.257
12	81	6 530	0.005129	19.77	31	1.586
13	72	5 178	0.004067	15.68	.....	1.999
14	64	4 107	0.003225	12.44	22	2.527
15	57	3 257	0.002558	9.86	.....	3.179
16	51	2 583	0.002028	7.82	14	4.009
17	45	2 048	0.001608	6.20	.....	5.055
18	40	1 624	0.001275	4.92	11	6.374

\* Approximate weight of weather-proof line-wire for outdoor work is 10% less than here given.

To find the smallest size of wire that will comply with the underwriters' rules it is only necessary to compute the total current in amperes, and from Table III select the wire having a capacity equal to or next above the required number of amperes. Table VI shows at a glance the maximum number of 16-candle-power 110-volt carbon lamps permitted by the National Code.

Formulas (1) and (2), page 1472, may also be used for MOTOR-WIRING, if the required current in amperes is known, by substituting the given number of amperes for  $N \times c$ .

**Table V. Maximum Length of Line for Given Number of Lamps that can be Used with a Two-Per-Cent Drop. Two-Wire System**

Based on  $\frac{1}{2}$  ampere per carbon-lamp. One 32-candle-power carbon-lamp = two 16-candle-power carbon-lamps. Four 40-watt tungsten-lamps = three 16-candle-power carbon-lamps

No. of wire, B. & S. gauge	Number of 16-candle-power, 110-volt carbon-lamps								
	4	6	8	10	11	12	16	20	24
	Maximum length of line, one side, in feet								
14	209	139	104	83	76	70	52	42	35
12	.....	221	166	133	120	110	83	66	55
10	.....	.....	264	211	192	176	132	105	88
8	.....	.....	.....	326	297	272	204	163	136
6	.....	.....	.....	.....	.....	440	334	267	220
	Number of 16-candle-power, 110-volt lamps								
	30	36	40	50	60	70	80	90	100
	Maximum length of line, one side, in feet								
12	44	37	.....	.....	.....	.....	.....	.....	.....
10	70	58	52	42	.....	.....	.....	.....	.....
8	109	91	81	65	54	37	40	.....	.....
6	178	148	133	107	89	76	66	59	53
5	225	187	168	135	112	96	84	75	67
4	.....	236	212	170	141	121	106	94	85
3	.....	.....	268	214	180	153	134	119	107
2	.....	.....	.....	270	225	193	169	150	135
1	.....	.....	.....	.....	285	243	213	190	170

For three-wire mains with 220 volts between outer wires and same number of lamps on each side, length of wire may be increased four times.

**Table VI. Maximum Carrying Capacity of Wires in Terms of 16-Candle-Power 110-Volt Lamps, However Short the Wires May Be**

Based on  $\frac{1}{2}$  ampere per lamp

Four 40-watt tungsten-lamps = three 16-candle-power carbon-lamps

No. of wire, B. & S. gauge	Number of lamps		No. of wire, B. & S. gauge	Number of lamps	
	Rubber-covered	Weather-proof		Rubber-covered	Weather-proof
14	24	32	4	130	184
12	34	46	3	152	220
10	48	64	2	180	262
8	66	92	1	214	312
6	92	130	0	254	370

**Example.** What should be the size of the wires to be run to a motor that requires 30 amperes at 220 volts and is situated 200 ft from the distributing pole, the drop in volts not to exceed 2%?

**Solution.** Using Formula (1), and substituting 30 for  $N \times c$ , we have

$$\text{Circular mils} = \frac{10.4 \times 400 \times 30}{4 \times 4} = 28,400$$

which requires a No. 5 wire. Either the watts or the current in amperes is

stamped on every motor. If watts are given, the current in amperes may be found by dividing the watts by the voltage. If kilowatts are given, multiply by 1,000 and then divide by the voltage.

**Wiring-Tables.** Several forms of wiring-tables which are very useful to electricians are published in various books on electricity. For ordinary interior wiring for 110-volt, 16-candle-power carbon-lamps, Table V, computed by Mr. Kidder, will show at a glance the number of wire, B. & S. gauge, required to supply the given number of lamps by first ascertaining the length of line (one way) through which the average current flows, as explained under **LOAD-CENTER**. (See page 1471 and Fig. 12.)

**Simple Example of Wiring.** To show the method of wiring an ordinary building for incandescent lighting we will take a two-story building having a floor-plan as shown in Fig. 13. Most of the light-outlets are on the ceiling and are indicated by a small circle. The outlet marked E is a special outlet for heating, etc., and must be described




Fig. 13. Wiring-diagram for Second Story. For Meaning of Symbols, see pages 1484-5.

in the specifications. Let us assume it is to take 320 watts. This is equivalent to adding eight 40-watt lamps to this circuit. F and G are wall-outlets. The meanings of the symbols used are explained on pages 1484-5. The numbers


and 2 inside the circles denote the number of 16-candle-power carbon-lamps at the outlet. The same number of 25-watt or 40-watt tungsten-lamps may also be used without overloading the circuits. See pages 1398 and 1399 Standard-Wiring Symbols. The current to be obtained from the wires of a public lighting company, which carry a current at 220 volts between the side wires, and at 110 volts between either outside wire and the neutral wire. The feed wires for the building should enter through the alley-wall at about the level of the second story and should drop in the partition just inside the wall to the main fuse-block and switch, which should be in a small cabinet and the meter (*M*). The distribution-cabinet should be located near the center of the building, say at *DC*, and there should be a cabinet on each story. From this cabinet we will run four circuits for each story, which are indicated by the letters *B*, *C* and *D*. Circuit *A* shows the wires run for a switch on the wall near the door of each of four rooms to control the lights in those rooms. All of the lights on circuit *C* should be controlled by keys in the lamp-sockets. The lights on circuits *B* and *D* are not switched, except the outlet at head of stairs, which is controlled by a snap or push-button switch at *S*. For a first-class job all of the four circuits would be controlled by knife-switches in the cabinet, as shown in Fig. 14, but this is not absolutely necessary.

F.F. FUSE-PLUGS

K.S. KNIFE-SWITCHES

Fig. 14. Cabinet-wiring for Knife-switch Control

**Size of Wires.** The load-center of circuits *A*, *C*, and *D* would be at about points marked *X* (Fig 13). For circuit *B* take one-half the distance *ab* and add to it the distance from *c* to the cabinet. In figuring the length of wire, 6 ft should be added for the drop from ceiling to the cabinet. Let us assume that tungsten-lamps are to be used. In computing the current taken by a lamp it is always assumed that no smaller than a 40-watt tungsten is used.

Drop-lights, marked  would probably be 25-watt lamps, but must be rated as 40-watt, according to the underwriters' rules. The number of lamps and length of wire for each circuit are as follows:

Circuit *A*, 8 lights, 41 ft one way to load-center.

Circuit *B*, 11 lights, 52 ft one way to load-center.

Circuit *C*, 16 lights, 37 ft one way to load-center.

Circuit *D*, 12 lights, 59 ft one way to load-center.

Total number of lamps, 47.

From Table V we see that the maximum length of line one way for No. 14 carrying twelve carbon or sixteen 40-watt lamps is 70 ft. Consequently, if the lamp-circuits can be No. 14 wire, which is the smallest size permitted.

**Feed-Wires.** These should be run on the three-wire system. Allowing for  $47$  or  $94$  lamps in first and second stories and eight in basement, the feed-wires must be capable of supplying  $102$  lamps. Each  $40$ -watt lamp would take  $40/110 = 0.364$  ampere. The distance from outside the building to distribution-cabinet is about  $72$  ft, allowing for three drops. Using Formula (1), and assuming that there will be fifty-one lamps on each side of the three-wire system, and doubling the drop in volts, gives

$$\text{Circular mils} = \frac{10.4 \times 144 \times 0.364 \times 51}{4} = 6\,960 \text{ c.m.}$$

which calls for No. 11 wire; but as this size is not carried in stock we must use No. 10. From the second story to the third No. 12 wires could be used. For almost all buildings lighted from a central station the lamp-circuits will not usually require a wire larger than No. 14, so that about the only wires which the architect needs to look after are the wires which run to the distribution-cabinets.

**Switches.** A switch is a device for opening or closing a circuit at will either at the fixture or at any other point. In the better class of buildings the majority, if not all, of the ceiling-lights are controlled by switches placed at a convenient place on a side wall. Lights may be controlled at any distance from the fixture by running a switch-loop. For controlling either a single lamp or fixture, or any number of lamps, a switch-loop is run as shown on circuits A and C, as in Fig. 13. As shown also in Fig. 4, one side of the loop must be connected with one of the distributing




Fig. 15. The Lamp May Be Turned Off or On From Any of the Five Points, A, B, C, D, or E




Fig. 16. The Lamps May Be Turned Off or On From Either the First or Second Story

wires and the other side to the lamp. When a number of lamps are to be controlled by one switch, as in the case of hall-lights, and the lamps in large rooms, such as churches, theaters, concert-halls, etc., a separate circuit is usually run for those lamps, and a switch anywhere in one of the distributing lines will turn on or off all of the lights on that line. As the underwriters do not permit more than twelve 16-candle-power carbon or sixteen 40-watt tungsten-lamps on one circuit, not more than these numbers of lamps can be controlled by one switch, except where the switch is placed on the mains. It is also practicable to control one lamp from two or three places. Thus by a duplex or three-point switch and proper wiring, a lamp may be lighted or turned off from either the first or second story at will. By means of two three-point switches and one four-point switch a first-story hall-lamp may be



controlled at will from either the first, second or third stories. Fig. 15 shows the method of control from any number of points, since any number of 4-point snap-switches, such as *B*, *C* and *D*, can be inserted between the 3-point switches *A* and *E* if more points of control are needed. Fig. 16 shows one method of wiring for controlling a hall-light from first and second stories by means of two 3-point switches. With the switches in the position shown the circuit is broken, as there is no connection between the lamps and line *B*. By turning either switch a connection is made with line *B* and the current will flow.

**Kinds of Switches.** For controlling lamps from one point three kinds of switches are used, namely, SNAP-SWITCHES, FLUSH OR PUSH-BUTTON SWITCHES and KNIFE-SWITCHES. When less than eight lamps are controlled by the switch, flush or push-button switch is commonly used where a neat appearance is desirable, and in places where this is of no importance, a snap-switch is used, as it is the cheaper. Where a circuit of twelve or more lamps is controlled by a switch, a double-pole (d.p.) knife-switch (Fig. 17) is commonly used, being generally placed in a cabinet. Knife-switches should always be used on main wires. Snap and push-button switches are made both single and double pole. A SINGLE POLE switch opens only one side of the circuit and a DOUBLE-POLE switch both sides. A double-pole knife-switch necessarily opens both sides.

Fig. 17. Common Knife-switch

A switch used on a three-wire system must have three poles. Double-pole snap and push button switches are seldom used for less than twelve lamps. DUPLEX SWITCHES, sometimes called THREE-MOUNT SWITCHES, are usually of the snap or of the push-button type.

**Conduit-Systems.** As weather-proof or rubber-covered wire cannot be run in brick walls or floors of brick, terra-cotta, or concrete without some protection other than the covering of the wires, it is necessary in such places to run the wires in tubes or conduits, and in fire-proof buildings all of the lighting-wires are generally run in a system of conduits.

**Kinds of Conduits.** There are two kinds of interior conduits now in common use

(1) **Lined Mild-Steel Pipe.** The lining consists of a thin coat of enamel which must be impervious to water, sulphuric acid, acetic acid, hydrochloric acid and carbonate-of-soda solutions. For regular conduit systems only mild-steel piping of the same thickness as ordinary gas-piping is approved by the underwriters. The conduit must be continuous from outlet to outlet or junction-boxes or cabinets and must properly enter and be secured to all fittings, and the wire system must be mechanically secured in position. Mild-steel pipe may be galvanized, coated, or enameled on the outside, but it must be enameled on the inside as stated above. Rigid conduit, WHETHER LINED OR UNLINED, are installed in the same manner as a good job of gas-fitting, except that for conduits of pipe may be bent to a curve and no elbow can be used having less than 18-in radius for the inner edge. Wherever branches are taken off, junction-boxes must be provided and every outlet must have an approved outlet-box or fitting. The wire drawn into conduits must be of at least No. 14 size, rubber-covered and with double braid. All conduit-systems must be GROUNDED by connecting the steel pipe by a conductor to the gas or water system.

(2) **Flexible Armored Conduit.** This is made of metal ribbon wound spirally, is generally used in wiring old houses because it is easier to install. **CIRCULAR LOOM** is flexible woven tubing treated with insulating material that makes it hold its shape. This may be used in dry places and for outlets through plastering if it extends back to the nearest porcelain knob holding the wire which the conduit covers.

**National Electrical Code.** The National Board of Fire Underwriters, in conjunction with committees from the American Institute of Architects, and from the national associations of electrical, mechanical and railway engineers, have prepared a code of rules and requirements for the installation of electrical lighting which is the generally recognized standard and with which all interior wiring must comply if it is desired to obtain insurance on the building. This code has also been made a part of the ordinances of most of the larger cities. It is revised every two years, in the odd-numbered years. The National Board of Underwriters also publishes, semi-annually, a **SUPPLEMENT** to the National Electrical Code which contains a list of all articles that have been examined and approved for use in connection with the code, together with the names of the manufacturers. Articles not included in this list will not be passed by the inspectors. Copies of the code and supplement can be obtained from the nearest Underwriters' Inspection Bureau, or by writing to the Underwriters' Laboratories, 382 Ohio Street, Chicago, Ill. The following requirements apply to almost every installation, and every architect should be conversant with them.

#### **Extracts from the National Electrical Code\***

(1) All wire for concealed work must be of the best approved rubber-covered brands, as shown in List of Fittings. No wire smaller than No. 14 B. & S. gauge to be used. All wire run in conduits must have double-braid covering.

(2) Where wires are concealed and run parallel to joists they must be supported on porcelain knobs which hold the wires at least 1 in from woodwork or surface wired over. Knobs must be **SECURELY FASTENED** and **MUST BE PLACED EVERY 4½ FT.** Where wires are run through joists they must be bushed with porcelain tubes the entire width of joists. All wires must be drawn tight, so as to have all slack removed.

(3) In concealed work all wires **MUST BE SEPARATED FROM EACH OTHER BY AT LEAST 5 IN.** Where wires run down partitions, especially partitions formed by 2 by 4-in studs, the wires must be so supported as to run in the middle of partition. If more than two wires are run down partition between studs, they must be separated by at least 5 in.

(4) Where wires pass through floors they must be protected from the floor up to a point 5 ft above the floor with conduit or with boxing. There must always be a space of 1 in between the wires and the boxing.

(5) All joints must be securely soldered and taped. A splice to be approved must be both mechanically and electrically secure without solder, but must be soldered unless made with some form of **APPROVED** splicing-device. Joints to be properly taped require, where rubber-covered wire is used, first to be taped with rubber tape and then with friction-tape. The insulation of a joint must equal that on the conductors.

(6) Where wires enter the building they must be provided with drip-loops.

(7) There must be a **MAIN CUT-OUT AND SWITCH** installed in an easily accessible place, as near as possible to the point where the wires enter the building.

\* The numbers here given do not correspond with those in the code, and several of the rules are much abridged. They are intended to give the substance, rather than the exact language.

This will require that cut-out and switch be placed where there is no need of a 12-ft ladder to reach them. (See Fig. 18.)

(8) Every lighting-circuit of 660 watts must be protected by a cut-out. This will limit the number to twelve 16-candle-power or sixteen 40-watt lights on a two-wire, 110-volt circuit, and to thirty-two 40-watt or twenty 16-candle-power lights on a three-wire, 220-volt circuit. By special permission, where No. 14 wire is carried directly to keyless sockets, and where the location of the sockets is such as to render unlikely the attachment of flexible cords thereto, the circuits may be so arranged that not more than 1320 watts (or 32 sockets) may be dependent upon the final cut-out. Sockets are to be considered as requiring not less than 40 watts each.

(9) All cut-outs must be placed in an ASBESTOS-LINED CABINET. The asbestos must be at least  $\frac{1}{8}$  in in thickness and securely held in place by shellac and tacks. Lumber of which cabinet is made must be at least  $\frac{3}{4}$  in in thickness. Cabinet must be furnished with snug-fitting door; door to be hung by strong hinges and to be furnished with a suitable catch.

(10) Cut-outs to be approved must be of the plug or of the cartridge-type.

(11) Enclosed arc-lamps and incandescent lamps must not be placed on same circuit. Arcs must be on separate circuits by themselves. Each arc-light must be protected by an approved cut-out. The cut-outs are to be placed in an asbestos-lined cabinet.

(12) The practice of using fused rosettes will not be approved, except in mills.

(13) Where wires run down the side wall they must be protected from mechanical injury.

(14) All outlets must be made to conform to Rule 24, National Electrical Code.

(15) Fans in series will not be approved.

(16) Runs of lamp-cord will not be approved. Lamp-cord is designed to be used for drops only. Ordinary insulated wire must be run to place desired.

(17) Electric heaters must be installed in accordance with Rule 25 a-f, National Electrical Code.

### General Suggestions for Electric Work \*

**General Principles and Recommendations.** In all electric-work conductors, however well insulated, should always be treated as bare, to the end that under no conditions, existing or likely to exist, a grounding or short circuit occur, and so that leakage from conductor to conductor, or between conductor and ground, may be reduced to the minimum. In wiring special attention must be paid to the mechanical execution of the work. Careful and correct running, connecting, soldering, taping of conductors, and securing and attaching of fittings, are specially conducive to security and efficiency, and will be strongly insisted on. In laying out an installation, except for constant-current systems, the work should, if possible, be started from a center of distribution, and the switches and cut-outs, controlling and connected with the several branches, be grouped together in a safe and easily accessible place, where they can be readily got at for attention or repairs. The load should be divided as




Fig. 18. Main Switch, Fuse-block and Meter Located Near the Point of Entrance of the Service-wires

evenly as possible among the branches, and all complicated and unnecessary wiring avoided. The use of wireways for rendering concealed wiring permanently accessible is most heartily indorsed and recommended; and this method of accessible concealed construction is advised for general use. Architects are urged, when drawing plans and specifications, to make provision for the channeling and pocketing of buildings for electric-light or power-wires, and in specifications for electric gas-lighting to require a two-wire circuit, whether the building is to be wired for electric lighting or not, so that no part of the gas-fixtures or gas-piping be allowed to be used for the gas-lighting circuit. Fig. 18 shows a common arrangement of main cut-out, switch and meter, to comply with Rule 7, page 1480. The main cut-out and switch should be as near as possible to the outside wall, but the meter may be at some distance from the switch if desirable for any reason.

### Specifications for Interior Wiring \*

**Specifications for Interior Wiring** should provide:

(1) That the wiring shall be installed in accordance with the latest rules and requirements of the National Board of Fire Underwriters, the local ordinances, and the rules of the local electric light company, where current is to be taken from the public mains.

(2) No electrical device or material of any kind to be used that is not approved by the Underwriters' National Electric Association, and all articles must have the name or trade-mark of the manufacturer and the rating in volts and amperes or other proper units marked where they may readily be observed after the device is installed.

Requirements (1) and (2) are sufficient to insure a SAFE installation.

(3) Contractor must obtain a satisfactory certificate of inspection from the city inspector or from the inspector of the local board of fire-underwriters.

(4) If the wires are to run in a conduit system it should be so specified. When a conduit system is used, THE WIRES SHOULD NOT BE DRAWN IN until all mechanical work as far as possible is completed. It is best to wait until after the plastering is dry. All conduit systems must be GROUNDED.

(5) Size of Wires. The best method is to specify the size of all wires, no wire to be less than No. 14 B. & S. gauge; but if the architect does not care to do this, the following clause is sufficient, provided he can have confidence that the contractor will comply with it: "All wires must be of such size that the drop in potential at farthest light-outlet shall not exceed 2% under maximum load."

(6) Cut-out cabinets and where they are to be placed; also location of main-line cut-out and fuse. For buildings containing not more than forty lights, one distributing point is generally sufficient, although in large houses it is often convenient to have a cut-out cabinet in each story.

(7) Number and kind of switches. All outlets should be marked on the plans, and the number of lights indicated by figures 1, 2, 3, 4, etc., as in Fig. 13. See pages 1484 and 1485 for standard symbols. The location of all switches for controlling lights should also be indicated on the plans.

**Approximate Cost of Wiring for Incandescent Lighting.** Approximate estimates of the cost of wiring buildings for electric lighting are usually based on the number of outlets (not lamps). The actual cost will depend upon the number of pounds of wire required, the kind and number of switches, character of cut-out cabinets, etc., and the time required to do the work, so that a close

\* Wiring specifications for buildings having their own generating plant should be prepared by an expert.

estimate cannot be made without plans and specifications. Again, wages and prices of material vary to a considerable extent in different parts of the country, so that an estimate that would be about right for one locality would not suffice for another. The following figures,\* however, will enable anyone to form an approximate idea of what any proposed wiring-job will cost.

Count cost of labor as not more than one-third the cost of the installation.

For knob-and-tube work in new houses of less than seventeen outlets or twenty-five lamps, with no switches except main switch and a rough cut-out box lined with asbestos, allow \$1.50 per outlet.

For same class of work, from 25 to 100 lamps, allow \$1.75 to \$2.00 per outlet.

The extra labor involved in wiring old buildings will add from 30 to 50% to the above figures.

For each switch-loop with a single-pole snap-switch, add from \$1.50 to \$1.75.

For each switch-loop with single-pole push-button switch, add from \$2.25 to \$2.50.

For each lamp controlled by duplex or three-point switches, add from \$5 to \$6.

For each hardwood cut-out cabinet with door and lock, add from \$7 up according to number of circuits and finish.

Iron cut-out cabinets cost from \$8.50 up.

Ordinary exposed wiring, as in factories, can usually be run for from \$1.00 to \$1.75 per drop, including rosettes, cord and sockets, the cost depending very largely upon how closely the drops are spaced.

Small installations with iron-armored conduit will probably cost from \$5 to \$6 per outlet. Large installations will cost somewhat less.

A private lighting-plant of 200 lamps, wired on the concealed knob-and-tube system, will cost from \$1 250 to \$1 500, and a similar plant with 600 lamps will cost from \$2 500 to \$3 000. These prices include engine, dynamo-switchboard, etc., complete, and wiring, but no switches for controlling lamps.

The iron-armored conduit-system will add about \$2.75 per outlet.

None of the above estimates include the cost of fixtures except in the case of exposed wiring.




























Drop-cord and sockets cost about 90 cts per lamp. Single-lamp fixtures may be purchased from \$1.25 upwards; double-lamp fixtures from \$2 upwards. Combination-fixtures cost about 25% more than straight electric fixtures.

The price of rubber-covered wire varies from \$8 to \$60 per 1 000 ft according to size, and of weather-proof wire from 16 cts to 25 cts per pound.

\* These are pre-war prices and the data are retained for purposes of comparison of relative values.

# Standard Wiring-Symbols Adopted by the National Contractors' Association and the American Institute of Architects

Copyrighted

	Ceiling-outlet; electric only. Numeral in center indicates number of standard 16-c.p. incandescent lamps.*	
	Ceiling-outlet; combination. $\frac{4}{2}$ indicates 4-16c.p. standard incandescent lamps and 2 gas-burners. If gas only.	
	Bracket-outlet; electric only. Numeral in center indicates number of standard 16-c.p. incandescent lamps.	
	Bracket-outlet; combination. $\frac{4}{2}$ indicates 4-16 c.p. standard incandescent lamps and 2 gas-burners. If gas only.	
	Wall or baseboard receptacle-outlet. Numeral in center indicates number of standard 16-c.p. incandescent lamps.	
	Floor-outlet. Numeral in center indicates number of Standard 16-c.p. incandescent lamps.	
	Outlet for outdoor standard or pedestal, electric only. Numeral indicates number of standard 16-c.p. incandescent lamps.	
	Outlet for outdoor standard or pedestal; combination. $\frac{6}{6}$ indicates 6-16 c.p. standard incandescent lamps; 6 gas-burners.	
	Drop-cord outlet.	
	One-lamp outlet, for lamp-receptacle.	
	Arc-lamp outlet.	
	Special outlet for lighting, heating and power-current, as described in specifications.	
	Ceiling-fan outlet.	
	S. P. switch-outlet.	<div> Show as many symbols as there are switches. Or in case of a very large group of switches, indicate number of switches by a Roman numeral, thus; S' XII, meaning 12 single-pole switches. </div>
	D.P. switch-outlets.	
	3-way switch-outlet.	
	4-way switch-outlet.	
	Automatic door switch-outlet.	
	Electrolier switch-outlet.	<div> Describe type of switch in specifications, that is, flush or surface, push-button or snap. </div>
	Meter-outlet.	
	Distribution-panel.	
	Junction or pull-box.	
	Motor-outlet. Numeral in center indicates horse-power.	
	Motor-control outlet.	
	Transformer.	

\* If tungsten-lamps are used instead of carbon-lamps, the figure in the circle may stand for the number of 25-watt tungsten-lamps, a 25-watt tungsten-lamp being the nearest in candle-power to a 16-candle-power carbon-lamp though consuming less than one-half the power. Since tungsten-lamps average about 1.1 watts to the candle-power, many architects place in the circle the number of watts to be used. Dividing this number

## Standard Wiring-Symbols Adopted by the National Contractors' Association and the American Institute of Architects (Continued)

	Main or feeder-run concealed under floor.
	Main or feeder-run concealed under floor above.
	Main or feeder-run exposed.
	Branch circuit-run concealed under floor.
	Branch circuit-run concealed under floor above.
	Branch circuit-run exposed.
	Pole-line.
	Riser.
	Telephone-outlet; private service.
	Telephone-outlet; public service.
	Bell-outlet.
	Buzzer-outlet.
	Push-button outlet. Numeral indicates number of pushes.
	Annunciator. Numeral indicates number of points.
	Speaking-tube.
	Watchman-clock outlet.
	Watchman-station outlet.
	Master time-clock outlet.
	Secondary time-clock outlet.
	Door-opener.
	Special outlet for signal-systems, as described in specifications.
	Battery-outlet.
	Circuit for clock, telephone, bell or other service, run under floor, concealed. Kind of service wanted ascertained by symbol to which line connects.
	Circuit for clock, telephone, bell or other service, run under floor above, concealed. Kind of service wanted ascertained by symbol to which line connects.

heights of center of wall-outlets (unless otherwise specified):

Living-rooms.....	5 ft 6 in
Chambers.....	5 ft 0 in
Offices.....	6 ft 0 in
Corridors.....	6 ft 3 in
heights of switches (unless otherwise specified).....	4 ft 0 in

r.x gives the candle-power per outlet. Thus means enough tungsten-lamps be placed in this outlet to total 120 watts, three 40-watt lamps, or two 60-watt lamps, etc. The candle-power in any case would be  $120/1.1 = 110$  candle-power.

## ARCHITECTURAL ACOUSTICS\*

By

WALLACE C. SABINE

LATE PROFESSOR OF PHYSICS, HARVARD UNIVERSITY

**Architectural Acoustics a Rational Engineering Problem.** Because familiarity with the phenomena of sound has so far outstripped the adequate study of the problems involved, many of them have been popularly shrouded in a wholly unnecessary mystery. Of none, perhaps, is this more true than of ARCHITECTURAL ACOUSTICS. The conditions surrounding the transmission of speech in an enclosed auditorium are complicated, it is true, but are only such as will yield an exact solution in the light of adequate data. It is not unreasonable, therefore, to include problems of architectural acoustics among the RATIONAL ENGINEERING PROBLEMS.

**Character and Application of the Problem.** The problem of architectural acoustics is necessarily complex, and each room presents many conditions which contribute to the result in a greater or less degree, according to circumstances. To take justly into account these varied conditions, the solution of the problem should be QUANTITATIVE, not merely QUALITATIVE; and to reach its highest usefulness and the dignity of an engineering science it should be such that its application can precede, not merely follow, the construction of the building.

**Conditions and Factors of the Problem.** In order that hearing may be good in any auditorium it is necessary that the sound should be sufficiently loud, that the simultaneous components of a complex sound should maintain their proper relative intensities, and that the successive sounds in rapidly moving articulation, either of speech or of music, should be clear and distinct, free from each other and from extraneous noises. These three are the necessary, as they are the entirely sufficient, conditions for good hearing. Scientifically the problem involves three factors:

- (1) Reverberation.
- (2) Interference.
- (3) Resonance.

As an engineering problem it involves the shape of the auditorium, its dimensions, and the materials of which it is composed.

**Rate of Absorption of Sound.** Sound, being energy, once produced in a confined space, will continue until it is either transmitted by the boundary walls or is transformed into some other kind of energy, generally heat. This process of decay is called ABSORPTION. Thus, in the lecture-room of Harvard University, in which, and in behalf of which, this investigation was begun, the RATE

\* Adapted and reproduced by permission from a paper read by Dr. W. C. Sabine before the Franklin Institute, Philadelphia, October 30, 1914 and published in the January 1915 issue of the Journal of the Franklin Institute. For information regarding further data, see other papers and treatises on the subject by the author of this article.



OF ABSORPTION was so small that a word spoken in an ordinary tone of voice was audible for five and a half seconds afterwards. During this time even a very deliberate speaker would have uttered the twelve or fifteen succeeding syllables. Thus the successive enunciations blended into a loud sound, through which and above which it was necessary to hear and distinguish the orderly progression of the speech. Across the room this could not be done; even near the speaker it could be done only with an effort wearisome in the extreme if long maintained.

**Multiple Reflection, Reverberation and Echoes.** With an audience filling the room the conditions were not so bad, but still not tolerable. This may be regarded, if one so chooses, as a process of MULTIPLE REFLECTION from walls, from ceiling, and from floor, first from one and then another, losing a little at each reflection until ultimately inaudible. This phenomenon will be called REVERBERATION, including, as a special case, the ECHO. It must be observed, however, that, in general, reverberation results in a mass of sound filling the whole room and incapable of analysis into its distinct reflections. It is thus more difficult to recognize and impossible to locate. The term ECHO will be reserved for that particular case in which a short, sharp sound is distinctly repeated by reflection, either once from a single surface, or several times from two or more surfaces.

**Rate of Decay of Sound.** In the general case of reverberation we are concerned only with the RATE OF DECAY of the sound. In the special case of the echo we are concerned not merely with its intensity, but with the interval of time elapsing between the initial sound and the moment it reaches the observer. In the room mentioned as the occasion of this investigation no discrete echo was distinctly perceptible, and the case will serve excellently as an illustration of the more general type of reverberation.

**Duration of Audibility of Residual Sound.** After preliminary gropings, first in the literature and then with several optical devices for measuring the intensity of sound, all established methods were abandoned. Instead, the RATE OF DECAY was measured by measuring what was inversely proportional to it, the duration of audibility of the reverberation, or, as it will be called here, the DURATION OF AUDIBILITY OF THE RESIDUAL SOUND. These experiments may be explained to advantage here, for they will give more clearly than would abstract discussion an idea of the nature of reverberation.

**Shape of Room and Nature of Furnishings.** Broadly considered there are two, and only two, variables in a room, SHAPE (including size), and MATERIALS (including furnishings). In designing an auditorium an architect can give consideration to both; in repair-work for bad acoustic conditions it is generally impracticable to change the shape, and only variations in materials and furnishings are allowable. This was, therefore, the line of work in this case.

**The Relative Absorbing Power of Different Substances.** It was evident that, other things being equal, the rate at which the reverberation would disappear was proportional to the rate at which the sound was absorbed. The first work, therefore, was to determine the RELATIVE ABSORBING POWER of various substances. With an organ-pipe as a constant source of sound, and a suitable kymograph for recording, the duration of audibility of a sound after the source had ceased in this room when empty was found to be 5.62 seconds. All the cushions from the seats in Sanders Theater, Boston, Mass., were then brought over and stored in the lobby. On bringing into the lecture-room a number

of cushions, having a total length of 8.2 meters, the duration of audibility fell to 5.33 seconds. On bringing in cushions of a total length of 17 meters the sound in the room after the organ-pipe ceased was audible for but 4.94 seconds. Evidently the cushions were strong absorbents and rapidly improving the room, at least to the extent of diminishing the reverberation. The result was interesting and the process was continued. Little by little more cushions were brought into the room, and each time the duration of audibility was measured. When all the seats, 436 in number, were covered, the sound was audible for 2.03 seconds. Then the aisles were covered, and then the platform. Still there were more cushions, almost half as many more. These were brought into the room, a few at a time, as before, and draped on a scaffolding that had been erected around the room, the duration of the sound being recorded each time. Finally, when all the cushions from a theater seating nearly 1500 persons were placed in the room, covering the seats, the aisles, the platform, and the rear wall to the ceiling, the duration of audibility of the residual sound was 1.14 seconds. This experiment, requiring, of course, several nights' work, having been completed, all the cushions were removed and the room was in readiness for the test of other absorbents. It was evident that a STANDARD OF COMPARISON had been established. Curtains of chenille, 1.1 meters wide and 17 meters in total length, were draped in the room. The duration of audibility was then 4.51 seconds. Turning to the data that had just been collected, it appeared that this amount of chenille was equivalent to 30 meters of cushions from Sanders Theater. Oriental rugs (Herez, Demirjik, and Hindoostanee) were tested in a similar manner, as were also cretonne cloth, canvas, and hair-felt. Similar experiments, but in a smaller room, determined the absorbing power of a man and of a woman, always by determining the number of running meters of Sanders Theater cushions that would produce the same effect. This process of comparing two absorbents by actually substituting one for the other is laborious, and it is given here only to show the first steps in the development of a method. Without going into details, it is sufficient here to say that this method was so perfected as to give not merely RELATIVE, but ABSOLUTE, COEFFICIENTS OF ABSORPTION.

**Coefficients of Absorption.** In this manner a number of COEFFICIENTS OF ABSORPTION were determined for objects and materials which could be brought into and removed from the room, for sounds having a pitch an octave above middle C. In the following table the numerical values are the ABSOLUTE COEFFICIENTS OF ABSORPTION:

Oil-paintings, inclusive of frames.....	0.28
Carpet-rugs.....	0.20
Oriental rugs, extra heavy.....	0.29
Cheese-cloth.....	0.019
Cretonne cloth.....	0.15
Shelia curtains.....	0.23
Hair-felt, 2.5 cm. thick, 8 cm. from wall.....	0.78
Cork, 2.5 cm. thick, loose on floor.....	0.16
Linoleum, loose on floor.....	0.12

When the objects are not extended surfaces, such as carpets or rugs, but essentially spacial units, it is not easy to express the absorption as an absolute coefficient. In the following table the absorption of each object is expressed in terms of a SQUARE METER OF COMPLETE ABSORPTION:

Audience, per person.....	0.44
Isolated woman.....	0.54
Isolated man.....	0.48
Plain, ash settees.....	0.039
Plain, ash settees, per single seat.....	0.0077
Plain, ash chairs, bent wood.....	0.0082
Upholstered settees, hair and leather.....	1.10
Upholstered settees, per single seat.....	0.28
Upholstered chairs, similar in style.....	0.30
Hair-cushions, per seat.....	0.21
Elastic-felt cushions, per seat.....	0.20

**Coefficient of Absorption of Floors, Ceilings and Wall-Surfaces.** Of even greater importance was the determination of the COEFFICIENT OF ABSORPTION of floors, ceilings, and wall-surfaces.

The accomplishment of this called for a very considerable extension of the method adopted. If the reverberation in a room is changed by the addition of absorbing material, the resulting curve will be found to be a portion of a hyperbola with displaced axes. An example of such a curve, as obtained in the lecture-room of the Fogg Art Museum, Cambridge, Mass., is plotted in the diagram in Fig. 1. If now the origin of this curve is




Fig. 1. Curve Showing the Relation of Duration of Residual Sound to Added Absorbing Material

placed so that the axes of coordinates are the asymptotes of the rectangular hyperbola (Fig. 2), the displacement of the origin measures the initial absorbing power of the room, its floors, walls and ceilings. Such experiments were carried out in a large number of rooms in which the different component materials differed in very different degrees, and an elimination between these different experiments gave the following COEFFICIENT OF ABSORPTION for different materials:

Open window.....	1.000
Wooden sheathing, hard pine.....	0.061
Plaster on wooden lath.....	0.034
Plaster on wire lath.....	0.033
Glass, single thickness.....	0.027
Plaster on tile.....	0.025
Brick set in Portland cement.....	0.025

**Calculating the Reverberation for Any Room.** If the experiments in these rooms are plotted in a single diagram, the result is a family of HYPERBOLAS (Fig. 3) showing a very interesting relationship to the volumes of the rooms. Indeed, if from these hyperbolas the parameter, which equals the product of the

coordinates, is determined, it will be found to be linearly proportional to the volume of the room. These results are plotted in Fig. 4, showing how strict the proportionality is even over a very great range in volume. We have thus




Fig. 2. Curve 5 Plotted as Part of its Corresponding Rectangular Hyperbola. The Solid Part was Determined Experimentally. The Displacement of This to the Right Measures the Absorbing Power of the Walls of the Room

at hand a ready method of calculating the REVERBERATION for any room, its volume and the materials of which it is composed being known. The first five years of the investigation were devoted to violin C, the C an octave above middle C, having a VIBRATION-FREQUENCY of 512 vibrations per second. This pitch was chosen because, in the art of telephony, it was regarded at that time as the characteristic pitch determining the conditions of articulate speech. The planning of Symphony Hall, Boston, Mass., forced an extension of this investiga-

tion to notes over the whole range of the musical scale, three octaves below and three octaves above violin-C.

**Absorption-Coefficient of an Audience.** In the very nature of the problem, the most important datum is the ABSORPTION-COEFFICIENT of an audience, and the determination of

this was the first task undertaken. By means of a lecture on one of the recent developments of physics, wireless telegraphy, an audience was thus drawn together and at the end of the lecture requested to remain for the experiment.

In this attempt the effort was made to determine the coefficients for the five octaves from  $C_{128}$  to  $C_{2048}$ , including notes E and G in each octave. For several reasons the experiment was not a success. A threatening thunderstorm made the audi-

ence a small one, and the sultriness of the atmosphere made open windows necessary; while the attempt to cover so many notes, thirteen in all, prolonged the experiment beyond the endurance of the audience. While this experiment failed, another, the following summer, was more successful. In the year that had elapsed the necessity of carrying the investigation further than the limits intended became evident, and now the experiment was carried from  $C_{164}$  to

Duration in seconds

120	120	240	300	300	420
640	780	900	1000	1000	1200

Total absorbing material

Fig. 3. Curves Entered as Parts of their Corresponding Rectangular Hyperbolas. Three Scales are Employed for the Volumes, by Groups, 1-7, 8-11, and 12

C<sub>14096</sub>, but included only the C notes, seven notes in all. Moreover, bearing in mind the experiences of the previous summer, it was recognized that even seven notes would come dangerously near overtaking the patience of the audience. Inasmuch as


the COEFFICIENT OF ABSORPTION for C<sub>4512</sub> had already been determined six years before, in the investigations mentioned, the coefficient for this note was not redetermined. The experiment was therefore carried out for the lower three and the upper three notes of the seven. The audience, on the night of this experiment, was much larger than that which came the previous summer, the night was a more comfortable one, and it was possible to close the windows during the experiment. The conditions were thus fairly satisfactory. In order to get as much data as possible, and in as short a time, there were nine observers stationed at different points in the room.

The instrument.

Volumes of rooms

Fig. 4. The Parameters  $k$ , Plotted Against the Volumes of the Rooms, Showing the Two Proportional

These observers, whose kindness and skill it is a pleasure to acknowledge, had prepared themselves, by previous practice, for this one experiment. The results of the experiment are shown on the lower curve in Fig. 5. This curve gives the COEFFICIENT OF ABSORPTION PER PERSON. It is to be observed that one of the points falls clearly off the smooth curve drawn through the other points. The observations on which this point is based were, however, much disturbed by a street-car passing not far from the building, and the departure of this observation from the curve does not indicate a real departure in the coefficient, nor should it cast much doubt on the rest of the work, in view of the circumstances under which it was secured. Counteracting the, perhaps, bad impression which this point may give, it is considerable satisfaction to note how accurately the point for C<sub>4512</sub>, determined six years before by a different set of observers, falls on the smooth curve through the remaining points. The upper curve represents the absorbing power of an audience per square meter, as ordinarily



ted. The vertical ordinates are expressed in terms of total absorption a square meter of surface. For the upper curve the ordinates are thus the binary coefficients of absorption. The several notes are at octave-intervals

as follows:  $C_{164}$ ,  $C_{2128}$ ,  $C_3$  (middle C) 256,  $C_{4512}$ ,  $C_{62024}$ ,  $C_{82048}$ ,  $C_{14096}$ . In the audience on which these observations were taken there were 77 women and 105 men. The courtesy of the audience in remaining for the experiment and the really remarkable silence which they maintained are gratefully acknowledged.

**Absorption of Sound by Wooden Sheathing.** The next experiment was on the determination of the ABSORPTION OF SOUND by wooden sheathing. It is not an easy matter to find conditions suitable for this experiment. The room in which the absorption by wooden sheathing was determined in the earlier experiments was not available for these. It was available then only because the building was new and empty. When these more elaborate experiments were under way the room became occupied, and in a manner that did not admit of its




Fig. 6. Absorbing Power of Wooden Sheathing

being cleared. Quite a little searching in the neighborhood of Boston failed to discover an entirely suitable room. The best one available adjoined a night-lunch room. The night-lunch was bought out for a couple of nights, and the experiment was tried. The work of both nights was much disturbed. The traffic past the building did not stop until nearly two o'clock, and began again at four. The interest of those passing on foot throughout the night, and the necessity of repeated explanations to the police, greatly interfered with the work. This detailed statement of the conditions under which the experiment was tried is made by way of explanation of the irregularity of the observations recorded on the curve, and of the failure to carry this particular line of work further. On the first night seven points were obtained for the seven notes  $C_{164}$  to  $C_{14096}$ . The reduction of these results on the following day showed variations indicative of maxima and minima, which, to be accurately located, would require the determination of intermediate points. In the experiment on the following night, points were determined for the E and G notes in each

octave between  $C_{2128}$  and  $C_{62048}$ . Other points would have been determined, but time did not permit. It is obvious that the intermediate points in the lower and in the higher octave were desirable, but no pipes were to be had on such short notice for this part of the range, and in their absence the data could not be obtained. In the diagram, Fig. 6, the points lying on the vertical lines were determined the first night. The points lying between the vertical lines were determined the second night. The sheathing of the room is of North Carolina pine, 2 centimeters thick. The absorption is here due almost wholly to yielding of the sheathing as a whole. It is not possible now to learn as much in regard to the framing and arrangement of the studding in the particular room tested as is desirable. The accuracy with which these points fall on a smooth curve is, perhaps, all that could be expected in view of the difficulty under which the ob-

servations were conducted and the limited time available. One point in particular falls far off from this curve, the point for  $C_{1256}$ , by an amount which is, to say the least, serious, and which can be justified only by the conditions under which the work was done. The general trend of the curve seems, however, established beyond reasonable doubt. It is interesting to note that there is one point of MAXIMUM ABSORPTION, which is due to resonance between the walls and the sound, and that this point of maximum absorption lies in the lower part, though not in the lowest part, of the RANGE OF PITCH tested. It would have been interesting to determine, had the time and facilities permitted, the shape of the curve beyond  $C_{14096}$ , and to see if it rises indefinitely, or shows, as is far more likely, a succession of maxima.

**Absorption of Sound by Cushions.** The experiment was then directed to the determination of the ABSORPTION OF SOUND by cushions, and for this purpose return was made to the constant-temperature room. Working in the manner indicated in the earlier papers for substances which could be carried in and out of a room, the curves represented in Fig.

were obtained. Curve 1 shows the ABSORPTION-COEFFICIENT for the Sanders heater cushions, with which the whole investigation was begun ten years ago (1904). These cushions were of a particularly open grade of packing, a sort of dry grass or vegetable fiber. They were covered with canvas ticking, and that, in turn, with a very thin, cloth covering. Curve 2 is for cushions borrowed from the Phillips Brooks House. They were of high grade, filled with long, curly hair, and covered with canvas ticking, which was, in turn, covered by a long-nap plush. Curve 3 is for the cushion of Appleton Chapel, hair-covered with a leatherette, and showing a sharper maximum and a more rapid diminution in absorption for the higher frequencies, as would be expected under such conditions. Curve 4

is probably the most interesting, because for more standard commercial conditions ordinarily used in churches. This curve is for the elastic-felt cushions of commerce, of elastic cotton covered with ticking and short-nap plush. The absorbing power is per square meter of surface. It is to be observed that all four curves fall off for the higher frequencies, all show a maximum located within an octave, and three of the curves show a curious hump in the second octave. This break in the curve is a genuine phenomenon, as it was tested again after time. It is perhaps due to a SECONDARY RESONANCE, and it is to be observed that it is the more pronounced in those curves that have the higher resonance in their principal maxima.

**Effects of Interference of Sound-Waves.** In both articulate speech and music the source of sound is rapidly and, in general, abruptly changing in its quality and loudness. In music one PITCH is held during the length of a note. In articulate speech the unit or ELEMENT OF CONSTANCY is the syllable, and, in speech it is even less than the length of a syllable, for the open-vowel




Fig. 7. Absorbing Power of Cushions



sound which forms the body of a syllable usually has a consonantal opening and closing. During the constancy of an element, either of music or of speech, a train of sound-waves spreads spherically from the source, just as a train of circular waves spreads outward from a rocking boat on the surface of still water. Different portions of this train of spherical waves strike different surfaces of the auditorium and are REFLECTED. After such reflection they begin to cross each other's paths. If their paths are so different in length that one train of waves has entirely passed before the other arrives at a particular point, the only phenomenon at that point is PROLONGATION of the sound. If the space between the two trains of waves is sufficiently great, the effect will be that of an ECHO. If there are a number of such trains of waves thus widely spaced, the effect will be that of MULTIPLE ECHOES. On the other hand, if two trains of waves have traveled so nearly equal paths that they overlap, they will, dependent on the difference in length of the paths which they have traveled, either reinforce or mutually destroy each other. Just as two equal trains of water-waves crossing each other may entirely neutralize each other if the crest of one and the trough of the other arrive together, so two sounds, coming from the same source, in crossing each other may produce silence. This phenomenon is called INTERFERENCE, and is a common phenomenon in all types of wave-motion. Of course, this phenomenon has its complement. If the two trains of water-waves so cross that the crest of one coincides with the crest of the other and trough with trough, the effects will be added together. If the two sound-waves are similarly retarded, the one on the other, their effects will also be added. If the two trains of waves are equal in intensity, the combined intensity will be quadruple that of either of the trains separately, as above explained, or zero, depending on their relative retardation. The effect of this phenomenon is to produce regions in an auditorium of LOUDNESS and regions of comparative or even complete SILENCE. It is a partial explanation of the so-called DEAF REGIONS in an auditorium.

**Distribution of Intensity of Sound.** It is not difficult to observe this phenomenon directly. It is difficult, however, to measure and record the phenomenon in such a manner as to permit of an accurate chart of the result. Without going into the details of the method employed, the result of these measurements for a room very similar to the Congregational Church in Naugatuck, Conn., is shown in the accompanying chart. The room experimented in was a simple, rectangular room with plain side walls and ends and with a barrel or cylindrical ceiling with the center of curvature at the floor-level. The result is clearly represented in Fig. 8, in which the INTENSITY OF THE SOUND has been indicated by contour-lines in the manner employed in the drawing of the geodetic survey-maps. The phenomenon indicated in these diagrams was not ephemeral, but was constant so long as the source of sound continued, and repeated itself with almost perfect accuracy day after day. Nor was the phenomenon one which could be observed merely instrumentally. To an observer moving about in the room it was quite as striking a phenomenon as the diagram suggests. At the points in the room indicated as HIGH MAXIMA OF INTENSITY in the diagram the sound was so loud as to be disagreeable, at other points so low as to be scarcely audible. It should be added that this distribution of intensity is with the source of sound at the center of the room at the head-level. Had the source of sound been at one end and on the axis of the cylindrical ceiling, the distribution of intensity would still have been bilaterally symmetrical, but not symmetrical about the transverse axis.

**Interference-Systems and Reverberation.** When a source of sound is maintained constant for a sufficiently long time, a few seconds will ordinarily suffice; the sound becomes steady at every point in the room. The distribution of the



intensity of sound under these conditions is called the **INTERFERENCE-SYSTEM**, for that particular note, of the room or space in question. If the source of sound is suddenly stopped, it requires some time for the sound in the room to be absorbed. This prolongation of sound after the source has ceased is called **REVERBERATION**. If the source of sound, instead of being maintained, is short and sharp, it travels as a discrete wave or group of waves about the room, reflected

Fig 8. Distribution of Intensity of Sound

om wall to wall, producing echoes. In the Greek theater there was ordinarily at one echo, "doubling the case-ending," while in the modern auditorium there are many, generally arriving at a less interval of time after the direct sound, and therefore less distinguishable, but stronger and therefore more disturbing.

**Photographing Air-Disturbances.** The formation and the propagation of **WAVES** may be admirably studied by an adaptation of the so-called **SCHLIEREN-**

Fig. 9 Photograph of Sound-wave. Vertical Section

Fig. 10. Photograph of Sound-wave. Vertical Section

Fig. 11. Photograph of Sound-wave and Echoes. Vertical Section

Fig. 12. Photograph of Sound-wave and Echoes. Vertical Section

**METHODE** device for photographing air-disturbances. It is sufficient here to say that the adaptation of this method to the problem in hand consists in the construction of a **MODEL** in proper scale, of the auditorium to be studied and an inven-

**Fig. 13. Photograph of Sound-wave and Echoes. Horizontal Section**

tigation of the propagation through it of a proportionally scaled sound-wave. To examine the formation of echoes in a vertical section, the sides of a model are taken off and, as the sound is passing through it, it is illuminated instantaneously

**Fig. 14. Photograph of Sound-wave and Echoes. Horizontal Section**

by the light from a very fine and somewhat distant electric spark. In the accompanying illustrations, reduced from the photographs, the silhouettes show parts of the shadows cast by the model, and all within are direct photographs of the actual

sound-wave and its echoes. Figs. 9 to 12 show the sound and its echoes at different stages in their propagation through the room, the particular part of the auditorium under investigation being the New Theater in New York City. It

Fig. 15. Photograph of Sound-wave and Echoes. Horizontal Section

is not difficult to identify the MASTER-WAVE and the various ECHOES which it generates, nor, knowing the velocity of sound, to compute the interval at which the echo is heard. To show the generation of echoes and their propagation in

Fig. 16. Photograph of Sound-wave and Echoes. Horizontal Section

a horizontal plane, the ceiling and floor of the model are removed and the photograph taken in a vertical direction. The photographs shown in Figs. 13 to 16 show the echoes produced in the horizontal plane passing through the marble parapet in front of the box.

**Solution of Problems Possible in Advance of Construction.** While these several factors, REVERBERATION, INTERFERENCE and ECHO, in an auditorium at all complicated are themselves complicated, nevertheless they are capable of an exact solution, or, at least, of a solution as accurate as are the architect's plans in actual construction; and it is entirely possible to calculate in advance of construction whether or not an auditorium will be good, and, if not, to determine the factors contributing to its poor acoustics and a method for its correction.

## SPECIFIC GRAVITY

**The Specific Gravity** of a substance is the number which expresses the ratio that the weight of a given volume of the substance bears to the weight of the same volume of distilled water at a temperature of 62° F.; or, the specific gravity of a body is equal to its weight divided by the weight of an equal volume of water. The specific gravity of a substance, multiplied by the weight of a cubic foot of water, will give the weight of a cubic foot of the given substance. The weight of a cubic foot of water, at 62° F. and at the sea-level, is about 62.355 lb.\* The specific gravity of a solid substance may be determined by first weighing a portion of it in air and then in water and dividing the weight in air by the loss of the weight in water; the quotient is the specific gravity required.

**Example.** A piece of granite weighs 5.32 lb in air; when immersed in water it weighs 3.32 lb.

**Solution.** Weight in air (5.32 lb) divided by loss of weight in water (2 lb) = 2.66, the specific gravity.

$$2.66 \times 62.355 \text{ lb} = 165.84 \text{ lb} = \text{weight per cubic foot}$$

**NOTE.** 1 cu ft = 7.48 gal.

\* The textbooks differ slightly in regard to this value.

## Specific Gravities and Weights per Cubic Foot of Various Substances\*

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb	Average specific gravity. Water = 1	Average weight of 1 cu ft lb
Agate, .....	2.5 to 2.8	162.1
Air, atmospheric at 60° F., under pressure of one atmos- phere, or 14.7 lb per sq in, weight $\frac{1}{815}$ the weight of water	0.00123	0.0767
Alabaster, carbonate.....	2.61 to 2.76	167.1
Alcohol, absolute, at 32° F.....	0.794	49.5
Alcohol, 50 per cent.....	0.934	58.24
Alcohol, 95 per cent.....	0.815	50.82
Alcohol, commercial.....	0.833	51.95
Alder, dry † .....	0.42 to 1.01	34.3
Alum.....	0.53	33.0
Aluminum, hammered.....	2.75	171.7
Aluminum, drawn.....	2.68	167.1
Aluminum, sheet.....	2.67	166.5
Aluminum, pure.....	2.67	166.5
Aluminum, cast.....	2.56	160.0
Amalgam,.....	13.7 to 14.1	868.0
Amber.....	1.08	67.4
Ambergris.....	0.87	54.3
Ammonia, 60° F.....	0.894	55.81
Antimony, cast.....	6.70	418.0
Antimony, native.....	6.67	416.0
Apple-wood, dry † .....	0.66 to 1.25	46.8
Arsenic.....	5.7 to 5.8	357.3
Asbestos.....	2.1 to 3.0	175.0
Asbestos sheathing-paper.....	1.20	75.0
Ash, American white, dry † .....	0.61	38.0
Ashes of soft coal, solidly packed.....	0.70	40 to 45
Asphalt, for street-paving.....	1.60	100.0
Asphaltum.....	1.11 to 1.23	69 to 75
Ballast, brick, gravel.....	1.79	111.6
Bamboo, dry † .....	0.36	22.5
Barium.....	3.88	242.0
Barytes.....	4.45	277.5
Basalt or trap-rock, average.....	2.96	184.6
Jersey City, N. J.....	3.00	187.1
Duluth, Minn.....	2.95	184.0
Staten Island, N. Y.....	2.86	178.3
Beech, dry † .....	0.65 to 1.12	46.0
Beeswax.....	0.95	59.0
Benzine.....	0.69	43.0
Beer.....	1.04	64.9
Birch, dry † .....	0.52 to 1.08	40.6
Bismuth, cast.....	9.76 to 9.90	612.3
Blood, at 32° F.....	1.06	66.2
Bone.....	1.8 to 2.0	118.6
Borax.....	1.7 to 1.8	109.2
Buxwood, French, dry † .....	1.33	83.0

\* The values given in this table are AVERAGE values. In the compilations of these tables the Editor is indebted to Mr. T. Z. Talley for valuable assistance.

See, also, pages 721, 722, and 723.

The word "dry" in this connection indicates that the wood contains not more than  $\frac{1}{10}$  of moisture. Green timbers usually weigh from one-fifth to nearly one-half more than dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances \***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb			Average specific gravity. Water = 1	Average weight of 1 cu ft lb
Boxwood, Dutch, dry †	}		1.035	64.5
Boxwood, Brazilian, dry †				
Brass (copper and zinc), cast. . . . . 7.8 to 9.			8.45	527.0
Brass, rolled . . . . .			8.56	533.8
Brass, sheet . . . . .			8.24	513.6
Brass, wire . . . . .			8.69	542.0
Bricks, common . . . . .			1.922	120.0
Bricks, light, inferior . . . . .			1.442	90.0
Bricks, lime-sand . . . . .			2.163	135.0
Bricks, magnesia . . . . .			2.643	165.0
Bricks, pressed . . . . .			2.163	135.0
Bricks, pressed, hard . . . . .			2.403	150.0
Bricks, soft . . . . .			1.602	100.0
Bricks, fire . . . . .	}		2.403	150.0
Bricks, paving . . . . .				
Brickwork, pressed bricks, fine joints . . . . .			2.24	140.0
Brickwork, medium quality . . . . .			2.00	125.0
Brickwork, coarse, inferior, soft . . . . .			1.60	100.0
Brickwork, at 125 lb per cu ft, 1 cu yd equals 1.507 tons and 17.92 cu ft equal 1 ton . . . . .				
Bromine . . . . .			3.19	199.0
Bronze, coin . . . . .			8.66	540.0
Bronze, gun-metal . . . . .			8.60	536.3
Bronze, ordinary . . . . .			8.40	524.0
Bronze, aluminum . . . . .			7.70	480.0
Butter . . . . .			0.86	53 to 54
Butternut-tree, dry † . . . . .			0.38	23.7
Cadmium . . . . . 8.6 to 8.7			8.65	539.4
Calcite . . . . . 2.6 to 2.8			2.70	168.5
Calcium . . . . .			1.58	98.6
Camphor, dry . . . . .			0.99	61.7
Caoutchouc (India Rubber) . . . . .			0.93	58.0
Carbon disulphide . . . . .			1.29	80.5
Castor-oil . . . . .			0.96	59.9
Caustic soda . . . . .				88.0
Cedar, red and white, dry † . . . . .			0.45	28.1
Cement, Natural (Rosendale), loose . . . . .			1.04	65.0
Cement, Portland, loose . . . . .			1.35	84.2
Cement, Natural, solid . . . . .			2.95	183.9
Cement, Portland, solid . . . . .			3.15	196.6
Chalk . . . . .			2.35	146.5
Champagne . . . . .			0.99	61.7
Charcoal of pines and oaks . . . . .				15 to 30
Cherry, dry . . . . .			0.66	41.2
Chestnut, dry . . . . .			0.63	39.3
Chromium . . . . .			5.00	312.0
Cider . . . . .			1.02	63.5

\* The values given in this table for specific gravities and for weights per cubic foot are AVERAGE values.

† The word "dry" in this connection indicates that the wood contains not more than 15% of moisture. Green timbers usually weigh from one-fifth to nearly one-half more than dry; ordinary building-timbers, tolerably seasoned, one-sixth more.



**Specific Gravities and Weights per Cubic Foot of Various Substances \***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb	Average specific gravity. Water = 1	Average weight of 1 cu ft lb.
Cinnabar.....	8.12	507.0
Clay, potters', dry.....1.8 to 2.1	1.90	118.5
Clay, dry, in lump, loose.....	1.01	63.0
Coal, anthracite, 1.3 to 1.84; of Penn., 1.3 to 1.7.....	1.50	93.5
Coal, anthracite, broken, of any size, loose, average.....	.....	52 to 56
Coal, anthracite, broken, moderately shaken.....	.....	56 to 60
Coal, anthracite, broken, heaped bushel, loose, 77 to 83 lb.....	.....	.....
Coal, anthracite, broken, a ton loose occupies 40 to 43 cu ft.....	.....	.....
Coal, bituminous, solid, 1.2 to 1.5.....	1.35	84.0
Coal, bituminous, solid, Cambria Co., Pa., 1.27 to 1.34.....	.....	79 to 84
Coal, bituminous, broken, of any size, loose.....	.....	47 to 52
Coal, bituminous, moderately shaken.....	.....	51 to 56
Coal, bituminous, a heaped bushel, loose, 70 to 78.....	.....	.....
Coal, bituminous, 1 ton occupies 43 to 48 cu ft.....	.....	.....
Coke, loose, good quality.....	.....	23 to 32
Coke, loose, a heaped bushel, 35 to 42 lb.....	.....	.....
Coke, loose, 1 ton occupies 80 to 97 cu ft.....	.....	.....
Concrete, stone.....130 to 150	2.33	145.0
Concrete, cinder.....100 to 110	1.68	105.0
Copper, hammered.....8.8 to 9.0	8.95	558.0
Copper, rolled.....8.9 to 9.0	8.95	558.0
Copper, drawn wire.....8.8 to 9.0	8.89	554.5
Copper, sheet.....	8.72	543.6
Copper, cast.....8.6 to 8.9	8.82	550.0
Copper, melted.....	8.23	513.0
Cork, dry.....	0.24	15.0
Corundum, pure.....3.92 to 4.01	3.96	247.5
Creosote oil.....1.04 to 1.10	1.07	66.8
Cypress, American, dry †.....	0.55	34.3
Dogwood, dry †.....	0.75	46.8
Douglas fir, dry †.....	0.51	31.8
Earth, common loam, perfectly dry, loose.....	.....	72 to 80
Earth, common loam, perfectly dry, shaken.....	.....	82 to 92
Earth, common loam, perfectly dry, rammed.....	.....	90 to 100
Earth, common loam, slightly moist, loose.....	.....	70 to 76
Earth, common loam, more moist, loose.....	.....	66 to 68
Earth, common loam, more moist, shaken.....	.....	75 to 90
Earth, common loam, more moist, packed.....	.....	90 to 100
Earth, common loam, as soft, flowing mud.....	.....	104 to 112
Earth, common loam, as soft, flowing mud, well-pressed bony.....	1.22	76.0
.....	1.09	68.0
Ida-pith.....	0.076	4.7
lm, dry †.....	0.56	35.0
lm, rock.....	0.80	50.0
emerald.....	2.70	168.5

The values given in this table for specific gravities and for weights per cubic foot are  
RAGE values.

The word "dry" in this connection indicates that the wood contains not more than  
of moisture. Green timbers usually weigh from one-fifth to nearly one-half more  
dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances \***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb	Average specific gravity. Water = 1	Average weight of 1 cu ft lb
Emery.....	4.00	249.5
Fats.....	0.93	58.0
Feldspar.....	2.57	160.2
Filbert-tree, dry †.....	0.60	37.5
Fir, Douglas (see Douglas Fir).		
Flint.....	2.63	164.0
Gamboge.....	1.20	74.8
Garnet.....3.4 to 4.3	3.85	240.1
Glass, optical.....	3.45	215.0
Glass, flint.....	3.00	187.0
Glass, white.....	2.89	180.2
Glass, plate.....	2.80	174.6
Glass, green.....	2.67	166.5
Glass, floor, heavy.....	2.53	158.0
Glass, window.....	2.50	156.0
Gneiss (see Granites).		
Gold, pure.....	19.50	1 215.9
Gold, hammered, native.....	19.40	1 209.7
Gold, cast.....	19.258	1 200.8
Granites and gneiss, Connecticut, Greenwich.....	2.84	177.3
California, Penryn (hornblende).....	2.77	172.9
New York.....	2.74	171.0
Maryland, Port Deposit.....	2.72	169.6
Massachusetts, Quincy (hornblende).....	2.70	168.5
Wisconsin, Athelstane.....	2.70	168.5
Georgia, Lithornia and Stone Mountain.....	2.69	167.9
Minnesota.....	2.68	167.3
California, Rocklin (muscovite).....	2.68	167.3
Rhode Island, Westerley.....	2.67	166.7
Connecticut, New London.....	2.66	166.0
New Hampshire, Keene.....	2.66	166.0
Maine, Hallowell.....	2.65	165.2
New Hampshire, Concord.....	2.65	165.2
Vermont, Barre.....	2.65	165.2
Wisconsin, Montello.....	2.64	164.6
Colorado, Georgetown (biotite).....	2.63	164.0
Maine, Fox Island.....	2.63	164.0
Massachusetts, Rockport.....	2.61	162.7
Graphite.....	2.26	140.0
Gravel, dry.....	1.79	112.0
Gravel, wet.....	2.00	125.0
Greenstone, trap.....2.8 to 3.2	3.00	187.0
Grindstone.....	2.14	133.5
Gum arabic.....	1.32	82.5
Gun-metal (see Bronze).		
Gunpowder (granular).....	1.00	62.4
Gutta-percha.....	0.98	61.0

\* The values given in this table for specific gravities and for weights per cubic foot are AVERAGE values.

† The word "dry" in this connection indicates that the wood contains not more than 15% of moisture. Green timbers usually weigh from one-fifth to nearly one-half more than dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances \***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water 62.355 lb			Average specific gravity. Water = 1	Average weight of 1 cu ft lb
gypsum, natural rock, free from surface-water.....			2.30	143.0
gypsum, crushed rock, not calcined, all passing 1-in ring.....			1.52	95.0
gypsum, ground rock, 90% passing 100 mesh, dried not calcined.....			1.25	78.0
gypsum, Plaster-of-Paris, stucco, stiff mortar, set and dried out.....			1.22	77.0
gypsum, Plaster-of-Paris, stucco, ground rock, 90% passing 100 mesh, calcined, loose.....			0.96	60.0
well shaken down or in bins.....			1.11	70.0
hackmatack (see Larch).....			....	....
hay, loose in stacks, about 512 cu ft per ton.....			....	....
hemlock, dry †.....			0.42	26.2
hickory, pignut, dry †.....			0.89	55.6
hickory, mocker-nut, dry †.....			0.85	53.1
hickory, shagbark, dry †.....			0.81	50.6
hickory, nutmeg, dry †.....			0.78	48.7
hickory, bitternut, dry †.....			0.77	48.1
hickory, water, dry †.....			0.73	45.6
holly.....			0.76	47.4
honey.....			1.45	90.5
horn.....			1.69	105.5
hornblende.....	3.0 to 3.5		3.25	202.7
iron.....	0.88 to 0.914		0.89	56.0
Indiana Limestone.....			2.31	144.0
iron.....			4.94	308.0
iridium, pure.....			22.12	1379.0
iron, cast.....	6.9 to 7.4		7.2	448.9
iron, gray, foundry, cold.....			7.21	450.0
iron, gray, foundry, molten.....			6.94	433.0
iron, wrought.....			7.70	480.0
iron.....			1.88	117.0
juniper-wood.....			0.57	35.6
kaolin.....			2.20	137.2
lava.....			2.65	165.2
larch, or hackmatack, dry †.....			0.55	34.3
lead.....			0.94	58.7
lead, commercial, cast.....			11.36	708.0
lead, commercial, sheet.....			11.40	710.8
lead, pure.....			11.42	713.0
lead, molten.....			10.40	648.8
gum-vitre, dry †.....	0.65 to 1.33		0.99	41 to 84
me, quick, ground.....	1.04 to 1.20		1.12	65 to 75
limestone, Illinois.....			2.57	160.4
Indiana.....			2.31	144.0
Kentucky.....			2.685	167.4
Michigan.....			2.44	152.1
Minnesota.....			2.655	165.6
Missouri.....			2.32	144.8
New York.....			2.71	169.0
Average of limestones.....			2.57	160.4
seed-oil.....			0.935	58.3

The values given in this table for specific gravities and for weights per cubic foot are  
average values.

The word "dry" in this connection indicates that the wood contains not more than  
of moisture. Green timbers usually weigh from one-fifth to nearly one-half more  
dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances\***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb	Average specific gravity. Water = 1	Average weight of 1 cu ft lb
Locust, dry †.....	0.71	44.3
Magnesite.....	3.0	187.1
Magnesium, pure.....	1.72	107.0
Mahogany.....0.56 to 1.06	0.81	50.5
Manganese, pure.....	8.00	499.0
Manganese, ore, red.....	4.01	250.0
Manganese, ore, black.....	3.45	215.1
Marble, average.....2.6 to 164.4	2.6	162.1
domestic,		
New York.....	2.83	176.5
California.....	2.75	171.5
Georgia.....	2.73	170.2
Vermont, Dorset.....	2.66	166.0
foreign,		
Parian.....	2.84	177.1
African.....	2.80	174.6
Carrara.....	2.72	169.6
Biscayan.....	2.71	169.0
British.....	2.71	169.0
French.....	2.65	165.2
Marl.....	2.10	131.0
Masonry, brickwork (see Brickwork)		
Masonry, concrete, stone.....	2.33	145.3
Masonry, concrete, cinder.....	1.68	105.0
Masonry, granite, dressed.....	2.64	165.0
Masonry, granite, rubble in cement.....	2.48	155.0
Masonry, limestone, dressed.....	2.60	162.0
Masonry, marble, dressed for buildings.....	2.72	170.0
Masonry, sandstone.....	2.41	151.0
Mastic, gum resin.....	0.85	53.0
Mercury, at 32° F.....	13.62	849.0
Mica.....2.75 to 3.1	2.93	183.0
Milk, at 32° F.....	1.032	64.3
Molybdenum, pure.....	8.63	538.1
Mortar, lime.....	1.65	103.0
Mortar, cement.....	1.68	105.0
Mud, dry, close.....		80 to 110
Mud, wet, moderately pressed.....		110 to 130
Mud, wet, fluid.....		104 to 120
Mulberry-tree, dry †.....	0.75	46.8
Naptha-oil, wood, at 32° F.....	0.85	52.9
Nickel.....	8.56	517 to 550
Oak, live, dry †.....0.88 to 1.02	0.95	59.3
Oak, white, dry †.....0.66 to 0.88	0.77	48.0
Oak, red and black, dry †.....		32 to 45
Ochre.....	3.50	218.0
Olive-oil, 32° F.....	0.916	57.12

\* The values given in this table for specific gravities and for weights per cubic foot are AVERAGE values.

† The word "dry" in this connection indicates that the wood contains not more than 15% of moisture. Green timbers usually weigh from one-fifth to nearly one-half more than dry: ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances \***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb			Average specific gravity. Water = 1	Average weight of 1 cu ft lb
Oolitic stones.....			2.25	140.3
Opal.....			2.15	134.0
Opium.....			1.34	83.6
Orange-tree.....			0.71	44.3
Palladium.....			11.80	735.8
Paper.....			0.95	59.3
Paraffin.....			0.88	54.9
Pear-tree wood, dry †.....			0.67	41.8
Peat, pressed.....			0.72	45.0
Petroleum, oil.....			0.878	54.8
Pine, Cuban, dry †.....			0.63	39.3
Pine, yellow, long-leaf, dry.....			0.61	38.1
Pine, loblolly, dry.....			0.53	33.1
Pine, yellow, short-leaf, dry.....			0.51	31.8
Pine, red, Norway, dry.....			0.50	31.2
Pine, spruce, dry.....			0.44	27.5
Pine, white, dry.....			0.38	23.7
Pitch.....			1.08	67.0
Plaster of Paris (see Gypsum).....			2.25	140.3
Platinum.....			21.50	1 340.6
Plumbago.....			2.10	131.0
Poplar, dry †.....			0.47	29.3
Porcelain, china.....			2.30	143.4
Porphyry.....			2.76	172.3
Potash.....			2.26	141.0
Potassium.....			0.865	54.0
Pumice-stone.....			0.92	57.4
Quartz.....			2.65	165.3
Quince-tree wood, dry †.....			0.71	44.3
Red lead.....			8.94	557.5
Resin.....			1.09	68.0
Rock-crystal.....			2.60	162.0
Rosewood.....			0.73	45.6
Rosin.....			1.10	68.6
Rubber, India.....			0.93	58.0
Ruby.....			3.90	243.0
Salt, coarse, per struck bushel, Syracuse, N. Y., 56 lb.....				45.0
Saltpetre.....			2.02	122 to 130
Sand, of pure quartz, perfectly dry and loose.....				90 to 106
Sand, of pure quartz, voids full of water.....				118 to 129
Sand, of pure quartz, very large and small grains, dry.....				117.0
Sandstone, average.....			2.44	152.1
Massachusetts, Longmeadow.....			2.49	155.4
Connecticut, Portland.....			2.50	156.0
New York.....2.40 to 2.70			2.60	162.1
New Jersey, Belleville.....			2.40	149.7
Pennsylvania.....			2.63	164.2
Virginia, Bristow.....			2.60	162.0

The values given in this table for specific gravities and for weights per cubic foot are average values.

The word "dry" in this connection indicates that the wood contains not more than 6% of moisture. Green timbers usually weigh from one-fifth to nearly one-half more when dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

**Specific Gravities and Weights per Cubic Foot of Various Substances\***  
(Continued)

The basis for specific gravities is pure water at 62° F., barometer 30 in. Weight of 1 cu ft of water, 62.355 lb	Average specific gravity. Water = 1	Average weight of 1 cu ft lb
<b>Sandstone, (continued)</b>		
Ohio.....	2.22	138.6
Michigan.....	2.35	146.5
Wisconsin.....	2.22	138.6
Minnesota.....	2.25	140.5
Colorado.....	2.33	145.3
California, Angel Island.....	2.73	170.0
Shales, red or black.....	2.60	162.0
Silica.....	2.66	166.0
Silver.....	10.50	654.5
Slate.....	2.81	175.0
Snow, freshly fallen.....		5 to 12
Snow, moistened, compacted by rain.....		15 to 50
Soapstone.....	2.73	170.0
Sodium.....	0.978	61.0
Spelter.....	7.10	443.0
Spirit, rectified.....	0.824	51.4
Spruce.....	0.40	25.0
Steel, cast.....	7.9	492.6
Steel, wrought.....	7.85	489.6
Sugar.....	1.60	100.0
Sycamore, dry.....	0.58	36.5
Talc.....	2.81	175.2
Tallow.....	0.94	58.6
Tamarack.....	0.38	23.6
Tar.....	1.00	62.4
Teak.....	0.70	43.7
Terra-cotta, solid blocks.....		120 to 122
hollow blocks, 1½-in thick, smaller pieces heaviest.....		65 to 85
Tiles, solid.....	2.20	136.5
Tin, rolled.....	7.40	461.5
Tin, cast.....	7.30	455.0
Tin, molten.....	7.02	437.7
Trap (see Basalt).		
Tungsten.....	19.129	1 192.8
Turpentine.....	0.87	54.3
Type-metal, cast.....	10.45	651.8
Uranium.....	18.49	1 153.0
Vinegar.....	1.08	67.5
Walnut, black, dry.....	0.60	37.5
Water, pure rain, distilled, at 32° F., barometer 30 in. ....		62.4
Water, pure rain, distilled, at 62° F., barometer 30 in. ....	1.00	62.355
Water, pure rain, distilled, at 212° F., barometer 30 in. ....		59.7
Water, sea.....	1.026 to 1.030	64.1
Wax (see Beeswax).		
Willow.....	0.49	30.5
Wine.....	1.01	63.0
Zinc or spelter.....	7.00	436.5

\* The values given in this table for specific gravities and for weights per cubic foot are AVERAGE values.

† The word "dry" in this connection indicates that the wood contains not more than 15% of moisture. Green timbers usually weigh from one-fifth to nearly one-half more than dry; ordinary building-timbers, tolerably seasoned, one-sixth more.

## WIRE-GAUGES\* AND METAL-DATA

A **Wire-Gauge** is a method of designating the diameter of wires or the thickness of sheets of metal by the numbers of a table arranged on a certain fixed basis. There are at the present time several gauges, resulting in great confusion. Table XIII, page 402, gives the diameters of the gauges in common use. The only legal gauge in this country is the United States standard gauge, described on page 1600. It is used by most of the manufacturers of sheet iron and steel and tin plate. The Brown & Sharpe gauge is commonly used for designating the size of copper wires (see page 1510); also for sheet copper and brass. Nearly all copper wire, bare and insulated, is ordered, manufactured, and carried in stock in accordance with this gauge. This might be called the Copper Wire Gauge. The American Steel & Wire Company uses the old Washburn & Moen and Roebling gauges for all their steel and iron wire and also for wire nails. The sectional areas for these gauges are given on pages 403 and 1512, taken from the Washburn & Moen and Roebling and American Steel & Wire Company's lists. When placing orders for sheets and wire, it is always best to specify the weight per square or linear foot or the thickness or diameter in thousandths of an inch or in circular mils. The standard gauge for steel wire, used by the J. A. Roebling's Sons Company, is given on page 403, and the circular-mil gauge on page 1473. The gauge used by this company is the same as the Washburn & Moen gauge, or the American Steel & Wire gauge, except that the diameters in most cases are given to the nearest 1/16 inch. This gauge is so generally used for steel wire that it is sometimes called the Steel Wire Gauge or the Market Wire Gauge. The Birmingham Wire gauge is the same as Stubs' Iron-Wire gauge, but entirely different from Stubs' Steel-Wire gauge. Galvanized telegraph and telephone-wire, both bare and insulated, and galvanized armor-wire are usually designated by this gauge. Its use is not very extensive and is becoming less. The new British Standard gauge is the legal standard for Great Britain and is used there for all kinds of wire. Its use in this country is very limited. It is known, also, as the English Legal Standard gauge and the Imperial Wire gauge.

\* See, also, pages 401, 402, 403, 1469, 1473, 1510, 1512, and 1600.

**Weights in Pounds per Square Foot of Sheets of Wrought Iron, Steel, Copper,  
and Brass**

Thickness by American (Brown & Sharpe) gauge \*

No. of gauge	Thickness in inches	Iron	Steel	Copper	Brass
0000	0.46	18.40	18.77	20.84	19.69
000	0.4096	16.39	16.71	18.56	17.53
00	0.3648	14.59	14.88	16.53	15.61
0	0.3249	12.99	13.25	14.72	13.90
1	0.2893	11.57	11.80	13.11	12.38
2	0.2576	10.31	10.51	11.67	11.03
3	0.2294	9.18	9.36	10.39	9.82
4	0.2043	8.17	8.34	9.26	8.74
5	0.1819	7.28	7.42	8.24	7.79
6	0.1620	6.48	6.61	7.34	6.93
7	0.1443	5.77	5.89	6.54	6.18
8	0.1285	5.14	5.24	5.82	5.50
9	0.1144	4.58	4.67	5.18	4.90
10	0.1019	4.08	4.16	4.62	4.36
11	0.0907	3.63	3.70	4.11	3.88
12	0.0808	3.23	3.30	3.66	3.46
13	0.0720	2.88	2.94	3.26	3.08
14	0.0641	2.56	2.61	2.90	2.74
15	0.0571	2.28	2.33	2.59	2.44
16	0.0508	2.03	2.07	2.30	2.18
17	0.0453	1.81	1.85	2.05	1.94
18	0.0403	1.61	1.64	1.83	1.73
19	0.0359	1.44	1.46	1.63	1.54
20	0.0320	1.28	1.30	1.45	1.37
21	0.0285	1.14	1.16	1.29	1.22
22	0.0253	1.01	1.03	1.15	1.08
23	0.0226	0.903	0.921	1.02	0.966
24	0.0201	0.804	0.820	0.911	0.860
25	0.0179	0.716	0.730	0.811	0.766
26	0.0159	0.638	0.650	0.722	0.682
27	0.0142	0.568	0.579	0.643	0.608
28	0.0126	0.506	0.516	0.573	0.541
29	0.0113	0.450	0.459	0.510	0.482
30	0.0100	0.401	0.409	0.454	0.429
31	0.0089	0.357	0.364	0.404	0.382
32	0.0080	0.318	0.324	0.360	0.340
33	0.0071	0.283	0.289	0.321	0.303
34	0.0063	0.252	0.257	0.286	0.270
35	0.0056	0.224	0.229	0.254	0.240
Specific gravity.....		7.704	7.85	8.72	8.24
Weight per cubic foot.....		480.00	489.60	543.6	513.6
Weight per cubic inch.....		0.2778	0.2833	0.3146	0.2972

\* For other gauges see pages 401, 402, 403, 1469, 1473, 1509, 1512, and 1600.



Thickness or diameter, in	Lead			Copper			Brass			Thickness or diameter, in
	Sheets, per sq ft, lb	Square bars 1 ft long, lb	Round bars 1 ft long, lb	Sheets, per sq ft, lb	Square bars 1 ft long, lb	Round bars 1 ft long, lb	Sheets, per sq ft, lb	Square bars 1 ft long, lb	Round bars 1 ft long, lb	
$\frac{1}{32}$	1.86	0.005	0.004	1.44	0.004	0.003	1.35	0.004	0.003	$\frac{1}{32}$
$\frac{1}{16}$	3.72	0.019	0.015	2.89	0.015	0.012	2.71	0.014	0.011	$\frac{1}{16}$
$\frac{3}{32}$	5.58	0.044	0.034	4.33	0.034	0.027	4.06	0.032	0.025	$\frac{3}{32}$
$\frac{1}{8}$	7.44	0.078	0.061	5.77	0.060	0.047	5.42	0.056	0.044	$\frac{1}{8}$
$\frac{5}{32}$	9.30	0.121	0.095	7.20	0.094	0.074	6.75	0.088	0.069	$\frac{5}{32}$
$\frac{3}{16}$	11.20	0.174	0.137	8.66	0.135	0.106	8.13	0.127	0.100	$\frac{3}{16}$
$\frac{7}{32}$	13.00	0.237	0.187	10.10	0.184	0.144	9.50	0.173	0.136	$\frac{7}{32}$
$\frac{1}{4}$	14.90	0.310	0.244	11.50	0.240	0.189	10.80	0.226	0.177	$\frac{1}{4}$
$\frac{5}{16}$	18.60	0.485	0.381	14.40	0.376	0.295	13.50	0.353	0.277	$\frac{5}{16}$
$\frac{3}{8}$	22.30	0.698	0.548	17.30	0.541	0.425	16.30	0.508	0.399	$\frac{3}{8}$
$\frac{7}{16}$	26.00	0.950	0.746	20.30	0.736	0.578	19.00	0.691	0.543	$\frac{7}{16}$
$\frac{1}{2}$	29.80	1.240	0.974	23.10	0.962	0.755	21.70	0.903	0.709	$\frac{1}{2}$
$\frac{9}{16}$	33.50	1.570	1.230	26.00	1.220	0.955	24.30	1.140	0.900	$\frac{9}{16}$
$\frac{5}{8}$	37.20	1.940	1.520	28.90	1.500	1.180	27.10	1.410	1.110	$\frac{5}{8}$
$1\frac{1}{16}$	40.90	2.340	1.840	31.70	1.820	1.430	29.80	1.700	1.340	$1\frac{1}{16}$
$\frac{3}{4}$	44.60	2.790	2.190	34.60	2.160	1.700	32.50	2.030	1.600	$\frac{3}{4}$
$1\frac{1}{8}$	48.30	3.270	2.570	37.50	2.550	1.990	35.20	2.380	1.870	$1\frac{1}{8}$
$\frac{7}{8}$	52.10	3.800	2.980	40.40	2.940	2.310	37.00	2.760	2.170	$\frac{7}{8}$
$1\frac{1}{2}$	56.00	4.370	3.420	43.30	3.380	2.650	40.60	3.180	2.490	$1\frac{1}{2}$
1	59.50	4.960	3.900	46.20	3.850	3.020	43.30	3.610	2.840	1
$1\frac{1}{8}$	66.50	6.270	4.920	52.00	4.870	3.820	48.70	4.570	3.600	$1\frac{1}{8}$
$1\frac{1}{4}$	74.40	7.750	6.090	57.70	6.010	4.720	54.20	5.640	4.430	$1\frac{1}{4}$
$1\frac{3}{8}$	81.80	9.370	7.370	63.50	7.280	5.720	59.60	6.820	5.370	$1\frac{3}{8}$
$1\frac{1}{2}$	89.30	11.200	8.770	69.30	8.650	6.800	65.00	8.120	6.380	$1\frac{1}{2}$
$1\frac{3}{4}$	96.70	13.100	10.30	75.10	10.200	7.980	70.40	9.530	7.490	$1\frac{3}{4}$
$1\frac{7}{8}$	104.00	15.200	11.90	80.80	11.800	9.250	75.90	11.100	8.680	$1\frac{7}{8}$
$2$	112.00	17.500	13.70	86.60	13.500	10.600	81.30	12.700	9.970	$2$
	119.00	19.800	15.60	92.30	15.400	12.100	86.70	14.400	11.305	

**Sizes and Weights of Smooth Steel Wire \***  
**As made by the American Steel & Wire Company**

No. of gauge	Diameters			Sectional area, sq in	Weight †		No. of feet per pound
	Fractions of inch	Decimals of inch	Milli- meters		Pounds per 100 feet	Pounds per mile	
000000	.....	0.4615	11.72	0.16728	56.81	2999.0	1.76
.....	$\frac{7}{16}$	0.4375	11.11	0.15033	51.05	2696.0	1.959
00000	.....	0.4305	10.93	0.14556	49.43	2610.0	2.023
.....	$1\frac{3}{32}$	0.40625	10.32	0.12962	44.02	2324.0	2.272
0000	.....	0.3938	10.00	0.12180	41.36	2184.0	2.413
.....	$\frac{3}{8}$	0.3750	9.525	0.11045	37.51	1980.0	2.666
000	.....	0.3625	9.2075	0.10321	35.05	1851.0	2.853
.....	$1\frac{1}{32}$	0.34375	8.731	0.092806	31.52	1664.0	3.173
00	.....	0.3310	8.407	0.086049	29.22	1543.0	3.422
.....	$\frac{5}{16}$	0.3125	7.938	0.076699	26.05	1375.0	3.839
0	.....	0.3065	7.785	0.073782	25.06	1323.0	3.991
1	.....	0.2830	7.188	0.062902	21.36	1128.0	4.681
.....	$\frac{9}{32}$	0.28125	7.144	0.062126	21.10	1114.0	4.740
2	.....	0.2625	6.668	0.054119	18.38	970.4	5.441
.....	$\frac{1}{4}$	0.2500	6.350	0.049087	16.67	880.2	5.999
3	.....	0.2437	6.190	0.046645	15.84	836.4	6.313
4	.....	0.2253	5.723	0.039867	13.54	714.8	7.386
.....	$\frac{7}{32}$	0.21875	5.556	0.037583	12.76	673.9	7.835
5	.....	0.2070	5.258	0.033654	11.43	603.4	8.790
6	.....	0.1920	4.877	0.028953	9.832	519.2	10.17
.....	$\frac{3}{16}$	0.1875	4.763	0.027612	9.377	495.1	10.66
7	.....	0.1770	4.496	0.024606	8.356	441.2	11.97
8	.....	0.1620	4.115	0.020612	7.000	369.6	14.29
.....	$\frac{5}{32}$	0.15625	3.969	0.019175	6.512	343.8	15.36
9	.....	0.1483	3.767	0.017273	5.866	309.7	17.05
10	.....	0.1350	3.429	0.014314	4.861	256.7	20.57
.....	$\frac{1}{8}$	0.125	3.175	0.012272	4.168	220.0	24.00
11	.....	0.1205	3.061	0.011404	3.873	204.5	25.82
12	.....	0.1055	2.680	0.0087417	2.969	156.7	33.69
.....	$\frac{3}{32}$	0.09375	2.381	0.0069029	2.344	123.8	42.66
13	.....	0.0915	2.324	0.0065755	2.233	117.9	44.78
14	.....	0.0800	2.032	0.0050266	1.707	90.13	58.58
15	.....	0.0720	1.829	0.0040715	1.383	73.01	72.32
16	$\frac{1}{16}$	0.0625	1.588	0.0030680	1.042	55.01	95.98
17	.....	0.0540	1.372	0.0022902	0.7778	41.07	128.60
18	.....	0.0475	1.207	0.0017721	0.6018	31.77	166.20
19	.....	0.0410	1.041	0.0013203	0.4484	23.67	223.00
20	.....	0.0348	0.8839	0.00095115	0.3230	17.05	309.60
21	.....	0.0317	0.8052	0.00078924	0.2680	14.15	373.10
.....	$\frac{1}{32}$	0.03125	0.7938	0.00076699	0.2605	13.75	383.00
22	.....	0.0286	0.7264	0.00064242	0.2182	11.52	458.40
23	.....	0.0258	0.6553	0.00052279	0.1775	9.37	563.30
24	.....	0.0230	0.5842	0.00041548	0.1411	7.45	708.70

\* For other gauges, see pages 401, 402, 403, 1469, 1473, 1509, 1510 and 1600.

† For iron wire, the values in columns 6 and 7 should be multiplied by 0.98 and for copper wire, by 1.12.

**Kinds of Wire Manufactured by the American Steel and Wire Company**

Market-wire, Nos. 0000 to 18.

Annealed stone-wire or weaving-wire, Nos. 16 to 47.

Tinned market-wire, Nos. 0 to 18.

Tinned stone-wire, Nos. 16 to 40.

Gun-screw wire, finished with great care as regards roundness and exactness of gauge, Nos. 18 to 50.

Machinery-wire, Nos. 00000 to 18.

Cast-steel wire,  $\frac{1}{2}$ -in diameter, down to No. 26.

Drill and needle-steel wire, Nos. 12 to 25.

The term MARKET-WIRE applies to the ordinary and most used forms of Bessemer ANNEALED, BRIGHT, GALVANIZED, TINNED and COPPERED wires.

**Galvanized-Iron-Wire Strand.** The diameter, list-price per 100 ft, weight per 100 feet and approximate breaking-load in pounds for this wire is given in Table XVI, Chapter XI.

# Weights and Areas of Square and Round Bars and Circumferences of Round Steel Bars \*

Weights are for steel, at 489.6 lb per cu ft

Thickness or diameter, in	Weight of □ bar 1 ft long, lb	Weight of ○ bar 1 ft long, lb	Area of □ bar, sq in	Area of ○ bar, sq in	Circumfer- ence of ○ bar, in
1/16	0.013	0.010	0.0039	0.0031	0.1963
5/64	0.021	0.016	0.0061	0.0048	0.2454
3/32	0.030	0.023	0.0088	0.0069	0.2945
7/64	0.041	0.032	0.0120	0.0094	0.3436
1/8	0.053	0.042	0.0156	0.0123	0.3927
9/64	0.067	0.053	0.0198	0.0155	0.4418
5/32	0.083	0.065	0.0244	0.0192	0.4909
11/64	0.100	0.079	0.0295	0.0232	0.5400
3/16	0.120	0.094	0.0352	0.0276	0.5890
13/64	0.140	0.110	0.0413	0.0324	0.6381
7/32	0.163	0.128	0.0479	0.0376	0.6872
15/64	0.187	0.147	0.0549	0.0431	0.7363
1/4	0.213	0.167	0.0625	0.0491	0.7854
17/64	0.240	0.188	0.0706	0.0554	0.8345
9/32	0.269	0.211	0.0791	0.0621	0.8836
19/64	0.300	0.235	0.0881	0.0692	0.9327
5/16	0.332	0.261	0.0977	0.0767	0.9817
11/32	0.402	0.316	0.1182	0.0928	1.0799
3/8	0.478	0.376	0.1406	0.1104	1.1781
13/32	0.561	0.441	0.1650	0.1296	1.2763
7/16	0.651	0.511	0.1914	0.1503	1.3744
15/32	0.747	0.587	0.2197	0.1726	1.4726
1/2	0.850	0.668	0.2500	0.1963	1.5708
17/32	0.960	0.754	0.2822	0.2217	1.6690
9/16	1.076	0.845	0.3164	0.2485	1.7671
19/32	1.199	0.941	0.3525	0.2769	1.8653
5/8	1.328	1.043	0.3906	0.3068	1.9635
11/16	1.607	1.262	0.4727	0.3712	2.1598
3/4	1.913	1.502	0.5625	0.4418	2.3562
13/16	2.245	1.763	0.6602	0.5185	2.5525
7/8	2.603	2.044	0.7656	0.6013	2.7489
15/16	2.989	2.347	0.8789	0.6903	2.9452

\* Adapted from the 1919 Edition of the Handbook of the Cambria Steel Company, Johnstown, Pa.

## Weights and Areas of Square and Round Steel Bars \*

Weights are for steel, at 489.6 lb per cu ft

Thick- ness, in	□		○		Thick- ness, in	□		○	
	Area, sq in	Weight per foot, lb	Area, sq in	Weight per foot, lb		Area, sq in	Weight per foot, lb	Area, sq in	Weight per foot, lb
1	1.000	3.400	0.785	2.670	3	9.000	30.60	7.069	24.03
$\frac{1}{8}$	1.129	3.838	0.887	3.014	$\frac{1}{8}$	9.379	31.89	7.366	25.04
$\frac{1}{4}$	1.266	4.303	0.994	3.379	$\frac{1}{4}$	9.766	33.20	7.670	26.08
$\frac{3}{8}$	1.410	4.795	1.108	3.766	$\frac{3}{8}$	10.16	34.55	7.980	27.13
$\frac{1}{2}$	1.563	5.312	1.227	4.173	$\frac{1}{2}$	10.56	35.92	8.296	28.20
$\frac{5}{8}$	1.723	5.857	1.353	4.600	$\frac{5}{8}$	10.97	37.31	8.618	29.30
$\frac{3}{4}$	1.891	6.428	1.485	5.049	$\frac{3}{4}$	11.39	38.73	8.946	30.42
$\frac{7}{8}$	2.066	7.026	1.623	5.518	$\frac{7}{8}$	11.82	40.18	9.281	31.56
$1\frac{1}{8}$	2.250	7.650	1.767	6.008	$1\frac{1}{8}$	12.25	41.65	9.621	32.71
$1\frac{1}{4}$	2.441	8.301	1.918	6.520	$1\frac{1}{4}$	12.69	43.14	9.968	33.90
$1\frac{1}{2}$	2.641	8.978	2.074	7.051	$1\frac{1}{2}$	13.14	44.68	10.32	35.09
$1\frac{3}{4}$	2.848	9.682	2.237	7.604	$1\frac{3}{4}$	13.60	46.24	10.68	36.31
$2\frac{1}{8}$	3.063	10.41	2.405	8.178	$2\frac{1}{8}$	14.06	47.82	11.05	37.56
$2\frac{1}{4}$	3.285	11.17	2.580	8.773	$2\frac{1}{4}$	14.54	49.42	11.42	38.81
$2\frac{1}{2}$	3.516	11.95	2.761	9.388	$2\frac{1}{2}$	15.02	51.05	11.79	40.10
$2\frac{3}{4}$	3.754	12.76	2.948	10.02	$2\frac{3}{4}$	15.50	52.71	12.18	41.40
2	4.000	13.60	3.142	10.68	4	16.00	54.40	12.57	42.73
$2\frac{1}{8}$	4.254	14.46	3.341	11.36	$2\frac{1}{8}$	16.50	56.11	12.96	44.07
$2\frac{1}{4}$	4.516	15.35	3.547	12.06	$2\frac{1}{4}$	17.02	57.85	13.36	45.44
$2\frac{1}{2}$	4.785	16.27	3.758	12.78	$2\frac{1}{2}$	17.54	59.62	13.77	46.83
$2\frac{3}{4}$	5.063	17.22	3.976	13.52	$2\frac{3}{4}$	18.06	61.41	14.19	48.24
$3\frac{1}{8}$	5.348	18.19	4.200	14.28	$3\frac{1}{8}$	18.60	63.23	14.61	49.66
$3\frac{1}{4}$	5.641	19.18	4.430	15.07	$3\frac{1}{4}$	19.14	65.08	15.03	51.11
$3\frac{1}{2}$	5.941	20.20	4.666	15.86	$3\frac{1}{2}$	19.69	66.95	15.47	52.58
$3\frac{3}{4}$	6.250	21.25	4.909	16.69	$3\frac{3}{4}$	20.25	68.85	15.90	54.07
$4\frac{1}{8}$	6.566	22.33	5.157	17.53	$4\frac{1}{8}$	20.82	70.78	16.35	55.59
$4\frac{1}{4}$	6.891	23.43	5.412	18.40	$4\frac{1}{4}$	21.39	72.73	16.80	57.12
$4\frac{1}{2}$	7.223	24.56	5.673	19.29	$4\frac{1}{2}$	21.97	74.70	17.26	58.67
$4\frac{3}{4}$	7.563	25.71	5.940	20.20	$4\frac{3}{4}$	22.56	76.71	17.72	60.25
$5\frac{1}{8}$	7.910	26.90	6.213	21.12	$5\frac{1}{8}$	23.16	78.74	18.19	61.84
$5\frac{1}{4}$	8.266	28.10	6.492	22.07	$5\frac{1}{4}$	23.77	80.81	18.67	63.46
$5\frac{1}{2}$	8.629	29.34	6.777	23.04	$5\frac{1}{2}$	24.38	82.89	19.15	65.10

\* Adapted from the 1919 Edition of the Handbook of the Cambria Steel Company  
 Johnstown, Pa.

Weights and Areas of Square and Round Steel Bars \* (Continued)

Weights are for steel, at 489.6 lb per cu ft

Thick- ness, in	□		○		Thick- ness, in	□		○	
	Area, sq in	Weight per foot, lb	Area, sq in	Weight per foot, lb		Area, sq in	Weight per foot, lb	Area, sq in	Weight per foot, lb
5	25.00	85.00	19.64	66.76	7	49.00	166.6	38.49	130.9
5 <sup>1</sup> / <sub>16</sub>	25.63	87.14	20.13	68.44	7 <sup>1</sup> / <sub>4</sub>	52.56	178.7	41.28	140.4
5 <sup>1</sup> / <sub>8</sub>	26.27	89.30	20.63	70.14	7 <sup>1</sup> / <sub>2</sub>	56.25	191.3	44.18	150.2
5 <sup>3</sup> / <sub>16</sub>	26.91	91.49	21.14	71.86	7 <sup>3</sup> / <sub>4</sub>	60.06	204.2	47.17	160.3
5 <sup>1</sup> / <sub>2</sub>	27.56	93.72	21.65	73.60	8	64.00	217.6	50.27	171.0
5 <sup>9</sup> / <sub>16</sub>	28.22	95.96	22.17	75.37	8 <sup>1</sup> / <sub>4</sub>	68.06	231.4	53.46	181.8
5 <sup>1</sup> / <sub>2</sub>	28.89	98.23	22.69	77.15	8 <sup>1</sup> / <sub>2</sub>	72.25	245.6	56.75	193.0
5 <sup>7</sup> / <sub>16</sub>	29.57	100.5	23.22	78.95	8 <sup>3</sup> / <sub>4</sub>	76.56	260.3	60.13	204.4
5 <sup>3</sup> / <sub>2</sub>	30.25	102.8	23.76	80.77	9	81.00	275.4	63.62	216.3
5 <sup>11</sup> / <sub>16</sub>	30.94	105.2	24.30	82.62	9 <sup>1</sup> / <sub>4</sub>	85.56	290.9	67.20	228.5
5 <sup>1</sup> / <sub>2</sub>	31.64	107.6	24.85	84.49	9 <sup>1</sup> / <sub>2</sub>	90.25	306.8	70.88	241.0
5 <sup>13</sup> / <sub>16</sub>	32.35	110.0	25.41	86.38	9 <sup>3</sup> / <sub>4</sub>	95.06	323.2	74.66	253.9
5 <sup>3</sup> / <sub>4</sub>	33.06	112.4	25.97	88.29	10	100.0	340.0	78.54	267.0
5 <sup>15</sup> / <sub>16</sub>	33.79	114.9	26.54	90.22	10 <sup>1</sup> / <sub>4</sub>	105.1	357.2	82.52	280.6
5 <sup>3</sup> / <sub>2</sub>	34.52	117.4	27.11	92.17	10 <sup>1</sup> / <sub>2</sub>	110.3	374.9	86.59	294.4
5 <sup>17</sup> / <sub>16</sub>	35.25	119.9	27.69	94.14	10 <sup>3</sup> / <sub>4</sub>	115.6	392.9	90.76	308.6
6	36.00	122.4	28.27	96.14	11	121.0	411.4	95.03	323.1
6 <sup>1</sup> / <sub>8</sub>	37.52	127.6	29.47	100.2	11 <sup>1</sup> / <sub>4</sub>	126.6	430.3	99.40	337.9
6 <sup>1</sup> / <sub>4</sub>	39.06	132.8	30.68	104.3	11 <sup>1</sup> / <sub>2</sub>	132.3	449.6	103.9	353.1
6 <sup>3</sup> / <sub>8</sub>	40.64	138.2	31.92	108.5	11 <sup>3</sup> / <sub>4</sub>	138.1	469.4	108.4	368.6
6 <sup>1</sup> / <sub>2</sub>	42.25	143.6	33.18	112.8	12	144.0	489.6	113.1	384.5
6 <sup>5</sup> / <sub>8</sub>	43.89	149.2	34.47	117.2	.....	.....	.....	.....	.....
6 <sup>3</sup> / <sub>2</sub>	45.56	154.9	35.79	121.7	.....	.....	.....	.....	.....
6 <sup>7</sup> / <sub>8</sub>	47.27	160.8	37.12	126.2	.....	.....	.....	.....	.....

\* Adapted from the 1919 Edition of the Handbook of the Cambria Steel Company, Johnstown, Pa.

## Weights in Pounds of Flat Rolled Steel Bars

PER LINEAR FOOT

One cubic foot of steel weighs 489.6 lb

For thicknesses from  $\frac{1}{16}$  in to  $\frac{9}{16}$  in and widths from  $\frac{1}{4}$  in to  $\frac{3}{4}$  in

Thickness, inches	Width of bar, inches								
	$\frac{1}{4}$	$\frac{5}{16}$	$\frac{3}{8}$	$\frac{7}{16}$	$\frac{1}{2}$	$\frac{9}{16}$	$\frac{5}{8}$	$1\frac{1}{16}$	$\frac{3}{4}$
$\frac{1}{16}$	0.053	0.066	0.080	0.093	0.106	0.120	0.133	0.146	0.159
$\frac{3}{64}$	0.066	0.083	0.100	0.116	0.133	0.149	0.166	0.183	0.199
$\frac{1}{32}$	0.080	0.100	0.120	0.139	0.159	0.179	0.199	0.219	0.239
$\frac{3}{64}$	0.093	0.116	0.139	0.163	0.186	0.209	0.232	0.256	0.279
$\frac{1}{8}$	0.106	0.133	0.159	0.186	0.212	0.239	0.266	0.292	0.319
$\frac{5}{64}$	0.120	0.149	0.179	0.209	0.239	0.269	0.299	0.329	0.359
$\frac{1}{16}$	0.133	0.166	0.199	0.232	0.266	0.299	0.332	0.365	0.398
$1\frac{1}{64}$	0.146	0.183	0.219	0.256	0.292	0.329	0.365	0.402	0.438
$\frac{3}{16}$	0.159	0.199	0.239	0.279	0.319	0.359	0.398	0.438	0.478
$1\frac{3}{64}$	0.173	0.216	0.259	0.302	0.345	0.388	0.432	0.475	0.518
$\frac{7}{32}$	0.186	0.232	0.279	0.325	0.372	0.418	0.465	0.511	0.558
$1\frac{5}{64}$	0.199	0.249	0.299	0.349	0.398	0.448	0.498	0.548	0.598
$\frac{1}{4}$	0.213	0.266	0.319	0.372	0.425	0.478	0.531	0.584	0.638
$1\frac{7}{64}$	0.226	0.282	0.339	0.395	0.452	0.508	0.564	0.621	0.677
$\frac{9}{32}$	0.239	0.299	0.359	0.418	0.478	0.538	0.598	0.657	0.717
$1\frac{9}{64}$	0.252	0.315	0.379	0.442	0.505	0.568	0.631	0.694	0.757
$\frac{5}{16}$	0.266	0.332	0.398	0.465	0.531	0.598	0.664	0.730	0.797
$2\frac{1}{64}$	0.279	0.349	0.418	0.488	0.558	0.628	0.697	0.767	0.827
$1\frac{1}{32}$	0.292	0.365	0.438	0.511	0.584	0.657	0.730	0.804	0.877
$2\frac{3}{64}$	0.305	0.382	0.458	0.535	0.611	0.687	0.764	0.840	0.916
$\frac{3}{8}$	0.319	0.398	0.478	0.558	0.638	0.717	0.797	0.877	0.956
$2\frac{5}{64}$	0.332	0.415	0.498	0.581	0.664	0.747	0.830	0.913	0.996
$1\frac{3}{32}$	0.345	0.432	0.518	0.604	0.691	0.777	0.863	0.950	1.04
$2\frac{7}{64}$	0.359	0.448	0.538	0.628	0.717	0.807	0.896	0.986	1.08
$\frac{7}{16}$	0.372	0.465	0.558	0.651	0.744	0.837	0.930	1.02	1.12
$2\frac{9}{64}$	0.385	0.481	0.578	0.674	0.770	0.867	0.963	1.06	1.16
$1\frac{5}{32}$	0.398	0.498	0.598	0.697	0.797	0.896	0.996	1.10	1.20
$2\frac{1}{64}$	0.412	0.515	0.618	0.721	0.823	0.926	1.03	1.13	1.24
$\frac{1}{2}$	0.425	0.531	0.638	0.744	0.850	0.956	1.06	1.17	1.28
$2\frac{3}{64}$	0.438	0.548	0.657	0.767	0.877	0.986	1.10	1.21	1.31
$1\frac{7}{32}$	0.452	0.564	0.677	0.790	0.903	1.02	1.13	1.24	1.35
$2\frac{5}{64}$	0.465	0.581	0.697	0.813	0.930	1.05	1.16	1.28	1.39
$\frac{9}{16}$	0.478	0.598	0.717	0.837	0.956	1.08	1.20	1.31	1.43

Weights in Pounds of Flat Rolled Steel Bars (Continued)

PER LINEAR FOOT

For thicknesses from 1/16 to 2 in and widths from 1 to 3 in

Thickness, inches	Width of bar, inches								
	1	1 1/4	1 1/2	1 3/4	2	2 1/4	2 1/2	2 3/4	3
1/16	0.21	0.26	0.32	0.37	0.43	0.48	0.53	0.58	0.63
1/8	0.42	0.53	0.64	0.75	0.85	0.96	1.06	1.17	1.28
3/16	0.63	0.79	0.96	1.11	1.28	1.44	1.59	1.75	1.91
1/4	0.85	1.06	1.28	1.49	1.70	1.91	2.12	2.34	2.55
5/16	1.06	1.33	1.59	1.86	2.12	2.39	2.65	2.92	3.19
3/8	1.28	1.59	1.92	2.23	2.55	2.87	3.19	3.51	3.83
7/16	1.49	1.86	2.23	2.60	2.98	3.35	3.72	4.09	4.46
1/2	1.70	2.12	2.55	2.98	3.40	3.83	4.25	4.67	5.10
9/16	1.92	2.39	2.87	3.35	3.83	4.30	4.78	5.26	5.74
5/8	2.12	2.65	3.19	3.72	4.25	4.78	5.31	5.84	6.38
11/16	2.34	2.92	3.51	4.09	4.67	5.26	5.84	6.43	7.02
3/4	2.55	3.19	3.83	4.47	5.10	5.75	6.38	7.02	7.65
13/16	2.76	3.45	4.14	4.84	5.53	6.21	6.90	7.60	8.29
7/8	2.98	3.72	4.47	5.20	5.95	6.69	7.44	8.18	8.93
15/16	3.19	3.99	4.78	5.58	6.38	7.18	7.97	8.77	9.57
1	3.40	4.25	5.10	5.95	6.80	7.65	8.50	9.35	10.20
1 1/16	3.61	4.52	5.42	6.32	7.22	8.13	9.03	9.93	10.84
1 1/8	3.83	4.78	5.74	6.70	7.65	8.61	9.57	10.52	11.48
1 3/16	4.04	5.05	6.06	7.07	8.08	9.09	10.10	11.11	12.12
1 1/4	4.25	5.31	6.38	7.44	8.50	9.57	10.63	11.69	12.75
1 5/16	4.46	5.58	6.69	7.81	8.93	10.04	11.16	12.27	13.39
1 3/8	4.67	5.84	7.02	8.18	9.35	10.52	11.69	12.85	14.03
1 7/16	4.89	6.11	7.34	8.56	9.78	11.00	12.22	13.44	14.66
1 1/2	5.10	6.38	7.65	8.93	10.20	11.48	12.75	14.03	15.30
1 9/16	5.32	6.64	7.97	9.30	10.63	11.95	13.28	14.61	15.94
1 5/8	5.52	6.90	8.29	9.67	11.05	12.43	13.81	15.19	16.58
1 11/16	5.74	7.17	8.61	10.04	11.47	12.91	14.34	15.78	17.22
1 3/4	5.95	7.44	8.93	10.42	11.90	13.40	14.88	16.37	17.85
1 13/16	6.16	7.70	9.24	10.79	12.33	13.86	15.40	16.95	18.49
1 7/8	6.38	7.97	9.57	11.15	12.75	14.34	15.94	17.53	19.13
1 15/16	6.59	8.24	9.88	11.53	13.18	14.83	16.47	18.12	19.77
2	6.80	8.50	10.20	11.90	13.60	15.30	17.00	18.70	20.40



## Weights in Pounds of Flat Rolled Steel Bars (Continued)

PER LINEAR FOOT

For thicknesses from  $\frac{1}{16}$  to 2 in and widths from  $3\frac{1}{2}$  to  $7\frac{1}{2}$  in

Thickness, inches	Width of bar, inches								
	$3\frac{1}{2}$	4	$4\frac{1}{2}$	5	$5\frac{1}{2}$	6	$6\frac{1}{2}$	7	$7\frac{1}{2}$
$\frac{1}{16}$	0.75	0.85	0.96	1.06	1.17	1.28	1.39	1.49	1.60
$\frac{1}{8}$	1.49	1.70	1.92	2.13	2.34	2.55	2.77	2.98	3.19
$\frac{3}{16}$	2.23	2.55	2.87	3.19	3.51	3.83	4.14	4.46	4.78
$\frac{1}{4}$	2.98	3.40	3.83	4.25	4.67	5.10	5.53	5.95	6.36
$\frac{5}{16}$	3.72	4.25	4.78	5.31	5.84	6.38	6.90	7.44	7.97
$\frac{3}{8}$	4.47	5.10	5.74	6.38	7.02	7.65	8.29	8.93	9.57
$\frac{7}{16}$	5.20	5.95	6.70	7.44	8.18	8.93	9.67	10.41	11.16
$\frac{1}{2}$	5.95	6.80	7.65	8.50	9.35	10.20	11.05	11.90	12.75
$\frac{9}{16}$	6.70	7.65	8.61	9.57	10.52	11.48	12.43	13.39	14.34
$\frac{5}{8}$	7.44	8.50	9.57	10.63	11.69	12.75	13.81	14.87	15.94
$1\frac{1}{16}$	8.18	9.35	10.52	11.69	12.85	14.03	15.20	16.36	17.53
$\frac{3}{4}$	8.93	10.20	11.48	12.75	14.03	15.30	16.58	17.85	19.13
$1\frac{1}{8}$	9.67	11.05	12.43	13.81	15.19	16.58	17.95	19.34	20.72
$\frac{7}{8}$	10.41	11.90	13.39	14.87	16.36	17.85	19.34	20.83	22.32
$1\frac{1}{4}$	11.16	12.75	14.34	15.94	17.53	19.13	20.72	22.32	23.91
1	11.90	13.60	15.30	17.00	18.70	20.40	22.10	23.80	25.50
$1\frac{1}{8}$	12.65	14.45	16.26	18.06	19.87	21.68	23.48	25.29	27.10
$1\frac{1}{4}$	13.39	15.30	17.22	19.13	21.04	22.95	24.87	26.78	28.68
$1\frac{3}{8}$	14.13	16.15	18.17	20.19	22.21	24.23	26.24	28.26	30.28
$1\frac{1}{2}$	14.87	17.00	19.13	21.25	23.38	25.50	27.62	29.75	31.88
$1\frac{5}{8}$	15.62	17.85	20.08	22.32	24.54	26.78	29.01	31.23	33.48
$1\frac{3}{4}$	16.36	18.70	21.04	23.38	25.71	28.05	30.39	32.72	35.06
$1\frac{7}{8}$	17.10	19.85	21.99	24.44	26.88	29.33	31.77	34.21	36.66
$1\frac{1}{2}$	17.85	20.40	22.95	25.50	28.05	30.60	33.15	35.70	38.26
$1\frac{9}{8}$	18.60	21.25	23.91	26.57	29.22	31.88	34.53	37.19	39.84
$1\frac{3}{4}$	19.34	22.10	24.87	27.63	30.39	33.15	35.91	38.67	41.44
$1\frac{11}{16}$	20.08	22.95	25.82	28.69	31.55	34.43	37.30	40.16	43.03
$1\frac{3}{4}$	20.83	23.80	26.78	29.75	32.73	35.70	38.68	41.65	44.63
$1\frac{13}{16}$	21.57	24.65	27.73	30.81	33.89	36.98	40.05	43.14	46.22
$1\frac{7}{8}$	22.31	25.50	28.69	31.87	35.06	38.25	41.44	44.63	47.82
$1\frac{15}{16}$	23.06	26.35	29.64	32.94	36.23	39.53	42.82	46.12	49.41
2	23.80	27.20	30.60	34.00	37.40	40.80	44.20	47.60	51.00

**Weights in Pounds of Flat Rolled Steel Bars (Continued)**

PER LINEAR FOOT

For thicknesses from 1/16 to 2 in and widths from 8 to 12 in

Thickness, inches	Width of bar, inches								
	8	8½	9	9½	10	10½	11	11½	12
1/16	1.70	1.81	1.91	2.02	2.13	2.23	2.34	2.45	2.55
1/8	3.40	3.61	3.82	4.04	4.25	4.46	4.68	4.89	5.10
3/16	5.10	5.42	5.74	6.06	6.38	6.70	7.02	7.32	7.65
1/4	6.80	7.22	7.65	8.08	8.50	8.92	9.34	9.78	10.20
5/16	8.50	9.03	9.56	10.10	10.62	11.16	11.68	12.22	12.75
3/8	10.20	10.84	11.48	12.12	12.75	13.39	14.03	14.68	15.30
7/16	11.90	12.64	13.40	14.14	14.88	15.62	16.36	17.12	17.85
1/2	13.60	14.44	15.30	16.16	17.00	17.85	18.70	19.55	20.40
9/16	15.30	16.26	17.22	18.18	19.14	20.08	21.02	22.00	22.95
5/8	17.00	18.06	19.13	20.19	21.25	22.32	23.38	24.44	25.50
11/16	18.70	19.86	21.04	22.21	23.38	24.51	25.70	26.88	28.05
3/4	20.40	21.68	22.96	24.23	25.50	26.78	28.05	29.33	30.60
13/16	22.10	23.48	24.86	26.24	27.62	29.00	30.40	31.76	33.15
7/8	23.80	25.30	26.78	28.26	29.75	31.24	32.72	34.21	35.70
15/16	25.50	27.10	28.69	30.28	31.83	33.48	35.06	36.66	38.25
1	27.20	28.90	30.60	32.30	34.00	35.70	37.40	39.10	40.80
1 1/16	28.90	30.70	32.52	34.32	36.12	37.92	39.74	41.54	43.35
1 1/8	30.60	32.52	34.43	36.34	38.25	40.17	42.08	44.00	45.90
1 1/4	32.30	34.32	36.34	38.36	40.38	42.40	44.42	46.44	48.45
1 1/2	34.00	36.12	38.26	40.37	42.50	44.63	46.76	48.88	51.00
1 5/8	35.70	37.93	40.16	42.40	44.64	46.86	49.08	51.32	53.55
1 3/4	37.40	39.74	42.08	44.41	46.75	49.08	51.42	53.76	56.10
1 7/8	39.10	41.54	44.00	46.44	48.88	51.32	53.76	56.21	58.65
1 1/2	40.80	43.35	45.90	48.45	51.00	53.55	56.10	58.65	61.20
1 9/16	42.50	45.16	47.82	50.48	53.14	55.78	58.42	61.10	63.75
1 5/8	44.20	46.96	49.73	52.49	55.25	58.02	60.78	63.54	66.30
1 11/16	45.90	48.76	51.64	54.51	57.38	60.24	63.10	65.98	68.85
1 3/4	47.60	50.58	53.56	56.53	59.50	62.48	65.45	68.43	71.40
1 13/16	49.30	52.38	55.46	58.54	61.62	64.70	67.80	70.86	73.95
1 7/8	51.00	54.20	57.38	60.56	63.75	66.94	70.12	73.31	76.50
1 15/16	52.70	56.00	59.29	62.58	65.88	69.18	72.46	75.76	79.05
2	54.40	57.80	61.20	64.60	68.00	71.40	74.80	78.20	81.60

# Rules for Estimating the Weight of any Piece of Wrought Iron, Steel or Cast Iron

## Wrought Iron.

One cubic foot of wrought iron weighs.....	480 lb
One square foot, one inch thick, weighs.....	40 lb
One square inch, one foot long, weighs.....	3¼ lb

To find the weight per square foot of sheet iron, multiply the thickness in inches by 40.

To find the weight per linear foot of bars of any section, multiply the cross-sectional area in square inches by 3¼.

## Steel.

One cubic foot of steel weighs.....	489.6 lb
(Or just 2% more than wrought iron.)	
One square foot, one inch thick, weighs.....	40.8 lb
One square inch, one foot long, weighs.....	3.4 lb

To find the weight per linear foot, of bars of any section, multiply the cross-sectional area in square inches by 3.4; or, if the weight is known, the exact sectional area may be obtained by dividing by 3.4.

## Cast Iron.

One cubic foot of cast iron weighs.....	450 lb
One square foot, one inch thick, weighs.....	37¼ lb
One square inch, one foot long, weighs.....	3¼ lb
One cubic inch weighs.....	0.26 lb

The weight of irregular castings must be estimated by the cubic inch.

## Rules for Weights of Castings

Multiply the weight of the pattern by 18 for cast iron, 13 for brass, 19 for lead, 12.2 for tin, 11.4 for zinc; the product is the weight of the casting.

## Reduction for Round Cores and Core-Prints

**Rule.** Multiply the square of the diameter by the length of the core in inches, and the product multiplied by 0.017 is the weight of the pine core to be deducted from the weight of the pattern.

## Shrinkage in Castings

Pattern-makers' Rule	{	Cast iron... ¼	}	of an inch longer per linear foot
		Brass..... ⅜		
		Lead..... ½		
		Tin..... ⅝		
		Zinc..... ¾		

Weights of Square Cast-Iron Columns in Pounds per Linear Foot \*

$a \square b$ $2a + 2b$ $\uparrow$	Thickness of metal, inches								
	$\frac{5}{8}$ in. lb	$\frac{3}{4}$ in. lb	$\frac{7}{8}$ in. lb	1 in. lb	1 $\frac{1}{8}$ in. lb	1 $\frac{1}{4}$ in. lb	1 $\frac{1}{2}$ in. lb	1 $\frac{3}{4}$ in. lb	2 in. lb
12	18.6	21.1	23.3	25.0	26.4	27.3	28.1	.....	.....
14	22.5	25.8	28.7	31.3	33.4	35.1	37.5	.....	.....
16	26.4	30.5	34.2	37.5	40.4	43.0	46.9	49.2	50.0
18	30.3	35.2	39.7	43.8	47.4	50.8	56.3	60.2	62.5
20	34.2	39.8	45.1	50.0	54.5	58.6	65.6	71.1	75.0
22	38.1	44.5	50.6	56.3	61.5	66.4	75.0	82.0	87.5
24	42.0	49.2	56.1	62.5	68.5	74.2	84.4	93.0	100.0
26	45.9	53.9	61.5	68.8	75.6	82.0	93.8	103.9	112.5
28	49.8	58.6	67.0	75.0	82.6	89.8	103.1	114.8	125.0
30	53.7	63.3	72.5	81.3	89.6	97.7	112.5	125.8	137.5
32	57.6	68.0	77.9	87.5	96.7	105.5	121.9	136.7	150.0
34	61.5	72.7	83.4	93.8	103.7	113.3	131.3	147.7	162.5
36	65.4	77.3	88.9	100.0	110.7	121.1	140.6	158.6	175.0
38	69.3	82.0	94.3	106.3	117.8	128.9	150.0	169.5	187.5
40	73.2	86.7	99.8	112.5	124.8	136.7	159.4	180.5	200.0
42	77.1	91.4	105.3	118.8	131.8	144.5	168.8	191.4	212.5
44	81.0	96.1	110.8	125.0	138.8	152.3	178.1	202.3	225.0
46	84.9	100.8	116.2	131.3	145.9	160.2	187.5	213.3	237.5
48	88.8	105.5	121.7	137.5	152.9	168.0	196.9	224.2	250.0
50	92.8	110.2	127.2	143.8	159.9	175.8	206.3	235.2	262.5
52	96.7	114.8	132.6	150.0	167.0	183.6	215.6	246.1	275.0
54	100.6	119.5	138.1	156.3	174.0	191.4	225.0	257.0	287.5
56	104.5	124.2	143.6	162.5	181.0	199.2	234.4	268.0	300.0
58	108.4	128.9	149.0	168.8	188.1	207.0	243.8	278.9	312.5
60	112.3	133.6	154.5	175.0	195.1	214.9	253.2	289.8	325.0
62	116.2	138.3	160.0	181.3	202.1	222.7	262.5	300.8	337.5
64	120.1	143.0	165.4	187.5	209.2	230.5	271.9	311.7	350.0
66	124.0	147.7	170.9	193.8	216.2	238.3	281.3	322.7	362.5
68	127.9	152.3	176.4	200.0	223.2	246.1	290.6	333.6	375.0
70	131.8	157.0	181.8	206.3	230.3	253.9	300.0	344.5	387.5
72	135.7	161.7	187.3	212.5	237.3	261.7	309.4	355.5	400.0
74	139.6	166.4	192.8	218.8	244.3	269.5	318.8	366.4	412.5
76	143.5	171.1	198.3	225.0	251.3	277.3	328.1	377.3	425.0
78	147.4	175.8	203.7	231.3	258.4	285.2	337.5	388.3	437.5
80	151.3	180.5	207.2	237.5	265.4	293.0	346.9	399.2	450.0

\* Birkmire.

†  $a$  and  $b$  = either side, outside measurement.  $2a + 2b$  = number. Allowance has been made in this table for corners counted twice.

**Example.** What is the weight per linear foot of a 12 by 16 by 1 in thick column?

**Solution.**  $2a + 2b = 24 + 32 = 56$ . Opposite this number, under 1-in-thick metal, we find 162.5, or weight per linear foot of a column 12 by 16 by 1-in-thick.

**Note.** For flanges, brackets, etc., calculate the cubical contents of same and multiply by 0.26; cast iron averages 450 lb per cu ft.

## Weights per Linear Foot of Circular Cast-Iron Columns \* †

Outside diameter, inches	Thickness of metal, inches							
	½ in, lb	¾ in, lb	¾ in, lb	¾ in, lb	1 in, lb	1 ¼ in, lb	1 ½ in, lb	1 ¾ in, lb
3	12.3	14.6	16.60	18.30	19.6	.....	.....	.....
4	17.2	21.0	24.00	27.00	29.5	32.1	33.8	35.4
5	22.1	27.0	31.30	35.50	39.3	43.0	46.0	49.0
6	27.0	33.0	39.00	44.00	49.1	54.1	58.3	62.4
7	32.0	39.1	46.00	53.00	59.0	65.1	70.6	76.1
8	36.8	45.3	53.40	61.20	69.1	76.1	83.1	89.5
9	41.7	51.4	61.10	70.00	78.6	87.1	95.1	103.1
10	46.6	57.5	68.13	78.41	88.4	98.0	107.4	116.4
11	51.6	64.0	75.50	87.10	98.2	109.1	120.1	130.1
12	56.5	70.0	82.87	96.10	108.0	120.0	132.1	143.5
13	61.4	76.0	90.23	104.20	118.1	131.2	144.2	157.1
14	66.3	82.1	97.60	113.20	128.1	142.0	156.5	170.4
15	71.2	88.2	104.96	121.40	137.5	153.3	169.4	184.1
16	76.1	94.4	112.33	130.10	147.3	164.3	181.0	197.4
17	81.0	100.5	120.10	139.10	157.1	175.4	193.3	211.0
18	86.0	107.0	127.00	147.00	167.0	186.4	206.0	224.4
19	91.0	113.0	134.40	156.00	177.1	197.5	218.1	238.0
20	96.0	119.0	142.10	164.30	186.6	208.8	230.1	251.5
21	100.6	125.0	149.10	173.10	196.6	219.6	242.4	265.0
22	105.6	131.2	156.50	181.50	206.2	230.6	255.0	278.0
23	110.5	137.3	164.10	190.10	216.1	242.0	267.0	292.0
24	115.4	143.5	171.20	199.00	226.0	253.0	279.2	305.4

Outside diameter, inches	Thickness of metal, inches							
	1 ¼ in, lb	1 ½ in, lb	1 ¾ in, lb	1 ¾ in, lb	2 in, lb	2 ¼ in, lb	2 ½ in, lb	2 ¾ in, lb
3	.....	.....	.....	.....	.....	.....	.....	.....
4	.....	.....	.....	.....	.....	.....	.....	.....
5	51.54	54.1	55.84	57.5	.....	.....	.....	.....
6	66.30	69.9	73.02	76.0	78.6	80.84	82.83	.....
7	81.00	85.6	90.20	94.3	98.2	101.70	105.00	107.84
8	95.80	101.8	107.40	112.8	117.8	122.60	127.00	131.20
9	110.50	117.7	124.60	131.2	137.5	143.40	149.10	154.50
10	125.20	133.7	142.00	149.6	157.1	164.30	171.20	177.80
11	140.00	149.6	159.00	168.0	176.8	185.20	193.30	201.10
12	154.70	165.6	176.00	186.4	196.4	206.00	215.40	224.40
13	169.40	181.5	193.30	204.8	216.0	226.90	237.50	247.70
14	184.10	197.4	210.50	223.2	235.7	247.70	259.60	271.10
15	198.90	213.4	227.70	241.6	255.3	268.20	281.70	294.40
16	213.50	229.4	244.90	260.0	274.9	289.50	303.70	317.70
17	228.30	245.3	262.00	278.4	294.5	310.30	325.80	341.00
18	243.00	261.3	279.20	296.8	314.2	331.20	348.00	364.30
19	257.70	277.2	296.40	315.2	338.8	352.10	370.00	387.70
20	272.50	293.2	313.60	333.6	353.4	372.90	392.10	411.00
21	287.20	309.0	330.80	352.1	373.1	393.80	414.20	434.30
22	302.00	325.1	348.00	370.5	393.0	414.60	436.30	457.60
23	316.70	341.0	365.10	388.9	412.3	435.50	458.40	481.00
24	331.40	357.0	382.30	407.3	432.0	456.40	480.50	504.20

\* Birkmire.

† The table is arranged for the weight of plain shaft. For brackets, flanges, etc., calculate the cubical contents and multiply by 0.26.

Weight of Cast-Iron Plates

Weights, in Pounds, of Cast-Iron Plates One Inch Thick  
Calculated at 450 lb per cu ft

Length, inches	Width, inches									
	6 in, lb	8 in, lb	10 in, lb	12 in, lb	14 in, lb	16 in, lb	18 in, lb	20 in, lb	24 in, lb	30 in, lb
4	6.25	8.3	10.4	12.5	14.6	16.6	18.7	20.8	25	31
6	9.37	12.5	15.6	18.7	21.8	25.0	28.1	31.2	38	47
8	12.50	16.6	20.8	25.0	29.1	33.3	37.4	41.6	50	62
10	15.60	20.8	26.0	31.2	36.4	41.6	46.8	52.0	63	78
12	18.70	25.0	31.2	37.5	43.7	49.9	56.2	62.4	75	94
14	21.80	29.2	36.4	43.7	51.0	58.2	65.5	72.8	88	109
16	24.90	33.3	41.6	50.0	58.2	66.6	74.9	83.2	100	125
18	28.10	37.5	46.8	56.2	65.5	74.9	84.2	93.6	113	140
20	31.20	41.6	52.0	62.3	72.8	83.2	93.6	104.0	125	156
22	34.30	45.8	57.2	68.6	80.1	91.5	103.0	114.4	138	172
24	37.50	50.0	62.4	75.0	87.4	99.8	112.3	124.8	150	187
26	40.60	54.0	67.6	81.2	94.6	108.2	121.7	135.2	163	203
28	43.60	58.2	72.8	87.5	101.9	116.5	131.0	145.6	175	218
30	46.80	62.4	78.0	93.7	109.2	124.8	140.4	156.0	188	234
32	49.80	66.6	83.2	100.0	116.5	133.1	150.3	166.4	200	250
36	56.10	75.0	93.6	112.5	131.0	150.0	168.4	187.2	225	281

For larger plates take size of plate ONE-HALF smaller and multiply by 2. Thus a plate 28 by 32 in will weigh twice as much as one 14 by 32 in. For plates more or less than one inch in thickness multiply weight of plate by thickness in inches.

Approximate Weights of Square-Ribbed Cast-Iron Column-Bases

The following table, giving the weight of cast-iron column-bases, will be useful when estimating the steel and iron in tall buildings.\*


Size of square base, in	Weight, lb	Size of square base, in	Weight, lb
22×22	600	32×32	1 340
24×24	750	34×34	1 450
26×26	880	36×36	1 600
28×28	1 020	38×38	1 720
30×30	1 180	40×40	1 850

\* H. G. Tyrrell, in Architects and Builders Magazine, January, 1903.

## Screw-Threads, Nuts, and Bolt-Heads

## Standard Screw-Threads

Recommended by Franklin Institute, December 15, 1864, and adopted by Navy Department of the United States; by the R. R. Master Mechanics' and Master Car-Builders' Associations; by Jones & Laughlin Steel Company; and by many other of the prominent engineering and mechanical establishments of the country.



Angle of thread 60°. Flat at top and bottom  $\frac{1}{8}$  of pitch.

Diam of screw, in	Threads per inch	Diam at root of thread, in	Area at root of thread, sq in	Diam of screw, in	Threads per inch	Diam at root of thread, in	Area at root of thread, sq in
$\frac{1}{4}$	20	0.185	0.027	2	$4\frac{1}{2}$	1.712	2.302
$\frac{5}{16}$	18	0.240	0.045	$2\frac{1}{4}$	$4\frac{1}{2}$	1.962	3.023
$\frac{3}{8}$	16	0.294	0.068	$2\frac{1}{2}$	4	2.176	3.719
$\frac{7}{16}$	14	0.344	0.093	$2\frac{3}{4}$	4	2.426	4.620
$\frac{1}{2}$	13	0.400	0.126	3	$3\frac{1}{2}$	2.629	5.428
$\frac{9}{16}$	12	0.454	0.162	$3\frac{1}{4}$	$3\frac{1}{2}$	2.879	6.510
$\frac{5}{8}$	11	0.507	0.202	$3\frac{1}{2}$	$3\frac{1}{4}$	3.100	7.548
$\frac{3}{4}$	10	0.620	0.302	$3\frac{3}{4}$	3	3.317	8.641
$\frac{7}{8}$	9	0.731	0.420	4	3	3.567	9.963
1	8	0.837	0.550	$4\frac{1}{4}$	$2\frac{7}{8}$	3.798	11.329
$1\frac{1}{8}$	7	0.940	0.694	$4\frac{1}{2}$	$2\frac{3}{4}$	4.028	12.753
$1\frac{1}{4}$	7	1.065	0.893	$4\frac{3}{4}$	$2\frac{5}{8}$	4.256	14.226
$1\frac{3}{8}$	6	1.160	1.057	5	$2\frac{1}{2}$	4.480	15.763
$1\frac{1}{2}$	6	1.284	1.295	$5\frac{1}{4}$	$2\frac{1}{2}$	4.730	17.572
$1\frac{5}{8}$	$5\frac{1}{2}$	1.389	1.515	$5\frac{1}{2}$	$2\frac{3}{8}$	4.953	19.267
$1\frac{3}{4}$	5	1.491	1.746	$5\frac{3}{4}$	$2\frac{3}{8}$	5.203	21.262
$1\frac{7}{8}$	5	1.616	2.051	6	$2\frac{1}{4}$	5.423	23.098

**Nuts and Bolt-Heads** are determined by the following rules, which apply to both square and hexagon nuts:

Short diameter of rough nut =  $1\frac{1}{2} \times$  diam of bolt +  $\frac{1}{8}$  in.

Short diameter of finished nut =  $1\frac{1}{2} \times$  diam of bolt +  $\frac{1}{16}$  in.

Thickness of rough nut = diam of bolt.

Thickness of finished nut = diam of bolt -  $\frac{1}{16}$  in.

Short diameter of rough head =  $1\frac{1}{2} \times$  diam of bolt +  $\frac{1}{8}$  in.








Short diameter of finished head =  $1\frac{1}{2} \times$  diam of bolt +  $\frac{1}{16}$  in.

Thickness of rough head =  $\frac{1}{2}$  short diam of head.

Thickness of finished head = diam of bolt -  $\frac{1}{16}$  in.

The long diameter of a hexagon nut may be determined by multiplying the short diameter by 1.155, and the long diameter of a square nut by multiplying the short diameter by 1.414.

## Standard Dimensions of Nuts and Bolt-Heads

Diam of bolt	Short diam, rough 	Short diam, finished 	Long diam, rough 	Long diam, rough 	Thick- ness, rough. Nut 	Thick- ness, finished. Both 	Thick- ness, rough. Head 
$\frac{3}{4}$	$\frac{1}{2}$	$\frac{7}{16}$	$2\frac{7}{64}$	$\frac{7}{16}$	$\frac{1}{4}$	$\frac{3}{16}$	$\frac{3}{4}$
$5\frac{1}{16}$	$1\frac{9}{32}$	$1\frac{7}{32}$	$1\frac{1}{16}$	$1\frac{9}{16}$	$5\frac{1}{16}$	$\frac{1}{4}$	$1\frac{9}{16}$
$\frac{3}{8}$	$1\frac{1}{16}$	$\frac{5}{8}$	$5\frac{1}{64}$	$6\frac{3}{64}$	$\frac{3}{8}$	$5\frac{1}{16}$	$1\frac{1}{32}$
$\frac{7}{16}$	$2\frac{3}{32}$	$2\frac{3}{32}$	$\frac{9}{16}$	$1\frac{7}{64}$	$\frac{7}{16}$	$\frac{3}{8}$	$2\frac{3}{64}$
$\frac{1}{2}$	$\frac{7}{8}$	$1\frac{3}{16}$	1	$1\frac{1}{64}$	$\frac{1}{2}$	$\frac{7}{16}$	$\frac{7}{16}$
$9\frac{1}{16}$	$2\frac{1}{32}$	$2\frac{9}{32}$	$1\frac{1}{8}$	$1\frac{3}{64}$	$9\frac{1}{16}$	$\frac{1}{2}$	$2\frac{1}{64}$
$\frac{5}{8}$	$1\frac{1}{16}$	1	$1\frac{7}{32}$	$1\frac{1}{2}$	$\frac{5}{8}$	$9\frac{1}{16}$	$1\frac{1}{32}$
$\frac{3}{4}$	$1\frac{1}{4}$	$1\frac{3}{16}$	$1\frac{7}{16}$	$1\frac{9}{64}$	$\frac{3}{4}$	$1\frac{1}{16}$	$\frac{5}{8}$
$\frac{7}{8}$	$1\frac{7}{16}$	$1\frac{3}{8}$	$1\frac{1}{32}$	$2\frac{1}{32}$	$\frac{7}{8}$	$1\frac{3}{16}$	$2\frac{3}{32}$
1	$1\frac{3}{8}$	$1\frac{9}{16}$	$1\frac{7}{8}$	$2\frac{1}{64}$	1	$1\frac{5}{16}$	$1\frac{3}{16}$
$1\frac{1}{8}$	$1\frac{1}{32}$	$1\frac{3}{4}$	$2\frac{3}{32}$	$2\frac{9}{16}$	$1\frac{1}{8}$	$1\frac{1}{16}$	$2\frac{9}{32}$
$1\frac{1}{4}$	2	$1\frac{3}{16}$	$2\frac{1}{16}$	$2\frac{3}{64}$	$1\frac{1}{4}$	$1\frac{3}{16}$	1
$1\frac{3}{8}$	$2\frac{3}{16}$	$2\frac{3}{8}$	$2\frac{1}{32}$	$3\frac{3}{32}$	$1\frac{3}{8}$	$1\frac{5}{16}$	$1\frac{1}{32}$
$1\frac{1}{2}$	$2\frac{3}{8}$	$2\frac{5}{16}$	$2\frac{3}{4}$	$3\frac{3}{64}$	$1\frac{1}{2}$	$1\frac{7}{16}$	$1\frac{3}{16}$
$1\frac{5}{8}$	$2\frac{9}{16}$	$2\frac{1}{2}$	$2\frac{1}{32}$	$3\frac{5}{8}$	$1\frac{5}{8}$	$1\frac{9}{16}$	$1\frac{9}{32}$
$1\frac{3}{4}$	$2\frac{3}{4}$	$2\frac{1}{16}$	$3\frac{1}{16}$	$3\frac{5}{64}$	$1\frac{3}{4}$	$1\frac{1}{16}$	$1\frac{7}{8}$
$1\frac{7}{8}$	$2\frac{5}{16}$	$2\frac{7}{8}$	$3\frac{1}{32}$	$4\frac{1}{32}$	$1\frac{7}{8}$	$1\frac{3}{16}$	$1\frac{5}{32}$
2	$3\frac{1}{8}$	$3\frac{1}{16}$	$3\frac{5}{8}$	$4\frac{2}{64}$	2	$1\frac{5}{16}$	$1\frac{9}{16}$
$2\frac{1}{4}$	$3\frac{3}{8}$	$3\frac{7}{16}$	$4\frac{1}{16}$	$4\frac{1}{64}$	$2\frac{1}{4}$	$2\frac{3}{16}$	$1\frac{3}{4}$
$2\frac{1}{2}$	$3\frac{7}{8}$	$3\frac{3}{16}$	$4\frac{1}{2}$	$5\frac{1}{64}$	$2\frac{1}{2}$	$2\frac{7}{16}$	$1\frac{5}{16}$
$2\frac{3}{4}$	$4\frac{1}{4}$	$4\frac{3}{16}$	$4\frac{2}{32}$	6	$2\frac{3}{4}$	$2\frac{1}{16}$	$2\frac{3}{8}$
3	$4\frac{3}{8}$	$4\frac{9}{16}$	$5\frac{3}{8}$	$6\frac{1}{32}$	3	$2\frac{5}{16}$	$2\frac{5}{16}$
$3\frac{1}{4}$	5	$4\frac{5}{16}$	$5\frac{1}{16}$	$7\frac{1}{16}$	$3\frac{1}{4}$	$3\frac{3}{16}$	$2\frac{1}{2}$
$3\frac{1}{2}$	$5\frac{3}{8}$	$5\frac{5}{16}$	$6\frac{7}{64}$	$7\frac{3}{64}$	$3\frac{1}{2}$	$3\frac{7}{16}$	$2\frac{1}{16}$
$3\frac{3}{4}$	$5\frac{3}{4}$	$5\frac{1}{16}$	$6\frac{1}{32}$	$8\frac{1}{8}$	$3\frac{3}{4}$	$3\frac{1}{16}$	$2\frac{3}{8}$
4	$6\frac{1}{8}$	$6\frac{1}{16}$	$7\frac{3}{8}$	$8\frac{1}{64}$	4	$3\frac{5}{16}$	$3\frac{1}{16}$
$4\frac{1}{4}$	$6\frac{1}{2}$	$7\frac{7}{16}$	$7\frac{9}{16}$	$9\frac{3}{16}$	$4\frac{1}{4}$	$4\frac{3}{16}$	$3\frac{1}{4}$
$4\frac{1}{2}$	$6\frac{3}{8}$	$6\frac{3}{16}$	$7\frac{1}{32}$	$9\frac{1}{4}$	$4\frac{1}{2}$	$4\frac{7}{16}$	$3\frac{3}{16}$
$4\frac{3}{4}$	$7\frac{1}{4}$	$7\frac{3}{16}$	$8\frac{1}{32}$	$10\frac{1}{4}$	$4\frac{3}{4}$	$4\frac{1}{16}$	$3\frac{5}{8}$
5	$7\frac{3}{8}$	$7\frac{9}{16}$	$8\frac{2}{32}$	$10\frac{1}{64}$	5	$4\frac{5}{16}$	$3\frac{1}{16}$
$5\frac{1}{4}$	8	$7\frac{5}{16}$	$9\frac{9}{32}$	$11\frac{3}{64}$	$5\frac{1}{4}$	$5\frac{3}{16}$	4
$5\frac{1}{2}$	$8\frac{3}{8}$	$8\frac{5}{16}$	$9\frac{3}{32}$	$11\frac{7}{8}$	$5\frac{1}{2}$	$5\frac{7}{16}$	$4\frac{3}{16}$
$5\frac{3}{4}$	$8\frac{3}{4}$	$8\frac{1}{16}$	$10\frac{1}{32}$	$12\frac{3}{8}$	$5\frac{3}{4}$	$5\frac{1}{16}$	$4\frac{7}{8}$
6	$9\frac{1}{8}$	$9\frac{1}{16}$	$10\frac{1}{64}$	$12\frac{1}{16}$	6	$5\frac{5}{16}$	$4\frac{9}{16}$



## Weights of One Hundred Bolts With Square Heads and Nuts

INCLUDES WEIGHT OF NUT

Hoopes &amp; Townsend's List

Length under head to point in	Diameter of bolts								
	¼ in.	⅜ in.	½ in.	⅝ in.	¾ in. lb	⅞ in. lb	¾ in. lb	⅞ in. lb	1 in. lb
1½	4.00	7.00	10.50	15.20	22.50	39.50	63.00	.....	.....
1¾	4.40	7.50	11.25	16.30	23.82	41.62	66.00	.....	.....
2	4.75	8.00	12.00	17.40	25.15	43.75	69.00	109.00	163
2¼	5.15	8.50	12.75	18.50	26.47	45.88	72.00	113.25	169
2½	5.50	9.00	13.50	19.60	27.80	48.00	75.00	117.50	174
2¾	5.75	9.50	14.25	20.70	29.12	50.12	78.00	121.75	180
3	6.25	10.00	15.00	21.80	30.45	52.25	81.00	126.00	185
3¼	7.00	11.00	16.50	24.00	33.10	56.50	87.00	134.25	196
4	7.75	12.00	18.00	26.20	35.75	60.75	93.10	142.50	207
4½	8.50	13.00	19.50	28.40	38.40	65.00	99.05	151.00	218
5	9.25	14.00	21.00	30.60	41.05	69.25	105.20	159.55	229
5½	10.00	15.00	22.50	32.80	43.70	73.50	111.25	168.00	240
6	10.75	16.00	24.00	35.00	46.35	77.75	117.30	176.60	251
6½	.....	.....	25.50	37.20	49.00	82.00	123.35	185.00	262
7	.....	.....	27.00	39.40	51.65	86.25	129.40	193.65	273
7½	.....	.....	28.50	41.60	54.30	90.50	135.00	202.00	284
8	.....	.....	30.00	43.80	59.60	94.75	141.50	210.70	295
9	.....	.....	.....	46.00	64.90	103.25	153.60	227.75	317
10	.....	.....	.....	48.20	70.20	111.75	165.70	224.80	339
11	.....	.....	.....	50.40	75.50	120.25	177.80	261.85	360
12	.....	.....	.....	52.60	80.80	128.75	189.90	278.90	382
13	.....	.....	.....	.....	86.10	137.25	202.00	295.95	404
14	.....	.....	.....	.....	91.40	145.75	214.10	313.00	426
15	.....	.....	.....	.....	96.70	154.25	226.20	330.05	448
16	.....	.....	.....	.....	102.00	162.75	238.30	347.10	470
17	.....	.....	.....	.....	107.30	171.00	250.40	364.15	492
18	.....	.....	.....	.....	112.60	179.50	262.60	381.20	514
19	.....	.....	.....	.....	117.90	188.00	274.70	398.25	536
20	.....	.....	.....	.....	123.20	206.50	286.80	415.30	558
Per inch additional	1.37	2.13	3.07	4.18	5.45	8.52	12.27	16.70	21.82

## Weights of Nuts and Bolt-Heads, in Pounds

For calculating the weight of longer bolts

Diameter of bolt, in inches		¼	⅜	½	⅝	¾	⅞
Weight of hexagon nut and head...	....	0.017	0.057	0.128	0.267	0.43	0.73
Weight of square nut and head....	....	0.021	0.069	0.164	0.320	0.55	0.88

Diameter of bolt, in inches	1	1¼	1½	1¾	2	2½	3
Weight of hexagon nut and head...	1.10	2.14	3.78	5.6	8.75	17	28.8
Weight of square nut and head....	1.31	2.56	4.42	7.0	10.50	21	36.4

## Weights of Rivets and Round-Headed Bolts Without Nuts. Steel

POUNDS PER HUNDRED

Length, in	$\frac{3}{8}$ in diam	$\frac{1}{2}$ in diam	$\frac{5}{8}$ in diam	$\frac{3}{4}$ in diam	$\frac{7}{8}$ in diam	1 in diam	$1\frac{1}{4}$ in diam	$1\frac{1}{2}$ in diam
$1\frac{1}{4}$	5.5	12.8	22.0	29.3	43.9	66.6	93.3	127
$1\frac{1}{2}$	6.3	14.2	24.1	32.4	48.2	72.1	100	136
$1\frac{3}{4}$	7.0	15.5	26.3	35.5	52.5	77.7	107	145
2	7.9	16.9	28.5	38.7	56.7	83.3	114	153
$2\frac{1}{4}$	8.7	18.3	30.7	41.8	61.0	88.8	121	162
$2\frac{1}{2}$	9.4	19.7	32.8	44.9	65.2	94.4	128	171
$2\frac{3}{4}$	10.2	21.1	35.0	48.0	69.5	100.	136	179
3	11.0	22.5	37.2	51.1	73.7	105.	143	188
$3\frac{1}{4}$	11.7	23.9	39.3	54.3	78.0	111	150	197
$3\frac{1}{2}$	12.6	25.3	41.5	57.4	82.3	116	157	205
$3\frac{3}{4}$	13.4	26.7	43.7	60.5	86.5	122	164	214
4	14.1	28.1	45.9	63.6	90.8	128	170	223
$4\frac{1}{4}$	14.9	29.4	48.0	66.7	95.0	134	177	231
$4\frac{1}{2}$	15.7	30.8	50.2	69.9	99.3	139	185	240
$4\frac{3}{4}$	16.5	32.2	52.4	73.0	104	145	192	249
5	17.2	33.6	54.5	76.1	108	150	199	258
$5\frac{1}{4}$	18.1	35.0	56.7	79.2	112	156	206	266
$5\frac{1}{2}$	18.8	36.4	58.9	82.3	116	161	213	275
$5\frac{3}{4}$	19.6	37.8	61.1	85.5	120	166	220	284
6	20.4	39.2	63.2	88.6	124	172	227	292
$6\frac{1}{2}$	21.9	42.0	67.6	95.1	133	184	241	310
7	23.5	44.7	71.9	101	142	195	255	327
$7\frac{1}{2}$	25.1	47.5	76.1	108	150	206	269	345
8	26.6	50.3	80.6	114	159	217	284	362
$8\frac{1}{2}$	28.2	53.1	85.0	120	167	227	298	379
9	29.8	55.9	89.3	126	176	239	312	397
$9\frac{1}{2}$	31.3	58.7	93.7	133	185	250	325	414
10	32.8	61.4	98.0	139	193	261	340	431
$10\frac{1}{2}$	34.5	64.2	103	145	202	272	354	449
11	36.0	67.0	107	151	210	284	368	466
$11\frac{1}{2}$	37.6	69.8	111	158	218	295	382	484
12	39.2	72.5	115	164	227	306	396	501
Heads.....	1.8	5.8	11.1	13.6	22.6	39.0	58.0	83.5

For length of shaft required to form rivet-head, see Table IV, page 420.

## NAILS AND SCREWS\*

**Nails.** Based upon the process of manufacture there are three kinds of nails in common use, namely, plate or cut nails, wire nails, and clinch-nails. These are briefly described in the following subdivisions of this article and other data bearing on the subject is included.

(1) **Cut Nails.** Cut nails are made from a strip of rolled iron or steel of the same thickness as the finished nail and a little wider than its length, the fiber of the iron being parallel with the length of the nail. Special machinery cuts the nails out in alternate wedge-shaped slices, the heads are then stamped on them and the finished nails dropped into the casks. Cut nails made from iron are generally preferred for use in exposed positions. Cut nails are made in a variety of shapes to suit special uses. For ordinary use in building, nails of three different shapes are made, and the nails are called **COMMON NAILS**, **FINISH-NAILS** and **CASING-NAILS**. The common nails are used for rough work, finish-nails for finished work, and casing-nails for flooring, matched ceiling and sometimes for pine casings, although the heads are rather too large for finish-work. Cut nails are beginning to return to favor as they have holding power and lasting qualities superior to wire nails.

(2) **Brads.** Brads are thin nails with a small head, used for small finish, panel-moldings, etc. They vary from  $\frac{1}{4}$  to 2 in in length.

(3) **Clout-Nails.** Clout-nails are made with broad, flat heads, and are sold in sizes varying from  $\frac{3}{4}$  to  $2\frac{1}{2}$  in in length. They are used chiefly for fastening gutters and metal-work. Special nails are also made for lathing, slating, shingling, etc.

(4) **Wire Nails.** These have of late years become as common as the cut nails, and are sold at about the same price. They are said to be stronger for driving than the cut nails, not so liable to bend or break, especially when driven into hard woods, and less liable to split the wood; for these reasons they are generally preferred by carpenters. Wire nails are made from wire, of the same section-diameter as the shank of the nail, by a machine which cuts the wire in even lengths, heads and points them, and, when desired, also barbs them. In general the same classification is used for cut nails. It should be noticed that the gauge of the wire and the shape of the head vary in the different kinds, and that some are barbed, others plain. The various types of wire nails are drawn **ROUND**, **SMOOTH** or **BARBED**, for the domestic trade; for export they are drawn **OVAL**, **SQUARE**, or **DIAMOND-SHAPED**, according to the country to which they are to be shipped and its requirements. It is customary to charge 15 cents more per 100 for standard nails, **BARBED**, than for the same nails, **SMOOTH**.

(5) **Clinch-Nails.** These are made from open-hearth or Bessemer-steel wire. Any ordinary wire nail will clinch, especially when made with **DUCK-BILL** or flattened points for clinching purposes, or even otherwise, if annealed. These nails are used only in places where it is desired to turn over the ends of the nails to form a clinch, as in the case of battens or cleats.

(6) **Length and Weight of Nails.** The length of nails is designated by **PENNIES (d's)**. Two explanations are given for the origin of this classification; for example, that tenpenny nails originally sold for tenpence a hundred, or that 1000 tenpenny nails originally weighed 10 lb. The designation is retained by manufacturers, both for cut and wire nails. The weights expressed in pennies run from two pennies to sixty pennies, the larger sizes being designated by

\* Condensed from article by Thomas Nolan in chapter on Builders' Hardware in revised edition of Building Construction and Superintendence, Part II, Carpenters' Work, F. E. Kidder.

fractions of an inch. The sizes and lengths of various kinds of nails and tacks are given in tables on pages 1531 to 1534.

(7) **Sizes of Nails for Different Classes of Work.** It is imperative for first-class work that nails of proper size should be used and to insure the best results it is well in certain classes of work to specify the sizes which are to be used. For framing, twentypenny, forty penny and sixty penny nails, or spikes, are used according to the size of the timber. For sheathing and roof-boardings, under floors and cross-bridging, tenpenny common nails should be used. For over floors tenpenny floor-nails or casing-nails should be used for jointed boards, and ninepenny or tenpenny for matched flooring, although eightpenny nails are sometimes used. Ceiling when  $\frac{3}{4}$  in thick is generally put up with eightpenny casing-nails, and when thinner stuff is used, with sixpenny nails. For inside finish any size of finish-nails or brads from eightpenny down to twopenny is used, according to the thickness and size of the moldings. For pieces exceeding 1 in in thickness, tenpenny nails should be used. Clapboarding is generally put on with sixpenny finish-nails or casing-nails. Threepenny to fourpenny are used for shingling and slating, and threepenny for lathing. For slating, galvanized nails should be used, and they are also better for shingling. Whether wire or cut nails should be used may generally be left to the builder; but in places where there is any danger of the nails being drawn out either by the warping of the boards or from the pull of the nail, cut nails should be used, as they have greater holding power than the wire nails under certain conditions. In regard to the comparative holding power of cut nails and wire nails, and barbed nails and smooth nails, and tests made to determine this property, see page 1531.

(8) **Copper and Brass Nails.** Nails are also made of copper and cast brass, and these are sometimes used in connection with boat-building, refrigerator-work, etc. One wing of the Physical Laboratory Building of Harvard College is put together entirely with brass and copper. As the rooms were intended for use in delicate electrical work, no iron was used in their construction.

(9) **Cement-coated Wire Nails.** The coating consists of various resinous gums mixed by a secret formula, and put on the nails by a baking-process which involves the use of quite complicated machinery. Although the chief market for coated nails is among the users of packages to be shipped, there is a limited market for them among builders, for construction-purposes. The chief merit of the coating is that it gives the nail an adhesive resistance approximately twice that of ordinary wire nails. This quality appeals especially to the manufacturers and users of packages to be shipped, for which strength is particularly wanted. It is desirable for construction-purposes also, but the lack of holding power in plain wire nails is not so apparent in building. About 90% of the output goes to factories and large shippers. Cement-coated nails are quite widely used, also, in laying both ordinary and parquetry-flooring. The use of these nails, with a special head which leaves a small hole, gives a firm floor and prevents springing. Though the makers do not claim that the nails are absolutely rust-proof, they do claim that nails thus treated will resist the effects of moisture from 20 to 50% better than the uncoated wire nails. But it is when in use that the non-rusting quality is most evident. There is more coating on the nails than is actually necessary for holding power. The heat caused by the friction of driving the nail softens the coating and the surplus is forced toward the head, completely closing the opening; this prevents the admission of moisture between the wood and the nail. Under similar conditions, the life of a cement-coated nail will be about twice as long as that of an uncoated one. Less force is needed to drive a coated nail as the softened coating forms a lubricant. These nails are made in

two types, differing only in the heads, and are either COOLERS or SINKERS. The former have large flat heads; the latter, heads slightly reinforced by counter-sinking. They are made to replace common nails, in sizes from  $\frac{1}{4}$  in to 1 in, and are used for framing, boarding, shingling and staging, and for boxes and crates. Results of tests made with cement-coated nails to determine their adhesive resistance in comparison with the common smooth-wire nails are given below.

The following table shows the result of tests made at the United States Arsenal, Watertown, Mass., in 1902, the wood being pine:

**Comparative Adhesive Resistance of Common Smooth-Wire Nails and Cement-Coated Nails**

All nails were driven into the same piece and were perpendicular to the grain

Size and name	Diameter, in	Length driven,* in	Adhesive resistance,† lb
Twenty-penny, common, smooth.....	0.145	2½	167
Twenty-penny, coated.....	0.117	2½	418
Ninepenny, common, smooth.....	0.132	2¼	182
Ninepenny, coated.....	0.114	2¼	327
Eightpenny, common, smooth.....	0.132	2	189
Eightpenny, coated.....	0.112	2	316
Sixpenny, common, smooth.....	0.097	1¾	106
Sixpenny, coated.....	0.092	1¾	226

\* All of the nails were left with their heads projecting from  $\frac{1}{4}$  to  $\frac{1}{2}$  in.

† Average of three trials.

**Holding Power of Nails.** A committee appointed by the Wheeling nail-manufacturers, a number of years ago, to test the comparative holding power of cut and wire nails, published the following data. The kind of wood is not named. The effect of barbs is slight, and definite conclusions await complete tests.

**Pounds Required to Pull Nails Out**

	Cut	Wire		Cut	Wire
Twenty-penny.....	1 593	703	Sixpenny.....	383	200
Ninepenny.....	908	315	Fourpenny.....	286	123
Eightpenny.....	597	227			

The holding power of nails varies with the kind of wood into which they are driven. Austin T. Byrne gives the relative holding power of woods as ABOUT as follows: White pine, 1; yellow pine, 1.5; white oak, 3; chestnut, 1.6; beech, 3.2; elm, 2; basswood, 1.2.

**Comparative Holding Power of Cut and Wire Nails**

From thorough tests of the comparative holding power of wire nails and cut nails OF EQUAL LENGTHS AND WEIGHTS were made at the U. S. Arsenal in 1892 and

From forty series, comprising forty sizes of nails driven in spruce wood, it was found that the cut nails showed an average superiority of 60.50%, the common nails showing an average superiority of 47.51% and the finishing-nails an average of 72.22%. In eighteen series, comprising six sizes of BOX-NAILS driven in pine wood, in three ways the cut nails showed an average superiority of 70%. In no series of tests did the wire nails hold as much as the cut nails.

Quantity of Nails Required for Different Kinds of Work

For 1 000 shingles\* allow 3½ to 6½ lb fourpenny nails or 3½ to 4½ lb threepenny  
1 000 laths, 7 lb threepenny fine, or for 100 sq yd of lathing, 10 lb threepenny fine  
1 000 sq ft of beveled siding, 18 lb sixpenny  
1 000 sq ft of sheathing, 20 lb eightpenny or 25 lb tenpenny  
1 000 sq ft of flooring, 30 lb eightpenny or 40 lb tenpenny  
1 000 sq ft of studding, 15 lb tenpenny and 5 lb twentypenny  
1 000 sq ft of 1 by 2½-in furring, 12-in centers, 9 lb eightpenny or 14 lb tenpenny  
1 000 sq ft of 1 by 2½-in furring, 16-in centers, 7 lb eightpenny or 10 lb tenpenny

\* Depends upon width and length of shingles and kind of nails.

Cut Steel Nails and Spikes

Sizes, lengths, and approximate number per pound  
Taken from the Handbook of the Cambria Steel Company

Sizes	Length, inches	Common	Clinch	Finishing	Casing and box	Fencing	Spikes
2d	1	740	400	1 100	.....	.....	.....
3d	1¼	460	260	880	.....	.....	.....
4d	1½	280	180	530	420	.....	.....
5d	1¾	210	125	350	300	100	.....
6d	2	160	100	300	210	80	.....
7d	2¼	120	80	210	180	60	.....
8d	2½	88	68	168	130	52	.....
9d	2¾	73	52	130	107	33	.....
10d	3	60	48	104	88	26	.....
12d	3¼	46	40	96	70	20	.....
16d	3½	33	34	86	52	18	17
20d	4	23	24	76	33	16	14
25d	4¼	20	.....	.....	.....	.....	.....
30d	4½	16½	.....	.....	30	.....	11
40d	5	12	.....	.....	26	.....	9
50d	5½	10	.....	.....	20	.....	7½
60d	6	8	.....	.....	16	.....	6
.....	6½	.....	.....	.....	.....	.....	5½
.....	7	.....	.....	.....	.....	.....	5

Sizes	Length, inches	Barrel	Light barrel	Slating	Sizes	Length, inches	Flat grip, fine	Edge- grip, fine
.....	5⁄8	750	.....	.....	.....	¾	1 462	.....
.....	¾	600	.....	.....	.....	7⁄8	1 300	.....
.....	7⁄8	500	.....	.....	2d	1	1 100	960
2d	1	450	.....	340	3d	1¼	800	750
.....	1½	310	400	.....	4d	1½	650	600
3d	1¾	280	304	280	Tobacco		Brads	Shingle
.....	1¾	210	.....	.....			.....	.....
4d	1½	190	224	220	.....		.....	.....
5d	1¾	.....	.....	180			.....	.....
6d	2	.....	.....	.....	.....		120	.....
7d	2¼	.....	.....	.....			94	.....
8d	2½	.....	.....	.....	.....		74	90
9d	2¾	.....	.....	.....			62	71
10d	3	.....	.....	.....	.....		50	60
12d	3¼	.....	.....	.....			40	.....
16d	3½	.....	.....	.....	.....		27	.....
.....	.....	.....	.....	.....			.....	.....

## Steel-Wire Nails, Spikes, and Tacks

SIZE, LENGTH, GAUGE AND APPROXIMATE NUMBER TO THE POUND

Compiled from Catalogue of American Steel and Wire Company, 1910

American Steel and Wire Company's gauge. (See page 1512.)

Common nails and brads *				Casing-nails †		Finishing-nails †	
Size	Length, in	Gauge	Number to pound	Gauge	Number to pound	Gauge	Number to pound
2d	1	15	876	15½	1 010	16½	1 351
3d	1¼	14	568	14½	635	15½	807
4d	1½	12½	316	14	473	15	584
5d	1¾	12½	271	14	406	15	500
6d	2	11½	181	12½	236	13	309
7d	2¼	11½	161	12½	210	13	238
8d	2½	10½	106	11½	145	12½	189
9d	2¾	10½	96	11½	132	12½	172
10d	3	9	69	10½	94	11½	121
12d	3¼	9	63	10½	87	11½	113
16d	3½	8	49	10	71	11	90
20d	4	6	31	9	52	10	62
30d	4½	5	24	9	46	.....	.....
40d	5	4	18	8	35	.....	.....
50d	5½	3	14				
60d	6	2	11				

Spikes †				Shingle-nails			
Size	Length, in	Gauge	Number to pound	Size	Length, in	Gauge	Number to pound
3d	1¼	13	429	3d	1¼	13	429
3½d	1¾	12½	345	3½d	1¾	12½	345
4d	1½	12	274	4d	1½	12	274
5d	1¾	12	235	5d	1¾	12	235
6d	2	12	204	6d	2	12	204
7d	2¼	11	139	7d	2¼	11	139
8d	2½	11	125	8d	2½	11	125
9d	2¾	11	114	9d	2¾	11	114
10d	3	10	83	10d	3	10	83

Fine nails			
2d	1	16½	1 351
3d	1¼	15	778
4d	1½	14	473
2d	1	17	1 560
extra fine			
3d	1¼	16	1 015
extra fine			

Common brads differ from common nails only in the head and point.

Lengths are the same as common nails for corresponding size.

Spikes are made with chisel-points and diamond points; also with convex heads and heads.

Steel-Wire Nails (Continued)

Clinch-nails				Fence-nails *		Slating-nails *	
Size	Length, in	Gauge	Number to pound	Gauge	Number to pound	Gauge	Number to pound
2d	1	14	710	No 5 smallest size		12	411
3d	1 1/4	13	429			10 1/2	235
4d	1 1/2	12	274			10 1/2	187
5d	1 3/4	12	235			10	142
6d	2	11	157			9	103
7d	2 1/4	11	139	10	142	Barbed roofing-nails †	
8d	2 1/2	10	99	10	124		
9d	2 3/4	10	90	9	92		
10d	3	9	69	9	82		
12d	3 1/4	9	62	8	62		
16d	3 1/2	8	49	7	50		
20d	4	7	37	6	40		
				5	30	3/4" X No 13	714
				4	23	7/8" X No 12	469
						1" X No 12	411
						1 1/8" X No 12	365
						1 1/4" X No 11	251

\* Length same as clinch-nails of corresponding size.

† Roofing-nails are designated by the length, not by PENNY. These nails are made in lengths up to 2 in.

Wire Tacks

Title, ounce	Length, in	Number per pound	Title, ounce	Length, in	Number per pound	Title, ounce	Length, in	Number per pound
1	1/8	16 000	4	7/16	4 000	14	1 3/16	1 143
1 1/2	3/16	10 666	6	9/16	2 666	16	3/8	1 000
2	1/4	8 000	8	5/8	2 000	18	1 1/4	888
2 1/2	5/16	6 400	10	1 1/8	1 600	20	1	800
3	3/8	5 333	12	3/4	1 333	22	1 1/2	727
.....	.....	.....	.....	.....	.....	24	1 5/8	666

Wire carpet-tacks are made polished, blued, tinned, or coppered; there are also upholsterers' and bill-posters' or railroad tacks.




Expansion-bolt. These are commonly used for bolting wood or iron to masonry that is already built. A hole is drilled in the masonry of such size that the expansion-nut will fit closely, and when the bolt is screwed up the nut expands and binds firmly in the masonry. The illustration shows the Evans expansion-bolt, which is also furnished with screw-bolts. There are other forms of expansion-bolts on the market. From experiments on expansion-bolts it was found that the holding capacity was 264 lb per sq in when embedded in Portland-cement mortar, 843 per sq in when embedded in sulphur and 485 lb per sq in when embedded in lead. For average working unit-stresses it is safe to use about one-fifth the values given. When the work is exposed to rain or moisture sulphur should



not be used as the acid which results will rust the metal and will also tend to disintegrate the masonwork at the point of entrance of the bolt.

**Screws.** The substitution of screws for nails in building operations is a marked feature of modern work. Trimming hardware of all descriptions is put on with screws, and a great deal of panel-work, inside finish, etc., is put together with them. Stop-heads, the casings of plumbing-fixtures, etc., should be fastened with screws, as well as all kinds of store and office-fixtures, and cabinet-work in general, except where the joints are glued. Screws are also largely used in making furniture. They present a neater appearance than nails, have greater holding power and are less apt to injure the material if it should be removed and replaced. By making holes for the screws with a bit, all danger of splitting the finish is averted. The ordinary type of screw has a gimlet-point by which it can be turned into the wood without the aid of a bit. The heads are made in various forms to suit different uses. Screws are made ordinarily of steel, but sometimes of brass and bronze. The latter sort are used for screwing in place finished hardware of the same material, and have heads finished to correspond with the trimmings. Steel screws, also, are finished with blue, bronze, lacquered, galvanized, or tinned surface, to match the cheaper class of trimmings. The galvanized finish is used in building operations at the seashore. Screws with blue surface, called **BLUED SCREWS**, are generally used with japanned hardware and for stop-heads, and wherever a cheap round-headed screw is desired. Silver, nickel, and gold-plated screws are also manufactured for use in connection with similar hardware. Steel screws for wood are made in twenty different lengths, varying from  $\frac{1}{4}$  to 6 in, and each length of screw has from six to eighteen varieties in thickness, there being in all thirty-one different gauges; so that altogether there are in the market about two hundred and fifty different sizes of ordinary screws used for woodwork. The most common shapes are the ordinary flat head, round head and oval head. The oval-head screw is tapered for countersinking but is slightly rounded on top. Stout diamond-point steel screws are made



Lag and Coach-screws

specially for driving with a hammer. These can be driven with a hammer their entire length into any hard wood, and then held by one or two turns as securely as the ordinary screw. In ordering screws both the length and number of the gauge or diameter of the shank, the material and finish, and the use to which they are to be put, should be given.

**Screws for Metal** have the same diameter throughout and the threads are V-shaped.

**Sizes of Screws.** The sizes of screws are given in length in inches and the number of the gauge, the gauge denoting the diameter. Thus, a 1-in No. 12 screw is 1 in long and 0.2158 in in diameter. The gauge-numbers range from 0 to 30 and the lengths from  $\frac{1}{4}$  to 6 in. The lengths vary by eighths of an inch up to 1 in, by quarters of an inch up to 3 in and by halves of an inch up to 5 in. Screws from  $\frac{5}{8}$  to  $4\frac{1}{2}$  in long are made in about sixteen different gauge-numbers. Table II, page 402, gives the diameter to four places in decimals of an inch of the American screw-gauge. It should be noticed that, unlike the ordinary wire-gauges, the 0 of the screw-gauge indicates the diameter of the smallest screw while the diameter of the screw increases with the number of the gauge.

**Lag-Screws and Coach-Screws** are large, heavy screws used where great length is required, as in heavy framing, and for fixing ironwork to timber.

Lag-screws with conical point are made with diameters of  $\frac{3}{16}$ ,  $\frac{3}{8}$ ,  $\frac{7}{16}$ ,  $\frac{1}{2}$ ,  $\frac{9}{16}$ ,  $\frac{5}{8}$ ,  $\frac{3}{4}$ , and 1 in, and in lengths from  $1\frac{1}{2}$  to 12 in; coach-screws in diameters from  $\frac{1}{4}$  to  $\frac{3}{4}$  in and in lengths from  $1\frac{1}{2}$  to 12 in. For putting in lag-screws a hole should be bored which has a diameter a little greater than the unthreaded shank of the screw and it should be bored to a depth corresponding to the length of the unthreaded shank. A second hole should then be bored at the bottom of the first hole of a diameter somewhat less than that of the threaded shank and to a depth of about half its length.

Holding Power of Lag-Screws

Tests made by A. J. Cox, University of Iowa, 1891, quoted by Kent, page 324

Kind of wood	Size of screw, in	Size of hole bored, in	Length in wood, in	Maximum resist- ance, lb	Number of tests
Seasoned white oak.....	$\frac{5}{8}$	$\frac{1}{2}$	$4\frac{1}{2}$	8 037	3
Seasoned white oak.....	$\frac{9}{16}$	$\frac{7}{16}$	3	6 480	1
Seasoned white oak.....	$\frac{1}{2}$	$\frac{3}{8}$	$4\frac{1}{2}$	8 780	2
Yellow-pine stick.....	$\frac{5}{8}$	$\frac{1}{2}$	4	3 800	2
White cedar, unseasoned.....	$\frac{5}{8}$	$\frac{1}{2}$	4	3 405	2

Hoopes & Townsend give the force required to draw screws out of yellow pine as follows:

Screw.....	$\frac{1}{2}$ in	$\frac{5}{8}$ in	$\frac{3}{4}$ in	$\frac{7}{8}$ in	1 in
Wood, depth.....	$3\frac{1}{2}$ in	4 in	4 in	5 in	6 in
Force, pounds.....	4 960	6 000	7 685	11 500	12 620

Wooden-screws are sold by the gross, lag-screws and coach-screws by the pound.

DATA ON EXCAVATING \*

Excavating is almost invariably measured by the cubic yard of 27 cu ft. For measuring excavations of irregular depth see page 65. For computing the contents of wells and cesspools, the circular area in square feet may be obtained from the table on page 51, and this circular area multiplied by the depth in feet will give the contents in cubic feet. The cost of excavating and removing earth is ordinarily made up of the following items:

- (1) Loosening the earth for the shovelers;
- (2) Loading by shovels into carts or barrows;
- (3) Hauling or wheeling it away, including emptying and returning;
- (4) Spreading it out on the dump;

For every large job, such as railroad-work, it is also necessary to make an allowance for keeping the hauling-road in repair, for sharpening and repair of tools, and for carts, harness, superintendence and water-carriers. Where the dirt excavated can be spread over the ground immediately surrounding the excavation the loosened dirt may be removed by scrapers without shoveling.

Data for Estimating Cost of Loosening Earth. Two men with a plough and team of horses will loosen from 20 to 30 cu yd of strong, heavy soil per hour or

\* All prices given are pre-war prices and are retained for purposes of comparison of relative values.

from 40 to 60 cu yd of ordinary loam. One man with a pick will loosen  $1\frac{1}{4}$  yd per hour of stiff clay or cemented gravel, 4 yd of common loam, or 6 yd of light sand.

The average quantity of LOOSENED EARTH that a man can shovel into a cart per hour is:

Loam or sand.....	2.0 cu yd
Clay and heavy soils.....	1.7 cu yd
Rock.....	1.0 cu yd

Average earth when loosened swells to from  $1\frac{1}{4}$  to  $1\frac{1}{2}$  times its original bulk in place.

The capacity of vehicles used for moving excavated materials is about as follows:

Wheelbarrows.....	3 to 4 cu ft
One-horse dump-carts.....	18 to 22 cu ft
Two-horse dump-wagons.....	27 to 45 cu ft *
Drag-scrapers.....	3 to 7 cu ft
Wheel-scrapers.....	10 to 17 cu ft
Dump-cars on rails.....	27 to 80 cu ft

The Economical Length of Haul with drag-scrapers is about 150 ft; with wheel-scrapers, 500 ft; with wheelbarrows, 250 ft; with one-horse dump-carts, 100 ft.† The average speed of horses is given as about 200 ft per minute.

Much valuable data for estimating ‡ the cost of excavating may be found in the Civil Engineer's Handbooks.

**Weight of Earth, Sand and Gravel.** For general calculations the following average values may be taken:

14 cu ft of chalk weigh 1 ton	19 cu ft of gravel weigh 1 ton
18 cu ft of clay weigh 1 ton	22 cu ft of sand weigh 1 ton
21 cu ft of earth weigh 1 ton	

**Rock-Excavation.** A cubic yard of rock, in place, when broken up by blasting or removal by wheelbarrows or carts, will occupy a space of about  $1\frac{1}{4}$  cu yd; consequently the cost of hauling or removal is about 50% more than for dirt.

"With labor at \$1 per day, the actual cost for loosening hard rock, including tools, drilling, powder, etc., will average about 45 cents per cubic yard, in place, under all ordinary circumstances. In practice it will generally range between 30 and 60 cents, depending on the position of the strata, hardness, toughness, water and other considerations. Soft shales and other allied rocks may frequently be loosened by pick and plough as low as 15 to 20 cents, while on the other hand shallow cuttings of very tough rock with an unfavorable position of strata, especially at the bottoms of excavations, may cost \$1 per cu yd, or even considerably more. The quarrying of average hard rock requires about  $\frac{1}{4}$  to  $\frac{1}{2}$  lb of powder per cu yd, in place, but the nature of the rock, the position of the strata, etc., may increase to  $\frac{1}{2}$  lb or more. Soft rock frequently requires more powder than hard. A rod churn-driller will drill 8 to 10 ft in depth of holes about  $2\frac{1}{2}$  ft deep and 2 in diameter per day in average hard rock, at from 12 to 18 cents per ft." §

\* The ordinary load for two-horse wagons such as are commonly used for hauling dirt, sand and gravel is from  $1\frac{1}{4}$  to  $1\frac{1}{2}$  cu yd.

† Inspectors' Pocket-Book, by A. T. Byrne.

‡ See, also, Handbook of Cost Data, by H. P. Gillette.

§ The Civil Engineer's Pocket-Book, J. C. Trautwine.

## DATA ON STONEWORK \*

**Kinds of Stonework.** The commonest kind of stonework, that is, for walls is called **RUBBLEWORK**. No work whatever is done on the stones except to break them up with a hammer. If the wall is built in courses it is designated **COURSED RUBBLE**. When the stones showing on the outside face of the wall are squared, the work is designated **ASHLAR**. Ashlar is of two kinds: **COURSED ASHLAR**, in which the stones are laid to form courses around the building, all the stones in any course being of the same height, and **BROKEN ASHLAR**, in which stones of different heights are used. **HAMMER-DRESSED ASHLAR** designates work where the stones are roughly squared with a hammer. This is a very cheap class of work. Good ashlar work should be squared on the bench with chisels, and with beds and end-joints cut square to the face. Stonework which requires a chisel or any other tool except a hammer for dressing is called **CUT WORK**. Cut work costs considerably more than hammer-dressed work.

**Measurement of Stonework.** Rough stone from the quarry is usually sold under two classifications: rubble-stone and dimension-stone. Rubble includes the pieces of irregular size most easily obtained from the quarry, and suitable for cutting into ashlar 12 in or less in height and about 2 ft long. Stone ordered to be of a certain size, to **SQUARE** over 24 in each way and to be of a particular thickness, is called **DIMENSION-STONE**. The price of the latter varies from two to four times the price of **RUBBLE**. Rubble is generally sold by the ton or car load. Footings and flagging are usually sold by the square foot; dimension stone by the cubic foot. In Boston, granite blocks for foundations are usually sold by the ton.

In **Estimating on the Cost of Stonework** put into a building, the custom varies with different localities, and even among contractors in the same city. Dimension-stone footings, that is, squared stones 2 ft or more in width, are usually measured by the square foot. If built of large rubble or irregular stones the footings are measured in with the wall, allowance being made for the projection of the footings. Rubblework is almost universally measured by the **PERCH** of 16½ cu ft. The author has been unable to find any locality where the legal perch of 24¾ cu ft is used by stone-masons. In Philadelphia, St. Louis and some sections of Illinois, 22 cu ft are called a perch. Railroad-work is usually measured by the cubic yard. When stonework is let by the perch, the number of cubic feet to the perch should be stated in the contract, and it should be stated also, whether or not openings are to be deducted. As a rule no deductions are made for openings of less than 70 superficial feet.

**Data for Estimating Cost.†** The price of common rubble as it comes from the quarry will vary from 55 cts to \$1.65 per ton, free on board cars at point of delivery, according to the cost of quarrying, transportation, etc. \$1.35 a perch is probably a fair average.

A ton of most of the different kinds of stones will make from 1 perch to 1½ perches.

The cost of laying one perch of stone may be estimated by the following items:

Labor: mason 2¾ hrs, helper 1¾ hrs, based on two helpers to three masons; sand ¼ load; lime ¾ bu, or if laid in all-cement mortar, one perch will require from ½ to ½ bbl of cement.

At average wages, rubble cellar-walls, from 18 in to 2 ft thick, laid in lime mortar

\* The prices given are pre-war prices.

† For wages different from those named, the average costs may be calculated by proportion.

tar, vary in cost from \$2.75 to \$4.50 per perch, \$3.50 a perch being a fair average; in all-cement mortar, from \$3.50 to \$4.50 per perch.

The cost of ashlar depends very largely upon the kind of stone used and the distance it has to be brought. The price of the rough stock on the cars at the point of delivery may vary from 75 cts to \$1.35 per cu ft for granite and from 60 cts to \$1.10 for sandstones and limestones, depending largely upon cost of transportation. 1 cu ft of stone should make 2 sq ft of ashlar, at least. Some quarries get out stone especially suitable for ashlar and sell it at about 30 cts per lin ft for courses 12 in high.

The cost of cutting ashlar, with stone-cutters' wages at \$4 per day, will average about 15 cts per sq ft for soft stones, from 15 to 20 cts per sq ft for hard sandstones and limestones, and from 25 to 30 cts for granite. The cost of setting ashlar will vary from 10 cts per sq ft to 25 cts for soft stones or 30 cts for granite, 15 cts being an average price for sandstones and limestones.

The cost of cut-stone trimmings depends so largely upon the kind of stone that it is quite impossible to give prices that would be of very much service. The following figures, however, may serve as a general guide in forming a rough estimate, the prices if anything being probably a little above the cost of the local stone in most localities.

**Flagstones for Sidewalks**, ordinary stock, natural surface, 3 in thick, with joints pitched to line, in lengths, along walk, from 3 to 5 ft, will cost, for a 3-ft walk, about 10 cts per sq ft, or if 2 in thick, 7 cts; for a 4-ft walk, 10 cts; and for 5-ft walk, 12 cts per sq ft. The cost of laying all sizes will average about 4 cts per sq ft. The above figures do not include the cost of hauling.

**Curbing.** 4 by 24-in granite will cost at the quarry from 30 to 35 cts per lin ft; digging and setting will cost from 12 to 14 cts additional; and the cost of freight and hauling must also be added.

**Cut Bluestone.** The following figures show the approximate cost of cut bluestone for various uses:

Flagstone, 5 in, size 8 by 10 ft, edges and top bush-hammered, per square foot face-measure.....	\$0.75
Flagstone, 4 in, size 5 by 5 ft, select stock, edges clean-cut, natural top, per square foot.....	0.45
Door-sills, 8 by 12 in, clean-cut, per linear foot.....	1.35
Window-sills, 5 by 12 in, clean-cut, per linear foot.....	0.80
Window-sills, 4 by 8 in, clean-cut, per linear foot.....	0.45
Window-sills, 5 by 8 in, clean-cut, per linear foot.....	0.60
Lintels, 4 by 10 in, clean-cut, per linear foot.....	0.65
Lintels, 8 by 12 in, clean-cut, per linear foot.....	1.25
Water-table, 8 by 12 in, clean-cut, per linear foot.....	1.25
Coping, 4 by 21 in, clean-cut, per linear foot.....	1.20
Coping, 4 by 21 in, rock-face edges and top, per linear foot.....	0.50
Coping, 3 by 15 in, rock-face edges and top, per linear foot.....	0.35
Coping, 3 by 18 in, rock-face edges and top, per linear foot.....	0.40
Steps, sawed stock, 7 by 14 in, per linear foot.....	1.10
Platform, 6 in thick, per square foot.....	0.50

To the prices of cut stone above given must be added the cost of setting, which, for water-tables, steps, etc., will be about 10 cts per linear foot, and for window-sills, etc., about 5 cts per linear foot. For fitting, about 10 cts per cu ft, and for trimming the joints after the pieces are set in place, about 5 cts per cu ft should be added.

## DATA ON BRICKS AND BRICKWORK

**Clay Bricks.** The word brick as commonly used refers to the material of clay, molded into the required shape and size and burned in a kiln; and until quite recently, practically all bricks were made from clay. At the present time, however, bricks are also made from sand and lime, and from cement and concrete. Clay bricks may be broadly classified as common bricks, face-bricks, fire-bricks and paving-bricks. As to the process of manufacture, bricks are classified as soft-mud bricks, stiff-mud bricks, dry-pressed bricks and repressed bricks.

**Soft-Mud Bricks** are made by tempering clay with water until it becomes soft and plastic and then pressing it into molds either by hand or by a machine. Practically all handmade bricks are soft-mud bricks. Soft-mud bricks are often **REPRESSED** to make face-bricks.

**Stiff-Mud Bricks** are machine-made. The clay is first ground, and only enough water is added to make a stiff mud. The stiff clay is forced through a die or dies in the machine in a continuous stream, which is cut up automatically into pieces the size either of the end or side of the brick. If the opening is the size of the end of the brick, the bricks are **END-CUT BRICKS**; if of the size of the side of the brick, they are **SIDE-CUT BRICKS**. Stiff-mud bricks can readily be distinguished from soft-mud bricks by their appearance. As good if not better bricks can be made by the soft-mud process as by the stiff-mud process, and in the Eastern States the soft-mud bricks are probably the stronger. As far as the author's observation has extended in the Western States, the stiff-mud bricks are as a rule preferable to those made by the soft-mud process. Stiff-mud bricks are usually heavier than soft-mud bricks or hand-made bricks.

**Dry-pressed Bricks** are made almost entirely for face-work, although in some localities dry-pressed bricks are also used as common bricks. Hydraulic-pressed bricks are dry-pressed.

**Molded Bricks** are always dry-pressed. Very fine bricks are made by this process.

**Burning of Bricks.** Bricks made by any of the above processes require to be burned in a kiln. According to their position in the kiln, common bricks are designated **ARCH-BRICKS** or hard-burned bricks, **RED BRICKS** or well-burned bricks, and **SALMON BRICKS** or soft bricks. As a rule, salmon bricks are not fit to use in an exterior or bearing-wall.

**Color of Bricks.** The color of bricks depends principally upon the presence of iron, lime, or magnesia in the clay. A large proportion of oxide of iron gives a clear bright red. Magnesia produces a brown color, and when in the presence of iron, a light-drab color. Dry-pressed bricks are often colored artificially either by mixing clays of different composition, or by mixing mineral colors with the finely ground clay.

**Fire-Bricks** are ordinarily made from a mixture of flint clay and plastic clay. They are usually white, or white mixed with brown, in color and are used for the lining of furnaces, fireplaces and tall chimneys.

**Paving-Bricks** are very hard bricks, usually vitrified or annealed. They are much more expensive than common bricks and are seldom used in the construction of buildings.

**Size and Weight of Clay Bricks.** In this country there is no legal standard for the **SIZE OF BRICKS**, and the dimensions vary with the maker and also with the

locality. Common standard sizes are 8 by  $3\frac{3}{4}$  by  $2\frac{1}{4}$  in. and 8 by  $3\frac{1}{2}$  by  $2\frac{1}{4}$  in. In the New England States the common brick averages about  $7\frac{3}{4}$  by  $3\frac{3}{4}$  by  $2\frac{1}{4}$  in. In most of the Western States common bricks measure about  $8\frac{1}{4}$  by  $4\frac{1}{4}$  by  $2\frac{1}{2}$  in, and the thicknesses of the walls measure about 9, 13, 18 and 22 in for thicknesses of 1,  $1\frac{1}{2}$ , 2 and  $2\frac{1}{2}$  bricks. The sizes of all common bricks vary considerably in each lot, according to the degree to which they are burned; the hard bricks being from  $\frac{1}{8}$  to  $\frac{3}{16}$  in smaller than the salmon bricks. In England the common standard is  $8\frac{3}{4}$  by  $4\frac{3}{4}$  by  $2\frac{3}{4}$  in. Pressed bricks or face-bricks are more uniform in size, as most of the manufacturers use the same size of mold. The prevailing sizes for pressed bricks are  $8\frac{3}{4}$  by  $4\frac{1}{4}$  by  $2\frac{3}{4}$  and  $8\frac{3}{4}$  by 4 by  $2\frac{1}{4}$  in. Pressed bricks are also made  $1\frac{1}{2}$  in thick and 12 by 4 by  $1\frac{1}{2}$  in, those of the latter size being generally termed ROMAN BRICKS or TILES.

The WEIGHT OF BRICKS varies considerably with the quality of the clay from which they are made, and also, of course, with their size. Common bricks average about  $4\frac{1}{4}$  lb each, and pressed bricks vary from 5 to  $5\frac{1}{4}$  lb each. For the STRENGTH OF BRICKS and brickwork, see Chapter V. The FIRE-BRICKS are made in various forms to suit the required work. A straight brick measures 9 by  $4\frac{1}{2}$  by  $2\frac{1}{2}$  in and weighs about 7 lb. To secure the best results fire-bricks should be laid in the same clay from which they are manufactured, this being mixed with water into a thin paste. The thinner the joint, the better the wall will stand heat. For PAVING-BRICKS the size and weight vary according to the locality and to the requirements of the specifications. Former STANDARDS were,  $8\frac{1}{2}$  by 4 by 8 in, required 61 bricks to the square yard, on edge, and weighed 7 lb each. REPRESSED bricks,  $2\frac{1}{2}$  by 4 by  $8\frac{1}{2}$  in, require 58 to the square yard and weigh  $6\frac{1}{2}$  lb each. METROPOLITAN bricks were 3 by 4 by 9 in, required 45 to the square yard, and weighed  $9\frac{1}{2}$  lb each.\*

**Lime-Mortar Bricks.†** General Description. The so-called SAND-LIME BRICKS were originally made of lime mortar, molded in brick form and hardened by exposure to the air. Such bricks are said to have been largely used in ancient times, and it is claimed that remains of such materials are now in evidence and in a good state of preservation. It is known that they were formerly used in European localities where other materials were not readily available, and that they have been used in some localities in this country during the past thirty-five years. The writer knows of several houses in Haddonfield, N. J., built of such bricks, generally with the exterior surfaces plastered. One of them, however, said to be about twenty-five years old, has not been plastered, and an inspection (1915) shows the bricks to be in an excellent state of preservation. Lime-mortar bricks harden by the absorption of carbonic-acid gas from the air. This gas enters into combination with the lime, forming carbonate of lime. The hardening process requires several weeks' exposure under cover and the product has not virtues sufficient to commend it where other materials are available.

**Sand-Lime Bricks.** It was discovered in Germany about 1875 that lime-mortar bricks could be hardened in a few hours under heat and pressure, and it was found later that the chemical reaction under the new process differs essentially from that just described, and that the percentage of lime can be greatly reduced. The fundamental principles of sand-lime-brick manufacture are now common property and only the details of the manufacture are patentable. Sand-lime bricks were first made in Germany about 1880, and the more extended commercial development of the industry dates back in Europe to about 1888,

\* Building Inspectors' Pocket-book, A. T. Byrne.

† Condensed from article on Sand-Lime Bricks by Professor Thomas Nolan in the revised edition of Building Construction and Superintendence. Part I, Masons' Work, by E. Kidder.



and in this country, to about 1900. There are now (1915) several factories in operation in this country.

**Manufacture of Sand-Lime Bricks.** Pure silica sand, mixed with from 5 to 10% of high-calcium lime and a certain proportion of water, is molded under very high pressure into the form of bricks. These are piled loosely on cars holding about 1000 bricks each and placed in a steel cylinder large enough to hold from 10 to 20 cars. The cylinder is then closed and steam is turned in and maintained at a pressure of from 120 to 135 lb to the square inch for from 8 to 10 hours, when the cylinder is opened and the bricks removed, ready for use. The tremendous pressure, which is said to be 100 tons on each brick, under which the bricks are formed, causes great density and a bringing of the component elements into close contact. The heat in the cylinder dries the bricks and causes a chemical reaction between the lime and a portion of the silica, forming a hydrosilicate of lime, an insoluble and durable element, which bonds the remaining particles of the sand together and forms a comparatively strong cementing material. The small residue of uncombined lime combines, in the course of time, either with silica or with carbonic-acid gas from the air, until no free lime remains. The bricks thus become harder and stronger with age. In regard to the constitution of sand-lime bricks, Edwin C. Eckel says:\* "It may be safely assumed that a sand-lime brick as marketed consists of (1) sand-grains held together by a network of (2) hydrous lime silicate, with probably (if a magnesian lime is used) some allied magnesium silicate, and (3) lime hydrate or a mixture of lime and magnesia hydrates. These three elements will always be present, and the structural value of the brick will depend in large part on the relative percentage in which the sand and the hydrates occur."

**Quality of Sand-Lime Bricks.** The quality of the product depends mainly upon the selection and treatment of the sand and the lime. Pure silica sand, containing a large percentage of fine grains passing through screens of from 80 to 150 mesh, are preferable. Clay or kaolin are dangerous elements and should not be present in quantities of more than 5%. The lime should be, preferably, high-calcium lime, the magnesium silicates formed by impure limes not being as strong as calcium silicates. Some manufacturers use ready-hydrated lime, others hydrate the lime themselves, before mixing it with the sand, and others grind the quicklime, mix it with the sand and slake it in the sand. The other most important element affecting quality is the press. After pressing and before steaming, the bricks are very fragile and the press should be such that they are subjected to no shaking or friction after the pressure is removed from the mold. Vertical clay-brick presses have been commonly used, but do not appear to be well adapted to the purpose. The rotary table-presses seem to be most successful.

**Tests of Sand-Lime Bricks.** If the sand is reasonably clean and pure, and the lime finely divided, and if the bricks are sound and have a good metallic ring, they will stand weather-exposure well. If a brick stands in still water for an hour and the moisture rises more than  $\frac{1}{4}$  in, it is not a first-class brick; if the moisture rises 2 in, its use for facings is questionable; and if the moisture rises 3 in, it should not be used on outside work of any importance. Authentic tests have been made for crushing, fire-resistance, frost-resistance, acid-resistance and absorption, from which it may be concluded that under proper conditions

\* "The Production of Lime and Sand-lime Brick in 1906," in the Government Report dated 1907 and published in 1908, on The Mineral Resources of the United States for the Calendar Year, 1906.

† See, also, Tests Upon Sand-Lime Bricks, made by Ira H. Woolson, November, 1906, at the Testing Laboratory, Columbia University, New York, for The National Association of Manufacturers of Sand-Lime Products.



Manufacture sand-lime bricks are produced having the following physical characteristics: Crushing strength, average, between 2 500 and 3 000 lb per sq in, although some specimens have shown over 5 000 lb per sq in; modulus of rupture, average, about 450 lb per sq in; fire-resistance, but little inferior to that of fire-brick; frost-resistance, generally good; acid-resistance, superior; absorption, from 7 to 10% in 48 hours; rate of absorption, slower than for clay bricks; average absorption for complete saturation, 14%; reduction of compressive strength by saturation for absorption-test, average 33%.

**Special Properties of Sand-Lime Bricks.** The bricks are square, straight, uniform in size and homogeneous in composition and density. They cleave accurately under the stroke of the trowel and present a weather-surface with the good qualities of stone. They can be cut, carved or sand-blasted, are easily washed clean and show no efflorescence. These claims are well established for properly manufactured sand-lime bricks. It should be further stated that common bricks and facings are made in the same press, the only difference being in the selection of the materials and in the handling of the raw bricks. It is therefore claimed that a rational and homogeneous exterior wall-structure is possible, face backings and facings may be built and bonded in even courses, with hemish or other ornamental bonds. Some factories, however, manufactured, first, inferior bricks and care should still be taken in selections from their outputs. Frequently the ordinary runs of sand-lime bricks are not as strong as the average clay building bricks and some of them are too low in their resistance to test.

**Colors of Sand-Lime Bricks.** The natural color is pearl-gray, varying in warmth with the composition of the sand. Permanent colors are produced by introducing mineral oxides with the raw materials in quantities varying according to the intensity of color desired; but as the oxides are foreign materials in the bricks, they affect the quality of the latter in proportion to the quantity used.

**Glazed and Enameled Bricks.** The term GLAZED BRICKS and ENAMELED BRICKS as commonly used, refer practically to the same product, and further includes what is known as SALT-GLAZED BRICK. The enameled or glazed bricks are generally dipped or sprayed and then burned, whereas the salt-glaze is obtained by the introduction of salt into the fire-boxes of kilns while the bricks are being burned. Glazed or enameled bricks are generally divided into two classes: (1) true enameled bricks, which have a glaze containing the coloring matter applied to it without any intermediate SLIP; (2) bricks which have a transparent glaze placed over a white or colored slip, the slip lying between the glaze and the material to be glazed. The latter is the process most used in this country. Manufacturers differ as to which process produces the best bricks although it would seem as though the true enamel would not chip or peel as readily. These bricks can be made in a variety of colors, from white to dark green or chocolate, and either in a HIGHLY GLAZED GLOSS or in a DULL, SATIN-FINISH, the latter finish being quite desirable in many instances on account of its doing away with the glare of the more highly glazed bricks or tiles. An enameled surface may be distinguished from a glazed surface by chipping off a piece of the brick. The glazed brick will show a layer of slip between the glaze and the body of the brick; while the enameled brick will show no line of demarcation between the body of the brick and the enamel. American enameled and glazed bricks are now extensively used on the exterior surfaces of buildings, particularly for street-fronts and light-houses, and for interior side walls and partitions of rooms or buildings used for a great variety of purposes.

**Sizes of Enameled Bricks.** Enameled bricks are made in two regular sizes: (1) English size, 9 by 3-in enameled surface,  $4\frac{1}{4}$ -in bed, and (2) American size,  $8\frac{3}{4}$  by  $2\frac{1}{4}$ -in enameled surface,  $4\frac{1}{4}$ -in bed. The English-size bricks cost about \$10 per 1 000 more than the American, but on account of the saving in the number of bricks, labor of laying and mortar in joints, the former really effect a saving of about 7 cts per sq ft. Enameled bricks are made, also, with a 12 by  $4\frac{1}{4}$ -in enameled surface,  $2\frac{1}{4}$ -in bed.

**Cost of Enameled Bricks.\*** The selling price of enameled bricks varies from \$75 per 1 000 for the American size to \$85 for the English size and \$100 for the 12 by  $4\frac{1}{4}$  by  $2\frac{1}{4}$ -in size; and at these prices the cost of the bricks per square foot is:

	cts
American size, 7 bricks to the foot.....	52½
English size, $5\frac{1}{4}$ bricks to the foot.....	45½
English flat, $3\frac{3}{4}$ bricks to the foot.....	36
12 by $4\frac{1}{4}$ by $2\frac{1}{4}$ -in, 3 bricks to the foot.....	30

**Colors of Enameled Bricks.** The standard colors carried in stock are white, cream and buff; other colors are made to order.

### Estimating Quantities and Cost of Brickwork \*

**Methods of Calculation.** The almost universal method of calculating the cost of brickwork is by estimating the number of thousands of bricks, WALL MEASURE, and then multiplying by a certain price per thousand, which is usually determined by experience and which is intended to include every item affecting the cost, and very often the profit. All of the common brickwork in any given building is usually figured at the same price per thousand bricks, the adjustment for the more expensive portions of the work being made in the manner of measuring. The principle underlying this system is explained as follows:

"The plain dead wall of brickwork is taken as the standard, and the most difficult, complicated, ornamental, or hazardous kinds of work are measured up to it so as to make the compensation equal. To illustrate, if, in one day, a mason can lay 2 000 bricks in a plain dead wall, and can lay only 500 in a pier, arch, or chimney-top in the same time, the cost of labor per thousand in such work is four times as much as in the dead wall, and he is entitled to extra compensation; but instead of varying the price, the custom is to vary the measurement to compensate for the difference in the time, and thus endeavor to secure a uniform price per thousand for all descriptions of ordinary brickwork, instead of a different price for the execution of the various kinds of work." †

**Measurements of Brick-Quantities.** PLAIN WALLS are quite universally figured at 15 bricks to the square foot of an 8 or 9-in wall,  $22\frac{1}{4}$  bricks per square foot of a 12 or 13-in wall, 30 bricks per square foot of a 16 or 17-in wall, and 7 bricks for each additional 4 or  $4\frac{1}{4}$  in in the thickness of the wall. These figures are used without regard to the size of the bricks, the effect of the latter being taken into account in fixing the price per thousand. No deduction is made for OPENINGS of less than 80 sq ft, and when deductions are made for larger openings the width is measured 2 ft less than the actual width. HOLLOW WALLS are also measured as if solid. To the number of bricks thus obtained is added 1

\* The prices given are pre-war prices.

† From Rules of Measurement adopted by the Brick Contractors' Exchange of Denver, Col.

measurement for piers, chimneys, arches, etc. **FOOTINGS** are generally measured in with the wall by adding the width of the projection to the height of the wall. Thus if the footings project 6 in on each side of the wall, 1 ft is added to the actual height of the wall. **CHIMNEY-BREASTS** and **PILASTERS** are measured by multiplying the girth of each breast or pilaster from the intersections with the wall by the height, and then by the number of bricks corresponding with the thickness of the projection. **FLUES** in chimneys are always measured solid. Detached **CHIMNEYS** and **CHIMNEY-TOPS** are measured as a wall having a length equal to the sum of the side and two ends of the chimney, and a thickness equal to the width of the chimney. Thus a chimney measuring 3 ft by 1 ft 4 in would be measured as a 16 or 17-in wall, 5 ft 8 in long. The rule for **INDEPENDENT PIERS** is to multiply the height of each pier by the distance around it in feet, and consider the product as the superficial area of a wall whose thickness is equal to the width of the pier. In practice, many masons measure only one side and one end of a pier or chimney. **ARCHES** of common bricks over openings of less than 80 sq ft are usually disregarded in estimating. If the arch is over an opening larger than 80 sq ft, the height of the wall is measured from the springing-line of the arch. No deduction is made in the wall-measurement for stone sills, caps, or belt-courses, nor for stone ashlar, if the same is set by the brick-mason. If the ashlar is set by the stone-mason, the thickness of the ashlar is deducted from the thickness of the wall. The sum of all of these measurements represents a certain number of **THOUSANDS OF BRICKS**, and the whole is then multiplied by a common price per thousand, as \$6, \$8, \$12, or \$16, according to whatever the cost of plain brickwork may be. If the building is to be faced with **PRESSED BRICKS**, the actual cost of the pressed bricks, as nearly as it can be computed, is added to the estimated price of the common brickwork, nothing being added for laying the pressed bricks, nor anything deducted from the common-brick measurement, the measurement of the common work displaced by the pressed bricks being assumed to offset the difference in the cost of laying the pressed and common brickwork. In arriving at the **COST OF THE PRESSED BRICKS**, the external superficial area of the walls faced with such bricks is computed, and all openings, belt-courses, stone caps, etc., are deducted. Five-in stone sills are not usually deducted. If a portion of the wall is covered by a porch, so that common bricks may be used back of it, this space, also, is deducted. The net pressed-brick surface is then multiplied by 6,  $6\frac{1}{2}$ , or 7 to obtain the number of bricks required,  $6\frac{1}{2}$  giving about the number of pressed bricks of the standard size required to the square foot. The **TOPPING OUT** of chimneys, if of face-brick, is measured by girting the chimneys, multiplying by the heights, and adding the sums to the wall-area.

**Example.** As a simple example of this system of estimating consider a small brick house, 28 by 32 ft in plan, without cross-walls, the basement-walls being 12 in thick, with footings 2 ft 6 in wide; the first-story walls, 13 in thick; the second-story walls, 9 in thick; the height of the basement-walls from the trench to the top of the first-story joists, 8 ft 6 in; the height of the walls from the first-story joists to the top of the second-story joists, 10 ft 6 in; and from the second-story joists to the plate, 9 ft.

**WALL-MEASUREMENTS.** Basement-walls: 120 ft (girth of building) by 9 ft 6 in (height and projection of footing) by  $22\frac{1}{2}$  bricks per square foot; equal to 550 bricks.

First-story walls: 120 ft by 10 ft 6 in by  $22\frac{1}{2}$  bricks per square foot; equal to 28360 bricks.

Second-story walls: 120 ft by 9 ft by 15 bricks per square foot; equal to 200 bricks.

Topping out two chimneys, each 1 ft 9 in by 1 ft 5 in by 14 ft high above roof:

2 by 14 ft by (1 ft 5 in plus 1 ft 9 in plus 1 ft 5 in) by 30 bricks per square foot, equal to 3 850 bricks.

Total brickwork: 74 960 bricks. At \$9 per 1 000, the cost is \$674.64.

**PRESSED BRICKS.** From the grade to the under side of the plates, the wall measures 22 ft 6 in and it is to be faced with pressed bricks of the standard size, costing \$15 per 1 000. The door-openings and window-openings measure 384 sq ft.

The surface of pressed bricks equals 120 by 22½ ft, equal to.....	2 700 sq ft
The deduction for openings is.....	384 sq ft

Area, after deduction.....	2 316 sq ft
Addition for two chimneys, 2 by 14 by 6 ft 4 in, equal to.....	177 sq ft

Total	2 493 sq ft
-------	-------------

2 493 by 6½ equals 16 204 pressed bricks, which, at \$15 per 1 000 cost, equal \$243.

The total amount of the bid is \$674.64 plus \$243, or \$917.64.

The above figures are supposed to include the necessary lime, sand, water, scaffolding, etc., required to make the mortar and put up the walls, and also a profit for the contractor; but anything in the way of ironwork, such as ties, thimbles, ash-doors, etc., are figured as additions to this amount.

**Detailed Estimates of Brickwork.** In estimating by the above method, the price per thousand is to some extent a matter of guesswork, and while an experienced contractor may perhaps make as accurate an estimate by this method as is possible by any, yet it is often necessary to estimate the work in detail; and even when the work has been estimated as above, it is necessary for the contractor to know how many bricks and how much sand and lime will be required to do the work. The following data will assist in making such detailed estimates.

With the size of bricks used in the Western States, from 16½ to 17¾ common bricks are required to the cubic foot after deducting openings, and figuring the thickness of walls at 8, 12, 16, 20 in, etc., the actual number of bricks required will run about two-thirds of the WALL-MEASURE when the openings are of about the average number and size.

The number of pressed bricks will be about 6 or 6½ bricks to the foot, after deducting openings.

To lay 1 000 common bricks, kiln-count, requires 2½ bushels or 200 lb of white lime and ¾ cu yd of sand. For a good lime-and-cement mortar, allow 2 bushels of lime, 1 bbl of cement and ¾ cu yd of sand. For 1 : 3 cement-and-sand mortar, allow 1½ bbl of cement and ¾ cu yd of sand, or one-half a load.

To lay 1 000 pressed bricks with buttered joints will require 2 bushels of lime (160 lb) and ¾ cu yd of sand; with spread joints, from 2 to 2½ bushels of lime and from ¾ to 1 cu yd of sand.

If colored mortar is used, about \$1 per 1 000 bricks should be added for the mortar-color.

A brick-mason, working on a city job under a good foreman, will lay, on an average, 60 pressed (face) bricks per hour, and from 150 to 175 common bricks per hour, 160 being a fair average. In country towns the average is nearer 120 per hour.

With wages at 62½ cts per hour for masons, 31¼ cts for hod-carriers, and 30 cts for mortar-mixers and carriers, sand at 60 cts per cu yd, and lime at 40 cts per bushel of 80 lb, brick-masons in Denver state that the average cost of laying common bricks in 12-in walls is about \$6 per 1 000, kiln-count, and of laying pressed bricks about \$10 per 1 000.

For common brickwork, one helper will be required for every mason, and on 9-in walls, faced with pressed bricks, one helper to every two masons. In building common-brick fireplaces and chimneys one mason and helper will lay about 600 bricks in a day of nine hours.

As a rule, chimneys built of common bricks and with 4-in walls cost about 50 cts per running foot, in height, for single flues, and 90 cts for double flues.

**Space Required for Piling Bricks.** One thousand bricks closely stacked occupy about 56 cu ft of space. One thousand old bricks, cleaned and loosely stacked, occupy about 72 cu ft.

A brick-layer's hod measures 21 by 7 by 7 in, and will hold 18 bricks.

A mortar-hod measures 24 by 12 by 12, and 12 in across the top.

**Mortar-Colors** are usually in the form of dry powders, or of pulp or paste. The powders are put up in barrels, the number of pounds to the barrel and price per pound being about as follows:

Red, in 500-lb barrels, dry . . . . .	from 1¾ to 2	cts per lb
Brown, in 450-lb barrels, dry . . . . .	from 1¾ to 2½	cts per lb
Buff, in 400-lb barrels, dry . . . . .	from 1¾ to 2½	cts per lb
Black, in 1 000-lb barrels, dry . . . . .	from 3 to 3½	cts per lb

For lots of less than full barrels an extra charge is sometimes made for packing and drayage.

In pulp or paste-form:

Red, brown and buff . . . . .	1¾ cts per lb
Black . . . . .	3 cts per lb
All other colors . . . . .	2 cts per lb

Colors in paste-form can be obtained in casks, barrels, half-barrels and kegs, all (except black and buff) weighing, in casks, 900 lb; in barrels, 550 lb; and in half-barrels, 375 lb. The buff weighs, in casks, 700 lb; in barrels, 450 lb; and in half-barrels, 300 lb. Black weighs, in barrels, 450 lb; and in half-barrels, 275 lb. To color the mortar for laying 1 000 bricks with ½-in joints requires about 50 lb of red, terra-cotta color, amber, fern-green and salmon; 40 lb for buff, brown, colonial drab or French gray; and 25 lb for black. For wider joints, a larger quantity of stain must be used. For paste-colors an average mixture is, 1 bucket of paste-color to 7 buckets of mortar for brickwork with ½-in joints. When the colors are in the form of dry powder they are first mixed with dry sand, the cold slaked lime is then added and again mixed thoroughly. It is very important that the color be uniformly mixed. If it is not added at first, but left until the mortar is made, the labor of mixing is doubled. The more thorough the mixing the less color is required. Mortar colors should never be mixed with wet lime. When the color is in the form of a pulp or paste, it should be thoroughly hoed in, in order to secure a uniform and smooth shade. For very fine pressed bricks, the stained mortar should be strained through a coarse sieve.

**Efflorescence on Brickwork.** A white EFFLORESCENCE often appears on brickwork, especially in moist climates and damp places. It may spread over large areas of the wall-surface although originating in the mortar joints. Soluble salts, principally of soda, potash and magnesia, in the cement or lime mortar, are dissolved by the water absorbed by the mortar and later precipitated on the surface of the brickwork as a white deposit, when the water evaporates. This deposit seems to be greater with the natural than with the Portland-cement mortars and still heavier with lime mortar. The origin of the efflorescence may be in the bricks themselves as well as in the mortar used. This is the case when the bricks are made from clays containing iron pyrites or burned with sulphurous

coal. Moisture in such bricks tends to dissolve the sulphate of magnesia and sulphate of lime, which, in the evaporation of the water, are deposited on the surface as crystals of these salts. Efflorescence may result, also, from water impregnated from the mortar, absorbed by the bricks and then evaporated, leaving the whitish deposits; and it is sometimes caused by adulterations in certain MORTAR-COLORS. As a PREVENTIVE, General Gilmore recommended the addition to every 300 lb of the cement powder, 100 lb of quicklime, and from 8 to 12 lb of any cheap ANIMAL FAT, which is to be thoroughly incorporated with the quicklime before the latter is slaked, preparatory to adding it to the cement. The alkaline salts tend to be SAPONIFIED by the fat. This is not an entirely satisfactory treatment, and as a rule it only partly prevents or removes the objectionable deposits; and this addition to the cement retards its setting and somewhat diminishes its strength. It is claimed by some that boiled LINSEED-OIL, applied to brickwork in two coats, will lessen the absorption of moisture for from one to three years and thus lessen the tendency to efflorescence. It is usually mixed in the proportion of 2 gal of oil to 300 lb of dry cement, either with or without lime; but it is injured by the mortar and, like the fat, retards the setting of the cement mortar and weakens it. In order to diminish the chances of efflorescence on brickwork, the walls should be made as IMPERVIOUS as possible by laying the bricks in a rich well-mixed Portland-cement mortar and filling all joints full and solid. If the building is on damp ground, carefully constructed DAMP-PROOF COURSES of the proper materials should be built into the walls or a course of horizontal joints near the bottom of the walls should be WATERPROOFED. Reasonably hard bricks should be used for facing, projections and exposed top surfaces waterproofed and provided with drips, and the roof, cornice and gutters made water-tight. When efflorescence is due to the penetration of rain-water or moisture into the brickwork and it is required to preserve the texture and color of the work, the surface may be coated with preparations of PARAFFINE or with various patented WATERPROOFING MIXTURES. The preparations containing paraffine are usually applied hot, and the walls, also, are heated by portable heaters previous to the application. They give fairly good results, but are quite expensive, owing to the time and labor required for their application. Brick walls may be rendered impervious to moisture by washes applied by the SYLVESTER PROCESS. These washes consist of an ALUM-SOLUTION made by dissolving 1 lb of alum per gallon of water, and a SOAP-SOLUTION made by dissolving 2½ lb of pure hard soap per gallon of water. The brick walls should be dry and clean and it is recommended that they should not be colder than 50° F. The soap-wash is made boiling hot and then applied to the brickwork. The temperature of the alum-solution is usually from 60° to 70° F. when put on. One wash is applied and allowed to dry for about 24 hours, after which the other wash is put over it. When ALUMINIUM SULPHATE, improperly called ALUM, is substituted for the alum, the cost of the wash is less, only two-thirds as much sulphate as alum is required and the results are better.

## LIME \*

**Nature and Properties of Lime.** Chemically, lime is calcium oxide. Used in a broader sense, it is the class-name of a great variety of products manufactured by the calcination of LIMESTONE. Limestone consists of the carbonates of calcium and magnesium which vary widely in their ratio to each other. The limestones used in the manufacture of lime products may be divided into two

\* Valuable practical data relating to lime and plaster has been furnished by the **Charles Warner Company**, of **Wilmington, Del.**

classes, **CALCIUM LIMESTONES** and **DOLOMITIC LIMESTONES**. High-calcium limestones contain only a relatively low percentage of magnesium carbonate, while dolomitic limestones contain a considerable amount of it. Dolomitic limestone usually corresponds roughly to the theoretical formula of dolomite ( $\text{CaCO}_3$ ) ( $\text{MgCO}_3$ ). The **CALCINATION** of limestone consists of heating to expel the carbon dioxide. The product resulting from calcination of limestone is known as **QUICKLIME** and possesses great affinity for water. **SLAKING** is the process of adding water to quicklime. During the process of slaking, heat is energetically evolved and much of the water driven off in the form of steam. During this slaking process, also, high-calcium quicklimes must be agitated and stirred continually or a portion will fail to receive the proper quantity of water and will contain unslaked particles which are likely to slake after being used in the work, causing **POPPING**, **PITTING** and disintegration. Dolomitic limes do not slake so energetically, and while they should be stirred while slaking, this is not so necessary as with high-calcium limes. Either class of quicklime, through faulty manufacture, is likely to contain over-burned portions which slake with difficulty and may cause popping, etc., if the lime-paste is not carefully screened before use. The **SETTING** and **HARDENING** of common lime mortar is due, first, to the drying out and, secondly, to the absorption of carbon dioxide from the atmosphere and the formation of crystals of calcium carbonate to which the strength of the mortar is ascribed. In the manufacture and use of common lime mortar, therefore, the raw material, limestone, is first calcined, and the carbon dioxide expelled; it is then slaked with water and forms calcium hydroxide, in which the water is gradually replaced by carbon dioxide. The lime thus eventually returns to its original carbonate form. As far as the ultimate result is concerned, there is generally little difference between high-calcium and dolomitic quicklimes. Owing to greater familiarity with one or the other of the classes of lime, architects and builders in certain sections of the country prefer one to the other.

**Specifications for Quicklime.** The lime industry has in recent years been made the subject of careful study and the following clauses give the various requirements of Standard Specifications for Quicklime adopted by the American Society for Testing Materials in 1915.

1. **DEFINITION.** Quicklime is a material the major part of which is calcium oxide or calcium and magnesium oxides, which will slake on the addition of water.

2. **GRADES.** Quicklime is divided into two grades:

(a) **Selected.** Shall be well-burned, picked free from ashes, core, clinker or other foreign material.

(b) **Run-of-Kiln.** Shall be well-burned, without selection.

3. **FORMS.** Quicklime is shipped in two forms:

(a) **Lump.** Shall be kiln-size.

(b) **Pulverized Lime.** Lump lime reduced in size to pass a  $\frac{1}{4}$ -in screen.

4. **CLASSES.** Quicklime is divided into four classes: (a) High-Calcium; (b) Calcium; (c) Magnesian; (d) High-Magnesian.

5. **BASIS OF PURCHASE.** The particular grade, form and class of quicklime desired shall be specified in advance by the purchaser.

## I. Chemical Properties and Tests

### (A) Sampling

1. **LIME IN BULK.** When quicklime is shipped in bulk, the sample shall be so taken that it will represent an average of all parts of the shipment from top to bottom, and shall not contain a disproportionate share of the top and bottom layers, which are most subject to changes. The samples shall comprise at least shovelfuls taken from different parts of the shipment. The total sample



taken shall weigh at least 100 lb and shall be crushed to pass a 1-in ring and quartered to provide a 15-lb sample for the laboratory.

7. **LIME IN BARRELS.** When quicklime is shipped in barrels, at least 3% of the number of barrels shall be sampled. They shall be taken from various parts of the shipment, dumped, mixed and sampled as specified in Section 6.

8. **LABORATORY SAMPLES.** All samples to be sent to the laboratory shall be immediately transferred to an air-tight container in which the unused portion shall be stored till the quicklime is finally accepted or rejected by purchaser.

### (B) Chemical Tests

9. **CHEMICAL PROPERTIES.** (a) The classes and chemical properties of quicklime shall be determined by standard methods of chemical analysis. (b) Samples shall be taken as specified in Sections 6, 7 and 8. (c) Quicklime shall conform to the following requirements as to chemical composition:

#### CHEMICAL COMPOSITION

Properties considered	High-Calcium		Calcium		Magnesian		High-Magnesian	
	Select-ed	Run of kiln	Select-ed	Run of kiln	Select-ed	Run of kiln	Select-ed	Run of kiln
Calcium oxide, per cent..	90 (min)	90 (min)	85-90	85-90	..	..	..	..
Magnesium oxide, per ct.	..	..	..	..	10-25	10-25	25 (min)	25 (min)
Calcium oxide plus magnesium oxide, min, per cent.....	90	85	90	85	90	85	90	85
Carbon dioxide, max, per cent.....	3	5	3	5	3	5	3	5
Silica plus alumina plus oxide of iron, max, per cent.....	5	7.5	5	7.5	5	7.5	5	7.5

### II. Physical Properties and Tests

10. **PERCENTAGE OF WASTE.** An average 5-lb sample shall be put into a box and slaked by an experienced operator with sufficient water to produce the maximum quantity of lime putty, care being taken to avoid burning or drowning the lime. It shall be allowed to stand for 24 hours and then washed through a 20-mesh sieve by a stream of water having a moderate pressure. No material shall be rubbed through the screens. Not over 3% of the weight of the selected quicklime nor over 5% of the weight of the run-of-kiln quicklime shall be retained on the sieve. The sample of lump lime taken for this test shall be broken so that all of it will pass a 1-in screen and be retained on a 1/4-in screen. Pulverized lime shall be tested as received.

### III. Inspection and Rejection

11. **INSPECTION.** (a) All quicklime shall be subject to inspection.

(b) The quicklime may be inspected either at the place of manufacture or the point of delivery, as arranged at time of purchase.

(c) The inspector representing the purchaser shall have free entry, at all times while work on the contract of the purchaser is being performed, to all parts of the manufacturer's works which concern the manufacture of the quicklime ordered. The manufacturer shall afford the inspector all reasonable facilities for inspection and sampling, which shall be so conducted as not to interfere unduly with the operation of the works.



(d) The purchaser may make the tests to govern the acceptance or rejection of the quicklime in his own laboratory or elsewhere. Such tests, however, shall be made at the expense of the purchaser.

12. **REJECTION.** Unless otherwise specified, any rejection based on failure to pass tests prescribed in accordance with these specifications shall be reported within five days from the taking of samples.

13. **REHEARING.** Samples which represent rejected quicklime, shall be preserved in air-tight containers for five days from the date of the test-report. In case of dissatisfaction with the results of the tests, the manufacturer may make claim for a rehearing within that time.

**Hydrated Lime.** The slaking of quicklime is an operation which is almost invariably carried on by laborers who have little or no conception of the importance of their task. As a result, many failures have been charged to lime in the past which actually were due to improper preparation during the slaking operation. The new product known as **HYDRATED LIME** has been offered widely to the trade in recent years and has met with much success. Hydrated lime is a dry flocculent powder resulting from the slaking of quicklime by mechanical means, with an amount of water which is sufficient to satisfy the calcium oxide, but insufficient to make a paste or putty. Hydrated lime is manufactured in mechanical hydrators in which the batches of quicklime and water used are carefully proportioned by weight. After passing from the hydrator, hydrated lime is subjected to a mechanical system of separation which eliminates the coarse or impure particles which may cause popping, etc. Hydrated lime is sold in bags of definite weight and requires only to be mixed with sand and water to make the mortar. The bags have usually been made of heavy burlap or duck cloth, containing 100 lb, or of paper, containing 40 lb. Several of the more prominent manufacturers of hydrated lime in the United States employ chemists who regularly superintend the manufacture of hydrated lime, just as the chemists in Portland-cement factories superintend the proportioning of the raw mix going to the kilns to be burned for Portland cement. The hydrated lime manufactured under such chemical supervision is a reliable product free from tendencies which might give rise to popping, pitting or disintegration. Hydrated lime of good quality may be used for almost any purpose for which lime mortar is used, and is by some considered a more reliable product than quicklime. Among the fewer uses for hydrated lime may be mentioned its employment in cement mortars and concrete. An addition of about 15% of hydrated lime to cement mortar or concrete decreases its permeability to water, reduces the cracking due to shrinkage, etc., and increases the plasticity of the mortar or concrete, thus preventing separation of the sand, stone and cement and causing the mixture to flow and fill the forms more readily. (See Macgregor tests, page 276.)

**Specifications for Hydrated Lime.** The following clauses give the various requirements of Standard Specifications for Hydrated Lime adopted by the American Society for Testing Materials in 1915.

1. **DEFINITION.** Hydrated lime is a dry flocculent powder resulting from the hydration of quicklime.

2. **CLASSES.** Hydrated lime is commercially divided into four classes: (a) High-Calcium; (b) Calcium; (c) Magnesian; (d) High-Magnesian.

3. **BASIS OF PURCHASE.** The particular type of hydrated lime desired shall be specified in advance of purchase.

#### I. Chemical Properties and Tests

1. **SAMPLING.** The sample shall be a fair average of the shipment. Three per cent of the packages shall be sampled. The sample shall be taken from the face to the center of the package. A 2-lb sample to be sent to the laboratory

shall immediately be transferred to an air-tight container, in which the unused portion shall be stored until the hydrated lime has been finally accepted or rejected by the purchaser.

5. **CHEMICAL PROPERTIES.** (a) The classes and chemical properties of hydrated lime shall be determined by standard methods of chemical analysis. (b) The non-volatile portion of hydrated lime shall conform to the following requirements as to chemical composition:

#### CHEMICAL COMPOSITION

Properties considered	High-Calcium	Calcium	Magnesian	High-Magnesian
Calcium oxide, per cent. ....	1/90 (min)	85-90	....	25 (min)
Magnesium oxide, per cent. ....	....	....	10-25	....
Silica plus alumina plus oxide of iron, max, per cent. ....	5	5	5	5
Carbon dioxide, max, per cent. ....	5	5	5	5
Water.....	Sufficient to hydrate the calcium-oxide content	Sufficient to hydrate the calcium-oxide content	Sufficient to hydrate the calcium-oxide content	Sufficient to hydrate the calcium-oxide content

#### II. Physical Properties and Tests

6. **FINENESS.** A 100-g. sample shall leave by weight a residue of not over 5% on a standard 100-mesh sieve and not over 0.5% on a standard 30-mesh sieve.

7. **CONSTANCY OF VOLUME.** Hydrated lime shall be tested to determine its constancy of volume in the following manner: Equal parts of hydrated lime under test and volume-constant Portland cement shall be thoroughly mixed together and gauged with water to a paste. Only sufficient water shall be used to make the mixture workable. From this paste a pat about 3 in in diameter and  $\frac{1}{2}$  in thick at the center, tapering to a thin edge, shall be made on a clean glass plate about 4 in square. This pat shall be allowed to harden 24 hours in moist air and shall be without popping, checking, cracking, warping or disintegration after 5 hours' exposure to steam above boiling water in a loosely closed vessel.

#### III. Packing and Marking

8. **PACKING.** Hydrated lime shall be packed either in cloth or paper bags and the weight shall be plainly marked on each package.

9. **MARKING.** The name of the manufacturer shall be legibly marked or tagged on each package.

#### IV. Inspection and Rejection

10. **INSPECTION.** (a) All hydrated lime shall be subject to inspection.

(b) The hydrated lime may be inspected either at the place of manufacture or the point of delivery, as arranged at the time of purchase.

(c) The inspector representing the purchaser shall have free entry, at all times while work on the contract of the purchaser is being performed, to all parts of the manufacturer's works which concern the manufacture of the hydrated lime ordered. The manufacturer shall afford the inspector all reasonable facilities for inspection and sampling, which shall be so conducted as not to interfere unnecessarily with the operation of the works.

(d) The purchaser may make the tests to govern the acceptance or rejection of the hydrated lime in his own laboratory or elsewhere. Such tests, however, made at the expense of the purchaser.

**11. REJECTION.** Unless otherwise specified, any rejection based on failure to pass tests prescribed in these specifications shall be reported within five working days from the taking of samples.

**12. REHEARING.** Samples which represent rejected hydrated lime shall be preserved in air-tight containers for five days from the date of the test-report. In case of dissatisfaction with the results of the tests, the manufacturer may make claim for a rehearing within that time.

**Alca Lime.** A recent development in the lime industry is Alca Lime.\* This is a material said to combine the plasticity and sand-carrying qualities of lime mortar with the strength, hardness and quicker set of the gypsum plasters. It is composed of approximately 85% of hydrated lime and 15% of a specially prepared material containing alumina and silica in such proportions as to combine, forming bodies which greatly contribute to the strength, hardness and plasticity of the product. It is sold in 100-lb packages and requires only to be mixed with sand and water before use. When used for plastering, it has the characteristics of lime mortar, and while it becomes hard and strong, it is claimed that it is free from the so-called sounding-board effects noticed in some hard-wall plasters. It is not injured by water and is often used for outside stucco-work and also as a brick-laying mortar in place of lime mortar gauged with Portland cement. The manufacturers' directions for the use of Alca Lime should be carefully observed, and this may be said of all prepared plastering or cementing materials.

**Useful Data on Quicklime.** Quicklime is shipped either in barrels or in bulk. In dry climates it will keep for a long time in bulk, but in damp climates and along the coast it soon slakes unless enclosed in barrels. By Act of Congress, August 23, 1916, it is required that lime in barrels shall be packed only in barrels containing 280 lb or 180 lb, net weight. When shipped in bulk it is generally sold by the bushel of 80 lb,  $3\frac{1}{2}$  bushels or 280 lb, net, of lime being considered as equivalent to a large barrel. Other weights are 180 lb, net, per small barrel, and 64 lb per cu ft. The average yield of LIME-PASTE from the best Eastern limes has been found to be 2.62 times the bulk of unslaked lime. A barrel of good quality well-burned lime should make 8 cu ft, or 20 pails, of lime-paste or putty. Careful experiments conducted by United States engineers have demonstrated that the best mortar is obtained by mixing one part of lime paste to two parts of sand.

**Cements.** For data on cements, see Chapter III.

## SAND AND GRAVEL

**Sand** is obtained from banks or pits, from river-beds and from the seashore. Pit-sand or bank-sand, free from clay or earthy materials, is generally considered the best for mortar, although excellent sand is often obtained from river-beds. Sea-sand contains alkaline salts which attract and retain moisture and which, unless thoroughly washed, cause efflorescence when used in brickwork. Both sea-sand and river-sand have more or less rounded grains, to which lime or cement will not adhere as well as to sharp, angular grains. Both are extensively used, however, for lack of better materials. The use of sand in mortar is to prevent excessive shrinkage and to save the cost of lime or cement. Sand, when used in the proportion of 1 : 2, strengthens lime mortar, but any addition of sand to cement weakens it.

**Screening Sand.** Sand for mortar must ordinarily be screened. Sand for brown mortar for plastering or common brickwork is ordinarily run through a

\* This is a patented article and is offered for sale by many licenses in the United States under the Spackman patents.

No. 4 screen having 4 by 4 meshes to the inch. For sand finish and mortar pressed brickwork, either a No. 10 or a No. 12 screen with 10 by 10 or 12 by 12 meshes to the inch is commonly used. For rubble stonework the sand is ordinarily screened, unless it contains much gravel, in which case it should be screened through a  $\frac{3}{8}$ -in mesh.

**Weight of Sand.** Dry sand weighs from 80 to 115 lb per cu ft. The average weight of damp (not wet) sand is about 96 lb per cu ft, or about 2 600 lb per cu yd. The voids for ordinary sand range from 0.3 to 0.5 of the volume, the average for screened sand suitable for mortar being 0.35 of the volume. The more uneven the grains in size the smaller the percentage of the voids. A one-horse load of sand contains about 22 cu ft. Two-horse loads vary from  $1\frac{1}{4}$  to 2 yd. The amount hauled per load in the larger cities is generally fixed by the Team Owners' Association.  $1\frac{1}{4}$  yd is a fair load,  $1\frac{1}{2}$  yd a good load and 2 yd a large load.

## LATHING AND PLASTERING

**Wooden Laths** should be well seasoned, free from sap, bark and dead knots. Bark on laths is quite sure to stain the plaster. White pine is generally considered the best wood for laths, although spruce and hemlock laths are much used. Hard pine is not a good material, as it contains too much pitch. The regular size of laths is  $\frac{3}{4}$  in by  $1\frac{1}{2}$  in by 4 ft. The width and thickness vary somewhat in different mills. There is a new lath on the market, which is only 32 in long and which costs from \$1.75 to \$2 less than the 48-in lengths. Laths are sold by the thousand, in bunches containing 100 laths, from \$4.50 to \$5.50 being about the average prices. (Pre-war prices.)

**Metal Lathing.** (See Chapter XXIII, pages 883 to 887.)

Plastering on laths is generally done in three coats.\* The first coat is called the SCRATCH-COAT; the second, the BROWN COAT, and the third, the WHITE COAT, SKIM-COAT, or FINISH. On brickwork or stonework the scratch-coat is generally omitted. For first-class work each coat should be permitted to dry thoroughly before the next coat is applied, and under no circumstances should the finish-coat be applied before the brown coat is thoroughly dry.

**Drawn Work** is a brown coat applied to a scratch-coat from the same staging, immediately after the scratch-coat is applied. It is a little cheaper than DRY SCRATCH, and much of it is done in the Western States.

The Scratch-Coat should always be made rich in lime, and should contain  $1\frac{1}{2}$  bu of hair, or an equivalent quantity of fiber to each cask of lime, or 1 bu of hair to 2 of lime. A proportion of one part lime-paste to two parts of sand will require 1 cask ( $2\frac{1}{2}$  bu) of lime to  $5\frac{1}{2}$  bbl of screened sand.

The Brown Coat should contain 1 cask ( $2\frac{1}{2}$  bu) of lime to 7 bbl of screened sand, and 1 bu of hair to 5 of lime. Very little plaster is mixed by measure, however, the usual custom being to mix as much sand with the slaked lime as the mortar-mixer thinks it will stand and give satisfaction, the tendency being always to make the lime go as far as possible.

The Third or Finishing Coat is designated by various terms, such as SKIM-COAT, WHITE COAT, PUTTY-COAT, SAND-FINISH, etc. The skim-coat as used in the

\* In the Eastern States, dwellings of moderate cost are generally plastered with two-coat work, the first or scratch-coat being brought nearly to the grounds, and carefully finished to receive the skim-coat.

**Eastern States** is generally composed of lime-putty and washed beach-sand in equal proportions.

**Sand Finish**, which has a rough surface resembling coarse sandpaper, is mixed in the same way, only that coarser sand and more of it is used, and it is finished with a wooden or cork-faced float.

**White Coating or Hard Finish** generally means a composition of lime-putty and plaster of Paris, to which marble-dust is sometimes added. Plaster of Paris and marble-dust when used should not be mixed with the lime-putty until a few moments before using, and no more should be prepared at one time than can be used up at once, as it soon SETS, after which it should not be used. The skim-coat or hard finish should be finished with a steel trowel and wet brush. The more the work is troweled the harder it becomes. A superior hard finish is obtained by mixing 4 parts of Best's Keene's cement to 1 part lime-putty.

**Mortar for Plastering.** To make sure that the lime is well slaked, it is customary to require that the mortar for plastering shall be mixed at least seven days before it is used.

**Hair** such as is used by plasterers is obtained from the hides of cattle, and after being washed and dried is put up in paper bags, each bag being supposed to contain 1 bushel of hair when beaten up. Each package is supposed to weigh from 5 to 8 lb but the weight often falls short. **ASBESTOS** and **MANILLA FIBER** are both used in place of hair; they are cleaner than hair and are said to be less injured by the lime. It is much better to add the hair to the lime-paste AFTER IT IS COLD and before mixing in the sand, as hot lime, and the steam caused by the slaking, will burn or rot the hair so as to greatly weaken it. The common practice is to put the hair in the mortar-box, run off the hot lime as soon as it is slaked, throw in the sand and mix the whole together. It is then thrown out of the box into a pile and a new batch mixed up.

**Machine-Made Mortar.** In several of the larger cities plants have been equipped for the mixing of mortar by machinery. Machine-mixed mortar should be much better than the ordinary hand-mixed mortar, for the reason that time can be given for the lime to slake, the lime and sand can be accurately measured, and the hair and lime are not mixed with the lime until just before delivery. The mixing may also be more thoroughly and evenly done by machinery than is possible by hand.

**Improved Wall-Plasters.** Owing to the difficulty of obtaining sufficient space for building operations in central sections of large cities to properly slake sufficient lime mortar to carry on the plastering with the necessary speed, other kinds of plastering materials have come into existence in recent years. These are known as **GYPSUM PLASTERS** or **HARD-WALL PLASTERS**. The base of these products is calcium sulphate or gypsum which has been calcined to partially expel the water. The setting and hardening of these products is dependent upon their combining chemically with the gauging water and crystallizing in the same chemical form as the material possessed before calcination. All hard-wall plasters contain material added for the purpose of controlling the SET. The straight calcined gypsum sets in a very few minutes, which time would be entirely too short to permit the workmen to apply the plaster to the wall and straighten it up before it had set. These plasters are characterized, also, by their inability to carry as much sand as lime mortar. Many of them contain other substances, such as clay or hydrated lime, added to improve their PLASTICITY. Hard-wall plasters manufactured in the eastern part of the United States from rock-gypsum invariably contain 15%, more or less, of clay or hydrate, added for this purpose. Plasters made in Kansas, Oklahoma, Texas and other

Western and Southwestern States are made from earth-gypsum. In the case of these materials, clay and hydrated lime are not added, for the reason that the earth-gypsum contains considerable clay matter, which renders further additions unnecessary.

**Use of Hard-Wall Plasters.** Hard-wall plasters are found to be very convenient in cases where space and time are the most important elements in the building operation. They set more rapidly than lime plasters, thus permitting the white coating and finishing of the job to be completed earlier. While hard-wall plasters become extremely hard, this property is sometimes considered objectionable, as it may give rise to what is called the SOUNDING-BOARD effect.

**Keene's Cement Plasters.** As distinguished from the ordinary hard-wall plasters, there exists another class of gypsum-products which, however, are somewhat different in the method of preparation and behavior. In the manufacture of these materials, the gypsum is calcined, immersed in a bath of alum or similar chemical and recalcined. The name KEENE'S CEMENT is usually applied to these materials, which are made by several manufacturers in this country. These are slow-setting and ultimately attain great strength and hardness. Keene's cement is generally used with considerable lime-putty or hydrated lime. The use of equal parts of hydrated lime and Keene's cement in making a plastering material is often recommended and found in specifications. (For Alca lime used as a wall-plaster, see page 1553.)

**Advantages of Improved Wall-Plasters.** Among the advantages gained by the use of these plasters are uniformity in strength and quality, extra hardness and toughness, freedom from pitting, saving in time required in making and drying, minimum danger from frost while being applied and before set, less weight and moisture in the building, and, in some cases, greater resistance to the action of fire.

**Measuring Plasterers' Work.** Lathing is always figured by the square yard and is generally included with the plastering, although in small country towns the carpenter often puts on the laths. Plastering on plane surfaces, such as walls and ceilings, is always measured by the square yard, whether it is one-coat, two-coat, or three-coat work, or lime or hard plaster. In regard to deductions for openings, custom varies somewhat in different parts of the country and also with different contractors. Some plasterers allow one-half the area of openings for ordinary doors and windows, while others make no allowance for openings of less than 7 sq yd.

**Miscellaneous Details.** Returns of chimney-breasts, pilasters and all strips less than 12 in in width should be measured as 12 in wide. Closets, soffits of stairs, etc., are generally figured at a higher rate than plain walls or ceilings, as it is not as easy to get at them. For circular or elliptical work, domes or groined ceilings, an additional price is made. If the plastering cannot be done from trestles an additional charge must be made for staging. Whenever plastering is done by measurement the contract should definitely state whether or not openings are to be deducted, and a special price should be made for the stucco-work, based on the full-size details.

**Cornices and Moldings.** Stucco cornices and molded work are generally measured by the superficial foot, measuring on the profile of the molding. When less than 12 in in girth they are usually rated as 1 ft. For each internal angle 1 lin ft should be added, and for external angles, 2 lin ft. For cornices on circular or elliptical work an additional price should be charged. Enriched moldings are generally figured by the linear foot, the price depending upon the design and size of the mold.

**Quantities of Materials for Lathing and Plastering**

**Miscellaneous Data.** To cover 100 sq yd requires from 1 400 to 1 500 laths, or say 1 450 for an average job, and 10 lb of threepenny fine nails.

Three-coat plastering on wooden laths, plaster-of-Paris finish, will require from 10 to 12 bu of lime,  $1\frac{1}{2}$  cu yd of sand, 2 bu of hair and 100 lb of plaster of Paris per 100 sq yd.

If the finish-coat is omitted, deduct 2 bu of lime and all of the plaster of Paris.

If sand-finished, omit the plaster of Paris and add  $\frac{1}{2}$  cu yd of sand.

To cover 100 sq yd with two coats on brick or stone walls, the brown coat and finishing coats, will require from 8 to 10 bu of lime,  $1\frac{1}{2}$  cu yd of sand, and 100 lb of plaster of Paris, to 100 sq yd.

Using Best's Keene's cement for brown mortar and Keene's finish on expanded-metal lath will require, for brown mortar, 550 lb of cement,  $5\frac{1}{2}$  bu of lime, 2 cu yd of sand and 2 bu of hair; for the finish, 300 lb of cement and 1 bu of lime per 100 yd.

Hard plasters on expanded-metal lath, plaster-of-Paris finish, require, for brown mortar, 2 000 lb of plaster and 2 cu yd of sand; for the finish, 1 bu of lime and 100 lb of plaster of Paris per 100 yd.

**Cost of Lathing and Plastering.** The average price for putting on wooden laths, labor only, is  $4\frac{3}{4}$  cts per yard. For expanded or sheet-metal laths on wooden studding,  $5\frac{3}{4}$  cts; on steel studding, wired, from 10 to 12 cts.

The cost of putting three coats on laths, plaster-of-Paris finish, labor only, runs about 22 cts per yard.

With sand finish the cost is about 23 cts.

These figures are based on plasterers' wages at 75 cts per hour, and 50 cts per hour for hod-carriers and mortar mixers.

The following schedule \* gives the average cost of different kinds of plastering, based on lime at 40 cts per bushel, sand at 75 cts per load of  $1\frac{1}{4}$  cu yd, hair at 40 cts per bushel, plaster of Paris at 50 cts per 100 lb.

scratch and brown coat (lime) on wooden laths.....	25 cts per sq yd.
three coats (lime) on wooden laths, plaster-of-Paris finish ..	30 cts per sq yd.
three coats (lime) on wooden laths, sand finish.....	30 cts per sq yd.
brown coat and finish on brick walls... ..	23 cts per sq yd.
For hard-wall plaster instead of lime, add.....	3 cts per sq yd.
three coats (lime), plaster-of-Paris finish, metal lath on wooden studding .....	65 cts per sq yd.
three coats (lime) plaster-of-Paris finish, metal lath on steel studding.....	68 cts per sq yd.
For Keene's cement finish, add.....	10 cts per sq yd.
For blocking in imitation of tile, add.....	50 cts per sq yd.
two coats hard-wall plaster, plaster-of-Paris finish, metal lath, wooden studding.....	70 cts per sq yd.
two coats hard-wall plaster, plaster-of-Paris finish, metal lath on steel studs.....	73 cts per sq yd.
For Keene's cement finish, add.....	10 cts per sq yd.
portland cement, brown coat, finished with Keene's cement blocked in imitation of tile, 3 by 6 in.....	\$2.80 per sq yd.
for running base, 9 in high, in Best's Keene's cement.....	10 cts per ft.
for running plain moldings in plaster of Paris, from 3 to 5 cts per inch of girth.	
for finishing shafts of columns, from 16 to 24 in in diam., from 12 to 14 ft high,	
\$3 per column (labor only).	

\* These are pre-war prices and the unit values per sq yd must be largely increased on account of the increase in wages and materials.

These prices, of course, vary somewhat in different sections of the country. In some localities prices for materials or labor are less, in others higher.

Staff is a composition of plaster of Paris and hemp-fiber, cast in molds, and nailed or wired in place. All of the buildings of the Columbian Exposition at Chicago (1893) were covered with this material and all of the temporary buildings of the St. Louis Exposition (1904). It is not sufficiently durable for permanent work unless it is frequently painted. The cost of staff, as used on the buildings at Chicago in 1893, varied from \$2 to \$2.25 per sq yd.

DATA ON LUMBER AND CARPENTERS' WORK

**Relative Hardness of Woods.** Taking shell-bark hickory as the highest standard of our forest-trees, and calling that 100, other trees will compare with it for hardness as follows:

Shell-bark hickory.....	100	Yellow oak.....	60
Pignut hickory.....	96	Hard maple.....	56
White oak.....	84	White elm.....	56
White ash.....	77	Red cedar.....	56
Dogwood.....	75	Wild cherry.....	55
Scrub-oak.....	73	Yellow pine.....	54
White hazel.....	72	Chestnut.....	52
Apple-tree.....	70	Yellow poplar.....	51
Red oak.....	69	Butternut.....	48
White beech.....	65	White birch.....	48
Black walnut.....	65	White pine.....	50
Black birch.....	62		

Weight of Rough Lumber per 1 000 Feet

BOARD-MEASURE, APPROXIMATE

For weight of various woods see tables on pages 1501 to 1508

Kind of wood	Green from saw, lb	Shipping-dry, lb	Well-seasoned, lb	Kiln-dried, lb
Ash.....				
Chestnut.....	4 600	.....	3 500	3 200
Hemlock.....	4 200	3 000	.....	.....
Maple, hard.....	5 400	4 150	3 900	3 400
Maple, soft.....	5 000	3 650	3 300	3 000
Oak, red.....	5 500	4 250	4 000	3 400
Oak, white.....	5 700	4 500	4 100	3 600
Pine, long-leaf.....	4 500	3 500	.....	.....
Pine, white.....	3 500	2 500	2 400	2 200
Poplar.....	4 000	3 000	2 900	2 400
Spruce.....	3 150	2 700	2 300	2 200
Sycamore.....	4 750	3 200	3 000	.....
Walnut, black.....	4 900	4 000	3 800	.....

\* A comprehensive booklet giving the rules for the grading and classification of yellow pine lumber and dressed stock may be obtained from The Southern Pine Association, New Orleans, La.



**Framing-Lumber** may commonly be purchased in any of the following nominal sizes, except that common pine, spruce, and hemlock cannot usually be obtained in larger sizes than 12 by 12 in.

**Nominal Sizes of Framing-Lumber**

in	in	in	in
2 X 4	3 X 6	4 X 12	8 X 12
2 X 6	3 X 8	4 X 14	8 X 14
2 X 8	3 X 10	6 X 6	10 X 10
2 X 10	3 X 12	6 X 8	10 X 12
2 X 12	3 X 14	6 X 10	10 X 14
2 X 14	3 X 16	6 X 12	10 X 16
2 X 16	4 X 4	6 X 14	12 X 12
2½ X 12	4 X 6	6 X 16	12 X 14
2½ X 14	4 X 8	8 X 8	12 X 16
2½ X 16	4 X 10	8 X 10	14 X 14
.....	.....	.....	14 X 16

In some of the New England mills, the following sizes, also, are sawed: 2 by 3, 2 by 5, 2 by 7, 2 by 9, 3 by 4 and 3 by 5 in. These sizes are not commonly carried in stock, and in most localities would have to be obtained by ripping larger sizes. Most of the long-leaf yellow pine and Douglas fir is SHIPPED SURFACED ONE SIDE AND EDGE, the actual dimensions being from ¼ in to ¾ in, and sometimes ½ in, scant of the nominal dimensions. When framing-lumber is required to be full to dimensions it should be ordered IN THE ROUGH, and a special contract made on that understanding.

**Lengths of Framing-Timbers.** All timber is cut and sold in even lengths, as 10, 12, 14 and 16 ft. Odd and fractional lengths are counted as the next higher even length; consequently it is, in certain cases, possible and economical to plan buildings so that timbers of even lengths may be used without waste.

**Measurement of Rough Lumber.** All rough lumber is sold by the foot, BOARD-MEASURE, one foot being the equivalent of a board 1 ft wide, 1 ft long, and 1 in thick. To compute the board-measure in any board, plank, or timber, divide the nominal sectional area, in inches, by 12, and multiply by the length in feet. Thus the number of FEET in a 2 by 4-in scantling, 8 ft long =  $(2 \times 4/12) \times 8 = 5\frac{1}{3}$  ft, board-measure. A 10-in board, 12 ft long, contains  $(1 \times 10/12) \times 12 = 10$  ft, board-measure. Extensive tables are published showing the feet, in board-measure, for almost any commercial size of timber. The following table, however, although compact, will enable one to readily estimate the number of FEET in any of the standard sizes of boards, planks, or timbers. To use the table, find the product of the lateral dimensions of the cross-section; then in the column having a heading equal to this product, and in the horizontal line opposite the given length will be found the number of feet in board-measure. Thus, for a 3 by 4, 2 by 6, or 1 by 12-in timber look in the column headed 12; for a 2 by 12, 4 by 6, or 3 by 8-in piece, look in the column headed 24. For lengths not given in the table, take either twice the length and divide by 2, or one-half the length and multiply by 2. Where timbers of the same size abut end to end, it economizes labor in reducing to board-measure to take the full length; for this reason the lengths in the table are carried beyond those for single sticks.

**Table of Board-Measure**  
For explanation, see page 1559

Length in feet	Sectional area in square inches																
	4		6	8		10		12		14		16		18	20		
	ft	in	ft*	ft	in	ft	in	ft	in	ft	in	ft	in	ft	in	ft	in
6	2	0	3	4	0	5	0	6	7	0	8	0	9	10	0		
8	2	8	4	5	4	6	8	8	9	4	10	8	12	13	4		
10	3	4	5	6	8	8	4	10	11	8	13	4	15	16	8		
12	4	0	6	8	0	10	0	12	14	0	16	0	18	20	0		
14	4	8	7	9	4	11	8	14	16	4	18	8	21	23	4		
16	5	4	8	10	8	13	4	16	18	8	21	4	24	26	8		
18	6	0	9	12	0	15	0	18	21	0	24	0	27	30	0		
20	6	8	10	13	4	16	8	20	23	4	26	8	30	33	4		
22	7	4	11	14	8	18	4	22	25	8	29	4	33	36	8		
24	8	0	12	16	0	20	0	24	28	0	32	0	36	40	0		
26	8	8	13	17	4	21	8	26	30	4	34	8	39	43	4		
28	9	4	14	18	8	23	4	28	32	8	37	4	42	46	8		
30	10	0	15	20	0	25	0	30	35	0	40	0	45	50	0		
32	10	8	16	21	4	26	8	32	37	4	42	8	48	53	4		
34	11	4	17	22	8	28	4	34	39	8	45	4	51	56	8		
36	12	0	18	24	0	30	0	36	42	0	48	0	54	60	0		
38	12	8	19	25	4	31	8	38	44	4	50	8	57	63	4		
40	13	4	20	26	8	33	4	40	46	8	53	4	60	66	8		
42	14	0	21	28	0	35	0	42	49	0	56	0	63	70	0		

Sectional area in square inches												
24	28		30	32		35		36	40		42	48
ft *	ft	in	ft *	ft	in	ft	in	ft *	ft	in	ft *	ft *
6	12	14	0	15	16	0	17	6	18	20	0	24
8	16	18	8	20	21	4	23	4	24	26	8	32
10	20	23	4	25	26	8	29	2	30	33	4	40
12	24	28	0	30	32	0	35	0	36	40	0	48
14	28	32	8	35	37	4	40	10	42	46	8	56
16	32	37	4	40	42	8	46	8	48	53	4	64
18	36	42	0	45	48	0	52	6	54	60	0	72
20	40	46	8	50	53	4	58	4	60	66	8	80
22	44	51	4	55	58	8	64	2	66	73	4	88
24	48	56	0	60	64	0	70	0	72	80	0	96
26	52	60	8	65	69	4	75	10	78	86	8	104
28	56	65	4	70	74	8	81	8	84	93	4	112
30	60	70	0	75	80	0	87	6	90	100	0	120
32	64	74	8	80	85	4	93	4	96	106	8	128
34	68	79	4	85	90	8	99	2	102	113	4	136
36	72	84	0	90	96	0	105	0	108	120	0	144
38	76	88	8	95	101	4	110	10	114	126	8	152
40	80	93	4	100	106	8	116	8	120	133	4	160
42	84	98	0	105	112	0	122	6	126	140	0	168

\* The measurements in these columns come out in even feet.

Table of Board-Measure (Continued)

For explanation, see page 1559

Length in feet	Sectional area in square inches									
	56 ft in	60 ft *	64 ft in	72 ft *	80 ft in	84 ft *	96 ft *	100 ft in	112 ft in	
4	18 8	20	21 4	24	26 8	28	32	33 4	37 4	
6	28 0	30	32 0	36	40 0	42	48	50 0	56 0	
8	37 4	40	42 8	48	53 4	56	64	66 8	74 8	
10	46 8	50	53 4	60	66 8	70	80	83 4	93 4	
12	56 0	60	64 0	72	80 0	84	96	100 0	112 0	
14	65 4	70	74 8	84	93 4	98	112	116 8	130 8	
16	74 8	80	85 4	96	106 8	112	128	133 4	149 4	
18	84 0	90	96 0	108	120 0	126	144	150 0	168 0	
20	93 4	100	106 8	120	133 4	140	160	166 8	186 8	
22	102 8	110	117 4	132	146 8	154	176	183 4	205 4	
24	112 0	120	128 0	144	160 0	168	192	200 0	224 0	
26	121 4	130	138 8	156	173 4	182	208	216 8	242 8	
28	130 8	140	149 4	168	186 8	196	224	233 4	261 4	
30	140 0	150	160 0	180	200 0	210	240	250 0	280 0	
32	149 4	160	170 8	192	213 4	224	256	266 8	298 8	
34	158 8	170	181 4	204	226 8	238	272	283 4	317 4	
36	168 0	180	192 0	216	240 0	252	288	300 0	336 0	
38	177 4	190	202 8	228	253 4	266	304	316 8	354 8	
40	186 8	200	213 4	240	266 8	280	320	333 4	373 4	
42	196 0	210	224 0	252	280 0	294	336	350 0	392 0	
44	205 4	220	234 8	264	293 4	308	352	366 8	410 8	
46	214 8	230	245 4	276	306 8	322	368	383 4	429 4	
48	224 0	240	256 0	288	320 0	336	384	400 0	448 0	
50	233 4	250	266 8	300	333 4	350	400	416 8	466 8	
52	242 8	260	277 4	312	346 8	364	416	433 4	485 4	
54	252 0	270	288 0	324	360 0	378	432	450 0	504 0	
56	261 4	280	298 8	336	373 4	392	448	466 8	522 8	
58	270 8	290	309 4	348	386 8	406	464	483 4	541 4	
60	280 0	300	320 0	360	400 0	420	480	500 0	560 0	
62	289 4	310	330 8	372	413 4	434	496	516 8	578 8	
64	298 8	320	341 4	384	426 8	448	512	533 4	597 4	
66	308 0	330	352 0	396	440 0	462	528	550 0	616 0	
68	317 4	340	362 8	408	453 4	476	544	566 8	634 8	
70	326 8	350	373 4	420	466 8	490	560	583 4	653 4	
72	336 0	360	384 0	432	480 0	504	576	600 0	672 0	
74	345 4	370	394 8	444	493 4	518	592	616 8	690 8	
76	354 8	380	405 4	456	506 8	532	608	633 4	709 4	
78	364 0	390	416 0	468	520 0	546	624	650 0	728 0	
80	373 4	400	426 8	480	533 4	560	640	666 8	746 8	
82	382 8	410	437 4	492	546 8	574	656	683 4	765 4	
84	392 0	420	448 0	504	560 0	588	672	700 0	784 0	

\* The measurements in these columns come out in even feet.

Table of Board-Measure (Continued)

For explanation, see page 1559

Length in feet	Size and sectional area in inches							
	120 10×12 ft *	140 10×14 ft in	144 12×12 ft *	160 10×16 ft in	168 12×14 ft *	192 12×16 ft *	196 14×14 ft in	224 14×16 ft in
4	40	46 8	48	53 4	56	64	65 4	74 8
6	60	70 0	72	80 0	84	96	98 0	112 0
8	80	93 4	96	106 8	112	128	130 8	149 4
10	100	116 8	120	133 4	140	160	163 4	186 8
12	120	140 0	144	160 0	168	192	196 0	224 0
14	140	163 4	168	186 8	196	224	228 8	261 4
16	160	186 8	192	213 4	224	256	261 4	298 8
18	180	210 0	216	240 0	252	288	294 0	336 0
20	200	233 4	240	266 8	280	320	326 8	373 4
22	220	256 8	264	293 4	308	352	359 4	410 8
24	240	280 0	288	320 0	336	384	392 0	448 0
26	260	303 4	312	346 8	364	416	424 8	485 4
28	280	326 8	336	373 4	392	448	457 4	522 8
30	300	350 0	360	400 0	420	480	490 0	560 0
32	320	373 4	384	426 8	448	512	522 8	597 4
34	340	396 8	408	453 4	476	544	555 4	634 8
36	360	420 0	432	480 0	504	576	588 0	672 0
38	380	443 4	456	506 8	532	608	620 8	709 4
40	400	466 8	480	533 4	560	640	653 4	746 8
42	420	490 0	504	560 0	588	672	686 0	784 0
44	440	513 4	528	586 8	616	704	718 8	821 4
46	460	536 8	552	613 4	644	736	751 4	858 8
48	480	560 0	576	640 0	672	768	784 0	896 0
50	500	583 4	600	666 8	700	800	816 8	933 4
52	520	606 8	624	693 4	728	832	849 4	970 8
54	540	630 0	648	720 0	756	864	882 0	1 008 0
56	560	653 4	672	746 8	784	896	914 8	1 045 4
58	580	676 8	696	773 4	812	928	947 4	1 082 8
60	600	700 0	720	800 0	840	960	980 0	1 120 0
62	620	723 4	744	826 8	868	992	1 012 8	1 157 4
64	640	746 8	768	853 4	896	1 024	1 045 4	1 194 8
66	660	770 0	792	880 0	924	1 056	1 078 0	1 232 0
68	680	793 4	816	906 8	952	1 088	1 110 8	1 269 4
70	700	816 8	840	933 4	980	1 120	1 143 4	1 306 8
72	720	840 0	864	960 0	1 008	1 152	1 176 0	1 344 0
74	740	863 4	888	986 8	1 036	1 184	1 208 8	1 381 4
76	760	886 8	912	1 013 4	1 064	1 216	1 241 4	1 418 8
78	780	910 0	936	1 040 0	1 092	1 248	1 274 0	1 456 0
80	800	933 4	960	1 066 8	1 120	1 280	1 306 8	1 493 4
82	820	956 8	984	1 093 4	1 148	1 312	1 339 4	1 530 8
84	840	980 0	1 008	1 120 0	1 176	1 344	1 372 0	1 568 0

\* The measurements in these columns come out in even feet.

**Measurement of Finishing-Lumber, Flooring, Ceiling, Etc.** Most, if not all, lumber for finishing is sawed for use in thicknesses of 1 in,  $1\frac{1}{4}$  in,  $1\frac{1}{2}$  in, and 2 in, and some woods, such as white pine and poplar, are sawed into thicknesses  $2\frac{1}{4}$  in and 3 in.

When surfaced both sides, the thickness is reduced to  $1\frac{3}{16}$ ,  $1\frac{1}{16}$ ,  $1\frac{5}{16}$ ,  $1\frac{3}{4}$ ,  $2\frac{1}{4}$ , and  $2\frac{1}{16}$  in.

All dressed stock is measured and sold **STRIP-COUNT**, that is, full size of rough material necessarily used in its manufacture. Thus  $1\frac{1}{16}$ -in boards are measured though  $1\frac{1}{4}$  in thick. The number of feet, board-measure, for  $1\frac{1}{4}$ -in stock (finished) is  $1\frac{1}{4}$  times that in a 1-in board, and in the same way for  $1\frac{1}{2}$ -in and  $2\frac{1}{2}$ -in stock.  $1\frac{3}{4}$ -in planks are always measured 2 in thick, and  $2\frac{1}{4}$ -in stock,  $2\frac{1}{2}$  in thick. Boards less than 1 in thick are measured the same as 1-in boards, but for  $\frac{3}{8}$ -in and  $\frac{1}{2}$ -in stock a reduced price is generally made.

**Matched Ordinary Flooring.\*** The standard sizes for flooring (other than hardwood, parqueting or parquet-flooring) are 1 by 3, 1 by 4 and 1 by 6; or  $1\frac{1}{4}$  by  $1\frac{1}{4}$  by 4 and  $1\frac{1}{4}$  by 6. The thickness of 1-in flooring should be  $1\frac{3}{16}$  in, and  $1\frac{1}{4}$ -in flooring,  $1\frac{3}{16}$  in. 3-in flooring should show  $2\frac{1}{4}$  in on the face, after it is dressed; 4-in,  $3\frac{1}{4}$  in; and 6-in,  $5\frac{1}{4}$  in.

**Matched Maple Flooring** is usually made in 2-in,  $2\frac{1}{4}$ -in and  $3\frac{1}{4}$ -in face, and thicknesses of  $1\frac{3}{16}$ ,  $1\frac{1}{16}$  and  $1\frac{5}{16}$  in.

**Ceiling, matched and beaded boards,** is regularly stuck in the same widths as flooring. The standard (nominal) thicknesses of yellow-pine ceiling are  $\frac{3}{4}$ ,  $\frac{1}{2}$ , and  $\frac{3}{4}$  in, the actual thickness of each being  $\frac{1}{16}$  in less. The  $\frac{3}{8}$ -in ceiling is dressed one side only, the other thicknesses both sides.

**Yellow Pine Drop-Siding.** Dressed and matched yellow pine drop-siding is by  $3\frac{1}{2}$  and  $\frac{3}{4}$  by  $5\frac{1}{2}$  in, showing  $3\frac{1}{4}$  and  $5\frac{1}{4}$ -in face; and worked shiplap is by  $3\frac{1}{2}$  and  $\frac{3}{4}$  by  $5\frac{1}{2}$  in, showing 3 and 5-in face.

**Beveled Siding** is resawed on a bevel from stock  $1\frac{3}{16}$  by  $3\frac{1}{2}$  and  $1\frac{3}{16}$  by  $5\frac{1}{2}$  in, after surfacing.

**New England Clapboards** are 4 ft long, 6 in wide,  $\frac{1}{2}$  in thick at the butt, and about  $\frac{1}{8}$  in thick at the other edge. They are put up in bunches and sold by the thousand.

**Rules for Estimating Quantities of Sheathing, Flooring, Etc.** For common sheathing laid horizontally on a wall or roof without openings, add one-fifth to the actual superficial area to allow for waste. On the walls of dwellings, treat the walls as though without openings and allow nothing for waste. If sheathing is laid diagonally, add one-sixth to the actual superficial area. For tight sheathing laid horizontally, add one-fifth for 6-in boards, one-seventh for 8-in boards, and one-ninth for 10-in boards. If laid diagonally add one-fourth for 6-in boards, one-sixth for 8-in boards, and one-eighth for 10-in boards. For 3-in matched flooring add one-half to the actual superficial area to be covered.

For 4-in flooring add one-third and for 6-in flooring add one-fifth. Ceiling is measured the same as flooring.

For drop-siding, add one-fifth to the superficial area.

For lap-siding, laid 4 in to the weather, add one-half to the actual superficial area; if  $4\frac{1}{2}$  in to the weather, add one-third.

\* Everywhere except in New England **FLOORING** is always understood to be tongued and grooved.

**Cost of Labor for Carpenters' Work.** There are so many items and conditions which enter into the cost of carpenters' work, and the cost varies widely with the locality, that it is quite impossible to give figures which are of general practical value, although several books \* have been published on estimating labor and materials for buildings.

The following figures of the cost, † for labor and nails, of framing and putting on sheathing and siding and laying flooring were computed on the basis of carpenters' wages at \$3 a day of eight hours (37½ cts per hour). The cost of framing is almost always figured at a certain price per thousand feet of lumber board-measure. The cost of laying flooring, sheathing, etc., is almost always figured by the square of 100 sq ft (10 by 10 ft).

Character of work	Cost
For setting up studding and framing walls of wooden dwellings.....	\$10.00 per 1000
For framing and setting floor-joists, 2 by 8 to 2 by 12...	\$9.00 to \$10.00 per 1000
Framing and setting heavy joists and girders, 6 by 12 to 10 by 14.....	\$ 8.50 per 1000
Framing gable roofs and setting in place.....	10.00 per 1000
Framing hip-roofs and setting in place.....	\$11.00 to \$12.00 per 1000
For putting in bridging, after it is cut, per 100 lin ft in the row.....	\$1.25
For covering the sides or roofs of wooden buildings with dressed sheathing, laid horizontally.....	60 cts per square
The same, if laid diagonally.....	75 cts per square
The cost of labor and nails for laying 6-in flooring, blind-nailed to every joist, without dressing after laying, is about.....	\$2.00 per square
For 4-in flooring, not dressed, allow.....	2.25 per square
For 3-in flooring, not dressed, allow.....	2.50 per square
For 3-in hard-pine flooring, hand-smoothed or traversed.	3.75 per square
For 3-in red-oak flooring, hand-smoothed or traversed..	6.00 per square
For 3-in white-oak flooring, hand-smoothed or traversed	8.00 per square
For 3-in maple flooring, hand-smoothed or traversed....	\$10.00 to \$12.00 per sq

## BUILDING PAPERS, BUILDING FELTS AND QUILTS

**Sheathing-Papers, ‡ Felts, Quilts, Etc.** It is well known that frame buildings when merely sheathed and clapboarded or shingled on the outside and simply lathed and plastered on the inside, are almost sure to be hot in summer and cold in winter; and as the wood almost always shrinks, cracks result through which the wind finds its way. For these reasons some extra provision should be made for keeping out the wind and the heat and cold; and it is generally admitted that

\* Readers are referred to The Building Estimator's Reference Book, by F. R. Wall; The New Building Estimator, by William Arthur; Handbook of Cost Data, by H. Gillette and the Estimators' Price Book, by I. P. Hicks. To all of these, architects and builders are referred for detailed information and valuable data on costs of labor and material.

† The wages of carpenters varied (1916) in the United States from 35 to 70 cts per hour or from \$2.80 to \$5.60 per day of 8 hours. For rates per day higher than those given, the figures showing the costs in the schedule must be raised proportionately.

‡ The terms BUILDING PAPER and SHEATHING-PAPER are by the public indiscriminately applied to all kinds of paper used in connection with building-construction. In the trade, however, the term BUILDING PAPER is confined to the rosin-sized and cheap grades of paper, while the heavier and better grades are classed as SHEATHING-PAPER.

There is no material that will do this so well and at so small an expense as good sheathing-papers or sheathing-felts. The papers made for this purpose are commonly known as SHEATHING-PAPERS or BUILDING PAPERS. There is a great variety of sheathing-papers manufactured, many of them of great excellence, and even the best are comparatively inexpensive, costing only about \$1.00 per 100 sq ft; so that only the better qualities of any kind of felt or paper should be specified. Where the cost of the sheathing-paper on an ordinary house is only a few dollars, it is poor economy to use a cheap paper, as the labor of applying it is an important item and the poorer the paper the more difficult the work of putting it on. The qualities which good sheathing-paper should possess are permanence, impenetrability to air and water and sufficient strength to permit of nailing without tearing. Protection or proof against vermin and insects is another important requirement. It should not be brittle nor have a lasting strong odor and, for the convenience of the builder, should be clean for handling. There are so many papers possessing all or most of these qualities that it is deemed inexpedient to mention particular brands. The architect should decide for himself, from the samples with which he has probably been furnished, what papers are best adapted to the particular conditions; and he should then specify those brands, giving, also, the manufacturers' names, instead of leaving the choice to the builder, who will be quite sure to be guided by price rather than by quality. Many object to tarred or saturated sheathing-papers and felts because of their tendency to become brittle and because they emit a strong odor and are somewhat disagreeable to handle. On the other hand, the advocates of tarred felts emphasize their cheapness, warmth and even their odor, which makes them vermin-proof. The odor gradually disappears after the clapboards, siding or shingles are put on and the inside walls finished. Sheathing-paper is usually applied just previous to putting on the clapboards, siding, or shingles. It is generally placed horizontally and should lap about 2 in over each sheet and over the paper previously placed around the window and door-frames. If sheathing-quilt or similar material is to be placed under the clapboards or siding, laths should be nailed vertically over it, opposite each stud, and the siding or clapboards nailed to the laths; otherwise it will be difficult to put them on evenly, owing to the thickness and elastic quality of the QUILT. Shingles, however, may be applied directly over it. Sheathing-quilt possesses marked fire-resisting properties. The sheathing-paper and the labor of putting it on should be included in the carpenter's specifications.

**Rosin-Sized Building-Papers.** These are the common grades of building paper; they are not water-proof, and should not be used on roofs or on walls in damp climates. In dry places they protect from dust, draughts, and to some extent from heat and cold. They are generally either a dull red or gray in color, have a hard, smooth surface, and are clean to handle. They are always put up in rolls 36 in wide and usually contain 500 sq ft. The weight varies from 18 to 24 lb to the roll of 500 sq ft.

**Insulating and Deadening-Quilts.** Among the insulating and deadening-quilts much in use are those mentioned below. There are also other good materials in this line which are manufactured and used for insulating and deadening purposes.

**Sheathing-Quilt.\*** This consists of a felted matting of eel-grass held in place between two layers of strong Manila paper by quilting. "The long, flat fibers of eel-grass cross each other at every angle and form within each layer of quilt innumerable minute dead-air spaces, that make a soft, elastic cushion. This

\* Made by Samuel Cabot (Inc.), Boston, Mass.

gives the most perfect conditions for non-conduction." Eel-grass is chosen for the filling because of its long, flat fibers, which especially adapt it to felting; because of its great durability,\* and its resistance to fire; and because owing to the large percentage of iodine which it contains, it is repellent to rats and vermin. This quilt is made in single and double-ply thickness, and is packed up in bales of 500 sq ft. It is also now made with a covering of asbestos, which renders it thoroughly fire-proof. The material is also very efficient for heat insulation. When used for this purpose there is no objection to nails passing through it.

**Keystone Hair Insulator.** Another material used for similar purposes is the Keystone Hair Insulator.† This consists of thoroughly cleansed cattle's hair between two layers of strong, non-porous building paper, securely stitched together. The hair is chemically treated, so that it is coated with lime, which makes the finished material vermin-proof and odorless.

**Mineral-Wool Deadeners,** which are fire-proof sound-deadening quilts of rock-fiber wool stitched between two sheets of building paper or of asbestos paper according to the grade desired, are made by the Union Fibre Company, Winona, Minn., and other firms. This company makes, also, what is called Lith and Feltlino, which are sound-deadening materials in board form. They are manufactured, also, Linofelt, a building-quilt of flax-fibers (unbleached linen threads), stitched between water-proof paper or asbestos paper according to grade. It is  $\frac{1}{4}$  in thick. Linofelt for sheathing in place of ordinary building paper adds from 1 to  $1\frac{1}{2}\%$  to the cost of a house.

**Felt-Papers.** There are a great many felt-papers for lining floors and walls, and they are made fire-proof by means of chemicals. As a rule these felts are cheaper than Cabot's QUILT, although the saving in an ordinary residence would be but little, and even among the felts themselves there is quite a difference in cost. In choosing a felt-paper for lining, the architect should select one that is soft and elastic enough to form a cushion, and the thicker the felt, provided it has the above qualities, the greater will be its non-conduction. Some felts are made water-proof by an asphalt center, which is an advantage in case of fire or leak, but some authorities think that it is doubtful if such felts obstruct the passage of sound as well as felts without the asphalt center. The experience of some acoustical experts seems to show that one of the best methods of deadening is a combination of heavy hair-felt or felt-paper with sheets of galvanized iron. Two layers of felt, each from  $\frac{1}{2}$  to 1 in thick, are placed on either side of a single layer of galvanized iron, the latter resting freely between the felt layers. This form of construction is to be preferred where the deadening-material is not attached to the enclosing woodwork. An additional layer of iron and of felt increases the effectiveness of the combination.

**Saturated Felts.**‡ Common roofing-felts are made by saturating common dry felt with coal-tar pitch. Roofing-felts are commonly made in weights of 10, 15, and 20 lb to the 100 sq ft. Nothing lighter than 12 lb should be used for roofing. They are usually sold by weight. Asphalt-felts are commonly made in the same weights.

**Dry Saturated Tarred Felts** are specially run through a tier of calender to give a hard, uniform surface and contain a minimum amount of coal-tar.

\* A sample of eel-grass 250 years old and in a perfect state of preservation, may be seen at Mr. Cabot's office.

† Made by Johns-Manville, Inc., New York.

‡ The Barrett Company and other manufacturers make numerous brands of the sheathing and roofing-papers.



They are especially adapted for slaters' use, as they will carry a chalk line and are easy to handle. The rolls are 36 in wide, contain 500 sq ft and weigh about 16 lb.

**Asbestos Building Felts** are usually made about 6, 10, 14 and 16 lb to the 100 sq ft, although different manufacturers make different weights. They come in rolls 36 in wide and are sold by weight.

**Sound-Deadening Felts.** These deadening-felts are made by various manufacturers. In one of these felts \* the material itself is rather hard and thin, but is pressed in such a way as to form small indentations or air-cells. This makes them elastic and breaks up the sound-waves.

**Asbestos Sheathing.** Sheathing-papers or building felts, made of asbestos, are used to a considerable extent for floor-linings and for covering the outside walls of wooden buildings, principally on account of their fire-proof and vermin-proof qualities. These papers are well known in the trade and can be procured without difficulty. They are supplied by the manufacturers in 50 or 100-lb rolls, 36 in wide, on a basis of the following scale of weights:

4 lb to the 100 sq ft	18 lb to the 100 sq ft
6 lb to the 100 sq ft	20 lb to the 100 sq ft
8 lb to the 100 sq ft	24 lb to the 100 sq ft
10 lb to the 100 sq ft	32 lb to the 100 sq ft
12 lb to the 100 sq ft	$\frac{1}{16}$ in thick
14 lb to the 100 sq ft	$\frac{3}{32}$ in thick
16 lb to the 100 sq ft	$\frac{1}{8}$ in thick

The sheathing in the  $\frac{1}{16}$ ,  $\frac{3}{32}$  and  $\frac{1}{8}$ -in thicknesses is used only for special purposes where an unusually thick lining is desired for possible fire-protection and exposed flues, for chimney-breasts, etc. When the weight of paper equals 32 lb to the square foot it is known as **ROLL-BOARD** and is no longer classed by weight per 100 sq ft, but by thickness. For floor-linings, 16-lb paper is generally employed, this weight being sufficiently thick and strong to resist ordinary damage in application and in handling. Asbestos felts and building papers appear to have approximately the same effect in retarding the passage of sound-waves as other felt-papers of a relatively similar thickness and quality, while their fire-proof and vermin-proof qualities are a distinct advantage. The cost of asbestos paper and building-felt, while somewhat greater than that of the ordinary papers used for similar purposes, is not excessive. The market price varies and depends upon the fluctuations of the market. For example, the cost of 100 sq ft of 16-lb asbestos paper varied from 32 to 40 cts, according to the market, before the war.†

**Water-Proof Papers.** Neponset Black Sheathing is water-proof and fire-proof, odorless and clean to handle, and is an excellent paper under shingles, slate, or tin. The rolls are 36 in wide, containing 250 and 500 sq ft.

**Neponset Red Rope Sheathing and Roofing.** This is made of rope-hemp, has great strength and flexibility, and is absolutely water-proof and air-proof. It is one of the best sheathing-papers and makes a good cheap roofing for sheds, poultry-houses, etc. The rolls are 36 in wide, containing 100, 250 and 500 sq ft.

**Neponset Florian Sound-Deadening Felt**, supplied by Bird & Son, East Walpole,

These prices are now much higher.

**Parchment Water-Proof Sheathing.** There are various parchment-sheatings on the market which are semitransparent, have smooth surfaces, and are odorless, water-proof, air-proof and vermin-proof. They are adapted for general sheathing purposes. In general 1-ply weighs 25 lb to 900 sq ft; 2-ply, 25 lb to 500 sq ft; 3-ply, 25 lb to 275 sq ft. They are 36 in wide.

**Cost of Building and Sheathing-Papers in Place.\*** The following, though necessarily restricted to a few lines, will give a general idea of the cost of different kinds and grades of sheathing-papers, the prices given being fair averages for the materials APPLIED to an outside wall or roof:

	Price per 100 square feet
Common tarred felts (15 lb per square) . . . . .	30 cts
Red rosin-sized sheathing, best grades . . . . .	25 cts
Monahan's parchment-sheathing, single-ply . . . . .	26 cts
Monahan's parchment-sheathing, double-ply . . . . .	40 cts
Monahan's ship-rigging tar-sheathing, 2-ply . . . . .	75 cts
"Neponset" black (water-proof) paper . . . . .	45 cts
"Neponset" red-rope roofing . . . . .	\$1.20
Sheathing-papers with asphalt center . . . . .	40 to 50 cts
Asbestos building or sheathing-felt, 10 lb per square . . . . .	22½ cts
Asbestos building or sheathing-felt, 14 lb per square . . . . .	31½ cts
Cabot's sheathing-quilt, single-ply . . . . .	\$1.05
Cabot's sheathing-quilt, double-ply . . . . .	\$1.25
Barrett's specification-felt . . . . .	35 cts
Barrett's DEFENDER, felt-sheathing . . . . .	80 cts
Sackett's water-proof sheathing . . . . .	30 cts
Empire parchment-sheathing, 1-ply . . . . .	25 cts
Empire parchment-sheathing, 2-ply . . . . .	36 cts
Empire parchment-sheathing, 3-ply . . . . .	50 cts
Barrett's red rope . . . . .	\$1.00
Barrett's black, water-proof sheathing . . . . .	40 cts

## PAINT AND VARNISH †

**Pigments and Vehicles.** The solid ingredient of a paint is called the **PIGMENT** and is a fine powder, nearly all of which will pass through a brass-wire sieve of 100 meshes to the linear inch; in fact, most pigments are much finer than this and those formed as precipitates by chemical processes are so fine that there is no way to measure them. The liquid part is called the **VEHICLE**. This is usually linseed-oil, sometimes with the addition of a little turpentine or other volatile solvent. In the enamel paints it is varnish and in kalsomine and other oil-soluble water paints it is a solution of glue, casein, albumen, or some similar cementing material. The cementing material is sometimes called the **BINDER**.

**Ingredients of Oil-Paint.** White lead and white zinc are the common white pigments. There are white pigments of variable composition called leaded white and zinc lead, furnace-products, composed of zinc oxide and lead sulphate. There is also a basic lead sulphate, commercially called sublimed white lead, which is a similar furnace-product consisting chiefly of sulphate of lead. These composite white pigments are largely used in mixed paints. **LITHOPONE** is a mixture of sulphide of zinc and sulphate of barium. It is very white, and

\* All prices quoted are pre-war prices and the data are retained for purposes of comparison and relative values.

† The editor is indebted to Professor Alvah H. Sabin for valuable assistance in the collection of the data relating to this subject.

and opaque and largely used as the basis of flat wall-finishes for interior work, but it is not durable for exterior work. It is discolored (grey) by strong light, but this is not a very serious practical objection. White lead is used everywhere, but it tends to yellow somewhat in the dark. White zinc is chiefly used on interior work, being the whitest paint known. Both are often mixed and both are used in mixed paints. Yellow paint is commonly chromate of lead, or chrome yellow; green is chrome green, which is a mixture of chrome yellow and Prussian blue; blue is ultramarine, or sometimes Prussian blue. The brilliant reds are coal-tar colors as a rule; the dull reds and browns are oxides of iron. Ochres are dull yellow. Carbon forms the base of all black paints, either as lampblack, drop-black (boneblack), or graphite. Linseed-oil is either raw or boiled. Raw oil is the oil in its natural state as it is extracted from the seed; it should be settled and filtered perfectly clear; it is yellow or greenish yellow in color. Boiled oil is raw oil which has been heated to 400° or 500° F. with compounds (usually oxides) of lead and manganese; it is darker in color than raw oil, and dries quicker. Raw oil exposed in a thin film to the air is converted in about five days into a tough leathery substance; boiled oil undergoes this change in from 10 to 24 hours.

**Driers.** These are compounds of lead and manganese, dissolved in oil, and the solution thinned with turpentine or benzine. They act as carriers of oxygen between the air and the oil, and their addition to a paint makes it dry more rapidly. Some driers are also called JAPANS. Not more than 10% by volume of any of these liquid driers should be added to oil. Excess of drier causes the paint to lack durability. Cheap driers often contain rosin. It is well to specify that driers and japans should be free from ROSIN (not resin, as varnish-resins are present in some of the best driers).

**Priming Coat.** This is the first coat applied to the clean surface. A priming coat for wood is chiefly oil, and is usually equivalent to a gallon of ordinary paint thinned with a gallon of raw linseed-oil. Paint, however, is not thinned to make a priming coat for structural metal. In all wood-work, nail-holes and other defects are filled with putty after the priming coat has been applied; but if the wood is resinous, knots and resinous places must be covered with shellac varnish before the priming coat is put on. Pitchy woods, such as southern yellow pine and cypress, do not readily absorb oil, and turpentine should be substituted for part of the oil. Red lead is successfully used as a primer (2 parts to 1 of white lead) on such woods; this is the standard practice in England, and is better than the use of all white lead.

**Outside Painting.** The priming coat having largely been absorbed by the wood, a second and third coat of paint are to be applied. The most common paint used on houses is white lead. This is commonly sold as paste white lead, containing 8% of oil; 100 lb of this is equal to 2.8 gal in volume, and is commonly mixed with 3½ gal of raw linseed-oil, 1 qt of turpentine and 1 pt of drier to make 1 gal of paint for the second coat; or with 4 gal of oil, 1 pt of turpentine and 1 qt of drier for the finishing coat. If white zinc is used, 9½ lb of dry zinc oxide and 5.7 lb of oil make 1 gal of paint; to this, turpentine and drier should also be added. White lead, after about a year, begins to CHALK, that is, its surface becomes dry and chalky; this does not indicate failure, however, and it makes a good surface for repainting. Finely reticulated checking, not extending through the film, occurs later, and when sufficiently marked indicates need of repainting. In any paint, when cracks begin to extend through to the wood, repainting is needed for; these cracks occur sooner on pitchy woods. White zinc, if used alone on outside (not inside) work, is very hard and tends to peel off. MIXED PAINTS (prepared proprietary paints) generally contain zinc mixed with either white lead or some of the pigments based on basic lead sulphate, and some auxiliary

Table of Board-Measure  
For explanation, see page 1559

Length in feet	Sectional area in square inches									
	4		6		8		10		12	
	ft	in	ft	in	ft	in	ft	in	ft	in
6	2	0	3		4	0	5	0	6	
8	2	8	4		5	4	6	8	8	
10	3	4	5		6	8	8	4	10	
12	4	0	6		8	0	10	0	12	
14	4	8	7		9	4	11	8	14	
16	5	4	8		10	8	13	4	16	
18	6	0	9		12	0	15	0	18	
20	6	8	10		13	4	16	8	20	
22	7	4	11		14	8	18	4	22	
24	8	0	12		16	0	20	0	24	
26	8	8	13		17	4	21	8	26	
28	9	4	14		18	8	23	4	28	
30	10	0	15		20	0	25	0	30	
32	10	8	16		21	4	26	8	32	
34	11	4	17		22	8	28	4	34	
36	12	0	18		24	0	30	0	36	
38	12	8	19		25	4	31	8	38	
40	13	4	20		26	8	33	4	40	
42	14	0	21		28	0	35	0	42	

	Sectional area in square inches									
	24		28		30		32		35	
	ft	in	ft	in	ft	in	ft	in	ft	in
6	12		14	0	15		16	0	17	6
8	16		18	8	20		21	4	23	4
10	20		23	4	25		26	8	29	2
12	24		28	0	30		32	0	35	0
14	28		32	8	35		37	4	40	10
16	32		37	4	40		42	8	46	8
18	36		42	0	45		48	0	52	6
20	40		46	8	50		53	4	58	4
22	44		51	4	55		58	8	64	2
24	48		56	0	60		64	0	70	0
26	52		60	8	65		69	4	75	10
28	56		65	4	70		74	8	81	8
30	60		70	0	75		80	0	87	6
32	64		74	8	80		85	4	93	4
34	68		79	4	85		90	8	99	2
36	72		84	0	90		96	0	105	0
38	76		88	8	95		101	4	110	10
40	80		93	4	100		106	8	116	8
42	84		98	0	105		112	0	122	6

\* The measurements in these columns come out in even feet.

Table of Board-Measure (Continued)

For explanation, see page 1559

Length in feet	Sectional area in square inches									
	56 ft in	60 ft *	64 ft in	72 ft *	80 ft in	84 ft *	96 ft *	100 ft in	112 ft in	
4	18 8	20	21 4	24	26 8	28	32	33 4	37 4	
6	28 0	30	32 0	36	40 0	42	48	50 0	56 0	
8	37 4	40	42 8	48	53 4	56	64	66 8	74 8	
10	46 8	50	53 4	60	66 8	70	80	83 4	93 4	
12	56 0	60	64 0	72	80 0	84	96	100 0	112 0	
14	65 4	70	74 8	84	93 4	98	112	116 8	130 8	
16	74 8	80	85 4	96	106 8	112	128	133 4	149 4	
18	84 0	90	96 0	108	120 0	126	144	150 0	168 0	
20	93 4	100	106 8	120	133 4	140	160	166 8	186 8	
22	102 8	110	117 4	132	146 8	154	176	183 4	205 4	
24	112 0	120	128 0	144	160 0	168	192	200 0	224 0	
26	121 4	130	138 8	156	173 4	182	208	216 8	242 8	
28	130 8	140	149 4	168	186 8	196	224	233 4	261 4	
30	140 0	150	160 0	180	200 0	210	240	250 0	280 0	
32	149 4	160	170 8	192	213 4	224	256	266 8	298 8	
34	158 8	170	181 4	204	226 8	238	272	283 4	317 4	
36	168 0	180	192 0	216	240 0	252	288	300 0	336 0	
38	177 4	190	202 8	228	253 4	266	304	316 8	354 8	
40	186 8	200	213 4	240	266 8	280	320	333 4	373 4	
42	196 0	210	224 0	252	280 0	294	336	350 0	392 0	
44	205 4	220	234 8	264	293 4	308	352	366 8	410 8	
46	214 8	230	245 4	276	306 8	322	368	383 4	429 4	
48	224 0	240	256 0	288	320 0	336	384	400 0	448 0	
50	233 4	250	266 8	300	333 4	350	400	416 8	466 8	
52	242 8	260	277 4	312	346 8	364	416	433 4	485 4	
54	252 0	270	288 0	324	360 0	378	432	450 0	504 0	
56	261 4	280	298 8	336	373 4	392	448	466 8	522 8	
58	270 8	290	309 4	348	386 8	406	464	483 4	541 4	
60	280 0	300	320 0	360	400 0	420	480	500 0	560 0	
62	289 4	310	330 8	372	413 4	434	496	516 8	578 8	
64	298 8	320	341 4	384	426 8	448	512	533 4	597 4	
66	308 0	330	352 0	396	440 0	462	528	550 0	616 0	
68	317 4	340	362 8	408	453 4	476	544	566 8	634 8	
70	326 8	350	373 4	420	466 8	490	560	583 4	653 4	
72	336 0	360	384 0	432	480 0	504	576	600 0	672 0	
74	345 4	370	394 8	444	493 4	518	592	616 8	690 8	
76	354 8	380	405 4	456	506 8	532	608	633 4	709 4	
78	364 0	390	416 0	468	520 0	546	624	650 0	728 0	
80	373 4	400	426 8	480	533 4	560	640	666 8	746 8	
82	382 8	410	437 4	492	546 8	574	656	683 4	765 4	
84	392 0	420	448 0	504	560 0	588	672	700 0	784 0	

\* The measurements in these columns come out in even feet.

a fire. It is especially suitable for cleaning out moldings and all irregular surfaces from which the varnish may then be removed with stiff brushes, if it is not convenient to use scrapers. It is especially desirable to have floors occasionally cleaned in this way; but if a house has been varnished originally with a first class varnish it may be necessary only to wash it thoroughly and then apply another coat of varnish. Smoke and dirt may often be thoroughly removed from ceilings with the crumbs of fresh bread, where washing would not be desirable. A 10% solution of carbonate of soda (sal soda) in hot water may be used to remove old floor-wax.

**The Painting of Structural Steel.** Steel being usually more perishable than wood, as well as more expensive, and used for service where its strength is essential to the stability of the structure, its protection from corrosion by painting is of much importance. It must first of all be recognized that the precaution always taken in painting wood, to secure a clean surface for the paint, must not be omitted with steel. Mud and dirt must first be removed from the steel; then it must be examined for rust, and any rust-spots must be thoroughly cleaned. Loose scale may be removed with wire brushes, but thick and closely adherent rust must be removed with steel scrapers, or with hammer and chisel if necessary. No doubt the best way to clean steel is to use the sand-blast, but it is not available for much architectural work. In any case much care must be taken to obtain a clean surface. On wood the priming coat sinks into the wood and forms a perfect bond between it and the succeeding coats; but on metal no such thing is possible and it is a case of simple adhesion, which demands a clean surface for efficient results. The paint for structural metal should be tough and elastic, and to as great a degree as possible it should be water-proof. Less than two coats should never be applied, and three are better. Paint is always thin on edges and angles, and also on bolt and rivet-heads; it is therefore good practice, after the first full coat, to apply a partial or striping coat, covering the angles and edges and the surface for at least 1 in back from the edges, and covering all bolt-heads and rivet-heads. After this striping coat has become dry, the second full coat is applied, and it may then be assumed that the whole surface has received two full coats. At least a week should elapse between coats. In designing the steelwork, all cavities which may be filled with rain during erection should be properly drained; and during erection all small cavities should be filled with cement, and all contact-surfaces thickly painted.

**Kinds of Paint for Structural Steel.** RED LEAD is more generally used than anything else as a paint for structural steel. It is a "true red lead" ( $\text{Pb}_2\text{O}_3$ ), usually made from litharge ( $\text{PbO}$ ), and frequently containing from 10 to 20% of the latter. If it contains much litharge, it rapidly thickens when mixed with oil and finally hardens; this makes it a paint difficult to apply. If, however, the material from which it is made is reduced to a sufficiently fine powder before it is oxidized an almost completely oxidized red lead is produced, which is as easily worked as white lead, and better in every respect. The requirements of the government of the United States have for years called for red lead of not less than 94% of "true red lead" ( $\text{Pb}_2\text{O}_3$ ), and the Navy Department, as well as several large railway companies, is now using large amounts of red lead which has not less than 98% of "true red lead." It may now be obtained in paste-form, similar to white lead and containing about  $6\frac{1}{2}\%$  of raw linseed-oil. 33 lb of red lead (dry pigment) to 1 gal of oil is the maximum and this is especially suitable for hydraulic work; 28 lb to 1 gal of oil (containing 20 lb of pigment in a gallon of paint) is more common; while 25 lb to a gallon of oil is a common requirement for road-specifications. Finely ground GRAPHITE in linseed-oil is a favorite paint for metal; it flows well, is easily applied, less expensive than red lead, and if well

made gives excellent results. Graphite is sometimes mixed with lampblack, probably with advantage. Boneblack is also an important ingredient of CARBON PAINTS. Formerly oxide of iron in linseed-oil was used more than all other paints for this purpose; but while many engineers still like it, its use has very greatly diminished. ASPHALTUM has been used and is still used, as a varnish either alone or in combination, and some of these asphaltic preparations are fairly satisfactory. The fact is, that a really competent paint-manufacturer can make a reasonably good paint out of any of these, and if the paint is carefully applied the results will be satisfactory. There are great differences in painters. In regard to the surface of structural steel covered by a gallon of paint, there is a great difference of opinion among experts. Some say from 300 to 400 sq ft, others 1000 or 1200 sq ft. The truth is that any paint may be brushed out into an exceedingly thin film by a skilled workman, while ordinary usage results in a film at least twice as thick. The general opinion is that it is not wise to estimate more than 400 sq ft to the gallon for one coat. Varnish-paints cover less than oil-paints, but if well made they are very durable.

**Painting on Cement and Concrete.** Cement and concrete-work are difficult to paint, because they are strongly alkaline and even caustic when new. Work in these materials should be allowed to stand a year or two if possible before it is painted; then it may be painted with any ordinary paint. A practice which has been highly recommended is to wash the surface, repeatedly if possible, with a strong solution of zinc sulphate, the sulphuric acid uniting with the free lime and the zinc being left in the pores as an oxide or hydrate. Some preparations for this purpose are on the market; and while some are probably good, others are to be distrusted. The best way is to allow the surface to age, if this is at all possible.

## WINDOW-GLASS AND GLAZING \*

**Glazing.** The glazing of windows originally belonged to the painter's trade, and when glass is broken, it is still customary to go to a painter to have it replaced; but custom has so changed in some parts of the country, that when new windows are to be glazed, the work is sometimes done at the mill or factory where the sashes are made, sometimes by the local glass-jobber in the town where the building is being erected, and again, in other localities, the glazing of new buildings is still done by the painter. COMMON WINDOW-GLASS is usually set with putty and secured with triangular pieces of zinc called GLAZIERS' POINTS, driven into the wood over the glass and covered with putty. In the best work, a thin layer of putty is first put in the rebate of the sash and the glass is then placed in it and pushed down to a solid bearing. This is called BACK-PUTTYING. The points are then driven about 8 or 10 in apart and the putty applied over the glass and points so as to fill the rebate. Outside windows should always be glazed on the outside of the sash. Common window-glass has a slight bend in it, the result of its original cylindrical shape; it should be glazed, therefore, with the convex side out, as this reduces to a minimum the effects of the waviness when looking through it either from the outside or inside. Plate glass, in window-sashes and door-lights, should be back-puttied and secured by wooden beads.

**Leaded Glass.** It was formerly a common practice for architects to name in the specifications a certain sum of money to be allowed by the carpenter for the leaded glass and to be expended under the direction of the architect. Where

\* Condensed from article on Window-Glass and Glazing by Professor Thomas Nolan in *Building Construction and Superintendence, Part II, Carpenters' Work*, by F. E. Alder.

clear glass was used, the pattern was sometimes shown on the drawings and the glass was specified in the same manner as any other work. When colored glass was to be used, it was customary to make a definite allowance and then to entrust the work to a good art-glass manufacturer. But leaded glass should be designed, furnished and put in place by those who are entirely familiar with its manufacture and its limitations; the purchase of the same should be left entirely in the hands of the owner; and no specification as to its price or make should be used by the architect. The colored-glass windows should show as much individual artistic taste as any other picture or decoration used in the building. The cheap and inartistic leaded glass is fast becoming a thing of the past and owners are confining themselves to purely works of art placed in some appropriate location in the building.

**Sheet Glass. General Description.** Common window-glass is technically known as SHEET GLASS or CYLINDER GLASS. "It is made by the workmen dipping a tube with an enlarged end in the molten glass or METAL until from 7 to 10 lb are gathered up. Then it is blown out slightly by the workman, taken on a blowing-tube and still further blown and manipulated, until a cylinder about 15 in in diameter and 60 in long is formed. This cylinder has the two ends trimmed off and is then cut longitudinally and gradually warmed. It is then placed on a large flat stone supported by a carriage, where it is heated until it softens sufficiently to open out flat; the carriage is then pushed into the annealing-chamber and the sheet taken off." About the year 1910, sheet glass blown by machinery, utilizing compressed air, was perfected, and the result has been a gradual decrease in its cost. The cylinder blown by compressed air is split open and flattened out in just the same manner and by the same process as in the mouth-blown cylinder.

**Grades and Qualities of Sheet Glass.** Sheet glass is graded as DOUBLE-THICK, or SINGLE-THICK, and each thickness is further divided into three qualities, FIRST, SECOND, or THIRD, according to its relative freedom from defects. The price varies according to the strength and quality. It should be remembered that sheet glass is always wavy, the result of the flattening of the cylinder. Many suppose that by designating sheet glass, CRYSTAL-SHEET GLASS, SELECTED-SHEET GLASS, or SHEET GLASS FREE FROM WAVES AND IMPERFECTIONS, a sheet glass free from waves and blemishes can be obtained. The terms and names do not change the nature of this glass, which still remains sheet glass, characterized by the defects inherent in the method by which it is manufactured. To obtain a thin glass, free from waviness, plate glass,  $\frac{1}{8}$  in thick, sometimes known as CRYSTAL PLATE, or plate glass  $\frac{3}{16}$  in thick, must be specified. Since the improvement in the manufacture of window-glass in this country, scarcely any sheet glass is now imported for glazing purposes. A small amount of Belgian sheet glass is brought to this country and used along the Atlantic seaboard for picture-framing. The low prices of the American sheet glass, and its excellent quality, have practically forced imported sheet glass out of the market. All common sheet glass, without regard to quality, is graded according to thickness, as SINGLE-THICK or DOUBLE-THICK. The thickness of the double-thick glass is a scant  $\frac{1}{4}$  in while that of the single-thick averages about  $\frac{1}{8}$  in. It is customary to use the double thickness for sheet glass over 24 in in width. The best quality of sheet glass is specified as AA, the second as A and the third as B.

**Sizes of Sheet Glass.** The regular stock-sizes vary by inches from 6 to 16 in in width. Above that they vary by even inches up to 60 in in width and 70 in in length for double thickness, and up to 30 by 50 in for single thickness.

**Cost of Sheet Glass.** The prices for sheet glass, as for all other clear glass, vary with size, strength and quality. Prices are determined by a schedule



or price-list,\* giving the price for each size, in both thicknesses, and all qualities; and from these prices a very large discount is allowed. Fluctuations in prices are regulated by the discount, the list usually remaining unchanged for a number of years. The price-list prevailing in 1913 was in use from October 1, 1903. The only way to ascertain the price of a light of glass of a given size is to find it from the price-list, from which the discount, quoted by the glass-dealer, must be deducted. For the benefit of the Pacific Coast trade there is a Western Glass List † which differs somewhat from the Eastern list. The list is for sheet glass, the plate glass lists being the same in the East and West. The price per square foot increases rapidly as the size of the pane increases, so that it is much cheaper to divide a large window into eight or twelve lights than into two lights. Compared with the cost of the building, however, the glass is a small item and in the better classes of buildings each sash is usually glazed with a single light of glass. In factories, workshops, etc., where there is usually a large amount of glass-surface, the size of the lights is not of so much importance, while the saving by using small lights is quite an item; hence twelve-light and even sixteen-light windows are generally used in such buildings. The following table shows quite clearly the relative cost (1913) per square foot of different-sized panes of American glass, the prices given being an average at that time for the whole country.

**Comparative Cost (1913) of American Sheet Glass per Square Foot, Based  
Upon a Discount of 90 and 20 Per Cent on the List of  
October 1, 1903 ‡**

Grades	Sizes of lights in inches						
	10×12	15×20	24×34	30×36	36×40	40×60	60×70
	Prices in cents per square foot						
<b>Double strength:</b>							
First quality.....	7.0	8.3	9.4	10.0	10.8	14.0	29.2
Second quality....	6.0	7.3	8.3	9.0	10.0	14.4	27.0
<b>Single strength:</b>							
First quality.....	5.0	4.8	6.4	6.8	.....	.....	.....
Second quality....	4.3	4.5	5.6	6.0	.....	.....	.....

**Crystal-Sheet Glass, 26-Ounce.** This glass is made by the cylinder-process, it is a little thicker than the ordinary double-strength glass. It is probably the best glass made, next to plate glass, but owing to the method of its manufacture is necessarily characterized by a wavy appearance. If good glass is required for first-class residences, hotels, office-buildings, etc., polished plate glass should be used. The latter invariably gives satisfaction, while sheet glass, no matter of what thickness, is usually disappointing in its appearance.

**Defects of Sheet Glass.** All sheet glass, when looked upon from the outside, has a wavy, watery appearance, like the surface of a lake slightly agitated by

\* The price-lists of glass have been omitted as they can readily be obtained from the glass-dealers in any city. Such lists are not of much service unless they are complete; and the full lists are too long to be inserted in a condensed handbook.

† This list, with discounts from the prices given, may be obtained from the W. P. Fuller Company, San Francisco, Cal.

‡ Much valuable information in regard to Window-Glass and Glazing was furnished by E. S. C. Gilmore of the Hires-Turner Glass Company. Philadelphia, Pa.

the wind; and when the sunshine falls upon it the irregularity of the surface is greatly emphasized. This characteristic of sheet glass is due to its being made in the shape of a cylinder and then stretched or flattened out into a sheet, and it cannot be wholly avoided. Besides this universal defect, the cheaper grades are often STRINGY, BLISTERY, SULPHURED, SMOKED, or STAINED; so that, in looking through the glass, objects seen at a distance are deformed and distorted.

**Plate Glass. General Description.** Plate glass is commonly known as POLISHED PLATE GLASS because its surface is finely polished and thus made clear and transparent. It is more largely used every year for windows of fine residences, hotels and office-buildings, where transparency is desired from the inside and an elegant appearance required on the outside. The process of manufacture of plate glass is entirely different from that of sheet glass. In making plate glass the metal, which is prepared with great care, is melted in large pots and then cast on a perfectly flat cast-iron table. "The width and thickness of the plate is determined by means of metal strips called GUNS, which are fastened on, and on which a heavy, metal roller travels. The ends of the guns are tapered so that when the roller is at one extremity, it and the guns form three sides of a shallow, rectangular dish. The molten metal is poured on and the roller passed along slowly, forcing the metal in front of it and rolling out the sheet." The sheet is then annealed and forms what is known as ROUGH PLATE, which is used for vault-lights, skylights, floor-lights and the like. "For polished plate the rough plate is carefully examined for flaws, which are cut out, leaving the largest-sized sheet practicable. The plate is then fastened to a revolving table by means of plaster of Paris, and two heavy shoes, shod with cast iron, are mounted over it. The table is then revolved and sand and water fed onto the surface; the shoes revolve also, going over all parts of the plate and grinding it down to a true plate. Emery-powder is then fed on, in successive degrees of fineness until the plate is made absolutely smooth and all grit removed. After this, new rubbers, shod with very fine felt, are put on and liquid rouge is added for the polishing. When one side is completed the other side is similarly treated, the plate losing about 40% in weight by the operation."

**Qualities of Polished Plate Glass.** For glazing purposes there is but one quality of plate glass on the market. The best of this is selected for manufacturing mirrors. At one time, plate glass was extensively imported, but the gradually improving methods of the American manufacturers, as well as the great cheapening of the process, have practically eliminated imported plate glass from the market. The American plate glass is equal in every respect to that which was imported. The usual thickness of polished plate glass is from  $\frac{1}{4}$  to  $\frac{3}{16}$  in, but it can be made thinner than this; and when required for residence-windows or car-windows, may be obtained in  $\frac{3}{16}$  or  $\frac{1}{8}$ -in thicknesses. It is manufactured from the same thickness of rough plate used for the ordinary thicknesses, but is ground down thinner and, owing to the additional cost of grinding, as well as to the risk, is more expensive than glass of the ordinary thickness.

**Cost\* of Polished Plate Glass.** The cost of plate glass of ordinary thickness varies with the size of the lights. The net price of polished plate glass (1913) glazing quality, was about 45 cts (\$0.45) per sq ft, for sizes of not more than 10 sq ft per plate, 50 cts (\$0.50) per sq ft for sizes containing from 10 to 50 sq ft per plate, and 65 cts (\$0.65) per sq ft for sizes containing not more than 120 sq ft per plate. For larger sizes the price increased rapidly up to \$2.00 per sq ft. The price, however, can be accurately determined only by means of a price-list and discount. The price-list in use (1913) was introduced in March, 1910, and the

\* These are pre-war prices and the data are retained for purposes of comparison.

discount was about 90%. Plate glass  $\frac{3}{16}$  in thick costs 15% more than glass of the regular thickness on account of the extra expense of grinding it down. Plate glass  $\frac{1}{8}$  in thick costs from 25 to 40% more than glass of the regular thickness.

**Sizes of Polished Plate Glass.** Plate glass is cut into stock sizes, varying by even numbers from 6 by 6 in up to 144 by 240 in, or 138 by 260 in.

**Comparative Cost of Different Kinds of Window-Glass.** The following table gives an idea of the comparative cost of the different kinds and qualities of glass used in this country for glazing. The prices for the sizes are the 1914, net, average prices. The first column of the table gives the kinds of glass, and includes both the American plate and the American sheet glass. The other columns of the table give the sizes of the different lights in inches.

**Comparative Cost of Different Kinds of Window Glass \***

Kinds of glass	Sizes of lights in inches			
	24×32	30×36	36×40	48×60
<b>American Plate Glass</b>				
Glazing-quality .....	\$2.35	\$3.38	\$4.60	\$9.80
Crystal-sheet glass, 26-oz .....	1.00	1.54	2.34	6.66
<b>American Sheet Glass</b>				
Double-strength, first quality .....	0.54	0.83	1.25	3.55
Double-strength, second quality .....	0.47	0.73	1.13	3.30
Single-strength, first quality .....	0.37	0.56	.....	.....
Single-strength, second quality .....	0.32	0.50	.....	.....

It will be seen from this table that the relative difference in the cost of plate and sheet glass decreases rapidly as the sizes of the lights increase. The prices in this table are based on the list of October 1, 1903, on a discount of 90% for plate glass, 90 and 20% for American sheet glass and 85% on AA double-strength for 26-oz crystal-sheet glass.

**Wire-Glass.** This is described in Chapter XXIII, page 821.

**Figured Rolled Glass.** This is a translucent or OBCURED glass with a pattern stamped on one surface. As the molten metal is rolled out on the table, the design, cut into the table, imprints itself into the soft glass. This kind of glass has almost entirely supplanted the ordinary ground glass because of its greater cleanliness. There are several popular designs on the market, made by various manufacturers. Some of the designs in common use are known as MOSS, MAZE, COLONIAL, FLORENTINE, COBWEB, etc. This glass is usually made  $\frac{1}{8}$  in thick and in large sheets from 24 to 42 in wide and from 8 to 10 ft long. MAZE, FLORENTINE and COBWEB designs can be had either with or without the wire mesh in them. One important property of figured rolled glass is that of diffusing the light which passes through it. (See, also, pages 1453 and 1554.)

**Pressed Prism-Plate Glass.†** This is manufactured in different patterns and for different purposes and includes (1) Imperial Prism-Plate Ornamental Glass in five different patterns, (2) Imperial Prism-Plate Glass and (3) Imperial Sky-light Prism Glass. The general description is as follows:

\* These are pre-war prices and the data are retained for purposes of comparison.

† Manufactured by the Pressed Prism Plate Glass Company, Chicago, Ill. See Appendix D, pages 1453 to 1456.

(1) **Imperial Prism-Plate Ornamental Glass** is plate glass ground and polished on one side. It is manufactured in plates, 54 by 72 or 72 by 54 in, can be cut into smaller sizes, and is made in five different stock patterns. It is used in modern mercantile, office and public buildings for partitions, transoms, door-lights, vestibule doors, ornamental ceiling-lights, bank-windows and other street-windows, and in all places where semiobscurity and ornamental effect are desired. On account of its prismatic qualities it gives a strong diffusion of light for office-use where privacy is desired.

(2) **Imperial Prism-Plate Glass.** This is manufactured in large sheets, 54 by 72 or 72 by 54 in, and can be cut into smaller sizes. It is made in several different angles in order to obtain the proper diffusion of light for varying conditions. It is a plate glass, ground and polished on one side. There are no wires or bars to collect dirt and retard the light and it is very easily cleaned. It is used in the upper sashes of windows and in transoms, store-fronts, etc.

(3) **Imperial Skylight Prism Glass.** This is made in unit plates, 18 by 60 in, with a  $\frac{1}{2}$ -in back, and conforms to the requirements of the Board of Fire Insurance Underwriters. It is used for skylights, roofs over areaways and in light-wells, etc. The possibility of leakage is lessened on account of the large-sized plates in which it may be obtained. These plates, however, can be cut into smaller sizes if required. It is particularly adapted for lighting the rear parts of stores and for railway-stations, sheds, etc.

**Prism Glass**, for glazing windows, skylights and sidewalk-lights, is now manufactured in a large number of forms in both prisms and sheets, and by several companies. The diffusing properties of several types are described on pages 1453 to 1456 under the subject of Illumination. This glass is made with sharp prisms which are glazed horizontally in the windows and by refracting the light throw it back horizontally into the rooms, adding very materially to the interior lighting. It is manufactured by several companies and can be procured from glass-jobbers in practically all the cities of the United States. (See, also page 821.) Glass prisms for lighting are made of pieces of glass of standard dimensions, about 4 in square, with a smooth outer surface and an inner surface divided into a series of prisms. They are, in many cases, formed into plates by the process of electroglazing, the edges of the prism-lenses being welded together, so to speak, by a narrow line of copper which gives the desired stiffness and strength for use in large frames, and also an attractive appearance considered by some to be superior to ordinary leaded work. These prism-plates can be made in any desired size, but for very large surfaces two or more plates, divided by means of metal sash-bars, are generally used. (See, also, page 821.)

The commercial value of these prisms depends on that property of glass which causes what is known as REFRACTION. Prism-plates receive the light from the sky, not necessarily from the sun, and refract or turn it back into the room which is to be lighted. With an ordinary window the light from the sky, passing through the glass, strikes the floor at a point not very far distant from the window. As the color of the floor is usually dark, reflecting perhaps only one-tenth part of the light falling on it, the rear parts of the room receive only a small portion of the light which enters the window. For this reason it has been necessary to make very high stories for deep rooms, in order to light, even moderately, those parts which are at a distance from the window. When prisms are substituted for the common window-glass or plate glass, the rays of light as they enter the glass are refracted, and by employing prisms of the proper angle, the rays may be given almost any direction. Moreover, by utilizing different prisms in the same plate, some of the rays may be directed to the rear of the room while others are thrown so as to strike near the front. The prism-plates do not increase

quantity of light entering the window, but simply redistribute it, directing it into those portions of the room in which it is most needed. By thus changing the direction of light-rays a room with a low ceiling can be better lighted than when sheet or plate glass is used. To insure success in the lighting of interiors by means of prisms requires, however, a superior quality of glass, and careful scientific calculations and experiments, besides practical and attractive means of glazing and methods of installation. These requirements have been met by the several companies making these prisms and their products may be considered among the relatively new building materials. They have been very successfully applied to the lighting of dark rooms by daylight. The application of prisms to any particular building depends upon the surrounding conditions and requirements, each case requiring some special treatment; but in a general way the various appliances used in the installations may be divided into four classes as follows:

(1) Vertical Plates, which are set directly in the sashes in place of the ordinary window-glass. They are commonly used for the transom-lights of store-windows and the upper sashes of double-hung windows. They may also fill the entire window.

(2) Foriluxes, which are vertical prism-plates set in independent frames and placed in window-openings substantially flush with the face of the wall.


(3) Canopies, which are external prism-plates in independent frames, placed over window-openings and set at an angle with the vertical, a position similar to that of an ordinary awning.

(4) Pavement-Prisms, which are set in iron frames in the pavements or sidewalks, in place of the ordinary bull's-eye lights. In connection with the pavement-prisms, when a

well-lighted basement is desired, vertical plates of prisms, hung below and opposite the pavement-lights, are often used. These hanging, vertical plates receive the light from the pavement-prisms, and again change its direction, project horizontally into the basement. This feature is illustrated in the

figure here given, reproduced through the courtesy of the Luxfer Prism Company.

The canopies may be made either stationary or adjustable and may be employed in a variety of ways, combining the useful with the ornamental. The hanging, vertical plates lend themselves to a highly decorative treatment. In both the fixed and hanging vertical plates the prisms may be arranged to produce ornamental effects, and designs may be wrought on the face of the prism-plates to correspond with the designs worked into the surfaces of the building with the style of the entire façade. The prism-plates weigh no more, and are less, than plate glass of the same size, while they are much stronger in resisting wind-pressure, the action of hail and the impact of flying fragments. Although transmitting a very large amount of light, these prism-plates are not transparent in the ordinary sense, and may thus be used as screens to hide unattractive views or to prevent persons looking either in or out of a window. At



Refraction and Transmission of Light by Prisms

the same time a maximum quantity of light is admitted. The prism-plating, owing to the stiff, durable manner in which they are united by the etching and glazing process, serve, also, as a fire-retardant or as a partial substitute for ordinary iron fire-shutters. The copper glazing forms, as it were, a continuous rivet, which holds the individual prism-lights together, even after they have become badly cracked by the action of fire and water. The details of the various makes of prisms are too complicated to be set forth in a few pages, but they are well described in the various handbooks and catalogues published by the different manufacturers. From a commercial point of view the special advantages of these systems of interior lighting are manifold. They transform dark rooms, particularly basements, otherwise too dark for occupancy, into bright, producing spaces; in many buildings they do away with the use of light-shades, thus saving a large amount of valuable floor-space; and in all large or crowded rooms they effect a great saving in artificial lighting. Once installed, there is no cost for maintenance. The extent to which these prisms have been used by architects, in both new and old buildings, shows that they have had a decided influence upon commercial architecture.

**Glass for Skylights. General Description.** The glass ordinarily used for skylights is either rough or ribbed skylight-glass, and since the great cheapening in the process of manufacturing glass with wire mesh in it, wire-glass, also, being largely used for this purpose. The sizes used depend largely upon the pitch of the skylight, small sizes being more desirable when the pitch is slight. The weight of rough or ribbed glass, with or without wire mesh, is approximately as follows:

Weight of Rough or Ribbed Glass

Thickness in inches.....	1/8	3/16	1/4	3/8	1/2	5/8	3/4	1
Weight in pounds.....	2	2 1/2	3 1/2	5	7	8 1/2	10	12 1/2

**Cost of Skylight-Glass.\*** The different kinds of skylight-glass in small quantities were quoted (1914) about as follows:

Cost of Skylight-Glass

Kinds of glass	Cost
Rough or ribbed skylight-glass, 1/8-in.....	6 cts per sq. ft.
Rough or ribbed skylight-glass, 3/16-in.....	8 cts per sq. ft.
Rough or ribbed skylight-glass, 1/4-in.....	12 cts per sq. ft.
Rough or ribbed wire-glass, 1/4-in.....	16 cts per sq. ft.
Maze, Cobweb, or Florentine wire-glass.....	20 cts per sq. ft.
Sheet prism glass.....	20 cts per sq. ft.

**Glass for Mirrors.** Mirrors are made by silvering one side of a sheet of polished plate glass. This is the only kind of glass suitable for making mirrors, because, unless the surface of glass is polished, the reflection is distorted. A generation ago, mirrors were made by the old-style process of pressing the glass by means of heavy weights onto mercury, backed by tinfoil, the affinity of mercury for tin forming an amalgam which protected the back of the mirror and gave the reflection. This was a very slow and expensive process. During the twenty-five years prior to 1913, practically all of the mirrors made in America were manufactured by what is known as the PATENT-BACK process, in which nitrate of silver is deposited on the back of the glass.

\* The prices have materially advanced and as they change from year to year, the manufacturers' lists must be consulted.

silver is precipitated in a film over the surface of the glass, thus giving it the property of reflecting. This film is afterward covered and protected by shellac, varnish and paint. This modern method of manufacture has made it possible to supply mirrors in considerably less time, and at a very much lower cost, than when manufactured by the old-fashioned MERCURY-BACK process. There are many who claim that in spite of modern processes of manufacture, the old method produced the best results as far as durability is concerned. This is evidenced by the following statement inserted by Mr. Kidder in the preceding editions of the Pocket-Book: "There are two kinds of mirrors on the market, the old time reliable mercury-back mirror, the other the nitrate of silver, or what is better known to the trade as the patent-back mirror. The latter is now sold and has, in recent years, been most extensively sold as a substitute for the former. In the manufacture of mercury-back mirrors no chemicals are used, only two materials, mercury and tin-foil. The affinity of mercury for tin forms an amalgam impervious to and not affected by the atmosphere. A mercury-back mirror is universally considered to be the only durable and permanent mirror. A nitrate-silver or patent-back mirror is produced by the precipitation of a chemical solution of nitrate of silver and other media on the surface of the glass, to which is added one coat of shellac varnish overlaid with one or more coats of paint. This mirror, irrespective of the quality of the glass from which it is made, will readily deteriorate from the date of its manufacture to that of its final collapse, which may occur at any time from a few months, but certainly within a few years."

## MEMORANDA ON ROOFING

**Shingles.\*** The best shingles are those made from cypress, cedar, redwood, white and yellow pine and spruce, in the order mentioned. Redwood, while perhaps not quite as durable as cypress, is less inflammable; sawed pine shingles inferior to cedar, and spruce shingles are not suitable for good work.

**Number and Weight of Cedar and Pine Shingles Per Square of One Hundred Square Feet**

Length, in	Assumed width, in	Weather or gauge, in	Number of shingles per square †	Weight per square		Number of nails per square	Weight of nails per square, lb
				Cedar, lb	Pine, lb		
14	4	4	900	210	233	1 800	4.50
15	4	4½	800	200	222	1 600	4.00
16	4	5	720	192	213	1 440	3.60
18	4	5½	655	197	218	1 310	3.28
20	4	6	600	200	222	1 200	3.00
22	4	6½	554	203	226	1 108	2.77
24	4	7	515	206	229	1 030	2.58

**Sizes of Shingles.** Cedar and redwood shingles as commonly sawed are 20 in length, and cypress shingles usually from 20 to 24 in long, the longer ones allow-

For more complete information see Kidder's Building Construction and Superintendence, Part II, Carpenters' Work, pages 321 to 325.

To allow for waste, add from 6 to 10%, the greater allowance being for the shorter shingles.



ing a greater exposure to the weather. Redwood shingles and the cedar shingles from the States of Washington and Oregon, which States furnish most of the shingles used west of the Mississippi, are  $\frac{9}{16}$  and  $\frac{9}{16}$  in thick at the butt. Cypress shingles are usually sawed thicker. Those used in Boston are  $\frac{7}{8}$  in thick. Ordinary roofing-shingles are of random widths, varying from 2 $\frac{1}{2}$  to 14 and sometimes 16 in. They are put up in bundles, usually four bundles to the thousand. A THOUSAND common shingles means the equivalent of 1000 shingles 4 in wide.

**Dimension-Shingles** are sawed to uniform width, either 4, 5, or 6 in. Dimension-shingles with the butt sawed to various patterns are also carried in stock.

On hip-roofs, or for four valleys, add 5% for cutting. On irregular roofs with dormer-windows, add 10%. It is claimed that redwood shingles will go farther than cedar shingles. With a rise to the roof of from 8 to 10 in to the foot, cedar shingles, or any shingles 16 or 18 in in length, should be laid from 4 to 4 $\frac{1}{4}$  in to the weather; with a rise from 10 to 12 in, from 4 $\frac{1}{4}$  to 4 $\frac{3}{8}$  in to the weather; and on steeper roofs they may be laid from 4 $\frac{3}{8}$  to 5 in. Redwood shingles may be laid  $\frac{1}{2}$  in more to the weather. Some authorities allow slightly greater exposures for these lengths. Where the longer shingles are used the exposure to the weather may be increased up to 7 in for the 24-in lengths. On walls cedar shingles are commonly laid 5 in to the weather, and redwood shingles 6 in.

**Labor.** An average shingler should lay 1500 shingles in 9 hours on plain work; on irregular roofs with dormers, 1000 per 9 hours.

**Nails.** It requires from 3 $\frac{1}{2}$  to 4 $\frac{1}{2}$  lb of threepenny or from 3 $\frac{1}{2}$  to 6 $\frac{1}{2}$  lb of fourpenny nails to 1000 shingles, depending upon width and length of shingles.

### Slate Roofs

**Characteristics of Good Slate.** A good slate should be both hard and tough. If the slate is too soft, however, the nail-holes will become enlarged and the slate will become loose. If it is too brittle the slate will fly to pieces in the process of squaring and holing and will be easily broken on the roof. "A good slate should give out a sharp metallic ring when struck with the knuckles; should not split under the slater's axe; should be easily HOLED without danger of fracture, and should not be tender or friable at the edges." The surface when freshly split should have a bright metallic luster and be free from all loose flakes or dull surfaces. Very few of the Vermont slates, however, have the metallic luster or ribbons. Most slates contain ribbons or seams which traverse the slate in approximately parallel directions. Slates containing soft ribbons are inferior and should not be used in good work.

**Color.** The color of slates varies from dark blue, bluish black, and purple to gray and green. There are also a few quarries of red slate. The color of a slate does not appear to indicate the quality. All slate quarried in Maine is black as is also that quarried in Virginia, while that quarried in Pennsylvania and Maryland is also black but borders on dark blue and is advertised by some firms as dark blue. Slate quarried in New York State is red, of various shades, while that quarried in Vermont is of various colors, such as green, purple, variegated, etc. The red and dark colors were formerly considered the most desirable but at the present time the greens are going on some of the largest and finest of the new residences. Some slates are marked with bands or patches of a different color, and the dark-purple slates often have large spots of green on them. These spots do not as a rule affect the durability of the slate but they greatly detract from its appearance.



**Grading of Slates.** The Monson, Me., slates and Brownville, Me., slates are graded as follows: No. 1. Every sheet to be full  $\frac{3}{16}$  in thick, both sides smooth and all corners full and square. No pieces to be winding or warped.

No. 2. Thickness may vary from  $\frac{1}{8}$  to  $\frac{1}{4}$  in, all corners square, one side generally smooth, one side generally rough, no badly warped slates.

The Bangor, Pa., slates are graded:

No. 1 Clear. A pure slate without any faults or blemishes.

No. 1 Ribbon. As well made as No. 1 Clear, except that it contains one or more RIBBONS (a black band or streak across the slate), which, however, are high enough on the slate to be covered when laid, thus presenting a No. 1 roof.

No. 2 Ribbon. This contains several RIBBONS, some of which cannot be covered when laid.

No. 2 Clear. A slate without RIBBONS, made from rough beds.

Hard Beds. A clear Bangor slate, not quite as smooth as No. 1 Clear, but much better than No. 2 Clear.

Ordinary Bent Slate. A smooth slate similar to No. 1 Clear, but bent at a radius of about 12 ft.

**Punching.** Formerly nail-holes in slates were punched on the job; now, however, slates are bored and countersunk at the quarry, when so ordered. Architects should always specify that the slates are to be bored and countersunk, as punching badly damages the slates.

**Sizes.** The sizes of slates range from 9 by 7 in to 24 by 14 in, there being some thirty-seven different sizes; the more common sizes, however, are the following: The sizes of slates best adapted for plain roofs are the large wide slates, such as 16 by 16 in, 18 by 12 in, 20 by 12 in, or 24 by 14 in. Slates from 8 by 16 to 10 by 20 in are popular sizes, 9 by 18-in slates being probably used oftener than those of any other size. The 11 by 22 and 12 by 24-in slates are used principally on very large high buildings. The lower grades of slate are used largely on warehouses and barns. The larger sizes make fewer joints in the roof, require fewer tiles, and diminish the number of small pieces at hips and valleys. For roofs cut up into small sections the smaller sizes, such as 14 by 7 in or 16 by 8 in, look the best.

**Thickness.** Slates vary in thickness from  $\frac{1}{8}$  to  $\frac{3}{8}$  in;  $\frac{3}{16}$  in is the usual thickness for ordinary sizes (see Grading of Slates in the preceding paragraphs). It is of utmost importance for architects to specify the thickness of slates, either fully  $\frac{3}{16}$  in thick, or fully  $\frac{1}{4}$  in thick, to secure a strong and durable roof.

**Laying.** Slates are laid either on a board sheathing (rough, or tongued and grooved) covered with tarred or water-proof paper or felt, or on roofing-laths 2 to 3 in wide and from 1 to  $1\frac{1}{4}$  in thick, nailed to the rafters at distances apart to suit the gauge of the slates. Each slate should lap the slate in the second course below, 3 in. The slates are fastened with two threepenny or fourpenny nails, one near each upper corner. For slates 20 by 10 in or larger, fourpenny nails should be used. Copper, composition, tinned, or galvanized nails should be used. Plain-iron nails are speedily weakened by rust, and they break and allow the slates to be blown off. On iron roofs slates are often fastened directly on small iron purlins spaced at suitable distances apart to receive them, and fastened with wire or special forms of fasteners. THE GAUGE of a slate is the portion exposed to the weather, which should be one-half the remainder obtained by subtracting 3 in from the length of the slate. Roofs to be covered with slate should have a rise of not less than 6 in to the foot for 20-in or larger slates, or 8 in for smaller sizes.

**Elastic Cement.** In first-class work, the top course of slate on the ridge, and slate for from 2 to 4 ft from all gutters and 1 ft each way from all valleys and hips, should be bedded in elastic cement.

**Flashings.** By FLASHINGS are meant pieces of tin, zinc, or copper laid on slate and up against walls, chimneys, copings, etc.

**Counterflashings** are of lead or zinc, and are laid between the courses in brick and turned down over the flashings. In flashing against stonework, grooves and reglets often have to be cut to receive the counterflashings.

**Close and Open Valleys.** A close valley is one in which the slates are mitred and flashed in each course and laid in cement. In such valleys no metal can be seen. Close valleys should only be used for pitches above 45°. An open valley is one formed of sheets of copper or zinc 15 or 16 in wide, over which the slates are laid.

**Old English Method of Laying Slates.\*** This method of laying slates involves the use of different shades of colored slates in graduated courses and in random widths beginning at the eaves, for example, with slates 28 in long and 1 in thick, and using the different thicknesses from 1¼ to ¾ in, in shorter lengths in working upward on the roof. The use of this kind of work for roofs has increased in recent years and the method possesses vast possibilities for carrying out architects' ideas for varied artistic effects. The slates are made with rough-cut edges in all thicknesses from ¾ to 1¼ in, in a combination of various shades carefully selected in such proportion as to produce the best possible harmony, when laid. As all of these colors and shades are unfading, the weathering effect is obtained at once and is permanent. These slates are made not only in usual sizes, but in the OLD-ENGLISH STYLE, to be laid in graduated courses of different lengths and in random widths. The Old English color-combination roofing-slates should be specified to secure the light-and-shadow effect, and it is of the utmost importance to specify the thickness desired, as the price is the same for all sizes, while the cost varies according to thickness. When graduated courses are desired, specifications should call for the number of courses to be laid in each length and thickness beginning at the eaves courses, where the thickest slates are used in the largest sizes, sometimes 30 or even 36 in in length, and working upward on the roof with the shorter lengths and thinner slates to the ridges where the smallest sizes and thinnest slates are used. To secure a rough effect at minimum cost, specifications should call for Old English color-combination, all slates to be fully ¾ in thick with rough cut edges and graduated courses in sizes ranging from 24 by 16 to 12 by 6 in, with nail-holes drilled and countersunk. To secure the best rough effect, specifications should call for eaves-courses not less than ¾ in thick, stating the thickness desired for the eaves, and the number of courses desired in each length and thickness. Among the good specimens of the Old English style of roofing may be mentioned the buildings of Princeton University for the Graduate College, where different shades of unfading-graduated slates are used in thicknesses running from 1¼ in at the eaves to ¾ in at the ridge.

**Measurement.** Slates are sold by the SQUARE, by which is meant a sufficient number of slates of any size to cover 100 sq ft of surface on a roof, with 3 in lap, over the head of those in the second course below. The square is also the basis on which the cost of laying is measured. "Eaves, hips, valleys, and flashings against walls or dormers are measured extra; 1 ft wide by their width."

\* Full information in regard to the details of the slates for this purpose and the methods employed in laying them can be obtained from the various companies.

ngth, the extra charge being made for waste material and the increased labor required in cutting and fitting. Openings less than 3 sq ft are not deducted, and all cuttings around them are measured extra. Extra charges are also made for orders, figures, and any change of color of the work and for steeples, towers, and perpendicular surfaces."\*

**Cost.†** The cost of slates varies with the size, color and quality. The prices given in the following table were about the average in 1915 for blue-black slate, of No. 1 grade, loaded on the cars at the Pennsylvania quarry. The freight in car-load lots of 60 squares or over to Philadelphia from Bethlehem, Pa., was 60¢ per square, from Pennsylvania to Omaha, Neb., \$2.60 and from Vermont, about the same. It will be seen that slates of the MEDIUM sizes cost the most, and those of the larger and smaller sizes the least. Special prices are quoted for special sizes. The larger sizes make the cheapest roofs. Red slates cost from 10 to 150% more than black slates. The green slates are more expensive than the black with the exception of the Maine and Peach Bottom varieties.

**Number and Cost † of Slates, and Pounds of Nails to 100 Square Feet of Roof  
3-inch Lap**

Sizes of slates, in	Exposed when laid, in	Number to a square	Weights of galvanized nails, lb oz	Cost per square at quarry
14×24	10½	98	4d { 1 6 1 10 1 12 1 15 2 0 2 6	\$4.50
12×24	10½	115		4.50
12×22	9½	126		4.75
11×22	9½	138		4.75
11×20	8½	155		5.25
10×20	8½	170		5.25
12×18	7½	160	3d { 1 13 2 3 2 7 2 2 2 8 3 0 3 2 3 0 3 12 4 4 4 9 5 3 6 1	.....
10×18	7½	192		5.25
9×18	7½	214		5.25
12×16	6½	185		.....
10×16	6½	222		.....
9×16	6½	247		5.25
8×16	6½	277		5.25
10×14	5½	262		.....
8×14	5½	328		4.75
7×14	5½	375		4.75
8×12	4½	400		.....
7×12	4½	457		4.25
6×12	4½	534		4.25

The cost of blue-black-slate roofs, complete, varies from \$9 to \$16 per square, depending on the class of work and remoteness from the quarries. The additional cost of laying slate in elastic cement varies from \$1.75 to \$2.50 per square. An experienced roofer will lay, on an average, 2½ squares of slate in 8 hours.

**Weight.** Slate roofing ¾ in thick will weigh on the roof about 6½ lb per sq ft, and if ¼ in thick, 8¾ lb, the smaller sizes weighing the most on account of the thickness. The actual weight of a square foot of slate ¼ in thick is 3.63 lb. A cubic

\* The Building Trades Pocket-book.

† These prices have advanced and the manufacturers' lists must be consulted.

foot of Vermont slate weighs approximately 175 lb. The average shipping weight for No. 1,  $\frac{3}{16}$ -in slates, is approximately 725 lb; for  $\frac{1}{4}$ -in slates, 1 000 lb; for  $\frac{1}{2}$ -in slates, 2 000 lb, etc.

### Roofing-Tiles

**General Notes on Roofing-Tiles.** The term ROOFING-TILE is commonly understood to refer to exterior roof-covering made from clay in units of various shapes and laid with overlapping edges. Clay or terra-cotta roof-tiles have long been very largely used in Europe, where their cost is much less than in America. Since the year 1893 the advance here in the character and extent of roofing-tile has been marked and rapid. This material can now be had at much lower prices than formerly prevailed, and the result has been that thousands of squares of terra-cotta tiles have been placed on shops and factories which would under former conditions have been covered with slate or metal. Whether or not a tile roof is as durable and satisfactory as one of No. 1 slate is a much-disputed question. Mr. Kidder was of the opinion that, considering the quantities used, slates have given better satisfaction than tiles. A tile roof, however, is certainly more attractive than a slate roof, and it is generally held that there are many roofing-tiles on the market which if properly laid prove as tight and durable as slates. There are so many patterns of roofing-tiles that it is impossible here to enter into a description of them. Of the various patterns, those which interlock are considered from a practical standpoint, to make the most satisfactory roof.

**Laying Roofing-Tiles.** Roofing-tiles have been laid directly on a porous book tile or concrete base or on a sheathed surface over such base, or they have been fastened to stripping over the sheathing or wooden or steel purlins by means of copper wires. When thus fastened by wires, the joints were usually pointed on the under side after they were laid, to prevent the entrance of dust or dirt or snow. Tiles of the older patterns were nailed to the sheathing, but later on this method was superseded by the practice of fastening with copper wires from pierced lugs near the lower ends of the tiles. The best modern method, however, seems to be the one involving a solid continuous base for the roofing-tiles, whether or not purlins are used. "Such purlins should be filled in between either with book tiles or a concrete base and felt should be laid thereon. The book tiles, if used, should be of a porous quality. Instead of regarding the nailing of tiles as a defective method, we have returned to it as the only proper method of fastening tiles and have eliminated the stripping of sheathed roofs and the use of copper wires. Such methods would do in some portions of central Europe where the winds and other climatic conditions are not severe, but through a twenty-five years' experience in the varied climatic conditions of the United States, we have found that the nailing of tiles with copper nails is the only satisfactory method of application. We have also found that a roof should be sheathed and covered with a good asphaltum-felt to prevent wind-suction." \* Roofing-tiles weigh from 750 to 1 200 lb per square of 100 sq ft.

### Specifications for Tile Roofing

The following specification † contains valuable suggestions for the proper laying of tile roofs:

All pitched roofs shall be covered with (—) tiles with fittings suitable for the same.

\* Quoted by permission from data on roof-tiling, by the Ludowici-Celadon Company, Chicago, Ill.

† Prepared from data furnished by the Ludowici-Celadon Company, Chicago, Ill.

each pattern unless otherwise selected by the architect. The tiles as specified above are to be hard-burned, of red color, and in accordance with samples deposited in the office of the architect.

(1) Preparation of Roof. Before the roofer is sent for, the owner or general contractor is to construct the roofs in strict accordance with the plans, sheath the roofs **TIGHT**, have all chimneys and walls above the roof-line completed, have all vent-pipes put through the roofs, furnish all strips of required width used under hip-rolls, furnish all 1 by  $\frac{3}{4}$ -in cant-strips used under the tiles at the eaves and have all the scaffolding ready for the roofers' use. The metal-contractor is to have all gutters in place on the roof (gutters, whether box, hanging or secret gutters, are to extend over the roof-sheathing and cant-strips, and run under the felt and tiles at least 8 in) and is to have in place, also, all valley-metal, the width of which is to be not less than 24 in, with both edges turned up  $\frac{1}{4}$  in through the entire length of the valley. The valley-metal is to be fastened with clips and never nailed or punctured in any manner. The valley-metal is to be laid over one layer of felt running lengthwise the entire distance of the valley. The metal-contractor is to have in readiness all flashing-metal used alongside and in front of dormers, gables, skylights, towers and perpendicular walls, and around vent-pipes and chimneys, and is to place the same after the arrival of the tile-roofer and under his direction.

(2) Laying the Felt. After the roofs have thus been prepared to receive the felt and tiles, the tile-roofer is to cover the sheathing of the roofs with one thickness of asphalt roofing-felt weighing not less than 30 lb to the square, laying the same with a  $2\frac{1}{2}$ -in lap and securing it in place by capped nails. The felt is to be laid parallel with the eaves, lapped over all valley-metal about 4 in and laid under all flashing-metal about 6 in.

(3) Laying the Tiles. The roof having thus been prepared, the tile-layer is to fasten the tiles with copper nails. The roofer is to see that the tiles are well locked together and that they lie smoothly, and no attempt is to be made to stretch the courses. The tiles are to be laid so that the vertical lines are parallel with each other and at right-angles to the eaves. The tiles that verge along the hips are to be cut close against the hip-boards, and a water-tight joint made by cementing cut hip-tiles to the hip-boards with elastic cement. Each piece of hip-roll is then to be nailed to the hip-board, and the hip-rolls are to be cemented where they lap each other. The interior spaces of hip-rolls and ridge-rolls are not to be filled with the pointing-material.

**Cost of Roofing-Tiles.\*** The prices of tiles vary from \$7 to \$30 per square, according to the character of the surface-finish and to the pattern. The cost of laying, including asphalt-felt, varies from \$5 to \$10 per square, according to the pattern of tiles used, the number of layers of felt and the character and extent of the roof. If roofing-tiles are laid on book tiles or on cement, 20% must be added to the cost for laying on wooden sheathing. Fluctuating values of copper make the item of copper nails, when these are used, one of importance.

**Sheet-Metal Tiles.** Roofing-tiles stamped from sheet steel, plain or galvanized, and also from sheet copper, in imitation of clay tiles, are made by several manufacturers and have been extensively used for factories and buildings of secondary importance. The first cost of these tiles, except those made of copper, is much less than that of clay tiles and they do not require as heavy roof-framing. Tin or galvanized-iron tiles, however, must be painted every few years, so that for a long period of years they probably cost as much as clay tiles and more than slate.

\* These prices have advanced and the manufacturers' lists must be consulted.

## Tin Roofs

**The Sheets.** Roofing-plates are made of soft steel of various special analyses or wrought iron (more commonly of the former), covered with a mixture of lead and tin, and are designated **TERNE-PLATES**, in distinction from plates coated only with tin and therefore called **BRIGHT TIN**. Roofing-plates are coated by two methods. (1) The original method of coating the plates consisted in dipping the black plates by hand into the mixture of tin and lead, and allowing the sheets to absorb all the coating that was possible; and at least one brand of roofing-tin is still made by this process. (2) The other process, by which the majority of roofing-plates are now made, is known as the **PATENT-ROLLER-PROCESS**, by which the plates are put into a bath of tin and lead, and are passed through rolls. The pressure of these rolls leaves on the iron or steel a thickness of coating which, to a great extent, determines the value of the plates. These rolls can be adjusted to leave a relatively large amount of coating on the plate, an ordinary coating, or a very scant coating. The heavier the coating the more valuable the plate. Some makers employ a variation of this patent process, by which the plates are given an extra dip, by hand, in an open pot, to give a **HAND-DIPPED FINISH**. It is claimed that hand-dipped plates will last much longer than those made by the new process, although the latter process is much more extensively used and many good roofing-sheets are made by it.

**Brands.** The best roofing-plates always have the **BRAND** stamped on them, and as the manufacturers have a pecuniary interest in keeping up the reputation of these brands, the only way of being sure of a good tin roof is to specify a brand of tin that has a reputation for quality and durability. Some of the best-known brands are Taylor's Target-and-Arrow (formerly Old Style); Merchant's Old Method, MF; Follansbee's Banfield Process; and Margaret. Machine-made plates are usually stamped with the weight of coating per box of 112 sheets, 28 by 20-in size.

**Sizes of Sheets.** The common sizes of tin plates are 10 by 14 in and multiples of that measure. The sizes generally used are 14 by 20 in and 28 by 20 in. The larger size is the more economical to lay, and hence roofers prefer to use it; but for flat roofs the 14 by 20-in size makes the better roof.

**Thicknesses of Sheets.** Terne-plates are made in two thicknesses, **IC**, in which the iron body weighs about 50 lb per 100 sq ft, and **IX**, in which it weighs 62½ lb per 100 sq ft. For roofing, the **IC**, or lighter weight, is to be preferred, because the seams do not contract and expand as much as they do when the thicker plates are used. For spouts, valleys and gutters, however, **IX** plates should always be specified, and should preferably be used for flashings, as they are stiffer and less liable to be dented or punched. The thickness of the iron does not add to the durability of the plates, as this depends entirely upon the tin coating.

**Weights of Sheets.** The standard weight of 14 by 20-in **IC** terne-plates is 107 lb for 112 sheets, the number usually packed in one box, and of 14 by 20-in **IX** sheets, 135 lb. The 28 by 20-in sheets should weigh just twice as much. The black sheets, before coating, should weigh, per 112 sheets, from 95 to 100 lb for **IC**, 14 by 20-in sheets, and from 125 to 130 lb for **IX**, 14 by 20-in sheets. The difference between the weights of the black sheets and finished sheets is the weight of the tin. A heavily coated tin should weigh from 115 to 120 lb per 112 sheets for **IC**, 14 by 20-in sheets, and from 145 to 150 lb for **IX**, 14 by 20-in sheets. The 28 by 20-in sheets should, of course, weigh twice as much.

**The Roof.** Roofs of less than one-third pitch are made with **FLAT SEAMS** and should preferably be covered with 14 by 20-in sheets rather than with 28 by 20-in

heets, because the larger number of seams stiffens the surface and helps to prevent buckles and rattling in stormy weather. For a flat-seam roof, the edges of the sheets are turned  $\frac{1}{2}$  in, locked together and well soaked with solder. The sheets are fastened to the sheathing-boards by cleats spaced 8 in apart and locked in the seams. Two 1-in barbed and tinned-wire nails are used in each cleat. No nails should be driven through the sheets. The seams must be made with great care and sufficient time taken to properly SWEAT the solder into the seams. Steep roofs should be made with STANDING SEAMS and with 28 by 20-in sheets. The sheets are first single-seamed or double-seamed and usually soldered together, preferably end to end, into long strips that reach from eaves to ridge. The sloping seams are composed of two UPSTANDS, interlocked at the upper edge, and held to the sheathing-boards by cleats. The standing seams are usually not soldered but simply locked together with the cleats folded in about 1 ft apart. Nails should be driven into the cleats only. The use of acid in soldering the seams of a tin roof should be carefully avoided as acid coming in contact with the bare iron on the cut edges and corners, where the sheets are folded and seamed together, causes rusting. No other soldering-flux but good rosin should ever be used.

**Durability of Tin Roofs.** A tin roof of good material, properly put on, and kept properly painted, will last from forty to fifty years, or longer. All traces of rosin left on the roof should be removed as soon as the tin is laid and soldered, and one coat of paint should be applied promptly; a second coat should follow two weeks after the first. One or more layers of felt or water-proof paper should be placed under the tin, to serve as a cushion, and also to deaden the noise produced by rain striking the tin. The durability of tin roofing, and especially of tin gutters, valleys and flashings, is generally increased by painting the tin on the back before laying. An excellent paint for tin roofs is composed of 10 lb of Venetian red, 1 lb of red lead and 1 gal of pure linseed-oil.

**Maintenance of Tin Roofs.** The tin roof should be given one coat of paint after it is laid and an additional coat of paint at four-year or five-year intervals should be amply sufficient to keep its upper surface in first-class condition as long as the building stands. With each painting the roof is fully restored to its original condition. Graphite and tar paints should be avoided on tin roofs. Metallic brown, Venetian red, red oxide or red lead, only, should be used as pigments, with pure linseed-oil. Tinned gutters should be swept clear of accumulations of leaves, dirt, etc., and if water has a tendency to lie in the gutters they should be painted yearly.

**Number of Sheets Required to a Square.** For FLAT-SEAM ROOFING a sheet of tin 14 by 20 in, with  $\frac{1}{2}$ -in edges, measures, when edged or folded, 13 by 19 in, or 247 sq in; but its covering capacity when joined to other sheets on the roof is only  $12\frac{1}{2}$  by  $18\frac{1}{2}$  in, or 231.25 sq in. The number of sheets to a square, therefore, equals  $14\ 400$  divided by 231.25 or 63, and an area of 1 000 sq ft requires 625 sheets. A box of 112 14 by 20-in sheets will cover, approximately, 180 sq ft. Sheets 28 by 20 in, when edged or folded, have a covering capacity of 490.25 sq in each. To cover 1 000 sq ft (10 squares) requires 294 sheets. For STANDING-SEAM ROOFING the locks require  $2\frac{3}{4}$  in off the width and  $1\frac{1}{8}$  in off the length of the sheet. A 28 by 20-in sheet, with the seams on the long edges, will cover 463 sq in. To cover 1 000 sq ft requires 312 sheets.

**The Cost\* of Tin Roofing** varies from \$8 to \$12 per square, according to the grade of the tin, the locality and nature of the work and the scale of wages. Standing-seam roofs cost about 50 cts a square less than flat-seam roofs. The cost, when 14 by 20-in sheets are used, is about 25% more than for 28 by 20-in

\* Variations in cost must be ascertained from manufacturers' lists.



sheets, owing to the greater number of seams; hence, more tin, solder, cleats and work are required.

### How a Tin Roof Should be Laid \*

**The Slope of the Roof.** If the tin is laid with a flat seam or flat lock, the roof should have an incline of  $\frac{1}{2}$  in or more to 1 ft. If laid with a standing seam, there should be an incline of not less than 2 in to 1 ft. Although tin is used on roofs of less pitch than this and on some which are almost flat, a good pitch is desirable to prevent the accumulation of water and dirt in shallow puddles. Gutters, valleys, etc., should have sufficient incline to prevent water from standing in them or backing up far enough to reach standing seams. Tongued and grooved sheathing-boards of well-seasoned dry lumber are recommended. Narrow widths are preferable, and the boards should be free from holes, and of even thickness. A new tin roof should never be laid over old tin, rotten shingles, or tar roofs. Sheathing-paper is not necessary where the boards are laid as specified above. If steam, fumes, or gases are likely to reach the under side of the tin, some good water-proof sheathing-paper should be used. Tarred paper should never be used. No nails should be driven through the sheets.

**Flat-Seam Tin Roofing.** When the sheets are laid singly, they should be fastened to the sheathing-boards by cleats, using three to each sheet, two on the long side and one on the short side. Two 1-in barbed-wire† nails should be used to each cleat. If the tin is put on in rolls the sheets should be made up into long lengths in the shop, and the cross-seams locked together and well soaked with solder. They should be edged  $\frac{1}{2}$  in, and fastened to the roof with cleats spaced 8 in apart, and the cleats locked into the seam and fastened to the roof with two 1-in barbed-wire nails to each cleat.

**Standing-Seam Tin Roofing.** The sheets should be put together in long lengths in the shop, and the cross-seams locked together and well soaked with solder. They should be applied to the roof the narrow way, and fastened with cleats spaced 1 ft apart. One edge of the course is turned up  $1\frac{1}{4}$  in at a right angle, and the cleats are installed. The adjoining edge of the next course is turned up  $1\frac{1}{2}$  in, and these edges are locked, turned over and the seam flattened to a rounded edge.

**Valleys and Gutters.** These should be lined with IX tin, and formed with flat seams, the sheets being applied the narrow way. It is important to see that good solder, bearing the manufacturer's name, is used, that it is guaranteed one-half tin and one-half lead, new metals, and that nothing but rosin is used as a flux. The solder should be well sweated into all seams and joints.

**Painting.** All painting should be done by the roofer. The tin should be painted one coat on the under side before it is applied to the roof. The upper surface of the tin roof should be carefully cleaned of all rosin-spots, dirt, etc., and immediately painted. The approved paints are metallic brown, Venetian red, red oxide, and red lead, mixed with pure linseed-oil. No patent drier or turpentine should be used. All coats of paint should be applied with a hand-brush, and well rubbed on. A second coat should be applied two weeks after the first and a third coat one year later.

**Caution.** No unnecessary walking over the tin roof, or use of it for storage of materials, should be allowed at any time. Workmen should wear rubber-soled

\* These suggestions are in accordance with the standard working specifications adopted by the National Association of Sheet Metal Contractors.

† The effect of barbing on the holding power of nails is a disputed question.



des or overshoes when on the roof. Wherever the slope is steep enough the tin could be laid with standing seams, which allow for expansion and contraction.

### Sizes, Weights, Etc., of Roofing-Tin \*

Roofing-tin is usually furnished in two sizes, sheets 14 by 20 in and 28 by 20 in, packed 112 sheets to the box. Target-and-Arrow tin is furnished in three thicknesses: IC thickness, approximately No. 30 gauge, U. S. Standard; IX thickness, approximately No. 28 gauge, U. S. Standard; 2X thickness, approximately No. 26 gauge, U. S. Standard, etc. Weight per 100 sq ft laid on the roof, about 65 lb for IC thickness.

### Covering Capacity of Roofing-Tin

**Flat-Seam Tin Roofing.** The following table shows the quantity of 14 by 20-in sheets required to cover a given number of square feet with flat-seam tin roofing. A sheet 14 by 20 in with  $\frac{1}{2}$  in edges measures, when edged or folded, 13 by 19, 247 sq in, but its covering capacity when joined to other sheets on the roof is only  $12\frac{1}{2}$  by  $18\frac{1}{2}$  in, or 231.25 sq in. In the following table each fractional part of a sheet is counted a full sheet.

No. of square feet.	100	110	120	130	140	150	160	170	180	190	200
Sheets required...	63	69	75	81	88	94	100	106	112	119	125
No. of square feet.	210	220	230	240	250	260	270	280	290	300	310
Sheets required...	131	137	144	150	156	162	169	175	181	187	193
No. of square feet.	320	330	340	350	360	370	380	390	400	410	420
Sheets required...	200	206	212	218	224	231	237	243	249	256	262
No. of square feet.	430	440	450	460	470	480	490	500	510	520	530
Sheets required...	268	274	281	287	293	299	305	312	318	324	330
No. of square feet.	540	550	560	570	580	590	600	610	620	630	640
Sheets required...	337	343	349	355	362	368	374	380	386	393	399
No. of square feet.	650	660	670	680	690	700	710	720	730	740	750
Sheets required...	405	411	418	424	430	436	442	448	455	461	467
No. of square feet.	760	770	780	790	800	810	820	830	840	850	860
Sheets required...	474	480	486	492	499	505	511	517	523	530	536
No. of square feet.	870	880	890	900	910	920	930	940	950	960	970
Sheets required...	542	548	554	561	567	573	579	586	592	598	604
No. of square feet.	980	990	1000	...	...	...	...	...	...	...	...
Sheets required...	610	617	625	...	...	...	...	...	...	...	...

A box of 112 sheets 14 by 20 in laid in this way will cover 180 sq ft.

**Flat-Seam Tin Roofing.** The following table shows the number of 28 by 20-in sheets required to cover a given number of square feet with flat-seam tin roofing. The flat seams edged  $\frac{1}{2}$  in take  $1\frac{1}{2}$  in off the length and width of the sheet. The covering capacity of each sheet is, therefore,  $26\frac{1}{2}$  by  $18\frac{1}{2}$  in, or 490.25 sq in. In the following table each fractional part of a sheet is counted a full sheet.

The following tables of sizes, weights, covering capacities and costs are adapted from data compiled for the use of sheet-metal workers by the N. & G. Taylor Company, Philadelphia, Pa.

No. of square feet.	100	110	120	130	140	150	160	170	180	190	200
Sheets required...	30	33	36	39	42	45	47	50	53	56	59
No. of square feet.	210	220	230	240	250	260	270	280	290	300	310
Sheets required...	62	65	68	71	74	77	80	83	86	89	92
No. of square feet.	320	330	340	350	360	370	380	390	400	410	420
Sheets required...	94	97	100	103	106	109	112	115	118	121	124
No. of square feet.	430	440	450	460	470	480	490	500	510	520	530
Sheets required...	127	130	133	136	139	141	144	147	150	153	156
No. of square feet.	540	550	560	570	580	590	600	610	620	630	640
Sheets required...	159	162	165	168	171	174	177	180	183	186	189
No. of square feet.	650	660	670	680	690	700	710	720	730	740	750
Sheets required...	191	194	197	200	203	206	209	212	215	218	221
No. of square feet.	760	770	780	790	800	810	820	830	840	850	860
Sheets required...	224	227	230	233	235	238	241	244	247	250	253
No. of square feet.	870	880	890	900	910	920	930	940	950	960	970
Sheets required...	256	259	262	265	268	271	274	277	280	282	285
No. of square feet.	980	990	1000	...	...	...	...	...	...	...	...
Sheets required...	288	291	294	...	...	...	...	...	...	...	...

A box of 112 sheets 28 by 20 in laid in this way will cover 381 sq ft.

**Standing-Seam Tin Roofing.** The following table shows the number of 14 by 20-in sheets required to cover a given number of square feet with standing-seam roofing. The standing seams, edged  $1\frac{1}{4}$  and  $1\frac{1}{2}$  in, take  $2\frac{3}{4}$  in off the width and the flat cross-seams, edged  $\frac{3}{8}$  in, take  $1\frac{1}{4}$  in off the length of the sheet. The covering capacity of each sheet is, therefore,  $11\frac{1}{4}$  by  $18\frac{3}{4}$  in, or 212.34 sq in. In the following table each fractional part of a sheet is counted a full sheet.

No. of square feet.	100	110	120	130	140	150	160	170	180	190	200
Sheets required...	68	75	82	89	95	102	109	116	123	129	135
No. of square feet.	210	220	230	240	250	260	270	280	290	300	310
Sheets required...	143	150	156	163	170	177	184	190	197	204	211
No. of square feet.	320	330	340	350	360	370	380	390	400	410	420
Sheets required...	218	224	231	238	245	251	258	265	271	279	285
No. of square feet.	430	440	450	460	470	480	490	500	510	520	530
Sheets required...	292	299	306	312	319	326	333	340	346	353	360
No. of square feet.	540	550	560	570	580	590	600	610	620	630	640
Sheets required...	367	374	379	387	393	401	407	414	421	428	435
No. of square feet.	650	660	670	680	690	700	710	720	730	740	750
Sheets required...	441	447	455	462	468	475	482	489	495	501	509
No. of square feet.	760	770	780	790	800	810	820	830	840	850	860
Sheets required...	515	523	529	536	543	550	557	563	570	577	584
No. of square feet.	870	880	890	900	910	920	930	940	950	960	970
Sheets required...	590	597	604	611	618	623	630	637	644	651	658
No. of square feet.	980	990	1000	...	...	...	...	...	...	...	...
Sheets required...	665	672	679	...	...	...	...	...	...	...	...

A box of 112 sheets 14 by 20 in laid in this way will cover 165 sq ft.

**Standing-Seam Tin Roofing.** The following table shows the number of 28 by 20-in sheets required to cover a given number of square feet with standing-seam roofing. The standing seams take  $2\frac{1}{4}$  in off the width, and the flat cross-seams, spaced  $\frac{3}{4}$  in, take  $1\frac{1}{4}$  in off the length of the sheet. The covering capacity of the sheet is, therefore,  $26\frac{3}{4}$  by  $17\frac{1}{4}$  in, or 463.59 sq in. In the following table the fractional part of a sheet is counted a full sheet.

No. of square feet.	100	110	120	130	140	150	160	170	180	190	200
Sheets required...	32	35	38	41	44	47	50	53	56	59	62
No. of square feet.	210	220	230	240	250	260	270	280	290	300	310
Sheets required...	65	68	71	74	77	80	84	87	90	94	97
No. of square feet.	320	330	340	350	360	370	380	390	400	410	420
Sheets required...	100	103	106	109	112	115	118	121	125	128	131
No. of square feet.	430	440	450	460	470	480	490	500	510	520	530
Sheets required...	134	137	141	144	147	150	153	156	159	162	165
No. of square feet.	540	550	560	570	580	590	600	610	620	630	640
Sheets required...	168	171	174	177	180	184	187	190	193	196	199
No. of square feet.	650	660	670	680	690	700	710	720	730	740	750
Sheets required...	202	205	208	211	214	218	221	224	227	230	233
No. of square feet.	760	770	780	790	800	810	820	830	840	850	860
Sheets required...	236	239	242	245	249	252	255	258	261	265	268
No. of square feet.	870	880	890	900	910	920	930	940	950	960	970
Sheets required...	271	274	277	280	283	286	289	292	296	299	302
No. of square feet.	980	990	...	...	...	...	...	...	...	...	...
Sheets required...	305	308	...	...	...	...	...	...	...	...	...

A box of 112 sheets 28 by 20 in laid in this way will cover 360 sq ft.

**Laying the Long or Short Way.** Sheets 14 by 20 in can be laid either the long or short way. The best roof is made by laying the sheets the 14-in way; similarly, in using the 28 by 20-in sheets, they should always be laid the 20-in way, that is, with the short dimension crosswise.

### Cost of Roofing-Tin

#### Cost of Tin for Standing-Seam Roofing

Sheets 28 by 20 in. Price per box and per square foot

When tin costs per box.....	\$11.00	\$11.50	\$12.00	\$12.50	\$13.00	\$13.50	\$14.00	\$14.50	\$15.00	\$15.50
Standing-seam roofing costs per sq ft.....	0.0297	0.0310	0.0324	0.0337	0.0351	0.0364	0.0378	0.0391	0.0404	0.0418
When tin costs per box.....	16.00	16.50	17.00	17.50	18.00	18.50	19.00	19.50	20.00	20.50
Standing-seam roofing costs per sq ft.....	0.0432	0.0446	0.0459	0.0473	0.0486	0.0500	0.0513	0.0526	0.0540	0.0553
When tin costs per box.....	21.00	21.50	22.00	22.50	23.00	23.50	24.00	24.50	25.00	....
Standing-seam roofing costs per sq ft.....	0.0567	0.0580	0.0594	0.0607	0.0621	0.0634	0.0648	0.0661	0.0675	....

The above estimates do not include cost of laying. The cost, using 14 by 20-in sheets, amount to about 25% more than the cost, using 28 by 20-in sheets, owing to the larger number of seams. More tin, solder, cleats and work are therefore necessary.

Tin in Rolls, or Gutter-Strips

Number of sheets required per linear foot for 20 and 28-in widths

Feet	Widths		Feet	Widths		Feet	Widths		Hun- dred feet	Widths	
	20	28		20	28		20	28		20	28
1	1	1	35	16	23	69	31	44	2	89	12
2	1	2	36	16	23	70	32	45	3	134	14
3	2	2	37	17	24	71	32	45	4	178	16
4	2	3	38	17	24	72	32	46	5	223	18
5	3	4	39	18	25	73	33	47	6	267	20
6	3	4	40	18	26	74	33	47	7	312	22
7	4	5	41	19	27	75	34	48	8	356	24
8	4	5	42	19	27	76	34	48	9	401	26
9	4	6	43	20	28	77	35	49	10	445	28
10	5	7	44	20	28	78	35	50	11	490	30
11	5	7	45	20	29	79	36	50	12	534	32
12	6	8	46	21	29	80	36	51	13	578	34
13	6	9	47	21	30	81	36	52	14	623	36
14	7	9	48	22	31	82	37	52	15	667	38
15	7	10	49	22	31	83	37	53	16	712	40
16	8	11	50	23	32	84	38	54	17	756	42
17	8	11	51	23	33	85	38	54	18	801	44
18	8	12	52	24	33	86	39	55	19	845	46
19	9	12	53	24	34	87	39	55	20	890	48
20	9	13	54	24	34	88	40	56	21	934	50
21	10	14	55	25	35	89	40	57	22	979	52
22	10	14	56	25	36	90	40	57	23	1 023	54
23	11	15	57	26	36	91	41	58	24	1 068	56
24	11	16	58	26	37	92	41	59	25	1 112	58
25	12	16	59	27	38	93	42	59	26	1 157	60
26	12	17	60	27	38	94	42	60	27	1 201	62
27	12	18	61	28	39	95	43	61	28	1 246	64
28	13	18	62	28	40	96	43	62	29	1 290	66
29	13	19	63	28	40	97	44	62	30	1 335	68
30	14	19	64	29	41	98	44	63	31	1 379	70
31	14	20	65	29	41	99	44	64	32	1 424	72
32	15	21	66	30	42	100	45	64	33	1 468	74
33	15	21	67	30	43	....	....	....	34	1 513	76
34	16	22	68	31	43	....	....	....	35	1 557	78

Cost of Tin in Rolls or Gutter-Strips

Labor, solder, paint, rosin and other materials not included

- A box of 112 sheets in 28-in roll will cover 175 lin ft
- A box of 112 sheets in 20-in roll will cover 248 lin ft
- A box of 112 sheets in 14-in roll will cover 350 lin ft
- A box of 112 sheets in 10-in roll will cover 496 lin ft

Cost per box (28 by 20 in).....	\$10.00	\$11.00	\$12.00	\$13.00	\$14.00	\$15.00
Cost per linear foot, 28 in wide.....	0.05714	0.06285	0.06856	0.07426	0.07996	0.08566
Cost per linear foot, 20 in wide.....	0.04032	0.04435	0.04838	0.05241	0.05644	0.06047
Cost per box (28 by 20 in).....	\$16.00	\$17.00	\$18.00	\$19.00	\$20.00	.....
Cost per linear foot, 28 in wide.....	0.08566	0.09136	0.09706	0.10276	0.10846	.....

**Tin in Rolls.** For the convenience of roofers and for rush-orders, Target-and-row tin is put up in rolls 14, 20 and 28 in wide. Each roll contains 108 sq ft (about 63 lin ft, 28 by 20-in sheets laid 20 in wide). The tin is painted on one or both sides, as wanted, with an approved metallic brown paint. The seams are carefully soldered by hand, good 100 to 100 solder and rosin being used as flux.

### Slag or Gravel Roofing

**The Ordinary Gravel Roofing** over boards is formed by first covering the surface of the roof with dry felt (paper) and over this laying three, four, or five layers of tarred or asphaltic felt lapping each other like shingles, so that only 6 to 10 in of each layer are exposed. In laying roofs over concrete the dry felt is omitted, a mopping of pitch is placed directly on the concrete and the first layer of the felt embedded in it.

**Flashing** against walls, chimneys, curbs of skylights, etc., is done by turning the felt up 6 in against the walls. Over this is laid an 8-in strip with half its width on the roof. The upper edge of the strip and of the several layers of felt is then fastened to the walls by nailing wooden strips or laths over the felt and into the walls. Metal flashings to protect the felt are better than the wooden strips and should be used when possible. At the eaves and on all exposed edges, metal gravel-stops should be used.

**A Better Method of Slag or Gravel Roofing** is to lay two plies of tarred felt, lapping each other 17 in, and then spreading a coat of pitch over the entire roof. On this again three more layers of felt are laid and then coated with pitch, into which the crushed slag or screened gravel is embedded.

**Specifications for Pitch-Slag or Gravel Roofing.** The following specification-notes \* describe the latter method more in detail and also the materials that should be used to secure a first-class job. These roofs are most efficient and durable on comparatively flat inclines. The usual built-up roof consists of successive layers of saturated felt cemented together and surfaced with coal-tar pitch or asphalt, into which is embedded the gravel or slag. Tile is also used as a facing material. The saturants used in the felt are generally coal-tar or asphalt-compounds.

#### (1) Specification for Pitch-Slag or Pitch-Gravel Roofing Over Wooden Sheathing

This specification should not be used when the roof-incline exceeds 3 in to 1 ft. Lay one thickness of sheathing-paper or unsaturated felt weighing not less than 5 lb per 100 sq ft, lapping the sheets at least 1 in.

Over the entire surface lay two plies † of tarred felt, lapping each sheet 17 in over the preceding one, and nail as often as is necessary to hold them in place until the remaining felt is laid.

Coat the entire surface uniformly with pitch.

\* Condensed and adapted from the roofing specifications published by the Barrett Company and known, in their full form, as "The Barrett Specifications." They can be obtained from the manufacturers.

† In the Western States the number of "plies" is construed to mean the total number of layers, including dry as well as saturated felt, and the terms 3-ply, 5-ply, etc., are hereinafter used on that basis. In the Eastern States, 3-ply, 5-ply, etc., usually refers to the number of layers of saturated felt. The total number of layers should always be specified if there is any doubt as to the exact meaning of the term as used in the specifications.

Over the entire surface lay three plies of tarred felt, lapping each sheet 22 in over the preceding one and mopping with pitch the full 22 in on each sheet, so that in no place felt touches felt. Do such nailing as is necessary so that all nails are covered by not less than two plies of felt.

Diagram of Gravel or Slag Roofing on  
Wooden Sheathing

Diagram of Gravel or Slag Roofing on  
Concrete Base

Spread over the entire surface a uniform coating of pitch, into which, while hot, embed not less than 400 lb of gravel or 300 lb of slag to each 100 sq ft. The grains of the gravel or slag are to be from  $\frac{3}{4}$  to  $\frac{5}{8}$  in in size, and dry and free from dirt.

The roof may be inspected before the gravel or slag is applied, by cutting a strip not less than 3 ft long at right-angles to the direction in which the felt is laid. All felt and pitch is to bear the manufacturer's label.

(3) Specification for Pitch-Slag or Pitch-Gravel for Roofing over Concrete

This specification should not be used when the roof-incline exceeds 3 in to 1 foot. When the incline exceeds 1 in to 1 ft the concrete must permit of nailing; nailing-strips must be provided.

Coat the concrete uniformly with hot pitch.

Over the entire surface lay two plies of tarred felt, lapping each sheet 17 in over the preceding one, mopping with pitch the full 17 in on each sheet, so that in no place felt touches felt.

Coat the entire surface uniformly with pitch.

Over the entire surface lay three plies of tarred felt, lapping each sheet 22 in over the preceding one and mopping with pitch the full 22 in on each sheet, so that in no place felt touches felt.

Spread over the entire surface a uniform coating of pitch, into which

not, embed not less than 400 lb of gravel or 300 lb of slag to each 100 sq ft. The grains of the gravel or slag are to be from  $\frac{1}{4}$  to  $\frac{5}{8}$  in in size, and dry and free from dirt.

The roof may be inspected before the gravel or slag is applied, by cutting a slit not less than 3 ft long at right-angles to the direction in which the felt is laid. All felt and pitch is to bear the manufacturer's label.

**Notes on Slag and Gravel Roofing.** The difference between slag and gravel roofing is that for the former crushed slag is used instead of gravel. The greater the number of plies of tarred felt, the greater the amount of pitch that it is practical to use, and it is the pitch that gives life to the roof. As there are several different weights and qualities of tarred felt, a specification should state either the minimum weight per 100 sq ft, single thickness (the most practical weight is from 14 to 16 lb), or some known quality, such as Barrett's "Specification Tarred Felt." Felt weighing less than 12 lb per 100 sq ft is not economical even on the cheaper work. To comply with the Barrett specification the materials necessary for each 100 sq ft of completed roof are approximately as follows:

Over boards	Material	Over concrete
108 sq ft	Sheathing-paper	None
80 to 85 lb	Specification tarred felt	80 to 85 lb
120 to 160 lb	Specification-pitch	180 to 225 lb
400 lb	Gravel	400 lb
300 lb	Slag	300 lb

In estimating felt, the average weight is practically 15 lb per 100 sq ft, single thickness, and about 10% additional is required for laps. In estimating pitch the weather-conditions and expertness of the workmen will affect the amount necessary for the moppings and for a proper embedding of the gravel or slag. As there are several qualities of pitch, a specification should either specify it by name, such as "Specification-Pitch" or "Straight-Run Coal-Tar Pitch," or in specifying asphalt-pitch, the brand or origin should be plainly defined. The use of an under-layer of sheathing-paper next to board-sheathing is mainly for the purpose of preventing any pitch which might penetrate the felt from cementing the roofing to the sheathing. It is also of value in preventing the drying out of the roof from below through open joints. Where a less expensive roof is desired, four plies or three plies of saturated felt may be used. With the four plies there should be used from 90 to 100 lb of pitch per 100 sq ft of completed roof; and with the three plies from 70 to 80 lb of pitch.

**Durability of Slag or Gravel Roofs.** These roofs, mentioned in the preceding paragraph, will last from five to ten years, or even longer, depending upon the quality of the materials used and the care with which they have been applied. Roofing put on strictly as provided for in the standard specifications will last twenty years or more, and if a tile surface is used, instead of gravel or slag, the roofing will last as long as the structure itself.

**Resistance to Fire, Acid-Fumes, Etc.** The fire-resisting properties of the slag or gravel roof are due principally to the incombustible material on the surface. It is claimed that the gravel or slag tends to prevent the successive layers of felt and pitch from burning and the whole mass has a blanketing influence on fires originating within the building. Some carefully conducted tests seem to indicate that gravel roofing protects a wooden roof better than tin. The general effect of a fire upon gravel roofing is to soften the pitch or asphalt in the roofing,

to burn out the inflammable oil in them and to cause the residue to swell and form a porous, incombustible coke. This type of roofing is not attacked by corrosive gases or acid-fumes, and is used extensively on railroad-roundhouses and other structures where the conditions are particularly severe. Coal-tar or tar should not be added to the pitch to soften it.

**Guarantee.** Roofers generally give a five-year guarantee with gravel roofing.

**Cost\* of Pitch-Slag or Gravel Roofing.** The cost of this type of roofing varies greatly, depending on the location, size and quality of the work, the extremes being approximately \$2.50 and \$3.50 per square for three-ply, \$3.50 and \$4.50 per square for four-ply, and \$4.50 and \$7.00 per square for five-ply roofing.

### Asphalt-Gravel Roofing

**Asphalt-Gravel or Asphalt-Slag Roofing** differs from coal-tar roofing principally in the substitution of asphalt or asphaltic cement for the coal-tar pitch, saturating the felt as well as for mopping and surface-coating. It is claimed that the oils of asphalt do not evaporate as quickly as do those of coal-tar pitch under ordinary temperatures and that therefore the flexibility and life of asphaltic felts and coatings are not as quickly destroyed. As a matter of fact, asphalt roofs do not always last longer than some coal-tar roofs, but the chances are that they will last fully as long and possibly longer, depending upon the quality of the materials and the workmanship. The asphalt used for roofing is obtained principally from the island of Trinidad.

**Specifications for Asphalt Roofing.†** The following specifications were prepared by the above-named company and are for Warren's heavy standard Anchor-brand roofing. The manner of laying the felting differs from that ordinarily employed for coal-tar roofing.

#### (1) Specification for Asphalt-Gravel Roofing Over Wooden Sheathing

Cover the roof with two thicknesses of Warren's Composite roofing-felt, manila-paper side down, lapping each sheet 17 in over the preceding one, and securing with nails through tin discs about 2¼ ft apart.

Over the entire surface of the Composite felt thus laid, mop an even coating of Warren's Anchor Brand roofing-cement, into which, while hot, lay two thicknesses of Anchor Brand felt, lapping each sheet 17 in over the sheet preceding, sticking these laps the full width with hot Anchor cement and securing with nails through tin discs not more than 20 in apart.

Over the entire surface of the felt thus prepared, spread an even coating of cement, covering it immediately with a sufficient body of well-screened gravel or crushed slag.

If the roofing is applied in cold weather the gravel or slag must be heated.

Slag only should be used if the incline of the roof exceeds 3 in to the foot.

All layers of felt must be turned up at least 4 in over battlement-walls, sky-light-curbs, or any projections raised above the roof.

#### (2) Specification for Asphalt-Gravel Roofing Over Concrete

The concrete foundation is to be smooth and perfectly graded to carry the water to the outlets or gutters.

Over the entire surface of the concrete first mop a smooth, even coating of Eclipse Asphalt cement, into which, while hot, lay two thicknesses of Warren's Anchor Brand roofing-felt, lapping each sheet 17 in over the sheet preceding.

\* These prices have advanced and the manufacturers' lists must be consulted.

† The asphalt-roofing materials manufactured by the Warren Chemical & Manufacturing Company of New York have been used for many years and have given great satisfaction.



Mop back for the full width between the laps of the felt thus laid, with Warren's Anchor Brand roofing-cement.

Over the entire exposed surface of the felt mop an even coating of said Anchor cement, into which, while hot, lay two thicknesses of Anchor Brand felt, lapping each sheet 17 in over the sheet preceding, and sticking these laps thoroughly the full width with hot cement.

Over the entire surface of the felt thus prepared, spread an even coating of the cement, covering it immediately with a sufficient body of well-screened, dry gravel or crushed slag.

If the roofing is applied in cold weather, the gravel or slag must be heated. Slag only should be used if incline of roof exceeds 3 in to the foot. On steep surfaces nailing-strips should be provided in the concrete, unless the latter is sufficiently soft to admit of nailing. All layers of felt must be turned up at least 4 in over battlement-walls and skylight-curbs, or any projections raised above the roof.

**Cost of Asphalt-Gravel or Slag Roofing.** Asphalt-gravel roofing costs a little more than pitch-gravel roofing of the same grade. (See Cost of Pitch-gravel or Gravel Roofing, page 1598.)

**Roof-Incline.\*** Asphalt-gravel or asphalt-slag roofing should not be applied on roofs which are steep enough to make the material run in hot weather. The manufacturers of various roofings will guarantee the permanency of their roofings on certain maximum slopes.

**Prepared Roofing.** There is a large number of so-called PREPARED ROOFINGS or READY ROOFINGS, which are made by cementing together two, three, or more layers of saturated felt or felt and burlap and then coating the combination either with a hard solution of the same cementing material, or with hot pitch or asphalt to which is embedded sand or fine gravel. These roofings are commonly put up in rolls 36 in wide and are applied by lapping the strips 2 in with a coat of cementing material between, and nailing every 2 or 3 in with tin-capped roofing-nails. A sufficient quantity of cement, nails and tin caps is packed in the middle of the rolls. The particular advantage of these roofings is that no previous experience is required for laying them and no kettles are required; for this reason they are extensively used in the country, and on railroad-shops, factories, and mill-buildings. In cities there is no particular advantage in using them except for roofs that are too steep for coal-tar pitch, as they cost on the roof about the same as good gravel roofing. Many of these prepared roofings are as durable under ordinary conditions as the light-weight gravel roofs. In Colorado, however, it has been found that they are badly damaged by severe hail-storms, probably owing to the lack of the protecting gravel. For roofs having a rise of 1 in or more to the foot, these roofings make economical and durable roofs, and for some buildings are to be preferred to other materials.

## Corrugated Iron and Steel Sheets

**Corrugated Sheets** of iron and steel are very extensively used for the roofing and siding of mills, sheds, grain-elevators and warehouses. The best grades of corrugated sheets are now made of double-refined box-annealed iron or steel.†

The Editor has been notified by the Warren Chemical & Manufacturing Company, New York, that when put on according to their directions, their Anchor Brand roofing has been successfully used on relatively steep surfaces where the slope was as high as 9 in to the foot.

It is claimed that "the life of a genuine PUDDLED-IRON sheet when exposed only to pure air and natural elements is from five to eight times longer, and when exposed to

The corrugations are usually made lengthwise of the sheet, either by passing them through rolls or by pressing the plain sheets in a press made to give the desired corrugations. It is claimed that the latter method gives the more perfect and uniform corrugations. The weight and thickness of the metal is represented by the gauge-number of the black sheets from which the corrugated sheets are made. The standard gauge\* for sheet iron and steel in this country is that established by act of Congress, March 3, 1893. (See page 402.)

**Gauges.** The following table gives the weights and thicknesses of the different gauges, from No. 7 to No. 30, for flat BLACK SHEETS. The gauge extends from No. 7—0,  $\frac{1}{8}$  in thick, up to No. 40, 0.005469 in thick, but sheet steel is not commonly made thinner than No. 30, and above  $\frac{3}{16}$  in, the thickness is generally designated by fractions of an inch. Section 3 of the act of Congress provides that in the practical use and application of this gauge, a variation of  $\pm\frac{1}{2}\%$  either way may be allowed.

United States Standard Gauge for Sheet Iron and Steel \*

Number of gauge	Thicknesses		Weights	
	Approximate thickness in fractions of an inch	Approximate thickness in decimal parts of an inch	Weight per square foot in ounces, avoirdupois	Weight per square foot in pounds avoirdupois
7	$\frac{3}{16}$	0.1875	120	7.5
8	$1\frac{1}{64}$	0.171875	110	6.875
9	$\frac{5}{32}$	0.15625	100	6.25
10	$\frac{9}{64}$	0.140625	90	5.625
11	$\frac{1}{8}$	0.125	80	5.0
12	$\frac{7}{64}$	0.109375	70	4.375
13	$\frac{3}{32}$	0.09375	60	3.75
14	$\frac{5}{64}$	0.078125	50	3.125
15	$\frac{9}{128}$	0.0703125	45	2.8125
16	$\frac{1}{16}$	0.0625	40	2.5
17	$\frac{9}{160}$	0.05625	36	2.25
18	$\frac{1}{20}$	0.05	32	2.0
19	$\frac{7}{160}$	0.04375	28	1.75
20	$\frac{3}{80}$	0.0375	24	1.50
21	$1\frac{1}{320}$	0.034375	22	1.375
22	$\frac{1}{32}$	0.03125	20	1.25
23	$\frac{9}{320}$	0.028125	18	1.125
24	$\frac{1}{40}$	0.025	16	1.0
25	$\frac{7}{320}$	0.021875	14	0.875
26	$\frac{3}{160}$	0.01875	12	0.75
27	$1\frac{1}{640}$	0.0171875	11	0.6875
28	$\frac{1}{64}$	0.015625	10	0.625
29	$\frac{9}{640}$	0.0140625	9	0.5625
30	$\frac{1}{80}$	0.0125	8	0.5

Galvanizing the Sheets adds approximately  $2\frac{1}{2}$  oz per sq ft to the above weights. The regular sizes of the corrugations are  $2\frac{1}{2}$ ,  $1\frac{1}{4}$ ,  $\frac{3}{4}$  and  $\frac{3}{8}$  in, measured from center to center. Besides these sizes, 5-in, 3-in and 2-in corrugations are made. Galvanized sheets are much more resistant to atmospheric sulphurous and other gases from ten to twenty times longer, than a sheet of steel or semi-steel of the same gauge, or a light-gauge sheet made from pure puddled pig-iron; and that it will wear longer than steel sheets of the heaviest gauges, or galvanized sheets of the same gauge."

\* For other gauges, see pages 401, 402, 403, 1469, 1473, 1509, 1510 and 1512.

corrugated  
roof  
(connection)

3 corrugating companies. Corrugated sheets are 7-ft, 8-ft, 9-ft and 10-ft lengths. Sheets can be ordered at a cost of 5% extra. The 8-ft length, however, is the standard length of the sheets, as a rule, is 24 in between centers so that the covering width is 24 in when one sheet is laid over another. This applies to all sizes of corrugations, all standard sheets. The 2-in, 2½-in and 3-in corrugated sheets are standard from No. 16 to No. 28, the 1½-in corrugated sheets from No. 24 to No. 28 and the 1-in, 1½-in, 2-in, 2½-in and 3-in corrugated sheets from No. 16, 27 and 28 only. No. 28 gauge is the one common size. Sheets are generally painted with a red mineral oil. Galvanized sheets, also, can be obtained if desired. The weight of the square (100 sq ft), measuring the actual corrugated sheets.

### Corrugated-Steel Roofing \*

Roofs, either 3-in, 2½-in, or 2-in corrugations are the most common size. The thickness or gauge depends on the supports on which the sheets are laid. They can be laid on close sheathing, or strips not more than 4 in apart. The maximum distances between supports for different gauges are:

1-in, 1½ ft, center to center.

2-in, 2 to 3 ft, center to center.

3-in, 3 to 4 ft, center to center.

For No. 16 gauge, 5 to 6 ft, center to center.

The least pitch which should be given to roofs that are to be covered with corrugated sheets is 3 in to the foot, and for trussed roofs it is not desirable to




Fig. 1. Approved Method of Laying for Side Lap

have less than a one-fourth pitch (6 in to the foot). When laid on a roof, corrugated sheets should have a lap at the lower end of from 3 to 6 in, according to the pitch of the roof. For a ¼ pitch, a 3-in lap is used; for a ⅓ pitch, a 4-in lap; and for a ½ pitch, a 5-in lap. For the side lap it is recommended that each alternate sheet be laid upside down and lapped as shown in Fig. 1. By this method, when water is blown through the first lap, it will stop and not pass the half lap, but run down and out at the end of the sheet. A great deal of roofing, however, is laid as in Fig. 2. In applying to sheathing or wooden strips, the sheets are secured by nailing through the tops of the corrugations, the nails being driven through every alternate corrugation at the ends, and about 8 in

\* Much practical information regarding the use of corrugated sheets on mill-buildings, with many details, is contained in Steel Mill Buildings and in the Structural Engineers' Handbook, by Milo S. Ketchum.

† For the strength of corrugated sheets, see the books above mentioned.

apart at the sides. When applied to iron or steel purlins, the side laps should extend over at least  $1\frac{1}{2}$  corrugations, and the sheets should be riveted together every 8 in on the sides and at every alternate corrugation at the ends. The Cincinnati Corrugating Company makes a patent edge-corrugation which makes a tight joint with a lap of only one corrugation. To fasten the sheets




Fig. 2. Common Method of Laying for Side Lap

the purlins, which are usually steel angles, cleats of band-iron,  $\frac{3}{4}$  or  $\frac{1}{2}$  in wide may be passed around or under the purlins and riveted at both ends to the sheets, as shown in Fig. 3. By contracting or pressing these cleats toward the web, a tight, secure fastening results, which allows for contraction and expansion of the sheets. Cleats, however, are generally used only with channel or Z-purlins.




Fig. 3. Sheets Fastened to Angle-purlin by Band-iron Cleats




Fig. 4. Sheets Fastened to Angle-purlin by Clinch-nails

purlins. For angle-iron purlins, clinch-nails, made of soft-iron wire, are commonly used, as shown in Fig. 4; they make very satisfactory fastenings.

The following table shows the sizes of clinch-nails to be used with different sizes of angle-purlins and also the number of nails to the pound in each instance.

Purlin-angles.....	2X2 in	2½X3 in	3½X3½ in	4X4½ in
Lengths of nails.....	4 in	5 in	6 in	7 in
Number of nails per pound.....	48	38	33	27

The nails should be placed through the TOP of every second or third corrugation. At the eaves of the building and along the edges of the ventilators special pains should be taken in fastening the roofing, as these are the places where the force of the wind is the greatest and where it tends to strip the roofing from the purlins. For these parts of the roof the best method of fastening is that shown in Fig. 5. These fastenings consist of strips of sheet iron about 2 in wide and the purlins, made of No. 12 iron and riveted to the purlins with  $\frac{1}{4}$ -in rivets spaced 10 in apart. To these strips the corrugated sheets are riveted, every 5 in or every two corrugates, with 6-lb rivets. The method of fastening shown in Fig. 6, also, answers very well and is less expensive.

in ordering corrugated sheets an allowance must be made for the laps. The following table gives the number of square feet necessary to cover one square of




Fig. 5. Approved Fastening for Sheets at Eaves




Fig. 6. Alternate Method of Fastening at Eaves

al surface, using sheets 8 ft long. If shorter sheets are used, the allowance st be slightly increased.

Number of Square Feet of Corrugated Sheets to Cover 100 Square Feet of Roof

Mid-laps.....	1 in	2 in	3 in	4 in	5 in	6 in
	sq ft	sq ft	sq ft	sq ft	sq ft	sq ft
Side lap, 1 corrugation.....	110	111	112	113	114	115
Side lap, 1½ corrugations....	116	117	118	119	120	121
Side lap, 2 corrugations.....	123	124	125	126	127	128

Approximate Weights in Pounds of 100 Square Feet of 2¼-in Corrugated Sheets

Gauge.....	No. 28	No. 27	No. 26	No. 24	No. 22	No. 20	No. 18	No. 16
Painted....	69	77	84	111	138	165	220	275
Galvanized.	86	93	99	127	154	182	236	291

Anti-Condensation Lining. Wherever corrugated steel is laid on purlins a no sheathing or paper underneath, if the building is heated, moisture will variably collect on the under side, and if the air in the building is warm and aid, considerable dripping will result. To prevent this dripping, it is neces- to protect the under side of the corrugated steel with paper or felt. This be done by first stretching poultry-netting over the purlins, from eaves to e, and wiring the strips together at the edges. Over this should be laid one kness of asbestos paper and one or two layers of saturated felt. The cor- ated steel may then be fastened to the purlins in the usual way. The side may be secured by stove-bolts, with 1 by ½ by 4-in plate washers on the ar side, to support the lining.

Corrugated Siding

er Siding, either the 2½, 2, or 1¼-in corrugations are used. The 1¼-in size, ever, makes the best appearance. For the laps, 1 in at the bottom and one gation at the sides are sufficient.

er Sheds, etc., the sheets may be nailed to cross-pieces cut in between the s horizontally and spaced from 2 to 3 ft apart, the studs being from 3 to 4 ft

on centers. For elevators, either cross-corrugated sheets or sheets not more than 32 in long should be used. The nails should be driven in the trough of each alternate corrugation, 2 in above the lower end of the sheet, which will be 1 in ABOVE the top end of the under sheet. This allows the sheet to slide in 32 in as the building settles, before the nail will strike the upper end of lower sheet. The side lap should not be nailed.

**Ceilings.** For the ceilings of stores, stables, etc.,  $\frac{3}{16}$  or  $\frac{5}{16}$ -in corrugated sheets are much used; and the construction is an excellent one for the purpose.

**Galvanized Iron.** This term is commonly applied to all galvanized steel metal. Formerly most of the galvanized sheets had a steel base, but about 1906 a nearly pure iron, called Toncan Metal, has been largely used in sheets of very fine quality. Galvanized sheets come in lengths of 6, 7 and 8 ft in United States Gauge-Nos. 14, 16, 18, 20, 22, 24, 26, 27, 28 and 30, in widths of 24, 26, 28, 30 and 36 in for all gauges except No. 30, which is made in widths of 24, 26 and 28 in. Sheets of No. 28 gauge are also made in widths of 32 and 34 in. The widths commonly carried in stock are 24, 28 and 36 in. Most of the galvanized iron used for cornices and ornamental work is No. 28 gauge. No. 28 is sometimes used for gutters and conductors.

### Copper for Roofs

**Method of Applying.** This is usually in  $2\frac{1}{2}$  by 5-ft sheets, making 12 sq ft and weighing from 10 to 14 lb per sheet. It is laid on boards to which it is fastened by copper cleats. No solder is employed, as it is in tin roofs, in horizontal joints, and the horizontal and sloping joints are made by simply overlapping and bending the sheets. The horizontal joints are locked together and then tightly flattened down.

## MEMORANDA ON TILING

### Floor-Tiling and Wall-Tiling

**Tile Floors** are extensively used in the better class of buildings, and particularly in those portions which are used by the public, on account of their durability, sanitary qualities and decorative effects. As a matter of fact a tile floor is also cheaper in the long run than a wooden floor if it is subject to much wear. The materials used for tiling floors are tiles made from different grades of clay, marble, slate, glass and rubber. Of these probably the most durable and sanitary are the vitreous clay tiles. For walls and wainscoting glazed tiles, marbles and glass are extensively used.

**Floor-Tiles.** The following include some of the principle kinds of clay tiles.

(1) **Common Encaustic Tiles.** These belong to the cheapest grades, and are made of naturally colored clays, red, buff, gray, chocolate and black. These tiles are of a porous, absorbent nature and are used for common floors where sanitary requirements are not exacting.

(2) **Semivitreous Tiles.** These belong to a somewhat better grade than the first mentioned and are less porous and absorbent.

(3) **Vitreous Tiles.** These are the hardest tiles known, cannot be scratched by steel or sand, and are non-absorbent and thoroughly aseptic. They are used principally for floors requiring a perfect sanitary condition and are manufactured in white, blue, gray, green and pink colors of great delicacy.

**Ceramic Tiles or Ceramic Roman Mosaic.** This material is made of **REFRIGERANT** clay in tesseral pieces representing the tesserae of the Roman mosaics. It is made into regular tiles ranging from  $\frac{1}{2}$  to  $\frac{3}{4}$ -in squares and also in hexagonal shapes from  $\frac{3}{4}$  in to 1 in in size. A rounded **LOZENGE TILE** is also manufactured to be laid in tesseral paving. (See, also, *Flooring of Mosaic, Terrazzo*, page 1607.)

The material itself is of great hardness and well suited for work of a monumental or public character. The even and regular texture of the tesserae admits adoption of **DAMASK DESIGNS** which have become identified and associated with this material. The minuteness of the tesserae admits of a great range in coloring and the following of the architectural lines. The ceramic Roman mosaic is much preferred to mosaic consisting of natural marbles, because of the great variety in colors and its greater durability. The vitreous-clay tiles are immune to attacks of any acids contained in the atmosphere, while marbles, especially, are subject to rapid disintegration caused by the sulphuric acid condensed in the smoke-laden atmosphere of our cities.

**Florentine Mosaics and Flint Tiles.** These are the largest and heaviest manufactured in this country. They are either plain or inlaid and are in especially in ecclesiastic work on account of their relation to mediæval architecture. The material is vitreous, annealed and tougher than it is brittle. It is also in use for exterior polychrome work.

**Aseptic Tiles.** These are large, heavy and thoroughly vitreous tiles used in hospital work. They are the only vitreous tiles of large size made in this country. As the tiles are large and generally of hexagonal shape, the joints are reduced to a minimum, and they are, therefore, especially adapted for hospitals, operating-rooms and wards for contagious diseases.

**Enameled Tiles, Wall-Tiles and Mantel-Tiles.** The following include some of the enameled tiles:

**White, Wall-Tiles.** These are glazed tiles for wainscots. They have a white, soft body and a surface covered with a clear glaze. The brilliancy of the glaze and its reflecting properties make the white wall-tiles especially desirable for dark passages.

**Colored, Glazed or Enameled Tiles.** These tiles are about the same as the former in quality; the **GLAZE OR ENAMEL**, however, is stained with metallic oxides, which produces a brilliant decorative effect.

**Dull-Satin, etc., Finished, Enameled Tiles.** These are glazed tiles with a **DULL OR BLIND** enamel-finish. The dull finish is produced either by sanding or by devitrifying enamels. It is principally used for quaint decorative effects in mantel-work.

**Glazed Roman Mosaics.** This is a type of enameled tiling which has many decorative possibilities. It has the same tesseral texture as the ceramic tiles and is readily applied to wainscots and mantel-work.

**Laying of Tiles.** Clay tiles are set in Portland-cement mortar as a rule, and flooring of this character should always be provided with a substantial concrete base. Ceramic mosaics are sometimes laid on a flexible base. With this construction wooden floors can be provided with tile covering, and owing to the elasticity and lightness of the material, floors in elevators, boats and other light structures can be safely tiled.

**Marble Tiles,** from 9 to 12 in square, have been extensively used for flooring, especially on account of their decorative effect. None of the marbles, however, are as hard and consequently as durable as the vitreous and ceramic tiles, and

from all practical standpoints the marbles do not make as good floor-coverings. When used, they should be  $1\frac{1}{4}$  in thick and not over 12 in square, and should be bedded in cement on a concrete base. Marbles should not be used for floors in hospitals, as they yield rapidly to the usual antiseptic floor-washes.

Slate, although non-absorbent and not affected even by dilute mineral acids, is too cold and dingy to commend itself for floor-tiles, but because it is conveniently handled in large slabs it is valuable as a cheap base and as a cover for wiring and pipe-trenches in the floors. As these often follow a wall, it may be used in the capacity of a border and as such be extended around the floor-edges. Slate slabs for floors should be about  $1\frac{1}{4}$  in thick.

**Marbleithic Tiles or Slabs** are made of small pieces or chips of marble of irregular shapes, set in a backing of sand and Portland cement. After the cement has set, the top surface is rubbed until it becomes flat and smooth. Marbleithic resembles mosaic or TERRAZZO, except that it is laid in the form of tiles instead of being put down on the floor in a plastic condition. Much objection has been made to TERRAZZO because of the cracks which commonly occur in it, due to the slight settlements which are unavoidable in a new building. (See, *Flooring of Mosaic, Terrazzo, etc.*, page 1607.) With tile floors of any material the joints allow for any slight movement of the floor-construction without causing visible cracks. By the process of manufacture, marbleithic is much harder than it is possible to make mosaic floors that are laid in a plastic condition, so that they have a much better wearing surface. Floors of this material have been in use since 1895 and show little if any wear. Marbleithic tiles are made of various colored marbles and in different sizes, shapes, and patterns, so that a great variety of effects may be produced. Sanitary bases, stair-treads, and wainscotings, also, are made of this material.

**Cast-Glass Tiles**, while quite resistant to a blow when the polish is broken, will break very easily when the surface is scratched. All glass tiles should, therefore, be very thick and small or protected by metal framing.

**Novus Sanitary Glass \*** is a sanitary structural glass manufactured in thicknesses from  $\frac{1}{4}$  in up to 2 in and in slabs of all widths and lengths up to 120 in width and 180 in in length. It is made in various colors and designs and has the following finishes: natural-fire finish, hone, semipolished and polished. It can be worked and handled the same as marble, it is readily drilled and shaped to accommodate fixtures, etc., and is very handsome in appearance. It is impervious to discoloration and is non-crazing. These qualities make it especially desirable for floors, wainscoting, tables, shelves, etc., in all places where a completely sanitary condition combined with a handsome appearance is required.

### Interlocking Rubber Tiling

**General Description.** There is an interlocking rubber tiling,† which, because of its being noiseless, non-slippery, and more comfortable to the feet than inelastic substances, has met with great favor for floors in banking-rooms, counting-rooms, vestibules, elevators, stairs, cafés, libraries, churches, etc. In elevators it is one of the most durable and practical floors that can be used. It is also especially and peculiarly adapted for floors of yachts and steamships. The interlocking feature unites the tiles into a smooth, unbroken sheet of rubber, unlimited in area. The tiles do not pull apart or come up, and being distinct, almost any color-scheme can be employed, the tiles being made in a carefully selected variety of colors. The tiles are laid directly over

\* Made by the Penn-American Plate Glass Company, Pittsburgh, Pa.

† Manufactured by the New York Belting and Packing Company, New York.



final floor, like a carpet, except that they are not fastened. Experience has shown that they are very durable. Each tile is  $2\frac{3}{4}$  in square and  $\frac{3}{8}$  in thick; 16 tiles are required to the square foot. Rubber nosing for stairs is made to lock with the tiles.

### Cost \* of Different Tiles

**Approximate Cost.** The following prices are approximately the cost, to the factory, at the factory. To these should be added the freight and the dealers' profits. The cost of laying the tiles on a cement base, in addition to the cost of the tiles, should not exceed 25 cts per sq ft.

Floor-Tiles	
Kinds of tiles	Factory price per sq ft
Common encaustic tiles, unglazed.....	15 cts
Translucent tiles, white.....	22 $\frac{1}{10}$ cts
Colors, large sizes.....	from 23 to 26 cts
Ceramic tiles, or ceramic Roman mosaic.....	from 20 to 35 cts
Wall-Tiles and Mantel-Tiles	
Kinds of tiles	Factory price per sq ft
White glazed wall-tiles.....	23 cts
Colored glazed or enameled tiles.....	35 cts
Enameled tiles, dull satin-finish.....	50 cts
Marble tiles, from 45 cts, upwards, laid.....	.....
Hand-made faience, plain colors.....	from \$0.60 to \$1

### Flooring of Mosaic, Terrazzo,† etc.

**Flooring of Mosaic Work** is largely used. (See, also, Ceramic Tiles, or Ceramic Roman Mosaic, page 1605, and Marbleithic Tiles, page 1606.) It is composed of small pieces of stone, marble, pottery or glass, usually laid in some ornamental design or pattern. A bed of concrete is first laid and the small pieces of the material used set in a floating of cement and made from  $\frac{1}{2}$  to 1 in thick. When cubes of varicolored marble are used, pressed into the cement mortar, it is called ROMAN MOSAIC. A somewhat cheaper flooring is made by setting marble chips of irregular shape over the surface of the cement, pressing them into it with plasterers' floats and rolling them with iron rollers. This is called TERRAZZO MOSAIC. The following is from the specifications for the new Field Museum, Chicago, Ill., D. H. Burnham, architects: "Filling for terrazzo shall be composed 1 part cement, 2 parts sand and 4 parts brick. When concrete filling commences to set spread a  $\frac{3}{4}$ -in wearing surface composed of marble chips with only enough neat Portland cement to firmly unite the chips. Trowel and roll, and after the mortar has set, rub the terrazzo to a smooth, even surface and wash clean." "Terrazzo floors in the East cost from 30 cts per sq ft, contractor's profit included."†

\*These prices have advanced and the manufacturers' lists must be consulted.

See article on Terrazzo Floors, by C. R. Marsh, in Journal of the Society of Constructors of Federal Buildings, July, 1914.

†Quoted from The New Estimator, by William Arthur, 1914.

## ASPHALTUM

**Bitumen, Asphaltum, Asphalt.** "Bitumen is the name used to denote a group of mineral substances, composed of different hydrocarbons, found widely diffused throughout the world in a variety of forms which grade from thin volatile liquids to thick semifluids and solids, sometimes in a free or pure state, but more frequently intermixed with or saturating different kinds of inorganic organic matter. To designate the condition under which bitumen is found, different names are employed; thus the liquid varieties are known as NAPHTHA and PETROLEUM, the semifluid or viscous as MALTHA or MINERAL TAR, and the solid or compact as ASPHALTUM or ASPHALT." \*

**Asphaltum** is found in extensive beds or lake-like deposits on both continents; the most notable of these are the PITCH lakes on the island of Trinidad, and Bermundez, Venezuela. It is also found saturating the limestone and sandstone formations in certain localities. Deposits of very nearly pure asphaltum are found in Utah, Mexico, Cuba, and various parts of the United States. ELATERITE, GILSONITE and WURTZILITE are varieties of very nearly pure asphaltum.

**Asphaltic Roofing-Materials** are manufactured principally from Trinidad asphalt. These deposits have also been the main source of supply for the asphaltum used in street-paving in the United States.

**Rock-Asphalt.** The term ROCK-ASPHALT is commonly used to designate the material obtained from the bituminous limestone deposits at Seyssel and Mont, in the valley of the Rhône, France, in the Val-de-Travers, canton of Neuchâtel, Switzerland, and at Ragusa, on the island of Sicily. It is extensively employed for paving purposes throughout Europe, and is considered to make much more durable pavement than can be made with asphaltum. Rock asphalt is prepared for shipment in two forms: (1) COMPRESSED ASPHALT BLOCKS, which are used for paving in much the same way as stone blocks, and (2) MASS ASPHALT, which is put up in cakes of varying shape, generally bearing the manufacturer's trade-mark.

**Mastic-Asphalt.** In the Eastern States MASTIC-ASPHALT is used for floors of cellars, stores, breweries, malt-houses, hotel-kitchens, stables, laundries, conservatories, public buildings, carriage-factories, sugar-refineries, mills, rinks, and for any place where a hard, smooth, clean, dry, fire-proof and water-proof, odorless and durable covering of a light color is required, either in the basement or upper stories. It can be laid over cement concrete, brick, or wood, in sheet without seams; also over cement concrete for roofs for fire-proof buildings. For dwelling-house cellars, especially on moist or filled land, this material is especially adapted, being water-tight, non-absorbent, free from mold or mildew, impervious to sewer-gases, and for sanitary purposes, invaluable. Mastic asphalt is also valuable for DAMP-COURSES over foundations, and for covering vaults and arches under ground.

**Asphalt Floors and Pavements.** For floors of cellars, courtyards, etc., laid on the ground, a base of cement concrete 3 in thick should first be laid; over this a layer of asphalt from  $\frac{3}{4}$  in to  $1\frac{1}{2}$  in thick, according to the use for which it is to be put. For ordinary cellar-floors, the asphalt need not be more than  $\frac{3}{4}$  in thick; for yards on which heavy teams are to drive, it should be  $1\frac{1}{2}$  in thick. In specifying asphalt pavement, both the thickness of the concrete and of the asphalt should be given; it should also be remembered that ASPHALT PAVEMENT does not include the CONCRETE FOUNDATION unless so specified.

ing asphalt over planks or boards, a layer of stout, dry, but not tarred, sheathing-paper should first be put down and the asphalt laid on this. Asphalt floors in stables should be at least 1 in thick. Architects and owners desiring to employ ROCK-ASPHALT for any of the above purposes should be careful to secure the genuine VAL-DE-TRAVERS, SEYSSSEL, or SICILIAN ROCK-ASPHALT, as there are imitations which are of but little value.

The Bituminous Sandstones of California have been extensively used for paving streets in Western cities. They are prepared for use as paving-materials by crushing to powder. With this powder a considerable proportion of sand and gravel is generally mixed and the mixture heated until it becomes plastic; it is then spread over the roadways and compressed by rolling.

## MINERAL WOOL

**Sources of Mineral Wool.** There are at least two kinds of mineral wool made in this country. The more common quality is made by mixing certain kinds of stone with the MOLTEN SLAG from blast-furnaces and converting the whole mass into a fibrous state. The best slag for the purpose is that which is made from iron. The appearance of the finished product is much like that of wool, being soft and fibrous, but in no other respect are the materials alike. Mineral wool made from slag appears in a variety of colors, principally white, but often yellow or gray, and occasionally quite dark. The color, however, is said to be no indication of the quality, as all of the peculiar properties of the material are present in equal proportions in any of the shades. The other kind of mineral wool is known as ROCK-WOOL, and is made from granite rock raised to 200° F. It is claimed that as it is absolutely free from sulphur, it is the only fireless wool manufactured. It has been approved by the United States War Department. It has the same general appearance as that made from slag, and is white in color.

**Nature of Mineral Wool.** Both of these materials consist of a mass of very fine, pliant, but inelastic, vitreous fibers interlacing in every direction and forming an innumerable number of minute air-cells. Its great value in the insulation and protection of buildings lies in the number of air-cells which it contains, consequent non-conduction of heat, and its fire-resisting qualities. In wool made from common slag, 92% of the volume consists of air held in minute cells, while in the best grade the proportion of air reaches as high as 96%. This condensed air makes it one of the best, if not the best, of the non-conductors of heat. Made from these qualities it is very durable and contains nothing that can decay or become musty. Being itself incombustible it greatly retards the burning of wooden floors or partitions if their inner spaces are filled with it.

**Uses of Mineral Wool.** The greatest value of this material is as an insulator of heat, but it is also a valuable non-conductor of sound. It is the general opinion, however, that it can be considered only as a MUFFLER of the sounds, for there seems to be no practical way in which it can be used so as to insulate entirely the floor and ceiling. It would be crushed by laying floorboards upon it. As a muffler or filling between the beams, however, there is probably nothing that is superior. In the end, then, it would seem that the most complete insulation from sound, without separate beams, would be obtained by FLOATING the flooring on some material like Cabot's Quilt or on a very thick layer with the spaces between the floor-cleats filled with mineral wool.

**Manner of Applying Mineral Wool.** Mineral wool, when used alone as fire-deadening, may be laid on boards cut in between the joists, or on top of sheathing-lath when that material is used. The wool should be at least 2 in

thick. Again, mineral wool is particularly desirable for filling the spaces between the studs of outside walls and partitions and between the rafters of roofs. It may be used to great advantage, also, in partitions around bath-rooms or water closets, and around water-pipes when placed in partitions. In outside walls and attic roofs, as a protection from the heat of summer or the cold of winter, it is of the greatest value. By lathing the under side of the rafters with shingle-lath, and spreading on top a layer of 2 or 3 in of mineral or rock-wool, the comfort of the room is greatly increased. Flat roofs over inhabited rooms may be covered with rough boards and 1¾-in cleats nailed on top, the spaces filled with wool, and the roof-sheathing then nailed to the cleats. This not only greatly increases the comfort of the rooms, but greatly retards the progress of fire from the outside. When insulating against heat, nails driven through the insulating material do no harm. When using mineral wool in floors it should be packed in very closely, but not jammed so as to break the fibers, which are naturally very brittle. In partitions it is packed between the studs and lathed so as to completely fill the spaces, the wool being put in after the lathing has reached a height of 2 or 3 ft. More laths are then put on, the spaces filled, and so on to the top. The wool should not be dropped from any considerable height, as the breaking up of the fibers destroys the insulating qualities of the material. In fact the tendency of mineral wool to settle and consolidate, if improperly too loosely packed, is the only drawback, except cost, to its use for insulating. The wool behind the lathing will not prevent the plaster from keying.

**Cost of Mineral Wool.** Mineral wool is sold by the pound, and in estimating the quantity of wool required, 1 lb per sq ft of filling, 1 in thick, should be allowed for ordinary wool and ¾ lb for selected wool.

## ESTIMATING THE COST OF BUILDINGS \*

**Cost of Buildings per Cubic Foot.** The method of CUBIC-FOOT VALUES has been used more than any other in estimating the cost of any proposed building, before the plans and specifications are sufficiently complete for taking off the actual quantities. "Comparison of UNIT COSTS is the only scientific criterion by which to judge the economic merit of a structure, a machine or a method of doing work." † Two buildings in the same city, or district built in the same style and for the same purpose, of the same materials, and on the same scale of wages and prices of materials, should cost the same, or very nearly the same, per cubic foot, although one building may be somewhat larger than the other and of different shape. It therefore follows that if we know the COST PER CUBIC FOOT of different classes of buildings, in different localities, we can approximate quite closely the cost of any proposed building by multiplying its cubic contents in feet by the known cost per cubic foot of a similar building already built in that locality.

**Size of Building Proportioned to Cost per Cubic Foot.** If the cost of a proposed building must be kept absolutely within a certain sum, the size of the building should be proportioned so that the CUBIC CONTENTS shall not exceed the quotient obtained by dividing the amount appropriated by the AVERAGE COST PER CUBIC FOOT of similar buildings. Even then it may be found, when the bids are opened, that they exceed the appropriation; but the excess is often a relatively small percentage of the total cost and the necessary reductions can be made without altering the main features of the building.

**Methods of Computation.** In estimating the cost by the METHOD OF CUBIC CONTENTS, it is of course necessary that the contents be computed on the same basis, in both the proposed building and the one already built. The cubic contents are generally computed from the basement or cellar-floor, to the average height of a flat roof, or, if there is a pitched roof, the finished portion of the attic is included, or that part which might be finished, mere air-spaces and open porches not being included. Vaults and areas under sidewalks, etc., are generally included as part of the basement. All measurements are to the outside of the walls and foundations. The estimated cost may or may not include the fees of the architect and other experts.

**Other Methods of Estimating the Cost of Buildings.** The cost of buildings, such as hospitals, theaters, schools, churches, barracks, large stables, etc., are sometimes estimated by the COST PER BED, SITTING, INMATE, etc. Estimates are also based upon the COST PER SQUARE FOOT OF GROUND OCCUPIED or of all the FLOOR-SPACE, in certain types of buildings.

\* The editor is indebted to E. S. Hand and others for valuable data relating to this subject. Readers are referred to the Handbook of Cost Data for Contractors and Engineers, by H. P. Gillette, The New Building Estimator, by William Arthur, and The Building Estimator's Reference Book, by F. R. Walker. Values given are pre-war values and may be used for relative costs.

† H. P. Gillette, in the preface to his Handbook of Cost Data for Contractors and Engineers.

## Data \* on Cubic-Foot Values as a Basis for Preliminary Estimates of Building Costs

**Notes on Modifying Conditions.** Buildings of a given TYPE, such as office buildings and school-buildings, when similar in construction and finish and built under similar market-conditions as to cost of labor and materials, are found to be nearly identical in CUBIC-FOOT COSTS. The buildings of any such type do not differ widely in bulk, and this is always very considerable when compared with such structures as dwellings and small business buildings. This seems only another way of saying that similar causes produce similar effects, but it goes a step farther by indicating that the results here are virtually identical; so near, so, that the AVERAGE CUBIC-FOOT COST of a certain kind of building can be relied on to produce an estimate within from 3 to 5% of the actual cost of new work of the same kind and under the same conditions. Other types of large structures such as public buildings, hotels, churches and theaters, are less subject to standardization because more variable in equipment and finish. This is true also of dwellings, shops and other small structures whose lesser bulk, moreover, renders even less possible a close prediction as to their cost. These uncertainties do not, however, warrant the rejection of the CUBIC-FOOT-COST METHOD for preliminary estimating. They do indicate that it is less closely approximate for some types than for others. But the degree of uncertainty on even the most variable types may be minimized and should be reduced to perhaps 10% under a careful system of cost-computation. Such system should cover a considerable number of examples, taking account of all factors of material influence upon cost in each type, and must follow a consistently uniform method of determining cubic-foot values.

**The Factors Which Influence Cost** include the following.

- (1) Prevailing market prices of labor and materials.
- (2) Type of construction employed, depth and kind of foundations and existence of special features such as towers or domes.
- (3) Finish: external facing and ornamentation; internal surfacing and decoration.
- (4) Equipment: (a) number and complexity of heating, lighting, ventilation, sanitary, elevator and other systems; (b) extent to which apparatus or equipment, such as laboratory-devices, opera-chairs, bank-counters etc., is provided for direct use of occupants of building.
- (5) Fees of architect and other experts.
- (6) Locality. Costs of structures of a given type will vary with the locality because of differing standards of practice and building laws, availability of building materials, labor, etc.
- (7) Other items, developing in the experience of the architect.

**The Method of Determining Cubage** may either simply recognize the GEOMETRICAL VOLUME of the building or, better, may employ a COEFFICIENT OF VALUE for any part whose cost varies materially from the average. The latter method may be preferred as allowing a closer calculation of variations from known examples. For instance, an unfinished cellar or other story or small light-court would cost less per cubic foot than the remainder of the building.

\* The data on this page and page 1613 on cubic-foot values are quoted, by permission, from notes relating to this subject, compiled by Professor Warren P. Laird in the study of a large number of public and private buildings erected in widely separated districts of the United States. For these buildings Professor Laird acted as the professional adviser for the selection of the architect, and in all cases the estimate of the cost of the buildings was based strictly upon a total number of cubic feet and a fixed cost per cubic foot.

ing, while a tower or dome of finished basement containing, also, an expensive mechanical plant, would cost more. Foundations sometimes cost so much that they require figuring to their full depths as though the finished building were carried down to that level.

**Cubic-Foot Costs.** Subject to the foregoing considerations, the following data on fire-proof buildings were average pre-war values. These unit prices no longer prevail as labor and materials have in some cases almost doubled in cost since the war. The values must be increased from 50 to 100%, depending upon the kind of building.

Construction: steel and terra-cotta, stone and brick facings, complete equipment and superior grade of interior finish:

Type of building	Cents per cubic foot
Office-buildings.....	32 to 35
Public buildings.....	40 to 45
School-buildings.....	20 to 25

Construction: reinforced concrete; facing, common brick; equipment, type equal in such structures; inside finish, the simplest.

Type of building	Cents per cubic foot *
Factories †.....	14 to 16
Lofts †.....	15 to 18

### Table for Estimating Roughly the Approximate Cost of Some Small Buildings

Based on prices for labor and materials in 1920. The cost of first-class fire-proof buildings is greater in the Western and Southern States than in the Eastern States, because of the distance from the great steel and material-centers.

#### Farm and Country Property

	Cost per cubic foot, cents
Wellings, frame; small box house, no cornice.....	10
Wellings, frame; shingle roof, small cornice, no sash weights, plain.	12 to 14
Wellings, brick; same class.....	16 to 18
Wellings, frame; shingle roof, good cornice, sash weights, blinds (good house).....	16 to 18
Wellings, brick; same class (good house).....	20 to 22
arns, frame; shingle roof, not painted, plain finish.....	4 to 6
arns, frame; shingle roof, painted, good foundation.....	6 to 8
res, frame; shingle roof, painted, plain finish.....	12 to 16
res, brick; shingle roof, painted, good cornice, well finished.....	16 to 20
inary frame churches and schoolhouses; country.....	12 to 16

These pre-war values must be increased from 50% to 100%, depending upon the kind of building.

If such subcontracts as plumbing, heating, lighting-fixtures, elevators, etc., are not included, of course these figures were reduced. See Cost of Reinforced-Concrete Buildings, page 1618.

Brick churches and schoolhouses; country.....	18
If the roofs are slate or metal, add $\frac{3}{4}$ ct per cu ft.	

City and Village Property

Dwellings, frame; shingle roof, pine floors and finish, no bathroom or furnace, plain finish (good house).....	14
Dwellings, brick; same class.....	18
Dwellings, frame; shingle roof, hard-wood floor in hall and parlor, bath, furnace, and fair plumbing.....	18
Dwellings, brick; same class.....	18
Dwellings, frame; shingle roof, hard-wood in first story, good plumbing, furnace, artistic design, some interior ornamentation, well painted.....	22
Dwellings, brick; with good plumbing, bath, hot and cold water, pine finish, well painted, no hard-wood finish.....	24

Examples of Actual Costs of Pre-war Buildings per Cubic Foot

In order to illustrate the subject further, examples of buildings erected before the war are given. The lists were furnished through the courtesy of architects of the buildings. Such lists could be indefinitely extended, but the submitted are deemed sufficient to give some idea of the similarities and variations of costs based upon cubage. With the exception of reinforced-concrete buildings, it is probably true that for twenty or twenty-five years (1890 to 1914) the cost of buildings increased, with some variations in the rate of increase, the rate of about 1% per year. Costs have increased since the war from 30 to 100%, depending upon the kind of building.



## Examples of the Actual Cost of Pre-war Buildings per Cubic Foot

These buildings were designed by Boring &amp; Tilton

Name and location of building	Date	Height and type	Approximate cost	Cost per cubic foot, cents
Memorial Hall, Tome Institute, Port Deposit, Md.	1900	Three stories and basement, fire-proof	\$150 000	16
West Side Branch Library, Cleveland, Ohio	1908	One story and basement, non-fire-proof	85 000	17
Stamford Grammar School, Stamford, Conn.	1908	Two stories and basement, non-fire-proof	50 000	15
St. Agatha's School, 87th St. and West End Ave., New York City	1907	Six stories and basement, fire-proof	275 000	29
American Seamen's Friend Society, Jane and West Sts., New York City	1909	Five stories and basement, fire-proof	200 000	32
Eastern District Branch Y. M. C. A., Brooklyn, N. Y.	1906-1909	Six stories and basement, fire-proof	255 000	27
Tarrytown Hospital, Tarrytown, N. Y.	1910	Two stories and basement, non-fire-proof	65 000	26
Hair Hospital, Huntingdon, Pa.	1909	Three stories and basement, fire-proof	90 000	20
Elizabeth Library, Elizabeth, N. J.	1912	Three stories and basement, fire-proof	100 000	35
Springfield Library, Springfield, Mass.	1908	Two stories, mezzanine and basement, fire-proof	350 000	35
Sioux City Library, Sioux City, Iowa	1912	Two stories and basement, non-fire-proof	75 000	21½
11 Park Avenue, New York City	1912	Twelve stories and basement, fire-proof	350 000	45
United States Immigrant Station, Ellis Island, New York Harbor. Main building	1898	Two stories and basement, fire-proof	625 000	17½
Hospital building	1898	Three stories and basement, fire-proof	150 000	28
Mount St. Mary's College, Plainfield, N. J.	1912	Three stories and basement, fire-proof	250 000	22

These buildings were designed by Palmer, Hornbostle & Jones

Name and location of building	Date	Notes	Cubic contents, cubic feet	Approximate cost *	Cost per cubic foot, cents
Oakland City Hall, Oakland, Cal.	1914	Based on all contracts except for lighting-fixtures	2 999 442	\$1 400 000	45½
Allegheny County Soldiers' Memorial, Pittsburgh, Pa.	1911	.....	2 855 892	913 721	32
New York State Education Building, Albany, N. Y.	1912	Original contract completed, Dec. 1912	11 281 691	3 744 521	33¼

These buildings were designed by Robert D. Kohn

Name and location of building	Date	Height, character of construction and finish	Cost per cubic foot, cents
Hermitage Hotel, New York City.	1907	Size of lot, 50 by 100 ft; height, 150 ft; 15 bedrooms and 11 baths on each floor; basement and sub-basement; power, electric light and refrigerating-plants; complete kitchen-equipment; brick and limestone exterior; cement floors.	58
Trades School Building, Manassas, Va.	1910	Main wing, 50 by 100 ft, two and one-half stories; shop-wing, 75 by 105 ft, one story, brick; shops, mill-constructed roof, cement floor; brick exterior throughout; heating-plant in extension; common wooden-floor construction, tin roof, classrooms plastered; cheaply built.	22
Ethical Culture Meeting House.	1910	Height, 100 ft; basement, assembly-room; main floor, auditorium for 1 200 people; two stories above auditorium, Sunday school and offices; limestone exterior; fire-proof construction; oak finish.	38

**Cost \* of Some Notable Buildings in New York City.** Some of the prominent buildings in the Borough of Manhattan, City of New York, are included in the following table. For all these structures the costs per cubic are given. By reason of its height the Woolworth Building may be considered the most notable of the list. It is not only the highest building in New York City or the United States, but in the world. The cubic contents total 12 000 000 cu ft. Its foundations are carried to rock, which is about 15 ft below the street-surface. The approximate weight of its steel frame is 3 tons.

\* See notes on cost on page 1614.

Cost-Data \* of Some Notable Pre-war Buildings in New York City †

		Ground- area, sq ft	Total floor- area, sq ft	Cost	Cubic contents, cu ft	Costs per cubic foot, cents
Altman Building †	8-story department-store	54 850	495 000	.....	..	33
Banker's Trust Co.'s Building †	39-story office-building	9 721	345 000	.....	..	70
Heckscher Building †	50 E. 42nd St. . . . .	10 750	147 172	\$700 000	1 793 351	39
Masonic Building †	19-story lobbies and meeting-rooms	23 300	432 000	2 250 000	5 701 000	39
Walker-Lispénard Building †	24-story telephone-exchange	27 580†	.....	..	..	40
Woolworth Building †	55-story office-building	15 600	790 000	..	7 250 000	62½
United States Rubber Co.'s Building †	20-story office-building	10 800	236 000	1 628 707	3 090 205	52¾
The Madison Avenue Building †	20-story office-building	14 700	315 000	1 300 000	4 708 000	37½
Auerbach Candy-Factory †	11-story factory	35 100	343 680	915 000	5 200 000	17½
Edgian Building †	17-story lobbies	15 700	244 724	2 000 000	4 225 000	47½

\* See notes on cost on page 1614.

† The editor is greatly indebted to Mr. E. S. Hand and to the architects mentioned for the data for this table ‡ Typical floor-area.

These buildings were designed by the following architects: † Trowbridge & Livingston; † Jardine, Hill & Murdock; † H. P. Knowles; † McKensie, Voorhees & Gmelin; † Cass Gilbert; † Carrère & Hastings; † Charles A. Valentine; † Robert D. Kohn; † Warren & Wetmore.

The Grand Central Station, as a complete terminal, is a very complex structure, but there is a distinct part which contains the passenger-concourse and waiting-rooms, restaurant and other parts that are considered necessary to the traffic. The cubic contents of this part total about 14 000 000 cu ft. Other parts of the building are not considered in the present reference. Some interesting facts as to the main station, only, are:

Cost,* about.....	\$8 000 000
Ground-area above street-level, square feet.....	266 000
Additional station-facilities under street, square feet.....	80 000
Floor-area devoted to station-purposes, square feet.....	1 188 000
Cubic contents, about, cubic feet.....	32 857 800
Steel used in construction, tons.....	35 767
Weight of largest girder used, tons.....	30

**Costs\* of Pre-war Reinforced-Concrete Buildings.††** In judging the cost of a building by CUBICAL CONTENT or by AREAS OF FLOORS the shape of the building in plan should be taken into consideration. A long, narrow building will cost more per cubic or square foot than one more nearly square in plan; and in computing costs by the cubic-foot or square-foot unit prices these conditions as well as the judgment and experience of the architect or engineer who makes the estimates affect the accuracy of the results. The following notes quoted from data furnished by the architects and engineers of the buildings mentioned include useful information relating to costs of some reinforced-concrete buildings of different types, erected in Philadelphia and vicinity (1906-1915).

(1) 'A reinforced-concrete building of the FACTORY-TYPE, erected (1914-15) in the City of Philadelphia. It is a concrete cage, with no brick veneer, four stories in height, no basement, size, 60 by 159 ft, stair-shafts and elevator shafts projecting beyond the building; cubical contents, 603 000 cu ft. The cost, without equipment, was  $7\frac{1}{2}$  cts per cu ft. Drainage is included in the price, but no plumbing, heating, lighting or elevators. The total floor-area of the building is 40 140 sq ft and the cost per square foot is \$1.14 $\frac{1}{2}$ . This is built according to the building laws of Philadelphia.

(2) "A MILL-CONSTRUCTED BUILDING, about the same size as building (1) recently erected in a manufacturing town forty miles from Philadelphia. It is four stories in height and has a part-basement, a wing 30 by 40 ft, and a one-story boiler-room and engine-room. The total cubical contents are 524 160 cu ft, and the cost,  $6\frac{1}{2}$  cts per cu ft. The total floor-area is 37 900 sq ft, and the cost, \$0.85 $\frac{1}{2}$  per sq ft. This is without power, heat, or light. There are a few plumbing-fixtures in this building.

"In comparing the costs of the two buildings, it must be borne in mind that one is located forty miles from Philadelphia, and was not erected under the rigid building laws that are in force there. It is usually possible to erect a building of any type at less expense outside of Philadelphia than in that city and this can probably be said of any city where there are no state building codes.

(3) "A MILL-CONSTRUCTED BUILDING, three stories in height, erected in 1906 in Camden, N. J., and having 575 044 cu ft. It cost 7 cents per cu ft. It has 38 912 sq ft of floor-area, at a cost of \$1.04 per sq ft. This price is without power, heat, light, or elevators, but includes some plumbing.

(4) "The new municipal REPAIR-SHOP of the City of Philadelphia. This is a reinforced-concrete building with brick veneer of an ornamental type, and cost  $9\frac{1}{2}$  cts per cu ft for 1 080 591 cu ft or \$1.74 per sq ft for 57 323 sq ft of total

\* See notes on costs on page 1614. Prices given must be at least doubled (1920).

† Valuable data on this subject have been furnished the Editor by Ballinger & Perdue the architects and engineers of the five reinforced-concrete buildings described.

‡ See, also, page 1613.

er-area. This is without plumbing, power, heat, light, or elevators. The extremely high cost per square foot for this building is due to the fact that the crane run-way takes up a considerable portion of the building, so that a floor is omitted where the crane is placed, and the floor-area accordingly reduced.

5) "The new building for the AUTOMOBILE CLUB of Philadelphia. This is a three-story building, of reinforced-concrete cage-construction, and contains 11 966 cu ft, at a cost of 10½ cts per cu ft. The total floor-area is 90 602 sq ft, costing \$1.54 per sq ft. This is without power, heat, light, or any equipment, but includes plumbing. The shape of this building favors economy of construction, as it is nearly square in plan."

In summing up the conclusions arrived at in regard to the average costs of reinforced buildings, E. G. Perrot states \* that the cost can best be considered by classifying them under three general heads:

- 1) Warehouses and manufactories. Cost, from 8 to 11 cts per cu ft.
- 2) Stores and loft-buildings. Cost, from 11 to 17 cts per cu ft.
- 3) Miscellaneous buildings, such as school-houses, hospitals, etc. Cost from 17 to 20 cts per cu ft.

**Cost of Mills and Factories Built on the Slow-Burning Principle.**  
For data relating to total and unit costs of buildings of this type, see Chapter II, pages 802 to 810.

### Percentages of Cost of Items of Construction in Fire-Proof Buildings

The tables† on the following six pages show, on pages 1620 to 1625, the DIVISION OF THE COSTS of fire-proof buildings among the different materials and items of the construction, the data having been furnished the compiler by architects and builders in the cities mentioned in the tables. Each column of figures in the tables gives the data for an individual building, except the values for New York City, in the second, third and fifth columns, which show the averages for a large number of buildings. The tables on the first four pages include only buildings approximating closely the standard specifications of the National Board of Fire Underwriters. The tables show that the foundations and steel frames, the only parts little damaged in conflagrations, represent, approximately, only 25% of the entire sound value of a building. For example, in the tables on the first four pages, the average cost of all the foundations is 6.5%, while the average cost of the steel frames is 17.88%. The tables show, also, on pages 1624 and 1625 the percentages of cost of the classified items of construction of eight buildings damaged by the Baltimore conflagration (1904), the averages of these eight buildings being given in the last column.

\* See "Comparative Costs of Reinforced Concrete Buildings," by E. G. Perrot, in Proceedings of the National Association of Cement Users, Vol. V, 1909. See, also, notes on costs on page 1614.

† The tables on the first four pages were compiled by F. J. T. Stewart, Continental Insurance Company, and those on the last two pages by the Baltimore Committee of the National Board of Fire Underwriters. All are reproduced, by permission, from J. K. Zeitag's Fire Prevention and Fire Protection. Those parts of the Baltimore tables which gave the proportion of fire-damage to sound value of the various items have been omitted as this article of the Pocket-Book deals more especially with original costs.

Classified construction	New York			Chicago			Baltimore								
	Otes	Hofes	W.H.	Otes	Hofes	Merc	Otes	Hofes	Otes	Hofes	Otes	Hofes	Otes	Hofes	
Height, in stories	10	..	..	30 3	34 8	32 3	..	14	23 6	11	12	7	8	10	7
Cost, cents per cubic foot *	..	..	..	4 4	2 34	3 67	..	6.00	10 74	3 62	4 37	7 25	..	..	..
Foundations	..	..	..	..	..	..	..	..	..	1 22	1 25	2 07	..	..	4 3
ing	..	..	..	..	..	..	..	..	..	1 06	1 06	..	..	..	4 3
l concrete	..	..	..	..	..	..	..	..	..	4 4	0 74	5	..	..	..
e pier-caps	..	..	..	..	..	..	..	..	..	..	0 65	..	..	..	..
Steel frames	24.0	18 4	16 0	22.90	36 3	10.70	14.0	11.86	10 6	13 6	14 34	10 52	10.5	11.4	17 5
Material	..	..	..	..	..	..	..	..	..	..	11 79	..	..	..	..
Erection	..	..	..	..	..	..	..	..	..	..	1.7	..	..	..	..
Shop-drawings	..	..	..	..	..	..	..	..	..	..	0 49	..	..	..	..
Painting	..	..	..	..	..	..	..	..	..	..	0 24	..	..	..	..
Tearing	..	..	..	..	..	..	..	..	..	..	0.32	..	..	..	..
Masonry	26 96	26 2	31 5	20 70	32 5	26 31	27 06	22 3	38 5	27 6	28 5	34 15	30 15	31.31	37 2
Brick, common	..	..	..	..	..	..	..	..	..	10 1	6 59	11 21	..	..	29 0
Brick, faced or pressed	..	..	..	..	..	..	..	..	..	..	1 82	1 26	..	..	8.98
Brick, enameled	..	..	..	..	..	..	..	..	..	..	0.86	..	..	..	13 5
ing and pointing	..	..	..	..	..	..	..	..	..	..	0 21	..	..	..	..
..	1.41	..	..	2 06	..	10.04	..	5 76	..	4 34	7 61	5.07	3.9	2 5	3 5
..	2.75	..	..	1 50	..	10.30	..	..	..	2 55	4 22	9 34	4.05	7 4	8.7
..	..	..	..	10 90	..	..	..	..	..	..	..	..	..	0 83	9 4
x furring	..	..	..	..	..	..	..	..	..	0 77	..	..	..	1 8	..
Floor-arches, roof, etc.	..	..	..	..	..	11.06	9 16	5 8	..	3 87	4 73	3 68	6.8	6.6	6 6
Cinder-concrete filling over arches	..	..	..	..	..	1.06	1 30	1.24	..	0 57	0 58	0 49	..	..	6.
Partitions	..	..	..	..	..	..	..	..	..	1 56	1.88	3 1	..	..	..
Partitions, cleaning and wrecking	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..
Safety-deposit vaults	..	..	..	..	..	..	..	..	..	..	..	..	..	..	..
Miscellaneous scaffolding and wrecking	..	..	..	..	..	..	..	..	..	..	..	..	7 6	..	5.16
New buildings masonry	48 40	..	..	4 12	7 2	9 6	..	..	..	..	..	..	7.0	11.79	9.2

The figures opposite each item represent percentages of total cost of building

	New York										Chicago										Baltimore																			
	20	65	21	2	12	0	20	89	11	25	24	46	24	54	25	04	23	2	20	8	2	19	18	24	54	15	06	18	69	26	71	15	23	22	23	12	69			
Elevator-plant.....	5	70					5	28			4	65	7	81	5	48					0	85		7	6	7	68	8	15	5	5	68	3	8	7	7	4	02		
Plumbing.....	3	49					4	16			6	58	5	90	6	19							3	26	3	55	2	61	4	13	3	5	3	7	3	4	3	36		
Heating-system.....	5	85					5	85					0	67	5	88							4	6	7	06	3	54	4	2	3	6	2	2	6	7	4	15		
Boiler-plant.....														1	92	1	86					0	85								1	9								
Lighting-system, wiring and fixtures.....	5	37					5	6			3	82	2	76									2	54	5	05	1	38	2	03	1	9	1	6	3		1	10		
Dynamoes, switchboards, etc.....														3	34																2	18								
Fixtures.....													0	32	1	24							0	7	0	49			1	05	0	65								
Mail-chute.....	0	24									0	24	0	06	0	13							0	48	0	27	0	28	0	18			0	33	0	43				
Filter-plant.....																									0	44														
Refrigerating-plant.....																													0	93										
.....																															1	9								
Flash-signals and indicators.....											0	24	0	29	0	32					0	56								0	61		3	6						
Furniture.....																														0	54		5	4						
Ventilation.....											9	43	4	80	0	60																								
Trim and finish.....	28	40	20	8	33	25	22	26	14	75	24	44	29	45	35	28	27	7	18	3			36	06	27	56	22	81	36	20	28	78	36	61	26	89	25	04		
Carpentry, rough.....											8	90	6	53	8	54					2	86		2	03	2	59	0	22	10	9	9	8	5	4	7	9	1	6	
Carpentry, finish.....	20	50					10						1	88								5	27	4	31	0	51										5	7		
Hardware, rough.....											0	96	1	70	1	5						0	32	0	29	1	7			0	83		0	64	0	9	1	16	1	95
Hardware, finish.....											5	02	4	17	7	61							0	74	0	88	5	1	0	83								2	8	
Marble.....	2	83					9	85														0	25	6	74	7	11	1	42	10	5	5	4	10	1	6	2			
Mosaic.....	1	25									1	03	1	32	3	37							0	14				1	09					1	2			0	89	
Glass.....																							1	44	9			1	13	1	4	7	5	1	4					
Slate.....																																								
Plastering.....	3	82					2	41			2	97	3	68	2	35						2	94	3	05	2	96	2	9	4	21	3	7	2	7	1	4			
Presco.....											1	84	3	49	1	78						0	88																	
Paint and varnish.....											1	64	2	05	1	39					0	30	2	00	1	34	1	45	2	9	1	6	1	4	2	9	1	5		
Office-partitions (wood and glass).....											1	09	2	58	6	19						2	65																	
Ornamental iron.....											1	00	2	05	2	55						9	70	5	87	4	62	6	4	5	0	10	5	5	5	6	8			
Skylights and sheet metal.....											1	00	2	05	2	55					0	96	0	71	1	22	1	54	0	37	0	63	0	83	0	53	2	4		
Office-grill.....																						0	5					0	19				1	2						

## Estimating the Cost of Buildings

## Part

[illegible]





## Estimating the Cost of Buildings

## Part

[illegible]

Classified construction	Percentage of total cost of building								Average for eight buildings
	Union Trust Building	Calvert Building	Herald Building	Continental Building	Equitable Building	Mer Nat Bank Building	Maryland Trust Building	C & P Tel Co Building	
and fixtures . . . . .	2 54	5.05	1.38	2 03	1 9	1 6	3	1.16	1 9
, etc. . . . .					1 9				2 33
	0.7	0.49		1 05	2 18				2 18
	0.48	0.27	0.28	0 18	0.65	0.33	0.43		0.72
		0.44							0.32
				0 93					0.44
Sales									0.93
Vault-doors and safe-doors					1 9				1 9
Flash-signals and indicators				0 63		3 6			2 11
Turkish baths				0 54					0.54
Furniture					0 68				0.68
Piping, high pressure . . . . .					5 4				5 4
					0 70				0 70
Trim and finish	36.06	27.96	22.83	36.20	28.78	36.63	26.89	23.04	29.99
Carpentry, rough . . . . .	2 03	2.99	0.22	10.9	9 8	5 4	7 9	1.6	5.05
Carpentry, finish . . . . .	5.27	4.31	0.51					5.7	3.94
Hardware, rough . . . . .	0.32	0.29	1.7		0.64	0.9	1.16	1.95	0.99
Hardware, finish . . . . .	0.74	0.88	5.1	0.83					1.88
Marble . . . . .	6.74	7.11	1.42	10.5	5 4	10.1	6.2	2.8	6.28
Mosaic . . . . .	0.14		1.99			1.2			1.11
Glass . . . . .	1.44	9	1.13	1.4	7.5	1.4		0.89	1.23
Slate . . . . .									
Plastering . . . . .	2.94	3.05	2.96	2.9	4.21	3.7	2.7	1.4	2.98
Presco . . . . .	0.88								0.88
Paint and varnish . . . . .	2.60	1.34	1.45	2.9	1.6	1.4	2.9	1.5	1.88
Office partitions (wood and glass)	2.65								2.65
Ornamental iron . . . . .	9.70	5.87	4.62	6.4	5.0	10.5	5.5	6.8	6.79
Skylights and sheet metal . . . . .	0.71	1.22	1.54	0.37	0.63	0.83	0.53	2.4	1.02
Office-grill . . . . .	0.5		0.19			1.2			0.63
General expenses . . . . .	1.83	1.92		5.17	4.31	0.36	11.2	6.94	4.33
Miscellaneous . . . . .	1.83	1.92		0.27	0.67	0.36	10	1.94	2.43
Architects' fees, etc. . . . .				4.9	1.82			5.0	3.91

Costs \* of Different Kinds of Work per Cubic Foot of Building

Some estimates † have been made by F. W. Fitzpatrick showing the proportionate COST OF THE DIFFERENT BRANCHES OF WORK which go to make up a completed building. Believing that these data will be found useful in making up approximate estimates, Mr. Kidder obtained permission to use them in the Pocket-Book. The following figures represent the actual cost of a TEN-STORY OFFICE-BUILDING, 60 by 130 ft in plan, built in the Middle West, a first-class fire-proof structure, with two street-fronts faced with granite and resting on a pile foundation.

Kind of work	Per cubic foot of entire building, cents	Kind of work	Per cubic foot of entire building, cents
Foundations.....	1¾	Heating.....	1¼
Steel framing.....	2½	Plumbing.....	½
Granite and all masonry..	11½	Elevators.....	1
Cornice, roofs and skylights.....	¾	Stairs, scenic structural framing, "making ends meet," lamp-fixtures, etc. What might be called a fair amount for "contingencies" in such a building, including lesser items not mentioned here but grouped together.....	42½
Fire-proof floors.....	¾	Architect's fee.....	1½
Partitions, tile.....	¾		
All plastering and stucco..	1¼		
Elevator-fronts and all ornamental metalwork....	2		
Marblework.....	3½		
Hardware.....	¾		
Joiners' work.....	1½		
Glass.....	5½		
Painting and varnishing...	¾		
Electric wiring.....	¾		
		Total.....	34½

The Chicago post-office building, containing 12 000 000 cu ft and of monumental character and finish; cost,\* in some of its items, as follows:

Kind of work	Per cubic foot of entire building, cents	Kind of work	Per cubic foot of entire building, cents
Foundations.....	1¾	Ornamental metalwork....	2¼
Steel framing.....	2½	Marble.....	5½
Granite and masonry.....	13½	Plumbing.....	½
Fire-proof floors.....	¾	Heating.....	1¼
Plaster, plain and ornamental.....	1¾		

It will be noticed that the relative cost of several of these items is the same as in the office-building. The total cost \* of this building was 42 ½ cts per cu ft.

\* These pre-war figures must be increased from 50% to 100%.  
† "Fireproof," March, 1903.

## Cost \* of Buildings per Square Foot

**One-Story Buildings of Large Area**, such as exposition-buildings, etc., may be estimated almost as accurately by the square foot of ground covered as the cubic foot of building, as there are few or no interior partitions, and usually no plastering or interior finish.

**Iron and Steel Buildings.** "Roughly speaking, the cost of one-story iron and steel buildings, complete, is, for sheds and storage-houses, from 40 to 60 cts per sq ft of ground, and for such buildings as machine-shops, foundries, and electric-light plants, that are provided with traveling cranes, the cost is from 60 to 100 cts per sq ft of ground covered." †

**Structural Steel.** For estimates of cost of structural steel for buildings, see pages 1204 to 1207.

**Wooden and Brick Mills and Warehouses.** See Chapter XXII, pages 810 to 810.

**Exposition-Buildings.** The cost ‡ of the World's Fair buildings (Chicago, 1893) per square foot of ground covered, including sculpture and decoration, are as follows:

Manufactures and Liberal Arts Building.....	\$1.39
Transportation Building.....	1.08
Electricity Building.....	1.69
Machinery Hall.....	2.12
Agricultural Building.....	1.44
Administration Building.....	9.18
Horticultural Building.....	1.41
Mines and Mining Building.....	1.04
Fisheries Building.....	2.35
Forestry Building.....	0.75

**Cost \* of Structures for the St. Louis Exposition (1904).** The following prices were issued by Isaac S. Taylor, at that time Director of Works, of the

Building	Dimensions, ft	Area, acres	Total cost	Cost, sq ft
Art Pavilions, each.....	161×346	1.42 }	\$967 833.90	\$5.45
Government Building Annex.....	144×423	3.14 }		
Government Building.....	106×150	0.41	39 388.99	2.48
Government Fisheries.....	200×736	3.86	328 980.00	2.23
Mines and Metallurgy.....	136×136	0.42	45 000.00	2.43
Liberal Arts.....	525×750	9.08	488 848.50	1.24
Education and Social Economy.....	525×750	8.80	471 820.95	1.20
Manufactures.....	525×758	7.70	323 950.75	0.81
Electricity.....	525×1 200	13.47	711 510.00	1.13
Dried Industries.....	525×758	6.67	408 531.57	1.03
Machinery.....	525×1 200	10.28	704 067.96	1.12
Team, Gas and Fuel.....	525×1 000	9.48	509 110.50	0.97
Transportation.....	301×326½	2.25	135 480.00	1.38
Horticulture.....	525×1 300	15.70	674 853.42	0.99
Agriculture.....	374×782	5.42	225 342.27	0.77
Forestry, Fish and Game.....	500×1 600	18.62	520 491.07	0.52
Festival Hall.....	300×600	4.07	168 883.38	0.94
	195 in diameter, exclusive of annex	1.09	215 899.00	.....

These pre-war prices must be increased from 50% to 100%.  
Given by E. C. Chankland, chief engineer.

† H. G. Tyrell.

World's Fair, showing the area and cost of the principal exhibition-buildings. The total area of twenty-two buildings was 123.51 acres, and the total cost was \$6 939 992.26. The cost was for the bare buildings, and did not include structural or other decorations, or the architects' compensation.

**Recent Exposition Buildings.** The cost of buildings of this class erected since 1904, shows a pretty general increase up to 1914, with considerable variations in the rate of change, of from 1 to 2% per year. Increase since 1904 would be from 50 to 100%.

**Cost \* of United States Government Buildings.** There was published in 1900, by the United States Treasury Department, a history of the buildings of the United States, giving their cost, and in 1902, there was published † a list of 287 buildings, giving the cost per cubic foot, the material used for the walls and the date of erection. There was also published, in 1911, by the Committee on Public Buildings and Grounds of the United States Senate, a list of sites and plans for public buildings, giving data of much value in relation to the cost of public buildings, their cubical contents and their cost per cubic foot, including buildings erected from 1816 to 1910. "As a rule, these buildings have cost more per cubic foot than private buildings, so that their cost can always be used as a guide, except for government buildings." ‡

**Unit Prices \* per Cubic Foot for Recent Government Buildings of the Same Type. §** The data included in the following paragraphs relate to buildings erected before or in process of construction in 1914. They are of certain FIXED TYPES and in different parts of the United States. The buildings are post-office buildings and the location, brief description of the general construction, ground-area covered, cubical contents and comparative rates per cubic foot are given. The buildings are grouped under five different types, and the VARIATIONS IN COSTS PER CUBIC FOOT of similar or identical buildings in each type, located in different sections of the country, are shown. Following each of the five types is a list of buildings of various sizes and descriptions showing variations in the cubic-foot rates. The conclusions arrived at and summarized at the end of the lists, include a table which shows what was considered by the office of the Supervising Architect to be a fair DIFFERENCE IN COST OF BUILDINGS OF THE SAME TYPE in different sections of the United States. It was considered also, by that office, that the method of estimating the cost of buildings by the CUBIC-FOOT UNIT PRICE is productive of very uncertain results, inasmuch as there are many variable conditions entering into the construction of buildings located in different localities. The principal items affecting the cost of different types of buildings are:

- (1) Labor; rates and efficiency.
- (2) Materials; quality and freight-rates.
- (3) Season; time of year when building is constructed.
- (4) Contractors; finances, ability, equipment, overhead expenses and margin of profit desired.

\* Pre-war figures must be increased from 50% to 100%.

† Published in the Architects' and Builders' Magazine, Aug., 1902, and in the Architect, April, 1902.

‡ F. E. Kidder, in previous editions of the Pocket-Book.

§ The information relating to the cost of recent government buildings of certain types was furnished by J. W. Ginder, Superintendent of the Computing Division, Office of the Supervising Architect, by permission of Mr. O. Wenderoth, the Supervising Architect, through whose courtesy and valuable assistance the editor is able to present the data referred to. The editor regrets that limited space prevents the reproduction of the carefully prepared and most interesting series of photographs of the plans, elevations and sections of the government buildings, the costs of which per cubic foot are discussed.

**Location;** as to supply-centers, distance from railroads, and facilities for building materials.

**Variations in Unit Costs \* of Identical Buildings in Different Localities**  
 In order to compare the costs of identical buildings, with slight modification, the following are given as examples, to show the variance in different localities.

**Type 1.** Post-office buildings at Grenada, Miss., Bennettsville, S. C., Covington, Tenn., and Burlington, N. J.

**Description.** Main building, two stories and basement; rear projection, one story and basement; non-fire-proof construction throughout; brick facing; stone trim; wooden cornice; slate-covered gable roof, with dormers over two-story portion, and flat, composition roof over one-story portion.

Area and contents		
Ground-area.....		3 825 sq ft
Cubical contents.....		138 210 cu ft
Rate per cubic foot *		
Location	Non-fire-proof	First floor, fire-proof
Grenada, Miss.....	\$0.322	\$0.327
Covington, Tenn.....	0.315	0.324
Bennettsville, S. C.....	0.304	0.309
Burlington, N. J.....	0.293	0.298

**Type 2.** Post-office buildings at Winchester, Tenn., McPherson, Kan., and Longview, Tex.

**Description.** Main building, two stories; rear projection, one story; partly excavated basement; non-fire-proof construction throughout; brick facing; stone trim; wooden cornice and pilasters at front entrance; slate-covered gable roof with dormers over two-story portion, and flat, composition roof over one-story portion.

Area and contents		
Ground-area.....		3 825 sq ft
Cubical contents.....		138 210 cu ft
Rate per cubic foot *		
Location	Non-fire-proof	First floor, fire-proof
Winchester, Tenn.....	\$0.344	\$0.350
McPherson, Kan.....	0.346	0.351
Longview, Tex.....	0.332	0.337

\* These pre-war figures must be increased from 50 to 100%.

**Type 3.** Post-office buildings at Cookeville, Tenn., and Jackson, Ky.

Description. Three-story-and-basement building; stone-faced to top course over water-table; selected, common-brick facing and ornamental terra-cotta trim; composition and slate roof and non-fire-proof construction, except the first floor.

Area and contents	
Ground-area.....	4 942 sq ft
Cubical contents.....	290 300 cu ft
Rate per cubic foot *	
Cookeville, Tenn.....	\$0.275
Jackson, Ky.....	0.269

**Type 4.** Post-office buildings at Garden City, Kan., and Lake City, Minn. (identical buildings).

Description. One-story-and-basement, brick-faced building, with stone water-table course and trimmings and ornamental terra-cotta cornice, architrave and parapet-coping; non-fire-proof construction, except the first floor; composition roof.

Area and contents	
Ground-area.....	3 888 sq ft
Cubical contents.....	141 456 cu ft
Rate per cubic foot *	
Garden City, Kan.....	\$0.405
Lake City, Minn.....	0.341

**Type 5.** Post-office buildings at Abilene, Kan., and Bellefontaine, Ohio.

Description. One story and basement; stone facing; granite steps, and tin roof; fire-proof construction, except roof.

Area and contents	
Ground-area.....	5 000 sq ft
Cubical contents.....	183 000 cu ft
Rate per cubic foot *	
Abilene, Kan.....	\$0.359
Bellefontaine, Ohio.....	0.367

**Buildings of Various Sizes and Descriptions.** The following list is of buildings of various sizes and descriptions throughout the country and shows the variance in the cubic-foot rate.

\* These pre-war figures must be increased from 50 to 100%.



Post-office building at New Rochelle, N. Y.

Description. This building is of an irregular plan; two-story and basement; center pavilion; sides and rear one-story and basement; clearstory over workroom; stone facing to first-floor level; brick facing above this point, with terra-cotta trim and cornice; composition roof; fire-proof construction.

Ground-area.....	7 512 sq ft
Cubical contents.....	258 900 cu ft
Rate per cubic foot *	\$0.259

Post-office building at Mobile, Ala.

Description. Front portion, two stories, and rear portion, one story over workroom. Only a small portion of basement excavated for heating-plant. Front building faced with limestone and rear second story portion with ornamental terra-cotta. Fire-proof construction; long and short spans, and concrete joists with terra-cotta fillers; copper deck and Spanish-tile roofs.

Ground-area.....	18 054 sq ft
Cubical contents.....	670 476 cu ft
Rate per cubic foot *	\$0.341

Post-office building at Muskogee, Okla.

Description. A four-story-and-basement building. Granite to the first-floor line, stone-faced above (except in interior court, which is brick); terra-cotta cresting at roof; copper roofing and fire-proof construction throughout. Standard types of concrete and terra-cotta floor-construction. Monumental in design. Corinthian colonnade at entrance. Eight heavy bronze standards. Six flights of marble stairs. Entire lobby of marble, and ornamental plaster-work in lobby and court-room.

Ground-area.....	20 400 sq ft
Cubical contents.....	1 326 612 cu ft
Rate per cubic foot *	\$0.43

Post-office building at New Bedford, Mass.

Description. One story, basement and mezzanine with clearstory over rear portion; granite facing, except clearstory, which is faced with terra-cotta; main roof of composition; clearstory roof of copper; fire-proof construction.

Ground-area.....	27 750 sq ft
Cubical contents.....	1 080 690 cu ft
Rate per cubic foot *	\$0.323

Post-office building at Newark, Ohio.

Description. Two-story, basement and unfinished attic. The workroom extends through two stories. Offices in second story over balance of building. Fire-proof construction throughout. Terra-cotta floors, ceilings, roofs, partitions, furring, etc. Exterior faced with pink granite to the first-floor level and white marble above, including cornice, parapet, etc. Flat tin roof; bronze grilles at first and second-story windows on front of building. Cast-iron grilles at first-story and basement-windows on sides and rear; bronze-faced post-office screens, desks, revolving doors, vestibules, etc., and drawn-bronze covered windows, window-frames, doors, etc., in lobby. Caen-stone cornice and coffered ceiling in lobby. Bronze and marble stairs to second story.

\* These pre-war figures must be increased from 50 to 100%.

Ground-area.....	6 912 sq ft
Cubical contents.....	369 640 cu ft
Rate per cubic foot *	\$0.487

Post-office building at Minot, N. D.

Description. Three-story-and-basement building; fire-proof, except roof, which is plank on steel beams; stone facing to second-story window-sills; brick facing above, with stone cornice, parapet-coping, etc.

Ground-area.....	6 700 sq ft
Cubical contents.....	427 300 cu ft
Rate per cubic foot *	\$0.328

Post-office building at McAlester, Okla.

Description. Three stories and basement; fire-proof, except roof; terra-cotta floors, etc.; suspended ceilings; stone facing to second-floor level; brick facing above, with stone trim; cornice and balustrade; tin roof.

Ground-area.....	7 482 sq ft
Cubical contents.....	394 765 cu ft
Rate per cubic foot *	\$0.38

Post-office building at North Tonawanda, N. Y.

Description. The building has two stories and basement; granite to first-floor line; brick-faced above with stone trimming and slate roof; fire-proof construction to and including the second floor.

Ground-area.....	5 475 sq ft
Cubical contents.....	276 320 cu ft
Rate per cubic foot *	\$0.289

**Conclusions Regarding Variations in Unit Costs.** In the foregoing unit costs, the APPROACH-WORK, such as walks, platforms, terraces, etc., is included. This, in some cases, is quite expensive, and is generally from 5 to 10 per cent of the entire cost of the building. In federal buildings, there are many requirements not met with in the ordinary mercantile buildings, and the permanent character of the building necessitates all materials, workmanship and construction to be of the very best in each case. This is guaranteed by iron-clad specifications, long-time guarantees for several items of the work, and permanent government inspection. The office of the supervising architect has determined that the RELATIVE INCREASE in cost of buildings throughout the country over the cost in the Mississippi Valley district was about as follows, taking the Mississippi Valley district, as a BASE, at 100%, and the labor and market conditions which prevailed in October, 1914.

	Per cent
Mississippi Valley district.....	100
New England (except Maine).....	110
Maine.....	115
Southern States .....	100
Northwest Mountain district.....	130
Southwest Mountain district.....	120
Pacific Coast.....	125

\* These pre-war figures must be increased from 50 to 100%.

In the grouping of districts, the Mississippi Valley district is intended to cover the Middle States as far east as Ohio and Pennsylvania, and the states, generally, bordering on the western bank of the Mississippi River. This is intended to be a part of the country in which the LOWEST PRICES have been obtained. The other districts represent the approximate greater cost for buildings than that in the Mississippi Valley or Middle States, and is intended to represent the DIFFERENCE IN COST AT ANY TIME; but is not intended to represent difference in cost at different periods.

**Illustration of Variation in Cost \* of Buildings of Identical Area and Contents.** The following notes are taken from photographs of drawings and data accompanying them.† The drawings were for a Post-Office building at Menomonie, Wis. This building contains 4 770 sq ft of ground-area, and the cubical contents are 147 570 cu ft. The contract was awarded (1913) \$45 380, or at the rate of \$0.308 per cu ft. It is a one-story-and-basement building, faced with brick, with stone water-table, brick parapet and tin and composition roof. The first floor, only, is fire-proof. Proposals were opened (1914) for a Post-Office building at Uvalde, Tex. This building, except for the slight modifications, is as nearly like the Menomonie building as it is possible to make it without using the same drawings. The ground-area of the Uvalde building is 4 672 sq ft and the cubical contents, 151 875 cu ft. The work in connection with the approaches is practically the same as that at Menomonie. If these buildings had been erected in the same town, it does not appear that there would have been any difference in the costs, but the lowest proposal received for the Uvalde building was \$56 400, or at the rate of \$0.371 per cu ft. This comparison of the amounts for these two buildings further illustrates the unreliability of any universal application of the cubic-foot rate in determining costs of buildings, and also shows that the difference in cost of construction of buildings in different sections of the country varies considerably.

**Cost per Cubic Foot of Some Important Federal Buildings.** The following tabulations contain additional unit costs and other data for public buildings.

**Cost \* per Cubic Foot of Some Important Federal Buildings.**

Location and building	Cost per cubic foot, cents *
New York, N. Y., Custom-House (completed 1908).....	74
Cleveland, Ohio, Post-Office, Custom-House and Court-House.....	68
San Francisco, Cal., New Post-Office and Court-House (completed 1906).....	66
Denver, Col., new Mint (completed 1905).....	65
San Francisco, Cal., Subtreasury Building (estimated).....	60
Baltimore, Md., new Custom-House (completed 1908).....	55
Washington, D. C., Senate Office-Building.....	50
Salt Lake City, Utah, Post-Office (completed 1905).....	47
Indianapolis, Ind., new Post-Office (completed 1906).....	46
Philadelphia, Pa., new Mint (completed 1901).....	45
Washington, D. C., National Museum Building.....	43
Washington, D. C., Agricultural Buildings (portions completed).....	40
Washington, D. C., House Office-Building.....	36

These pre-war figures must be increased from 50 to 100%.

These photographs of plans, elevations and sections, together with many others, and accompanying explanations and data, were furnished the editor by J. W. Ginder, Superintendent of the Computing Division, Office of the Supervising Architect, by permission of Mr. O. Wenderoth, the Supervising Architect (1914), and have been of great assistance in the presentation of notes on the costs of buildings.

## Cost \* per Cubic Foot and per Square Foot of Some New Public Buildings

Location	Facing	Cost	Contents, cu ft	Area, sq ft	Cost	
					Cu ft	Sq ft
Bangor, Me.....	Granite	\$271 297	793 720	15 600	\$0.342	\$7.4
Augusta, Ga.....	Marble	288 800	576 000	11 000	0.500	26.2
South Chicago, Ill.....	Stone	132 702	377 668	11 000	0.390	12.8
Long Branch, N. J.....	Limestone	95 200	256 210	6 470	0.373	14.5
Plymouth, Mass.....	Brick	81 532	256 210	6 470	0.318	12.5
Piqua, Ohio.....	Limestone	116 689	448 300	9 984	0.360	11.7
New Bedford, Mass...	Granite	295 051	1 080 000	21 732	0.300	13.5

## Depreciation of Buildings †

**Discounts from Values of New Buildings.** The figures given on the preceding pages are for new buildings. To ascertain their value at any time subsequent to their erection, a discount from the value when new should be made as follows:

	Per cent per year
Brick, occupied by owner.....	1 to 1½
Brick, occupied by tenant.....	1½ to 1¾
Frame, occupied by owner.....	2 to 2½
Frame, occupied by tenant.....	2½ to 3

If built of long-leaf yellow pine, or of spruce from the New England States, add from 20 to 30%, or if of short-leaf yellow pine, add from 40 to 50% to the values. If of redwood or cedar from the Pacific Coast, use about one-half of these estimates, which are for white pine or white pine with oak framing-timber. These figures for depreciation are to include buildings in which ordinary repairs have been made. If extraordinary repairs have been made, the discount should not be so heavy. Good judgment must be used in estimating the amount of depreciation in buildings.

**The Depreciation of Mill-Buildings.** The annual depreciation of a mill building of slow-burning construction varies from 1 to 1½%, while the depreciation of a reinforced-concrete factory-building is relatively much less, since it is confined entirely to such details as windows, doors, roofing, etc.

**The Wear and Tear of Building Materials.** At the tenth annual meeting of the Fire Underwriters' Association of the Northwest, held at Chicago, September, 1879, Mr. A. W. Spalding read a paper on the wear and tear of building materials and tabulated the results of his investigations in the following form:

\* These pre-war figures must be increased from 50 to 100%.

† Reproduced, by permission, from the Journal of the Society of Constructors of Federal Buildings, September, 1914, through the courtesy of C. R. Marsh, Editor. Publications of the Society of Constructors of Federal Buildings. This Journal, published monthly, contains data of much interest to architects and builders.

‡ From Tiffany's Estimate of Depreciation, used by the United States Government.

Material in building	Frame dwelling		Brick dwelling (shingle roof)		Frame store		Brick store (shingle roof)	
	Average life years	Depreciation per annum %	Average life years	Depreciation per annum %	Average life years	Depreciation per annum %	Average life years	Depreciation per annum %
Brick.....	....	.....	75	1½	....	.....	66	1½
Plastering.....	20	5	30	3½	16	6	30	3½
Painting, outside...	5	20	7	14	5	20	6	16
Painting, inside....	7	14	7	14	5	20	6	16
Shingles.....	16	6	16	6	16	6	16	6
Cornices.....	40	2½	40	2½	30	3½	40	2½
Weather-boarding..	30	3½	....	.....	30	3½	....	.....
Sheathing.....	50	2	50	2	40	2½	50	2
Flooring.....	20	5	20	5	13	8	13	8
Doors, complete....	30	3½	30	3½	25	4	30	3½
Windows, complete.	30	3½	30	3½	25	4	30	3½
Stairs and newels...	30	3½	30	3½	20	5	20	5
Rails.....	40	2½	40	2½	30	3½	30	3½
Inside blinds.....	30	3½	30	3½	30	3½	30	3½
Building hardware.	20	5	20	5	13	8	13	8
Piazas and porches	20	5	20	5	20	5	20	5
Outside blinds.....	16	6	16	6	16	6	16	6
Walls and first-floor joists.....	25	4	40	2½	25	4	30	3½
Dimension-lumber.	50	2	75	1½	40	2½	66	1½

These figures represent the averages deduced from the replies made by eighty-five competent builders unconnected with fire-insurance companies in twenty-five cities and towns of the eleven Western States.

## THE QUANTITY SYSTEM \*

**Explanation of the System.** The QUANTITY SYSTEM is not, as some persons are supposed, merely the taking off of a list of items by one person probably with uncertain accuracy, for some other person's use. It means the careful measurement by a disinterested expert specially trained in this kind of work, that is, a QUANTITY SURVEYOR. This specialist proceeds in a manner quite different from that of the average contractor. He follows a certain recognized order and system in taking off quantities, abstracting and billing, with a view to eliminating errors. He uses certain uniform standards of measurements and expressions well understood by bidders. His checking and rechecking methods ensure accuracy must be studied to be appreciated by those to whom the quantity system is unknown. A record is kept of every item, however small, giving a money-value. These items are classified and arranged, each under proper trade or department, in methodical order. Guess-work methods

The quantity "system" which is not merely a survey of items, has been systematically located since 1891 by G. Alexander Wright, A.I.A., 354 Pine Street, San Francisco, is the founder of the movement to adapt the Quantity System to American building practice. It has attracted much attention among contractors, architects, and engineers. In course of time this system of estimating must be adopted, as it stands for a square dealing between owner and contractor. The movement in aid of this work is purely a practical one, an honest effort to bring about better methods.

are unknown to the quantity surveyor, while his accuracy and attention to even small details is worthy of comment. Every bidder figures from a copy of the surveyor's quantities furnished to each one, with (if desired) the plans and specifications. The surveyor who does this work is a professional man similar to the engineer or the architect. He should, in fact, have, and he usually has had, experience in these professions, and in addition, a practical experience acquired in the field in actual contact with and superintendence of construction work.

**Method of Procedure.** Such a surveyor, in taking off quantities from an architect's or engineer's drawings, readily detects any discrepancies due to haste, preparation or other cause. The attention of the architect or engineer is called to such matters by the quantity surveyor, as he goes on with his work. Detected in this way, all uncertainties are at once corrected and adjusted, so that by the time the drawings and specifications reach contractors, everything has been made plain and accurate and the possibility of error in quantities can therefore be disregarded. The resulting document, the BILL OF QUANTITIES is then either printed or otherwise reproduced, and a facsimile copy supplied free of cost to each bidder who inserts his unit price opposite each item and in an hour or two furnishes up the money-cost in dollars and cents. This is really all that a contractor should be expected to do (for nothing). The BILL OF QUANTITIES contains everything the contractor is called upon to perform and furnish, in order to complete his contract. In short, the bid becomes a proposal to do a certain FIXED QUANTITY of work, no more and no less. This, briefly, is the main underlying principle of the QUANTITY SYSTEM: a definite quantity of work for a definite price, and the elimination of every condition which now compels bidders to take chances.

**The Present Unsatisfactory Conditions.** Most architects are familiar with the wasteful, unsatisfactory methods followed to-day. They injure both parties to a contract because of bidders' mistakes in figuring, accuracy being so often sacrificed for speed. While wonderful strides in methods of construction have been made, no attention has been given to STANDARDIZING METHODS of measuring builders' work, and so both owner and contractor suffer. As a result of the movement in aid of better methods (initiated in San Francisco in 1891) more conservatism, and a closer adherence to business principles are being preferred in place of gambling methods of estimating. Architects and engineers who now permit an unduly low bidder to take a contract are causing trouble every time.

**Use of the Quantity System in Other Countries.** The principle of payment by measurement is based upon equity and square dealing. On a large scale it is used in England, Ireland, Scotland, France, Germany, Australia, and South Africa, and to some extent in the United States and Canada. It is a significant fact, that in no instance in which this measurement system has been once established, has it ever been abandoned for the former haphazard methods.

**Advantages Claimed for the Quantity System.** The following are the advantages claimed for the system:

(1) An immense saving of time and money now wasted by bidders, each doing the same thing, going over the same ground, and each arriving at a different result.

(2) Safer bids, as the work to be performed is clearly written out in a bill of quantities, which can be the essence of the contract.

- (3) No expense to the bidder; the owner pays for the quantities knowingly, the owners pay now, but this fact is not brought to their attention, and it does not occur to them. The percentage added to a bidder's net cost is not profit, a certain portion being absorbed in overhead charges, including cost estimating, which, of course, is ultimately borne by owners.
- (4) Saving of disputes arising from ambiguities, oversights, and even errors, causing extra claims more or less just, but usually vexatious, and sometimes embarrassing.
- (5) Better opportunities for the competent bidder, as the bidders all work on the same basis and price from the same basis.
- (6) Better work and greater harmony. If no part of the work is omitted there is less reason to skin the work, a proceeding which produces friction, or worse.
- (7) Misunderstandings are reduced. The bill of quantities states clearly what is intended, and is a sort of clearing-house for the drawings and specifications.
- (8) Neither party can obtain an advantage over the other on quantity or description of work.
- (9) No disputes with subbidders, it being clearly stated what each trade is to furnish.
- (10) Contractors have no figuring of quantities to do and can therefore devote more time to buildings in hand and save profits now lost for want of their personal supervision.
- (11) Fewer inferior contractors as lowest bidders.
- (12) Fewer extras, which are usually a trouble to all concerned.
- (13) The architect or engineer has the assistance by collaboration of the professional quantity surveyor, who is available, also, for preliminary figures. This advance-information, now so often furnished by a prospective bidder, states undesirable obligations.
- (14) No change or reorganizing of architects' offices is entailed. Much tail-work now involved in receiving bids could be taken care of in the quantity surveyor's office.
- (15) The drawings and specifications having been previously made as complete as possible, subsequent inconvenience to contractors and foremen on the job, and inquiries at the architects' offices for explanations become unnecessary. The BILL OF QUANTITIES gives detailed information which cannot be well given by drawings.

**Adaptation to American Practice.** In the United States any such universal system must conform to American needs and sentiment, and be a practical system. For many reasons it would be unpractical to follow the English practice. The principles it stands for can, however, be accepted and applied everywhere with great advantage.

## DIMENSIONS AND DATA USEFUL IN THE PREPARATION OF ARCHITECTS' DRAWINGS AND SPECIFICATIONS \*

**Dimensions for Furniture.** For the convenience of draughtsmen when signing furniture or providing space for a special article the following dimensions are given: †

\* See, also, the additional tables with more detailed and classified lists.

† Many of these dimensions were first contributed to the American Architect of November 10, 1894, by Alvin C. Nye.

**Chairs and Seats.** The average figures taken from a variety of good chairs are: Height of the seat above the floor, 18 in; depth of the seat, 19 in; the height of the back above the floor, 38 in. Usually the seat increases in depth and decreases in height, while the back is higher and slopes more. Twenty inches inside is a comfortable depth for a seat of moderate size. Chair-arms are 9 in above the seat. The slope of the back should not be more than one-third the depth of the seat. A LOUNGE is 6 ft long and about 30 in wide.

Tables vary in shape and size almost as much as chairs. Writing-tables and dining-tables are made 2 ft 5 in high, and the type of sideboard called a *carver's table* is made 3 ft high to the principal shelf; but tables for general use are 2 ft 6 in high. DINING-TABLES are made from 3 ft 6 in to 4 ft wide and to extend from 12 ft to 16 ft by means of slides within the frame. This frame should not be so deep as to interfere with the knees of any one sitting at the table; that is, there must be about 2 ft clear space between it and the floor. The smallest size practicable for the KNEE-HOLES of desks and library-tables is 2 ft high by 1 ft 5 in wide, the width to be increased as much as possible.

Bedsteads are classed as SINGLE, THREE-QUARTERS, and DOUBLE. A single bed is from 3 to 4 ft wide inside; a three-quarter bed, from 4 ft to 4 ft 6 in; a double bed, 5 ft. Bedsteads are from 6 ft 6 in to 6 ft 8 in long inside. Footboards are from 2 ft 6 in to 3 ft 6 in and headboards from 5 ft to 6 ft 6 in high. Single beds for dormitories are often made only 2 ft 8 in wide.

Bureaus vary in shape and size to such an extent that it is almost impossible to say that any dimension is fixed. Convenient sizes are: body, 3 ft 5 in wide, 1 ft 6 in deep and 2 ft 6 in high; or 4 ft wide, 1 ft 8 in deep and 3 ft high.

Commodore is 1 ft 6 in square on the top and 2 ft 6 in high.

Chiffoniers are about 3 ft wide, 1 ft 8 in deep and 4 ft 4 in high.

Cheval-Glasses are made, if large, 6 ft 4 in high and 3 ft 2 in wide. If small, 5 ft high and 1 ft 8 in wide. If medium, 5 ft 6 in high and 2 ft wide.

Wash-Stands of large sizes are 3 ft long, 1 ft 6 in wide and 2 ft 7 in high. Smaller sizes are from 2 ft 4 in to 2 ft 8 in long.

Wardrobes may be 8 ft high, 2 ft deep and 4 ft 6 in wide; or 6 ft 9 in high, 1 ft 5 in deep and 3 ft wide.

Sideboards may be from 4 to 6 ft long and from 20 in to 2 ft 2 in deep.

Upright Pianos vary from 4 ft 10 in to 5 ft 6 in in length, from 4 to 4 ft 9 in in height and are about 2 ft 4 in deep over all.

Miniature and Baby-Grand Pianos vary from 5 ft 10 in to 6 ft in length, and are about 4 ft 10 in in width.

Parlor-Grand Pianos vary from 5½ ft to 6 ft 10 in in length, and are about 4 ft 10 in in width.

Concert-Grand Pianos are about 8 ft 10 in in length and 5 ft in width.

Billiard-Tables (Collender), 4 by 8 ft, 4 ft 2 in by 9 ft and 5 by 10 ft. Size of room required 13 by 17 ft, 14 by 18 ft and 15 by 20 ft, respectively.

**Classified Tables \* of Furniture-Dimensions.** The following more detailed and classified tables of average dimensions of furniture are added to those already given and are taken from recent data furnished by manufacturers.

\* These additional tables were compiled by E. S. Hand, and much of this data is taken from several editions of the Pocket-Book has been taken, by permission, from the valuable treatise on Furniture Designing and Draughting, by A. C. Nye.



niture. While some of these measurements vary slightly from the dimensions given in the preceding paragraphs they represent average dimensions of furniture as made at the present time.

## Dimensions of Tables

Kind of table	Length	Width	Height	Remarks
Bedroom-table.....	31	22	29	.....
Bedroom-table.....	18	18	30	Commode
Bijou-table.....	30	22	30	.....
Carving-table.....	42	20	36	.....
Dressing-table.....	36	20	30	.....
Extension table.....	66	66	30	Round
Extension table.....	54	54	30	Square
Library-table.....	51	41	30	Oval
Library-table.....	42	27	29	.....
Library-table.....	54	34	29	.....
Library-table.....	60	36	29	.....
Tea-table.....	13	13	20	Round
	18	18	24	Square
	23	17	29	Upper shelf
	30	23	18	Lower shelf

All dimensions are in inches. Heights are from the floor.

## Dimensions of Chairs

Kind of chair	Height	Seat-width,		Depth, outside	Back		Arms, height from floor
		Front	Back		Height	Slope	
Bedroom-chair.....	18	16	13	17	34	3½	.....
Baby's high chair *....	20	14	12	13½	37	3	27
Cheek-chair †.....	17	29	25	27½	44	4½	.....
Chip-chair.....	17	22	17½	17	39	.....	.....
Chip-chair.....	18	22	17	17¾	38	.....	.....
Dining-chair.....	20	24	22	22	45	2½	26½
Dining-chair.....	20	19	17	19	43	2	.....
Dining-chair.....	19	19	17	18	38½	1½	.....
Dining-chair.....	18	20	15	15	36	2	.....
Easy chair.....	17	33	28	24 ¶	43	5	21
Easy chair †.....	17	27	25	27½	41	6½	26
Hepplewhite chair.....	18	21½	17	17	34½	2	27
Parlor-chair ‡.....	16½	24	19½	18¾	36	4	25¾
Parlor-chair †.....	14	21	21	18 ¶	29	.....	.....
Parlor-chair †.....	18	26½	22½	26½	37	4	25
Parlor-chair §.....	18	20	13	19	36	3	23
Piano-bench.....	20	40	.....	15	.....	.....	.....
Reception-chair   .....	17	21	19	21	30	2	.....
Rocking-chair.....	16	23½	20½	19½	41	2	24
Roundabout chair....	18	18	18	18	29½	0	28½
Rubens chair.....	20½	17½	17½	15	40	0	.....
Slipper-chair.....	12	18	15	17	28	3	.....

\* Foot rest 12 in above floor. † Overstuffed. ‡ French cane seat and back.

§ Wooden arm and back. || Upholstered seat. ¶ Depth inside.

All dimensions are in inches. Heights are from the floor. •The slope of the back is measured at the seat-level to a perpendicular through the highest point of the back.

## Dimensions of Sofas

Kind of sofa	Height	Seat-width		Depth, outside	Back		Area, height from floor
		Front	Back		Height	Slope	
Small.....	18	43	40	21	32½	3	24
Extra large.....	16	78	76	36	29	2	25
Ordinary sofa.....	15	54	51	24	34	5½	24
Lounge.....	17	68	68	28	35	2½	29
Lounge.....	17	57	57	29	23	12	34

All dimensions are in inches. Heights are from the floor. The slope of the back is measured at the seat-level to a perpendicular through the highest point of the back.

## Dimensions of Case-Work

Kind of case-work	Body			Remarks
	Width	Depth	Height	
Bureau.....	45	20½	36½	.....
Bureau.....	51	23	37½	.....
Bureau.....	48	22	36½	.....
Bureau.....	54	20	42	.....
Bookkeeper's desk.....	60	33	42	.....
Bookkeeper's desk.....	60	32	44	Deck, 11 in; slope, 22 in
Chiffonier.....	39	20	48	.....
Chiffonier.....	36	20	51	.....
Cheval-glass.....	25	.....	65	.....
Commode.....	16	16	31	.....
Sideboard.....	84	32	30	.....
Wardrobe.....	36	19	69	.....
Wardrobe.....	54	24	96	.....

All dimensions are in inches. Heights are from the floor. The slope of the back is measured at the seat-level to a perpendicular through the highest point of the back.

## Dimensions of Bedsteads

Kind of bed	Inside		Heights		Width, side rail	Height, bottom of side rail
	Length	Width	Foot	Head		
Single bed.....	78	42	40	62	9½	9½
Single bed.....	78	42	41	60	10	10
Double bed.....	78	58½	42	63	11	10½
Double bed.....	78	56	36	67	13	9½

All dimensions are in inches. Heights are from the floor.

**Dimensions of Plumbing-Fixtures. Enameled-Iron Bath-Tubs.** Standard sizes for roll-rim baths with sloping ends are: nominal lengths, 4 ft, 4½ ft, 5 ft, 5½ ft and 6 ft; width over all, from 30 to 34 in. Specially narrow tubs are made from 25 to 29 in wide. The actual length over rim is usually 1 or 2 in more than the nominal length, and 2 in will include an ordinary overflow-pipe.

**Wash-Basins.** Crockery basins, to go with marble slabs, are made round and oval. Round bowls are made 10, 12, 13, 14 and 16 in in diam, measured from the outside of the rim. Oval bowls, 14 by 17 in, 15 by 19 in and 16 by 21 in. The 12 and 14-in round, and 15 by 19-in oval, are commonly used.

**Marble Basin-Slabs** may be 20 by 24 in, 20 by 30 in, 22 by 28 in, or 24 by 30 in, the last being a very common size. They can be made any size, to order. They should be  $1\frac{1}{4}$  in thick, countersunk on top, and should have molded edges where exposed.

**Corner-Slabs** are commonly made 21 by 21 in and 24 by 24 in. Marble backs are usually 8 or 10 in high, and sometimes 12 in.

**Enameled-Iron Wash-Basins or Lavatories** made in one piece: common sizes are 16 by 20 in, 11 by 14-in basin; 18 by 21-in, 11 by 15 in basin; 18 by 24 in, 12 by 15-in basin; back,  $10\frac{1}{2}$  in high. The smallest-sized wash-basin is 13 in wide at the back.

**Corner-Basins**,  $12\frac{1}{2}$  by  $12\frac{1}{2}$  in, 12-in round basin; 15 by 15 in, 11 by 14-in basin; 16 by 16 in, 11 by 14-in basin; 19 by 19 in, 11 by 15-in basin. The standard height of wash-basins is 2 ft 6 in from the floor.

**Foot-Baths**, enameled iron, roll-rim, are  $22\frac{1}{2}$  by 19 in; width, including fittings, 1 ft 11 in; height 17 in; depth inside, 11 in.

**Seat-Baths**, enameled iron, average about 32 in long over fittings, and 27 in wide.

**Water-Closets.** The dimensions of water-closet bowls vary considerably, the following being about an average: width of bowl over all, 13 in; depth from wall to front of seat, 23 in; height from floor to seat, 17 in; width of seat, from 15 to 16 in. Closets with low-down tanks measure about 28 in from front of seat to wall. The distance from center of outlet-opening to the walls, or the **ROUGHING-IN** dimensions, are given in manufacturers' catalogues, as they vary with different closets. The smallest space permissible for water-closet compartments, where doors open out, is 2 ft 4 in by 4 ft. If the doors open in, the compartment should be 3 by 5 ft.

**Closet-Ranges**, used in schools and factories, are made 24, 27 and 30 in, center to center of partitions. For graded schools, 24 in is ample, and for factories, 27 in. The range usually occupies a space 28 in in depth, if set against wall.

**Urinal-Stalls** should be from 24 to 27 in, center to center of partitions; depth of partitions, 20 or 22 in; of ends, 2 ft; of bottom slab, 2 ft; height of partitions, from 4 ft 6 in to 5 ft 6 in.

**Kitchen-Sinks** of cast iron are made in a great variety of sizes, those most commonly used being 16 by 24 in, 18 by 30 in, 18 by 36 in, 20 by 30 in and 20 by 36 in; 24 by 50 in is the largest size for enameled sinks. The depth inside, for the sizes given, is 6 in. Plain cast-iron sinks are made as large as 32 by 56 in, or 36 by 78 in. Steel sinks are made in all of the above sizes up to 20 by 40 in.

**Porcelain Sinks.** Common sizes of porcelain sinks are 20 by 30 in, 23 by 36 in and 24 by 42 in.

**Cast-Iron Slop-Sinks**, common sizes, are 16 by 16 in, 16 by 20 in, 18 by 22 in and 20 by 24 in; 12 in deep.

**Copper Pantry-Sinks.** Common sizes are 12 by 18 in, 14 by 20 in and 16 by 24 in.

**Laundry-Tubs** of slate or soapstone are commonly made 2 ft wide over all, and 16 in deep. Lengths over all, two-part tubs, 4 ft and 4 ft 6 in; three-

part tubs, 6 ft, 6 ft 6 in and 7 ft. Earthen and porcelain tubs come separately, and are connected as required. The dimensions of each tub are 2 ft or 2 ft 7½ in in length, 2 ft 1½ in in width and 15 in in depth, inside. The length required for two 2-ft tubs is 4 ft 1 in; for three tubs, 6 ft 2 in; and for four tubs 8 ft 3 in. Wolff's roll-rim enameled-iron wash-tubs are 55 in over all, for two tubs, and 82 in for three tubs.

**Range-Boilers** are 12 in diameter for 30-gal, 14 in for 40-gal, 16 in for 50-gal and 63-gal, 22 in for 100-gal and 120-gal boilers.

**Dimensions of Carriages. Covered Buggy (Goddard).** Length over all, 14 ft; width, 5 ft; height, 7 ft 4 in. Will turn in space from 14 to 20 ft square, according to skill.

**Coupé.** Length over all, 18 ft; width, 6 ft; height, 6 ft 6 in.

**Buggy (Piano-Box).** Length over all, 14 ft; width, 4 ft 10 in.

**Landau.** Length over all, 19 ft 6 in; width, 6 ft 3 in; height, 6 ft 3 in; length of pole, 8 ft 0 in.

**Stanhope Gig, Two Wheels.** Length over all, 10 ft 6 in; width, 5 ft 8 in; height, 7 ft 6 in.

**Victoria.** Length, without pole, 9 ft 6 in; length of pole, 8 ft; width over all, 5 ft 4 in.

**Light Brougham.** Length, without pole or shaft, 9 to 11 ft; width over all, 5 ft 4 in; height, 6 ft 4 in.

**Automobiles.** Length, from 11 to 19 (average 16) ft; width, 6 ft; height, 7 ft.

**Dimensions and Weight of Fire-Engines.** From measurements of different fire-engines belonging to the city of Boston, it was found that the greatest length, including pole, was 22 ft 6 in. The widths varied from 5 ft to 5 ft 11 in, the average height being 8 ft 8 in. The average weight (computed from 9 engines), 8 000 lb; the greatest weight, 9 420 lb and the least, 4 780 lb.

**Dimensions and Weight of Hose-Carriages.** Extreme length with horse, 19 ft 6 in, without horse, 17 ft 6 in; width, from 5 ft 9 in to 7 ft; height, from 5 ft 8 in to 7 ft; average weight (computed from 11 carriages), 2 943 lb; greatest weight, 3 500; least weight, 2 120.

**Dimensions and Weight of Ladder-Wagons.** Length of truck, 35 ft; total length, with ladders on, 45 ft; width, 6 ft 2 in; average weight (computed from 12 wagons), 6 660 lb; greatest weight, 8 800; least, 4 350.

**Dimensions of Locomotives and Cars.** The dimensions of locomotives and freight-cars vary considerably, but the following will cover those in common use:

**Locomotives.** From 15 ft 4 in to 15 ft 10 in to top of stack from top of rail; extreme width of cab, 10 ft 2 in. Doors to admit locomotives should be from 12 to 13 ft wide and 18 ft high.

**Furniture-Cars** are 14 ft 1 in, from top of track to top of brake-staff; floor, 3 ft 8 in from track; extreme width, 9 ft 10 in.

**Stock-Cars,** 13 ft 5 in, from top of track to top of brake-staff; floor, 4 ft from track; extreme width, 9 ft 8 in.

**Refrigerator-Cars,** 14 ft 6 in, from top of track to top of brake-staff; floor, 4 ft from track; extreme width, 9 ft 7 in.

**Ordinary Freight-Cars** are about 13 ft high to top of brake-staff and 9 ft 4 in in extreme width. The height of floor of freight-cars varies from 3 ft 8 in to 4 ft above top of track for STANDARD-GAUGE, and from 3 ft to 3 ft 6 in for NARROW-GAUGE cars. Standard-gauge, 4 ft 8½ in.

**Passenger-Coaches** vary from 14 to 16 ft in height and from 10 to 11 ft in width. Doors to admit cars should give at least 12 in clearance on each side, and 2 ft overhead.

**Street Trolley-Cars** are about 8 ft 6 in wide for the car proper, and the steps project about 8 in. Height from track to top of coach, 11 ft 6 in; the trolley-end is 18 in higher. The length varies, up to 42 ft. Trucks for a 41 ft 6 in car are about 24 ft apart. Wheel-bases, 4 ft center to center. Radius of short-curve in Denver, Colo., 35 ft to midway between rails.

**The Gauge** of a railroad track is the distance between the inner sides of the heads of the two rails. The STANDARD GAUGE is 4 ft 8½ in.

**Capacity of Freight-Cars. Car-Loads.** The capacity of freight-cars, and the minimum car-loads, vary so greatly that no accurate general information can be given. For heavy freight, 25 tons is an average load; for light freight, from 12 to 15 tons; for household goods, 10 tons is about the minimum; for coal, 15 tons is about a minimum load; for cement, 20 tons. The minimum car-load, to obtain car-load rates, varies with different roads, and also with the rate made; a low rate is usually made on the basis of a big load. Thirty tons is a good load for heavy freight, and 40 tons is about the maximum, except for special cars.

**Miscellaneous Dimensions. Horse-Stalls.** Width, from 3 ft 10 in to 4 ft or else 5 ft or over; length, 9 ft. The width should never be between 4 ft and 5 ft, as a horse is liable to cast himself.

**Dimensions of Standard Bowling-Alleys.\*** For ONE PAIR OF ALLEYS: Room necessary, 83 ft over all; 11 ft 6 in wide, 60 ft from foul-line to head pin, 3 ft from pins to back of alley, 4 ft for pin-pit, 8 in deep in front, 6 in in back; alleys, maple flooring, should extend on and beyond the foul-line 12 ft, and then come back, making a 16-ft approach to the foul-line for the player to run to deliver ball. For ONE ALLEY: Same length, 83 ft; width, 6 ft ¾ in; closer dimensions; beds 42 in, gutters 9 in, division-pieces 2¾ in, ball-return 9¾ in.

	In		In
ONE ALLEY: Ball-return.....	9¾	ONE PAIR OF ALLEYS: Ball-return	9¾
First-division piece.....	2¾	First-division piece.....	2¾
Gutter.....	9	Gutter.....	9
Bed.....	42	Bed.....	42
Gutter.....	9	Gutter.....	9
Second-division piece.....	2¾	Second-division piece.....	2¾
	<hr/>		<hr/>
6 ft ¾ in =	75¼	6 ft ¾ in =	75¼

To the 75¼ in of the PAIR OF ALLEYS, should be added

Gutter.....	9
Bed.....	42
Gutter.....	9
First-division piece.....	2¾
	<hr/>
	138

Additional room should be provided for the bowlers and spectators as these dimensions are for the alleys only.

**Dimensions of Drawings for Patents** (United States). 10 by 15 in, with border-line 1 in inside all around.

Dimensions furnished by The Brunswick-Balke-Collender Company, New York City.

**Dimensions of a Barrel.** Diameter of head, 17 in; diameter at bung, 13 in; length, 28 in; volume, 7 680 cu in.

**Miscellaneous Memoranda. Weight of Men and Women.** The average weight per person of twenty thousand men and women weighed at Boston, Mass in 1864, was, men, 141½ lb; women, 124½ lb.

**Wooden Flagpoles.** For a flagpole, extending from 30 to 60 ft above roof, the following proportions give satisfactory results: The diameter at roof should be ⅓ the height above the roof, and the top diameter one-half lower. To profile the pole, divide the height into quarters; make the diameter at the first quarter above the roof, fifteen-sixteenths of the lower diameter; at the second quarter, seven-eighths, and at the third quarter, three-quarters the lower diameter.\*

**Steel Flagpoles.†** The Department of Education, City of New York, has abandoned the use of wooden flagpoles and is using steel flagpoles. For an ordinary building, 60 ft in height above the curb, a pole 43½ ft in height is used, which is sufficient for the tackle of a large or post-flag, for the reason that the parapets are very low. Each pole is required to be fitted complete with a cap of iron, galvanized, revolving truck, mounted on crucible-steel pins, the cap and truck, also, being of galvanized iron. The truck is fitted with two 4-in bronze sheaves on Tobin-bronze pins, surmounted with an 8-in 20-oz copper ball, acid-cleaned and painted with four coats of the best English weather-proof sizing, and covered with XXXX leaf-gold. One or more field-joints are permitted in the length of the pole, which are determined according to standard details, the bands being secured to the male tube, and both edges of the female band and the shoe being machine-beveled to insure a perfect fit. The female tube is drilled and secured to the male shoe with tap-screws of sufficient strength to carry the upper section of the pole, and the ends of the screws are upset. The exposed ends of the female tube are chamfered and caulked tight. A steel collar or band, to receive the copper flashing, is secured to the pole and band just above the roof-lines.

**Dimensions of Schoolrooms, Boston Schools.‡** The sizes of the rooms in the Boston school-houses, as adopted by the school board, are, for grammar schools, 28 by 32 ft in plan by 13 ft 6 in in height; for primary schools, 24 by 32 by 12 ft. This accommodates 56 scholars per room, in each grade, allowing 216 cu ft per scholar in the grammar schools, and 165 cu ft in the primary grades. A width of 27 ft is very satisfactory for schoolrooms, and is commonly adopted because it permits of the use of 28-ft joists, without waste.

**Heights of Blackboards in Schoolrooms.‡** The heights from floor to top of chalk-rail should be about as follows:

For third and fourth grades,	chalk-rail. . . . .	2 ft 1 in from floor
For fifth grade,	chalk-rail. . . . .	2 ft 2½ in from floor
For sixth grade,	chalk-rail. . . . .	2 ft 4 in from floor
For seventh and eighth grades,	chalk-rail. . . . .	2 ft 6 in from floor

Slate blackboards are made 3 ft 6 in, 4 ft and 4 ft 6 in high, 4 ft being a very common and satisfactory height.

\* The Building Trades Pocketbook.

† From data compiled by E. S. Hand from notes furnished by C. B. J. Snyder, Superintendent of School Buildings, New York City.

‡ F. E. Kidder, in previous editions.

## Sizes of Seats and Desks for Schools and Academies \*

Number of desk	Age of scholar	Height of seat or chair	Height of desk (next scholar)	Space occupied by desk and seat (back to back)	
	years	in	in	ft	in
0	16 to 18	16½	29½	2	9
1	14 to 16	15½	28	2	9
2	12 to 14	15½	27½	2	8
3	10 to 12	14½	26½	2	7
4	8 to 10	13½	25½	2	5
5	7 to 8	12½	24	2	4
6	6 to 7	11½	22½	2	3
7	5 to 6	10½	21	2	2
.....	4 to 5	9½	19	2	0

Desks for two scholars are 3 ft 10 in long, and for a single scholar, 2 ft long.

Isles are from 2 ft to 2 ft 4 in wide, according to age of scholars and size of room.

## Additional Data† on School-Houses

**Sizes of Rooms.** The Department of Education, New York City, has adopted, for the dimensions of the schoolrooms, the German standard of 22 by 30 ft in plan by 14 ft in height, with unilateral lighting. These dimensions are used for all grades of elementary schools, the sittings being on the basis of 15 sq ft of floor-space per pupil. Good light cannot be had on desks which are placed at a greater distance from the windows than one and one-half times the height of the top of the upper sash from the floor.

## Sizes of Seats and Desks for Elementary and High Schools

Number of desk	Age of scholar	Height ‡ of seat or chair	Height ‡ of desk	Space§ occupied by desk and seat (back to back)
	years	in	in	in
0	16 to 18	17	31	32
1	14 to 16	16	30	32
2	12 to 14	15	28	31
3	10 to 12	14	26	30
4	8 to 10	13	24	29½
5	7 to 8	12	23	27
6	6 to 7	11	22	27
7	5 to 6	10	20½	26

**Blackboards.** For first and second-year scholars the chalk-rail is placed 2 ft above the floor, and the boards are 4 ft high. This allows the smaller children

F. E. Kidder, in previous editions.

From data compiled by E. S. Hand from notes furnished by C. B. J. Snyder, Superintendent of School Buildings, New York City.

Heights are measured as follows: From the floor to the top of ink-well strips of desks, and from floor to top of front edge of seats, and should not vary more than ½ in from the heights given in this table.

Isles have a minimum width of 18 in for the lower grades and 22 in for the upper grades.

If chairs are used, this distance must be increased from 1½ to 2 in.





Number of treads or risers

Story-height or horizontal length of run

Haight of riser or width of tread, inches	Number of treads or risers										Story-height or horizontal length of run																	
	15	16	17	18	19	20	21	22	23	24	25	26	27	ft	in	ft	in	ft	in	ft	in	ft	in	ft	in	ft	in	
6	7	8	8	9	9	10	10	11	11	12	12	13	13	6	0	12	0	12	0	12	0	12	0	13	0	13	0	
6 1/4	7	8	8	9	9	10	10	11	11	12	12	13	13	6 1/4	0 1/4	12 1/4	6 1/4	12 1/4	6 1/4	12 1/4	6 1/4	12 1/4	6 1/4	13 1/4	0 1/4	13 1/4	6 1/4	
6 1/2	8	8	9	9	10	10	11	11	12	12	13	13	14	6 1/2	1	13	0	13	0	13	0	13	0	14	1	14	7 1/2	
6 3/4	8	9	9	10	10	11	11	12	12	13	13	14	14	6 3/4	7 1/2	13 1/2	6 3/4	13 1/2	6 3/4	13 1/2	6 3/4	13 1/2	14	7 1/2	14	2 1/4		
7	8	9	9	10	11	11	12	12	13	13	14	14	15	7	2	14	0	14	0	14	0	14	7	15	2	15	9	
7 1/8	8	9	10	10	11	11	12	12	13	13	14	14	15	7 1/8	5 1/4	14 1/4	3	14 1/4	3	14 1/4	3	14 1/4	15	5 1/4	15	5 1/4	16	0 3/8
7 1/4	9	9	10	10	11	12	12	13	13	14	14	15	15	7 1/4	8 1/2	14 1/2	6	14 1/2	6	14 1/2	6	14 1/2	15	8 1/2	15	8 1/2	16	3 3/4
7 3/8	9	9	10	10	11	12	12	13	13	14	14	15	15	7 3/8	9 1/4	15 1/4	9	15 1/4	9	15 1/4	9	15 1/4	16	9 1/4	16	9 1/4	16	7 1/8
7 1/2	9	10	10	11	11	12	12	13	13	14	14	15	15	7 1/2	10	15 1/2	10	15 1/2	10	15 1/2	10	15 1/2	16	10	16	10	16	10 1/2
7 5/8	9	10	10	11	12	12	13	13	14	14	15	15	16	7 5/8	11 1/4	16 1/4	11 1/4	16 1/4	11 1/4	16 1/4	11 1/4	16 1/4	16	11 1/4	17	11 1/4	17	17 1/8
7 3/4	9	10	10	11	12	12	13	13	14	14	15	15	16	7 3/4	12 1/2	16 1/2	12 1/2	16 1/2	12 1/2	16 1/2	12 1/2	16 1/2	16	12 1/2	17	12 1/2	17	5 1/4
7 7/8	9	10	11	11	12	12	13	13	14	14	15	15	16	7 7/8	13 1/4	17 1/4	13 1/4	17 1/4	13 1/4	17 1/4	13 1/4	17 1/4	16	13 1/4	17	13 1/4	17	8 5/8
8	10	10	11	12	12	13	13	14	14	15	15	16	16	8	4	17 1/2	14	17 1/2	14	17 1/2	14	17 1/2	17	14	18	14	18	0
8 1/4	10	11	11	12	13	13	14	14	15	15	16	16	17	8 1/4	5 1/4	18 1/4	15 1/4	18 1/4	15 1/4	18 1/4	15 1/4	18 1/4	17	15 1/4	18	15 1/4	18	6 3/4
8 1/2	10	11	12	12	13	14	14	15	15	16	16	17	17	8 1/2	6 1/2	18 1/2	16 1/2	18 1/2	16 1/2	18 1/2	16 1/2	18 1/2	18	16 1/2	19	16 1/2	19	1 1/2
9	11	12	12	13	14	15	15	16	16	17	17	18	18	9	7	19	17	19	17	19	17	19	19	18	19	19	20	3
9 1/8	11	12	13	13	14	15	16	16	17	17	18	18	19	9 1/8	8 1/4	19 1/4	18 1/4	19 1/4	18 1/4	19 1/4	18 1/4	19 1/4	19	18 1/4	20	18 1/4	20	4 1/2
10	12	13	14	14	15	16	17	17	18	18	19	19	20	10	9	20	19	20	19	20	19	20	20	19	21	20	21	6
10 1/4	13	14	15	15	16	17	18	18	19	20	20	21	21	10 1/4	10 1/2	21 1/2	20 1/2	21 1/2	20 1/2	21 1/2	20 1/2	21 1/2	21	20 1/2	22	21 1/2	22	7 1/2
11	13	14	15	16	16	17	18	19	20	20	21	21	22	11	11 1/2	22 1/2	21 1/2	22 1/2	21 1/2	22 1/2	21 1/2	22 1/2	22	21 1/2	23	22 1/2	23	9
11 1/8	13	14	15	16	17	17	18	19	20	21	21	22	22	11 1/8	12 1/4	23 1/4	22 1/4	23 1/4	22 1/4	23 1/4	22 1/4	23 1/4	22	22 1/4	23	23 1/4	24	10 1/2
11 1/4	13	14	15	16	17	18	18	19	20	21	22	22	23	11 1/4	13 1/4	24 1/4	23 1/4	24 1/4	23 1/4	24 1/4	23 1/4	24 1/4	22	23 1/4	23	24 1/4	24	11 1/2
11 1/2	14	15	16	16	17	18	19	20	20	21	22	23	23	11 1/2	14 1/2	25 1/2	24 1/2	25 1/2	24 1/2	25 1/2	24 1/2	25 1/2	23	24 1/2	24	25 1/2	25	12 1/2
12	14	15	16	17	17	18	19	20	21	22	22	23	24	12	15	26	25	26	25	26	25	26	23	25	24	26	26	13 1/2
10 3/4	13	14	15	16	17	18	19	20	21	22	23	23	24	10 3/4	16 1/4	27 1/4	26 1/4	27 1/4	26 1/4	27 1/4	26 1/4	27 1/4	24	26 1/4	25	27 1/4	26	14 1/2
11	14	15	16	17	18	19	20	20	21	22	23	24	24	11	17 1/2	28 1/2	27 1/2	28 1/2	27 1/2	28 1/2	27 1/2	28 1/2	24	27 1/2	25	28 1/2	27	15 1/2
13	16	17	18	19	20	21	22	22	23	24	25	25	26	13	19 1/2	30 1/2	29 1/2	30 1/2	29 1/2	30 1/2	29 1/2	30 1/2	24	29 1/2	26	30 1/2	28	17 1/2
11	14	15	16	17	18	19	20	21	22	23	24	25	26	11	21 1/2	32 1/2	31 1/2	32 1/2	31 1/2	32 1/2	31 1/2	32 1/2	24	31 1/2	27	32 1/2	29	19
13	16	17	18	19	20	21	22	23	24	25	26	27	28	13	23 1/2	34 1/2	33 1/2	34 1/2	33 1/2	34 1/2	33 1/2	34 1/2	26	33 1/2	28	34 1/2	30	23
13	16	17	18	19	20	21	22	23	24	25	26	27	28	13	25 1/2	36 1/2	35 1/2	36 1/2	35 1/2	36 1/2	35 1/2	36 1/2	27	35 1/2	29	36 1/2	31	26
14	17	18	19	20	21	22	23	24	25	26	27	28	29	14	27 1/2	38 1/2	37 1/2	38 1/2	37 1/2	38 1/2	37 1/2	38 1/2	28	37 1/2	30	38 1/2	32	29

\* The editor is indebted to T. Z. Talley for the calculations and arrangement of this table.

to use the lower portion. The upper part of the surface is at a height convenient for the use of the teacher, there being much display-work employed in the lower grades. For scholars in grades from the third to the eighth year, inclusive, and for high schools the chalk-rail is placed  $2\frac{1}{2}$  ft from the floor and the boards at 3 ft 6 in in height.

**Doors and Stairways.** Wardrobes should be entered from the classroom only. Classroom-doors should open into the rooms, so as to afford the teacher control in case of panic. All exit-doors should open out. All stairways should be shut off from corridors by means of self-closing doors, which, together with the stairways and the enclosures, should be of fire-proof materials. Stairways should be of sufficient number to permit of the building being vacated within three minutes from the time a signal is given. This can be effected by allowing a linear width of 4 ft for the first 50 persons and 12 in additional for each 25 persons in excess thereof. No stairway is to be less than 4 ft nor more than 5 ft in width. Exits should be planned so as to provide 15 lin ft for the first 50 persons and 6 in additional for each 100 persons in excess thereof. No stairway should have more than 15 steps in any one flight, changes in direction being effected by a square platform and no winders being used. No stair-door or exit-door should open out over a step. Platforms are to be provided for side doors and are to extend at least 1 ft beyond the edge of the door when standing open.

**Stairs.\*** The **RISE** of a stair is the height from the top of one step to the top of the next. The **TOTAL RISE** is the height from floor to floor. The **RUN** is the horizontal distance from the face of one riser to the face of the next. **RISERS** are the upright boards or other materials forming the faces of the steps, and the **TREADS** are the horizontal pieces or surfaces on which the feet tread. Treads are usually from  $1\frac{1}{4}$  to  $1\frac{3}{4}$  in wider than the run, on account of the **NOSING**. The height of an individual riser or the **RISE** of any stairs is found by dividing the **TOTAL RISE** by the number of risers. The **RUN** of the stairs may be fixed at will unless the space is cramped, but to secure a comfortable stair the run must bear a certain relation to the rise.

**Rules for Dimensions of Treads and Risers.** For ordinary use a rise of from 7 to  $7\frac{1}{2}$  in makes a very comfortable flight of stairs. For schools and for stairs used by children the rise should not exceed 6 in. Stairs having a rise greater than  $7\frac{3}{4}$  in are steep. The width of the run should be determined by the height of the rise; the less the rise the greater should be the run, and *vice versa*. Several rules have been given for proportioning the run to the rise:

- (1) THE SUM OF THE RISE AND RUN should be equal to from 17 to  $17\frac{1}{2}$  in.
- (2) THE SUM OF TWO RISERS AND A TREAD should not be less than 24 nor more than 25 in.
- (3) THE PRODUCT OF THE RISE AND RUN should not be less than 70 nor more than 75.

These rules apply only to stairs with nosings. Stone stairs without nosings should have at least 12-in treads for adults. (See Tables, pages 1646-7.)

**Height of Hand-Rail.** In dwellings, hotels, apartments, etc., the height of the rail should be about 2 ft 6 in above the tread, on a line with the face of the riser. For grand staircases the height may be reduced to 2 ft 4 in. On school stairs the height should be from 2 ft 7 in to 2 ft 9 in. The rail should also be raised over winders. On landings, the height of the rail should be equal to the height of the stair-rail, measured at the center of the tread, the usual height in residences being from 2 ft 8 in to 2 ft 10 in.

\* This subject is quite fully treated in *Building Construction and Superintendence*, Part II, *Carpenters' Work*, by F. E. Kidder.

**Sash-Cords.\*** Until a few years ago, linen or cotton cord only was used for connecting weights with the sashes of double-hung windows, and cord is still more extensively used than either ribbons or chains. For windows of ordinary size a good brand of cord will wear for a long time, and this material will probably never be entirely displaced by metal. "Tests made at the Massachusetts Institute of Technology show that cords wear much longer than chains, though they have less tensile strength. Cords should be smooth and round, so that each strand bears its part of the stress, and well glazed, so that they have a smooth surface and consequently less wear from friction with the wheel of the pulley." It has been found that cord can be braided too hard for durability, yet if it is braided so as to be very flexible it may be so soft that it will stretch and cause great annoyance by permitting the weight to hit the bottom of the weight-box. The architect, however, should always specify the particular BRAND and SIZE of cord to be used, and also the diameter of the pulley. Among the leading brands of sash-cord at present are the Samson Spot,† and the Silver Lake A.‡ These brands are superior to the ordinary braided cords, which are made from inferior yarns to meet the jobbers' requirements for price. In addition to other most excellent qualities, the Samson cord offers an additional advantage that architects will appreciate; it has a colored strand woven through it, which shows spots on the surface and thus enables one to tell at a glance that no other cord has been substituted. The Silver Lake A sash-cord has the name Silver Lake A branded on every foot of cord; but unless the letter A accompanies the name a second grade of cord is denoted. The marking of the cord by color, or any other device, does not alter the quality of the cord. Special marks may be applied to inferior cords as well as to the best. The following numbers should be specified for the different weights of sash-weights:

**Relative Sizes of Sash-Cords, Weights and Pulleys**

Size-number.....	6	7	8	9	10	12
Diameter in inches.....	$\frac{3}{16}$	$\frac{7}{32}$	$\frac{1}{4}$	$\frac{9}{32}$	$\frac{5}{16}$	$\frac{3}{8}$
Feet per pound.....	66	55	44	36	27	20
Suitable for weights in pounds up to.....	5	12	20	30	40	50
Minimum diameter in inches of pulley allowable.....	$1\frac{1}{2}$	$1\frac{3}{4}$	2	$2\frac{1}{4}$	$2\frac{1}{2}$	3

For hanging sashes weighing over 40 lb, only the largest size of Samson or Silver Lake A cord, or some form of sash-chain or sash-ribbon, should be used, and the pulleys should be selected to fit the cord or chain. A guarantee that the cord will last at least twenty years may be had from either of the manufacturers mentioned above. The Samson wire-center sash-cord has recently been put on the market. This is really a metal sash-cord protected by a braided-cotton surface which acts as a noiseless cushion. It is claimed that it harmonizes with the window-finish and that it has greater durability than other sash-cords or metal devices. (See record of tests made at Massachusetts Institute of Technology, page 1651.) The standard color is that of dark mahogany, but this cord is made to order for large buildings in other colors to match the finish.

The following notes, relating to Sash-Cords, Sash-Chains, Sash-Ribbons, Sash-Weights and Sash-Balances, are condensed and revised from articles by Professor Thomas H. Van. in Kidder's Building Construction and Superintendence, Part II, Carpenters' Work.

Manufactured by the Samson Cordage Works, Boston, Mass.

Manufactured by the Silver Lake Company, Boston, Mass.

**Sash-Chains.** Of several styles of sash-chains on the market, the style most largely used is the flat-link chain.\* This chain is made either of steel, or of bronze composed of 95% copper and 5% of tin. For suspending very heavy sash doors and gates, a cable-chain has been extensively used. Star† sash-chain made of bronze-metal. The manufacturers of the Norris sash-pulley claim that a riveted chain that has joints only one way is almost sure to break when even slightly twisted, and that it is better to use two chains of the link-pattern running side by side over the same pulley. The strongest sash-chains are of steel made rust-proof by the hot-galvanizing process, and electro-copperplated to give a bronze finish; and of a bronze-mixture which looks like copper, but is tougher and harder. One firm‡ claims that its galvanized-steel sash-chain is from 11 to 45% stronger than any bronze or copper sash-chain and that it will resist fire for a much longer period. The tensile strength of their chain varies from 475 to 850 lb, according to the weight used.

**Sash-Ribbons.** These are now also extensively used in hanging the sashes in the better class of buildings. The ribbons are made of steel and aluminum, bronze or of some mixture of aluminum, and in  $\frac{3}{8}$ ,  $\frac{1}{2}$ ,  $\frac{5}{8}$ ,  $\frac{3}{4}$  and  $\frac{7}{8}$ -in width. They are claimed to be practically indestructible, but according to one series of tests it would appear that in some cases they do not wear as long as sash-cords or sash-chains. Some people object that the ribbons snap against the pulley stiles, when the sash is raised or lowered, and thus make considerable noise. The  $\frac{3}{8}$ -in ribbon may be used for a sash weighing up to 100 lb and requiring 50-lb weights. For a window 6 ft 10 in high and 3 ft wide, glazed with plate glass, the ribbons with attachments cost about 75 cts. Sash-ribbons are now manufactured by a number of firms who also make the necessary attachments for weight and sash. For the best working of windows hung with ribbons, pulleys of the following sizes should be used:

For sashes weighing not over 40 lb,	2 in
For sashes weighing not over 60 lb,	2½ in
For sashes weighing not over 100 lb,	2½ in
For sashes weighing not over 150 lb,	3 in
For sashes weighing not over 250 lb,	3½ in
For sashes weighing not over 300 lb,	4 in
For sashes weighing not over 350 lb,	4½ in

**Comparative Strength of Sash-Cords and Chains.** The comparative strength and durability of sash-cords and chains have been determined by careful tests, but there is a great variation in both cases, due partly to variation in material, but principally to the relative sizes of the chain and pulley or cord and pulley. The cords or chains may be too light for the weights used, or the pulleys too small in diameter to carry the cord without undue bending. The pulleys may also have too narrow a groove or an uneven groove with sharp edges which cut the cords. The larger the diameter of the pulley, the less the wear.

**Tests § on Wire-Center Sash-Cord and Bronze Sash-Chains.** The cord tested was size No. 8,  $\frac{1}{4}$ -in diam, Samson solid braided cotton cord with steel

\* One type of this kind of sash-chain is manufactured by the Bridgeport Chain Company, Bridgeport, Conn.

† Manufactured by the U. T. Hungerford Brass & Copper Company, New York City.

‡ The Oneida Community, Ltd., Oneida, N. Y.

§ Made at the Massachusetts Institute of Technology, May, 1914, by Professor J. H. Miller.

wire cable center,  $\frac{1}{16}$  in in diam. The chains tested were of two different makes of bronze, size No. 2, purchased in the open market as typical bronze sash-chains, each recommended by a reputable dealer as the proper chain for use with a 25-lb window-weight. The tests for the better of the two chains are those given. Durability-tests were made by raising and lowering a 25-lb weight over a 2-in pulley, each movement corresponding to once opening and shutting a window. The cord was tested over the regular round grooved pulley ordinarily used for cords, and the chains were tested over the combination grooved pulley usually furnished for sash-chains. For the fire-tests the cords or chains were hung through an asbestos box in which a Bunsen flame under pressure was applied to all alike, the temperature being about  $2200^{\circ}$  F. A 25-lb weight was attached in each case to keep the cord or chain under the same tension. The wire-center cord took about twice as long to burn through and wore about seventeen times as long as the bronze chain.

#### Tests on Wire-Center Sash-Cord and Bronze Sash-Chain

Durability-tests		Fire-tests	
Number of lifts before breaking		Length of time before parting	
Bronze chain	Samson wire-center cord	Bronze chain, sec	Samson wire-center cord, sec
34 944	659 892	42.5	78.5
37 486	592 559	40	75.5
37 381	632 230	39	77
32 948	594 114	32	75
40 356	631 286	.....	.....
31 234	577 154	.....	.....
40 790	504 032	.....	.....
27 874	637 796	.....	.....
Average 35 377	Average 603 633	Average 38.4	Average 76.5

**Weights of Sashes and Glass.** In figuring the weights of windows, the weight of the glass may be taken at  $3\frac{1}{2}$  lb per sq ft for plate glass,  $1\frac{1}{2}$  lb for double-strength glass and 1 lb for single-strength glass. For the weight of the wooden sash, add together the height and width, in feet, of each sash, and multiply by 2.1 for  $2\frac{1}{4}$ -in sash, by  $1\frac{3}{4}$  for  $1\frac{3}{4}$ -in sash and by  $1\frac{1}{2}$  for  $1\frac{3}{8}$ -in sash. These values are sufficiently accurate for determining the size of sash-cords and pulleys, but the weights should be determined by weighing each sash after it is glazed, as the weight of the glass varies considerably.

**Iron Sash-Weights.** The weights ordinarily used for balancing windows are made of cast iron, in the form of solid cylinders from  $1\frac{3}{8}$  to  $2\frac{1}{8}$  in in diameter, and from  $7\frac{1}{2}$  to 31 in long, with an eye cast in the upper end of each. The lengths vary with the weights, which are from 2 to 25 lb. Flat weights, which usually are called for in the Philadelphia and some other markets, are from 6 to  $34\frac{1}{2}$  in long, from 2 to 30 lb in weight, and from  $1\frac{1}{4}$  by  $1\frac{5}{8}$  to  $1\frac{5}{8}$  by  $2\frac{1}{4}$  in in cross-section. In ordering sash-weights the number of pounds of each weight, and the sections and lengths of the boxes in which the weights will work, should be given. Ordinary weights have very rough eyes for the sash-cords. There are few manufacturers in the East who make weights with a patent eye that will

not cut the cord. A sectional sash-weight\* made with a well-designed hooking device which has given satisfaction, is said to be one of the best on the market. Usually from three to six sections are required on each side to balance a sash properly. If the hooking-device fails near the top the upper sash cannot be closed and if at the bottom the window cannot be opened. It is then necessary to open the weight-box and rehang the sections before the window can be operated. In theory, sectional weights are ideal; in practice, however, they are not considered as satisfactory as solid weights. The Brown† sectional weights are made  $2\frac{1}{4}$  by  $2\frac{3}{8}$  in and in weights of 6, 7, 8, 9 and 10 lb. They are made of both cast-iron and lead. It frequently occurs after a contract is let, that the glass is changed from double-thick to plate or prism glass. This means increased weight; but the length of the sash-weight cannot be increased and it, therefore, becomes necessary to increase the area of its cross-section. If the weight-box is detailed to take the regular round sash-weight, its general construction will be such that it will take a 2-in round sash-weight, but not a 2-in square sash-weight. This difficulty can be avoided by a little thought at the start. An added depth of  $\frac{1}{4}$  in in the weight-box permits the use of a rectangular cast-iron sash-weight. The Sanborn sectional sash-weight‡ is intended for use in large buildings of heavy construction. Because of the lack of uniformity in the weight of plate glass the required weights of sash-weights cannot be accurately determined previous to the hanging of the sashes. By the use of a sectional sash-weight, combinations of units can be made up to suit the requirements. The units are made square or rectangular in section in order to secure a maximum weight with a minimum length. An opening of 12 in in the side of the pocket is sufficient for hanging the largest unit. These units are manufactured in standard sizes to meet the general conditions found in the building trades.

**Lead Sash-Weights.** It often happens that for wide and low windows the weights if of iron would be so long that they would touch the bottom of the pocket before the bottom sash was fully raised. In such cases lead weights are usually resorted to, lead being 80% heavier than cast iron. By casting the weights square in section, whether of iron or lead, a considerable saving can be made in the lengths. One sash-weight manufacturer§ makes a specialty of compressed-lead sash-weights, with wrought and malleable-iron fastenings, centered so that the weights hang perfectly plumb; and when lead weights are necessary the architect will do well to specify the weights made by this company. These weights are made under hydraulic pressure, by which greater smoothness, solidity and density of metal is secured than is possible by the casting-process. A wrought-iron rod is run through the center, to which are securely attached the malleable-iron fittings. In hanging the sashes the weights for the upper sash should be about  $\frac{1}{2}$  lb heavier than the sash, and for the lower sash,  $\frac{1}{2}$  lb lighter.

**Sash-Balances.** Within a comparatively few years several devices have been patented for balancing sashes by means of springs instead of weights, but the author believes that only one type, known as the SASH-BALANCE, has proved a practical success. The sash-balance consists of a drum on which the ribbon is wound, and which contains a coiled-steel clock-spring, immersed in oil; the spring sustains the weight of the sash. The common type very much resembles in outward appearance the ordinary sash-pulley, and is applied in practically the same way; the ribbons, which are made usually of aluminum-bronze, are

\* Manufactured by E. E. Brown & Company, Philadelphia, Pa.

† Manufactured by E. E. Brown & Company, Philadelphia, Pa.

‡ Manufactured by the Lidgerwood Manufacturing Company, New York City.

§ Raymond Lead Works, Chicago, Ill.

ached to the sashes in the same manner as cords when weights are used. While the sash-balance in its best form works very satisfactorily, it will probably never entirely supplant the weight and axle-pulley for ordinary windows. There are many windows, however, for which sufficient pocket-room for weights cannot be obtained without spoiling the effect desired or narrowing the glass, as in some of the windows, or where it is undesirable to break the frame into the brick jamb. In such cases the sash-balance is almost invaluable. For hanging the glass doors of show-cases, sash-balances are usually preferable to weights. Sash-balances are made in both side and top-patterns, but the former are recommended wherever there is room at the side of the frame for the depth of mortise required. For windows of the sizes usually found in residences, the depth of the sash-balance measured from the face of the pulley-stile will vary from 3 to 4 in; this can be provided for usually by cutting a hole, if necessary, in the masonry studding back of the frame. As sash-balances require only a plank frame, the consequent reduction in the cost of the frame offsets the extra cost of the balance. In remodeling old buildings which have plank frames without weights, sash-balances are found to be a great convenience, since they can easily be inserted in the old frames. An advantage which all spring-balances possess is that they act most strongly when the sash is down, and so enable one to raise a window more readily than if it were hung with weights; while when the sash is up the springs barely suffice to hold it in position, and do not offer resistance to drawing it down. Of the various sash-balances on the market, the Pullman \* and the Caldwell † are the most extensively used, and are undoubtedly valuable. The Pullman Unit sash-balance has been on the market many years and has proved satisfactory. These balances are now made with uniform-size steel-plates for the various weights of sash with which they are to be used, and this makes it possible to have all mortises for the balances cut at the mill, as is now done for the regular cord-pulleys. The Caldwell sash-balance, both top and side-types, is much used by the United States Post Office and Navy Departments. It is used also by the leading car-builders. The springs are made of high-grade cold-rolled tempered-steel wire, a material similar to that used for truck-springs. The manufacturers guarantee these sash-balances for from ten to fifteen years.

**Seating-Space in Churches and Theaters.** The minimum spacing for pews, back to back, is 30 in. This spacing is fairly comfortable for occupants, but is a little cramped for persons passing by others into or out of the pews. A spacing of 32 in is to be preferred, and if there is abundance of room, the spacing may be made 33 in. Anything over 33 in is a waste of room. A space of 34 in in the length of the pew is considered a **SITTING**. ‡

**Opera or Theater-Chairs** are made 19, 20, 21 and 22 in wide, center to center of arms, and in arranging them in rows where the aisles converge, the ends are brought to a line on the aisles by using a few chairs that are either narrower or wider than the standard width. For churches, a standard width of 20 in is at least that is desirable. For theaters, 21 or 22-in chairs are commonly used on the parquet, 20 or 21-in in the dress-circle, and 20 and 19-in in balcony and gallery, although there is no accepted rule in this respect. On account of the difficulty of lifting, opera or theater-chairs may be comfortably spaced 31 in, back to back, and this is the usual spacing in halls and churches. In theaters the chairs are usually set on steps. In the upper gallery these steps should not be more than 30 in wide; in the balcony they are usually made either 30 or 31 in

\* Manufactured by the Pullman Manufacturing Company, Rochester, N. Y.

† Manufactured by the Caldwell Manufacturing Company, Rochester, N. Y.

‡ For dimensions of pew-bodies see page 48 of *Churches and Chapels*, by F. E. Kidder.

wide, and in the parquet, 31 or 32 in wide. As a rule the higher-priced are more commodious than the lower-priced.

**Estimating Seating Capacity.** The actual seating capacity of theaters and audience-rooms can be determined only by drawing the seats to an actual scale, on the floor-plan, and then counting the number of chairs, or measuring the linear feet of pews.

**Approximate Seating Capacity.** For approximate purposes the seating capacity or required size of room may be determined by allowing from 7 to 8 sq ft to each seat, or sitting, when on a curve, and from 6 to 7 sq ft to each seat when in straight rows, the smaller number being used only for large rooms. This allows for aisles and pulpit-platform. For small concert-halls and narrow rectangular rooms, 6 sq ft per sitting will usually be sufficient allowance, provided only that the actual floor-space utilized for seats and aisles is considered.

Seating Capacity of Several of the Older Cathedrals, Churches, Theaters and Opera-Houses \*

European Cathedrals and Churches			
Estimating that one person occupies an area of 19.7 inches square †			
St. Peter's, Rome.....	54 000	Notre Dame, Paris.....	21 000
Milan Cathedral.....	37 000	Pisa Cathedral.....	13 000
St. Paul's, Rome.....	32 000	St. Stephen's, Vienna.....	12 400
St. Paul's, London.....	25 600	St. Dominic's, Bologna.....	12 000
St. Petronio's, Bologna.....	24 400	St. Peter's, Bologna.....	11 400
Florence Cathedral.....	24 300	Cathedral of Sienna.....	11 000
Antwerp Cathedral.....	24 000	St. Mark's, Venice.....	7 000
St. Sophia's, Constantinople.	23 000	Spurgeon's Tabernacle,	
St. John Lateran, Rome....	22 900	London.....	7 000

European Theaters and Opera-Houses			
Carlo Felice, Genoa.....	2 560	Drury Lane, London.....	1 900
Opera-House, Munich.....	2 370	Covent Garden, London....	3 000
Alexander, St. Petersburg...	2 332	Opera House, Berlin.....	1 600
San Carlo, Naples.....	2 240	Adelphi, London.....	2 300
Imperial, St. Petersburg.....	2 160	Lancaster, London.....	1 800
La Scala, Milan.....	2 113	Globe, London.....	1 100
Academy of Paris.....	2 092	.....	.....

Some Early American Theaters and Opera-Houses, outside of New York			
The Auditorium, Chicago...	4 200	Castle Square Theater, Boston.....	1 600 to 1 800
Academy of Music, Philadelphia.....	3 124	Gaiety Theater, Boston...	nearly 3 000
Boston Theater, Boston.....	3 000	Grand Opera-House, Cincinnati.....	1 700
.....	.....		

\* The table following this one gives the seating capacities of theaters in use in 1911 in some of the boroughs of New York City. The above table of seating capacities of some of the earlier churches and theaters is retained for purposes of comparison. So many important structures of these types have been erected in recent years in the larger cities of the world, or are now in process of erection, that it has been found impossible to make any list that would be and would remain, for any length of time, complete.

† See note on page 1655.



## Seating Capacity of New York Theaters (1914)

Boroughs of Manhattan and the Bronx			
Name	Seating capacity	Name	Seating capacity
Academy of Music.....	2 653	Gaiety... ..	806
Alhambra.....	1 389	Garden.....	1 090
American.....	1 683	Garrick.....	844
American, Roof.....	1 134	Globe.....	1 194
Ator.....	1 137	Gotham.....	1 626
Belasco.....	984	Grand.....	1 888
Berkley Lyceum.....	416	Grand Opera-House.....	2 093
Boulevard.....	814	Greeley Square (Loew's)....	1 906
Broadway.....	1 776	Harlem Casino.....	*
Bronx.....	1 764	Harlem Opera-House.....	1 393
Carnegie Hall.....	2 632	Harris.....	847
Carnegie Lyceum.....	640	Herald Square.....	1 160
Casino.....	1 465	Hippodrome.....	5 200
Century.....	2 078	Hudson.....	1 077
Century, Roof.....	1 150	Hurtig and Seamon's (Music-	
Circle.....	1 684	Hall).....	1 093
City.....	2 289	Illington.....	*
Clinton Street (Odeon).....	904	Irving Place.....	1 079
George M. Cohan.....	1 072	Keith's Union Square.....	1 080
Colonial.....	1 541	Kessler's 2nd Avenue.....	1 803
Columbia.....	1 315	Kessler's 2nd Avenue, Roof..	734
Comedy.....	696	Knickerbocker.....	1 351
Criterion.....	916	Lafayette.....	1 042
Daly's.....	1 074	Liberty.....	1 211
Delaney Street.....	1 242	Lincoln Square.....	1 547
Dixes (Dewey).....	1 310	Lipzin.....	1 030
East Street.....	1 436	Little.....	299
Edgington.....	895	Longacre.....	*
Empire.....	1 099	Loew's Fifth Avenue.....	964
Family.....	687	Loew's 7th Avenue.....	1 626
Fifth Avenue (Proctor's)....	1 204	Loew's National.....	2 333
Fourth Street.....	1 255	Lyceum.....	957
Fourth Street (Brady's).....	969	Lyric.....	1 452
Hamilton.....	662	Madison Square Garden....	3 366

\* Data not furnished.

Note Regarding Unit Area for Seating Capacity. The unit area given in the book on page 1654 appears in the former editions of this book and seems to be small. The original authority for the data cannot be determined. A more reasonable minimum area would be about  $23\frac{1}{2}$  inches square, or about 18 by 30 or 540 sq in, or about 3.8 sq ft. Editor.

## Seating Capacity of New York Theaters (1914) (Continued)

Boroughs of Manhattan and the Bronx			
Name	Seating capacity	Name	Seating capacity
Madison Sq Garden, Roof...	700	Proctor's 23rd Street.....	1 28
Manhattan Opera-House.....	3 200	Proctor's 58th Street.....	1 57
Maxine Elliott.....	904	Proctor's 125th Street.....	1 08
Metropolis.....	1 150	Prospect.....	1 75
Metropolitan Opera-House...	3 305	Republic.....	1 08
McKinley Square.....	1 500	Richmond.....	1 08
Miner's Bowery.....	1 168	Riverside.....	1 73
Miner's Bronx (Acme).....	1 798	Savoy.....	1 57
Miner's 8th Avenue.....	1 178	Star.....	2 28
Minsky.....	1 866	St. Nicholas.....	1 08
Moulin Rouge.....	1 615	Thalia.....	1 28
Murray Hill.....	1 224	Third Avenue (Keeney's)...	1 17
Mount Morris.....	*	39th Street.....	1 07
Nemo.....	941	Tremont.....	1 08
New Amsterdam.....	1 618	Victoria.....	1 57
New Amsterdam, Roof.....	610	Victoria, Roof.....	1 08
New York Theater, Roof....	1 337	Wadsworth.....	1 08
Olympic.....	745	Wallack's.....	1 23
116th Street.....	1 743	Washington.....	1 57
Odeon 145th Street.....	904	Weber's.....	1 08
Park.....	1 513	West End.....	1 53
People's.....	1 693	Weber and Field Music-Hall.	1 53
Philipps.....	*	Winter Garden.....	1 08
Plaza.....	1 544	Yorkville.....	1 08
Playhouse.....	879		

\* Data not furnished.

## Borough of Brooklyn

Academy of Music.....	2 200	Jones.....	1 08
Amphion.....	1 589	Liberty.....	1 08
Bijou.....	1 562	Linden.....	1 08
Broadway.....	1 969	Lyceum.....	1 08
Bushwick.....	2 228	Lyric.....	1 08
Casino.....	1 503	Majestic.....	1 08
Columbia.....	1 673	Myrtle.....	1 08
Comedy.....	1 123	New Montauk.....	1 53
Crescent.....	1 610	Novelty.....	1 08
DeKalb.....	2 232	Olympic.....	1 08
Empire.....	1 740	Orpheum.....	1 08
Fifth Avenue.....	1 063	Oxford.....	1 08
Folly.....	1 840	Payton's.....	1 08
Fulton.....	1 492	Prospect Hall.....	1 08
Gayety.....	1 455	Royal.....	1 08
Gotham.....	958	Shubert's.....	1 08
Grand Opera-House.....	1 515	Star.....	1 08
Greenpoint.....	1 776		

## Dimensions of Some Theaters and Opera-Houses \*\*

The following are the dimensions, in feet, of some of the earlier theaters in this country in Europe.

Name and location	Auditorium			Proscenium-opening		Stage		
	Width	Depth	Height	Width	Height	Width	Depth*	Height†
Alexander, St. Petersburg..	58	76	58	56	.....	75	84	.....
—, Berlin.....	51	78	47	41	.....	92	76	.....
Scala, Milan.....	71	95	64	49	.....	86	78	.....
San Carlo, Naples.....	74	73	83	52	.....	66	74	.....
Grand, Bordeaux.....	47	56	57	37	.....	80	69	.....
Le Peletier, Paris.....	66	76	66	43	.....	78	82	.....
St. James's Park, London...	51	66	.....	32	.....	86	55	.....
Drury Lane, London.....	56	64	.....	32	.....	48	80	.....
Academy, Boston.....	.....	71	58	46	.....	87	68	.....
Academy of Music, New York.....	62	87	.....	48	.....	83	71	.....
Academy of Music, Philadelphia.....	66	78	74	48	.....	90	72	.....
Orpheum, Boston.....	60	65	.....	30	.....	62	38	.....
Academy, Boston.....	68	61	.....	31	.....	68	46	.....
Metropolitan Opera-House, New York §.....	.....	.....	.....	54	50	100	73	88
Chicago Auditorium, Chicago..	.....	.....	.....	.....	.....	110	70	95
Empire, New York.....	69	66	.....	34	34	67	30	65
Wackerbocker, New York.....	70¾	79	47¾†	35	34	40	65½	.....
Wackerbocker, New York.....	56½	52	.....	27	.....	71½	28½	.....
4th Avenue, New York...	.....	.....	.....	.....	.....	80	35	.....
American, New York.....	74½	74½	.....	39	39	77¾	43½	73½
Victor's Pleasure Palace, New York.....	74½	74½	.....	34	34	70	40	70
Edison, New York.....	67½	67	.....	32	30	67½	30¾	.....
Grand Opera-House, Cincinnati.....	67	69	.....	36	34	67	41	.....
Little Square, Boston ¶.....	79½	85½	70†	40	34	68	45½	.....
Academy, Boston.....	77	80¾	.....	.....	.....	60	42	70

**Notes on Theater-Dimensions.††** "The utmost distance from the front of stage to the rear ought not to exceed 75 ft, or the limit the voice is capable of traveling in a lateral direction."

Measured from the curtain-line, the San Carlo Theater in Naples is 73 ft; the

From the curtain or back line of proscenium opening.

Measured from stage to center of ceiling.

To the "gridiron" or rigging-loft.

As remodeled in 1893.

Can be enlarged to 40 by 40 ft.

The plan of this theater is in the shape of a horseshoe.

See footnote with table of Seating Capacities of Churches, Theaters, etc., page 1654, and to data relating to recently constructed buildings of these types.

From The Planning and Construction of American Theaters, by Wm. H. Birkmire.

theater at Bologna, 74 ft. Of the London theaters, the Adelphi is 74 ft, Covent Garden 80 ft, the Gaiety 53 ft 6 in, Lancaster 58 ft 4 in, Marylebone 74 ft, and the Globe 47 ft 6 in."

The width of the ideal theater, between inside walls, should be from 70 to 75 ft, and "the ceiling should be from 55 to 65, or even 70 ft above the stage-level."

"The depth of the parquet-floor at the orchestra-rail is governed by the stage-level, and is generally from 3 ft 6 in to 4 ft 3 in below the stage. A depth of 3 ft 9 in is a good height, as it fixes the eye of the spectator 5 in above the stage-level."

"The height of the stage, that is, from the floor to the bottom of the gridiron or rigging-loft, should be 2 or 3 ft over twice the height of proscenium-opening in order that the fire-curtain may be raised the full height of the opening. There should be a height of 7 ft above the gridiron to enable the fly-men to adjust their ropes with facility.

**Proportioning Gutters and Conductors to the Roof-Surface.** The sizes of gutters and down-spouts and their distance apart for roofs of mill-buildings with a ¼ pitch and of different spans are shown in the following table: \*

One-half roof-span, in feet.....	10	20	30	40	50	60	70	80
Size of gutter, in inches.....	5	5	6	6	7	7	8	8
Size of down-spouts, in inches...	3	3	4	4	5	5	6	6
Spacing of down-spouts, in feet..	50	50	50	50	40	40	30	30

The specifications of the American Bridge Company provide as follows for the size of gutters and conductors: †

Span of roof	Gutters	Conductors
Up to 50 ft	6 in	4 in every 40 ft
From 50 to 70 ft	7 in	5 in every 40 ft
From 70 to 100 ft	8 in	5 in every 40 ft

Hanging gutters should have a slope of about 1 in in every 16 ft.

"The Produce Exchange Building in New York City, with a roof-area of three-fourths of an acre, roughly speaking, has twelve leaders, each about 6 in in diameter. The roof, which is paved with fire-brick, is graded with a slope of perhaps one in fifty toward the points at which the leader-openings are placed. Most of these draining-surfaces being about 40 by 70 ft each. The proportion here made is equivalent to about 1 sq in of leader-opening to 140 sq ft of roof surface. On the Sloane Building, at 19th Street and Broadway, New York City, with a roof-area of 18 000 or 20 000 sq ft, sloping one in twenty-five, there are two leaders, each about 6 in in diameter, and a third rectangular leader about 4 by 6 in in cross-section. This gives an allowance of 240 sq ft of surface to the square inch of leader-opening, while on the Massachusetts Hospital Life Insurance Company's Building and the Hemenway Building, in Boston, the proportion is only from 60 to 70 sq ft to the square inch of opening." ‡

\* H. G. Tyrrell.  
† M. S. Ketchum.  
‡ Dwight Potter in The Technology Quarterly.

## ELEVATOR-SERVICE IN BUILDINGS \*

**General Considerations.** An efficient elevator-service may be obtained by machines of any one of several types, the choice of the one decided upon for any building depending upon varying conditions. The following is a general classification of elevators (see, also, page 1668):

### 1. Hydraulic elevators:

- (1) Vertical, geared hydraulic type.
- (2) Horizontal, geared hydraulic type.
- (3) Direct-lift plunger-type.
- (4) Inverted (high pressure) plunger-type.

### 2. Electric elevators:

- (1) Drum-type.
- (2) Worm-gear traction-type.
- (3) Helical-gear type.
- (4) Gearless, traction-type.
  - (a) Direct-drive (one-to-one) type.
  - (b) Two-to-one type.

In addition to these, there are also the BELT-DRIVEN type of elevators, and the HAND-POWER elevators. The belt-driven type may be either SINGLE-BELT or DOUBLE-BELT driven, the former being used with a reversible motor and the latter where driving-power is taken from a line-shaft. In view of varying and sometimes conflicting claims of competing manufacturers, the architect's decision must be governed by impartial engineering judgment rendered after a careful study of the problem in each case.

**Geared Versus Gearless Types of Elevators.** (See, also, page 1669.) There has been much discussion regarding the merits and demerits of geared and gearless machines for elevators and the efficiency and future of each. Manufacturers of gearless traction-machines have claimed that the use of the helical gear, for example, for elevator-machines, being a relatively recent development, has not extended over a sufficient length of time to permit of extensive definite data; that they are used for different and less severe service than that for which the gearless traction-machines are employed; and that they cannot rival the gearless traction-machines from the standpoint of efficiency. On the other hand, the manufacturers of helical-gear elevator-machines claim that gears have been in successful use for many years, the substitution of helical gears for worm-gears being the only difference made in the application to their type of elevators; that the helical-gear elevators installed in some of the highest office-buildings are doing as much work as any gearless traction-machines; and that the mechanical efficiency of the helical-gear machines is only a little below that of the gearless traction, the electrical efficiency under local or ordinary running conditions, greater, and the car-mile consumption in kilowatt-hours, less.

**Questions of Cost and Efficiency of Elevators.** The principal demerit of elevator-machines of the gearless type is their relatively high first cost, although even that is much lower than the initial cost of elevators of the plunger-type. The use of any gear, whether of the helical, worm or spur-type, is, in the opinion of many engineers, to be recommended only for the purpose of obtaining

\* The matter relating to elevators and elevator-service is condensed and adapted by permission, from data furnished by various engineers and manufacturers, and papers from the Otis Elevator Company, New York City; The H. J. Reedy Company, Cincinnati; R. P. Bolton of The R. P. Bolton Company, Consulting Engineers, New York, and author of "Elevator Service"; C. E. Knox, Consulting Engineer, New York; M. W. Ulrich, Consulting Engineer, New York; and others.

a higher-speed motor, because a higher-speed motor costs less than a low-speed motor. The helical gear is generally considered a more efficient type of gear than the worm-gear and has a deserved place in the development of the elevator-industry. The helical-gear traction-elevators will undoubtedly be extensively used, for the reason that, even if they are not considered by some engineers to be as good in some details as machines of the gearless, traction type, they are less expensive. It is undoubtedly true, however, that the introduction of any gear means some loss in power, and it is claimed that tests show that low-speed motors can be designed which are in every way as efficient as high-speed motors. The data and statements in the following paragraphs relating to elevator-service in buildings are presented as useful aids to architects and include some opinions and conclusions which are to be accepted or modified in the light of constant additions to engineering knowledge.

### A. General Conditions Affecting the Requirements of Specifications for Elevator-Service \*

**Electric Versus Hydraulic Elevators.** The question of the type of elevators, whether electric or hydraulic, is best determined by the local conditions and the special conditions which exist in every plant. The relation of the elevator equipment to the entire mechanical equipment should be carefully considered and should be decided only after mature deliberation and consultation with unprejudiced engineers and elevator-manufacturers. At the present time (1917) about 90% of the elevators being installed are electric, and this includes all types of buildings from the small one with but one elevator to the tall skyscrapers of the big cities. The electric equipment recommends itself, for while it has all of the safety-features of the hydraulic equipment, it is a more flexible system, is more adaptable to all kinds of conditions, and requires much less space. The question of space is a particularly important consideration in office-buildings. Furthermore, the control-system is more automatic, the acceleration and retardation of the car can be made more rapid, and the stops more accurate; the efficiency, also, is higher and in most cases the cost of operation lower. (See the paragraph on Comparison of Merits of Electric, Traction and Hydraulic, Passenger Elevators, page 1670.)

**Location of Hoistways and Machinery-Room.** The location of the hoistways is rather a matter for the good judgment of the architect. In the best equipment all elevators serving one portion of the building and for the same character of service, should be placed in one BANK and not distributed or separated. Thus, all express-elevators should be together and in one bank, as should also, the locals. The hoistways should be so placed that the entrances, in all stories, are on the same side of the car. In some of the larger cities, two entrances for a passenger-car are not permitted, unless the doors can be controlled by the attendant without leaving the operating-device. The machinery-room should be well ventilated, light and clean as possible, in order that the machines may be given proper attention. This room should also be large enough to make the machines readily accessible for repairs and inspection. Where the machines have heavy parts, which it may be necessary to remove from time to time for repairs, it is advisable to locate a trolley-beam with hand-hoist above them to facilitate the handling of these parts.

\* The Otis Elevator Company, New York, has been of assistance in furnishing much of the engineering data of Section A, of this article on elevators. Among other things it considers especially those conditions which should be considered and made definite by the architect preliminary to the preparation of the elevator-specifications. The paragraphs of Section A should be read in connection with those of Section B, page 1661, and the data compared.

**Number and Sizes of Elevators.** (See, also, pages 1673 and 1675.) The number and sizes of elevators are governed by the following considerations: (1) the character of the building, (2) the height of the building, (3) the rentable area, (4) the time-intervals between the departures of cars, (5) the number of stories to be served, (6) the average number and length of stops per trip, (7) the speed of the elevators and (8) the type of elevators used. No iron-clad rules can be given for all types of buildings, but the larger office-buildings, apartment-buildings or light-manufacturing buildings have been sufficiently regular in design to warrant some general rules, based upon experience; even in these cases, however, the governing conditions vary with the size of the building. One of the most essential requirements for a satisfactory plant is QUICK SERVICE; and in first-class office-buildings the intervals between cars should not exceed 30 seconds. The number of stories to be served by a car should be a consideration. For example, in a fifteen-story building, assuming that stops are made at 80% of the stories for one passenger each, and allowing 2 sq ft for each passenger, and 4 sq ft for the operator, the car should have an inside area of at least 28 sq ft. In order to facilitate unloading and thus increase the efficiency of the system, it is desirable to have the width of the car greater than the depth. In the above case, a car with outside dimensions of about 6 ft wide by 5 ft deep would give the best results, showing a difference of from 15 to 20% between the height and width. In specifying the equipment, it is better to call for several moderate-sized cars and a high speed, than for a few large cars of slower speed and larger capacities. Thus, three cars, each carrying one-third of all the passengers, are better than two cars, each carrying one-half, as the service is increased by making the period between cars less. As the elevator-service largely determines the success of a building, it is of vital importance that a sufficient number of elevators be installed to handle the regular traffic, as well as emergency-conditions in case of a shut-down. To illustrate what is considered the proper proportion of passenger-elevators for buildings of various heights, the following table is given, based upon a rentable area of 8 000 sq ft per story and 125 sq ft per person. This table shows the various combinations for elevators with a speed of from 400 to 500 ft and of 600 ft per min for buildings of from 10 to 20 stories above the ground.

Table Showing Number of Elevators Required

Number of stories	Express 600 ft per min	Local 600 ft per min	Express 600 ft per min	Local 500 ft per min	Express 500 ft per min	Local 400 ft per min
10	.....	4	.....	5	.....	5
12	.....	5	.....	5	.....	6
15	.....	6	.....	7	.....	7
18	.....	7	.....	8	.....	8
18	Express to 11 5	1 to 11 5	Express to 10 5	1 to 10 5	Express to 11 5	$\left. \begin{array}{l} \text{500 ft} \\ \text{per min} \\ \text{1 to 11} \end{array} \right\}$ 5
20	.....	All locals 8	.....	.....	.....	.....
20	Express to 12 5	1 to 12 5	Express to 11 5	1 to 11 5	Express to 12 6	1 to 12 6
25	Express to 15 6	1 to 15 6	Express to 14 6	1 to 14 6	Express to 15 7	1 to 15 7
25	Express to 18	1 to 18	Express to 17	1 to 17	Express to 18	1 to 18

Buildings equipped with both local and express-service should have the number of elevators for each class of service. In the case of the twenty-story building for 600 ft-per-min speed, it is to be noted that the local elevators are shown serving from the first to fifteenth story, whereas the express-elevators serve from the fifteenth to the twenty-fifth story. The express-elevators do not serve as many stories as the locals on account of the extra time consumed in the run to the first express-landing. With the distribution as shown, the schedule for all stories is about equal, and both express-elevators and local elevators operate on about the same schedule. In the fourth and fifth columns are shown what is considered the best arrangement with the express-elevators operating at a 600 and the locals at a 500 ft-per-min speed. Upon comparison with the second and third columns, it will be noted that the express-elevators are to serve one additional story. This is due to the difference in speed between the express-elevators and local elevators and is done so that the schedules will still remain the same for both. (See, also, paragraph on the Local and Express Round-Trip Time, page 1675.)

**Loads and Speeds.** The sizes of the machines or hoisting-apparatus are determined by the loads and speeds. The loads for passenger-cars should be figured on a basis of 75 lb per sq ft of inside area of platform. The speed is a very important factor, as the foregoing indicates. This is usually limited by local ordinances, and in New York City, cars stopping at all stories are not permitted to exceed a speed of 500 ft per min. For express-service, in that portion of the shaft where no stop is made, a speed of 700 ft per min is allowed. The NO-STOP DISTANCE must be at least 80 ft or more. The best companies for elevator-insurance will not permit electric-drum elevators for a speed much over 400 ft per min, whereas the gearless, traction-drive type and the hydraulic type are approved up to the limits, as noted above. In hydraulic plants it is necessary to specify the number of round trips per hour for the entire elevator-equipment. This is required in order to determine an adequate pumping-plant.

**Hoistways.** The hoistways should be finished to plumb-line dimensions so that the car running on guide-rails set to plumb-line will at all points have the same clearance. Supports should be provided adjacent to the hoistway for the overhead beams at a distance, if possible, of at least 4 ft from the top of the car frame when the platform is flush with the top landing. This distance should be increased where possible so that the car will have ample clearance, thus preventing accidents due to striking the overhead work, in case it should rise past the top landing. The minimum clearances between the top of the car frame and the overhead apparatus are usually limited by the local building regulations, and these should be consulted. In the case of the elevators operating at a speed greater than 350 ft per min, the distance given above would probably have to be increased in order to comply with these regulations. A pit should be provided at the bottom of the shaft. This should be at least 3 ft deep, and, as is the case with the overhead clearances, the depth is usually regulated by the building regulations, in accordance with the speed of the elevator. Where possible, the hoistways should be so planned that the main guide-rails may be placed at the sides of the car. Supports should be provided at all the floors for these rails, and where the distance between floors is greater than 12 ft, intermediate supports should be provided. The distance from the supports for the overhead beams, to the penthouse or skylight-roof, varies with the type of installation, but can be accurately obtained from the elevator-manufacturer.

**Protection of Counterweights.** In New York City the Bureau of Building requires that where the counterweights run in the same shaft as the car, they must be protected with a substantial screen of iron from the top of the rail to



at 15 ft below, except where the plunger-type or traction-type elevator is  
l.

**Building Laws Governing Elevator-Installation.** The Bureau of Building, Borough of Manhattan, New York City, issued regulations \* governing construction, inspection and operation of all types of elevators, and the special attention of all architects is called to them, as they are not only obligatory, but are excellent guides to practice at all times. The foregoing paragraphs are intended to give an idea of what the architect must consider and provide for in building for the reception of the elevator-apparatus, and what he must determine in order to enable the manufacturer to intelligently design and lay out his machinery.

**Standard Designs and Special Apparatus.** The specifying of apparatus of special construction is, as a rule, not to be recommended. Standard designs should be used as much as possible, as (1) they are more apt to be well designed, erected and built, (2) they are undoubtedly less expensive, both in initial cost and maintenance and (3) repair-parts may be more easily and quickly obtained at less cost.

**Specifications for Elevator-Installation.** The specifications should include what is included in the following classification.

- (1) Kinds of service and number of elevators of each service.
- (2) Maximum load wanted.
- (3) Maximum speed.
- (4) Load with maximum speed.
- (5) Maximum number of round trips per hour for each elevator.
- (6) Method of control. For electric elevators, car-switch control should be used for passenger-service and for all elevators for a speed over 150 ft per min.
- (7) Size of hoistways and area of car-platforms.
- (8) Travel of car-platform in feet, number of car-landings, and number of openings at each landing.
- (9) System used. If electric, direct or alternating current, the voltage and, also, the phase of cycles for alternating current should be given. If hydraulic, the steam-pressure or electric current characteristics for the pump-motors or the water-pressure, if the purchaser provides the pumps, tanks or other source of water-pressure supply.
- (10) A sketch-elevation showing landings, supports for overhead beams, space for the overhead sheaves, and runbys at top and bottom; a sketch-plan showing size and shape of hoistways, entrances, position of car and counterweight, guide-rails, and location of space available for machines, pumps, tanks, etc., with reference to hoistways.
- 1) Car and counterweight guide-rails, whether of wood or steel.
- 2) Supports for fastening the rails, character of these supports, and where and how located.
- 3) Value of finished car or cage, that is, the specified amount to be allowed for each, the design being subject to the approval of the architect.
- 4) Number and size of ropes, if not left to the judgment of the elevator-contractor. The largest sheaves possible should always be required, as this factor determines largely the life of the ropes.
- 5) System of signals, that is, (a) annunciators in the cars with push-buttons at the landings, (b) UP and DOWN signals in the cars, with UP and DOWN buttons at the landings, so arranged that a car going up receives only

\* Published in the Record and Guide, July 29th, 1911.

UP signals, and a car going down receives only DOWN signals, a signal being automatically reset by the first car stopping at the floor from which the signal is given. This system adds greatly to the efficiency of a battery of elevators, as it avoids the confusion of more than one car answering a signal, or a car going in one direction stopping for a passenger going in the opposite direction. The number of stories at which each car is to land should always be specified.


- (16) Indicators. Whether at the ground-floor only, for the information of the starter regarding the position of the cars, or at all floors. Indicators are unnecessary with the automatic signals last described, except at the ground-floor, as there is at each floor an UP and DOWN signal to show the first available car in either direction.
- (17) Source of power. It should be specified whether the connections will be brought to the elevator-apparatus by the purchaser or by the elevator-contractor. If by the latter, a sketch should be made showing the distance, and for the electric system the specifications should state whether the wiring is to be open, that is, on cleats, in moldings, or in conduits; the sizes of wire, and the switches, cut-outs, etc. For a hydraulic system, the size of pipe for steam-supply should be given. The sizes of water-piping should be left to the elevator-contractor as he should be held responsible for them. Also, in the case of an electric hydraulic system operating from street-mains, the specifications should state by whom the piping is to be done and who is to furnish the water meter.
- (18) Pumps and tanks in hydraulic plants. These should be furnished by the elevator-contractor. The specifications should state whether the capacity is to be just ample to do the work, or whether there is to be a reserve capacity, with reserve-units, to provide against interference with the service in case of accident to a pump or tank, or for future elevator expansion, but the sizes and design should be left to the judgment of a responsible elevator-contractor.
- (19) Foundations for the machine, whether they are to be provided by the purchaser or by the contractor.
- (20) Miscellaneous. Gratings underneath the overhead work, pitpans, painting in addition to the standard factory-finish and all items not mentioned above are generally furnished by the purchaser under separate contracts, but this should be clearly set forth in the elevator-specifications.

**Safety-Devices for Elevators.** (See, also, page 1672.) The question of safety-devices cannot be too carefully considered for all elevators, and for passenger-elevators in particular only the best and most thoroughly tested apparatus should be installed. Each car should be equipped with the mechanical device designed to grip the rails and stop the car in case it exceeds a predetermined maximum descending-speed, either from breaking of the cables or from any other causes. This safety-device should be mounted upon the car-frame beneath the platform, and should be operated by means of a speed governor located overhead. For speeds above 150 ft per min, this gripping of the rails should be done gradually. In New York City the instantaneous stopping is not allowed above a speed of 100 ft per min. A switch for emergency use should be placed in the car of electric elevators. The opening of this switch should stop the car immediately and independently of the regular operating-device. All electric elevator-machines should be equipped with an electric brake. This brake should be automatically applied when the car stops or when

current-supply is interrupted. The brake should be released electrically and held by means of spring-pressure. Automatic limits should be placed at top and bottom of the hoistway, to automatically slow down and stop the car at the limits of travel, independently of the operator.

**Gearless Traction-Elevators.\*** Among the more recent developments of the elevator industry is the electric, gearless, traction-elevator (Figs. 1 and 2).

(e, also, Fig. 5.) The designing of an efficient slow-speed motor made it practical to build a traction-machine with the driving-sheave mounted directly upon the arma-



1. Roping for 1 to 1 Traction-machine

ture-shaft, thus eliminating the use of gears to reduce to the desired car-speed. This gearless machine is used for speeds from 250 ft per min and above. The manufacturers of this type of machine claim that it is the outcome of a general tendency toward simplicity in design with efficiency in operation. The machines are generally located over the hatchway. The car is supported by cables which lead from the car directly over the driving-sheave, with overhead installation, then partially around the auxiliary idler or leading-sheave and again over the driving-sheave to the counterweight. With this arrangement a complete turn around the driving-sheave and the idler-sheave is obtained, giving sufficient tractive effort to drive the car. The machine being placed overhead, the cables can lead directly to the car and counterweights; and as this allows the cables




Fig. 2. Roping for 2 to 1 Traction-machine

bend in the same direction, it is claimed by the manufacturers that this is an advantage and that the life of the cables is appreciably lengthened. Special hitches are used for connections to the car and counterweight to counteract the twisting effort due to the reaving of the cables. As soon as either the car or counterweight is obstructed, the tension in the cables is increased and consequently the tractive effort reduced. This arrangement, it is claimed, brings either the car or counterweight to rest and prevents running by the limits of travel, and into the overhead beams, should either car or counterweight land on the buffers at the bottom of the shaft. Underneath both car and counterweight are placed oil-buffers designed to bring the car or counterweight to rest at the limits of travel, from full speed. At the top and bottom of the hatchway the car is stopped automatically by a series of electric switches. The operation of these switches is so timed that the car is brought to a smooth and gradual stop. The slow-speed shunt-motor, with its control, makes a flexible system. The acceleration and retardation may be arranged to suit the particular service-requirements. For speeds below 450 ft per min, it is the practice to obtain the slow speed by passing the cables around sheaves mounted in

For full and valuable data relating to the relative advantages of the helical-gear traction-elevators as compared with those of the traction-type, see papers published by the H. J. Hardy Company, Cincinnati, Ohio, and others advocating the geared machines. Editor.

the cross-head of the car and of the counterweight, and anchoring the ends of the cables at the top of the hoistway. These sheaves, with their ball bearings, are specially made to withstand the heavy service to which they are subject. In addition to the above details, elevators of this type should be provided with all of the regular safety-devices used with passenger-elevators.

**Electric Elevators with Push-Button Control.** One of the most ingenious and serviceable developments in the elevator-industry is that of the automatic electric elevator with push-button control. In New York City this type of elevator is permitted only in residences, but in other cities it is used in apartments, hospitals, and other places where the service is very light and intermittent and it is desired to dispense with an attendant. In the design of these elevators it has been the aim to provide all safety-devices and appliances to make their installation absolutely safe, so that the elevators may be operated even by a child alone, without danger. In each story is located a button, similar in appearance to the ordinary signal-button, and the passenger, by pressing this, may call the car, if it is unoccupied or not in use, to any story. The car comes to the story at which it is required, and stops automatically. When it comes to rest in the story, the entrance-door to the hoistway is automatically unlocked, and it is then possible for the passenger to open the door and the car-gate, and enter the




Fig. 3. Standard Hatchway and Car-platform. Side-guides




Fig. 4. Standard Hatchway and Car-platform. Corner-guides

car. The hoistway-gates and the car-gate are so arranged that the machine is inoperative until both are tightly closed. The hoistway-doors can be opened from a hall, only when the car is at the landing of that particular hall. Inside the car is a bank of buttons corresponding to the various stories served, and also a stop-button or emergency-button. After entering the car, and closing the hatchway-door and the car-gate, the passenger can push the button in the car corresponding to the story to which he desires to go. The car will proceed to the designated story and stop automatically. Should the passenger desire for any reason, to stop the car at any point of its travel, he can do so by pushing the stop or emergency-button. The car is in the complete control of the passenger, as, after the initial operation of calling or sending it to a landing, no further operation cannot be interfered with until after both the hatchway-door and the car-gate are opened and closed. This means that no other person can call the car until after the passenger has reached the desired landing, left the car, and closed the gate and door. In some equipments for elevators of this type the device for releasing the door-lock is prevented from operating while the car is in motion. This is a very desirable safety-feature, as otherwise each

temporarily released as the car passes up or down the hoistway, and a person landing can open the door during the momentary period that it is unlocked. In some cases the gate on the car is omitted; but this is a very dangerous practice and should not be permitted. Elevators of this type are designed for operation with direct current or alternating current, and single or multiphase circuits. Single phase should be avoided, if possible, and before deciding upon type of current, the consent of the electric power company should be obtained for placing upon their lines a motor with the heavy inrush of current required at starting.

**Standard Relations of Hatchway, Platform and Car-Sizes.** (See, also, page 1675.) In Figs. 3 and 4 are shown some typical elevator layouts for electric installations, with side and corner-posts and steel construction. (See, also, Fig. 7.) The clearances shown are for elevators traveling at a speed of 100 ft per min or more, and may be reduced about 1½ in for elevators of slower speed. Some of the minimum dimensions given with Figs. 3 and 4 vary slightly from those given with Fig. 7 and in Table D, page 1676, but agree in the essential requirements.

### B. Electric, Passenger-Elevator Systems \*

**Elevator-Development.** The object in view in presenting this material is to discuss all the details of elevator-construction or the mechanical features, but to outline the results of a study in connection with the economic division of passenger-elevators and an efficient elevator-service for the traffic of the modern commercial or distinct type of office-building. The requirement of such building is a very ample and adequate elevator-service, not only because the monetary value of the building may otherwise be affected, but in time of necessity, during a fire or other panic, the occupants must be readily brought to safety. During the early development of the sky-scraper the necessity for a proper elevator-service was partly overlooked, and perhaps not altogether realized, for many of the older buildings suffer from a lack of traveling-facilities, resulting in inconvenience to the many occupants. The tenants of the upper stories are therefore obliged to wait on the up trip of the elevator, and the people occupying the lower portion of the building are left behind on the down trip.

**The Extensive Use of Elevators.** To fully indicate the extensive use to which the elevator has been adopted for passenger traffic in large cities, the incidence of the Borough of Manhattan of New York City is given. There were in 1914 about 10 000 machines in service, twice the number that were in operation in 1904, and these were divided among the different classes of buildings approximately as follows:

- 5 000 elevators in office-buildings over 10 stories high.
- 1 500 elevators in office-buildings under 10 stories high.
- 500 elevators in loft-buildings.
- 700 elevators in residences.
- 800 elevators in apartment-houses.
- 500 elevators in department and other stores.
- 1 000 elevators in hotels, clubs, institutions, etc.

The matter in Section B of this article on Elevators is, by permission, condensed and adapted from data contained in papers by M. W. Ehrlich, consulting engineer. The matter first appeared in the April, May and June, 1914, issues of *Electrical Engineering*, and afterwards were published in condensed form in *Lefax*, by the Standard Corporation of Philadelphia. Section B includes a brief outline of elevator-development, some economic considerations and some installation-data, and the paragraphs of this Section should be read in connection with those of Section A, page 1580, and the data compared.

Besides these passenger-cars, the buildings requiring freight-service need an additional 10 000 machines.

**Two Common Types of Elevators.** In modern elevator-practice are but two common types of successful machines in use, the hydraulic and electric elevators. These may both be subdivided in the classification and




Fig. 5. Some Types and Varieties of Elevators

to the mode of drive or operation and the transmission of power, thereby creating an apparent variety of elevators. The machine of the hydraulic type may be of the vertical-cylinder pattern or of the plunger-type, while the electric type may be of the drum, worm-gear or gearless traction-type. Some of these types and varieties are illustrated in Fig. 5. (See, also, Figs. 1 and 2, page 1659, and general classification on page 1659.)

**A Short Historical Account of the Development of the Commercial Passenger-Elevator** brings one back a little more than half a century

production of the first STEAM-ELEVATOR. This form of drive was soon replaced by the WATER-BALANCE type of hydraulic elevator, which, even though a faster machine, proved to be, in operation, quite dangerous. For a number of years this type enjoyed the distinction of being the only high-speed apparatus until the advent of the VERTICAL-CYLINDER HYDRAULIC ELEVATOR, about twenty years later. Running-speeds as high as 400 ft per min were readily attained, and on account of the ease in handling and the safety in operation, these elevators soon gained favor and were the only types of machines installed in the tall buildings. The electric DRUM-MACHINE made its first appearance in New York during the year 1889, and owing to the merits of this new system, the electric machine soon established itself as a successful competitor with the hydraulic type. The only obstacle remaining was to overcome the slower speed, and this brought out the Sprague LONG-SCREW ELECTRIC ELEVATOR. Elevators of this type proved quite costly to maintain and operate, but on account of their possibilities of speed and high rise, were installed in several tall structures. These different types of elevators helped considerably in the development of the sky-scraper buildings, and as further building projects required an extension in height, a hitherto unknown condition of passenger-elevator service had to be met. About the year 1900 the DIRECT-ACTING PLUNGER HYDRAULIC ELEVATOR was introduced to fulfil this increasing demand for continued high rise with high speed. The inherent safety in operation and the relatively high economy allowed for no doubt as to the possibilities of the PLUNGER, but after several years, experience pointed out that the advantages of the hydraulic plunger-elevator were somewhat limited in certain directions, and only under conditions of a rise not exceeding 150 ft could the characteristics of the safe and economical plunger-elevator be maintained.

**Traction and Geared Elevators.** (See, also, page 1659.) Recent experiments conducted to perfect an electric elevator that would meet the growing requirements of heavy passenger traffic in the newest form of tall office-buildings have resulted in the production of what is now commercially known as the TWO-ONE, or GEARLESS TRACTION-ELEVATOR. Among the earliest New York installations of this type of electric elevator may be named those in the Singer Building and Tower, and later those in the Metropolitan Building and Tower, and the latest developments include the Woolworth and the Equitable Buildings.

The apparatus used in the Municipal Building is one in which the machines are an adaptation of the usual double-worm-and-gear drive between a relatively high-speed motor and a cable-drum, a double set of intermeshing gears being employed between the two gear-shafts. In summarizing, it may be well to mention that the commercial or useful life of an elevator and its combined mechanisms seldom exceeds fifteen years, and that where remodeling has been resorted to, the ELECTRIC DRUM and WORM-GEAR TRACTION have usually been substituted for the HYDRAULIC TYPE in buildings not exceeding twelve to sixteen stories in height; and that in higher structures the GEARLESS traction-elevator or its modification in the form of an electric TWO-ONE TRACTION-ELEVATOR has been resorted to.

**Safety of Electric and Hydraulic Elevators.** (See page 1664.) It is generally held, however, that both the electric and hydraulic types of elevators have been perfected to a state of high efficiency, and they may, therefore, be used with entire safety. Of the hydraulic types it may be said that the plunger-elevators are inherently safer than those which are suspended, or than even the modern electric traction-elevators; but it cannot be denied that the many improvements and improved appliances attached to elevators of the various electric types have made the latter as reliable as hydraulic machines designed according



to best practice. It is claimed that the electric traction-elevator is ~~red~~ free from the element of danger because of the improved methods of ~~p~~ transmission and the peculiar form of windings used for the drive.

**Comparison of Merits of Electric, Traction, and Hydraulic Plunger Elevators.** In narrowing down the question as to the merits of the ~~the~~ TRACTION-ELEVATOR and of the HYDRAULIC PLUNGER-ELEVATOR for ~~pass~~ service in tall office-buildings of to-day, it might be well to note that the elevator-installations, almost without exception, have favored the ~~the~~ Not only is the cost of installing the traction-machine from 25 to 35% less than that of the plunger-type, but the room occupied by the driving-machine reduced to a minimum, and, as a matter of fact, may be placed at the head directly over the elevator-shaft. If no local supply of electricity is available the premises, the public source may be resorted to. The difficulty with plunger-elevator for high-rise, high-speed work lies in the requirement for lifting the mass of water and the massive plunger proper, and as this ~~mass~~ weight cannot be readily and smoothly stopped, the result is a sluggish starting and stopping. At any rate, it remains an open question as to ~~the~~ the economic values attached to modern buildings would favor the install of the plunger-elevator, with its accompanying pumping-plant, which necessarily occupies considerable floor-space. The choice, therefore, would ~~be~~ favor the HIGH-RISE, HIGH-SPEED ELECTRIC TRACTION-ELEVATOR for ~~pass~~ service. (See, also, paragraph on Electric Versus Hydraulic Elevators, 1660.)

Table A. Relative Operating-Costs of Elevators

	Office-building				Loft-building				Apartment-house		
	Traction electric	Worm-gear electric	Vertical-cylinder hydraulic	Direct plunger	Traction	Worm-gear	Hydraulic	Plunger	Traction	Worm-gear	Hydraulic
Is	8.5	7.2	6.8	6.5	8.0	6.8	1		8	6.0	5.5
Cents per car-mile	25	22	20	19	23.8	20	21		18	17	1
Dollars per car per annum . . . . .	2,100	1,850	1,680	1,600	2,075	900	1		60	530	480
Percent of all operating-costs . . . .	14.1	12.0	11.3	11.0	18.0	15.4	11		6	12.0	11.0

**Relative Operating-Costs of Elevators.** The figures given in Table may prove of interest in pointing out the relatively higher operating-costs of different ELECTRIC types over the VERTICAL-CYLINDER HYDRAULIC and PLUNGER ELEVATORS. The values given represent only the cost of labor, power, and supplies. By a close perusal of the amounts listed, it will be ~~clear~~ that the economies of the plunger cannot be utilized beneficially in tall buildings, on account of the mechanical difficulties, and in other types of buildings, allowing for a low rise, the installation cost becomes exorbitant, the relatively high first cost of this type of machine were taken into consideration, with an addition for the extra cost in building-construction, necessitated by the space occupied by the pump and tank-equipment, the total expenditure for the whole would show no great favor either way. In explaining the figures given in Table A, it should be understood that the figures are computed on the basis of actual records of several buildings that have been brought to the will



**e.** The general method of comparing records in business buildings is to compare the costs with the total annual income or rental. The total operating-costs include the expense in the mechanical, electrical and building departments, covering all costs of labor and material for the maintenance of the entire divisions of service. Therefore the annual cost of operating an elevator-system is given as a percentage of the gross rentals received, and is further stated as a percentage of the total operating-expenditure of the building under consideration. The average cost in cents per car-mile traversed is given, together with the average annual cost in dollars to pay for the cost of operating and repairing, the necessary power, and the material and supplies required per single elevator.

**Economic Considerations.** The efficient operation of an elevator-system does not rest altogether on the economic division and disposition of the cars, as the human element becomes one of the main factors. It is self-evident, therefore, that the service of an elevator is limited not only by the different classes of passengers entering, riding and leaving the conveyance, but by the experience of the hallman or STARTER, and his ability to understand the demands of the passengers and the personal peculiarities of the elevator-operators.

**Time-Schedules.** It is now common practice to dispatch the various cars of an elevator-system on a predetermined time-schedule, thus avoiding to a great extent any confusion or overcrowding that would otherwise arise. It has been well established that the travel of elevators under consecutive-trip rule-operation allows for a highly efficient service, not only in the handling of the traffic, but in the demand for power, which is thereby reduced to a minimum.




Fig. 6. Recorded Current-consumption of Gearless Traction-elevators

**Power-Diagrams.** The POWER-DIAGRAMS (Fig. 6) point to the effect of a proper schedule and a proper service under different conditions. The upper curve (a) was taken under test-conditions and represents the operation of one elevator. The current in the single car is approximately equal to the designed machine-balance, on the up and down trips, and the number of stops corresponds to the average per car per mile under actual service in office-buildings. This diagram is given mainly to allow for a proper understanding of the combined curve (b), showing the actual round-trip operation of a bank of elevators in one of the New York sky-scraper buildings at an early-morning hour. The full or solid-line curve shows an excessive power-demand due to an inconsistent SCHEDULE, the

cars having been dispatched by a starter who may be identified as X, while dotted or broken-line curve shows the more expert handling under the constant trips by starter Y, the same operators running the cars in each case.

**Safety-Appliances.** (See, also, page 1664.) To minimize the many accidents in elevator-practice, a SAFETY-LOCK is recommended, so attached it will not permit the elevator to leave a landing until the gate has been locked. Accidents are seldom, if ever, due to the faulty behavior of the elevator, but sometimes the breaking of suspension-ropes, as recorded by a relatively few cases, will result in a serious accident. The most frequent cause of accidents connected with the operation of elevators, is that due directly to the negligence of the operator in handling the doors or elevator-gates, and this may be avoided by the installation of the safety-locks above recommended. So far as has been practically demonstrated, many of the safety-appliances on older installations designed to stop a falling elevator have usually failed, but the improved wedge-type of JAW-SAFETY, actuated by a SPEED-COVER and attached to the more recent installations, usually acts when the elevator exceeds its normal running-speed. This generally occurs when the design safe-distance limit has been passed, and the jar occasioned by the final stop of the car is not altogether a pleasant experience. The serious injuries and fatalities due to the falling of an elevator are proportionately small when compared with the entire list, and amount to about 20% of the total, whereas the loss of life caused by open and unlocked gates in elevator-practice accounts for the remaining 80%. The only safety-device, therefore, that may be called useful, as it eliminates the personal element, is a SAFETY-LOCK. Of the several automatic devices now available for this provision of safety, all have some merit; and while some are purely mechanical, others are actuated electrically, and only by the installation of such automatic locks will unnecessary elevator-accidents be avoided.

**Signal-Systems.** A SIGNAL-SYSTEM is essential to an efficient service. Automatic electric-light indicators at the different landings, with a mechanical indicator on the ground-floor or street-landing, will be found highly efficient even though not the simplest. Briefly described, the system is composed of a dynamotor supplying current for the magnets, push-buttons and lamps. On each landing one or more sets of push-buttons are arranged for both the UP and DOWN signal, and over each elevator-gate two lamps of different color, one red and another, to indicate the direction of car-travel; and each elevator-car is provided with a signal-lamp and a transfer-switch or push-button. A mechanical indicator on the main landing informs the starter as to the location of the different elevators, and thereby aids him in exercising full discretion as to when to dispatch the next car. The general system operates in a manner approximately as follows: When a push-button is pressed for either direction in any story, it actuates a magnet corresponding to that story, which in turn signals to the operator in any approaching car, thereby indicating a waiting passenger, and, according to the movement of the elevator, further contact is made with the outside signal-lamps at that story showing to the waiting person the elevator approaching that floor. In a properly proportioned elevator-system the transfer-switch is seldom used, but in buildings in which the travel becomes overloaded during the rush-hours, and when an approaching car is filled to its capacity, the operator may press the transfer-button and thereby signal the car to follow.

**Traffic-Capacity of Elevators.** The TRAFFIC-CAPACITY of an elevator is determined by its passenger accommodations must necessarily be of such proportions as to handle the travel of the tenants of the building and also of their visitors and ensure a proper working schedule. From a study of existing systems in which

ator-service is considered adequate, it is found that the questions of BUILD-OCCUPANCY as related to BUILDING-AREA and elevator TRAFFIC-CAPACITY be combined into a consideration of a proper UNIT AREA for the elevator. regard to the determination of the MAXIMUM TRAFFIC-CAPACITY of a passenger-ator, experience shows that an average weight of 140 lb may be allowed for 1 passenger, and as each size of car has its corresponding load at the rated d, the total load divided by 140 gives the maximum number of passengers an ator can accommodate at its designed speed. In another simple computa-for this result, an allowance of 2 sq ft of car is made for each passenger. The imum capacity of an elevator may be of interest in computing the time reed to empty a building in case of emergency; but when a car of proper unit is installed, this condition is taken care of. Tests have shown that the RAGE PASSENGER TRAFFIC of an elevator-system bears a definite relation to TENANCY of the building, and to the MAXIMUM TRAVEL, the result being that essed in Formula (6).

umber of Elevators. (See, also, page 1661.) Modern practice tends to r that the NUMBER OF ELEVATORS required for any office-building is really rned by the physical aspects and conditions of that building. Wherever it ot practicable to use a car of large area, the number required will certainly n excess of that necessary when large cars are used. It is not advisable, efore, to base any conclusions on the number of cars to adequately satisfy rtain condition, unless the UNIT AREA OF THE CAR is considered.

ocal and Express-Elevators. Another important consideration is the ion so common in high-class office-buildings, namely, the proper service of L and EXPRESS-elevators.

ormulas for Elevator-Service. The formulas given below are well sub-iated, and give economical service-conditions based on existing systems in arger cities of the United States. By these formulas the number of eleva-required, the division of service, and their operation may be determined.

$$E = A/24\ 000 \quad (1)$$

$$f = n/2 + 2 \quad (2)$$

$$Te = (25/s + 5/100) n \text{ and } Tl = (25/s + l/10) n \quad (3)$$

$$Me = 2 n/7 Te \text{ and } Ml = 2 n/7 Tl \quad (4)$$

$$Ce = 115 n/100 Te \text{ and } Cl = 115 n/100 Tl \quad (5)$$

$$pe = 300/Te \text{ and } pl = 300/Tl \quad (6)$$

notations in the formulas are:

$E$  = number of elevators required

$A$  = square feet of gross building-area served

$f$  = story at which express-run terminates

$n$  = total number of stories served

$s$  = speed of elevator, in feet per minute

$Tl$  = local round-trip time, in minutes

$Te$  = express round-trip time, in minutes

$Ml$  = miles traveled per hour by local

$Me$  = miles traveled per hour by express

$Cl$  = current consumed per hour by local, in kilowatt-hours

$Ce$  = current consumed per hour by express, in kilowatt-hours

$pl$  = passengers carried per hour by local, one way, up or down

$pe$  = passengers carried per hour by express, one way, up or down

e figures in Table B represent the AVERAGE LOAD AND SPEED-COMBINATIONS rious heights of buildings, together with the usual AREA OF THE ELEVATOR-

CAR consistent with the standard sizes manufactured, and should be used as a basis for selecting the proper unit areas in connection with Formula (1). Many factors entering into the operation of an elevator would affect the car consumption to a considerable extent, as may be seen in Fig. 6, previously explained. But Formula (5) agrees with modern service under average operating conditions.

**Table B. Unit Area, Load and Speed-Combinations**

Number of stories	Car-area, sq ft	Load, lb	Speed, ft per min
8 to 13	25	1 700	250 to 350
14 to 22	30	2 000	350 to 600
23 to 30	40	3 000	400 to 600

**Table C. Elevator-Installation Data**

1	2	3	4	5	6	7
Building		Number of elevators required				
Number of stories	Gross area, sq ft	Total car-area, sq ft	Cars at 25 sq ft	Cars at 30 sq ft	Cars at 40 sq ft	By Formula
8	80 000	89	4	.....	.....	4
10	100 000	111	4	.....	.....	4
12	120 000	133	5	.....	.....	5
14	210 000	262	11	9	.....	9
16	240 000	300	12	10	.....	12
18	270 000	337	14	11	.....	11
20	300 000	375	15	13	10	13
25	375 000	577	.....	19	15	16
30	800 000	1 221	.....	40	30	36

	8	9	10	11	12
Number of stories	Round trip time in minutes				1, or expressed in stories
	Tl at 350 ft per min	Tl at 500 ft per min	Te at 500 ft per min	Te at 600 ft per min	
8	1.3	.....	.....	.....	.....
10	1.7	.....	.....	.....	.....
12	2.0	.....	.....	.....	.....
14	2.4	2.1	.....	.....	.....
16	2.7	2.4	1.6	.....	13
18	.....	2.7	1.8	.....	11
20	.....	3.0	2.0	1.8	12
25	.....	.....	2.5	2.3	15
30	.....	.....	3.0	2.7	17

**Installation-Data.** In order to facilitate the ready understanding of the various formulas given, Table C, embodying the computations, is presented. The various headings included are numbered in respective order from 1 to 12, so that an explanation of the items considered will not be confusing. Under column 1 is listed the heights of buildings, with the assumed floor-areas, extending to the full height of the structure, given in column 2. In column 3 are listed the actual square feet of car-area now provided in many buildings of similar floor-space and with an adequate service. This is intended as a guide where the considerations in planning the building have included a means of accommodating the standard-sized elevators most suitable for that building and where previous attention has been given to the disposition of the cars. But, on the other hand, the values listed may also be used to advantage in proportioning the number of elevators required under any conditions, and where the physical aspect of the building does not allow for an economic disposition of the elevators. Any conservative unit area best suited to the conditions may then be allotted for each car, and the number of elevators then determined. Columns 4, 5 and 6 give the numbers of cars for various standard unit areas, while the values in column 7 are computed by Formula (1).

**The Local and Express Round-Trip Time** for different running-speeds given in columns 8, 9, 10 and 11 of Table C, and the value for  $f$  as given by Formula (2) is given in column 12. It will be noticed that in columns 8 and 9 the time occupied in traversing the heights of buildings exceeding eighteen stories is slightly more than would actually prove economical. It might be well, therefore, to point out that the speeds of local elevators for high buildings might be increased to advantage; but whether the service is local or express, it is not advisable to exceed a speed-rate of 600 ft per min. In order to rectify this condition, under the speeds considered, the number of express-elevators must then be more than half the total number in the system, and a subdivision of express-service proper is also necessary. (See, also, Table Showing Number of Elevators Required and notes following, page 1661.)

**Sizes of Hatchways and Car-Platforms.** (See, also, page 1661.) The sizes of elevator-car platforms and hatchways of unit areas heretofore con-




Fig. 7. Typical Layouts for Elevator-hatchways and Car-platforms

red are shown in the following diagrams (Fig. 7) illustrating three typical layouts of modern installations with steel guide-rails. (See, also, Figs. 3 and 4.) The gate or door-opening may be either right-hand or left-hand, as best suited to the planning, structural, or other conditions. The clear inside dimensions of the necessary hatchway are given, and also the clearances required between this and the car. Some of the minimum dimensions given with Fig. 7 and in Table D are slightly from those given with Figs. 3 and 4, page 1666, but agree in the essential requirements.

Table D. Sizes of Elevator-Car Platforms and Hatchways

Dimensions	Area of car-platform					
	25 sq ft		30 sq ft		40 sq ft	
	ft	in	ft	in	ft	in
<i>W</i> =inside width of car.....	6	0	6	3	7	0
<i>D</i> =inside depth of car .....	4	3	4	9	5	1
<i>O</i> =space for operator.....	2	3	2	3	2	3
<i>G</i> =gate-opening .....	3	9	4	0	4	9
<i>HW</i> =hatch-width, car A .....	7	0	7	3	8	0
car B.....	7	4	7	7	8	4
car C.....	7	3	7	6	8	3
<i>HD</i> =hatch-depth, car A .....	5	1	5	7	6	1
car B .....	4	9	5	3	6	3
car C.....	5	2	5	8	6	1




Fig. 8. Motor-sizes for Electric Elevators

**Size of Motor.** It is often helpful to be informed as to the **SIZE OF MOTOR** required for an installation, and the diagram (Fig. 8) may be used for this purpose. For sake of illustration in the use of the diagram, a speed of 400 ft per min is assumed, with a combined load of 2 500 lb. Following the line marked with an arrow from the speed of 400 ft, the point of intersection is then at 2 500 lb. From this point follow the line as indicated to the scale of motor-sizes, and the result is about 40 horse-power.

Table E. Current-Consumption

Motor-size	Starting-current	Running-current
20 horse-power	102 amperes	74 amperes
40 horse-power	202 amperes	147 amperes
60 horse-power	292 amperes	213 amperes

**Current-Consumption.** Table E gives the **CURRENT-CONSUMPTION** of motors common in elevator-practice. The figures are for direct-current motors operating at 230 volts and are based on the results of tests.

**Electric Feeders.** To aid in the selection of well-proportioned **ELECTRIC FEEDERS** for elevator-motors, Table F is given. The figures are for 230-volt, direct-current machines.

Table F. Wire and Conduit-Sizes for Electric Elevators, 2-Wire, 230-Volt, Direct-Current Systems

Motor-h.p.	Wire		Maximum run or distance for 2% drop, ft	Conduit		
	Size of each wire	Underwriters carrying capacity, amperes		Trade size for 2 wires	Inside diameter, in	Outside diameter, in
15	No. 3	80	154	1¼	1.38	1.66
20	No. 1	100	174	1½	1.61	1.90
25	No. 0	125	186	1½	1.61	1.90
30	No. 00	150	198	2	2.06	2.37
35	No. 000	175	212	2	2.06	2.37
40	No. 0000	225	226	2	2.06	2.37
45	No. 0000	225	226	2	2.06	2.37
50	300 000 c.m.*	275	248	2½	2.46	2.87
55	300 000 c.m.*	275	248	2½	2.46	2.87
60	400 000 c.m.*	325	272	3	3.06	3.50

\* Circular mils.

## MAIL-CHUTES

**General Description.** This system of mailing letters by means of a specially constructed chute connected with the receiving-box at the bottom, has come into such general use in public buildings, office-buildings, apartment-houses, hotels, that the restrictions affecting the same and what is required in the way of preparation should be known to architects. The system is installed by patentees, under regulations of the Post-Office Department governing its

construction and location, and for this reason it is well to consult the maker before permanently locating the apparatus on the plans. It may be placed in any building of more than one story, used by the public, where there is a mail delivery and collection-service, in the discretion of the local postmaster, subject to whose approval the contracts are made.

**The Chute and Receiving-Box.** The chute is required to be made with a removable front and a continuous, rigid, vertical support is absolutely necessary. It must be of metal, its front must be of plate glass, and it must bear the inscription prescribed by the department; and the whole apparatus, when erected and a Government lock put on the box, passes under the exclusive care and control of the Post-Office Department, and the chutes become a part of the receiving-boxes. These boxes may be of various patterns and highly ornamented and are furnished by the makers in connection with the chutes. The work of preparing a rigid support for the chute and cutting and finishing the openings in the floor is of the utmost importance, and details showing the usual arrangements are always given.

**Preparatory Work.** The requirements for what the manufacturers of PREPARATORY WORK include a flat, vertical, continuous surface not less than




Fig. 1. Wooden Support for Mail-chute




Fig. 2. Steel Support for Mail-chute




Fig. 3. Alternate Steel Support for Mail-chute




Fig. 4. Preparatory Work Complete for Mail-chute

10 1/2 in wide, extending from the floor of the ground-story to a point 4 ft 6 in above the finished floor in the top story, and an opening in each floor direct in front of and centered upon this surface. These openings are neatly finished and their size and shape determined by setting in them thimbles of iron which



are furnished and delivered by the patentees, as part of their contract. In ordinary installations a casing of wood, suitably molded and finished to match the trim of the building, answers every purpose. Such a casing is shown in plan, fig. 1, with the opening finished by the iron thimble. In buildings, or sometimes in a few stories, where a more elaborate finish is desired, marble is substituted for wood, the form and construction of the casing being adapted to the material, but of course without disturbing the size and form of the front surface. Steel angles are used where the use of wood is objected to, or where it is necessary to run the chute in front of an elevator-screen, or in other locations where a solid wall is not available to support the casing. Steel square-root angles, 2 by 2 by  $\frac{1}{2}$  in in section, are generally used, and set as in Fig. 2, but sometimes, where it is desirable to fill up the space between them and the elevator-screen, they are reversed, as in Fig. 3. The angles are usually bolted to the beams, and in any case must be straightened so that they are without twists or kinks, and the surface which receives the mail-chute plumb and flush in all stories. Fig. 4 gives a general view of the mail-chute casings and floor-openings ready to receive the chutes themselves. This work of preparing the building, except the cutting or saving ready the necessary openings in the floors, is now usually included in the mail-chute contract, as it has been found for many reasons undesirable to separate it. The necessary openings in floors, and all patching around such openings, should be included in the mason's or other proper specifications.

**Essential Points** to be remembered are (1) that no bends or offsets can be made, a vertical fall being absolutely essential, and (2) that the entire apparatus must be exposed to view and must be accessible, that is, it is not permitted to attend the work behind an elevator-screen or partition or through any part of the building except a public corridor.

## REFRIGERATORS \*

**General Requirements.** The following information is given as a guide to architects in providing for refrigerators in large residences, hotels, clubs, hospitals and other institutions. Consultation with a reliable refrigerator-builder, however, is always desirable before deciding upon spaces to be occupied by refrigerators, refrigerating-rooms, etc., as a satisfactory refrigerator cannot be adapted to a badly proportioned space. (See, also, Design of Refrigerators, under Mechanical Refrigeration, page 1691.)

**Residence-Refrigerators.** Care should be taken to select a refrigerator which is simple in operation and easily cleansed, as modern sanitary science has traced much illness to faulty refrigeration. Thorough insulation is an important feature in a refrigerator, as upon this depends economy in the use of ice and the securing and maintaining of the low temperature necessary to the proper preservation of food. Fig. 1 shows a kitchen-refrigerator for use of families of ordinary size. The ice-compartment is located in the middle division. The depth should not be more than 3 ft nor less than 2 ft, and the height may vary from 6 ft 6 in to 7 ft. The length of the front largely determines the capacity and should range from about 4 to 7 ft. Fig. 1 shows, also, a most satisfactory method of accomplishing the outside-icing feature which consists of a double outside icing-door complete, with frame and jamb. This is provided by the refrigerator-builder to fit the rough opening furnished by the owner in the outside wall of

\* Valuable data and the drawings relating to this subject were furnished the author and editor by The Jewett Refrigerator Company, Buffalo, N. Y. Practical data were furnished, also, by The Brunswick-Balke-Collender Company, New York City. There are numerous other reliable firms whose refrigerator-work has the highest reputation.

the building. With this method a minimum outside opening is required to furnish a maximum inside opening for ice. The DRAIN-PIPES should be as short and straight as possible and should be readily detachable for cleansing purposes. The drain should be properly trapped in the floor of the refrigerator and carried through the floor of the building, discharging over the plumber's connection as shown in the elevation of Fig. 1.




Fig. 1.\* Kitchen-refrigerator for Small Family

ments consists of white plate glass for the walls and ceilings and tile for the flooring. The usual complement of refrigerators for use in ordinary families consists of one adjacent to the kitchen and one in the butler's pantry. For large families the number could be the same with the capacity greater.

**Refrigerators for Hotels, Clubs, Etc.** MECHANICAL REFRIGERATION has largely superseded ice as a cooling-agent where the refrigerator-equipment consists of several units, as in hotels, clubs and institutions. (See, also, *Mechanical Refrigeration*, page 1691.) The arrangement of refrigerators is similar to that employed where ice is used, as the refrigerating-coils are often contained in compartments corresponding to ice-compartments; the alternative method is to place the coils against walls of storage-compartments. Refrigerating-coils are generally of 1½-in pipe, the length of coil depending upon the temperature required. Fig. 3 shows a practical layout for the working-department of a

connection as shown in the elevation of Fig. 1.

Fig. 2 shows a refrigerator in use in a butler's pantry where economy of space is important. The ice-compartment is of galvanized steel throughout and is removable for convenience in filling as it slides on roller-bearing runways. When the ice-compartment is replaced in position the outside door closes over it. The adjoining storage-compartment is generally fitted with one removable shelf, below which is a bottle-rack for horizontally placed bottles and a space for standing bottles. The depth should be about 1 ft and the height 2 ft 8 in. under counter-top. The length of the front determines the capacity, but it should never be less than 3 ft. For a double refrigerator with a central ice-compartment and storage-compartments at either side, 5 ft is a convenient length. The exterior finish and hardware should correspond with the adjacent trim. The interior finish for storage-compartments

\* The Jewett Refrigerator Company.

mod-sized club, and illustrates the proper complement of mechanically cooled refrigerators, together with adjacent operating-equipment. No. 1, a store-room refrigerator, has the front arranged in one full-height door and is fitted with three tiers of shelves throughout. No. 2, a meat-refrigerator, is also accessible through full-height door and is fitted with shelves and meat-racks. No. 3, a broiler and fish-refrigerator, has the front arranged in two doors, each door opening onto a series of six galvanized sheet-steel pans sliding on self-sustaining roller-bearing runways. No. 4, a serving-pantry refrigerator, is divided by an insulated partition into three separate and distinct compartments, those at the left and right being each accessible through two doors, while the middle compartment is accessible through one door, below which is a series of four drawers sliding on self-sustaining roller-bearing runways. The doors open onto removable shelves throughout. No. 5, an ice-cream refrigerator, occupies a position in the serving-pantry counter and has the top arranged in one lift-cover. Its interior fittings consist of three 20-quart porcelain-lined ice-cream jars and one glacé-frame for icy forms of ice-cream. No. 6, a pastry-refrigerator, has the front arranged in four doors, two upper doors opening onto removable shelving, and two lower doors onto pastry-pans sliding on angle-iron runways. No. 7, a bar-refrigerator, is subdivided by an insulated partition into two separate and distinct compartments, each accessible through four doors. The upper doors open onto three tiers of removable shelves for standing bottles, while the lower doors open onto five tiers of racks arranged specially for horizontal bottles. The equipment described above will also satisfactorily cover the requirements of a moderate-sized hotel.

**Refrigerators for Hospitals.** The usual complement of refrigerators for all hospitals consists of one large storage-refrigerator, one refrigerator for the chef's use in or near the kitchen, one for milk and butter and one iron-lined chest for broken ice. For large hospitals the same number with increased capacity and with the addition of small diet-kitchen refrigerators, and possibly a mortuary-refrigerator for two or three bodies, will meet the requirements.

**The Height of Large Refrigerators** for hotels, clubs and institutions, to be entered through full-height doors, should be from 10 to 12 ft, if equipped with overhead ice or coil-compartments; with side ice-compartments or coils placed against walls, the height should be 7 ft 6 in or 8 ft. The smaller refrigerators,




Fig. 2.\* Refrigerator for Butler's Pantry




Fig. 3.\* Plan of Refrigerators for Large Club-house

\* The Jewett Refrigerator Company.

possible through half-height doors, hinged covers, drawers, etc., should be placed on a 3-in sanitary cement platform finished with cove to floor of building. These refrigerators should not be higher than 6 ft 6 in unless provided with overhead ice or coil-compartments, in which case the height should be from 7 to 9 ft.

**Insulation.** (See, also, The Value of Good Insulation, page 1690.)

Mortuary refrigerators in modern hotels, clubs, institutions, etc., are insulated with government-standard corkboard, the large refrigerators being constructed of 4-in cork throughout, in two courses of 2 in thickness, and with all joints broken. Cork is applied to adjacent walls of a building with Portland cement,  $\frac{1}{2}$  in thick, and this cement is used, also, in applying the inner course of cork to the outer course in walls, partitions and ceilings. All work in the flooring is asphalted water-tight. Interior finish may be of Portland cement throughout or of galvanized sheets on walls and ceilings and of Portland cement on floors. For the walls and ceilings may be of enameled-on porcelain or white plate glass, and the floors of tile, all depending upon the grade and character of the building to be equipped. The insulation of smaller refrigerators consists of (1) an exterior course of  $\frac{3}{4}$ -in tongued and grooved lumber, (2) two courses of water-proof insulating paper and (3) a 3-in thickness of sheet cork in two  $1\frac{1}{2}$ -in courses, all joints being broken. To this insulation is applied the interior lining.

**Mortuary-Refrigerators.** Mortuary-refrigerators should be cooled by mechanical refrigeration, the coils being placed longitudinally on both sides of the mortuary-trays. Fig. 4 illustrates a mortuary-refrigerator for three bodies. This may be used as a unit in designing mortuary-refrigerators of larger capacity, or the height may be reduced to 5 ft and the bodies placed in two instead of three horizontal tiers. Mortuary-refrigerators sometimes have both fronts finished and equipped with doors so that bodies are accessible for identification or examination from both fronts.

\* The Jewett Refrigerator Company.





Fig. 4.\* Mortuary-refrigerator

## MECHANICAL REFRIGERATION \*

### A Brief Description of Methods in Common Use for Producing and Applying Refrigeration, with Special Reference to Small Plants

A **British Thermal Unit**, (Btu), is the quantity of heat required to raise the temperature of 1 lb of water 1° F. Heat used in this way, that is, to raise the temperature of water or other substance, is said to be present in that substance as **SENSIBLE HEAT**, or, in other words, heat, the presence of which we can feel, or sense.

The **Heat of Liquefaction**, or so-called **LATENT HEAT OF LIQUEFACTION** of a mass of ice, is the amount of heat it will absorb in melting. One pound of ice at 32° F. will absorb 144 Btu in melting to water at 32° F. Heat coming into a cake of ice is thus absorbed in melting the ice and becomes what is known as **LATENT HEAT**, or heat absorbed without any rise in temperature. If the ice is at a lower temperature than 32° F., or if the water resulting from the melting rises above 32° F., additional heat will be absorbed as **SENSIBLE HEAT**.

The **Specific Heat** of a substance is the ratio of the quantity of heat required to raise the temperature of a certain weight of the substance one degree to that required to raise the same weight of water from 62° to 63° F.

The **Heat of Vaporization** of water or of any other liquid is the amount of heat it will absorb in vaporizing, in evaporating from a liquid to a gas, or in giving out in returning from the gaseous to the liquid state.

**Transfer of Heat** occurs in three ways: (1) by convection, (2) by radiation and (3) by conduction. For instance, if particles of air in a refrigerator adjacent to a source of heat become warmed they circulate and distribute the heat by **CONVECTION** through the refrigerator-box. Heat will pass from a warm substance, as from the filament of an incandescent lamp, out into the box by **RADIATION**. Heat will enter the box through the walls by **CONDUCTION**.

**Heat-Transmission.** When the temperatures on opposite sides of any surface, as for instance, a wall, are unequal, heat will pass by conduction through the material from the warmer to the cooler side. The rate of this movement is called the **RATE OF HEAT-TRANSMISSION** and is stated in terms of the quantity of heat (Btu) which will pass through 1 sq ft of surface in 24 hours, per degree temperature-difference between the two sides of the wall.

### Some Advantages Claimed for Mechanical Refrigeration.

- (1) Lower temperatures can be obtained with refrigerating-machines than with ice.
- (2) The inconvenience of handling ice is avoided.
- (3) There is no accumulation of slime in the refrigerators as from the melting of even the best ice.
- (4) Refrigerators cooled mechanically are dryer than ice-cooled boxes because the moisture is frozen out of the air and deposited on the cooling surfaces.
- (5) There is generally a better air-circulation, resulting in a more uniform temperature and dryer atmosphere throughout the compartment.
- (6) With proper design of refrigerator and refrigerating-machine any desired temperature can be obtained.
- (7) Refrigeration produced mechanically is often cheaper than refrigeration produced by melting ice. (See page 1695.)

\* Compiled and adapted, by permission, from data included in a paper by R. F. Mann, Sec., also, *Refrigerators*, pages 1679 to 1683.

**Operation of Refrigerating-Machines.** In almost all methods of producing advantage is taken of the fact that when a liquid evaporates it usually cools itself and its surroundings, and changes into a gas or vapor. There are many liquids which are easily made to evaporate and produce this cooling effect, and were it not for their cost, refrigeration could be very simply produced by applying a steady stream of the liquid and allowing the vapor or gas evaporated to escape into the atmosphere. A refrigerating-machine is practically an apparatus for saving this gas which has evaporated and returning it to its liquid state to be used over again. In this process of recovery and condensation the machine gives out the heat which it has previously absorbed in evaporating. This heat is carried away by flowing water, which, in absorbing the heat, rises in temperature.

**Types of Refrigerating-Machines.** In the (1) COMPRESSION-TYPE of refrigerating-machines the recovery of the gas is effected by drawing it away from the point where it has been evaporated and pumping it under increased pressure into a chamber where it gives out its heat to the water-cooled walls of the chamber and returns to the liquid state ready to be used over again. In the ABSORPTION-TYPE of refrigerating-machines ammonia is generally used and the recovery of the gas is effected by bringing it into contact with water with which it unites chemically. The solution thus formed is pumped into another chamber, and heat is applied to drive off the ammonia-gas which is then condensed under high pressure. It is now ready to be reevaporated and reproduce its cooling effect. In all cases of large units, and in all cases of either large or small plants where exhaust-steam is available in sufficient quantities, absorption refrigerating-machines are very economical.

**Liquids Used in Refrigerating-Machines.** A number of liquids have been used in refrigerating-machines, the ones commonly employed being (1) AMMONIA, (2) CARBON DIOXIDE and (3) SULPHUR DIOXIDE. Various practical considerations determine which is to be used in any particular design of machine. With (1) AMMONIA the advantage is the lower working pressures, from 15 to 100 lb per sq in, which are easy to deal with. An advantage over carbon dioxide is that leaks are very easily located. Ammonia-fumes, however, are offensive and sometimes dangerous in case of a break. With (2) CARBON DIOXIDE the advantage is in its inoffensive odor. Its disadvantages are the high pressure at which it works, from 300 to 1200 lb per sq in, the relative difficulty of holding these pressures and of finding small leaks, owing to its slight odor and chemical activity. With (3) SULPHUR DIOXIDE the advantage is its comparatively low working pressure, which is not above 75 lb per sq in. Its great disadvantage is that with moisture it forms an acid which rapidly corrodes the apparatus. At one time this disadvantage was fatal, since with the old-type machines, air and moisture were constantly being drawn into the system more or less rapidly and mixed with the sulphur dioxide. This difficulty has recently been overcome in the modern types of machines \* in which the refrigerant is hermetically sealed in the machine and chemical action, therefore, prevented.

**Rating of Refrigerating-Machines.** A 1-TON REFRIGERATING-MACHINE is a machine which, if operated for 24 hours, will absorb the amount of heat which one ton of ice would absorb in melting. If the machine is operated a shorter time each day, a less amount of heat will of course be absorbed, and in order to maintain the temperature during the period when the machine is not running, some

The Audiffren Refrigerating-Machine, a small machine intended for domestic uses, is manufactured by Johns-Manville, Inc., New York. There are many other reliable firms making refrigerating-machines of other distinct types, and the architect should look carefully into the merits and claims of each when called upon to specify them.

means must be adopted for storing cold. (See paragraph below.) Refrigerating machines are sometimes rated in terms of ICE-MAKING CAPACITY, that is, in terms of the amount of ice the machine will make in 24 hours. This is always less than the refrigerating capacity because some refrigerating effect is required to cool the water down to  $32^{\circ}$  F. before the freezing can begin, and the ice is usually cooled several degrees below  $32^{\circ}$  F., which requires a still greater capacity. There is also some flow of heat into the apparatus. These elements vary considerably so that from some points of view ICE-MAKING CAPACITY might be considered an unsatisfactory method of rating some refrigerating-machines.

**Applying the Cold.** According to one classification there are three common systems of applying the cold. These are, (1) the DIRECT-EXPANSION SYSTEM, (2) the BRINE-SYSTEM and (3) the COLD-AIR SYSTEM.

(1) In the DIRECT-EXPANSION SYSTEM the refrigerant is evaporated in a coil of pipe placed directly in the room to be cooled.

(2) In the BRINE-SYSTEM the refrigerant is used to cool brine, which is then circulated through coils of pipe in the room to be cooled.

(3) In the COLD-AIR SYSTEM a current of air is chilled by passing it over a coil of pipe cooled directly by the evaporating refrigerant, or by brine, or by passing it through a spray of cold brine; and this chilled air is then passed into the room and circulated back to the cooling-coils, the whole operation being repeated indefinitely.

All of these systems have their advantages and disadvantages. While the brine-system is a little more expensive to operate in large plants, the temperature is more easily controlled than with the direct-expansion system, and in practice in small plants it is found as economical in operation in spite of its theoretical disadvantage. Furthermore, in case of any breakdown in the machine, the temperature can be held for a time by circulating the brine until it becomes too warm to be of use, whereas with direct expansion the temperature will begin to rise immediately upon the stopping of the machine. The cold-air system is not as applicable where any drying of the goods stored would be harmful and there is some risk of carrying fire in the air-passages. It is much more expensive nevertheless, for such service as chocolate-dipping rooms, ice-cream hardening, fur-storage, etc.

**Storage of Cold.** When temperatures are to be maintained while the refrigerating-machine is shut down, COLD must be STORED. In the brine-system this is effected by cooling a comparatively large body of brine which warms slightly as it is circulated. Where the brine-circulating pump as well as the machine must be stopped, so-called PRESSURE-TANKS may be placed in the piping system in the room being cooled; the mass of brine in these tanks absorbs the heat and helps to maintain an approximately even temperature. Where the direct-expansion system is used, a part of the cooling-coils may be immersed in a tank of brine placed in the room and the remainder of the coils arranged for the direct cooling of the room. In some places the spaces available will not permit the use of brine-storage tanks. In cases of this kind smaller tanks may be used and filled with water, or a weak brine which will freeze at a temperature a little below  $32^{\circ}$  F. Since 1 lb of ice in melting will absorb 144 Btu and 1 lb of brine rising in temperature, say  $20^{\circ}$ , will absorb only from 14 to 16 Btu the saving of space is apparent. It must be absolutely certain that the refrigerant reaches the tank first at the bottom and that the air to be cooled reaches it first at the top so that the ice in forming shall not bulge or burst the tank. If the congealing mass were to freeze from the top down the tank would be strained and finally leak, because of the expansion of the ice in freezing. Another fact to be considered is that where water, only, is frozen, a resulting high



temperature may be obtained in the refrigerator, since the brine must be warmer than the ice in order to melt it, and the refrigerator just that much warmer, or warmer than an ice-cooled box. In calculating the proper sizes of tanks for storing brine, it should be remembered that, usually, the period during which the machine is shut down coincides with the period during which the demand for refrigeration in the box is the least. The amount of heat to be absorbed is usually only that entering through the insulation, as the doors are shut and no food is put in or removed.

**Description of Refrigerating-Machines.** As explained in the preceding paragraphs refrigerating-machines may be divided generally into two classes, (1) the COMPRESSION-TYPE and (2) the ABSORPTION-TYPE.

(1) **The Compression-Type of Refrigerating-Machines** may be subdivided as follows:

(a) The open type of machine, which is made both vertical and horizontal, and both single and double-acting, that is, compressing the gas at one end or both ends of the cylinder. (b) The partially enclosed type of machine, in which all the moving parts of the compressor proper are enclosed within the frame of the machine, except the fly-wheel and the main shaft which enters the frame of the machine through a stuffing-box. Such valves, also, as are required for the system are exposed. (c) The wholly enclosed type of machine,\* in which all of the working parts are enclosed in a hermetically sealed container.

(a) One advantage of the open type of machine is that any lack of adjustment due to wear can be readily corrected; so that, with proper attention, it gives excellent results. For large installations this is considered by many to be a most efficient type of machine.

(b) The enclosed type of machine resulted from the effort to reduce the amount of attention required by the open machine, to cheapen its construction and to reduce the possibility of trouble from inexperienced tampering. An objection to machines of this type is that when adjustments have to be made the working parts are relatively inaccessible.

(c) With the wholly enclosed type of machine it is claimed that the loss of the refrigerant is prevented by the hermetical sealing of the apparatus, and that the working parts, being completely enclosed, are protected from deterioration due to outside causes or tampering.

(2) **The Absorption-Type of Refrigerating-Machines** are of two kinds, differing principally in the proportioning of the parts. In the one machine high-pressure steam is used; in the other the proportions are such that low-pressure exhaust-steam may be used. Where exhaust-steam is available machines of this type are found to be very economical, and this is true, also, for all large units whether or not exhaust-steam is used. Full descriptions of these machines, with detailed plans and layouts may be obtained from the various manufacturers.

**Calculations for the Capacity of a Refrigerating-Machine.** Heat enters the refrigerated compartments, (1) through the walls, (2) with warm goods, (3) by the interchange of the outside air when doors are opened and by air-leaks, (4) since the cooled air is the heavier and immediately flows out when a door is opened, (4) from lights or from the heat of the bodies of workers, and (5) from any change of state occurring in the goods, such as freezing, fermenting, etc. In large rooms these various sources of heat should be analyzed separately. In small refrigerators, as in hotels, kitchens, dwellings, etc., a rough estimate, quite as accurate as a more elaborate analysis, allows a certain number of Btu per cubic foot of refrigerated space per 24 hours. This amount varies

\* Referred to on page 1685.

with the character and location of the box, the nature of its insulation, the temperatures desired and so on. It will be seen that the insulation, while of great importance, is not by any means the only important factor in this class of boxes. For domestic refrigerators in which a temperature of from 35 to 50° F. is maintained, 300 Btu per cu ft of refrigerator per 24 hours should be allowed. For boxes in hotel or restaurant-kitchens, 600 Btu, or even 900 Btu in extreme cases and where low temperatures are required, should be allowed. For butchers' coolers or large storage-boxes in hotels, etc., from 200 to 250 Btu per cu ft per 24 hours should be allowed. A check on the above figures for the large type of box is the following: \* "When the exact conditions under which cold-storage rooms are to be operated are known, namely, the size and shape of the rooms, the quality of the insulation, the kind and quantity of goods to be handled per day and the temperatures at which they are received and at which they are to be held, the amount of refrigeration required can be estimated very closely by the following rule: (1) Calculate the exact area of exposed surface in the walls, floor and ceiling of the room in square feet, multiply the total number of square feet by the number given in the table for the required temperature and divide the product by 288 000. (2) Multiply the amount of goods in pounds, to be stored per day by the number of degrees of heat to be extracted by the specific heat of the goods, and divide by 288 000. This will give the amount of refrigeration, in tons per day, necessary to maintain the temperature required for the goods. (3) Add these two amounts together. The total will be the amount of refrigeration, in tons per day, required to maintain the temperature required for the goods and for the room. (4) If the goods are to be frozen, the latent heat of freezing should be added to the number of Btu to be extracted."

For rooms containing less than 1 000 cu ft

If maintained at 0° F. multiply the exposed surface by	1 775
If maintained at 5° F. multiply the exposed surface by	710
If maintained at 10° F. multiply the exposed surface by	535
If maintained at 20° F. multiply the exposed surface by	355
If maintained at 32° F. multiply the exposed surface by	265
If maintained at 36° F. multiply the exposed surface by	180

For rooms containing from 1 000 to 10 000 cu ft

If maintained at 0° F. multiply the exposed surface by	1 250
If maintained at 5° F. multiply the exposed surface by	600
If maintained at 10° F. multiply the exposed surface by	300
If maintained at 20° F. multiply the exposed surface by	190
If maintained at 32° F. multiply the exposed surface by	160
If maintained at 36° F. multiply the exposed surface by	125

For rooms containing more than 10 000 cu ft

If maintained at 0° F. multiply the exposed surface by	1 100
If maintained at 5° F. multiply the exposed surface by	550
If maintained at 10° F. multiply the exposed surface by	275
If maintained at 20° F. multiply the exposed surface by	180
If maintained at 32° F. multiply the exposed surface by	140
If maintained at 36° F. multiply the exposed surface by	110

\* Taken from Levey's Refrigeration Memoranda, page 41.

With small machines it is necessary to allow a greater capacity of machine for a given size of box than with large machines, since, with the latter, one can always throw a large part of the machine-capacity to any given box where special need may exist; whereas to do this with the small machine would almost certainly rob some other box, if indeed there happened to be another box. It is never possible to determine with mathematical certainty exactly how much refrigeration is required for a given case. It is best to allow for this fact and be sure the machine is amply large. Where an existing ice-cooled box is to be cooled mechanically one check upon the size of the machine required is the amount of ice used. This check is more apt than any other, however, to lead to erroneous conclusions unless the figures are properly analyzed.

**Another Method of Determining the Capacity of a Refrigerating-Machine.** The following is a method that gives good results, except that allowance may be made in the larger boxes and where brine-storage tanks are provided in the box for the steadying effect of the mass of cold brine:

(1) The ice-consumption for the hottest month of the year should be determined. This will give the average ice-consumption for that month.

(2) The average temperature that is maintained in the box with ice should be accurately determined. This will usually be from 55 to 65° F. It will commonly be stated to be anywhere from 40 to 45° F., but these temperatures are seldom obtained. Even if they are, with a full ice-chamber and the box closed for long periods the average will be above these figures. Unless, therefore, there is positive assurance to the contrary, from 55 to 60° F. should be considered the average temperatures.

(3) A calculation should then be made of the heat-inflow through the insulation, with a temperature of 55° F. in the box and with the average summer temperature outside. The difference between the heat-inflow through the insulation and the total heat actually absorbed by the melting of the ice is the amount entering the box from other sources than through the insulation. This excess of heat ordinarily occurs during the hours of daytime only, that is, when the box is being opened, since at night the box will remain closed. A machine of sufficient capacity to produce the temperature actually obtained with ice must, therefore, be of larger rated capacity than that indicated by the actual ice-consumption; and how much larger it should be can be determined by this method.

(4) A further fact which it is claimed should be taken into account in determining the proper size of a machine is that temperatures obtainable with ice are often unsatisfactory. If they were always satisfactory one reason for putting in cooling-machinery would be done away with. Where 55° F. is obtained with ice, from 35 to 45° F. will be required with mechanical cooling and the machine-size must be further increased in the ratio of the temperature-differences between average summer temperatures and 35° F., and average summer temperatures and 55° F.

(5) The cooling-machine if installed in accordance with these figures would handle average-weather conditions but would not be adequate for extreme weather conditions, the most important conditions to be met by cooling-machinery. It is necessary, therefore, to further increase the size of the machine in the ratio of the difference in temperature between maximum summer temperature and 35° F., and average summer temperature and 35° F.

(6) A further allowance should be considered, namely, the fact that in many cases, for one reason or another, it is not possible, or else not desirable, to operate the machine except during certain periods of the day, and the machine-size must be increased as much as may be required to take care of these conditions.

(7) If the machine is not placed directly at the box to be cooled, allowance must be made for the heat-inflow into the insulated brine-mains. The amount of heat entering from this source is often of considerable importance, particularly with small machines. The table below gives heat transmissions for oil-pipe-covering and some other materials.

**Water and Milk-Cooling.** Mechanical refrigeration as applied to cooling water and milk differs in one respect from other classes of refrigerating-machines. A relatively intense quantity of cooling effect is called for in a brief interval of time. For instance, in a drinking-water system the heaviest requirement may come at the noon-hour. In a bakery, also, the demand for chilled water will be intermittent, a large quantity of water being required for the dough-mixing. In dairy-work the milk must be cooled very rapidly to check the development of bacteria which grow with incredible rapidity within the temperature-range of from 110 to 50° F. To install a large enough refrigerating machine to produce the required cooling effect as it is needed would in most cases call for a very large machine. This is overcome by using a smaller machine and allowing it to operate for a longer time, say throughout the day, storing the refrigerating effect produced by cooling a large body of brine or melting the ice as rapidly as may be required. For instance, if 50 cans of milk, of 40 qts each, are to be cooled from a temperature of from, say, 75 to 35° F., in 1 hour, the refrigeration required will be 50 cans times 40 qts times 2 lb per qt times (75° F. - 35° F.), which equals 320 000 Btu. Milk is treated in the calculation as having the same specific heat as water, since water is so large a percentage of its total weight. This amount of refrigeration produced by a machine running 12 hours per day would require the machine to absorb 320 000 Btu divided by 12, or 26 000 Btu per hour. The quantity of brine necessary to store the cooling effect may be calculated closely enough for practical purposes by using the following approximate figures. The specific heat of brine is 0.75. The weight of the brine is 9 lb per gallon. The permissible temperature-range of the brine depends upon the conditions and may vary from, say, 30 to 15° F., or lower. In other words, the temperature to which the brine can be permitted to rise is limited to the temperature it must produce in the room or in the substance being cooled, and the temperature to which the brine can be cooled in storing cold is limited by the decrease in economy of the refrigerating-machine at the low temperatures.

**The Value of Good Insulation.** (See, also, Insulation, page 1683.) The importance of good insulation cannot be too strongly emphasized. A cold storage room or refrigerator and its contents may be cooled by ice or mechanical means, but unless the walls are adequately insulated, the demand caused by the inflow of heat through the poor insulation may be more than the supply or refrigerating-machine can meet to maintain the required temperature. The almost universal standard of insulation for cold-storage rooms is a 4-in thickness of pure-cork sheet. The following table shows the heat transmitted through 1 in thickness of each of the substances, per square foot of exposed surface per degree difference in temperature per 24 hours.

Pure-cork sheets.....	6.4 Btu
Hair-felt.....	7.3 Btu
Impregnated cork boards.....	8.5 Btu
Rock-wool blocks.....	8.0 Btu
Waterproofing lith-blocks.....	8.5 Btu
Spruce, clear and dry.....	16.0 Btu
White oak.....	26.0 Btu

**Design of Refrigerators. Disposition of Cooling-Surfaces.** (See, also, Subject of Refrigerators, page 1679.) No attempt need be made to describe all the many arrangements of refrigerated compartments that are to be found in service. The intention is to point out some of the more important things to be considered in determining upon the design of a box. It is desirable in a refrigerator to produce not only a low temperature, but a relatively dry atmosphere.

**Cooling-Surface and Temperature.** Securing the low temperature is merely a question of supplying sufficient cooling-surface to produce the desired results with the temperature available in the refrigerant. The amount of surface required is influenced by the arrangement of the box, that is, whether or not the air passes freely or sluggishly over the surface, whether the cooling-surface is placed on the ceiling or walls of the compartment or in a loft and, if the latter arrangement is used, whether or not the air-passages are of proper size and the circulation between the loft and the compartment sufficient.

**Dryness of Atmosphere and Temperature.** To secure a box of satisfactory dryness it is necessary to have a relatively low temperature in the refrigerant. The air which passes over the cooling-surfaces is practically in a saturated condition when it leaves them. If it is to be dry at the temperature required in the box, it must have been, necessarily, cooled well below the box-temperature. For instance, in a box, the temperature of which is maintained at 35° F., the refrigerant should be run at a temperature of from about 20° to 25° F. It is further desirable to so locate the cooling-surface that frost in melting will pass out of the box quickly and not remain to be reabsorbed by the air in the box.

**Arrangements of Cooling-Surfaces.** There are several common arrangements of cooling-surfaces in refrigerators. Sometimes the coils are arranged overhead, or directly in the compartment to be cooled. This is one of the efficient ways in which a cooling-surface can be arranged, so far as the cooling effect alone is concerned. It is not, in general, a good arrangement, however, since frost melting from the coils drips on the goods. In another arrangement the cooling-surfaces are on the wall. This is preferable to the ceiling-arrangement, as far as the dripping is concerned. The objection to it is that goods placed close to the walls are apt to be overchilled, while goods nearer the center of the compartment are not cooled quickly enough. It also wastes floor-space, because packing goods close to the coils is not practicable on account of possible overchilling and also on account of the liability of retarding the air-circulation. The wall-arrangement for cooling-surfaces is, nevertheless, often the most practical method. Another method involves a modified form of wall-coil arrangement in which a brine-storage tank is used to assist in maintaining the temperature when the machine is shut down. A further modification is often introduced, in which a partition or baffle-plate is used in front of the coils. The best types of box-arrangement are those in which the cooling-surface is separated from the storage-space and is so arranged as to secure an active circulation of the air over the coils and through the compartments. In all of these plans the one requirement calling for the greatest care is that the air-passages shall be as direct as possible and of ample size. The force causing the air to circulate, namely, the difference in weight due to differences in temperature and density between the column of air in the coil-compartment and that in the storage-compartment, is so extremely small that any slight interference is a serious matter. An extra turn in the passage or a slight reduction in the size of the passage will produce a marked effect. A good rule to follow is to make the passage as large as it can be made without allowing any drip to reach the storage-compartment. This will work out in many cases to show a ratio of

1 to 8 or 9 between the area of the passage and the floor-area of the compartment; but even 1 to 6 is just that much better if it can be secured. The art of proportioning the size of the air-passages is of much less importance when the air is circulated by fans. Forced circulation is not usual, however, even in large storage-refrigerators, and no attempt will be made here to consider it. One precaution that must be taken in arranging the cooling-surface, especially in small and frequently opened boxes, is the avoidance of any undue cooling of walls or ceilings that are exposed to currents of warm air when the door is opened. Moisture from the incoming air deposits on these surfaces and causes the offensive so-called SWEATING of the box. This is most often seen on the storage-compartment side of uninsulated coil-compartment floors or partitions and also occurs on walls or ceilings where the cooling-pipes are set very close to these surfaces. The obvious and effective cure is to insulate the partitions between coil-compartment and storage-compartment and keep cooling-surfaces well away from walls or ceilings, from 3 to 8 in, depending upon the temperature of the brine.

**Incidental Notes on Refrigerators. Drawers.** In restaurant-kitchens and elsewhere it is sometimes convenient to have a box fitted with a number of refrigerated drawers. The heat-leakage through the many joints, through slides which are invariably only partially closed, and through the poor insulation of the drawers, is very great. Where it is at all possible to do so, it is best to arrange an insulated door covering the entire drawer-space.

**Anterooms.** In storage-rooms of medium to large size the air-interchange due to opening doors is reduced to a minimum by arranging an anteroom or entry which, after it is entered, has its outer door closed before the door to the storage-room proper is opened. Where two rooms are side by side, it is often possible to reduce the interchange of air by treating the one room as an anteroom of the other, having but one door to the outside air.

**Doors.** Special note should be made as to the design of doors for refrigerator-rooms or boxes. There is a common idea that a refrigerator-door should be beveled. As a matter of fact no more certain means of ensuring air-tightness could be devised. A perfectly fitted beveled door, hung accurately in place, could perhaps be made tight in the beginning. This door in service at once begins to sag, since a refrigerator-door is always heavy. It immediately becomes impossible to force it to a tight seat and continuous leakage of air begins. A refrigerator-compartment door is most readily made tight by having a flat surface on the door come up against a corresponding surface on the frame, with a soft gasket of some kind between them. There are several well made refrigerator-doors on the market at prices low enough to make it doubtful economy to attempt the home-made article.

**Arrangement of Brine-Mains.** In laying out mains to carry brine from the refrigerating-machine to the refrigerator, there are a few simple points to be cared for. For the convenience of the pipe-covering man, the flow and return lines should be placed far enough apart so that he can get his covering over each pipe without cutting it to pieces, or else they should come close together so as to be covered together. A common difficulty experienced in brine-systems of refrigeration, where the cooling-coils in several compartments are fed from the same main, is that when the adjustment of the valve controlling the flow of brine through one coil is changed, it upsets the adjustment of the whole system. This is due to too small mains or too small a pump, or both. A similar action is observed when the opening of a faucet on a water-pipe checks the flow from other open faucets on the line. The ideal cross-section area is

brine-mains is as nearly as possible equal to the combined cross-section of the coils which they serve at any one time. Even with this proportion, however, it is not possible to absolutely ensure that the lower coils will not rob upper ones, or even drain them completely in some systems of piping. A more effective, even if somewhat expensive method of overcoming this difficulty, is by the addition of a third main. In this arrangement it is not possible for one coil to rob another to the point of draining it.

**Calculations for the Necessary Amount of Cooling-Surfaces.** No simple and fast rule can be given regarding the proper amount of cooling-surface for compartments of various sizes, since the design and arrangement of the cooling-surface and the freedom with which the air circulates over it greatly affect the amount required. As a general guide, however, and where the conditions are such as to permit a good circulation of the air, the following formula will give good results. It will be understood, of course, that the refrigeration required in the given room has been determined as previously indicated. The cooling-surface required, in square feet, per ton of refrigeration equals  $100/(T - t)$  in which  $T$  is the temperature desired in the compartment, and  $t$  the average temperature of the brine.

#### Approved Cold-Storage Temperatures

Articles stored	Degrees Fahrenheit
Ref.	36 to 40
Lamb and mutton.	32 to 36
Eggs.	29 to 32
Fruit.	34 to 36
Vegetables, in pickle or brine.	35 to 40
Butter, must be kept separate from other goods.	0 to 38
Butter.	29 to 32
Cheese.	32 to 34
Hard.	38 to 40
Poultry, to freeze.	5 to 10
Poultry, when frozen.	25 to 28
Fish, to freeze.	5 to 10
Fish, when frozen.	25 to 28
Fish, retail fish-counters should be cooled with ice rather than mechanically.	25 to 28
Wursts.	33 to 45
Meat.	33 to 42
Meat.	40 to 45
Meat.	30 to 40
Fruits.	33 to 36
Vegetables.	34 to 40
Canned goods.	38 to 40
Flour and meal.	40
Wine.	25 to 32
Machine for ice-cream freezing.	5 to 10
Ice-cream, air-hardening.	5
Ice-cream, serving-temperature.	14 to 16

**Ice-Making.** If the following facts of physics are kept in mind in considering methods of making ice the results obtainable may be understood or predicted:



- (1) Chemically pure water will freeze solid and clear.
- (2) Water containing impurities in solution tends in freezing to force the impurities out of solution. The slower the process of freezing the more completely is the purification effected.
- (3) Ice forming in still water sends out long slender crystals which increase in number and size, forming a meshwork that gradually becomes a solid mass.
- (4) Agitation of water during freezing aids in the separation of impurities and therefore in forming solid, clear ice.
- (5) Practically all natural waters contain more or less organic or inorganic material in solution and invariably contain air in solution. These substances are, therefore, frozen out of solution and tend to cause the ice formed to be opaque, the lighter substances tending to rise and collect near the surface, and the heavier ones tending to sink.
- (6) The rate of freezing of ice decreases as the thickness already formed increases, so that the time required to freeze increases as the square of the thickness to be frozen. In the formation of natural ice the freezing is from the top down and impurities frozen out of solution float to the surface. This and the motion of the water, especially in quiet running streams, tends to make naturally frozen ice transparent. American manufacturers of ice have always tried to duplicate this clearness.

**Methods of Ice-Making.** The method first adopted in this country was the one in which DISTILLED WATER was used. From a sanitary point of view such ice would be theoretically ideal. Practical difficulties make it almost impossible to secure pure ice in this way. Some of these difficulties are:

- (1) Removal of oil from the distilled water, this oil being picked up as the steam passes through the cylinder of the engine. It is difficult to remove organic oil which is present in the lubricant.
- (2) Assurance that the filters are in proper shape, an assurance often impossible to obtain since this apparatus is ordinarily used the season through without overhauling.
- (3) Possibility of contamination in the storage-tank where the distilled water is held and usually PRECOOLED to as near 32° F. as possible, before passing to the freezing-cans, thus saving time in the freezing process in the tank.
- (4) Possible contamination from handling the cans and the wooden covers over them. These covers form the top of the freezing-tank in which the cans of water are immersed in cold brine for freezing and are tramped over by the ice-harvester with the consequent possibility of dirt getting into the cans.

A second system of ice-making in common use in this country is the PLATE SYSTEM. In this process the ice is formed on vertical steel plates. Natural or raw water is used and the bath is agitated by various methods. The resulting ice is very clear and dense. In this system when the ice is formed to the desired thickness, usually about 12 in, it is loosened from the freezing plate by various thawing-arrangements in different forms of the apparatus. The ice-plates, often 9 by 16 ft by 12 in in thickness, are lifted from the bath by overhead cranes and carried to a table where they are cut to common sizes. While the plate process is usually very slow on account of the fact that the freezing is from one side only, it is largely used and lends itself to great economy in steam-consumption, whereas in the old-style distilled-water ice-making plant the amount of steam required to make the ice was more than



nomical engine would use and it was not possible to obtain fuel-economy. The modified form of this system, now coming into considerable favor, is arranged so that STATIONARY CANS are filled with raw water and kept agitated with compressed air bubbling up through it. When the freezing has progressed somewhat the remaining water is drawn off and replaced by fresh water, thus removing the greater part of the impurities that have been frozen out of solution. Various other modifications of these two systems of ice-making have been and are being developed. All of them depend, however, upon the series of physical facts stated in the preceding paragraphs, and the results may be analyzed by reference to them.

### Relative Economy of Producing Refrigeration Mechanically and by Ice.

(1) In determining the cost of REFRIGERATION BY ICE, account must be taken not only of the cost of the ice but of melting, of the uncertain ice-harvest, of the amount of ice left over at the end of the season and of that ice frozen together in the storage and, therefore, practically useless. Regarding melting, it may run anywhere up to 50% of the total ice-harvest. The quantity left over at the end of the season is, of course, so variable that it is impossible to estimate it, this being purely a matter of chance. In many cases, however, it is a very large item. The loss by the ice freezing together in the storage can be reduced to a very small amount where the ice is properly packed with distance-strips between the ice-cakes. Proper packing is much more readily carried out, however, where artificial ice is stored than where natural ice is held, and a mechanically cooled ice-storage is less subject to this difficulty, since the temperature is, of course, constantly held below the melting-point of ice. (2) The total cost of REFRIGERATION PRODUCED MECHANICALLY includes the cost of power, water, oil, refrigerant (usually ammonia), labor, and attendance, and interest and depreciation on the investment. The figures for these items vary between wide limits. The following figures, however, will be of interest. Care should be taken in drawing conclusions from them as to the cost in prospective installations. These figures are from the annual cost of an ice-manufacturing company having a capacity of 1 500 tons per day in plants ranging in size from 50 to 100 tons per day each.

Coal.....	40 cts per ton of ice produced.
Labor.....	50 cts per ton of ice produced.
Ammonia.....	10 cts per ton of ice produced.
Water.....	5 cts per ton of ice produced.
Waste, power, oil, etc.....	10 cts per ton of ice produced.
Total.....	\$1.15 per ton of ice produced.

## TOWER-CLOCKS \*

**Rule for Diameter of Dials.** "To look well and show plainly, dials should be 1 ft in diameter for every 10 ft of elevation and should set out flush with or close to the line of the building or tower." †

**Dimensions of Some Large Clock-Faces.** Colgate's Factory, Jersey City, N. J. The diameter of the dial is 40 ft. The minute-hand is 20 ft long and 2 ft 11 in in extreme width, and the hour-hand is 15 ft long and 3 ft 10 in in extreme width. The minute-hand weighs 640 lb and the hour-hand 500 lb. This is the largest clock in the world.

\* For a description of the requirements of installation of tower-clocks, see page 154 "Churches and Chapels," by F. E. Kidder.  
Seth Thomas Clock Company, Thomaston, Conn.

**Bromo-Seltzer Building, Baltimore, Md.** The dials are 24 ft in diameter. The minute-hand is 12 ft 7 in and the hour-hand 9 ft 8 in from tip to tip. The minute-hand weighs 175 lb, the hour-hand 145 lb.

**Daniels-Fisher Building, Denver, Colo.** The dials are 15 ft 6 in in diameter. The minute-hand is 7 ft 10 in and the hour-hand 5 ft 7 in long.

**Maryland Casualty Building, Baltimore, Md.** The dials are 17 ft in diameter. The minute-hand is 8 ft 4 in and the hour-hand 5 ft 11 in long.

**Elgin Watch Company's Factory, Elgin, Ill.** The dials are 14 ft 6 in in diameter. The minute-hand is 7 ft 4 in and the hour-hand 5 ft 4 in long.

**Tower-clock, Station of the Central Railroad of New Jersey, at Camden, N. J.** The diameter of the single dial is 14 ft 3 in; the minute-hand 7 ft long and weighs 40 lb; the hour-hand is 5 ft long and weighs 28 lb. The motive power is furnished by a weight of 700 lb, hung from a  $\frac{3}{8}$ -in steel cable.

**Four-dial clock, Produce Exchange Building, New York.** The diameter of each dial is 12 ft 6 in.

**Four-dial clock, Chronicle Tower,\* San Francisco, Cal.** The diameter of each dial is 16 ft 6 in; length of minute-hands, 8 ft; length of hour-hands, 5 ft 6 in. The mechanism of the clock is 6 ft 1 in high and weighs 3 000 lb.

**Pneumatic clock, City Hall and Court-House, Minneapolis, Minn.** The dials are 23 ft 4 in in diameter.

## LIBRARY BOOK-STACKS

**The Stack-Work in General.** The stack-room of a library is usually set off by fire-proof doors from the rest of the building. The customary practice among architects is to make the stack-work a separate contract and have the general contractor turn the stack-room over to the stack-contractor with finished floors, walls and ceilings. The stacks, made entirely of incombustible materials, are then built as an independent structure.

**Book-Ranges.** The book-ranges are usually double-faced and are placed in parallel rows with aisles between. The minimum aisle-width is about 4 ft. Radial ranges waste space and are costly. Single-faced ranges are relatively more expensive than double-faced ranges.

**Tiers.** All stacks are divided in their height into tiers by deck-floors in order that all shelves may be easily reached. The regular tier-height is 7 ft or 7 ft 6 in.

**Deck-Floors.** Deck-floors are composed of slabs of  $\frac{3}{4}$ -in rough plate glass or 1 $\frac{1}{4}$ -in white marble, supported on steel framework. A long narrow opening or deck-slit is left between the edge of each deck-floor and the face of each range to allow proper ventilation of the stack-tiers. The net thickness from top of deck to bottom of steel framework is from 3 $\frac{1}{4}$  to 3 $\frac{3}{4}$  in for ordinary spans. The deck-floors are carried by the shelf-supports.

**Vertical Communication.** Continuous flights of stairs of simple design and construction are placed at central points. Books are moved up and down by means of dumb-waiters operated by hand, for short runs, or by electric power controlled by push-buttons.

**Shelf-Supports.** The shelf-supports are made in various ways, each with each manufacturer. In the best construction they extend the full width of the shelves so as to hold up the shelves and books without the use of projecting brackets. They are made of sufficient strength to carry the combined loads of books, deck-floors and superimposed stack-tiers. They should

\* Destroyed in the earthquake and fire.

vide for a uniform shelf-adjustment at intervals of about 1 in. Compactness is important. Open-work shelf-supports promote proper lighting and ventilation.

**Shelves.** In each tier of regular height there are usually six rows of adjustable shelves and one row of fixed shelves. Shelves are generally 8 or 10 in wide and 3 ft long. Other sizes are supplied if necessary. The adjustable shelves are made of solid plates of sheet steel or of parallel bars with spaces between. The fixed shelves are placed about 2 in above each floor-level. They are made of solid plates of steel to form dust-stops, fire-stops and water-stops between the tiers.

**Finish.** The adjustable shelves are always completely finished with baked enamel before delivery. The fixed parts, also, of the stack-construction may be finished at the shop with baked enamel, or preferably with air-drying enamel, before erection at the building, so as to permit repair.

**Lighting.** Electric-light wires are carried in metal conduits supported by the steel framework of the deck-floors. Lights of 16 candle-power are spaced about 6 ft apart in range-aisles and 12 ft apart in main aisles.

**Heating.** Indirect radiation is best for books. The lower tiers, only, of a stack should be heated, to prevent the upper tiers from becoming too warm.

**Ventilation.** Large stacks are usually ventilated artificially to prevent the entry of dust and outside air through open windows. In the Library of Congress, in Washington, D.C., fresh, filtered and tempered air is forced in at the bottom tier, finds its way up through the stack by means of the deck-slits and is drawn out at the top tier.

**Weights.** The shelves and shelf-supports \* weigh from 7 to 10 lb per cu ft of book-range. Books weigh about 20 or 25 lb per cu ft of book-range. The steel deck-floor framing weighs from 4 to 6 lb per sq ft of gross area of deck-floor. Marble floor-slabs, 1¼ in thick, weigh about 20 lb per sq ft, and ¾-in-thick, plate-glass slabs, about 10 lb per sq ft of net area.

**Book-Capacities.** Book-capacities per linear foot of shelf may be figured on the following basis: law-books, 5 volumes; reference books, 6 volumes; scientific books, 7 volumes; general literature, from 8 to 10 volumes. The average of the Library of Congress is 8½ volumes per linear foot. An ordinary stack, 7 shelves high with double-faced ranges 16 in deep (or 8-in shelves) and 32 in wide, with a reasonable allowance made for cross-aisles, stairways, etc., will contain about 22 volumes per sq ft of gross area.


**Cost.** The cost in the United States of library-stacks of standard construction varies from 50 cts to \$1 or more per linear foot of shelving. Economy is secured by following established standards while special designs increase the cost.

## CLASSICAL MOLDINGS

**Moldings** are so called because they are of the same shape throughout their length as though the whole had been cast in the same mold or form. The regular moldings, as found in remains of classic architecture, are eight in number, as shown in the accompanying illustration, and are known by the following names: The last two are commonly called, also, OGEE MOLDINGS. Some of these names are derived thus: FILLET, from the French word FIL, a thread; ASTRAGAL, from ASTRAGALOS, a bone of the heel, or the curvature of the heel; BEAD, because a molding, when properly carved, resembles a string of beads; TORUS, or TORE,

\* As made by Sned & Co., Jersey City, N. J.

the Greek for rope, which it resembles when on the base of a column; **SKOTIA**, darkness, because of the strong shadow cast in its hollow, and which is increased by the projection of the torus above it; **OVOLO**, from **OVUM**, an egg, which this member resembles when carved, as in the Ionic capital; **CAVETTO**, from **CAVUS**, hollow; **CYMATIUM**, from **KUMATON**, a wave.



### Characteristics of Moldings

None of these moldings is peculiar to any one of the orders of architecture, and although each has its appropriate use, it is by no means confined to any certain position in an assembly of moldings. The use of the fillet and also of the astragal and torus, which resemble ropes, is to bind the parts together. The ovolo and cyma-reversa are strong at their upper extremities, and are therefore used to support projecting

parts above them. The cyma-recta and cavetto, being weak at their upper extremities, are not used as supporters, but are placed uppermost to cover and shelter the upper parts. The scotia is introduced in the base of a column to separate the upper and lower torus, and to produce a pleasing variety of relief. The form of the bead and that of the torus are the same; the reason for giving distinct names to them is that the torus, in every order, is always considerably larger than the bead and is placed among the base-moldings, whereas the bead is never placed there, but on the capital or entablature. The torus, also, is seldom carved, whereas the bead is; and while the torus among the Greeks, was frequently elliptical in its form, the bead retains its circular shape. While the scotia is the reverse of the torus, the cavetto is the reverse of the ovolo, and the cyma-recta and cyma-reversa are combinations of the ovolo and cavetto.

## THE CLASSICAL ORDERS\*

**Origin of the Orders.** "In the classical styles several varieties of column and entablature are in use. These are called the **ORDERS**. Each order comprises a **COLUMN** with a **BASE**, **SHAFT** and **CAPITAL**, with or without a **PEDESTAL**, with a **BASE**, **DIE** and **CAP**, and is crowned by an **ENTABLATURE**, consisting of **ARCHITRAVE**, **FRIEZE** and **CORNICE**. The entablature is generally about one-fourth as high as the column, and the pedestal one-third, more or less. Among the Greek forms used by the Doric race, which inhabited Greece itself and had colonies in Sicily and Italy, were much unlike those of the Ionic race, which inhabited the western coast of Asia Minor, and whose art was greatly influenced by that of Assyria and Persia. Besides the **IONIC** and **DORIC** styles, the Romans devised a third, which employed brackets, called **MODILLIONS**, in the cornice, and was much more elaborate than either of them; this they called the **CORINTHIAN**. They used also a simple Doric called the **TUSCAN**, and a cross between the Corinthian and Ionic called the **COMPOSITE**. These are the **FIVE ORDERS**. The

\* The paragraphs in quotation-marks are taken from *The American Vignola* by Professor W. R. Ware, by permission of the owners of the copyright, the International Book Company, Scranton, Pa., proprietors of the International Correspondence School. The engravings were made especially for this book, and correspond with the original drawings prepared by Giacomo Barozzi da Vignola.

cient examples vary much among themselves and differ in different places, and in modern times still further varieties are found in Italy, Spain, France, Germany and England. The best known and most admired forms for the orders are those worked out by Giacomo Barozzi da Vignola in the sixteenth century from the study of ancient examples."


### The Tuscan Order.

The distinguishing characteristic of the TUSCAN ORDER (Fig. 1) is simplicity. Any forms of pedestal, column and entablature that show but few moldings, and whose plain, are considered to be TUSCAN."

### The Doric Order.

The distinguishing characteristics of the DORIC ORDER are features in the FRIEZE and the BED-MOLD above called TRIGLYPHS and MUTULES, which are supposed to be derived from the ends of beams and rafters in a primitive wooden construction with large beams. Under each triglyph, and beneath the TÆNIA which crowns the architrave, is a little fillet called the REGULA. Under the regula are six long drops, called GUTTÆ, which are sometimes conical, sometimes pyramidal. There are also either eighteen or thirty-six short cylindrical guttæ under the offset of each mutule. The guttæ are supposed to represent the heads of wooden pins, or treenails. Two different Doric cornices are in use, the MUTULARY with bracket and the DENTICULATED with dentils, the principal difference being in the BED-MOLD." The order shown in Fig. 2 is the denticulated cornice.

**The Ionic Order.** "The prototypes of the IONIC ORDER (Fig. 3) are to be found in Persia, Assyria, and Asia Minor. It is characterized by BANDS in the architrave and DENTILS in the bed-mold, both of which are held to represent small sticks laid together to form a beam or a roof. But the most conspicuous



Dimensions are in 24ths of Diameter.

Fig. 1. The Tuscan Order

and distinctive feature is the **SCROLLS** which decorate the **CAPITAL** of the column. These have no structural significance, and are purely decorative forms derived from Assyria and Egypt. Originally the Ionic order had no **FRIEZE** and no **ECHINUS** in the capital. These were borrowed from the Doric order, and in

Dimensions are in fifths of Diameter

Fig. 2. The Doric Order

like manner, the dentils and bands in the Doric were borrowed from the Ionic. The Ionic frieze was introduced in order to afford a place for sculpture, and was called by the Greeks the **ZOOPHOROUS**, or figure-bearer. The typical Ionic base is considered to consist mainly of a **SCOTIA**, as in some Greek examples. It is common, however, to use instead what is called the **ATTIC BASE**, consisting of a




Fig. 3. The Ionic Order

SCOTIA and two FILLETS between two large TORUSES, mounted on a PLINTH, the whole half a diameter high. The plinth occupies the lower third, or one-sixth of a diameter. Vignola adopted for his Ionic order a modification of the Attic base, substituting for the single large scotia two small ones, separated by one or two beads and fillets, and omitting the lower torus." This is the base shown in Fig. 3. "The Ionic frieze is plain, except for the sculpture upon it. It sometimes has a curved outline, as if ready to be carved, and is then said to be PULVINATED, from pulvinar, a bolster, which it much resembles. The SHAFT of the column is ornamented with twenty-four FLUTINGS, semicircular in section, which are separated not by an ARRIS, but by a FILLET of about one-fourth their width. This makes the flutings only about two-thirds as wide as the Doric channels, or about one-ninth of a diameter, instead of one-sixth."




Fig. 4. The Ionic Volute


**To Describe the Ionic Volute.** There are several methods of doing this, the simplest being by means of centers found as shown by the diagram in Fig. 4. First locate the center of the EYE  $\frac{1}{4} D$  vertically below the point A, Fig. 3. Then describe a circle with a diameter equal to  $\frac{1}{16} D$  to form the eye. Inside of this circle inscribe a square at 45 degrees to a horizontal; then draw the axes 1-3 and 2-4, and divide each of these into six equal parts. Then with the point 1 as a center, and a radius extending to A, Fig. 3, draw a quarter-circle to line 1-2 produced, with 2 as a center, continue the curve until it intersects

2-3 produced, and so on. The centers for the outer curve of the volute are at the points 1, 2, 3, 4, 5, 6, etc. For the centers for the inner curve, start with a point one-third the way from 1 to 5, then a point one-third the way from 2 to 6, and so on.

**The Corinthian Order.** "The three distinguishing characteristics of the CORINTHIAN ORDER (Fig. 5) are a tall, bell-shaped capital, a series of small brackets called MODILLIONS, which support the cornice instead of MUTULES, in addition to the DENTILS, and a general richness of detail which is enhanced by the use of the ACANTHUS LEAF in both capitals and modillions. Here, again, the ATTIC BASE is commonly used, but sometimes, especially in large columns, a base is used which resembles Vignola's IONIC BASE, except that it has two BEADS between the SCOTIAS instead of one, and also a lower TORUS. The SHAFT is fluted like the Ionic shaft, with twenty-four semicircular FLUTINGS, but there are sometimes filled with a convex molding or CABLE to a third of their height. Almost all the buildings erected by the Romans employ the Corinthian order."

**The Composite Order.** "The COMPOSITE ORDER is a heavier Corinthian, just as the Tuscan is a simplified Doric. The chief proportions are the same as in the Corinthian order, but the details are fewer and larger. It owes its name to the CAPITAL, in which the two lower rows of leaves and the CAULICOLI are the same as in the Corinthian. But the caulicoli carry only a stunted LEAF-STYL and the upper row of leaves and the sixteen VOLUTES are replaced by the large ECHINUS, SCROLLS and ASTRAGAL of a complete Ionic capital. Vignola's composite entablature differs from his Ionic chiefly in the shape and size of the





Dimensions are in fths of Diameter

THE CORINTHIAN ORDER

Fig. 5. The Corinthian Order

**DENTILS.** They are larger, and are more nearly square in elevation, being fifth of a diameter high and one-sixth wide, the **INTERDENTIL** being one-tenth

H	P
12	65
60	
8	25
30	25
12	20
9	38
49	25
20	20
20	
30	
70	
60	30
25	32.5
15	30



Fig. 6. An Egyptian Order. Diameter Divided into Sixty Parts

forms and general features of Egyptian columns. For practical use the column shown in Fig. 6 may be taken as a standard of the Egyptian style.

and they are set one-half a diameter apart, on an octagonal capital. The composite capital is employed in the Arch of Titus in Rome, and elsewhere, in the Corinthian entablature, and the BLOCK CORNICE occurs in the temple of Apollo at Didyma, called **FRONTISPIECE** of the temple at Athens, in connection with the Corinthian capital."

**Egyptian Style.\*** The architecture of the ancient Egypt is characterized by boldness of outline, solidity, and grandeur. The principal features of the **EGYPTIAN STYLE** of architecture are: uniformity of plan, not deviating from right lines and angles; thick walls, having the outer surface slightly convex inwardly from the perpendicular; the whole building low, roof composed of stones reaching from one pier to the next, these being supported by enormous columns, very stout in proportion to their height. The shaft sometimes polygonal, having no base, but with a variety of handsome capitals. The foliage of these being of palm, lotus and other leaves. The **ENTABLATURES** having an **ARCHITRAVE**, crowded with huge **CAVETTO** ornamented with sculpture; and the **INTERCOLUMNATION** very narrow, usually  $1\frac{1}{2}$  diameters and seldom exceeding  $2\frac{1}{2}$ . A great dissimilarity exists in the proportions

## LIGHTNING-CONDUCTORS

**Rules for the Erection of Lightning-Conductors.** The following rules for the erection of lightning-conductors were issued in 1853 by the Department of Explosives of the English Home Office to the occupiers of all factories and

\* From The American House Carpenter, by R. G. Hatfield.

for explosives, and to those local and police authorities upon whom devolves the inspection of stores of explosives:

- (1) **Material of Rod.** Copper, weighing not less than 6 oz per ft run, the electrical conductivity of which is not less than 90% of that of pure copper, either in the form of rod, tape, or rope of stout wires, no individual wire being smaller than No. 12, Birmingham Wire-Gauge (0.109 in) the English standard wire-gauge. Iron may be used, but should not weigh less than 2½ lb per foot run.
  - (2) **Joints.** Every joint, besides being well cleaned and screwed, scarfed, riveted, should be thoroughly soldered.
  - (3) **Form of Points.** The point of the upper terminal\* of the conductor should not have an angle sharper than 90°. A foot below the extreme point a copper ring should be screwed and soldered on to the upper terminal, in which should be fixed three or four sharp copper points, each about 6 in long. It is desirable that these points should be so platinized, gilded, or nickel-plated as to resist oxidation.
  - (4) **Number and Height of Upper Terminals.** The number of conductors or upper terminals required will depend upon the size of the building, the material of which it is constructed, and the comparative height above ground of the principal parts. No general rule can be given for this, except that it may be assumed that the space protected by the conductor is, as a rule, a cone, the base of whose base is equal to the height of the conductor from the ground.
  - (5) **Curvature.** The rod should not be bent abruptly around sharp corners. In no case should the length of a curve be more than half as long again as its radius. A hole should be drilled in string-courses or other projecting masonry, when possible, to allow the rod to pass freely through it.
  - (6) **Insulators.** The conductor should not be kept from the building by glass or other insulators, but attached to it by fastenings of the same metal as that of the conductor itself.
  - (7) **Fixing.** Conductors should preferentially be taken down the side of the building which is most exposed to rain. They should be held firmly, but the holdfasts should not be driven in so tightly as to pinch the conductor or prevent contraction and expansion due to change of temperature.
  - (8) **Other Metalwork.** All metallic spouts, gutters, iron doors, and other projections of metal about the building should be electrically connected with the conductor.
  - (9) **Earth-Connection.** It is most desirable that, whenever possible, the lower extremity of the conductor should be buried in permanently damp soil. Proximity to rain-water pipes and to drains or other water is desirable. It is a very good plan to bifurcate the conductor close below the surface of the ground, and to adopt two of the following methods for securing the escape of lightning into the earth: (a) A strip of copper tape may be led from the bottom of the rod to a gas or water-main (not merely to a leaden pipe), if such is near enough, and be soldered to it; (b) a tape may be soldered to a sheet of copper, 3 by 3 ft by ¼ in thick, buried in permanently wet earth and surrounded by cinders or coke; (c) many yards of copper tape may be laid in a trench filled with coke, having not less than 18 sq ft of copper exposed.
  - (10) **Protection from Theft, etc.** In places where there is any likelihood of the copper being stolen or injured, it should be protected by being enclosed in a tube.
- The upper terminal is that portion of the conductor which is between the top of the building and the point of the conductor.

in an iron gas-pipe, reaching 10 ft (if there is room) above ground and a distance into the ground.

(11) **Painting.** Iron conductors, galvanized or not, should be painted. optional with copper ones.

(12) **Inspection.** When the conductor is finally fixed it should in all cases be examined and tested by a qualified person, and this should be done in the case of new buildings after all work on them is finished. Periodical examination and testing, should opportunities offer, are also very desirable, especially when iron earth-connections are employed.

**Lightning-Protection for High Chimneys.** The following is a description of the system of lightning-protection for the radial-brick chimney 350 ft in height, for the plant of the St. Joseph Lead Company, Hercules Mo.

**Conductor.** The conductor used is of commercially pure copper, No. Brown & Sharpe gauge, in the form of a cable, consisting of twenty-wires, seven strands, four wires to the strand, and  $\frac{5}{16}$  in in diameter, 230 circular mils. The vertical conductors are of continuous lengths from the top of the chimney to and into the ground. A circuit-conductor is placed below the top of the chimney and connected to each down-conductor by a two-way splice.

**Points.** The air-terminals are eight in number equally spaced around the top of the chimney, and consist of solid, copper bars 1 in in diam and 10 ft length, the upper 12 in tapering to a point and covered with a 12-in thick genuine platinum. Air-terminals extend 5 ft above the top of the stack; the lower end of each copper bar is set in a heavy copper T coupler, which connects the same into the circuit-conductor. Each rod is held in place by four anchor-fasteners, bolted from the inside of the stack. These anchors are cased in copper tubes set in the solid masonry.

**Grounding.** At a point below the ground-level and at the chimney the conductor is carried in a downward course from the chimney, in a trench bedded in charcoal, to a point 5 ft outside the foundation-line. An additional conductor is spliced into the main cable at this point, forming a Y with branches terminating 15 ft apart. Two well-holes are bored to a depth of approximately 20 ft into permanent moisture. The end of each Y conductor is electrically soldered into perforated, copper reservoirs  $4\frac{1}{2}$  in in diam and 12 in in length, and filled with pea-size charcoal. The effect of the reservoirs is to give the required amount of surface-contact with the earth and to insure permanent moisture through the charcoal by capillary attraction. Each conductor is thus grounded in two places instead of in one place.

**Lead Covering.** To preserve the conductor system against decomposition in ozone, in which sulphuric or other acid gases may exist, all of the conductor system at the top, and to a point 75 ft below the top of the chimney is covered with lead  $\frac{1}{8}$  in in thickness. Exception is made to the platinum-covered top of each rod, which requires no lead covering. Where splices are made at anchor-fasteners set, the whole is covered with lead sleeves or hoods thoroughly wiped and hermetically sealed. Connections of point-bar T's etc, are soldered, lead-covered and sealed. Practical experience seems to show that all lightning-conductor systems on chimneys should be lead-covered and hermetically sealed to a point, approximately 25 ft downward from the top to protect the copper against decomposition, not necessarily as thick as on the chimney, but, say,  $\frac{1}{16}$  in, the thickness being determined by the size and use.

of the stack. It has been found that in from three to five years there is a decided honeycombing of the copper, through the action of the sulphuric and other acid gases. It has often been necessary to replace points, sections of cable, etc., entirely eaten away from this cause.

## INTERPHONES. AUTOMATIC TELEPHONES FOR INTERCOMMUNICATING SERVICE

**Description.** The interphone system is an application of the telephone for interior use. It is an automatic, intercommunicating system, requiring neither switchboard nor operator, and being self-contained within the walls of the establishment for whose benefit it has been installed.

**Advantages.** In brief, the advantages of such a system are these: (1) the mere pressing of a button gives a person telephone-connection with any desired party, without the loss of time involved in first calling up a third party; (2) recourse to directory or information bureau is made unnecessary through the use of labels, properly inscribed, on the face of the instrument; (3) no maintenance-expense is involved, and the system, consequently, is as inexpensive to operate as an electric door-bell; (4) the wiring-arrangement is such that the system may be provided for when the original plans for a new building are being drawn up, and in this respect it does not differ much from a system of electric lights or plumbing.

**The Use of Interphones** in residences, schools, hospitals, factories, mills, offices, stores and clubs is constantly increasing. The same general features apply to all of these types of installations, and in practically every case it is the simplicity of the system that especially recommends it for service. The interphone usually fits in where formerly call-bells, speaking-tubes, messenger service and other inadequate methods were the rule. The interphone field of service is in the establishment whose needs call for from four to thirty-two telephone-stations. When there are more than thirty-two the installation of a private telephone-exchange, with a switchboard, is better practice.

**Types of Interphones.** There are several types of interphones for varying degrees of service.

(1) The most familiar instrument is a wall-interphone, of the **NON-FLUSH TYPE**. The telephone is of metal, with connecting buttons, labels, bells, mouth-piece, hook and receiver, all mounted on its face. This instrument is to be attached directly to the wall.

(2) The **FLUSH TYPE** resembles the first-mentioned type in every particular but the one implied in its title. The instrument is mounted into the wall, with its face flush with the rest of the wall-surface. These two instruments are most popular for installation in club-hallways, in stores and factories, in residences, and in all places where wall-telephones would ordinarily be used. Busy offices and stores often employ variations of types (1) and (2) and use a **DESK-SET**, a separate instrument taking care of the connecting buttons and labels, or a **HAND-SET**.

(3) The **DESK-STAND** telephone is of the type often used for local and long-distance service. Connected with it is a metal box containing the rows of buttons and labels, each label being opposite the button through which is secured connection with the corresponding station. The telephone in this case stands on the desk, and the key-box is conveniently close at hand, either on the desk or on the wall.

(4) Some prefer for this service the **HAND-SET**, with the receiver and transmitter in one piece. This is a convenient, compact instrument, well fitted for use in an office.

(5) From two to six instruments of still another type make up a **PARTY-LINE INTERPHONE SYSTEM**. Here there are no connecting buttons, the principle involved being the same as that of the elementary, farmers' line. This makes a convenient private-line system for a small residence, and is appropriate for a house-to-garage circuit.

**Variations from Standard Types.** There are systems with variations from the standard types. Many schools are using a combination of interphones of type (1) or (2) with (5). In the principal's office is an instrument of type (1) or (2) with a connecting button for each outside station, while the classroom-telephones are all of type (5). With this system the principal can at any time call up any teacher; but a teacher can call up another classroom only through the medium of this **MASTER-STATION**, which acts as a sort of exchange. The advantages of this arrangement for a school are obvious. In a hospital the instruments are usually placed outside of the more important operating-rooms and wards and in the offices and reception-rooms.

**Wiring and Batteries.** All wiring is enclosed in cables. Energy is obtained from dry cells. The only maintenance-expense connected with an interphone system is the occasional renewal of these batteries.

## VACUUM-CLEANING

**General Description.** Vacuum-cleaners are appliances which have come into use during recent years and which are for the purpose of removing dirt and dust from rooms of buildings, cars, steamships, etc., or from furniture, carpets, curtains, or other interior fittings. The dust and dirt are removed by suction and the apparatus consists of an air-pump which is arranged to draw the air and the dirt or dust contained in it through pipe and nozzle. The nozzle is drawn or passed over the surfaces which are to be cleaned. Screens of muslin or other appropriate cloth are used to separate by filtration the dirt and dirt which are borne along with the stream of air; and in some types of apparatus this process is assisted by what are called baffle-plates which are added to make the heavier particles of dust drop by their own weight to the lower part of the receptacle placed to receive them. About the year 1890 compressed air was used for the first time in railroad-cars for purposes of cleaning and dust-removal. There were serious objections to this method of cleaning, however, as it was found that the jets of compressed air blew out the dust and dirt in such a way that it was difficult to arrange for their collection and retention; the principle of suction was consequently introduced to overcome these difficulties.

**Types of Vacuum-Cleaners.** The machines belonging to the earliest type usually consist of a pump, the motor-power of which is either a gas-engine or an electric motor, the machines being portable. They can be moved about from one building to another as occasion demands. Cleaners of the next type introduced involve an installation in the basement or lower part of a building and a fixed and permanent position. From the central plant pipes are run to various rooms and apartments and are fitted in such rooms or apartments or in adjacent halls or corridors, with valves to which are attached the hose with the cleaning appliances at the end. In some cases this vacuum-arrangement is combined with another for washing floors, the secondary system including a second set of pipes from a tank filled with soap and water. Compressed air is employed to spray the latter over the floor, and both dirt and water are finally removed.

through pipes to the street-sewers. A portable tank is used for the soap and water. Vacuum-cleaners of a third type consist of small machines which take the place of the brooms and dusters or are used in connection with them. They are now very generally used and may be driven by an electric motor, by foot, or by hand. These last-mentioned, smaller, portable cleaners are used for many other purposes than the ordinary cleaning of rooms and furniture.

**Details and Specifications for Vacuum-Cleaning Installations.** Complete plans and specifications for the installation of a vacuum-cleaning plant for a building may be obtained from any of the numerous manufacturers making such apparatus and taking contracts to put it in place. There are several types of machines and systems of installation and detailed descriptions would exceed the limits of space in this handbook.

## WATERPROOFING FOR FOUNDATIONS \*

**The Waterproofing of Substructure Work** is, comparatively speaking, a modern branch of engineering. It is only within recent years that it has become necessary to construct deep basements for buildings. In the past, the more important structures, such as cathedrals, capitol, state-buildings and the like, were usually built upon high ground, and water was prevented from entering the basements of such buildings by means of drainage. Waterproofing, as we now know it, was generally unnecessary. With the advent of the so-called skyscrapers, however, requiring large mechanical plants, deep basements became an actual necessity, and as these basements are usually carried below ground-water level, and in many instances below tide-level, the question became one of utmost importance. Like almost every detail of a modern building, waterproofing is a specialty. Each building presents its own problems, and the safest plan is to leave the solution of these problems to some one expert in the knowledge of waterproofing who has made it a special study and knows how best to overcome the existing difficulties. It may be laid down as an invariable rule that, where conditions are at all serious, the owner or the general contractor will save money in the long run if he employs the services of an expert waterproofer to place his waterproofing-seal, regardless of the method he wishes to use.

**Pressure-Resistance Versus Waterproofing.** In waterproofing large basements where actual pressure exists, it is a question for the engineer to decide whether it is more economical to attempt to secure an absolute **PRESSURE-JOB** or a **WATER-PROOF JOB** in connection with a drainage system. As a general rule, it may be stated that where a building is generating its own power, it is more economical to use a drainage system with an open sump than to construct a pressure-cellar, the cost of pumping being much less than the interest charges on the cost of a floor-slab sufficiently strong to withstand the pressure.

**Waterproofing Concrete Foundations.** The three following subdivisions of this subject, discussing the causes of permeability of concrete, the addition of substances to render it more water-proof, and the treatment of its surfaces to make it less permeable, embody the conclusions of Committee D-8 of the American Society for Testing Materials.† This committee, since its organization in 1905 has, through laboratory-tests and experiments, together with examinations of work during construction and after completion, as well as the study of literature on the subject, sought to secure sufficient information to enable it to for-

\* For foundations in general, see Chapter II.

† This article, to the middle of page 1713, is the substance of a Report submitted to the American Society for Testing Materials at its meeting, June 24-28, 1913. This society has (1920) no Standard Specifications for Waterproofing, but published in 1918 our Tentative Specifications on this subject.

ulate definite methods for securing water-proof concrete structures. The work of the committee was complicated by reason of the facts that there seemed to be so little concordance between results of tests obtained under laboratory-conditions and in the field and that it was necessary to extend its investigations over a period of years in order to determine the permanency of the action noted. The committee reported that while it had not been able to arrive at sufficiently definite conclusions to enable it to formulate specifications for the making of concrete structures water-proof or for materials to be used in such work, it had reached certain general conclusions which might be of assistance to the constructor in securing the desired result of impermeable concrete. Early in the investigation, the work was found to subdivide naturally into three branches, and the conclusions reached will be grouped in order under these subdivisions, which are:

(1) The determination of causes of the permeability of concrete as usually made from mixtures of Portland cement, sand and stone, or other coarse aggregate, in proportions of from 1 of cement, 2 of sand and 4 of stone, to 1 of cement, 3 of sand and 6 of stone, and the best methods of avoiding these causes.

(2) The rendering of concrete more water-proof by adding to ordinary mixtures of cement, sand and stone, other substances which, either by their void-filling or repellent action, would tend to make the concrete less permeable.

(3) The treatment of exposed surfaces after the concrete or mortar has been put in place and hardened more or less, either by penetrative, void-filling or repellent liquids, making the concrete itself less permeable; or by extraneous protective coatings, preventing water from having access to the concrete.

Considering these several subdivisions separately and in the order named, the committee arrives at the following conclusions:

(1) **Causes of Permeability of Concrete.** In the laboratory and under test-conditions where properly graded and sized coarse and fine aggregates are used, in mixtures ranging from 1 of cement, 2 of sand and 4 of stone, to 1 of cement, 3 of sand and 6 of stone, impermeable concrete can invariably be produced. Even with sand of poor granulometric composition, with mixtures as rich as 1 of cement, 2 of sand and 4 of stone, permeable concrete is seldom, if ever, found and is a rare occurrence with mixtures of 1 of cement, 3 of sand and 6 of stone. But the fact remains, nevertheless, that the reverse often obtains in actual construction, permeable concretes being encountered even with mixtures of 1 of cement, 2 of sand and 4 of stone and are of frequent occurrence where the quantity of the aggregate is increased. This the committee attributes to:

(a) Defective workmanship, resulting from improper proportioning, lack of thorough mixing, separation of the coarse aggregate from the fine aggregate and cement in transporting and placing the mixed concrete, lack of density through insufficient tamping or spading, improper bonding of work-joints, etc.

(b) The use of imperfectly sized and graded aggregates.

(c) The use of excessive water, causing shrinkage-cracks and formation of laitance-seams.

(d) The lack of proper provision to take care of expansion and contraction causing subsequent cracking.

Theoretically, none of these conditions should prevail in properly designed and supervised work, and they are avoided in the laboratory and in the field, under test-conditions, where speed of construction and cost are negligible items, instead of being governing features as they must be in actual construction. Properly graded sands and coarse aggregates are rarely, if ever, found in nature in sufficient quantities to be available for large construction, and the effect of poorly graded



aggregates in producing permeable concrete is aggravated by poor and inefficient field-work. Even if the added expense of screening and remixing the aggregates could be afforded, so as to secure proper granulometric composition to give the density required to make untreated concretes impermeable, it is seemingly often a commercial impossibility on large construction to obtain workmanship even approximating that found in laboratory-work.

(2) **Addition of Foreign Substances to Cement Before or During Mixture.** The committee finds that in consequence of the conditions outlined above, substances calculated to make the concrete more impermeable, either incorporated in the cement or added to the concrete during mixing, are often used. This has resulted in the development and placing on the market of numerous patented or proprietary waterproofing-compounds, the composition of which is more or less of a trade-secret. While it has been impossible for the committee to test all of the special waterproofing-compounds being placed on the market, it has investigated a sufficient number of these, as well as the use of certain very finely divided, naturally occurring or readily obtainable commercial mineral products, such as finely ground sand, colloidal clays, hydrated lime, etc., to form a general idea of the value of the different types. The committee finds:

(a) That the majority of patented and proprietary integral compounds tested have little or no immediate or permanent effect on the permeability of concrete and that some of these even have an injurious effect on the strength of mortar and concrete in which they are incorporated.

(b) That the permanent effect of such integral waterproofing-additions, if dependent on the action of organic compounds, is very doubtful.

(c) That in view of their possible effect, not only upon the early strength, but also upon the durability of concrete after considerable periods, no integral waterproofing-material should be used unless it has been subjected to long-time practical tests under proper observation to demonstrate its value, and unless its ingredients and the proportion in which they are present are known.

(d) That in general, more desirable results are obtainable from inert compounds acting mechanically, than from active chemical compounds whose efficiency depends on change of form through chemical action after addition to the concrete.

(e) That void-filling substances are more to be relied upon than those whose value depends on repellent action.

(f) That, assuming average quality in sizing of the aggregates and reasonably good workmanship in the mixing and placing of the concretes, the addition of from 10 to 20% of very finely divided void-filling mineral substances may be expected to result in the production of concrete which, under ordinary conditions of exposure, will be found impermeable, provided the work-joints are properly bonded, and cracks do not develop on drying, or through change in volume due to atmospheric changes, or by settlement.

(3) **External Treatment.** While external treatment of concrete would not be necessary if the concrete itself, either naturally or by the addition of waterproofing-material, was impermeable to water, it has been found in practice that in large construction, no matter how carefully the concrete itself has been made, cracks are apt to develop, due to shrinkage in drying out, expansion and contraction under change of temperature and moisture-content, and through settlement. It is, therefore, often advisable in important construction to anticipate and provide for the possible occurrence of such cracks by external treatment with a protective coating. Such coating must be sufficiently elastic and cohesive to prevent the cracks extending through the coating itself. The application of merely penetrative void-filling liquid washes will not prevent the passage of

water due to cracking of the concrete. The committee has, therefore, considered surface-treatment under two heads:

(a) Penetrative void-filling liquid washes.

(b) Protective coatings, including all surface-applications intended to prevent water coming in contact with the concrete.

**Penetrative Washes.** While some penetrative washes may be efficient in rendering concrete water-proof for limited periods, their efficiency may decrease with time and it may be necessary to repeat such treatment. Some of these washes may be objectionable, due to discoloring the surface to which they are applied. The committee, therefore, believes that the first effort should be made to secure a concrete that is impermeable in itself and that penetrative void-filling washes should only be resorted to as a corrective measure.

**Protective Coatings.** While protective extraneous bituminous or asphaltic coatings are unnecessary, so far as the major portion of the surface of the concrete is concerned, provided the concrete, either in itself or through the addition of integral compounds, is made impermeable, they are valuable as a protection where cracks develop in a structure. It is therefore recommended that a combination of inert void-filling substances and extraneous waterproofing be adopted in especially difficult or important work.

**Bituminous or Asphaltic Coatings.** Considering the use of bituminous or asphaltic coatings, the committee finds:

(a) That such protective coatings are often subject to more or less deterioration with time, and may be attacked by injurious vapors or deleterious substances in solution in the water coming in contact with them.

(b) That the most effective method for applying such protection is either the setting of a course of impervious brick dipped in bituminous material into a solid bed of bituminous material, or the application of a sufficient number of layers of satisfactory membranous material cemented together with hot bitumen.

(c) That their durability and efficiency are very largely dependent on the care with which they are applied. Such care refers particularly to proper cleaning and preparation of the concrete to insure as dry a surface as possible before application of the protective covering, the lapping of all joints of the membranous layers, and their thorough coating with the protective material. The use of this method of protection is further desirable because proper bituminous coverings offer resistance to stray electrical currents, the possible attack from which is referred to in succeeding paragraphs.

**Rich Mixtures.** So far, the committee has considered only concretes of the usual proportions, namely, those ranging from 1 of cement, 2 of sand and 4 of stone, to 1 of cement, 3 of sand and 6 of stone. It has been suggested that impermeable concretes could be assured by using mixtures considerably richer in cement. While such practice would probably result in an immediate impermeable concrete, it is believed by many that the advantage is only temporary, as richer concretes are more subject to check-cracking and are less constant in volume under changes of conditions of temperature, moisture, etc. Therefore, the use of more cement in mass-concrete would cause increased cracking, unless some means of controlling the expansion and contraction is discovered. With reinforced concretes the objection is not so great, as the tendency to cracking is more or less counteracted by the reinforcement.

**Fine Flour Mixtures.** It has also been suggested that the presence in the cement of a larger percentage of very fine flour might result in the production of a denser and more impermeable concrete, through the formation of a larger amount of colloidal gels. Neither of these suggestions has been especially investigated by the committee. Both appeal to the committee, however, for the

reason that they substitute active cementitious substances for the largely inactive void-filling materials previously recommended, thus increasing the strength of the concrete.

**Character of Workmanship.** In conclusion, the committee would point out that no addition of waterproofing-compounds or substances can be relied upon to completely counteract the effect of bad workmanship, and that the production of impermeable concrete can only be hoped for where there is determined insistence on good workmanship.

**Saline Waters. Electrical Action.** The production of impermeable concrete has assumed greater importance since the appointment of this committee, owing to the well-known injurious action of saline or alkaline waters and to the suggested possible effect of the moisture in concrete occasioning or aggravating electrical action from stray currents. Originally, the question of waterproofing involved mainly the physical troubles resulting from water passing through concrete without any special consideration of its effect on its durability, other than a gradual leaching out of the cement. Recent developments suggest the possibility that, owing to the increased conductivity of damp concrete to electrical currents, such currents, if present, may so affect damp concrete as to seriously lessen its integrity; and this possibility further emphasizes the importance of the recommendation that no waterproofing-compound of unknown chemical composition be added to concrete, as recent tests seem to show that the action of electrical currents is aggravated by the presence of certain solutions.

**Waterproofing by External Linings of Brick, Tar, or Asphalt, and Felt.** The oldest method of waterproofing is the one involving the use of a tar-and-felt or asphalt-and-felt seal (Fig. 1). This consists of building first a supporting wall and a supporting concrete slab to hold the seal. On the floors, this slab is usually composed of concrete, 4 in thick. The walls are generally of brick from 4 to 8 in thick, but occasionally 4-in terra-cotta tiles are used. Upon this base a swabbing of tar or asphalt is placed and before this has become cold or set, one thickness of paper, saturated with coal-tar, is laid. This paper receives a swabbing of coal-tar and asphalt and another layer of paper is placed, the operation being continued until there are three or more layers of paper with four or more swabbings of the tar or asphalt. For damp-proof work, three layers of paper with four swabbings of tar are usually sufficient. For waterproofing-work not less than five and usually six layers of paper with from six to seven swabbings of tar are used. The main walls of the structure are then built against the wall-waterproofing, and after these are in place, the main concrete basement-floor is laid immediately on top of the floor-seal, the idea being to form a continuous water-proof seal enveloping the entire basement below grade. The difficulties of this system consist chiefly in securing perfect laps at all points in the work, and unless extreme care is used and unless there is perfect coöperation between the waterproofer and the mason-contractor, there is apt to be a break somewhere in the seal, usually where the wall-waterproofing is supposed to be joined to the floor-work. The disadvantages of this system are due to the fact that the seal is not permanent in all soils as the subsurface water frequently contains acids which destroy the seal. Then again, the seal may be easily punctured by the mason-contractor in building his wall against it or in laying the concrete floor upon the flat work. The chief disadvantage, however, is that the waterproofing-seal is invariably buried behind a mass of masonry, either brick or concrete, which means that should there be a leak, due to either carelessness or accident, through the waterproofing-seal, it is frequently impossible to stop it. It not infrequently happens that when a leak has developed in tar-and-felt work, the actual presence of the water does not show opposite the leak,

but following some line of least resistance, appears from 50 to 100 ft, or more away from where the actual damage causing the leak occurs. In actual waterproofing work it is seldom attempted to secure a bottle-tight job with tar and felt. Instead, some system of drainage is installed beneath the water-proof seal which is on the floors of the building, and the water is conducted through it

Fig. 1.\* Felt-Waterproofing for Foundations

or other pipes to some central sump from which it is mechanically pumped to a sewer. The purpose of the waterproofing in this case, therefore, is to concentrate or drive the water to this sump. For shallow cellars and especially damp-proofing-work, this tar-and-felt method is the most economical and most frequently employed.

**Waterproofing by Coating with Water-Proof Cement.** For deep and difficult work a comparatively new method of waterproofing is often used (Fig 2). This consists of placing a coating of water-proof cement upon the interior surface of the exterior walls of the building and over the upper surface of the concrete floor-slab in the basement or subbasement. Fig. 3 shows a foundation for an engine, the concrete being waterproofed as shown. The pit is made somewhat larger than the foundation, the extra space being filled in with cinders, dry bricks or terra-cotta blocks, which may be readily removed to allow access to the bed-plate bolts for which hand-holes have been cast in the concrete, thus permitting the complete removal of the engine. The figure

\* Reproduced, by permission, from a pamphlet published by The Waterproofing Company New York, and showing the greater thickness of walls and floor required for the outside-surface brick-and-felt method of waterproofing as compared with the inside-surface water-proof-cement coating. Taken from design for waterproofing in a prominent New York building. See, also, Fig. 2.

is a 2-in sand cushion and a 2-in layer of planks under the engine-foundation. is not a part of the waterproofing but is put in to prevent the communication of vibration. Fig 4 shows reinforced-concrete floors for an engine-room boiler-room, the concrete slab being 12 in thick under the former and 24 in

Fig. 2.\* Cement Waterproofing for Foundations

under the latter. Both floors are covered with a 1-in course of water-proof cement. The reinforcement is put in as shown and in sizes and spacing as follows:

12-in slab	24-in slab
<p>Rods in two courses</p> <p>Lower rods, 4 in on centers, 6 in from surface</p> <p>Upper rods, 6 in on centers, 2 in from surface</p> <p>Five rods, total area of cross-section 0.703 sq in; per square foot of surface, 2.39 lb</p>	<p>Rods in three courses</p> <p>Lowest rods, 3 in on centers, 12 in from surface</p> <p>Intermediate rods, 3 in on centers, 7 in from surface</p> <p>Upper rods, 6 in on centers, 2 in from surface</p> <p>For ten rods, total area of cross-section, 1.4 sq in; per square foot of surface, 4.78 lb</p>

from a pamphlet published by The Waterproofing Company, New York, and showing the total thickness of walls and floor required for the inside-surface water-proof method of waterproofing. Taken from design for waterproofing of the same type as shown in Fig. 1. The walls and floors were put in place in the monolithic form.

There are many compounds advertised to make cement or concrete waterproof. Besides these, there are water-proof cements manufactured by secret processes and applied by companies that make a specialty of waterproofing. Some of the many waterproofing-compounds have merit; but the main factors

Fig. 3.\* Engine-foundation with Water-proof Cement

successful job of waterproofing are the skill and experience of the waterproofers who do the work. It is claimed that to apply cement waterproofing so as to obtain efficient results requires more skill than to apply a tar-and-felt seal. In a cement waterproofing, once properly applied, seems to possess some advantages




Fig. 4.\* Reinforced-concrete Floor with Water-proof Cement

over the older method of tar and felt. One advantage is that the waterproofing is accessible, and that if any leaks develop, they are apparent and can be readily and economically repaired by cutting out the old waterproofing and applying a new coating where the damage exists. Another advantage claimed for cement waterproofing is generally permanent and not damaged by the oil

\* Reproduced by permission of The Waterproofing Company, New York.

found in solution with water in soil. By the cement method the cost of brick supporting walls and the concrete supporting slab is eliminated as is the corresponding cost of the necessary excavation for them; and finally, waterproofing on the floor serves the double purpose of waterproofing and finishing-surface, thus saving the cost of the cement finish usually found in basements and subbasements. One of the disadvantages of cement waterproofing is that the material is rigid and is fractured by any settlement of the building or contraction in the concrete upon which it is placed. Experience has shown, however, that settlement-cracks usually take place before the waterproofing contractor has left the building and that there is little or no trouble from these causes after his work is completed. Contraction-cracks in concrete, however, seem to develop at any time within twenty-four months after concrete has been placed. In order to prevent these cracks, users of the cement waterproofing have adopted a system of reinforcement in the concrete, and it is claimed that this reinforcement is, in the long run, an economy, as it permits of less contraction and gives a better and stronger floor or wall. On brick and stone walls trouble is experienced from contraction and expansion. It should be remembered that this work is all below grade where contraction and expansion are reduced to a minimum, regardless of the materials used.

**Waterproofing by Adding Substances to Cement.** This is another method of waterproofing now being advocated by some. If this method could ever be made efficient, it would be highly advantageous. It is claimed by manufacturers of these compounds that in order to secure a water-proof basement, for example, a certain percentage of the compound is to be mixed with the cement before it is incorporated in the concrete. The opponents of this method claim, however, that it is impossible to construct a basement in any way without incurring the danger of serious leaks at the joinings of one part of work with that of another; that leakage at these points of cleavage may be increased by the use of waterproofing-compounds; and that their principal objection is that they produce a very dense mass of concrete. It is always difficult to join old concrete to new, and if concrete is made water-proof, or, in other words, nonabsorbent, the difficulty of joining new concrete to a nonabsorbent old concrete is increased. This method is effective, however, and is to be commended in work which can be carried on without interruption, such, for instance, as small elevator-pits or small swimming-pools, where the concrete may be started in the morning and completed by night or before any part of the day has had time to attain its initial set.

## FORCE OF THE WIND

**Relation Between the Pressure and Velocity of Wind.** According to experiments made in 1890 or thereabouts, by C. F. Marvin, United States Signal Service, the relation between wind-pressure and velocity is given very approximately by the formula  $p = 0.004 V^2$ , where  $p$  is the pressure in pounds per square foot on a flat surface normal to the direction of the wind, and  $V$  the velocity of the wind in miles per hour. Smeaton considered the pressure as equal to  $0.005 V^2$ . The following table, based on Marvin's formula,\* is quoted from Turneaure and Ketchum.†

If Marvin's formula is written  $p = 0.0032 V^2$  the values in this table will be slightly reduced. See Chapter XXVII, pages 1052 and 1053; Chapter XXX, page 1199; and also page 1394. † The formula used by the United States Signal Service is  $p = 0.004 V^2$ . The pressure is probably somewhere between  $0.005 V^2$  and  $0.004 V^2$ , near the former for low velocities and near the latter for high velocities. See, also, Trautwine's Pocket-Book, page 321.

Table Showing the Force of the Wind

Miles per hour	Feet per minute	Feet per second	Force, in pounds, per square foot	Description
1	88	1.47	0.004	Hardly perceptible
2	176	2.93	0.014	Just perceptible
3	264	4.40	0.036	
4	352	5.87	0.064	Gentle breeze
5	440	7.33	0.1	
10	880	14.67	0.4	Pleasant breeze
15	1 320	22.0	0.9	
20	1 760	29.3	1.6	Brisk gale
25	2 200	36.6	2.5	
30	2 640	44.0	3.6	High wind
35	3 080	51.3	4.9	
40	3 520	58.6	6.4	Very high wind
45	3 960	66.0	8.1	
50	4 400	73.3	10.0	Storm
60	5 280	88.0	14.4	Great storm
70	6 160	102.7	19.6	
80	7 040	117.3	25.6	Hurricane
100	8 800	146.6	40.0	

## COPIES OF TRACINGS

**Blue-Prints from Tracings.** The following directions \* cover the whole ground. The sensitized paper can be procured, all prepared, at stores where artists' materials are sold, so that the process of preparing the paper by use of chemicals can then be omitted. The materials required are as follows:

(1) A board a little larger than the tracing to be copied. The drawing board on which the drawing and tracing are made can always be used.

(2) Two or three thicknesses of flannel or other soft white cloth, which is to be smoothly tacked to the board to form a smooth surface, on which to lay the sensitized paper and tracing while printing.

(3) A plate of common double-thick window-glass, of good quality, slightly larger than the tracing to be copied. The function of the glass is to keep the tracing and sensitized paper closely and smoothly pressed together while printing.

(4) The chemicals for sensitizing the paper. These consist simply of equal parts, by weight, of citrate of iron and ammonia, and red prussiate of potash and can be obtained at any drug-store. The price should not be over 8 to 10 cts per ounce for each.

(5) A stone or yellow-glass bottle to keep the solution of the above chemicals in. If there is but little copying to do, an ordinary glass bottle will do, and the solution can be freshly made whenever it is wanted for immediate use.

(6) A shallow earthen dish in which to place the solution when using it. A common dinner-plate is as good as anything for this purpose.

(7) A soft paste-brush, about 4 in wide.

(8) Plenty of cold water in which to wash the copies after they have been exposed to the sunlight. The outlet of an ordinary sink may be closed by placing a piece of paper over it with a weight on top to keep the paper down, and the sink filled with water, if the sink is large enough to lay the copy

\* Taken from The Locomotive.



If it is not, it is better to make a water-tight box 5 or 6 in deep, and 6 in wider and longer than the drawing to be copied.

(9) A good quality of white book-paper.

The following directions are to be followed:

Dissolve the chemicals in cold water in these proportions: 1 oz of citrate of iron and ammonia; 1 oz of red prussiate of potash; and 8 oz of water. They may all be put into a bottle together and shaken up. Ten minutes will suffice to dissolve them.

Lay a sheet of the paper to be sensitized on a smooth table or board, pour a little of the solution into the earthen dish or plate, and apply a good even coating of it to the paper with the brush. Then tack the paper to a board by two adjacent corners, and set it in a dark place to dry. One hour is sufficient for the drying. Place the paper, with its sensitized side up, on the board on which you have smoothly tacked the white flannel cloth; lay the tracing to be copied on top of it; on top of all lay the glass plate, being careful that paper and tracing are both smooth and in perfect contact with each other, and lay the whole thing out in the sunlight. Between eleven and two o'clock in the summer-time, on a clear day, from 6 to 10 minutes will be sufficiently long to expose it; at other seasons a longer time will be required. If the location does not admit of direct sunlight, the printing may be done in the shade, or even on a cloudy day; but from 1 to 2½ hours will be required for exposure. A little experience will soon enable any one to judge of the proper time for exposure on different days. After exposure, place the print in the sink or trough of water before mentioned, and wash thoroughly, letting it soak from 3 to 5 minutes. Upon immersion in the water, the drawing, hardly visible before, will appear in clear white lines on a dark-blue ground. After washing, tack up against the wall, or other convenient place, by the corners, to dry. This finishes the operation, which is very simple and thorough. After the copy is dry, it can be written on with a common pen and a solution of common soda, which makes a white line.

**Alternate Recipe for Making Blue-Prints.** The following is an alternative recipe to the one given above. The paper should be prepared by floating it for one minute in a solution of ferricyanide of potassium (red prussiate of potash), 1 oz, and water, 5 oz. It should then be dried in a dark room, afterwards exposed beneath the negative until the dark shades have assumed a deep blue color, and immersed in a solution of water, 2 oz, and bichloride of mercury, 1 gr. The print should be washed, immersed in a hot solution of oxalic acid, 4 dr, and water, 4 oz, washed again and dried. Where a copy of a drawing is to be made the prepared paper is placed, sensitive side uppermost, on a flat board covered with two or three thicknesses of blanket or its equivalent. A tracing of the drawing is made, laid on the sensitized paper and held in place by a sheet of glass clamped to the board. The sensitized paper is exposed to the sunlight from 4 to 10 minutes or to a clear sky from 20 to 30 minutes and then removed, washed and dried. The only requisite as to paper is that it must stand washing. Prepared paper may be purchased.

**Black-Line Copies from Tracings.\*** The directions for making the sensitizing solution used in this process are as follows: Dissolve separately, gum arabic, 13 dr, in 17 oz water; tartaric acid, 13 dr, in 6 oz 6 dr water; persulphate of iron, 3 dr, in 6 oz 6 dr of water. Pour the third solution into the second, stir thoroughly, and then pour the resulting mixture into the first, the stirring being continued. When the mixture is complete, add slowly, still stirring, 3 fl oz and 3 dr of liquid perchloride of iron; filter into a bottle and keep in the dark. Use a strong well-sized paper, apply a thin, smooth coat of the solution with a large brush or sponge, and then dry in a dark room with moderate heat. The

\* There is as yet no known recipe resulting in jet-black lines.

paper should be yellowish in tint and will not keep long. Place the tracing made with very black ink, in the printing-frame, the drawing being in the contact with the glass, and place over it the sensitized paper, with the prepared side in contact with the back of the tracing. After an exposure of 10 or 15 minutes, the print should show a yellow drawing on a white ground. Take the print from the frame and float for a minute, face down, in a developing bath of gallic acid, or tannin, from 31 to 46 gr; oxalic acid,  $1\frac{1}{4}$  gr; and water, 34 oz. Then plunge it in clear water, rinse well and dry. The orange-yellow lines will be changed into a purplish-black.

**Brown-Line Copies from Tracings.** The directions for making the sensitizing solution used in this process are as follows: Dissolve gelatine, 6 gr; water, 1 oz; swell in cold water, give water-bath and add tartaric acid, 8 oz; silver nitrate, 9 gr; and ammonia citrate of iron, 40 gr. Filter in a subdued light. Print in a bright light until slightly darker than ordinary printing-out paper; wash for 5 minutes; immerse in a  $2\frac{1}{2}\%$  solution of hypo until desired color is obtained; and wash and dry. Blue-prints may be turned to a rich-brown color by immersing in a solution of caustic soda the size of a bean dissolved in 5 oz of water, until the blue has changed to orange-yellow. They are then washed thoroughly, immersed in a bath of water in which has been dissolved a heaping teaspoonful of tannic acid, rinsed in clear water and dried. Paper may be sized for brown-prints by soaking it in a mixture of 90 gr of arrowroot and 5 oz of cold water, rubbed into a cream and mixed with 20 gr of glucose and 5 oz of hot water. The mixture should be boiled 2 minutes and then permitted to cool before use.

## **HORSE-POWER,\* PULLEYS, GEARS, BELTING AND SHAFTING**

**Horse-Power.** A horse can travel 400 yd at a walk in  $4\frac{1}{2}$  min, at a trot in 2 min, and at a gallop in 1 min; he occupies at a picket 3 ft by 9 ft; and his average weight is 1 000 lb. An AVERAGE HORSE carrying 225 lb can travel 25 miles in a day of 8 hr. A DRAUGHT-HORSE can draw 1 600 lb 25 miles a day, weight of carriage included. In a HORSE-MILL a horse moves at the rate of  $\frac{1}{2}$  in a second. The diameter of the track should not be less than 25 ft.

A Horse-Power, in Machinery, is estimated at 33 000 lb, raised 1 ft in a minute; but as a horse can exert that force but 6 hr a day, one MACHINERY HORSE-POWER is equivalent to that of four horses.

**Rules to Determine the Size and Speed of Pulleys or Gears.** The driving-pulley is called the DRIVER, and the driven pulley the DRIVEN. If the number of teeth in the gears are used instead of the diameter, in these calculations, number of teeth must be substituted wherever diameter occurs.

(1) To Find the Diameter of the Driver, the diameter of the driven and its revolutions, and also revolutions of driver, being given. Multiply the diameter of the driven by its revolutions, and divide the product by the revolutions of the driver; the quotient will give the diameter of the driver.

(2) To Find the Diameter of the Driven, the revolutions of the driven, also the diameter and revolutions of the driver, being given. Multiply the diameter of the driver by its revolutions, and divide the product by the revolutions of the driven; the quotient will give the diameter of the driven.

(3) To Find the Revolutions of the Driver, the diameter and revolutions of the driven, also the diameter of the driver, being given. Multiply the diameter

\* See, also, pages 1274 and 1397.

of the driven by its revolutions, and divide the product by the diameter of the driver; the quotient will give the revolutions of the driver.

(4) To Find the Revolutions of the Driven, the diameter and revolutions of the driver, also the diameter of the driven, being given. Multiply the diameter of the driver by its revolutions, and divide the product by the diameter of the driven; the quotient will give the revolutions of the driven.

**Horse-Power Transmitted by Belting.** The efficiency of belting to transmit power, or to turn a wheel or PULLEY, depends upon the width and thickness of the belt, the arc-contact with the pulley, the position of the belt, whether horizontal, vertical, or at an angle, and the velocity. The greater the velocity and the thicker the belt, the more power it will transmit. A belt running vertically or inclined will transmit less power than one running horizontally, but in figuring the horse-power capacity of belting only the velocity, width and thickness of belt are usually considered, it being assumed that the pulleys are of proper size and located so that the belt will be nearly horizontal. Belts are commonly assumed to be of LEATHER, unless otherwise designated. The term SINGLE BELT is used to designate a belt made of a single thickness of cowhide leather. A DOUBLE BELT is made by cementing and riveting together two thicknesses of leather. There is no standard thickness for either single or double belts.

**Rules.** Many rules have been given for determining the horse-power that belting will transmit.\* Those commonly used are:

(1) For Single Belts. Multiply the width, in inches, by the velocity in feet per minute and divide by 1 000.

(2) For Double Belts. Multiply the width by the velocity and divide by 700. The answer is the number of horse-powers.

Some authorities give divisors of 800 and 733 for single belts, and 550 and 513 for double belts. For the velocity of the belt multiply the number of revolutions per minute of either pulley by the circumference of that pulley.

**Notes on Belting.** For continuous use a double belt is the most economical in the long run, except on very small pulleys or for very light duty. Triplex and quadruple belts are sometimes used for very heavy duty, but such belts are not commonly carried in stock. Single belts should always be used with the hair-side next the pulley. The belt-speed for maximum economy should be from 4 000 to 4 500 ft per minute. IDLER-PULLEYS work most satisfactorily when located on the slack side of the belt about one-quarter way from the driving-pulley. Belts are more durable and work more satisfactorily when made narrow and thick than when made wide and thin. As belts increase in width they should also be made thicker. For dynamo-work or electric motors the ends of the belt should be fastened together by splicing and cementing instead of by lacing. For all other cases the ends are fastened by hooks or lacing. Belts should be cleaned and greased every 5 to 6 months.

**Distance from Center to Center of Shafts.\*** In locating shafts that are to be connected with each other by belts, care should be taken to separate them by a proper distance. This distance should be such as to allow a gentle sag to the belt when in motion.

**Rule.** A general rule may be stated thus: Where narrow belts are to be run over small pulleys, 15 ft is a good average, the belt having a sag of from 1½ to 2 in. The minimum distance between shafts is about 10 ft. For larger belts, working on larger pulleys, a distance of from 20 to 25 ft does well, with a sag

\* For a discussion of belting, belt-dressing, care of belting, shafting, etc., see Kent's Mechanical Engineers' Pocket-Book.

of from 2½ to 4 in. For main belts, working on very large pulleys, the distance should be from 25 to 30 ft, the belts working well with a sag of from 4 to 5 in. If too great a distance is attempted, the belt will have an unsteady flapping motion, which will destroy both the belt and the machinery.

**Arrangement of Belts and Pulleys.\*** If possible to avoid it, crossed shafts should never be placed one directly over the other, as in such case the belt must be kept very tight to do the work. For this purpose belts should be carefully selected of well-stretched leather. It is desirable that the angle of the belt with the floor should not exceed 45°. It is also desirable to locate the shafting and machinery so that belts will run off from each shaft in opposite directions, as this arrangement will relieve the bearings from the friction that would result if all pulled one way on the shaft. If possible, machinery should be so placed that the direction of the belt-motion will be from the top of the driving to the top of the driven pulley, so that the sag will increase the area of contact. The pulley should be a little wider than the belt required for the work, and should have a crowning face, except where the belt is to be shifted. The motion of driving should run with and not against the laps of the belts.

**Rubber Belts** are cheaper than leather belts and should always be used in wet places, but for ordinary use in dry places they are not as durable as leather belts. They should always be kept free from grease or animal oils. If they slip, their inside surfaces should be moistened with boiled linseed-oil. Some fine chalk, sprinkled on over the oil, will help the belt.

**Rule for Finding the Lengths of Belts.** Add the diameter of the two pulleys together, multiply by 3¼, divide the product by 2, add to the quotient twice the distance between the center of the shafts, and the sum will be the required length.

The Horse-Power that Shafting will Transmit

Diameter of shaft		Revolutions per minute						
		100	150	200	250	300	350	400
in	16th	H.P.	H.P.	H.P.	H.P.	H.P.	H.P.	H.P.
0	15	1.2	1.7	2.4	3.1	3.6	4.3	5.0
1	3	2.4	3.7	4.9	6.1	7.3	8.5	9.7
1	7	4.3	6.4	8.5	10.5	12.7	14.8	16.9
1	11	6.7	10.1	13.4	16.7	20.1	23.4	26.8
1	15	10.0	15.0	20.0	25.0	30.0	35.0	40.0
2	3	14.3	21.4	28.5	35.6	42.7	49.8	57.0
2	7	19.5	29.3	39.0	48.7	58.5	68.2	78.0
2	11	26.0	39.0	52.0	65.0	78.0	87.0	104.0
2	15	33.8	50.6	67.5	84.4	101.3	118.2	135.0
3	3	43.0	64.4	85.8	107.3	128.7	150.3	171.6
3	7	53.6	79.4	107.2	134.0	158.8	187.6	214.4
3	11	65.9	97.9	131.8	164.8	195.7	230.7	263.6
3	15	80.0	120.0	160.0	200.0	240.0	280.0	320.0
4	7	113.9	170.8	227.8	284.7	341.7	398.6	455.6
4	15	156.3	234.4	312.5	390.6	468.7	546.8	625.0

\* See Kent's Mechanical Engineers' Pocket-Book.

CHAIN-BLOCKS, HOLSTS, HOOKS, ETC.

**General Description.** These are portable hoisting-devices which enable one to raise a very heavy load and which sustain the load at any point. In al, they resemble pulleys operated by chains. Since the invention of the ential pulley-block by T. A. Weston, about the year 1863, chain-blocks come into very general use for economical hoisting, particularly where it is ad to hold the load at any point. Chain-blocks are of three general classes:

**The Differential Block.** This is the original and the simplest and cheap-orm of self-sustaining pulley;

**The Screw-Block or Worm-Geared Block.** Of these, the Yale & Towne x block is the most efficient type;

**The Triplex Block.** This is spur-gearred.

fferential and worm-geared blocks of all kinds depend upon friction to pre-the load from running down. In the triplex block a separate device is duced which automatically holds the load safely, and yet enables it to be ed with slight effort and at high velocity but without acceleration or danger. is the most efficient of all chain-blocks, and the most economical wherever : work is wanted and economy in time and labor sought. For information the kind of block best adapted to any particular service, the manufacturers d be consulted. The following data on the power and efficiency of chain- s were supplied by the Yale & Towne Manufacturing Company.

**Power and Efficiency of Chain-Hoists.** The table below gives the work done by the operator at the hand-pulling chain with each size of the various s of chain-blocks in lifting the stated capacity, that is, the amount of work ulling required to lift this load ONE FOOT by stating the force exerted in ds and the distance in feet of operating-chains to be pulled. The product se two factors determines the efficiency of the block and the ease and speed isting. The 12, 16, and 20-ton-capacity chain-blocks have each two hand-s.

Work Done by Operator with Chain-Blocks

Capacity, tons	Triplex spur-gearred, lb ft	Duplex worm-gearred, lb ft	Differential lb ft
1/2	62 X 21	68 X 40	122 X 24
1	82 X 31	87 X 59	216 X 30
1 1/2	110 X 35	94 X 80	246 X 36
2	120 X 42	115 X 93	308 X 42
3	114 X 69	132 X 126	557 X 38
4	124 X 84	142 X 155	.....
5	110 X 126	145 X 195	.....
6	130 X 126	145 X 252	.....
8	135 X 168	160 X 310	.....
10	140 X 210	160 X 390	.....
12	130 X 126	.....	.....
16	135 X 168	.....	.....
20	140 X 210	.....	.....

he capacities are given in tons. The figures give the number of feet to perated on each hand-chain. A man cannot pull more than his own ht on the operating chains, and can pull faster in proportion as the pull red is lighter. The maximum pull usually required of one man is 82 lb, he will do more work with less fatigue if the hand-chain pull is not over

40 lb, because he can then pull the chain hand over hand a little more than as fast as he could when pulling twice as hard. When the hand-chain is less than 20 lb the speed of hoisting an equal load is diminished, because he is tired by moving his arms too rapidly, and cannot do as much work as a heavier pull. The best result is obtained by using a chain-block with a capacity of double the usual load. The operator then works to the advantage with average loads, and occasional heavy loads are easily handled out overstraining either the operator or the chain-block, which should not be used beyond its capacity for fear of stretching the chain so that it will not run smoothly.

**Proportions of Hooks.\*** For the manufacture of hooks of different sizes made from some regular commercial size of round iron. The basis, or initial size in each case is, therefore, the size of iron of which the hook is to be made. It is indicated by the dimension  $A$  in the diagram. The dimension  $D$  is arbitrarily assumed. The other dimensions, as given by the formulas, are those which, in preserving a proper bearing face on the interior of the hook for the ropes or chains which may be passed through it, give the greatest resistance to spreading and ultimate rupture which the amount of material in the original bar admits of. The symbol  $\Delta$  is used in the formulas to indicate the NOMINAL CAPACITY of the hook in tons of 2 000 lb. The formulas which determine the lines of the other parts of the hooks of the several sizes are as follows, all the measurements being expressed in inches:

$$\begin{array}{ll}
 D = 0.5 \Delta + 1.25 & G = 0.75 D \\
 E = 0.64 \Delta + 1.60 & O = 0.363 \Delta + 0.66 \\
 F = 0.33 \Delta + 0.85 & Q = 0.64 \Delta + 1.60 \\
 H = 1.08 A & L = 1.05 A \\
 I = 1.33 A & M = 0.50 A \\
 J = 1.20 A & N = 0.85 B - 0.16 \\
 K = 1.13 A & U = 0.866 A
 \end{array}$$

**Example.** To find the dimension  $D$ , for a 2-ton hook. The formula is

$$D = 0.5 \Delta + 1.25$$

and as  $\Delta = 2$ , the dimension  $D$  by the formula is found to be  $2\frac{1}{4}$  in. The dimensions  $A$ , are necessarily based upon the ordinary merchant sizes of round iron. The sizes which it has been found best to select are the following:

Capacities of hooks	$\frac{1}{8}$	$\frac{3}{8}$	$\frac{1}{2}$	1	$1\frac{1}{2}$	2	3	4	5	6	8	10 tons
Dimension $A$ . . .	$\frac{3}{8}$	$1\frac{1}{8}$	$\frac{3}{4}$	$1\frac{1}{4}$	$1\frac{3}{4}$	$1\frac{7}{8}$	$1\frac{3}{4}$	2	$2\frac{1}{4}$	$2\frac{3}{4}$	$2\frac{3}{4}$	$3\frac{1}{4}$ inches

The formulas which give the sections of the hook at the several points are all expressed in terms of  $A$ , and can therefore be readily ascertained by reference to the foregoing scale.

\* By Henry R. Towne, in his *Treatise on Cranes*, which includes the results of extensive experimental and mathematical investigation.

**Example.** To find the dimension  $I$ , in a 2-ton hook. The formula is

$$I = 1.33 A$$

For a 2-ton hook,  $A = 1\frac{3}{4}$  in. Therefore  $I$ , in a 2-ton hook, is found to be in.

**Manner of Failure of Hooks.** Experiment has shown that hooks made according to the above formulas will give way first by the opening of the jaw, and, however, will not occur except with a load much in excess of the nominal capacity of the hook. This yielding of the hook when overloaded becomes a matter of safety, as it constitutes a signal of danger which cannot easily be overlooked, and which must proceed to a considerable length before rupture occurs after the load is dropped. A comparison of these hooks with most of those in ordinary use shows that the latter are, as a rule, badly proportioned, and frequently dangerously weak.

## BELLS

### Dimensions and Weights of Church-Bells

Manufactured by Meneely Bell Company, Troy, N. Y.

Bells		Mountings			
Weights, lb	Medium tones	Diameters, in	Sizes of frames, outside, in	Diameters of wheels, ft in	
400	D	27	42×42	4	4
450	C♯	28	42×42	4	4
500	C	29	45×47	4	4
550	C	30	45×47	4	4
600	B	31	45×47	4	9
700	B	33	48×48	5	6
800	B♭	34	48×54	5	6
900	A	36	54×54	5	9
1 000	A	37	54×54	5	9
1 100	A	38	54×59	5	9
1 200	A♭	39	56×59	6	3
1 300	A♭	40	56×59	6	3
1 400	G	41	60×60	6	6
1 500	G	42	60×60	6	6
1 600	G	43	60×60	6	6
1 800	F♯	45	65×68	7	
2 000	F	46	65×68	7	
2 100	F	47	65×68	7	
2 300	E	49	70×72	7	6
2 500	E	50	70×72	7	6
2 800	E♭	51	74×78	8	
3 000	E♭	53	74×78	8	
3 500	D	56	74×78	8	6
4 000	C♯	58	78×81	9	
4 500	C	61	78×81	9	
5 000	C	63	84×84	9	
5 500	B	65	84×84	9	
6 000	B♭	67	84×84	9	6
6 500	B♭	68	90×90	9	6
7 000*	B♭	69	101×90	9	6

A notable example of a 7 000-lb bell is the large bell of the peal in the tower of the Metropolitan Life Insurance Building, in New York.

The actual weights usually exceed the patterns, noted above, from 2 to 3%.

Meneely School-Bells

Bells		Mountings			
Weights, lb	Diameters, in	Sizes of frames, outside,			
		ft in		ft in	
100	17	2	6	2	8
125	18½	2	6	2	8
150	19½	2	6	2	8
200	21½	2	8	3	0
250	23	3	0	3	2
300	24½	3	0	3	4
350	26	3	0	3	4

Sizes of Rope for Bells

	Diameter, in
For bells of less than 500 lb.....	½
For bells of 500 to 800 lb.....	¾
For bells of 800 to 1 800 lb.....	¾
For bells above 1 800 lb.....	1 to 1

The Largest Bells in the World \*

Names and locations of bells	Date cast	Actual vibra- tion	Key- note	Diam- eter, in	Sound-bow		Weight
					Inches	Stroke	
Moscow, Tzar Kolokol †	1733	74	D	272	23	0.84	113 7/8
Burmah, Mingoona .....	.....	94	F♯	203?	16?	0.80	221 1/2
Moscow, St. Ivan's.....	1819	105	G♯	185	14.75	0.80	117 1/2
Pekin, Great Bell.....	.....	.....	.....	156	.....	.....	120 1/2
Burmah, Maha Ganda..	.....	125	B	155	12.5	0.80	95 1/2
Nishni Novgorod.....	.....	125	B	151	12	0.80	69 1/2
Moscow, Church of Re- deemer.....	1879	141	C♯	136.3?	10.6	0.80	60 1/2
Nankin, China.....	.....	.....	.....	112	.....	.....	6 1/2
London, St. Paul's.....	1881	157	E♭	114.25	8.75	0.76	42 1/2
Olmütz, Bohemia.....	.....	157	E♭	121	9.125	0.75	40 1/2
Vienna, Austria.....	1711	157	E♭	118	9.5	0.80	42 1/2
Westminster, London....	1856	166	E	113.5	9.375	0.83	35 1/2
Erfurt, Saxony.....	1487	176	F	103.6	9.75	0.75	30 1/2
Notre Dame, Paris.....	1680	166	E	103	7.5	0.73	26 1/2
Montreal, Canada.....	1847	176	F	103	7.8	0.76	26 1/2
York, England.....	1845	187	F♯	100	8	0.80	24 1/2
St. Peter's, Rome.....	1786	187	F♯	97.25	7.5	0.77	18 1/2
Great Tom, Oxford.....	1680	210	G♯	84	6.125	0.73	17 1/2
Cologne, Germany.....	1477	198	G	95	7.2	0.76	16 1/2
Brussels, Belgium.....	.....	210	G♯	95.81	7.75	0.71	15 1/2
State-house, Philadelphia	1875	198	G	88	6.375	0.73	13 1/2
Lincoln, England.....	1834	210	G♯	82.85	6	0.73	12 1/2
St. Paul's, London.....	1716	222	A	81	6.08	0.75	11 1/2
Exeter, England.....	1675	210	G♯	76	5	0.66	10 1/2
Old Lincoln, England...	1610	249	B	75.5	5.94	0.78	9 1/2
Westminster, London....	1857	249	B	72	5.75	0.79	8 1/2

\* John W. Nystrom, in the Journal of the Franklin Institute, Philadelphia.  
† This bell is fractured and has not been rung for many years.



## SYMBOLS FOR THE APOSTLES AND SAINTS

From the constant occurrence of symbols in the edifices of the Middle Ages and many of the cathedrals of the present day, the following list of symbols, as commonly attached to the apostles and saints, may be found useful:

### Holy Apostles

**Peter.** Bears a key, or two keys with different wards.  
**Andrew.** Leans on a cross so called from him; called by heralds the saltire.  
**John the Evangelist.** With a chalice, in which is a winged serpent. When this symbol is used, the eagle, another symbol of him, is never given.  
**Bartholomew.** With a flaying-knife.  
**James the Less.** A fuller's staff bearing a small square banner.  
**James the Greater.** A pilgrim's staff, hat and escalop-shell.  
**Thomas.** An arrow, or with a long staff.  
**Simon.** A long saw.  
**Jude.** A club.  
**Matthias.** A hatchet.  
**Philip.** Leans on a spear or has a long cross in the shape of a T.  
**Matthew.** A knife or dagger.  
**Mark.** A winged lion.  
**Luke.** A bull.  
**John.** An eagle.  
**Paul.** An elevated sword, or two swords in saltire.  
**John the Baptist.** An Agnus Dei.  
**Stephen.** With stones in his lap.

### Saints

**Agnes.** A lamb at her feet.  
**Cecilia.** With an organ.  
**Tlement.** With an anchor.  
**David.** Preaching on a hill.  
**Denis.** With his head in his hands.  
**George.** With the dragon.  
**Nicholas.** With three naked children in a tub, in the end whereof rests his pastoral staff.  
**Vincent.** On the rack.

## CIRCULAR OF ADVICE RELATIVE TO PRINCIPLES OF PROFESSIONAL PRACTICE AND THE CANONS OF ETHICS, BY THE AMERICAN INSTITUTE OF ARCHITECTS \*

### A Circular of Advice

**Prefatory.** The American Institute of Architects, seeking to maintain a standard of practice and conduct on the part of its members as a safeguard of the important financial, technical and esthetic interests entrusted to them, presents the following advice relative to professional practice: The profession of architecture calls for men of the highest integrity, business capacity and artistic

The American Institute of Architects, Document No. 141, Washington, D. C., 1919. Reprinted by permission. This circular relates to the principles of professional practice and the canons of ethics.

ability. The architect is entrusted with financial undertakings in which honesty of purpose must be above suspicion; he acts as professional adviser to his client and his advice must be absolutely disinterested; he is charged with the exercise of judicial functions as between client and contractors and must act with entire impartiality; he has moral responsibilities to his professional associates and subordinates; finally, he is engaged in a profession which is charged with it grave responsibility to the public. These duties and responsibilities cannot be properly discharged unless his motives, conduct and ability are such as to command respect and confidence. No set of rules can be framed which will particularize all the duties of the architect in his various relations to his clients, to contractors, to his professional brethren, and to the public. The following principles should, however, govern the conduct of members of the profession and should serve as a guide in circumstances other than those enumerated:

(1) **On the Architect's Status.** The architect's relation to his client is primarily that of PROFESSIONAL ADVISER; this relation continues throughout the entire course of his service. When, however, a contract has been entered into between his client and a contractor by the terms of which the architect becomes the official interpreter of its conditions and the judge of its performance, an additional relation is created under which it is incumbent upon the architect to side neither with client nor contractor, but to use his powers under the contract to enforce its faithful performance by both parties. The fact that the architect's payment comes from the client does not invalidate his obligation to act with impartiality to both parties.

(2) **On Preliminary Drawings and Estimates.** The architect at the outset should impress upon the client the importance of sufficient time for the preparation of drawings and specifications. It is the duty of the architect to make or secure PRELIMINARY ESTIMATES when requested, but he should accept the client with their conditional character and inform him that complete final figures can be had only from complete and final drawings and specifications. If an unconditional limit of cost be imposed before such drawings are made and estimated, the architect must be free to make such adjustments as seem to be necessary. Since the architect should assume no responsibility that may prevent him from giving his client disinterested advice, he should not, by his estimate, otherwise, guarantee any estimate or contract.

(3) **On Superintendence and Expert Services.** On all work except the simplest, it is to the interest of the owner to employ a SUPERINTENDENT OF THE WORKS. In many engineering problems and in certain specialized architectural problems, it is to his interest to have the services of special experts and the architect should so inform him. The experience and special knowledge of the architect make it to the advantage of the owner that these persons, when paid by the owner, should be selected by the architect under whose direction they are to work.

(4) **On the Architect's Charges.** The SCHEDULE OF CHARGES of the American Institute of Architects is recognized as a proper minimum of payment. The locality or the nature of the work, the quality of services to be rendered, the skill of the practitioner or other circumstances frequently justify a charge greater than that indicated by the schedule.

(5) **On Payment for Expert Service.** The architect when retained as an EXPERT, whether in connection with competitions or otherwise, should receive a compensation proportionate to the responsibility and difficulty of the service. No duty of the architect is more exacting than such service, and the honor

profession is involved in it. Under no circumstances should experts know-name prices in competition with each other.

**On Selection of Bidders or Contractors.** The architect should advise client in the selection of BIDDERS and in the AWARD OF THE CONTRACT. In seeing that none but trustworthy bidders be invited and that the award be made only to contractors who are reliable and competent, the architect protects the interests of his client.

**On Duties to the Contractor.** As the architect decides whether or not the intent of his plans and specifications is properly carried out, he should exercise special care to see that these drawings and specifications are complete and correct, and he should never call upon the contractor to make good oversights or errors in them nor attempt to shirk responsibility by indefinite clauses in the contract or specifications.

**On Engaging in the Building Trades.** The architect should not directly or indirectly engage in any of the BUILDING TRADES. If he has any financial interest in any building material or device, he should not specify or use it without the knowledge and approval of his client.

**On Accepting Commissions or Favors.** The architect should not accept any COMMISSION or any substantial service from a contractor or from any interested person other than his client.

**On Encouraging Good Workmanship.** The large powers with which the architect is invested should be used with judgment. While he must condemn bad work, he should commend good work. Intelligent initiative on the part of craftsmen and workmen should be recognized and encouraged and the architect should make evident his appreciation of the dignity of the ARTISAN'S Vocation.

**On Offering Services Gratuitously.** The seeking out of a possible client and the offering to him of professional services on approval and WITHOUT COMPENSATION, unless warranted by personal or previous business relations, tends to lower the dignity and standing of the profession and is to be condemned.

**On Advertising.** Publicity of the standards, aims and progress of the profession, both in general and as exemplified by individual achievement, is essential. Advertising of the individual, meaning self-laudatory publicity initiated by the person advertised or with his consent, tends to defeat its own purpose to the individual as well as to lower the dignity of the profession, and is to be deplored.

**On Signing Buildings and Use of Titles.** The unobtrusive SIGNATURE OF THE ARCHITECT ON BUILDINGS after completion is desirable. The placing of the ARCHITECT'S NAME ON A BUILDING DURING CONSTRUCTION serves a legitimate purpose for the dissemination of information, but it is to be deplored if done obtrusively for individual publicity. The use of INITIALS designating membership in the Institute is desirable in all professional relationships, in order to promote a general understanding of the Institute and its standards through a knowledge of its members and their professional activities. Upon the members devolves the responsibility to associate the symbols of the Institute with acts representative of the highest standards of professional practice.

**On Competitions.** An architect should not take part in a competition as COMPETITOR or JUROR unless the competition is to be conducted according to the best practice and usage of the profession, as evidenced by its having received the approval of the Institute, nor should he continue to act as PROFESSIONAL ADVISER after it has been determined that the program cannot be so

drawn as to receive such approval. When an architect has been authorized to submit sketches for a given project, no other architect should submit sketches for it until the owner has taken definite action on the first sketches. As far as the second architect is concerned, a competition is thus established. Except as an authorized competitor, an architect may not attempt to secure work for which a competition has been instituted. He may not attempt to influence the award in a competition in which he has submitted drawings. He may not accept the commission to do the work for which a competition has been instituted if he has acted in an advisory capacity either in drawing the project or in making the award.

**(15) On Injuring Others.** An architect should not falsely or maliciously injure, directly or indirectly, the professional reputation, prospects or business of a fellow architect.

**(16) On Undertaking the Work of Others.** An architect should not undertake a commission while the claim for compensation or damages or both of an architect previously employed and whose employment has been terminated remains unsatisfied, unless such claim has been referred to arbitration or has been joined at law; or unless the architect previously employed agrees to press his claim legally; nor should he attempt to supplant a fellow architect after definite steps have been taken toward his employment.

**(17) On Duties to Students and Draughtsmen.** The architect should advise and assist those who intend making architecture their career. A beginner must get his training solely in the office of an architect, the latter should assist him to the best of his ability by instruction and advice. An architect should urge his draughtsmen to avail themselves of educational opportunities. He should, as far as practicable, give encouragement to all worthy agencies and institutions for architectural education. While a thorough technical preparation is essential for the practice of architecture, architects cannot too strongly insist that it should rest upon a broad foundation of general culture.

**(18) On Duties to the Public and to Building Authorities.** An architect should be mindful of the public welfare and should participate in all movements for public betterment in which his special training and experience qualify him to act. He should not, even under his client's instructions, create or encourage any practices contrary to law or hostile to the public interest. For as he is not obliged to accept a given piece of work, he cannot, by urging that he has but followed his client's instructions, escape the condemnation attached to his acts. An architect should support all public officials who have charge of building in the rightful performance of their legal duties. He should fully comply with all building laws and regulations, and if any such appear to him unwise or unfair, he should endeavor to have them altered.

**(19) On Professional Qualifications.** The public has the right to expect that he who bears the TITLE OF ARCHITECT has the knowledge and ability necessary for the proper invention, illustration and supervision of all building operations which he may undertake. Such qualifications alone justify the assumption of the title of architect.

### The Canons of Ethics \*

The following Canons are Adopted by The American Institute of Architects as a general guide, yet the enumeration of particular duties is

\* Adopted, December 14-16, 1909. Revised, December 10-12, 1912. Revised, 1918.

It be construed as a denial of the existence of others equally important although not specially mentioned. It should also be noted that the several sections indicate offenses of greatly varying degrees of gravity. It is unprofessional for an architect

- (1) To engage directly or indirectly in any of the building or decorative trades.
- (2) To guarantee an estimate or contract by bond or otherwise.
- (3) To accept any commission or substantial service from a contractor or from any interested party other than the owner.
- (4) To take part in any competition which has not received the approval of the Institute or to continue to act as professional adviser after it has been determined that the program cannot be so drawn as to receive such approval.
- (5) To attempt in any way, except as a duly authorized competitor, to secure work for which a competition is in progress.
- (6) To attempt to influence, either directly or indirectly, the award of a competition in which he is a competitor.
- (7) To accept the commission to do the work for which a competition has been instituted if he has acted in an advisory capacity, either in drawing the program or in making the award.
- (8) To injure falsely or maliciously, directly or indirectly, the professional reputation, prospects, or business of a fellow architect.
- (9) To undertake a commission while the claim for compensation, or damages, both, of an architect previously employed and whose employment has been terminated remains unsatisfied, until such claim has been referred to arbitration or issue has been joined at law, or unless the architect previously employed neglects to press his claim legally.
- (10) To attempt to supplant a fellow architect after definite steps have been taken toward his employment, that is, by submitting sketches for a project for which another architect has been authorized to submit sketches.
- (11) To compete knowingly with a fellow architect for employment on the basis of professional charges.

### **Professional Practice of Architects. Details of Service to be Rendered and Schedule of Proper Minimum Charges \***

- (1) The architect's professional services consist of the necessary conferences, the preparation of preliminary studies, working drawings, specifications, large-scale and full-size detail drawings; the drafting of forms of proposals and contracts; the issuance of certificates of payment; the keeping of accounts, the general administration of the business and supervision of the work, for which, except as hereinafter mentioned, the minimum charge, based upon the total cost of the work † complete, is 6 per cent.
- (2) On residential work, alterations to existing buildings, monuments, furniture, decorative and cabinetwork and landscape-architecture, it is proper to make a higher charge than above indicated.

\* As adopted at the Washington, D. C., Convention, December 15-17, 1908, and revised in form at the Minneapolis convention, December 6-8, 1916.

† The words "the cost of the work," as used in Articles (1) and (9) hereof, are ordinarily to be interpreted as meaning the total of the contract-sums incurred for the execution of the work, not including architect's and engineer's fees or the salary of the clerk of the works, but in certain rare cases, that is, when labor or material is furnished by the owner at its market cost or when old materials are reused, the cost of the work is to be interpreted as the cost of all materials and labor necessary to complete the work, as such cost would have been if all materials had been new and if all labor had been fully paid at market prices current when the work was ordered, plus contractor's profits and expenses.

(3) The architect is entitled to compensation for articles purchased in his direction, even though not designed by him.

(4) Where the architect is not otherwise retained, consultation-fees for professional advice are to be paid in proportion to the importance of the question involved and services rendered.

(5) The architect is to be reimbursed for the costs of transportation and living incurred by him and his assistants while traveling in discharge of duty connected with the work, and the costs of the services of heating, ventilating, mechanical, and electrical engineers.

(6) The rate of percentage arising from Articles (1) and (2) hereof, that is the basic rate, applies when all of the work is let under one contract. Should the owner determine to have certain portions of the work executed under separate contracts, as the architect's burden of service, expense, and responsibility is thereby increased, the rate in connection with such portions of the work is greater (usually by 4 per cent) than the basic rate. Should the owner determine to have substantially the entire work executed under separate contracts then such higher rate applies to the entire work. In any event, however, the basic rate, without increase, applies to contracts for any portions of the work on which the owner reimburses the engineer's fees to the architect.

(7) If, after a definite scheme has been approved, the owner makes a decision which, for its proper execution, involves extra services and expense for change in or additions to the drawings, specifications, or other documents; or if a contract be let by cost of labor and materials plus a percentage or fixed sum; or if the architect be put to labor or expense by delays caused by the owner or a contractor, or by the delinquency or insolvency of either, or as a result of damage by fire, he is to be equitably paid for such extra service and expense.

(8) Should the execution of any work designed or specified by the architect or any part of such work be abandoned or suspended, the architect is to be paid in accordance with or in proportion to the terms of Article (9) of this Schedule for the service rendered on account of it, up to the time of such abandonment or suspension.

(9) Whether the work be executed or whether its execution be suspended or abandoned in part or whole, payments to the architect on his fee are subject to the provisions of Articles (7) and (8), made as follows: Upon completion of the preliminary studies, a sum equal to 20 per cent of the basic rate computed upon a reasonable estimated cost. Upon completion of specifications and general working drawings (exclusive of details) a sum sufficient to increase payments on the fee to sixty per cent of the rate or rates of commission agreed upon as influenced by Article (6), computed upon a reasonable cost estimated of such completed specifications and drawings, or if bids have been received then computed upon the lowest bona-fide bid or bids. From time to time during the execution of work and in proportion to the amount of service rendered by the architect, payments are made until the aggregate of all payments made on account of the fee under this Article reaches a sum equal to the rate or rates of commission agreed upon as influenced by Article (6), computed upon the final cost of the work. Payments to the architect, other than those on his fee, fall due from time to time as his work is done or as costs are incurred. No deduction is made from the architect's fee on account of penalty, Equitable damages or other sums withheld from payments to contractors.

(10) The owner is to furnish the architect with a complete and accurate survey of the building-site, giving the grades and lines of streets, pavements and adjoining properties; the rights, restrictions, easements, boundaries and contours of the building-site, and full information as to sewer, water, gas and

technical service. The owner is to pay for borings or test-pits and for chemical or mechanical or other tests, when required.

(11) The architect endeavors to guard the owner against defects and deficiencies in the work of contractors, but he does not guarantee the performance of their contracts. The supervision of an architect is to be distinguished from a continuous personal superintendence to be obtained by the employment of a clerk of the works. When authorized by the owner, a clerk of the works, acceptable to both owner and architect, is to be engaged by the architect at a salary satisfactory to the owner and paid by the owner, upon presentation of the architect's monthly certificates.

(12) When requested to do so, the architect makes or procures preliminary estimates on the cost of the work and he endeavors to keep the actual cost of the work as low as may be consistent with the purpose of the building and with proper workmanship and material, but no such estimate can be regarded as other than an approximation.

(13) Drawings and specifications, as instruments of service, are the property of the architect, whether the work for which they are made be executed or not.

## ARCHITECTURAL COMPETITIONS \*

This Circular of Advice furnishes information as to the best methods of conducting architectural competitions and states the conditions which are prerequisite to participation in them by members of The American Institute of Architects. It does not apply to competitions for work to be erected elsewhere than in the United States, its territories and possessions.

**The Attitude of The American Institute of Architects to Competitions.** Since its foundation, more than sixty years ago (1857), The American Institute of Architects has given much attention to the conduct of ARCHITECTURAL COMPETITIONS. These contests, instituted when the direct selection of an architect could not be made, were for many years conducted without proper regulation and often in disregard of the interests both of the owner and of the competitors. The owner, totally unfamiliar with the intricacies of the subject, assumed, without skilled assistance, to prepare the programme, laying down, or more frequently borrowing, rules to govern procedure. With the growth of the country, the increase in expenditures for public and private buildings, and the increase in the number of architects, all the evils of ill-regulated competitions became more marked. Programmes varied from loose and careless forms, difficult to understand and often open to the suspicion that only the initiator knew what they meant, to over-elaborate ones necessitating useless study of details and needless drawings. Those instituting the competition often had no legal authority to pay the competitors, still less to employ the winner. There was great economic waste, the total cost of participation exceeding the total net profit accruing to the profession from work secured through competitions. Architects have learned from the outcome of a competition, unless governed by well-defined agreements, that it was largely a matter of chance. The owner has, to be sure, a choice of designs, but

The American Institute of Architects, Document 114. Reprinted by permission. Authorized by the 43d annual convention at Washington, D. C., December 14-16, 1909; amended March 30, 1910, amended June 10, 1910; and January 3, 1911; ratified by the 44th annual convention at San Francisco, January 16-21, 1911; reaffirmed by the 45th annual convention at Washington, D. C.; amended January 3, 1912, as authorized by the 46th annual convention; amended December 9, 1912, and ratified by the 46th annual convention at Washington, D. C., December 10-12, 1912; amended December 2, 1913, and ratified by the 47th annual convention at New Orleans, La., December 3-5, 1913; amended and ratified by the 48th annual convention at Washington, D. C., December 2-4, 1914.

he is no more likely to make the wisest selection or to obtain the best building than if he selects his architect directly, guided by the results previously achieved by the men he is considering. When a competition is necessary or desirable it should be of such form as to establish equitable relations between the owner and the competitors. To insure this:

(1) The REQUIREMENTS should be clear and definite, and the statement of them, since it must be in technical terms, should be drawn by one familiar with such terms.

(2) The COMPETENCY of all competing should be assured. The drawings submitted in a competition are evidence, only in part, of the ability of the architect to execute the building. The owner, for his own protection, should admit to the competition only those to whom he would be willing to entrust the work; that is, to men of known honesty and competence.

(3) The AGREEMENT between the owner and the competitors should be definite, as becomes a plain statement of business relations.

(4) The JUDGMENT should be based on knowledge, and since ideas presented in the form of drawings are intelligible only to a trained mind, judgment should not be rendered until the owner has received competent technical advice as to the merits of those ideas.

To sum up: To insure the best results, a competition should have (1) a clear programme, (2) competent competitors, (3) a business agreement, (4) a fair judgment.

Fifteen years ago many competitions had none of these provisions and few had all of them. The commonest form of competition was one that was open to all, had a programme prepared by a layman, was judged by the owner without professional assistance, contained no agreement, and made no provision to eliminate the incompetent. All this demanded correction. The Institute, seeking a means of reform, perceived at once that its relation to the owner could be only an ADVISORY one. It might advise him how to hold a competition, but it could go no further. To architects in general the Institute could scarcely presume to offer even its advice, but being a professional body charged with maintaining ethical standards among its own members, its duty was to see that they did not take part in competitions that fell below a reasonable standard.

It was, therefore, voted in convention of the Institute that members should be free to take part in competitions only when their terms had received the APPROVAL OF THE INSTITUTE. Thereupon the Institute fully stated the principles which should govern competitions and defined the conditions prerequisite to the giving of its approval. These are contained in the CIRCULAR OF ADVICE here following, which is intended as a guide to all who are interested in competitions. Committees of the Institute throughout the country are authorized to give its approval to competitions when properly conducted, but unless a programme has received such approval members of the Institute do not accept a position as competitor or juror, nor does a member continue to act as professional adviser after it becomes evident that the owner will not permit his programme to be brought into harmony with the principles approved by the Institute.

The position thus taken by the Institute is by no means an arbitrary one, since it governs the action of none but its own members. To the owner its service has been of great value in giving him information and useful advice and in saving him from the delays, cost and disappointment incident to the amateur conduct of a competition. The owner who disregards the standard set by the Institute finds it increasingly difficult to get men of standing in the profession to enter. He who raises his programme to that standard has no difficulty in securing the



vices of architects of the greatest ability. Even in the few years since the Institute first made its firm stand against the abuses of competitions, the effect of that action has been far greater than could have been foreseen. It has not only eliminated ill-regulated competitions, but it has greatly reduced their number, and it is safe to say that no competition of prime importance is now conducted except in accordance with the principles stated in the following CIRCULAR OF ADVICE:

### **Circular of Advice and Information Relative to the Conduct of Architectural Competitions**

Competitions are instituted to enable the OWNER \* to choose an ARCHITECT through comparison of the designs submitted. The American Institute of Architects, believing that the interests of both owner and competitors are best served by fair and equitable agreements between them, issues this circular as a STATEMENT OF THE PRINCIPLES which should underlie such agreements. The Institute does not assume to dictate the owner's course in conducting competitions, but seeks to assist him by advising the adoption of such methods as experience has proved to be just and wise. So important, however, does the adoption of such methods appear to architects that members of the Institute do not take part in competitions except under conditions based on this circular and specifically set forth in Articles (16) and (18).

1) **On Competitions in General.** A competition exists when two or more architects prepare sketches at the same time for the same project, but no architect who prepares drawings for comparison in problems of an altruistic or educational nature, where the problem does not involve a definite proposed building operation, shall be held as having taken part in a competition, within the meaning of this circular of advice.

2) **On the Employment of a Professional Adviser.** No competition shall be instituted without the aid of a competent ADVISER. He should be an architect of the highest standing and his selection should be the owner's first choice. He must be chosen with the greatest care, as the success of the competition depends largely upon his experience and ability. The EXPERT'S ADVICE is of great value to the owner, for example, in so drawing the programme as to guard him against the employment of an architect who submits a design greatly exceeding in cost of execution the sum at his disposal, and in helping him to avoid the disappointment, embarrassment and litigation which so often result from competitions conducted without expert technical advice. The DUTIES OF THE EXPERT are to advise those who hold the competition as to its form and conditions, to draw up the programme, to advise in choosing the competitors, to answer their questions, and to conduct the competition.

3) **On the Forms of Competition.** The following forms of competition are recognized:

**LIMITED.** In this form, participation is limited to a certain number of architects whose names should be stated in the programme and to any one of whom the owner is willing to entrust the work. In a LIMITED COMPETITION the competitors may be chosen (a) from among architects whose ability is so evident that no formal inquiry into their qualifications is needed, or (b) from among architects who make application accompanied by evidence of their education and experience. The limited form has the advantage that the owner and the professional adviser may meet competitors and discuss the terms of the com-

The person, corporation or other entity instituting a competition, whether acting directly or through representatives, is herein called the OWNER.

petition with them before the issuance of the programme Form (a) is the simplest and most direct form of competition.

**OPEN.** The Institute believes that a competition **OPEN TO ALL** who wish to participate without regard to their qualifications is detrimental to the interests alike of owner and of architects. It will, therefore, give its approval to that form only when conducted in two stages, since by that means alone it is possible to insure anonymity of submission while safeguarding the owner's interests against the selection as winner of a person lacking the qualifications set forth in Article (4) hereof. In this form there is a **FIRST STAGE** open to all, in which the competitive drawings are of the slightest nature, involving only the fundamental ideas of the solution. These drawings are accompanied by evidence of the competitor's education and experience. From the first stage a small number who have thus demonstrated their competence to design the work and to carry it successfully into execution are chosen to take part in a **FINAL** and strictly **ANONYMOUS STAGE** involving competitive drawings of the type indicated in Article (4) hereof.

**(4) On the Qualification of Competitors.** The interests of the owner may be seriously prejudiced by admitting to a limited competition or to the second stage of an open competition any architect who has not established to the satisfaction of the owner his competence to design and execute the work. It is sometimes urged that by admitting all who wish to take part some unknown but brilliant designer may be found. If the object of a competition were a series of sketches, such reasoning might be valid. But sketches give no evidence that their author has the matured artistic ability to fulfil their promise, or that he has the technical knowledge necessary to control the design of the highly complex structure and equipment of a modern building, or that he has executive ability for large affairs, or the force to compel the proper execution of contracts. Attempts have often been made to defend the owner's interests by associating an architect of ability with one lacking in experience. These have generally resulted in failure. As the owner should feel bound, not only legally, but at a point of honor, to retain as his architect the competitor to whom the award is made, it is essential that the competitors in a limited competition, or in the second stage of an open competition, should be selected with the greatest care in consultation with the professional adviser, and that there should be included among them only architects in whose ability and integrity the owner has absolute confidence, and to any one of whom he is willing to entrust the work.

**(5) On the Number of Competitors.** Experience has demonstrated that the admission of **MANY COMPETITORS** is detrimental to the success of a competition. When there are many, each knows that he has but a slight chance of success, and he is therefore less aroused to his best effort than when there are a few. As the owner is interested only in the best result, he is ill-advised to sacrifice quality for quantity.

**(6) On Anonymity of Competitors.** Absolute and effective **ANONYMITY** is a necessary condition of a fair and unbiased competition. The **SIGNATURES** on **DRAWINGS** should not be permitted nor should they bear any motto, device or distinguishing mark. Drawings and the accompanying sealed envelopes containing their authors' names should be numbered upon receipt, the envelopes remaining unopened until after the award.

**(7) On the Cost of the Proposed Work.** No statement of the intended **COST OF THE WORK** should be made unless it has been ascertained that the work as described in the programme can be properly executed within the sum named. In general it is wiser to limit the cubic contents of the building than to state

of cost. The programme should neither require nor permit competitors to furnish their own or builders' estimates of the cost of executing the work in accordance with their designs. Such estimates are singularly unreliable. If cubage be properly limited they are unnecessary.

**3) On the Jury of Award.** To insure a wise and just award and to protect the interests of both the owner and the competitors, the competitive drawings should be submitted to a JURY so chosen as to secure expert knowledge and freedom from personal bias. Such a jury thoroughly understands and can explain the intent of the drawings. It discovers from them their authors' skill in design, arrangement and construction. Because of its trained judgment, its advice as to the merits of the designs submitted is of the highest value to the owner. The jury must consist of at least three members, one of whom must, and a majority of whom should, be PRACTICING ARCHITECTS. One or more members of the jury may be chosen by the competitors. It is the DUTY OF THE JURY to study carefully the programme and all conditions relating to the problem of the competition before examining the designs submitted; to refuse to make or recommend an award in favor of the author of any design that does not fulfil the conditions distinctly stated as mandatory in the programme; to give ample time to the careful study of the designs; and to render a decision only after mature consideration. The jury should see to it that a copy of its report reaches every competitor. The professional adviser should not be a member of the jury, as his judgment is apt to be influenced by his previous study of the problem.

**4) On the Competitive Drawings.** The purpose of an architectural competition is not to secure fully developed plans, but such evidence of skill in treating the essential elements of the problem as will assist in the SELECTION OF AN ARCHITECT. The drawings should, therefore, be as few in number and as simple in character as will express the general design of the building. A jury of experts does not need elaborate drawings.

**5) On the Programme.** The programme should contain rules for the conduct of the competition, instructions for competitors and the jury, and the agreement between the owner and the competitors. Uniform conditions for all competitors are fundamental to the proper conduct of competitions. Lengthy programmes and detailed instructions as to the desired accommodations should be avoided as they confuse the problem and hamper the competitors. The problem should be stated broadly. Its solutions should be left to the competitors. A distinction should be clearly drawn between the MANDATORY and the NON-MANDATORY provisions of the programme, that is, between those which, if not met, preclude an award in favor of the author of a design so failing, and those which are merely optional or of a suggestive character. The mandatory requirements should be set forth in such a way that they cannot fail to be recognized as such. They should be as few as possible, and should relate only to matters which cannot be left to the discretion of the competitors. It is difficult to summarize fully the programme, but it should at least:

a) Name the owner of the structure forming the subject of the competition, and state whether the owner institutes the competition personally or through representatives; if the latter, name the representatives, state how their authority is derived, and define its scope.

b) State the kind of competition to be instituted, and in limited competitions name the competitors; or in open competitions, if the competition is limited graphically or otherwise, state the limits.

c) Fix a time and place for the receipt of the designs. The time should not be altered except with the unanimous consent of the competitors.

d) Furnish exact information as to the site.

- (e) State the desired accommodation, avoiding detail.
- (f) State the cost if it be fixed or, better, limit the cubic contents.
- (g) Fix uniform requirements for the drawings, giving the number, the size or scales, and the method of rendering.
- (h) Forbid the submission of more than one design by any one competitor.
- (i) Provide a method for insuring anonymity of submission.
- (j) Name the members of the jury or provide for their selection. Define their powers and duties. If for legal reasons the jury may not make the award, state such reasons and in whom such power is vested.
- (k) Provide that no award shall be made in favor of any design until the jury shall have certified that it does not violate any mandatory requirement of the programme.
- (l) Provide that during the competition there shall be no communication relative to it between any competitor and the owner, his representatives, or a member of the jury, and that any communication with the professional adviser shall be in writing. Provide also that any information, whether in answer to such communications or not, shall be given in writing simultaneously to all competitors. Set a date after which no questions will be answered.
- (m) State the number and amount of payments to competitors.
- (n) Provide that the professional adviser shall send a report of the competition to each competitor, including therein the report of the jury.
- (o) Provide that no drawing shall be exhibited or made public until after the award of the jury.
- (p) Provide for the return of unsuccessful drawings to their respective authors within a reasonable time.
- (q) Provide that nothing original in any of the unsuccessful designs shall be used without consent of, and compensation to, the author of the design in which it appears.
- (r) Include the contract between the owner and the competitors.
- (s) Include the contract between the owner and the architect receiving the award.

(11) **On the Agreement.** An owner who institutes a competition assumes a moral obligation to retain one of the competitors as his architect. In order that architects invited to compete may determine whether they will take part it is essential that they should know the terms upon which the winner will be employed; and it is of the utmost importance to the owner that those terms should be so clearly defined that no disagreement as to their meaning can arise after the award is made. Unless they be so defined, delay is likely to occur and disagreements to arise at a time when a complete understanding between owner and architect is most important for the welfare of the work. Therefore, there must be included in the programme a form which guarantees the appointment of one of the competitors as architect and provides an agreement appended upon that appointment, defining his employment in terms consonant with the best practice. This must conform in all fundamental respects to the typical form of agreement appended to this circular.

(12) **On Payments to Unsuccessful Competitors.** In a limited competition and in the second stage of an open competition each competitor except the winner, should be paid for his services.

(13) **On Legality of Procedure.** It is highly important that each act taken in connection with a competition and every provision of the programme should be in consonance with law. Those charged with holding the competition should know and state their authority. If they are not empowered to bind the principal by contracts with the competitors, they should seek and receive

authority before issuing an invitation. If authority cannot legally be granted to the jury to make the award, that fact should be stated, and the body named in which such authority is vested.

(14) **On the Conduct of the Owner.** In order to maintain absolute impartiality toward all competitors, the owner, his representatives and all connected with the enterprise should, as soon as a professional adviser has been appointed, refrain from holding any communication in regard to the matter with any architect except the adviser or the jurors. The meeting with competitors described in Article (3) is of course an exception.

(15) **On the Conduct of Architects.** An architect should not attempt in any way, except as a duly authorized competitor, to secure work for which a competition is in progress, nor should he attempt to influence, either directly or indirectly, the award in a competition in which he is a competitor. An architect should not accept the commission to do the work for which a competition has been instituted if he has acted in an advisory capacity, either in drawing the programme or making the award. An architect should not submit in competition a design which has not been produced in his own office or under his own direction. No competitor should enter into association with another architect, except with the consent of the owner. If such associates should win the competition, their association should continue until the completion of the work thus won. During the competition, no competitor should hold any communication relative to it with the owner, his representatives or any member of the jury, nor should he hold any communication with the professional adviser, except it be in writing. When an architect has been authorized to submit sketches for a given project, no other architect should submit sketches for it until the owner has taken definite action on the first sketches, since, as far as the second architect is concerned, a competition is thus established.

(16) **On the Participation of Members of the Institute.** Members of the American Institute of Architects do not take part as competitors or jurors in any competition the programme of which has not received the formal approval of the Institute, nor does a member continue to act as professional adviser after it has been determined that the programme cannot be so drawn as to receive such approval.

(17) **Committees.** In order that the advice of the Institute may be given to those who seek it and that its approval may be given to programmes in conformance with its principles, the Institute maintains the following committees:

(a) The **STANDING COMMITTEE ON COMPETITIONS**, representing the Institute in its relation to competitions generally. This committee advises the subcommittees and directs their work and they report to it.

(b) A **SUBCOMMITTEE** for the territory of each chapter, representing the Institute in its relation to competitions for work to be erected within such territory.

The president of the chapter is **EX-OFFICIO** chairman of the subcommittee, and the other members of which he appoints. The subcommittees derive their authority from the Institute and not from the chapters. An appeal from the decision of a subcommittee may be made to the standing committee. The standing committee may approve, modify or annul the decision of a subcommittee.

(18) **The Institute's Approval of the Programme.** The approval of the Institute is not given to a programme unless it meets the following essential conditions:

(a) That there be a professional adviser.

(b) That the competition be of one of the forms described in Article (3).

(c) That the programme contain an AGREEMENT and CONDITIONS OF CONTRACT between architect and owner in conformity with those printed in the Appendix of this circular, that it include no provision at variance therewith that it contain terms of payments in accord with good practice, and that it specifically set forth the nature of expert engineering services for which the architect will be reimbursed.

(d) That the programme make provision for a jury of at least three persons

(e) That the programme conform in all particulars to the spirit of this circular.

When the programme meets the above essential conditions, the approval of the Institute may be given to it by the subcommittee for the territory in which the work is to be erected, or if there be no subcommittee for that territory, then by the standing committee on competitions. If, for legal or other reasons, the standing committee deem that deviations from the essential conditions are justified, it may give the approval of the Institute to a programme containing such deviations. Power to give approval in such cases is, however, vested only in the standing committee. The professional adviser, when duly authorized in writing by the proper committee, may print the Institute's approval as a part of the programme or otherwise communicate it to those invited to compete.

### Typical Form of Agreement between Owner and Competitors

In consideration of the submission of drawings in this competition (here insert the name of the owner or of the body duly authorized to enter into contract on behalf of the owner), hereinafter called the OWNER, agrees with the competitors jointly and severally that the owner will, within . . . . . days of the date set for the submission of drawings, make an award of the commission to design and supervise the work forming the subject of this competition to one of the competitors who submit drawings in consonance with the mandatory requirements of this programme, and will thereupon pay him, on account of his services as architect, one-tenth of his total estimated fee as stated below. And further in consideration of the submission of drawings as aforesaid and the mutual promises enumerated in the subjoined CONDITIONS OF CONTRACT BETWEEN ARCHITECT AND OWNER, the owner agrees and each competitor agrees, if an award be made in his favor, immediately to enter into a contract containing the CONDITIONS here following, and until such contract is executed to be bound by the said CONDITIONS.

### Conditions of Contract between Architect and Owner

#### ARTICLE I. DUTIES OF THE ARCHITECT

(1) **Design.** The architect is to design the entire building and its immediate surroundings and is to design or direct the design of its constructive, engineering and decorative work and its fixed equipment and, if further retained, its movable furniture and the treatment of the remainder of its grounds.

(2) **Drawings and Specifications.** The architect is to make such revision of his competitive scheme as may be necessary to complete the preliminary studies; and he is to provide drawings and specifications necessary for the conduct of the work. All such instruments of service are and remain the property of the architect.

(3) **Administration.** The architect is to prepare or advise as to all matters connected with the making of proposals and contracts, to issue all certificates

payment, to keep proper accounts and generally to discharge the necessary administrative duties connected with the work.

(4) **Supervision.** The architect is to supervise the execution of all the work committed to his control.

## ARTICLE II. DUTIES OF THE OWNER

(1) **Payments.** The owner is to pay the architect for his services a sum equal to ..... per cent \* upon the cost of the work. (The times and amounts payments should be here stated.) †

(2) **Reimbursements.** The owner is to reimburse the architect, from time to time, the amount of expenses necessarily incurred by him or his deputies while traveling in the discharge of duties connected with the work.

(3) **Service of Engineers.** The owner is to reimburse the architect the cost of the services of such engineers for heating, mechanical and electrical work as specifically provided for in each programme. The selection of such engineers and their compensation shall be subject to the approval of the owner.

(4) **Information, Clerk of the Works, etc.** The owner is to give all information as to his requirements; to pay for all necessary surveys, borings and tests, and for the continuous services of a clerk of the works, whose competence approved by the architect.

## Standard Form of Competition-Programme‡

The following standard form of COMPETITION-PROGRAMME, prepared by The American Institute of Architects, contains those provisions which the Institute considers essential to the fair and equitable conduct of a competition. The Institute in no way assumes or attempts to dictate an OWNER's course in conducting a competition; it claims only the right to control its own members, and having found by experience the danger to the interests of both OWNER and COMPETITOR from a competition in which such provisions are lacking, it permits no member to take part in any competition which does not meet those essential conditions, and the programme of which has not been specifically approved. A competition should be of such form as to establish equitable relations between the OWNER and the COMPETITOR. To insure this, the requirements should be clear and definite; the competency of the COMPETITORS should be assured; the agreement between the OWNER and COMPETITORS should be definite, as becomes a plain statement of business relations; and the judgment should be based on expert knowledge. The following programme will, if adhered to, be duly approved by the Institute SUBCOMMITTEES ON COMPETITIONS for the various chapters of the Institute, and by the STANDING COMMITTEE ON COMPETITIONS of the Institute.

\* The percentage inserted should be in accord with good practice.

† Good practice has established the payments on account as follows: Upon completion of the preliminary studies one-fifth of the total estimated fee less the previous payment; upon completion of contract-drawings and specifications two-fifths additional of such fee; for other drawings, for supervision and for administration, the remainder of the fee, from time to time, in proportion to the progress of the work.

‡ As authorized by the 48th annual convention, 1914. The American Institute of Architects, Document, Series A, No. 115, Washington, D. C., January, 1918. Reprinted by permission.

## Programme of Competition for

.....  
(Insert name of proposed building)

NOTE. Throughout this programme the word OWNER is used to indicate either owner in person, or those to whom he has delegated his powers.

### PART I

(1) Proposed Building. The.....

(Insert name of owner)

proposes to erect a new.....

(Insert name of building)

on the site at.....

(Insert location)

(2) Authority. The.....

(Insert name of owner)

has (delegated to.....

(Insert name or names of individuals)

authority to select an ARCHITECT to prepare the plans for, and supervise the erection of the building.

NOTE. If authority for the erection of the proposed building is granted by act of legislature, ordinance, etc., it is desirable to make clear the source of such authority.

(3) Architectural Adviser. The OWNER has appointed as his expert PROFESSIONAL ADVISER.....

(Insert name and address of adviser)

to prepare this programme and to act as his ADVISER in the conduct of the competition.

NOTE. No competition shall be instituted without the aid of a competent adviser. He should be an architect of the highest standing and his selection should be the Owner's first step. He should be chosen with the greatest care, as the success of the competition will depend largely upon his experience and ability. The duties of the expert are to advise those who hold the competition in regard to its form and terms, to draw up the programme, to advise in choosing the COMPETITORS, to answer inquiries from COMPETITORS and in general to direct the competition.

(4) Competitors. Participation in this competition is limited (A), to the following ARCHITECTS:.....

(Insert names of invited competitors)

or and (B) To such ARCHITECTS as shall have made application on or before.....

(Insert date)

accompanied by evidence of their education and experience, satisfactory to the OWNER and the PROFESSIONAL ADVISER. It is agreed that the names of all those admitted to the competition shall be made public on or before.....

(Insert date)

The OWNER agrees that he will admit no one as a COMPETITOR to whom he is not willing to award the commission to erect the building, in case of his success in the competition.



(5) **Jury of Award.** The OWNER agrees that there will be a JURY OF AWARD which will consist of the following members:.....

(Insert names of jury)

(B) which will consist of.....members. Of these, the OWNER (Insert number)

is appointed the following:.....and

(Insert names of those so selected)

The COMPETITORS will select the remaining members of the JURY.

**NOTE.** To insure a just and wise award and to protect the interests of both the OWNER and the COMPETITORS, the drawings should be submitted to a JURY chosen to secure expert knowledge and freedom from personal bias. The JURY shall consist of at least three members, one of whom must, and the majority of whom should, be practicing architects, for example, a layman and an architect selected by the OWNER or the BUILDING COMMITTEE, and an architect selected by the COMPETITORS. For work of great importance it is desirable to increase the size of the JURY, adding to it architects and specially qualified laymen. Some of the advantages of a JURY so constituted are that it thoroughly understands and can explain the intent of the drawings, and discovers from them their author's skill in design, arrangement and construction. Because of its expert knowledge, its judgment on the merits of the designs submitted is of the highest value to the OWNER. The adoption of the recommendation that the architectural members of the JURY be in a majority, is not necessarily a cause of expense, for the reason that in order to insure proper conduct of competitions, many architects of standing are willing, if the occasion warrants, to serve as JURORS without payment, other than actual expenses. It is customary and desirable that the COMPETITORS should elect one or more of the architectural members of the JURY. It is not advisable that the PROFESSIONAL ADVISER, who has drawn up the programme, be permitted to vote as a member of the JURY, although he may with advantage take part in the deliberations of the JURY.

(6) **Authority of Jury.** The OWNER agrees that the JURY above named, or selected as above provided, will have authority to make the award and that its decision in the matter shall be final. Moreover, this JURY will make an award to one of those taking part in this competition, unless no design is submitted which fulfils the mandatory requirements of this programme. The OWNER further agrees to employ as architect for the work as more fully set forth hereinafter, the author of the design selected by the JURY as its first choice.

**NOTE.** If, under the law, authority to make the award cannot be delegated to the JURY, the following form should be substituted for Section (6):

The OWNER agrees that the JURY above named or selected as above provided, will select the design which appears to it to be the most meritorious and make a written report to the OWNER, designating it by number. The OWNER will then consider this design and the report of the JURY and will thereupon, without learning the identity of the COMPETITORS, select as the winner of the competition the author of the design selected by the JURY, unless in his judgment there be cause to depart from such selection, in which case he will, still without learning the identity of the COMPETITORS, select one of the other designs submitted in competition. The OWNER further agrees that he will pay to the author of the design designated as most meritorious by the JURY, in case he should not be appointed ARCHITECT of the building, a prize of \$.....

(State amount of prize)

The opening of the envelope containing the name of the author of the design selected by the OWNER will automatically close the contract between him and the OWNER, printed Part III hereof.

(7) **Examination of Designs and Award.** The PROFESSIONAL ADVISER will examine the designs to ascertain whether they comply with the mandatory re-

quirements of the programme, and will report to the JURY any instance of failure to comply with these mandatory requirements. The OWNER further agrees that the JURY will satisfy itself of the accuracy of the report of the PROFESSIONAL ADVISER, and will place out of competition and make no award to any design which does not comply with these mandatory requirements. The JURY will carefully study the programme and any modifications thereof, which may have been made through communications (see Section (12)), and will then consider the remaining designs, holding at least two sessions on separate days, and considering at each session all the drawings in competition, and will make the award, and the classification of prize-winners, if prizes are given, by secret ballot, and by majority vote, before opening the envelopes which contain the names of the COMPETITORS. In making the award the JURY will thereby affirm that it has made no effort to learn the identity of the various COMPETITORS, and that it has remained in ignorance of such identity until after the award was made. The opening of the envelope containing the name of the author of the selected design will automatically close the contract between him and the OWNER, printed at Part III hereof.

(8) **Report of the Jury.** The JURY will make a full report which will state its reasons for the selection of the winning design and its reason for the classification of the designs placed next in order of merit, and a copy of this report, accompanied by the names of prize-winners, if prizes are given, will be sent by the PROFESSIONAL ADVISER to each COMPETITOR. Immediately upon the opening of the envelopes, the PROFESSIONAL ADVISER will notify all COMPETITORS, by wire, of the result of the competition.

(9) **Compensation to Competitors.** The OWNER agrees to pay to the successful COMPETITOR within ten days of the judgment, on account of his fee for services as ARCHITECT, one-tenth of his total estimated fee.

In full discharge of his obligation to them (in case prizes or fees are offered) the OWNER agrees:

(A) To pay the following prizes to those ranked by the JURY next to the successful design: To the design placed second \$....., to the design placed third \$....., to the design placed fourth \$....., to the design placed fifth \$....., etc., within ten days of the judgment, or

(B) To pay to each of the COMPETITORS invited to take part in this competition, other than the successful COMPETITOR, a fee of \$..... within ten days of the judgment.

(10) **Exhibition of Drawings.** It is agreed that no drawings shall be exhibited or made public until after the award of the JURY. There will be a public exhibition of all drawings after the judgment, and all drawings, except that of the successful COMPETITOR, will be returned to their authors at the close thereof.

(11) **Use of Features of Unsuccessful Designs.** Nothing original in the unsuccessful designs shall be used without consent of, or compensation to, the author of the design in which it appears. In case the OWNER desires to make use of any individual feature of an unsuccessful design, the same may be obtained by adequate compensation to the designer, the amount of such compensation to be determined in consultation with the author and the PROFESSIONAL ADVISER.

(12) **Communications. (Mandatory.)** If any COMPETITOR desires information of any kind whatever in regard to the competition, or the programme, he shall ask for this information by anonymous letter addressed to the PROFESSIONAL ADVISER, and in no other way, and a copy of this letter and the

answer thereto will be sent simultaneously to each COMPETITOR, but no request received after.....

(Insert date)

will be answered.

(13) **Anonymity of Drawings. (Mandatory.)** The drawings to be submitted shall bear no name or mark which could serve as a means of identification, nor shall any such name or mark appear upon the wrapper of the drawings, nor shall any COMPETITOR directly or indirectly reveal the identity of his designs, or hold communication regarding the competition with the OWNER or with any member of the BUILDING COMMITTEE or of the JURY, or with the PROFESSIONAL ADVISER, except as provided for under COMMUNICATIONS. It is understood that in submitting a design, each COMPETITOR thereby affirms that he has complied with the foregoing provisions in regard to anonymity and agrees that any violation of them renders null and void this agreement and any agreement arising from it. With each set of drawings must be enclosed a plain, opaque, sealed envelope without any superscription or mark of any kind, same containing the name and address of the COMPETITOR. These envelopes shall be opened by the PROFESSIONAL ADVISER after the final selection has been made, and preferably in the presence of the JURY.

(14) **Delivery of Drawings. (Mandatory.)** The drawings submitted in this competition shall be securely wrapped, addressed to the PROFESSIONAL ADVISER at ..... in plain lettering and

(Insert address for delivery of drawings)

with no other lettering thereon, and delivered at this address not later than .....

(Insert date and hour)

In case drawings are sent by express, they may be delivered to an express company at the above date and hour, in which case the express company's receipt, bearing date and hour, shall be mailed immediately to the PROFESSIONAL ADVISER as evidence of delivery.

## PART II

(15) **Site.** The site of the building is as follows.....  
(Insert description of site, and provide topographical map giving dimensions, grades, etc.)

NOTE. The site should be carefully described and a survey of the property should be attached and included as part of the programme. Conditions pertaining to the site and to neighboring buildings frequently become determining factors in a design. Photographs showing surrounding buildings and landscape-conditions may with advantage be included.

(16) **Cost. (Mandatory.)** For the purpose of this competition the cost of the building shall be figured at.....cts per cu ft, and the total thereof  
(Insert number)

figured on this basis shall not exceed.....  
(Insert limit of cost)

(17) **Cubage. (Mandatory.)** Cubage shall be so computed as to show as exactly as possible the actual volume of the building, calculated from the finished level or levels of the lowest floor to the highest points of the roofs, and contained within the outside surfaces of the walls. Pilasters, cornices, balconies and other similar projections shall not be included. Porticos with engaged columns and similar projections shall be taken as solids and figured to the outer face of the columns. When columns are free-standing, one-half of the volume of the porti-

cos shall be taken. There shall also be included in the cubage the actual volume of all parapets, towers, lanterns, dormers, vaults, and other features adding to the bulk of the building, also the actual volume of exterior steps above grade. Light-wells of an area of less than 400 sq ft shall not be deducted. In calculating cubage, account shall be taken of variations in the exterior wall-surface, as for example, the projection of a basement-story beyond the general line of the building. A figured diagram showing method adopted in cubing shall accompany each set of drawings.

(18) Drawings. (Mandatory.) The drawings submitted shall be made according to the following list, at the scale given, and rendered as noted; and no other drawings than these shall be submitted:

.....  
(Insert list, scale and method of rendering)

NOTE. The drawings submitted should be the least number necessary to set forth clearly the solution of the problem, and the scale of these drawings the smallest compatible with the requirement that the intention of each COMPETITOR be made clear to an expert JURY. Where the number and scale of drawings is reduced to the minimum, and simple methods of rendering imposed, the COMPETITORS are enabled to devote their time and energy to the study of the problem, which is the serious business of a competition, instead of upon draughtsmanship and rendering, which when carried beyond a certain point, are of no value whatever in determining the fitness of the COMPETITORS to handle the work of erecting the building, for which the competition is being held.

PART III

Agreement between Owner and Competitors

In consideration of the submission of drawings in this competition, and the mutual promises enumerated in the subjoined CONDITIONS OF CONTRACT BETWEEN ARCHITECT AND OWNER the OWNER agrees, and each COMPETITOR agrees if the award be made in his favor, immediately to enter into a contract containing all the CONDITIONS here following, and until such contract is executed, to be bound by the said CONDITIONS.

Conditions of Contract between Architect and Owner

Duties of the Architect

(1) Design. The ARCHITECT is to design the entire building and its immediate surroundings and is to design or direct the design of its constructive, engineering and decorative work and its fixed equipment and, if further retained, its movable furniture and the treatment of the remainder of its grounds.

(2) Drawings and Specifications. The ARCHITECT is to make such revision of his competitive scheme as may be necessary to complete the preliminary studies; and he is to provide drawings and specifications necessary for the conduct of the work. All such instruments of service are and remain the property of the ARCHITECT.

(3) Administration. The ARCHITECT is to prepare or advise as to all forms connected with the making of proposals and contracts, to issue all certificates of payment, to keep proper accounts and generally to discharge the necessary administrative duties connected with the work.

(4) Supervision. The ARCHITECT is to supervise the execution of all the work committed to his control.

(5) **Payments.** The Owner is to pay the Architect for his services a sum equal to . . . . . per cent upon the cost of the work.

**(6) Reimbursements.** The OWNER is to reimburse the architect from time to time, the amount of expenses necessarily incurred by him or his deputies while traveling in the discharge of duties connected with the work.

The selection of such ENGINEERS and their compensation shall be subject to the approval of the OWNER.

## PART IV

**NOTE.** For the same reason that elaborate drawings are undesirable, it is advisable to avoid lengthy and detailed instructions as to the desired accommodations, as they confuse the problem and hamper the COMPETITORS; and the OWNER loses thereby the benefit he might gain in allowing the COMPETITORS freedom to develop solutions which they would not otherwise be at liberty to suggest. It should be borne in mind that either the cost of the building, as determined by its cubical contents, should be fixed, or the requirements of the OWNER in regard to the design, materials of construction, dimensions of rooms, etc., should be fixed, but not both. If, on the one hand, the cubical contents and cost is fixed, it should be stated that the requirements of the OWNER must be adhered to as closely as possible by COMPETITORS; if, on the other hand, the requirements of the OWNER are definitely fixed, it may be stated that the cubical contents of each design, while not limited, will be taken into consideration in making the award. In case the cost of certain rooms, etc., are definitely fixed, the word MANDATORY should be placed at the head of the paragraph referring to these rooms.

Here should follow a list of rooms required, together with sizes and other data which apply to the building under consideration.

[illegible]

## THE STANDARD DOCUMENTS OF THE AMERICAN INSTITUTE OF ARCHITECTS\*

**Introductory Notes.** This introductory paragraph is from an article† by Clipston Sturgis, President of The American Institute of Architects. "For many years builders and owners have commonly used an agreement recognized as adequate and imperfect, and one apt to lead to serious misunderstandings, if not to legal difficulties. Architects entrusted with important work and its accompanying responsibilities have endeavored to have agreements drawn which would adequately safeguard the interests involved. When, some nine years ago (1906), the Institute attempted to prepare a new standard agreement, it found already in use a considerable number of forms prepared by architects, differing in detail but agreeing in one main point. This one point was that the contract and the conditions of the contract should be treated as two branches of the same agreement, not as one document, nor yet as two. The contract was to be as brief as possible, stating simply what the obligation was. The conditions of the contract, complicated and involved, yet essential to the contract, were of necessity comparatively lengthy. The most difficult part of the work, surveying the field and breaking out the way, was done by the Committees on Contracts and Specifications during the years 1906 to 1911, and resulted in the first edition of the STANDARD DOCUMENTS, published in 1911. At that time some thought the problem solved; others thought it but an important step forward; which latter proved to be the fact. These first documents, excellent as they were as text-books, were not suitable for everyday use. The Institute again took up the problem at that time with the definite aim to produce a document which should entirely replace the uniform agreement when the contract for its publication expired in May 1915. This has been done and the carefully studied AGREEMENT and CONDITIONS OF THE CONTRACT presented to the convention in December, 1914, have been further studied and improved and are now (1915) on the market for general use. In the final study between January and May, 1915, the Institute had the advantages of coöperation with representatives of many of the building trades and the advice of counsel representing the Institute and counsel representing the building trades. The document, like its predecessor, will now come to the test of actual use. It will prove to be imperfect and revised sections will be necessary, but it is believed to be in the main a fair and comprehensive agreement and one that is practical and fit for general use. Architects everywhere are urged to use and test this form, and criticism from owners and builders will be gladly received and considered. In addition to this most important document the committee has prepared and the Institute has published a form of BOND, a LETTER OF ACCEPTANCE by a contractor of a sub-contractor's bid, and an AGREEMENT between a contractor and sub-contractor. Many architects who have done work on which a bond has been required have been surprised at the ease with which the obligations of the bond could be evaded. In most cases, because someone, architect, contractor, or owner, had invalidated the bond. The new form of bond is prepared for insuring, as far as possible, that the bonding company shall discharge its obligations and protect the owner who pays for the protection. The LETTER FROM CONTRACTOR TO SUB-CONTRACTOR is intended to provide a simple form whereby the mutual obligations of the two shall be clearly defined. The AGREEMENT BETWEEN CONTRACTOR AND SUB-CONTRACTOR accomplishes the same purpose in a somewhat more formal way."

\* Third Edition, copyrighted by The American Institute of Architects, 1915-1918, inserted here by permission.

† Published in the Journal of The American Institute of Architects, June, 1915.

**The Development of the Standard Documents.** In the year 1887 The American Institute of Architects, the Western Association of Architects and the National Association of Builders, thinking it desirable to establish better practice in the matter of building contracts, undertook the preparation of a form of contract satisfactory to all. Under the name of THE UNIFORM CONTRACT this form obtained wide acceptance and has been long in use. About the year 1907, feeling that practice had advanced to a point no longer fully reflected by the UNIFORM CONTRACT, the Institute undertook a general study of the subject with a view to developing a form of contract clear in thought, equitable, applicable to work in almost all classes, binding in law and a standard of good practice. The work was entrusted to the Standing Committee on Contracts and Specifications, who spent four years on it, studying the UNIFORM CONTRACT and forms in use by some thirty well-known architects, and submitted various drafts for criticism to the chapters of the Institute and to engineers, contractors and architects throughout the country. The documents were prepared under the advice of Francis Fisher Kane, counsel for the Institute, and Ernest Eidlitz, and with the able and careful criticism of Professor Samuel Williston of the Harvard Law School, and with the assistance of James W. Pryor, in their editing. The Institute gave its approval to the work in 1911. The Standing Committee on Contracts and Specifications, during the preparation of the first edition of the STANDARD FORMS, consisted of Rosvenor Atterbury, Chairman; Allen B. Pond, Secretary; Frank Miles Day, William A. Boring, Frank C. Baldwin, Frank W. Ferguson, Alfred Stone and J. L. Heins. Criticisms of the first edition of the DOCUMENTS were invited by the Institute and during the year 1913 a group of architects and builders in Boston, known as the Joint Committee of the Boston Society of Architects, and of the Master Builders' Association, gave much sincere study to the subject. At the same time the National Association of Builders' Exchange offered a detailed criticism of the documents.

In 1914 the Institute instructed its Standing Committee on Contracts and Specifications to undertake a general revision with a view to making the CONDITIONS simpler in wording and more equitable. The committee was empowered to hold conferences with organizations so desiring. Subcommittees for the territory of the several chapters of the Institute were appointed and collaborated with the standing committee. The Boston group presented its ideas in the form of an entirely new draft which proved of high value and its Chairman, W. Stanley Parker, was present with the Standing Committee at nearly all its meetings. The Committee had a joint meeting with representatives of the National Association of Builders' Exchanges and thereafter the counsel of the Association, W. B. King, and the counsel of the Institute, Louis Barcroft Runk, collaborated most effectively with the committee. The GENERAL CONDITIONS were entirely rewritten and in response to the strong desire of contractors and subcontractors, the principle of GENERAL ARBITRATION, subject to limitations in the documents, was adopted, and provisions relative to the RELATIONS OF THE CONTRACTOR AND HIS SUBCONTRACTORS were included in the documents. After much study, conference and criticism, a draft of the second edition was issued by authority of the Institute, April 1, 1915. During the revision of the documents, the Standing Committee on Contracts and Specifications consisted of Frank Miles Day, Chairman; Allen B. Pond, Sullivan W. Jones, Clarence A. Martin, Norman M. Isham, Octavius Morgan, Thomas Nolan, A. O. Elzner, M. B. Medary, Jr., Jos. Evans Sperry, Frank W. Ferguson and Samuel Stone.

**The Construction of the Standard Documents.** An AGREEMENT, and DRAWINGS and SPECIFICATIONS are the necessary parts of a building contract. Many conditions of a general character may be placed at will in the AGREEMENT

or in the SPECIFICATIONS. It is, however, wise to assemble them in a single document and, since they have as much bearing on the DRAWINGS as on the SPECIFICATIONS, and even more on the business relations of the contracting parties, they are properly called the GENERAL CONDITIONS OF THE CONTRACT. As the AGREEMENT, GENERAL CONDITIONS, DRAWINGS and SPECIFICATIONS are the constituent elements of the CONTRACT and are acknowledged as such in the AGREEMENT, they are correctly termed the CONTRACT DOCUMENTS. Statements made in any one of them are just as binding as if made in the AGREEMENT. The Institute's forms, although intended for use in actual practice, should also be regarded as a code of reference representing the judgment of the Institute as to what constitutes good practice and as such they may be drawn upon by architects in improving their own forms. Although the forms are suited for use in connection with a single or general contract, they are equally applicable to an operation conducted under separate contracts.

**Titles of the Standard Contract Documents.\*** The new STANDARD CONTRACT DOCUMENTS of The American Institute of Architects are now on sale† by dealers in office and drafting-supplies in all the large cities of the country, and replace the old UNIFORM CONTRACT. The following are the titles of the STANDARD DOCUMENTS: A. 1. FORM OF AGREEMENT AND A. 2. GENERAL CONDITIONS OF THE CONTRACT. B. BOND OF SURETYSHIP. C. FORM OF SUBCONTRACT. D. LETTER OF ACCEPTANCE OF SUBCONTRACTOR'S PROPOSAL. A cover in heavy paper with valuable EXPLANATORY NOTES is sent without charge with each complete set of the documents. These documents have received the full approval of the Institute, through its conventions, board of directors and officers. They are the outcome of nine years of continuous work, by a Standing Committee on Contracts and Specifications. This committee, comprising some of the ablest American architects, was assisted by the Institute's thirty-nine chapters; advised by eminent legal specialists in contract law and aided by representatives of the Building and Trade Associations of the United States. The Standard Documents have received the formal approval of the

\* Third Edition, copyrighted by the American Institute of Architects.

† Notice to Architects, Builders and Contractors. The CONTRACT FORMS may be obtained singly or in lots from the local dealers. If your dealer cannot supply you send your order and his name to The Executive Secretary, A. I. A., The Octagon, Washington, D. C. All orders must include the necessary remittance irrespective of A. I. A. membership and irrespective of commercial standing of purchaser. The Institute has adopted these CASH TERMS, from which no exception will be made to anybody, in order to reduce cost of accountancy and thereby reduce expense to the user. Remittances may be by check, money-order, cash, or stamps.

**Prices for Single Copies:** Agreement and General Conditions in cover, \$0.14; General Conditions without Agreement, \$0.10; Agreement without General Conditions, \$0.05; Bond of Suretyship, \$0.02; Form of Subcontract, \$0.03; Letter of Acceptance of Subcontractor's Proposal, \$0.02; Cover (heavy paper, with valuable notes), \$0.01; Complete set in cover, \$0.20. A Trial set will be delivered upon receipt of ten 2-cent stamps.

**Prices for Quantities and Discounts to Architects, Builders and Contractors.** Orders for quantities are subject to the following discounts (which are also given by all dealers):

Five per cent on lots of 100 (one kind or assorted); 10% on lots of 500 (one kind or assorted); 15% on lots of 1 000 (one kind or assorted). As these DOCUMENTS are printed on sheets, 8½ by 11 ins, and in large quantities, they cannot be supplied with any individual names or printing different from the standard forms. The Institute does not wish to encourage the use of the AGREEMENT with general conditions other than those endorsed by it, but on request will sell the AGREEMENTS separate from the STANDARD GENERAL CONDITIONS at 3 cts each.



ional Association of Builders' Exchanges, the National Association of Master  
 mbers, the National Association of Sheet Metal Contractors of the United  
 tes, the National Electrical Contractors' Association of the United States,  
 National Association of Marble Dealers, the Building Granite Quarries  
 ociation, the Building Trades Employers' Association of the City of New  
 k, and the Heating and Piping Contractors' National Association.

# **1. THE STANDARD FORM OF AGREEMENT BETWEEN CONTRACTOR AND OWNER\***

**ISSUED BY THE AMERICAN INSTITUTE OF ARCHITECTS †**

his form has been approved by the National Association of Builders' Exchanges, The  
 onal Association of Master Plumbers, the National Association of Sheet Metal  
 ractors of the United States, the National Electrical Contractors' Association of  
 United States, the National Association of Marble Dealers, the Building Granite  
 ries Association, the Building Trades Employers' Association of the City of New  
 t, and the Heating and Piping Contractors' National Association.

ED EDITION, COPYRIGHT 1915-1918, BY THE AMERICAN INSTITUTE OF ARCHI-  
 TECTS, THE OCTAGON, WASHINGTON, D. C. THIS FORM IS TO BE USED ONLY  
 WITH THE STANDARD GENERAL CONDITIONS OF THE CONTRACT

**S AGREEMENT**, made the.....  
 of.....in the year Nineteen Hundred and:.....  
 nd between.....(Two blank lines) † .....  
 inafter called the Contractor, and.....(Two blank lines).....  
 .....hereinafter called the Owner  
**ENNESSETH**, that the Contractor and the Owner for the considerations  
 inafter named agree as follows:

**Article 1.** The Contractor agrees to provide all the materials and to perform  
 he work shown on the Drawings and described in the Specifications entitled  
 ere insert the caption descriptive of the work as used in the Proposal, General Con-  
 as, Specifications, and upon the Drawings.)

.....(Five blank lines).....  
 ared by.....(Two blank lines).....  
 g as, and in these Contract Documents entitled the Architect, and to do  
 ything required by the General Conditions of the Contract, the Specifica-  
 and the Drawings.

**Article 2.** The Contractor agrees that the work under this Contract shall  
 bstantially completed.

(Here insert the date or dates of completion, and stipulations as to liquidated  
 damages if any.)  
 .....(Eight blank lines).....

**Article 3.** The Owner agrees to pay the Contractor in current funds for the  
 rformance of the Contract.

.....(\$.....) subject  
 ditions and deductions as provided in the General Conditions of the Con-

ublished by permission of The American Institute of Architects.  
 or use when a stipulated sum forms the basis of payment.  
 otted lines, as indicated, are in the standard documents and are omitted here to  
 space.

tract and to make payments on account thereof as provided therein, as follows: On or about the.....day of each month..... per cent of the value, proportionate to the amount of the Contract, of labor and materials incorporated in the work..... up to the first day of that month as estimated by the Architect, less the aggregate of previous payments. On substantial completion of the entire work, a sum sufficient to increase the total payment to.....per cent of the contract price, and.....days thereafter, provided the work be fully completed and the Contract fully performed, the balance due under the Contract.

.....(Five blank lines).....

**Article 4.** The Contractor and the Owner agree that the General Conditions of the Contract, the Specifications and the Drawings, together with this Agreement, form the Contract, and that they are as fully a part of the Contract as hereto attached or herein repeated; and that the following is an exact enumeration of the Specifications and Drawings:

.....(Thirty-five blank lines).....

The Contractor and the Owner for themselves, their successors, executors, administrators and assigns, hereby agree to the full performance of the covenants herein contained.

IN WITNESS WHEREOF they have executed this agreement, the day of ....., 19.. year first above written.

.....  
 .....  
 .....  
 .....  
 .....  
 .....  
 .....

# **A. 2. THE GENERAL CONDITIONS OF THE CONTRACT** **STANDARD FORM OF THE AMERICAN INSTITUTE OF ARCHITECTS**

This form has been approved by the National Association of Builders' Exchanges, the National Association of Master Plumbers, the National Association of Sheet Metal Contractors of the United States, the National Electrical Contractors' Association of the United States, the National Association of Marble Dealers, the Building Granite Quarries Association, the Building Trades Employers' Association of the City of New York and the Heating and Piping Contractors' National Association.

THIRD EDITION, COPYRIGHT 1915-1918, BY THE AMERICAN INSTITUTE OF ARCHITECTS, THE OCTAGON, WASHINGTON, D. C.

## **Index to the Articles of the General Conditions**

- |                              |                                        |
|------------------------------|----------------------------------------|
| 1. Definitions.              | 8. Samples.                            |
| 2. Documents.                | 9. The Architect's Status.             |
| 3. Details and Instructions. | 10. The Architect's Decisions.         |
| 4. Copies Furnished.         | 11. Foreman, Supervision.              |
| 5. Shop Drawings.            | 12. Materials, Appliances, Employment. |
| 6. Drawings on the Work.     | 13. Inspection of Work.                |
| 7. Ownership of Drawings.    | 14. Correction Before Final Payment.   |

\* Published by permission of The American Institute of Architects.

Deductions for Uncorrected Work.  
Correction After Final Payment.  
Protection of Work and Property.  
Emergencies.  
Contractor's Liability Insurance.  
Owner's Liability Insurance.  
Fire Insurance.  
Guaranty Bonds.  
Cash Allowances.  
Changes in the Work.  
Claims for Extras.  
Applications for Payments.  
Certificates and Payments.  
Payments Withheld.  
Liens.  
Permits and Regulations.  
Royalties and Patents.

32. Use of Premises.  
33. Cleaning Up.  
34. Cutting, Patching and Digging.  
35. Delays.  
36. Owner's Right to Do Work.  
37. Owner's Right to Terminate Contract.  
38. Contractor's Right to Stop Work or Terminate Contract.  
39. Damages.  
40. Mutual Responsibility of Contractors.  
41. Separate Contracts.  
42. Assignment.  
43. Subcontracts.  
44. Relations of Contractor and Subcontractor.  
45. Arbitration.

#### **Art. 1. Principles and Definitions.**

- a) The Contract Documents consist of the Agreement, the General Conditions of the Contract, the Drawings and Specifications, including all modifications thereof incorporated in the documents before their execution. These are the Contract Documents.
- b) The Owner, the Contractor and the Architect are those named as such in the Agreement. They are treated throughout the Contract Documents as if they were of the singular number and masculine gender.
- c) The term Subcontractor, as employed herein, includes only those having direct contract with the Contractor and it includes one who furnishes material or labor to a special design according to the plans or specifications of this work, but does not include one who merely furnishes material not so worked.
- d) Written notice shall be deemed to have been duly served if delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended, or if delivered at or mailed to the last business address known to him who gives the notice.
- e) The term "work" of the Contractor or Subcontractor includes labor or materials or both.
- f) All time-limits stated in the Contract Documents are of the essence of the contract.
- g) The law of the place of building shall govern the construction of this contract.

**Art. 2. Execution, Correlation and Intent of Documents.** The Contract Documents shall be signed in duplicate by the Owner and Contractor. In the event of failure to sign the General Conditions, Drawings or Specifications the Architect shall identify them. The Contract Documents are complementary, and what is called for by any one shall be as binding as if called for by all. The intention of the documents is to include all labor and materials reasonably necessary for the proper execution of the work. It is not intended, however, that materials or work not covered by or properly inferable from any drawing, branch, class or trade of the specifications shall be supplied unless distinctly so noted on the drawings. Materials or work described in words which so applied have a well-known technical or trade meaning shall be held to refer to such recognized standards.

**Art. 3. Detail Drawings and Instructions.** The Architect shall furnish, with reasonable promptness, additional instructions, by means of drawings or otherwise, necessary for the proper execution of the work. All such drawings

and instructions shall be consistent with the Contract Documents, true developments thereof, and reasonably inferable therefrom. The work shall be executed in conformity therewith and the Contractor shall do no work without proper drawings and instructions. In giving such additional instructions, the Architect shall have authority to make minor changes in the work, not involving extra costs, and not inconsistent with the purposes of the building. The Contractor and the Architect, if either so requests, shall jointly prepare a schedule, subject to change from time to time in accordance with the progress of the work, fixing the latest dates at which the various detail drawings will be required, and the Architect shall furnish them in accordance with that schedule. Under like conditions, a schedule shall be prepared, fixing dates for the submission of shop drawings, for the beginning of manufacture and installation of material and for the completion of the various parts of the work.

**Art. 4. Copies Furnished.** Unless otherwise provided in the Contract Documents the Architect will furnish to the Contractor, free of charge, a certain number of copies of drawings and specifications reasonably necessary for the execution of the work.

**Art. 5. Shop Drawings.** The Contractor shall submit, with such promptness as to cause no delay in his own work or in that of any other contractor, two copies of all shop or setting drawings and schedules required for the work of the various trades and the Architect shall pass upon them with reasonable promptness. The Contractor shall make any corrections required by the Architect, file with him two corrected copies and furnish such copies as may be needed. The Architect's approval of such drawings or schedules shall not relieve the Contractor from responsibility for deviations from drawings or specifications, unless he has in writing called the Architect's attention to such deviations at the time of submission, nor shall it relieve him from responsibility for errors of any sort in shop drawings or schedules.

**Art. 6. Drawings and Specifications on the Work.** The Contractor shall keep one copy of all drawings and specifications on the work, in good order and available to the Architect and to his representatives.

**Art. 7. Ownership of Drawings and Models.** All drawings, specifications and copies thereof furnished by the Architect are his property. They are not to be used on other work and, with the exception of the signed contract documents, are to be returned to him on request, at the completion of the work. All models are the property of the Owner.

**Art. 8. Samples.** The Contractor shall furnish for approval all samples directed. The work shall be in strict accordance with approved samples.

**Art. 9. The Architect's Status.** The Architect shall have general supervision and direction of the work. He is the agent of the Owner, only to the extent provided in the Contract Documents and when in special instances he is authorized by the Owner so to act, and in such instances he shall, upon request, show the Contractor written authority. He has authority to stop the work whenever such stoppage may be necessary to insure the proper execution of the Contract. As the Architect is, in the first instance, the interpreter of the Contract and the judge of its performance, he shall side neither with the Owner nor with the Contractor, but shall use his powers under the Contract to enforce its faithful performance by both. In case of the termination of the employment of the Architect, the Owner shall appoint a capable and reputable Architect whose status under the contract shall be that of the former Architect.

**Art. 10. The Architect's Decisions.** The Architect shall, within a reasonable time, make decisions on all claims of the Owner or Contractor and on

matters relating to the execution and progress of the work or the interpretation of the Contract Documents. The Architect's decisions, in matters relating to the aesthetic effect, shall be final, if within the terms of the Contract Documents. Except as above or as otherwise expressly provided in these General Conditions and the specifications, all the Architect's decisions are subject to arbitration.

**Art. 11. Foreman, Supervision.** The Contractor shall keep on the work a competent foreman and any necessary assistants, all satisfactory to the Architect. The foreman shall not be changed except with the consent of the Architect, unless the foreman proves to be unsatisfactory to the Contractor or ceases to be in his employ. The foreman shall represent the Contractor in his absence and all directions given to him shall be as binding as if given to the Contractor. Important directions shall be confirmed in writing to the Contractor. Other directions shall be so confirmed on written request in each case.

The Contractor shall give efficient supervision to the work, using his best skill and attention. He shall carefully study and compare all drawings, specifications and other instructions and shall at once report to the Architect any error, inconsistency, or omission which he may discover.

**Art. 12. Materials, Appliances, Employees.** Unless otherwise stipulated, the Contractor shall provide and pay for all materials, labor, water, tools, equipment, light and power necessary for the execution of the work. Unless otherwise specified, all materials shall be new and both workmanship and materials shall be of good quality. The Contractor shall, if required, furnish satisfactory evidence as to the kind and quality of materials. The Contractor shall not employ on the work any unfit person or any one not skilled in the work assigned to him.

**Art. 13. Inspection of Work.** The Owner, the Architect and their representatives shall at all times have access to the work wherever it is in preparation or progress and the Contractor shall provide proper facilities for such access and inspection. If the specifications, the Architect's instructions, laws, ordinances or any public authority require any work to be specially tested or proved, the Contractor shall give the Architect timely notice of its readiness for inspection, and if the inspection is by another authority than the Architect, a date fixed for such inspection. Inspections by the Architect shall be promptly made. If any such work should be covered up without approval or consent of the Architect, it must, if required by the Architect, be uncovered for examination at the Contractor's expense. Reexamination of questioned work may be ordered by the Architect. If such work be found in accordance with the contract, the Owner shall pay the cost of reexamination and replacement.

If such work be found not in accordance with the contract, through the fault of the Contractor, the Contractor shall pay such cost, unless he shall show that the defect in the work was caused by another contractor, and in that case the Owner shall pay such cost.

**Art. 14. Correction of Work Before Final Payment.** The Contractor shall promptly remove from the premises all materials condemned by the Architect as failing to conform to the Contract, whether incorporated in the work or not, and the Contractor shall promptly replace and re-execute his own work in accordance with the Contract and without expense to the Owner and shall bear the expense of making good all work of other contractors destroyed or damaged by such removal or replacement. If the Contractor does not remove such condemned work and materials within a reasonable time, fixed by written notice, the Owner may remove them and may store the material at the expense of the Contractor. If the Contractor does not pay the expense

of such removal within five days thereafter, the Owner may, upon written notice, sell such materials at auction or at private sale and account for the net proceeds thereof, after deducting all the cost and expense that should have been borne by the Contractor.

**Art. 15. Deductions for Uncorrected Work.** If the Architect or Owner deem it inexpedient to correct work injured or not done in accordance with the Contract, the difference in value together with a fair allowance for damage shall be deducted.

**Art. 16. Correction of Work After Final Payment.** Neither the final certificate nor payment nor any provision in the Contract Documents shall release the Contractor of responsibility for negligence or faulty materials or workmanship and he shall remedy any defects due thereto and pay for any damage to other work resulting therefrom, which shall appear within a period of two years from the time of installation. The Owner shall give notice of observed defects with reasonable promptness. All questions arising under this Article shall be decided under Articles 10 and 45.

**Art. 17. Protection of Work and Property.** The Contractor shall continuously maintain adequate protection of all his work from damage and shall protect the Owner's property from injury arising in connection with this Contract. He shall make good any such damage or injury, except such as may be directly due to errors in the Contract Documents. He shall adequately protect adjacent property as provided by law and the Contract Documents.

**Art. 18. Emergencies.** In an emergency affecting the safety of life or of a structure or of adjoining property, not considered by the Contractor as within the provisions of Article 17, then the Contractor, without special instruction or authorization from the Architect or Owner, is hereby permitted to act, at his discretion, to prevent such threatened loss or injury and he shall so act, without appeal, if so instructed or authorized. Any compensation claimed to be due him therefor shall be determined under Articles 10 and 45 regardless of any limitations in Article 25 and in the second paragraph of Article 24.

**Art. 19. Contractor's Liability Insurance.** The Contractor shall maintain such insurance as will protect him from claims under workmen's compensation acts and from any other claims for damages for personal injury, including death, which may arise from operations under this contract, whether such operations be by himself or by any subcontractor or anyone directly or indirectly employed by either of them. Certificates of such insurance shall be filed with the Owner, if he so require, and shall be subject to his approval for adequacy of protection.

**Art. 20. Owner's Liability Insurance.** The Owner shall maintain such insurance as will protect him from his contingent liability for damages for personal injury, including death, which may arise from operations under this Contract.

**Art. 21. Fire Insurance.** The Owner shall effect and maintain fire insurance upon the entire structure on which the work of this contract is to be performed and upon all materials, in or adjacent thereto and intended for use thereon to at least eighty per cent of the insurable value thereof. The loss, if any, is to be made adjustable with and payable to the Owner as Trustee for himself it may concern. All policies shall be open to inspection by the Contractor. If the Owner fails to show them on request or if he fails to effect or maintain insurance as above, the Contractor may insure his own interest and charge the cost thereof to the Owner. If the Contractor is damaged by failure of

mer to maintain such insurance, he may recover under Art. 39. If required writing by any party in interest, the Owner as Trustee shall, upon the occurrence of loss, give bond for the proper performance of his duties. He shall deposit any money received from insurance in an account separate from all his other funds and he shall distribute it in accordance with such agreement as the parties in interest may reach, or under an award of arbitrators appointed, one by the Owner, another by joint action of the other parties in interest, all other procedure being in accordance with Art. 45. If after loss no special agreement is made, replacement of injured work shall be ordered under Art. 24. The Trustee shall have power to adjust and settle any loss with the insurers unless one of the contractors interested shall object in writing within three working days of the occurrence of loss and thereupon arbitrators shall be chosen as above. The Trustee shall in that case make settlement with the insurers in accordance with the directions of such arbitrators, who shall also, if distribution by arbitration is required, direct such distribution.

**Art. 22. Guaranty Bonds.** The Owner shall have the right to require the Contractor to give bond covering the faithful performance of the contract and the payment of all obligations arising thereunder, in such form as the Owner may prescribe and with such sureties as he may approve. If such bond is required by instructions given previous to the receipt of bids, the premium shall be paid by the Contractor; if subsequent thereto, it shall be paid by the Owner.

**Art. 23. Cash Allowances.** The Contractor shall include in the contract all allowances named in the Contract Documents and shall cause the work covered to be done by such contractors and for such sums as the Architect may direct, the contract sum being adjusted in conformity therewith. The Contractor declares that the contract sum includes such sums for expenses and profit on account of cash allowances, as he deems proper. No demand for expenses or profit other than those included in the contract sum shall be allowed. The Contractor shall not be required to employ for any such work persons against whom he has a reasonable objection.

**Art. 24. Changes in the Work.** The Owner, without invalidating the contract, may make changes by altering, adding to or deducting from the work, the contract sum being adjusted accordingly. All such work shall be executed under the conditions of the original contract except that any claim for extension of time caused thereby shall be adjusted at the time of ordering such change. Except as provided in Articles 3, 9 and 18, no change shall be made unless in pursuance of a written order from the Owner signed or countersigned by the Architect, or a written order from the Architect stating that the Owner has authorized the change, and no claim for an addition to the contract sum shall be valid unless so ordered.

The value of any such change shall be determined in one or more of the following ways:

- (a) By estimate and acceptance in a lump sum.
- (b) By unit prices named in the contract or subsequently agreed upon.
- (c) By cost and percentage or by cost and a fixed fee.
- (d) If none of the above methods is agreed upon, the Contractor, provided he receives an order as above, shall proceed with the work, no appeal to arbitration being allowed from such order to proceed.

In cases (c) and (d), the Contractor shall keep and present in such form as the Architect may direct, a correct account of the net cost of labor and materials, together with vouchers. In any case, the Architect shall certify to the

amount, including a reasonable profit, due to the Contractor. Pending determination of value, payments on account of changes shall be made on Architect's certificate.

**Art. 25. Claims for Extras.** If the Contractor claims that any instructions, by drawings or otherwise, involve extra cost under this contract, he shall give the Architect written notice thereof before proceeding to execute the work and, in any event, within two weeks of receiving such instructions, and the procedure shall then be as provided in Art. 24. No such claim shall be valid unless so made.

**Art. 26. Applications for Payments.** The Contractor shall submit to the Architect an application for each payment and, if required, receipts or other vouchers showing his payments for materials and labor as required by Article 24. If payments are made on valuation of work done, such application shall be submitted at least ten days before each payment falls due, and, if required, the Contractor shall before the first application, submit to the Architect a schedule of values of the various parts of the work, including quantities, aggregating the total sum of the contract, divided so as to facilitate payments to subcontractors in accordance with Article 44 (e), made out in such form, and if required, supported by evidence as to its correctness, as the Architect may direct. This schedule when approved by the Architect, shall be used as a basis for certificates of payment, unless it be found to be in error. In applying for payments, the Contractor shall submit a statement based upon this schedule and, if required, itemized in such form, and supported by such evidence, as the Architect may direct, showing his right to the payment claimed.

**Art. 27. Certificates and Payments.** If the Contractor has made application as above, the Architect shall, not later than the date when each payment falls due, issue to the Contractor a certificate for such amount as he deems to be properly due. No certificate issued nor payment made to the Contractor nor partial or entire use or occupancy of the work by the Owner shall be a basis for acceptance of any work or materials not in accordance with this contract. The making and acceptance of the final payment shall constitute a waiver of all claims by the Owner, otherwise than under Articles 16 and 29 of these conditions or under requirement of the specifications, and of all claims by the Contractor, except those previously made and still unsettled. Should the Owner fail to pay the sum named in any certificate of the Architect or in an award by arbitration, upon demand when due, the Contractor shall receive in addition to the sum named in the certificate, interest thereon at the legal rate in force at the place of building.

**Art. 28. Payments Withheld.** The Architect may withhold or, on account of subsequently discovered evidence, nullify the whole or a part of any certificate for payment to such extent as may be necessary to protect the Owner from loss on account of:

- (a) Defective work not remedied.
- (b) Claims filed or reasonable evidence indicating probable filing of claims.
- (c) Failure of the Contractor to make payments properly to subcontractors or for material or labor.
- (d) A reasonable doubt that the contract can be completed for the balance then unpaid.
- (e) Damage to another contractor under Article 40.

When all the above grounds are removed certificates shall at once be issued for amounts withheld because of them.

**Art. 29. Liens.** Neither the final payment nor any part of the retainage



centage shall become due until the Contractor, if required, shall deliver to Owner a complete release of all liens arising out of this contract, or receipts in lieu thereof and, if required in either case, an affidavit that so far as he has knowledge or information the releases and receipts include all the labor and material for which a lien could be filed; but the Contractor may, if any subcontractor refuses to furnish a release or receipt in full, furnish a release satisfactory to the Owner, to indemnify him against any claim by lien or otherwise. If any lien or claim remain unsatisfied after all payments are made, the Contractor shall refund to the Owner all moneys that the latter may be compelled to pay in discharging such lien or claim, including all costs and a reasonable attorney's fee.

**Art. 30. Permits and Regulations.** The Contractor shall obtain and pay for all permits and licenses, but not permanent easements, and shall give all notices, pay all fees, and comply with all laws, ordinances, rules and regulations governing the work, as drawn and specified. If the Contractor observes that drawings and specifications are at variance therewith, he shall promptly notify the Architect in writing, and any necessary changes shall be adjusted under Art. 24. If the contractor performs any work knowing it to be contrary to such laws, ordinances, rules and regulations, and without such notice to the Architect, he shall bear all costs arising therefrom.

**Art. 31. Royalties and Patents.** The Contractor shall pay all royalties and license fees. He shall defend all suits or claims for infringement of any patent rights and shall save the Owner harmless from loss on account thereof, except that the Owner shall be responsible for all such loss when the product of a particular manufacturer or manufacturers is specified; if the Contractor has information that the article specified is an infringement of a patent he shall be responsible for such loss unless he promptly gives information to the Architect or Owner.

**Art. 32. Use of Premises.** The Contractor shall confine his apparatus, storage of materials and the operations of his workmen to limits indicated by laws, ordinances, permits, or directions of the Architect and shall not unreasonably encumber the premises with his materials. The Contractor shall not load or permit any part of the structure to be loaded with a weight that will endanger safety. The Contractor shall enforce the Architect's instructions regarding advertisements, fires and smoking.

**Art. 33. Cleaning Up.** The Contractor shall at all times keep the premises free from accumulations of waste material or rubbish caused by his employees and at the completion of the work he shall remove all his rubbish from about the building and all his tools, scaffolding and surplus materials, and leave his work "broom clean" or its equivalent, unless more exactly specified. In case of dispute the Owner may remove the rubbish and charge the cost to the several contractors as the Architect shall determine to be just.

**Art. 34. Cutting, Patching and Digging.** The Contractor shall do all cutting, fitting, or patching of his work that may be required to make its several parts come together properly and fit it to receive or be received by work of other contractors shown upon, or reasonably implied by, the Drawings and Specifications for the completed structure, and he shall make good after them, as the Architect may direct. Any cost caused by defective or ill-timed work shall be borne by the party responsible therefor. The Contractor shall not endanger the work by cutting, digging, or otherwise and shall not cut or alter the work of any other contractor, save with the consent of the Architect.

**Art. 35. Delays.** If the Contractor is delayed in the completion of the work

by any act or neglect of the Owner or the Architect, or of any employee of the Owner or by any other contractor employed by the Owner, or by changes ordered in the work, or by strikes, lockouts, fire, unusual delay by common carriers, unusual casualties, or any causes beyond the Contractor's control, or by any cause authorized by the Architect pending arbitration, or by any cause which the Architect shall decide to justify the delay, then the time of completion shall be extended for such reasonable time as the Architect may decide. No extension shall be made for delay occurring more than seven days before the extension therefor is made in writing to the Architect. In the case of a continuing extension of delay, only one claim is necessary. If no schedule is made under Article 35, no claim for delay shall be allowed on account of failure to furnish drawings until two weeks after demand for such drawings and not then unless the claim be reasonable. This article does not exclude the recovery of damages for delay by either party under Article 39 or other provisions in the Contract Documents.

**Art. 36. Owner's Right to Do Work.** If the Contractor should neglect to prosecute the work properly or fail to perform any provision of this contract, the Owner, after three-days' written notice to the Contractor, may, without prejudice to any other remedy he may have, make good such deficiencies. The Owner may deduct the cost thereof from the payment then or thereafter due the Contractor; provided, however, that the Architect shall approve both the action and the amount charged to the Contractor.

**Art. 37. Owner's Right to Terminate Contract.** If the Contractor should be adjudged a bankrupt, or if he should make a general assignment for the benefit of his creditors, or if a receiver should be appointed on account of his insolvency, or if he should, except in cases recited in Article 35, persistently or repeatedly refuse or fail to supply enough properly skilled workmen or proper materials, or if he should fail to make prompt payment to subcontractors or for materials and labor, or persistently disregard laws, ordinances or the instructions of the Architect, or otherwise be guilty of a substantial violation of any provision of the contract, then the Owner, upon the certificate of the Architect that sufficient cause exists to justify such action, may, without prejudice to any other right or remedy, and after giving the Contractor seven-days' written notice, terminate the employment of the Contractor and take possession of the premises and the materials, tools and appliances thereon and finish the work by whatever means he may deem expedient. In such case the Contractor shall not be entitled to receive any further payment until the work is finished. If the unpaid balance of the contract price shall exceed the expense of finishing the work, including compensation to the Architect for his additional services, such excess shall be paid to the Contractor. If such expense shall exceed such unpaid balance, the Contractor shall pay the difference to the Owner. The expense incurred by the Owner as herein provided, and the damage incurred through the Contractor's default, shall be certified by the Architect.

**Art. 38. Contractor's Right to Stop Work or Terminate Contract.** If the work should be stopped under an order of any court, or other governmental authority, for a period of three months, through no act or fault of the Contractor or of any one employed by him, or if the Owner should fail to make payment to the Contractor, within seven days of its maturity and presentation, and the same be certified by the Architect or awarded by arbitrators, then the Contractor may, upon three-days' written notice to the Owner and the Architect, stop and terminate this contract and recover from the Owner payment for all work performed and any loss sustained upon any plant or material and reasonable expenses and damages.

**39. Damages.** If either party to this contract should suffer damage in manner because of any wrongful act or neglect of the other party or of one employed by him, then he shall be reimbursed by the other party such damage. Claims under this clause shall be made in writing to the liable within a reasonable time of the first observance of such damage not later than the time of final payment, except in case of claims under 16, and shall be adjusted by agreement or arbitration.

**40. Mutual Responsibility of Contractors.** Should the Contractor cause damage to any other contractor on the work, the Contractor agrees, upon notice, to settle with such person by agreement or arbitration, if he will not settle. If such other contractor sues the Owner on account of damage alleged to have been so sustained, the Owner shall notify the Contractor, who shall defend such proceedings at the Owner's expense and, if judgment against the Owner arise therefrom, the Contractor shall pay the same and pay all costs incurred by the Owner.

**41. Separate Contracts.** The Owner reserves the right to let other contracts in connection with this work. The Contractor shall afford other contractors reasonable opportunity for the introduction and storage of their materials and the execution of their work and shall properly connect and coordinate their work with theirs. If any part of the Contractor's work depends for proper execution or results upon the work of any other contractor, the Contractor shall inspect and promptly report to the Architect any defects in such work that render it unsuitable for such proper execution and results. His failure so to inspect and report shall constitute an acceptance of the other contractor's work as proper for the reception of his work, except as to defects which may appear in the other contractor's work after the execution of his work. To insure the proper execution of his subsequent work the Contractor shall measure the work already in place and shall at once report to the Architect any discrepancy between the executed work and the drawings.

**42. Assignment.** Neither party to the Contract shall assign the contract without the written consent of the other, nor shall the Contractor assign moneys due or to become due to him hereunder, without the previous written consent of the Owner.

**43. Subcontracts.** The Contractor shall, as soon as practicable after signing of the contract, notify the Architect in writing of the names of subcontractors proposed for the principal parts of the work and for such others as the Architect may direct and shall not employ any that the Architect may at a reasonable time object to as incompetent or unfit. If the Contractor has not submitted, before signing the contract, a list of subcontractors and the name of any name on such list is required or permitted after signature of the contract, the contract price shall be increased or diminished by the difference between the two bids. The Architect shall, on request, furnish to any subcontractor, wherever practicable, evidence of the amounts certified to on his behalf. The Contractor agrees that he is as fully responsible to the Owner for the acts or omissions of his subcontractors and of persons either directly or indirectly employed by them, as he is for the acts and omissions of persons directly employed by him. Nothing contained in the Contract Documents shall create any contractual relation between any subcontractor and the Owner.

**44. Relations of Contractor and Subcontractor.** The Contractor shall bind every subcontractor and every subcontractor agrees to be bound, by the terms of the General Conditions, Drawings and Specifications, as far as applicable to his work, including the following provisions of this Article, unless

specifically noted to the contrary in a subcontract approved in writing adequate by the Owner or Architect. This does not apply to minor contracts.

The Subcontractor agrees:

(a) To be bound to the Contractor by the terms of the General Conditions, Drawings and Specifications and to assume toward him all the obligations and responsibilities that he, by those documents, assumes toward the Owner.

(b) To submit to the Contractor applications for payment in such reasonable time as to enable the Contractor to apply for payment under Article 25 of the General Conditions.

(c) To make all claims for extras, for extensions of time and for damages, delays or otherwise, to the Contractor in the manner provided in the General Conditions for like claims by the Contractor upon the Owner, except that time for making claims for extra cost as under Article 25 of the General Conditions is one week.

The Contractor agrees:

(d) To be bound to the Subcontractor by all the obligations that the Owner assumes to the Contractor under the General Conditions, Drawings and Specifications and by all the provisions thereof affording remedies and redress to the Contractor from the Owner.

(e) To pay the Subcontractor, upon the issuance of certificates, if issued in the schedule of values described in Article 26 of the General Conditions, the amount allowed to the Contractor on account of the Subcontractor's work to the extent of the Subcontractor's interest therein.

(f) To pay the Subcontractor, upon the issuance of certificates, if issued otherwise than as in (e), so that at all times his total payments shall be as large as the proportion to the value of the work done by him as the total amount certified by the Contractor is to the value of the work done by him.

(g) To pay the Subcontractor to such extent as may be provided by the Contract Documents or the subcontract, if either of these provides for equal or larger payments than the above.

(h) To pay the Subcontractor on demand for his work or materials as far as executed and fixed in place, less the retained percentage, at the time the certificate should issue, even though the Architect fails to issue it for any cause except the fault of the Subcontractor.

(j) To pay the Subcontractor a just share of any fire-insurance money received by him, the Contractor, under Article 21 of the General Conditions.

(k) To make no demand for liquidated damages or penalty for delay in excess of such amount as may be specifically named in the subcontract.

(l) That no claim for services rendered or materials furnished by the Contractor to the Subcontractor shall be valid unless written notice thereof is given by the Contractor to the Subcontractor during the first ten days of the calendar month following that in which the claim originated.

(m) To give the Subcontractor an opportunity to be present and to submit evidence in any arbitration involving his rights.

(n) To name as arbitrator under Article 45 of the General Conditions a person nominated by the Subcontractor, if the sole cause of dispute is the work, materials, rights, or responsibilities of the Subcontractor; or, if of the Contractor and any other subcontractor jointly, to name as such arbitrator a person upon whom they agree.

The Contractor and the Subcontractor agree that:

(o) In the matter of arbitration, their rights and obligations and all procedures shall be analogous to those set forth in Article 45 of the General Conditions.

Nothing in this Article shall create any obligation on the part of the Owner pay to or to see to the payment of any sums to any Subcontractor.

**Art. 45. Arbitration.** Subject to the provisions of Article 10, all questions dispute under this contract shall be submitted to arbitration at the choice either party to the dispute. The Contractor agrees to push the work vigorously during arbitration proceedings. The demand for arbitration shall be in writing with the Architect, in the case of an appeal from his decision, within ten days of its receipt and in any other case within a reasonable time after cause thereof and in no case later than the time of final payment, except to questions arising under Article 16. If the Architect fails to make a decision within a reasonable time, an appeal to arbitration may be taken as if his decision had been rendered against the party appealing. No one shall be nominated or act as an arbitrator who is any way financially interested in this contract or in the business affairs of either the Owner, Contractor or Architect. The general procedure shall conform to the laws of the State in which the work is to be erected. Unless otherwise provided by such laws, the parties may agree upon one arbitrator; otherwise there shall be three, named, in writing, by each party to this contract, to the other party and the Architect, and the third chosen by these two arbitrators, or if they fail to select a third within ten days, then he shall be chosen by the presiding officer of the Bar Association nearest to the location of the work. Should the party demanding arbitration fail to name an arbitrator within ten days of his demand, his right to arbitration shall lapse. Should the other party fail to choose an arbitrator within said ten days, then such presiding officer shall appoint such arbitrator. Should either party refuse or neglect to supply the arbitrators with papers or information demanded in writing, the arbitrators are empowered to proceed ex parte. The arbitrators shall act with promptness. Where there be one arbitrator his decision shall be binding; if three the decision of any two shall be binding. Such decision shall be a condition precedent to the right of legal action, and wherever permitted by law it may be filed in court to carry it into effect. The arbitrators, if they deem that the case demands it, are authorized to award to the party whose contention is sustained such sums as they shall deem proper for the time, expense and trouble incident to the appeal and, if the appeal was taken without reasonable cause, damages for delay. The arbitrators shall fix their own compensation, unless otherwise provided by agreement, and shall assess the costs and charges of the arbitration on either or both parties. The award of the arbitrators must be in writing, and, if in writing, it shall not be open to objection on account of the form of the proceedings or the award, unless otherwise provided by the laws of the State in which the work is to be erected. In the event of such laws providing for any matter covered by this article otherwise than as hereinbefore specified, the method of procedure throughout and the legal effect of the award shall be wholly in accordance with the said State laws, it being intended hereby to lay down a principle of action to be followed, leaving its local application to be adapted to the legal requirements of the place in which the work is to be erected.

## **B. THE STANDARD FORM OF BOND \***

**USE IN CONNECTION WITH THE THIRD EDITION OF THE STANDARD FORM OF AGREEMENT AND GENERAL CONDITIONS OF THE CONTRACT**

This form has been approved by the National Association of Builders' Exchanges, The National Association of Master Plumbers, the National Association of Sheet Metal

\* Published by permission of The American Institute of Architects.

Contractors of the United States, the National Electrical Contractors' Association, the United States, the National Association of Marble Dealers, the Building and Quarries Association, the Building Trades Employers' Association of the City of New York, and the Heating and Piping Contractors' National Association.

COPYRIGHT 1915 BY THE AMERICAN INSTITUTE OF ARCHITECTS, THE OCTAGON WASHINGTON, D. C.

**KNOW ALL MEN:** That we.....

(Here insert the name and address or legal title of the Contractor.)

.....(Two blank lines)\*  
hereinafter called the Principal, and.....

(Here insert the name and address or legal title of one or more sureties.)

.....(Two blank lines).....

.....(Two blank lines).....

hereinafter called the Surety or Sureties, are held and firmly bound unto.....

(Here insert the name and address or legal title of the Owner.)

.....(Two blank lines).....

hereinafter called the Owner, in the sum of.....

.....(Two blank lines).....(\$.....

for the payment whereof of the Principal and the Surety or Sureties bind themselves, their heirs, executors, administrators, successors and assigns jointly and severally, firmly, by these presents.

**Whereas,** the Principal has, by means of a written Agreement, dated.....

.....entered into a contract with the Owner.....

.....(Two blank lines).....

a copy of which Agreement is by reference made a part hereof:

**Now, Therefore,** the Condition of this Obligation is such that if the Principal shall faithfully perform the Contract on his part, and satisfy all claims and demands, incurred for the same, and shall fully indemnify and save harmless the Owner from all cost and damage which he may suffer by reason of failure so to do, and shall fully reimburse and repay the Owner all outlay and expense which the Owner may incur in making good any such default, and shall pay all persons who have contracts directly with the Principal for labor or materials, this obligation shall be null and void; otherwise it shall remain in full force and effect.

**Provided,** however, that no suit, action or proceeding by reason of any default whatever shall be brought on this bond after.....months from the day on which the final payment under the Contract falls due.

**And Provided,** that any alterations which may be made in the terms of the Contract, or in the work to be done under it, or the giving by the Owner of an extension of time for the performance of the Contract, or any other forbearance on the part of either the Owner or the Principal to the other shall not in any way release the Principal and the Surety or Sureties, or either or any of them, their heirs, executors, administrators, successors, or assigns from their liability hereunder, notice to the Surety or Sureties of any such alteration, extension, or forbearance being hereby waived.

Signed and Sealed this.....day of..... 19.....

In Presence of

..... } as to .....  
(Repeated three times) (Repeated three times)  
..... }

\* Dotted lines, as indicated, are in the standard documents and are omitted here to save space.

# THE STANDARD FORM OF AGREEMENT BETWEEN CONTRACTOR AND SUBCONTRACTOR \*

USE IN CONNECTION WITH THE THIRD EDITION OF THE STANDARD FORM OF AGREEMENT AND GENERAL CONDITIONS OF THE CONTRACT

This form has been approved by the National Association of Builders' Exchanges, The National Association of Master Plumbers, the National Association of Sheet Metal Contractors of the United States, the National Electrical Contractors' Association of the United States, the National Association of Marble Dealers, the Building Granite Carriers Association, the Building Trades Employers' Association of the City of New York, and the Heating and Piping Contractors' National Association.

COPYRIGHT 1915 BY THE AMERICAN INSTITUTE OF ARCHITECTS, THE OCTAGON, WASHINGTON, D. C.

THIS AGREEMENT, made this.....day of.....19... and between.....hereinafter called Subcontractor and.....hereinafter called the Contractor.

WITNESSETH, That the Subcontractor and Contractor for the consideration as hereinafter named agree as follows:

**Section 1.** The Subcontractor agrees to furnish all material and perform all work as described in Section 2 hereof for.....(Here name the kind of building).....(Blank lines).....(Here insert the name of the Owner).....(Blank lines).....hereinafter called the Owner, at.....(Here insert the location of the work.).....(Blank lines).....in accordance with the General Conditions of the Contract between the Owner and the Contractor, and in accordance with the Drawings and the Specifications prepared by.....hereinafter called the Architect, all of which General Conditions, Drawings and Specifications signed by the parties hereto or identified by the Architect, form a part of a Contract between the Subcontractor and the Owner dated.....19.. and hereby become a part of this Contract.

**Section 2.** The Subcontractor and the Contractor agree that the materials to be furnished and work to be done by the Subcontractor are (Here insert a brief description of the work, preferably by reference to the numbers of the Drawings and the pages of the Specifications.).....(Blank lines).....

**Section 3.** The Subcontractor agrees to complete the several portions and the whole of the work herein sublet by the time or times following:.....(Here insert the dates or date and if there be liquidated damages state them.).....(Blank lines).....

**Section 4.** The Contractor agrees to pay the Subcontractor for the performance of his work the sum of .....(Blank line).....(\$.....) out of his current funds, subject to additions and deductions for changes as may be made upon, and to make payments on account thereof in accordance with Section 5 hereof.

**Section 5.** The Contractor and Subcontractor agree to be bound by the terms of the General Conditions, Drawings and Specifications as far as applicable to this subcontract, and also by the following provisions:†

† Published by permission of The American Institute of Architects.

† Article 44 of the General Conditions of the Contract is here repeated in full with the exception of references to other articles. See page 1761.

**Section 6** .....

.....(One page of blank lines) .....

Finally. The Subcontractor and Contractor, for themselves, their heirs, successors, executors, administrators and assigns, do hereby agree to the performance of the covenants herein contained.

IN WITNESS WHEREOF they have herunto set their hands the day and date first above written.

In Presence of

.....  
Subcontractor.....  
Contractor

## **D. STANDARD FORM OF ACCEPTANCE OF SUBCONTRACTOR PROPOSAL \***

FOR USE IN CONNECTION WITH THE THIRD EDITION OF THE STANDARD FORM OF AGREEMENT AND GENERAL CONDITIONS OF THE CONTRACT

This form has been approved by the National Association of Builders' Exchanges, the National Association of Master Plumbers, the National Association of Sheet Metal Contractors of the United States, the National Electrical Contractors' Association of the United States, the National Association of Marble Dealers, the Building Ground Quarries Association, the Building Trades Employers' Association of the City of New York, and the Heating and Piping Contractors' National Association.

COPYRIGHT 1915 BY THE AMERICAN INSTITUTE OF ARCHITECTS, THE OCTAGON, WASHINGTON, D. C.

Dear Sir: Having entered into a contract with (Here insert the name and address or corporate title of the Owner.) .....

.....(Blank line).....

for the erection of (Here insert the kind of work and the place at which it is to be erected.) .....

.....(Blank line).....

in accordance with plans and specifications prepared by (Here insert the name and address of the Architect.) .....

.....(Blank line).....

and in accordance with the General Conditions of the Contract prefixed to the specifications, the undersigned hereby accepts your proposal of (Here insert date) .....

to provide all the materials and do all the work of (Here insert the kind of work to be done, as plumbing, roofing, etc., accurately describing by number, page, etc., the drawings and specifications governing such work.) .....

.....(Blank lines).....

The Undersigned agrees to pay you in current funds for the faithful performance of the subcontract established by this acceptance of your proposal the sum of ..... (\$ .....

Our relations in respect of this subcontract are to be governed by the plans and specifications named above, by the General Conditions of the Contract as far as applicable to the work thus sublet and especially by Article 44 of those conditions printed on the reverse hereof.†

Very truly yours,

\*Published by permission of The American Institute of Architects.

† Article 44 of the General Conditions of the Contract is printed in full on the reverse side of the Institute's standard form. See page 1761.



The Subcontractor entering into this agreement should be sure that not only the above Article 44, but the full text of the General Conditions of the Contract as signed by the Owner and Contractor is known to him, since such text, though not herein repeated, is binding on him.

**OFFICIAL INSTITUTE DOCUMENTS OF A PERMANENT NATURE PUBLISHED (1932) BY THE AMERICAN INSTITUTE OF ARCHITECTS.**  
**TITLES AND PRICES**

The Journal of the American Institute of Architects, monthly, 50 cts; yearly, to A. I. A. members.....	\$2.50
Yearly, to non-Institute members.....	5.00
Monograph on the Octagon (Thirty Drawings, 12 X 18, Photos and Text)	12.50
Standard Contract Documents:	
Agreement and General Conditions in Cover.....	.20
General Conditions without Agreement.....	.14
Agreement without General Conditions.....	.05
Bond of Suretyship.....	.03
Form of Subcontract.....	.04
Letter of Acceptance of Subcontractor's Proposal.....	.03
Cover (heavy paper, with valuable notes).....	.01
Complete set in Cover.....	.30
Form of Agreement, Owner and Architect (Percentage Basis).....	.05
Circular of Information on the Fee-Plus-Cost System of Charges..... (Explains Owner-Architect Agreement, Fee-Plus-Cost Basis)	.03
Form of Agreement, Owner and Architect (Fee-Plus-Cost Basis).....	.05
Form of Agreement, Owner and Contractor (Cost-Plus-Fee Basis)....	.10
Circular of Information Relative to Cost-Plus-Fee System of Contracting (Explanatory of Contractor-Owner Agreement)	.06
Circular of Advice and Information Relative to the Conduct of Architectural Competitions.....	Free
Standard Form of Competition-Programme.....	.10
Proceedings of the Convention.....	Free
Directory to Institute Members.....	Free
Official Documents of the Institute.....	Free
Circular on Functions of the Architect.....	.03
Circular of Information Concerning Requirements for Institute Membership.....	Free
Circular of Information Concerning Requirements for Chapter Associateship.....	Free
Constitution and By-laws.....	Free
Standard Form of Chapter Constitution and By-laws.....	Free
Circular of Advice Relative to Principles of Professional Practice. The Canon of Ethics.....	Free
Schedule of Proper Minimum Charges.....	.02
Circular Relative to the Size and Character of Advertising Matter.....	Free
Standard Symbols for Wiring Plans.....	Free
Standard Construction Classification, Filing System for Architects' Offices.....	Free

Model Registration Law.....	1769
List of Institute Documents.....	1770

For the convenience of the members of the Institute, and the profession generally, who use in their practice, by reference or otherwise, the various official documents of the American Institute of Architects, the above schedule of Titles and Prices is issued. On single copies of pamphlet-documents postage will be prepaid, otherwise not. The prices quoted in practically every case are to cover the actual cost of printing and handling. The Institute has no desire to make a profit on documents issued primarily for the benefit of the profession. For distinctly educational work, and for Chapter-work, no charge will be made for small quantities of documents, except for postage. Requests of this kind should come through the Chapter-Secretary or a Committee Chairman. Communications and remittances should be sent to the Executive Secretary, The Octagon House, Washington, D. C. All orders are filled the day received.

## REGULATION OF THE PRACTICE OF ARCHITECTURE BY STATE LEGISLATION \*

**States Having Registration Laws (1923).** Twenty-three have registration or license laws (1923) for the practice of architecture: California, Colorado, Florida, Georgia, Idaho, Illinois, Louisiana, Michigan, Minnesota, Montana, New Jersey, New York, North Carolina, North Dakota, Oregon, Pennsylvania, South Carolina, Tennessee, Utah, Virginia, Washington, West Virginia, and Wisconsin. Laws are pending (1923) in Indiana, Iowa, Kansas, and other states.

**Theory of Registration Laws.** The reason for the REGULATION OF ARCHITECTURAL PRACTICE BY LAW is the fact that men improperly qualified for practice can otherwise, at will, assume the title of ARCHITECT and impose upon the public, thereby discrediting the profession. In some States and in Canada it seems evident that legislation was enacted for protection of local architects against encroachment on the part of non-resident architects. Such a move is unworthy of the profession, whose efforts through legislation should be to encourage design of higher artistic quality and to insure safe construction. Some laws, like the first one formulated (Illinois 1897), are LICENSE LAWS in that they tax every architect. Other laws, that in New York, for example, are REGISTRATION LAWS, undertake to issue certificates only to those qualified for practice. Registration laws should not in a retroactive way attempt to deprive those of their right who, by virtue of having been in bona-fide practice at the time the law was enacted, have the legal right to continue in such practice, subject to the effect of public sentiment which may be created against non-resident architects, and subject also to responsibilities imposed by building ordinances requiring safe construction. The THEORY OF THE REGISTRATION LAW is that an architect should attain to a certain minimum general education, a certain minimum technical education, plus a certain minimum of practical experience before beginning practice on his own account. That theory is carried into effect by requiring under penalty that no person may assume the title ARCHITECT whether he is a new practitioner, or an experienced practitioner from within the State, without first establishing his qualifications and receiving a certificate authorizing him to use that title. The NEW YORK STATE LAW, printed in

\* This matter was prepared by D. Everett Waid, President (1922) of the New York State Board of Examiners and Registration of Architects.

th, is typical of recent laws which attempt to embody this theory. References are made to this law and the notation also that the American Institute of Architects is prepared to cooperate with any persons interested who desire to improve upon the laws already passed when trying to secure in other States such legislation as will tend to raise the standard of qualifications of architects. Such legislation will certainly achieve its highest end if looked upon as educational in purpose. Incidentally it may be remarked that the best interests of the public will be conserved if earnest efforts are made toward a COMMON STANDARD which will encourage reciprocal relations among the States. An architect who has demonstrated his qualifications by passing a proper examination in one State should not be harassed by repetitions of the test in other States in which he may choose to practice.

**Standards of Education.** The GENERAL EDUCATION required under the New York law is the completion of a high-school course, or equivalent thereof; also the satisfactory completion of such courses in mathematics, history, and the modern language, as are included in two years of an approved institution granting the degree of A.B. Five years' PRACTICAL EXPERIENCE in the office of a reputable architect, beginning after the high-school course, is required before a candidate can take the TECHNICAL EXAMINATION conducted by the Board of Examiners. This technical examination is not required of graduates of recognized schools of architecture who shall have had, also, three years' practical experience.

**Administration of Registration Laws.** In New York State, architects are admitted to practice by the Regents of the University of the State, who administer the law through a BOARD OF EXAMINERS AND REGISTRATION OF ARCHITECTS. In other States, the Boards of Examiners are appointed by the Governors.

**Application for Certificates.** Application-blanks and information regarding admittance to practice, dates of examinations, etc., can be obtained by addressing the Board of Examiners and Registration of Architects, Education Building, Albany, N. Y. In other States, such inquiries may be addressed to the Secretary of State.

**Model Registration Law.** Those interested in STATE LEGISLATION REGULATING THE PRACTICE OF ARCHITECTURE AND THE EDUCATION OF ARCHITECTS may secure copies of a bill issued to serve as a BASIC MODEL which, with suitable modifications, may be enacted in any State. Address the Secretary, American Institute of Architects, The Octagon House, Washington, D. C.

## REGISTRATION OF ARCHITECTS IN THE STATE OF NEW YORK \*

**Law in relation to the practice of architecture and the rules of the State Board of Examiners and Registration of Architects approved by the Regents of The University of the State of New York**

The Assistant Commissioner and Director of Professional Education is in charge of universities, colleges, professional and technical schools, the execution of the laws concerning the professions, and the relations and chartering of institutions. All correspondence relating to the issuance of certificates, the rules of licensing examinations, and admissions to the practice of architecture

The form of the law itself and of the State official documents, with the exception of type, are inserted as enacted and printed, without further editing.

should be addressed to the Director of the Examinations and Inspection Division, Albany, N. Y.

## REGISTERED ARCHITECTS

General business law (L. 1909, Ch. 25) Chapter 20 of the consolidated law became a law February 17, 1909

### Article 7-A, Registered Architects

Became a law April 28, 1915 (Laws of 1915, Chapter 454). As amended by Laws of 1916, Chapter 77.

Section 77. Registered Architects.

Section 78. Board of Examiners.

Section 79. Qualifications. Examinations. Fees.

Section 79a. Certificates.

Section 79b. Violation of Article.

**77. Registered Architects.** Any person residing in or having a place of business in the State, who, before this article takes effect, shall not have been engaged in the practice of architecture in New York State, under the title of architect, shall, before being styled or known as an architect, secure a certificate of his qualification to practice under the title of architect, as provided by this article. Any person who shall have been engaged in the practice of architecture under the title of architect, before this article takes effect, may secure such certificate, in the manner provided by this article. Any person having a certificate pursuant to this article may be styled or known as a registered architect. No other person shall assume such title or use the abbreviation R. A., or any other words, letters or figures to indicate that the person using the same is a registered architect; but this article shall not be construed to prevent persons other than architects from filing applications for building permits or obtaining such permits.

**78. Board of Examiners and Registration.** There shall be a State Board of Examiners and Registration of Architects, who, and their successors, shall be appointed by and hold during the pleasure of the Board of Regents of the University of the State, and who, subject to the approval and to the rules of the Regents, may make rules for the examination and registration of candidates for the certificates provided for by this article. Such board of examiners shall be composed of five architects, who have been in active practice in the State of New York for not less than ten years, previous to their appointment, selected by the Regents. Such examiners shall be entitled to such compensation for their services under this article as the Board of Regents shall determine, not exceeding in the aggregate the amount of fees collected from applicants for certificates.

**79. Qualification. Examination. Fees.** Any citizen of the United States, or any person who has duly declared his intention of becoming a citizen, being at least twenty-one years of age and of good moral character, may apply for examination or certificate of registration under this article, but before securing such certificate shall submit satisfactory evidence of having satisfactorily completed the course in high school approved by the Regents of the University or the equivalent thereof and subsequent thereto of having satisfactorily completed such courses in mathematics, history and one modern language, as are included in the first two years in an institution approved by the Regents, conferring the degree of bachelor of arts. Such candidate shall

dition submit satisfactory evidence of at least five years' practical experience in the office or offices of a reputable architect or architects, commencing after completion of the high school course. The board of examiners may accept satisfactory diplomas or certificates from approved institutions covering the course required for examination. Upon complying with the above requirements, the applicant shall satisfactorily pass an examination in such technical and professional courses as are established by the board of examiners. The board of examiners in lieu of examinations may accept satisfactory evidence of any one of the qualifications set forth under subdivisions 1 and 2 of this section.

1. A diploma of graduation or satisfactory certificate from an architectural college or school approved by the Regents, together with at least three years' practical experience in the office or offices of a reputable architect or architects; the three years' experience shall be counted only as beginning at the completion of the course leading to the diploma or certificate; the State Board of Examiners and Registration of Architects may require applicants under this division to furnish satisfactory evidence of knowledge of professional practice;

2. Registration or certification as an architect in another state or country, where the qualifications required for the same are equal to those required in this State;

3. The board of examiners in lieu of all examinations shall accept satisfactory evidence as to the applicant's character, competency and qualifications, and that he has been continuously engaged in the practice of architecture for more than two years next prior to the date when this article shall take effect, or that he has been actually engaged in the practice of architecture on his own account as a member of a reputable firm or association for more than one year prior to the date when this article shall take effect; providing the application for a certification shall be made on or before January 1, 1918. Any architect who has lawfully practiced architecture for a period of more than ten years out of the State shall be required to take only a practical examination, which shall be of the nature to be determined by the State Board of Examiners and Registration of Architects. Every person applying for examination or certification of registration under this article shall pay a fee of twenty-five dollars to the Board of Regents.

**Sec. 10. Certificates.** 1. The result of every examination, or other evidence of qualification, as provided by this article, shall be reported to the Board of Regents by the board of examiners, and a record of the same shall be kept by the Board of Regents, and such board shall, unless deemed otherwise advisable, issue a certificate of registration to every person certified by the board of examiners as having passed such examination or as being otherwise qualified to be entitled to receive the same.

Every person securing such certificates shall register in the office of the county clerk of the county in which he maintains a place of business, in a book kept by the clerk for such purpose, his name, residence, place and date of birth, post office address, source, number and date of his certificate of registration, whether he practices architecture and the date of such registration, which registration shall be entitled to make only upon showing to the county clerk his certificate of registration and making an affidavit of the above facts, and that he is the principal person named in the certificate; that before receiving the same he has complied with all of the preliminary requirements of this article and the rules of the Regents and the board of examiners as to the terms and the amount of the study and examination; that no money other than the fees prescribed by

this article and such rules was paid directly or indirectly for such registration and that no fraud, misrepresentation or mistake in material regard was employed or occurred in order that such certificate should be made, which and shall be preserved in a bound volume by the county clerk. The county clerk shall indorse or stamp on the back of the certificate the date and his name preceded by the words "registered as authority to practice as a registered architect, in the clerk's office of.....county"; and shall issue to each person duly registering and making such affidavit a certificate of registration in his county which shall include a transcript of the registration. Such transcript and the certificate of registration may be offered as presumptive evidence in all courts of the facts stated therein. The county clerk's fee for taking such registration and affidavit and issuing such certificate shall be one dollar. Any person who, having lawfully registered as aforesaid, shall thereafter change his name in any lawful manner, shall register the new name with a marginal note of the former name, and shall note upon the margin of the former registration the fact of such change and a cross-reference to the new registration. A county clerk who knowingly shall make or suffer to be made upon the book of registry of architects kept in his office any other entry than is provided for in this article shall be guilty of a misdemeanor.

3. An architect having duly registered to practice as a registered architect in one county and removing his practice or a part thereof to another county or regularly engaging in practice or opening an office in another county, shall send, by registered mail, to the clerk of such other county, his certificate of registration. If such certificate clearly shows that the original registration was duly issued under seal by the Board of Regents, the clerk shall thereupon register the applicant in the latter county on receipt of a fee of 25 cents and shall stamp or indorse on such certificate the date and his name, preceded by the words "Registered also in.....county," and return the certificate to the applicant.

4. The Board of Regents may revoke any certificate, if such action be recommended by the board of examiners, after thirty days' written notice to the holder thereof and after a hearing before the board of examiners, upon proof that such certificate has been obtained by fraud or misrepresentation, or upon proof that the holder of such certificate has been guilty of felony in connection with the practice of architecture.

**79b. Violation of Article.** Any violation of this article shall be a misdemeanor, punishable for the first offense by a fine of not less than fifty dollars nor more than one hundred dollars, and for a subsequent offense by a fine of not less than two hundred nor more than five hundred dollars, or imprisonment for not more than one year, or both.

## SYNOPSIS OF SUBJECTS ON WHICH EXAMINATIONS ARE BASED

The examinations of applicants for certificates shall be based on the following subjects or groups:

**a. History of Architecture.** The candidate shall give evidence in the examination that he understands the essentials that give character to various historic styles of architecture by clear descriptive analyses of construction, general expression and ornament. Questions will be asked relating to:

(1) Architecture in various countries.

\* Taken from the Rules of the New York State Board of Examiners and Registrars of Architects.

- (2) Styles and orders. Sketches and names of examples.
- (3) Sculpture and painting and color as applied to architecture.
- (4) Furniture and decoration.

**b. Architectural Composition.** The candidate shall give evidence that understands the broad principles underlying the subject of architectural planning by the application of the same to specific problems stated in the examination. The social, economic and physical requirements of several architectural problems will be outlined and the candidate will be asked to state the principal considerations that would guide him in the choice of an arrangement of plan that would most adequately express and fulfill the conditions suggested. Small sketches will be required to illustrate the application of the principles involved. Questions will refer to:

(1) Principles of Planning: Problems in planning individual buildings, groups and towns; illustrations may be asked to show how plans may be influenced by considerations, esthetic, structural, and as to kinds of materials, and modifications of plan due to considerations of occupancy and of fire protection both for fireproof and non-fireproof buildings.

(2) Esthetic Design: Original examples will be required illustrating principles involved in the solution of practical problems and the relation of plan and elevation.

**c. Architectural Engineering.** In this examination the candidate shall give evidence that he has a thorough understanding of the appropriate use of the various materials used in buildings. He will be required also to solve certain technical problems such as the calculation of the proper economic dimensions of various structural members common to buildings, in the several materials noted. Candidates will not be required to make complicated calculations, and the use of handbooks will be permitted. Questions will be asked to test the knowledge of these subjects that an architect should possess in order properly to advise his clients and to design or to direct the designing of suitable mechanical equipment for buildings of different classes. Questions will be asked relating to:

(1) Structural Design:

Column, girder, joist and truss designs.

Wind bracing for buildings of different classes.

Various types of foundations and conditions under which their use is advisable.

Various kinds of bottom met with in ordinary practice and unit loads allowable for foundations in each case.

Different types of concrete floor slab construction in common use.

Structural design as affected by fire and resistive qualities of different building materials.

(2) Use of Materials:

Strength of materials, durability and considerations of wear and repair.

Esthetic reasons for use of different materials.

(3) Heating and Ventilating:

Various systems and reasons for and against use under specific conditions.

Important features of design that should be specified.

(4) Electric Equipment: General questions rather than technical.

Various kinds of current and considerations involved.

Methods of wiring and insulation; methods and materials.

Light distribution.

Lighting fixtures; esthetic and practical design; important mechanical details.

Generators, motors, storage batteries, and advice to clients regarding the same.

Independent power plant considerations.

(5) Plumbing and Fire Protection Equipment:

Supply and waste systems.

Kinds of material for piping and reasons for use.

Kinds of materials for fixtures.

Sewage disposal plants and considerations involved.

Water supply, different systems and considerations of supply and filtration.

Sprinklers and other fire protection equipment.

(6) Elevators:

Types of elevators.

Arrangement and location of elevators.

**d. Architectural Practice.** In this examination the candidate shall give evidence that he understands the moral and the legal responsibilities of the architect in the proper performance of his duties as such. He will be required to outline or draft clauses of contracts between owner and architect and state specifically the content of the clauses included in the contract between owner and contractor which are incorporated for the purpose of defining the architect's authority and responsibility to both parties of the contract. The candidate will be required to show that he understands the major provisions of state, county and municipal building laws and ordinances and how they affect the different classes of buildings. He shall be able also to cite the competent authority under whose jurisdiction permits for the erection and occupancy of various types of buildings must be obtained. Questions will be asked relating to:

(1) Business and Professional Functions of Architects:

Professional relation of clients and contractors.

Essential provisions in contract between architect and his client.

When the architect is disinterested arbitrator, and when he properly may act as an agent.

Relation of architects to each other in ordinary practice, in association, and in consultation, and when one architect displaces another on a given piece of work.

Sources and kinds of compensation for architect's services.

Responsibilities of architects and methods of conducting their business.

Scope of architect's work, esthetic and structural.

When expert's services should be advised.

Scope of architect's work, administrative business, and legal contracts, arbitrations, court evidence, contractors in default, when counsel of civil lawyer should be advised.

(2) Building Laws:

State, county and municipal laws, ordinances and regulations, and how they affect different classes of buildings.

Filing drawings and specifications and obtaining permits.

(3) Contracts:

Drawings, specifications and agreement as essential parts of the contract between owner and builder.

Variations in kinds and forms of agreements and contracts.

Definition of architect's authority.

Provisions as to bids, letting contracts, unit prices, requisitions, certificates and payments.

Insurance: fire, liability, compensation.



Bonding contractors.

(4) Specifications:

General conditions, purposes and scope.

Scope and purposes and limitations of general clauses.

Principles which should be observed in writing specifications.

Right and wrong methods of specifying qualities of materials and workmanship.

(5) Drawings:

Purposes, use and limitations of preliminary drawings.

Essentials which should be embodied in contract drawings.

Purposes and limitations of detail and other working drawings which are not contract drawings.

## REGISTRATION OF SCHOOLS OF ARCHITECTURE \*

A school of architecture may be registered as maintaining a satisfactory standard and may be legally incorporated. Incorporation by the Regents will be made on formal application and inspection by the Department which show that the school possesses the minimum requirements.

**Application.** An educational institution desiring admission to or incorporation or registration by the University must file a written application giving the information requested in the form prescribed by the Commissioner of Education. A form will be mailed on application to the Assistant Commissioner of Higher Education. Such application must be on file in the Education Department at least 10 days before the meeting of the Regents at which action thereon is to be taken.

**Accrediting.** Institutions unable to meet the standards required by the Regents for registration in full shall be accredited by the Department for one or more years of professional training as they meet the requirements for admission to the Department for professional training set by the Regents standards.

**Recognition Accorded Accredited Professional Schools.** Professional schools registered by the Regents shall give the work of accredited institutions higher recognition than that accorded such institutions in the Department's accredited list, viz.: (1) The successful completion of a four-year course in a professional school accredited by the Department for three years shall be accorded three years' recognition only; (2) the successful completion of a three-year course in a professional school accredited by the Department for two years shall be accorded two years' recognition only; (3) the successful completion of a two-year course in a professional school accredited by the Department for one year shall be accorded one year's recognition only. A registered school may refuse to accord an accredited institution the recognition accorded it by the Department but it may not give it any higher recognition.

**Comity of Action in the Transfer of Students from One Professional School to Another.** The Department does not consider a course in a school of architecture satisfactory if more than two conditions, one major of 100 hours and one minor of 50 hours, are allowed students for promotion from one year's course to the next.

Taken from the Rules of the New York State Board of Examiners and Registration of Architects. As schools may be added to the accredited lists, these lists must be revised from time to time.

## REGENTS' RULES

## Schools of Architecture \*

**440. Definitions.** SCHOOL OF ARCHITECTURE means any college or school of architecture, or school, department or course of architecture in a college or university, whatever the corporate title.

**441. Requirements.** A SCHOOL OF ARCHITECTURE, legally incorporated, may be registered as maintaining proper standards. It must afford satisfactory instruction in such technical and professional courses as are established by the board of examiners, for admission to the examinations in the history of architecture, architectural composition, architectural engineering and architectural practice.

**442. General Education.** A. PRELIMINARY. For admission to a school of architecture, evidence shall be required showing the satisfactory completion of a four-year course in a secondary school approved by the Board of Regents or the equivalent, 72 counts in the academic examinations. B. HIGHER. For admission to the examinations for the certificate of R. A. evidence shall be required of such courses in mathematics, history and modern languages as are included in the first two years of the curriculum leading to the degree of bachelor in arts, or the equivalent, graduation from a junior college approved by the Board of Regents.

### SCHOOLS OF THE UNITED STATES AND CANADA REGISTERED OR ACCREDITED.† JUNE, (1918)

Alphabetically Arranged by States

#### United States

**California.** REGISTERED: School of Architecture, University of California, Berkeley. (Graduate course, one or two years.)

**District of Columbia.** REGISTERED: Department of Architecture, George Washington University, Washington. (Course, four years.)

**Georgia.** REGISTERED: Department of Architecture, Georgia School of Technology, Atlanta. (Course, four years.)

**Illinois.** REGISTERED: Chicago School of Architecture, Armour Institute of Technology, Chicago. (Course, four years.)

Department of Architecture, University of Illinois, Urbana. (Course, four years.)

**Indiana.** REGISTERED: College of Architecture, University of Notre Dame, Notre Dame. (Course, four years.)

Department of Architectural Engineering, Rose Polytechnic Institute, Terre Haute. (Course, four years.)

**Kansas.** Department of Architecture, Kansas State Agricultural College, Manhattan. (Course, four years.)

Department of Architectural Engineering, University of Kansas, Lawrence. (Course, four years.)

\* Taken from the Rules of the New York State Board of Examiners and Registration of Architects. As schools may be added to the accredited lists, these lists must be revised from time to time.

† This is the list of Schools or Departments of Architecture in the United States and Canada, registered or accredited by the New York State Board of Examiners and Registration of Architects, and must be added to from time to time.

- Louisiana.** REGISTERED: School of Architecture and Architectural Engineering, Tulane University, New Orleans. (Courses, four years.)
- Massachusetts.** REGISTERED: Departments of Architecture and Architectural Engineering, Massachusetts Institute of Technology, Cambridge. (Courses, four years.)
- School of Architecture, Harvard University, Cambridge.** (Graduate Course, two years.)
- Michigan.** REGISTERED: College of Architecture, University of Michigan, Ann Arbor. (Course, four years.)
- Minnesota.** REGISTERED: Department of Architecture, University of Minnesota, Minneapolis. (Course, four years.)
- Missouri.** REGISTERED: School of Architecture, Washington University, St. Louis. (Course, four years.)
- Nebraska.** REGISTERED: Department of Architectural Engineering, University of Nebraska, Lincoln. (Course, four years.)
- New York.** REGISTERED: College of Architecture, Cornell University, Ithaca. (Course, four or five years.)
- Department of Architecture, Syracuse University, Syracuse.** (Course, four years.)
- School of Architecture, Columbia University, New York.** (Course, four years.)
- Ohio.** REGISTERED: Department of Architecture, Ohio State University, Columbus. (Course, four years.)
- Oklahoma.** REGISTERED: Department of Architecture, Oklahoma Agricultural and Mechanical College, Stillwater. (Courses, four years.)
- Pennsylvania.** REGISTERED: Department of Architectural Engineering, Pennsylvania State College, State College. (Course, four years.)
- Department of Architecture, University of Pennsylvania, Philadelphia.** (Courses, four years.)
- Department of Architecture, Carnegie Institute of Technology, Pittsburgh.** (Course, four years.)
- Texas.** REGISTERED: Departments of Architecture and Architectural Engineering, Agricultural and Mechanical College of Texas, College Station. (Courses, four years.)
- School of Architecture, University of Texas, Austin.** (Course, four years.)

#### Canada

- Ontario.** REGISTERED: Department of Architecture, University of Toronto, Toronto. (Course, four years.)
- Quebec.** Department of Architecture, McGill University, Montreal. (Course, five years.)

#### SYNOPSIS OF REGISTRATION LAWS \*

This study † is made for those who would see at a glance the statutory requirements for the practice of architecture throughout the United States.

As States are added to the list of those which have laws for the Registration of Architects, these lists must be revised from time to time. Georgia, Michigan, Pennsylvania, Virginia, and Washington have been added to the list, up to January, 1921. Taken from Handbook No. 35, published annually by The University of the State of New York, and containing information relating to the Registration of Architects.

There are four distinct lines of statutory requirements: (1) Preliminary education; (2) professional training; (3) licensing test; (4) registry. These items with (5) the title of the executive officer and the administrative board are given uniformly in this synopsis.\* If there are no statutory requirements, the word "none" covers the item.

**California.** (1) None; (2) none; (3) examination; (4) with the recorder of the county of residence annually; (5) secretary, State Board of Architects, San Francisco.

**Colorado.** (1) None; (2) none; (3) examination or certificate from a similarly constituted board of another state; (4) with the secretary of state annually with the board; (5) Secretary, State Board of Examiners of Architects, Denver.

**Idaho.** (1) Approved high school course or its equivalent and in addition two-year course in English and mathematics such as is required in an approved B. A. course; (2) three years' practical experience in the office of a reputable architect; (3) examination or in lieu of all examinations, graduation from an approved architectural school or registration as an architect in another state whose standard equals that of this board; (4) with the secretary of state; (5) Secretary, State Board of Examiners of Architects.

**Illinois.** (1) None; (2) none; (3) examination; (4) with the clerk of the county of practice, annually; (5) Secretary, Department of Registration and Examination, Springfield.

**Louisiana.** (1) Good primary education; (2) none; (3) examination or diploma from an approved school of architecture; (4) with the district clerk of the parish of residence and annually with the board; (5) Secretary, Board of Architectural Examiners, New Orleans.

**Montana.** (1) None; (2) none; (3) examination or a license from another state board; (4) with the clerk and recorder of the county of residence annually with the state treasurer; (5) Secretary, Board of Architectural Examiners.

**New Jersey.** (1) None; (2) none; (3) examination or a license from a similarly constituted board of another state or membership in the American Institute of Architects; (4) with the board, annually and with the secretary of state; (5) Secretary, State Board of Architects, Trenton.

**New York.** (1) Approved high school course or the equivalent and in addition such course in mathematics, history and one modern language as is included in an approved two-year B. A. course; (2) at least five years' practical experience in the office of a reputable architect; (3) examination or graduation from an approved architectural school with three years' experience or registration in another state or country having standards equal to that of this board; (4) with the Board of Regents; (5) Secretary, State Board of Examiners and Registration of Architects, New York.

**North Carolina.** (1) Prescribed by the board; (2) prescribed by the board; (3) examination or a certificate from a similarly constituted board in another state or membership in the American Institute of Architects; (4) with the clerk of the superior court of the county of residence; (5) Secretary, the Board of Architectural Examination and Registration.

**North Dakota.** (1) Approved high school course or its equivalent; (2) three years' practical experience in the office of a reputable architect; (3)

\* The names of the executive officers, Secretaries of the Boards, etc., are omitted here, as the personnel is constantly changing.

amination or a license from another state board whose standard equals that of this board or membership in the American Institute of Architects; (4) with the secretary of state and annually with the board; Secretary, State Board of Architecture, Bismarck.

**South Carolina.** (1) None; (2) at least two years' experience in architectural work; (3) examination or graduation from an approved school of architecture; (4) with the board, annually; (5) Secretary, State Board of Architectural Examiners, Columbia.

**Utah.** (1) None; (2) none; (3) examination; (4) with the board, annually; (5) Secretary, State Board of Architecture.

**Wisconsin.** (1) None; (2) at least five years' practical experience in the office of a reputable architect; (3) examination or a satisfactory certificate from a recognized architectural school with three years' experience or registration with the board of another state or country whose standards are not lower than those of this board; (4) with the Industrial Commission; (5) Secretary of the Board of Examiners of Architects, Madison.

## EDUCATIONAL INSTITUTIONS IN THE UNITED STATES AND CANADA OFFERING COURSES IN ARCHITECTURE. TRAVELLING FELLOWSHIPS AND SCHOLARSHIPS

### 1. Association of Collegiate Schools of Architecture

**Association of Collegiate Schools of Architecture.** Organized in 1912 to advance the standards of architectural education in the United States. Membership (1921) represents fifteen architectural schools in Columbia, Cornell, Harvard, Syracuse, Yale, and Washington Universities; the Universities of California, Illinois, Kansas, Michigan, Minnesota, Oregon and Pennsylvania, and the Carnegie and Massachusetts Institutes of Technology. (Officers 1921: President Emil Lorch; Vice-President, William Emerson; Secretary-Treasurer, Lawrence A. Martin, Cornell University, Ithaca, N. Y. The Association requires for the admission of an institution to membership the attainment of certain MINIMUM CONDITIONS in its course in architecture, a detailed list of which will be furnished upon application to the secretary. They are here broadly summarized as follows: (1) Collegiate rating under the Carnegie Foundation; (2) A course of at least 120 CREDIT-HOURS of both general and professional studies of certain minimum range and approved method of presentation, leading to a degree not less than BACCALAUREATE; (3) Such character of staff and administration, standing of course and adequacy of equipment as will reasonably assure quality of performance; (4) A demonstration of success in operation through a period of at least four years. The Association holds an annual conference on architectural education to which representatives of all American schools are welcomed.

### 2. Educational Institutions, Fellowships, and Scholarships

**Academy of Architecture and Industrial Science, St. Louis, Mo.** This is a private school founded by Mr. Maack in 1885, and designed more particularly to meet the wants of building tradesmen, offering them such instruction as is necessary to attain the highest proficiency in their trade and a thorough

understanding of the plans and details of complicated buildings. There is also a special course for those desiring to fit themselves for positions as draughtsmen in architects' offices. Tuition for the regular course is \$50 for a three months' term, or \$300 for the full course of eight terms, or \$100 for the year. Several special courses with varying tuition.

**Alabama Polytechnic Institute, Auburn, Ala.** DEPARTMENT OF ARCHITECTURE. (1) Full four-year course leading to the degree of Bachelor of Science in Architecture. (2) Full four-year course leading to the degree of Bachelor of Science in Architectural Engineering. (3) Two-year special course for draftsmen and college graduates. Tuition free to residents of Alabama; \$20 per year for others. About two dozen LOAN-SCHOLARSHIPS of \$100 or more per annum. Limited number of FELLOWSHIPS of \$250 for post-graduates. Illustrated Announcement giving details, sent on request.

**American Academy in Rome, Fellowship in Architecture.** ROMAN PRIZE. The fellowship is awarded annually and is of the value of \$1,000 a year for three years. The award is made on competitions which are open only to unmarried male citizens of the United States, who comply with the regulations of the Academy. Candidates are required to be (1) graduates of one of the architectural schools included in the accepted list of the Academy; or (2) graduates of a college or university of high standing who hold certificates of at least two years' study in one of such architectural schools; or (3) Americans who are pupils of the first class of the School of Fine Arts at Paris, and who have obtained at least three values in that class. There is no age-limit. Information as to the terms and conditions of the competitions may be obtained from the Secretary of the Academy, 101 Park Avenue, New York City.

**American School of Correspondence, Chicago, Ill.** Correspondence courses in Architecture, Architectural Engineering, Contracting and Building, Reinforced Concrete, Architectural Design, and Structural Draughting. Bulletin sent on application.

**Armour Institute of Technology, Chicago, Ill.** Full four-year course leading to the degree of Bachelor of Science in Architecture. Applicants for admission must have completed the regular four-year high-school course. A HOME TRAVELING-SCHOLARSHIP, four prizes, and a medal are awarded annually. Tuition, \$180 per year.

**Beaux Arts Institute of Design, 126 East 75th Street, New York, N. Y.** DEPARTMENT OF ARCHITECTURE. (Address all communications to this department.) The course, established in 1893, consists (1920) of a series of thirty-five competitions, issued annually, for the study of architectural design and the style of architecture, open to the draughtsmen and students in architectural schools in the United States and Canada, and modeled on the system of instruction adopted by the École des Beaux Arts in Paris. The course is free, except for the annual fee of \$2 for registration of each student. There are no restrictions as to the age, nationality, or sex of the students. No preliminary examinations are given, but new students are expected to have a knowledge of the five orders of architecture. BRONZE AND SILVER MEDALS are awarded for excellence in design and money-prizes are offered in special prizes for decoration, group-planning of buildings, etc. CERTIFICATES are presented to all students of Class A completing the course as defined in the circular of information, which is furnished on request. During the season 1917-1918 the work was carried on by one hundred and eleven correspondents of the Institute in eighty-eight different cities, with a total of seven hundred and seventy-four students.

DEPARTMENT OF INTERIOR DECORATION (Address all communications to the

partment): The course consists of programmes for competitions issued every six weeks to those who apply for them. These may be executed by students situated in any locality and sent in to the Institute where they will be criticized and judged on fixed dates by a jury of experts. BRONZE AND SILVER MEDALS are awarded for excellence. An atelier for male students under the instruction of several decorators exists in the building of the Institute. There are no fees of any kind. No formalities or examinations are necessary for admission to the atelier. A circular is furnished on request.

**DEPARTMENT OF SCULPTURE.** (Address all communications to this department.) Ateliers for male students for each one of the three courses (Architectural Ornament, Life Drawing, and Modeling and Composition) exist in the building of the Institute. No examinations, formalities, or fees of any kind. Open all day all the year round. Instructors visit their classes twice a week. Judgments by expert juries every four weeks on work of preceding month. BRONZE AND SILVER MEDALS awarded. Circular furnished.

**DEPARTMENT OF MURAL PAINTING.** (Address all communications to this department.) The course consists of problems, programmes of which are issued every month to those who apply for them. Judgments by a jury of artists every month on the designs handed in. BRONZE AND SILVER MEDALS awarded. No examinations, formalities, or fees of any kind. No atelier in this department at the Institute. Students work up their problems under their own instructors wherever they may be situated. Circular furnished.

**BEAUX ARTS ARCHITECTS, SOCIETY OF.** 126 EAST 75TH STREET, NEW YORK, N. Y. The course in Architectural Design established in 1893 and formerly conducted by the Committee on Education of this Society, is now carried on by the Beaux Arts Institute of Design. (See Beaux Arts Institute Design.)

**PARIS PRIZE.** THIS SCHOLARSHIP-PRIZE is usually conducted annually by the Society of Beaux Arts Architects. Under its conditions the winner receives \$1 200, per annum for two years and a half, to study architecture in Paris at the Ecole des Beaux Arts, into the upper class of which he is received without further examinations. The competition beginning January 10th, 1920, for this scholarship consisted of two preliminaries and one final competition and was open to all male citizens of the United States under thirty-two years of age on July 1st, 1920. A circular is furnished on request.

**Carnegie Institute of Technology, Pittsburgh, Pa. DIVISION OF THE ARTS; SCHOOL OF ARCHITECTURE.** (1) A complete course in architecture for day-students for which the degree of Bachelor of Architecture in Design is awarded those specializing in design and allied subjects (Option 1), and the degree of Bachelor of Architecture in Construction to those in construction and allied subjects (Option 2). From four to five years are required for the completion of prescribed work. (2) For graduate day-students a course of advanced studies in design and allied subjects, scheduled to cover one year, and leading to the degree of Master of Arts. (3) A partial day-course, scheduled to cover two years, for experienced draughtsmen and designers, for which a certificate of proficiency is awarded. (4) A course for night-students for which a Certificate of Proficiency is awarded. This course includes the same work as is required of day-students in design, freehand drawing and modeling. Tuition: For day-school, \$75; for night-school, \$20 per year.

**Catholic University of America, Washington, D. C.**

**Clemson Agricultural College of South Carolina, Clemson College, S. C.**

**Columbia University, New York, N. Y. SCHOOL OF ARCHITECTURE.**  
(1) Full four-year course leading to the degree of Bachelor of Architecture.

Receives only students with at least two years of college training. In connection with Columbia College, there is a six-year course giving the degree of A.B., at the end of four years and B.Arch. at the end of six years. Advanced courses leading to the degree of Master of Science in Architecture. Tuition \$6 per "tuition-point," totaling about \$250 per year. There are TRAVELING-FELLOWSHIPS, awarded as follows: One is available each year with a stipend of about \$1 500; the MCKIM FELLOWSHIP every third year beginning 1916-17; the SCHERMERHORN FELLOWSHIP, every third year, beginning 1918-19; and the PERKINS FELLOWSHIP, every third year, beginning 1920-21. Each of these requires the winner to devote one year to foreign travel and study.

EXTENSION-TEACHING, evening and afternoon courses. A course leading to a Certificate of Proficiency in Architecture is offered. This covers roughly six years, depending on how much is taken each year. Equivalent of day-course in instruction. Tuition, \$6 per "tuition-point," each course having a stated point-value. Graduation accepted in lieu of examinations for state license. There are Special Students, also, under Extension-Teaching who select their own course of study in subjects for which they are qualified. All information may be obtained from the Curator.

Cornell University, Ithaca, N. Y., COLLEGE OF ARCHITECTURE. (1) Four-year general course in architecture, leading to the degree of Bachelor of Architecture, and a similar course with engineering electives, leading to the degree of Bachelor of Science in Architecture. (2) Five-year courses in architecture, the same as the above, but with additional work in the arts and sciences leading to the same degrees. (3) Six-year courses in arts and sciences and architecture, or in engineering and architecture, leading to the degrees of A.B. and B.Arch., or C.E. and B.S.Arch. (4) A two-year special course in architecture, leading to a certificate. (5) Graduate courses in architecture, leading to the degree of Master of Architecture. Tuition, \$200 a year.

George Washington University, Washington, D. C. DEPARTMENT OF ARTS AND SCIENCES. Course in Architecture. Four-year course in architecture, leading to the degree of Bachelor of Science in Architecture. Courses of instruction open to qualified special students, without reference to any degree. Full tuition \$180; part-time students pay \$6 for each semester-hour credit.

Georgia School of Technology, Atlanta, Ga. DEPARTMENT OF ARCHITECTURE. (1) Full four-year course leading to the degree of Bachelor of Science in Architecture. (2) Two-year special course leading to a certificate of proficiency. Tuition, \$25 per year for residents of Georgia; \$100 for non-residents. The Georgia Chapter of the American Institute of Architects has provided a loan-fund in this department for one or two students needing assistance.

Harvard University, Faculty of Architecture, Cambridge, Mass. SCHOOL OF ARCHITECTURE. Professional training in architecture. (1) Open to graduates of colleges, scientific schools and professional schools of good standing, leading to the degree of Master in Architecture, or Master in Architectural Engineering. Length of period of study for men with professional preparation, commonly three years, depending on ability and previous training. (2) Open to competent special students, who must be over twenty-one years of age, and must have had at least three years of office experience; admitted to special course leading to certificate. Tuition \$300 per year.

Howard University, Washington, D. C.



**SCHOOL OF LANDSCAPE-ARCHITECTURE.** (1) Professional training in landscape-architecture, open to graduates of colleges and technical schools of good standing, leading to the degree of Master in Landscape-Architecture. (2) Special students admitted to courses for which their training fits them. Tuition, \$200. **TWO TRAVELING-FELLOWSHIPS**, the **JULIA AMORY APPLETON** and the **ROBINSON**, are offered for competition in alternate years, each having an annual value of \$1 100, tenable for two years, for travel and study in Europe under the direction of the School of Architecture. The **CHARLES ELIOT FELLOWSHIP IN LANDSCAPE-ARCHITECTURE** (stipend \$1 100) is offered for travel and study in landscape-architecture, under the direction of the School of Landscape-architecture. These fellowships are open for competition to graduates in architecture and in landscape-architecture, respectively.

**RESIDENT SCHOLARSHIPS.** **TWO AUSTIN SCHOLARSHIPS IN ARCHITECTURE** and **in LANDSCAPE-ARCHITECTURE**, annual value, \$350. The **CUMMINGS SCHOLARSHIP IN LANDSCAPE-ARCHITECTURE**, annual value, \$350. One **EVELETH SCHOLARSHIP IN ARCHITECTURE**, annual value, \$250. Three **SCHOLARSHIPS** **SPECIAL STUDENTS IN ARCHITECTURE**, open to competition to properly qualified draughtsmen, annual value, \$200. **SIX UNIVERSITY SCHOLARSHIPS** open to regular students in Architecture or Landscape-Architecture, annual value, \$50. Other scholarships available to candidates of special claims as to residence, college, or descent.

**International Correspondence Schools, Scranton, Pa.** A corporation organized to furnish instruction by correspondence and to hold examinations to establish proficiency. The architectural course is designed particularly to meet the wants of those already engaged in the building trades or drafting-room. It includes sixty-one subjects covering the elements of building-construction, masonry, carpentry, plumbing, etc., and the principles of design, drawing, lettering, and specification-writing. The tuition includes text-books and instruction, that is, criticisms on written lessons, sent to the schools, and also answers to questions on subjects connected with the course, that may be asked by the students. Information regarding fees can be obtained on inquiry. Other courses are available for building-contractors, building-foremen, and for special courses in structural engineering.

**Iowa State College of Agriculture and Mechanic Arts, Ames, Iowa.**

**Kansas State Agricultural College of, Manhattan, Kan.** **DEPARTMENT OF ARCHITECTURE.** Full four-year course in architecture, leading to a degree in Bachelor of Science. Tuition free to residents of the state. Incidental fees amount to about \$12 a semester.

**Massachusetts Institute of Technology, Boston, Mass.** Two four-year courses are offered in architecture, leading to the degree of Bachelor of Science: (1) Course in general architecture; (2) Course in architectural engineering. Opportunities are offered in each course for advanced professional work leading to the degree in (1) of Master in Architecture and in (2) of Master of Science. Special students must be college-graduates, or twenty-one years of age, with not less than two years of office-experience. In all cases they must demonstrate fitness for the work of the department by personal conference with the head of the department, or his representative, and by the presentation of letters from former employers, together with drawings covering their experience fully as possible. All special students must take in their first year of residence the Institute courses in descriptive geometry and mechanical drawing, unless the subjects have been passed at the September examinations for advanced standing, or excuse from one or both has been obtained on the basis of equivalent

work accomplished elsewhere. Tuition, \$250 per year. An ANNUAL TRAVEL FELLOWSHIP amounting to \$1 000 is given solely on the basis of distinguished merit, candidates being received from both regular and special students. Prizes, varying from \$10 to \$200 each, are equally divided between the regular and the special students. Certain funds are available for the assistance of qualified regular students for undergraduate and for post-graduate work.

**McGill University, Montreal, Canada. DEPARTMENT OF ARCHITECTURE.** (1) Full five-year course leading to the degree of Bachelor of Architecture. (2) Competent special students are admitted to take a partial course, but a university certificate is granted for this work. Tuition, \$150 per year.

**North Dakota Agricultural College, Fargo, N. D. DEPARTMENT OF ARCHITECTURE AND ENGINEERING.** Draughtsmen's and builders' course of three years (six months each). Full four-year course in architecture, leading to Bachelor of Science in Architecture. Full four-year course in Architectural Engineering, leading to Bachelor of Science in Architectural Engineering. Tuition free. Expenses amounting to \$35 per year.

**Ohio Mechanics' Institute, Cincinnati, Ohio. DEPARTMENT OF ARCHITECTURE.** Technical high-school course preparatory to architecture, continuing four years. Two-year intensive course in architecture. Evening department in architectural drawing and allied building-trade subjects. Graduates of grammar-schools are trained in draughting and elementary architectural subjects simultaneously with their high-school subjects. Graduates of high schools are trained intensively in technical architectural work, including collegiate mathematics and sciences, and receive a Certificate of Proficiency in Architecture. Tuition, \$75 per year.

**Ohio State University, Columbus, Ohio. COURSE IN ARCHITECTURE.** Two four-year courses, leading to the degrees of Bachelor of Architecture and Bachelor of Architectural Engineering. Tuition free.

**Oklahoma Agricultural and Mechanical College, Stillwater, Okla. DEPARTMENTS OF ARCHITECTURE AND ARCHITECTURAL ENGINEERING.** Four-year course in Architecture and Architectural Engineering, leading to a degree of Bachelor of Science. Two-year special course for draftsmen, leading to a certificate of completion in this work. Tuition free. The registration fee is \$2 a semester.

**Pennsylvania State College, State College, Pa. Course in Architectural Engineering.** Full four-year course, leading to the degree of Bachelor of Science in Architectural Engineering. Tuition is free. Incidental expenses amount to about \$30 per semester, these fees including the college fees. A course in architectural design.

**Pratt Institute, Brooklyn, N. Y. Course in Architecture. SCHOOL OF FINE AND APPLIED ARTS.** (1) Two-year course in architectural design. (2) Two-year course in architectural construction. (3) Full three-year course in architectural design and architectural construction. The course in architectural design aims to give students a general training that will prepare them to pursue the profession of architecture as competent assistants in architect's offices, and leads to positions of responsibility and independence. The course in architectural construction aims to fit the student for general draughting, builders' offices, or for general detailing and construction-work in an architect's office, and leads to the position of superintendent of construction-work. Tuition, \$80 per year.

**Princeton University, Princeton, N. J. SCHOOL OF ARCHITECTURE.**

courses in Architecture: (1) For students enrolled as candidates for degree of Bachelor of Arts on graduation and for the degree of Master of Arts in Architecture after two years of graduate work. (2) For students have not begun the study of architecture in the sophomore year, but wish to receive the degree of Bachelor of Arts on graduation and the degree Master of Fine Arts in Architecture after two years of graduate work. For students entering the School as candidates for the degree of Master of Arts in Architecture without previous study in architecture. For the average student, three years and a half are required for this course. Tuition, a year for students on full time, and \$40 for those on part time. Annual \$15. The GRADUATE FELLOWSHIP AND SCHOLARSHIPS of the University open to members of the School. They are over fifty in number, and range from \$150 to \$1 000 per annum.

ce Institute, Houston, Tex. ARCHITECTURAL DEPARTMENT. Full year course leading to the degree of Bachelor of Science in Architecture. on free.

chester Athenaeum and Mechanics Institute, Rochester, N. Y. DEPARTMENT OF APPLIED ARTS. Three-year courses in Architectural Drawing Design, and Architectural Construction, leading to Diplomas. There also courses for properly prepared students who do not wish to take the full courses. Tuition for full courses, \$90 per year; for part-time students, per term of twelve weeks for one session per week.

se Polytechnic Institute, Terre Haute, Ind. DEPARTMENT OF ARCHITECTURAL ENGINEERING. Full four-year course, designed to give a thorough training in architectural engineering, together with systematic instruction in architectural design. Tuition and incidental fees, \$110.

Arch Traveling-Scholarship, Inc. (For particulars address the Secretary, Beacon Street, Boston, Mass.) Candidates must be under thirty years of age at the date of the beginning of the preliminary examinations. At that time they must have been engaged in professional work during two years in Massachusetts in the employ of a practicing architect resident in Massachusetts, and will be required to pass preliminary examinations upon the following subjects: (1) History of architecture; (2) Freehand drawing from the imagination; (3) Construction, theory and practice; (4) An elementary knowledge of the French language. Holders of a degree in Architecture from the Massachusetts Institute of Technology, Columbia University, University of Pennsylvania, Cornell University, Harvard University, or University of Illinois will be allowed to present such diploma which will be accepted in lieu of the preliminary examinations in the preliminaries. Candidates who pass in these preliminary examinations are admitted to a competition in design, the successful candidate in which is awarded the scholarship and receives annually, for two years, \$1 400, to be expended in foreign travel and study. The Boston Society of Architects, through a committee, has complete charge of the examinations, and supervises the work of the scholar. The Society of Architects awards a sum of \$75 as a second prize.

Syracuse University, Syracuse, N. Y., College of Fine Arts. DEPARTMENT OF ARCHITECTURE. This school offers: Four-year courses in (1) Architecture, (2) Architectural Design, (3) Architectural Engineering, all leading to the degree of Bachelor of Architecture (B.Ar.); (4) Special two-year course for architectural draughtsmen of two or more years' experience; (5) Graduate work in architecture; (6) Interior architectural design and decoration.

Tuition, \$150 per year. Bulletins and full information available from Registrar.

**Texas. Agricultural and Mechanical College of Texas, College Station, Tex.** DEPARTMENT OF ARCHITECTURE. Four-year course in architecture offering an option through the junior and senior years in architectural engineering. Qualified special students admitted. Tuition free.

**Tulane University of Louisiana, New Orleans, La.** DEPARTMENT OF ARCHITECTURE IN THE COLLEGE OF TECHNOLOGY. (1) Full four-year course leading to a degree in architecture. (2) Special courses for students not candidates for a degree. Tuition, \$100 per year. Special attention given to subtropical conditions.

**University of California, Berkeley, Cal.** SCHOOL OF ARCHITECTURE. (1) Full four-year course leading to the degree of Bachelor of Arts. (2) Two-year graduate course leading to the degree of Master of Arts. (3) Two-year graduate course leading to the degree of Graduate in Architecture. (4) Special elective courses for students not candidates for a degree. Tuition free for residents of the state of California.

**University of Illinois, Urbana, Ill.** COURSES IN ARCHITECTURE AND ARCHITECTURAL ENGINEERING. (1) Full four-year course leading to the degree of Bachelor of Science in Architecture. (2) Full four-year course leading to the degree of Bachelor of Science in Architectural Engineering. Tuition is free. Incidental fee, \$30 per year. **PLYM TRAVELING-FELLOWSHIP** \$1 000 for one year of travel abroad; awarded by competition to graduates of the Department of Architecture of the University of Illinois.

**University of Kansas, Lawrence, Kan.** DEPARTMENT OF ARCHITECTURE AND ARCHITECTURAL ENGINEERING. Full four-year course in Architecture leading to the degree of Bachelor of Science in Architecture. Full four-year course in Architectural Engineering, leading to the degree of Bachelor of Science in Architectural Engineering. Four-year courses in each, based on one year in the College of Liberal Arts, leading to the degree of Bachelor of Science. Tuition free. Fees amounting to \$15 per year for residents of the state; \$25 per year for non-residents.

**University of Michigan, Ann Arbor, Mich.** COLLEGE OF ARCHITECTURE. (1) A general four-year course leading to the degree of Bachelor of Science in Architecture. (2) A four-year course in which architectural design is emphasized, leading to the same degree. (3) A four-year course in which there is a large proportion of engineering subjects, leading to the degree of Bachelor of Science in Architectural Engineering. (4) Five-year courses leading to the degrees of Master of Science in Architecture and Master of Science in Architectural Engineering. (5) A two-year course, leading to a Certificate, for special students (experienced draughtsmen or college-graduates). (6) Students may earn the degree of Bachelor of Arts and the degree in Architecture in five to six years. There are TWO SCHOLARSHIPS. Annual fees, \$57 for students from Michigan and \$87 for others.

**University of Minnesota, Minneapolis, Minn.** DEPARTMENT OF ARCHITECTURE. Full four-year course, leading to the degree of Bachelor of Science in Architecture. Fifth year, leading to the degree of Master of Science in Architecture. Special students of maturity and practical experience admitted. Instruction is provided in Architectural Engineering. Tuition free. Incidental fee, \$60 per year.

**University of Nebraska, Lincoln, Neb.** COLLEGE OF ENGINEERING

**Four-year course in architectural engineering, leading to Bachelor of Science in Architectural Engineering. Tuition free. Total fees for four years, \$110.**

**University of Notre Dame, Notre Dame, Ind. DEPARTMENT OF ARCHITECTURE. (1) Full four-year course in design leading to the degree of Bachelor of Science in Architecture. (2) Full four-year course in architectural engineering leading to the degree of Bachelor of Science in Architectural Engineering. Two-year special course leading to a Certificate of Proficiency. Tuition, per year; room \$60 and upwards; board, \$180 and upwards.**

**University of Oregon, Eugene, Ore. SCHOOL OF ARCHITECTURE AND FINE ARTS. Two architectural options in design and structural work. Four-year course leading to the degree of Bachelor in Architecture. Five-year course leading to the degree of Master in Architecture. (3) Extension-courses in Portland, Ore., in design, etc. (4) Special courses for experienced draughtsmen. Tuition free for university-courses; \$5 a term for design-courses.**

**University of Pennsylvania, Philadelphia, Pa. SCHOOL OF FINE ARTS, DEPARTMENT OF ARCHITECTURE. (1) Four-year course leading to the degree of Bachelor of Architecture. (2) Graduate course of one year, with choice between major subjects, leading to the degree of Master of Architecture. Two-year special course leading to a professional certificate. (4) Six-year arrangement of courses in liberal arts and architecture leading to the degrees of A. B. and also B. Arch. (5) Option in Architectural Engineering leading to the degree of Bachelor of Architecture. Summer school providing instruction in any architectural subjects of the regular session. The degree and certificate accepted by the American Institute of Architects in satisfaction of its educational requirements for membership and are credited by State Boards for licensing of architects. Tuition \$300 per year. Circular, including information on all courses in the School of Fine Arts, on application to the Dean of the School of Fine Arts, University of Pennsylvania, Philadelphia, Pa.**

**THE WOODMAN SCHOLARSHIP IN ARCHITECTURE of the University of Pennsylvania, for one year of foreign travel and study, is open to graduates of this school, they being also eligible to the general competition for the FELLOWSHIP OF THE AMERICAN ACADEMY IN ROME. The PARIS PRIZE OF THE BEAUX-ARTS INSTITUTE OF DESIGN is open to seniors and graduates and the STEWARDSON TRAVELING-SCHOLARSHIP is available to students who are residents of Pennsylvania. The MEDALS OF THE AMERICAN INSTITUTE OF ARCHITECTS and the MÉDAILLES DES ARCHITECTES DIPLÔMÉS are conferred in this school as well as OTHER MEDALS AND PRIZES open to its students alone.**

**University of Santa Clara, Santa Clara, Cal.**

**University of Southern California, Los Angeles, Cal. Four-year general course in architecture, leading to the degree of B.S. in Architecture.**

**University of Texas, Austin, Tex. SCHOOL OF ARCHITECTURE. (1) Four- and five-year courses leading, respectively, to the degrees of Bachelor of Science in Architecture, and Master of Science in Architecture. (2) Four-year course leading to the degree of Bachelor of Science in Architectural Engineering. Tuition free.**

**University of Toronto, Toronto, Canada. DEPARTMENT OF ARCHITECTURE. Full four-year course leading to the degree of Bachelor of Applied Science (B.A.Sc.) with an option of architectural engineering, replacing architectural design in the fourth year. The fees are, first year, \$100; second year, \$100; third and fourth years, \$120. The university is supported by the Province of Ontario.**

**University of Virginia. McINTIRE SCHOOL OF FINE ARTS.** Four-year course in architecture, leading to the degree of Bachelor of Science in Architecture. Annual average of tuition and laboratory fees: For non-Virginians, \$180; for Virginians, \$75.

**University of Washington, Seattle, Wash. COURSE IN ARCHITECTURE.** Four-year course, leading to the degree of Bachelor of Architecture. There is a fourth-year option in architectural engineering. Tuition, \$20 per year. Entrance fee, \$10; graduation fee, \$5.

**Washington, The State College of, Pullman, Wash. DEPARTMENT OF ARCHITECTURE.** (1) Full four-year course leading to the degree of Bachelor of Science in Architecture. (2) Two-year special course leading to a Certificate of Proficiency. (3) Special students, adequately prepared, are admitted to the classes. Tuition free.

**Washington University, St. Louis, Mo. SCHOOL OF ARCHITECTURE.** (1) Four-year courses in architecture and in architectural engineering leading to the degrees of Bachelor of Architecture, and Bachelor of Science in Architectural Engineering, respectively. (2) One-year course leading to the degree of Master of Architecture. (3) Special two-year course with Certificate of Proficiency. Tuition, \$150 per year.

**Wentworth Institute, Boston, Mass.** Courses in architectural construction, carpentry and building, and twelve other technical trades or industries. (1) Two-year course in architectural construction trains for positions of foremen, superintendents, detail-designers, etc. Tuition, \$54 per year and \$15 laboratory fee. (2) One-year course in carpentry and building plans for those wishing to enter the wood-working-trades and industries as advanced apprentices or high-grade artisans. Tuition \$30 per year and \$15 laboratory fee.

**Yale University, New Haven, Conn. DEPARTMENT OF ARCHITECTURE.** Regular course covers four years. Special degree, Bachelor of Fine Arts, may be competed for at end of course. Portions of the first-year's work, including lectures on history of chief styles of architecture and principles of composition, and practice in elementary design, may be taken as electives by juniors and seniors in the academic course. ALICE KIMBALL ENGLISH SCHOLARSHIP, supported from fund of \$11 000, for a year's travel abroad. WILLIAM WIRT CHESTER SCHOLARSHIP, supported from fund of \$20 000, for a year's travel abroad. Tuition, \$180 per year.

## ARCHITECTURAL SOCIETIES AND ORGANIZATIONS OF THE WORLD

### 1. United States

#### (1) THE AMERICAN INSTITUTE OF ARCHITECTS

The Octagon, Washington, D. C.

#### LIST OF CHAPTERS (1923) OF THE THE AMERICAN INSTITUTE OF ARCHITECTS

The year indicates the date of the chapter's organization

Alabama Chapter. 1916	Central New York Chapter. 1887
Baltimore Chapter. 1870	Cincinnati Chapter. 1870
Boston Chapter. 1870	Cleveland Chapter. 1890
Brooklyn Chapter. 1894	Colorado Chapter. 1892.
Buffalo Chapter. 1890	Columbus (Ohio) Chapter. 1913

Connecticut Chapter. 1902	Philadelphia Chapter. 1869
Con Chapter. 1899	Pittsburgh Chapter. 1891
Dakota Chapter. 1906	Rhode Island Chapter. 1875
Delaware Chapter. 1869	St. Louis Chapter. 1890
Florida Chapter. 1903	San Francisco Chapter. 1881
Gas City Chapter. 1890	South Carolina Chapter. 1913
Idaho Chapter. 1908	Southern California Chapter. 1894
Illiana Chapter. 1910	Southern Pennsylvania Chapter. 1909
Illigan Chapter. 1887	Tennessee Chapter. 1919
Minnesota Chapter. 1892	Texas Chapter. 1913
Nebraska Chapter. 1919	Toledo Chapter. 1914
New Jersey Chapter. 1900	Virginia Chapter. 1914
New York Chapter. 1867	Washington (D. C.) Chapter. 1887
North Carolina Chapter. 1913	Washington State Chapter. 1894
Ohio Chapter. 1911	Wisconsin Chapter. 1911

These chapters were organized since 1920: Arkansas, Central Illinois, Erie, Florida, Kansas, Kansas State, Montana, St. Paul, Scranton-Wilkesbarre, South Georgia, and

#### OF STATE ASSOCIATIONS OF THE AMERICAN INSTITUTE OF ARCHITECTS

New York State Society of Architects. 1919  
 State Association. 1915  
 Pennsylvania State Association. 1909

#### (2) MISCELLANEOUS SOCIETIES \*

American Society of Landscape Architects  
 Architects' Association of Indianapolis  
 Architectural Club of Minneapolis  
 Architectural League of Pacific Coast  
 Architectural League of New York  
 Architectural Society of the University of California  
 Architectural Society of the University of Pennsylvania  
 Association of Collegiate Schools of Architecture  
 Astoria Architectural Club  
 Birmingham Society of Architects  
 Boston Architectural Club  
 Boston Society of Architects  
 Brooklyn Institute of Arts and Sciences  
 Chicago Architects' Business Association  
 Chicago Architectural Club  
 Chicago Association of Architects  
 Cincinnati Architectural Club  
 Cleveland Architectural Club  
 Columbus Society of Architects  
 Detroit Architectural Club  
 Durham Architectural Club  
 Engineers' and Architects' Club of Louisville, Ky.  
 Florida Association of Architects  
 Boyle Club of St. Paul  
 Georgia Architectural Association  
 Indianapolis Architectural Club  
 Kansas State Architects' Association

Reproduced by permission from the Architects' Directory and Specification Index,  
 published by The William T. Comstock Company, New York City.  
 Changes are necessarily made in these lists from time to time.

Los Angeles Architectural Club  
 Massachusetts Institute of Technology Architectural Association  
 Minneapolis Architectural Club  
 Minneapolis Society of Architects  
 New Orleans Architectural Club  
 New York Society of Architects  
 Norfolk Society of Architects  
 North Carolina Architectural Association  
 Oakland Architects' Association  
 Oakland Architectural Club  
 Oklahoma State Association of Architects  
 Pittsburgh Architectural Club  
 Portland, Oregon, Architectural Club  
 Portland, Oregon, Association of Architects  
 St. Joseph, Missouri, Society of Architects  
 St. Louis Architectural Club  
 St. Paul Architectural Club  
 San Antonio Society of Architects  
 San Diego Architectural Association  
 San Francisco Architectural Club  
 Society of Architects of Akron, Ohio  
 Society of Architects of Columbia University  
 Society of Beaux-Arts Architects  
 Society of Naval Architects and Marine Engineers  
 South Bend Architectural Club  
 South Carolina Association of Architects  
 Southern States Engineering Society  
 Spokane Architectural Club  
 T Square Club of Philadelphia  
 Tacoma Society of Architects  
 Texas State Association of Architects  
 Utah Association of Architects  
 Washington, D. C., Architectural Club

## 2. Argentine Republic

Sociedad Central de Arquitectos. Buenos Aires

## 3. Austria

Austrian Society of Civil Engineers and Architects. Vienna  
 Architekten-Klub der Wiener Kunstlergenossenschaft. Vienna  
 Gesellschaft Österreichischer Architekten. Vienna  
 Wiener Bauhütte. Vienna  
 Towarzystwo Politechniczne we Lwowie. Leopold  
 Towarzystwo Techniczne we Krakowie. Cracow

## 4. Belgium

Association des Architectes, de Liège. Liège  
 Société Centrale D'Architecture de Belgique. Brussels  
 Société Royale des Architectes D'Anvers. Antwerp  
 Kring Voor Bouwhunde D'Anvers. Antwerp  
 Chambre Syndicale des Architectes de Bruxelles. Brussels



ciation des Architectes de Bruxelles. Brussels  
 ité des Architectes de la Flandre Orientale. Ghent  
 ité des Architectes de la Flandre Orientale. Bruges

### 5. Bulgaria

ité des Ingénieurs et des Architectes Bulgares. Sofia

### 6. Canada

#### ARCHITECTURAL ASSOCIATION OF CANADA

ral Architectural Institute of Canada. Montreal  
 erta Association of Architects. Calgary and Edmonton, Alta.  
 hitects' Association of Victoria. Victoria, B. C.  
 ish Columbia Association of Architects.  
 gary Architectural Club  
 nitoba Association of Architects. Winnipeg, Man.  
 ario Association of Architects. Toronto  
 vince of Quebec Association of Architects. Montreal  
 gina Architectural Association. Regina, Sask.  
 katchewan Association of Architects. Regina, Sask.

### 7. Cuba

ety of Engineers and Architects of Havana. Havana

### 8. France

manent Committee of International Congresses of Architects. Paris  
 iété des Architectes Diplômés par le Gouvernement. Paris.  
 iété Nationale des Architectes de France. Paris.  
 iété Centrale des Architectes Français. Paris  
 ion Syndicale des Architectes Français. Paris  
 iété des Diplômés de l'École Spéciale d'Architecture. Paris  
 ociation Provinciale des Architectes Français. Versailles  
 iété Régionale des Architectes du Centre de la France. Bourges  
 iété Regionale des Architectes de Dauphiné et de la Savoie. Grenoble  
 iété des Architectes de l'Est de la France. Nancy  
 iété Régionale des Architectes du Limousin, de l'Angoulême et du Perigord.  
 Guéret (Creuse)  
 iété Régionale des Architectes du Midi. Toulouse  
 iété Régionale des Architectes du Nord. Lille  
 iété Régionale des Architectes du Poitou et de la Saintonge. Parthenay  
 iété Régionale des Architectes du Puy-de-Dôme, du Cantal, de la Haute-  
 Loire et de l'Allier. Clermont-Ferrand  
 iété Régionale des Architectes de Saône-et-Loire, de l'Ain et du Jura. Châ-  
 lons-sur-Saône  
 ociation Régionale des Architectes du Sud-Est. Nice  
 iété des Architectes de l'Aisne. St. Quentin  
 iété des Architectes de l'Allier. Moulins  
 iété des Architectes de l'Anjou. Angers  
 iété des Architectes de l'Aube. Troyes  
 iété des Architectes de Blois. Blois  
 iété des Architectes de Bordeaux et du Sud-Ouest. Bordeaux  
 iété des Architectes des Bouches-du-Rhône. Marseilles

Société des Architectes du Doubs; Besançon  
 Société des Architectes de la Drôme et de l'Ardèche. Valence  
 Société des Architectes d'Eure-et-Loir. Chartres  
 Société Amicale et Syndicat des Architectes du Gard. Nîmes  
 Société des Architectes de la Haute-Marne. Châlons-sur-Marne  
 Société Académique d'Architecture de Lyon. Lyon  
 Société des Architectes de la Marne. Paul-Chandon  
 Société des Architectes de Nantes. Nantes  
 Société des Architectes de l'Oise. Compiègne  
 Société des Architectes d'Orléans. Orléans  
 Société des Architectes de Rennes. Rennes  
 Société des Architectes de la Seine Inférieure et de l'Eure. Rouen  
 Société des Architectes de Seine-et-Marne. Melun  
 Société des Architectes de Seine-et-Oise. Versailles  
 Société des Architectes de la Touraine. Tours  
 Société des Architectes de l'Yonne. Joigny  
 Association Amicale des Architectes. Paris  
 Réunion Amicale des Anciens Élèves de l'Atelier Questel-Pascal. Paris  
 Union Mutuelle des Architectes. Paris  
 Association Provinciale des Architectes Français. Bordeaux  
 Société des Architectes de la Côte-d'Or. Dijon  
 Société des Architectes du Nord-Ouest. Guingamp (Côtes-du-Nord)  
 Société des Architectes de la Loire. Saint-Étienne  
 Société des Architectes du Loiret. Orléans  
 Société des Architectes, Géomètres et Experts de la Lozère. Mende  
 Syndicat des Architectes du Rhône. Villeurbanne  
 Société des Architectes du Havre. Le Havre (Seine-Inférieure)  
 Union Architecturale de Lyon. Lyon  
 Association des Architectes Français. Marseilles  
 Syndicat des Architectes de Basse-Normandie. Caen  
 Société Historique de Compiègne. Compiègne  
 Société d'Assistance Confraternelle des Architectes Français. Versailles

## 9. Germany

Architekten Verein zu Berlin. Berlin. W.  
 Verbund. Deutscher Architekten und Ingenieur Verein. Berlin. S. W.  
 Württembergerischer Verein für Baukunde. Stuttgart  
 Sächsischer Ingenieur und Architekten Verein. Dresden  
 Vereinigung Berliner Architekten. Berlin. W.  
 Architekten und Ingenieur Verein zu Hannover. Hannover  
 Architekten und Ingenieur Verein zu Osnabrück. Osnabrück  
 Architekten und Ingenieur Verein zu Hamburg. Hamburg  
 Architekten und Ingenieur Verein zu Cassel. Cassel  
 Architekten und Ingenieur Verein zu Lübeck. Lübeck  
 Schleswig-Holsteinischer, Architekten und Ingenieur Verein. Kiel  
 Baierischer Architekten und Ingenieur Verein. Munich  
 Architekten und Ingenieur Verein zu Breslau. Breslau  
 Badischer Architekten und Ingenieur Verein. Karlsruhe  
 Architekten und Ingenieur Verein zu Oldenburg. Oldenburg  
 Ostpreussischer Architekten und Ingenieur Verein. Königsberg  
 Frankfurter Architekten und Ingenieur Verein. Frankfurt-on-Main  
 Westpreussischer Architekten und Ingenieur Verein zu Danzig. Danzig  
 Architekten und Ingenieur Verein für Elsass Lothringen. Strassburg

Rheinischer Architekten und Ingenieur Verein. Darmstadt  
 sächsischer Architekten Verein. Dresden  
 Architekten und Ingenieur Verein für Niederrhein und Westfalen. Cologne  
 sächsischer Leipziger Architekten. Leipzig  
 Architekten und Ingenieur Verein für das Herzogtum Braunschweig. Brunswick  
 Architekten und Ingenieur Verein zu Magdeburg. Magdeburg  
 Architekten und Ingenieur Verein zu Bremen. Bremen  
 Architekten und Ingenieur Verein zu Aachen. Aix-la-Chapelle  
 Architekten und Ingenieur Verein zu Metz. Metz  
 Mecklenburgischer Architekten und Ingenieur Verein zu Schwerin, i.M.  
 Schwerin  
 Vereinigung Berliner Architekten. Berlin. W.  
 Architekten und Ingenieur Verein zu Düsseldorf. Düsseldorf  
 Bromberger Architekten und Ingenieur Verein. Bromberg  
 Architekten und Ingenieur Verein zu Münster, i.W. Münster  
 Architekten und Ingenieur Verein zu Potsdam. Potsdam  
 Architekten und Ingenieur Verein zu Stettin. Stettin  
 Architekten und Ingenieur Verein zu Posen. Posen  
 Architekten und Ingenieur Verein zu Erfurt. Erfurt  
 Verein der Architekten und Bauingenieur zu Dortmund. Dortmund  
 Vereinigung Schlesischer Architekten. Breslau  
 Towarzystwo Przyjaciół Nauk. Posen

### 10. Great Britain

Royal Institute of British Architects. London, W.  
 Northern Architectural Association. Newcastle-upon-Tyne  
 Leeds and Yorkshire Architectural Society. Leeds  
 Sheffield Society of Architects and Surveyors. Sheffield  
 Manchester Society of Architects. Manchester  
 Liverpool Architectural Society (Inc.). Liverpool  
 Nottingham Architectural Association. Nottingham  
 Birmingham Architectural Association. Birmingham  
 Leicester and Leicestershire Society of Architects. Leicester  
 Bristol Society of Architects. Bristol  
 Cardiff, South Wales and Monmouth Architects' Society. Cardiff  
 Devon and Exeter Architectural Society. Exeter  
 Glasgow Institute of Architects. Dundee  
 Dundee Institute of Architects. Dundee  
 Aberdeen Society of Architects. Aberdeen  
 Edinburgh Architectural Association. Edinburgh  
 York and Yorkshire Architectural Society. York  
 Royal Institute of Architects of Ireland (Inc.). Dublin  
 Architectural Association of Ireland. Dublin  
 Institute of Architects of New South Wales (Inc.). Sydney  
 Royal Victorian Institute of Architects (Inc.). Melbourne  
 West Australian Institute of Architects (Inc.). Perth  
 Cape Town Institute of Architects. Cape Town, South Africa  
 Transvaal Institute of Architects. Johannesburg. Transvaal, South Africa  
 Natal Institute of Architects. Durban. Natal, South Africa  
 London Architectural Association. London, E.C.  
 Society of Architects, London.

### 11. Greece

Hellenic Polytechnical Society. Athens

### 12. Holland

Society for the Propagation of Architecture. Amsterdam  
Genootschap Architectura et Amicitia. Amsterdam  
Bouwkunst en Vriendschap. Rotterdam

### 13. Hungary

Society of Engineers and of Architects. Budapest  
Magyar Mernok-es Epitesz-Egyelet. Budapest  
Society of Private Architects. Budapest

### 14. Italy

Societa degli Ingegnerie e degli Architetti. Rome  
Associazione Artistica fra i Cultori di Architettura. Rome  
College des Ingenieurs et des Architectes de Gènes. Gènes  
Collegio degli Ingegneri ed Architetti in Palermo. Palermo  
Collegio Toscano degli Ingegneri ed Architetti in Firenze. Florence  
Societa degli Ingegneri di Bologna. Bologna  
Collegio degli Ingegneri ed Architetti di Milano. Milan  
Collegio degli Ingegneri ed Architetti di Torino. Turin  
Collegio degli Ingegneri ed Architetti di Messina  
Collegio degli Ingegneri ed Architetti Puglie. Bari  
Collegio Veneto degli Ingegneri Venezia. Venice

### 15. Japan

Society of Architects. Tokyo

### 16. Norway

Société des Architectes et des Ingenieurs. Christiania

### 17. Portugal

Real Associao dos Architectos Civis e Archeologos Portuguezes. Lisbon  
Sociedad dos Architectos Portuguezes. Lisbon

### 18. Russia

Société Impériale des Architectes Russes. Petrograd  
Société des Architectes de Moscow. Moscow  
Stowarzyszenie Technikow Kolo Architektow. Varsovie

### 19. Spain

Sociedad Centrale de Arquitectos de Madrid. Madrid  
Associacion des Architectes de Cataluna. Bajos  
Associacion des Architectes de Vizcaya. Bilbao  
Associacion des Architectes de Navarra. Pamplona  
Associacion de Arquitectos de Valencia. Valencia  
Associacion de Arquitectos de Galicia. Santiago (Coruna)  
Associacion de Arquitectos de Guipuzcoa. San Sebastian  
Agrupacion Regional Central de Arquitectos de Castilla la Nueva. Madrid

Asociacion Regional de Arquitectos de Castilla la Vieja. Zamora  
Asociacion Regional de Arquitectos de Norte. Bilbao  
Asociacion Regional de Arquitectos de Catalana-Balear. Bajos  
Asociacion Regional de Arquitectos de Andalucia. Cadiz  
Asociacion Regional de Arquitectos de Galicia. Santiago (Coruna)  
Asociacion Regional de Arquitectos de Cantabrico-Leonesa. Santander  
Asociacion Regional de Arquitectos de Aragon. Teruel  
Asociacion Regional de Arquitectos de Levante. Valencia  
Asociacion Regional de Arquitectos de Canarias. Canaries  
Asociacion Regional de Arquitectos de Occidente. Caceres

## 20. Sweden

Sällskapet för Arkitekter och Ingenjörer. Stockholm  
Teknologiska Sällskapet. Stockholm

## 21. Switzerland

Schweizerischer Ingenieur und Architekten Verein. Bâle

## 22. Venezuela

Academia de Arquitectura y Construccion de Venezuela. Caracas

## GLOSSARY \*

## Technical Terms, Ancient and Modern, Used by Architects, Builders, and Draughtsmen

**Aaron's-Rod.** An ornamental figure representing a rod with a serpent twined about it. It is sometimes confounded with the caduceus of Mercury. The distinction between the caduceus and the Aaron's-rod is that the former has two serpents twined in opposite directions, while the latter has but one.

**Abacus.** The upper member of the capital of a column. It is sometimes square and sometimes curved, forming on the plan segments of a circle called the arch of the abacus, and is commonly decorated with a rose or other ornament in the center, having the angles, called horns of the abacus, cut off in the direction of the radius or curve. In the Tuscan or Doric, it is a square tablet; in the Ionic, the edges are molded; in the Corinthian, its sides are concave and frequently enriched with carving. In Gothic pillars it has a great variety of forms.




CORINTHIAN ABACUS

**Abbey.** A term for the church and other buildings used by conventual bodies presided over by an abbot or abbess, in contradistinction to cathedral, which is presided over by a bishop; and priory, the head of which was a prior or prioress.

**Abutment.** That part of a pier from which the arch springs.

**Abuttals.** The boundings of a piece of land on other land, street, river, &c.

**Acanthus.** A plant found in the south of Europe, representations of whose leaves are employed for decorating the Corinthian and Composite capitals. The leaves of the acanthus are used on the bell of the capital, and distinguish the two rich orders from the three others.



ACANTHUS

**Acroteria.** The small pedestals placed on the extremities and apex of a pediment. They are usually without bases or plinths, and were originally intended to receive statues.

**Aile, Aisle.** The wings; inward side porticos of a church; the inward lateral corridors which enclose the choir, the presbytery, and the body of the church along its sides. Any one of the passages in a church or hall into which the people or seats open.

**Alcove.** The original and strict meaning of this word, which is derived from the Spanish *alcoba*, is confined to that part of a bed-chamber in which the bed stands, separated from the other parts of the room by columns or pilasters. It is now commonly used to express any large recess in a room, generally separated by an arch.

**Alipterion.** In ancient Roman architecture, a room used by bathers for anointing themselves.

\* This Glossary was compiled by Mr. Kidder from various sources, and with the exception of some changes in typographical details to make it conform generally to the matter in the rest of the book it is left as published in the preceding editions.

**Almonry.** The place or chamber where alms were distributed to the poor in churches, or other ecclesiastical buildings. At Bishopstone Church, Wiltshire, gland, it is a sort of covered porch attached to the south transept, but not communicating with the interior of the church. At Worcester Cathedral, England, the alms are said to have been distributed on stone tables, on each side, within the great porch. In large monastic establishments, as at Westminster, seems to have been a separate building of some importance, either joining the church-house or near it, that the establishment might be disturbed as little as possible.

**Altar.** In ancient Roman architecture, a place on which offerings or sacrifices were made to the gods. In Protestant churches, the communion table is often designated as the Altar, and in Roman Catholic churches it is a square table placed at the east end of the church for the celebration of mass.

**Altar of Incense.** A small table covered with plates of gold on which was placed the smoking censer in the temple at Jerusalem.

**Altar-piece.** The entire decorations of an altar; a painting placed behind an altar.

**Altar-screen.** The back of the altar from which the canopy was suspended, and separating the choir from the lady chapel and presbytery. The Altar-screen is generally of stone, and composed of the richest tabernacle work of niches, scrolls, and pedestals, supporting statues of the tutelary saints.

**Alto-relievo.** High relief. A sculpture, the figures of which project from the surface on which they are carved.

**Ambo.** A raised platform, a pulpit, a reading-desk, a marble pulpit — an long enclosure in ancient churches, resembling in its uses and positions the modern choir.

**Ambry.** A cupboard or closet, frequently found near the altar in ancient churches to hold sacred utensils.

**Ambulatory.** An alley — a gallery — a cloister.

**Amphiprostylos.** A Grecian temple which has a columned portico on both sides.

**Amphitheater.** A double theater, of an elliptical form on the plan, for the exhibition of the ancient gladiatorial fights and other shows. Its arena or pit, in which those exhibitions took place, was encompassed with seats rising above each other, and the exterior had the accommodation of porticos or arcades for the public.

**Amphora.** A Grecian vase with two handles, often seen on medals.

**Ancones.** The consoles or ornaments cut on the key-stones of arches or on the sides of door-cases. They are sometimes made use of to support busts or other figures.

**Angle-bar.** In joinery, an upright bar at the angles of polygonal windows; mullion.

**Angle-capital.** In Greek architecture, those Ionic capitals placed on the flank columns of a portico, which have one of their volutes placed horizontally at an angle of a hundred and thirty-five degrees with the plane of the frieze.

**Annulated Columns.** Columns clustered together by rings or bands; much used in English architecture.

**Annular Vault.** A vault rising from two parallel walls — the vault of a corridor. Same as *Barrel Vault*.

**Annulet.** A small square molding used to separate others. The fillet separates the flutings of columns is sometimes known by this term.

**Anta, Antæ.** A name given to a pilaster when attached to a wall. Vitruvius calls pilasters *perastata* when insulated. They are not usually diminished, and in all Greek examples their capitals are different from those of the columns they accompany.




ANNULET

**Antechamber.** An apartment preceded by a vestibule and from which approached another room.

**Antechapel.** A small chapel forming the entrance to another. There are examples at Merton College, Oxford, and at King's College, Cambridge, England besides several others. The antechapel to the lady-chapel in cathedrals is generally called the Presbytery.

**Ante choir.** The part under the rood loft, between the doors of the choir and the outer entrance of the screen, forming a sort of lobby. It is also called the Fore-choir.

**Antefixa.** In classical architecture (gargoyles, in Gothic architecture), ornaments of lions' and other heads below the eaves of a temple, through channels in which, usually by the mouth, the water is carried from the eaves. By some this term is applied to the upright ornaments above the eaves in ancient architecture, which hid the ends of the *Harmi* or joint tiles.



ANTEFIXA

**Apophyge.** The lowest part of the shaft of an Ionic or Corinthian column or the highest member of its base if the column be considered as a whole. The Apophyge is the inverted cavetto or concave sweep, on the upper edge of which the diminishing shaft rests.

**Apron.** A plain or molded piece of finish below the stool of a window, used on to cover the rough edge of the plastering.

**Apse.** The semicircular or polygonal termination to the chancel of a church.

**Apteral.** A temple without columns on the flanks or sides.

**Aqueduct.** An artificial canal for the conveyance of water, either above or under ground. The Roman aqueducts are mostly of the former construction.

**Arabesque.** A building after the manner of the Arabs. Ornaments used by the same people, in which no human or animal figures appear. Arabesque is sometimes improperly used to denote a species of ornaments composed of capricious fantasies and imaginary representations of animals and foliage so much employed by the Romans in the decorations of walls and ceilings.

**Arabian Architecture.** A style of architecture the rudiments of which appear to have been taken from surrounding nations, the Egyptians, Syrians, Chaldeans, and Persians. The best preserved specimens partake chiefly of the Græco-Roman, Byzantine, and Egyptian. It is supposed that they constructed many of their finest buildings from the ruins of ancient cities.

**Aræostyle.** That style of building in which the columns are distant from one another from four to five diameters. Strictly speaking, the term should be limited to intercolumniation of four diameters, which is only suited to the Tuscan order.

**Aræosystylos.** That style of building in which four columns are used in the space of eight diameters and a half; the central





**arcolumnation** being three diameters and a half, and the others on each side being only half a diameter, by which arrangement coupled columns are reduced.

**Arbores.** Large bronze candelabra, in the shape of a tree, placed on the floor of ancient churches, so as to appear growing out of it.

**Arcade.** A range of arches, supported either by columns or on piers, and detached or attached to the wall.

**Arch.** In building, a mechanical arrangement of building materials arranged in the form of a curve, which preserves a given form when subjected to pressure, and enables them, supported by piers or abutments, to carry weights and resist pressure.

**Arch-buttress.** Sometimes called a flying buttress; an arch springing from a buttress or pier.

ARCADE

**Architrave.** That part of an entablature which rests upon the capital of a column, and is beneath the frieze.

**Architrave Cornice.** An entablature consisting of an architrave and cornice, without the intervention of the frieze, sometimes introduced when inconvenient to give the entablature the usual height.

**Architrave of a Door.** The finished work surrounding the aperture; the upper part of the lintel is called the traverse; and the sides, the jambs.

**Archives.** A repository or closet for the preservation of writings or records.

**Archivolt.** A collection of members forming the inner contour of an arch, a band or frame adorned with moldings running over the faces or the arches, and bearing upon the imposta.

**Atrium.** The superficial contents of any figure; an open space or court within a building; also, an uncovered space surrounding the foundation walls to give access to the basement.

**Atrium.** The plain space in the middle of the amphitheater or other place of public resort.

**Angle.** The meeting of two surfaces producing an angle.

**Arsenal.** A public storehouse for arms and ammunition.

**Artificer, or Artisan.** A person who works with his hands, and manufactures any commodity in iron, brass, wood, etc.

**Ashlar, or Ashler.** A facing made of squared stones, or a facing made of large slabs, used to cover walls of brick or rubble. *Coursed ashlar* is where the courses run in level courses all around the building, *random ashlar*, where the courses are of different heights, but level beds. Common freestones of small size, as they come from the quarry, are also called ashlar.

**Asphaltum.** A kind of bituminous stone, principally found in the province of Neufchatel. Mixed with stone, it forms an excellent cement, incorruptible by air and impenetrable by water.

**Astragal.** A small semicircular molding, sometimes plain and sometimes ornamented.

**Asymptote.** A straight line which continually approaches to a curve without touching it.

**Atlases, or Atlantes.** Figures or half-figures of men, used instead of columns or pilasters to support an entablature; called also Telamones.

**Atrium.** A court in the interior division of Roman houses.

**Attached Columns.** Those which project three-fourths of their diameter from the wall.

**Attic.** A low story above an entablature, or above a cornice which limits the height of the main part of an elevation. Although the term is evidently derived from the Greek, we find nothing exactly answering to it in Greek architecture; but it is very common in both Roman and Italian practice. What are otherwise called tholobates in St. Peter's and St. Paul's Cathedrals are frequently termed attics.



ATLANTES

**Attic Order.** A term used to denote the low pilasters employed in the decoration of an attic story.

**Attributes.** In painting and sculpture, symbols given to figures and statues to indicate their office and character.

**Auditory.** In ancient churches, that part of the church where the people usually stood to be instructed in the Gospel, now called the nave.

**Aula.** A court or hall in ancient Roman houses.

**Aviary.** A large apartment for breeding birds.

**Axis.** The spindle or center of any rotative motion. In a sphere, an imaginary line through the center.

**Back-choir.** A place behind the altar in the principal choir, in which there is, or was, a small altar standing back to back with the former.

**Backing of a Rafter or Rib.** The forming of an upper or outer surface that it may range with the edges of the ribs or rafters on either side.

**Backing of a Wall.** The rough inner face of a wall; earth deposited behind a retaining wall, etc.

**Back of a Window.** That piece of wainscoting which is between the bottom of the sash frame and the floor.

**Balcony.** A projection from the face of a wall, supported by columns or consoles, and usually surrounded by a balustrade.

**Baldachin.** A building in the form of a canopy, supported with columns, and serving as a crown or covering to an altar.

**Baluster.** A small pillar or column, supporting a rail, of various forms, used in balustrades.

**Baluster Shaft.** The shaft dividing a window in Saxon architecture. At St. Albans are some of these shafts, evidently out of the old Saxon church, which have been fixed up with Norman capitals.

**Balustrade.** A series of balusters connected by a rail.

**Band.** A sort of flat frieze or fascia running horizontally round a tower or other parts of a building, particularly the base tables in perpendicular work, commonly used with the long shafts characteristic of the thirteenth century. It generally has a bold, projecting molding above



BALDACHIN

and below, and is carved sometimes with foliages, but in general with cusped circles, or quatrefoils, in which frequently are shields of arms.

**Band of a Column.** A series of annulets and hollows going round the middle of the shafts of columns, and sometimes of the entire pier. They are often beautifully carved with foliages, etc., as at Amiens. In several cathedrals there are rings of bronze apparently covering the junction of the frusta of the columns. At Worcester and Westminster they appear to have been gilt; they are therefore properly called Shaft-rings.

**Baptistery.** A separate building to contain the font, for the rite of baptism. They are frequent on the Continent; that at Rome, near St. John Lateran, and those at Florence, Pisa, Pavia, etc., are all well-known examples. The only examples in England are at Cranbrook and Canterbury; the latter, however, is supposed to have been originally part of the treasury.

**Barbican.** An outwork for the defence of a gate or drawbridge; also, a sort of pent-house or construction of timber to shelter warders or sentries from arrows and other missiles.

**Barge Board.** See *Verge Board*.

**Bartizan.** A small turret, corbeled out at the angle of a wall or tower, to protect a warder and enable him to see around him. They generally are furnished with oylets or arrow-slits.

**Basement.** The lower part of a building, usually in part below the grade of the lot or street.

**Base Moldings.** The moldings immediately above the plinth of a wall, pillar, or pedestal.

**Base of a Column.** That part which is between the shaft and the pedestal, or, if there be no pedestal, between the shaft and the plinth. The Grecian Doric had no base, and the Tuscan has only a single torus, or a plinth.

**Basilica.** A term given by the Greeks and Romans to the public buildings devoted to judicial purposes.

**Bas-relief.** See *Basso-rilievo*.

**Basse-cour.** A court separated from the principal one, and destined for stables, etc.


**Basso-rilievo, or Bas-relief.** The representations of figures projected from a background without being detached from it. It is divided into three parts: *alto-rilievo*, when the figure projects more than one-half; *Mezzo-rilievo*, that in which the figure projects one-half; and *Basso-rilievo*, when the projection of the figure is less than one-half, as in coins.

**Bat.** A part of a brick.

**Batten.** Small scantlings, or small strips of boards, used for various purposes. Small strips put over the joints of sheathing to keep out the weather.

**Batten-door.** A door made of sheathing, secured by strips of board, put crossways, and nailed with clinched nails.

**Batter.** A term used by bricklayers, carpenters, etc., to signify a wall, piece of timber, or other material, which does not stand upright, but inclines from you when you stand before it; but when, on the contrary, it leans toward you, it is said to overhang.



BARTIZAN

**Battlement.** A parapet with a series of notches in it, from which arrows may be shot, or other instruments of defence hurled on besiegers. The raised portions are called merlons; and the notches, embrasures or crenelles. The former were intended to cover the soldier while discharging his weapon through the latter. Their use is of great antiquity; they are found in the sculptures of Nineveh, in the tombs of Egypt, and on the famous François vase, where there is a delineation of the siege of Troy. In ecclesiastical architecture the early battlements have shallow embrasures at some distance apart. In the Decorated period they are closer together, and deeper, and the moldings on the top of the merlon and bottom of the embrasure are richer. During this period, and the early part of the Perpendicular, the sides or cheeks of the embrasures are perfectly square and plain. In later times the moldings were continued round the sides, as well as at top and bottom, mitring at the angles, as over the doorway of Magdalen College, Oxford, England. The battlements of the Decorated and later periods are often richly ornamented by paneling, as in the last example. In castle work the merlons are often pierced by narrow arrow-slits. (See *Oylet*.) In South Italy some battlements are found strongly resembling those of old Rome and Pompeii; in the Continental ecclesiastical architecture, the parapets are very rarely embattled.



BATTLEMENT

**Bay.** Any division or compartment of an arcade, roof, etc. Thus each span from pillar to pillar, in a cathedral, is called a bay, or sever.

**Bay Window.** Any window projecting outward from the wall of a building either square or polygonal on plan, and commencing from the ground. If they are carried on projecting corbels, they are called Oriel windows. Their use seems to have been confined to the later periods. In the Tudor and Elizabethan style they are often semicircular in plan, in which case some think it more correct to call them Bow Windows.

**Bazaar.** A kind of Eastern mart, of Arabic origin.

**Bead.** A circular molding. When several are joined, it is called *Reeding*; when flush with the surface, it is called *Quirk-bead*; and when raised, *Cock-bead*.

**Beam.** A piece of timber, iron, stone, or other material, placed horizontally or nearly so, to support a load over an opening, or from post to post.

**Bearing.** The portion of a beam, truss, etc., that rests on the supports.

**Bearing Wall, or Partition.** A wall which supports the floors and roofs of a building.

**Beaufet, or Buffet.** A small cupboard, or cabinet, to contain china. It may either be built into a wall, or be a separate piece of furniture.

**Bed.** In bricklaying and masonry, the horizontal surfaces on which the stones or bricks of walls lie in courses.

**Bed of a Slate.** The lower side.

**Bed Moldings.** Those moldings in all the orders between the cornice and frieze.

**Belfry.** Properly speaking, a detached tower or campanile containing bells as at Evesham, England, but more generally applied to the ringing-room or bell-chamber of the tower of a church. See *Tower*.

**Bell-cot, Bell-gable, or Bell-turret.** The place where one or more bells are hung in chapels, or small churches which have no towers. Bell-cots are sometimes double, as at Northborough and Coxwell, England; a very common form in France and Switzerland admits of three bells. In these countries, also, they are frequently of wood, and attached to the ridge. Those which stand on the gable, dividing the nave from the chancel, are generally called Sanctus Bells. A very curious and, it is believed, unique example at Cleves Abbey, England, juts out from the wall. In later times bell-turrets were much ornamented; these are often called Flèches.

**Bell of a Capital.** In Gothic work, immediately above the necking is a deep, hollow curve; this is called the bell of a capital. It is often enriched with foliages. It is also applied to the body of the Corinthian and Composite capitals.

**Belt.** A course of stones or brick projecting from a brick or stone wall, generally placed in a line with the sills of the windows; it is either molded, fluted, plane, or enriched with patras at regular intervals. Sometimes called Stone string.

**Belvedere, or Look-out.** A turret or lantern raised above the roof of an observatory for the purpose of enjoying a fine prospect.

**Bema.** The semicircular recess, or hexedra, in the basilica, where the judges sat, and where in after-times the altar was placed. It generally is roofed with a half-dome or concha. The seats of the priests were against the wall, looking into the body of the church, that of the bishop being in the center. The bema is generally ascended by steps, and railed off by cancelli.

**Bench Table.** The stone seat which runs round the walls of large churches, and sometimes round the piers; it very generally is placed in the porches.

**Bevel.** An instrument for taking angles. One side of a solid body is said to be beveled with respect to another, when the angle contained between those two sides is greater or less than a right angle.

**Bezantee.** A name given to an ornamental molding much used in the Norman period, resembling bezants, coins struck in Byzantium.

**Billet.** A species of ornamented molding much used in Norman, and sometimes in Early English work, like short pieces of stick cut off and arranged alternately.

**Blocking, or Blocking-course.** In masonry, a course of stones placed on the top of a cornice crowning the walls.

**Bond.** In bricklaying and masonry, that connection between bricks or stones formed by lapping them upon one another in carrying up the work, so as to form an inseparable mass of building, by preventing the vertical joints falling over each other. In brickwork there are several kinds of bond. In common brick walls in every sixth or seventh course the bricks are laid crossways of the wall, called Headers. In face work, the back of the face brick is clipped so as to get a diagonal course of headers behind. In Old English bond, every alternate course is a header course. In Flemish bond, a header and stretcher alternate in each course.

**Bond-stones.** Stones running through the thickness of the wall at right angles to its face, in order to bind it together.

**Bond-timbers.** Timbers placed in a horizontal direction in the walls of a brick building in tiers, and to which the battens, laths, etc., are secured. In rubble work, walls are better plugged for this purpose.

**Border.** Useful ornamental pieces around the edge of anything.

**Boss.** An ornament, generally carved, forming the key-stone at the intersection of the ribs of a groined vault. Early Norman vaults have no bosses. The carving is generally foliage, and resembles that of the period in capitals, &c. Sometimes they have human heads, as at Notre Dame at Paris, and sometimes grotesque figures. In Later Gothic vaulting there are bosses at every intersection.

**Boutell.** The mediæval term for a round molding, or torus. When it follows a curve, as round a bench end, it is called a Roving Boutell. |

**Bow.** Any projecting part of a building in the form of an arc of a circle. A bow, however, is sometimes polygonal.

**Bow Window.** A window placed in the bow of a building.

**Brace.** In carpentry, an inclined piece of timber, used in trussed partitions or in framed roofs, in order to form a triangle, and thereby stiffen the framing. When a brace is used by way of support to a rafter, it is called a strut. Braces in partitions and span-roofs are, or always should be, disposed in pairs, and introduced in opposite directions.

**Brace Mold.** [{}]. Two ressaunts or ogees united together like a brace in printing, sometimes with a small bead between them.

**Bracket.** A projecting ornament carrying a cornice. Those which support vaulting shafts or cross springers of a roof are more generally called Corbels.

**Break.** Any projection from the general surface of a building.

**Breaking Joint.** The arrangement of stones or bricks so as not to allow two joints to come immediately over each other. See *Bond*.

**Breast of a Window.** The masonry forming the back of the recess and the parapet under the window-sill.

**Bressummer.** A lintel, beam, or iron tie, intended to carry an external wall and itself supported by piers or posts; used principally over shop windows. This term is now seldom used, the word *beam*, or *girder*, taking its place.

**Bridging.** A method of stiffening floor joist and partition studs, by cutting pieces in between. Cross bridging of floor joist is illustrated in cut.



**Bulwark.** In ancient fortification, nearly the same as Bastion in modern.

CROSS-BRIDGING

| **Burse, or Bourse.** A public edifice for the assembly of merchant traders and an exchange.

**Bust.** In sculpture, that portion of the human figure which comprises the head, neck, and shoulders.

**Buttery.** A store-room for provisions.

**Butt-joint.** Where the ends of two pieces of timber or molding butt together.

| **Buttress.** Masonry projecting from a wall, and intended to strengthen the same against the thrust of a roof or vault. Buttresses are no doubt derived from the classic pilasters which serve to strengthen walls where there is a pressure of a girder or roof-timber. In very early work they have little projection, and, in fact, are "strippilasters." In Norman work they are wider, with very little projection, and generally stop under a cornice or corbel table. Early English buttresses project considerably, sometimes with deep sloping weatherings in several




BUTTRESS

**stages, and sometimes with gabled heads.** Sometimes they are chamfered, and sometimes the angles have jamb shafts. At Wells and Salisbury, England, they are richly ornamented with canopies and statues. In the Decorated period they became richly paneled in stages, and often finish with niches and statues and elegantly carved and crocketed gablets, as at York, England. In the Perpendicular period the weatherings became waved, and they frequently terminate with niches and pinnacles.

**Buttress, Flying.** A detached buttress or pier of masonry at some distance from a wall, and connected therewith by an arch or portion of an arch, so as to discharge the thrust of a roof or vault on some strong point.

**Buttress Shafts.** Slender columns at the angle of buttresses, chiefly used in the Early English period.

**Byzantine Architecture.** A style developed in the Byzantine Empire. The capitals of the pillars are of endless variety and full of invention; some are founded on the Greek Corinthian, some resemble the Norman and the Lombard style, and are so varied that no two sides of the same capital are alike. They are comprised under the style Romanesque, which comprehends the round-arch style. Byzantine architecture reached its height in the Church of St. Sophia at Constantinople.



FLYING BUTTRESS

**Cabinet.** A highly ornamented kind of buffet or chest of drawers set apart for the preservation of things of value.

**Cabling.** The flutes of columns are said to be cabled when they are partly occupied by solid convex masses, or appear to be refilled with cylinders after they had been formed.

**Caduceus.** Mercury's rod, a wand entwined by two serpents and surmounted by two wings. The rod represents power; the serpents, wisdom; and the wings, diligence and activity.

**Caisson.** A panel sunk below the surface in flat or vaulted ceilings. See *Casoon*

**Caisson.** In bridge building, a chest or vessel in which the piers of a bridge are built, gradually sinking as the work advances till its bottom comes in contact with the bed of the river, and then the sides are disengaged, being so constructed as to allow of their being thus detached without injury to its floor or bottom.

**Caliber, or Caliper.** The diameter of any round body; the width of the mouth of a piece of ordnance.

**Camber.** In carpentry, the convexity of a beam upon the surface, in order to prevent its becoming concave by its own weight, or by the burden it may have to sustain.

**Campanile.** A name given in Italy to the bell-tower of a town-hall or church. In that country this is almost always detached from the latter.

**Candelabrum.** Stand or support on which the ancients placed their lamps. Candelabra were made in a variety of shapes and with much taste and elegance. The term is also used to denote a tall ornamental candlestick with several arms, or a bracket with arms for candles.

**Canopy.** The upper part or cover of a niche, or the projection or ornament over an altar, seat, or tomb. The word is supposed to be derived from cono-



CADUCEUS

**canopy**, the gauze covering over a bed to keep off the gnats; a mosquito curtain. Early English canopies are generally simple, with trefoiled or cinque-toiled hoods, but in the later styles they are very rich, and divided into compartments with pendants, knots, pinnacles, etc. The triangular arrangement over an Early English and Decorated doorway is often called a canopy. The triangular canopies in the North of Italy are peculiar. Those in England are generally part of the arrangement of the arch moldings of the door, and form, as it were, the hood-molds to them, as at York. The former are above and independent of the door moldings, and frequently support an arch with a tympanum, above which is a triangular canopy, as in the Duomo at Florence. Sometimes the canopy and arch project from the wall, and are carried on small jamb shafts, as at San Pietro Martiro at Verona. Canopies are often used over windows, as at York Minster over the great west window, and lower tiers in the towers. These are triangular, while the upper windows in the towers have ogee canopies.

**Capital.** The upper part of a column, pillar, pier, etc. Capitals have been used in every style down to the present time. That mostly used by the Egyptians was bell-shaped, with or without ornaments. The Persians used the double-headed bell, forming a kind of bracket capital. The Assyrians apparently made use of the Ionic and Corinthian, which were developed by the Greeks, Romans, and Italians into their present well-known forms. The Doric was apparently an invention or adaptation by the Greeks, and was altered by the Romans and Italians. But in all these examples, both ancient and modern, the capitals of an order are all of the same form throughout the same building, so that if one be seen the form of all the others is known. The Romanesque architects altered all this, and in the carving of their capitals often introduced such figures and emblems as helped to tell the story of their building. Another form was introduced by them in the curtain capital, rude at first, but afterward highly decorated. It evidently took its origin from the cutting off of the lower angles of a square block, and then rounding them off. The process may be distinctly seen in its several stages, in Mayence Cathedral. But this form of capital was more fully developed by the Normans, with whom it became a marked feature. In the early English capitals a peculiar flower of three or more lobes was used, spreading from the necking upward in most graceful forms. In Decorated and Perpendicular styles this was abandoned in favor of more realistic forms of crumpled leaves, enclosing the bell like a wreath. In each style bold abacus moldings were always used, whether with or without foliage.

**Caravansary.** A huge, square building, or inn, in the East, for the reception of travelers and lodging of caravans.

**Carriage.** The timber or iron joist which supports the steps of a wooden stair.

**Carton, or Cartoon.** A design made on strong paper, to be transferred on the fresh plaster wall to be afterward painted in fresco; also, a colored design for working in mosaic tapestry.

**Cartouche.** An ornament which like an escutcheon, a shield or an oval or oblong panel has the central part plain, and usually slightly convex, to receive an inscription, armorial bearings, or an ornamental or significant piece of painting or sculpture. Frequently used in French Renaissance and Modern Architecture.

**Caryatides.** Human female figures used as piers, columns, or supports. *Caryatic* is applied to the human figure generally, when used in the manner of caryatides.

**Cased.** Covered with other materials, generally of a better quality.





**Casement.** A glass frame which is made to open by turning on hinges fixed to its vertical edges.

**Cassoon, or Caisson.** A deep panel or coffer in a soffit or ceiling. This term is sometimes written in the French form, *caisson*; sometimes derived directly from the Italian *cassone*, the augmentative of *cassa*, a chest or coffer.

**Cast.** A term used in sculpture for the impression of any figure taken in plaster of Paris, wax, or other substances.

**Catacombs.** Subterranean places for burying the dead. Those of Egypt, and near Rome, are believed to be the most important.

**Catafalco.** An ornamental scaffold used in funeral solemnities.

**Cathedral.** The principal church, where the bishop has his seat as diocesan.

**Cauliculus.** The inner scroll of the Corinthian capital. It is not uncommon, however, to apply this term to the larger scrolls or volutes also.

**Causeway.** A raised or paved way.

**Cavetto.** A concave ornamental molding, opposed in effect to the ovolo—the quadrant of a circle.

**Ceiling.** That covering of a room which hides the joists of the floor above, or the rafters of the roof. Most European churches either have open roofs, or are groined in stone. At Peterborough and St. Albans, England, there are very old flat ceilings of boards curiously painted. In later times the boarded ceilings, and, in fact, some of those of plaster, have molded ribs, locked with bosses at the intersection, and are sometimes elaborately carved. In many English churches there are ceilings formed of oak ribs, filled in at the spandrels with narrow, thin pieces of board, in exact imitation of stone groining. In the Elizabethan and subsequent periods the ceilings are enriched with most elaborate ornaments in stucco. Matched and beaded boards, planed and smoothed, used for wainscoting. In the New England States it is called *beathing*.

**Cenotaph.** An honorary tomb or monument, distinguished from monuments by being empty, the individual it is to memorialize having received interment elsewhere.

**Centaur.** A poetical imaginary being of heathen mythology, half-man and half-horse.

**Centring.** In building, the frames on which an arch is turned.

**Chamfer, Champfer, or Chaumfer.** When the edge or arris of any work is cut off at an angle of  $45^\circ$  in a small degree, it is said to be chamfered; if on a large scale, it is said to be a canted corner. The chamfer is much used in mediæval work, and is sometimes plain, sometimes hollowed out, and sometimes molded.

**Chamfer Stop.** Chamfers sometimes simply run into the arris by a plane face; more commonly they are first stopped by some ornament, as by a bead; they are sometimes terminated by trefoils, or cinque-foils, double or single, and in general form very pleasing features in mediæval architecture.

**Chancel.** A place separated from the rest of a church by a screen. The word is now generally used to signify the portion of an Episcopal or Catholic church containing the altar and communion table.

**Chantry.** A small chapel, generally built out from a church. They generally contain a founder's tomb, and are often endowed places where masses might

be said for his soul. The officiator, or mass priest, being often unconnected with the parochial clergy. The chantry has generally an entrance from the outside.

**Chapel.** A small, detached building used as a substitute for a church in a large parish; an apartment in any large building, a palace, a nobleman's house, a hospital or prison, used for public worship; or an attached building running off of and forming part of a large church, generally dedicated to different saints, each having its own altar, piscina, etc., and screened off from the body of the building.

**Chapter House.** The chamber in which the chapter or heads of the monastic bodies assembled to transact business. They are of various forms; some are oblong apartments, some octagonal, and some circular.

**Chapitel.** In Gothic architecture, the capital of a pier or column which receives an arch.

**Charnel House.** A place for depositing the bones which might be thrown up in digging graves. Sometimes it was a portion of the crypt; sometimes it was a separate building in the church-yard; sometimes chantry chapels were attached to these buildings. M. Viollet-le-Duc has given two very curious examples of *ossuaires* — one from Fleurance, the other from Faouet.



CHAPTEL

**Cherub—Gothic.** A representation of an infant's head joined to two wings, used in the churches on key-stones of arches and corbels.

**Chevron—Gothic.** An ornament turning this and that way, like a zigzag, or letter Z.

**Chiaro-oscuro.** The effects of light and shade in a picture.

**Choir.** That part of a church or monastery where the breviary service, or "horæ," is chanted.




CHEVRON

**Church.** A building for the performance of public worship. The first churches were built on the plan of the ancient basilicæ, and afterward on the plan of a cross: a church is said to be in Greek cross when the length of the transverse is equal to that of the nave; in Latin cross, when the nave is longer than the transverse part; in rotundo, when it is a perfect circle; simple, when it has only a nave and choir; with aisles, when it has a row of porticos in form of vaulted galleries, with chapels in its circumference.

**Ciborium.** A tabernacle or vaulted canopy supported on shafts standing over the high altar.

**Cincture.** A ring, list, or fillet at the top and bottom of a column, serving to divide the shaft of the column from its capital and base.

**Cinque-foil.** A sinking or perforation, like a flower, of five points or leaves, as a quatre-foil is of four. The points are sometimes in a circle, and sometimes form the cusping of a head.



CINQUE-FOIL

**Civic Crown.** A garland of oak-leaves and acorns, given as honorary distinction among the Romans to such as had preserved the life of a fellow-citizen.

**Clere-story, Clear-story.** When the middle of the nave of a church rises above the aisles and is pierced with windows, the upper story is thus called. Sometimes these windows are very small, being mere quatrefoils, or spherical triangles. In large buildings, however, they are important objects both for beauty and utility. The window of the clere-story of Norman work, even in large churches, are of less importance than in the later styles. In Early English they became larger; and in the Decorated they are more important still, being lengthened as the triforium diminishes. In Perpendicular work the latter often disappears altogether, and in many later churches the clere-stories are close ranges of windows. The word *clere-story* is also used to denote a similar method of lighting other buildings besides churches, especially factories, depots, sheds, etc.

**Cloister.** An enclosed square, like the atrium of a Roman house, with a walk or ambulatory around, sheltered by a roof, generally groined, and by tracery windows, which were more or less glazed.

**Close.** The precinct of a cathedral or abbey. Sometimes the walls are raceable, but now generally the boundary is only known by tradition.

**Close String, or Box String.** A method of finishing the outer edge of stairs, by building up a sort of curb or string on which the balusters set, and the treads and risers stop against it.

**Clustered.** In architecture, the coalition of several members which penetrate each other.

**Clustered Column.** Several slender pillars attached to each other so as to form one. The term is used in Roman architecture to denote two or four columns which appear to intersect each other at the angle of a building to answer at each return.

**Coat.** A thickness or covering of paint, plaster, or other work, done at one time. The first coat of plastering is called the scratch coat, the second coat (when there are three coats) is called the brown coat, and the last coat is variously known as the slipped coat, limcoat, or white coat. It varies in composition in different localities.

**Coffer.** A deep panel in a ceiling.

### *Bath Abbey*

#### FLYING BUTTRESS AND CLERE-STORY

A, buttress with pinnacle; B, flying buttress supporting clere-story; C, vaulted roof of aisle; D D, pier dividing nave from aisle; E, vaulted roof of nave.



CLUSTERED  
COLUMN

**Coffer Dam.** A frame used in the building of a bridge in deep water similar to a caisson.

**Collar Beam.** A beam above the lower ends of the rafters, and spiked to them.

**Colonnade.** A row of columns. The colonnade is termed, according to the number of columns which support the entablature: Tetrastyle, when there are four; hexastyle, when six; octostyle, when eight, etc. When in front of a building they are termed porticos; when surrounding a building, peristyle; and when double or more, polystyle.

**Colosseum, or Coliseum.** The immense amphitheater built at Rome by Flavius Vespasian, A. D. 72, after his return from his victories over the Jews. It would contain ninety thousand persons sitting, and twenty thousand more standing. The name is now employed to denote an unusually large audience building, generally of a temporary nature.

**Colossus.** The name of a brazen statue which was erected at the entrance of the harbor at Rhodes, one hundred and five feet in height. Vessels could sail between its legs.

**Column.** A round pillar. The parts are the base, on which it rests; its body, called the shaft; and the head, called the capital. The capital finishes with a horizontal table, called the abacus, and the base commonly stands on another, called the plinth. Columns may be either insulated or attached. They are said to be attached or engaged when they form part of a wall, projecting one-half or more, but not the whole, of their substance.


**Common.** A line, angle, surface, etc., which belongs equally to several objects. Common centring is a centring without trusses, having a tie beam at bottom. Common joists are the beams in naked flooring to which the joists are fixed. Common rafters in a roof are those to which the laths are attached.

**Composite Arch.** Is the pointed or lancet arch.

**Composite Order.** The most elaborate of the orders of classical architecture.

**Compound Arch.** A usual form of medieval arch, which may be resolved into a number of concentric archways, successively placed within and behind each other.

**Conduit.** A long narrow passage between two walls or underground for secret communication between different apartments; also, a canal or pipe for the conveyance of water.



SECTION OF COLUMN AND ENTABLATURE  
(Divided according to the Tuscan Order)

**Confessional.** The seat where a priest or confessor sits to hear confessions  
**Conge.** Another name for the echinus or quarter round.

**Conservatory.** A building for the protection and rearing of tender plants, often attached to a house as an apartment. Also, a public place of instruction, designed to preserve and perfect the knowledge of some branch of learning or the fine arts; as, a *conservatory of music*.

**Consistory.** The judicial hall of the College of Cardinals at Rome.

**Consol, or Console.** A bracket or truss, generally with scrolls or volutes at the two ends, of unequal size and contrasted, but connected by a flowing line from the back of the upper one to the inner convolving face of the lower.

**Coping.** The capping or covering of a wall. This is of stone, weathered to throw off the wet. In Norman times, as far as can be judged from the little there is left, it was generally plain and flat, and projected over the wall with a sloping to form a drip. Afterward it assumed a torus or bowtell at the top, and became deeper, and in the Decorated period there were generally several sets-off. The copings in the Perpendicular period assumed something of the wavy section of the buttress caps, and mitred round the sides of the embrasure, as well as the top and bottom.

## CONSOLES

**Corbel.** The name, in mediæval architecture, for a piece of stone jutting out of a wall to carry any superincumbent weight. A piece of timber projecting in the same way was called a tassel or a bragger. Thus, the carved ornaments from which the vaulting shafts spring at Lincoln are corbels. Norman corbels are generally plain. In the Early English period they are sometimes elaborately carved. They sometimes end with a point, apparently growing into the wall, or forming a knot, and often are supported by angles and other figures. In the later periods the foliage or ornaments resemble those in the capitals. In modern architecture, a short piece of stone or wood projecting from a wall to form a support, generally ornamented.

**Corbel Out.** To build out one or more courses of brick or stone from the face of a wall, to form a support for timbers.

**Corbel Table.** A projecting cornice or parapet, supported by a range of corbels a short distance apart, which carry a molding, above which is a plain face of projecting wall forming a parapet, and covered by a coping. Sometimes small arches are thrown across from corbel to corbel, to carry the projection.

**Cornice.** The projection at the top of a wall finished by a blocking-course, common in classic architecture. In Norman times, the wall finished with a corbel table, which carried a portion of plain projecting work, which was finished by a coping, and the whole formed a parapet. In Early English times the parapet was much the same, but the work was executed in a much better way, especially the small arches connecting the corbels. In the Decorated period the corbel table was nearly abandoned, and a large hollow, with one or two subordinate moldings, substituted; this is sometimes filled with the ball-flowers, and sometimes with running foliages. In the Perpendicular style the parapet frequently did not project beyond the wall-line below; the molding then became a string though often improperly called a cornice), and was ornamented by a quatre-foil, or small rosettes, set at equal intervals immediately under the battlements. In many French examples the molded string is very bold, and enriched with foliage ornaments.

**Corona.** The brow of the cornice which projects over the bed moldings throw off the water.

**Corridor.** A long gallery or passage in a mansion connecting various apartments and running round a quadrangle. Any long passage-way in a building.

**Countersink.** To make a cavity for the reception of a plate of iron, or the head of a screw or bolt, so that it shall not project beyond the face of the work.

**Coupled Columns.** Columns arranged in pairs.

**Course.** A continued layer of bricks or stones in buildings; the term is also applicable to slates, shingles, etc.

**Court.** An open area behind a house, or in the center of a building and its wings. Courts admit of the most elegant ornamentations, such as arcades, &c.

**Cove — Coving.** The molding called the cavetto, or the scotia inverted, on a large scale, and not as a mere molding in the composition of a cornice, is called a cove or a coving.

**Cove-bracketing.** The wooden skeleton mold or framing of a cove, applied chiefly to the bracketing of a cove ceiling.

**Cove Ceiling.** A ceiling springing from the walls with a curve.


**Coved and Flat Ceiling.** A ceiling in which the section is the quadrant of a circle, rising from the walls and intersecting in a flat surface.

**Cradling.** Timber work for sustaining the lath and plaster of vaulted ceilings.

**Cresting.** An ornamental finish in the wall or ridge of a building, which is common on the Continent of Europe. An example occurs at Exeter Cathedral, the ridge of which is ornamented with a range of small fleurs-de-lis in lead.

**Crocket.** An ornament running up the sides of gables, hood-molds, pinnacles, spires; generally, a winding stem like a creeping plant, with flowers or leaves projecting at intervals, and terminating in a finial.

**Cross.** This religious symbol is almost always placed on the ends of gables, the summit of spires, and other conspicuous places of old churches. In early times it was generally very plain, often a simple cross in a circle. Sometimes they take the form of a light cross, crosslet, or a cross in a square. In the Decorated and later styles they became richly floriated, and assumed an endless variety of forms. Of memorial crosses the finest examples are the Eleanor crosses, erected by Edward I. Of these a few yet remain, one of which has recently been reërected at Charing Cross. Preaching crosses were often set up by the wayside as stations for preaching; the most noted is that in front of St. Paul's, England. The finest remaining sepulchral crosses are the old elaborately carved examples found in Ireland.



CROCKET

**Cross-aisle.** An old name for a transept.

**Cross-springer.** The transverse ribs of a vault.

**Cross-vaulting.** A common name given to groins and cylindrical vaults.

**Crown.** In architecture the uppermost member of the cornice; called also Corona and Larmier.

**Crypt.** A vaulted apartment of greater or less size, usually under the choir.

**Cupola.** A small room, either circular or polygonal, standing on the top of a dome. By some it is called a Lantern.


**Surb Roof, or Mansard Roof.** A roof formed of four contiguous planes, the two having an external inclination.

**Curtail Step.** The first step in a stair, which is generally finished in the form of a scroll.

**Cusp.** The point where the foliations of tracery intersect. The earliest example in England of a plain cusp is probably that at Pythagoras School, at Cambridge, of an ornamental cusp, at Ely Cathedral, where a small roll, with a pette at the end, is formed at the termination of a cusp. In the later styles the terminations of the cusps were more richly decorated; they also sometimes terminate not only in leaves or foliages, but in rosettes, heads, and other fanciful ornaments.


**Cyclostyle.** A structure composed of a circular range of columns without a core is cyclostylar; with a core, the range would be a peristyle. This is the species of edifice called by Vitruvius *monopteral*.

**Cyma.** The name of a molding of very frequent use. It is a simple, waved line, concave at one end and convex at the other, like an *allic f*. When the concave part is uppermost it is called *cyma recta*, but if the convexity appear above, and the concavity below, it is then a *cyma reversa*.



CYMA RECTA

**Cymatium.** When the crowning molding of an entablature is of the cyma form, it is termed the *Cymatium*.



CYMA REVERSA

**Cyrtostyle.** A circular projecting portico. Such are those of the transept entrances to St. Paul's Cathedral, London.

**Dado, or Die.** The vertical face of an insulated pedestal between the base and cornice, or surbase. It is extended also to the similar part of all stereobates which are arranged like pedestals in Roman and Italian architecture.

**Dais.** A part of the floor at the end of a mediæval hall, raised a step above the rest of the floor. On this the lord of the mansion dined with his friends at the great table, apart from the retainers and servants. In mediæval halls there is generally a deep recessed bay window at one or at each end of the dais, supposed to be for retirement, or greater privacy than the open hall could afford. In France the word is understood as a canopy or hanging over a seat; probably the name was given from the fact that the seats of great men were then surrounded by such an ornament.

**Darby.** A flat tool used by plasterers in working, especially on ceilings. It is generally about seven inches wide and forty-two inches long, with two handles at the back.

**Decastyle.** A portico of ten columns in front.

**Decorated Style.** The second stage of the Pointed or Gothic style of architecture, considered the most complete and perfect development of Gothic architecture, the best examples of which are found in England.

**Demi-metope.** The half of a metope, which is found at the retiring or projecting angles of a Doric frieze.

**Dentil.** The cogged or toothed member, common in the bed-mold of a Corinthian entablature, is said to be dentiled, and each cog or tooth is called a dentil.

**Depressed Arches, or Drop Arches.** Those of less pitch than the equilateral.

**Design.** The plans, elevations, sections, and whatever other drawings may be necessary for an edifice, exhibit the design, the term plan having a restricted application to a technical portion of the design.

**Detail.** As used by architects, detail means the smaller parts into which composition may be divided. It is applied generally to moldings and other enrichments, and again to their minutiae.

**Diameter.** The line in a circle passing through its center, or thickest part, which gives the measure proportioning the intercolumniation in some of the orders.

**Diameters.** The diameters of the lower and upper ends of the shaft of a column are called its inferior and superior diameters, respectively; the former the greatest, the latter the least diameter of the shaft.

**Diaper.** A method of decorating a wall, panel, stained glass, or any plain surface, by covering it with a continuous design of flowers, rosettes, etc., either in squares or lozenges, or some geometrical form resembling the pattern of a diapered table-cloth, from which, in fact, the name is supposed by some to have been derived.

**Diastyle.** A spacious intercolumniation, to which three diameters are assigned.

**Dipteros.** A double-winged temple. The Greeks are said to have constructed temples with two ranges of columns all around, which were called dipteroi. A portico projecting two columns and their interspaces is of dipteral or pseudo-dipteral arrangement.

**Discharging Arch.** An arch over the opening of a door or window, to discharge or relieve the superincumbent weight from pressing on the lintel.

**Distemper.** Term applied to painting with colors mixed with size or other glutinous substance. All the cartoons of the ancients, previous to the year 1473, are said to be done in distemper.

**Distyle.** A portico of two columns. This is not generally applied to the narrow porch with two columns, but to describe a portico with two columns in antis.

**Ditriglyph.** An intercolumniation in the Doric order, of two triglyphs.

**Dodecastyle.** A portico of twelve columns in front. The lower one of the west front of St. Paul's Cathedral, London, is of twelve columns, but they are coupled, making the arrangement pseudo-dodecastyle. The Chamber of Deputies in Paris has a true dodecastyle.

**Dog-tooth.** A favorite enrichment used from the latter part of the Norman period to the early part of the Decorated. It is in the form of a four-leaf flower, the center of which projects, and probably was named from its resemblance to the dog-toothed violet.

**Dome.** A cupola or inverted cup on a building. The application of this term to its generally received purpose is from the Italian custom of calling an archiepiscopal church, by way of eminence, *Il Duomo*, the temple; for to one of that rank, the Cathedral of Florence, the cupola was first applied in modern practice. The Italians themselves never call a cupola a dome; it is on this side of the Alps the application has arisen, from the circumstance, it would appear, that the Italians use the term with reference to those structures whose most distinguishing feature is the cupola, tholus, or (as we now call it) dome.

**Domestic Architecture.** That branch which relates to private buildings.

**Donjon.** The principal tower of a castle, generally containing the prison.

**Door Frame.** The surrounding case into and out of which the door shuts and opens. It consists of two upright pieces, called jambs, and a head, generally fastened together by mortices and tenons, and wrought, rebated, and beaded.

**Doric Order.** The oldest of the three orders of Grecian architecture.



**Dormer Window.** A window belonging to a room in a roof, which consequently projects from it with a valley gutter on each side. They are said not to be earlier than the fourteenth century. In Germany there are often several rows of dormers, one above the other. In Italian Gothic they are very rare; in fact, the former have an unusually steep roof, while in the latter country, where the Italian tile is used, the roofs are rather flat.

**Dormitory.** A room, suite of rooms, or building used to sleep in. The name was first applied to the place where the monks slept at night. It was sometimes a long room like a barrack, and sometimes divided into a succession of small chambers or cells. The dormitory was generally on the first floor, and connected with the church, so that it was not necessary to go out-of-doors to attend the nocturnal services. In the large houses of the Perpendicular period, and also in some of the Elizabethan, the entire upper story in the roof formed one large apartment, said to have been a place for exercise in wet weather, and also for a dormitory for the retainers of the household, or those of visitors.

**Double Vault.** Formed by a duplicate wall; wine cellars are sometimes so formed.

**Dovetailing.** In carpentry and joinery, the method of fastening boards or other timbers together, by letting one piece into another in the form of the expanded tail of a dove.

**Dowel.** A pin let into two pieces of wood or stone, where they are joined together. A piece of wood driven into a wall so that other pieces may be nailed to it. This is also called plugging.

**Draw-bridge.** A bridge made to draw up or let down, much used in fortified places. In navigable rivers, the arch over the deepest channel is made to draw up and revolve, in order to let the masts of ships pass through.

**Drawing-room.** A room appropriated for the reception of company; a room to which company withdraws from the dining-room.

**Dresser.** A cupboard or set of shelves to receive dishes and cooking utensils.

**Dressing.** Is the operation of squaring and smoothing stones for building; also applied to smoothing lumber.

**Dressing-room.** An apartment appropriated for dressing the person.

**Drip.** A name given to the member of a cornice which has a projection beyond the other parts for throwing off water by small portions, drop by drop. It is also called Larmier.

**Drip-stone.** The label molding which serves on a canopy for an opening, and to throw off the rain. It is also called Weather Molding.

**Drop-scene.** A curtain suspended by pulleys, which descends or drops in front of the stage in a theater.

**Drum.** The upright part of a cupola over a dome; also, the solid part or vase of the Corinthian and Composite capitals.

**Dry-rot.** A rapid decay of timber, by which its substance is converted into dry powder, which issues from minute cavities resembling the borings of worms.

**Dungeon.** The prison in a castle keep, so called because the Norman name for the latter is donjon, and the dungeons, or prisons, are generally in its lowest story.

**Dwarf Wall.** The walls enclosing courts above which are railings of iron; low walls, in general, receive this name.

**Eaves.** In slating and shingling, the margin or lower part of the slats hanging over the wall, to throw the water off from the masonry or brickwork.

**Echinus.** A molding of eccentric curve, generally cut (when it is carved) into the forms of eggs and anchors alternating, whence the molding is called by the name of the more conspicuous. It is the same as Ovolo.



ECHINUS

**Edifice.** Is synonymous with the terms building, fabric, erection, but is more strictly applicable to architecture distinguished for size, dignity, and grandeur.

**Efflorescence.** In architecture, the formation of a whitish loose powder, or crust, on the surface of stone or brick walls.

**Egyptian Architecture.** The earliest civilization and cultivation of the arts was in Upper Egypt. The most remarkable and most ancient monuments of the Egyptians, with the exception of the pyramids, are nearly all included in Upper Egypt. The buildings of Egypt are characterized by solidity and massiveness of construction, originality of conception, and boldness of form. The walls, the pillars, and the most sacred places of their religious buildings were ornamented with hieroglyphics and symbolical figures, while the ceilings of the porticos exhibited zodiacs and celestial planispheres. The temples of Egypt were generally without roofs, and, consequently, the interior colonnades had no pediments, supporting merely an entablature, composed of only architrave, frieze, and cornice, formed of immense blocks united without cement and ornamented with hieroglyphics.

**Element.** The outline of the design of a Decorated window, on which the centers for the tracery are formed. These centers will all be found to fall on points which, in some way or other, will be equimultiples of parts of the openings. To draw tracery well, or understand even the principles of its composition, much attention should be given to the study of the element.

**Elevation.** The front façade, as the French term it, of a structure; a geometrical drawing of the external upright parts of a building.

**Embattlement.** An indented parapet; battlement.

**Emblazon.** To adorn with figures of heraldry, or ensigns armorial.

**Embossing.** Sculpture in rilievo, the figures standing partly out from the plane.

**Embrasure.** The opening in a battlement between the two raised solid portions or merlons, sometimes called a crenelle.

**Encaustic.** Pertaining to the art of burning in colors, applied to painting on glass, porcelain, or tiles, where colors are fixed by heat; hence, encaustic tiles, bricks, etc.

**Engaged Columns.** Are those attached to, or built into walls or piers, a portion being concealed.

**Enrichment.** The addition of ornament, carving, etc., to plain work; decoration; embellishment.

**Ensemble.** Means the whole work or composition considered together, and not in parts.

**Entablature.** The assemblage of parts supported by the column. It consists of three parts: the architrave, frieze, and cornice.

**Entail.** In Gothic architecture, delicate carving.

**Entasis.** The swelling of a column, etc. In mediæval architecture, some pires, particularly those called "broach spires," have a slight swelling in the sides, but no more than to make them look straight; for, from a particular *deceptio visus*, that which is quite straight, when viewed at a height, looks hollow.

**Entry.** A hall without stairs or vestibule.

**Epistyle.** This term may with propriety be applied to the whole entablature, with which it is synonymous; but it is restricted in use to the architrave, or lowest member of the entablature.

**Escutcheon.** (Her.) The field or ground on which a coat-of-arms is represented. (Arch.) The shields used on tombs, in the spandrels of doors, or in ring-courses; also, the ornamented plates from the centre of which door rings, knockers, etc., are suspended, or which protect the wood of the key-hole from the wear of the key. In mediæval times these were often worked in a very beautiful manner.

**Etching.** A mode of engraving on glass or metal (generally copper) by means of lines, eaten in or corroded by means of some strong acid.

**Eustyle.** A species of intercolumniation to which a proportion of two diameters and a quarter is assigned. This term, together with the others of similar import — *pycnostyle*, *systyle*, *diastyle*, and *aræostyle* — referring to the distance of columns from one another in composition, is from Vitruvius, who assigns to each the space it is to express. It will be seen, however, by reference to them individually, that the words themselves, though perhaps sufficiently applicable convey no idea of an exactly defined space, and, by reference to the columnar structures of the ancients, that no attention was paid by them to such limitations. It follows, then, that the proportions assigned to each are purely conventional, and may or may not be attended to without vitiating the power of applying the terms. Eustyle means the best or most beautiful arrangement; but, as the effect of a columnar composition depends on many things besides the diameter of the columns, the same proportioned intercolumniation would look well or ill according to those other circumstances, so that the limitation of Eustyle to two diameters and a quarter is absurd.

**Extrados.** The exterior or convex curve forming the upper line of the arch stones; the term is opposed to the *intrados*, or concave side.

**Eye of a Dome.** The aperture at its summit.

**Eye of a Volute.** The circle in its center.

**Façade, or Face.** The whole exterior side of a building that can be seen at one view; strictly speaking, the principal front.

**Face Mold.** The pattern for marking the plank or board out of which ornamental hand-railings for stairs and other works are cut.

**Fan Tracery.** The very complicated mode of roofing used in the Perpendicular style, in which the vault is covered by ribs and veins of tracery.

**Fascia.** A flat, broad member in the entablature of columns or other parts of buildings, but of small projection. The architraves in some of the orders are composed of three bands, or *fasciæ*; the Tuscan and the Doric ought to have only one. Ornamental projections from the walls of brick buildings over any of the windows, except the uppermost, are called *Fasciæ*.

**Fenestral.** A frame, or "chassis," on which oiled paper or thin cloth was strained to keep out wind and rain when the windows were not glazed.


**Festoon.** An ornament of carved work, representing a wreath or garland of flowers or leaves, or both, interwoven with each other. It is thickest in the middle, and small at each extremity, where it is tied, a part often hanging down below the knot.



FESTOON

**Fillet.** A narrow vertical band or listel of frequent use in congeries of moldings, to separate and combine them, and also to give breadth and firmness to the upper edge of a crowning cyma or cavetto, as in an external cornice. The narrow slips or breadth between the flutes of Corinthian and Ionic columns are also called fillets. In medieval work the fillet is a small, flat, projecting square, chiefly used to separate balustrades and rounds, and often found in the outer parts of shafts and boudoirs. In the situation the center fillet has been termed a keel, and the two side ones, wings, but, apparently, this is not an ancient usage.

**Finial.** The flower, or bunch of flowers, with which a spire, pinnacle, gable, canopy, etc., generally terminates. Where there are crockets, the finial generally bears as close a resemblance as possible to them in point of design. They are found in early work where there are no crockets. The simplest form more resembles a bud about to burst than an open flower. They soon became more elaborate, as at Lincoln, and still more, as at Westminster and the Hôtel Cluny at Paris. Many perpendicular finials are like four crockets bound together. Almost every known example of a finial has a sort of necking separating it from the parts below



FINIALS

**Fish-joint.** A splice where the pieces are joined butt end to end, and are connected by pieces of wood or iron placed on each side and firmly bolted to the timbers, or pieces joined.

**Flags.** Flat stones, from 1 to 3 inches thick, for floors.

**Flamboyant.** A name applied to the Third Pointed style in France, which seems to have been developed from the Second, as the English Perpendicular from the Decorated. The great characteristic is, that the element of the tracery flows upward in long wavy divisions like flames of fire. In most cases, also, every division has only one cusp on each side, however long the division may be. The moldings seem to be as much inferior to those of the preceding period as the Perpendicular moldings were to the Early English, a fact which seems to show that the decadence of Gothic architecture was not confined to one country.

**Flange.** A projecting edge, rib, or rim. Flanges are often cast on the top and bottom of iron columns, to fasten them to those above or below; the top and bottom of I-beams and channels are called the flange.

**Flashings.** Pieces of lead, tin, or copper, let into the joints of a wall so as to lap over gutters or other pieces; also, pieces worked in the slates or shingles around dormers, chimneys, and any rising part, to prevent leaking.

**Flatting.** Painting finished without leaving a gloss on the surface.

**Flèche.** A general term in French architecture for a spire, but more particularly used for the small, slender erection rising from the intersection of the nave and transepts in cathedrals and large churches, and carrying the sanctus bell.

**Fleur-de-lis.** The royal insignia of France, much used in decoration.

**Light.** A run of steps or stairs from one landing to another.

**Floating.** The equal spreading of plaster or stucco on the surface of walls, means of a board called a float; as a rule, only rough plastering is floated.

**Floriated.** Having florid ornaments, as in Gothic pillars.

**Flue.** The space or passage in a chimney through which the smoke ascends. Each passage is called a flue, while all together make the chimney.

**Flush.** The continued surface, in the same plane, of two contiguous masses.

**Flute.** A concave channel. Columns whose shafts are channeled are said to be fluted, and the flutes are collectively called Flutings.

**Flying Buttress.** An arched buttress used when extra strength was required to the upper part of the wall of the nave, etc., to resist the outward thrust of a vaulted ceiling. The flying buttress generally rests on the wall and buttress of an aisle.

**Foils.** The small arcs in the tracery of Gothic windows, panels, etc.

**Foliage.** An ornamental distribution of leaves on various parts of buildings.

**Foliation.** The use of small arcs or foils in forming tracery.

**Font.** The vessel used in the rite of baptism. The earliest extant is supposed to be that in which Constantine is said to have been baptized; this is a porphyry urn from a Roman bath. Those in the baptisteries in Italy are all large, and are intended for immersion; as time went on, they seem to have become smaller. Fonts are sometimes mere plain hollow cylinders, generally a little smaller below than above; others are massive squares, supported on a thick stem, and which sometimes there are smaller shafts. In the Early English this form was still pursued, and the shafts are detached; sometimes, however, they are hexagonal and octagonal, and in this and the later styles assume the form of a vessel on a stem. Norman fonts frequently have curious carvings on them, approaching the grotesque; in later times the foliages, etc., partook absolutely of the character of those used in other architectural details of their respective periods. The font in European churches is usually placed close to a pillar near the entrance, generally that nearest but one to the tower in the south arcade; or, in large buildings, in the middle of the nave, opposite the entrance porch, and sometimes in a separate building. In Protestant churches in this country, the font is generally placed inside the communion rail, or on the steps of the chancel.

**Footings.** The spreading courses at the base or foundation of a wall. When a layer of different material from that of the wall (as a bed of concrete) is used, it is called the Footing.

**Foundation.** That part of a building or wall which is below the surface of the ground.

**Foretail Wedging.** Is a peculiar mode of mortising, in which the end of the tenon is notched beyond the mortise, and is split and a wedge inserted, which, when forcibly driven in, enlarges the tenon and renders the joint firm and immovable.

**Frame.** The name given to the wood-work of windows, doors, etc.; and in carpentry, to the timber works supporting floors, roofs, etc.

**Framing.** The rough timber work of a house, including the flooring, roofing, partitioning, ceiling, and beams thereof.

**Freestone.** Stone which can be used for moldings, tracery, and other work required to be executed with the chisel. The oölitic and sandstones are those generally included by this term.

**Fresco.** The method of painting on a wall while the plastering is wet. The color penetrates through the material, which, therefore, will bear rubbing or rubbing to almost any extent. The transparency, the chiaro-oscuro, and lucidity, as well as force, which can be obtained by this method, cannot be conceived until the frescos of Fra Angelico or Raphael are studied. The word, however, is not applied improperly to painting on the surface in distemper or body color, mixed with size or white of egg, which gives an opaque effect.

**Fret.** An ornament consisting of small fillets intersecting each other at right angles.

**Frieze.** That portion of an entablature between the cornice above and architrave below. It derives its name from being the recipient of the sculptured enrichments either of foliage or figures which may be relevant to the object of the sculpture. The frieze is also called the Zoophry.



FRET

**Frigidarium.** An apartment in the Roman bath, supplied with cold water.

**Furniture.** A name given to the metal trimmings of doors, windows, and other similar parts of a house. In this country the word "hardware" is more generally used to denote the same thing.

**Furrings.** Flat pieces of timber used to bring an irregular framing to an even surface.

**Gable.** When a roof is not hipped or returned on itself at the ends, its ends are stopped by carrying up the walls under them in the triangular form of the roof itself. This is called the gable, or, in the case of the ornamental and ornamented gable, the pediment. Of necessity, gables follow the angles of the slope of the roof, and differ in the various styles. In Norman work they are generally about half-pitch; in Early English, seldom less than equilateral, and often more. In Decorated work they become lower, and still more so in the Perpendicular style. In all important buildings they are finished with copings or parapets. In the Later Gothic styles gables are often surmounted with battlements, or enriched with crockets; they are also often paneled or perforated, sometimes very richly. The gables in ecclesiastical buildings are mostly terminated with a cross; others, by a finial or pinnacle. In later times the parapets or copings were broken into a sort of steps, called corbic steps. In buildings of less pretension the tile or other roof covering passed over the front of the wall, which then, of course, had no coping. In this case, the outer pair of rafters were concealed by moldings or carved verge boards.

**Gable Window.** A term sometimes applied to the large window under a gable, but more properly to the windows in the gable itself.

**Gabled Towers.** Those which are finished with gables instead of parapets. Many of the German Romanesque towers are gabled.

**Gablets.** Triangular terminations to buttresses, much in use in the Early English and Decorated periods, after which the buttresses generally terminate in pinnacles. The Early English gablets are generally plain, and very sharp at pitch. In the Decorated period they are often enriched with paneling and crockets. They are sometimes finished with small crosses, but oftener with finials.

**Gain.** A beveled shoulder on the end of a mortised brace, for the purpose of giving additional resistance to the shoulder.

**Gallery.** Any long passage looking down into another part of a building, or into the court outside. In like manner, any stage erected to carry a rood or an organ, or to receive spectators, was latterly called a gallery, though originally

. In later times the name was given to any very long rooms, particularly those intended for purposes of state, or for the exhibition of pictures.

**Mansard Roof.** A roof with two pitches, similar to a mansard or curb roof.

**Gargoyle, or Gurgyle.** The carved termination of a spout which conveyed away the water from the roof, supposed to be called so from the gurgling noise made by the water passing through it. Gargoyles are mostly grotesque figures.

**Gate-house.** A building forming the entrance to a town, the door of an abbey, or the enceinte of a castle or other important edifice. They generally had a large gateway protected by a gate, and also a portico, over which were battlemented parapets with machicolations for throwing down darts, melted lead, or hot sand on the besiegers. Gate-houses always had a lodge, with apartments for the porter,

GARGOYLE

guard-rooms for the soldiers; and, generally, rooms over for the officers, and often places for prisoners beneath. The name is commonly applied to the gate-keeper's lodge on large estates.

**Gauge.** To mix plaster of Paris with common plaster to make it set quick, or to add gauged mortar. A tool used by carpenters, to strike a line parallel to the edge of a board.

**Header.** A large timber or iron beam, either single or built up, used to support joists or walls over an opening.

**Keyhole.** A vertical channel in a frieze.

**Gothic Style.** The name of Gothic was given to the various Mediæval styles of a period in the sixteenth century when a great classic revival was going on, and everything not classic was considered barbarian, or Gothic. The term was originally intended as one of stigma, and, although it conveys a false idea of the character of the Mediæval styles, it has long been used to distinguish them from the Grecian and Roman. The true principle of Gothic architecture is the logical division, relation and subordination of the different parts, distinct and yet in unity with each other, and while this principle was adhered to, Gothic architecture may be said to have retained its vitality.

**Grange.** A word derived from the French, signifying a large barn or granary. Granges were usually long buildings with high wooden roofs, sometimes divided by posts or columns into a sort of nave and aisles, with walls strongly buttressed. In England the term was applied not only to the barns, but to the whole of the buildings which formed the detached farms belonging to the monasteries; in some cases there was a chapel either included among these or standing apart as a separate edifice.

**Grillage.** A framework of beams laid longitudinally and crossed by similar beams notched upon them, used to sustain walls to prevent irregular settling.

**Grille.** The iron-work forming the enclosure screen to a chapel, or the protecting railing to a tomb or shrine; more commonly found in France than in England. They are of wrought iron, ornamented by the swage and punch, and put together either by rivets or clips. In modern times grilles are used extensively for protecting the lower windows in city houses, also the glass opening in iron doors.

**Groin.** By some described as the line of intersection of two vaults where they meet each other, which others call the groin point; by others the curved section



of spandrel of such vaulting is called a groin, and by others the whole system of vaulting is so named.

**Groin Arch.** The cross-rib in the later styles of groining, passing at right angles from wall to wall, and dividing the vault into bays or travees.


**Groin Ceiling.** A ceiling to a building composed of oak ribs, the spandrels of which are filled in with narrow, thin slips of wood. There are several in England; one at the Early English church at Warmington, and one at Winchester Cathedral, exactly resembling those of stone.

**Groin Centring.** In groining without ribs, the whole surface is supported by centring during the erection of the vaulting. In ribbed work the stone ribs only are supported by timber ribs during the progress of the work, any light stuff being used while filling in the spandrel.

**Groin Point.** The name given by workmen to the arris or line of intersection of one vault with another where there are no ribs.

**Groin Rib.** The rib which conceals the groin point or joints, where the spandrels intersect.

**Groined Vaulting.** The system of covering a building with stone vault which cross and intersect each other, as opposed to the barrel vaulting, or series of arches placed side by side. The earliest groins are plain, without any ribs except occasionally a sort of wide band from wall to wall, to strengthen the construction. In later Norman times ribs were added on the line of intersection of the spandrels, crossing each other, and having a boss as a key common to both. These ribs the French authors call *nerfs en ogive*. Their introduction, however, caused an entire change in the system of vaulting; instead of arches of uniform thickness and great weight, these ribs were first put up as the main construction, and spandrels of the lightest and thinnest possible material placed upon them. The haunches only being loaded sufficiently to counterbalance the pressure from the crown. Shortly after, half-ribs against the walls (*formerets*) were introduced to carry the spandrels without cutting into the walling, and to add to the appearance. The work was now not treated as continued vaulting, but as divided into bays, and it was formed by keeping up the ogive, or intersecting ribs and their bosses, a sort of construction having some affinity to the dome was formed, which added much to the strength of the groining. Of course, the top of the soffit or ridge of the vault was not horizontal, but rose from the level of the top of the formerets to the boss and fell again; but this could not be perceived from below. As the system of construction got more into use, and as the vaults were required to be of greater span and of higher pitch, the spandrels became larger, and required more support. To give this, another set of ribs was introduced, passing from the springers of the ogive ribs, and going to about half-way between these and the ogive, and meeting on the ridge of the vault; these intermediate ribs are called by the French *tiercerons*, and began to come into use in the transition from Early English to Decorated. About the same period a system of vaulting came into use called *hexpartite*, from the fact that every bay is divided into six compartments instead of four. It was invented to cover the naves of churches of unusual width. The filling of the spandrels in this style is very peculiar, and, where the different compartments meet at the ridge, some pieces of harder stone have been used, which give rather a pleasing effect. The arches against the walls being of smaller span than the main arches, cause the centre springers to be



GROINED VAULTING



dicular and parallel for some height, and the spandrels themselves are very low. As styles progressed, and the desire for greater richness increased, the series of ribs, called *liernes*, was introduced; these passed crossways from *ogives* to the *tiercerons*, and thence to the *doubleaux*, dividing the spandrels nearly horizontally. These various systems increased in the Perpendicular period, so that the walls were quite a net-work of ribs, and led at last to the florid, or, as it is called by many, fan-tracery vaulting. In this system the ribs are no part of the real construction, but are merely carved upon the *voussoirs*, which form the actual vaulting. Fan Tracery is so called because the ribs radiate from the springers, and spread out like the sticks of a fan. These later methods are not strictly groins, for the pendentives are not square on plan, but circular, and there is, therefore, no arris intersection or groin point.

**Groins, Welsh, or Underpitch.** When the main longitudinal vault of any building is higher than the cross or transverse vaults which run from the windows, this system of vaulting is called underpitch groining, or, as termed by the workmen, Welsh groining. A very fine example is at St. George's Chapel, Windsor, England.

**Groove.** In joinery, a term used to signify a sunk channel whose section is semicircular. It is usually employed on the edge of a molding, stile, or rail, into which a tongue corresponding to its section, and in the substance of the wood to which it is joined, is inserted.

**Grotesque.** A singular and fantastic style of ornament found in ancient buildings.

**Grotto.** An artificial cavern.

**Ground Floor.** The floor of a building on a level, or nearly so, with the ground.


**Ground Joist.** Joist that is blocked up from the ground.

**Grounds.** Pieces of wood embedded in the plastering of walls to which painting and other joiner's work is attached. They are also used to stop the plastering around door and window openings.

**Grouped Columns.** Three, four, or more columns put together on the same pedestal. When two are placed together, they are said to be coupled.

**Grout.** Mortar made so thin by the addition of water that it will run into all the joints and cavities of the mason-work, and fill it up solid.


**Gulloche, or Gullochos.** An interlaced ornament like net-work, used most frequently to enrich the torus.



GULLOCHE

**Guttæ.** The small cylindrical drops used to enrich the mutules and regulæ of the Doric entablature are so called.

**Gutter.** The channel for carrying off rain-water. The mediæval gutters differed little from others, except that they are often hollows sunk in the top of stone chimes, in which case they are generally called channels in English, and *cheneaux* in French.



GUTTÆ

**Gymnasium.** A building classed in the first rank by the Greeks; it was in them they instructed the youth in all the arts of peace and war; a building for athletic exercises.

**Hall.** The principal apartment in the large dwellings of the Middle Ages, used for the purposes of receptions, feasts, etc. In the Norman castles it was generally in the keep above the ground floor, where the retained basement being devoted to stores and dungeons for confining prisoners. Halls — indeed, some Norman halls (not in castles) — are generally on the ground floor, as at Westminster, approached by a porch either at the end, as at the example, or at the side, as at Guildhall, London, having at one end a raised floor or estrade. The roofs are generally open and more or less ornamented. In the middle of these was an opening to let out the smoke, though in later halls have large chimney-places with funnels or chimney-shafts for the smoke. At this period there were usually two deeply recessed bay windows at the ends of the dais, and doors leading into the withdrawing-rooms, or the bed-chambers; they are also generally wainscoted with oak, in small panels, two or three of five or six feet, the panels often being enriched. Westminster Hall was originally divided into three parts, like a nave and side aisles, as are halls on the Continent of Europe. A room or passage-way at the entrance of a suite of chambers. A place of public assembly, as a town-hall, a market-place, etc.

**Halving.** The junction of two pieces of timber, by letting one into the other.

**Hammer Beam.** A beam in a Gothic roof, not extending to the ends of the side; a beam at the foot of a rafter.

**Hanging Buttress.** A buttress not rising from the ground, but supported by a corbel, applied chiefly as a decoration and used only in the Decorated and Perpendicular style.

**Hanging Stile.** Of a door, is that to which the hinges are fixed.

**Hangings.** Tapestry; originally invented to hide the coarseness of the walls of a chamber. Different materials were employed for this purpose, but they were then exceedingly costly and beautifully worked in figures, gold and silver.

**Hatching.** Drawing parallel lines close together for the purpose of shading a section of anything. The lines are generally drawn at an angle of 45 degrees to a horizontal.

**Haunches.** The sides of an arch, about half-way from the springing to the crown.

**Headers.** In masonry, are stones or bricks extending over the thickness of a wall. In carpentry, the large beam into which the common joists are framed in framing openings for stairs, chimneys, etc.

**Heading Courses.** Courses of a wall in which the stone or brick are all headers.

**Head-way.** Clear space or height under an arch, or over a stairway, and the like.

**Heel.** Of a rafter, the end or foot that rests upon the wall plate.

**Height.** Of an arch, a line drawn from the middle of the chord to the intrados.

**Helix.** A small volute or twist like a stalk, representing the twisted tops of the acanthus, placed under the abacus of the Corinthian capital.

**Hermes.** A rough quadrangular stone or pillar, having a head, usually of Hermes or Mercury, sculptured on the top, without arms or body, placed by the Greeks in front of buildings.



**ing-bone Work.** Bricks, tile, or other materials arranged diagonally  
ling.

**astyle.** A portico of six columns in front is of this description.

**Altar.** The principal altar in a cathedral or church. Where there is a  
it is generally at the end of the choir or chancel, not in the lady chapel.

**knob.** The finial on the hip of a roof, or between the barge boards of a

**roof.** A roof which rises by equally inclined planes from all four sides  
building.

**podrome.** A place appropriated by the ancients for equestrian exercises.

**s.** Those pieces of timber placed in an inclined position at the corners or  
of a hip-roof.

**ed-mold.** A word used to signify the drip-stone for label over a window  
opening, whether inside or out.

**al de Ville.** The town-hall, or guild-hall, in France, Germany, and  
ern Italy. The building, in general, serves for the administration of justice,  
ceipt of town dues, the regulation of markets, the residence of magistrates,  
ks for police, prisons, and all other fiscal purposes. As may be imagined,  
differ very much in different towns, but they have almost invariably  
ed to them, or closely adjacent, a large clock-tower containing one or  
bells, for calling the people together on special occasions.

**tel Dieu.** The name for a hospital in mediæval times. In England there  
at few remains of these buildings, one of which is at Dover; in France there  
any. The most celebrated is the one at Angers, described by Parker.  
do not seem to differ much in arrangement of plan from those in modern  
the accommodation for the chaplain, medicine, nurses, stores, etc., being  
the same in all ages, except that in some of the earlier, instead of the sick  
placed in long wards like galleries, as is now done, they occupied large  
ings, with naves and side aisles, like churches.

**using.** The space taken out of one solid to admit the insertion of another.  
base on a stair is generally housed into the treads and risers; a niche for a  
e.

**pæthros.** A temple open to the air, or uncovered. The term may be the  
easily understood by supposing the roof removed from over the nave of a  
h in which columns or piers go up from the floor to the ceiling, leaving the  
s still covered.

**pozea.** Constructions under the surface of the earth, or in the sides of a  
r mountain.

**anography.** A horizontal section of a building or other object, showing its  
dimensions according to a geometric scale, a ground plan.

**pluvium.** The central part of an ancient Roman court, which was un-  
red.

**post.** A term in classic architecture for the horizontal moldings of piers  
ilasters, from the top of which spring the archivolts or moldings which go  
d the arch.

**Antis.** When there are two columns between the antæ of the lateral walls  
the cella.

**cise.** To cut in; to carve; to engrave.

**dent.** Toothed together.

**Inlaying.** Inserting pieces of ivory, metal, or choice woods, or the like, in a groundwork of some other material, for ornamentation.

**Insulated.** Detached from another building. A church is insulated, when contiguous to any other edifice. A column is said to be insulated, when standing free from the wall; thus, the columns of peripteral temples were insulated.

**Intaglio.** A sculpture or carving in which the figures are sunk below the general surface, such as a seal the impression of which in wax is in bas-relief; opposed to Cameo.

**Intercolumniation.** The distance from column to column, the clear space between columns.

**Interlaced Arches.** Arches where one passes over two openings, and the consequently cut or intersect each other.

**Intrados.** Of an arch, the inner or concave curve of the arch stones.

**Inverted Arches.** Those whose key-stone or brick is the lowest in the arch.

**Ionic Order.** One of the orders of Classical architecture.

**Iron Work.** In mediæval architecture, as an ornament, is chiefly confined to the hinges, etc., of doors and of church chests, etc. In some instances not only do the hinges become a mass of scroll work, but the surface of the doors is covered by similar ornaments. In almost all styles the smaller and less important doors had merely plain strap hinges, terminating in a few bent scrolls, and latterly in fleurs-de-lis. Escutcheon and ring handles, and the other furniture, partook more or less of the character of the time. On the Continent of Europe the knockers are very elaborate. At all periods doors have been ornamented with nails having projecting heads, sometimes square, sometimes polygonal, and sometimes ornamented with roses, etc. The iron work of windows is generally plain and the ornament confined to simple fleur-de-lis heads to the stanchions. The iron work of screens enclosing tombs and chapels is noticed under *Grille*, &c.

**Jack.** An instrument for raising heavy loads, either by a crank, screw, or pinion, or by hydraulic power, and in all cases worked by hand.

**Jack Rafter.** A short rafter, used especially in hip-roofs.

**Jamb.** The side-post or lining of a doorway or other aperture. The jamb of a window outside the frame are called Reveals.

**Jamb-shafts.** Small shafts to doors and windows with caps and bases; when in the inside arris of the jamb of a window they are sometimes called Escamots.

**Joggle.** A joint between two bodies so constructed by means of jogs and notches as to prevent their sliding past each other.

**Joinery.** That branch in building confined to the nicer and more ornamental parts of carpentry.

**Joist.** A small timber to which the boards of a floor or the laths of ceiling are nailed. It rests on the wall or on girders.

**Keep.** The inmost and strongest part of a mediæval castle, answering to the citadel of modern times. The arrangement is said to have originated with Gundulf, the celebrated Bishop of Rochester. The Norman keep is generally a massive square tower, the basement or stories partly below ground being used for stores and prisons. The main story is generally a great deal above ground level, with a projecting entrance, approached by a flight of steps and drawbridge. This floor is generally supposed to have been the guard-room or place of assembly for soldiery; above this was the hall, which generally extended over the whole of the building, and is sometimes separated by columns; above this are other apartments for the residents. There are winding staircases in the angles of the

**Buildings, and passages and small chambers in the thickness of the walls.** The keep was intended for the last refuge, in case the outworks were scaled and the other buildings stormed. There is generally a well in a mediæval keep, ingeniously concealed in the thickness of a wall, or in a pillar. The most celebrated of Norman times are the White Tower in London, the castles at Rochester, Lundel, and Newcastle, Castle Hedingham, etc. The keep was often circular.

**Key-stone.** The stone placed in the center of the top of an arch. The character of the key-stone varies in different orders. In the Tuscan and Doric it is only a simple stone projecting beyond the rest; in the Ionic it is adorned with moldings in the manner of a console; in the Corinthian and Composite it is a rich-sculptured console.

**King-post.** The middle post of a trussed piece of framing for supporting the rafter-beam at the middle and the lower ends of the struts.

**Knee.** A piece of timber naturally or artificially bent to receive another to relieve a weight or strain.

**Knob, Knot.** The bunch of flowers carved on a corbel, or on a Boss.

**Kremlin.** The Russian name for the citadel of a town or city.

**Label.** Gothic: the drip or hood-molding of an arch, when it is returned to the square.

**Label Terminations.** Carvings on which the labels terminate near the springing of the windows. In Norman times those were frequently grotesque heads of fish, birds, etc., and sometimes stiff foliage. In the Early English and decorated periods they are often elegant knots of flowers, or heads of kings, queens, bishops, and other persons supposed to be the founders of churches. In the Perpendicular period they are often finished with a short square, mitred return or knee, and the foliage are generally leaves of square or octagonal form.

**Lacunar.** A paneled or coffered ceiling or soffit. The panels or caseons of ceiling are by Vitruvius called lacunaria.

**Lady-chapel.** A small chapel dedicated to the Virgin Mary, generally found in ancient cathedrals.

**Lancet.** A high and narrow window pointed like a lancet, often called a lancet window.

**Landing.** A platform in a flight of stairs between two stories; the terminating of a stair.

**Lantern.** A turret raised above a roof or tower and very much pierced, the better to transmit light. In modern practice this term is generally applied to a small, square or polygonal, raised part in a roof or ceiling containing vertical windows, but covered in horizontally. The name was also often applied to the cover or femerell on a roof to carry off the smoke; sometimes, too, to the open constructions at the top of towers, as at Ely Cathedral, probably because lights are placed in them at night to serve as beacons.

**Lanterns of the Dead.** Curious small slender towers, found chiefly in the north and west of France, having apertures at the top, where a light was exhibited at night to mark the place of a cemetery. Some have supposed that the round towers in Ireland may have served for this purpose.

**Lath.** A slip of wood used in slating, tiling, and plastering.

**Lattice.** Any work of wood or metal made by crossing laths, rods, or bars, so as to form a net-work. A reticulated window, made of laths or slips of iron,

separated by glass windows, and only used where air rather than light is to be admitted, as in cellars and dairies.

**Lavabo.** The lavatory for washing hands, generally erected in cloisters of monasteries. A very curious one at Fontenay, surrounding a pillar, is given by Viollet-le-Duc. In general, it is a sort of trough, and in some places has an almy for towels, etc.

**Lavatory.** A place for washing the person.

**Lean-to.** A small building whose rafters pitch or lean against another building, or against a wall.

**Lectern.** The reading-desk in the choir of churches.

**Ledge, or Ledge ment.** A projection from a plane, as slips on the side of window and door frames to keep them steady in their places.

**Ledgers.** The horizontal pieces fastened to the standard poles or timbers of scaffolding raised around buildings during their erection. Those which rest on the ledgers are called putlogs, and on these the boards are laid.

**Lewis.** An iron clamp dovetailed into a large stone to lift it by.

**Lich-gate.** A covered gate at the entrance of a cemetery, under the shelter of which the mourners rested with the corpse, while the procession of the clergy came to meet them. There are several examples in England.

**Light.** A division or space in a sash for a single pane of glass; also a pane of glass.

**Linen Scroll.** An ornament formerly used for filling panels, and so called from its resemblance to the convolutions of a folded napkin.

**Lining.** Covering for the interior, as casing is covering for the exterior surface of a building; also, such as linings of a door for windows, shutters, and similar work.



LINEN SCROLL

**Lintel.** The horizontal piece which covers the opening of a door or window.

**Lip Mold.** A molding of the Perpendicular period like a hanging lip.

**List, or Listel.** A little square molding, to crown a larger; also termed a fillet.

**Lithograph.** A print from a drawing on stone.

**Lobby.** An open space surrounding a range of chambers, or seats in a theatre; a small hall or waiting room.

**Lodge.** A small house in a park.

**Loft.** The highest room in a house, particularly if in the roof; also, a gallery raised up in a church to contain the rood, the organ, or singers.

**Loggia.** An outside gallery or portico above the ground, and contained within the building.

**Loop-hole.** An opening in the wall of a building, very narrow on the outside and splayed within, from which arrows or darts might be discharged at an enemy. They are often in the form of a cross, and generally have round holes at the ends.

**Lombard Architecture.** A name given to the round-arched architecture of Italy, introduced by the conquering Goths and Ostrogoths, and which superseded the Romanesque. It reigned between the eighth and twelfth centuries, during the time that the Saxon and Norman styles were in vogue in England, and corresponded with them in its development into the Continental Gothic.

**Lotus.** A plant of great celebrity amongst the ancients, the leaves and blossoms of which generally form the capitals of Egyptian columns.

**Louver.** A kind of vertical window, frequently in the peaks of gables, and in the top of towers, and provided with horizontal slats which permit ventilation and exclude rain.

**Lozenge Molding.** A kind of molding used in Norman architecture, of many different forms, all of which are characterized by lozenge-shaped ornaments.

**Lunette.** The French term for the circular opening in the roining of the lower stories of towers, through which the bells are drawn up.



LOZENGE MOLDING

**Machicolation.** A parapet or gallery projecting from the upper part of the wall of a house or fortification, supported by brackets or corbels, and perforated in the lower part so that the defenders of the building might throw down darts, stones, and sometimes hot sand, molten lead, etc., upon their assailants below.

**Man-hole.** A hole through which a man may creep into a drain, cesspool, steam-boiler, etc.

**Manor-house.** The residence of the suzerain or lord of the manor; in France the central tower or keep of a castle is often called the *manoir*.

**Mansard Roof.** Curb roof, invented by François Mansard, a distinguished French architect, who died in 1666.

**Mansion.** A residence of considerable size and pretension.

**Mantel.** The work over a fireplace in front of a chimney; especially, a shelf, usually ornamented, above the fireplace.

**Marquetry.** Inlaid work of fine hard pieces of wood of different colors, also of shells, ivory, and the like.

**Mausoleum.** A magnificent tomb or sumptuous sepulchral monument.

**Medallion.** Any circular tablet on which are embossed figures or busts.



MACHICOLATION

**Mediæval Architecture.** The architecture of England, France, Germany, etc., during the Middle Ages, including the Norman and Early Gothic styles. It comprises also the Romanesque, Byzantine and Saracenic, Lombard, and other styles.

**Members.** The different parts of a building, the different parts of an entablature, the different moldings of a cornice, etc.

**Merlon.** That part of a parapet which lies between two embrasures.

**Metope.** The square recess between the triglypus in Doric frieze. It is sometimes occupied by sculptures.

**Mezzanine.** A low story between two lofty ones; is called by the French *entresol*, or inter-story.

**Mezzo-rilievo.** Or mean relief, in comparison with alto-rilievo, or high relief.



METOPE

**Minaret.** Turkish: a circular turret rising by different stages or divisions, each of which has a balcony.

**Minster.** Probably a corruption of *monasterium* — the large church attached to any ecclesiastical fraternity. If the latter be presided over by a bishop, it is generally called a Cathedral; if by an abbot, an Abbey; if by a prior, a Priory.

**Minute.** The sixtieth part of the lower diameter of a column; it is the measure used by architects to determine the proportions of an order.

**Miserere.** A seat in a stall of a large church made to turn up and afford support to a person in a position between sitting and standing. The under side is generally carved with some ornament, and very often with grotesque figures and caricatures of different persons.

**Miter.** A molding returned upon itself at right angles is said to miter. In joinery, the ends of any two pieces of wood of corresponding form, cut off at  $45^\circ$ , necessarily abut upon one another so as to form a right angle, and are said to miter.

**Modillion.** So called because of its arrangement in regulated distances; the enriched block or horizontal bracket generally found under the cornice of the Corinthian entablature. Less ornamented, it is sometimes used in the Ionic.

**Module.** This is a term which has been generally used by architects in determining the relative proportions of the various parts of a columnar ordinance. The semi-diameter of the column at its base is the module, which being divided into thirty parts called minutes, any part of the composition is said to be of so many modules and minutes, or minutes alone, in height, breadth, or projection. The whole diameter is now generally preferred as a module, it being a better rule of proportion than its half.

**Monastery.** A set of buildings adapted for the reception of any of the various orders of monks, the different parts of which are described in the separate article, *Abbey*.

**Monotriglyph.** The intercolumniations of the Doric order are determined by the number of triglyphs which intervene, instead of the number of diameters of the column, as in other cases; and this term designates the ordinary intercolumniation of one triglyph.

**Monument.** A name given to a tomb, particularly to those fine structures recessed in the walls of mediæval churches.

**Mosaic.** Pictorial representations, or ornaments, formed of small pieces of stone, marble, or enamel of various colors. In Roman houses the floors are entirely of mosaic, the pieces being cubical. The best examples of mosaic work are found in St. Mark's, at Venice.

**Mosque.** A Mahometan temple, or place of worship.

**Molding.** When any work is wrought into long regular channels or projections, forming curves or rounds, hollows, etc., it is said to be molded, and each separate member is called a molding. In mediæval architecture the principal moldings are those of the arches, doors, windows, piers, etc. In the Early English style, the moldings, for some time, formed groups set back in square, and frequently very deeply undercut. The scroll molding is also common.




MINARET



MODILLION



all fillets now become very frequent in the keel molding, from its resemblance to the bottom of a ship; sometimes, also, it has a peculiar hollow on its side, like two wings. Later in the Decorated style the moldings are more varied in design, though hollows and rounds still prevail. The undercutting is so deep, fillets abound, ogees are more frequent, the wave mold, double ogee, or double ressaunt, is often seen. In many places the strings and labels are rounded, the lower half of which is cut off by a plain surface. The moldings in the later styles in some degree resemble those of the Decorated, flattened and rounded; they run more into one another, having fewer fillets, and being, as it were, less grouped. One of the principal features of the change is the substitution of one, or perhaps two (seldom more), large hollows in the set of moldings. These hollows are neither circular nor elliptical, but obovate, like an egg cut across, so that one half is larger than the other. The brace mold also has a small hollow, where the two ogees meet. Another sort of molding, which has been called a lip mold, is common in parapets, bases, and other things.



MOLDINGS

*a*, astragal; *b*, ogee; *c*, cymatium; *d*, cavetto; *e*, scotia, or case-ment; *f*, apophyges; *g*, ovolo, or quarter round; *h*, torus; *i*, reeding; *j*, band.

**Moldings, Ornamented.** The Saxon and early Norman moldings do not seem to have been much enriched, but the complete and later styles of Norman are remarkable for a profusion of ornamentation, the most usual of which is that called the zigzag. This seems to be to Norman architecture what the under or fret was to the Grecian; but it was probably derived from the Persians, as it is very frequently found in their pottery. Bezants, quatrefoils, arabesques, crescents, billets, heads of nails, are very common ornaments. Besides these, battlements, cables; large ropes round which smaller ropes are turned, or, as sailors say, "wormed"; scallops, pellets, chains, a sort of conical barrels, and stiff foliages, beaks of birds, heads of fishes, ornaments of almost every conceivable kind, are sculptured in Norman moldings; and they are used in such profusion as has been attempted in no other style. The decorations on Early English moldings are chiefly the dog-tooth, which is one of the great characteristics of this style, though it is to be found in the Transition Norman. It is usually placed in a deep hollow between two projecting moldings, the dark shadow in the hollow contrasting in a very beautiful way with the light in these projections. In this period and in the next the tympanum over doorways, particularly if they are double doors, is highly ornamented. Those of the Decorated style resemble the former, except that the foliage is more natural and the dog-tooth gives way to the ball-flower. Some of the hollows, also, are ornamented with rosettes set at intervals, which are sometimes connected by a running tendril, and the ball-flowers are frequently. Some very pleasing leaf-like ornaments in the tracery of windows are often found in Continental architecture. In the Perpendicular period the moldings are ornamented very frequently by square four-lobed flowers set at intervals, but the two characteristic ornaments of the time are running patterns of vine leaves, tendrils, and grapes in the hollows, which old writers are called "vignettes in casements," and upright stiff leaves, usually called the Tudor leaf. On the Continent moldings partook much of the same character.

**Column, Munion.** The perpendicular pieces of stone, sometimes like columns, sometimes like slender piers, which divide the bays or lights of windows

**o screen-work** from each other. In all styles, in less important work, the lions are often simply plain chamfered, and more commonly have a very flat low on each side. In larger buildings there is often a bead or boutell on the top and often a single very small column with a capital. As tracery grew richer, windows were divided by a larger order of mullion, between which came a lesser or subordinate set of mullions, which ran into each other. The term is also applied to a wood or iron division between two windows.

**Multifoil.** A leaf ornament consisting of more than five divisions, applied to foils in windows.

**Mutule.** The rectangular impending block under the corona of the Doric cornice, from which guttæ or drops depend. Mutule is equivalent to modillions but the latter term is applied more particularly to enriched blocks or brackets such as those of Ionic and Corinthian entablatures.

**Narthex.** The long arcaded porch forming the entrance into the Christian basilica. Sometimes there was an inner narthex, or lobby, before entering the church. When this was the case, the former was called *exo-narthex*, and the latter *eso-narthex*. In the Byzantine churches this inner narthex forms part of the solid structure of the church, being marked off by a wall or row of columns, whereas in the Latin churches it was usually formed only by a wooden or other temporary screen.

**Natural Beds.** In stratified rocks, the surface of a stone as it lies in the quarry. If not laid in walls in their natural bed the laminæ separate.

**Nave.** The central part between the arches of a church, which formerly was separated from a chancel or choir by a screen. It is so called from its fancied resemblance to a ship. In the nave were generally placed the pulpit and altar. In continental Europe it often also contains a high altar, but this is of rare occurrence in England.

**Necking.** The annulet or round, or series of horizontal moldings, which separate the capital of a column from the plain part or shaft.

**Newel.** In mediæval architecture, the circular ends of a winding stair, which stand over each other, and form a sort of cylindrical column.

**Newel Post.** The post, plain or ornamented, placed at the first, or last step, to receive or start the hand-rail upon.

**Niche.** A recess sunk in a wall, generally for the reception of a statue. Niches sometimes terminate by a simple label, but more commonly by a canopy and with a bracket or corbel for the figure, in which case they are often called *tabernacles*.

**Norman Style.** Was that species of Romanesque which was practised by the Normans, and which was introduced and fully developed in England after they had established themselves in it. The chief features of this style are plainness and massiveness. The arches, windows, and doorways were semicircular. The pillars were very massive, and often built up of small stones laid like bricks.

**Nosings.** The rounded and projecting edges of the treads of a stair, or the edge of a landing.

**Obelisk.** Lofty pillars of stone, of a rectangular form, diminishing towards the top, and generally ornamented with inscriptions and hieroglyphics among the ancient Egyptians.

**Observatory.** A building erected on an elevated spot of ground for making astronomical observations.

**Octostyle.** A portico of eight columns in front.

- Offsets.** When the face of a wall is not one continued surface, but sets in by horizontal jogs, as the wall grows higher and thinner, the jogs are called offsets.
- Ogee.** The name applied to a molding, partly a hollow and partly a round, derived no doubt from its resemblance to an O placed over a G. It is rarely found in Norman work, and is not very common in Early English. It is of frequent use in Decorated work, where it becomes sometimes double, and is called a wave molding; and later still, two waves are connected with a small bead, which has been called a brace molding. In ancient MSS. it is called a Ressaunt.
- Orchestra.** In ancient theaters, where the chorus used to dance; in modern theaters, where the musicians sit.
- Order.** A column with its entablature and stylobate is so called. The term is the result of the dogmatic laws deduced from the writings of Vitruvius, and has been exclusively applied to those arrangements which they were thought to warrant.
- Oriel Window.** Gothic: a projecting angular window, commonly of a triangular or pentagonal form, and divided by mullions and transoms into different lights and compartments.
- Orthography.** A geometrical elevation of a building or other object in which it is represented as it actually exists or may exist, and not perspectively, or as it would appear.
- Orthostyle.** A columnar arrangement in which the columns are placed in a straight line.
- Ovolo.** Same as *Echinus*.
- Pagoda.** A name given to temples in India and China.
- Palace.** The dwelling of a king, prince, or bishop.
- Pale.** A fence picket, sharpened at the upper end.
- Pane.** Probably a diminutive of *panneau*, a term applied to the different pieces of glass in a window; same as *Light*.
- Panel.** Properly a piece of wood framed within four other pieces of wood, as the styles and rails of a door, filling up the aperture, but often applied both to the whole square frame and the sinking itself; also to the ranges of sunken compartments in wainscoting, cornices, corbel tables, groined vaults, ceilings, etc.
- Pantograph, or Pentagraph.** An instrument for copying on the same, or an enlarged or reduced scale.
- Pantry.** An apartment or closet in which bread and other provisions are kept.
- Papier-maché.** A hard substance made of a pulp from rags or paper mixed with size or glue, and molded into any desired shape. Much used for architectural ornaments.
- Parapet.** A dwarf wall along the edge of a roof, or round a terrace walk, etc., to prevent persons from falling over, and as a protection to the defenders in case of siege. Parapets are either plain, embattled, perforated, or paneled. The first two are found in all styles except the Norman. Plain parapets are simply projections of the wall generally overhanging a little, with coping at the top and a level table below. Embattled parapets are sometimes paneled, but oftener left plain for the discharge of arrows, etc. Perforated parapets are pierced in various devices — as circles, trefoils, quatrefoils, and other designs — so that the interior is seen through. Paneled parapets are those ornamented by a series of panels, either oblong or square, and more or less enriched, but are not perforated. They are common in the Decorated and Perpendicular periods.

**Pargeting.** A species of plastering decorated by impressing patterns on when wet. These seem generally to have been made by sticking a number of pins in a board in certain lines or curves, and then pressing on the wet plaster in various directions, so as to form geometrical figures. Sometimes these designs are in relief, and in the time of Elizabeth represent figures, birds, foliage, &c. **Rough plastering,** commonly adopted for the interior surface of chimneys.

**Parlor.** A room in a house which the family usually occupy for society and conversation, and for receiving visitors. The apartment in a monastery or nunnery where the inmates are permitted to meet and converse with each other, or with visitors and friends from without.

**Parochial.** Belonging or relating to a parish.


**Parquetry, or Marquetry.** A kind of inlaid floor composed of small pieces of wood either square or triangular, which are capable of forming, by their position, various combinations of figures; this description of joinery is well suited for the floors of libraries, halls, and public apartments.

**Party Walls.** Partitions of brick or stone between buildings on two adjoining properties.

**Patera.** A circular ornament resembling a dish, often worked in relief on friezes, etc.

**Pavement.** Tessellated, a pavement of mosaic work, used by the ancients, made of square pieces of stone, etc., called Tessera.

**Pavilion.** A turret or small insulated building, and comprised beneath a single roof; also, the projecting part in front of a building which marks the centre, and which sometimes flanks a corner, when it is termed an angular pavilion.



PATERA

**Pedestal.** The square support of a column, statue, etc.; and the base or lower part of an order of columns: it consists of a plinth for a base, the die, and a talon crowned for a cornice. When the height and width are equal, it is termed a square pedestal; one which supports two columns is a double pedestal; and if it supports a row of columns without any break, it is a continued pedestal.

**Pediment.** A low triangular crowning, ornamented, in front of a building and over doors and windows. Pediments are sometimes made in the form of a segment; the space enclosed within the triangle is called the tympanum. At the gable ends of classic buildings, where the horizontal cornice is carried around the front, forming a triangle with the end of the roof.

**Pendent.** A name given to an elongated boss, either molded or foliated, such as hang down from the intersection of groins, especially in fan tracery, at the end of hammer beams. Sometimes long corbels, under the wall piers, have been so called. The name has also been given to the large masses depending from enriched ceilings, in the later works of the Pointed style.

**Pendent Posts.** A name given to those timbers which hang down the side of a wall from the plate in hammer beam trusses, and which receive the hammer braces.

**Pendentive.** A name given to an arch which cuts off, as it were, the corner of a square building internally, so that the superstructure may become an octagon or a dome. In mediæval architecture these arches, when under a spire in the interior of a tower, are called Squinches.

**Pendentive Bracketing, or Cove Bracketing.** Springing from the rectangular walls of an apartment upward to the ceiling, and forming the horizontal part of the ceiling into a circle or ellipse.

**Pentastyle.** Having five columns in front.

**Pent-roof.** A roof with a slope on one side only.

**Perch.** A measure used in measuring stone work, being  $24\frac{3}{4}$  cu ft and  $16\frac{3}{4}$  ft, according to locality and custom.

**Periptery.** An edifice or temple surrounded by a peristyle.

**Peristyle.** A range of columns encircling an edifice, such as that which surrounds the cylindrical drum under the cupola of St. Paul's. The columns of a Greek peripteral temple form a peristyle also, the former being a circular, and the latter a quadrilateral peristyle.

**Perpendicular Style.** The third and last of the Pointed or Gothic styles; so called the Florid style.

**Perspective Drawing.** The art of making such a representation of an object on a plane surface as shall present precisely the same appearance that the object itself would to the eye situated at a particular point.

**Pews.** A word of uncertain origin, signifying fixed seats in churches, composed of wood framing, mostly with ornamented ends. They seem to have come to general use early in the reign of Henry VI, and to have been rented and well paid for" before the Reformation. Some bench ends are certainly of a decorated character, and some have been considered to be of the Early English kind. They are sometimes of plain oak board, two and a half to three inches thick, chamfered, and with a necking and finial, generally called a poppy head; others are plainly paneled with bold cappings; in others the panels are ornamented with tracery or with the linen pattern, and sometimes with running images. The divisions are filled in with thin chamfered boarding, sometimes reaching to the floor, and sometimes only from the capping to the seat.

**Picket.** A narrow board, often pointed, used in making fences; a pale or ling.

**Pier-glass.** A mirror hanging between windows.

**Piers.** The solid parts of a wall between windows, and between voids generally. The term is also applied to masses of brick-work or masonry which are utilized to form supports to gates or to carry arches, posts, girders, etc.

**Pilasters.** Are flat square columns, attached to a wall, behind a column, or along the side of a building, and projecting from the wall about a fourth or a fifth part of their breadth. The Greeks had a slightly different design for the capitals of pilasters, and made them the same width at top as at bottom, but the Romans gave them the same capitals as the columns, and made them of diminished width at the top, similar to the columns.

**Pile.** A large stake or trunk of a tree, driven into soft ground, as at the bottom of a river, or in made land, for the support of a building. (See p. 188.)

**Pillar, or Pyller.** A word generally used to express the round or polygonal shafts, or those surrounded with clustered columns, which carry the main arches of a building. Saxon and Early Norman pillars are generally stout cylindrical shafts built up of small stones. Sometimes, however, they are quite square, sometimes with other squares breaking out of them (this is more common in French and German work), sometimes with angular shafts, and sometimes they are plain octagons. In Romanesque Norman work the pillar is sometimes square, with two or more semicircular or half-columns attached. In the Early

**English period** the pillars become loftier and lighter, and in most important buildings are a series of clustered columns, frequently of marble, placed side by side, sometimes set at intervals round a circular centre, and sometimes almost touching each other. These shafts are often wholly detached from the central pillar, though grouped round it, in which case they are almost always of Purbeck or Bethersden marbles. In Decorated work the shafts on plan are very often placed round a square set anglewise, or a lozenge, the long way down the square; the centre or core itself is often worked into hollows or other moldings, to serve as a base between the shafts, and to form part of the composition. In this and the later part of the previous style there is generally a fillet on the outer part of the shaft, forming what has been called a keel molding. They are also often, as it were, tied together by bands formed of rings of stone and sometimes of metal. The small pillars at the jambs of doors and windows, and in arcades, and also those slender columns attached to pillars, or standing detached, are generally called shafts.

**Pin.** A cylindrical piece of wood, iron, or steel, used to hold two or more pieces together, by passing through a hole in each of them, as in a mortise and tenon joint, or a pin joint of a truss.

**Pinnacle.** An ornament originally forming the cap or crown of a buttress or small turret, but afterwards used on parapets at the corners of towers and in many other situations. It was a weight to counteract the thrust of the groining of roofs, particularly where there were flying buttresses; it stopped the tendency to slip of the stone copings of the gables, and counterpoised the thrust of spires; it formed the piers to steady the elegant perforated parapets of later periods; and in France, especially, served to counterbalance the weight of overhanging corbel tables, huge gargoyles, etc. In the Early English period the smaller buttresses frequently finished with gablets, and the more important with pinnacles supported with clustered shafts. At this period the pinnacles were often supported on these shafts alone, and were open below; and in larger work in this and the subsequent periods they frequently form niches and contain statues. In France, pinnacles, like spires, seem to have been in use earlier than in England. There are small pinnacles at the angles of the tower in the Abbey of Saintes. At Roulet there are pinnacles in a similar position, each composed of four small shafts, with caps and bases surmounted with small pyramidal spires. In all these examples the towers have semicircular headed windows.



PINNACLE.

**Pitch of a Roof.** The proportion obtained by dividing the height by the span; thus, we speak of its being one-half, one-third, one-fourth. When the length of the rafters is equal to the breadth of the building it is denominated Gothic.

**Pitching-piece.** A horizontal timber, with one of its ends wedged into the wall at the top of a flight of stairs, to support the upper end of the rough strings.

**Place.** An open piece of ground surrounded by buildings, generally decorated with a statue, column, or other ornament.

**Plan.** A horizontal geometrical section of the walls of a building; or indications, on a horizontal plane, of the relative positions of the walls and partitions with the various openings, such as windows and doors, recesses and projections, chimneys and chimney-breasts, columns, pilasters, etc. This term is often incorrectly used in the sense of *Design*.

**Planceer.** Is sometimes used in the same sense as soffit, but is more correctly applied to the soffit of the corona in a cornice.

**Plastering.** A mixture of lime, hair, and sand, to cover lath-work between members or rough walling, used from the earliest times, and very common in Roman work. In the Middle Ages, too, it was used not only in private, but in public constructions. On the inside face of old rubble walls it was not only used for purposes of cleanliness, rough work holding dirt and dust, but as a ground for distemper painting (tempera, or, as it is often improperly called, fresco), a species of ornament often used in the Middle Ages. At St. Albans Abbey, England, the Norman work is plastered, and covered with lines imitating the joints of stone. The same thing is found in English Perpendicular work. On the outside of rubble walls, and often of wood framing, it was used as roughcast; when ornamented in patterns outside, it is called pargeting.

**Plate.** The piece of timber in a building which supports the end of the rafters.

**Plinth.** The square block at the base of a column or pedestal. In a wall, the masonry plinth is applied to the projecting base or water table, generally at the level of the first floor.

**Plumb.** Perpendicular; that is, standing according to a plumb line, as, the roof of a house or wall is plumb.

**Plumbing.** The lead and iron pipes and other apparatus employed in conveying water, and for toilet purposes in a building; originally the art of casting and working in lead.

**Ply.** Used to denote the number of thicknesses of roofing paper, as three ply, or ply, etc.

**Podium.** A continued pedestal; a projection from a wall, forming a kind of gallery.

**Polytriglyph.** An intercolumniation in the Doric order of more than two triglyphs.

**Poppy Heads.** Probably from the French *poupes*: the finials or other ornaments which terminate the tops of bench ends, either to pews or stalls. They are sometimes small human heads, sometimes richly carved images, knots of foliage, or finials, and sometimes fleurettes simply cut out of the thickness of the bench end and chamfered.

**Porch.** A covered erection forming a shelter to the entrance of a large building. The earliest known are the long arcaded porches in front of the early Christian basilicas, called Narthex. In later times they assume two forms—one, the projecting erection covering the entrance at the west front of cathedrals, and divided into three or more doorways, etc.; and the other, a kind of covered ambler open at the ends, and having small windows at the sides for a protection from rain.



POPPY HEAD

**Portal.** A name given to the deeply recessed and richly decorated entrance doors to the cathedrals in Continental Europe.

**Portcullis.** A strong-framed grating of oak, the lower points shod with iron, and sometimes entirely made of metal, hung so as to slide up and down in grooves with counterbalances, and intended to protect the gateways of castles, etc.

**Portico.** An open space before the door or other entrance to any building, bounded with columns. A portico is distinguished as *prostyle* or *in antis* accord-

ing as it projects from or recedes within the building, and is further designated by the number of columns its front may consist of.

**Post.** Square timbers set on end. The term is especially applied to those which support the corners of a building, and are framed into bressummers and crossbeams under the walls.

**Posticum.** A portico behind a temple.

**Presbytery.** A word applied to various parts of large churches in a very ambiguous way. Some consider it to be the choir itself; others, what is now named the sacristy. Traditionally, however, it seems to be applied to the vacant space between the back of the high altar and the entrance to the choir-chapel, as at Lincoln and Chichester; in other words, the back- or retro-choir.

**Priming.** The laying on of the first shade of color, in oil paint, and generally consisting mostly of oil, to protect and fill the wood.

**Priory.** A monastic establishment, generally in connection with an abbey, and presided over by a prior, who was a subordinate to the abbot, and held much the same relation to that dignitary as a dean does to a bishop.

**Profile.** The outline; the contour of a part, or the parts composing an order, as of a base, cornice, etc.; also, the perpendicular section. It is in the just proportion of their profiles that the chief beauties of the different orders of architecture depend. The ancients were most careful of the profiles of their moldings.

**Proscenium.** The front part of the stage of ancient theaters, on which the actors performed.

**Prostyle.** A portico in which the columns project from the building to which it is attached.

**Protractor.** A mathematical instrument for laying down and measuring angles on paper, used in drawing or plotting.

**Pseudo-dipteral.** False double-winged. When the inner row of columns of a dipteral arrangement is omitted and the space from the wall of the building to the columns is preserved, it is pseudo-dipteral.

**Puddle.** To settle loose dirt by turning on water, so as to render it firm and solid.

**Pugging.** A coarse kind of mortar laid on the boarding, between floor joists, to prevent the passage of sound; also called deafening.

**Pulpit.** A raised platform with enclosed front, whence sermons, homilies, &c., were delivered. Pulpits were probably derived in their modern form from the ambones in the early Christian church. There are many old pulpits of stone, though the majority are of wood. Those in the churches are generally hexagonal or octagonal; and some stand on stone bases, and others on slender wooden stems, like columns. The designs vary according to the periods in which they were erected, having paneling, tracery, cuspings, crockets, and other ornaments then in use. Some are extremely rich, and ornamented with color and gilding. A few also have fine canopies or sounding boards. Their usual place is in the nave, mostly on the north side, against the second pier from the chancel arch. Pulpits for addressing the people in the open air were common in the Middle Ages, and stood near a road or cross. Thus, there was one at Spitalfields, and one at St. Paul's, London. External pulpits still remain at Magdalen College, Oxford, and at Shrewsbury, England.

**Purlins.** Those pieces of timbers which support the rafters to prevent them from sinking.



**Putlog.** Horizontal pieces for supporting the floor of a scaffold, one end being inserted into putlog holes, left for that purpose in the masonry.

**Putty in Plastering.** Lump lime slacked with water to the consistency of cream, and then left to harden by evaporation till it becomes like soft putty. It is then mixed with plaster of Paris, or sand, for the finishing coat.

**Puzzolana.** A grayish earth used for building under water.

**Pyramid.** A solid, having one of its sides, called a base, a plane figure, and the other sides triangles, these points joining in one point at the top, called the vertex. Pyramids are called triangular, square, etc., according to the form of their bases.

**Pyx.** In Roman Catholic churches, the box in which the host, or consecrated wafer, is kept.

**Quadrangle.** A square or quadrangular court surrounded by buildings, as was often done formerly in monasteries, colleges, etc.

**Quarry.** A pane of glass cut in a diamond or lozenge form.

**Quarry-face.** Ashlar as it comes from the quarry, squared off for the joints only, with split face. In distinction from Rock-face, in that the latter may be weather-worn, while Quarry-face should be fresh split. The terms are often used indiscriminately.

**Quatrefoil.** Any small panel or perforation in the form of a four-leaved flower. Sometimes used alone, sometimes in circles and over the aisle windows, but more frequently in square panels. They are generally cusped, and the cusps are often feathered.

**Queen Truss.** A truss framed with two vertical tie-posts, in distinction from the king-post, which has but one. The upright ties are called Queen-posts.

**Quirk Moldings.** The convex part of Grecian moldings when they recede at the top, forming a reëntrant angle, with the surface which covers the moldings.

**Quoins.** Large squared stones at the angles of buildings, buttresses, etc., generally used to stop the rubble or rough stone work, and that the angles may be true and stronger. Saxon quoin stones are said to have been composed of one long and one short stone alternately. Early quoins are generally roughly hewed; in later times they had a draught tooled by the chisel round the outside edges, and later still were worked fine from the saw.

**Rafters.** The joist to which the roof boarding is nailed. *Principal rafters* are the upper timbers in a truss, having the same inclination as the common rafters.

**Rail.** A piece of timber or metal extending from one post to another, as in fences, balustrades, staircases, etc. In framing and paneling, the horizontal pieces are called rails, and the perpendicular, *stiles*.

**Raking.** Moldings whose arrises are inclined to the horizon.

**Ramp.** A concavity on the upper side of hand railings formed over risers, made by a sudden rise of the steps above. Any concave bend or slope in the cap or upper member of any piece of ascending or descending workmanship.

**Rampant.** A term applied to an arch whose abutments spring from an inclined plane.

**Random Work.** A term used by stone-masons for stones fitted together at random without any attempt at laying them in courses. *Random Coursed Work* is a like term applied to work coursed in horizontal beds, but the stones are of any height, and fitted to one another.

**Range Work.** Ashlar laid in horizontal courses; same as coursed ashlar.

**Rebate.** A groove on the edges of a board.

**Recess.** A depth of some inches in the thickness of a wall, as a niche, etc.

**Refectory.** The hall of a monastery, convent, etc., where the religious take their chief meals together. It much resembled the great halls of manor castles, etc., except that there frequently was a sort of ambo, approached by steps, from which to read the *Legenda Sanctorum*, etc., during meals.

**Reglet.** A flat, narrow molding, used to separate from each other the parts or members of compartments and panels, to form frets, knots, etc.

**Renaissance** (a new birth). A name given to the revival of Roman architecture which sprang into existence in Italy as early as the beginning of the fifteenth century, and reached its zenith in that country at the close of the century. There are several divisions of this style as developed in different localities; viz.

*The Florentine Renaissance*, of which the Pitti Palace, by Brunelleschi, is one of the best examples.

*The Venetian Renaissance*, characterized by its elegance and richness.

*The Roman Renaissance*, which originated in Rome, under the architects known as Bramante, Vignola, and Michael Angelo. Of this style the Farnese Palace, St. Peter's, and the modern Capitol at Rome are the best examples.

*The French Renaissance*, introduced into France in the latter part of the fifteenth century, by Italian architects, where it flourished until the middle of the seventeenth century. The Renaissance style was introduced into Germany about the middle of the sixteenth century, and into England about the same time by John of Padua, architect to Henry VIII. This style in England is generally known under the name of Elizabethan.

**Rendering.** In drawing, finishing a perspective drawing in ink or color, to bring out the spirit and effect of the design. The first coat of plaster on brick or stone work.

**Reredos, Dorsal, or Dossel.** The screen or other ornamental work at the back of an altar. In some large English cathedrals, as Winchester, Durham, St. Albans, etc., this is a mass of splendid tabernacle work, reaching nearly to the groining. In smaller churches there are sometimes ranges of arcades or panelings behind the altars; but, in general, the walls at the back and sides of them were of plain masonry, and adorned with hangings or paraments. In the large churches of Continental Europe the high altar usually stands under a sort of canopy or ciborium, and the sacrarium is hung round at the back and sides with curtains or movable rods.

**Reticulated Work.** That in which the courses are arranged in a form like the meshes of a net. The stones or bricks are square and placed lozenge-wise.

**Return.** The continuation of a molding, projection, etc., in an opposite direction.

**Return Head.** One that appears both on the face and edge of a work.

**Reveal.** The two vertical sides of an aperture, between the front of a wall and the window or door frame.

**Rib.** A molding or projecting piece upon the interior of a vault, or used to form tracery and the like. The earliest groining had no ribs. In early Norman times plain flat arches crossed each other, forming ogive ribs. These by degrees became narrower, had greater projection, and were chamfered. In later Norman work the ribs were often formed of a large roll placed upon the flat band, and then of two rolls side by side with a smaller roll or a fillet between them.

such like the lower member. Sometimes they are enriched with zigzags and other Norman decorations, and about this time bosses became of very general use. As styles progressed, the moldings were more undercut, richer, and more elaborate, and had the dog-tooth or ball-flower or other characteristic ornament in the hollows. In all instances the moldings are of similar contours to those of arches, etc., of the respective periods. Later, wooden roofs are often formed into cants or polygonal barrel vaults, and in these the ribs are generally a cluster of rounds, and form square or stellar panels, with carved bosses or shields at the intersections.

**Ridge.** The top of a roof which rises to an acute angle.

**Ridge-pole.** The highest horizontal timber in a roof, extending from top to top of the several pairs of rafters of the trusses, for supporting the heads of the back rafters.

**Rilievo, or Relief.** The projection of an architectural ornament.

**Rise.** The distance through which anything rises, as the rise of a stair, or inclined plane.

**Riser.** The vertical board under the tread in stairs.

**Rococo Style.** A name given to that variety of the Renaissance which was in vogue during the seventeenth and the latter part of the sixteenth century.

**Romanesque Style.** The term Romanesque embraces all those styles of architecture which prevailed between the destruction of the Roman Empire and the beginning of Gothic architecture. In it are included the Early Roman Christian architecture, Byzantine, Mahometan, and the later Romanesque architecture proper, which was developed in Italy, France, England, and Germany. This later Romanesque, which was quite different from the preceding, came into vogue during the tenth century, and reached its height during the twelfth century, and in the thirteenth century gave way to the Pointed or Gothic style. In England, Romanesque architecture is known under the name of the Saxon, Norman, and Lombard styles, according to the different political periods.

**Rood.** A name applied to a crucifix, particularly to those which were placed in the rood-loft or chancel screens. These generally had not only the image of the crucified Saviour, but also those of St. John and the Virgin Mary standing one on each side. Sometimes other saints and angels are by them, and the top of the screen is set with candlesticks or other decoration.

**Rood-loft, Rood-screen, Rood-beam, Jube Gallery, etc.** The arrangement to carry the crucifix or rood, and to screen off the chancel from the rest of the church during the breviary services, and as a place whence to read certain parts of those services. Sometimes the crucifix is carried simply on a strong transverse beam, with or without a low screen, with folding-doors below but forming no part of such support. In European churches the general construction of wooden screens is close paneling beneath, about 3 feet to 3 feet 6 inches high, on which stands screen work composed of slender turned balusters or regular wooden mullions, supporting tracery more or less rich, with cornices, cresting, etc., and often painted in brilliant colors and gilded. These not only enclose the chancels, but also chapels, chantries, and sometimes even tombs. In English mansions, and some private houses, the great halls were screened off by a low passage at the end opposite to the dais, over which was a gallery for the use of minstrels or spectators. These screens were sometimes close and sometimes glazed.

**Rood-tower.** A name given by some writers to the central tower, or that over the intersection of the nave and chancel with the transepts.

**Roof.** The covering or upper part of any building.

**Roofing.** The material put on a roof to make it water-tight.

**Rose Window.** A name given to a circular window with radiating tracery; called also wheel window.

**Rostrum.** An elevated platform from which a speaker addresses an audience.

**Rotunda.** A building which is round both within and without. A circular room under a dome in large buildings is also called the rotunda.

**Roughcast.** A sort of external plastering in which small sharp stones are mixed, and which, when wet, is forcibly thrown or cast from a trowel against the wall, to which it forms a coating of pleasing appearance. Roughcast work has been used in Europe for several centuries, where it was much used in timber houses, and when well executed the work is sound and durable. The mortar for roughcast work should always have cement mixed with it.

**Rubble Work.** Masonry of rough, undressed stones. When only the roughest irregularities are knocked off, it is called scabbled rubble, and when the stones in each course are rudely dressed to nearly a uniform height, ranged rubble.

**Rudenture.** The figure of a rope or staff, which is frequently used to fill up the flutings of columns, the convexity of which contrasts with the concavity of the flutings, and serves to strengthen the edges. Sometimes, instead of a convex shape, the flutings are filled with a flat surface; sometimes they are ornamentally carved, and sometimes on pilasters, etc. Rudentures are used in relief without flutings, as their use is to give greater solidity to the lower part of the shaft, and secure the edges. They are generally only used in columns which rise from the ground and are not to reach above one-third of the height of the shaft.

**Rustic or Rock Work.** A mode of building in imitation of nature. This term is applied to those courses of stone work the face of which is jagged or picked so as to present a rough surface. That work is also called rustic in which the horizontal and vertical channels are cut in the joinings of stones, so that when placed together an angular channel is formed at each joint. *Frosted rustic work* has the margins of the stones reduced to a plane parallel to the plane of the wall, the intermediate parts having an irregular surface. *Vermiculated rustic work* has these intermediate parts so worked as to have the appearance of having been eaten by worms. *Rustic chamfered work*, in which the face of the stones is smooth, and parallel to the face of the wall, and the angles beveled to an angle of one hundred and thirty-five degrees with the face so that two stones coming together on the wall, the beveling will form an internal right angle.

**Sacristy.** A small chamber attached to churches, where the chalices, vestments, books, etc., were kept by the officer called the sacristan. In the early Christian basilicas there were two semicircular recesses or apses, one on each side of the altar. One of these served as a sacristy, and the other as the *bibliotheca* or library. Some have supposed the sacristy to have been the place where the vestments were kept, and the vestry that where the priests put them on; but we find from Durandus that the *sacrarium* was used for both these purposes. Sometimes the place where the altar stands enclosed by the rails has been called *sacrarium*.

**Saddle Bars.** Narrow horizontal iron bars passing from mullion to mullion, and often through the whole window, from side to side, to steady the stone work, and to form stays, to which the lead work is secured. When the bays of the windows are wide, the lead lights are further strengthened by upright bars passing through eyes forged on the saddle bars, and called *stanchions*. When

**Saddle bars** pass right through the mullions in one piece, and are secured to the arms, they have sometimes been called stay bars.

**Sagging.** The bending of a body in the middle by its own weight, or the load upon it.

**Salient.** A projection.

**Salon.** A spacious and elegant apartment for the reception of company, or for state purposes, or for the reception of paintings, and usually extending through two stories of the house. It may be square, oblong, polygonal, or circular.

**Sanctuary.** That part of a church where the altar is placed; also, the most sacred or retired part of a temple. A place for divine worship; a church.

**Sanctus Bell-cot, or Turret.** A turret or enclosure to hold the small bell sounded at various parts of the service, particularly where the words "Sanctus," &c., are read. This differs but little from the common bell-cot, except that it is generally on the top of the arch dividing the nave from the chancel. Sometimes, however, the bell seems to have been placed in a cot outside the wall. In England sanctus bells have also been placed over the gables of porches. In Continental Europe they run up into a sort of small slender spire, called *flèche* in France, and *guglio* in Italy.

**Saracenic Architecture.** That Eastern style employed by the Saracens, and which distributed itself over the world with the religion of Mahomet. It is a modification and combination of the various styles of the countries which they conquered.

**Sarcophagus.** A tomb or coffin made of stone, and intended to contain the body.

**Sash.** The framework which holds the glass in a window.

**Scabble.** To dress off the rougher projections of stones for rubble masonry with a stone axe or scabbling hammer.

**Scagliola.** An imitation of colored marbles in plaster work, made by a combination of gypsum, glue, isinglass, and coloring matter, and finished with a high polish, invented between 1600 and 1649.

**Scantling.** The dimensions of a piece of timber in breadth and thickness; also, studding for a partition, when under five inches square.

**Scarfing.** The joining and bolting of two pieces of timber together transversely, so that the two appear as one.

**Sconce.** A fixed hanging or projecting candlestick.

**Scotia.** A concave molding, most commonly used in bases, which projects a deep shadow on itself, and is thereby a most effective molding under the eye, as in a base. It is like a reversed ovolo, or, rather, what the mold of an ovolo would present.

**Scratch Coat.** The first coat of plaster, which is scratched to afford a bond for the second coat.

**Screeds.** Long narrow strips of plaster put on horizontally along a wall, and carefully faced out of wind, to serve as guides for plastering the wide intervals between them.

**Screen.** Any construction subdividing one part of a building from another, as a choir, chantry, chapel, &c. The earliest screens are the low marble podia shutting off the chorus cantantium in the Roman basilicas, and the perforated cancelli enclosing the bema, altar, and seats of the bishops and presbyters. The chief screens in a church are those which enclose the choir or the place where

the breviary services are recited. In Continental Europe this is done not only by doors and screen work, but also, when these are of open work, by curtains, the laity having no part in these services. In England screens were of two kinds, one, of open wood-work, generally called rood-screens or jubes, and which the French call *grilles, clôtures du chœur*; the other, massive enclosures of stone, enriched with niches, tabernacles, canopies, pinnacles, statues, crestings, etc., as at Canterbury, York, Gloucester, and many other places.

**Scribing.** Fitting wood-work to an irregular surface.

**Section.** A drawing showing the internal heights of the various parts of a building. It supposes the building to be cut through entirely, so as to exhibit the walls, the heights of the internal doors and other apertures, the heights of the stories, thicknesses of the floors, etc. It is one of the species of drawings necessary to the exhibition of a Design.

**Sedilia.** Seats used by the celebrants during the pauses in the mass. They are generally three in number — for the priest, deacon, and sub-deacon — and are in England almost always a species of niches cut into the south wall of churches, separated by shafts or by a species of mullions, and crowned with canopies, pinnacles, and other enrichments more or less elaborate. The piscina and ambry sometimes are attached to them. In Continental Europe the sedilia are often movable seats; a single stone seat has rarely been found.

**Set-off.** The horizontal line shown where a wall is reduced in thickness, and consequently, the part of the thicker portion appears projecting before the thinner. In plinths this is generally simply chamfered. In other parts of work the set-off is generally concealed by a projecting string. Where, as in parapets, the upper part projects before the lower, the break is generally hid by a corbel table. The portions of buttress caps which recede one behind another are also called set-offs.

**Shaft.** In Classical architecture that part of a column between the necking and the apophyge at the top of the base. In later times the term is applied to slender columns either standing alone or in connection with pillars, buttress-jambs, vaulting, etc.

**Shed Roof, or Lean-to.** A roof with only one set of rafters, falling from a higher to a lower wall, like an aisle roof.

**Shore.** A piece of timber placed in an oblique direction to support a building or wall temporarily while it is being repaired or altered.

**Shrine.** A sort of ark or chest to hold relics. It is sometimes merely a small box, generally with a raised top like a roof; sometimes an actual model of churches; sometimes a large construction, like that of Edward the Confessor at Westminster, of St. Genevieve at Paris, etc. Many are covered with jewels in the richest way; that of San Carlo Borromeo, at Milan, is of beaten silver.

**Sills.** Are the timbers on the ground which support the posts and superstructure of a timber building. The term is most frequently applied to those pieces of timber or stone at the bottom of doors or windows.

**Skewback.** The inclined stone from which an arch springs.

**Skirtings.** The narrow boards which form a plinth around the margin of a floor, now generally called the base.

**Sleeper.** A piece of timber laid on the ground to receive floor joists.

**Soffit.** The lower horizontal face of anything as, for example, of an entablature resting on and lying open between the columns, or the under face of an arch where its thickness is seen.

- Sound Board.** The covering of a pulpit to deflect the sound into a church.
- Spall.** Bad or broken brick; stone chips.
- Span.** The distance between the supports of a beam, girder, arch, truss, etc.
- Spandrel, or Spandril.** The space between any arch or curved brace and the label, beams, etc., over the same. The spandrels over doorways in Perpendicular works are generally richly decorated.
- Specification.** Architect's. The designation of the kind, quality, and quantity of work and material to go in a building, in conjunction with the working drawings.
- Spire.** A sharply pointed pyramid or large pinnacle, generally octagonal in plan, and forming a finish to the tops of towers. Timber spires are very common in England. Some are covered with lead in flat sheets, others with the same metal in narrow strips laid diagonally. Very many are covered with tiles. In Continental Europe there are some elegant examples of spires of pure timber work covered with lead.
- Spliced.** The jamb of a door, or anything else of which one side makes an oblique angle with the other.
- Springer.** The stone from which an arch springs; in some cases this is a capital, or impost; in other cases the moldings continue down the pier. The lowest stone of the gable is sometimes called a springer.
- Squins.** Small arches or corbeled set-offs running diagonally and, as it were, cutting off the corners of the interior of towers, to bring them from the square to the octagon, etc., to carry the spire.
- Squint.** An oblique opening in the wall of a church; especially, in mediæval architecture, an opening so placed as to afford a view of the high altar from the transept or aisles.
- Staging.** A structure of posts and boards for supporting workmen and material in building.
- Stall.** A fixed seat in the choir for the use of the clergy. In early Christianity the *thronus cathedra*, or seat of the bishop, was in the center of the apse or bema behind the altar, and against the wall; those of the presbyters also were against the wall, branching off from side to side around the semicircle. In later times the stalls occupied both sides of the choir, return seats being placed at the ends for the prior, dean, precentor, chancellor, or other officers. In general, in cathedrals, each stall is surmounted by tabernacle work, and rich canopies, generally of oak.
- Stanchion.** A word derived from the French *étançon*, a wooden post, applied to the upright iron bars which pass through the eyes of the saddle bars or horizontal irons to steady the lead lights. The French call the latter *traverses*, the stanchions *montants*, and the whole arrangement *armature*. Stanchions frequently finish with ornamental heads forged out of the iron.
- Steeple.** A general name for the whole arrangement of tower, belfry, spire, etc.
- Stereobate.** A basement, distinguished from the nearly equivalent term stylobate by the absence of columns.
- Stile.** The upright piece in framing or paneling.
- Stilted.** Anything raised above its usual level. An arch is stilted when its centre is raised above the line from which the arch appears to spring.
- Stoop.** A seat before the door; often a porch with a balustrade and seats on the sides.

**Stoup.** A basin for holy water at the entrance of Roman Catholic churches into which all who enter dip their fingers and cross themselves.

**Straight Arch.** A form of arch in which the intrados is straight, but with joints radiating as in a common arch.

**Strap.** An iron plate for connecting two or more timbers, to which screwed by bolts. It generally passes around one of the timbers.

**Stretcher.** A brick or block of masonry laid lengthwise of a wall.

**String Board.** A board placed next to the well-hole in wooden stairs, terminating the ends of the steps. The string piece is the piece of board put between the treads and risers for a support, and forming the support of the stair.

**String-course.** A narrow, vertically faced and slightly projecting course on an elevation. If window-sills are made continuous, they form a string-course, but if this course is made thicker or deeper than ordinary window-sills, or of a set-off in the wall, it becomes a blocking-course. Also, horizontal moldings running under windows, separating the walls from the plain part of the parapet, dividing towers into stories or stages, etc. Their section is much the same as the labels of the respective periods; in fact, these last, after passing round windows, frequently run on horizontally and form strings. Like labels, they are often decorated with foliages, ball-flowers, etc.

**Studs, or Studding.** The small timbers used in partitions and outside walls, to which the laths and boards are nailed.

**Style.** The term style in architecture has obtained a conventional meaning beyond its simpler one, which applies only to columns and columnar arrangements. It is now used to signify the differences in the moldings, general outlines, ornaments, and other details which exist between the works of various nations, and also those differences which are found to exist between the works of any nation at different times.

**Stylobate.** A basement to columns. Stylobatè is synonymous with pedestal, but is applied to a continued and unbroken substructure or basement to columns, while the latter term is confined to insulated supports. The Greek temples generally had three or more steps all around the temple, the base of the column resting on the top step; this was the stylobate.

**Subsellium.** A name sometimes given to the seat in the stalls of churches, the same as miserere.

**Summer.** A girder or main-beam of a floor; if supported on two-story posts and open below, it is called a Brace-summer.

**Surbase.** A cornice or series of moldings on the top of the base of a pedestal, podium, etc.; a molding above the base.

**Surface.** To make plane and smooth.

**Systyle.** An intercolumniation to which two diameters are assigned.

**Tabernacle.** A species of niche or recess in which an image may be placed. They are generally highly ornamented and often surmounted with crockets and gables. The word tabernacle is also often used to denote the receptacle for relics, which was often made in the form of a small house or church.

**Tabernacle Work.** The rich ornamental tracery forming the canopy, or baldachin, to a tabernacle, is called tabernacle work; it is common in the stalls and screens of cathedrals, and in them is generally open or pierced through.

**Tail Trimmer.** A trimmer next to the wall, into which the ends of joists are fastened to avoid flues.



**Tamp.** To pound the earth down around a wall after it has been thrown in.

**Tapestry.** A kind of woven hangings of wool or silk, ornamented with figures, and used formerly to cover and adorn the walls of rooms. They were often of the most costly materials and beautifully embroidered.

**Temple.** An edifice destined, in the earliest times, for the public exercise of religious worship.

**Templet, or Template.** A mold used by masons for cutting or setting work. A short piece of timber sometimes laid under a girder.

**Terminal.** Figures of which the upper parts only, or perhaps the head and shoulders alone, are carved, the rest running into a parallel piped, and sometimes into a diminishing pedestal, with feet indicated below, or even without them, are called terminal figures.

**Terra-cotta.** Baked clay of a fine quality. Much used for bas-reliefs for adorning the friezes of temples. In modern times employed for architectural ornaments, statues, vases, etc.

**Tessellated Pavements.** Those formed of tessæ, or, as some write it, tessellæ, or small cubes from half an inch to an inch square, like those of pottery, stone, marble, enamel, etc.

**Tetrastyle.** A portico of four columns in front.

**Tholobate.** That on which a dome or cupola stands. This is a term not in general use, but it is not the less of useful application. What is generally termed the attic above the peristyle and under the cupola of St. Paul's, London, would be correctly designated the tholobate. A tholobate of a different description, and one to which no other name can well be applied, is the circular substructure to the cupola of the University College, London.

**Throat.** A channel or groove made on the under-side of a string-course, cornice, etc., to prevent water from running inward toward the walls.

**Tie.** A timber, rod, chain, etc., binding two bodies together, which have a tendency to separate or diverge from each other. The *tie-beam* connects the bottom of a pair of principal rafters, and prevents them from bursting out the wall.

**Tiles.** Flat pieces of clay burned in kilns, to cover roofs in place of slates or lead. Also, flat pieces of burned clay, either plain or ornamented, glazed or unglazed, used for floors, wainscoting, and about fireplaces, etc. Small square pieces of marble are also called tile.

**Tongue.** The part of a board left projecting, to be inserted into a groove.


**Tooth Ornament.** One of the peculiar marks of the Early English period of Gothic architecture, generally inserted in the hollow moldings of doorways, windows, etc.

**Torso.** A mutilated statue of which nothing remains but the trunk. Columns and twisted shafts have also this term. Of this kind there are several varieties.

**Torus.** A protuberance or swelling, a molding whose form is convex, and generally nearly approaches a semicircle. It is most frequently used in bases, and is generally the lowest molding in a base.



ANCIENT TERMINI



TORUS

**Tower.** An elevated building originally designed for purposes of defense. Those buildings are of the remotest antiquity, and are, indeed, mentioned in the earliest Scriptures. In mediæval times they were generally attached to churches, to cemeteries, to castles, or used as bell-towers in public places of large cities. In churches, the towers of the Saxon period were generally square. Norman towers were also generally square. Many were entirely without buttresses, others had broad, flat, shallow projections which served for this purpose. The lower windows were very narrow, with extremely wide splays inside, probably intended to be defended by archers. The upper windows, like those of the preceding style, were generally separated into two lights, but by a shaft or short column and not by a baluster. Early English towers were generally taller, and of more elegant proportions. They almost always had large projecting buttresses, and frequently stone staircases. The lower windows, as in the former style, were frequently mere arrow-slits; the upper were in couplets or triplets, and sometimes the tower top had an arcade all around. The spires were generally broach spires, but sometimes the tower tops finished with corbel courses and plain parapets, and (rarely) with pinnacles. There are a few Early English towers which break into the octagon from the square toward the top, and still fewer which finish with two gables. Both these methods of termination, however, are common in Continental Europe. At Vendôme, Chartres, and Senlis the towers have octagonal upper stages surrounded with pinnacles, from which elegant spires arise. In the North of Italy, and in Rome, they are generally tall square shafts in four to six stages, without buttresses, with couplets or triplets of semicircular windows in each stage, generally crenellated at top, and covered with a low pyramidal roof. The well-known leaning tower at Pisa is cylindrical, in five stories of arcaded colonnades. In Ireland there are in some of the churchyards very curious round towers.

**Tracery.** The ornamental filling in of the heads of windows, panels, circular windows, etc., which has given such characteristic beauty to the architecture of the fourteenth century. Like almost everything connected with mediæval architecture, this elegant and sometimes fairy-like decoration seems to have sprung from the smallest beginnings. The circular-headed window of the Norman gradually gave way to the narrow-pointed lancets of the Early English period, and, as less light was afforded by the latter system than by the former, it was necessary to have a greater number of windows; and it was found convenient to group them together in couplets, triplets, etc. When these couplets were assembled under one label, a sort of vacant space or spandrel was formed over the lancets and under the label. To relieve this, the first attempts were simply to perforate this flat spandrel, first by a simple lozenge-shaped or circular opening, and afterward by a quatrefoil. By piercing the whole of the vacant spaces in the window head, carrying moldings around the tracery, and adding cusps to it, the formation of tracery was complete, and its earliest result was the beautiful geometrical work such as is found at Westminster Abbey.

**Transept.** That portion of a church which passes transversely between the nave and choir at right angles, and so forms a cross on the plan.

**Transom.** The horizontal construction which divides a window into heights or stages. Transoms are sometimes simple pieces of mullions placed transversely as cross-bars, and in later times are richly decorated with cuspings, etc.

**Traverse.** To plane in a direction across the grain of the wood, as to traverse a floor by planing across the boards.

**Tread.** The horizontal part of a step of a stair.

**Trefoil.** A cusping the outline of which is derived from a three-leaved flower leaf, as the quatrefoil and cinque-foil are from those with four and five.

**Trellis.** Lattice-work of metal or wood for vines to run on.

**Trestle.** A movable frame or support for anything; when made of a cross piece with four legs it is called by carpenters a horse.

**Triforium.** The arcaded story between the lower range of piers and arches and the clere-story. The name has been supposed to be derived from *tres* and *for* — three doors, or openings — that being a frequent number of arches in each bay.

**Triglyph.** The vertically channeled tablets of the Doric frieze are called glyphs, because of the three angular channels in them — two perfect and one divided — the two chamfered angles or hemiglyphs being reckoned as one. The square sunk spaces between the triglyphs on a frieze are called metopes.

**Trim.** Of a door, sometimes used to denote the locks, knobs, and hinges.

**Trimmer.** The beam or floor joist into which a header is framed.

**Trimmer Arch.** An arch built in front of a fireplace, in the thickness of the wall, between two trimmers. The bottom of the arch starting from the chimney and the top pressing against the header.

**Tuck-pointing.** Marking the joints of brickwork with a narrow parallel ridge of fine putty.

**Tudor Style.** The architecture which prevailed in England during the reign of the Tudors; its period is generally restricted to the end of the reign of Henry VIII.

**Turret.** A small tower, especially at the angles of larger buildings, sometimes overhanging and built on corbels, and sometimes rising from the ground.

**Tuscan Order.** The plainest of the five orders of Classic architecture.

**Tympanum.** The triangular recessed space enclosed by the cornice which bounds a pediment. The Greeks often placed sculptures representing subjects connected with the purposes of the edifice in the tympana of temples, as at the Parthenon and Ægina.

**Under-croft.** A vaulted chamber under ground.

**Upset.** To thicken, and shorten as by hammering a heated bar of iron on the anvil.

**Vagina.** The upper part of the shaft of a terminus, from which the bust or figure seems to rise.

**Valley.** The internal angle formed by two inclined sides of a roof.

**Valley Rafters.** Those which are disposed in the internal angle of a roof to form the valleys.

**Vane.** The weathercock on a steeple. In early times it seems to have been of various forms, as dragons, etc.; but in the Tudor period the favorite design was a beast or bird sitting on a slender pedestal, and carrying an upright rod, on which a thin plate of metal is hung like a flag, ornamented in various ways.

**Vault.** An arched ceiling or roof. A vault is, indeed, a laterally conjoined series of arches. The arch of a bridge is, strictly speaking, a vault. Intersecting vaults are said to be groined. See *Groined Vaulting* for fuller description of vaults.

**Verge.** The edge of the tiling, slate or shingles, projecting over the gable of a roof, that on the horizontal portion being called eaves.


**Verge Board.** Often corrupted into Barge Board; the board under the verge of gables, sometimes molded, and often very richly carved, perforated, and cusped, and frequently having pendants, and sometimes finials, at the apex.

**Vermiculated.** Stones, etc., worked so as to have the appearance of having been worked by worms.

**Vestibule.** An anti-hall, lobby, or porch.

**Vestry.** A room adjoining a church, where the vestments of the minister are kept and parish meetings held. In American Protestant churches, the Sunday-school room is often called the vestry.

**Viaduct.** A structure of considerable magnitude, and usually of masonry, for carrying a railway across a valley.



VERMICULATED

**Vignette.** A running ornament, representing, as its name imports, a little vine, with branches, leaves, and grapes. It is common in the Tudor period, and runs or roves in a large hollow or casement. It is also called Trayle.

**Villa.** A country house for the retreat of the rich.

**Volute.** The convolved or spiral ornament which forms the characteristic of the Ionic capital. Volute, scroll, helix, and cauculus are used indifferently for the angular horns of the Corinthian capital.

**Vousoir.** One of the wedge-like stones which form an arch; the middle one is called the key-stone.

**Wainscot.** The wooden lining of walls, generally in panels.

**Wall Plates.** Pieces of timber which are placed on top of brick or stone walls so as to form the support to the roof of a building.

**Warped.** Twisted out of shape by seasoning.

**Water Table.** A slight projection of the lower masonry or brickwork on the outside of a wall a few feet above the ground as a protection against rain.

**Weather Boarding.** Boards lapped over each other to prevent rain, etc., from passing through.

**Weathering.** A slight fall on the top of cornices, window-sills, etc., to throw off the rain.

**Wicket.** A small door opening in a larger. They are common in medieval doors, and were intended to admit single persons, and guard against sudden surprises.

**Wind.** A turn, a bend. A wall is *out of wind* when it is a perfectly flat surface.

**Wing.** A side building less than the main building.

**Withes.** The partition between two chimney flues in the same stack.

## ARCHITECTURAL TERMS AS DEFINED IN VARIOUS BUILDING LAWS

COMPILED BY THE AMERICAN ARCHITECT AND BUILDING  
NEWS, PAGE 150, VOL. XXXIII

(Republished by permission of Ticknor & Co.)

---

### Terms Defined

*The following terms chance to be defined in sundry building codes, which are mentioned in each case. The fact that other codes are not mentioned is not necessarily a proof that the term is not also elsewhere in use as defined.]*

**Adjoining Owner.** The owner of the premises adjoining those on which work is doing or to be done. [*District of Columbia.*]

**Alteration.** Any change or addition except necessary repairs in, to, or upon a building affecting an external, party, or partition wall, chimney, floor, or driveway, and "to alter" means to make such change or addition. [*Boston and New York.*]

**Appendages.** Dormer-windows, cornices, moldings, bay-windows, towers, cupolas, ventilators, etc. [*Chicago and Minneapolis.*]

**Basement Areas.** Sub-surface excavations adjacent to the building-line for lighting or ventilation of cellars or basements. [*District of Columbia.*]

**Attic Story.** A story situated either in whole or in part in the roof. [*Denver and District of Columbia.*]

**Base.** "The base of a brick wall" means the course immediately above the foundation wall. [*Cincinnati and Cleveland.*]

**Basement Story.** One whose floor is 12" or more below the sidewalk, and whose height does not exceed 12' in the clear; all such stories that exceed 12' high shall be considered as first stories. [*Chicago and Louisville.*]

A story whose floor is 12" or more below the grade of sidewalk. [*Milwaukee.*]

A story whose floor is 3' or more below the sidewalk, and whose height does not exceed 11' in the clear; all such stories that exceed 11' high shall be considered as first stories. [*Minneapolis.*]

A story suitable for habitation, partially below the level of the adjoining street ground.\* [*District of Columbia and Denver.*]

(See Cellar.)

**Bay-window.** A first-floor projection for a window other than a tower-projection or show-window. [*District of Columbia.*]

Any projection for a window other than a show-window. [*Denver.*]

**Bearing Walls.** Those on which beams, trusses, or girders rest. [*New York and San Francisco.*]

**Brick Building.** A building the walls of which are built of brick, stone, iron, or other substantial and incombustible materials. [*Boston, Denver, and Kansas City.*]

\* And below the first floor of joists. [*District of Columbia.*]

**Building.** Any construction within the scope and purview of these regulations. [*District of Columbia.*]

**Building Line.** The line of demarcation between public and private property. [*District of Columbia.*]

**Building Owner.** The owner of premises on which work is doing or to be done. [*District of Columbia.*]

**Business buildings** shall embrace all buildings used principally for business purposes, thus including, among others, hotels, theaters, and office-buildings. [*Chicago, Louisville, Milwaukee, and Minneapolis.*]

**Cellar.** Basement or lower story of any building, of which one-half or more of the height from the floor to the ceiling is below the level of the street to which it joins.† [*Boston, Denver, and Kansas City.*]

Portion of building below first floor of joists, if partially or entirely below level of the adjoining parking, street, or ground, and not suitable for habitation. [*District of Columbia.*]

**Cement-mortar.** A proper proportion of cement and sand without the admixture of lime. [*Kansas City.*]

**Division Wall.** One that separates part of any building from another part of the same building. [*Cincinnati and Cleveland.*]

Floor-bearing walls extending through buildings from front to rear, and separating stores and tenements in buildings or blocks owned by the same party. [*Minneapolis.*]

(See Partition-wall.)

**Dwelling-house Class.** All buildings except public buildings and buildings of the warehouse class. [*Cincinnati and Cleveland.*]

Shall not apply to buildings accommodating more than three families. [*San Francisco.*]

**External Wall.** Every outer wall or vertical enclosure of a building other than a party-wall. [*Boston, Cincinnati, Cleveland, Denver, District of Columbia, Kansas City, and Providence.*]

**First Story.** The story the floor of which is at or first above the level of the sidewalk or adjoining ground, the other stories to be numbered in regular succession, counting upward. [*Denver and District of Columbia.*]

**Footing Course.** A projecting course or courses under base of foundation wall. [*Cincinnati and Cleveland.*]

**Foundation.** That portion of wall below level of street curb,† and, where the wall is not on a street, that portion of wall below the level of the highest ground next to the wall. [*Boston, Kansas City, New York, and Providence.*]

Portion of exterior wall below surface of adjoining earth or pavement, and portion of partition or party wall below level of basement or cellar floor. [*District of Columbia and Denver.*]

**Foundation, Basement, or Cellar Walls.** That part of walls of building that is below the floor or joists, which are on or next above the grade line. [*Denver.*]

Portion of the wall below the level of street curb, in front of the central line of building. [*San Francisco.*]

\* Ground. [*Providence.*]

† And not suitable for habitation. [*Denver.*]

‡ "And serve as supports for piers, columns, girders, beams, or other walls." [*New York.*]

**Non-combustible Scantling Partition.** One plastered on both sides upon iron or wire cloth, and filled in with brickwork 8" high from floor, provided the height is not over 80' high. [*Chicago.*]

**Non-combustible Roofing.** Covered with not less than three (3) thicknesses of felt, and good coat of tar and gravel, or with tin, corrugated-iron, or other existing material with standing-seam or lap-joint. [*Denver.*]

**Lengths.** Walls are deemed to be divided into distinct *lengths* by return walls, and the length of every wall is measured from the center of one return wall to the center of another, provided that such return walls are external or party walls of the thickness herein required, and bonded into the walls so deemed to be divided. [*Cincinnati and Cleveland.*]

**Flammable Material.** Dry goods, clothing, millinery, and the like in stores, flyings or goods in factories, or other substance readily ignited by drops or flyings from electric lights. [*Minneapolis.*]

**Lodging-house.** A building in which persons are temporarily accommodated in sleeping \* apartments, and includes hotels. [*Boston and Kansas City.*]

**Any building or portion thereof in which persons are lodged for hire for less than a week at one time.** [*District of Columbia and Providence.*]

**Any building or portion thereof in which persons are lodged for hire temporarily, and includes hotels.** [*Denver.*]

**mansard Roof.** One formed with an upper and under set of rafters, the upper set more inclined to the horizon than the lower set. [*Denver and District of Columbia.*]

**Oriel Window.** A projection for a window above the first floor. [*District of Columbia.*]

**Partition.** An interior division constructed of iron, glass, wood, lath and plaster, or other destructible materials. [*District of Columbia.*]

**Partition-wall.** Any interior wall of masonry in a building. [*Boston, Kansas City, and Providence.*]

**Any interior wall of non-combustible material.** [*District of Columbia.*]

**Any interior division constructed of iron, glass, wood, lath and plaster, or combination of those materials.** [*Denver.*]

**See Division Wall.)**

**Party-wall.** Every wall used, or built, in order to be used, as a separation of two or more buildings.† [*Boston, Cincinnati, Cleveland, Denver, Kansas City, and Providence.*]

**Any wall built upon dividing line between adjoining premises for their common use.** [*District of Columbia.*]

**Parking.** The space between the sidewalk and the building line. [*District of Columbia.*]

**Parking Line.** The line separating parking and sidewalk. [*District of Columbia.*]

**Public Building.** Every building used as church, chapel, or other place of public worship; also every building used as a college, school, public hall, hospital, theater, public concert-room, public ball-room, public lecture-room, or for any public assemblage. [*Boston, Chicago, Cincinnati, Cleveland, Denver, Kansas City, and Minneapolis.*]

\* Staying apartments. [*Kansas City.*]

† To be used jointly by separate buildings. [*Cincinnati and Cleveland.*]

Such buildings as shall be owned and occupied for public purposes for State, the United States, the corporation of the City of Brooklyn, or other schools within said city. [*Brooklyn.*]

**Public Hall.** Every theater, opera-house, hall, church, school, or other building intended to be used for public assemblage. [*Milwaukee and Louisville.*]

**Return Wall.** No wall subdividing any building shall be deemed a return wall, as before mentioned, unless it is two-thirds the height of the external party-walls. [*Cincinnati and Cleveland.*]

**Shed.** A skeleton structure for storage or shelter. [*District of Columbia.*]

Open structure, enclosed only on one side and end, and erected on the ground. [*San Francisco.*]

Open or closed board structure. [*Denver.*]

**Show-window.** A store-window in which goods are displayed for sale or advertisement. [*District of Columbia and Denver.*]

**Square thereof.** The square or level of the walls before commencing pitch for roof. [*District of Columbia.*]

**Standard Depth for Foundations.** For brick and stone buildings below curb line. [*San Francisco.*]

**Standard Depth of Cellars.** 16', measured down from sidewalk grade to property line. [*Memphis.*]

**Standard Iron Door.** Made of No. 12 plate-iron, frame or casing 2" x 2" x 3/8" angle-iron, firmly riveted. Two panel doors, to have proper cross bars, one panel on either side, fastened together with hooks or proper bolts at top and bottom, and with not less than two lever-bars. All doors hung on iron frames of 3/8" x 4" iron, securely bolted together through wall, swung on cast hinges, fitting close to frame all around; sill between doors, iron, brick, or stone, to rise not less than two (2) inches above floor on each side of opening. Lintel over door, brick, iron, or stone. Floors of basement, when doors are to swing in, stone or cement, in no case wood. [*Denver.*]

**Standard Skylight.** Constructed of wrought-iron frames, with hammer or desk-light glass not less than 1/2" thick; not larger than 10' by 12', except by special permission of the Inspector. [*Denver.*]

**Storehouse.** (See Warehouse Class.)

**Street.** All streets, avenues, and public alleys. [*Minneapolis.*]

**Tenement-house.** A building which, or any portion of which, is to be occupied, or is occupied, as a dwelling by more than three\* families living independently of one another, and doing their cooking upon the premises. [*Boston, Denver, and Kansas City.*]

Or by more than two families† above the second floor, so living and cooking. [*Boston and Kansas City.*]

Building which shall contain more than two rooms in front on each floor, which shall be built with a passage or arched way between distinct parts of the same building, or which building shall be intended for the separate accommodation of different families or occupants. [*Charleston.*]

**Theater.** Public hall containing movable scenery or fixed scenery which is not made of metal, plaster, or other incombustible material. [*Chicago, Louisville, and Milwaukee.*]

\* Two instead of three. [*District of Columbia and Minneapolis.*]

† Upon one floor, but having a common right in the halls, stairways, yards, etc. [*Providence.*]



**Thickness of a Wall.** The minimum thickness of such wall.\* [*Boston, Cincinnati, Cleveland, Kansas City, Milwaukee, and Providence.*]

**Double Covered Fire-door.** Wood doors or shutters, double thickness of wood, cross or diagonal construction, covered on both sides and all edges with sheet-iron, joints securely clinched and nailed. [*Denver.*]

**Door Projection.** A projection designed for an ornamental door-entrance, ornamental windows, or for buttresses. [*District of Columbia.*]

**Basement.** An underground construction beneath parking or sidewalk. [*District of Columbia.*]

**Veneered Building.** Frame structure, the walls covered above the sill by a layer of brick, instead of clapboards. [*Common understanding in Chicago, Milwaukee, and Minneapolis, but not defined by law.*]

**Warehouse Class.** Buildings used for the storage of merchandise, manufactures in which machinery is operated, breweries, and distilleries. [*Cincinnati and St. Louis.*]

**Width of buildings** shall be computed by the way the beams are placed; the lengthwise of the beams shall be considered and taken to be the widthwise of the building. [*New York and San Francisco.*]

**Wholesale store, or storehouse,** shall embrace all buildings used (or intended to be used) exclusively for purpose of mercantile business or storage of goods. [*Chicago, Louisville, and Milwaukee.*]

**Wooden Building.** A wooden or frame† building. [*Boston, Kansas City, and Minneapolis.*]

Any building of which an external or party wall is constructed in whole or in part of wood. [*Denver and District of Columbia.*]

Having more wood on the outside than that required for the door and window frames, doors, shutters, sash porticos, and wooden steps, and all frame buildings, although the sides and ends are proposed to be covered with corrugated iron or other metal, shall be deemed a wooden building under this law. [*Charleston and Nashville.*]

\* As applied to solid walls. [*Minneapolis and Providence.*]

† Or veneered. [*Minneapolis.*]



# INDEX

By

CLINTON L. BOGERT

Associate Member of American Society of Civil Engineers

Numbers refer to Pages. Consult also the Glossary, pages 1796-1850.

as (Glossary), 1796  
 eviations of terms, 122, 123  
 tments, arch, 305  
 er, 306  
 ylene gas, 1431  
 atics, architectural, 1486-1500  
 rtising, ethics, 1729  
 a radiator, 1266  
 e, 130, 1501  
 egate, concrete, 241, 287, 908, 909,  
     945  
 cement, form, 1765  
 cements, 1751  
 compressor, water-supply, 1396  
 conditioning, 1352  
 nsity, 1247, 1339  
 ow, resistance, 1333  
 xt-water systems, removal, 1307  
 roperties, 1254-1256  
 antity, symbol, 1247  
 ecific heat, 1250, 1255  
 ntilation, requirements, 1260, 1354,  
     1356  
 tiated, effects, 1352  
 ducts, 1333-1341  
 lift, 1396  
 lock, pneumatic caisson, 211  
 pressure, pneumatic caisson, 211  
 aster, 131, 1501  
 lime, 1553  
 hol, specific gravity and weight,  
     1501  
 ury (Glossary), 1797  
 ations, defined, 1851  
 minum, specific gravity and weight,  
     1501  
 ican Blower Co., heater, 1329-  
     1332  
 ican Institute of Architects,  
     canons of ethics, 1730  
 apters, 1788  
 ompetitions, 1733  
 ocuments, 1767  
 essional practice, 1727  
 chedule of charges, 1728, 1731  
 tandard documents, 1748

American Steel & Wire Co's gauge,  
     401, 402  
 Amperes, defined, 1457  
 Anchor, box, 753, 790, 792, 793  
     reinforced-concrete, 919  
     steel beams, 619  
     trusses, 1150, 1152, 1168  
     wooden beams, 616, 762, 783-800  
 Anchor-bolts, adhesion, 240  
     placing, 1194  
     steel beams, 619  
     steel stacks, 1377  
 Ancient measures and weights, 34  
 Aneroid, barometer, 1249  
 Angle in geometry, 36  
     bisected, 69  
     critical, domes, 1213  
     friction, retaining walls, 253  
     measure, two-foot rules, 68  
     repose, materials, 253, 254, 256  
 Angle of structural steel, 361-367  
     beams, safe loads, 566, 586-590  
     connections, beams, 616  
     double, properties, 370-372  
     moment of inertia, 339, 362-367  
     oblique loading, 593  
     price, 1204, 1211  
     properties of, steel, 362-367  
     shelf, 787-790  
     struts, 488, 501-503  
     tension-members, loads, 385, 399  
         deduction, 399, 400, 702  
 Angle-anchor, 619  
 Angle-and-plate columns, 475, 476  
 Angle-bar (Glossary), 1797  
 Angle-bracket, 422  
 Angular measure, 30, 68  
 Anhydrite, 131  
 Annealing, rivets, 382, 414  
 Anthracite coal, combustibles, 1271  
     for hot-air heating, 1317  
 Apartment-houses, floor-joists, 737  
     live loads, 149, 1198  
     I beams in floor, size, 864  
     steel, weight, 1207  
 Apatite, 131

- Apostles and Saints, symbols, 1727**  
**Apothecaries' weight, 29**  
**Apple-tree, wood, hardness, 1558**  
**Apron, retaining-walls, 263**  
**Aragonite, 131**  
**Arbitration, contract, 1763**  
**Arbitration-bar, cast-iron test, 380**  
**Arc, arcs, circular, 38, 69, 70**  
     lengths, 54  
**Arc-lamps, 1462**  
**Arch, arches, masonry, 305-321 (Glossary), 1799**  
     angle of friction, 311  
     brick, 306  
     center of pressure, 311, 313  
     centers, 308  
     concrete, reinforced, 321  
     out-stone, 310  
     depth of keystone, 308-310  
     elliptical, 306  
     failure of, 311-313  
     floor, 827-844  
     forms of, 306  
     groined, 1235-1240  
     inverted, in footings, 227, 228  
     keystone, 305, 308-310  
     line of fracture, 316  
     line of pressure, 311-321  
     line of resistance, 311-321  
     load, actual, masonry, 318  
     loaded, 317  
     middle third, principle of, 311-315,  
         1225, 1227, 1240  
     New York City requirements, 307  
     plate-girder arches, 1131  
     pointed, failure of, 312  
     rings, 308, 317  
     rise, 307  
     segmental, 305, 306, 307, 321  
     semicircular, 306  
     semielliptical, 321  
     solid ribs, 1132  
     stability, determination, 311-321  
     strength, 306  
     surcharged, 317  
     three-centered, 306  
     thrust, 305, 307, 311-321  
     tie-rods, for I beams, 619, 865  
         roof-trusses, 1120  
         segmental arches, 307  
     trussed, 1121  
     unloaded, 311  
     voussoirs, 305, 311  
**Arched trusses, 1035-1043**  
     stresses, 1118-1120  
     wooden, 1020-1024  
**Architects, canons of ethics, 1730**  
     certificates, 1771  
     charges, schedule, 1728, 1731  
     competitions, 1733-1747  
     drawings, 1718, 1728, 1731, 1754  
**Architects, estimates, 1728**  
     examinations, 1772  
     inspection of work, 1755  
     organizations, 1788-1795  
     professional practice, 1727  
     registration laws, 1768-1773  
     status and decisions, 1754  
     superintendence, 1728  
**Architectural acoustics, 1486-1500**  
**Architectural engineering, terms, 1128**  
**Architectural fellowships, 1779-1788**  
     medals, 1779-1788  
**Architectural societies, 1788-1795**  
**Architectural terms (Glossary), 11850**  
     building laws, 1851-1855  
**Architecture, schools of, 1779**  
**Areas, circles, tables, 42-54**  
     elementary, 332  
     geometrical figures, 38-54, 99  
         334-338, 348-351  
     net sectional, of tension-membranes, 386  
**Arithmetic, practical, 3-24**  
**Armories, steel, weight, 1208**  
**Artificial cements, 236-240**  
**Asbestic plaster, 818, 819**  
**Asbestos, building-lumber, 819**  
     corrugated sheathing, 819  
     metal, 819  
     products, 819  
     roofing-shingles, 819  
     sheathing, 819, 1501, 1567  
     specific gravity and weight, 1501  
**Ash (wood) deflection in beams, 619**  
     hardness, 1558  
     specific gravity, 1501  
     ultimate unit stresses, 651  
     weight, 651, 1501, 1558  
**Ashes, angle of repose, 256**  
     specific gravity, 1501  
     weight, 651, 1501, 1558  
**Ashlar (Glossary), 1799**  
     masonry, 233, 260, 441, 1553, 1554  
**Asphalt, 1608**  
     floors, 1608, 1609  
     mastic, 1608  
     pavements, 1608  
     rock, 1608  
     roofing, 1608  
     specific gravity and weight, 1501  
**Asphalt-gravel roofing, 871, 1505**  
**Asphaltum, 1608, 1799**  
     specific gravity and weight, 1501  
**Assembly-halls, joists, 730, 744**  
     live-loads, 719, 720, 1193  
**Asylums, non-fire-proof, height, 1135**  
     ventilating and heating, 1335  
**Asymptote (Glossary), 1799**

manta building code, loads on founda-  
 tion-beds, 143  
 office-building loads, 151  
 atoriums, heating and ventilating  
 requirements, 1354  
 ighting, 1451  
 ve loads, 719, 720, 1198  
 pite, 131  
 omobile factory, design and cost, 803  
 omobiles, dimensions, 1642  
 irdupois weight, 28  
 al force, definition, 375  
 s, conjugate, 38  
 eutral, 295, 332-338, 555, 621  
 ransverse, 38  
 k, arch, 305  
 timore, fire, reinforced concrete in,  
 957  
 uilding code, steel columns, 481  
 ad of column (Glossary), 1801  
 rometer, 1249  
 ressure, measurement, 1249, 1252  
 rns, cost, 1613  
 rrel, dimensions, 1644  
 rrel vault, 1231-1235  
 rrett specifications, roofing, 1595  
 rs (steel), 385-398  
 reas, 1514-1521  
 ase price, 1205  
 ircumferences, 1514-1521  
 acing, 385  
 reinforcing, 915-921  
 ase loads, 388-392  
 standard, classification and cost, 1211  
 eights, 1514-1521  
 rtizan (Glossary), 1801  
 salt, 131  
 specific gravity and weight, 1501  
 se, columns (Glossary), 1801  
 cast-iron column, 457, 459  
 material, 1195  
 mill-construction, 782-788  
 pipe columns, 470, 471, 472  
 pressures, 265, 441, 1200  
 steel columns, 473-477  
 se-plates, 440-445, 1524  
 sement, defined, 1851  
 walls, 228, 229  
 sin-slabs, marble, 1641  
 th, foot, 1641  
 plunge, 1422  
 seat, 1641  
 th-tubs, dimensions, 1640  
 symbols for, 1426  
 tter, 1801  
 cellar walls, 229  
 retaining-walls, 259  
 ttlement (Glossary), 1802  
 ay window (Glossary), 1802  
 am, beams (see also Girders)

Beam, bearing on wall, 634, 687  
 bearing-plate areas, 440-444  
 bending moment, 324-331, 555, 939  
 continuous beams, 673  
 influence-lines, 1134  
 reinforced-concrete, 935  
 Bethlehem, 357, 358, 592-602  
 buckling, 183, 565, 567, 569  
 girders, 686, 705  
 separators, 612  
 wooden, 627  
 cantilever (see Cantilever, beams)  
 Carnegie, 352-356, 574-591, 605, 606  
 cast-iron (see Lintels)  
 channel (see Channels)  
 clamps for connecting, 616  
 coefficient of strength, 556, 628  
 compound, 652-654, 763  
 compression in, 555  
 concrete fire-protection, 860  
 concrete, not reinforced, 628, 637  
 connections, steel beams (see Fram-  
 ing, steel beams)  
 wooden beams, 749-757, 789, 790  
 continuous, 555, 671-680, 979, 980  
 cross-section irregular, 557  
 cylindrical, 667  
 deck, 565  
 deflection, 663-670  
 allowed, 566, 628, 664, 736  
 continuous girders, 674-676  
 steel, 566, 612, 668-670, 676  
 wooden, 636, 653, 654, 664, 667  
 double, 564, 603, 604, 607-611  
 elasticity, 555, 663  
 external forces, 325  
 factors of safety, 556  
 fixed, strengths, 331, 634  
 flexure, 324-331, 332-334, 555  
 reinforced-concrete beams, 924-941  
 steel beams, 564-573  
 wooden beams, 627-637, 652-656  
 floor, steel, specifications, 1201, 1202  
 girder (see I beams; also Girders)  
 grillage, foundations, 165-169, 181-  
 185, 678-680  
 H beams, 356, 474, 585, 1204  
 I beams (see I beams)  
 inclined, 564, 665  
 influence-lines, 1134  
 internal forces, 325  
 keyed, 653-655  
 lateral deflection, 566, 670  
 loads, general principles, 555, 565,  
 593, 629, 665  
 tables (see Beams, steel, etc.)  
 materials used for, 564  
 neutral axis, definition, 555  
 neutral surface, definition, 555  
 overhanging (see Cantilever, beams)  
 reactions, 324-324

**Beam, rectangular, relative strength,**  
 633, 634  
 stiffness, 665, 666  
 reinforced-concrete, 924-941, 971-975  
 resisting moment, 333, 555, 635, 683,  
 929  
 shear, 183, 411, 413, 565, 567-570  
 simple, 323-330, 555  
 span, 555  
 span-limit, 566  
 steel, anchors for, 619  
   base price, 1204  
   bending moments, table of maxi-  
   mum, 574-576  
   Bethlehem, 357, 358, 592-602  
   buckling, 183, 565, 567, 569, 612,  
   627  
   Carnegie, 352-356, 574, 591, 605,  
   606  
   channels (see Channels)  
   connections (see Framing, steel  
   beams)  
   crippling (same as buckling)  
   deflection, vertical (see above)  
   dimensions, 352, 565  
   economy and strength, 565  
   end-reactions, 569, 574-576  
   fiber-stress, 556, 557, 569  
   fireproofing, 780-782, 827-842,  
   844, 849, 854-860  
   flange-thickness, 592  
   forms of, 565  
   framing and connecting (see  
   Framing)  
   H beams, 474, 585, 1204  
   H beams, properties, 356  
   heavy, 565  
   I beams (see I beams)  
   lateral deflection, 566, 670  
   light, 565  
   loads, safe, 565, 577-591, 594-602  
   separators, 612-614, 1202  
   shearing-stresses, 181-185, 567,  
   568, 569, 574, 575  
   standard, 352  
   strength affected by dimensions,  
   556, 565  
   strut, 571, 572  
   T beams, 337, 368, 369, 591, 1211,  
   1212  
   tie, 572  
   tie-rods, 619, 865  
   unit stresses, 1200  
   web-buckling, 181-185, 565, 567,  
   569, 612  
   web-thickness, 592  
 stiffness, 565, 635, 663-670  
 stone, 637  
   coefficients of strength, 556, 628  
 stresses, 555-557, 567, 569, 603, 604,  
 628, 635

**Beam, strut, steel 571, 572**  
 wooden, 633  
 supplementary, 352, 561  
 T beam, 337, 368, 369, 591, 1211,  
 1212  
 tension in, 555  
 tie-beams, steel, 572  
   wooden, 430-432, 434, 435, 633  
 wall-support, 612  
 wooden, 627-668, 717-757, 780, 781,  
 795  
   anchors, 616, 762, 783-800  
   bolted, 429, 653, 655  
   buckling, 627  
   built-up, 652, 656  
   cantilever, 629  
   cedar, 628, 640, 664  
   chestnut, deflection, 664  
   distributed loads, 641  
   coefficients, 628  
   compound, 652-654, 763  
   connections, 749-757, 789, 791 (see  
   also Framing, floors, wooden)  
   conversion factors, 637, 663  
   cross-sections, 627, 637  
   cut from log, strongest, 634  
   cylindrical, 634, 667  
   cypress, distributed loads, 641  
   deflection, 636, 653, 654, 664, 667  
   Douglas fir, distributed loads, 641,  
   642, 664  
   dressed, 667  
   Eastern fir, loads, 639  
   end-bearing, 634  
   flitch-plate, 655  
   framing, 749-757  
   framing to steel beams, 789, 790  
   hangers (see Hangers)  
   hemlock, loads, 628, 638, 664  
   keyed, 653-655  
   loads, safe, 638-646, 667  
   mill-construction, 758-769  
   nominal dimensions, 636, 667,  
   736, 1559  
   Norway pine, loads, 641, 664  
   redwood, loads, 640  
   shear, horizontal, 412, 635  
   sizes, nominal and actual, 636,  
   667, 736, 1559  
   spans, maximum, 737-746  
   spruce, loads, 628, 639, 664  
   stiffness, 664  
   strongest cut from log, 634  
   strut, 633  
   tension, 635  
   tie, 430-432, 434, 435, 633  
   trussed, 656-662  
   unit stresses, 557, 627, 635, 647-651  
   white oak, loads, 643, 664  
   white pine, loads, 639, 664  
   yellow pine, 628

**Beam, wooden, yellow pine, deflection,**  
     664  
     loads, 642, 643, 666  
     wrought iron, 628  
     deflection, 664  
**Beam-box, 753, 762, 790, 792, 793**  
**Beam girders (see I beams)**  
**Beam-hangers (see Hangers)**  
**Bearing-brackets, cast-iron columns,**  
     445-447  
**Bearing-plates, 440-445, 1524**  
     pressures, 441, 1200  
**Bearing values (see materials in ques-**  
     **tion)**  
**Bed, masonry (Glossary), 1802**  
**Bedsteads, dimensions, 1638, 1640**  
**Beechwood, hardness, 1558**  
**Bell-cot or gable (Glossary), 1803**  
**Bells, 1725**  
**Belt, for shafting, 1721**  
     mill-construction, 764, 765  
**Bending moments, beams, 324-331,**  
     555, 939  
     bolts in wooden construction, 429,  
         431  
     channels, table, 576  
     columns, 485  
     continuous girders, 673  
     diagrams for beams and girders, 328,  
         330, 564, 678, 690, 695, 698  
     footings, 174, 175, 178  
**I beams, table of maximum, 574,**  
     575  
     influence lines, 1134  
     moving loads, 1134-1135  
     pins, 423-429  
     reinforced concrete, 934, 935  
     slabs, concrete, 932, 936, 984-991,  
         994  
**T beams, concrete, 992**  
**Berger's studding, 881**  
     metal lumber, 852, 858, 881  
**Bessemer steel, 380**  
**Bethlehem beams, 357, 358, 592, 594-**  
     604  
**Bethlehem columns, 475, 479, 482-488,**  
     loads, 483, 506-515  
**Bevels, 90**  
**Billard-tables, dimensions, 1638**  
**Birchwood, hardness, 1558**  
**Bitumen, 1608, 1609**  
**Bituminous coal, combustibles, 1271**  
**Blackboards, dimensions, 1644, 1645**  
**Black-line prints, 1719**  
**Black-tin, pipe, 1419**  
**Blocks, hollow building, filling, 287**  
     concrete (see Concrete, blocks)  
**Blower system, heating, 1324**  
**Blue-prints, 1718**  
**Bluestone, beams, coefficient for, 628**  
     flagging, 282, 1539

**Board-measure, table, 1560-1562**  
**Boiler, 1273-1283**  
     connections, 1279  
     covering, 1361  
     horsepower, 1274  
     incrustation, 1429  
     location, 1357  
         in mills, 765  
         in warehouses, 780  
     rating, 1301  
     residence, specification, 1362  
     shops, steel, weight, 1208  
     symbols, 1351  
     water, for ranges, 1642  
**Boiler-plants, mill-construction, 765**  
**Bolsters, mill-construction, 454, 795**  
**Bolt, bolts, anchoring, 240**  
     bearing strength, 429, 439, 1138  
     bending, 1138  
     bending moment, 429, 431  
     beveled washers, 1202  
     built-up beams, 652, 654  
     expansion, 1534  
     fiber-stress, 1138  
     foot of rafter, 437  
     girders, 432, 433  
     heads, 1525-1528  
     safe bearing in timber, 430  
     screw-ends, upset, 387  
     shearing value, 412, 429-439, 1138  
     shock loads, 1202  
     steel, table, 431  
         stresses, 618, 1138, 1200  
     strap-joints in trusses, 436  
     swedge, 619  
     tension, 431, 1138  
     truss-joints (see Roof-trusses)  
     weight, 1527  
     wrought iron, table, 431, 1138  
**Bolt-heads, 1525-1528,**  
     standard dimensions, 1525-1526  
     weight, 1526-1528  
**Bonanza reinforced-cement tiles, 868**  
**Bond, brickwork, 268, 306**  
     masonry (Glossary), 1803  
     timber (Glossary), 1803  
**Bond-stones in piers, 269**  
**Bonds, form, 1763**  
     guaranty, 1757  
**Book-stacks, library, 1696**  
**Book-tile, roofing, 868**  
**Borings, for foundations, 144**  
**Boss (Glossary), 1804**  
**Boston building code, column-formula,**  
     460, 481, 493-496  
     loads on foundation-beds, 142  
     loads on masonry, 267  
     office-buildings, assumed loads, 151  
     rivets, bearing and shear, 419  
     steel column formula. 481, 493-496  
     thickness of walls, 230, 231, 232

- Boston, Chamber of Commerce Building,** 192  
**Bostwick lath,** 884  
**Boulders,** 134, 136, 141  
     safe loads on, foundations, 141  
**Bowling-alleys, dimensions,** 1643  
**Bowstring truss,** 1035  
     stresses, 1094, 1096  
**Box anchors, beam-supports,** 753, 762, 790, 792, 793  
**Box columns,** 467, 479, 484  
     moment of inertia, 342  
     plate-and-angle, 479  
**Box girders,** 681-716  
     bending moment, 683, 695, 697, 698, 699  
     buckling, 686, 705  
     construction, details of, 682  
     cover-plates, 696  
     end-reactions, maximum, 703, 706-716  
     examples, 694-703  
     flange-area, 683, 692, 696, 699,  
     framing and connections, 615  
     moment of inertia, section, 341, 342  
     rivet-holes, loss of area, 702  
     shear, 684-687, 690, 691, 696, 698  
     specification, 1201, 1202, 1203  
     steel-beam, 607-611  
     stiffeners, 681, 686, 691, 696, 1201, 1203  
     web-plate, buckling value, 686, 705  
     shearing value, 684, 703  
     weight, 687, 701  
**Box-hangers (see Beam-boxes)**  
**Bracing, steel structures,** 1202  
     wind, buildings, 1171-1193  
**Brackets, cast-iron columns,** 445-447  
     terra-cotta, 278  
**Brads,** 1529  
**Brass, castings, shrinkage,** 1521  
     specific gravity, 1502, 1510, 1511  
     weight, 1502, 1510, 1511  
**Breast-walls,** 262-263  
**Breeching, dimensions,** 1366  
**Brechaud method, underpinning,** 221  
**Brick, bricks, angle of friction,** 253  
     arches, laying, 306-307  
     burning, 1540  
     clay, 275, 1540  
     coefficient of friction, 253  
     color, 1540, 1543, 1544, 1547  
     cost, 1544  
     crushing-height, 269  
     crushing strength, 270, 271  
     dry-pressed, 1540  
     enameled, 1543  
     fiber-stresses, 557  
     fire, 1540  
     fire-resistance, 814  
     flexure, 178  
     glazed, 1543  
     lime-mortar, 1541  
     machine-made, 1540  
     manufacture, 1542  
     molded, 1540  
     paving, 1540  
     piers, 268-276, 278  
     piling, space required, 1547  
     repressed, 1540  
     retaining-walls, 259, 260  
     sand-lime, 1541  
         properties of, 1543  
     size, 1540, 1543  
     soft-mud, 1540  
     specific gravity, 1502  
     strength, ultimate, 270  
     stiff-mud, 1540  
     tests, 270, 275, 281, 1542  
     vaults, 1238  
     weight, 1502, 1541  
**Brickwork,** 1540-1548 (see, also, **Masonry, Walls, etc.**)  
     arches, 306  
     bond, effect on strength, 268  
     cement mortar required, 239  
     compared with concrete, 968  
     cost, 1544-1547  
         mill-buildings, 808-810  
     crushing strength, 270-276  
     data, 1540-1548  
     efflorescence, 1547  
     estimating quantities and cost, 1547-1546  
     fire-resistance, 814  
     floor-arches, 827-828  
     footings, 226, 227  
     lintels supporting, 623  
     loads, safe, 265-268, 287, 441  
     moisture, 1547  
     mortar, 239, 276, 818  
     mortar-colors for, 1547  
     piers, 267-276, 278  
         bond-stones, 269  
         crushing strength, 271-276  
         safe loads, 267-268  
         tests, 272-278  
     pressures, 265, 441, 1200  
     quantity estimates, 1544-1547  
     specific gravity, 1502  
     strength, safe, 265-268, 287, 441  
     tensional strength, 178  
     walls, safe loads, 265, 441  
     warehouse, 778  
     weight, 1502  
**Bridging (Glossary, 1804) floor-joist**  
     748, 749  
**British thermal unit,** 33, 1250, 1251-1255, 1684  
**Bronze, door-frames,** 895  
     specific gravity and weight, 1502



size, window-frames, 895  
 Town & Sharpe wire-gauge, 401, 402,  
     1469, 1473, 1509, 1510  
 Town-line prints, 1720  
 Townstone, crushing strength, 279, 281  
 Trussing, plate girders, 686, 705  
 Steel beams, 565, 567-569, 612, 627  
 Web, box girders, 705  
     plate girders, 705  
 Wooden beams, 627  
 Fire building code, loads on founda-  
     tion, 142  
 Masonry loads, 267, 287  
 Office-buildings, assumed loads, 151  
 Building, alterations, 1851  
     steel, drafting, 1207  
 Cost, 1611-1634  
     of slow-burning, 758, 802, 1619  
     per cubic foot, 1611-1634  
     per square foot, 1627-1634  
     reinforced-concrete, 1618  
 Cubage, 1612  
 Depreciation, 1634  
 Drainage, 1407-1414, 1419-1421  
 Factory, 968  
 Fire-proof, cost, 802, 812, 1619-1625  
 Fireproofing, 811-905  
 Government, cost, 1628-1634  
 Heating, 1247-1363  
     temperatures, 1256  
 Iron and steel, 1627  
 Legal definition, 1852  
 Loads, 1196  
 Mill-construction, 1618  
 Non-fire-proof, 812, 813  
 Office, specifications, 1194-1212  
 Papers, 1564  
 Protection from outside hazard, 901-  
     903  
 Reinforced-concrete, 968-997  
 Shrinkage in, 1427-1428  
 Signing by architects, 1729  
 Steel, cost, 1206  
     weight, 1207  
 Structural-steel specifications, 1194-  
     1212  
 Veneered, 269, 1855  
 Ventilating, 1348-1354, 1356  
 Wind bracing, 1171-1193, 1202  
 Wooden, defined, 1855  
 Building laws, bearing on masonry, 441  
 Bearing-walls, 269  
 Brickwork, 267  
 Column-protection, 822-826  
 Concrete columns, length of, 941  
 Concrete fire-protection, 955-960  
     floor-slabs, 937  
 Electric work, 1480-1481  
 Elevator-installation, 1663  
 Fire-proof construction, 811-905,  
     1618-1620

Building laws, fire-proof paint, 821  
     fire-proof wood, 820  
     floor fire tests, 827  
     flooring, fire-proof, 892-893  
     floor-loads, 719, 730, 1198  
     footings, assumed loads on, 151  
     formulas, steel columns, 481  
     foundation-beds, loads on, 142  
     hooped columns, 942  
     loads, on brickwork, 269  
         on floors, 719, 730  
         on foundation-beds, 142  
         on masonry, 267, 287  
     non-fire-proof buildings, areas, 812  
         heights, 812, 813  
     reinforced-concrete columns, 940, 941  
     sand in concrete, 908  
     terms defined, 1851-1855  
     unit stresses for woods, 647  
     walls, thickness, 230, 231, 232  
     wind-bracing, 1171-1172  
 Building materials, 1634-1637  
     depreciation, 1634  
     estimating, 1635  
     quantity system, 1635-1637  
     wear and tear, 1634  
 Building papers, 1564-1568  
 Bureaus, dimensions, 1638, 1640  
 Butternut wood, hardness, 1558  
     unit stresses, 651  
 Buttresses, 1804  
     center of gravity, 300, 303  
     stability, 297-304  
  
 Cables, carrying capacity, 1473  
     measure, 25  
 Caissons, 210-214  
 Calcareous minerals, 130, 131  
 Calcite, 131  
     specific gravity and weight, 1502  
 Calendar, old and new, 30  
 California, registration law, 1778  
 Cambered truss (see Roof-truss,  
     cambered)  
 Calorimetry, 1250  
 Candle-power, 1439, 1440, 1462  
 Canopy (Glossary), 1805  
 Cantilever, beams, 555, 1043  
     moments, 325, 326, 558, 559  
     wooden, 629  
     buildings as cantilevers, 1173  
     compound footings, 178  
     flat slabs, concrete, 950  
     foundations, 165-169, 978  
     truss, 1043-1045, 1105-1107  
 Canvas roofs, 801  
 Cap, cast-iron columns, 459  
     mill-construction, 762  
     steel-pipe columns, 470, 471  
     stone (see Coving)  
     wooden columns, 454

- Cap-plates**, 795  
**Capital (Glossary)**, 1806  
**Car-barns**, steel, weight, 1209  
**Carbon**, in steel, 381  
**Carnegie shapes** (see **Beams**, etc.)  
**Carpenter's rule**, heat-loss, 1261  
**Carpenter's work**, data on lumber and work, 1558-1564  
     cost of labor, 1564  
**Carriages**, dimensions, 1642  
**Cars**, railroad, capacities, 1643  
     dimensions, 1642  
**Case-work**, dimensions, 1640  
**Cast iron**, 379  
     appearance, 379  
     castings, 379, 380  
         shrinkage, 1521  
     columns (see **Columns**)  
     crushing-loads, 449  
     defects, 379  
     fiber-stresses, 557  
     fire-resistance, 819-820  
     lintels, 620-628  
     manufacture, 379  
     modulus of elasticity, 664  
     plates, weight, 1524  
     shearing-stresses, 1505  
     specific gravity, 1505  
     specifications, 379  
     strength, 376, 379, 412  
     tension, 376  
     weight, 1505, 1521, 1524  
         estimating, 1505, 1521  
         weight of castings, 1521  
**Castings**, shrinkage, 1521  
     specifications, for cast iron, 379, 1196  
     steel, stresses, 1138, 1200  
     structural, painting, 1203  
     weights, 1521  
**Cathedrals**, seating capacity, 1654  
**Cedar**, beams, deflection, 664  
     fiber-stress, flexure, 557  
     safe loads, 640  
     columns, safe loads, 450, 452  
     crushing strength, 449, 454  
     hardness, 1558  
     specific gravity, 1502  
     unit stresses, 557, 647, 650  
     weight, 650, 1502  
**Ceiling (Glossary)**, 1807  
     corrugated metal, 1604  
     loads, 1197  
     matched, 1563  
     suspended, 871-872  
**Ceiling-joists**, wooden, framing to roof-trusses, 1004  
     maximum spans, 736, 737, 742  
**Cellar**, defined, 1852  
     walls, 129, 228, 229  
**Cellar-drainer**, 1421  
**Celsius thermometer**, 1250  
**Cement**, 235-240, 907, 908  
     artificial, 236  
     chemical composition, 237, 908  
     constancy of volume, 907  
     corrosion of steel, 960  
     cost, 238, 248, 910  
     fineness, 237, 907  
     grappier, 236  
     La Farge, 236, 238  
     manufacture, 236  
     mixing, 238  
     mortars, freezing, 239  
         proportions, 235, 247  
         specific gravity and weight, 1506  
         water required, 238  
     natural, 235, 284 (see **Hydraulic lime**)  
     neat, 237, 907  
     painting of, 1573  
     Portland (see **Portland cement**)  
     Puzzolan, 236, 237  
     quantities in concrete, 247, 248, 249  
     reinforced-concrete, 907  
     setting, 237, 907  
     slag, 236, 237, 238  
     specific gravity, 237, 907, 1502  
     specifications, 236, 907  
     stainless, 238  
     strength, 235, 237, 240, 283, 284, 907  
     tests, 237, 240, 907  
     water required, 238  
     waterproofing, 1711, 1717  
     weight, 235, 723, 1502  
**Cement blocks**, 269  
**Cement-gun**, column-protection, 826  
**Cement-plants**, steel, weight, 1209  
**Center**, striking for arch, 308  
**Center of gravity**, 127, 291-296  
     circle, sector and segment of, 293  
     compound figures, 294, 295  
     found by moments, 294  
     irregular figures, 292, 295  
     lines, 292  
     particles, heavy, 293, 294  
     quadrant of circle, 293  
     quadrilaterals, 292  
     regular figures, 292  
     surface, 292  
     table of, 293  
     triangles, 292, 293  
     voussoir of arch, 313, 318  
     wall and buttress, 300-301  
**Center of pressure**, arches, 311, 313  
     pier-joints, 300  
**Centigrade thermometer**, 1250  
**Ceramic tile**, 1605, 1607  
**Certificates**, architects, 1771  
**Chain**, 408-410  
**Chain-blocks**, 1723  
**Chain-cables**, 409  
**Chain-hoists**, 1723  
**Chain-hooks**, 1724

ahrs, dimensions, 1638, 1639, 1653  
 alk, 132  
 specific gravity and weight, 1502  
 Chamber of Commerce Building, Boston, piling-plan, 192  
 amfer (Glossary), 1807  
 annel, beams, safe loads, 582-584  
 bending moments, table, 576  
 buckling, 576  
 columns, 467, 476-480, 486-489  
   safe loads, 499, 500, 533-554  
 deflection, coefficients, 582-584  
 depth, 576  
 dimensions of standard, 353, 360  
 double sections, 359, 373, 374, 499-500  
 end-bearing, 576  
 moment of inertia, 337, 338  
 oblique loading, 573  
 properties of, 359, 360, 373, 499, 500  
 radius of gyration, 337, 338  
 sections, 359  
 set flatwise, 572  
 bearing, 576  
 small grooved, 360  
 steel, prices, 1204, 1212  
 web-resistance, table, 576  
 weight, 360, 576  
 Apel (Glossary), 1808  
 arcoal, combustion, 1272  
 arges, schedule, 1728, 1731  
 arles' law, gases, 1254  
 ack-nuts, shock-loads, 1202  
 ort, 130  
 astnut, beams, coefficients for, 628  
   deflection, 664  
   distributed loads, 641  
   fiber-stress, safe, flexure, 557  
 columns, safe loads, 450, 452  
 rushing strength, across the grain, 454  
 rushing-loads, with the grain, 449  
 ardness, 1558  
 specific gravity, 1502  
 ension, 376  
 nit stresses, 647, 648, 651  
 weight, 651, 1502, 1558  
 rry, hardness, 1558  
 weight, 1502  
 val-glasses, dimensions of, 1638, 1640  
 Chicago building code, bearing pressure, masonry, 441  
 column-formula, 450, 460, 481, 482  
   safe loads, 493-495  
   steel-pipe column, 469, 474, 497, 498  
 compression, steel members, 495  
 concrete flat slabs, 997  
 masonry-loads, 267, 287, 441  
 method of excavating, 209

Chicago building code, office-buildings  
   assumed loads, 151  
   piers, strength, 268  
   skeleton construction, 234  
   thickness of walls, 230, 231, 232  
 Chiffoniers, dimensions, 1638, 1640  
 Chimneys, 1281, 1364-1380  
   for boilers, 1281, 1282, 1283, 1367  
   for fire places, 1282  
   for kitchen ranges, 1282  
   formula, 1366, 1368  
   for tall buildings, 1283, 1368  
   gas-velocity, 1364  
   height, draft-relation, 1281, 1364  
   radial-brick, 1368-1373, 1377  
   reinforced-concrete, 1373-1375  
   steel, 1376  
     wind load, 1199, 1368  
   tall, list of, 1379  
 Chlorite, 131  
 Chords, of arcs, 38  
   of truss, definitions, 998  
   table, 81-89  
 Churches (Glossary), 1808  
   air-changes, 1260, 1353  
   cost, 1613  
   floor-loads, 719, 720, 1198  
   seating-space, 1653, 1654  
 Cincinnati building code, office-buildings, assumed loads, 151  
   loads on foundation-beds, 143  
 Cinder, cinders, angle of repose, 256  
   Concrete, 242, 250, 909, 930  
   corrosive action, 818, 960  
   reinforced work, 242  
   weight, 250  
   weight of loose, 256  
 Circles and parts, 37, 38, 41  
   areas, tables, 42-54  
   arcs, mensuration, 54-59  
   chords, tables, 81-89  
   circumferences, 42-54  
   geometrical problems, 66-74  
   moment of inertia, 337  
   radius of gyration, 337  
   section-modulus, 337  
 Circuit-breakers, 1461  
 Circular measure, 30  
 Circular mil, 1469, 1473  
 Circular ring, 61  
 Circumference, 37  
   circles, 42-54  
 Cisterns, capacity of, 1404-1405  
 Clapboards, 1563  
 Classical moldings, 1697  
 Classical orders, 1698-1704  
 Clay, angle of repose, 256  
   bricks, 275  
   foundation-beds, 135, 138, 139  
   moisture in, 138  
   safe loads, 141, 143

**Clay, specific gravity, 1503**  
     weight, loose, 256, 1503  
**Clerestory or Clearstory, (Glossary), 1809**  
**Clerk of the works, 1728, 1733**  
**Cleveland building code, loads on**  
     foundation-beds, 143  
     office-buildings, assumed loads, 151  
**Clevises, standard, 387, 398**  
**Climax, cellar-drainer, 1421**  
     floor system, 855  
**Clinched lath, 886**  
**Clinton stiffened lath, 887**  
**Clips, for steel beams, 616**  
**Clocks, tower, 1695**  
**Closet, water, 1411, 1428, 1641**  
**Closet-ranges, dimensions, 1641**  
**Coach-screws, 1535**  
**Coal, calorific value, 1271**  
     classification, 1271  
     composition, 1271  
     specific gravity and weight, 1503  
**Coal-bunkers, steel weight, 1209**  
     loads, 1198  
**Coal-fields, 1271**  
**Coal-gas, 1273, 1431**  
**Codes, building terms, 1851-1855**  
**Coefficient of elasticity (see Modulus)**  
**Coefficients, beams, 556, 628**  
     deflection, steel beams, 668  
     expansion, steel, 382  
     flow of water, 1383  
     friction, 253  
     sound absorption, 1488-1493  
**Coins, weights, 29**  
**Coke, combustion, 1272**  
     specific gravity and weight, 1503  
**Cold-air ducts, furnaces, 1319**  
**Cold-bending tests, iron and steel, 378,**  
     384, 385, 914  
**Cold-storage, temperature, 1693**  
**Collar-beam, 1810**  
**Colleges, architectural, 1779**  
**Color, light-sources, 1438**  
     mortar, 1547  
**Colorado, registration law, 1778**  
**Column, columns,**  
     bases (see Bases, columns)  
     base-plates, 440-445, 1524  
     bearing-brackets, 445-447  
     bearing-plates, 440-445, 1524  
     bending moments, 485  
     Bethlehem, 475, 479, 482-488  
         loads, tables, 483, 506-515  
     box, 342, 467, 479, 484  
     caps (see Column-caps)  
     cast-iron, 455, 466  
         advantages and disadvantages, 455  
         bearing-brackets, 445-447  
         breaking-loads, 462  
         connections, 445, 447, 457, 458,  
         945-946

**Column, cast-iron, cylindrical, 491, 495,**  
     459, 461, 1523  
     design, 456-459  
     failure by fire, 780  
     fireproofing for, 781, 822-826  
     H-shape, 456, 458  
     inspection, 456  
     reinforced-concrete, connections,  
         945  
     safe loads, 461-466  
     square, hollow, 456, 458, 461, 1524  
     strength, 459-466, 480-481  
     weight, 1522, 1523  
     channel (see Channel, columns)  
     classification, 448  
     concrete, not reinforced, 284  
     cross-sections, moments of inertia,  
         342, 343  
         radii of gyration, 344, 345  
     definitions, 448, 467, 477, 1810  
     eccentric loading, pipe columns, 477  
     eccentric loading, steel columns, 477,  
         488  
     eccentric loading, wooden columns,  
         453, 454  
     fireproofing for, 468, 780-781, 822-826,  
         959, 960  
     footings (see Column-footings)  
     general principles, 448  
     H columns, 456, 458, 459  
         economy, 458, 474, 483  
         safe loads, cast-iron, 466  
         safe loads, steel, 506-515  
     I-beam columns, 474, 488, 504, 505  
     Lally, 467, 474, 477  
         loads, 488, 516  
     lattice, 477-479  
     lengths, schedule for, 492  
     loads, live, proportion, 145-152, 488,  
         490, 1196, 1198  
         tables, 488-490, 493-554  
     mill-construction, 782-788, 969, 977,  
         978, 980, 981  
         cost, 810  
     pipe, 469-474, 488  
         loads, 488, 497, 498  
     plate-and-angle (see Columns, steel)  
     reinforced-concrete, 941-946, 948-950,  
         980  
         calculations for, 976, 977  
         fire-proofed, 958-959  
         metal-core, 944-945  
     safe loads, tables, 482, 490, 495-497,  
         554  
     slenderness-ratio, 448  
     steel, 467-554  
         bases for, 473-477  
         beam columns, safe loads, 504-505  
         box, 342, 343, 467, 479  
         channel (see Channel, columns)  
         choice of type, 467-468

- column, steel, connections, 468, 470, 471, 473-478, 945-946
  - connections in wind-bracing, 1174, 1175, 1179, 1189, 1190
  - cost, 467, 468, 1207
  - design, 482-485
  - eccentric loading, 485-488
  - examples, 482-488
  - failure, 469, 819
  - fireproofing for, 468, 780, 782, 819, 822-826
  - formulas, 480-482, 485, 493-496
    - diagram, 496
    - Gordon's formula, 481, 484, 485, 486, 487, 493-485, 496
    - Rankine's formula, 481, 484, 493, 496
    - straight-line, 481, 482, 493, 496, 1139
  - H-column, table of loads, 483, 504-515
  - lattice, 477-479
  - loads, 1196, 1198, 1201
  - loads, proportion, 148-152, 489-490, 1196, 1198
  - loads, tables, 488-490, 493-554
  - plate-and-angle, 467, 488, 517-532 (see Plate-and-angle column)
  - reinforced concrete, 946
  - section, 467, 468
  - splices, 1201
  - strength, general principles, 480-482
  - stresses, 618, 1138, 1200
  - struts, angle, safe loads, 488, 501-503
  - types, 467, 477
- steel-pipe, 469-474
  - loads, 488, 497, 498
- struts in trusses, 480, 499-503
- wind-bracing, 1174, 1183, 1189, 1190
- wooden, bases for, 782-788
  - bolsters, 454, 795
  - eccentric loading, 453, 454
  - factor of safety, 448
  - formulas, 450, 1139
  - metal caps, 454, 762, 782-788, 795-800
  - mill-construction, 782-788
  - safe loads, 448, 449, 450
    - tables, 451, 452
  - strength, general principles, 448-450
- wrought-iron, fireproofing, 780, 819
- column-bases (see Bases)
- column-caps, metal for wood, 454, 762, 782-788, 795-800
  - for steel-pipe columns, 470, 471, 472
- column-footings, bearing-plates for, 440-445
  - design, 178-188
- Column-footings, loads for design, 151, 152, 160
  - moments, 176-178
  - plan, 1195
  - proportioning, 152-164
  - reinforced concrete, 186, 974, 978-982
- Column-sheets, 490
- Combined stresses, 128, 480, 572, 1114
- Commercial weights and measures, 28
- Commodore, dimensions, 1638, 1640
- Competitions, architectural, 1733-1747
  - ethics, 1729
- Composite Order, 1702
- Composite piles, timber and concrete, 198
- Composition, forces, 288
- Compound sections, moment of inertia, 339
  - radius of gyration, 344
- Compression, 127
  - members, steel, specification, 1201-1203
  - sig-, 1065, 1068
- Concrete (see, also, Reinforced concrete), 240
  - adhesion to steel, 912, 919, 920, 938, 940
  - aggregates, 241, 287, 908, 909, 945
    - effect of heat, 817
    - strength, 287
  - beam-protection, 860
  - beams, not reinforced, 628, 637
    - coefficients for, 628
    - fiber-stresses, 557
  - bearing surface, 285
  - blocks, 816, 956
    - fire test, 956, 957
    - machinery for, 816
    - walls, 233
  - bonding old and new, 965
  - capping of piles, 191
  - cinder, 242, 250, 909, 930
    - corrosion of steel, 818, 960, 961
    - fire-resistance, 818
    - weight, 250
  - column-protection, 780-782, 822-826
  - columns, 284
  - compression-tests, 283
  - compressive strength, 283, 287, 441
    - tests, 284-286
    - working stresses, 265-267, 287, 441, 911
  - consistency, 243, 286
  - corrosion of steel, 818, 960, 961
  - cost, 249-250, 910
  - dehydration of, 245
  - design of massive, 246
  - electrical action, 1713
  - finish of surfaces, 246, 965

**Concrete, fireproofing, column-protection**, 780, 782, 822-826  
 concrete blocks, 816, 956  
 roofs, 866, 871  
 tests, 245, 955-960  
 warehouse-construction, 780-782  
 flour-mixtures, 1712  
 forms, 245, 962-965  
 freezing-temperature, 244  
 gravel, 241, 286, 908  
 heat, conductivity, 245  
   effect of, 245, 817, 957-958  
 I-beam protection, 780, 847  
   ceilings, 849  
   roofs, 871  
 I beams, 854  
 laitance, 244  
 limestone, weight, 250  
 mass, strength, 267  
   design, 246  
 materials, proportions, 243, 247, 907, 909-910, 945  
 mechanical analysis, 910  
 mixers, 963  
 mixing, 242, 243, 963  
 mixtures, 909-910, 945, 963-964, 1712  
 modulus of elasticity, 934, 935  
   blocks, heated, 956  
   design, assumption, 924  
   ratio to steel, 912  
 modulus of rupture, 284  
 molds for, 962-966  
 natural cement, 235, 267, 284  
 painting, 1573  
 partitions, 876, 881  
 penetrative washes, 1712  
 permeability, causes, 1710  
 pile-capping, 191  
 piles (see **Piles**)  
 pipe-column filling, 469  
 placing, 244  
 plant-cost, 250  
 Portland-cement, 240-251  
 pouring, 964  
 preparing, 242  
 properties, 240  
 proportions, 240, 243, 247-249, 907, 910, 945, 1712  
 protective coatings, 1712  
 ramming, 964  
 reinforced (see **Reinforced concrete**)  
 retempering, 244  
 rubble, 244  
 saline waters, 1713  
 sand in, 241, 247, 908  
   grading, 241  
 shearing strength, 284  
 shrinkage, 245  
 slag, fire-resistance, 817  
 specific gravity, 1503

**Concrete, stone** (see **Concrete, gate**)  
 strength (see **Concrete, compressive**)  
   tensile, 284  
 surface-finish, 246, 965, 1555  
 temperature-changes, 245  
 tensile strength, 284  
 test for hardening, 245  
 tests, 283-287, 817  
 tile, strength of, 817  
 tiles, 816  
 tools, 963-964  
   cost, 250  
 transporting, 964  
 trap-rock, 250, 817  
 tremie, use of, 244  
 under-water, 244  
 uses, 240, 906  
 walls, 228-229, 946-947, 965, 966  
   cost, 250  
 water used in, 242, 909  
 waterproofing, 246, 1709-1717  
 weight, 250, 1503  
**Conductors, electricity**, 1458  
 lightning, 1704-1707  
 water, roofs, 1658  
**Conduits, electric-wiring**, 1479  
**Cone**, 38  
   center of gravity, 295  
   frustum, 38, 61, 63  
   surface, 61  
   volume, 63  
**Conic sections**, 38  
**Coniferous woods, ultimate unit stress**, 649  
**Connections** (see under **Columns**, **Beams**, etc.)  
**Consoles (Glossary)**, 1811  
   terra-cotta, 278  
**Construction, insurance during**, 1754  
**Continuous beams and girders**, 31  
   671-680, 979, 980  
**Contract drawings**, 1753  
**Contracts, arbitration**, 1763  
   architect and owner, 1740, 1746  
   contractor and owner, 1751  
   forms, 1750, 1752  
   owner and competitor, 1740, 1746  
   subcontractor and contractor, 1746  
   uniform, 1749  
**Contractor vs. Architect, relation**, 1751  
**Contractor's insurance**, 1756  
**Conversion tables, metric**, 33-35  
**Coping (Glossary)**, 1811  
   stone, 1539  
**Copper, roofs**, 1604  
   sheets, 1049, 1510-1511  
   specific gravity and weight, 1510  
   1510  
   wire, 401, 1469, 1474, 1513  
   current capacity, 1470

rbel (Glossary), 1811  
 rds, sash (see Sash-cords)  
 re-borings, foundation-bed testing,  
     145  
 res, steel, in concrete columns, 441  
 reduction for, in castings, 1521  
 nthian Order, 1702, 1703  
 mer-basins, dimensions, 1641  
 mer-slabs, dimensions, 1641  
 mices (Glossary), 1811  
 mills, 764, 769  
 r-bars, 916, 923  
 r-mesh, 853  
 rosion, cinder concrete on steel, 818,  
     960, 961  
 rugated bars, 916  
 rugated iron and steel roofing, 1046,  
     1049, 1599-1604  
 rugated sheets, 1599-1604  
 nti-condens. tion lining, 1603  
 eilings, 1604  
 overing capacity, 1603  
 loors and roofs, 851  
 alvanizing, 1600, 1604  
 auges, 402, 1510, 1600  
 aying, 1601  
 ides, building, 1603  
 eight, 1600, 1603  
 ecants, tables of natural, 117  
 nes, tables of natural, 95  
 t, costs, brickwork, 1544-1547  
     mill-buildings, 808-810  
 ildings, cubic foot, 1611-1634  
 ilding-papers, 1568  
 arpenters' work, 1564  
 ement, 238, 248, 910  
 olumns, mill-construction, 810  
 oncrete, 249-250, 910, 1613, 1618  
 ubic foot, buildings, 1611-1634  
 ut stonework, 1539  
 rafting, structural steel, 1206  
 riving wooden piles, 195  
 wellings, 1613  
 levators, 1659, 1670  
 named bricks, 1544  
 recting structural steel, 1206  
 stimating, buildings, 1611-1635  
 xcavating, 1536  
 xposition-buildings, 1627  
 ederal buildings, 1613, 1626-1633  
 elts, 1565, 1568  
 re-proof partitions, 889  
 agstones, 1539  
 oors in mills, 810  
 lass, 1574-1577  
     polished plate, 1576  
     sheet, 1575  
     skylight, 1580  
     window, 1577  
 icandescent lighting, 1482  
 labor, 1564

Cost, lathing and plastering, 1557  
     library-stacks, 1697  
     mill-construction, reinforced-concrete,  
         777, 1613, 1618  
         slow-burning, 758, 777, 802-810  
     mineral wool, 1610  
     office-buildings, 1613  
     partitions, sound-deadening, 889  
     piles, driving, 195  
     pitch-slag, roofs, 1598  
     plumbing-fixtures, 810  
     public building, 1613, 1628-1634  
     refrigeration, 1695  
     reinforced concrete, 250, 910, 1613,  
         1618  
     roofs, mill-buildings, 777, 810  
     roofing, asphalt-gravel, 1599  
         gravel, 1598  
         slag, 1598  
         slate, 1046, 1585  
         tile, 1046, 1587, 1607  
         tin, 1046, 1589, 1593, 1594  
     saw-tooth roofs, 777  
     school-buildings, 1613, 1614, 1616  
     slates, 1046, 1585  
     slow-burning construction, 758, 802-  
         810, 1619  
     square foot, buildings, 1627-1634  
     steel, structural, 1204-1212  
     stonework, 1538  
     tiles, 1046, 1587, 1607  
     tin, gutter-strips, 1594  
         rolls, 1594  
         roofing, 1046, 1589, 1593, 1594  
     trusses, steel, 1206  
     warehouses, 777, 802-810  
 Cotangents, tables of natural, 115  
 Cotton, weight, 722  
 Cotton-mill, design and cost, 803  
 Cotton rope, 406  
 Counterbraces, wooden trusses, 1000-  
     1006, 1034, 1104  
 Counterforts, retaining walls, 263  
 Counter-ties, 386  
 Counterthrust, 305  
 Cover-plates, box girders, 696  
     plate girders, 687  
     riveting, 421, 422  
 Crane, chain, 410  
     clearance-diagram, 1195  
     load, 1197, 1201  
     truss, 1069  
 Creosote, 1570  
     oil, 1503  
 Crockery, weight, 723  
 Cross (Glossary), 1812  
 Cross-sections, 332-374  
 Crown, of arch, 305  
 Crushing strength (see under each ma-  
     terial)  
 Cubage, 1612

- Cube, cubes, 38
- Cube root, 4
  - tables, 8-24
- Cubic measure, 27
  - metric, 31
- Cummings system, reinforcing, 923
- Cupola process, iron, 1379
- Curbing-stones, 1539
- Cycloid, definition, 80
  - problems on, 80
- Cylinders, 38, 63
  - contents of, various diameters 1403
- Cypress, beams, distributed loads, 641
  - deflection, 664
  - flexure-stress, 557, 650
  - columns, safe loads, 450, 452
  - crushing-loads, across the grain, 454
    - with the grain, 449
  - specific gravity, 1503
  - ultimate stresses, 650
  - weight, 650, 1503
  - working stresses, 647
- Dahlstrom metal doors, 896
- Dams, concrete, cost of, 250
- Dead load, definition, 126
- Deadening partitions, 890
- Deadening-quilts, 1565
- Decagon, 37
- Decimals of inch, table, 26
- Deck-beams, steel, loads, 565
- Deflection, beams, 663-670
  - allowed, 566, 628, 664, 736
  - steel, 566, 612, 668-670, 677
  - wooden, 636, 653, 654-657
  - continuous girder, 674-676
  - diagram, 670
- Deformation, definition, 125
- Degree, degrees, of heat, 1250
- Density, 1247
- Denver building code, masonry-loads, 267, 287
  - thickness of walls, 231-232
- Department-stores, steel, weight, 1208
- Depreciation of buildings, 1634
- Derrick, rope for, 408
- Desks, sizes, 1640, 1645
- Details, structural, specifications, 1202
- Diagonals, 37
- Diameters, 37, 1814
- Diamond bar, reinforcement, 917
- Diamond bits, foundation-bed, testing, 145
- Diamond-mesh lath, 884
- Dimensions, useful, 1637-1658
- Dodecagon, 37
- Dogwood, hardness, 1558
- Dolomite, 131, 132
- Domes, 1213-1231
  - (Glossary), 1814
  - angle, critical, 1213
  - reinforced concrete, 1217, 1225-1231
- Domes, ribbed, 1222
  - secondary stresses, 1220
  - smooth-shell, 1213
  - steel, 1222
    - weight, 1224
- Door, doors, fire-resisting, 801
  - iron, standard, definition, 1854
  - metal and metal-covered, 894-897
    - 901-902
  - school-buildings, 1648
- Door-frames, cement, 898
  - metal, 897
  - terra-cotta, 898-899
- Door-sills, stone, 1539
- Doric Order, 1699-1700
- Double-plenum-chamber system, 1227
  - ing, 1327
- Douglas fir, beams, distributed loads, 642
  - deflection in, 664
  - flexure, 557, 628, 647, 650
  - columns, safe loads, 451
  - crushing-loads, with the grain, 449
  - crushing strength, across the grain, 454
  - specific gravity, 1503
  - unit stresses, 376, 412, 647, 650
  - weight, 650, 1503
- Dovetailing (Glossary), 1815
- Dowel (Glossary), 1815
- Documents, American Institute of Architects, list, 1767
  - standard, American Institute of Architects, 1748
- Draft, definition, 1364
  - natural, air-velocity, 1302
- Drafting, structural, cost, 1206
- Drain, drains, 1407-1414
  - area, 1408
  - cellar, 1421
  - house, 1407-1414, 1419-1421
- Drain-pipes (see Pipes)
- Drainage of buildings, 1407-1414, 1421
- Drainer, cellar, 1421
- Drawings, architect's, 1720, 1751
  - competitive, 1737, 1744, 1745, 1746
  - contract, 1753
  - property of architect, 1733
  - shop, 1754
  - working, steelwork, 1195
- Drift-pins, 414, 682
- Drill-rooms, floor-loads, 719
- Drop-hammer, pile-driving, 190
- Drum-trap, 1413
- Dry measure, 27
- Dry-rot, 759
- Du Long's formula, heat of coal, 127
- Duchemin's formula, wind, 1199
- Ducts, air, design, 1333-1341
  - cold-air, furnaces, 1319



ducts, fresh-air, sizes, 1322  
 hot-air, area, 1301  
 metal gauge, 1336  
 system, design, 1346  
 wellings (see also Residences)  
 cellar walls, 229  
 cost of constructing, 1613, 1614  
 floor-joists, 737, 742  
 floor-loads, 149, 719, 1198  
 heating, 1256, 1353, 1361-1363  
 wall-thickness, 230, 232  
 yestuffs, weight of, 723  
 earthy material, 132  
 weight, 1537  
 eastern fir, safe load, 639  
 safe stress, 647  
 eccentric loads (see Loads, eccentric)  
 echoes, acoustics, 1487  
 education, registration laws, 1769  
 educational institutions, 1779  
 efflorescence, brickwork, 1547  
 Egyptian long measures, 34  
 Egyptian style, architecture, 1704  
 elastic limit, definition, 126, 381, 913  
 elasticity, coefficient or modulus of,  
     126, 626, 662  
 reinforced concrete, 912, 934  
 steel, 381, 912, 934  
 timber, 647, 731-734  
 bows, heating, pressure-loss, 1338  
 electric work for buildings, 1457-1485  
 cabinet-wiring, 1477, 1481  
 center of distribution, 1471  
 circuit-breakers, 1461  
 code-requirements, 1480-1482  
 conductors, 1458  
 conduit system, 1479  
 cost, of lighting-equipment, 1482  
     of wiring, 1482  
 design of lighting systems, 1446-1448  
 drop of potential, 1470  
 feed-wires, 1478  
 fuse, enclosed, 1461  
 fuse-block, 1481  
 insulators, 1458  
 interior wiring, 1482  
 knife-switch, 1477, 1479  
 lamp-arrangement, 1465, 1466  
 lamps, number of, 1446, 1449, 1475  
 national electrical code, 1480  
 power-computations, 1459  
 specifications, 1482  
 switches, 1478, 1479  
 systems of lighting, 1464-1469  
 wire-calculations, 1469-1472  
 wire, dimensions, weights, 1474, 1475,  
     1477  
     carrying capacity, 1470, 1473, 1475  
 wiring-diagram, 1476  
 symbols, 1476-1478, 1484

Electricity, 1457-1464  
 Electrolysis, reinforced-concrete foot-  
     ings, 186  
 Elevator, 1659-1677  
     car-platform, 1661, 1666, 1675, 1676  
     comparison of types, 1660, 1664,  
         1670  
     cost, 1659, 1670  
     counterweights, protection of, 1662  
     development of systems, 1667-1669  
     economic considerations, 1671  
     efficiency, 1659  
     electric, 1659, 1666, 1669, 1676, 1677  
         versus hydraulic, 1660, 1664, 1670  
         passenger systems, 1667-1670  
     express, 1661, 1673, 1675  
     geared, 1659, 1669  
     gearless, 1659, 1665  
     hatchway, size, 1660, 1667, 1675, 1676  
     hoistway, 1660, 1662  
     hydraulic plunger, 1670  
         versus electric, 1660, 1664, 1670  
     installation-data, 1663, 1674, 1675  
     laws governing, 1663  
     loads, 1662, 1674  
     local, 1661, 1673, 1675  
     machinery-room, 1660  
     motors, current-consumption, 1677  
         feeders, 1677  
         sizes, 1676, 1677  
     number required, 1661, 1673  
     operating-costs, 1670  
     power-diagrams, 1671  
     push-button control, 1666  
     safety-appliance, 1664, 1669, 1672  
     service, formulas for, 1673  
     signal-systems, 1672  
     sizes, 1661, 1667, 1675  
     specifications, 1663  
     speeds, 1662, 1674  
     standard designs, 1663  
     time-schedule, 1671  
     towers for, in mills, 764, 765, 768  
     traction, 1665, 1669, 1670  
     traffic-capacity, 1672  
     types, 1660, 1668  
     use of, 1667  
 Elevator-tower, mill-construction, 764,  
     765  
     storehouse, 768  
 Ellipse, 38  
     center of gravity, 293  
     problems on, 74-79  
 Ellipsoids, 60, 65  
 Elm, hardness, 1558  
     specific gravity, 1503  
     ultimate unit stresses, 651  
     weight, 651, 1503  
     working stress, flexure, 557  
 Elongation, eye-bars, 386  
     steel, 381, 384, 913

- Enamel, painting, 1570**  
**Enameled tile, 1605-1607**  
**Energy, work, 1248**  
     and power, relation, 1250  
**Engineering, architectural, terms used, 124, 128**  
**Engineering News formula for pile foundations, 193**  
**Engines, fire, dimensions, 1642**  
     foundations for, 1716  
     hot-air, 1393  
**Enneagon, 37**  
**Entasis (Glossary), 1817**  
**Entropy, of steam, 1254**  
**Equilibrium, 124**  
     of parallel forces, 290  
     polygon, forces, 289, 299, 313-315, 319  
**Estimates, architects', 1728**  
     guaranteed, 1731  
**Estimating (see Costs)**  
     quantity system of, 1635-1637  
**Ethics, professional, 1729, 1731**  
**Eustyle (Glossary), 1817**  
**Evaporation, 1251-1254**  
     equivalent, boiler, 1274  
**Evolution, mathematics, 3-5**  
**Examination, architects, New York state, 1772**  
**Excavation, 200-222**  
     below water, 203  
     bracing, 201  
     Chicago method, 209  
     data on, 1536  
     dredged wells, 210  
     earth-pressure, 201, 205  
     freezing process, 214  
     needling, 218-222  
     open-caisson method, 210  
     pneumatic-caisson method, 211-214  
     poling-board method, 209  
     protecting adjoining structures, 214-222  
     quicksand, 137, 211  
     rock, 1537  
     sheet piling, 200-209  
     shoring, 214-222  
     underpinning, 214, 218-222  
     volume of, computing, 65  
     well-curb method, 210  
     well-digger's method, 211  
**Expanded metal, 846-847, 883-884, 919**  
**Expansion-bolts, 1534**  
**Expansion-tank, 1360**  
     hot-water heating, 1307, 1308  
**Exposition-buildings, cost of, 1627**  
**Expenses, architects, 1731**  
**Expert, in competitions, 1735**  
     services, payment, 1728  
**Extrados, arch, 305**  
**Eye-bars, 386, 395**
- Face, arch, 305**  
**Face-wall, definition, 155**  
**Factor of safety, 126, 375, 556**  
**Factories, air-changes, 1260, 1353**  
     brick, 808-810  
     heating, direct radiation, 1296  
     hot-blast, 1324, 1336, 1342-1347  
     temperature, 1256  
     non-fireproof, height, 813  
     reinforced-concrete, 968-969  
     steel, 1210, 1627  
     wooden construction, 758-810, 1631  
**Fahrenheit thermometer, 1250**  
**Fan, maximum speed, 1357**  
     ventilation, 1341-1347, 1357  
**Fan system, heating, 1324-1341**  
**Fan trusses, 1025-1029, 1145**  
     stresses, 1058-1060, 1078, 1145  
**Federal buildings, cost, 1613, 1620, 1621**  
**Feed-wires, electric, 1478**  
**Fees, architects', 1731**  
**Feet converted into meters, 34, 55**  
**Feldspar, 131**  
     specific gravity and weight, 1504  
**Fellowships, architectural, 1779-1780**  
**Felts, asbestos, 1567**  
     building, 1564-1568  
     cost, 1565, 1568  
**Ferrocilave, floors, 850-851**  
     roofs, 851  
     stair-construction, 900-901  
**Fiber-stresses (see, also, under material), 126, 556, 557**  
**Field-rivets (see Rivets)**  
**Fillers, web-stiffeners, 686**  
**Filters, water, 1421**  
**Finial (Glossary), 1818**  
**Fink truss, 1025-1030, 1161-1164**  
     cambered, stresses, 1079-1081  
     stresses, 1058-1061  
     steel members, 1148, 1161-1164  
**Fir, Douglas (see Douglas fir)**  
     Eastern, beams, safe loads, 639  
     unit stresses, 647  
**Fire-clay, flue-linings, 1281**  
**Fire-doors, metal-covered, 894-895**  
     901-902  
     stairways, 779  
     tin-covered, 901, 1855  
**Fire-engines, dimensions, 1642**  
**Fire-escapes, warehouses, 764, 765**  
     778, 779  
**Fire-extinguishers, 903-905**  
**Fire-protection, alarm system, electric, 903-905**  
     doors (see Fire-doors)  
     fire-extinguishers, 903-905  
     fire-retardants, 759  
     hose, 768  
     hose-reels, 905  
     outside hazard, 901-903

e-protection, partitions, 801  
 pumps for fire-streams, 759, 1401  
 roof nozzles, 801  
 scuppers, 767  
 shutters, 759, 778, 801, 901, 902  
 signaling systems, 905  
 sprinklers, 801, 903-905  
   mill-buildings, 759, 768  
   timber-spacing, 777  
   tanks, 779  
 stairways, 764, 765, 778, 779  
 standpipes, 768, 801, 905  
 steam-pumps, 1401  
 steelwork, 468, 760, 780-782, 819, 822-826  
 tanks, 779, 1402  
 water-supplies, 802  
 wire-glass, 759, 778, 821  
 e-pumps, steam, 759, 1401  
 e-resistance of materials (see Fireproofing)  
 e-stops, mill-construction, 759  
 e-streams, 1397  
 pumps for, 1401  
 e-tests (see Tests)  
 e-towers, 764, 765, 778, 779  
 e-walls, storehouses, 765  
 eplaces, flues, 1282  
 eproofing, asbestic plaster, 818  
 asbestos, 819  
 beams and girders, 780-782, 827-842, 844, 849, 854-860  
 brickwork, 814  
 buildings, 811-905  
   cost of, 802, 812, 1619-1625  
   percentages of cost, 1619  
 ceilings, 871-872  
 columns, cast-iron, 781, 822-826  
   steel, 468, 780-782, 822-826  
   wrought-iron, 780, 819  
 concrete, column-protection, 824-826  
   concrete blocks, 816-818, 956  
   floors, 860-866  
   roofs, 866  
   tests, 245, 955-960  
   warehouse-construction, 780-782  
 flooring, 892-893  
 doors, 826-866  
 interior finish and fittings, 893-901  
 materials, 811-905  
   fire-resistance, 245, 814-822, 955-960  
 mortars, 818  
 municipal definitions, 811, 1853  
 paint, 821-822, 894  
 partitions, 873-892  
 plaster, 818, 878-882, 889-891  
 plaster of Paris, 818  
 prism glass, 821  
 reinforced-concrete, 781, 811, 955-960

Fireproofing, roofs, 801, 866-872, 1597  
   stairs, 899-900, 947, 983  
   steel, 468, 760, 780, 822-826  
   stone, 814  
   terra-cotta, 234, 814-815, 828, 874  
   trusses, 860  
   wall-coverings, 881-892  
   wire-glass, 821  
   wood, fire-proof, 820, 894-895  
 Fires, cast-iron in, 819  
   steel and wrought-iron in, 819  
   concrete affected, 245, 955-960  
 Fish-plate, roof-trusses, 1155  
 Flagpoles, dimensions, 1644  
 Flagstones, 282, 1539  
 Flashings (Glossary), 1818  
 Flats, steel, safe loads, 389  
 Flexure, 126, 324-331, 332-334, 555  
   reinforced-concrete beams, 924-941  
   steel beams, 564-573  
   wooden beams, 627-637, 647-656  
 Flint, 130  
   specific gravity and weight, 1504  
   tile, 1605  
 Fitch-plates, beams and girders, 655, 656  
 Floor, floors, asphalt, 1608  
   Akme system, 949  
   beam-and-slab, 968  
   Berger's metal lumber and concrete, 852, 858  
   brick arches, 827  
   cantilever flat slab, 950  
   Climax system, 855  
   Corr-plate system, 950  
   Excelsior, tile, 838  
   expanded-metal and concrete, 847  
   Ferroinclave, 850-851  
   fire-proof, brick and tile, 826-842  
     concrete, 842-866  
   fire tests, 827  
   flat reinforced, 845-846, 949-952  
   Floredome system, 953  
   Floretyle system, 952-953  
   framing, steel (see Framing)  
   girderless, 968, 993-997  
   girders, steel, specifications, 1201, 1202  
   Guastavino, 841-842, 843, 1243  
   heat-transmission, 1259  
   heating pipes through, 1360  
   Herculean, 838-839  
   I-beam system, concrete, 854-855  
   Johnson construction, 837-841  
   joists (see Floor-joists)  
   keys, tile, 835  
   loads (see Loads)  
   lock-woven fabric, 849-850  
   M system, 948-949  
   metal lumber, 858

- Floor, mill,** 730, 760, 766, 769, 782-794  
 (see **Mill-construction**)  
**New York, tile,** 840  
**reinforced-concrete,** 842-856, 924-940, 948-955, 968, 971  
 cost, 250  
 design, 985-997  
 four-way reinforcement, 949  
 girderless, 968, 993-997  
 mushroom system, 950, 993-997  
 S. M. I. system, 950  
 top coat, 239  
 triangular-mesh fabric, 850  
**reinforced tile,** 838-842  
**sectional systems,** 853-854  
**segmental, concrete,** 844-845  
 tile, 831, 832  
 separately-molded, 953  
 side-construction, 830-833  
**Sieglwart system,** 855  
 skewbacks, tile, 834, 835  
 square-panel system, 968  
 steel framing, computations, 861-866  
**System M,** 948  
 terra-cotta, 828-840, 1604-1607  
 tie-rods, 307, 832  
 tile, 828-840, 953, 1604-1607  
 tile-and-concrete, 951-952  
 end-construction, 829, 833, 837  
**Vaughan system,** 856  
**Waite's concrete I-beam system,** 854  
**warehouses,** 764, 777  
**Watson system,** 856  
**weight (see Loads)**  
 of wooden construction, 718  
**welded-metal fabric,** 848  
**wire fabrics,** 848-850  
**wooden, cost,** 810  
 estimating, 1563  
 framing, 721-731, 746-757  
 mill-construction, 730, 760, 766  
 old, strength, 749  
 plank, 730-735  
 strength and stiffness, 717-757  
 warehouses, 764, 777, 893  
**workshop,** 769
- Floor-joists, wooden, assembly-halls,**  
 maximum span, 739, 744  
 bridging, 748, 749, 1804  
 churches, 738, 743  
 continuous, 717  
 corridors, 739, 744  
 dwellings, span, 737, 742  
 framing-details, 749-757, 782-795  
 hangers, 750-757, 782-794  
 nominal and actual sizes, 637  
 office-buildings, 738, 743  
 plans, 717, 727, 747  
 school-buildings, 717, 737, 742  
 size, 637  
 spans, maximum, 736-746
- Floor-joists, wooden, stiffness, tables,**  
 635, 638-646  
 stirrups, 750, 751, 754-757, 787-794  
 stores, span, 739, 744  
 strength, tables, 635, 638-646  
 tenements, 737, 742  
 theaters, maximum span, 738, 743  
 weight, wooden, 718
- Floor-slabs (see Reinforced concrete slabs)**
- Floor-tiling (see Flooring)**
- Flooring, banks,** 893  
 cement, 831, 893  
 composition, 893  
 concrete finish, 965  
 fire-proof, 893  
 hotels, 893  
 matched, 1563  
 mortar over concrete, 965  
**Mosaic,** 1607  
 slate, 1606  
 terrazzo, 1607  
 tiling, 1604-1607  
 toilet-rooms, 893  
 warehouses, 764, 777, 892, 893  
 wooden, cost, 810  
 estimating, 1563  
 mill-construction, 760, 766  
 old, strength, 749  
 plank, 730-735  
 strength and stiffness, 717-757
- Floredome,** 953  
**Floretyle,** 952-953  
**Floriluxe,** 1579  
**Flues, 1281-1283, 1365**  
 gas-velocity, 1364  
 vent, 1356, 1357
- Fluid measure,** 28
- Flushometer, Kenney,** 1420
- Font (Glossary),** 1819
- Foot-baths, dimensions,** 1641
- Foot-candle,** 1439, 1440
- Footings, 129, 223 (see also, Foundations)**  
 areas, minimum, 152  
 bending-stresses, 172-178  
 brick, 226, 227  
 cantilever, 165-169, 978  
 columns, design, 178-188  
 loads for design, 151, 152, 160  
 proportioning, 155-164  
 moments, 176-178  
 reinforced-concrete, 974, 978-981  
 compound, 178  
 concentric loads, 160  
 concrete, 225, 226  
 cost, 250  
 design, 179  
 reinforced, 186, 946, 978  
 conditions affecting, 188  
 continuous beams, 979

ottings, courses, 129, 169-172, 223  
 cracks in, 224  
 crushing, failure by, 171  
 defined, 1852  
 depth of, minimum, 188  
 design of, 178, 978  
 eccentric loads, 162  
 factor of safety, 178  
 failure of, 170-172  
 flexural strength, 178-179  
 grillage, steel, 166-169, 181-185  
 homogeneous slabs, 178  
 inverted arches, 227-228  
 light buildings, 223  
 loads, 148-163, 170, 223, 265-267, 978  
 offsets, 163-165, 179, 223-227  
 piers (see Footings, columns, and Piers, footings)  
 projection and depth, ratio, 180-181  
 reinforced-concrete, 186, 946, 978  
     electrolysis 186  
 retaining-walls, 261, 262  
 settlement, 152-160  
 shear, failure by, 170-171  
 size and form, 169  
 slabs, homogeneous, 178  
 spreading, failure by, 171  
 steel beams in, 181-185  
 stone, 223-224  
 stresses, 169-178  
 timber, 186-188  
 unit and separate-layer compared, 180  
 oot-pound, 290  
 oot-pound-second system, 1247, 1250  
 to B.t.u., 1251  
 orce, forces, 124  
     axial, 375  
     center of gravity, 127, 291-296  
     composition, 288, 1065  
     compression, 127, 1065, 1068-1072  
     equilibrium, 124, 289, 299, 313-315, 319  
     external, 125, 325, 1066  
     graphic statics, 1065  
     internal, 125, 325, 1066  
     lever, principle of, 165, 290-294  
     line of action, 289  
     magnitude, 288  
     moments of, 127, 289, 322  
     parallel, 290-291  
     parallelogram of, 289  
     point of application, 289  
     polygon of, 289, 1070  
     reactions, beams, 322-324  
         trusses, 1066  
     resolution, 288, 1065  
     resultant, 288  
     sense of, 289  
     signs for, 1065, 1068, 1072  
     shear, 128

Force, stress (see Stress)  
     tension, 127, 1065, 1068, 1072  
     torsion, 228  
     triangle of, 289  
 Forge-shop, steel, weight, 1209  
 Forked loop, tension-member, 387  
 Forms for concrete, 245, 962-965  
 Fossiliferous limestones, 132  
 Foundation (see, also, Footings and Foundation-beds), 129-222  
     adjoining excavations, 130, 147  
     adjoining structures, protecting, 214  
     brick, 226-227  
     caisson, 210-214  
     cantilevers in, 165-169, 978  
     Cathedral of St. John the Divine, 251  
     columns, 161-163, 176-178, 184, 974, 978-982  
     concrete, 225, 226, 249-251  
         early examples, 251  
         pile, 188, 196-200  
         reinforced, 186, 196, 978  
     conditions affecting, 188  
     definition, 129, 1852  
     depth, 188  
     engine, water-proof cement, 1716  
     excavating for, 200-214 (see, also, Excavation)  
     footings (see Footings)  
     general requirements, 129, 130  
     girdering-method, 166-169  
     grillage, steel, 166-169, 181-185, 678  
     light buildings, 223-229  
     Manhattan Life Insurance Building, 251  
     mining districts, 147  
     needling, 218-222  
     piers, 129, 188 200  
     pile, reinforced-concrete, 196-200  
         sheet, 201-209  
         wooden, 188-196  
     reinforced-concrete, 186, 946-947, 978  
     screw-jacks, 215, 216, 221  
     settlement, equal, 152-160  
     sewers, 147  
     shafts, 147  
     shoring, 214-222  
     spread, 166-169, 181-188, 978, 980  
     subways, 148  
     temporary buildings, 187  
     timber, spread, 186-188  
     trenches, 147  
     tunnels, 148  
     underpinning, 214, 218-222  
     walls, 129, 200, 228, 229, 979  
     Washington Monument, 251  
     waterproofing, 1709-1717  
     wedges, 215  
     wells, 147  
 Foundation-beds (see, also, Foundations), 129-148, 223

- Foundation-beds, boulders, 134, 136, 141**  
 clay, 135, 138, 139, 141, 143  
 dirt, 135  
 drill tests, 145  
 earthy material, 132-133, 135, 138-140  
 filled ground, 140  
 geological considerations, 130  
 glacial deposits, 133  
 hard-pan, 135, 141, 143  
 gravel, 134, 136, 141, 143  
 loads on, 140-143, 148-160, 223  
 tests, 142-146  
 loam, 135, 143  
 materials composing, 130-140  
 mould, 135  
 mud, 135, 139  
 peat, 135, 139  
 pipe-borings, 144, 145  
 quicksand, 136, 137, 141, 143  
 river-deposits, 133  
 rock, 130-132, 134, 135, 141  
 sand, 134, 136-138, 141, 143  
 shale, 135  
 silt, 135, 139  
 soil, 132, 135, 143  
 testing, 141-146  
 topographical conditions, 146  
 trenches for footings, 226  
 varying pressure on, 163-164
- Foundry-castings, 379**
- Foundry, heating-temperature, 1256**  
 lighting, 1451  
 steel, weight, 1209
- Frames, door, 898, 899**  
 window (see Window-frames)
- Framing, floors, wooden, 721-731, 746-757**  
 mill-construction, 760-764, 766, 769, 782-794  
 saw-tooth roof, 772-777  
 steel beams, 612-618  
 cast-iron columns, 445, 447, 457, 458, 946  
 fire-proof floors, 861-866  
 Lally columns, 474, 477  
 steel columns, 468, 470, 471, 473-478, 945, 946  
 wooden floors, 616, 752, 753, 755, 786-792  
 truss-joints, 1149-1170  
 arched, 1024, 1039  
 heel, 434-439, 1003, 1150-1170  
 iron ties, 1019  
 lattice truss, 1008, 1009  
 pin-connected, 423-429  
 wind-bracing, 1174-1176, 1183-1193
- Freight rates, structural steel, 1205**
- Freight-cars, capacity, 1643**
- French truss, 1026**
- Friction, theorem, 252-254**  
 water in pipes, 1388
- Frostproofing, pipes, 1400**
- Frustum, of cone, 38, 61, 63-64**  
 of pyramid, 38, 61, 64
- Fuels, 1271-1273**  
 air required, 1272  
 boiler-rating affected, 1277  
 calorific value, 1271, 1272, 1273  
 combustion, 1272, 1273  
 consumption, heating-boilers, 1278  
 heating, example, 1317
- Fulcrum, grillage, 166**
- Furnace, combination, 1358**  
 pipes, 1311, 1318, 1322, 1358-1360  
 ratings, 1314  
 registers, 1317-1320, 1355, 1358-1360  
 air-velocity, 1367  
 pressure loss, 1338  
 symbol, 1350  
 stack, 1312, 1317, 1322, 1358  
 work, specifications, 1357-1359
- Furnace-heating, 1310-1324**  
 fuels, 1317  
 specifications, 1357-1359  
 where used, 1355
- Furnace-iron, 379**
- Furnace-leaders, 1311, 1317, 1324, 1358**
- Furniture, dimensions, 1637-1640**  
 metallic, 898-899  
 weight, 149
- Furring, metal, 881, 892**  
 mill-construction, 759  
 outside walls, 891
- Fuses, electric work, 1461**
- Fusion, latent heat, 1251**
- Gable (Glossary), 1820**
- Gallon, capacity, 1247**
- Galvanized iron and steel, 1600, 1604**
- Garage, floor-load, 1198**
- Gargoyle (Glossary), 1821**
- Gas, acetylene, 1431**  
 coal, 1431  
 as fuel, 1273  
 gasoline, 1432  
 illuminating, 1431-1436  
 illumination by, 1448, 1450, 1451  
 lamps, 1451  
 natural, 1431  
 perfect, 1256  
 piping for, 1432-1436, 1445  
 velocities, flue and chimney, 1364  
 water, 1431  
 weight, 1273
- Gas-pipe, separators, steel beam, 614**
- Gas-piping, 1432-1436**  
 symbols, 1445
- Gaskets, pipe, 1389**
- Gasoline, 1432**

**Auges, American Steel and Wire**, 401, 402, 1512  
**Brown & Sharpe**, 401, 402, 1469, 1473, 1509, 1510  
**Circular-mil, wire**, 1469, 1473  
**Corrugated sheets**, 1510, 1600  
   for air-duct metal, 1336  
**piano wire**, 401  
**pressure**, 1248  
**railroad-tracks**, 1642, 1643  
**Roebeling's wire**, 403, 1509  
**sheet-thickness**, 1509  
**standard, compared**, 400, 402  
**U. S. standard, metal sheets**, 402, 1600  
**Washburn & Moen, wire**, 402, 1509  
**ears, size and speed**, 1720  
**enerator, electric**, 1463  
   heat, 1309, 1316  
**geological data, foundations**, 130-140  
**geometrical problems**, 66-90  
**Geometry and Mensuration**, 36-65  
**girder, girders (see, also, Beams)**  
   bearing, 634, 687  
   Bethlehem girder beams, 358, 594-597  
   box (see Box girders)  
   built-up, wooden, 652-656  
   continuous, 555, 671-680, 979-980  
   deflection, 663-670  
     continuous girders, 674-676  
   double-beam, 564, 603, 604  
     tables, 607-611  
   fireproofing for, 780-782, 827-842, 849, 854-860  
   framing (see under Framing)  
   grillage-foundations, 678  
   I beam, 603-611  
   latticed, 1008-1010, 1089-1091, 1181  
     wind-bracing, 1176, 1181, 1182  
   loads, tables of safe, 574-591, 594, 602, 605-611  
   plate (see Plate girders)  
   reinforced-concrete, 972-974  
   riveted (see Box and Plate girders)  
   steel (see Beams, steel)  
   wall-support, 612, 792  
   wind-bracing, 1121  
   wooden (see Beams, wooden)  
**Girdering, cantilever foundations**, 166, 169, 978  
**Glacial deposits**, 133  
**Glass, cast**, 1606  
   cost, 1574-1577  
   crystal-sheet, 1575  
   defects, 1575  
   diffusion of light, 1453-1456, 1577-1580  
   figured rolled, 1577  
   grades, 1574  
   leaded, 1573

**Glass, mills and warehouses**, 759, 763, 764, 769, 772  
   saw-tooth roof, 775  
   mirrors, 1580  
   Novus sanitary, 1606  
   plate, 1576  
   prism, 821, 1454-1456, 1578-1580  
   prism-plate, 1577  
   polished-plate, 1576  
   saw-tooth roof, 775  
   sheet, 1574  
   sizes, 1574-1577  
   skylights, 1580  
   specific gravity, 1504  
   tile, 1606  
   types of, for lighting, 1454  
   weight, 723, 1504, 1651  
   window, 1577  
   wire, fire-protection, 759, 821  
**Glossary**, 1796-1850  
**Gneiss**, 132, 282  
   specific gravity and weight, 1504  
**Gold, specific gravity and weight**, 1504  
**Gordon's formula, cast-iron and steel columns**, 460, 461, 481, 484, 485, 487, 493-495, 496  
**Government buildings, cost**, 1628-1634  
**Grain, weight**, 723  
**Granite**, 131  
   angle of friction, 253  
   beams, coefficients for, 628  
   fiber-stress, 557  
   compressive strength, 266, 280, 281, 282  
     allowed, 267, 287  
   curbing for sidewalks, 1539  
   fire-resistance, 814  
   modulus, of elasticity, 282  
     of rupture, 282  
   shearing strength, 282  
   specific gravity, 282, 1504  
   tension, 282  
   weight, 282, 1504  
**Graphical analysis, arches**, 311-321  
   bending moments in beams, 328-336, 564, 678, 690, 695, 698  
   bending moments, in pins, 426-429  
   column formulas, 496  
   deflection of beams, 670  
   domes, 1224  
   forces, 252, 288-291  
   friction, 252  
   moment of inertia, 345  
   piers and buttresses, 297-304  
   retaining-walls, 257-259  
   roof-trusses, 1065-1137  
   vaults, 1234-1243  
**Graphite, specific gravity and weight**, 1504  
**Grappier cement**, 236

**Grate-area, boilers, 1276, 1283**  
**Grate, furnace, 1321**  
     surface, heating-furnace, 1315  
**Gravel, angle of repose, 256**  
     beds of, 133, 134  
     concrete aggregate, 286, 908  
     graded, 241  
     cost, 249, 250  
     definition of, 134, 136  
     roofing, 871, 1027, 1595-1599  
     safe loads for foundations, 141, 143  
     specific gravity, 1504  
     weight, 256, 1504, 1537  
**Gravity, center of (see Center of gravity)**  
**Gravity, specific, substances, 1500-1508**  
**Gray-iron castings, 379**  
     specific gravity and weight, 1505  
**Grease-traps, 1414**  
**Grecian long measures, 34**  
**Greek letters, symbols, 123**  
**Grillages, beams, spacing, 182**  
     cantilever foundations, 166  
     column-footings, 184  
     foundations, 166-169, 181-185  
         continuous girders, 678  
     fulcrum, foundations, 167  
**Groin (Glossary), 1821**  
**Groined vaults, 1235-1240, 1822**  
**Groins, 1235**  
**Grouting, 269**  
     brick footings, 227  
**Guastavino tile-arch system, 841, 842, 1243**  
**Gum wood, unit stresses, 651**  
     weight, 651  
**Gunnite, column-protection, 826**  
**Gunter's chain, measure, 25**  
**Gusset-plates, truss-joints, 1160, 1161**  
     wind-bracing, 1176, 1179-1186, 1189, 1190, 1193  
**Gutters, 1590**  
     mill-building, 769  
     proportioning, 1658  
     saw-tooth roof, 775  
**Gutter-strips, tin, cost, 1594**  
**Guys, wire, 406**  
**Gypsinite, partitions, 877-878**  
**Gypsum, 131**  
     floors, 856  
     plaster, 818, 1555  
     slabs, heat-transmission, 1259  
     specific gravity and weight, 1505  
**Gypsum-block, partitions, 876**  
**Gyrations, radius of (see Radius of gyration)**  
**H beams, base price, 1204**  
     loads, table, 585  
     properties, 356  
     struts and columns, 474

**H columns, 456, 458, 459**  
     Bethlehem, 473, 475, 476  
     table of loads, 456, 459  
     cast-iron, 456, 458, 459  
     safe loads, 466  
**Hair in plaster, 1555**  
**Halls, air-changes, 156, 157**  
**Hammer-beam truss, 1089**  
**Hammers, pile-driven, 1089**  
     sheeting-plank, 101, 102  
**Hangers, beam and joint, 795**  
     box, 753, 790, 792, 793  
     Duplex, 752-754, 754, 755  
     794  
     Goetz, 752, 792, 793  
     I-beam, 752, 753, 755, 756  
     Ideal, 754, 786  
     Lane, 756  
     mill-construction, 781, 782  
     National, 755, 756  
     stirrup, 750, 756-757  
     strength, 756  
     Van Dorn, 755, 786, 791, 792  
     wall, 750-757, 783-785, 786  
**Hard-pan, 135, 141, 143**  
**Hardwoods, unit stresses, 649**  
**Hatchway, elevators, 1660, 1676**  
**Haunch, arch, 305, 312**  
     arches, filling of, 831  
**Havermeyer bar, 917**  
**Hawser-rope, 404**  
**Hazlewood, hardness, 1553**  
**Headers (Glossary), 1824**  
     brick footings, 226  
     floor-framing, 728, 747, 749  
**Heat, 1249-1251**  
     absolute, 1250  
     British thermal unit, 33, 1251  
     concrete fireproofing, effect of  
         827, 937, 955-959  
     furnace-rating, 1314  
     horse-power equivalent, 1251  
     insulation, 1360, 1363, 1430  
     intensity, 1249-1251  
     latent, 1251-1252  
     loss, 1256-1264  
         furnace heating, 1312  
         walls, 1256  
     measurement, 1247-1250  
     mechanical equivalent, 1251  
     of evaporation, 1251  
     of liquefaction, 1684  
     of the liquid, 1251  
     of vaporization, 1684  
     sensible, 1251  
     specific, 1250, 1684  
     steam, 1249-1254  
     thermometers, 1250



al, vapor, 1254  
 of, 1256-1264, 1684  
 ssion by walls, 1256-1264, 1684  
 om, location, 1357  
 hot-blast, 1329  
 1247-1363  
 nges per hour, 1260, 1261,  
 53, 1354  
 system, 1324  
 r supply, 1319, 1333  
 indirect radiation, 1264  
 radiation, 1264, 1283, 1296  
 stem, 1324-1341  
 ce heating, 1310-1324, 1355  
 see Furnace heating)  
 y systems, 1283, 1298  
 r, 1310-1324  
 and-cold system, 1327  
 last system, 1324-1341, 1346  
 mple, 1342-1347  
 ater, 1302-1310  
 Radiators, 1264, 1270  
 rification, 1359  
 easury Department, 1303, 1308  
 S. Gov't Buildings, 1303-1306,  
 1308  
 ere used, 1355  
 s and branches, 1284, 1289, 1291,  
 1350  
 ating-surface, walls and win-  
 dows, 1256, 1258, 1259  
 ators (see Radiators)  
 isters (see Registers)  
 lences, air-changes, 1353  
 ot-air, 1310-1324, 1357  
 ot-water, 1302-1310, 1359  
 emperatures, 1256  
 ules, 1354  
 team, 1361-1363  
 uirements, buildings, 1256-1264,  
 1354  
 r-tooth roofs, 776  
 fications (see under each system)  
 am, 1264, 1283-1302  
 Bishop - Babcock - Becker system,  
 1287  
 direct, 1283-1291  
 gravity system, 1283, 1298  
 hot-blast, 1324  
 low-pressure system, 1291-1298  
 one-pipe gravity system, 1283-1285  
 Paul system, 1286  
 pipes (see Pipes)  
 special gravity system, 1286  
 specification, 1361-1363  
 two-pipe gravity system, 1286  
 where used, 1355  
 tructures, large, 1324  
 ymbols used, 1350  
 tanks, 1400  
 vacuum system, 1287-1291

Heating, water, by steam-coils, 1430  
 workshops, 769, 776  
 Hemlock, beams, coefficients for, 628  
 deflection, 664  
 flexural strength, 557, 648  
 columns, safe loads, 452  
 compression, 449, 454, 647, 648, 650  
 crushing strength, across grain, 454,  
 648  
 crushing strength, with grain, 449, 648  
 modulus of elasticity, 647  
 safe loads, 638  
 shearing-stresses, 412, 647, 648, 650  
 specific gravity, 1505  
 tensile strength, 376, 647, 648, 650  
 weight, 650, 1505, 1558  
 Hemp rope, 405-408  
 Hennebique system, 920, 940  
 Heptagon, 37  
 Herculean floor-arch, 838-839  
 Herringbone metal lath, 884, 885  
 Hexagon, 37  
 Hickory, hardness, 1558  
 specific gravity, 1505  
 unit stress, 651  
 weight, 651, 1505  
 Hides, weight, 723  
 Hip-rafters, lengths and bevels, 90  
 Hoists, 1723  
 rope for, 404, 407  
 Hollow tile (see Terra-cotta)  
 Homes, heating and ventilating re-  
 quirements, 1354  
 Honeywell heat-generators, 1309, 1310  
 Hook-splice, roof-trusses, 1155  
 Hooks, for chains, 1723-1725  
 Hoops, water-tanks, 1398  
 Hornblende, 131  
 specific gravity and weight, 1505  
 Horse-power, 1248, 1250, 1460, 1720-  
 1722  
 boilers, 1274  
 chimney, 1368  
 electrical, 1460  
 heat-equivalent, 1251  
 machinery, 1720  
 pumps, 1397  
 raising water, 1397  
 transmitted, by belting, 1721  
 by shafting, 1722  
 windmills, 1394  
 Horse-stalls, dimensions, 1643  
 Hose, 768  
 Hose-carriages, dimensions, 1642  
 Hose-reels, 905  
 Hospitals, heating-temperature, 1256  
 and ventilating requirements,  
 1354-1357  
 non-fire-proof, height, 813  
 ventilation, 1349, 1352, 1353, 1354-  
 1357

- Hot-air engines**, 1393  
**Hot-air heating**, 1310-1324  
   fuels, 1317  
**Hot-and-cold system**, heating, 1327  
**Hot-blast heating**, 1324-1341  
   example, 1342-1347  
   radiation, 1324  
**Hot-water heating**, direct, 1302-1310  
   radiators, 1264  
   specification, 1359  
   U. S. Gov't Buildings, 1303, 1306, 1308  
   where used, 1355  
**Hotels**, fire-hose in, 905  
   floor-loads, live, 719, 1198  
   flooring, fire-proof, 892-893  
   furniture, weight of, 149  
   non-fire-proof, height, 813  
   steel, weight, 1208  
   ventilation, 1353  
**House-tanks**, size, 1415  
**Howe truss**, 999-1003  
   design of, 1142-1143  
   joint-details, 1151-1156  
   stresses by computation, 1063, 1065  
   by graphics, 1075-1077, 1102-1105  
   types, 1000-1008  
   weight, 1057  
**Humidifying-apparatus**, hot-blast heating, 1324  
**Humidity**, temperature-relation, 1352  
**Hydrants**, mills, 759  
**Hydrated lime**, 1551  
**Hydraulic jacks**, shoring, 215, 216, 221  
**Hydraulic lime**, 235 (see **Cements**)  
**Hydraulic limestone**, 132  
**Hydraulic ram**, 1390  
**Hydraulics**, 1381-1406  
**Hyperbola**, 38  
   problems on, 79-80  
**Hyperboloid of revolution**, volume, 65  
**Hy-rib**, concrete-reinforcement, 853, 886  
**I beams**, anchors for, 619  
   bending moments, maximum, 574-575  
   Bethlehem, 592  
   loads, safe, 592, 593, 598-602  
   properties, 357  
   buckling of web, 181-185, 565, 567-569, 612  
   table, 574, 575  
   Carnegie, dimensions, 352-353  
   properties, 354, 355  
   safe loads, 577-581  
   concrete, 854  
   connections, anchors, 619  
   floor-framing, 612-619  
   limiting values, 618  
   separators, 612-614, 1202  
**I beams**, connections, standard, 616, 617  
   with Bethlehem H columns, 171  
   with built-up columns, 475, 476  
   with cast-iron columns, 446, 461, 457, 458  
   with plate and box girders, 615  
   continuous, 677-680  
   cost, base price, 1204  
   crippling of web (same as buckling)  
   deflection, lateral, 566, 670  
   vertical, 566, 577-581, 668, 669  
   dimensions, 352, 353, 565  
   double-beam girders, loads, 561, 603, 604, 607-611  
   economy, relative, 565  
   end-bearing, minimum, 574-575  
   end-reactions, 569, 574, 575  
   fireproofing (see **Beams**, steel, fireproofing)  
   framing, between columns, 614  
   to wooden beams and joists, 614, 752, 753, 755, 786-792  
   girders, 603-611  
   double, safe loads, 607-611  
   single, safe loads, 605-606  
   grillage foundations, 167-169, 181-185, 678-680  
   light versus heavy, 565  
   loads, Bethlehem, table, 594-602  
   Carnegie, table, 577-581  
   examples solved, 570-573  
   moment of inertia, 336  
   needling, 218-221  
   oblique loading, 573  
   properties, 352-355, 357, 358  
   radius of gyration, 336  
   separators for, 612-614, 1202  
   shearing, 181-185, 567, 568, 569  
   table, 574-575  
   single-beam girders, loads, 605, 606  
   span-lengths, limiting, 618  
   standard, dimensions, 352-353  
   properties, Bethlehem, 357-358  
   properties, Carnegie, 352-355  
   supplementary, 352  
   tie-rods for, 619, 865  
   web-resistance, 181-185, 567-569  
   table, 574-575  
**Ice**, melting-temperature, 1251  
   specific gravity and weight, 1505  
**Ice-making**, 1693-1695  
**Idaho**, registration law, 1778  
**Igneous rocks**, 131  
**Illinois**, registration law, 1778  
**Illuminants**, hygiene of, 1452  
   selection, 1452  
**Illuminating gas**, lighting, 1431-1454  
   1451  
**Illumination** (see **Lighting and Illumination**)  
**Incandescent lamps**, 1462, 1471, 1481

incandescent lighting (see Lighting)  
 inch, equivalents, 25, 26  
 inch-pound, 290  
 inclined plane, friction, 252  
 incrustation, boilers, 1429  
 inertia, moment of (see Moment of inertia)  
 influence lines, 1134-1137  
 institutions, educational, architectural, 1779  
 insulating quilts, 1565  
 insulation, 1683, 1690  
 heat, 1430, 1566  
 mineral wool, 1610  
 pipe, 1430  
 insulators, electric, 1458  
 insurance during construction, 1756  
 interphones, 1707  
 intrados, arch, 305  
 inverse squares, law, light, 1440  
 evolution, arithmetic, 3  
 Ionic Order, 1699-1702  
 Ionic Volute, 1702  
 iron, cast (see Cast iron)  
 galvanized, 1604  
 properties, 375  
 wire, 400  
 iron, wrought (see Wrought iron)  
 isosceles triangle, 293  
 jack, jacks, hydraulic, 216, 221  
 jack-rafters, lengths and bevels, 90  
 jack-screws, shoring, 215, 216, 221  
 jacket, furnace, 1310, 1311  
 wish long measures, 34  
 Johnson floor-construction, 837-840, 841  
 joint, rupture, dome, 1213  
 joints (see under each subject)  
 joint (Glossary), 1826  
 joists, floor (see Floor-joists)  
 ceiling (see Ceiling-joists)  
 joist-hangers (see Hangers)  
 joist, 1250  
 joy, competitions, 1737, 1743  
 Johnson bar, 921  
 system, 940  
 flame iron, 894-895  
 Johnson's cement plasters, 1556  
 Johnson's warm-air generator, 1316  
 Johnson's flushometer, 1420  
 Johnson's chimney-formula, 1366  
 Johnson's expanded-metal lath, 884  
 joisted beams, 653-655  
 joists, compound beams, 654  
 jointstone arches, 305, 308, 310 (Glossary), 1827  
 Rankine's formula, 308  
 Trautwine's formula, 309  
 jointstone hair insulator, 1566

Kilowatts, defined, 1460  
 King-post truss (see Roof-truss)  
 King-rod truss (see Roof-truss)  
 Kitchen ranges, flues, 1282  
 Kitchen-sinks, dimensions, 1641  
 Knee-braces, trusses, 1025-1027 1116-1118, 1164, 1168  
 wind-bracing, 1179, 1181, 1185-1190  
 Knife-switch, 1477, 1479  
 Kno-burn lath, 884  
 Kno-fur lath, 885  
 Labor, cost, 1564  
 Laboratories, lighting for, 1451  
 Lacing-bars, 385  
 Ladder-wagons, dimensions, 1642  
 La Farge cement, 236, 238  
 Lag-screws, 1535  
 roof-trusses, 1157  
 Laitance, 244  
 Lally columns, 467, 474, 477  
 loads, 488, 516  
 Lamps, arc, 1462, 1463  
 arrangement, 1465, 1466  
 bowl-size, 1443  
 brilliancy, 1439  
 gas, 1451  
 height, 1444  
 incandescent, 1462, 1471, 1482  
 kinetic burner, 1451  
 location, 1442, 1443, 1446  
 number, 1446, 1449, 1475  
 sizes, 1443, 1444  
 tungsten, 1444, 1447  
 Welsbach, 1444, 1451  
 Land, measure, 27  
 Lard-oil, weight, 723  
 Lath, metal (see Metal lath)  
 wire (see Metal lath)  
 wooden, 1554  
 Lathing, 1554  
 cost, 1557  
 Lattice-bars, columns, 477-479  
 specifications, 1202  
 Lattice columns, 477-479  
 Lattice girders, 1008-1010, 1089-1091  
 wind-bracing, 1176, 1181, 1182  
 Lattice trusses, 1008-1010, 1089-1091  
 Laundry-tubs, dimensions, 1641  
 Lava, 131  
 crushing strength, 280  
 Lavatories, dimensions, 1641  
 Laws, building (see Building laws)  
 registration, architects, 1768-1779  
 ventilation, 1354  
 Lead, anchor-bolts, 240  
 castings, shrinkage, 1521  
 pipe, 1408, 1413, 1416-1418  
 sheet, 1418, 1511  
 specific gravity, 1505  
 weight, 1505, 1511

**Leaders, furnace, 1311, 1317, 1324, 1358**  
**Leather, weight, 723**  
**Length, unit of, 1247**  
**Lever, principle of, 165, 290, 293, 294**  
**Libraries, book-stacks, 1696**  
     ventilation, 1353  
**Licence law, architects, 1768-1779**  
**Liens, 1758**  
**Light, brilliancy, 1439**  
     candle-power, 1439, 1440, 1462  
     diffusion, 1453-1456, 1577-1580  
     heat, emission, 1261  
     intensity, 1439  
     nature of, 1438  
     refraction, 1453-1456, 1577-1580  
     sources, 1438  
         colors, 1438  
**Lighting and illumination, 1437-1456**  
     accounting-offices, 1446  
     auditoriums, 1451  
     bibliography, 1456  
     ceiling-lights, 1446  
     ceiling-outlets, 1449  
     class-rooms, 1451  
     coloring of ceilings, 1442  
     design of system, 1444, 1446  
     diffusion by glass, 1453-1456, 1577-1580  
     direct, 1441, 1442, 1446-1448  
     drafting-rooms, 1451  
     electric-lighting systems, 1464-1469  
         cost, 1482  
         design, 1446-1448  
     electric power required, 1441  
     factories, 969  
     feed-wires, 1478  
     fixtures, care of, 1443  
         in direct systems, 1446-1448  
         in semiindirect systems, 1448-1450  
     foundries, 1451  
     gas, 1448, 1450, 1451  
         amount of gas required, 1441  
         calculations, 1448  
         pipe, sizes, 1432-1436  
         piping, symbols, 1445  
     general principles, 1437  
     heights of lamps, 1444  
     Holophane reflector, 1447  
     hygiene of, 1452  
     indirect, 1441, 1442, 1448-1450  
     intensity, 1439, 1440  
     laboratories, 1451  
     law of inverse squares, 1440  
     lecture-halls, 1451  
     machine-shops, 1451  
     mill-buildings, 969  
     outlets, 1442, 1443, 1446  
     piping for gas, 1432-1436, 1445  
     reflectors, 1447, 1448  
     roof-lights, 775

**Lighting and illumination, saw-logs**  
     roofs, 772, 775  
     school-rooms, 1451  
     semiindirect, 1442, 1448-1450  
     single-phase system, 1464  
     switches, 1478, 1479, 1481  
     systems, 1464-1469  
     three-phase system, 1464-1469  
     three-wire system, 1464-1469  
     two-wire system, 1464  
     windows, 775, 1453-1456  
     wiring, cost, 1482  
     workshops, 769, 1451  
**Lightning-conductors, 1704-1707**  
**Lignite, combustible, 1271, 1272**  
**Lignum-vitæ, ultimate unit stress**  
     651  
     weight, 651  
**Lime, 1548-1553**  
     Alca, 1553  
     chemical properties, 1550  
     classification, 1549  
     data, 1553  
     hydrated, 1551  
     hydraulic, 235  
     inspection, 1550, 1552  
     nature, 1548  
     properties, 1548, 1550, 1552  
     sampling, 1549  
     specific gravity, 1506  
     specifications, 1549-1551  
     tests, 1549  
     weight, 723, 1506  
**Limestone, 132**  
     beams, coefficients for, 628  
     calcite, 131  
     calcium, 1549  
     compressive strength, 266, 280, 282, 287  
     constituents, 1548  
     dolomitic, 131, 1549  
     fiber-stresses, 557  
     fire-resistance, 814  
     modulus of elasticity, 282  
         of rupture, 282  
     shearing strength, 282  
     specific gravity and weight, 282, 1506  
     tensile strength, 282  
**Line of fracture, arches, 316**  
**Linear measures, 25**  
     metric, 31  
     Gunter's chain, 25  
     ropes and cables, 25  
**Lines, center of gravity of, 292**  
     geometrical problems, 66  
**Lines of pressure, arches, 311-321**  
     buttresses, 297-304  
**Links, strength of, chains, 410**  
**Linseed-oil, 1568, 1569**  
     specific gravity and weight, 1505

- stels, 305**  
**cast-iron, 620-627**  
   cross-section, ideal, 620  
   deflection, 628, 664  
   formulas, 620-621  
   safe load, tables, 624-627  
**reinforced-concrete, 975**  
**stone, 1539**  
**liquid measure, 27**  
**metric, 32**  
**liquefaction, heat of, 1684**  
**live loads (see member loaded)**  
   definition, 126, 149  
   dead, loads (see, also, each member loaded; also Weight)  
**cast-iron columns, 461**  
   footings, 162-165  
**eccentric, columns, 489, 946**  
   footings, 162-165  
   steel column, 485-489  
   steel-pipe column, 472  
   wooden column, 453  
**oblique, steel beams, 573, 593**  
**on columns, method of computing, 148-152, 489, 490**  
**on floors, fire-proof, 833, 837-844, 850-852, 856, 863-865**  
   mill-buildings, 802-808  
   reinforced concrete, 936, 948, 967, 971, 984-987  
   steel, 1197  
   various buildings, 149  
   wooden, 717-749  
**on foundation-beds, 141-143, 148-160**  
**on masonry, 265-267, 287, 441, 442, 1200**  
**on roofs, 740-741, 745, 746, 1048-1057, 1196**  
**on reinforced-concrete slabs, 984-987**  
**safe-load, definition, 125**  
**snow-loads, 1049, 1052-1057**  
**tests, fire-proof floors, 827, 866, 956-958, 967**  
   foundation-beds, 141-146  
   wind-loads, 148-160, 1049, 1052-1057, 1171-1173, 1198  
**lock-woven fabric, 849**  
**locomotives, dimensions, 1642**  
**locust, safe fiber-stress, flexure, 557, 648**  
   specific gravity, 1506  
   unit stresses, 651  
   weight, 651, 1506  
**lodging-house, defined, 1853**  
**loft-buildings, chimneys, 1368**  
**lofts, cost, 1613**  
   live loads on floors, 149, 1197  
**logwood, extract of, 723**  
**loop-eyes, 386**  
**loop-rods, 386, 396**  
**Louisiana, registration law, 1778**  
**Louisville code, loads on foundation-beds, 143**  
   masonry loads, 287  
**Lumber (see, also, Timber and different woods)**  
   asbestos, 819  
   data, 1558-1564  
   framing, 1559  
   hardness, relative, 1558  
   measurement, 1559-1563  
   metal, 858  
   specific gravity, 1501-1508  
   weight, 1501-1508, 1558  
**Luten truss, 923**  
**McGill University, tests on brick piers, 275**  
**Machine-shop, design and cost, 802-803**  
   saw-tooth roofs, 774  
   steel, weight, 1209  
**Machinery, vibration of, 763**  
**Machines, dynamo-electric, 1463**  
   refrigerating, 1685-1690  
**Mackolite, partition-blocks, 877**  
**Mahogany, unit stresses, 651**  
   specific gravity, 1506  
   weight, 651, 1506  
**Mail-chutes, 1677-1679**  
**Mains, steam, 1284, 1289, 1291, 1350**  
**Manhattan Life Insurance Building, foundations, 251**  
**Manila rope, 406-408**  
**Mansard roof, tiles for, 870**  
**Mantel-tile, 1605**  
**Maple, deflection in beams, 664**  
   hardness, 1558  
   unit stresses, 651  
   weight, 651, 1558  
**Marble, beams, coefficients for, 628**  
   compression, 266, 282  
   crushing strength, 280, 282  
   fiber-stresses, flexure, 557  
   fire-resistance, 814  
   loads, safe, masonry, 266  
   shearing strength, 282  
   specific gravity, 282, 1506  
   strength, 267  
   tension, 282  
   tile, 1605  
   weight, 282, 1506  
**Marblethic tile, 1606, 1607**  
**Masonry, 1538, 1539 (see, also, Brick-work, Stonework, Walls, etc.)**  
   arches (see Arches)  
   bearing pressure, allowable, 441-444  
   bed (Glossary), 1802  
   bond (Glossary), 1803  
   bond-stones, effect of, 269  
   building codes, 267, 287  
   cement mortar required, 239, 247

- Masonry, classification, 1538**  
 coefficients of friction, 253  
 compressive strength, 265, 441  
 cost, 1538, 1539  
 crushing strength of stone, 279-282  
 footings, 178, 223-225  
   tensional strength, 178-179  
 grouting, 269  
 measurement, 1538  
 mortar for, 229-239, 247  
 piers, 270  
 pressures allowed, 265, 267, 287, 441, 1200  
 safe working loads, 265-267, 287, 441  
 strength, 265-282, 441, 1200  
 stresses in, 265  
 thickness of walls, 229-234  
 walls, 228-234  
 weight, 1506
- Mass-concrete, strength, 267**
- Mathematical signs and characters, 3**
- Mathematics, practical, 3-5**  
 McGill University, tests on brick piers, 275
- Measure, measures, 25-35**  
 ancient, 34  
 circular and angular, 30  
 conversion tables, 33-35  
 cubic, 27  
   metric, 31  
 dry, 27  
   metric, 32  
 Egyptian long, 34  
 fluid, 28  
 Grecian long, 34  
 Jewish long, 34  
 land, 27  
 linear, metric, 31  
 liquid, 27  
   metric, 32  
 metric system, 30-33  
 miscellaneous, 26, 28, 34  
 nautical, 26  
 Roman long and weight, 34  
 Scripture and ancient, 34  
 surface, 27, 31  
 time, 30  
 value, 29  
 volume, 27, 31  
 weight, 28-29  
   metric, 32
- Mechanical refrigeration, 1684-1695**
- Mechanics, applied, definition, 124**
- Mechanics of materials, terms used, 124**
- Medals, architectural, 1779-1788**
- Melan arch, 844**
- Mensuration, 38-65**  
 definition, 38  
 solids, 61-65  
 surfaces, 38-61
- Merchandise, weights, 721-723**
- Merchant-bar iron, 577**
- Metal, asbestos-protected, 819**  
 data, 1509  
 doors, 894-897, 901, 902  
 finish, 896  
 sheet, standard gauges, 402
- Metal frames, fire-proof buildings, 54**
- Metal furring, 881, 892**
- Metal lath, 882-892, 919**  
 column-protection, 822  
 expanded, 884  
 fireproofing, 781  
 partitions, 878, 882, 888, 890  
 sheet, 402, 886, 1510, 1599  
 woven-wire, 887
- Metal lumber, 858**
- Metal-rib plaster-board, 888**
- Metal sashes, fire-proof buildings, 54**
- Metallic furniture and fittings, 598-599**
- Metamorphic rocks, 131, 132**
- Metric system, 30-32**  
 conversion tables, 32-35
- Mica, 131**  
 specific gravity and weight, 1506
- Mica-schist, 132**
- Middle third, theorem of, 254**  
 arches, 311-315  
 buttresses, 301, 304  
 domes, 1225, 1227  
 footings, 164  
 retaining-walls, 259  
 vaults, 1233, 1234, 1240
- Mill-buildings (see, also, Mill-construction), brick, 808-810**  
 cost, 808-810, 1206  
 depreciation, 1634  
 reinforced concrete, 968-997  
 steel, cost, 1206  
   weight, 1208, 1209, 1210  
 wooden, 758-810
- Mill-construction, reinforced-concrete, 948, 968-997**  
 columns, 969, 976, 978, 980  
   loads, distribution, 976  
 cost, 777, 1613, 1618  
 floors, 968, 971, 993  
   beams, secondary, 971  
   formulas for design, 985-997  
   girderless, 968, 993-997  
 footings, 978, 982  
 girders, 974, 975  
 lighting, 969  
 lintels, 975  
 stairs, 899-901, 982, 983
- Mill-construction, slow-burning, 753-810**  
 belts, shafts, 765  
 boiler-plant, 765, 780  
 columns, cost, 810  
   fireproofing, 780, 781, 822-826

**Mill-construction, slow-burning col-**  
 umns, framing, 769, 782-800  
**conductors, 775**  
**cornices, 764, 769**  
**cost, 758, 777, 802-810, 1613, 1618**  
**doors, 801**  
**dry-rot, 759**  
**elevator-towers, 764, 768**  
**fire-protection, 768, 777, 779, 801,**  
 903-905  
**fire-retardants, 759**  
**fire-shutters, 759, 778, 801, 901, 902**  
**fire-stops, 759**  
**fireproofing metal members, 780-782**  
**floors, 760-764, 766**  
 cost, 810  
 estimating, 1563  
 framing (see **Framing, floors**)  
 old, strength, 749  
 plank, 730-735  
 strength and stiffness, 717-757  
 surfacing, 769  
 warehouses, 777  
**frames and shutters, 764**  
**framing, steel, 786, 788**  
**general description, 758-760**  
**girder-supports, 792**  
**glass, 759, 763, 764, 769, 772, 775**  
**gutters, 769, 775**  
**hangers, 782, 785, 789**  
**heating, 769, 776**  
**height, of buildings, 777-778, 813**  
 of stories, 765, 810  
**hoist-supports, 792-794**  
**painting, 759, 763**  
**partitions, 759, 801**  
**plumbing-fixtures, 810**  
**post and girder-connections, 795-800**  
**post-caps and bases, 782-788, 791,**  
 795-800  
**pumps, 759**  
**roofing-materials, 760, 800-801**  
**roofs, 760**  
 cost, 810  
 example, 769  
 materials (see **Roofing, materials**)  
 timber framing, 765  
 walls, 768  
**saw-tooth, 772-777**  
**scuppers, 767,**  
**hafting, 765**  
**skylights, 765**  
**sprinklers, 768, 777, 779, 801, 904**  
**stairways, 759, 810**  
 tower, 764, 768, 778, 779  
**steam-pipes, 764**  
**struttings, wrought-iron, 750, 754-**  
 757, 787-794  
**storehouses, 765-788**  
**structural details, 782-792, 1194-**  
 1212

**Mill-construction, slow-burning tim-**  
 bers, 759, 762, 763  
 towers, 764, 768, 779, 779  
 trusses, 772  
 ventilation, 769, 775, 776  
 of timbers, 763  
 walls, 760, 765, 768, 778, 809  
 warehouses, 777-782  
 weave-shed, 773  
 windows, 763, 769, 772, 775, 778  
 fire-guards, 759  
 frames, 764  
**Milwaukee building code, formula for**  
 steel columns, 481  
**Mineral wool, 1566, 1609, 1610**  
**Minneapolis building code, formula for**  
 steel columns, 481  
 loads on foundation-beds, 143  
 office-buildings, assumed loads, 151  
 thickness of walls, 231-232  
**Mineral oil, fuel, 1272**  
**Minerals, forming rock, 130**  
**Mirrors, 1580**  
**Modulus of elasticity, 126, 626, 662**  
 concrete, 912, 924, 934, 935, 956  
 definition, 126  
 notation, symbols, 122  
 steel, 381, 912, 934  
 stone, 282-283  
 various materials, 647, 664  
**Modulus of rupture, 126**  
 concrete, mortar, and stone, 282-283  
 woods, 650-651  
**Modulus, section (see Section-modulus)**  
**Molding (Glossary), 1830**  
**Moldings, classical, 1697, 1698**  
 plaster, 1556  
**Molds, concrete, 962-966**  
**Moment of force, definitions, 127, 289,**  
 322  
**Moments, bending (see Bending mo-**  
 ments)  
 of inertia (see **Moments of inertia**)  
 of resistance, 333, 556  
 principle of, 289-291, 294, 301, 322-  
 324  
**Moments of inertia, areas, 332-352**  
 compound sections, 339-345  
 definitions, 332-333  
 determined graphically, 345  
 notation, 122  
 rectangles, tables, 346-347  
 structural shapes, 354-359, 362-369  
 transferring, 338-345  
**Moments of resistance, flexure-for-**  
 mula, 333, 556  
**Money, United States, 29**  
**Montana registration law, 1778**  
**Mortar, adhesive strength, 240**  
 aggregates, 241  
 alca lime, 1553

- Mortar, brickwork**, 227, 271  
 cement, 235-240  
 cement-gun, 826  
 colors, 1547  
 durability, 818  
 fire-resistance, 818  
 floor-tiles, 829  
 for plastering, 239, 1554-1558  
 freezing, effect of, 239  
 grouting, 227, 269  
 hair in, 1555  
 hot water in, 239  
 hydrated lime, 1551  
 lime, compressive strength, 282  
 mixing, cement, 239  
 natural-cement, 235  
     compressive strength, 283  
 Portland-cement, 238  
     compressive strength, 283  
 quantity required, 239, 247  
 relative compressive and tensile strength, 283  
 salt in, 239  
 specific gravity, 1506  
 stone walls, 229, 230  
 water required, 238  
 weight, 1506
- Mortar-colors**, 1547
- Mortuary, refrigerator**, 1683
- Mosaics (see, also, Tile)**  
 Ceramic, 1605, 1607  
 Florentine, 1605  
 Roman, 1605, 1607  
 terrazzo, 1607
- Motion, definition**, 124  
 rate, 1247
- Motor**, 1463  
 for elevator, 1676, 1677  
 for fan-drive, 1347  
 heat-emission, 1261
- Mud**, 139
- Mullion and munion (Glossary)**, 1831
- Mushroom system, reinforced concrete**, 950, 993-997
- Nails**, 1529-1534
- National Board of Fire Underwriters code, masonry-load**, 287  
 concrete, 958
- National Electric code**, 1480, 1481
- Natural cement**, 235  
 concrete, 235, 267, 284  
 mortar, 235  
     compressive strength, 283  
 production, 235  
 strength, 235, 284  
 weight, 235  
 where used, 235
- Natural gas**, 1431
- Nautical measures**, 26
- Needling**, 218-222
- Neutral axis, beam-sections**, 337-555, 621
- New Jersey registration law**, 1773
- New Orleans building code**, 1011  
 foundation-bed, 142  
 thickness of walls, 231
- New York City building code**, 1711  
 307  
 bearing pressure on masonry, 441, 448  
 column-formula, cast-iron, 460  
 compression, steel members, 495  
 formula for steel columns, 481, 495  
 loads on foundation-beds, 143  
 masonry-loads, 267  
 office-buildings, assumed loads, 151  
 pipe-column formula, 469, 474, 498  
 rivets, bearing and shear, 419  
 skeleton construction, 234, 1171  
 terra-cotta, 276  
 thickness of walls, 230, 231-237  
 wind bracing, 1171
- New York State, registration law**, 1776, 1778
- Nickel tubing**, 1415
- Nicking test, wrought iron**, 378
- Nonagon**, 37
- North Carolina, registration law**, 1773
- North Dakota, registration law**, 1773
- Novus sanitary glass**, 1606
- Norway pine, beams, loads**, 641  
 deflection, 664  
 fiber-stress, safe, 557  
 columns, safe loads, 450, 451  
 crushing-load, 449  
 crushing strength, across grain, 454  
 specific gravity, 1507  
 unit stresses, 376, 647, 650  
 weight, 650, 1507
- Notation mathematical**, 122, 123
- Nozzles, roof**, 801
- Nuts**, 1525  
 standard dimensions, 1526  
 weight, 1527
- Oak, beams, coefficients for**, 628  
 deflection, 664  
 distributed loads, safe, 643  
 fiber-stresses, 557  
 columns, safe loads, 450, 451  
 crushing-load, with the grain, 449  
 crushing strength, across the grain, 454  
 hardness, 1558  
 shearing-stresses, 412  
 specific gravity, 1506  
 unit stresses, 376, 412, 647, 648, 651  
 weight, 651, 1506, 1558
- Obsidian**, 131
- Octagon** 37



**Ice-buildings**, chimney, 1368  
**Cost**, 1613  
**Fire-hose** in, 905  
**Floor-joists**, 738, 743  
**Floor-loads**, 149, 151, 719, 720, 1198  
**Furniture**, weight, 149  
**I beams**, sizes, 864  
**Steel**, weight, 1207, 1208  
**Ices**, air-change, 1353  
**Islets**, footings, 163-165, 179, 223-227  
**Iron**, defined, 1458  
**L**, mineral, as fuel, 1272  
**Open-hearth**, steel, 380  
**Opera-houses**, dimensions, 1657  
**Chairs**, 1653  
**Seating capacity**, 1654-1656  
**Orders**, classical, 1698-1704  
**Oregon Pine** (see **Douglas fir**)  
**Organizations**, architectural, 1788-1795  
**Ottawa sand**, 235, 241, 908  
**Overdraft**, in furnace, 1310  
**Owner**, competitions, 1739, 1740, 1746  
**Owner's right**, in contract, 1760  
**Paint, Painting**, 1568-1573  
**Cement and concrete**, 1573  
**Driers**, 1569  
**Enamel**, 1570  
**Fire-proof**, 821-822, 894  
**Inside**, 1570  
**Mill-construction**, 759  
**Old work**, 1571  
**Outside**, 1569  
**Paints**, 1568-1570  
**Pigments**, 1568  
**Plastered walls**, 1571  
**Priming**, 1569  
**Repainting**, 1571  
**Steelwork**, 1203, 1206, 1572  
**Timbers**, 763  
**Tin roofs**, 1570, 1589, 1590  
**Varnish**, 1568, 1570, 1573  
**Vehicle**, 1568  
**Pantry-sinks**, dimensions, 1641  
**Paper**, building, 1564-1568  
**Weight**, 722  
**Paper-mills**, cost, 805  
**Steel**, weight, 1210  
**Parabola**, 38  
**Center of gravity**, 293  
**Problems**, 79  
**Paraboloid of revolution**, volume, 65  
**Parallelogram**, 37, 39  
**Of forces**, 289  
**Parallels**, 36  
**Parapets on mills**, 768  
**Architecture**, 1833  
**Parchment**, water-proof sheathing, 1568  
**Parking**, defined, 1853  
**Partitions**, brick, 873  
**Concrete**, 876, 880

**Partitions**, defined, 1853  
**Double**, 880, 890  
**Fire-proof**, 873-892  
**Fire test**, 873, 889  
**Gypsum-block**, 876  
**Heating pipes through**, 1358, 1360  
**Hollow-tile**, 873-874, 890  
**Mackolite**, 877  
**Metal-lath**, 878, 882-888, 890  
**Mill-construction**, 759, 801  
**Rib-stud**, 881  
**Soundproofing**, 889-891  
**Scantling**, incombustible, defined, 1853  
**Solid plaster**, 878, 880, 890  
**Terra-cotta**, 873, 875, 890  
**Types**, 873  
**Wooden**, 725-727, 748  
**Partition-wall**, defined, 1853  
**Party walls**, 873  
**Defined**, 1853  
**Floor-loads on**, 234  
**Patent rights**, payment, 1759  
**Patterns**, castings, 1521  
**Paul**, air-line system, heating, 1286  
**Pavement-prisms**, 1579  
**Pavements**, asphalt, 1608  
**Payments**, on contract, 1758  
**Pearl-alum**, weight, 723  
**Peat**, 139, 1272  
**Pedestal-piles**, 198  
**Peerless radiators**, 1265, 1266  
**Pentagon**, 37  
**Perimeter**, 37  
**Of triangles**, center of gravity, 292  
**Persons**, heat-emission, 1261  
**Pews** (Glossary), 1835  
**Philadelphia building code**, bearing  
**Pressure on masonry**, 444  
**Formula for steel columns**, 481, 493  
**Loads on foundation-beds**, 143  
**Masonry-loads**, 267  
**Pipe-column formula**, 469, 474  
**Phosphorus in steel**, 381, 383  
**Pianos**, dimensions, 1638  
**Piers**, arch, 305  
**Brick**, 268-269, 271-276, 278  
**Bond-stones**, 269  
**Safe loads**, 265, 268  
**Strength**, 268, 271-276, 278  
**Tests**, 275  
**Caisson**, 212, 214  
**Center of gravity**, 300, 301, 302  
**Footings for**, 161, 162, 176-178, 184, 185  
**Foundation**, 129, 188, 200  
**Line of pressure**, 300  
**On concrete and wooden piles**, 199  
**Grillage**, 184, 185  
**Pneumatic-caisson method**, 212, 214  
**Reinforced-concrete**, 980

- Piers, stability, 297-304**  
 stone, 270  
 terra-cotta, 276-278  
 thrust, 297, 298
- Pigments, paints, 1568-1570**
- Pilasters (Glossary), 1835**
- Pile-drivers, 190, 194-196, 202-204**
- Piles, durability, 188, 196**  
 iron-pipe, 199  
 reinforced concrete, 196-200, 945  
 versus wooden, strength, 196  
 wooden, 188-196  
   capping, 190-192, 198  
   timber-grillage, 191, 192  
 cost of driving, 195  
 crushing strength, 196  
 driving, 189, 190, 194-196, 202-204  
 durability, 188, 196  
 Engineering News formula, 193  
 municipal requirements, 189  
 plan of, for building, 192  
 safe loads, 189, 193, 195  
 specifications, 193  
 strength versus concrete piles, 196  
 under piers, 199  
 woods used, 189
- Piling, sheet, 200-209**
- Pillars (Glossary), 1835**
- Pin, pins, in trusses, 423-429**  
 steel, stresses, 618, 1138, 1200
- Pine, specific gravity and weight, 1507**  
 Norway (see **Norway pine**)  
 white (see **White pine**)  
 yellow (see **Yellow pine**)
- Pinnacle (Glossary), 1836**
- Pipe, pipes (see, also, Ducts)**  
 block-tin, 1418, 1419  
 brass, 1429  
 capacity, 1383, 1403  
 cast-iron, 1389, 1407, 1427, 1428  
 conduits, 1479  
 coverings, 1360, 1363, 1430, 1610  
 drain, 1407-1412, 1419, 1420  
 expansion, 1427-1429  
 flow of water through, 1382-1400,  
   1420  
 friction in, 1388  
 frostproofing, 1400  
 furnace, 1311, 1318, 1322, 1358,  
   1360  
 gas, 1432-1436  
 hot-water heating, covering, 1360,  
   1430  
   size, 1305, 1306  
   specifications, 1359  
 hot-water supply, 1415, 1428, 1429  
 lead, 1408, 1413, 1415, 1416-1418  
 location, fireproof, 826  
 sewer, 1407-1409, 1419, 1420-1422  
 sheet-metal, 1337  
 smoke, 1362
- Pipe, soil, 1407-1410, 1427**  
 steam-heating, 764, 1362  
   covering, 1363  
   pressure-loss, 1292  
   size, 1294  
   specifications, 1362  
 steel, 1408  
 supply, 1390-1398, 1415  
 symbols, 1350, 1424-1426  
 tests, 1388, 1412  
 tin-lined, 1418  
 vent, 1407, 1410  
 warm-air, size, 1318  
 waste, 1407-1411, 1416, 1417, 1427  
 wrought-iron, 1408, 1429, 1432-1436
- Pipe-columns, 469-474, 488**  
 loads, 488, 497-498
- Pipe-coverings, steam-pipes, 1360, 1363,  
 1430, 1610**
- Pitch of roofs, 867, 869, 1046, 1053**
- Pitch, gravel roofs, 1595-1599**  
 slag roofs, 1595-1599  
 specific gravity and weight, 1507
- Plane, 36**  
 inclined, 252
- Plaster, alca-lime, 1553**  
 asbestic, 818  
 fire-resistance, 818  
 gypsum, 818, 1555  
 hard-wall, 1556  
 hydrated-lime, 1551  
 Keene's cement, 1556  
 machine-made, 1555  
 measuring, 1556  
 mortar for, 239, 1554-1558  
 staff, 1558  
 wall, 1555  
 weight, 723
- Plaster-blocks, 876**
- Plaster of Paris, column-protection, 122**  
 fire-resistance 818
- Plastering, 1554-1558**  
 coats, 1554  
 cornices and moldings, 1556  
 cost, 1557
- Plate, base, forms of, 441**  
 bearing, 440  
   pressures, 441, 1200  
 cast-iron, weight, 1524  
 cover, riveted joints, 421  
 steel, 384, 385  
   base price, 1204, 1205  
   punching, effect, 382, 414, 658  
 wall (see **Wall-plates**)
- Plate-and-angle columns, 46, 479**  
 connections, 477  
 moment of inertia, 343  
 radius of gyration, 344  
 tables, 488, 517-532
- Plate girders, 681-716**  
 construction, details, 682-683

ate girders, elements, 706-716  
 end-reactions, maximum, 703, 706-716  
 examples, 688-694  
 framing and connections, 614-616, 682  
 moment of inertia, section, 340-342  
 safe loads, 706-716  
 shear, 684-687, 690, 691, 696, 698, 703  
 specifications, 1201, 1202, 1203  
 splice-plates, 693  
 stiffeners, 681, 686, 691, 696, 1201, 1203  
 stresses, design, 683, 1201  
 web, 681, 703-705  
     buckling, 686, 705  
     shearing value, 703-704  
     stresses, 684, 686, 691  
 weight, 687  
 atforms, stone, 1539  
 enum chamber, 1350  
 enum system, ventilating, 1356  
 umbing, 1407-1430  
     definition of terms, 1407  
     fixtures (see Plumbing-Fixtures)  
     pipes (see Pipes)  
     symbols, 1423-1426  
     testing, 1412  
 umbing-fixtures, 1410-1415, 1420-1426  
     cost, mill-buildings, 810  
     dimensions, 1640-1642  
 unge-bath, 1422  
 ltonic rocks 131, 132  
 neumatic, caisson, 211-214  
     water-supply, 1396  
 oint, 36  
 oling-board method, foundations, 209  
 olygons, definition, 36  
     equilibrium, 289, 299, 313-315, 319  
     factors for determining elements, 40  
     force, 289, 1070  
 olyhedrons, regular, 63  
 oplar (see, also, Whitewood)  
     columns, safe loads, 450, 452  
     crushing-loads, with the grain, 449  
     hardness, 1558  
     specific gravity, 1507  
     unit stresses, 651  
     weight, 651, 1507, 1558  
 ortal bracing, 1176, 1182  
 ortland, Ore., building code, loads on  
     foundation-beds, 143  
 ortland cement, 236-240  
     adhesive strength, 240  
     composition, 236  
     concrete, reinforced, 907, 908  
     concrete blocks, 233  
     cost, 238  
     defined, 237  
     fineness, 237, 907

Portland cement, manufacture, 236  
     mixing, 238  
     mortar, 238  
         compressive strength, 283  
         proportions, 235, 247  
         specific gravity and weight, 1506  
     quantities in concrete, 247, 248, 249  
     setting-time, 237, 907  
     specific gravity, 237, 907, 1502  
     specifications, 236, 907  
     strength, 237, 240, 283, 284, 907  
     testing, 237, 240, 907  
     weight, 235, 723, 1502  
 Post-caps, 782-788, 791, 795-800  
 Post-office buildings, cost, 1630  
 Posts (see Columns)  
 Pound-feet, 290  
 Pound-inches, 290  
 Power, 1248, 1250  
 Power-hammer, underpinning, 221  
 Power-houses, steel, weight, 1210  
 Pratt truss, 1026, 1029, 1031, 1032  
     economy, 1055  
     with inclined ties, 1077  
 Pressure, barometric, 1249  
     earth, 201, 205  
     gauges, 1248  
 Prism, 38, 62  
 Prism-glass, 1454-1456, 1578-1580  
     fire-resistance, 821  
 Prismoid, quadrangular, 62  
 Prisons, ventilation, 1353  
 Prizes, architecture, 1779-1788  
 Professional practice, A.I.A., 1727  
 Programme, competitions, 1737, 1741  
 Public building (see, also, Federal buildings)  
     cost, 1613, 1628-1634  
     defined, 1853  
     registers, heating, 1355  
 Pulleys, arrangement, 1722  
     sash, 1649  
     size and speed, 1720  
 Pulpit (Glossary), 1838  
 Pumice, 131  
 Pumps, air-lift, 1395  
     deep-well, 1391  
     fire, 1401  
     mills, 759  
     plunger, 1391  
     pneumatic system, 1396  
     private water-supply, 1390  
     single-acting, 1393  
     slip, 1247  
     steam, 1401  
     vacuum, size, 1290  
 Punching, effect on steel plates, 382, 414, 688  
 Purlins (Glossary, 1838), 998, 1838  
     channels, 1169  
     connections, 1153, 1169, 1170

**Purlins, design, 1144, 1169, 1170**

- I-beam, 1169
- oblique, stress, 573, 593
- spacing, 1003-1004, 1006
- steel, specifications, 1201, 1204
- supports, 1004, 1046, 1047
- weight, 1050, 1055
- wooden, 1003, 1144, 1153, 1169
- workshops, 771
- Z-bar, 1169

**Puzzolan cement, 236, 237****Pyramid, 38**

- center of gravity, 293
- frustum, 38
  - surface-area, 61
  - volume, 64
- surface-area, 61
- vertex, 38
- volume, 64

**Pyrometer, 1249, 1250****Quadrangular prismoid, 62****Quadrangular truss, 1032, 1033, 1091, 1094****Quadrant of circle, center of gravity, 293****Quadrilaterals, 36**

- center of gravity, 292-293

**Quantity system of estimating, 1635-1637****Quartz, 130**

- specific gravity and weight, 1507

**Quartzite, 132****Queen truss, 999-1004**

- example, of analysis, 1055, 1139
- graphic analysis, 1071
- wind-stresses, 1112-1116

**Quicklime, 1549****Quicksand, 136**

- excavations in, 137, 211
- foundation-beds in, 137, 141
- pockets, 137
- safe load on, 141

**Quilts, building, 1564-1568****Quoins (Glossary), 1839****Radial Brick Chimney, 1369-1373, 1377****Radiation, 1264-1271**

- versus hot-blast heating, 1324

**Radiators, 1264-1271**

- air-removal, 1285
- cast-iron, 1265-1267
- concealed, 1270
- connections, 1264, 1283
- direct, 1264, 1283
- direct-indirect, 1264, 1268
- hot-water, 1264, 1270
- indirect heating, 1264, 1299, 1300, 1356
- location, 1355
- specifications, 1360, 1362

**Radiators, indirect heating, symbol, 19**

- materials, 1264
- measurement, 1265
- pipe coil, 1267, 1269
- pressed-metal, 1264, 1265, 1267, 1268
- rating, 1265
- types, 1265-1270
- wall, 1268

**Radius of gyration, 333**

- areas, 334-338 (see, also, **Moment of inertia**)
- compound sections, 344
- definition, 333
- hollow-round sections, table, 348-349
- hollow-square sections, table, 348-350-351
- notation, 122
- steel-pipe columns, 472, 497-498
- structural shapes, 354-359, 362-371
  - double angles, 371, 372, 503
  - double channels, 373, 374, 499, 500
  - plates and angles, 344, 517-532
  - plates and channels, 533-554

**Rafters, 1003, 1046, 1836**

- bevel and length, 90
- details, 1150-1154
- hammer-beam truss, 1014-1016
- on steel purlins, 1169
- span, maximum, 740, 741, 745, 746
- stresses, 1140, 1141
- weight, 1050

**Rags, weight, 722****Rams, hydraulic, 1390****Random work (Glossary), 1839****Range-boilers, dimensions, 1642****Rankine's formula, cast-iron columns, 460-461**

- depth of keyseat, 308-309
- steel columns, 481, 484, 493-496

**Raymond concrete pile, 197****Reactions, beams, 322, 671****Reaming, steel, 382, 414, 423, 652****Reaumur thermometer, 1250****Reciprocals, 7, 8, 24****Rectangles, 37, 39**

- axis of moments, 335
- moment of inertia, 335, 346
- radius of gyration, 335
- section-modulus, 335

**Redwood, beams, loads, 640**

- deflection, 664
- fiber-stress, safe, 557
- columns, safe loads, 450, 452
- crushing-loads, with the grain, 449
- crushing strength, across the grain, 454
- shear, 647
- tension, safe stress, 376, 647
- unit stresses, 647, 650
- weight, 650

**Reflection, multiple (acoustics), 1487**

refraction of light, 1453-1456, 1577-1580  
 refrigeration, mechanical, 1684-1695  
 refrigerators, 1679-1683, 1691-1693  
 register-boxes, 1358  
 registers, air-velocity, 1357  
 furnace, 1317-1320  
 pressure-loss, 1338  
 in public buildings, 1355  
 size, 1358  
 specifications, 1360  
 symbol, 1350  
 registration of architects, 1768-1776  
 reinforced concrete (see, also, Concrete and Reinforcement), 906-997  
 adhesion (see bond, below)  
 aggregate, 241, 287, 908, 909, 945  
 beams, 924-941  
     bending moments, 935-936  
     compression-roads, 921-922, 941  
     diagonal tension, 921, 938  
 bond, 940  
     allowed stresses, 911, 912  
     tests, 919  
     use in design, 938  
 cantilever flat-slab system, 950  
 cast-iron column-connections, 945-946  
 cement used, 907  
 chimneys, 1373-1375  
 cinders, 242, 250, 909, 930  
     corrosion of steel, 818, 960-961  
 columns, 941-946, 969, 980  
     calculations, 976  
     fire-proofed, 958, 959  
     metal-cored, 944-945  
 compressive strength, 910-911  
 conductivity, 955  
 connections, 944-947  
 construction in general, 906-967  
 corrosion-protection, 960-962  
 cost, 250, 910, 1613, 1618  
 Cummings system, 923, 945  
 design of, 924-947  
 diagonal tension, 921, 938  
 electrolysis, 186  
 erection, 906, 962-963  
 factors of safety, 911  
 factory-construction, 968-997  
 fire tests, 956, 957, 960  
 Fire Underwriters' requirements, 958  
 fireproofing, 781, 811, 955, 957-958  
 flat-slab construction, 949  
 floors, 842-856, 924-940, 948-955  
     (see slabs, below)  
     load tests, 967  
     surface-finish, 239, 246, 965  
 footings, 186, 946-947, 978  
 forms, 245, 962, 964-965, 966  
     permanent centering, 852, 853  
 foundations, 186, 196, 946-947, 978  
 four-way system, 949, 950, 993-997

Reinforced concrete, gravel, 908  
     heat, effect of, 245, 827, 937, 955-959  
     Hennebique system, 919-920, 940  
     historical notes, 906  
     hollow-tile and concrete, 951-952  
     I beams, reinforced, 854  
     inspection, 965-966  
     joining new work to old, 965  
     Kahn system, 921, 940  
     metal-core columns, 944-945  
     materials used, 907-923  
     mill-construction, 948, 968-997  
     mixing, 963, 964  
     mixtures, 909-910, 945, 963, 964  
     modulus of elasticity, 912, 924, 934, 935, 956  
     molds, 962, 963, 964-965, 966  
         permanent centering, 852, 853  
     Mushroom system, 950, 993-997  
     piers, 978  
     piles, 196-200, 945  
     pouring and ramming, 964, 966  
     proportions of materials, 240, 247-249, 910, 1712  
     protected from fire, 958  
     reinforcements (see Reinforcement)  
     retaining-walls, 261-263  
     roofs, 866-872, 968, 976  
     sand, 908  
     sectional systems, 853-854  
     separately moulded system, 953-955  
     shear, 912, 921, 937-940  
     shrinkage-stresses, 937  
     skeleton construction, 948  
     slabs (see, also, floors, above)  
         bending moments, 932, 936, 984, 987  
         cost, 250  
         design, example, 971  
         diagrams for strength, 984-987  
         flat-slab construction, 845, 846, 949-952  
         girderless floors, 968, 993-997  
         loads, safe, 984-987  
         rectangular, formulas, 932  
         separately molded, 953  
         strength, 932, 971, 984-987  
         in T-beam design, 934, 975  
     stairs, 900, 947, 982, 983  
     stirrups, 921-923, 939, 940, 973  
     stone, 908-909, 935  
     superintendence, 965-966  
     System M, 948-949  
     T beams, 932, 933, 937, 940, 971, 975, 988-991  
     temperature-stresses, 937  
     tension-members, 913-915  
     tensional stress, 924  
     tests, adhesion, 920  
         corrosion, 961

**Reinforced concrete, tests, fire-resistance,** 955-960  
     hooped columns, 942  
     loads, 967  
     thickness of concrete, 958  
     tile-and-concrete floors, 952  
     tile-protection, 959  
     two-way tile system, 949-953  
     types of construction, 948-955, 968  
     unit system of reinforcement, 922-923  
     Vaughan system, 856  
     Waite's concrete I beam, 854  
     wall-piers, 978  
     walls, 946, 948, 968, 975-978  
     water for, 909  
     wet-concrete mixtures, 963-964  
     working stresses, 911-913, 935  
     wrought iron, 907

**Reinforcement, 913-924 (see, also, Reinforced concrete)**

adhesion (see Reinforced concrete, bond)

Akme system, 949-950

bars, 915-921

    area, 1514-1521

compression, 921, 922, 941

Corr-mesh, 853

corrosion, 960, 961

corrugated bars, 916

Cummings system, 923, 945

deformed bars, 915, 919

Diamond bar, 917

dovetailed corrugated sheets, 850

expanded metal, 846, 883, 884, 919

Ferroinclave, 850-851

grades used, 913

Havermeyer bar, 917

Hennebique system, 919, 920, 940

hollow-tile and reinforced, 951

Hy-rib, 853

Kahn bar, 921, 940

Kalman bar, 918

lock-woven fabric, 849

loop truss, 923

Luten truss, 923

metal fabric, welded, 848

metal lath, 882-888, 922

Monotype, 918

multiplex, Berger's, 852

Ovoid bar, 918

percentage, 925, 937

permanent centering, 852, 853

Ransome bar, 915

Rib-bar, 917-918

rib-metal, 847-848

rib-truss, 853

rivet-grip bar, 919

rods, number, 937-938

rust, 186

Self-Centering, Duplex, 853

Self-Sentering, 853, 885-886

**Reinforcement, spacing, 922, 938**

    specifications, 904

    System M, 948

    triangle mesh, 850

    types, 843, 855, 880-890, 913-913

    unit system, 922-923

    welded-metal fabric, 848

    wire-fabric, 850

    wire-mesh, 919

    working stresses, 912, 913

    wrought-iron, 907

**Repose, slopes and angles, 253, 254, 256**

**Residences (see, also, Dwellings)**

    air-change, 1353

    heat-temperature, 1256

    non-fireproof, height, 813

    steam-heating specifications, 1361-1363

**Resisting moment, 333, 556**

**Resolution, forces, 288, 289, 1065**

**Rest, definition, 124**

**Resultant, force, 288, 289**

**Retaining-walls, 252-264**

    angles of friction, 253

    angles of repose, 256, 259-260

    batter, 259-260

    breast walls, 262-263

    cleavage-plane, 257-258

    coefficients of friction, 253

    construction, details, 259

    footings, 261-262

    friction, theorem of, 252

        angles of, 253

    grouted, 269

    internal stresses, 257

    pressures on, 257

    principles of, 252-255

    proportions, 261

    reinforced-concrete, 261-264

    slopes of repose, 256

    thickness, 260

    theories, 255

    vault-walls, 263-264

**Reverberation, acoustics, 1487**

**Rhomboid, 37**

**Rhombus, 37**

**Rib-bar, 918**

**Rib-metal, properties, 847-848**

**Rib-stud, plaster partitions, 881-883**

**Rib-truss, 853**

**Richmond building code, loads on**

    foundation-beds, 143

    office-buildings, assumed loads, 151

**Risers, stairs, rules, 1648**

    table, 1646-1647

**River-deposits, 133**

**Rivet, rivets (see, also, Riveting), 413**

    American Bridge Co., standard table, 420

    annealing, 382, 414

**Rivet, arrangement, 414, 415**  
 base-price, 1205  
 bearing value, 415, 416  
   area used, 416  
   Boston law, 418  
   by proportion, 692  
   column-connections, 469  
   Cambria, 418  
   Carnegie, 418  
   determination of, 415  
   field-rivets, 618  
   formula for, 416  
   live loads, 415  
   New York law, 418  
   riveted girders, table, 418  
   shop-rivets, 618  
   steel-beam connections, table, 419  
   steel trusses, table, 419  
   tables, 418, 419  
   wrought iron, 415  
   wrought iron, table, 418  
 bending-stress, 422, 423  
 bridge-work, 423  
 butt-joints, comparative efficiency, 421  
 chain, definition, 421  
 clearance, 414  
 columns, number of rows, diagrams, 467  
 conventional sign, 417  
 cost, base-price for rivets, 1205  
   punching holes, 1204  
 cover-plates, diagrams, 421, 422  
 diameters, plate and box girders, 682  
   standard connections, 617  
 distance from edge of plate, 682  
 drift-pins, 414, 682  
 driving-tools, 1203  
 failure of joints, 415  
 field, 423  
   lengths, table, 420  
   shearing value, 618  
   symbols, 617  
   weight, percentage added, 617  
 grips, table, 420  
 heads, 413, 414, 682  
   diagram, 416  
   eccentric, 414  
 holes, 413  
   alinement, 414  
   allowance for errors, 615  
   deductions, plate girders, tables, 702, 703, 704  
   deductions, plates and angles, tables, 399, 400, 702  
   deductions, from various authorities, 603, 604  
   diameter, 414, 415, 682  
   punching, 382, 414, 415, 1203  
   flange-angles, 687, 691  
   spacing, specifications, 1202

**Rivet, in plate girders, diagram, 615**  
 in stiffeners, 687  
 initial slip, 422  
 inspection, 414  
 lap-joints, diagram, 421  
 lengths, 413  
   field-rivets, table, 420  
 loose, 414  
 machine-driven, 414, 683  
 material of, 413  
 number of, column-connections, 469  
   equation for determining, 687  
   examples, 699, 700, 701  
   joints, 421, 422  
   plate girders, 691, 696, 701  
   for double shear, 416  
   standard connections, 616, 617  
 pitch (see spacing)  
 proportions, diagrams, 416  
 punching, diameter of die, 414, 682  
 reaming, 382, 414, 423, 682  
 shanks, diagram, 416  
 shearing value, 411, 413, 416, 692  
   area used, 416  
   by proportion, 692  
   column-connections, 469  
   determination of, 415  
   double shear, 411, 416  
   field-rivets, 618  
   live loads, 415  
   shop-rivets, 618  
   single shear, 411, 416  
   steel-beam connections, table, 419  
   steel trusses, table, 419  
   tables, 418, 419  
   wrought iron, 415  
 shop, 414, 417, 423  
   bearing value, 618  
   shearing value, 618  
 signs, conventional diagram, 417  
 sizes, determination of, 415, 1201  
   diagrams, 416  
   for plate-thicknesses, 415  
   shop-practice, 415  
   table, 420  
 spacing, 414  
   cover-plates of plate girders, 683  
   flange-angle, examples, 696, 697, 699-701  
   plate girder, example, 691, 692, 693  
   specifications, 1202  
   standard connections, 617  
   steel columns, 469  
 staggering, 414  
 standard connections, 616, 617, 618  
 symbols, 417  
 taper-rivets, 423  
 weights, standard connections, 617  
   steel rivets, 1528  
 working stresses, 415, 416, 423, 618, 1138, 1200

**Rivet, working stresses, column-connections, 469**  
 compared, 692  
 for bridges, 423  
 standard connections, table, 618

**Riveting (see, also, Rivets), 413-423**  
 definitions, 413, 421  
 field, compared with shop, 423  
 machines, 414  
 shop, 414, 415, 423  
 single, definition, 421

**Robertson Process Metal, 819**

**Rock, angle of repose, 256**  
 argillaceous, 131, 132  
 boulders, 134, 136  
 classification, 131-132, 134  
 composition, 130  
 disintegration, 133, 134  
 excavation, cost, 1537  
 foundation-bed, 130-132, 134, 135, 141  
 loads, 143  
 igneous, 131  
 inclined strata, 146  
 ledge, 134, 135  
 loose, 134, 135  
 metamorphic, 131, 132  
 plutonic, 131, 132  
 rotten, 134, 135, 256  
 safe loads, 141, 143  
 sedimentary, 131  
 siliceous, 131  
 testing, 145  
 under caisson-piers, 214  
 weight, loose, 256

**Rococo radiator, 1265**

**Rods and bars, steel, 385-398**  
 forked-loop, 387  
 looped, 386, 396  
 safe loads, 388-392  
 screw-ends, 387, 393-398  
 weights, 1514-1521

**Roebbling's Sons, wire-gauge, 400**  
 standard wire lath, 887

**Roman long measures, 34**  
 weight, 34

**Roof, roofs (see, also, Roofing and Roof-trusses)**  
 cost, 777, 810  
 conductors, 1658  
 dampness, 800  
 fire-proof, 866-872  
 fire-protected, 801, 1597  
 flooding, 801  
 gutters, 1658  
 heat-transmission, 1259  
 leaks, 800  
 loads, 740, 741, 745, 746, 1048-1057, 1196  
 mansard, 870-871  
 mill-construction, 760 (see **Mill-construction**)

**Roof, mill-construction, cost, 810**  
 example, 769  
 materials (see **Roofing, materials**)  
 timbers and framing, 765  
 walls, 768  
 nozzles, 801  
 pitch or slope, 867, 869, 1016, 1017  
 rafters (see **Rafters**)  
 reinforced-concrete, 866-872, 964, 977  
 saw-tooth, 772-777  
 trusses (see **Roof-trusses**)

**Roof-loads (see Loads)**

**Roof-trusses, 998-1170 (see, also, Rafters and Roofing)**  
 anchoring, 1150-1152, 1168  
 arched trusses, 1035-1043  
 stresses in, 1118-1123  
 wooden, 1020-1024  
 arches, trussed, 1121-1133  
 bending moments, moving load, 1135  
 bolt-connections, 429-439, 1115  
 Bow's notation, 1066  
 bowstring, 1035, 1094, 1095  
 cambered, 1011-1019, 1026, 1027, 1033-1035 (see, also, **Scissors truss**)  
 stresses in, 1056, 1060, 1061, 1079, 1086, 1093-1095  
 cantilever, 1043-1045, 1105-1108  
 car-barn, 1018, 1056, 1209  
 cost, 1208  
 counterbracing, 1000-1006, 1034, 1035  
 crane, 1069  
 diagrams, lettering, 1066  
 fan (see **Fan truss**)  
 Fink (see **Fink truss**)  
 fireproofing for, 860, 861  
 fixed arch, 1043, 1131  
 fixed and free ends, wind-stress, 1109, 1110  
 flat roofs, example, 1057, 1121  
 stresses, graphics, 1075, 1077, 1084, 1092, 1102-1104  
 types, 1030-1034  
 forces acting, 1066, 1070  
 French, 1026  
 hammer-beam (see **Hammer-beam truss**)  
 hinged, 1038-1043, 1121-1130  
 hook-splice, 1155  
 horizontal chords, 1004  
 horizontal deflection, 1085-1087, 1119, 1129  
 horizontal thrust, 1085-1088, 1129-1130  
 Howe (see **Howe truss**)  
 influence-lines, 1134-1137  
 joints, steel, 423-429, 1160-1170  
 wooden, 412, 413, 429-439, 1160



**Roof-trusses, king-post, 998, 1000**  
   king-rod, 998, 1153, 1154  
   stresses, 1048, 1069, 1099  
**knee-braces, 1025-1027, 1116-1118,**  
   1164, 1168  
**lateral bracing, 1033**  
**lattice, 1008-1010, 1089-1091**  
**loads (see Loads)**  
**members, proportioning, 1139**  
**notation, Bow's, 1066**  
**pin-connections, 423-429**  
   use, 1030, 1032, 1034  
**Pratt, 1026, 1031, 1032, 1077**  
**putlins (see Putlins)**  
**quadrangular, 1032, 1033, 1091-1094**  
**queen, 999-1004, 1139, 1140**  
   load-distribution, 1055  
   stresses, 1071, 1112-1116  
**reactions, 1066**  
   unsymmetrical loads, 1096, 1098  
   wind-loads, 1110  
**roller-bearing, wind-stresses, 1111,**  
   1118  
**sag-tie, 1015**  
**saw-tooth roofs, 772-777**  
**scissors (see Scissors trusses)**  
**shed, 1025**  
**spacing, 1047, 1048, 1051**  
**splicing in wooden, 1155**  
**steel, 1025-1045, 1144-1149, 1160-**  
   1170  
   cost, 1206  
   saw-tooth roofs, 772-777  
   secondary stresses, 1137  
   shop-drawings, 1162, 1207  
   specifications, 1201  
   weight, 1050, 1051, 1209  
**steel columns in trusses, 1139**  
**stresses, 1046-1137, 1138**  
   influence-lines, 1134-1137  
   coefficients, 1058-1065  
   graphics, 1065-1137  
   unit, timber, 1138  
   wind-load, 1118, 1123-1128  
**suspended, 1032, 1089**  
**types, 998-1045**  
**unsymmetrical, 1096-1098, 1100-**  
   1107  
   loads, 1096, 1098  
**wall-plates, 1150-1152, 1156, 1158,**  
   1165, 1168  
**Warren (see Warren truss)**  
**weight, 1050-1051**  
**white-pine, 1138**  
**wooden, 439**  
   bolted connections, 429-439  
   cantilever, 1044  
   design, 1138-1144  
   joints, 1149-1160  
   types, 998-1024  
   unit stresses, 1138

**Roof-trusses, wooden, washers, 1157-**  
   1160  
   weight, 1050-1057  
**Roofing, 1581-1604 (see, also, Roofs**  
   **and Roof-trusses)**  
   asbestos, corrugated sheathing, 819  
   shingles, 819  
   asphalt-gravel, 871, 1598  
   asphaltic materials, 1608  
   Barrett, 1595  
   Bonanza tile, 868, 869  
   book-tile, 868  
   canvas, 801  
   cement tiles, 868, 869  
   copper, 1049, 1604  
   corrugated iron, 1046, 1049, 1599-  
     1604  
   dampness, 800  
   felt, weight, 1049  
   flat roofs, 866, 1046  
   galvanized, 1604  
   gravel, 871, 1027, 1595-1599  
     fire-resistance, 1597  
   incombustible, defined, 1853  
   leaks, 800  
   materials, 800, 1046, 1567, 1581-1604,  
     1608  
     fire-resistant, 819, 817, 1597  
     weight, 1049  
   mill-construction, 760, 800  
   pitched roofs, 867-869, 1046  
   prepared, 1599  
   ready, 1027, 1046, 1049, 1599  
   reinforced-cement tiles, 867, 868  
   sheathing, 1049, 1055, 1567  
     paper, 1567  
   shingles, 1046, 1581  
   slag, 801, 1595-1599  
   slate, 871, 1046, 1049, 1582-1586  
   steel sheets, 1599-1604  
     asbestos-covered, 819  
   tar-and-gravel, 871, 1027  
   tile, 866, 867, 871, 1586  
   tin, 801, 1046, 1049, 1588, 1595 (see  
     also, Tin, roofing)  
   warehouses, 800  
**Roofs, heat-transmission, 1259**  
**Room, fresh air for furnace, 1322**  
**Rope, for bells, 1726**  
   cotton, hemp and Manila, 406-408  
   weight, 723  
   wire, 404-406  
**Ropes and cables, measures, 25**  
**Rosin, weight, 723**  
**Rotary converter, 1463**  
**Rotten rock, 134, 135, 256**  
**Royalties, payments, 1759**  
**Round rods, safe loads, 388**  
**Rubble (Glossary), 1842**  
**Rubblework, 266, 441, 1538, 1842**  
   cement, 235

- Rupture, Modulus of** (see **Modulus of rupture**)  
**Rust, reinforced concrete footings,** 186  
**Safe load, definition,** 125  
**Safety, factor of, definition,** 126, 375, 556  
     appliances, elevators, 1664, 1669, 1672  
**St. John the Divine, Cathedral, founda-**  
     **tions,** 251  
**St. Louis building code, loads on foun-**  
     **dation-beds,** 143  
     loads on masonry, 267  
     office-buildings, assumed loads, 151  
     thickness of walls, 230-232  
**St. Paul building code, loads on foun-**  
     **dation-beds,** 143  
     office-buildings, assumed loads, 151  
**Saints, symbols,** 1727  
**San Francisco building code, loads on**  
     **foundation-beds,** 143  
     thickness of walls, 231  
**San Francisco fire, tests of materials,**  
     957  
**Sand, 134, 1553**  
     angle of repose, 256  
     beds of, 134  
     chemical analysis, 138  
     classification and composition, 136  
     cost, 249  
     foundation-beds on, 141  
     in reinforced concrete, 908  
     Ottawa, 235, 241, 908  
     proportions, in concrete, 241-243, 247-  
         251, 908  
     in lime mortar, 1553  
     quicksand, 136, 137, 141, 211  
     safe loads on, 141, 143  
     screening, 1553  
     sieve tests, 138, 241  
     source of, 130, 1553  
     specific gravity, 1507  
     voids, 247-249  
     weight, 248, 256, 1507, 1537, 1554  
**Sand-bars, formation of,** 133  
**Sand finish, plastering,** 1555  
**Sandstone, 131**  
     beams, coefficients for, 628  
     fiber-stresses, 557  
     tensional strength, 282  
     bituminous, paving, 1609  
     crushing strength, 266, 270, 279-282  
     fire-resistance, 814  
     loads, safe, 266, 267, 279, 282  
     modulus, of elasticity, 282  
     of rupture, 282  
     shearing strength, 282  
     specific gravity, 282, 1507, 1508  
     weight, 282, 1507, 1508  
**Sash, hollow-metal, 897**  
     Sash, weights for, 1649, 1651  
     Sash-balances, 1652  
     Sash-chains, 1650  
     Sash-cords, 1649  
     Sash-pulleys, 1649  
     Sash-ribbons, 1650  
     Sash-weights, 1649, 1651  
     Saw-tooth roofs, 772-777  
     Schedule of charges, architects, 1721  
         1731  
     Schists, 132  
     Schlierenmethode, photographing re-  
         disturbances, 1495-1499  
     Scholarships, architectural, 1779-1788  
     School-buildings, 1644-1648  
         cost, 1613, 1614, 1616  
         doors, 1648  
         flagpoles, 1644  
         floor-joists, 717  
         spans, 737, 742  
         floor-loads, live, 719, 720, 1198  
         heating-temperature, 1256  
         hot-blast heating, 1324  
         non-fire-proof, height, 813  
         size of rooms, 717  
         stairs, 1648  
         ventilation, 1353  
         water-closets, 1641  
     Schoolrooms, blackboards, 1644, 1645  
         desks, 1645  
         dimensions of, 717, 1644  
         floor-loads, 719, 720, 1198  
         heating, 1256, 1324  
         lighting, 1451  
         seats, 1645  
         ventilation, 1349, 1353  
     Schools, architectural, 1769, 1775, 1776  
         1779-1788  
     Scissors trusses, 1004, 1010-1013, 1053  
         1056  
         stresses, 1081-1087  
         wall-joint, 1156  
     Screen (Glossary), 1843  
     Screw-ends, 386-398  
     Screw-jacks, 215, 216, 221  
     Screws, 1535, 1536  
         lag, 1157, 1535  
         threads, standard, 1525  
     Scripture measures and weights, 34  
     Scuppers, 767  
     Seat-baths, dimensions, 1641  
     Seating capacity, 1653-1656  
     Seating-space, churches, 1653, 1654  
         schools, 1645  
         theaters, 1653-1656  
     Seats, dimensions of, 1638, 1641  
         1653  
     Seattle building code, masonry work,  
         287  
     Secants, table of natural, 116  
     Section-factor (see **Section-modulus**)

- Section-modulus**, 333  
   elementary sections, 334-338  
   structural shapes, 354-359, 362-369  
**Sector of circle**, 38  
   center of gravity, 293  
**Sedimentary rocks**, 131  
**Segment of circle**, 38  
   center of gravity, 293  
**Segmental arch**, 305, 307, 321  
**Selenite**, 131  
**Semicircle**, center of gravity, 293  
**Separators for steel beams**, 612-614, 1202  
**Services**, architects, 1731  
**Sewage**, ejectment of, 1422  
**Sewer-pipes**, 1407-1409, 1429, 1420, 1422  
**Sewers**, as affecting foundations, 147  
   house, 1409  
**Hexagon**, 37  
**Shaft**, elevator, 1659, 1660, 1666, 1675, 1676  
   fire-proof, 889, 890  
   for mills, 764, 768  
**Shafting**, loads, 1197  
   machinery, 1720-1722  
**Shale**, 132, 143  
   bricks, 275  
   specific gravity and weight, 1508  
**Shear**, 128, 411  
   beams (see **Beams**)  
   bolts (see **Bolts**)  
   buildings, wind-pressure, 1176-1183  
   cast iron, 412  
   double, 411  
   failures, illustrations, 170, 171, 411, 412  
   girders (see **Beams**)  
   horizontal, wooden beams, 412, 635  
   pins, 423, 424  
   plate girders, 684-687, 690, 691, 696, 698, 703  
   reinforced-concrete, 912, 921, 937-940  
   rivets (see **Rivets**)  
   single, 411  
   steel, 382, 412, 567, 569, 1132  
     specifications, 1203  
   vertical, beams, 411, 565, 567  
     diagrams, 685, 686, 690, 698  
     wind-bracing, 1176-1183  
   web-plates, in plate girders, 703  
   wind-bracing, 1176-1183  
   woods, 412, 647-651, 1138  
**hearing**, effect on steel, 382, 414, 688  
**heathing**, asbestos corrugated, 819  
   mill-construction, 759  
   papers, 1564-1568  
   roof, weight, 1049  
   wooden, 1049, 1563  
**heathing-quilt**, 1564-1568  
**Sheet lath**, 886  
**Sheet, metal**, 402, 886, 1510, 1511, 1599  
   tile, 1587  
**Sheet-piling**, 200-209  
**Sheet iron and steel**, asbestos-covered, 819  
   base-price, 1205  
   ceiling, 1604  
   corrugated, 1599-1604  
   galvanized, 1604  
   gauges, 402, 1510, 1600  
   roofing, 1599-1604  
   siding, 1603  
**Shelf-angle**, beam-framing, 787-790  
**Shelf-hangers**, 752, 788, 790  
**Shingles**, 1581  
   asbestos, 819  
   dimensions, 1582  
   nails required, 1581, 1582  
   sizes, 1581  
   staining, 1570  
   tin, 1046, 1049  
   weight, 1046, 1049, 1581  
   wooden, 1046, 1049, 1570, 1581  
**Shop drawings**, 1754  
**Shops**, hot-blast heating, 1324  
**Shoring**, excavations, 214-222  
**Shot-drills**, foundation-bed testing, 145  
**Shutters**, fire, 759, 778, 801, 901-902  
**Sideboards**, dimensions, 1638, 1640  
**Sidewalks**, flagstones, 1539  
   granite curbing, 1539  
   vault-walls, 263-264  
**Siding**, beveled and drop, wooden, 1563  
   corrugated metal, 1603  
**Silica minerals**, 130  
**Silicates**, 130  
**Sills**, stone, 1539  
**Silt**, 139  
**Silver**, specific gravity and weight, 1508  
**Simplex concrete pile method**, 197  
**Sines**, table of natural, 95  
**Sinks**, 1412, 1641  
**Sirocco**, fans, 1341, 1344  
**Skeleton construction**, 234, 948, 1171  
**Skewback**, arch, 305, 307  
   floor-arches, 834-835  
   vaults, 1232  
**Skylights**, glass for, 1580  
   mills and warehouses, 765  
   saw-tooth, 769, 772-777  
   standard, defined, 1854  
   weight, 1049  
**Sky-signs**, wind load, 1199  
**Slabs**, reinforced-concrete (see **Reinforced concrete**)  
**Slag**, in cement, 236, 237  
   roofing, 801, 1595-1599  
**Slag cements**, characteristics, 236, 237, 238  
**Slag concrete**, fire-resistance, 817

**Slate, 132, 1582**

beams, coefficients for, 628

safe fiber-stress, 557

cost, 1046, 1585

crushing strength, 282

flooring, 1606

grading of, 1583

laying, 1583

Old English method, 1584

measurement, 1584

modulus of elasticity, 282

modulus of rupture, 282

nails required, 1585

punching, 1583

roofs, 871, 1046, 1049, 1582-1586

sizes, 1583

specific gravity, 282, 1508

strength, 282, 537

thickness, 1583

tile, 1606

weight, 282, 1049, 1508, 1585

**Sleeve-nuts, 386, 387, 397****Slenderness-ratio, columns, 448****Slip, in pump action, 1247****Slop-sinks, dimensions of, 1641****Slope, of roofs, 867, 869, 1046, 1053  
of repose, 256****Slow-burning construction (see MHL-  
construction, slow-burning)****Smoke-pipe, 1362****Snow-loads, 1049, 1052-1057****Soapstone, 131****Societies, architectural, 1788-1795****Sofas, dimensions, 1640****Soffit, arch, 305****Softwoods, ultimate unit stresses, 649-  
651****Soil, 132**

angle of repose, 256

foundation-beds, 135-148, 980

weight of loose, 256

**Soil-pipes, 1407, 1410, 1427****Solids, mensuration of, 61****Sound (see Acoustics)****Soundproofing, partitions, 891****South Carolina, registration law, 1779****Span, arch, 305**

beams, definition, 555

wooden joists, 736-746

**Spandrels, arch, 305****Specifications, cast iron, 379**column-connections, cast-iron, 457,  
458

electric wiring, 1482

elevator-installation, 1663-1664

fire-shutters, tinned, 901-902

furnace-heating, 1357-1359

gravel roofing, 1595-1599

hot-water heating, 1359

hydrated lime, 1551

lime, 1549

**Specifications, paint, fire-proof, for**

plate girders, 682

plumbing-fixtures, 1640

Portland cement, 236, 907

reinforcing-steel, 914

roofing-tiles, 1586

slag roofing, 1595-1599

standard, A.I.A., 1752-1764

steam-heating, 1361

steel, in reinforced concrete, 914

structural, 383, 1194-1204

tile roofing, 1586

wiring, electric work, 1482

wooden-pile foundations, 193

wrought iron, 377

**Specific gravity, 1500-1508****Specific heat, 1250, 1684****Specific volume, gases, 1256****Spheres, 38, 60, 64****Spheroids, 60, 65****Spider, domes, 1222****Spikes, cut steel, 1532**

steel-wire, 1533

**Spinning-mills, cost, 805****Spring-line, arch, 305****Spring-needles, 221****Springers, arch, 305****Sprinklers, automatic, 801, 903-905**

framing to accommodate, 777

mills, 759, 768

tanks, 779

**Spruce, beams, coefficients for, 628**

deflection, 664

distributed loads, safe, 639

fiber-stress, 557, 647, 648

columns, safe loads, 451

crushing-loads, with the grain, 449

crushing strength, across the grain,  
454

modulus of elasticity, 647, 664

shearing strength, 412, 647, 648

specific gravity, 1508

stiffness, 664

tension, 376, 647, 648

unit stresses, 376, 412, 647, 648, 657

weight, 650, 1508, 1558

**Square, squares, 37, 39**

hollow, moment of inertia, 335

measures, 27

moment of inertia, 334

radius of gyration, 334

section-modulus, 334

tables of, 8-24

**Square roots, 3**

tables, 8-24

**Stability of structures, definition, 123****Stack, boiler, 1283**

furnace, 1312, 1317, 1322, 1358

steel, 1376

anchor-belts, 1377

tall buildings, 1283, 1368

**Staff**, 1558  
**Stainless cements**, 238  
**Stairs**, dimensions, 1646, 1647, 1648  
     Ferrocement foundation, 900  
     fire-proof, 899-900, 947, 983  
     hand-rail, 1648  
     hollow-tile steps, 899, 904  
     mill-construction, 759, 810  
     tower, 764, 768, 778, 779  
     reinforced-concrete, 900, 947, 983  
**risers**, 1648  
     table, 1646, 1647  
**school-houses**, 1648  
**towers** for, 764, 768, 778, 779  
**treads**, 899, 1648  
     table, 1646, 1647  
**airways**, loads, 1198  
     protection, fire, 764, 765, 778, 779  
**landpipes**, 768, 801, 905  
**ates**, registration of architects, 1768, 1777  
**statistics**, definition, 124  
**atus**, architects, 1728, 1754  
**eam**, 1251-1254  
     consumption, engines, 1247  
     heating, 1264, 1283-1302 (see **Heating**, steam)  
     saturated, properties, 1253  
**eam-cells**, heating water by, 1344  
**eam-heating** (see **Heating**)  
**eel**, adhesion to concrete, 912, 919, 920, 938, 940  
**bars**, 385-398  
     areas, etc., 1514-1521  
     safe loads, 388-392  
     weight, 1514-1521  
     base-price, 1204, 1210-1212  
**beams** (see **Beams**)  
**Bessemer process**, 380  
**branding**, 385  
**carbon-content**, 381  
**chemical properties**, 383  
**chimneys**, 1376  
**coefficient of expansion**, 382  
**cold-bend test**, 378, 384, 385, 914  
**columns** (see **Columns**)  
**compressive strength**, 449  
**corrosion in concrete**, 960-962  
**corrugated**, base-price, 1205  
     weight, 1600, 1603  
     cost, 1204-1212  
     defined, 380  
     elastic behavior, 382  
     elastic limit, 381, 913  
     elongation, 381, 384, 913  
     eye-bars, 386, 595  
     finished material, 384  
     fire-resistance, 819  
     form of test-specimen, 384  
     manufacture, 380, 383  
     merchant, cost, 1210

**Steel**, modulus of elasticity, 381, 912, 934  
     open-hearth process, 380  
     plates, 384, 385, 1204  
     phosphorus-content, 381, 383  
     properties, chemical and physical, 383  
     punching, effect on plates, 382, 414, 688  
     reinforcing (see **Reinforcement**)  
     roof-trusses (see **Roof-trusses**)  
     rope, 404-406  
     rupture-stress, 381  
     shearing, 382, 412, 567, 569, 1138  
     sheet, 1599-1604  
         asbestos-covered, 819  
         base-price, 1205  
         corrugated, 1205, 1599-1604  
         gauges, 402, 1510  
         specifications, 383  
         specimens for tests, 383, 384, 407  
         strength, 407, 914  
         carbon and phosphorus, effect, 381  
         specification, 383  
         ultimate, 382  
         wire, 401, 406  
         working, 376, 412, 557, 1138, 1199  
     stress-strain diagram, 382  
     stresses (see **strength**)  
     structural (see **Structural steel**)  
     tests, 383-385, 1195  
     thickness, corrosive agents, 1202  
     weight, 382, 1510-1521  
         estimating, rule for, 1521  
         sheets, 1510, 1511  
         variation in, 385  
     wire, 400-406, 1512  
         weight, 1512  
     yield-point, 381, 383, 912, 913  
**Steel-pipe columns**, 469-474, 488  
     safe loads, 488, 497, 498  
**Steelwork**, 1194-1206  
     bolted connections, 1204, 1206  
     buildings, weight, 1207-1209  
     cost-data, 1204-1212  
     cut to length, 1206  
     design, 1201  
     drafting, cost, 1206  
     erection, 1203, 1206  
     fire-protection, 468, 760, 780, 822-826  
     foundations, 1203  
     freight-rates, 1205  
     inspection, 1203, 1205  
     mill-buildings, 786, 788, 1210  
     painting, 1203, 1206, 1572, 1573  
     specifications, 383, 1194-1204  
     stresses, 618, 1138, 1199  
     weight, estimates, 1207-1210  
     workmanship, 1202  
**Steps**, hollow-tile, 899  
     stone, 1539

- Stevedore-rope**, 407
- Stiffeners**, girder-webs, 681, 686, 691, 921-923, 939, 940, 973
- Stiffness**, definition, 125
- Stirrups**, reinforced-concrete beams, 921-923, 939, 940, 973  
wooden beams, 750, 754-757, 787-794
- Stone** (see, also, **Stonework** and each kind of stone)  
angle of friction, 253  
beams, 628  
fiber-stress, 557  
building-data, 282  
caps, 1539  
coefficient of friction, 253  
concrete, 908  
coping, 1539  
cost, 1538, 1613  
crushed, cost, 249  
crushing height, 269  
crushing strength, 279-282  
fire-resistance, 814  
footings, 223, 224  
lintels, 1539  
masonry, 265-270, 1538  
modulus of elasticity, 282, 283  
piers, 270  
quantities in concrete, 247-249  
sills, 1539  
steps, 1539  
strength, 265-270, 279-282  
weights, 282
- Stonework** (see, also, **Masonry**, **Stone**, **Walls**, etc.)  
ashlar, 441, 1538  
bluestone, cut, 1539  
coefficients of friction, 253  
cost, data for estimating, 1538  
crushing strength, 265  
cut-work, 1538  
data, 1538-1539  
hammer-dressed, 1538  
loads, safe, 266  
measurement, 1538  
rubble, 441, 1538  
sidewalks, 1539
- Storehouse-construction**, 765-788
- Straight-line formula**, cast-iron columns, 460-461  
depth of keystone, 308-309  
steel columns, 481-482, 493-496
- Strain**, definition, 125
- Strength**, beams, law of variation, 565  
breaking, 556  
coefficient of, 556, 628  
compressive, 448  
definition, 125  
elastic, 126  
elongation-relation, steel, 381  
flexural, definition, 125, 556, 638
- Strength**, of materials, definition, 125  
shearing, 411, 635, 657, 667  
tensile, 375  
ultimate, definitions, 125, 375, 411, 448  
working, definition, 125, 375
- Strength of materials** (see name of material in question)  
definition, 125
- Stress**, stresses, 125, 254 (see, also, materials in question)  
bearing, 415  
bending, 265, 628, 647  
combined, 128, 480, 572, 1114  
compressive, 127, 647  
constants, wooden beams, 628  
diagrams and formulas, 1065-1137  
distribution of, 254  
elastic limit, 126, 381  
fiber, 126, 325, 555, 556  
flexural, 126, 305, 333, 555  
intensity, definitions, 125, 254, 375  
modulus of rupture, 126  
notation, 122  
resultant, 254, 1183  
reversal of, 1104  
rupture, 381  
secondary, 1137  
shearing, 128, 411, 415, 647  
horizontal, 635, 687  
shrinkage, in concrete, 937  
stress-strain diagram, 382  
temperature, in concrete, 937  
trusses, 1128  
tensional, 127, 375, 415, 647  
torsion, 128  
transverse, 265, 480, 555, 628  
ultimate, 375  
uniform, 254  
unit, definitions, 125, 126, 375, 1173  
varying, 254  
wind, trusses, 1109-1118, 1123-1128  
wind-bracing, 1176-1183  
working, definitions, 125, 375  
yield-point, 381
- Stress-strain diagram**, 382
- String-course** (Glossary), 1846
- Structural shapes**, 332-374 (see **Angles**, **Channels**, **I beams**, etc.)
- Structural steel** (see **Steelwork**)
- Structures**, definition, 124  
domical, 1213-1231  
large, heating, 1324  
theory of, 124  
vaulted, 1231-1243
- Struts**, angle, tables, 488, 501-503  
as beams, 571, 572  
bracing, formulas, 495  
cast-iron, trussed girders, 661  
channel, loads, table, 499-500  
compression-formulas, 496

**Struts, double-steel-angle, loads, 503**  
     eccentric loads, 453, 489  
     I-beam, strength of, 489  
     in trusses, steel, 480  
     loads, 1201  
         tables, 488, 493-495  
     single-steel-angle, loads, 501  
     trusses, 998  
     wood, 633  
         strength of, 448-452  
         trussed girders, 661  
**Subcontractor's agreement, 1765**  
**Subcontracts, 1761**  
**Sugar, specific gravity, 1508**  
     weight of, 723, 1508  
**Sulphur, anchoring-bolts, 240**  
**Superintendent, architects, 1728**  
**Surcharges, 306**  
**Surface, center of gravity, 292**  
     finish, concrete, 246, 965, 1555  
     measures, 27  
         metric, 31  
**Sway-rods, wind-bracing, 1176, 1181**  
**Wedge-bolts, steel columns, 619**  
**Switches, electric lighting, 1478, 1479, 1481**  
**Ycamore, specific gravity, 1508**  
     weight, 1508, 1558  
**Zenite, 131**  
     compression, 282  
     tension, 282  
**Symbols, Apostles and Saints, 1727**  
     electric wiring, 1476-1478, 1484  
     gas-piping, 1445  
     mathematical 122. 123  
     pipes and fittings, 1350  
     plumbing, 1424-1426  
**System of units, engineers', 1247**  
**Beams, reinforced concrete, diagrams**  
     for strength, 988-991  
     example, 971, 975  
     formulas, 933-934  
     reinforcement, 937, 940  
**Sections, steel, base-price, 1212**  
**Fire-proof ceilings, 872**  
**Girder flange, 682**  
     size and properties, 337, 368, 369, 565  
     strength, as beams, 591, 682  
**Tables, furniture, dimensions, 1638, 1639**  
**Tacks, wire, 1533, 1534**  
**Mail-beams, floors, 749**  
**Alc, 131**  
     specific gravity and weight, 1508  
**Ball buildings, stack, 1283, 1368**  
**Angents, 38**  
     tables of natural, 104  
**Tanks, capacity, 1404-1406**  
     construction, 1398-1402  
     expansion-tanks, 1307, 1360

**Tanks, frost-proofing pipes, 1400**  
     gravity-tanks, water, 779  
     heating, 1400  
     house-tanks, 1415  
     incrustation, 1429  
     materials, 1398  
     standard sizes, 1401  
     steel, 1402  
         wind-load, 1199  
     wooden, 1398  
**Telephones, automatic, 1707**  
**Telltale (Plumbing), 1400**  
**Temperature, absolute, 1250**  
     concrete, 244, 245  
     humidity-relation, 1352  
     inside, table, 1256  
     maintenance, heating buildings, 1256  
     outside, in U. S. table, 1257  
     roof-trusses affected by, 1128  
     United States, 1257  
**Tempering-coil, heating, 1328**  
**Tenement-house, defined, 1854**  
     floor loads, 719, 1198  
     specifications, 1200  
**Tension, 127, 375**  
     building materials, 376  
     members, steel, 385-387  
         safe loads, 388-392, 399  
     sign, 1065, 1068, 1072  
**Terms, architectural (Glossary), 1796-1850**  
     building codes, 1851-1855  
     building laws, 1851-1855  
     engineering, 124-129  
     technical, 1796-1855  
**Terra-cotta, beam-protection, 782**  
     book-tile, 867, 868  
     column-protection, 782, 822-826  
     composition, 276, 814  
     dense, 814, 816, 875  
     facing of walls, 269  
     fire-resistance, 234, 815, 816, 828, 874  
     floors, 828-840, 1604-1607  
     heat-transmission, 1258-1259  
     hollow walls, 233-234  
     ornamental, fire-resistance, 814  
         inside finish, 898-899  
         staircases, 899  
     partitions, 873-875, 889  
     piers, 276-278  
     porous, 815, 875  
     properties, 276  
     roof-construction, 866, 867, 871, 1586  
     semiporous, 815  
     sound-resistance, 889, 890  
     strength, 266, 276-278, 287, 815  
     tests, 276-278, 816, 873  
     truss-protection, 860  
     weight, 278

**Terrazzo flooring, 1607****Tests (see, also, materials in question)**

- brick piers, 272-278
  - bricks, 270, 281, 1542
  - cast iron, 380, 446, 819-820
  - cement, 236-237, 240, 907
  - chains, 408-410
  - column-coverings, 822-823
  - columns, cast-iron, 460, 823
    - steel, 822
    - steel-pipe, 472
    - wooden, 449
  - concrete, 283-287, 817, 911
  - eye-bars, 386
  - fire-proof floors, 827, 841, 844, 866
  - fire-proof partitions, 828, 873, 889
  - fire-proof wood, 820
  - floors, 720-721, 866, 967
  - foundation-beds, 141-146
  - joist-hangers, 756, 794
  - mortar, 283
  - nails, holding-power, 1531
  - pipe, water, 1388
  - plumbing, 1412
  - reinforced-concrete, adhesion, 919-920
    - corrosion, 961
    - elastic properties, 935
    - fire-resistance, 955-960
    - hooped columns, 942
    - loads on floors, 967
  - sash-cords and sash-chains, 1650
  - sound-absorption, 1486-1500
  - steel, 382-385
  - stone, 279-281
  - terra-cotta, 276, 278, 816, 873-874
  - wooden beams, built-up, 652-654
    - columns, 449
  - wrought iron, 377-379
- Theater-curtains, asbestos, 819**
- Theaters, chairs, 1653**
- defined, 1854
  - dimensions of, 1657
  - floor-loads, 719, 720, 1398
  - heating and ventilating layout, 1348, 1353
  - seating capacity, 1654-1656
  - seating-space, 1653
- Thermometers, thermometry, 1249**
- Threads of screws, standard, 1525**
- Thrusts, 305**
- Tie-beams, wooden, 430, 432, 434, 435, 633**
- built-up, 432
  - steel, stresses in, 572
- Tie-plates, steel, 1202**
- Tie-rods, for I beams, 619, 865**
- roof-trusses, 1120
  - segmental arches, 307, 832
- Tile, 1604-1607**
- aseptic, 1605

**Tile, cast-glass, 1606**

- cement, reinforced, 867-869
  - ceramic, 1605, 1607
  - concrete, 816
  - copper, 1587
  - cost, 1046, 1587, 1607
  - enameled, 1605, 1607
  - encaustic, 1604, 1607
  - faience, 1607
  - fireproofing, 234, 815, 828, 874
  - flint, 1605
  - flooring, 892-893, 1604-1607
  - Florentine mosaic, 1605
  - glass, 1606
  - glazed, 1605, 1607
  - hollow (see Terra-cotta)
    - and concrete, 951-952
  - interlocking rubber, 1606
  - lozenge, 1605
  - Ludowici, 1049
  - mantel, 1605
  - marble, 1605
  - mosaic, 1607
  - piers, 278
  - reinforced, 838-842
  - reinforced-cement, 867-869
  - Roman, 1049, 1605, 1607
    - floor-construction, 953
  - roofing, 866, 1586
    - cost, 1587
    - laying, 1586
    - specifications, 1586
  - rubber, 1606
  - semivitreous, 1604
  - sheet-metal, 1587
  - slate, 1606
  - Spanish, 1049
  - specific gravity, 1508
  - steel, 1587
  - terrazzo, 1607
  - tin, 1587
  - vaults, 1243
  - vitreous, 1604, 1605, 1607
  - wall, 1604, 1606, 1607
  - weight, 1049, 1508
- Tile-arch, Guastavino, 841, 842, 1242**
- Timber (see, also, Lumber and different woods)**
- board-measure, 1560-1562
  - bond (Glossary), 1803
  - data, 1558-1563
  - footings, temporary buildings, 18187
  - framing, sizes, 1559
  - hardness, relative, 1558
  - measurement, 1559-1563
  - modulus of elasticity, 647, 731-734
  - painting, 763
  - piles, 188-196, 198
  - shrinkage, table, 1428



**Timber, sizes in slow-burning construction,** 759, 762  
 stresses (see woods in question)  
 ventilation, 763  
 weight, 1501-1508, 1538  
 working unit stresses, 647, 648, 650, 1138  
**Time, measures,** 30  
 unit of, 1247  
**tin, block, pipe,** 1419  
 brands, 1588  
 casting, 1521  
 fire-doors, 894-897, 901-904, 1853  
 gutters, 1590  
 lined pipe, 1415  
 roofing, 801, 1588-1595  
   cost, 1046, 1589, 1593, 1594  
   covering capacity, 1591-1594  
   durability, 1589  
   gutters, 1590  
   laying, 1590-1593  
   painting, 1570, 1589, 1590  
   rolls, 1594  
   valley, 1590  
 sheets, 1588  
 specific gravity, 1508  
 terne-plates, 1588  
 weight, 723, 1049, 1508, 1521, 1588, 1591  
**finned fire-doors,** 894-897, 901-904, 1853  
**tin-can metal,** 1604  
**torsion, definition,** 128  
**tower (Glossary, 1848), belt,** 764, 765  
 elevator, 764, 765, 768  
 fire-escape, 779  
 stairway, 764, 765  
 warehouses, 768, 779  
 water, wind-bracing, 1184  
**tower-clocks,** 1695  
**tracings,** 1718-1720  
   black-line copies, 1719  
   blue-prints, 1718  
   brown-line copies, 1720  
**train-sheds, steel, weight,** 1210  
   trusses for, 1039  
**transferred heat,** 1684  
**transformers, current,** 1463  
**transmission of heat,** 1256-1259, 1684  
**trapezium,** 37  
**trapezoid,** 37, 40  
   moment of inertia, 336, 337  
   radius of gyration, 336  
   section-modulus, 336  
**trap-rock,** 131  
   compressive strength, 282, 287  
   concrete aggregate, 817  
   specific gravity and weight; 282, 1508  
**traps, plumbing,** 1410, 1412-1414  
   drum, 1413, 1414  
   grease, 1414

Traps, sewer, 1409  
   ventilation, 1412  
**Trautwine's formula, depth of keystone,** 309  
**Travertine,** 131  
**Treads, marble,** 900  
   rules for, 1648  
   slate, 900  
   table, 1646, 1647  
**Treasury Department, hot-water heating,** 1303, 1308  
**Tremies,** 244  
**Trenches, as affecting foundations,** 147  
   preparing for footings, 226  
**Triangles,** 36, 39, 71  
   center of gravity, 292  
   moment of inertia, 336  
   oblique-angled, 92  
   of forces, 289  
   radius of gyration, 336  
   section-modulus, 336  
   trigonometrical functions, 91-94  
**Trigonometry,** 90-117  
**Trim, cement,** 898  
   electroplated, 898  
   hollow-tile, 898, 899  
   metal-covered, 894-899  
**Trimmers, floor,** 728, 748  
   safe loads, 747  
**Troy weight,** 29  
**Truss-metal lath,** 885  
**Trusses (see Roof-trusses)**  
**Tubing, Benedict nickel,** 1415  
   seamless-drawn, 1415  
**Tungsten, specific gravity and weight,** 1508  
**Tungsten-lamps,** 1444, 1447  
**Turnbuckles,** 386, 387, 397  
**Tuscan Order,** 1699  
  
**Underpinning,** 214, 218-222  
**Unit stress, definitions,** 125, 126, 332, 375, 1172  
**Unit system, reinforcement,** 922  
**Units, system of,** 1247  
   electrical and mechanical, equivalents, 1248  
   foot-pound-second system, 1247  
**University of Illinois, tests on brick piers,** 275  
   tests on terra-cotta piers, 277  
**Urinal-stalls, dimensions of,** 1641  
**United States Government buildings, hot-water heating,** 1303, 1306, 1308  
**United States measure of value,** 29  
**United States Naval Observatory, foundations,** 251  
**Utah, registration law,** 1779  
  
**Vacuum-cleaners, types,** 1708  
**Vacuum-gauges,** 1248

**Vacuum, pumps, size, 1290**  
     systems, steam-heating, 1287-1291  
**Valleys and gutters, 1590**  
**Valves, equalizing, caissons, 212**  
     heating, symbol, 1350  
**Vapor, 1249-1254 (see Steam)**  
**Vaporization, heat of, 1684**  
**Varnish, 1568, 1570, 1573**  
**Vault, 1231-1243**  
     barrel, 1231-1235  
     (Glossary), 1849  
     framed, 1243  
     groined, 1235-1240, 1822  
     legal definition, 1855  
     ribbed, 1240  
     tile, 1243  
**Vault-walls, 263-264**  
**Vaulting (Glossary), 1822**  
**Velocity, unit, 1247**  
**Veneer, buildings, 269**  
     defined, 1855  
**Vent-flues, air-velocity, 1357**  
     coils, 1356  
**Vent-pipes, plumbing, 1407, 1410**  
     sizes, 1410  
**Vent-shafts, fire-proof, 889**  
**Vento heater, 1330-1332, 1338**  
**Ventilating fans, 1341-1347, 1357**  
**Ventilation, 1348-1354**  
     air required, amounts, 1260, 1354, 1356  
     buildings, 1348-1354, 1356  
     capacity of fans, 1341  
     fans, 1341-1347, 1357  
     furnace-heating, 1313  
     gravity indirect heating, 1299  
     hot-blast system, 1325, 1327  
     laws, 1354  
     mill-buildings, 769, 775-776  
     saw-tooth roofs, 776  
     systems, 1349  
     timbers, 763  
     warehouses, 776  
     workshops, 769, 1353  
**Verona radiators, 1266**  
**Vibration of machinery, 763**  
**Volt, defined, 1457**  
**Voltage, candle-power, 1462**  
**Volume, measures, 27, 31, 1247**  
**Volumes, geometrical, 38, 60-65**  
**Voussoirs, arch, 305, 311, 313**  
     center of gravity, 313, 318  
**Walks, cement, 239**  
**Wall (see, also, Brickwork, Masonry, Stonework, etc.)**  
     ashlar, thickness, 233  
     basement, 228, 229  
     bearing-plates on, 442  
     breast, 262-263  
     brick, 229  
         backing, 269

**Wall, brick, over openings, 318**  
     safe loads, 265, 441  
     buckling, 229  
     buildings, mercantile, 230-232  
     cantilevering, 169  
     cellar, 129, 228, 229  
     cement-block-faced, 269  
     center of gravity, 300, 301  
     concrete, 229, 946-947, 965, 966  
         cost, 250  
     concrete blocks, 233  
     crushing height, 269, 270  
     curtain, 234  
     dwellings, 230, 232  
     external, thickness, 229, 231  
     face, 269  
     faced, with ashlar, 233, 269  
         with cement blocks, 269  
         with terra-cotta, 269  
     fire, 765  
     fire-resistance, 229, 234  
     footings (see Footings)  
     foundation, 129, 200, 228, 234  
         979  
     heat-transmission, 1256  
     hollow-tile, 233  
     loads over openings, 318  
     mills and factories, 760, 765, 768  
         778, 809  
     needling, 218-222  
     openings in, 318, 778  
     parapet, 768  
     party, 234  
     reinforced-concrete, 946, 948, 949  
         975, 978  
     retaining (see Retaining-wall)  
     roof, 768  
     safe loads, 265-267  
     self-sustaining, 234  
     shoring, 214-222  
     skeleton construction, 234  
     stability, 229, 301  
     stone, 229, 233  
         safe loads, 266, 267  
     stone-faced, 233, 269  
         ashlar, 233, 269  
     strength, 265-267, 269, 270  
     superstructure, 229-234  
     supports, girders, 792  
     terra-cotta facing, 269  
     thickness, 229-234, 260-261, 265  
         760  
     tile, hollow, 233  
     tiling, 1604, 1605, 1607  
     underpinning, 214, 218-222  
     vault, 263-264  
     warehouses, 230-232, 768, 778  
**Wall-boards, asbestos, 819**  
     metal-rib, 888  
**Wall-boxes, 782, 785, 786, 792, 793**  
**Wall-hangers (see Hangers)**

all-openings, 318, 778  
 all-pipe (furnaces) dimensions, 1320  
 all-plasters (see Plaster)  
 all-plates, beams and girders, 783, 785, 787, 788, 793  
 roof-trusses, 1150-1152, 1156, 1158 1165, 1168  
 alnut, hardness, 1558  
 specific gravity, 1508  
 unit stresses, 651  
 weight, 651, 1508, 1558  
 ar Department, hot-water heating, 1303  
 ardrobes, dimensions, 1638, 1640  
 arehouses, basement walls, 229  
 beams, 762, 763, 779, 800  
 boilers, 780  
 cast-iron columns, 780, 781  
 cement floors, 892  
 construction, general, 758-810  
 cost, 777, 802-810  
 defined, 1855  
 fire-escape, 768, 778  
 fireproofing, 780-782  
 fire-protection (see sprinklers, below)  
 floor-areas, 765, 777, 778  
 floor-loads, 721, 1198  
 floors, 764, 777, 892, 893  
     size and weight of I beams, 865  
 girders, 762, 763, 779-800  
 gravity-tanks, 779  
 heating, 776  
 height, 777  
 live loads, 721  
 mill-construction for, 777-782  
 openings in walls, 778  
 roofs, 768, 772, 800  
 roofing-materials, 800, 801  
 scuppers, 767  
 sprinklers, 768, 777, 779, 801, 903-905  
 stairs, 759, 764, 768, 778, 779, 810  
 standpipes, 768, 801, 905  
 steel, weight, 1208  
 story-heights, 765  
 structural details, 780, 788, 810  
 towers, 768, 779  
 ventilation, 776  
 walls, 230-232, 768, 778  
 wooden columns versus iron and steel, 780  
 water-supplies, 802  
 arren truss, types, 1030, 1031  
     stresses, 1089-1091  
 ash-basins, dimensions, 1641  
 ashers, 437, 1157-1160  
     beveled, 437, 1202  
 ashington building code, steel columns, 481  
 ashington Monument, foundations, 251

Wash-pipes, foundation-bed testing, 144  
 Wash-stands, dimensions of, 1638  
 Wash-tubs, 1412  
 Waste-pipes, 1407-1411, 1416, 1417, 1427  
 Waste-stacks, expansion, 1427  
 Water, density, 1247  
     evaporation, 1251-1254  
     filters, 1421  
     flow in pipes, 1382-1388  
     freezing-point, 1250  
     hard, softening, 1429  
     head, 1381-1383, 1389  
     heating, house-supply, 1430  
     incrustation of tanks, 1429  
     pressure, 1381, 1382, 1389  
     properties, 1381  
     required for mortar, 238  
     softening, 1429  
     specific gravity, 1381, 1500, 1508  
     supply, 802, 1390-1398, 1415  
     tanks (see Tanks)  
     temperatures, boiling, 1251  
     weight, 1381, 1500, 1508  
 Water-backs, capacity, 1430  
 Water-closets, 1411, 1428, 1641  
 Water-curtains, 901, 903  
 Water-filters, 1421  
 Water-gas, 1431  
 Water-heaters, 1421, 1425  
 Water-meters, 1425  
 Water-pipes (see Pipes)  
 Water-seal, 1413  
 Water-supply, 1390-1398, 1415  
     fire-protection, 802  
 Water-tables, stone, 1539  
 Water-tanks (see Tanks)  
 Water-towers, wind-bracing, 1184  
 Waterproofing, 1709-1717  
     cement, 1711, 1717  
     concrete, 246, 1711, 1717  
     foundations, 1709  
     external, 1713  
     foundations, 1709-1717  
     water-proof cement, 1714  
     paper, 1567  
 Watt, 33, 1248, 1459  
 Web (see, also, Box Girders, Plate girders, and Beams, steel)  
     box girders, buckling value, 686, 705  
     shearing value, 684, 703  
     stiffeners, 681, 686, 691, 696, 1201, 1203  
     domes, 1241  
     plate girders, 681, 703-716  
         buckling value, 686, 705  
         shearing value, 703  
         stresses, 684, 686, 691  
     steel beams, web-buckling, 181-185, 565, 567-569, 612, 627  
     web-thickness, 592

**Wedges, shoring, 275**  
**Weight (see each substance, and also Loads)**  
   adult persons, 1644  
   measures of, 28-29  
     metric system, 32  
   merchandise, 721-723  
   sash, 1649-1651  
   substances, per cubic foot, 1501-1508  
   unit of, 1247  
**Weights and measures, 25-35**  
**Weld, iron, 377**  
   steel, 377  
**Welded-metal fabric, 948-949**  
**Wellington's formula for pile foundations, 193**  
**Wells, dredged, foundations, 210**  
   driven, water-supply, 1391  
   foundations affected, 147  
**Weisbach lamps, 1444-1451**  
**Wemlinger sheet-piling, 209**  
**Wheat, weight, 723**  
**White-coating, plastering, 1555**  
**White pine, beams, coefficients for, 628**  
   deflection, 664  
   fiber-stress, flexure, safe, 557, 647, 648, 1138  
   safe loads, 639  
   columns, safe loads, 450, 452  
   crushing-loads, with the grain, 449, 650  
   crushing strength, across the grain, 454, 650  
   hardness, 1558  
   modulus, of elasticity, 647, 664  
   of rupture, 650  
   safe loads on columns, 450, 452  
   shearing-stresses, 412, 647, 648, 1138  
   specific gravity, 1507  
   stiffness, 664  
   tension, 376, 647, 648, 650, 1138  
   unit stresses, 376, 412, 647, 650, 1138  
   weight, 650, 1507, 1558  
**Whitewood (poplar), columns, safe loads, 450, 452**  
   crushing-loads, with the grain, 449  
   hardness, 1558  
   specific gravity and weight, 651, 1507  
   unit stresses, 651  
**Wind, force of, 1171**  
   pressure, 1171-1173  
   resistance, 1175  
   stresses, bracing, 1176-1183  
   trusses, 1109-1118, 1123-1128  
**Wind-bracing, 1171-1193**  
   building law, 1171-1172, 1176, 1202  
   column-connections, 1174-1175, 1179, 1189, 1190  
   columns, types, 1183  
   conditions determining, 1172  
   details, 1189, 1190

**Wind-bracing, examples, 1187-1193**  
   general theory, 1173-1174  
   gusset-plate type, 1176, 1179, 1181, 1190  
   knee-brace type, 1176, 1179, 1180  
   lattice-girder type, 1176, 1181  
   moment-increments, 1176, 1178  
   portal type, 1176, 1181  
   resistance-factors, indeterminate, 1178  
   stresses, computation of, 1176-1183  
   sway-rods, 1176, 1181  
   types, 1174-1176, 1187-1193  
   water-towers, 1184  
**Wind-loads, 1053, 1198**  
**Wind-shields, scuppers, 767**  
**Wind-stresses (see Stresses)**  
**Windmills, capacity, 1394**  
**Window-frames, bronze, 895**  
   fire-resisting, 902  
   Kalamein iron, 895  
   metal, 897  
   metal-covered, 895  
   mill-construction, 764  
**Window-sashes, fire-resisting, 902**  
   metal, 897  
   metal-covered, 895  
   weights, 1649-1651  
**Window-sills, stone, 1534**  
**Windows, bay (Glossary), 1802**  
   fire-protection, 901  
   glazing, 1573-1580  
   heat-transmission, 1258  
   loads over, 318  
   metal-frame-and-wire-glass, 901-902  
   mill-construction, 759, 763, 769  
   saw-tooth, 772, 775, 778  
   sheet-metal, 902  
   water-curtains, 901, 903  
   wire-glass in warehouses, 778  
**Winslow formula, wooden columns, 45**  
**Wire, 402, 403**  
   annealed, 1513  
   aviator, 401  
   Bessemer, 1513  
   bright, 1513  
   copper, 401, 1469, 1470, 1474, 1513  
   electric wiring, 1466-1485 (see, also Wiring)  
   calculations, 1469-1479  
   lighting, 1469  
   resistance, 1474  
   fabric, reinforcement, 850  
   feed, 1478  
   finish, 400  
   fire-detecting, 903  
   galvanized, 406, 1513  
   gauges, 401, 1469, 1509, 1512  
   gun-screw, 1513  
   in glass, 759, 821  
   iron, 401  
   lath, 887

**Wire**, length per pound, 403  
     machinery, 1513  
     manufacture, 400, 1513  
     market, 1513  
     nails, 1529  
     piano, 401  
     plough, 401  
     rope, 404-406  
         weight, 403, 1474, 1512  
     size and weights, 403, 1474, 1475, 1477, 1512  
     steel, 400, 401, 403, 404, 406, 1513  
     strength, 400-401, 403, 1512  
     telegraph, 401  
     telephone, 401  
     tinned, 1513  
     uses, 401  
**Wire-glass**, 759, 778, 821  
**Wire-mesh**, 919  
**Wiring**, electric-lighting, 1466-1485  
     cabinet, 1477  
     conduits, 1479  
     cost, 1482  
     national electrical code, 1480  
     specifications, 1482  
     symbols, 1476-1478, 1484  
     tables, 1475  
**Wisconsin**, registration law, 1779  
**Wood** (see, also, **Lumber**, **Timber**, and **wood in question**)  
     beams (see **Beams**)  
     columns (see **Columns**, wooden)  
     compression, across the grain, 454, 647, 650, 651, 1138  
         with the grain, 449, 647, 650, 651, 1138  
     fire-proof, 820, 894  
     flexure, 557, 647, 650, 651, 1138  
     friction-coefficient, 253  
     fuel, 1272  
     hardness, relative, 1558  
     metal-covered, 894-895  
     modulus of elasticity, 647, 664  
     painting, 1569-1572  
     shear, 412, 647-651, 1138  
     sheathing, 1049, 1563, 1564  
     specific gravity, 1501-1508  
     tension, 376, 647, 650, 651, 1138  
     weight, 650, 651, 1501-1508, 1558  
     working stresses, 647, 648, 650, 1138  
**Wool**, weight, 721  
**Work**, contractor's charges, 1757  
**Energy**, 1248  
**Working stresses** (see **Stress and materials in question**)  
**Works**, Clerk of the, 1728, 1733  
**Workshops**, slow-burning, 769-771  
**Ventilation**, 769, 1353  
**Wrought iron**, 377  
     appearance, 377  
     beams, coefficients for, 628

**Wrought iron**, beams, deflection, 664  
     stiffness, 664  
     bending moments, 431  
     bolts, 431, 1138  
         bearing strength, 1138  
     chains, 408, 410  
     compression, bolts, 1138  
     crushing-loads, 449  
     elongation, 378, 410  
     finish, 378  
     fire-resistance, 819  
     flexure, 431, 557, 1138  
     grades, 378  
     manufacture of, 378  
     modulus of elasticity, 664  
     physical properties, 377, 378  
     pipe, 1408, 1429, 1432-1436  
     reinforcement, 907  
     rivets, 418  
     rope, 404-406  
     shearing-stresses, 412, 431, 1138  
     specific gravity, 1505, 1510  
     specifications, 377-378  
     stirrups, 750, 757  
     tension, 376, 377-378, 410, 431, 1138  
     tests, 377-379  
     use, 377  
     weight, 1505, 1510, 1521  
         estimating, 1521  
         sheets, 1510  
     welding, 377  
     yield-point, 378  
**Yellow pine**, beams, coefficients for, 628  
     deflection, 664  
     fiber-stress, flexure, 557, 647, 648  
     safe loads, 642, 643, 666  
     columns, safe loads, 450, 451, 452  
     crushing-loads, with the grain, 449, 650  
     crushing strength, across the grain, 464, 650  
     hardness, 1558  
     modulus of elasticity, 647, 664  
     modulus of rupture, 650  
     safe loads on columns, 450, 451  
     shearing-stresses, 412, 647, 648, 650  
     specific gravity, 1507  
     stiffness, 664  
     tension, 376, 647, 648, 650  
     unit stresses, 376, 412, 647, 648, 650  
     weight, 650, 1507, 1508  
**Yield-point**, steel, 381, 383, 912, 913  
     wrought iron, 378  
**Young's modulus**, 126  
**Z bars**, base price, 1204  
     purlins, 1169  
**Zinc**, castings, shrinkage, 1521  
     specific gravity and weight, 1508  
**Zone of sphere**, volume, 64

1534 41

21



# DATE DUE

JUN 14 1986	MAR 28 1995		
MAY 1 1986			
JAN 9 1987			
NOV 04 1987			
NOV 21 1989			
NOV 21 1989			
MAY 22 1991			
DEC 27 1994			
JAN 10 1995			

DEMCO 38-297

JUN 2 '7 1985

100 CAMBRIDGE STREET  
CHARLESTOWN, MASS.



3 2044 029 6/2 482

Kidder

5484